THE J. Mason Warren

WORKS

OF

AMBROSE PAREY,

Chyrurgeon to

HENRY II. FRANCIS II. CHARLES IX. and HENRY III.

Kings of France.

Wherein are Contained

An Introduction to CHIRURGERY in general:

A

Diſcourſe of ANIMALS, and of the Excellency of MAN.

THE

ANATOMY of MAN's BODY.

A

TREATISE of præternatural Tumors in general. Of their Cure in particular. Of Wounds in general. Of Wounds with their Cure in the particular parts of Man's Body. Of Wounds made by Gun-ſhot, and other deſtructive Engines. Of Contuſions and Gangrenes. Of Ulcers and Fiſtulaes. Of Bandage. Of Fractures and Diſlocations. Of almoſt all preternatural Affections, whoſe Cure is performed by manual Operation. Of the Gout. Of the French Pox, with all its Symptoms. Of the Small Pox and Meaſles. Of Worms and Leproſie. Of Poiſons, with the Cure of Wounds, made by the Biting of a mad Dog, and other Venomous Creatures. Of the Plague. Of artificial Supplying thoſe things which by Nature or Accident are wanting. Of Monſters and Prodigies. The way of making Reports, and Embalming Dead Bodies.

ILLUSTRATED

With Variety of Figures, and the Cuts of the moſt uſeful Inſtruments in Chirurgery.

RECOMMENDED

By the Univerſity of *Paris* to all Students in Phyſick and Chirurgery, particularly ſuch as Practiſed in Camps and the Sea.

LONDON:

Printed: and ſold by *Joſ. Hindmarſh*, at the *Golden Ball* over againſt the *Royal Exchange* in *Cornhil*. M DC XCI.

HARVARD UNIVERSITY
WARREN LIBRARY
JANUARY 2, 1929
LIBRARY OF THE MEDICAL SCHOOL

1.MW.1681.P

To the Right Honourable

EDWARD

Lord *Herbert* of *Cherbury* and *Caſtle-Iſland*,

and one of His Majeſties moſt Honourable Council of War.

My Lord,

IT is not the far-fetcht Pedegree of Noble Anceſtors nor thoſe Honors your Lordſhip deſervedly poſſeſſes, that make me crave your Patronage to this my Labour; but it is that Heroick mind, enriched with the choice endowments of Nature and Art, and that earneſt affection wherewith your Honour entertains all Sciences, Arts, and Artiſts, with that exquiſite Judgement which ſees into the inner man, which embolden and incite me to ſue for your Honours aſſiſtance, in protecting the fame of him, who by your many favours is made yours. I know the ſeeming and ſelf-pleaſing Wiſdom of our Times, conſiſts much in cavilling and unjuſtly carping at all things that ſee light, and that there are many who earneſtly hunt after the Publick Fame of Learning and Judgement, by this eaſily trod, and deſpicable Path, which notwithſtanding they tread with as much Confidence as Folly; for that oft-times which they vainly and unjuſtly brand with Opprobry, out-lives their Fate, and flouriſhes when it is forgot that ever any ſuch as they had being.

I know your Lordſhips diſpoſition to be far diſſenting from theſe men, and that you rather endeavour to build up the Fame of your Learning and Judgment upon a ſtrong laid Foundation of your own, than Heroſtratus-*like, by pulling down any, howſoever fair built Fabrick of another. I heartily wiſh that your Honour could propagate this Good, and that all Detractors might be turned into Actors, and then I know it would much mitigate their rigour in cenſuring others, when as they themſelves were alſo expoſed to the ſame Hazard.*

I think it impertinent to acquaint your Honour with the Nature of the Work, my Pains in Tranſlating, or the Benefit that may enſue thereon, for that I know your Honour ignorant of nothing in this kind; neither doubt I of your favourable acceptance of the good Will of him, that thinks himſelf much honoured by being

Yours,

THOMAS JOHNSON.

TO

TO THE
READER.

I Have here for the Publick Good taken pains to ſubject my ſelf to Common Cenſure, the which I doubt not but to find as various as the Faces of the Cenſurers; but I expect no thanks, nor hunt after other praiſe, than that I have laboured for my Countries good, if that deſerve any. I fear not Calumniation (though ſure to hear of it) and therefore I will not Apologize, but inform thee of ſome things concerning the Author, his Work, and the Reaſon that induced me to the Tranſlation thereof, with ſome few things beſides. For the Author, who was principal Surgeon to two or three Kings of *France*, he was a man very well verſed in the Writings of the Ancient and Modern Phyſicians and Surgeons, as you may evidently find by ſundry places alledged in his Works. For his Experience or Practice (the chief help to attain the higheſt perfection in this Art) it was wonderful great, as you may collect by his Voyages recorded in the laſt part of his Work; as alſo by that which *James Guillemau* Surgeon to the *French* King, a man both learned and judicious in his Profeſſion, avers, ſpeaking of his own Education and Progreſs in the Art of Surgery. I ſo laid (* ſaid he) the firſt Foundation of this Art in the Hoſpital of *Paris*, being as it were, an ample Theatre of Wounds and Diſeaſes of all kinds, that for two whole Years, during which time I was there converſant, nothing was conſulted of, nothing performed, the Phyſicians and Surgeons being preſent, whereof I was not an Auditor or Actor. There flouriſhed at theſe Times, and yet doth, *Ambroſe Parey*, Principal Surgeon to the moſt Chriſtian King, the Author of this great Work, moſt renowned for the moſt gracious favour of Kings, Princes and Nobles towards him, for his Authority amongſt his equals, for his Chirurgical Operations amongſt all men. Therefore I earneſtly endeavoured to be received into his Family, as unto another *Machaon*, or *Podalirius*: Once admitted, I ſo by all dutifulneſs and due reſpect acquired his Favour, that he, unleſs I were preſent and aſſiſting, did nothing (ſuch is his natural gentleneſs and curteſie to all ſuch as are ſtudious of the Art) at home or abroad, in the Field, in the Tents, or laſtly in this famous City of *Paris*, about the Bodies of Dukes, Noblemen, or Citizens, in whoſe Cure, he by the ardent deſire of them all, had ſtill the prime place.

* In his Epiſtle prefixed before the Latin Edition of this Author.

Now for this Work, hear what this ſame man in the ſame place affirmeth further: I not content with theſe means, which may ſeem ſufficient, and too much, as deſirous to ſatisfie my long thirſt, determined to trie whether I could draw or borrow any thing from Strangers, which our men wanted, to the fuller knowledge of Surgery. To this purpoſe I travelled over *Germany*, and then for four years ſpace I followed the *Spaniſh* Army in the Low-Countries; whereas I did not onely carefully cure the wounded Souldiers, but alſo heedfully and curiouſly obſerved what way of curing the renowned *Italian*, *German*, and *Spaniſh* Surgeons obſerved, who together with me were imployed in the Hoſpital, for the healing of the wounded and ſick. I obſerved them all to take no other courſe than that which is here delivered by *Parey*. Such as did not underſtand *French*, got ſome pieces of this Work for large rewards turned into *Latin*, or ſuch Languages as they underſtood, which they kept charily, and made great ſtore of; and they eſteemed, and admired, and embraced this Work alone, above all other Works of Surgery, &c. Our Author alſo himſelf, not out of a vain-glorious oſtentation, but a mind conſcious of the truth of his aſſertion, affirms thus much of this Work. I have (ſaith he) ſo certainly touched the mark whereat I aimed, that Antiquity may ſeem to have nothing wherein it may exceed us, beſides the Glory of *Invention*; nor Poſterity any thing left, but a certain ſmall hope to add ſome things, as it is eaſie to add to former Inventions. Thus much concerning our Author, and the excellency of his Work.

Now come I to the Tranſlation, the which, as deſiring more a publick Good than private Praiſe, I have performed plainly and honeſtly, labouring to fit it to the capacity of the meaneſt Artiſt; for theſe are they to whom I chiefly commend this Work, and from whom I expect acceptation. I being by the earneſt perſuaſions of

ſome of this Profeſſion, chiefly and almoſt wholly perſuaded and incited to take this pains, who knowing the diſability of underſtanding this Author in Latin or French, in many of the weaker Members of the large Body of their Profeſſion, diſperſed over this Kingdom, and the reſt of his Majeſties Dominions, whoſe good and increaſe in knowledge may be wiſhed, that ſo they may be the better enabled to do good to ſuch as ſhall implore their aid in their Profeſſion.

There are ſome I know will blame me for Engliſhing this Work, as laying open the Myſteries of a worthy Art to the unworthy view of the Vulgar. To ſuch I could anſwer as * *Ariſtotle* did to *Alexander:* but for the preſent I will give them theſe reaſons which I think may ſatisfie any but the purpoſely malicious. The firſt is drawn from the *goodneſs* of the thing, as intended for thoſe that want ſuch Guides to direct them in their Art; for it is commonly granted, that *Bonum quo communius eo melius.* Secondly, it hath been the cuſtom of moſt Writers in all Ages and Countries thus to do: *Hippocrates*, *Galen*, and the other *Greeks*, writ in their Mother Tongue the Myſteries of their Art. Thus did *Celſus*, *Serenus*, and others in *Latin: Meſue*, *Avicen*, *Serapio*, and others, in *Arabick:* as alſo, to go no farther, our Author writ this Work in his Native *French*, and learned men have done the like in this, and all other Arts. And it is a great hinderance to us in theſe days, that we muſt be forced to learn to underſtand two or three Tongues before we can learn any Science, whereas the Ancients learned and taught theirs in their Mother Tongue: ſo that they ſpent a great deal leſs time about Words, and more upon the Study of that Art or Science they intended to learn and follow. Thirdly, I muſt tell you, that, *Ex libris nemo evaſit Artifex*, No man becomes a Workman by Books: ſo that unleſs they have had ſome inſight in the Art, and be in ſome ſort acquainted both with the terms of Art, as alſo with the knowledge and uſe of the Inſtruments thereto belonging, if by reading this, or any other Book of the like nature, they become Surgeons, I muſt needs liken them (as *Galen* doth another ſort of men *) to Pilots by Book onely: to whoſe care, I think none of us would commit his ſafety at Sea; nor any any if wiſe, will commit themſelves to theſe at Land or Sea either, unleſs wholly deſtitute of other.

Vid. Aul. Gel. l. 2. c. 4.

Gal. de Simp. l. 6.

The other things whereof I muſt give you notice, are theſe. The Figures in the Anatomy are not the ſame uſed by my Author (whoſe were according to thoſe of *Veſalius*) but according to thoſe of *Bauhine*, which were uſed in the Work of Dr. *Crook*; and theſe indeed are the better and more compleat. Alſo *pag.* 519. I thought it better to give the true Figure of the Helmet flowered *Aconite*, mentioned out of *Pliny*, than to reſerve the feigned Picture of *Matthiolus* which in our Author was increaſed with the further fiction of a Helmet. I have in ſome few places in the Margent, which you ſhall find marked with a Star, put ſhort annotations, for the better illuſtration of that which is obſcure, &c. I have alſo in the Text to the ſame purpoſe, here and there put two or three words, contained in theſe limit [ ] which I find here and there turned into a plain Parentheſis, eſpecially toward the latter end of the Book; but the matter is not great. Further I muſt acquaint you that the Apology and Voyages, being the laſt part of this Work, and not in the Latin, but French Editions, were tranſlated into Engliſh out of French by *George Baker*, a Surgeon of this City, ſince that time, as I hear, dead beyond the Seas.

This is all, Courteous Reader, that I have thought neceſſary to acquaint thee withal concerning this, which I would deſire thee to take with the ſame mind that it is preſented to thee, by him that wiſheth thee all happineſs,

Thomas Johnſon.

THE

THE AUTHORS EPISTLE DEDICATORY TO HENRY III.

The most Christian King of *France* and *Poland*.

EVen as (most Christian King) we see the members of Mans Body by a friendly consent are always busied, and stand ready to perform those Functions for which they are appointed by Nature for the preservation of the whole, of which they are parts; so it is convenient that We, which are as it were Citizens of this Earthly Common-wealth, should be diligent in the following of that Calling which (by Gods appointment) we have once taken upon us: and content with our present Estate, not carried away with Rashness and Envy, desire different and divers things whereof we have no knowledge. He which doth otherwise, perverts and defiles with hated confusion the order and beauty, on which this Universe consists. Wherefore when I considered with my self that I was a Member of this great Mundane Body, and that not altogether unprofitable; I endeavoured earnestly that all Men should be acquainted with my duty, and that it might be known how much I could profit every Man. For God is my witness, and all good men know that I have now laboured fifty years with all care and pains in the Illustration and Amplification of Chirurgery; and that I have so certainly touched the mark whereat I aimed, that Antiquity may seem to have nothing wherein it may exceed us, beside the Glory of Invention; *nor Posterity any thing left but a certain small hope to add some things, as it is easie to add to former Inventions. In performance whereof, I have been so prodigal of my self, my watchings, faculties, and means, that I spared neither time, labour, nor cost, whereby I might satisfie and accomplish my own Desires, this my great Work, and the Desires of the Studious. Neither may we doubt but their Studies would at length wax cold, if they onely furnished with the Theorick and Precepts in Schools, and that with much labour, should see no manual operation, nor manifest way of performing the Art. For which cause I seeking the praise and profit of the* French Nation, *even with the hinderance of my particular Estate, have endeavoured to illustrate and increase Chirurgery, hitherto obscure either by the infelicity of the former Ages, or the envy of the Professors; and not onely with Precepts and Rules, but being a lover of Carved Works, I beautified it with 300 Forms, or Graven Figures, and apt Delineations, in which whosoever shall attentively look, shall find five hundred Anatomical or Organical Figures belonging to the Art, (if they be reckoned particularly.) To every of these I have given their Names and shewed their Use, lest they should seem to have been put in vainly for Ostentation or Delight. But although there be few men of this Profession which can bring so much authority to their Writings either with Reason or Experience, as I can; notwithstanding I have not been so arrogant, but intending to publish my Work, I first communicated it with Men the most excellent in the Art of Physick, who gave me greater encouragement to perfect*

fect and publiſh it, that it might be in common uſe: profeſſing they wiſhed nothing more, than that it might be turned into Latin, by which means it ſhould be known to foreign Nations, that there is no kind of Learning which is not delivered with great dexterity of Wit in this Kingdom over which you rule. And thus much I dare boldly affirm, that there is ſcarce any, be he never ſo ſtately or ſupercilious, but that he may here find ſome thing which may delight him, and by which he may better his knowledge. Therefore I doubted not to conſecrate this Book unto your Majeſty, both as a Pattern and Treaſury of my Labours, as well in reſpect of my duty, who am Yours by Nature and Education, as that I might manifeſt to all, your Highneſſes exceeding bounty towards me, in placing me (having heretofore enjoyed the Office of Principal Chirurgeon under three Kings, your Majeſties Predeceſſors) in the ſame dignity, and that of your own accord. And moreover I did conjecture that it would fall out, as now it doth, that this my Work carried through the World by the Fame of your Majeſties Name, ſhould neither fear the face nor view of any, ſupported by the Favour and Majeſty of a moſt invincible Monarch and moſt Excellent and Renowned Prince. Neither did King Charles IX. *of happy Memory, incited by the relation of the moſt gracious Queen his Mother, refuſe to read it, being he underſtood it proceeded from him, who having happily paſſed all his time in private and publick imployments, and converſed with all men of all ſorts, was judged moſt worthy to obtain this favour, as to have the Front of this Work adorned and beautified with the ſplendour of his prefixed Name. I, encouraged by this hope, deſired that my requeſt ſhould paſs as by a certain continuation and ſucceſſion from a moſt Powerful, to a moſt Invincible King; and do wholly conſecrate theſe my Labours taken for my Countries good unto your Sacred Majeſty. God grant that your Majeſty may have happy ſucceſs of all your Enterpriſes abundantly added to* Neſtors *Years.*

Paris February 8.

Anno Dom. 1579.

Your Moſt Chriſtian Majeſties

Faithful Servant,

Ambroſe Parey.

THE

THE

PREFACE.

MOst Men derive the Original of Phyſick from Heaven; for thoſe who hold the beſt opinion of the Creation of the World, affirm, the Elements being created and ſeparated each from other, Man being not as yet made; incontinently by the divine Decree, all Herbs and Plants, with infinite variety of the Flowers endued with various Sents, Taſts, Colours, and Forms, grew and ſprung forth of the Bowels of the Earth, enriched with ſo many and great Virtues, that it may be thought a great offence to attribute to any other than the Deity, the benefit of ſo great a bleſſing ſo neceſſary for ſo many uſes. Neither could Mans capacity ever have attained to the knowledge of theſe things without the guidance of the Divine Power. For God the great Creator and Faſhioner of the World, when firſt he inſpired Adam by the breath of his mouth into a living and breathing Man, he taught him the Nature, the proper Operations, Faculties and Virtues of all things contained in the circuit of this Univerſe. So that if there be any who would aſcribe the glory of this invenuion to Man, he is condemned of ingratitude even by the judgment of Pliny. But this knowledge was not buried in oblivion with Adam: but by the ſame gift of God was given to thoſe whom he had choſen and ordained for Phyſick, to put their helping hands to others that ſtood in need thereof. Which opinion was not onely received in the common manner and by the tacite conſent of all Nations, but confirmed by Moſes in the Scripture. Which thing Jeſus the ſon of Sirach, the wiſeſt amongſt the Jews, hath confirmed, ſaying, Honour the Phyſitian with the honour due unto him, for the Moſt High hath created him becauſe of neceſſity: and of the Lord cometh the gift of Healing. The Lord hath created Medicins of the Earth, and he that is wiſe will not abhor them. Give place and honour to the Phyſician, for God hath created him; let him not go from thee, for thou haſt need of him. The Græcians who firſt ſeem more fully and with greater fame to have profeſſed the Art of Phyſick, do in a manner conſent with this opinion, in acknowledging Apollo to have been the Inventer thereof, neither did they it without a reaſonable cauſe. For whether by Apollo they may underſtand the Sun, who by its gentle and vital heat doth bring forth, temper, and cheriſh all things; or elſe ſome Heroes, who incited by an excellent and almoſt divine underſtanding, firſt taught and put in practice the Medicinal Vertues of Herbs; in which ſenſe Ovid brings him in ſpeaking thus:

Gen. 1.
Eccluſ. 38. 1.

Herbs are of mine invention, and through all
The World, they me the firſt Phyſician call.

The original of Phyſick ariſing from thoſe beginnings, ſhall always be celebrated as celeſtial, and was increaſed principally after this manner. After Apollo, Æſculapius his ſon inſtructed by his Father, reduced this Art being as yet rude and vulgar, into a little better and more exquiſit form, for which cauſe he was reputed worthy to be accounted as one of the Gods. At the ſame time flouriſhed Chiron the Centaure, who for that he excelled in knowledge of Plants, and taught Æſculapius (as many report) their Faculties, is thought by Pliny and ſome others to have been the Inventer of Phyſick. Æſculapius had two ſons, Podalirius and Machaon, who following their Fathers ſteps, and profeſſing Phyſick, did principally beautifie and practiſe that part thereof which is called Chirurgery, and for that cauſe were accounted the Inventers thereof. After thoſe Aſclepiades left this Art much enlarged, as hereditary to his Poſterity; by whoſe ſtudy and diligence, that part of the Art was invented and annexed, which by a more curious skill ſearcheth and cureth thoſe diſeaſes which lie hid within the body. Hippocrates the Coan the ſon of Heraclidas, born of the noble race of Aſclepiades, Prince of the Phyſicians that were before him, perfected Phyſick, and reduced it into an Art, and wrote divers Books thereof in Greek. Galen ſucceeded him ſix hundred years after, who was a Man moſt famous, not onely for his knowledge in Phyſick, but alſo in all other Sciences, who faithfully interpreting every thing that was obſcure and difficult en the Writings of Hippocrates, enlarged the Science with many Volumes. Thus therefore was the beginning, thus the increaſe and perfecting the Art of Phyſick, as much as can be hoped for from Mans Induſtry. Although indeed we cannot deny but that experience hath much

Plin. l. 7. c. 3

profited

profited this Art as it hath and doth many other. For as men perceived that some things were profitable, some unprofitable for this or that disease, they set it down, and so by diligent observation and marking of singularities, they established universal and certain Precepts, and so brought it into an Art. For so we find it recorded in ancient Histories, before the invention of Physick, that the Babylonians and Assyrians had a Custom amongst them to lay their sick and diseased persons in the Porches and Entries of their Houses, or to carry them into the Streets or Market-places, that such as passed by and saw them, might give them counsel to take those things to cure their Diseases, which they had formerly found profitable in themselves, or any other in the like affects, neither might any pass by a sick man in silence. Also Strabo writes that it was a custom in Greece that those which were sick should resort to Æsculapius his Temple in Epidaurus, that there as they slept, by their dreams they might be admonished by the god what means they should use to be cured; and when they were freed from their Diseases, they writ the manner of their Infirmities, and the means by which they were cured, in Tables and fastned them to the Pillars of the Temple, not onely for the glory of the god, but also for the profit of such as should afterwards be affected with the like Maladies. All which Tables (as Fame reports) Hippocrates transcribed, and so from those drew the Art of Physick. Beasts also have added much to his Art. For one Man was not onely instructed by another, but learned also much from brute Beasts; for they by the onely instinct of Nature have found out divers Herbs and Remedies, by which they freed and preserved themselves from Infirmities, which might presently be transferred to Mans use. Wherefore considering that such and so many have concurred to bring this Art to perfection, who hereafter dare call in question the Excellency thereof? chiefly if he respected the subject thereof, Mans Body, a thing more noble than all other Mundane things, and for which the rest were created. Which thing moved Herophilus in times past to call Physicians, The Hands of the gods. For as we by putting forth our hand, do help any man out of the Water and Mud into which he is fallen: even so we do sustain those that are thrown down from the top of Health to the gates of Death by violence of Diseases, with happy Medicins, and as it were by some special and divine gift deliver them out of the jaws of Death. Homer the Prince of Greek Poets affirms, That one Physician is far more worthy than many other Men. All Antiquity gave Physicians such honour, that they worshiped them with great veneration as gods, or the sons of their gods. For who is it which is not much delighted with the divine force of healthful Medicins, with which (we see by daily experience) Physicians, as armed with Mercuries Rod, do bring back those languishing souls which are even entering the gates of Death? Hence it cometh to pass that the divine Poets of ancient Times, as Orpheus, and Musæus, and Hesiod, and the most renowned Philosophers, Pythagoras, Plato, Aristotle, Theophrastus, Chrysippus, Cato Censorius, and Varro esteemed nothing more excellent than to excel in the knowledge of Medicins, and to testifie the same by written monuments to Posterity. For what can be more noble and worthy of a generous disposition than to attain to that by the benefit of Physick, that adorned with the ornaments of dignity thou maist have power over other men, and favoured of Princes, Kings, and Emperours, maist appoint and prescribe to them those things which are profitable to preserve health, and cure their diseases? But if thou look for benefit by Sciences, then know that the Professors hereof have beside sufficient gain, acquired much honour and many friends. Hippocrates coming to Abdera to cure Democritus of his Madness, not onely the men of the City, but also the women and children, and people of every Age, Sex and Rank, went forth to meet him, giving him with a common consent and loud voice, the title of a Tutelary Deity and Father of their Country. But the Athenians, for freeing their Country from the Plague, with triumphant pomp celebrated Plays to his honour, and bountifully set upon his head, as if he had been a King, a Crown of Gold weighing 1000 pieces of their golden Coin, and erected his Statue for a perpetual Monument of his Piety and Learning. Erasistratus the Nephew of Aristotle by his daughter, received, freely given him by Ptolomy King of Egypt, for the cure of his Son, 100 talents of gold. The Emperour Augustus honoured Antonius Musa with a golden Statue. Quintus Stertinius yearly received out of the Emperours Treasury 12500 pieces of gold. In the time of our Grandfathers, Petrus Aponensis called Conciliator, was so famous through all Italy for his knowledge in Physick, that he could scarce be intreated to come to any man of fashion that was sick, unless he gave him 50 Crowns for every day he was absent from home: but when he went to cure Heronius the Bishop of Rome, he received 400 Crowns for every day he was absent. Our French Chronicles relate in what credit and estimation James Cotterius the Physician was with Lewis XI. King of France; for they report he gave him Monethly out of his Treasury 10000 Crowns. Physick in times past hath been in such

In what esteem Physicians have formerly been.

ſuch Eſteem with many famous and noble Perſonages, that divers Kings and Princes delighted with the Study thereof, and deſirous to attain glory thereby, called ſundry Herbs after their own names. For ſo Gentian *took its name of* Gentius *King of* Illyria; *the Herb* Lyſimachia *of* Lyſimachus *the King of* Macedon, *the* Mithridatick *Herb or* Scordium *of* Mithridates *the King of* Pontus *and* Bithynia, Achillea *of* Achilles, Centory *of* Chiron *the Centaure*, Artemiſia *of* Artemiſia *the Queen of* Caria. Attalus *King of* Pergamus, Solomon *of* Judæa, Evax *of* Arabia, *and* Juba *the King of* Mauritania, *were not onely inflamed with a deſire of the knowledge of Plants; but either they have written Books of it, or for the great commodity of Poſterity, invented by their skill, many choice Antidotes compounded of divers Simples; neither the deſire of Learning this moſt noble Science is yet altogether extinct; as may appear by that* Indian *Plant* Tobacco, *called by ſome the Noble Herb,* Catharines *Herb, and* Medices *Herb, but commonly the* Queens *Herb, becauſe* Catharine Medices *the Mother of our King, by her ſingular ſtudy and induſtry made manifeſt the excellent vertue it hath in curing malign Ulcers and Wounds, which before was unknown to the* French. *For theſe worthy men underſtood that their glory, thus faſtened and ingraffed into the deep, and as it were ever-living Roots of Plants, would never decay; but ſhould be propagated to all Poſterity in many ſucceeding Ages, growing up with their ſprouting and budding Shouts, Stalks, Flowers, and Fruits. Neither did theſe famous men whileſt they adorned this part of Phyſick, ſuffer the other, which treats of the Diſſection of Mans Body, be buried in oblivion, and without their knowledge; as inſtructed with the Precepts and Learning of the Wiſeſt Men, how artificial and unimitable by mortal hand this Fabrick of our Body is. Neither is it probable that* Apis, Oſiris, *and* Ptolomy *Kings of* Egypt, Solomon, Alexander *the Great*, Mithridates, Attalus, *ſeeing they dedicated themſelves wholly to the contemplation of Natural things, neglected the uſe of Anatomy, and being men moſt deſirous to know themſelves, to have been ignorant of the ſtructure of their own Bodies, being the habitation of their Souls immortal, and made to the Image of God: ſeeing they obſerved with certain judgement the different lights of the Sun, Moon, and Stars; and paſſed over ſo many Lands, ſo many Seas, ſo many Regions, ſo far remote one from another, by ways ſo terrible by reaſon of cold, uncouthneſs, darkneſs, by rocks, by fire and ſword, with great labour, charge, and danger of life, onely that they might ſatisfie their minds thirſting after the knowledge of things; and to have left untouched a thing truly noble, admirable, and moſt worthy of knowledge, eaſie to be attained by any, and to be acquired without any danger of life or fortunes.*

Names given to Plants.

Seeing there be three parts of that Phyſick which at this time we profeſs; Chirurgery, *which by the uſe of the hand,* Diet *which with the convenient manner of feeding and ordering the body, and* Pharmacy *that by Medicins attempt to expel Diſeaſes, and preſerve Health; The prime Phyſicians do not without reaſon contend which of theſe may be accounted the chief. Certainly* Herophilus *had* Pharmacy *in ſuch eſteem, that he thought Medicins were firſt mixed and adminiſtred to the Sick by* Apollo *(whom Antiquity thought a great Deity.) And* Pliny *had ſo good an opinion of* Diet, *that he exclaims, The true Remedies and Antidotes againſt Diſeaſes, are put into the Pot and eaten every day by the poor People. Verily all learned men confeſs, that the manner of curing which which is performed by Diet, is much more facil and proſperous than that which is done by Medicins; as thoſe things which ſought with much labour and coſt are taken with much loathing, and taken are ſcarce retained, but retained they oft work with much labour and pain: Which things long ago moved* Aſclepiades *to exclude the uſe of Medicins as hurtful to the ſtomach. Yet if we will believe* Celſus, *neither of theſe parts merit the preheminence, but both of them give place to* Chirurgery. *For ſeeing that Fortune is very powerful in Diſeaſes, and the ſame Meats and Medicins are often good and often vain, truly it is hard to ſay, whether the health is recovered by the benefit of Diet and Pharmacy, or by the ſtrength of the body. Moreover in thoſe caſes in which we moſt prevail with Medicins, although the profit be moſt manifeſt, yet it is evident that health is often ſought in vain even by theſe things, and often recovered without them. As it may be perceived by ſome troubled with ſore Eyes, and others with Quartan Fevers, who having been long troubled by Phyſicians, are healed without them. But the effect of Chirurgery as it is very neceſſary, ſo it is the moſt evident amongſt all the parts of Phyſick. For who without Chirurgery can hope to cure Broken or Luxated parts, who Wounds and Ulcers, who the Falling of the Matrix, the Stone in the Bladder, a Member infeſted with a Gangrene or Sphacele? Beſides, this part alſo is the moſt antient; for* Podalirius *and* Machaon *following their General* Agamemnon *to the* Trojan *Wars, yielded no ſmall comfort to their Fellow-Souldiers. Whom notwithſtanding* Homer *affirms not to have given any help in the Peſtilence, nor in divers other Diſeaſes, but onely were accuſtomed*

Phyſick is divided into three parts.

to

The excellency of Chirurgery.

to heal Wounds by Inſtruments and Medicins. And if the difficulty of learning it argue the excellency of the Art, who can doubt but Chirurgery muſt be the moſt excellent, ſeeing that none ought to be accounted a Chirurgeon, or which can perform his duty without the knowledge of Diet *and* Pharmacy? *But both the other can perform their parts without Chirurgery, if we may believe* Galen. *But if we conſider the matter more nearly according to truth, we ſhall underſtand thoſe three parts have a certain common bond, and are very near of kindred, ſo that the one implores the aid of the other; neither can the Phyſician do any thing praiſe-worthy without the conſpiracy and joint conſent of theſe three; therefore in ancient times there was but one Performer and Uſer of all the three Parts. But the multitude of men daily increaſing, and on the contrary, Mans life decreaſing, ſo that it did not ſeem able to ſuffice for to learn and exerciſe all the three, the Workmen divided themſelves. Wherefore that which happens to any man either by lot, or counſel, that let him follow, maintain and onely uſe, as mindful how ſhort his life is, and how long the Art.*

A Table of the Books and Chapters.

Chap. 1 WHat Chirurgery is Page 1
2 Of Chirurgical Operations ib.
3 Of things Natural 2
4 Of Elements ib.
5 Of Temperaments 3
6 Of Humours 6
7 Of the Practice of the aforesaid rules of temperaments 11
8 Of the Faculties 13
9 Of the Actions 14
10 Of the Spirits 15
11 Of the Adjuncts of things Natural, 16
12 Of things Not Natural 17
13 Of the Air 18
14 Of Meat and Drink 19
15 Of Motion and Rest 21
16 Sleep and Watching 22
17 Repletion, Inanition or Emptiness 23
18 Of the perturbations or passions of the Mind 24
19 Of things against Nature, and first of the cause of a Disease 25
20 Of a Disease 26
21 Of a Symptom ib.
22 Of Indications ib.
23 Of certain wonderful and extravagant ways of curing Diseases 31
24 Of certain jugling and deceitful ways of curing 32

Book II. Of living Creatures, and of the Excellency of Man, from 34 to 49.

Book III. Treating of the Anatomy of Mans Body 50

Ch. 1 The Division or Partition of Mans Body 52
2 Of the containing parts of the Epigastrium, and the preparation to anatomical administration 56
3 Of the outmost skin or cuticle ib.
4 Of the true skin 57
5 Of the fleshy Panicle ib.
6 Of the Fat 58
7 Of the common coat of the Muscles 59
8 What a Muscle is, and the differences thereof ib.
9 Of the parts of a Muscle 61
10 A more particular inquisition into each part of a muscle 62
11 Of the Muscles of the Epigastrium, or lower belly 63
Of the white line, and Peritonæum, or rim of the belly 64
12 Of the Epiploon, Omentum, or Zirbus, i.e. the Kall 66
13 Of the Ventricle or Stomach 67
14 Of the Guts 68
15 Of the Mesentery 70
16 Of the Glandules in general, and of the Pancreas or Sweetbread 71
17 Of the Liver ib.
18 Of the Bladder of the Gall 72
19 Of the Spleen or Milt 73
20 Of the Vena Porta, and Gate-vein, and the distribution thereof ib.
21 Of the original of the Artery, and the division of the branch descending to the natural parts 74
22 Of the distribution of the Nerves to the natural parts 75
23 The manner of taking out the Guts 76
24 The orig. and distribution of the descendent hollow vein ib.
25 Of the Kidnies or Reins 77
26 Of the Spermatick Vessels 78
27 Of the Testicles or Stones ib.
28 Of the varicous bodies or parastats, and of the ejaculatory Vessels, and the glandulous or prostates 79
29 Of the Ureters 81
30 Of the Bladder 81
31 Of the Yard 82
32 Of the Spermatick Vessels and Testicles in women 83
33 Of the Womb 85
34 Of the coats containing the Infant in the Womb 87
35 Of the Navel 88

Book IV. Treating of the Vital Parts contained in the Chest.

Ch. 1 What the Thorax or the Chest is, into what parts it may be divided, and the nature of these parts pag. 89
2 Of the containing and contained parts of the Chest 90
3 Of the Brests or Dugs ib.
4 Of the Clavicles, or Collar-bones and Ribs 91
5 The anatomical administration of the Sternon 92
6 Of the Pleura, or coat investing of the Ribs ib.
7 Of the Mediastinum 93
8 Of the Diaphragma or Midriff ib.
9 Of the Lungs 94
Of the Pericardium, or purse of the Heart ib.
10 Of the Heart 95
11 Of the Orifices and Valves of the Heart 96
12 Of the distribution of the Vena Arteriosa, and the Arteria Venosa 97
13 Of the distribution of the hollow Vein 98
14 Of the distribution of the nerves or sinews of the 6 conj. 101
15 The division of the Arteries ib.
16 Of the Thumus 103
17 Of the Aspera Arteria or Weason ib.
18 Of the Gullet 105

Book V. Of the Animal parts contained in the head.

Ch. 1 A general description of the Head pag. 106
2 Of the musculous skin of the Head, (commonly called the Hairy Scalp) and of the Pericranium ib.
3 Of the Sutures 107
4 Of the Cranium or Skull 108
5 Of the Meninges, that is, the two membranes called Dura Mater and Pia Mater 109
6 Of the Brain ib.
7 Of the Ventricles and Mamill. Processes of the Brain 111
8 Of the seven conjugations of the Nerves of the Brain, so called, because they always shew the Nerve conjugated and doubled, that is, on each side one 113
9 Of the Rete Mirabile, or wonderful Net, and of the Wedg-bone 115
10 Of the holes of the inner basis of the skull 116
11 Of the perforations of the external basis of the Brain ib.
12 Of the Spinal Marrow or Pith of the Back 117

Book VI. Treating of the Muscles, and Bones, and the other extreme parts of the Body.

Ch. 1 Of the Bones of the Face pag. 118
2 Of the Teeth 119
3 Of the Broad Muscle 120
4 Of the Eye-lids and Eye-brows ib.
5 Of the Eyes 121
6 Of the Muscles, Coats, and Humours of the Eye ib.
7 Of the Nose 124
8 Of the Muscles of the Face ib.
9 Of the Muscles of the lower Jaw 125
10 Of the Ears and Parotides, or Kernels of the Ears 126
11 Of the Bone Hyoides, and the Muscles thereof 128
12 Of the Tongue ib.

13 *Of the Mouth* 129
14 *Of the Gargareon or* Uvula ib.
15 *Of the* Larinx *or Throttle* ib.
16 *Of the neck and parts thereof* 131
17 *Of the muſcles of the Neck* 133
18 *Of the muſcles of the Cheſt and Loins* 139
19 *Of the muſcles of the ſhoulder-blade* 140
20 *The deſcription of the hand taken in general* 141
21 *The deſcription of the ſubclavian vein, and firſt of the* Cephalica *or* Humeraria 142
22 *The deſcription of the axillary vein* 143
23 *The diſtribution of the axillary artery* ib.
24 *Of the Nerves of the Neck, Back, and Arm* 144
25 *The deſcription of the bone of the Arm, and the muſcles which move it* 145
26 *A deſcription of the bones of the Cubit, and the muſcles moving them* 147
27 *A deſcription of the bones of the wriſt, after-wriſt and fingers* 148
28 *Of the muſcles which ſeated in the cubit move the Wand, and with it the hand* 150
29 *Of the muſcles of the inſide of the hand* 151
30 *A deſcription of the leg taken in general* 152
31 *A deſcription of the crural Vein* ib.
32 *A deſcription of the crural Artery* 153
33 *Of the Nerves of the Loins, Holy-bone and Thigh* ib.
34 *Of the proper parts of the thigh* 154
35 *Of the muſcles moving the thigh* 156
36 *Of the bones of the leg or ſhank* 157
37 *Of the muſcles of the legs* ib.
38 *Of the bones of the foot* 158
39 *Of the muſcles moving the foot* 161
40 *Of the muſcles moving the toes of the feet* 162
41 *An Epitome or brief recital of the bones in mans body*, ib.
42 *An Epitome of the names and kinds of compoſure of the bones* 165

Book VII. Of Tumors againſt Nature in general.

Ch. 1. *What a Tumor againſt Nature, vulgarly called an Impoſtume is, and what be the differences thereof* 169
2 *Of the general cauſes of Tumors* ib.
3 *The ſigns of Impoſtumes or Tumors in general* 170
4 *Of the Prognoſticks in Impoſtumes* 171
5 *Of the general Cure of Tumors againſt Nature* ib.
6 *Of the four principal and general Tumors, and of other Impoſtumes, which may be reduced to them* 172
7 *Of a Phlegmon* ib.
8 *Of the cauſes and ſigns of a Phlegmon* 173
9 *Of the Cure of a true Phlegmon* ib.
10 *Of the Cure of an ulcerated Phlegmon* 175
11 *Of Fevers, and the cure of the Fevers which accompany a Phlegmon* 176
12 *Of an* Eryſipelas, *or Inflammation* 178
13 *Of the Cure of an* Eryſipelas 179
14 *Of the* Herpes, i.e. *Tetters or Ringworms, or ſuch like*, ib.
15 *Of Fevers which happen upon eryſipelous Tumors* 180
16 *Of an* Oedema *or cold phlegmatick Tumor* 181
17 *Of the cure of flatulent and wateriſh Tumors* 182
18 *Of the cure of a flatulent and wateriſh Tumor* 183
19 *Of an* Atheroma, Steatoma *and* Meliceris 184
20 *Of the cure of* Lupiæ, i.e. *Wens, or Ganglions* ib.
21 *Of a* Ganglion *more particularly ſo called* 185
22 *Of the* Strumæ *or* Scrophulæ, i.e. *the Kings-evil* 186
23 *Of the Fever which happens upon an œdematous tum.* 187
24 *Of* Scirrhus, *or an hard tumor proceeding of melanch.* 188
25 *Of the cure of a* Schirrus ib.
26 *Of a Cancer already generated* 189
27 *Of the cauſes, kinds and prognoſticks of a Cancer* ib.
28 *Of the cure of a Canc. beginning and not yet ulcerated*, 190
29 *Of the cure of an ulcerated Cancer* ib.
30 *Of the topick medicins to be applied to an ulcerated and not ulcerated Cancer* 191
31 *Of the Fever which happeneth in ſcirrhous Tumors* 192
32 *Of an* Aneuriſma, i.e. *the dilation or ſpringing of an Artery, Vein, or Sinew* 194

Book VIII. Of the particular Tumors againſt Nature.

Ch. 1. *Of an* Hydrocephalos, *or watery tumor which commonly affects the heads of Infants* 195
2 *Of a* Polypus, *being an eating diſeaſe in the Noſe* 196
3 *Of the* Parotides, i.e. *certain ſwellings about the Ears*, ib.
4 *Of the* Epulis, *or over-growing of the fleſh of the gums*, 197
5 *Of the* Ranula ib.
6 *Of the ſwellings of the gland or almonds of the throat*, 198
7 *Of the inflammation and relaxation in the* Uvula *or* Columella ib.
8 *Of the* Angina *or ſquinzy* 200
9 *Of the* Bronchocele, *or rupture of the throat* 201
10 *Of the Pluriſie* ib.
11 *Of the Dropſie* 202
12 *Of the cure of the dropſie* 203
13 *Of the tumor and relaxation of the Navil* 205
14 *Of the tumors of the groins and cods called* Herniæ, i. e. *Ruptures* ib.
15 *Of the cure of Ruptures* 206
16 *Of the golden ligature or the* Punctus Aureus, *as they call it* 208
17 *Of the cure of other kinds of Ruptures* 210
18 *Of the falling down of the fundament* 211
19 *Of the* Paronychiæ 212
20 *Of the ſwelling of the Knees* ib.
21 *Of the* Dracunculus 213

Book IX. Of Wounds in general.

1 *What a wound is, what the kinds and differences thereof are, and from whence they may be drawn or derived* 216
2 *Of the cauſes of wounds* ib.
3 *Of the ſigns of Wounds* 217
4 *Of prognoſticks to be made in wounds* ib.
5 *Of the cure of Wounds in general* 218
6 *Of Sutures* 219
7 *Of the flux of bloud which uſually happens in wounds* 220
8 *Of the pain which happens upon Wounds* 221
9 *Of Convulſion by reaſon of a Wound* ib.
10 *The Cure of a Convulſion* 222
11 *Of the cure of a Convulſion by ſympathy and pain* ib.
12 *Of the Palſie* 223
13 *Of the cure of the Palſie* ib.
14 *Of Swouning* 224
15 *Of* Delirium, i.e. *raving, talking idlely, or doting* 225

Book X. Of the green and bloudy Wounds of each part.

Ch. 1. *Of the kinds and differences of a broken skull* 225
2 *Of the cauſes and ſigns of a broken skull* 227
3 *Of the ſigns of a broken skull, which are manifeſt to our ſenſe* ib.
4 *Of a Fiſſure being the firſt kind of a broken skull* 228
5 *Of a Contuſion which is the ſecond part of a Fracture*, 230
6 *Of an effracture, depreſſion of the bone, being the third kind of a Fracture* 232
7 *Of a ſeat, being the fourth kind of a broken skull* 213
8 *Of a* Reſonitus *or Counterfiſſure, being the fifth kind of Fracture* 234
9 *Of the moving or concuſſion of the Brain* 235
10 *Of prognoſticks to be made in Fractures of the skull* 236
11 *Why when the Brain is hurt by a wound of the head there may follow a convulſion of the oppoſite part* 237
12 *A convulſ. of the deadly ſigns in wounds of the head*, 238
13 *Of ſalutary ſigns in wounds of the head* 239
14 *Of the general cure of a broken skull, and of the ſymptoms uſually happening thereupon* ib.

15 *Of the particular cure of wounds of the Head, and of the musculous skin* 241
16 *Of the particular cure of a fracture or broken skull* 243
17 *Why we use trepanning in the fractures of the skull* 244
18 *A description of Trepans* 245
19 *Of the places of the skull whereto you may not apply a Trepan* 247
20 *Of the corruption and* Caries, *or rottenness of the bones of the Head* 248
21 *Of the discommodities which happen to the* Crassa Meninx *by fractures of the skull* 250
22 *Of the cure of the Brain, being shaken or moved* 251
23 *Of the Wounds of the Face* 252
24 *Of the Wounds of the Eys* 253
25 *Of the Wounds of the Cheeks* 255
26 *Of the Wounds of the Nose* 256
27 *Of the Wounds of the Tongue* 257
28 *Of the Wounds of the Ears* ib.
29 *Of the Wounds of the Neck and Throat* ib.
30 *Of the Wounds of the Chest* 259
31 *Of the Cure of the Wounds of the Chest* ib.
32 *Of differences, causes, signs, and cure of an Hect. Fever,* 262
33 *Of the Wounds of the* Epigastrium, *and of the whole lower belly* 264
34 *Of the cure of wounds of the lower belly* 265
35 *Of the Wounds of the Groins, Yard, and Testicles* 266
36 *Of the Wounds of the Thigh and Legs* ib.
37 *Of the Wounds of the Nerves and nervous parts* ib.
38 *Of the cure of the wounds of the nervous parts* 267
39 *Of the wounds of the joints* 268
40 *Of the Wounds of the Ligaments* 269

Book XI. Of Wounds made by Gun-shot, other Fiery Engines, and of all sorts of Weapons. The Preface.

The first discourse wherein wounds made by Gun-shot are freed from being burnt, or cauterized according to Vigo's *method* 272
Another discourse of these things, which King Charles IX. *returning from the Expedition, and taking of* Rouen, *inquired of me concerning wounds made by Gun-shot* 273
Ch. 1. *A division of wounds drawn from the variety of the wounded parts, and the bullets which wound* 278
2 *Of the signs of wounds made by Gun-shot* ib.
3 *How these wounds must be ordered at the first dressing,* ib.
4 *A description of fit Instruments to draw forth bullets, and other strange bodies* 279
5 *What dressing must first be used, after the strange bodies are pluckt or drawn out of the wound* 281
6 *How you shall order it at the second dressing* 282
7 *By what means strange bodies left in at the first dressing, may be drawn forth* 283
8 *Of Indications to be observed in this kind of wounds* ib.
9 *What remains for the Surg. to do in this kind of wo.* 284
10 *Of Bullets which remain in the body for a long time after the wound is healed up* 285
11 *How to correct the constitutions of the air, so that the noble parts may be strengthened, and the whole body beside* ib.
12 *Certain memorable Histories* 286
13 *An Apology concerning Wounds made by Gun-shot* 287
14 *Another Apology against those who have laboured with new reasons, to prove that wounds made by Gun-shot are poisoned* 290
15 *How wounds made by Arrows differ from those made by Gunshot* 291
16 *Of the diversity of Arrows and Darts* ib.
17 *Of the difference of the wounded parts* ib.
18 *Of drawing forth Arrows* ib.
19 *How arrows broken in a wound may be drawn forth,* 292
20 *What to be done when an arrow is left fastned or sticking in a bone* 293
21 *Of poisonous wounds* ib.

Book XII. Of Contusions and Gangrenes.

Ch. 1. *Of a Contusion* pag. 293
2 *Of the general Cure of great and enormous Contusions,* 294
3 *How we must handle Contusions when they are joined with a wound* ib.
4 *Of those Contusions which are without a wound* 295
5 *By what means the contused part may be freed from the fear and imminent danger of a Gangrene* ib.
6 *Of that strange kind of Symptome which happens upon Contusions of the Ribs* 296
7 *A Discourse of* Mummia, *or Mummy* ib.
8 *Of Combustions and their differences* 297
9 *Of hot and attractive Medicins to be applied to Burns,* ib.
10 *Of a Gangrene and Mortification* 299
11 *Of the general and particular causes of a Gangrene* ib.
12 *Of the antecedent causes of a Gangrene* ib.
13 *Of the signs of a Gangrene* 300
14 *Of the Prognosticks in Gangrenes* 301
15 *Of the general Cure of a Gangrene* ib.
16 *Of the particular cure of a Gangrene* ib.
17 *The signs of a perfect* Necrosis, *or Mortification* 302
18 *Where amputation must be made* ib.
19 *How the Section or Amputation must be performed* 303
20 *How to stanch the bleeding when the member is taken off* 304
21 *How after the bloud is stanched, you must dress the wounded member* ib.
22 *How you must stop the bleeding, if any of the bound up vessels chance to get loose* ib.
23 *How to perform the residue of the Cure of the amputated member* 305
24 *What just occasion moved the Author to devise this new form of remedy, to stanch the bloud after the amputation of a member, and to forsake the common way used almost by all Chirurgeons; which is by application of actual cauteries* ib.
25 *The practice of the former precepts is declared together with a memorable History of a certain Souldier, whose arm was taken off at the elbow* 306

Book XIII. Of Ulcers, Fistulaes, and Hæmorrhoids.

Ch. 1. *Of the nature causes, and differences of Ulcers* 307
2 *Of the signs of Ulcers* 309
3 *Of the Prognosticks of Ulcers* ib.
4 *Of the general cure of Ulcers* 310
5 *Of a distempered Ulcer* 311
6 *Of an Ulcer of pain* ib.
7 *Of Ulcers, with overgrowing or proudness of flesh* 512
8 *Of an Ulcer putrid and breeding worms* ib.
9 *Of a sordid Ulcer* ib.
10 *Of a virulent and malign Ulcer, which is termed* Cacoethes, *and of a Chironian Ulcer* 313
11 *An advertisement to the young Chirurgeon touching the distance of times wherein malign Ulcers are to be dressed,* 314
12 *How to bind up Ulcers* ib.
13 *Of the cure of particular Ulcers, and first of those of the Eyes* ib.
14 *Of the* Ozæna *and Ulcers of the Nose* 315
15 *Of the Ulcers of the mouth* ib.
16 *Of the Ulcers of the Ears* 316
17 *Of the Ulcers of the Wind-pipe, Weazon, Stomach, and Guts* 317
18 *Of the Ulcers of the Kidnies and Bladder* ib.
19 *Of the Ulcers of the Womb* 318
20 *Of the Varices and their Cure by cutting* 319
21 *Of Fistulaes* ib.
22 *Of the cure of Fistulaes* 320
23 *Of the Fistulaes in the Fundament* 321
24 *Of Hæmorrhoids* ib.

A Table of the Books and Chapters.

Book XIV. Of Bandages or Ligatures.

Ch. 1 *Of the differences of Bandages* pag. 322
2 *Sheweth the Indications and general Precepts of fitting of Bandages and Ligatures.* 323
3 *Of the 3 kinds of Bondages neceſſary in Fractures* 324
4 *Of the binding up of Fract. aſſociated with a wound* 325
5 *Certain common Precepts of the binding up of Fractures and Luxations* ib.
6 *Of the Uſes for which Ligatures ſerve* ib.
7 *Of Bolſters or Compreſſes* 326
8 *Of the Uſe of Splints, Junks, and Caſes* ib.

Book XV. Of Fractures.

Ch. 1 *What a Fracture is, and the differences thereof* 327
2 *Of the ſigns of a Fracture.* ib.
3 *Prognoſticks to be made in Fractures* 328
4 *The general cure of broken and diſlocated Bones* 329
5 *By what means you may perform the third Intention in curing Fractures and diſlocations, which is the hindering and correction of Accidents and Symptoms* 330
6 *Of the Fracture of the Noſe* 331
7 *Of the fracture of the lower Jaw* ib.
8 *Of the fracture of the Clavicle or Collar-bone* 332
9 *Of the fracture of the ſhoulder-blade* ib.
10 *Of the fracture and depreſſion of the* Sternon, *or Breſt-bone* 333
11 *Of the fracture of the Ribs* ib.
12 *Of certain preternatural affects which enſue upon broken Ribs* 334
13 *Of the fracture of the* Vertebræ *or Rack-bones of the Back, and their Proceſſes* 335
14 *Of the fracture of the Holy-bone* ib.
15 *Of the fracture of the Rump* ib.
16 *Of the fracture of the Hip, or* Os Ileum 336
17 *Of a fracture of the ſhoulder or arm-bone* ib.
18 *Of the fracture of the Cubit, or Ell and Wand* ib.
19 *Of the fracture of a Hand* 337
20 *Of the fracture of a Thigh* ib.
21 *Of the fracture of the Thigh nigh to the joint, or the upper or lower head of the bone* 339
22 *Of the fract. of the* Patella, *or whirl-bone of the knee* 340
23 *Of a broken Leg* ib.
24 *Of ſomething to be obſerved in Ligation, when a Fracture is aſſociated with a wound* 341
25 *What was uſed to the Authors leg after firſt dreſſing* 342
26 *What may be the cauſe of the convulſive twitchings of broken members* 343
27 *Certain documents concerning the parts whereon the Patient muſt neceſſarily reſt whileſt he lies in his bed* ib.
28 *By what means we may know the* Callus *is breeding* 344
29 *Of thoſe things that may hinder the generation of a* Callus, *and how to correct the fault thereof, if it be ill-formed* 345
30 *Of Fomentations which be uſed in broken bones* 346
31 *Of the fractures of the bones in the Feet* ib.

Book XVI. Of Diſlocations or Luxations.

Ch. 1 *Of the kinds and manners of Diſlocations* 346
2 *Of the differences of Diſlocations* 347
3 *Of the cauſes of Diſlocations* ib.
4 *The ſigns of Diſlocations* ib.
5 *Of Prognoſticks to be made upon Luxations* 348
6 *Of the general cure of Diſlocations* 349
7 *The deſcription of certain Engins ſerving for the reſtoring of Diſlocations* ib.
8 *Of the diſlocation of the Jaw-bone* 351
9 *How to ſet the Jaw diſlocated forwards on both ſides* ib.
10 *Of reſtoring the Jaw diſloc. forwards but on one ſide* ib.
11 *Of the luxation of the Collar-bone* 352
12 *Of the luxation of the Spine, or Back-bone* ib.
13 *Of the diſlocation of the Head* 353
14 *Of the diſloc. of the* Vertebræ *or rack-bones of the neck* ib.
15 *Of the diſlocated* Vertebræ *of the Back* ib.
16 *How to reſtore the Spine outwardly diſlocated* 354
17 *A more particular inquiry of the diſlocation of the* Vertebræ, *proceeding from an internal cauſe* ib.
18 *Prognoſticks of the diſlocated* Vertebræ *of the back* 355
19 *Of the diſlocation of the Rump* ib.
20 *Of the luxation of the Ribs* ib.
21 *Of a diſlocated ſhoulder* 356
22 *Of the firſt manner of ſetting a ſhoulder, which is with ones Fiſt* ib.
23 *Of the ſecond manner of reſtoring a ſhoulder, that is, with the Heel, when as the Patient by reaſon of pain can neither ſit nor ſtand* 357
24 *Of the third manner of reſtoring a ſhoulder* 358
25 *Of the fourth manner of reſtoring a diſlocated ſhoulder* ib.
26 *Of the fifth manner of putting the ſhoulder into joint, which is performed by a Ladder* 359
27 *The ſixth manner of reſtoring a ſhoulder luxated into the arm-pit* 360
28 *How to reſtore a ſhoulder diſlocated forwards* 361
29 *Of the ſhoulder luxated outwardly* 362
30 *Of the ſhoulder diſlocated upwards* ib.
31 *Of the diſlocation of the Elbow* 363
32 *How to reſtore the Elbow, diſlocated outwardly* ib.
33 *Of the diſlocation of the Elbow to the inſide, and of a compleat and uncompleat luxation* 364
34 *Of the diſlocation of the* Styliformis *or Bodkin-like proceſs of the Cubit or Ell* 365
35 *Of the diſlocation of the Wriſt* ib.
36 *Of the diſlocated bones of the Wriſt* ib.
37 *Of the diſlocated bones of the after-wriſt* ib.
38 *Of the diſlocated Finger* 366
39 *Of a diſlocated Thigh or Hip* ib.
40 *Prognoſticks belonging to a diſlocated Hip* ib.
41 *Of the ſigns of the Hip diſloc. outwardly or inwardly* 367
42 *Of the Thigh-bone diſlocated forwards* 368
43 *Of the Thigh-bone diſlocated backwards* ib.
44 *Of reſtoring the Thigh-bone diſlocated inwards* 369
45 *Of reſtoring the Thigh diſlocated outwardly* 370
46 *Of reſtoring the Thigh diſlocated forwards* ib.
47 *Of reſtoring the Thigh diſlocated backwards* ib.
48 *Of the diſlocation of the whirl-bone of the knee* 371
49 *Of the diſlocated Knee* ib.
50 *Of a Knee diſlocated forwards* ib.
51 *Of the ſeparation of the greater and leſſer focil* 372
52 *Of the Leg-bone or greater focil diſlocated, and divided from the paſtern-bone* ib.
53 *Of the diſlocation of the Heel* ib.
54 *Of the Symptoms which follow upon the contuſion of the Heel* ib.
55 *Of the diſlocated Paſtern, or Ankle-bone* 373
56 *Of the diſlocation of the Inſtep and back of the foot* ib.
57 *Of the diſlocation of the Toes* ib.
58 *Of the Symptoms and accidents which may befal a broken or diſlocated member* ib.

Book XVII. Of divers other preternatural affects whoſe cure is commonly performed by Surgery.

Ch. 1 *Of an* Alopecia, *or the falling away of the hairs of the Head.* pag. 374
2 *Of the* Tinea *or Scald-head* 375
3 *Of the* Vertigo, *or giddineſs* 376
4 *Of the* Hemicrania *or Meagrim* ib.
5 *Of certain affects of the Eyes, and firſt of ſtaying up the upper Eye-lid when it is too lax* 377
6 *Of* Lagopthalmus, *or the Hare-eye* ib.
7 *Of the* Chalazion *or Hail-ſtone, and the* Hordeolum *or Barley-corn of the Eye-lids* 378

8 *Of the* Hydatis, *or fatneſs of the Eye-lids* ib.
9 *Of the Eye-lids faſtned or glewed together* ib.
10 *Of the itching of the Eye-lids* 379
11 *Of* Lippitudo, *or blear-eyes* ib.
12 *Of the* Opthalmia, *or inflammation of the Eyes* ib.
13 *Of the* Proptoſis, *that is, the falling or the ſtarting forth of the Eye, and of the* Pthiſis *and* Camoſis *of the ſame* 380
14 *Of the* Ungula *or* Web 381
15 *Of the* Ægilops, Fiſtula lacrymoſa, *or weeping Fiſtula of the Eye* 382
16 *Of the* Staphyloma, *or Grape-like ſwelling* ib.
17 *Of the* Hypopion, i.e. *the ſuppurate or putrid Eye* 383
18 *Of the* Mydriaſis, *or dilation of the pupil of the Eye* ib.
19 *Of a Cataract* ib.
20 *Of the Phyſical cure of a beginning Cataract* 384
21 *By what ſigns ripe and curable Cataracts may be diſcovered from unripe and uncurable ones* ib.
22 *Of the couching a Cataract* 385
23 *Of the ſtopping of the paſſage of the Ears, and of the falling of things thereinto* 386
24 *Of getting little bones and ſuch like things out of the Jaws and Throat* ib.
25 *Of the Tooth-ach* ib.
26 *Of other affects of the Teeth* 387
27 *Of drawing of Teeth* 388
28 *Of cleanſing of Teeth* 389
29 *Of the impediment and contraction of the Tongue* 390
30 *Of ſuperfluous Fingers, and ſuch as ſtick together* ib.
31 *Of too ſhort a prepuce, and of ſuch as have been circumciſed* 391
32 *Of* Phimoſis *and* Paraphimoſis, *that is ſo great a conſtriction of the Prepuce about the Glans or Nut, that it cannot be bared or uncovered at pleaſure* ib.
33 *Of thoſe whoſe Glans is not rightly perforated, and of the too ſhort or too ſtrait ligament, bridle, or cord of the Yard* ib.
34 *Of the Cauſes of the Stone* 392
35 *Of the ſigns of the Stone in the Kidnies and Bladder* ib.
36 *Prognoſticks in the Stone* 393
37 *What cure is to be uſed when we fear the Stone* 394
38 *What is to be done when the Stone falleth out of the Kidney into the Ureter* 395
39 *What muſt be done, the Stone being fallen into the neck of the bladder* 396
40 *What courſe muſt be taken, if the Stone ſticking in the* Ureter, *or Urinary paſſage, cannot be gotten out by the forementioned Art* 397
41 *What manner of Section is to be made, when a Stone is in a Boys bladder* 397
42 *How to cut Men for the taking out of the Stone in the bladder* 398
43 *What cure muſt be uſed to the wound when the Stone is taken forth* 402
44 *How to lay the Patient after the Stone is taken away* 403
45 *How to cure the wound made by the inciſion* ib.
46 *What cure is to be uſed to Ulcers, when as the Urin flows through them long after the Stone is drawn out* ib.
47 *How to take Stones out of Womens bladders* 404
48 *Of the ſuppreſſion of the Urin by internal cauſes* 405
49 *A digreſſion concerning the purging of ſuch as are unprofitable in the whole body by the Urin* ib.
50 *By what external cauſes the Urin is ſuppreſt, and prognoſticks concerning the ſuppreſſion thereof* 406
51 *Of bloudy Urin* ib.
52 *Of the ſigns of the ulcerated Kidnies* ib.
53 *Of the ſigns of the ulcerated Bladder* 407
54 *Prognoſticks of the ulcerated Reins and Bladder* ib.
55 *What cure muſt be uſed in the ſuppreſſion of the Urin* ib.
56 *Of the* Diabete, *or inability to hold the Urin* 408
57 *Of the Strangury* ib.
58 *Of the Colick* 409
59 *Of Phlebotomy, or Blood-letting* 411
60 *How to open a Vein or draw bloud from thence* 412
61 *Of Cupping-glaſſes or* Ventoſes ib.
62 *Of Leeches, and their Uſe* 414

Book XVIII. Of the Gout.

Ch. 1 *Of the deſcription of the Gout* 414
2 *Of the occult Cauſes of the Gout* ib.
3 *Of the manifeſt Cauſes of the Gout* 416
4 *Out of what part the matter of the Gout may flow down upon the joints* ib.
5 *The ſigns of the Arthritick humour flowing from the brain* 417
6 *The ſigns of a gouty humour proceeding from the Liver* ib.
7 *By what ſigns we may underſtand this or that humour to accompany the Gout in malignity* ib.
8 *Prognoſticks in the Gout* ib.
9 *The general method of preventing and curing the Gout,* 418
10 *Of Vomiting* 419
11 *The other general remedies for the Gout* 420
12 *What Diet is convenient for ſuch as have the Gout* 421
13 *How to ſtrengthen the joints* ib.
14 *Of the palliative cure of the Gout, and the material Cauſes thereof* 422
15 *Of local Medicins that may be uſed to a cold Gout* 423
16 *Of local Medicins to be applied to a hot or ſanguine Gout* 424
17 *Of local Medicins for a cholerick Gout* 425
18 *What remedies muſt be uſed in pains of the joints proceeding of a diſtemper onely, without matter* 426
19 *What is to be done after the fit of the Gout is over* 427
20 *Of the* Tophi, *or knots which grow at the joints of ſuch as are troubled with the Gout* ib.
21 *Of the flatulencies contained in the joints, and counterfeiting true Gouts, and of remedies to be uſed thereto* 428
22 *Of the* Iſchias, *Hip-gout, or* Sciatica ib.
23 *The Cure of the* Sciatica 429
24 *Of the flatulent Convulſion, or convulſive Contraction, which is commonly called by the* French *Gout-Cramp, and by the* Engliſh *the Cramp* 430

Book XIX.

Ch. 1 *Of the* Lues Venerea, *and thoſe ſymptoms which happen by the means thereof* 430
2 *Of the Cauſes of the* Lues Venerea 431
3 *In what humour the malignity of the* Lues Venerea *reſides* 432
4 *Of the ſigns of the* Lues Venerea ib.
5 *Of Prognoſticks* 433
6 *How many, and by what means there are to oppugn this diſeaſe* ib.
7 *How to make choice of the wood* Guaiacum ib.
8 *Of the preparation of the decoction of* Guaiacum 434
9 *Of the ſecond manner of curing the* Lues Venerea, *which is performed by friction or unction* 435
10 *Of the choice preparation and mixing of* Hydrargyrum, ib.
11 *How to uſe the Unction* 436
12 *What cautions to be uſed in rubbing or anointing the Patient* ib.
13 *Of the third manner of Cure, which is performed by Cerates and Emplaſters, as ſubſtitutes of Unctions* 436
14 *Of the fourth manner of curing the* Lues Venerea 437
15 *Of the cure of the ſymptoms, or ſymptomatick affects of the* Lues Venerea, *and firſt of the Ulcers of the Yard* ib.
16 *How a Gonorrhœa differeth from a virulent ſtrangury,* 440
17 *Of the cauſes and difference of the ſcalding or ſharpneſs of the Urin* ib.
18 *Prognoſticks in a virulent Strangury* 441
19 *The chief heads of curing a Gonorrhœa* ib.
20 *The general cure both of the ſcalding of the water, and the virulent Strangury* ib.
21 *Of the proper Cure of a virulent Strangury* 442

22 *Of Caruncles, or fleshy excrescences which sometimes happen to grow in the* Urethra *by the heat or scalding of the Urin* 443
23 *What of the Remedies shall be used to Caruncles occasioned by the* Lues Venerea 444
24 *Of Venereal* Buboes, *or swellings in the groins,* 445
25 *Of the* exostosis, *bunches, or knots growing upon the bones, by reason of the* Lues Venerea 446
26 *Why the bones become rotten, and by what means it may be perceived* ib.
27 *Of actual and potential cauteries* 447
28 *Of the Vulnerary potion* 450
29 *Of Tetters, Ring-worms, or Chops, occasioned by the* Lues Venerea ib.
30 *Of curing the* Lues Venerea *in Infants and little children* 451

Book XX. Of the Small Pox and Meazles; as also of Worms and the Leprosie, *from pag.* 45 . *to pag.* 463.

Book XXI. Of Poisons and of the biting and stinging of a mad Dog, and the bitings and stingings of other venomous Creatures, *from pag.* 463. *to pag.* 490.

Book XXII. Of the Plague.

Ch. 1. *The description of the Plague* Pag. 490
2 *Of the Divine causes of an extraordinary Plague* ib.
3 *Of the Natural causes of the Plague* 491
4 *Of the preparation of humours to putrefaction, and admission of pestiferous impressions* 492
5 *What signs in the Air and Earth prognost. a Plague* ib.
6 *By using what cautions in Air and Diet, one may prevent the Plague* 493
7 *Of the cordial remedies by which we may preserve our bodies in fear of the Plague, and cure those already infected therewith* 494
8 *Of local Medicins to be applied outwardly* 496
9 *Of other things to be observed for prevention, in fear of the Plague* 497
10 *Of the office of Magistrates in time of the Plague* 498
11 *What caution must be used in choosing Physicians, Apothecaries, and Surgeons, who may have care of such as are taken with the Plague* 499
12 *How such as undertake the cure of the Plague ought to arm themselves* ib.
13 *Of the signs of such as are infected with the Plague* 500
14 *What signs in the Plague are mortal* ib.
15 *Signs of the Plague coming by contagion of the Air without any fault of the humours* 501
16 *Signs of the Plague drawn into the body by the fault and putrefaction of humours* ib.
17 *Of the Prognostication that is to be instituted in the Plague* 502
18 *How a pestilent Fever comes to be bred in us* 503
19 *Into what place the Patient ought to betake himself so soon as he finds himself infected* ib.
20 *What Diet ought to be observed, and first of the choice of meat,* 504
21 *What drink the Patient infected ought to use* 506
22 *Of Antidotes to be used in the Plague* 507
23 *Of Epithems to be used for the strengthening of the principal parts* 508
24 *Whether Purging and Bloud-letting be necessary in the beginning of Pestilent Diseases* ib.
25 *Of purging Medicins in a pestilent Disease* 510
26 *Of many Symptoms which happen together with the Plague, and first of the pain of the Head* 511
27 *Of the heat of the Kidnies* 512
28 *Of the eruptions and spots, which commonly are called by the name of Purples or Tokens* ib.
29 *Of the Cure of Eruptions and Spots* 513
30 *Of a pestilent* Bubo *or Plague-sore* 513
31 *Of the Cure of* Buboes *or Plague-sores* 514
32 *Of the nature, causes, and signs of a pestilent carbuncle* 516
33 *What prognosticks may be made in pestilent* Buboes *or Carbuncles* ib.
34 *Of the cure of a pestilent Carbuncle* 518
35 *Of the itching and inflammation happening in pestilent Ulcers, and how to cicatrize them* ib.
36 *Of sundry kinds of evacuations, and first of Sweating and Vomiting* 519
37 *Of Spitting, Salivation, Sneezing, Belching, Hicketting, and making Water* 520
38 *Of the Menstrual and Hæmorrhoidal Purgation* ib.
39 *Of procuring evacuation by stool, or a flux of the belly* 521
40 *Of stopping the flux of the belly* 522
41 *Of evacuation by insensible transpiration* 523
42 *How to cure Infants and Children taken with the Plague* ib.

Book XXIII. Of the means and manner to repair or supply the defects of Mans Body.

Ch. 1. *How the loss of the natural or true Eye may be covered, hidden, or shadowed* 524
2 *By what means a part of the nose that is cut off, may be restored; or how instead of the nose that is cut off, another counterfeit nose may be fastned or placed on* 525
3 *Of the placing of Teeth artificially made, instead of those that are lost or wanting* 526
4 *Of filling the hollowness of the palat* 527
5 *How to help such as cannot speak by reason of the loss of some part of the Tongue* ib.
6 *Of covering and repairing certain defects or defaults in the Face* 528
7 *Of the defects of the Ears* ib.
8 *Of amending the deformity of such as are crook-backt* ib.
9 *How to relieve such as have their Urin flow from them against their wills; and such as want their Yard* 529
10 *By what means the perished function or action of a thumb or finger may be corrected and amended* 530
11 *Of the helping those that are* Vari *or* Valgi, *crook-legg'd, or crook-footed inwards, or outwards* 531
12 *By what means arms, legs, and hands may be made by Art, and placed in the stead of natural arms, legs, or hands, that are cut off and lost* 532
13 *Of amending or helping lameness or halting* 533

Book XXIV. Of the Generation of Man.

Ch. 1. *Why the generative parts are endued with great pleasure* pag. 534.
2 *Of what quality the seed is, whereof the male, and whereof the female is engendered* 535
3 *What is the cause why females of all brute Brests, being great with young, do neither desire nor admit the males, until they have brought forth their young* 536
4 *What things ought to be observed, as necessary unto Generation in the time of copulation* ib.
5 *By what signs it may be known, whether the Woman have conceived or not* 537
6 *That the Womb so soon as it hath received the seed, is presently contracted or drawn together* ib.
7 *Of the generation of the Navel* 540
8 *Of the Umbilical vessels, or the vessels belonging to the Navel* ib.
9 *Of the ebullition or swelling of the seed in the Womb, and of the concretion of the bubbles or bladders, or the three principal entrails* 541
10 *Of the third bubble or bladder, wherein the head and the brain is formed* ib.
11 *Of the Life or Soul* 542

12 *Of*

12 *Of the natural excrements in general, and ſpecially of thoſe that the Child or Infant being in the Womb excludeth* 543
13 *With what travel the Child is brought into the World, and of the cauſe of this travail* 544
14 *Of the ſituation of the Infant in the Womb* ib.
15 *Which is the legitimate and natural, and which the illegitimate or unnatural time of child-birth* 545
16 *Signs of the birth at hand* 546
17 *What is to be done preſently after the Child is born* 547
18 *How to pull away the Secundine or after-birth* 548
19 *What things muſt be given to the Infant by the mouth, before he be permitted to ſuck the Teat or Dug* 550
20 *That Mothers ought to give ſuck to their own children,* ib.
21 *Of the choice of Nurſes* ib.
22 *What Diet the Nurſe ought to uſe, and in what ſituation ſhe ought to place the Infant in the Cradle* 552
23 *How to make Pap for Children* 553
24 *Of the weaning of Children* 554
25 *By what Signs it may be known whether the Child in the womb be dead or alive* ib.
26 *Of the Chirurgical extractions of the Child from the womb either dead or alive* 555
27 *What muſt be done unto the Woman in travail, preſently after her deliverance* 557
28 *What care muſt be uſed to the Dugs and Teats of thoſe that are brought to bed* 558
29 *What the cauſes of difficult and painful travail in child-birth are* 559
30 *The cauſe of abortion or untimely birth* ib.
31 *How to preſerve the Infant in the womb when the mother is dead* 560
32 *Of ſuperfœtation* 561
33 *Of the Tumor called* Mola, *or a Mole growing in the womb of Women* 562
34 *How to diſcern true conception from a falſe conception, or* Mola ib.
35 *What cure muſt be uſed to the* Mola 564
36 *Of Tumors or ſwellings happening to the* Pancreas *or Sweet-bread, and the whole Meſentery* 565
37 *Of the cauſe of barrenneſs in Women* 566
38 *Of the barrenneſs or unfruitfulneſs of Women* 567
39 *The ſigns of a diſtempered womb* ib.
40 *Of the falling down, or perverſion, or turning of the womb* 568
41 *The cure of the falling down of the womb* 569
42 *Of the tunicle or membrane called* Hymen 570
43 *A memorable hiſtory of the membrane called* Hymen, 571
44 *Of the ſtrangulation of the womb* 572
45 *The ſigns of imminent ſtrangulation of the womb* 573
46 *How to know whether the Woman be dead in the ſtrangulation of the womb, or not* ib.
47 *How to know whether the ſtrangulation of the womb comes of the ſuppreſſion of the Flowers, or the corruption of the Seed* ib.
48 *Of the cure of the ſtrangulation of the womb* 574
49 *Of womens monethly Flux or Courſes* 575
50 *The cauſes of Womens monethly Flux or Courſes* 576
51 *The cauſes of the ſuppreſſion of the Courſes or menſtrual Flux* 377
52 *What accidents follow the ſuppreſſion or ſtopping of the monethly Flux and Flowers* ib.
53 *Of provoking the Flowers or Courſes* ib.
54 *Of the ſigns of the approaching of the menſtr. Flux* 578
55 *Accidents follow immoderate fluxes of the Flowers or Courſes* 579
56 *Of ſtopping the immoderate flowing of the Flowers and Courſes* ib.
57 *Of local Medicins to be uſed againſt the immoderate flowing of the Courſes* ib.
58 *Of womens Fluxes, or the Whites* 580
59 *Of the cauſes of the Whites* 580
60 *The cure of the Whites* ib.
61 *Of the* Hæmorrhoides *and Warts of the Neck of the womb* 581
62 *Of the cure of the Warts that are in the Neck of the womb* 582
63 *Of Chaps, and thoſe wrinkled and hard Excreſcences, which the* Greeks *call* Condylomata 583
64 *Of the itching of the womb* ib.
65 *Of the relaxation of the great Gut, or inteſtine, which happeneth to women* ib.
66 *Of the relaxation of the Navel in Children* 584
67 *Of the pain that Children have in breeding of Teeth* ib.

Book XXV. Of Monſters and Prodigies; from pag. 585, to pag. 628.

Book XXVI. Of the Faculties of Simple Medicins, as alſo of their Compoſition and Uſe.

Ch. 1. *What a Medicin is, and how it differeth from nouriſhment* pag. 629
2 *The differences of Medicins in their matter and ſubſtance* ib.
3 *The difference of Simples in their qualities and effects,* 630
4 *Of the ſecond Faculties of Medicins* 631
5 *Of the third Faculties of Medicins* ib.
6 *Of the fourth Faculty of Medicins* 632
7 *Of Taſtes* ib.
8 *Of the preparation of Medicins* 634
9 *Of repelling or repercuſſive Medicins* ib.
10 *Of attractive Medicins* 635
11 *Of reſolving Medicins* 636
12 *Of Suppuratives* ib.
13 *Of mollifying things* 637
14 *Of deterſives, or mundificatives* 638
15 *Of Sarcoticks* ib.
16 *Of Epuloticks, or skinning Medicins* 639
17 *Of Agglutinatives* ib.
18 *Of Pyroticks, or Cauſtick Medicins* 640
19 *Of Anodynes, or ſuch as mitigate or aſſwage pain* ib.
20 *Of the Compoſition and Uſe of Medicins* 641
21 *Of the Weights and Meaſures, and the notes of both of them* ib.
22 *Of Clyſters* 642
23 *Of Suppoſitories, Nodules, and Peſſaries* 644
24 *Of Oils* 645
25 *Of Liniments* ib.
26 *Of Ointments* ib.
27 *Of Cerats and Emplaſters* 647
28 *Of Cataplaſms and Pultiſes* 649
29 *Of Fomentations* 650
30 *Of Embrocations* ib.
31 *Of Epithemes* 651
32 *Of Potential Cauteries* ib.
33 *Of Veſicatories* 652
34 *Of* Collyria 653
35 *Of Errhines, and Sternutatories* ib.
36 *Of Apophlegmatiſms, or Maſticatories* 654
37 *Of Gargariſms* ib.
38 *Of Dentifrices* 655
39 *Of Bags or Quilts* ib.
40 *Of Fumigations* 656
41 *Of a Particular, or Half-bath* ib.
42 *Of Baths* 657
43 *Of Stoves or Hot-houſes* 659
44 *Of* Fuci, i.e. *Waſhes and ſuch things for the ſmoothing and beautifying of the skin* 660
45 *Of the* gutta roſacea, *or a fiery Face* 661
46 *To black or colour the Hair* 662
47 *Of* Pſilothra, *or Depilatories, and alſo of ſweet waters,* ib.

Of

Book XXVII. Of Distillation.

Ch. 1. *What Distillation is, and how many kinds thereof there be* 663
2 *Of the matter and form of Fornaces* 664
3 *Of Vessels fit for Distillation* ib.
4 *What things are to be considered in Distillation* ib.
5 *Of what fashion the Vessels for the distilling of Waters ought to be* 665
6 *How the Materials must be prepared before Distillation* 667
7 *Of the Art of Distilling of Waters* ib.
8 *How to distil* Aqua Vitæ, *or the Spirits of Wine* 668
9 *Of the manner of rectifying, that is, how to increase the strength of Waters that have been once distilled* 669
10 *Of Distillation by Filtring* ib.
11 *What, and how many ways there are to make Oils* 670
12 *Of extracting of oils of Vegetables by Distillation* ib.
13 *Another manner how to draw the essence and spirits of Herbs, Flowers, Seeds, and Spices, as also of Rhubarb, Agarick, Turbith, Hermodactyls, and other Purgers* 671
14 *How to extract oil out of Gums, condensed Juices, and Rosins, as also out of some Woods* 672
15 *Of Extracting of Oils out of the harder sorts of Gums, as Myrrh, Mastich, Frankincense, and the like* 673
16 *The making of oil of Vitriol* ib.
17 *A Table or Catalogue of Medicins and Instruments serving for the Cure of Diseases* 674

Book XXVIII. How to make Reports, and to Embalm the Dead.

Book XXIX. A Treatise concerning divers Voyages.

A Table of the Contents of the Three Tracts.

Tr. 1. *Reckons up the branches or propagations of the* Vena porta, *or the Gate-vein, and explains an Aphorism of* Hippocrates, *that makes very much to the purpose* pag. 1
2 *Treats of the superiour, or ascendent Trunk of the* Vena cava *or Hollow vein, and the branches which it scatters through the head* 4
3 *Shews how the axillary vein is distributed through the arm* 8
4 *Explains the lower, or descendent Trunk of the hollow vein* 9
5 *Reckons up the propagations and branches of the outer Iliacal branch disseminated through the* crus, *or great foot, that reaches from the lower part of the buttock to the end of the toes* 12
An Explanation of the Table of the Veins. 14

Tract. II. Concerning the Arteries.

Tract. 1. *Shews the upper or ascendent Trunk of the great Artery, with its propagations that are distributed through the head* 19
2 *Declares the History of the axillary Artery being distributed through the arm* 21
3 *Shews the inferiour or descendent Trunk of the great Artery, and the propagation thereof through the middle and lowest bellies* ib.
4 *The propagations of the outer Iliacal branches which are distributed through the* crus *or great foot, containing the thigh, leg, and foot* 26
An Explanation of the Table of the Arteries 27

Tract. III. Concerning the Nerves.

Tract. 1. *Of the Nerves of the Brain* 31
2 *Concerning the Nerves of the spinal Marrow properly so called, and first of those of the Rack-bones of the neck* 35
3 *Concerning the Nerves of the Marrow of the Rack-bones of the Chest* 37
4 *Concerning the Marrow of the Rack-bones of the Loins* 38
5 *Concerning the Nerves of the Marrow of* Os sacrum, *or the great bone* ib.
6 *Concerning the Nerves which are distributed through the arms* 39
7 *Of the Nerves that are distributed through the* crura *or thighs, legs, and feet* 40
An Explanation of the Two Tables of the Nerves 43

AN

AN *INTRODUCTION* or *Compendious Way* TO CHIRURGERY.

Book I.

CHAP. I.

What Chirurgery is.

CHIRURGERY is an Art, which teacheth the way by reaſon, how by the operation of the hand we may cure, prevent and mitigate Diſeaſes, which accidentally happen unto us. Others have thought good to deſcribe it otherwiſe; as, That it is that part of Phyſic which undertaketh the cure of Diſeaſes by the ſole induſtry of the Hand: as by cutting, burning, ſawing off, uniting fractures, reſtoring diſlocations, and performing other works, of which we ſhall hereafter treat. Chirurgery alſo is thus defined by the Author of the *Medicinal Definitions*; The quick motion of an intrepid hand joined with experience; or, An artificial action by the hand uſed in Phyſic, for ſome convenient intent. Yet none muſt think to attain to any perfection in this Art, without the help of the other two parts of Phyſic; I ſay, of Diet and Pharmacy, and the diverſe applications of proper Medicines, reſpecting the condition of the Cauſes, Diſeaſes, Symptoms, and the like Circumſtances, which comprehended under the names of things natural, not natural and beſide nature, (as they commonly call them) we intend to deſcribe in their proper place. But if any reply, that there be many which do the works of Chirurgery, without any knowledge of ſuch like things, who notwithſtanding have cured deſperate Diſeaſes with happy ſucceſs: Let them take this for an anſwer, That ſuch things happen rather by chance, than by the induſtry of the Art; and that they are not provident that commit themſelves to ſuch. Becauſe that for ſome one happy chance, a thouſand dangerous errors happen afterwards, as *Galen* (in divers places of his Method) ſpeaks againſt the Empirics. Wherefore ſeeing we have ſet down Chirurgery to be, A diligent Operation of the hands, ſtrengthned by the aſſiſtance of Diet and Pharmacy, we will now ſhew what, and of what nature the operations of it are.

The Definition of Chirurgery.

What neceſſary for a Chirurgeon.

CHAP. II.

Of Chirurgical Operations.

FIve things are proper to the duty of a Chirurgeon; To take away that which is ſuperfluous; to reſtore to their places ſuch things as are diſplaced; to ſeparate thoſe things which are joined together; to join thoſe that are ſeparated; and to ſupply the defects of nature. Thou ſhalt far more eaſily and happily attain to the knowledg of theſe things by long uſe and much exerciſe, than by much reading of Books, or daily hearing of Teachers. For ſpeech, how perſpicuous and elegant ſoever it be, cannot ſo lively expreſs any thing, as that which is ſubjected to the faithful eyes and hands.

The nature of a Chirurgeon. Experience more neceſſary for a Chirurgeon than Art.

We have examples of taking away that which abounds, in the Amputation or cutting off a finger, if any have ſix on one hand, or any other monſtrous member that may grow out; in the lopping off a putrefied part inwardly corrupted; in the extraction of a dead child, the ſecondine, mole or ſuch like bodies out of a womans womb: In taking down of all Tumors, as Wens, Warts, Polypus, Cancers and fleſhy excreſcences of the like nature; in the pulling forth of bullets, of pieces of mail, of darts, arrows, ſhells, ſplinters, and of all kind of weapons in what part of the body ſoever they be. And he taketh away that which redounds, which plucks away the hairs of the eye-lids which trouble the eye by their turning in towards it: who cuts away the web, poſſeſſing all the **Adnata*, and the part of the **Cornea*: who letteth forth ſuppurated matter: who taketh out ſtones in what part ſoever of the body they grow; who pulls out a rotten or otherwiſe hurtful tooth; or cuts a nail that runs into the fleſh; who cuts away part of the *Uvula*, or hairs that grow on the eye-lids: who taketh off a Cataract; who cuts the navil or foreskin of a child newly born; or the skinny caruncles of womens privities.

Examples of taking away that which is ſuperfluous.

*Two tunicles of the eyes.

Examples of placing thoſe things which are out of their natural ſite, are manifeſt in reſtoring diſlocated bones; in re-placing of the guts and gall fallen into the cods, or out of the navil or belly by a wound; or of the falling down of the womb, fundament or great gut, or the eye hanging out of its circle or proper place.

Examples of re-placing.

But we may take examples of disjoining thoſe things which are continued; from the fingers growing together, either by ſome chance, as burning; or by the imbecillity of the forming faculty; by the disjunction of the membrane called *Hymen*, or any other troubling the neck of the womb; by diſſection

Example of ſeparating things joined together.

ction of the ligament of the tongue, which hinders children from ſucking and ſpeaking, and of that which hinders the *Glans* from being uncovered of the foreskin; by the diviſion of a various vein, or of a half-cut nerve or tendon, cauſing Convulſion, by the diviſion of the membrane ſtopping the auditory paſſage, the noſe, mouth or fundament, or the ſtubborn ſticking together of the hairs of the eye-lids. Refer to this place all the works done by Cauſtics, the Saw, Trepan, Lancet, Cupping-glaſſes, Inciſion-knife, Leeches, either for evacuation, derivation or revulſion ſake.

Examples of uniting things disjoined.

The Chirurgeon draws together things ſeparated, which healeth wounds by ſtitching them, by bolſtring, binding, giving reſt to, and fit placing the part: which repairs fractures, reſtoring luxated parts: who by binding the veſſel, ſtayeth the violent effuſion of blood: who cicatriceth cloven lips, commonly called Hare-lips: who reduceth to equality the cavities of Ulcers and Fiſtula's.

Examples of ſupplying defects.

But he repairs thoſe things which are defective either from the infancy or afterwards by accident, as much as Art and Nature will ſuffer; who ſets on an ear, an eye, a noſe, one or more teeth; who fills the hollowneſs of the palat eaten by the Pox, with a thin plate of gold or ſilver, or ſuch like; who ſupplies the defect of the tongue in part cut off, by ſome new addition: who faſtens to a hand, an arm, or leg with fit ligaments, workman-like: who fits a doublet bombaſted, or made with iron plates to make the body ſtreight; who fills a ſhoo too big with cork, or faſtens a ſtockin or ſock to a lame mans girdle to help his gate. We will treat more fully of all theſe in our following Work. But in performing thoſe things with the hands, we cannot but cauſe pain: (for who can without pain cut off an arm or leg, or divide and tear aſunder the neck of the bladder, reſtore bones put out of their places, open ulcers, bind up wounds, and apply cauteries, and do ſuch like?) notwithſtanding the matter often comes to that paſs, that unleſs we uſe a judicious hand, we muſt either die, or lead the remnant of our lives in perpetual miſery. Who therefore can juſtly abhor a Chirurgeon for this, or accuſe him of cruelty? or deſire they may be ſerved as in antient times the *Romans* ſerved *Archagatus*, who at the firſt made him free of the City; but preſently after, becauſe he did ſomewhat too cruelly burn, cut, and perform the other works of a good Chirurgeon, they drew him from his houſe into *Campus Martius*, and there ſtoned him to death, as we read it recorded by *Sextus Cheronæus*, *Plutarch*'s nephew by his daughter. Truly, it was an inhumane kind of ingratitude, ſo cruelly to murder a man intent to the works of ſo neceſſary an Art. But the Senate could not approve the act; wherefore to expiate the crime as well as then they could, they made his Statue in Gold, placed it in *Æſculapius* his Temple, and dedicated it to his perpetual memory. For my part, I very well like that ſaying of *Celſus*: A Chirurgeon muſt have a ſtrong, ſtable and intrepid hand, and a mind reſolute and mercileſs; ſo that to heal him he taketh in hand, he be not moved to make more haſte than the thing requires; or to cut leſs than is needful; but which doth all things as if he were nothing affected with their cries; not giving heed to the judgment of the vain common people, who ſpeak ill of Chirurgeons becauſe of their ignorance.

Archagatus the Chirurgeon.

In Præf. l. 7. The properties of a good Chirurgeon.

CHAP. III.
Of things Natural.

THat the Chirurgeon may rightly and according to Art perform the foreſaid works, he muſt ſet before his eyes certain Indications of working: Otherwiſe, he is like to become an Empiric, whom no Art, no certain reaſon, but only a blind temerity of fortune moves to boldneſs and action. Theſe Indications of actions are drawn from things (as they call them) natural, not-natural and beſide-nature, and their adjuncts, as it is ſingularly delivered of the Antients, being men of an excellent underſtanding. Wherefore we will proſecute according to that order, all the ſpeculations of this Art of ours. Firſt therefore, things Natural are ſo termed, becauſe they conſtitute and contein the nature of mans body, which wholly depends of the mixture and temperament of the four firſt bodies, as it is ſhewed by *Hippocrates* in his Book *de Nat. humana:* wherefore the conſideration thereof belongs to that part of Phyſic, which is named *Phyſiologia*; as the examination of things not natural to *Diætetice* or Diet, becauſe by the uſe of ſuch things it endevors to retein and keep health: but *Therapeutice*, or the part which cures the Diſeaſes, and all the affects beſide nature, challenges the contemplation of thoſe things which are not agreeable to nature. But the things which are called Natural, may be reduced to ſeven heads: beſide which there comes into their fellowſhip, thoſe which we term, Annexed.

From whence we muſt draw Indications.

What things are called natural.

To what part of Phyſic things not natural pertain.

To what, things beſides nature.

The ſeven principal heads of things Natural; are	*Elements*	To theſe are annexed, as ſomewhat near;	*Age*
	Temperaments		*Sex*
	Humors		*Colour*
	Parts or Members		*Compoſure*
	Faculties		*Time or ſeaſon*
	Actions		*Region*
	Spirits		*Vocation of life*

CHAP. IV.
Of Elements.

AN Element (by the definition which is commonly received among Phyſicians) is the leaſt and moſt ſimple portion of that thing which it compoſeth: or, that my ſpeech may be the more plain. The four firſt and ſimple bodies are called Elements; Fire, Air, Water and Earth; which accommodate and ſubject themſelves as matter to the promiſcuous generation of all things which the Heavens engirt, whether you underſtand things perfectly or unperfectly mixed. Such Elements are only to be conceived in your mind, being it is not granted to any external ſenſe to handle them in their pure and abſolute nature. Which was the cauſe that *Hippocrates* expreſſed them not by the names

What an Element is.

Elements are underſtood by reaſon, not by ſenſe.

names of ſubſtances, but of proper qualities, ſaying, Hot, Cold, Moiſt, Dry, becauſe ſome one of theſe qualities is inherent in every Element, as his proper and eſſential form, not only according to the exceſs of latitude, but alſo of the active faculty; to which is adjoined another ſimple quality, and by that reaſon principal, but which notwithſtanding attains not to the higheſt degree of his kind, as you may underſtand by *Galen* in his firſt Book of Elements. So, for Example ſake, in the Air we obſerve two qualities, Heat, and Moiſture, both principal, and not remitted by the commixture of any contrary quality, for otherwiſe they were not ſimple. Therefore thou maiſt ſay, what hinders that the principal effects of heat ſhew not themſelves as well in the Air, as in the Fire? Becauſe, as we ſaid before, although the Air have as great a heat according to his nature, extent, and degree, no otherwiſe than Fire hath, yet it is not ſo great in its active quality. The reaſon is becauſe that the calfactory force in the Air is hindered, and dulled by ſociety of his companion and adjoyned quality, that is, Humidity which abateth the force of heat, as, on the contrary, drineſs quickneth it. The Elements therefore are endued with qualities.

Why *Hipp.* expreſſed the Elements by theſe names of Qualities.

Two principal qualities are in each Element.

Why the Air heats not ſo vehemently, as the Fire.

Names of the ſubſtances	*Fire*	is	*Hot and dry*	Names of the qualities.
	Air		*Moiſt and hot*	
	Water		*Cold and moiſt*	
	Earth		*Cold and dry.*	

Theſe four Elements in the compoſition of natural bodies retain the qualities they formerly had, but that by their mixture and meeting together of contraries, they are ſomewhat tempered and abated. But the Elements are ſo mutually mixed one with another, and all with all, that no ſimple part may be found; no more than in a maſs of the Emplaiſter *Diacalcitheos* you can ſhew any *Axungia* oil, or Litharge by it ſelf; all things are ſo confuſed and united by the power of heat, mixing the ſmalleſt particulars with the ſmalleſt, and the whole with the whole, in all parts. You may know and perceive this concretion of the four Elementary ſubſtances in one compound body, by the power of mixture, in their diſſolution by burning a pile or heap of green wood: For the flame expreſſes the Fire; the ſmoak, the Air; the moiſture that ſweats out at the ends, the Water; and the aſhes, the Earth: You may eaſily perceive by this example ſo familiar and obvious to the ſenſes, what diſſolution is, which is ſucceeded by the decay of the compound body; on the contrary, you may know that the coagmentation, or uniting and joyning into one of the firſt mixed bodies is ſuch, that there is no part ſincere or without mixture. For if the heat which is predominant in the fire, ſhould remain in the mixture in its perfect vigor, it would conſume the reſt by its pernicious neighbourhood; the like may be ſaid of Coldneſs, Moiſture, and Drineſs; although of theſe qualities, two have the title of Active, that is, Heat and Coldneſs, becauſe they are the more powerful; the other two Paſſive, becauſe they may ſeem more dull and ſlow, being compared to the former. The temperaments of all ſublunary bodies ariſe from the commixture of theſe ſubſtances and elementary qualities, which hath been the principal cauſe that moved me to treat of the Elements. But I leave the force and effects of the Elementary qualities to ſome higher contemplation, content to have noted this, that of theſe firſt qualities, (ſo called, becauſe they are primarily and naturally in the four firſt bodies) others ariſe and proceed, which are therefore called the ſecond qualities: as of many, theſe, Heavineſs, Lightneſs, variouſly diſtributed by the four Elements, as the Heat, or Coldneſs, Moiſtneſs or Drineſs have more power over them. For of the Elements, two are called light, becauſe they naturally affect to move upwards: the other two heavy, by reaſon they are carryed downward by their own weight. So we think the fire the lighteſt, becauſe it holds the higheſt place of this lower world; the Air, which is next to it in ſite, we account light; for the water which lies next to the Air, we judg heavy; and the earth the center of the reſt we judg to be the heavieſt of them all. Hereupon it is, that light bodies, and the light parts in bodies, have moſt of the lighter Elements; as on the contrary heavy bodies have more of the heavier. This is a brief deſcription of the Elements of this frail world, which are only to be diſcerned by the underſtanding, to which I think good to adjoin another deſcription of other Elements, as it were ariſing or flowing from the commixture of the firſt: For beſides theſe, there are ſaid to be Elements of generation, and Elements of mans body. Which as they are more corporal, ſo alſo are they more manifeſt to the ſenſe. By which reaſon *Hippocrates* being moved, in his Book *de Natura humana*, after he had deſcribed the Nature of Hot, Cold, Moiſt, and Dry, he comes to take notice of theſe by the order of compoſition. Wherefore the Elements of our generation, as alſo of all creatures which have blood, are ſeed and menſtruous blood. But the Elements of our bodies, are the ſolid and ſimilar parts, ariſing from thoſe Elements of generation. Of this kind are bones, membranes, ligaments, veins, arteries, and many others manifeſt to the eyes, which we will deſcribe at large in our Treatiſe of Anatomy.

How the Elements may be underſtood to be mixed in compound bodies.

Why of the firſt qualities two are active and two paſſive.

Why the firſt qualities are ſo called.

What the ſecond qualities are.

What Elements light, what heavy.

What the Elements of generation are.

What the Elements of mixt bodies.

CHAP. V.

Of Temperaments.

A Temperament is defined, a proportionable mixture of hot, cold, moiſt, and dry; or, It is a concord of the firſt diſagreeing faculties. That harmony ſprings from the mixture of the four firſt bodies of the world. This whether Temperament or Concord is given to Plants and brute Beaſts for the beginning of their life, and ſo conſequently for their life and form. But as Plants are inferiour in order and dignity to beaſts, ſo their *life is more baſe and infirm, for they have only a growing faculty, by which they may draw an Alimentary juyce from the earth, as from their Mothers breaſts, to preſerve them and their life, by which they may grow to a certain bigneſs; and laſtly, by which they may bring forth their like for the perpetual continuance of their kind. But

What a Temperament is.

* *Anima.*

What the life performs in Plants.

* *Anima*, What in beasts. Mans soul comes from above.

the * life of beasts, have to the three former, the gift of sense annexed: by benefit whereof, as by a certain inward knowledg they shun those things that are hurtful, and follow those which profit them; and by the power of their will, they move themselves whither they please. But the soul of man far more perfect and noble than the rest, ariseth not from that earthly mixture and temper of the Elements, but acknowledgeth and hath a far more divine off-spring; as we shall teach hereafter.

The manifold division of a Temperament.

They divide a Temperament at the first division, into two kinds; as, one a temperate, another an untemperate. The untemperate is of two sorts: The one wholly vicious, which hath altogether exceeded the bounds of mediocrity: The other, which hath somwhat strayed from the mediocrity of temper, but notwithstanding is yet contained within the limits of health: as that which brings no such evident harm to the actions, but that it somwhat hinders them, so that they cannot so well and perfectly perform their duties. But the vicious Temperament doth three manner of ways corrupt the functions, either by weakning, depraving, or abolishing them. For so, *Stupor*, or astonishment, diminisheth and floweth the quickness of motion; Convulsion depraves it; the Palsie abolisheth it, and taketh it away.

A Temperament, *ad Pondus.*

Ad pondus, vel ad justitiam.

The temperate Temperament is also divided into two kinds; which is either to equality of weight or justice. It is called a Temperature to weight which ariseth from the equal force of exactly concurring qualities, and, as placed in a perfect ballance, draws down neither to this nor that part. They think the example of this Temperament to appear in the inner skin of the fingers ends of a man tempered to Justice. For seeing the most exquisite touch resides there, they ought to be free from all excess of contrariety; for otherwise being corrupted by too much heat or cold, moisture or driness, they could give no certain judgment of the tangible qualities. For which thing Nature hath excellently provided in the fabrick and coagmentation of the parts, of which the skin consists. For it is composed of hot and moist flesh, and therefore soft, and of a tendon and nerve cold and dry, and therefore hard; which are not only equally fitted and conjoyned, but wholly confused and mixed together, by which it comes, that removed from all extreams of opposition, it is placed in the midst, as a rule to judg of all the excesses that happen to the touch. So it was fit, the eye, which was to be the instrument of sight, should be tinctured with no certain colour, that it might be the less deceived in the judgment of colours. So it was convenient the Hearing should not be troubled with any distinct sound, whereby it might more certainly judg of equal and unequal sounds, not distinguished by a ratable proportion; neither was it fit the tongue should have any certain taste, lest the access of that taste should deceive it in knowing and judging of so many different tastes. The temperature tempered to justice, is that, which although it is a little absent from the exact and severe parility of mixed qualities, yet hath that equality which doth fully and abundantly suffice for to perform all the functions fitly and perfectly, which nature doth require; wherefore we can judg no otherwise of it than by the integrity of the Actions. For hence it took its name; for as distributive Justice equally gives to every one rewards, or punishment according to their deserts; so Nature, having regard to all the parts of the body, gives them all that temper which may suffice to perform those duties, for which they are ordained. Let us for an example consider a Bone; no man doubts, but that, like as the other similar parts of the body, proceeds from the mixture of the four Elements: but nevertheless nature weighing the use of it, and ordaining it to support the rest of the body, would have more of the terrene and dry Element infused into it, that it might be the stronger and firmer to sustain weight. But a Ligament, seeing it was made for other uses, hath less of that earthly driness than the bone, but more than the flesh, altogether fitted to its nature. So it hath seemed good to nature to endue all the parts of the body, not only with an equal portion, but also proportion of Elements and qualities; we call that a Temperament to justice: and we say, that it is in Plants, brute Beasts, and all natural bodies, which enjoy that temper and mediocrity, which may be agreeable to their nature. Hereupon by comparison arise eight kinds of intemperate tempers: As

A Temperament *ad justitiam.*

The Temperament of a bone.

The kinds of untemperate tempers.

Four simples { *Hot* / *Cold* } temperate in { *Driness* and *Moisture.* } Four Compounds { *Hot* and *Moist* / *Hot* and *Dry* }
Four simples { *Moist* / *Dry* } temperate in { *Heat* and *Cold.* } Four Compounds { *Cold* and *Moist* / *Cold* and *Dry.* }

But these Temperaments are either of the whole Body, or of some part thereof;

And that either { Principal, as { the *Brain* / the *Heart* / the *Liver* / the *Stones.* } Or / Of the rest of the parts composed of other which have no principality in the body. }

Again, such Temperaments are either healthful, which suffice perfectly to perform their actions; or unhealthful, which manifestly hurt them, the signs whereof may be read described by *Galen.* And you must observe that when we say the body, or any part of it, is hot; we understand more hot than is fit for one of that kind which is tempered to justice; as when we say a man hath a hot liver, we mean his liver is hotter, than a man justly tempered should have; for all other tempers, whether of the whole body, or any of the parts thereof, are to be referred to this; and in the cure of diseases we must look upon it, as the mark, and labour to preserve it by the use of convenient things, as much as lies in our power. Wherefore, because it is very necessary to know the distinction of Temperaments, I have thought good in this place, briefly to handle the Temperaments of the parts of the Body, Ages, Seasons of the year, Humors, and Medicins. Therefore the temperaments of the parts of our body are of this nature, not only by the judgment of the touch of a mans hand, which is justly tempered, (who is often deceived by flowing heat, which spread from the heart into all the body, imparts a certain kind of heat, to all the parts) but also by the rule of their reason, composure, and substance, as

Lib. 2. *de Temper. & in Arte medica.*

What the temperaments of mans body are.

A Bone is the moſt dry and cold.
A Griſle leſs than it.
A Ligament leſs than a Griſle.

A Tendon is ſo much drier and colder than the membrane, by how much it, in the ſame temper, exceeds a Vein and Artery. Then follow the harder Veins: for the ſofter are in a middle temper of dryneſs and moiſture, like as the Skin; although all, both ſoft and hard are of a cold temper. Wherefore all theſe parts of their own nature are cold and without blood: although the Veins and Arteries wax hot, by reaſon of the heat of the blood they contain, which notwithſtanding alſo borroweth that heat from the heart, as a part moſt hot, and ſofter than the skin; the Liver next followeth the heart, in the order of the hotter parts, which is far ſofter than the skin it ſelf: for if, according to *Galens* opinion, the heart is ſomewhat leſs hard than the skin, and that is far harder than the liver, as appears by touching them, it muſt neceſſarily follow that the liver much exceeds the skin in ſoftneſs; I underſtand the skin, ſimple and ſeparated from the fleſh lying under it, to which it firmly cleaves. The fleſh is more moiſt and hot than the skin, by reaſon of the blood diſperſed in it. The ſpinal marrow is colder and moiſter than the skin; but the brain ſo much exceeds it in moiſture, as it is exceeded by the fat. The lungs are not ſo moiſt as the fat? and the ſpleen, and kidneys are of the like nature, and nevertheleſs they are all moiſter than the skin. *Ad finem, lib. de Temper.*

According to the diverſities of ages, the temperaments both of the whole body, and all its parts, undergo great mutations; for the bones are far harder in old men than in children, becauſe our life is, as it were, a certain progreſs to drineſs; which when it comes to the height, conſequently cauſeth death. Wherefore in this place we muſt ſpeak of the Temperaments of Ages, when firſt we ſhall have defined what an age is. Therefore an Age is defined, A ſpace of life in which the conſtitution of the body of its ſelf and own accord, undergoeth manifeſt changes. The whole courſe of life hath four ſuch Ages. The firſt is Childhood, which extends from the birth to the eighteenth year of age, and hath a hot and moiſt temper, becauſe it is next to the hot and moiſt beginnings of life, ſeed, and blood. Youth followeth this, which is prolonged from the eighteenth to the twenty fifth year, and is temperate, and in the midſt of all exceſſes. Mans eſtate ſucceedeth Youth, which they deny to extend beyond the thirty fifth year of age; in its proper temper it is hot and dry; whereby it cometh to paſs that then the heat is felt more acid and biting, which in Childhood ſeemeth mild; becauſe the progreſs of the life to drineſs, hath much waſted the native humidity. The temperaments of ages. What an age is.

Then ſucceeds Old-age, ever divided into two parts; the firſt whereof extends from the thirty fifth, to the forty ninth year; thoſe of this age are called Old-men, *(but we commonly call them middle ag'd men.)* The latter is, as it were divided by *Galen* into three * degrees; the firſt whereof are thoſe, who having their ſtrength ſound and firm, undergo civil affairs and buſineſſes: which things thoſe which are in the ſecond degree of Old-age cannot do, becauſe of the debility of their now decaying ſtrength: but thoſe which are in the laſt degree, are afflicted with moſt extream weakneſs and miſery, and are as much deprived of their ſenſes and underſtanding, as of the ſtrength of their bodies; whereof aroſe this Proverb, *Old men, twice Children.* Thoſe Old men of the firſt rank are pleaſant and curteous; and thoſe we ſay, are beginning to grow Old, or in their green Old-age; thoſe of the ſecond ſort delight in nothing but the boord and bed; but old decrepit men of the laſt order, think of nothing elſe, than their graves and monuments. Their firm and ſolid parts are of a cold and dry temperature, by reaſon of the decay of the radical moiſture, which the inbred heat cauſeth in the continuance of ſo many years. Which thing may happen in a ſhort ſpace, by the vehement flame of the ſame natural heat, turned by feavers into a fiery heat. But if any to prove Old men moiſt, will object, That they cough oft, and ſpit much, I will anſwer him, as an old Doctor once ſaid; That a pitcher filled with water, may pour forth much moiſture; yet no man will deny but that ſuch a veſſel of its own terrene nature and matter is moſt dry; ſo old men may plainly be affirmed to be moiſt, by reaſon of their defect of heat, and abundance of excrements. But this deſcription of ages is not to be taken ſo ſtrictly as always to be meaſured by the ſpaces and diſtances of years; for there are many which by their own miſdemeanour ſeem elder at forty, than others do at fifty. Old-age divided into two parts. * Three degrees of the ſecond part of Old-age. Old men have their ſolid parts dry.

Laſtly, the famous Philoſopher *Pythagoras* divided mans life into four ages, and by a certain proportion compared the whole courſe thereof to the four ſeaſons of the year; as Childhood to the Spring, in which all things grow and ſprout out, by reaſon of plenty and abundance of moiſture. And Youth to the Summer, becauſe of the vigor and ſtrength which men enjoy at that age. And mans eſtate, or conſtant age, to Autumn; for that then after all the dangers of the fore-paſſed life, the gifts of diſcretion and wit acquire a ſeaſonableneſs or ripeneſs, like as the fruits of the earth enjoy at that ſeaſon. And laſtly, he compares Old-age to the ſterile and fruitleſs Winter, which can eaſe and conſolate its tedioufneſs by no other means, than the uſe of fruits gathered and ſtored up before, which then are of a cold and troubleſome condition. But for extreme Old-age, which extends to eighty or a hundred years, it is ſo cold and dry, that thoſe which arrive at that decrepit age are troubleſome, harſh, touchy, froward, crabby, and often complaining, until at the length, deprived of all their ſenſes, tongue, feet, and underſtanding, they doting return again to childiſhneſs, as from the ſtaff to the ſtart. And thus much of the Temperaments of ages. A compariſon of the four ages to the four ſeaſons of the year.

But now in like manner we will explain the Temperatures of the ſeaſons of the year, which are four; the Spring, Summer, Autumn, Winter. The Spring continues almoſt from the twelfth or thirteenth day of *March* to the midſt of *May*; *Hippocrates* ſeemeth to make it hot and moiſt; which opinion ſeemeth not to have ſprung from the thing it ſelf, but from an inveterate error of the ancient Philoſophers, who would fit the Temperaments of the four ſeaſons of the year, as anſwering in proportion to the temperatures of the four ages. For if the matter come to a juſt trial, all men will ſay, the Spring is temperate, as that which is in the midſt of the exceſs of heat, cold moiſture, and drineſs: not only by compariſon, becauſe it is hotter than Winter, and colder than Summer; but becauſe it hath that quality of its own proper nature. Wherefore it is ſaid of *Hippocrates*, The Spring is moſt *Aphor. 9. ſect. 3.* The temperatures of the ſeaſons of the year. How the ſpring is temperate.

wholesom, and least deadly; if so be that it keep its native temper, from which if it decline, or succeed a former untemperate season, as Autumn or Winter, it will give occasion to many diseases described by *Hippocrates*; not that it breeds them but because it brings them to sight, which before lay hid in the body. Summer is comprehended in the space of almost four months; it is of a hot and dry temper, a breeder of such diseases as proceed from choler, because that humour at this time is heaped up in many bodies by adustion of blood bred in the Spring; but all such diseases do speedily run their course. The beginning of Autumn, is from the time the Sun enters into Libra, and endures the like space of time as the Spring. But when it is dry, it hath great inequality of heat and cold, for the mornings and evenings being very cold, the noondays on the contrary are exceeding hot. Wherefore many diseases are in Autumn, and them long and deadly, especially if they incline towards Winter; because all daily and sudain changes to heat and cold are dangerous. The Winter possesses the remnant of the year, and is cold and moist, it increases natural heat, stirs up the appetite, and augments Phlegm. It increases heat by *Antiperistasis*, or contrariety of the encompassing air, which being then cold, prohibits the breathing out of heat: whereby it happens that the heat being driven in and hindered from dissipation, is strengthened by co-uniting its forces. But it augments Phlegm, for that men are more greedy, the Appetite being increased by the strengthened heat: from whence proceeds much crudity, and a large store of diseases, especially Chronic or Long, which spread and increase rather in this Winter-season than in any other part of the year. To this discourse of the temper of the seasons of the years, is to be revoked the variety of tempers which happens every day; which certainly is not to be neglected, that there may be place of election, especially if nothing urge. For hither belongs that saying of *Hippocrates*; When in the same day it is one while hot, another cold, Autumnal diseases are to be expected. Therefore an Indication taken from hence is of great consequence to the judgment of diseases; for if it agree with the disease, the disease is made more contumacious, and difficult to cure. Whereupon the Patient and Physician will have much trouble; but if on the contrary it reclaim and dissent, the health of the Patient is sooner to be expected. Neither is it a thing of less consequence to know the customs and habits of the Places and Countrys in which we live; as also the inclination of the Heavens, and temperature of the Air. But let us leave these things to be considered by Natural Philosophers, that we may deliver our judgment of the temperaments of *Humours*. Blood, as that which answers to the Air in proportion, is of a hot and moist nature, or rather temperate, as *Galen* testifies; for, saith he, it is certain and sure, that the Blood is neither hot nor moist, but temperate, as in its first composure none of the four first qualities exceeds other by any manifest excess, as he repeats it upon the 39th Sentence. Phlegm, as that which is of a waterish nature, is cold and moist; no otherwise than Choler being of a fiery temper, is hot and dry. But Melancholy assimilated to earth, is cold and dry. This which we have spoken in general of Phlegm and Melancholy, is not always true in every kind of the said Humours. For salt Phlegm is of a hot and dry temperature; as also all kinds of Melancholy which have arose or sprung by adustion from the native and alimentary, as we will teach in the following Chapter. Now the temperaments of Medicines have not the same form of judgment, as those things which we have before spoken of; as, not from the Elementary quality, which conquering in the contention and mixture, obtains the dominion; but plainly from the effects, which taken or applied, they imprint in a temperate body. For so we pronounce those things, hot, cold, moist, or dry, which produce the effects of Heat, Coldness, Moisture, or Driness. But we will defer the larger explication of these things to that place, where we have peculiarly appointed to treat of Medicines; where we will not simply enquire whether they be hot or cold, but what degree of heat and cold, or the like other quality: In which same place we will touch the temperature and all the nature of Tastes, because the certainest judgment of Medicines is drawn from their tastes. Hitherto of Temperaments; now we must speak of Humors, whose use in Physical speculation is no less than that of Temperaments.

Aphor. 20. *Sect.* 3.

Autumn unequal.

How Winter increases the native heat.

Aphor. 4. *Sect.* 3.

The temperaments of Humors.

Lib. de natura humana, ad. Sent. 36. sect. 1.

The temperature of the Blood.

From whence we judg of the temperature of Medicines.

CHAP. VI.

Of Humors.

The knowledg of the Humor is necessary. Lib. *De natura Humana.*

TO know the nature of *Humors*, is a thing not only necessary for Physicians, but also for Chirurgeons, because there is no disease with matter which arise not from some one, or the mixture of more *Humors*. Which thing *Hippocrates* understanding, writ, every Creature to be either sick or well according to the condition of the *Humors* in the body. And certainly all putrid feavers proceed from the putrefaction of *Humors*. Neither do any acknowledg any other original or distinction of the differences of Abscesses or Tumors: neither do ulcerated, broken, or otherwise wounded members hope for the restauration of continuity, from other than from the sweet falling down of Humors to the wounded part. Which is the cause that often in the cure of these affects, the Physitians are necessarily busied in tempering the blood, that is, bringing to a mediocrity the four Humors composing the mass of blood, if they at any time offend in quantity, or quality. For whether if any thing abound or digress from the wonted temper in any excess of heat, cold, viscosity, grosness, thinness, or any such like quality, none of the accustomed functions will be well performed. For which cause those chief helps to preserve and restore health have been divinely invented; *Phlebotomy*, or blood-letting, which amends the quantity of too much blood; and Purging, which corrects and draws away the vicious quality. But now let us begin to speak of the Humors, taking our beginning from the Definition.

The helps of Health.

What an Humor is.

An *Humor* is called (by Physicians) what thing soever is liquid and flowing in the body of living Creatures endued with Blood: and that is either natural, or against nature. The natural is so called because it is fit to defend, preserve, and sustain the life of a Creature. Quite different is the nature and reason of that which is against nature. Again, the former is either Alimentary or Excremen-

The manifold division of Humors.

mentitious: The Alimentary which is fit to nouriſh the body, is that Humor which is contained in the veins and arteries of a man which is temperate and perfectly well; and which is underſtood by the general name of blood, which is let out at the opening of a vein. For Blood otherwiſe taken, is an Humor of a certain kind, diſtinguiſhed by heat and warmneſs from the other Humors comprehended together with it, in the whole maſs of the blood. Which thing, that it may the better be underſtood, I have thought good in this place to declare the generation of Blood by the efficient and material cauſes. All things which we eat or drink, are the materials of Blood; which things drawn into the bottom of the Ventricle by its attractive force, and there detained, are turned by the force of concoction implanted in it, into a ſubſtance like to Almond-butter. Which thing, although it appear one and like it ſelf, yet it conſiſts of parts of a different nature, which not only the variety of meats, but one and the ſame meat yields of it ſelf. We term this *Chylus*, (when it is perfectly concocted in the ſtomach.) But the * Gate-vein receives it driven from thence into the ſmall Guts, and ſucked in by the Meſeraic-veins, and now having gotten a little rudiment of change in the way, carries it to the Liver, where by the Blood-making faculty, which is proper and natural to this part, it acquires the abſolute and perfect form of Blood. But with that Blood, at one and the ſame time and action all the Humors are made, whether alimentary or excrementitious. Therefore the Blood, that it may perform its Office, that is, the faculty of nutrition, muſt neceſſarily be purged and cleanſed from the too excrementitious Humors: of which the bladder of Gall draws one, which we call yellow Choler; and the Spleen the other, which we term Melancholy. Theſe two Humors are natural but not alimentary or nouriſhing, but of another uſe in the body, as afterwards we will ſhew more at large. The Blood freed from theſe two kinds of Excrements, is ſent by the veins and arteries into all parts of the body for their nouriſhment. Which although then it ſeem to be of one ſimple nature, yet notwithſtanding it is truly ſuch, that four different and unlike ſubſtances may be obſerved in it, as, Blood, properly ſo named; Phlegm, Choler, and Melancholy, not only diſtinct in colour, but alſo in taſte, effects, and qualities. For, as *Galen* notes in his Book *de Natura humana*, Melancholy is acid or ſowr, Choler bitter, Blood ſweet, Phlegm unſavoury. But you may know the variety of their effects, both by the different temper of the nouriſhed parts, as alſo by the various condition of the diſeaſes ſpringing from thence. For therefore ſuch ſubſtances ought to be tempered and mixed amongſt themſelves in a certain proportion; which remaining, health remains; but violated, diſeaſes follow. For all acknowledg, that an *Oedema* is cauſed by Phlegmatic; a *Scirrhus*, by Melancholic; an *Eryſipelas*, by Choleric; and a *Phlegmone*, by pure and laudable blood. *Galen* teaches by a familiar example of new wine preſently taken from the Preſs, that theſe four ſubſtances are contained in that one maſs and mixture of the blood. In which every one obſerves four diſtinct Eſſences; for the flower of the wine working up, ſwims at the top, the dregs fall down to the bottom, but the crude and watery moiſture, mixed together with the ſweet and vinous liquor, is every where diffuſed through the body of the wine: the flower of the wine, repreſents Choler, which bubbling up on the ſuperficies of blood, as it concretes and grows cold, ſhineth with a golden colour; the dregs, Melancholy, which by reaſon of its heavineſs ever ſinketh downward, as it were, the mud of the blood; the crude and watery portion, Phlegm: for as that crude humour, except it be rebellious in quantity, or ſtubborn by its quality, there is hope it may be changed into Wine, by the natural heat of the Wine; ſo Phlegm, which is blood half concocted, may by the force of native heat be changed into good and laudable blood. Which is the cauſe that nature decreed or ordained no peculiar place, as to the other two humors, whereby it might be ſevered from the blood: But the true and perfect liquor of the wine repreſents the pure blood, which is the more laudable and perfect portion of both humors of the confuſed maſs. It may eaſily appear by the following Scheme, of what kind they all are, and alſo what the diſtinction of theſe four Humors may be.

The material and efficient cauſes of blood.

What the *Chylus* is.

* *Vena porta.*

Where the Blood is perfected.

The receptacles of Choler and Melancholy.

Four unlike Humors in the Blood.

A compariſon of Blood and new Wine.

Phlegm is Blood half concocted.

Why it hath no proper receptacle.

	Nature.	Conſiſtence.	Colour.	Taſte.	Uſe.
Blood is	*Of Nature airy, hot and moiſt, or rather temperate.*	*Of indifferent conſiſtence, neither too thick nor too thin.*	*Of Colour, red roſie or crimſon.*	*Of Taſte ſweet.*	*Of ſuch uſe, that it chiefly ſerves for the nouriſhment of the fleſhy parts, and carryed by the veſſels imparts heat to the whole body.*
Phlegm is	*Of Nature watery, cold and moiſt.*	*Of Conſiſtence, liquid.*	*Of Colour, white.*	*Of Taſte, ſweet, or rather unſavory; for we commend that water which is unſavory.*	*Fit to nouriſh the brain, and all the other cold and moiſt parts, to temper the heat of the blood, and by its ſlipperineſs to help the motion of the joynts.*
Choler is	*Of Nature fiery, hot and dry.*	*Of Conſiſtence, thin.*	*Of Colour, yellow or pale.*	*Of Taſte, bitter.*	*It provoketh the expulſive faculty of the Guts attenuates the Phlegm cleaving to them, but the Alimentary is fit to nouriſh the parts of like temper with it.*
Melancholy is	*Of Nature earthly, cold, and dry.*	*Of Conſiſtence, groſs and muddy.*	*Of Colour, blackiſh.*	*Of Taſte, acide, ſour or biting.*	*Stirs up the Appetite, nouriſhes the Spleen, and all the parts of like temper to it, as the bones.*

Blood

Blood hath its neareſt matter from the better portion of the *Chylus:* and being begun to be laboured in the veins, at length gets form and perfection in the Liver; but it hath its remote matter from meats of good digeſtion and quality, ſeaſonably eaten after moderate exerciſe; but for that, one age is better than another, and one time of the year more convenient than another. For blood is made more copiouſly in the Spring, becauſe that ſeaſon of the year comes neareſt to the temper of the blood, by reaſon of which the blood is rather to be thought temperate, than hot or moiſt; for that *Galen* makes the Spring temperate, and beſides, at that time blood-letting is performed with the beſt ſucceſs: Youth is an age very fit for the generation of blood; or, by *Galens* opinion, rather that part of life that continues from the 25, to the 35. year of our age. Thoſe in whom this Humor hath the dominion, are beautified with a freſh and roſie colour, gentle, and wel-natured, pleaſant, merry, and facetious. The generation of Phlegm is not by the imbecillity of heat, as ſome of the Ancients thought; who were perſuaded that Choler was cauſed by a raging, Blood by a moderate, and Phlegm and Melancholy by a remiſs heat. But that opinion is full of manifeſt error: for if it be true, that the *Chylus* is laboured and made into blood in the ſame part, and by the ſame fire, that is, the Liver; from whence in the ſame moment of time ſhould proceed that ſtrong and weak heat, ſeeing the whole maſs of blood, different in its four eſſential parts, is perfected and made at the ſame time, and by the ſame equal temper of the ſame part, action, and blood-making faculty; therefore from whence have we this variety of Humors? From hence; for that thoſe meats by which we are nouriſhed, enjoy the like condition that our bodies do, from the four Elements, and the four firſt Qualities: for it is certain, and we may often obſerve, In what kind ſoever they be united or joyned together, they retain a certain hot portion imitating the fire; another cold, the water; another dry, the earth; and laſtly, another moiſt like to the air. Neither can you name any kind of nouriſhment, how cold ſoever it be, not Lettuce it ſelf, in which there is not ſome fiery force of heat. Therefore it is no marvail, if one and the ſame heat working upon the ſame matter of *Chylus*, varying with ſo great diſſimilitude of ſubſtances, do by its power produce ſo unlike humors, as from the hot, Choler; from the cold, Phlegm; and of the others, ſuch as their affinity of temper will permit.

Lib. 1. *de temp.*

One and the ſame Heat is the efficient cauſe of all humors at the ſame time.

The heat of the Sun alone doth melt wax and harden clay.

There is no cauſe that any one ſhould think that variety of humors to be cauſed in us, rather by the diverſity of the active heat, than wax and a flint placed at the ſame time, and in the ſame ſituation of climat and ſoil, this to melt by the heat of the Sun, and that ſcarce to wax warm. Therefore that diverſity of effects is not to be attributed to the force of the efficient cauſe, that is, of Heat, which is one, and of one kind in all of us; but rather to the material cauſe, ſeeing it is compoſed of the conflux, or meeting together of various ſubſtances, gives the heat leave to work, as it were out of its ſtore, which may make and produce from the hotter part thereof Choler; and of the colder and more rebellious, Phlegm. Yet I will not deny, but that more Phlegm, or Choler may be bred in one and the ſame body, according to the quicker, or ſlower provocation of the heat; yet nevertheleſs it is not conſequent, that the Original of Choler ſhould be from a more acid, and of Phlegm from a more dull heat in the ſame man. Every one of us naturally have a ſimple heat, and of one kind, which is the worker of divers operations, not of it ſelf, ſeeing it is always the ſame, and like it ſelf, but by the different fitneſs, pliableneſs, or reſiſtance of the matter on which it works. Wherefore Phlegm is generated in the ſame moment of time, in the fire of the ſame part, by the efficiency of the ſame heat, with the reſt of the blood, of the more cold, liquid, crude, and watery portion of the *Chylus*. Whereby it comes to paſs, that it ſhews an expreſs figure of a certain rude or unperfect blood, for which occaſion nature hath made it no peculiar receptacle, but would have it to run friendly with the blood in the ſame paſſages of the veins, that any neceſſity hapning by famin, or indigency, and in defect of better nouriſhment, it may by a perfecter elaboration quickly aſſume the form of blood. Cold and rude nouriſhment make this humor to abound principally in Winter, and in thoſe which incline to old age, by reaſon of the ſimilitude which Phlegm hath with that ſeaſon and age. It makes a man drowſie, dull, fat, ſwollen up, and haſtneth gray hairs. Choler is as it were, a certain heat and fury of humours, which generated in the Liver, together with the blood, is carryed by the veins and arteries through the whole body. That of it which abounds, is ſent, partly into the guts, and partly into the bladder of the gall, or is conſumed by tranſpiration, or ſweats; It is ſomewhat probable that the arterial blood is made more thin, hot, quick, and pallid, than the blood of the Veins, by the commixture of this Alimentary Choler. This Humor is chiefly bred and expel'd in youth, and acid and bitter meats give matter to it: but great labors of body and mind give the occaſion. It maketh a man nimble, quick, ready for all performance, lean, and quick to anger, and alſo to concoct meat. The Melancholic humor, or Melancholy, being the groſſer portion of the blood, is partly ſent from the Liver to the Spleen to nouriſh it, and partly carried by the veſſels into the reſt of the body, and ſpent in the nouriſhment of the parts endued with an earthly drineſs; it is made of meats of groſs juyce, and by the perturbations of the mind, turned to fear and ſadneſs. It is augmented in Autumn, and in the firſt and crude Old-age; it makes men ſad, harſh, conſtant, froward, envious and fearful. All men ought to think, that ſuch Humors are wont to move at ſet hours of the day, as by a certain peculiar motion or tide, Therefore the blood flows from the ninth hour of the night, to the third hour of the day; then Choler to the ninth of the day; then Melancholy to the third of the night; the reſt of the night that remains, is under the dominion of Phlegm. Manifeſt examples hereof appear in the French-Pox. From the elaborate and abſolute maſs of the blood, (as we ſaid before) two kind of Humors, as excrements of the ſecond concoction, are commonly and naturally ſeparated, the one more groſs, the other more thin. This is called either abſolutely Choler, or with an adjunct, yellow Choler. That is called Melancholy, which drawn by the Spleen in a thinner portion, and elaborate by the heat of the Arteries, which in that part are both many and large, becomes nouriſhment to the part; the remnant thereof is carried by the veiny Veſſel into the orifice of the ventricle, whereby it may not cauſe but whet the appetite, and by its aſtriction ſtrengthen the actions thereof. But yellow Choler drawn into the bladder of the gall, remains there ſo long, till being troubleſome; either in quantity

The diverſe condition of the matter alone, is the cauſe of variety.

The effect of Phlegm.

The effects of Choler.

The effects of Melancholy.

What motions are in each quarter of the body.

The Melancholy Humor doth not cauſe but whet the appetite.

quantity or quality, it is excluded into the guts, whereby it may caſt forth the excrements reſiding in them; the expulſive faculty being provoked by its acrimony, and by its bitterneſs kills the worms that are bred there. The ſame Humor is accuſtomed to die the urine of a yellow colour. There is another ſerous Humor, which is not fit to nouriſh but profitable for many other things, which is not an excrement of the ſecond, but of the firſt concoction. Therefore nature would that mixed with the *Chylus*, it ſhould come to the Liver, and not be voided with the excrements, whereby it might allay the groſneſs of the blood, and ſerve it for a vehicle; for otherwiſe the blood could ſcarce paſs through the capillary veins of the Liver, and paſſing the ſimous and gibbous parts thereof, come to the hollow vein. Part of this ſerous humor, ſeparated together with the blood which ſerves for the nouriſhment of the Reins, and ſtraight carried into the bladder, is turned into that urine which we daily make; the other part thereof, carried through all the body together with the blood, performing the like duty of tranſportation, is excluded by ſweats into which it degenerates. Beſides the forenamed, the *Arabians* have mentioned four other humors, which they term Alimentary and ſecondary, as being the next matter of nouriſhment, as thoſe four the blood contains, the remote. They have given no name to the firſt kind, but imagin it to be that humor, which hangs ready to fall like to little drops in the utmoſt orifices of the veins. They call the ſecond kind, * Dew; being that humor, which, entred already into the ſubſtance of the part, doth moiſten it. The third they call by a barbarous name, *Cambium*, which, already put to the part to be nouriſhed, is there faſtned. The fourth named *Gluten*, or Glew, is only the proper and ſubſtance-making humidity of the ſimilar parts, not their ſubſtance. The diſtinction of the degrees of nutrition recited by *Galen* in his books of Natural faculties, anſwer in proportion to this diſtinction of humors. The firſt is, that the blood flow to the part that requires nouriſhment; then that being there arrived, it may be agglutinated; then laſtly, that having loſt its former form of nouriſhment, it may be aſſimilated.

A ſerous or wheyiſh humor.

Secundary Humors.

* *Ros.*

Thoſe humors are againſt nature, which being corrupted, infect the body and the parts in which they are contained by the contagion of their corruption, retaining the names and titles of the humors, from whoſe perfection and nature they have revolted, they all grow hot by putrefaction, although they were formerly by their own nature cold. And they are corrupted, either in the veins only, or within and without the veins; In the veins Blood and Melancholy; but, both without and within the veins, Choler and Phlegm. When blood is corrupted in its thinner portion, it turns into Choler, when in its thicker, into Melancholy; for the Blood becomes faulty two manner of ways, either by the corruption of its proper ſubſtance by putrefaction, or by admixtion of another ſubſtance by infection. The Melancholy humor which is corrupted in the veins, is of three ſorts: The firſt is of a Melancholy juice putrefying, and by the force of a ſtrange heat, turned as it were, into aſhes, by which it becomes aduſt, acid and biting. The other ariſeth from that Choler which reſembles the yolks of eggs, which by aduſtion becomes leek-coloured, then æruginous, or of a blewiſh green, then red, and laſtly black, which is the very worſt kind of Melancholy, hot, malign, eating, and exulcerating, and which is never ſeen or voided with ſafety. The third comes from Phlegm putrefying in the veins, which firſt degenerates into ſalt Phlegm, but ſtraight by the ſtrength of extraneous heat degenerates into Melancholy.

Humors againſt nature.

Into what Humors the blood when it corrupts, doth degenerate.

The Melancholy Humor corrupted, is of three kinds.

- *Phlegm not natural is bred, either*
  - In the Veins, and is either
    - Acid and very crude, as which hath had none or very little impreſſion of heat, but that which it firſt had in the ſtomach.
    - Salt, which is bred by the ſweet, putrefying and aduſt, or mixture of aduſt and ſalt particles.
  - Or without the Veins, and is of four ſorts; either
    - Wateriſh, as is that thin moiſture which diſtils from the brain by the noſtrils.
    - Mucous, as when that wateriſh is thickned into filth by the help of ſome accidental or ſmall heat.
    - Glaſſie, or * Albuminous, reſembling molten glaſs, or rather the white of an egg, and is moſt cold.
    - *Gypſea*, or Plaiſter-like, which is concrete into the hardneſs and form of chalk, as you may ſee in the joints of the fingers in a knotty gout, or in inveterate diſtillations upon the Lungs.

* *Albuminea.*

- *Choler not natural is bred, either*
  - In the Veins, as the * Vitelline (like in conſiſtence to the yolk of a raw egg) which the acrimony of ſtrange heat breeds of yellow Choler, which ſame, in diſeaſes altogether deadly, degenerates into green, æruginous, and laſtly into a blue, or colour like that which is died by woad.
  - Or in the capacity of the upper belly, as the ventricle, and this is of five kinds.
    - The firſt is called *Porracea*, or leek-coloured, reſembling the juice of a leek in greenneſs.
    - The ſecond *æruginoſa*, or æruginous, like in colour to verdigreaſe.
    - The third bluiſh, or woad-coloured, like the colour died by woad.
    - The fourth red, differing in this from blood, whoſe colour it imitates, that it never cometh into knots, or clods like blood.
    - The fifth very red, generated by the exceſs of the former, which cauſeth burning feavers.

* *Vitellina.*

The kinds of ſuch Choler, are often caſt forth by vomit in diſeaſes, the ſtrength of the diſeaſe being paſt; being troubleſom to the parts through which they are evacuated, by their bitterneſs, acrimony, and biting.

The

The ſigns of a Sanguine Perſon.

I Think it manifeſt, becauſe the matter and generation of fleſh is principally from blood, that a man of a fleſhy, denſe, and ſolid habit of body, and full of a ſweet and vaporous juice, is of a Sanguine complexion. And the ſame party hath a flouriſhing and roſie colour in his face, tempered with an equal mixture of white and red; of white, by reaſon of the skin lying utmoſt; of red, becauſe of the blood ſpread underneath the skin: for always ſuch as the humor is, ſuch is the colour in the face. In manners he is curious, gentle, eaſie to be ſpoken to, not altogether eſtranged from the love of women, of a lovely countenance and ſmooth forehead, ſeldom angry, but taking all things in good part; for as the inclination of humors is, ſo alſo is the diſpoſition of manners. But blood is thought the mildeſt of all humors; but the ſtrong heat of the inward parts maketh him to eat and drink freely. Their dreams are pleaſant, they are troubled with diſeaſes ariſing from blood, as frequent Phlegmons and many ſanguine puſtles breaking through the skin, much bleeding, and menſtruous fluxes. Wherefore they can well endure blood-letting, and delight in the moderate uſe of cold and dry things; and laſtly, are offended by hot and moiſt things. They have great and ſtrong Pulſe, and much urine in quantity, but mild of quality, and of an indifferent colour and ſubſtance.

Such as the humor is, ſuch is the colour. The manners and diſeaſes of Sanguine perſons.

The ſigns of a Choleric Perſon.

Choleric are not commonly fat. The manners and diſeaſes of Choleric perſons.

CHoleric men are of a pale or yellowiſh color, of a lean, ſlender and rough habit of body, with fair veins and large Arteries, and a ſtrong and quick pulſe: their skin being touched, feels hot, dry, hard, rough and harſh, with a pricking and acid exhalation which breaths forth of their whole body. They caſt forth much choler by ſtool, vomit, and urine. They are of a quick and nimble wit, ſtout, hardy and ſharp vindicators of received injuries, liberal even to prodigality, and ſomewhat too deſirous of glory. Their ſleep is light, and from which they are quickly waked: their dreams are fiery, burning, quick, and full of fury; they are delighted with meats and drinks which are ſomewhat more cold and moiſt, and are ſubject to Tertian and burning feavers, the Phrenſie, Jaundiſe, Inflammations, and other Choleric puſtles, the Lask, Bloody flux, and bitterneſs of the mouth.

The ſigns of a Phlegmatic Perſon.

The manners and diſeaſes of Phlegmatic perſons.

THoſe in whom Phlegm hath the dominion, are of a whitiſh coloured face, and ſometimes livid and ſwollen, with their body fat, ſoft, and cold to touch.

They are moleſted with Phlegmatic diſeaſes, as Oedematous tumours, the Dropſie, Quotidian feavers, falling away of the hairs, and Catarrhs falling down upon the Lungs, and the *Aſpera Arteria*, or Weaſon: they are of a ſlow capacity, dull, ſlothful, drowſie; they do dream of rains, ſnows, floods, ſwiming, and ſuch like, that they often imagine themſelves overwhelmed with waters; they vomit up much watery and Phlegmatick matter, or otherwiſe ſpit and evacuate it, and have a ſoft and moiſt tongue.

And they are troubled with a dog-like hunger, if at any time it ſhould happen that their inſipid Phlegm become acid; and they are ſlow of digeſtion, by reaſon of which they have great ſtore of cold and Phlegmatic humors; which if they be carried down into the windings of the Colic-gut, they cauſe murmuring and noiſe, and ſometimes the Colic.

From whence noiſe or rumbling in the belly proceeds.

For much wind is eaſily cauſed of ſuch like Phlegmatic excrements wrought upon by a ſmall and weak heat, ſuch as Phlegmatic perſons have, which by its natural lightneſs is diverſly carried through the turnings of the guts, and diſtends and ſwells them up, and whiles it ſtrives for paſſage out, it cauſeth murmurings and noiſes in the belly, like wind breaking through narrow paſſages.

Signs of a Melancholic Perſon.

Diſeaſes familiar to Melancholy perſons.

THe face of Melancholy perſons is ſwart, their countenance cloudy and often cruel, their aſpect is ſad and froward; frequent Scirrhus or hard ſwellings, tumors of the Spleen, Hæmorrhoids, *Varices* (or ſwollen Veins) Quartan feavers, whether continual or intermitting; Quintan, Sextan, and Septiman feavers: and to conclude, all ſuch wandering feavers or agues ſet upon them. But when it happens, the Melancholy humor is ſharpened, either by aduſtion, or commixture of Choler, then Tetters, the black Morphew, the Cancer ſimple and ulcerated, the Leprous and filthy ſcab, ſending forth certain ſcaly and branlike excreſcences, (being vulgarly called St. *Manis* his evil;) and the Leproſie it ſelf invades them; They have ſmall veins and arteries, becauſe coldneſs hath dominion over them; whoſe property is to ſtraiten, as the quality of heat is to dilate. But if at any time their veins ſeem big, that largeneſs is not by reaſon of the laudable blood contained in them, but from much windineſs; by occaſion whereof it is ſomewhat difficult to let them blood; not only, becauſe that when the vein is opened, the blood flows ſlowly forth, by reaſon of the cold ſlowneſs of the humors; but much the rather, for that the vein doth not receive the impreſſion of the Lancet, ſliding this way and that way, by reaſon of the windineſs contained in it, and becauſe that the harſh drineſs of the upper skin, reſiſts the edge of the inſtrument. Their bodies ſeem cold and hard to the touch, and they are troubled with terrible dreams, for they are obſerved to ſeem to ſee in the night Devils, Serpents, dark dens and caves, ſepulchres, dead corpſes, and many other ſuch things full of horror, by reaſon of a black vapor, diverſly moving and diſturbing the brain, which alſo we ſee happens to thoſe who * fear the water, by reaſon of the biting of a mad Dog. You ſhall find them froward, fraudulent, parſimonious, and covetous even to baſeneſs, ſlow ſpeakers, fearful, ſad, complainers, careful, ingenious, lovers of ſolitarineſs, man-haters, obſtinate maintainers of opinions once conceived, ſlow to anger, but angred not to be pacified. But when Melancholy hath exceeded natures and its own bounds, then by reaſon of putrefaction and inflammation all things appear full of extreme fury and madneſs, ſo that they often caſt themſelves headlong down from ſome high place, or are otherwiſe guilty of their own death, with fear of which notwithſtanding they are terrified.

From, or by what their Veins are ſwollen.

Their dreams.

* *Hydrophobi.*

Their manners.

But

But we muſt note, that changes of the native Temperament, do often happen in the courſe of a mans life, ſo that he which a while agone was Sanguine, may now be Choleric, Melancholic, or Phlegmatic; not truly, by the changing of the blood into ſuch Humors, but by the mutation of Diet, and the courſe or vocation of life. For none of a Sanguine complexion, but will prove Choleric, if he eat hot and dry meats, (as all like things are cheriſht and preſerved by the uſe of their like, and contraries are deſtroy'd by their contraries) and weary his body by violent exerciſes and continual labors; and if there be a ſuppreſſion of Choleric excrements, which before did freely flow either by Nature or Art. But whoſoever feeds upon Meats generating groſs blood, as Beef, Veniſon, Hare, old Cheeſe, and all ſalt Meats, he without all doubt ſliding from his nature will fall into a Melancholy temper; eſpecially, if to that manner of Diet, he ſhall have a vocation full of cares, turmoils, miſeries, ſtrong and much ſtudy, careful thoughts and fears; and alſo if he ſit much, wanting exerciſe, for ſo the inward heat, as it were defrauded of its nouriſhment, faints and grows dull, whereupon groſs and droſſie humors abound in the body. To this alſo the cold and dry condition of the place in which we live, doth conduce, and the ſuppreſſion of the Melancholy humor accuſtomed to be evacuated by the Hemorrhoids, courſes and ſtools.

From whence the change of the native temper.

How one may become Choleric.

How Melancholic.

But he acquires a Phlegmatic temper, whoſoever uſeth cold and moiſt nouriſhment, much feeding, who before the former meat is gone out of the belly, ſhall ſtuff his paunch with more, who preſently after meat runs into violent exerciſes, who inhabit cold and moiſt places, who lead their life at eaſe in all idleneſs; and laſtly, who ſuffer a ſuppreſſion of the Plegmatic humor accuſtomably evacuated by vomit, cough or blowing the noſe, or any other way, either by Nature or Art. Certainly it is very convenient to know theſe things, that we may diſcern if any at the preſent be Phlegmatic, Melancholic, or of any other temper; whether he be ſuch by nature or neceſſity. Having declared thoſe things which concern the nature of Temperaments, and deferred the deſcription of the parts of the Body to our Anatomy, we will begin to ſpeak of the Faculties governing this our life, when firſt we ſhall have ſhewn, by a practical demonſtration of examples, the uſe and certainty of the aforeſaid Rules of Temperaments.

How Phlegmatic.

CHAP. VII.

Of the Practice of the aforeſaid Rules of Temperaments.

THat we may draw the Theoric of the Temperaments into practice, it hath ſeemed good for avoiding of confuſion which might make this our Introduction ſeem obſcure, if we would proſecute the differences of the Tempers of all men of all Nations, to take thoſe limits which Nature hath placed in the world; as South, North, Eaſt and Weſt, and, as it were, the Center of thoſe bounds, that the deſcribed variety of Tempers, in colour, habit, manners, ſtudies, actions, and form of life of men that inhabit thoſe Regions ſituated ſo far diſtant one from another, may be as a ſure rule, by which we may certainly judge of every mans temperature in particular, as he ſhall appear to be nearer or further off from this or that Region. Thoſe which inhabit the South, as the *Africans*, *Æthiopians*, *Arabians* and *Egyptians*, are for the moſt part deformed, lean, dusky-colored, and pale, with black eyes and great lips, curled hair, and a ſmall and ſhrill voice. Thoſe which inhabit the Northern parts, as the *Scythians*, *Moſcovites*, *Polonians*, and *Germans* have their faces of color white, mixt with a convenient quantity of blood, their skin ſoft and delicate, their hair long, hanging down and ſpreading abroad, and of a yellowiſh or reddiſh colour; of ſtature they are commonly tall, and of a well-proportioned, fat and compact habit of body, their eyes grey, their voice ſtrong, loud and big. But thoſe who are ſituated between theſe two former, as the *Italians* and *French*, have their faces ſomewhat ſwart, are well-favoured, nimble, ſtrong, hairy, ſlender, well in fleſh, with their eyes reſembling the color of Goats-eye, and often hollow-eyed, having a clear, ſhrill and pleaſing voice.

Four bounds or regions of the world.

The forces of temperatures in particular.

The temperature of the Southern people.

Of the Northern.

The Southern people prevail in wit, the Northern in ſtrength.

The Southern people learn'd and religious.

The Northern famous Warriers and Artificers.

The Southern people are exceeded ſo much by the Northern in ſtrength and ability of body, as they ſurpaſs them in wit and faculties of the mind. Hence is it you may read in Hiſtories, that the *Scythians*, *Goths* and *Vandals* vexed *Afric* and *Spain* with infinite incurſions, and moſt large and famous Empires have been founded from the North to South; but few or none from the South to the North. Therefore the Northern people thinking all right and law to conſiſt in Arms, did by Duel only determin all cauſes and controverſies ariſing amongſt the Inhabitants, as we may gather by the antient Laws and Cuſtoms of the *Lombards*, *Engliſh*, *Burgundians*, *Danes* and *Germans*; and we may ſee in *Saxo* the Grammarian, that ſuch a Law was once made by *Fronto* King of *Denmark*. The which Cuſtom at this day is every where in force amongſt the *Moſcovites*. But the Southern people have always much abhorred that faſhion, and have thought it more agreeable to Beaſts than Men. Wherefore we never heard of any ſuch thing uſed by the *Aſſyrians*, *Egyptians*, *Perſians* or *Jews*: But moved by the goodneſs of their wit, they erected Kingdoms and Empires by the only help of Learning and hidden Sciences. For ſeeing by nature they are Melancholic, by reaſon of the drineſs of their temperature, they willingly addict themſelves to ſolitarineſs and contemplation, being endued with a ſingular ſharpneſs of wit. Wherefore the *Ethiopians*, *Egyptians*, *Africans*, *Jews*, *Phœnicians*, *Perſians*, *Aſſyrians*, and *Indians*, have invented many curious Sciences, revealed the myſteries and ſecrets of Nature, digeſted the Mathematics into order, obſerved the motions of the Heavens, and firſt brought in the worſhip and religious ſacrifices of the gods: Even ſo far that the *Arabians* who live only by ſtealth, and have only a Wagon for their Houſe, do boaſt that they have many things diligently and accurately obſerved in Aſtrology by their Anceſtors, which every day made more accurate and copious, they as by an hereditary right, commend to poſterity, as it is recorded by *Leo* the *African*. But the Northern people, as the *Germans*, by reaſon of the abundance of humors and blood, by which the mind is as it were oppreſt, apply themſelves to works obvious to the ſenſes, and which may be done by the hand. For, their minds oppreſt with the earthly maſs of their bodies, are eaſily drawn

drawn from heaven and the contemplation of celeſtial things, to theſe inferior things, as to find out Mines by digging, to buy and caſt metals, to draw and hammer out works of Iron, Steel and Braſs. In which things they have proved ſo excellent, that the glory of the Invention of Guns and Printing belongs to them.

The endowments of ſuch as inhabit between them.

The people who inhabit the middle regions between theſe are neither naturally fit for the more abſtruſe Sciences, as the Southern people are; nor for Mechanic works, as the Northern; but intermeddle with civil affairs, commerce and Merchandizing. But are endued with ſuch ſtrength of body as may ſuffice to avoid and delude the crafts and arts of the Southern Inhabitants; and with ſuch wiſdom as may be ſufficient to reſtrain the fury and violence of the Northern. How true this is, any one may underſtand by the example of the *Carthaginians* and *Africans*, who when they had held *Italy* for ſome years by their ſubtle counſels, crafty ſleights and devices; yet could not eſcape, but at length their arts being eluded, and they ſpoil'd of all their fortunes, were brought in ſubjection to the *Romans*.

The Northern know how to overcome, but not how to uſe the victory.

The *Goths*, *Hunns* and other Northern People have ſpoiled and over-run the *Roman* Empire by many incurſions and inroads, but deſtitute of counſel and providence, they could not keep thoſe things which they had gotten by Arms and Valour.

The abundance of Counſellors and Lawyers from *France* and *Italy*.

Therefore the Opinion of all Hiſtorians is agreeing in this, that good Laws, the form of governing a Common-wealth, all politic Ordinances, the Arts of diſputing and ſpeaking have had their beginnings from the *Greeks*, *Romans* and *French*. And from hence in times paſt and at this day a greater number of Writers, Lawyers and Counſellors of State have ſprung up than in all the whole world beſides. Therefore that we may attribute their gifts to each Region, we affirm that the Southern People are born and fit for the ſtudies of Learning, the Northern for Wars, and thoſe between both for Empire and Rule. The *Italian* is naturally wiſe, the *Spaniard* grave and conſtant, the *French* quick and diligent; for you would ſay he runs when he goes, being compared to the ſlow pace of the *Spaniard*, which is the cauſe that *Spaniards* are delighted with *French* Servants for their quick agility in diſpatching buſineſs.

The manners of the Eaſtern people.

The Eaſtern people are ſpecially endued with a good, firm and well-temper'd wit, not keeping their counſels ſecret and hid. For haſte is of the nature of the Sun, and that part of the day which is next to the riſing of the Sun is counted the right ſide and ſtronger; and verily in all things living, the right ſide is always the more ſtrong and vigorous. But the Weſtern people are more tender and effeminate, and more cloſe in their carriage and mind, not eaſily making any one partaker of their ſecrets. For the Weſt is as it were ſubject to the Moon, becauſe at the change it always inclines to the Weſt, whereby it happens that it is reputed as nocturnal, ſiniſter and oppoſite to the Eaſt; and the Weſt is

The Eaſtwind healthful.

leſs temperate and wholſom. Therefore of the Winds none is more wholſom than the Eaſt-wind, which blows from the Weſt with a moſt freſh and healthful gale; yet it ſeldom blows, but only at Sun-ſet.

The Northern people great eaters and drinkers.

The Northern people are good eaters, but much better drinkers, witty when they are a little moiſtned with Wine, and talkers of things both to be ſpoken and concealed, not very conſtant in their promiſes and agreements, but principal keepers and preſervers of ſhame-fac'dneſs and chaſtity, far different from the Inhabitants of the South, who are wonderful ſparing, ſober, ſecret and ſubtle,

Who are to be counted barbarous.

and much addicted to all ſorts of wicked Luſt. *Ariſtotle* in his *Problems* ſaith, that thoſe Nations are barbarous and cruel, both which are burnt with immoderate heat, and which are oppreſt with exceſſive cold, becauſe a ſoft temper of the Heavens ſoftens the manners and the mind. Wherefore

The Northern and Southern have each their cruelties.

both as well the Northern as *Scythians* and *Germans*; and the Southern, as *Africans*, are cruel; but theſe have this of a certain natural ſtoutneſs and ſoldier-like boldneſs, and rather of anger than a wilful deſire of revenge; becauſe they cannot reſtrain by the power of reaſon the firſt violent motions of their anger by reaſon of the heat of their blood. But thoſe of a certain inbred and inhumane pravity of manners wilfully and willingly premeditating they perform the works of cruelty, becauſe they are of a ſad and melancholy nature. You may have an example of the Northern cruelty from the *Tranſylvanians* againſt their ſeditious Captain *George*, whom they gave to be torn in pieces alive and devoured by his Souldiers, (being kept faſting for three days before for that purpoſe) who was then unbowelled, and roſted, and ſo by them eaten up. The cruelty of *Hannibal* the Captain of the *Carthaginians* may ſuffice for an inſtance of the Southern cruelty. He left the Roman Captives wearied with burdens and the length of the way, with the ſoles of their feet cut off; But thoſe he brought into his Tents, joyning brethren and kinſmen together he cauſed to fight, neither was ſatisfied with blood before he brought all the victors to one man. Alſo we may ſee the cruel nature of the Southern *Americans*, who dip their children in the blood of their ſlain enemies, then ſuck their blood, and banquet with their broken and ſqueaſed Limbs.

Val. Max. l.9. c. 2.

The diſeaſes of the Southern people.

And as the Inhabitants of the South are free from divers Plethoric Diſeaſes, which are cauſed by abundance of blood (to which the Northern people are ſubject) as Feavers, Defluxions, Tumors, Madneſs with laughter, which cauſeth thoſe which have it to leap and dance, (the people commonly term it *S. Vitus his evil*) which admits of no remedy but Muſic: ſo they are often moleſted with the Frenſie, invading with madneſs and fury; by the heat whereof they are often ſo raviſht and carried beſide themſelves, that they foretel things to come; they are terrified with horrible dreams, and in their fits they ſpeak in ſtrange and forein tongues; but they are ſo ſubject to the ſcurf and all kind of ſcabs and to the Leproſie as their homebred diſeaſe, that no houſes are ſo frequently met withal by ſuch as travel through either of the *Mauritania's*, as Hoſpitals provided for the Lodging of Lepers.

Mountainers.

Thoſe who inhabit rough and mountainous places, are more brutiſh, tough and able to endure labour. but ſuch as dwell in Plains, eſpecially if they be mooriſh or fenniſh, are of a tender body, and ſweat much with a little labour; the truth of which is confirmed by the *Hollanders* and *Friſelanders*. But if the Plain be ſuch as is ſcorched by the heat of the Sun, and blown upon by much contrariety of winds, it breeds men who are turbulent, not to be tamed, deſirous of ſedition and novelty, ſtubborn, impatient of ſervitude, as may be perceived by the ſole example of the Inhabitants of *Narbon*, a Province of *France*. Thoſe who dwell in poor and barren places are commonly more witty and diligent

and

and moſt patient of labors; the truth of which the famous wits of the *Athenians*, *Ligurians* and *Romans*, and the plain country of the *Bœotians* in *Greece*, of the *Campanians* in *Italy*, and of the reſt of the Inhabiters adjoining to the *Ligurian* Sea, approves.

CHAP. VIII.
Of the Faculties.

A Faculty is a certain power and efficient cauſe, proceeding from the temperament of the part, and the performer of ſome actions of the body. There are three principal Faculties governing mans body, as long as it enjoys its integrity; the Animal, Vital and Natural. The Animal is ſeated in the proper temperament of the Brain, from whence it is diſtributed by the Nerves into all parts of the body which have ſenſe and motion. This is of three kinds; for one is Moving, another Senſitive, the third Principal. The Senſitive conſiſts in five external Senſes; Sight, Hearing, Taſte, Smell and Touch. The Moving principally remains in the Muſcles and Nerves, as the fit inſtruments of voluntary motion. The Principal comprehends the Reaſoning Faculty, the Memory and Fantaſie. *Galen* would have the common or inward Senſe to be comprehended within the compaſs of the Fantaſie, although *Ariſtotle* diſtinguiſh between them.

What a Faculty is.
3 Faculties.

The Vital abides in the heart, from whence heat and life is diſtributed by the Arteries to the whole body; this is principally hindred in the diſeaſes of the Breaſt; as the Principal is, when any diſeaſe aſſails the Brain; the prime Action of the vital faculty is Pulſation, and that continued agitation of the Heart and Arteries, which is of threefold uſe to the body: for by the dilatation of the Heart and Arteries, the Vital Spirit is cheriſhed by the benefit of the Air which is drawn in; by the contraction thereof, the vapors of it are purged and ſent forth, and the native heat of the whole body is tempered by them both.

The triple uſe of the Pulſe.

The laſt is the Natural Faculty which hath choſen its principal ſeat in the Liver, it ſpreads or carries the nouriſhment over the whole body; but it is diſtinguiſht into three other faculties; The Generative, which ſerves for the generation and forming of the Iſſue in the womb; the Growing or Increaſing faculty, which flouriſheth from the time the Iſſue is formed, until the perfect growth of the ſolid parts into their full dimenſions of length, heighth and breadth. The nouriſhing faculty, which as ſervant to both the other, repairs and repays the continual efflux and waſte of the threefold ſubſtance; for Nutrition is nothing elſe but a repleniſhing or repairing whatſoever is waſted or emptied. This nouriſhing faculty endures from that time the Infant is formed in the womb until the end of life. It is a matter of great conſequence in Phyſic, to know the four other faculties, which as Servants attend upon the nouriſhing faculty; which are the Attractive, Retentive, Digeſtive and Expulſive faculty. The Attractive draws that Juice which is fit to nouriſh the body; that, I ſay, which by application may be aſſimilated to the part. This is that faculty, which in ſuch as are hungry, draws down the meat ſcarce chewed, and the drink ſcarce taſted, into the gnawing and empty ſtomach. The Retentive faculty is that which retains the nouriſhment once attracted, until it be fully laboured and perfectly concocted; and by that means it yields no ſmall aſſiſtance to the Digeſtive faculty. For the natural heat cannot perform the office of concoction, unleſs the meat be embraced by the part, and make ſome ſtay therein. For otherwiſe the meat, carried into the ſtomach, never acquires the form of *Chylus*, unleſs it ſtay detained in the wrinkles thereof as in a rough paſſage, until the time of *Chylification*. The Digeſtive faculty aſſimilates the nouriſhment, being attracted and detained, into the ſubſtance of that part whoſe faculty it is, by the force of the inbred heat and proper diſpoſition or temper of the part. So the ſtomach plainly changes all things which are eat and drunk into *Chylus*, and the Liver turns the *Chylus* into blood. But the Bones and Nerves convert the red and liquid blood, which is brought down unto them by the capillary or ſmall veins, into a white and ſolid ſubſtance. Such concoction is far more laborious in a Bone and Nerve, than in the Muſculous fleſh. For the blood being not much different from its nature, by a light change and concretion turns into fleſh. But this Concoction will never ſatisfie the deſire of nature and the parts, unleſs the nouriſhment, purged from its excrements, put away the filth and droſs, which muſt never enter into the ſubſtance of the part. Wherefore there do not only two ſorts of excrements remain of the firſt and ſecond Concoction, the one thick, the other thin, as we have ſaid before; but alſo from the third Concoction which is performed in every part. The one of which we conceive only by reaſon, being that which vaniſheth into Air by inſenſible tranſpiration. The other is known ſometimes by ſweats, ſometimes by a thick fatty ſubſtance ſtaining the ſhirt; ſometimes by the generation of hairs and nails, whoſe matter is from fuliginous and earthly excrements of the third Concoction. Wherefore the fourth faculty was neceſſary which might yield no ſmall help to nouriſhment; it is called the Expulſive, appointed to expel thoſe ſuperfluous excrements which by no action of heat can obtain the form of the part. Such faculties ſerving for nutrition are in ſome parts twofold; as ſome common, the benefit of which redounds to the whole body, as in the ventricle, liver and veins; Others only attending the ſervice of thoſe parts in which they remain, and in ſome parts all theſe four, as well common as proper, are abiding and reſiding as in thoſe parts we now mentioned; ſome, with the four proper have only two common, asthe Gall, Spleen, Kidneys and Bladder. Others are content only with the proper, as the ſimilar and muſculous parts, who if they want any of theſe four faculties, their health is decayed either by want of nouriſhment, an ulcer, or otherwiſe. The like unnatural affects happen by the deficiency of juſt and laudable nouriſhment. But if it happen thoſe faculties do rightly perform their duty, the nouriſhment is changed into the proper part, and is truly aſſimilated as by theſe degrees. Firſt, it muſt flow to the part, then be joined to it, then agglutinated, and laſtly, as we have ſaid, aſſimilated. Now we muſt ſpeak of the Actions which ariſe from the faculties.

The natural Faculty is threefold.

What Nutrition is.

Four other Faculties attend upon the nouriſhing Faculty.

The neceſſity of the retentive Faculty.

Two excrements of every concoction.

The work of the expulſive Faculty.

By what degrees the nouriſhment is aſſimilated.

CHAP. IX.

Of the Actions.

What an Action is.

AN Action or Function is an active motion proceeding from a faculty; for as the faculty depends on the Temperament, ſo the Action on the faculty, and the Act or Work depends upon the Action by a certain order of conſequence. But although that the Words, Action and Act or work are often confounded; yet there is this difference between them, as that the Action ſignifies the motion uſed in the performance of any thing; but the Act or work, the thing already done and performed: For example, Nutrition and the Generating of fleſh are natural Actions; but the parts nouriſhed, and a hollow ulcer filled with fleſh are the works of that motion, or action. Wherefore the Act ariſeth from the Action, as the Action ariſeth from the Faculty, the integrity or perfection of the inſtruments concurring in both. For as, if the Faculty be either defective, or hurt, no Action will be well performed: ſo unleſs the inſtruments keep their native and due conformity (which is their perfect health, the operator of the Action proper to the inſtrument) none of thoſe things, which ought to be, will be well performed. Therefore for the performance of blameleſs and perfect actions, it is fit a due conformity of the inſtrument concur with the faculty. But Actions are two-fold: for they are either Natural, or Voluntary. They are termed Natural, becauſe they are performed not by our will, but by their own accord, and againſt our will: As are, that continual motion of the Heart, the beating of the Arteries, the expulſion of the Excrements, and ſuch other like, which are done in us by the Law of Nature whether we will or no. Theſe Action flow either from the Liver and Veins, or from the Heart and Arteries. Wherefore we may comprehend them under the names of Natural and Vital Actions. For we muſt attribute his Action to each faculty, leſt we ſeem to conſtitute an idle faculty and no way profitable for uſe. The unvoluntary vital Actions, are the dilatation and contraction of the Heart and Arteries, the which we comprehend under the ſole name of the Pulſe: by that they draw in, and by this they expel or drive forth. The unvoluntary vital actions be,

An Action and an Act are different.

Natural Actions.

Generation, Growth, and Nutrition, } which proceed from the { Generative, Growing, and Nouriſhing } Faculty.

What Generation is.

Generation is nothing elſe than a certain producing or acquiring of matter, and an introducing of a ſubſtantial form into that matter: this is performed by the aſſiſtance of two faculties; of the altering, which doth diverſly prepare and diſpoſe the ſeed and menſtruous blood to put on the form of a Bone, Nerve, Spleen, Fleſh, and ſuch like: of the Forming faculty, which adorns with figure, ſite, and compoſition, the matter ordered by ſo various a preparation.

What Growth is.

Growth is an inlarging of the ſolid parts into all the dimenſions, the priſtine and ancient form remaining ſafe and ſound in figure and ſolidity. For the perfection of every growth is judged only by the ſolid parts; for if the body ſwell into a maſs of fleſh, or fat, it ſhall not therefore be ſaid to be grown: but then only when the ſolid parts do in like manner increaſe, eſpecially the bones, becauſe the growth of the whole body follows their increaſe, even although at the ſame time it wax lean and pine away.

What Nutrition is.

Nutrition is a perfect aſſimilation of that nouriſhment which is digeſted, into the nature of the part which digeſts. It is performed by the aſſiſtance of four ſubſidiary or helping actions, Attractive, Retentive, Digeſtive and Expulſive.

Action voluntary.

The voluntary actions which we willingly perform, are ſo called, becauſe we can at our pleaſure hinder, ſtir up, ſlow or quicken them. They are three in general, the ſenſative, moving and principal Action. The ſenſitive * Soul comprehends all things in five ſenſes, in Sight, Hearing, Smell, Taſte, and Touch. Three things muſt neceſſarily concur to the performance of them, the Organ, the *Medium* or Mean and the Object. The principal Organ or Inſtrument is the Animal Spirit diffuſed by the Nerves into each ſeveral part of the body, by which ſuch actions are performed. Wherefore for the preſent we will uſe the parts themſelves for their Organs. The Mean is a Body, which carries the Object to the Inſtrument. The Object is a certain external quality, which hath power by a fit *Medium* or Mean to ſtir up and alter the Organ. This will be more manifeſt by relating the particular functions of the Senſes by the neceſſary concurring of theſe three.

* *Anima ſentiens.*

How Sight is performed.

Sight is an action of the ſeeing faculty, which is done by the Eye, fitly compoſed of its coats and humors, and ſo conſequently the Organical body of this Action. The Object is a viſible quality brought to the Eye. But ſuch an Object is two-fold; for either it is abſolutely viſible of itſelf, and by its own nature, as the Sun, the Fire, the Moon and Stars; or deſires, as it were, the help of another that it may be actually ſuch; for ſo by the coming of the light colours, which were viſible in power only, being brought to the Eye, they do ſeem and appear ſuch as they actually are. But ſuch Objects cannot arrive at the Eye, but through a clear and illuminate *Medium*, as the Air, Water, Glaſs, and all ſorts of Cryſtal.

How Hearing.

The Hearing hath for its Organ the Ear and Auditory paſſage, which goes to the ſtony-bone furniſhed with a Membrane inveſting it, an Auditory Nerve, and a certain inward ſpirit there contained. The Object is every ſound ariſing from the ſmitten or broken Air, and the Colliſion of two bodies meeting together. The *Medium* is the encompaſſing Air which carries the ſound to the Ear.

How Smelling.

Smelling (according to *Galen*'s opinion) is performed in the mamillary proceſſes produced from the proper ſubſtance of the brain, and ſeated in the upper part of the noſe: although others had rather ſmelling ſhould be made in the very foremoſt ventricles of the brain. This Action is weak in man, in compariſon of other Creatures: the Object thereof is every ſmell, or fumid exhalation breathing out of bodies. The *Medium* by which the Object is carried to the noſes of Men, Beaſts and Birds,

How the Taſt.

is the Air; but to Fiſhes the Water itſelf. The Action of Taſte, is performed by the Tongue, being

being tempered well and according to nature, and furniſhed with a Nerve ſpread over its upper part from the third and fourth Conjugation of the Brain. The Object is * Taſte, of whoſe nature and kinds we will treat more at large in our Antidotary. The *Medium* by the which the Object is ſo carried to the Organ, that it may affect it, is either external or internal: The external is that ſpattle which doth, as it were, anoint and ſupple the tongue; the internal is the ſpongy fleſh of the tongue it ſelf, which affected with the quality of the Object, doth preſently ſo poſſeſs the nerve that is planted in it, that the kind and quality thereof, by the force of the ſpirit, may be carried into the common ſenſe. All parts endued with a nerve, enjoy the ſenſe of touching, which is chiefly done, when a tractable quality doth penetrate even to the true and nervous skin, which lieth under the Cuticle, or ſcarf-skin; we have formerly noted, that it is moſt exquiſite in the skin which inveſts the ends of the fingers. The Object is every tractable quality, whether it be of the firſt rank of qualities, as Heat, Cold, Moiſture, Dryneſs; or of the ſecond, as Roughneſs, Smoothneſs, Heavineſs, Lightneſs, Hardneſs, Softneſs, Rarity, Denſity, Friability, Unctuoſity, Groſſneſs, Thinneſs. The *Medium* by whoſe procurement the inſtrument is affected, is either the skin or the fleſh interwoven with many Nerves.

* *Sapor.*

How touching.

The next Action, is that Motion which by a peculiar name we call Voluntary; this is performed and accompliſhed by a Muſcle, being the proper Inſtrument of voluntary Motion. Furthermore, every motion of a member poſſeſſing a Muſcle, is made either by bending and contraction, or by extenſion: Although generally there be ſo many differences of voluntary motion, as there are kinds of ſite in place; therefore Motion is ſaid to be made upward, downward, to the right hand, to the left, forward and backward: Hither are referred the many kinds of motions, which the infinite variety of Muſcles produce in the body. Into this rank of voluntary Actions, comes Reſpiration, or breathing, becauſe it is done by the help of the Muſcles, although it be chiefly to temper the heat of the Heart. For we can make it more quick or ſlow as we pleaſe, which are the conditions of a voluntary Motion.

Of motion.

How Reſpiration may be a voluntary motion.

Laſtly, that we may have ſomewhat in which we may ſafely reſt and defend our ſelves againſt the many queſtions which are commonly moved concerning this thing, we muſt hold, that Reſpiration is undergone and performed by the Animal faculty, but chiefly inſtituted for the Vital.

The principal Action and prime amongſt the Voluntary, is abſolutely divided into three, Imagination, Reaſoning and Memory.

The third principal Action.

Imagination is a certain expreſſing and apprehenſion, which diſcerns and diſtinguiſheth between the forms and ſhapes of things ſenſible, or which are known by the ſenſes.

Reaſoning is a certain judicial eſtimation of conceived or apprehended forms or figures, by a mutual collating or comparing them together.

Memory is the ſure ſtorer of all things, and as it were the Treaſury which the mind often unfolds and opens, the other faculties of the mind being idle and not imployed. But becauſe all the forementioned Actions, whether they be Natural, or Animal and Voluntary, are done and performed by the help and aſſiſtance of the Spirits; therefore now we muſt ſpeak of the Spirits.

CHAP. X.

Of the Spirits.

THe Spirit is a ſubtil and airy ſubſtance, raiſed from the purer blood, that it might be a vehicle for the faculties (by whoſe power the whole body is governed) to all the parts, and the prime inſtrument for the performance of their Office. For they, being deſtitute of its ſweet approach, do preſently ceaſe from action, and as dead, do reſt from their accuſtomed labours. From hence it is, that making a variety of Spirits according to the number of the faculties, they have divided them into three; as one Animal, another Vital, another Natural.

What a Spirit is.

Spirits threefold.

The Animal hath taken his ſeat in the Brain; for there it is prepared and made, that, from thence conveyed by the Nerves, it may impart the power of ſenſe and motion to all the reſt of the members. An Argument hereof is, that in the great cold of Winter, whether by the intercepting them in their way, or by the concretion, or, as it were, freezing of thoſe ſpirits, the joynts grow ſtiff, the hands numb, and all the other parts are dull, deſtitute of their accuſtomed agility of motion, and quickneſs of ſenſe. It is called Animal, not becauſe it is the * Life, but the chief and prime inſtrument thereof: Wherefore it hath a more ſubtil and airy ſubſtance; and enjoys divers names, according to the various condition of the Senſories, or ſeats of the ſenſes, into which it enters; for that which cauſeth the ſight, is named the Viſive: You may ſee this by night, rubbing your eyes, as ſparkling like fire. That which is conveyed to the Auditory paſſage, is called the Auditive or Hearing; that which is carried to the inſtruments of Touching, is termed the Tactive; and ſo of the reſt.

The Animal Spirit.

Why ſo called * *Anima.*

This Animal ſpirit is made and laboured in the windings and foldings of the Veins and Arteries of the brain, of an exquiſite ſubtil portion of the Vital brought thither by the *Carotidæ Arteriæ*, or ſleepy Arteries; and ſometimes alſo of the pure air, or ſweet vapour drawn by the Noſe in breathing. Hence it is, that with Ligatures we ſtop the paſſage of this ſpirit, from the parts we intend to cut off. An Humour which obſtructs or ſtops it paſſage, doth the like in Apoplexies and Palſies, whereby it happens that the members ſituate under that place do languiſh and ſeem dead, ſometimes deſtitute of motion, ſometimes wanting both ſenſe and motion.

How it is made.

The Vital ſpirit is next to it in dignity and excellency, which hath its chief Manſion in the left ventricle of the Heart, from whence, through the Channels of the Arteries, it flows into the whole body, to nouriſh the heat which reſides fixed in the ſubſtance of each part, which would periſh in

The Vital Spirit.

ſhort time, unleſs it ſhould be refreſhed with heat flowing thither together with the ſpirit. And becauſe it is the moſt ſubtil next to the Animal, Nature (leſt it ſhould vaniſh away) would have it contained in the nervous coat of an Artery, which is five times more thick than the coat of the Veins, as *Galen*, out of *Herophilus*, hath recorded.

What the matter of it is.

It is furniſhed with matter from the ſubtil exhalation of the blood, and that air which we draw in breathing. Wherefore, as it doth eaſily and quickly periſh by immoderate diſſipations of the ſpirituous ſubſtance, and great evacuations; ſo it is eaſily corrupted by the putrefaction of Humors, or breathing in of peſtilent air and filthy vapours; which thing is the cauſe of the ſo ſudden death of thoſe which are infected with the Plague. This Spirit is often hindred from entring into ſome part, by reaſon of obſtruction, fullneſs, or great inflammations; whereby it follows, that in a ſhort ſpace, by reaſon of the decay of the fixed and inbred heat, the parts do eaſily fall into a Gangrene, and become mortified.

There is ſome doubt of the Natural Spirit.

The Natural ſpirit (if ſuch there be any) hath its ſtation in the Liver and Veins. It is more groſs and dull than the other, and inferiour to them in the dignity of the Action, and the excellency of the uſe. The uſe thereof is to help the concoction both of the whole body, as alſo of each ſeveral part, and to carry blood and heat to them.

Fixed Spirits.

Beſides thoſe already mentioned, there are other Spirits fixed and implanted in the ſimilar and prime parts of the body, which alſo are natural, and Natives of the ſame place in which they are ſeated and placed. And becauſe they are alſo of an airy and fiery nature, they are ſo joyned, or rather united to the Native heat, that they can no more be ſeparated from it than flame from heat; wherefore they with theſe that flow to them, are the principal Inſtruments of the Actions which are performed in each ſeveral part: And theſe fixed Spirits have their nouriſhment and maintenance from the radical and firſt-bred moiſture, which is of an airy and oily ſubſtance, and is, as it were, the foundation of theſe Spirits, and the inbred heat. Therefore without this moiſture, no man can live a moment. But alſo the chief Inſtruments of life are theſe Spirits, together with the Native heat. Wherefore this radical Moiſture being diſſipated and waſted (which is the ſeat, fodder and nouriſhment of the Spirits and heat) how can they any longer ſubſiſt and remain? Therefore the conſumption of the natural heat, followeth the decay of this ſweet and ſubſtance-making moiſture, and conſequently death, which happens by the diſſipating and reſolving of natural heat.

The radical moiſture.

Natural death.

But ſince then theſe kinds of Spirits, with the natural heat, is contained in the ſubſtance of each ſimilar part of our body (for otherwiſe it could not perſiſt) it muſt neceſſarily follow, that there be as many kinds of fixed Spirits, as of ſimilar parts. For becauſe each part hath its proper temper and increaſe, it hath alſo its proper Spirit, and alſo its own proper fixed and implanted heat, which here hath its abode, as well as its Original. Wherefore the Spirit and heat which is ſeated in the bone, is different from that which is impact into the ſubſtance of a Nerve, Vein, or ſuch other ſimilar part; becauſe the temper of theſe parts is different, as alſo the mixture of the Elements from which they firſt aroſe and ſprung up. Neither is this contemplation of Spirits of ſmall account, for in theſe conſiſt all the force and efficacy of our Nature.

The uſe and neceſſity of the Spirits.

Theſe being by any chance diſſipated or waſted, we languiſh; neither is health to be hoped for, the flower of life withering and decaying by little and little. Which thing ought to make us more diligent, to defend them againſt the continual efflux of the threefold ſubſtance. For if they be decayed, there is left no proper indication of curing the diſeaſe; ſo that we are often conſtrained, all other care laid aſide, to betake our ſelves to the reſtoring and repairing the decayed powers. Which is done by meats of good juyce, eaſie to be concocted and diſtributed; good Wines, and fragrant ſmells.

What the remedy for the diſſipation of the Spirits.

But ſometimes theſe Spirits are not diſſipated, but driven in and returned to their fountains, and ſo both oppreſs and are oppreſt; whereupon it happens we are often forced to dilate, and ſpread them abroad by binding and rubbing the parts. Hitherto we have ſpoke of thoſe things which are called Natural, becauſe we naturally conſiſt of them; it remains that we now ſay ſomewhat of their Adjuncts and Aſſociates by familiarity of Condition.

What the remedy for oppreſſion of the Spirit is.

The Adjuncts and Aſſociates to things natural; are,

- *Age:* Of which, by reaſon of the ſimilitude of the Argument, we were conſtrained to ſpeak, when we handled the Temperatures.
- *Sex.*
- *Colour:* Of which we have already ſpoken.
- The Conformation of the *Inſtrumental* parts.
- *Time:* whoſe force we have alſo conſidered.
- *Region.*
- Order of *Diet*, and condition of *Life*.

CHAP. XI.

Of the Adjuncts of things Natural.

What ſex is.

SEX is no other thing than the diſtinction of Male and Female; in which this is moſt obſervable, that for the parts of the body, and the ſite of theſe parts, there is little difference between them; but the Female is colder than the Male. Wherefore their ſpermatical parts are more cold, ſoft, and moiſt; and all their natural actions leſs vigorous and more depraved.

The nature of women.

Of Eunuchs.

The Nature of Eunuchs is to be referred to that of women, as who may ſeem to have degenerated into a womaniſh nature, by deficiency of heat; their ſmooth body, and ſoft and ſhrill voyce do very much aſſimilate women. Notwithſtanding you muſt conſider, that there be ſome manly Women, which

which their manly voice, and chin covered with a little hairineſs, do argue; and on the contrary, theſe are ſome womanizing or womaniſh men, which therefore we term dainty and effeminate.

Of Hermaphrodites.

The Hermaphrodite is of a double nature, and in the middle of both Sexes, ſeems to participate of both Male and Female.

Colour the bewrayer of the Temperament.

The Colour which is predominant in the habit and ſuperficies of the body, and lies next under the skin, ſhews the Temperament of what kind ſoever it be; for, as *Galen* notes in *Comment. ad Aphor.* 2. *Sect.* 1. Such a colour appears in us, as the contained Humor hath. Wherefore if a Roſie hew colour the cheeks, it is a ſign the body abounds with blood, and that is carried abroad by the plenty of Spirits. But if the skin be died with a yellow colour, it argues Choler is predominant; if with a whitiſh and pallid hew, Phlegm; with a ſable and duskie, Melancholy. So the colour of the Excrements which are according to nature, is not of the leaſt conſideration. For thus, if an Ulcer being broken ſend forth white matter, it argues the ſoundneſs of the part from whence it flows; but if ſanious or bloody, green, blackiſh, or divers colours, it ſhews the weakneſs of the ſolid part, which could not aſſimilate by concoction the colour of the excrementitious humor. The like reaſon is of unnatural Tumors: For, as the colour, ſo the dominion of the Humor cauſing or accompanying the Swelling commonly is.

The perfection of the organical parts, conſiſts in four things.

The conformity and integrity of the Organical parts is conſidered by their figure, greatneſs, number, ſituation, and mutual connexion. We conſider the figure, when we ſay, almoſt all the external parts of the body are naturally round, not only for ſhew, but for neceſſity, that being ſmooth, and no way cornered, they ſhould be leſs obnoxious to external injuries. We ſpeak of Greatneſs, when we ſay, ſome are large and thick, ſome lank and lean. But we conſider their Number, when we obſerve ſome parts to abound, ſome to want, or nothing to be defective or wanting. We inſinuate Site and Connexion, when we ſearch, whether every thing be in its proper place, and whether they be decently fitted, and well joyned together.

We have handled the varieties of the four Seaſons of the Year, when we treated of Temperaments. But the conſideration of Region (becauſe it hath the ſame judgment that the Air) ſhall be referred to that diſquiſition or enquiry which we intend to make of the Air, amongſt the things Not-natural.

Diet.

The manner of life, and order of Diet, are to be diligently obſerved by us, becauſe they have great power either to alter, or preſerve the Temperament. But becauſe they are of almoſt infinite variety, therefore they ſcarce ſeem poſſible to fall into Art, which may proſecute all the differences of Diet and Vocations of life. Wherefore if the Calling of Life be laborious, as that of Husbandmen, Mariners, and other ſuch Trades, it ſtrengthens and dries the parts of the body. Although though thoſe which labour about Waters, are moſt commonly troubled with cold and moiſt diſeaſes, although they almoſt kill themſelves with labour.

Again, thoſe which deal with Metals, as all ſorts of Smiths, and thoſe which caſt and work braſs, are more troubled with hot diſeaſes, as Feavers. But if their Calling be ſuch, as they ſit much, and work all the day long ſitting at home, as Shoo-makers; it makes the body tender, the fleſh effeminate, and cauſeth great quantity of excrements. A life as well idle and negligent in body, as quiet in mind, in all riotouſneſs and exceſſes of Diet, doth the ſame. For from hence the body is made ſubject to the Stone, Gravel and Gout.

The commodities of an indifferent Diet.

That Calling of life which is performed with moderate labour, clothing and diet, ſeems very fit and convenient to preſerve the natural temper of the body. The ingenious Chirurgion may frame more of himſelf that may more particularly conduce to the examination of theſe things. Therefore the things natural, and thoſe which are near or neighbouring to them being thus briefly declared; the Order ſeems to require, that we make enquiry of things Not-natural.

CHAP. XII.

Of things Not-natural.

Why they are called things Not-natural.

THe things which we muſt now treat of, have by the later Phyſitians been termed Not-natural; becauſe they are not of the number of thoſe which enter into the conſtitution or compoſure of mans body; as, the Elements, Humors, and all ſuch things which we formerly comprehended under the name of Natural: Although they be ſuch as are neceſſary to preſerve and defend the body already made and compoſed. Wherefore they were called by *Galen* Preſervers; becauſe by the due uſe of them the body is preſerved in health. Alſo, they may be called Doubtful, and Neuters; for that rightly and fitly uſed, they keep the body healthful, but inconſiderately, they they cauſe diſeaſes. Whereby it comes to paſs, that they may be thought to pertain to that part of Phyſick which is of preſerving health; not becauſe ſome of theſe things ſhould be abſolutely and of their own nature wholſom, and others unwholſom; but only by this, that they are, or prove ſo by their convenient, or prepoſterous uſe. Therefore we conſider the uſe of ſuch like things from four conditions, Quantity, Quality, Occaſion, and Manner of uſing: If thou ſhalt obſerve theſe, thou ſhalt attain and effect this, That thoſe things which of themſelves are, as it were, doubtful, ſhall bring certain and undoubted health. For theſe four Circumſtances do ſo far extend, that in them, as in the perfection of Art, the Rules which may be preſcribed to preſerve health, are contained. But *Galen* in another place, hath in four words comprehended theſe things Not-natural; as, things Taken, Applied, Expelled, and to be Done. Things Taken, are thoſe which are put into the body, either by the mouth, or any other way; as the Air, Meat and Drink. Things applied, are thoſe which muſt touch the body, as the Air now mentioned, affecting the body with a diverſe touch of its qualities of heat, cold, moiſture or drineſs. Expelled, are what

Galen. 1. ad Glauconem.

Lib. de Sanitat. tuenda.

things ſoever being unprofitable, are generated in the body, and require to be expelled. To be Done, are labour, reſt, ſleep, watching, and the like. We may more diſtinctly, and by expreſſion of proper Names, revoke all theſe things to ſix:

Which are
- *Air.*
- *Meat* and *Drink.*
- *Labour* and *Reſt.*
- *Sleep* and *Watching.*
- *Repletion* and *Inanition*; or things to be expell'd, or retained and kept.
- *Perturbations* of the Mind.

CHAP. XIII.

Of the Air.

How neceſſary for life the Air is.

AIR is ſo neceſſary to life, that we cannot live a moment without it; if ſo be that breathing, and much more tranſpiration, be not to be ſeparated from life. Wherefore it much conduceth to know, what Air is wholſom, what unwholſom, and which by contrariety of qualities fights for the Patient againſt the Diſeaſe; or on the contrary, by a ſimilitude of qualities ſhall nouriſh the Diſeaſe, that if it may ſeem to burthen the Patient by increaſing or adding to the Diſeaſe, we may correct it by Art. So in curing the wounds of the head, eſpecially in Winter, we labour by all the means we may to make the Air warm. For cold is hurtful to the Brain, Bones, and the wounds of theſe parts; and heat is comfortable and friendly. But alſo the Air being drawn into the body by breathing when it is hotter than ordinary, doth with a new warmth over-heat the heart, lungs, and ſpirits, and weaken the ſtrength by the diſſipation of the Spirits too much attenuated; ſo being too cold, in like manner the ſtrength of the faculties faints and grows dull, either by ſuppreſſion of the vapors, or by the inſpiſſation or thickning of the Spirits.

What Air is hurtful.

Therefore to conclude, That air is to be eſteemed healthful, which is clear, ſubtil and pure, and free and open on every ſide, and which is far remote from all Carion-like ſmells of dead Carkaſſes, or the ſtench of any putrefying thing whatſoever: The which is far diſtant from ſtanding Pools, and Fens, and Caves, ſending forth ſtrong and ill vapors; neither too cloudy nor moiſt by the nearneſs of ſome River.

Such an Air, I ſay, if it have a vernal temper, is good againſt all diſeaſes, That Air which is contrary to this, is altogether unhealthful; as that which is putrid, ſhut up, and preſt by the ſtraitneſs of neighbouring Mountains, infected with ſome noiſom vapor. And becauſe I cannot proſecute all the conditions of Airs, fit for the expelling of all diſeaſes, as which are almoſt infinite; it ſhall ſuffice here to have ſet down, what we muſt underſtand by this word *Air.*

Three things are underſtood by the name of the Air.

Phyſicians commonly uſe to underſtand three things by the name of *Air:* The preſent ſtate of the Air, the Region in which we live, and the ſeaſon of the Year. We ſpoke of this laſt, when we treated of Temperaments. Wherefore we will now ſpeak of the two former. The preſent ſtate of the Air, one while for ſome ſmall time, is like the Spring, that is temperate; otherwhiles like the Summer, that is hot and dry; otherwhiles like the Winter, that is cold and moiſt; and ſometimes like the Autumn, which is unequal; and this laſt conſtitution of the Air is the cauſe of many diſeaſes. When upon the ſame day, it is one while hot, another cold, we muſt expect Autumnal diſeaſes. Theſe tempers and varieties of conſtitutions of the Air, are chiefly and principally ſtirred up by the Winds; as which being diffuſed over all the Air, ſhew no ſmall force by their ſudden change. Wherefore we will briefly touch their natures: That which blows from the Eaſt, is the Eaſt-wind, and is of a hot and dry nature, and therefore healthful, But the Weſtern wind is cold and moiſt, and therefore ſickly. The South-wind is hot and moiſt, the Author of putrefaction and putrid diſeaſes. The North-wind is cold and dry, therefore healthy: Wherefore it is thought, if it happen to blow in the Dog-days, that it makes the whole year healthful, and purges and takes away the ſeeds of putrefaction, if any chance to be in the Air. But this deſcription of the four Winds, is then only thought to be true, if we conſider the Winds in their own proper nature, which they borrow from thoſe Regions from which they firſt proceed. For, otherwiſe they affect the Air quite contrary, according to the diſpoſitions of the places over which they came; as, Snowy places, Sea, Lakes, Rivers, Woods, or ſandy Plains, from whence they may borrow new qualities, with which they may afterwards poſſeſs the Air, and ſo conſequently our bodies.

Aphor. 4. *ſect.* 2. The force of the Winds.

How the winds acquire other faculties, than they naturally have.

Hence it is we have noted the Weſtern-wind unwholſome, and breeding diſeaſes, by reaſon of the proper condition of the Region from whence it came; and ſuch that is cold and moiſt: The *Gaſcoins* find it truly to their ſo great harm, that it ſeldoms blows with them, but it brings ſome manifeſt and great harm, either to their bodies, or fruits of the earth. And yet the *Greeks* and *Latins* are wont to commend it for healthfulneſs, more than the reſt. But alſo the riſing and ſetting of ſome more eminent Stars, do often cauſe ſuch cold winds, that the whole Air is cooled, or infected with ſome other malign quality. For vapors and exhalations are often raiſed by the force of the Stars, from whence Winds, Clouds, Storms, Whirlwinds, Lightnings, Thunders, Hail, Snow, Rain, Earthquakes, Inundations, and violent raging of the Sea, have their original. The exact contemplation of which things, although it be proper to Aſtronomers, Coſmographers and Geographers, yet *Hippocrates* could not omit it, but that he muſt ſpeak ſomething in his Book *de Aere & Aquis*; where he touches, by the way, the deſcription of the neighbouring Regions, and ſuch as he knew.

The Weſtwind of it ſelf unwholſome.

What force Stars have upon the Air.

From this force of the Air, either hurtful, or helping in diſeaſes, came that famous obſervation of *Guido* of *Caulias*, That wounds of the head are more difficult to cure at *Paris*, than at *Avignon*, and

and the plain contrary of wounds of the legs; for the air of *Paris*, compared to that of *Avignon*, is cold and moiſt, wherefore hurtful and offenſive to the wounds of the head. On the contrary, the ſame Air, becauſe it obſcures the ſpirits, incraſſates the blood, condenſates the humors, and makes them leſs fit for defluxions, makes the wounds of the legs more eaſie to be healed, by reaſon it hinders the courſe of humors, by whoſe defluxion the cure is hindred. But it is manifeſt, that hot and dry places make a greater diſſipation of the natural heat, from whence the weakneſs of the powers; by which ſame reaſon the Inhabitants of ſuch places do not ſo well endure blood-letting; but more eaſily ſuffer purgation, though vehement, by reaſon of the contumacy of the humor, cauſed by drineſs. To conclude, the Air changes the Conſtitutions of our bodies, either by its qualities, as if it be hotter, colder, moiſter or drier; or by its matter, as if it be groſſer, or more ſubtil than is fit, or corrupted by exhalations from the earth, or by a ſudden and unaccuſtomed alteration, which any man may prove, who makes a ſudden change out of a quiet air into a ſtormy, and troubled with many winds. But becauſe, next to the Air, nothing is ſo neceſſary to nouriſh mans body, as Meat and Drink, I will now begin to ſpeak of them both.

How the air of *Paris* comes to be ill for wounds of the head, and good for thoſe of the legs.

By what means the air changes our bodies.

CHAP. XIV.

Of Meat and Drink.

THat this our Treatiſe of Meat and Drink may be more brief and plain, I have thought good to part it into theſe heads, as to conſider the goodneſs and illneſs of both of them, their quantity, quality, cuſtom, delight, order, time; and to accommodate them all to the ages and ſeaſons of the year. We judge of the goodneſs and pravity of meats and drinks, from the condition of the good or vicious humours or juyce which they beget in us. For evil juyce cauſeth many diſeaſes. As on the contrary, good juyce drives away all diſeaſes from the body, except the fault happen from ſome other occaſion, as from quantity, or too much exceſs. Wherefore it is principally neceſſary, that thoſe who will preſerve their preſent health, and hinder the acceſs of diſeaſes, feed upon things of good nouriſhment and digeſtion; as, are good wine, the yolks of eggs, good milk, wheaten bread well baked, the fleſh of Capons, Partridge, Thruſhes, Larks, Veal, Mutton, Kid, and ſuch like other, which you may find mentioned in the Books which *Galen* writ, *de Alimentorum facultatibus*; where alſo he examines thoſe which are of evil juyce by their manifeſt qualities; as Acrimony, Bitterneſs, Saltneſs, Acidity, Harſhneſs, and ſuch like.

The goodneſs of nouriſhments.

But unleſs we uſe a convenient quantity and meaſure in our meats, howſoever laudable they be, we ſhall never reap theſe fruits of health we hoped for. For they yield matter of diſeaſes, by the only exceſs of their quantity; but we may by this know the force of quantity on both parts, becauſe often the poiſonous quality of meats of ill nouriſhment doth not hurt, by reaſon they were not taken into the body into a great quantity. That meaſure of quantity is chiefly to be regarded in diſeaſes; for as *Hippocrates* ſaith, If any give meat to one ſick of a Feaver, he gives ſtrength to the well, and increaſes the diſeaſe to the ſick, eſpecially if he do not uſe a mean. Wherefore it is a thing of no ſmall conſequence, to know what diſeaſes require a ſlender, and what a large diet; of which thing there is a large relation made in *Sect.* 1. of the Aphoriſms of *Hippocrates*; where he teacheth, the ſick muſt feed more largely in the beginning of long diſeaſes, whereby they may be enabled to endure the length of the diſeaſe, and laſt to the ſtate thereof. But in ſharp and violent diſeaſes, which preſently come to their height, we muſt uſe a ſlender diet; but moſt ſlender, when the diſeaſe is in the height: And beſides, all our conſultations in this kind, muſt be referred to the ſtrength of the Patients. But thoſe who enjoy their perfect health, muſt uſe a quantity of meat, agreeable to their evacuation and tranſpiration; for men, by reaſon of the ſtrength of their heat, and the more copious diſſipation of the triple ſubſtance, have greater appetite than women; altogether by the ſame reaſon, that young people, and ſuch as grow, need more frequent and plentiful nouriſhment than old men; and alſo amongſt young men of the like age, ſome do rightly require more copious nouriſhment than otherſome, that is, according to the quantity of their evacuations and cuſtom. Certainly for Gluttony, it is ſuch as may be extended to all; but we all ſhould take ſo much meat and drink, that our powers may be refreſhed, and not oppreſſed; for by the decree of *Hippocrates*, theſe be the two compendiary ways of preſerving health; not to be over-filled with meat, and to be quick to work: And thus much of the quantity of meats. Neither muſt thoſe who are ſound or ſick, have leſs regard to the qualities of their meats; and thoſe are either the firſt, as heating, cooling, moiſtening, drying; or the ſecond, attenuating, incraſſating, obſtructing, opening, or ſome other-like, working according to the condition of their nature. The manner of our diet is not only to be framed according to theſe, but alſo to be varied; for the preſent ſtate of ſuch as be in health, requires to be preſerved by the uſe of like things. As hot and moiſt nouriſhments is to be preſcribed to children, as to thoſe which are hot and moiſt; and cold and dry to old men, as to thoſe who are cold and dry, if ſo be that vulgar ſaying be true, that, *Health delights in the uſe of like things*. Yet becauſe Old-age, how green and new begun howſoever it be, is of it ſelf, as it were, a diſeaſe, it ſeems to be more convenient, both to truth, and for health, that old people ſhould eat meats contrary to their nature, that is, hot and moiſt; that ſo we may defer, as much as we can, the cauſes of death, cold and drineſs, which haſten the deſtruction of that age. For we muſt reſiſt diſeaſes by the uſe of their contraries, as thoſe things which are contrary to nature. For otherwiſe, as much meat as you give to the ſick, you add ſo much ſtrength to the diſeaſe. And the ſame is the cauſe why *Hippocrates* ſaid, that a moiſt diet is convenient for all ſuch as are ſick of Feavers, becauſe a Feaver is a dry diſtemperature. Therefore we muſt diligently pry into the nature of the diſeaſe, that knowing it, we may endeavour to abate its fury by the uſe of contraries.

Their quantity.

The quantity of meats muſt be eſteemed according to the nature of the diſeaſe, and ſtrength of the Patient.

The qualities of meat.

Old-age a diſeaſe.

Aphor. 16. *Sect.* 1.

But

The force of Cuſtom.

But if Cuſtom (as they ſay) be another nature, the Phyſician muſt have a great care of it, both in ſound and ſick. For this ſometimes by little and little, and inſenſibly, changes our natural temperament, and inſtead thereof gives us a borrowed temper. Wherefore if any would preſently or ſuddenly change a Cuſtom, which is ſometimes ill, into a better, truly he will bring more harm than good; becauſe all ſudden changes (according to the opinion of *Hippocrates*) are dangerous. Wherefore if neceſſity require that we ſhould withdraw any thing from our Cuſtom, we muſt do it by little and little, that ſo nature may by degrees be accuſtomed to contraries without violence, or the diſturbance of its uſual government. For that meat and drink which is ſomewhat worſe, but more pleaſant and familiar by cuſtom, is to be preferred (in *Hippocrates* opinion) before better, but leſs pleaſant and accuſtomed. Hence is it, that Countrey-men do very well digeſt Beef and Bacon, which commonly they uſe; but will turn into nidorulent vapors, Patridg, Capons, and other meat of good nouriſhment, ſooner than change them into good and laudable *Chylus*. The cauſe of which thing is not only to be attributed unto the property of their ſtronger, and as it were, burning heat, but much more to Cuſtom; which by a certain kind of familiarity, cauſeth that means of hard digeſtion, are eaſily turned into laudable blood. For the force of Cuſtom is ſo great, that accuſtomed meats are more acceptable; whereby it comes to paſs, that while the ſtomach delights in them, it more ſtraitly embraces them, and happily digeſts them, without any trouble of loathing, vomiting, or heavineſs. All the contrary, meet and happen in the uſe of meats, which are unpleaſant to the taſte and ſtomach. For the ventricle abhorring thoſe things, makes manifeſt how it is troubled by its acid and nidorulent belchings, loathing, nauſeouſneſs, vomit, heavineſs, pain of the head, and trouble of the whole body.

Aphor. 91. *ſect.* 2.

Aphor. 38. *ſect.* 2.

Accuſtomed meats are more grateful, and ſo, by that means, more nouriſhing.

Wherefore we muſt diligently enquire, what meats the Patient chiefly delighted in, that by offering them, his appetite languiſhing by reaſon of ſome great evacuation, vomit, or the like, may be ſtirred up. For it will be better and more readily reſtored by things acceptable, though they be ſomewhat worſe, as we noted a little before out of *Hippocrates*. By which words he plainly taught, that it is the part of a good and prudent Phyſician to ſubſcribe to, and pleaſe, the palat of his Patient.

The order of eating our meats.

But ſeeing that Order is moſt beautiful in all things, it is truly very neceſſary in eating our meat: for how laudable ſoever the meats be in their quantity and quality, howſoever familiar by uſe, and grateful by cuſtom; yet unleſs they be eaten in due order, they will either trouble or moleſt the ſtomach, or be ill, or ſlowly and difficultly concocted; wherefore we muſt diligently obſerve, what meats muſt be eaten at the firſt, and what at the ſecond courſe; for thoſe meats which be hard to concoct, are not to be eaten before thoſe which are eaſie of digeſtion; neither dry and aſtringent things, before moiſtening and looſing.

We muſt begin our meals with moiſt or liquid meat.

But on the contrary, all ſlippery, fat and liquid things, and which are quickly changed, ought to go before, that ſo the belly may be moiſtned; and then aſtringent things muſt follow, that the ſtomach, by their help, being ſhut and drawn together, may more ſtraitly comprehend the meat on every ſide, and better perform the Chylification by its proper heat united and joyned together.

For this cauſe *Hippocrates*, *Lib. de Victu in acutis*, commands thoſe things to be always eaten in the morning, which are fit to looſen the belly, and in the evening ſuch as nouriſh the body. Yet notwithſtanding drink ought not to precede or go before meat, but on the contrary, meat muſt precede drink, by the order preſcribed by him.

The time of eating.

Neither ought we in our eating to have leſs care of the time, than we have of the order; for the time of eating of ſuch as are healthful, ought to be certain and fixt; for at the accuſtomed hour, and when hunger preſſes, any ſound man, and which is at his own diſpoſure may eat, but exerciſe and accuſtomed labours ought to go before; for it is fit, according to the Precept of *Hippocrates*, that labour precede meat, whereby the excrements of the third concoction may be evacuated, the native heat increaſed, and the ſolid parts confirmed and ſtrengthened, which are three commodities of exerciſe very neceſſary to the convenient taking of meat. But in ſick perſons we can ſcarce attend and give heed to theſe circumſtances of time, and accuſtomed hour of feeding; for, that indication of giving meat to the ſick, is the beſt of all, which is drawn from the motion of the diſeaſe, and the declining of the fit: For if you give meat in Feavers, ſpecially the fit then taking the Patient, you nouriſh not him, but the Diſeaſe. For the meat then eaten, is corrupted in the ſtomach, and yields fit matter for the diſeaſe: For meat (as we noted before out of *Hippocrates*) is ſtrength to the ſound, and a diſeaſe to the ſick, unleſs it be eaten at convenient time, and diligent care to be had of the ſtrength of the Patient, and greatneſs of the diſeaſe.

The profit of labour before meat.

We muſt not give meat in a fit of a Feaver.

Variety of meats.

But neither is it convenient that the meat ſhould be ſimple, and of one kind, but of many ſorts, and of divers diſhes dreſſed after different forms, leſt nature by the continual and hateful feeding upon the ſame meat, may at length loath it, and ſo neither ſtraitly contain it, nor well digeſt it; or the ſtomach accuſtomed to one meat, taking any loathing thereat, may abhor all other; and as there is no deſire of that we do not know, ſo the dejected appetite cannot be delighted and ſtirred up with the pleaſure of any meat which can be offered. For we muſt not credit thoſe ſuperſtitious or too nice Phyſicians, who think the digeſtion is hindred by the much variety of meats.

Why variety of meats is good.

The matter is far otherwiſe, for by the pleaſure of what things ſoever the ſtomach allured doth require, it embraces them more ſtraitly, and concocts them more perfectly. And our nature is deſirous of variety.

Moreover, ſeeing our body is compoſed of a ſolid, moiſt, and airy ſubſtance; and it may happen, that by ſo many labours, which we are compelled to undergo and ſuſtain in this life, one of theſe may ſuffer a greater diſſipation and loſs than another; therefore the ſtomach is neceſſarily compelled to ſeek more variety, leſt any thing ſhould be wanting to repair that which is waſted. But alſo the age and ſeaſon of the year, yield Indications of feeding; for ſome things are convenient for a young man, ſome for an old; ſome in Summer, ſome in Winter. Wherefore we ought to know what befits each age and ſeaſon. Children need hot, moiſt, and much nouriſhment, which may not only

Indications of feeding, taken from the age.

ſuffice

ſuffice to nouriſh, but increaſe the body. Wherefore they worſt endure faſting, and of them eſpecially thoſe who are the moſt lively and ſpiritful. With old men it is otherwiſe; for becauſe their heat is ſmall, they need little nouriſhment, and are extinguiſhed by much. Wherefore old men eaſily endure to faſt; they ought to be nouriſhed with hot and moiſt meats, by which their ſolid parts now growing cold and dry, may be heated and moiſtned, as by the ſweet nouriſhment of ſuch like meats. Middle ag'd men delight in the moderate uſe of contraries, to temper the exceſs of their too acrid heat. Young people as temperate, are to be preſerved by the uſe of like things.

The manner of Diet in Winter muſt be hot, and inclining to drineſs. Wherefore, then, we may more plentifully uſe roſt-meats, ſtrong wines, and ſpices; becauſe in the Winter-ſeaſon we are troubled with the cold and moiſt air, and at the ſame time, have much heat inwardly; for the inner parts, according to *Hippocrates*, are naturally moſt hot in the Winter, and the Spring, but fearveriſh in Summer; ſo the heat of Summer is to be tempered by the uſe of cold and moiſt things, and much drink. In the temperate Spring, all things muſt be moderate; but in Autumn, by little and little, we muſt paſs from our Summer to our Winter diet. Indication from the time of the year.

CHAP. XV.

Of Motion and reſt.

HEre Phyſicians admoniſh us, that by the name of Motion, we muſt underſtand all ſorts of Exerciſes, as walking, leaping, running, riding, playing at Tennis, carrying a burthen, and the like. Friction or rubbing is of this kind, which in times paſt was in great uſe and eſteem, neitheir at this day is it altogether neglected by the Phciyſians. They mention many kinds of it, but they may be all reduced to three; as, one gentle, another hard, a third indifferent; and that of the whole body, or only of ſome part thereof. That Friction is called hard, which is made by the rough, or ſtrong preſſure of the hands, ſpunges, or a coarſe and new linnen cloth: It draws together, condenſates, binds and hardens the fleſh, yet if it be often and long uſed, at length it rariſies, diſſolves, attenuates, and diminiſhes the fleſh, and any other ſubſtance of the body; and alſo it cauſeth revulſion, and draws the defluxion of humors from one part to another. The gentle Friction, which is performed by the light rubbing of the hand, and ſuch like, doth the contrary; as, ſoftens, relaxes, and makes the skin ſmooth and unwrinckled; yet unleſs it be long continued, it doth none of theſe worthy to be ſpoken of. The indifferent kinds, conſiſting in the mean betwixt the other two, increaſeth the fleſh, ſwells or puffs up the habit of the body, becauſe it retains the blood and ſpirits which it draws, and ſuffers them not to be diſſipated. What Motion ſignifies. Three kinds of Frictions. Hard. Gentle. Indifferent.

The benefit of Exerciſe is great, for it increaſes natural heat, whereby better digeſtion follows, and by that means nouriſhment, and the expulſion of the excrements; and laſtly, a quicker motion of the ſpirits, to perform their office in the body, all the ways and paſſages being cleanſed. Beſides, it ſtrengthens the reſpiration, and the other actions of the body, confirms the habit, and all the limbs of the body, by the mutual attrition of the one with the other; whereby it comes to paſs they are not ſo quickly wearied with labour. Hence we ſee, that Country-people are not to be tired with labour. The uſe of exerciſes.

If any will reap theſe benefits by Exerciſe, it is neceſſary that he take opportunity to begin his exerciſe, and that he ſeaſonably deſiſt from it, not exerciſing himſelf violently, and without diſcretion; but at certain times according to reaſon. What the fitteſt time for exerciſe.

Wherefore the beſt time for exerciſe will be before meat (that the appetite may be increaſed by augmenting the natural heat) all the excrements being evacuated, leſt Nature being hungry and empty, do draw and infuſe the ill humors contained in the guts and other parts of the body, into the whole habit, the Liver, and other noble parts. Neither is it fit preſently, after meat, to run into exerciſe, leſt the crude humours and meats not well concocted, be carried into the veins. The meaſure and bounds of exerciſe muſt be, when the body appears more full, the face looks red, ſweat begins to break forth, we breath more ſtrongly and quick, and begin to grow weary; if any continue exerciſe longer, ſtiffneſs and wearineſs aſſails his joynts, and the body flowing with ſweat ſuffers a loſs of the ſpirituous and humid ſubſtance, which is not eaſily repaired; by which it becomes more cold and lean, even to deformity.

The quality of exerciſe which we require, is in the midſt of exerciſe; ſo that the exerciſe muſt be neither too ſlow and idle, neither too ſtrong nor too weak, neither too haſty nor remiſs, but which may move all the members alike. Such exerciſe is very fit for ſound bodies. But if they be diſtempered, that ſort of exerciſe is to be made choice of, which by the quality of its exceſs, may correct the diſtemper of the body, and reduce it to a certain mediocrity. Wherefore ſuch men as are ſtuffed with cold, groſs, and viſcous humors, ſhall hold that kind of exerciſe moſt fit for them, which is more laborious, vehement, ſtronger, and long continued. Yet ſo, that they do not enter into it before the firſt and ſecond concoction, which they may know by the yellowneſs of their urin. But let ſuch as abound with thin and cholerick humors, chuſe gentle exerciſes, and ſuch as are free from contention, not expecting the finiſhing of the ſecond concoction, for the more acrid heat of the ſolid parts delights in ſuch half-concocted juices, which otherwiſe it would ſo burn up all the glutinous ſubſtance thereof being waſted, that they could not be adjoyned or faſtned to the parts. For the repeating or renewing of exerciſe, the body ſhould be ſo often exerciſed, as there is a deſire to eat. For exerciſe ſtirs up and revives the heat which lies buried and hid in the body; for digeſtion cannot be well performed by a ſluggiſh heat, neither have we any benefit by the meat we eat, unleſs we uſe exerciſe before. The quality of exerciſe. For whom ſtrong exerciſes are convenient.

The laſt part of exerciſe begun and performed according to Reaſon, is named, *The ridering of the body*, which is performed by an indifferent rubbing and drying of members; that ſo the ſweat breaking *Anoregnia.*

ing

ing forth, the filth of the body, and ſuch excrements lying under the skin, may be allured and drawn out; and alſo that the members may be freed from ſtiffneſs and wearineſs. At this time it is commonly uſed by ſuch as play at Tennis.

What diſcommodities proceed from Idleneſs.

But, as many and great Commodities ariſe from exerciſe conveniently begun and performed, ſo great harm proceeds from Idleneſs; for groſs and vicious juyces heaped up in the body, commonly produce crudities, obſtructions, ſtones both in the reins and bladder, the Gout, Apoplexy, and a thouſand other diſeaſes.

CHAP. XVI.

Of Sleep and Watching.

THat this our ſpeech of Sleep and Watching, which we now intend, may be more plain, we will briefly declare, what commodity or diſcommodity they bring; what time and what hour is convenient for both; what the manner of lying muſt be, and the choice thereof; what the dreams in ſleeping; and what, pains or heavineſs and chearfulneſs after ſleep may portend.

What ſleep is.

Sleep is nothing elſe than the reſt of the whole body, and the ceſſation of the Animal faculty from ſenſe and motion. Sleep is cauſed, when the ſubſtance of the brain is poſſeſſed, and after ſome ſort overcome and dulled by a certain vaporous, ſweet, and delightſome humidity; or when the ſpirits, almoſt exhauſt by performance of ſome labour, cannot any longer ſuſtain the weight of the body, but cauſe reſt by a neceſſary conſequence; by which means, nature may produce other, from the meat by concoction turned into blood.

The uſe of ſleep.

Sleep fitly taken, much helps the digeſtion of the parts, becauſe in the time of reſt, the heat being the worker of all concoction, is carried back to them, together with the ſpirits. Neither doth ſleep only give eaſe to the wearied members, but alſo leſſens our cares, and makes us to forget our labours.

Fit time for ſleep, and the nature of the night.

The night is a fit time to ſleep and to take our reſt in, as inviting ſleep by its moiſture, ſilence, and darkneſs. For the heat and ſpirits, in the thick obſcurity of night, are driven in and retained in the center of the body; as on the contrary by the daily, and as it were, friendly and familiar light of the Sun, they are allured and drawn forth into the ſuperficies, and outward part of the body; from whence they leave ſleeping, and begin to wake.

Sleep on the day-time.

Beſides alſo, which makes not a little to that opportunity and benefit which we look for from ſleep, the night ſeaſon ſuffices for the work of juſt and perfect concoction. Which is one reaſon, amongſt many, that ſleep in the day time may be hurtful. For we are wakened from our ſleep by the heat and ſpirits, called forth to the skin either by the light, or noiſe on the day time, before that the concoction which was begun be finiſhed. But, that ſleep cannot but be light which comes without neceſſity of ſleeping. Wherefore the concoction being attempted, but not perfected, the ſtomach is filled with crudities, diſtended with acid or ſour belchings, and the brain troubled with groſs vapors and excrementitious humidities. From whence proceed pain and heavineſs of the head, and ſtore of cold diſeaſes. But although ſleep on the night time be wholſome, yet it is fit that it be reſtrained within the limits of an indifferent time, For that which exceeds, hinders the evacuation of excrements both upwards and downwards: But in the mean time the heat, which is never idle, draws from them ſome portion or vapour, into the veins, principal parts and habit of the body, to become matter for ſome diſeaſe. We muſt meaſure this time, not by the ſpace of hours, but by the finiſhing the work of concoction, which is performed in ſome ſooner than in other ſome. Yet that which is longeſt is perfected and done in ſeven or eight hours. The ventricle ſubſiding and falling into its ſelf and its proper coats, and the urine tinctured yellow, gives perfect judgment thereof. For on the contrary, the extenſion of the ſtomach, acid belching, pain of the head, and heavineſs of the whole body, ſhew that the concoction is unperfect.

There ought to be a moderation of our nights ſleep.

How to be known.

What the form and ſite of our body ought to be while we ſleep.

In ſleeping we muſt have ſpecial care of our lying down; for firſt we muſt lie on our right ſide, that ſo the meat may fall into the bottom of our ſtomach, which being fleſhy, and leſs membranous, is the hotter, and more powerful to aſſimilate. Then a little after we muſt turn upon our left ſide, that ſo the Liver with its Lobes, as with hands, may on every ſide embrace the ventricle, and as a fire put under a kettle, haſten the concoction. Laſtly, towards morning it will not be unprofitable to turn again upon our right ſide, that by this ſituation the mouth of the ſtomach being opened, the vapours which ariſe from the elixation of the *Chylus* have freer paſſage.

The harm of lying on our backs.

Upon our bellies.

Lying upon the back is wholly to be avoided; for from hence the Reins are inflamed, the Stone is bred, Palſies, Convulſion, and all the diſeaſes which have their original from the defluxion into the ſpinal marrow, and to the Nerves taking beginning from thence. To lie upon the belly is not unprofitable for ſuch as have uſed to lie ſo, if they be not troubled with defluxions into the eyes; for ſo the humor will more eaſily flow into the part affected. But thus the work of concoction is not a little furthered, becauſe by that form of lying, not only the inward heat is contained and gathered about the Ventricle, but the encompaſſing warmneſs of the ſoft feathers of the bed aids and aſſiſts it.

The conſideration of dreams.

Neither are the Dreams which we have in our ſleep to be neglected, for by the diligent conſideration of theſe, the affections and ſuperfluous Humors which have chief power in the body are marvellouſly known. For thoſe who have raging choler running up and down their bodies while they ſleep, all things to them appear bright, ſhining, fiery, burning, full of noiſe and contention. Thoſe who abound with Phlegm, dream of floods, ſnows, ſhowers, and inundations and falling from high places. Thoſe who are Melancholy, dream of gapings and gulphs in the earth, thick and obſcure darkneſs, ſmoaks, caves, and all black and diſmal things. But thoſe whoſe bodies abound in blood, dream of marriages, dances, embraces of women, feaſts, jeſts, laughter, of orchards and gardens; and to conclude, of all things pleaſant and ſplendent.

Alſo

Alſo we muſt obſerve how the Patient doth after ſleep, whether more lively and chearful, or more heavy: for, by the opinion of *Hippocrates*,

Cum labor a ſomno eſt, lethalem collige morbum:
Sin profit ſomnus, nihil hinc lethale timendum eſt. *Aphor. 1. ſect. 2.*

Pain ſleep enſuing, an ill diſeaſe doth ſhow;
But if ſleep profit bring, no harm from thence will flow.

And as ſleep, ſo watching, if it exceed meaſure, is hurtful; for it hurts the temperature of the brain, weakens the ſenſes, waſtes the ſpirits, breeds crudities, heavineſs of the head, falling away of the fleſh, and leanneſs over all the body; and, to conclude, it makes Ulcers more dry, and ſo conſequently rebellious, difficult to heal and malign. There are many other things may be ſpoken of ſleep and watching, but theſe may ſuffice a Chirurgeon.

CHAP. XVII.

Of Repletion, and Inanition or Emptineſs.

THere are to be ſhort, two ſorts of Repletion, or of all exceſs; one is of a ſimple quality, without any defluxion, or ſociety of any humor, as appears in diſtempers without matter: The other is of quantity and maſs, the body being diſtended with two much meat, or too great quantity of humors; from whence proceed an infinite number of diſeaſes. They call the Repletion of meats, Satiety or Fulneſs; and it is of two kinds: The one which is called * Repletion or Fulneſs to the veſſels; the other Repletion to the ſtrength. *The kinds of Repletions, or rather of Exceſſes.* * *Repletio ad vaſa, ad vires*

We judge of Satiety to the veſſels, by the diſtention and ſwelling of the veins, and entrals, as the ſtomach. We call Satiety to the ſtrength, when the body is loaded with more meats than it can well bear. But alſo there is a double Repletion of humors. For either it is of ſome one humor, or of all the humors; they call this by a peculiar name, *Plethora*. For *Galen* defines *Plethora* to be an equal exceſs of all the humors. For if at any time he define a *Plethora* to be an exceſs of blood only; then verily by the name of blood, he underſtands an equal comprehenſion of the four humors as it is taught in Phyſick Schools, *Gal. Meth. 13. cap. 6.*

The Repletion which is cauſed by ſome one humor, is termed by *Galen* in the place before-mentioned, *Cacochymia* (that is, an evil juice) whether the Repletion proceed of a Cholerick, Melancholick, Phlegmatick, or ſerous Humor. *What Cacochymia is.*

Now Inanition or Evacuation, is no other thing than the expulſion or effuſion of humors which are troubleſome, either in quantity or quality. Of Evacuation, ſome are univerſal, which expel ſuperfluous humors from the whole body; ſuch are Purging, Vomiting, Tranſpiration, Sweats, Phlebotomy. Some particular, which are performed only to evacuate ſome part, as the Brain, by the noſe, palat, eyes, ears; the Lungs, by the weazon; the Stomach, by vomit and ſtool; the guts, by ſtool; the Liver and the Spleen, by urine and ordure. Theſe Evacuations are ſometimes performed by nature, freeing it ſelf of that which is troubleſome to it; otherwhiles by the Art of the Phyſician in imitation of nature. *The kinds of Evacuation.*

And again, one of theſe is good and requiſite, when only the humor which is hurtful either in quantity or quality, is evacuated: The other not requiſite, or immoderate, when the profitable Humors, together with the unprofitable, are expelled.

But what Evacuations ſoever theſe be, they are performed and done, either by the ſcratching and rubbing of the skin, as when a Cholerick, Salt or Serous Humor, or ſome windineſs lying between the skin and the fleſh, cauſe itching. For by ſcratching the skin, it gets paſſage out, which is manifeſt by the efflux of a ſerous matter burning, or cauſing ſcabs and ulcers, if the humor be ſomewhat groſs; but inſenſible and not ſo manifeſt, if it be windineſs, the skin by that rubbing being rarified, and the groſs flatulency attenuated. Wherefore they do ill who hinder their Patients from ſcratching, unleſs they ſcratch ſo cruelly and hard, that there may be danger (by reaſon of the great heat and pain thereby cauſed) of ſome defluxion or falling down of humors into the part. *The commodities of moderate ſcratching.*

Or theſe Evacuations are performed by much matter evacuated from an opened Bile, or running Ulcer, a Fiſtula, or ſuch like ſores. Or by ſweats which are very good and healthful, eſpecially in ſharp diſeaſes, if they proceed from the whole body, and happen on the critical days. By Vomit, which often violently draws theſe humors from the whole body, even from the utmoſt joynts, which purging Medicines could not evacuate, as we may ſee in the Palſie, and Sciatica, or Hip-gout. By ſpitting, as in all who are ſuppurated either in the ſides or lungs. By Salivation, or a Phlegmatick flux by the mouth, as in thoſe who are troubled with the French-pox. By ſneezing and blowing the noſe; for by theſe, the brain oppreſt with moiſture, disburtheneth it ſelf, whether it be done without, or with the help of ſternutatories and errhines; wherefore children, and ſuch as have ſomewhat moiſt brains, purge themſelves often this way. By hicket and belching; for by theſe the windineſs contained in the ſtomach, is often expelled. By urine, for by this not only Feavers, but which is more admired, the French-pox hath often been terminated and cured. *The force of Vomits.* *Salivation.* *The whole body is alſo purged by urine.*

For there have been ſome troubled with the Pox, in whom a flux of the vicious and venenate humor could not by Unctions of Quick-ſilver be procured, either from the mouth or belly; yet have been wonderfully freed by abundance of Urine, both from danger of death and their diſeaſe. By bleeding; for nature hath often found a way for grievous diſeaſes, eſpecially in young bodies, by bleeding at the noſe, and by their courſes in women. By a flux, or lask, purgations, ſweats, inſenſible

sible Evacuation and Transpiration; for so tumors, the matter being brought to suppuration, do sometimes vanish away and are dissolved, both of their own accord, as also by dissolving or discussing Medicines. We do the same by Exercise, Diet, Hot-houses, long sleep, walking, and shedding of tears. By sucking, as with Cupping-glasses, and Horse-leeches, in wounds made by venemous bitings.

We must observe three things in every Evacuation.

In all such kinds of Evacuations, we must consider three things, the quantity, quality and manner of Evacuation. As for an example, When an *Empiema* is opened, the matter which runs out, ought to be answerable in proportion to the purulent matter, which was contained in the capacity of the breasts; otherwise, unless all the matter be emptied, there may happen a relapse; the matter should be white, soft, equal, and nothing stinking: Lastly, you must let it forth, not all together, and one time, but by little and little, and at several times; otherwise, not a little quantity of the spirits and heat doth flow together with the unprofitable matter, and so consequently a dissolution of all the powers.

CHAP. XVIII.

Of the Perturbations or Passions of the Mind.

Why the Passions of the mind are called Accidents. Their force.

THe Perturbations are commonly called the Accidents of the Mind, because as bodily accidents from the body, so may these, be present and absent from the Mind, without the corruption of the subject. The knowledge of these must not be lightly passed over by the Chirurgeon; for they stir up great troubles in the bodies, and yield occasion of many and great diseases; of which things, joy, hope, and love, may give an apparent testimony. For by these motions the heat and spirits are sometimes gently, sometimes violently diffused over all the body, for the enjoying of the present, or hoped for good. For then the heart is dilated, as to embrace the thing beloved, and the face is died with a rosie and lively colour. For it is likely, that the faculty it self is stirred by the object, by whose power the heart it self is moved.

From whence they have their force.

For it is first necessary, before we be moved by any Passions, that the Senses in their proper seats, in which they are seldom deceived, apprehend the objects; and straight, as Messengers, carry them to the common sense, which sends their conceived forms to all the faculties. And then, that each faculty, as a Judge, may afresh examine the whole matter, how it is, and conceive in the presented objects some shew of good, or ill, to be desired or shunned. For, What man that was well in his wits, did ever fall into laughter, unless he formerly knew, or saw somewhat said or done, which might yield occasion of laughter? Therefore Joy proceeds from the heart, for the thing causing Mirth or Joy, being conceived, the faculty moves the heart, which shaken and moved by the faculty which hath dominion over it, is dilated and opened, as ready to embrace the exhilarating object. But in the mean time by the force of that dilatation, it sends forth much heat, and spirits together with the blood into all the Body. A great part of which coming to the face, dilates it, the fore-head is smooth and plain, the eyes look bright, the cheeks become red, as dyed with Vermilion, the lips and mouth are drawn together, and made plain and smooth; some have their cheeks dented with two little pits (which from the effects are called laughing cheeks) because of the contraction or curling, which the muscles suffer by reason of their fulness of blood and spirits; all which, to be brief, is nothing but to laugh.

The reason of Joy.

The effects of Joy.

Joy recreates and quickens all the faculties, stirs up the spirits, helps concoction, makes the body to be better liking, and fattens it, the heat, blood and spirits flowing thither, and the nourishing dew or moisture, watering and refreshing all the members; from whence it is, that of all the Passions of the mind, this only is profitable, so that it exceed not measure; for immoderate and unaccustomed joy carries so violently the blood and spirits from the heart, into the habit of the body, that sudden and unlook'd for death ensues, by a speedy decay of the strength, the lasting fountain of the vital humour being exhausted. Which thing principally happens to those who are less hearty, as women and old men.

Anger.

Anger causeth the same effusion of heat in us, but far speedier than Joy; therefore the spirits and humors are so enflamed by it, that it oftens causes putrid Feavers, especially if the body abound with any ill humour.

Sorrow.

Sorrow, or Grief, dries the body by a quite contrary way to that of Anger, because by this the heart is so straitned, the heat being almost extinct, that the accustomed generation of spirits cannot be performed; and if any be generated, they cannot freely pass into the members with the blood; wherefore the vital faculty is weakned, the lively colour of the face withers and decays, and the body wastes away with a lingering Consumption.

Fear.

Fear in like sort draws in and calls back the spirits, and not by little and little, as in Sorrow, but suddenly and violently; hereupon the face grows suddenly pale, the extreme parts cold, all the body trembles or shakes, the belly in some is loosed, the voice, as it were, stays in the jaws, the heart beats with a violent pulsation, because it is almost oppress by the heat, strangled by the plenty of blood, and spirits abundantly rushing thither: The hair also stands upright, because the heat and blood are retired to the inner parts, and the utmost parts are more cold and dry than a stone; by reason whereof the utmost skin and the pores, in which the roots of the hairs are fastned, are drawn together.

Hippocr. lib. 4. de Morb.

Shame.

Shame is a certain affection mixed, as it were, of Anger and Fear; therefore, if in that conflict of, as it were, contending Passions, Fear prevail over Anger, the face waxeth pale (the blood flying back to the heart;) and these or these Symptomes rise, according to the vehemency of the contracted and abated heat, But if on the contrary, Anger get the dominion over Fear, the blood runs violently to the face, the eyes look red, and sometimes they even fome at the mouth.

Shamefastness.

There is another kind of Shame, which the *Latins* call *Verecundia* (we, Shamefastness) in which there

there is a certain flux and reflux of the heat and bloud, first recoiling to the heart, then presently rebounding from thence again. But that motion is so gentle, that the heart thereby suffers no oppression, nor defect of spirits; wherefore no accidents worthy to be spoken of, arise from hence: this affect is familiar to young Maids and Boys, who if they blush for a fault committed unawares or through carelesness, it is thought an argument of a vertuous and good disposition.

An Agony.

But an agony, which is a mixt passion of a strong fear and vehement anger, involves the heart in the danger of both motions; wherefore by this passion the vital faculty is brought into very great danger. To these six Passions of the Mind all other may be revoked, as Hatred and Discord, to Anger; Mirth and Boasting to Joy: Terrours, Frights, and Swoundings, to Fear; Envy, Despair, and Mourning, to Sorrow.

By these it is evident how much the Passions of the mind can prevail, to alter and overthrow the state of the body; and that by no other means, than that by the compression and dilatation of the heart, they diffuse and contract the spirits, bloud, and heat; from whence happens the dissipation or oppression of the spirits.

Why the first signs of Passions of the mind appear in the face.

The signs of these Symptoms quickly shew themselves in the face; the heart, by reason of the thinness of the skin in that part, as it were painting forth the notes of its affections. And certainly the face is a part so fit to disclose all the affections of the inward parts, that by it you may manifestly know an Old man from a Young, a Woman from a Man, a temperate person from an untemperate, an *Ethiopian* from an *Indian*, a *Frenchman* from a *Spaniard*, a Sad man from a Merry, a Sound from a Sick, a Living from a Dead. Wherefore many affirm that the manners, and those things which we keep secret and hid in our hearts, may be understood by the Face and Countenance.

The use of Passions of the mind.

Now we have declared what commodity and discommodity may redound to the man from these fore-mentioned Passions, and have shewed that anger is profitable to none, unless by chance to some dull by reason of idleness, or oppress with some cold, clammy and phlegmatick humour; and Fear convenient for none, unless peradventure for such as are brought into manifest and extream danger of their life by some extraordinary sweat, immoderate bleeding, or the like unbridled evacuation: Wherefore it behoves a wise Chirurgeon to have a care, lest he inconsiderately put any Patient committed to his charge into any of these Passions, unless there be some necessity thereof, by reason of any of the fore-mentioned occasions.

CHAP. XIX.

Of things against Nature, and first of the Cause of a Disease.

What things against Nature are.

HAving treated of things Natural and not Natural, now it remains we speak of things (which are called) against Nature, because they are such as are apt to weaken and corrupt the state of our body. And they be three in number; The Cause of a Disease, a Disease, and a Symptom. The Cause of a Disease is an affect against Nature, which causes the Disease. Which is divided into Internal and External. The External, Original, or Primitive, comes from some other place, and outwardly, into the body: such be meats of ill nourishment, and such weapons as hostilely wound the body.

What, and how many the causes of diseases be.

The Primitive cause.

The Internal have their essence and seat in the body, and are subdivided into Antecedent and Conjunct. That is called an antecedent cause, which as yet doth not actually make a Disease, but goes near to cause one; so Humours copiously flowing, or ready to flow into any part, are the antecedent cause of Diseases. The Conjunct is that which actually causes the Disease, and is so immediately joined in affinity to the Disease, that the Disease being present it is present, and being absent it is absent.

Internal antecedent.

Internal conjunct.

Again, of all such Causes, some are born together with us, as the over-great quantity and malign quality of both the seeds, and the menstruous bloud from diseased Parents, are causes of many Diseases, and specially of those which are called Hereditary.

Other happen to us after we be born, by our diet and manner of life, a stroke, fall, or such other like. Those which be bred with us, cannot be wholly avoided or amended, but some of the other may be avoided, as a stroke and fall; some not, as those which necessarily enter into our body, as Air, Meat, Drink, and the like.

The congenit, or inevitable cause of death.

But if any will reckon up amongst the internal, inherent, and inevitable Causes, the daily, nay hourly dissipation of radical moisture, which the natural heat continually preys upon; I do not gainsay it, no more then that division of Causes celebrated and received of Philosophers, divided into Material, Formal, Efficient, and Final; for such a curious contemplation belongs not to a Chirurgeon, whom I onely intend plainly to instruct. Wherefore that we have written may suffice him.

CHAP. XX.
Of a Diſeaſe.

What a Diſeaſe is, and how various.

A Diſeaſe is an affect againſt Nature; principally, and by it ſelf hurting and depraving the action of the part in which it reſides. The Diviſion of a Diſeaſe is threefold; Diſtemperature, Ill Conformation, and the Solution of Continuity.

A Diſtemperature.

Diſtemperature is a Diſeaſe of the ſimilar parts diſſenting, and changed from their proper and native temper. That digreſſion from the native temper, happens two ways; either by a ſimple diſtemperature from the exceſs of one quality; and this is fourfold, Hot, Cold, Moiſt, and Dry: or by a compound diſtemperature, by the exceſs of two qualities, which alſo is fourfold, Hot and Moiſt, Hot and Dry; Cold and Moiſt, Cold and Dry. Again, every Diſtemper is the fault of one ſimple and ſingle quality, as an Inflammation; or hath ſome vicious humours joined with it, as a Phlegmon. Again, a Diſtemperature is either equal, as in a *Sphacele*; or unequal, as in a *Phlegmon*, beginning or increaſing.

Ill Conformation.

Ill Conformity is a fault of the organical parts, whoſe compoſure is thereby depraved. This hath four kinds; the firſt is, when the figure of the part is faulty, either by nature or accident, or ſome cavity aboliſhed; as if a part which Nature would have hollow for ſome certain uſe, do grow or cloſe up. Or laſtly, if they be rough, or ſmooth, otherwiſe then they ſhould, as if that part which ſhould be rough, be ſmooth, or the contrary. Another is in the magnitude of the part increaſed or diminiſhed contrary to Nature. The third is in the number of the parts increaſed or diminiſhed; as if a hand have but four, or elſe ſix fingers. The fourth is in the ſite and mutual connexion of the parts; as if the parts which ſhould be naturally united and continued, be pluckt aſunder, as happens in Luxations; or the contrary.

Solution of Continuity.

The third general kind of Diſeaſe, is the ſolution of continuity, a Diſeaſe common both to the ſimilar and organical parts, acquiring diverſity of names, according to the variety of the parts in which it reſides.

CHAP. XXI.
Of a Symptom.

What a Symptom is.

We do not in this place take the word Symptom in the moſt general acceptation, for every change or accident which happens to man beſides his own nature; but more reſervedly and ſpecially, onely for that change which the Diſeaſe brings, and which follows the Diſeaſe as a ſhadow doth the body.

Three kinds thereof.

There be three kinds of a Symptom properly taken. The firſt is, when the action is hurt; I ſay hurt, becauſe it is either aboliſhed, weakned, or depraved, ſo blindneſs is a deprivation or aboliſhing of the action of Seeing; dulneſs of ſight, is a diminution or weakning thereof; and a ſuffuſion, ſuch as happens at the beginning of a Cataract, and when they think Flies, Hairs, and ſuch like bodies fly to and fro before their eyes, is a depravation of the ſight.

The ſecond is a ſimple affect of the body, and a full fault of the habit thereof being changed, happening by the mutation of ſome qualities: ſuch is the changing of the native colour into a red by a Phlegmon, and into a livid and black by a Gangrene; ſuch is the filthy ſtench the Noſe affected with a *Polypus* ſends forth; the bitter taſte, in ſuch as have the Jaundice; and the rough and rugged skin in them which are Leprous.

The third is the fault of the overmuch retention of Excrements which ſhould be expelled, and expulſion of ſuch as ſhould be retained; for the evacuation of a humor profitable both in quantity and quality, is againſt nature, as bleeding in a body not full of ill humours, nor Plethorick; and alſo the retention of things hurtful in ſubſtance, quantity, and quality, as the Courſes in Women, the Urine, and the Stone in the Bladder.

CHAP. XXII.
Of Indications.

What Indication is.

The knowledge and exerciſe of Indications befits that Chirurgeon, whom no blind raſhneſs of Fortune but Reaſon, no Chance but Counſel, directs in the undertaking and performing the works of his Art. For an Indication is a certain ſafe and ſhort way, which leads the Phyſician, as by the hand, to the attainment of his purpoſed end, of preſerving the ſound, or curing the ſick.

See *Method.* Cap. 7. *Lib. de opt.* ſecta cap. 11.

For *Galen* doth define an Indication to be a certain inſinuation of what is to be done, or a quick and judicious apprehenſion of that which may profit or hurt. And as Faulconers, Mariners, Plowmen, Souldiers, and all manner of Artizans, have their peculiar terms and words, which are neither known, nor uſed by the vulgar; ſo this word Indication is proper and peculiar to Phyſicians and Chirurgeons, as a term of Art not vulgar; by conſideration of which, as by ſome ſign or ſecret token they are admoniſhed what is to be done to reſtore health, or repel an imminent danger.

The kinds of Indications.

There are three prime and principal kinds of Indications, every of which is ſubdivided into many other. The firſt is from things Natural. The ſecond from thoſe things which are termed Not Natural. The third from thoſe things which are contrary to Nature. Things natural ſhew they muſt be preſerved by their like, and in the compaſs of theſe are contained all the Indications which are drawn from the nature of the Patient, that is, from his ſtrength, temper, age, ſex, habit, cuſtom, diet.

Things

Things not Natural may be doubted as uncertain; for one while they indicate the ſame things with things natural; that is, they co-indicate with the ſtrength, temper, and the reſt; otherwhiles they conſent with things againſt Nature, that is, they co-indicate with the Diſeaſe. Wherefore *Galen* when he ſaith that Indications are drawn from three things; the Diſeaſe, the nature of the Patient, and the encompaſſing Air; by propoſing the familiar example of the Air, he would have us to underſtand the other things not Natural, becauſe we may ſhun or embrace them more or leſs as we will our ſelves; but we muſt whether we will or no endnre the preſent ſtate of the Air. Therefore the Air indicates ſomething to us, or rather co-indicates; for if it nouriſh the Diſeaſe, as conſpiring with it, it will indicate the ſame that the diſeaſe, that is, that it muſt be preſerved in the ſame ſtate. *Lib.9.Method. cap.9.*

Things contrary to Nature indicate they muſt be taken away by their contraries; therefore that we may more accurately and fully handle all the Indications drawn from things Natural, we muſt note, that ſome of theſe are concerning the ſtrength of the Patient; by care to preſerve which, we are often compelled for a time to forſake the cure of the proper Diſeaſe: for ſo, a great ſhaking happening at the beginning of an Ague or Fever, we are often forced to give ſuſtenance to the Patient, to ſtrengthen the Powers ſhaken by the vehemency of the ſhakings, which thing notwithſtanding lengthens both the general and particular fits of the Ague. Other pertain to the temper, other reſpect the habit, if the Patient be ſlender, if fat, if well fleſhed, if of a rare, or denſe conſtitution of body. Other reſpect the condition of the part affected in ſubſtance, conſiſtence ſoftneſs, hardneſs, quick or dull ſenſe, form, figure, magnitude, ſite, connexion, principality, ſervice, function or uſe. From all theſe, as from notes, the skilful Chirurgeon will draw Indications according to the time and part affected: for the ſame things are not fit for ſore eyes, which were convenient for the ears; neither doth the phlegmon in the jaws and throat admit the ſame form of cure, as it doth in other parts of the body. For none can there outwardly apply repercuſſives, without preſent danger of ſuffocation. So there is no uſe of repercuſſives in defluxions of thoſe parts which in ſite are near the principal, Neither muſt thou cure a wounded Nerve and Muſcle, after one manner. The temperature of a part, as Moiſture always indicates its preſervation, although the diſeaſe be moiſt, and give indication of drying, as an ulcer. The principality of a part always inſinuates an Indication of aſtringent things, although the diſeaſe require diſſolving, as an obſtruction of the Liver; for otherwiſe, unleſs you mix aſtringent things with diſſolving, you will ſo diſſolve the ſtrength of the part, that hereafter it cannot ſuffice for ſanguification. If the texture of a part be rare, it ſhews it is leſs apt or prone to obſtruction; if denſe, it is more obnoxious to that Diſeaſe, hence it is that the Liver is oftner obſtructed then the Spleen. If the part be ſituate more deep or remote, it indicates the medicines muſt be more vigorous and liquid, that they may ſend their force ſo far. The ſenſibleneſs, or quick ſenſe of the part, gives indication of milder Medicins, then peradventure the ſigns or notes of a great Diſeaſe require. For the Phyſician which applies things equally ſharp to the horny tunicle of the eye being ulcerated, and to the leg, muſt needs be counted either cruel or ignorant. Each Sex and Age hath its Indications, for ſome Diſeaſes are curable in youth, which we muſt not hope to cure in old age; for hoarſneſs and great diſtillations in very old men, admit no digeſtion, as *Hippocrates* ſaith; *Aphor.40. li.2.*

Indications drawn from things natural

What the conditions of the parts affected do indicate.

Indications from the Ages.

Nunquam decrepitus Bronchum coquit, atque Coryzam.
The feeble Sire, for Age that hardly goes,
Ne'r well digeſts the hurtful Rheum or poſe.

Moreover, according to his decree, the Diſeaſes of the Reins, and whatſoever pains moleſt the bladder, are difficultly healed in old men; and alſo reaſon perſuades that a Quartan admits no cure in Winter, and ſcarce a Quotidian; and Ulcers in like manner, are more hard to heal in Winter; that hence we may underſtand certain Indications to be drawn from time; and to increaſe the credit of the variety and certainty of Indications, ſome certain time, and ſeaſons in thoſe times command us to make choice of Medicins; for, as *Hippocrates* teſtifies; *Aphor.6. ſect.6.* *Aphor.5. ſect.4.*

Ad Canis ardorem, facilis purgatio non eſt.
In Dog-days heat it is not good,
By purging for to cleanſe the bloud,

Neither ſhalt thou ſo well preſcribe a ſlender diet in Winter, as in the Spring, for the air hath its Indications. For experience teaches us, that wounds of the head are far more difficultly and hardly cured, at *Rome*, *Naples*, and *Rochel* in *Xantoigne*. But the times of diſeaſes yield the principal Indications; for ſome Medicins are onely to be uſed at the beginning and end of Diſeaſes others at the increaſe and vigour of the Diſeaſe. We muſt not contemn thoſe Indications which are drawn from the vocation of Life, and manner of Diet; for you muſt otherwiſe deal with the painful Husbandman (when he is your Patient) which leads his life ſparingly and hardly, than with the Citizen, who lives daintily and idlely. To this manner of life and diet may be referred a certain ſecret and occult property, by which many are not onely ready to vomit at eating of ſome meats, but tremble over all their bodies when they hear them but ſpoken of. I knew a prime Nobleman of the *French* Nobility, who was ſo perplext at the ſerving in of an Eel to the Table, at the midſt of dinner and amongſt his friends, that he fell into a ſwound, all his powers failing him. *Galen* in his Book *De Conſuetudine* tells, that *Aerius* the *Peripatetick* died ſuddenly, becauſe compelled by the advice of thoſe Phyſicians he uſed, he drank a great draught of cold Water in the intolerable heat of a Fever. For no reaſon, ſaith *Galen*, than that becauſe he knowing he had naturally a cold ſtomach from his childhood, perpetually abſtained from cold Water.

From our diet.

Hatred ariſing from ſecret properties.

Indications taken from things againſt nature.

For as much as belongs to Indications taken from things againſt nature; the length and depth of

of a wound or ulcer indicates one way; the figure cornered, round equal and ſmooth, unequal and rough, with a hollowneſs ſtreight or winding, indicate otherwiſe; the ſite right, left, upper, lower in another manner, and otherwiſe the force and violence of antecedent and conjunct cauſes. For oftentimes the condition of the cauſe indicates contrary to the Diſeaſe, as when abundance of cold and groſs humours cauſe and nouriſh a Fever. So alſo a Symptom often indicates contrary to the Diſeaſe: in which contradiction, that indication muſt be moſt eſteemed which doth moſt urge; as for example ſake, If ſwounding happen in a Fever, the feveriſh burning ſhall not hinder us from giving Wine to the Patient,

Wherefore theſe Indications are the principalleſt and moſt noble, which lead us, as by the hand, to do theſe things which pertain to the cure, prevention and mitigating of Diſeaſes. But if any object, that ſo curious a ſearch of ſo many Indications is to no purpoſe; becauſe there are many Chirurgeons, which ſetting onely one before their eyes, which is drawn from the eſſence of the Diſeaſe, have the report and fame of skilful Chirurgeons, in the opinion of the vulgar; but let him know that it doth not therefore follow, that this Indication is ſufficient for the cure of all Diſeaſes; for we do not always follow that which the eſſence of the Diſeaſe doth indicate to be done. But chiefly, then where none of the fore-recited Indications doth reſiſt or gain-ſay. You may underſtand this by the example of a *Plethora*, which by the Indication drawn from the eſſence of the thing, requires Phlebotomy; yet who is it that will draw bloud from a child of three moneths old? Beſides, ſuch an Indication is not artificial but common to the Chirurgeon with the common people. For who is it that is ignorant, that contraries are the remedies of contraries? and that broken bones muſt be united by joyning them together? But how it muſt be performed and done, this is of Art and peculiar to a Chirurgeon, and not known to the Vulgar. Which the Indications drawn from thoſe Fountains we pointed at before, abundantly teach; which, as by certain limits of circumſtances, encompaſs the Indication which is taken from the eſſence of the Diſeaſe, leſt any ſhould think we truſt to that only. For there is ſome great and principal matter in it, but not all. For ſo the meaneſt of the common people is not ignorant that the ſolution of continuity is to be cured by repairing that which is loſt. But in what parts we may hope for reſtitution of the loſt ſubſtance, and in which not, is the part of a skilful Chirurgeon to know and pronounce. Wherefore he will not vainly beſtow his labour to cure the nervous part of the *Diaphragma* or Midriff being wounded, or the Heart, or ſmall Guts, Lungs, Liver, Stomach, Brair, or Bladder; and that I may ſpeak in a word, Empericks are not much more skilful then the common people, although they do ſo much extol themſelves above others by the name of experience. For although experience be another inſtrument to find out things with reaſon, yet without reaſon it will never teach what the ſubſtance of the part in which the diſeaſe lies, may be; or what the action, uſe, ſite, connexion, from whence ſpecial and proper Indications are drawn; with which the Chirurgeon being provided and inſtructed, ſhall not onely know by what means to find out a remedy, but alſo, leſt he may ſeem to mock any with vain promiſes, he ſhall diſcern what Diſeaſes are uncurable, and therefore not to meddled withall.

We do not always follow the Indication which is from the Diſeaſe.

In what parts we cannot hope for reſtoring of ſolution of continuity.

Experience without reaſon is like a blind man without a Guide.

But implicit or intricate Diſeaſes require each to be cured in their ſeveral order, except ſome one of them be deſperate, or ſo urge and preſs that the Phyſician think it neceſſary after a preposterous order to begin with it, although often he be forced to make ſome one of theſe Diſeaſes incurable, or give occaſion of cauſing ſome new one: into which ſtraits we are neceſſarily compelled to fall, when (for example) we determine to pull, or take away ſome extraneous body; for the performance whereof we are compelled to enlarge the wound. So we are forced by neceſſity to open the neck of the bladder, (that ſo we may draw forth the ſtone therein contained) with a wound which often degenerates into an uncurable Fiſtula. For that Diſeaſe which threatens danger of preſent death is of ſuch moment, that to ſhun that it may be counted a ſmall matter, and commodious for the ſick, to bring in other Diſeaſes, though incurable. For if a convulſion happen by pricking a Nerve, which we cannot heal by any remedies, then by cutting the Nerve aſunder we end the convulſion, but deprive the part into which that Nerve did go, of the uſe of ſome voluntary motion. So if in any great joint there happen a Luxation with a wound, becauſe there is danger of convulſion by trying to reſtore and ſet right the luxated part, we are forced for ſhunning thereof, to attend the wound only, and in the mean time to let alone the Luxation. Otherwiſe, in implicit Diſeaſes, if there be nothing which may urge, or call us from the ordinary cure, we muſt obſerve this order, that beginning with that affect, which hinders the cure of the principal Diſeaſe, we proſecute the reſt in the ſame and their proper order, untill all the Diſeaſes being overcome, we ſhall reſtore the part affected to its integrity. Therefore let us take for an example, an Ulcer in the Leg, a *Varix*, (or big-ſwollen Vein) and a Phlegmonous tumor round about it; and laſtly, a body wholly plethorick and filled with ill humours; Order and Reaſon require this, that uſing the advice of ſome learned Phyſician we preſcribe a convenient diet, and by what means we may bring him to an equality by purging and blood-letting, and then we will ſcarifie in divers places the part where it is moſt ſwollen, then preſently apply Leeches, that ſo we may free it from the burden of the conjunct matter; then uſe Cauteries to help the corruption of the bone, and in the mean time change the circular figure of the ulcer into an oval, or triangular; then at the length we will undertake the cutting of the *Varix*, and cure the ulcer which remains according to Art, and ſo at the length cicatrize it. In all this whole time the Patient ſhall neither walk, nor ſtand, nor ſit, but lie quietly, having his Leg orderly and decently rouled up. But if (as it often happens) the temper of the hurt part be different from the temper of the whole body, the manner of curing muſt be ſo tempered, that we increaſe the doſis of hot or cold medicins, according to the ratable proportion of the Indications requiring this or that, therefore imagine the part ulcerated to be ſuch, as that it is two degrees drier then the juſt temper; but the whole body to exceed the ſame temper in one degree of humidity: Reaſon and Art will require, that the medicin applied to the ulcer be drier by one degree then that which the part would otherwiſe require if it were temperate.

Indications in implicit Diſeaſes.

An example of Indications in implicit Diſeaſes.

What we muſt do when the temper of the part is different from the temper of the whole body.

But

But on the contrary let us ſuppoſe thus; the whole body to be one degree more moiſt than the temper requires, and the ulcerated part to be one degree drier: truly in this caſe the Medicin that is applied to the Ulcer by reaſon of the part it ſelf, ſhall not be increaſed in drineſs, but wholly compoſed and tempered to the Indication of the Ulcer, becauſe the force of the moiſture exceeding in the like degree, doth counterpoiſe the ſuperfluous degree of drineſs. But it is more eaſie by an artificial conjecture to determine of all ſuch things, than by any rules or precepts.

An artificial conjecture is of much force in Indications.

To theſe ſo many and various Indications, I think good to add two other; the one from ſimilitude, the other of a certain crafty device; and as the later Phyſicians term it, a certain ſubtle ſtratagem. We draw Indication from Similitude, in Diſeaſes which newly ſpring up and ariſe, as which cannot be cured by Indications drawn from their contraries, as long as their Eſſence is unknown and hid, wherefore they think it neceſſary to cure them by a way and Art like thoſe Diſeaſes with which they ſeem to have an agreeing ſimilitude of Symptoms and Accidents; our Anceſtors did the ſame in curing the *French-Pox*, at the firſt beginning thereof, as long as they aſſimilated the Cure to that of the *Leproſie*, by reaſon of that affinity, which both the Diſeaſes ſeem to have. But we follow crafty devices and ſubtle counſels, when the Eſſence of the Diſeaſe we meet with, is wholly ſecret and hid, either becauſe it is altogether of a hidden and ſecret nature, and which cannot be unfolded by manifeſt qualities, or elſe reſides in a ſubject which is not ſufficiently known to us, nor of a Phyſical contemplation, as the Mind. For then, we being deſtitute of Indications taken from the nature of the thing, are compelled to turn our cogitations to impoſtures and crafty counſels; and, they ſay, this Art and Craft is of chief uſe in Melancholy affects and fictions, which are often more monſtrous and deformed than the *Chimera* ſo much mentioned in the Fables of the Ancients; to which purpoſe, I will not think much to recite two Examples. A certain man troubled with a Melancholick Diſeaſe, I know not by what errour of Opinion, had ſtrongly perſuaded himſelf that he was without a head; the Phyſicians omitted nothing, by which they might hope to take this mad opinion out of his mind. But when they had in vain tried all Medicines, at length they deviſed this crafty, but profitable device: They faſtned and put upon his head a moſt heavy helmet, that ſo by the pain and trouble of his head nodding and drawn down by that weight, he might be admoniſhed of his errour.

Indication from ſimilitude.

Indication of a ſubtle device.

It is reported, another moleſted by the obſcurity and darkneſs of the ſame Diſeaſe, did verily believe, that he had horns upon his head; neither could he be drawn or diverted from that abſurd and monſtrous opinion, until that binding up his eyes, they miſerably bruiſed and ſcratched his forehead with the bony roughneſs of the lower parts of an Oxes horns, that ſo he begun to believe by the painful drawing of the bloud that ran down his face, that thoſe bloudy horns were forcibly plucked from him. Ingenious Chirurgeons in imitation of theſe examples may in like caſes do the like. For that caſe requires a man of a quick apprehenſion and advice, who may give manifeſt proof of his diligence and skill by medicinal ſtratagems, as who forthwith can politickly deviſe ſtratagems of divers ſorts.

A Phyſician ſhould be of a quick apprehenſion.

But now coming to the end of this our tract of Indications, we muſt chiefly and principally obſerve; That of Indications ſome are Indicative, which abſolutely and of themſelves command this to be done; other co-indicative, which indicate the ſame with the Indicative, and jointly ſhew it to be done, but in ſome ſort ſecondarily and not primitively. Some are repugnant, which of themſelves and their own nature perſuade quite contrary to that the indicative primitively did perſuade us; other correpugnant, which give their voice after the ſame form and manner with the repugnant againſt the indicative, as the co-indicative conſent to and maintain them. Let this ſerve for an example of them all:

Indications
Indicative.
Coindicative.
Repugnant.
Correpugnant.

A *Plethora*, or plenitude of humours, of its own nature, requires and indicates bloud-letting, the Spring time perſuades and co-indicates the ſame; but to this counſel is quite oppoſite and repugnant a weak faculty; and childhood is correpugnant.

Wherefore theſe four muſt be diligently weighed and conſidered when we deliberate what is to be done, and we muſt rather follow that which the indicative or repugnant ſhew and declare, as what the Diſeaſes and ſtrength of the Patient require, than that which the coindicative or correpugnant ſhall perſuade, becauſe they have a weaker and but ſecondary power of indicating, and not eſſential and primitive. But becauſe the kinds of Indications are ſo many and diverſe, therefore that the knowledge of them may be more perſpicuous and leſs confuſed, I have thought good to deſcribe and diſtinguiſh them by this following Scheme.

A TABLE of INDICATIONS.

An Indication is a certain plain and compendious way which leads the Chirurgeon to a certain determinate and proposed end for the cure of the present Diseases: of which there are three kinds.

- *The first, is drawn from things Natural which indicate their preservation by their like; of this kind are many other which are drawn either*
  - *From the strength and faculties of the Patient,* — *For whose preservation, oftentimes the proper cure of the disease must be neglected; for where these fail, it is impossible the Chirurgeon should perform what he desires and expects.*
  - *From the temperament; as if the Patient shall be* — *Sanguine, Cholerick, Flegmatick, Melancholick,* — *Of preservation of which the Chirurgeon must have care, and if they swerve from equality, to reduce them to that which formerly they naturally were.*
  - *From the habit of the body, as the Patient shall be* — *Dainty and delicate. Slender and weak. Low of stature. Rare or else dense and compact.*
  - *From the native condition of the hurt or affected part; in which we consider, either*
    - *The Substance thereof, as for as much as it is similar, we consider whether it be hot, cold, moist, dry; or as it is organical, and then whether it be a principal and noble part, or a subordinate and ignoble part.*
    - *Or the sense, whether quick or dull, by reason whereof the eye cannot endure such sharp and acid medicines, as simple flesh can.*
    - *Or the form, figure, magnitude, number, site, connexion, action, use.*
  - *From the Age; for each Age yields his peculiar Indications: hence you may observe most diseases to be incurable in old men, which are easily cured in young; others which in Youth admit of no cure, unless by the change of age and the ensuing temperament.*
  - *From Sex; for medicines work upon Women far more easily then upon Men.*
  - *From the time of the year; for some Meats and Medicines are fit in Winter, some in Summer.*
  - *From the Region; for as there are diversities of situations and habits of places, so also there are motions of humours, and manners of diseases: hence it is that wounds on the head at* Paris, *and sore shins at* Avignon *are more difficult to be cured.*
  - *From the times of Diseases, for some things in the beginning, others in the increase, state, and declining of the Disease, are more convenient.*
  - *From the manner of Diet; for this, as the proper temper, must be preserved. Wherefore such must be fed otherwise who live daintily then those who lead their lives sparingly and hardly. Hereunto add certain peculiar natures, which by a certain hidden property are offended at this, or that kind of meat; for there are some which not onely cannot concoct Ptoisan, Apples, Soles, Partridge, Water, and such like, but can scarce behold them without nauseousness.*
- *The second is drawn from things not Natural, which one while indicate their preservation by their like, another while their change by their contrary; for so*
  - *If the Air have as it were conspired with the Disease by a certain similitude of qualities to the destruction of the Patient, it must be corrected by its contraries according to Art.*
  - *But if by the disagreement of qualities it resist the disease, it must be kept in the same temper.*
- *The third from things contrary to Nature, which shew, they must be taken away by the use of their contraries, as*
  - *The Disease, the Indication being drawn from these,* — *The greatness, The complication or commixtion with other; so* — *In implicit, or mixed diseases we may draw Indications from these three heads.*
    - *From that which is most urgent,*
    - *From the cause*
    - *And*
    - *From that, without which the disease cannot be taken away.*

    such are — *Bitterness of pain, a defluxion into a part, a Varix, or big swollen Vein, a distemperature, if they be joined with a disease.*
  - *Cause of the Disease* / *Symptom* — *Which two often indicate and require medicines contrary to the Disease.*

CHAP.

CHAP. XXIII.

Of certain wonderful and extravagant ways of curing Diſeaſes.

AS Monſters happen ſometimes in Nature, ſo alſo in Diſeaſes, and in the events and cures of Diſeaſes. I underſtand by Monſters certain marvellous ſucceſſes in Diſeaſes, or certain ways of curing them, which ſwerve from Art, and happen beſides Reaſon, Nature, and common uſe. Monſtrous Diſeaſes.

Alexander ab Alexandro and *Peter Gilius* tell, that in *Apulia* a place in *Italy*, they have a certain kind of Spider very frequent, the Natives call it *Tarantula*, *Petrus Rhodius* calls it *Phalangium*. The Inhabitants find theſe Spiders in the firſt heat of Summer ſo venenate and deadly, that whomſoever they touch with their virulent biting, he preſently, without he have ſpeedy remedy, deprived of all ſenſe and motion falls down; or certainly, if he eſcape the danger of death, he leads the remnant of his life in madneſs. Experience hath found a remedy by Muſick for this ſo ſpeedy and deadly Diſeaſe: Wherefore, as ſoon as they can, they fetch Fidlers and Pipers of divers kinds, who by playing and piping may make Muſick; at the hearing whereof he which was fallen down by reaſon of the venemous bite, riſes chearfully, and dances ſo long to their meaſures and tunes, until by the painful and continued ſhaking and agitation of the whole body, all the malignity is diſſipated by tranſpiration and ſweats. The wonderful force of the bite of a certain Spider. Muſick the remedy thereof.

Alexander adds, That it happened once in his ſight, that the Muſicians, their wind and hands failing them, ceaſed playing, and then the Dancer preſently fell down as if he had been dead; but by and by the Muſick beginning anew, he roſe up again and continued his dancing till the perfect diſſipation of the venom. And that it hath happened beſides, that one not perfectly healed, certain reliques of the Diſeaſe yet remaining, when a long time after he heard by chance a noiſe of Muſicians, he preſently fell a leaping and dancing, neither could he be made to leave before he was perfectly cured.

Some affirm according to the opinion of *Aſclepiades*, that ſuch as are frantick are much helped with a ſweet and muſical harmony. *Theophraſtus* and *Aulus Gellius* ſay, that the pain of the Gout and Sciatica are taken away by Muſick. And the ſacred Scripture teſtifies, that *David* was wont by the ſweet ſound of the Harp to refreſh and eaſe King *Saul* when he was miſerably tormented by his evil ſpirit. *Herodotus* in *Clio* tells, That *Cræſus* the King of *Lydia* had a Son which of a long time could not ſpeak, and when he came to mans eſtate was accounted dumb: but when an enemy with his drawn Sword invaded his Father (overcome in a great fight, and the City being taken in which he was) not knowing that he was the King, the young man opened his mouth endeavouring to cry out, and with that ſtriving and forcing of the ſpirit, he broke the bonds and hindrances of his tongue, and ſpoke plainly and articulately, crying out to the Enemy that he ſhould not kill King *Cræſus*. So both the Enemy with-held his ſword, and the King had his life, and his Son had his ſpeech always after. *Plutarch* in his Book, *Of the Benefit to be received from our Enemies*, tells, That a *Theſſalian* called *Proteus*, had a certain inveterate and incurable Ulcer, in a certain part of his body, which could not be healed, before he received a wound in a conflict in the ſame place, and by that means the cure being begun afreſh, the Wound and Ulcer were both healed. Muſick gives eaſe to pain. A ſtrong perturbation of the mind helps by moving the ſpirits.

Quintus Fabius Maximus, as *Livy* writes, was long and very ſick of a quartan Ague, neither could have wiſhed ſucceſs from Medicins adminiſtred according to Art, until skirmiſhing with the *Allobroges*, he ſhaked off his old feveriſh heat, by a new heat and ardent deſire of fighting. It was credibly reported to me of late by a Gentleman of the Lord of *Lanſack*'s Chamber, that there was a French Gentleman in *Polonia*, who was grievouſly tormented with a quartan Fever, who on a time walking on the Bank of the River *Wexel*, to take away the irkſomneſs of his fit, was thruſt in jeſt into the River by a friend of his that met him by chance, by which (although he could ſwim, as he alſo knew that thruſt him in) he conceived ſo great fear, that the Quartan never troubled him after. King *Henry* the Second commanded me to go from the Camp at *Amiens* to the City *Dorlan*, that I might cure thoſe that were hurt in the conflict with the *Spaniards*: the Captain S. *Arbin*, although at that time he had a fit of a Quartan Ague, yet would he be preſent at the fight, in which he being ſhot through the ſide of the neck with a Bullet, he was ſtrucken with ſuch a terrour of death, that the heat of the Fever was aſſwaged by the cold fear, and he after lived free from his Ague. Chance ſometime exceeds Art.

Franciſcus Valeriola the famous Phyſician of *Arles* tells, That *John Berlam* his fellow-Citizen troubled with a Palſie of one ſide of his Body for many years, his houſe taking fire, and the flame coming near the Bed in which he lay, he ſtrucken with a great fear, ſuddenly raiſed himſelf with all the force he had, and preſently recovering the ſtrength of his body, leaps out at the window from the top of the houſe, and was preſently cured of his Diſeaſe; Senſe and Motion being reſtored to the part, ſo that afterward he went upright without any ſenſe of pain, who lay unmovable for many years before. He tells the like in the ſame place of his Couſin *John Sobiratius*; he was a long time lame at *Avignon*, by reaſon that the Nerves of his Hams were ſhrunk and drawn up, ſo that he could not go; being moved with a vehement and ſudden paſſion of anger againſt one of his Servants whom he endeavoured to beat, he ſo ſtirred his body, that forthwith the Nerves of his Hams being diſtended, and his Knees made pliant, he began to go and ſtand upright without any ſenſe of pain, when he had been crooked about the ſpace of ſix years before, and all his life time after he remained ſound. *Obſerv. lib. 2.*

Galen tells, he was once fetched to ſtanch the bleeding for one who had an Artery cut near his Ancle, and that by his means he was cured without any danger of an *Aneuriſma* (*i.e.*) a relaxation of a veinous veſſel; and beſides, by that accidental wound he was freed from a moſt grievous pain of his hip, with which he was tormented four years before: but although this eaſing of the pain of the Sciatica happened according to reaſon, by the evacuation of the conjunct matter, by the Artery of the Ancle *Cap. ult. lib. de cur. rat. per. ſanguinis miſſ.* *Galen* by a dream cures the Sciatica.

Ancle of the ſame ſide being opened; yet becauſe it was not cut for this purpoſe, but happened only by chance, I judged it was not much diſſenting from this argument.

Pliny writes that there was one named *Phalereus*, which caſting up bloud at his mouth, and at the length, medicines nothing availing, being weary of his life, went unarmed in the front of the Battel againſt the Enemy, and there receiving a wound in his Breſt, ſhed a great quantity of bloud, which gave an end to his ſpitting of bloud; the wound being healed, and the vein which could not contain the bloud being condenſate.

At *Paris*, *Anno* 1572. in *July*, a certain Gentleman being of a modeſt and courteous carriage, fell into a continual Fever, and by that means became Frantick, moved with the violence of which, he caſt himſelf headlong out of a window two ſtories high, and fell firſt upon the ſhoulder of *Valterra* the Duke of *Alenzons* Phyſician, and then upon the pavement; with which fall he cruelly bruiſed his ribs and hip, but was reſtored to his former judgment and reaſon. There were preſent with the Patient beſides *Valterra*, witneſſes of this accident, theſe Phyſicians, *Alexis*, *Magnus*, *Duretus*, and *Martenus*. The ſame happened in the like Diſeaſe, and by the like chance, to a certain *Gaſcoyn*, lying at the houſe of *Agrippa* in the Paved Street.

Othomannus Doctor of Phyſick of *Monpelier*, and the King's Profeſſor, told me that a certain Carpenter at *Broquer* a Village in *Switzerland*, being frantick, caſt himſelf headlong out of an high window into a River, and being taken out of the Water was preſently reſtored to his underſtanding.

The cauſe of the laſt recited Cures.

But if we may convert Caſualties into Counſel and Art, I would not caſt the Patients headlong out of a window, but would rather caſt them ſuddenly, and thinking of no ſuch thing, into a great Ciſtern filled with cold Water, with their heads foremoſt, neither would I take them out until they had drunk a good quantity of Water, that by that ſudden fall and ſtrong fear, the matter cauſing the Frenzy might be carried from above downwards, from the noble parts to the ignoble; the poſſibility of which is manifeſt by the fore-cited Examples, as alſo by the example of ſuch as bit by a mad Dog, fearing the Water, are often ducked into it to cure them.

CHAP. XXIV.

Of certain jugling and deceitful ways of Curing.

HEre I determine to treat of thoſe Impoſtors, who taking upon them the perſon of a Chirurgeon, do by any means, either right or wrong, put themſelves upon the works of the Art; but they principally boaſt themſelves amongſt the ignorant common ſort, of ſetting bones which are out of joint and broken, affirming, as falſly as impudently, that they have knowledge of thoſe things from their Anceſtors, as by a certain hereditary right; which is a moſt ridiculous fiction: for our minds when we are born, is as a ſmooth Table, upon which nothing is painted. Otherwiſe what need we take ſuch labour and pains to acquire and exerciſe Sciences? God hath endued all brute Beaſts with an inbred knowledge of certain things neceſſary for to preſerve their life, more than Man.

Sciences are not hereditary.

But on the contrary, he hath enriched him with a Wit furniſhed with incredible celerity and judgment, by whoſe diligent and laborious fatigation, he ſubjects all things to his knowledge. For it is no more likely that any man ſhould have skill in Chirurgery, becauſe his Father was a Chirurgeon, than that one who never endured ſweat, duſt, nor Sun in the Field, ſhould know how to ride and govern a great Horſe, and know how to carry away the credit in tilting, onely becauſe he was got by a Gentleman, and one famous in the Art of War.

A moſt impudent ſort of Impoſtors.

There is another ſort of Impoſtors, far more pernicious and leſs ſufferable, boldly and inſolently promiſing to reſtore to their proper unity and ſeat, bones which are broken and out of joint, by the onely murmuring of ſome conceited charms, ſo that they may but have the Patients name and his girdle. In which thing I cannot ſufficiently admire the idleneſs of our Countreymen ſo eaſily crediting ſo great and pernicious an errour; not obſerving the inviolable Law of the ancient Phyſicians, and principally of Divine *Hippocrates*, by which it is determined, that three things are neceſſary to the ſetting of Bones diſlocated and out of joint; to draw the bones aſunder, to hold the bone receiving firmly immovable with a ſtrong and ſteddy hand; to put the bone to be received into the cavity of the receiving. For which purpoſe the diligence of the Ancients hath invented ſo many Engines, Gloſſocomies and Bands, leſt that the hand ſhould not be ſufficient for that laborious Work. What therefore is the madneſs of ſuch Impoſtors to undertake to do that by words which can ſcarce be done by the ſtrong hands of ſo many Servants, and by many artificial Engins?

Three things neceſſary for the cure of a Luxation.

Of late years another kind of Impoſture hath ſprung up in *Germany*: they beat into fine powder a ſtone which in their mother-tongue they call *Bembruch*, and give it in drink to any who have a bone broken or diſlocated, and affirm that it is ſufficient to cure them. Through the ſame *Germany* there wander other Impoſtors, who bid to bring to them the Weapon with which any is hurt; they lay it up in a ſecret place and free from noiſe, and put and apply medicines to it, as if they had the Patient to dreſs, and in the mean time they ſuffer him to go about his buſineſs, and impudently affirm that the wound heals by little and little, by reaſon of the Medicin applied to the Weapon.

But it is not likely that a thing inanimate, which is deſtitute of all manner of ſenſe, ſhould feel the effect of any Medicin; and leſs probable by much, that the wounded party ſhould receive any benefit from thence. Neither if any ſhould let me ſee the truth of ſuch juggling by the events themſelves and my own eyes, would I therefore believe that it was done Naturally, and by Reaſon, but rather by Charms and Magick.

In the laſt aſſault of the Caſtle of *Heſdin*, the Lord of *Martigues* the Elder, was ſhot through the Breſt

Breſt with a Musket bullet. I had him in cure together with the Phyſicians and Chirurgeons of the Emperour *Charles* V. and *Emanuel Philibert* the Duke of *Savoy*, who becauſe he entirely loved the wounded Priſoner, cauſed an Aſſembly of Phyſicians and Chirurgeons to conſult of the beſt means for his cure. They were all of one opinion, that the wound was deadly and incurable, becauſe it paſſed through the midſt of his Lungs, and beſides had caſt forth a great quantity of knotted bloud into the hollowneſs of his Breſt.

There was found at that time a certain *Spaniard*, a notable Knave, and one of thoſe Impoſtors, who would pawn his life that he would make him ſound; wherefore this Honourable Perſonage being in this deſperate caſe, was committed unto his care. Firſt of all, he bid they ſhould give him the Patients ſhirt, which he tore into ſhreds and pieces, which preſently framing into a Croſs, he laid upon the wounds, whiſpering ſome conceived or coined words, with a low murmur. For all other things he wiſhed the Patient to reſt content, and to uſe what diet he pleaſed, for he would do that for him, which truly he did. For he eat nothing but a few Prunes, and drunk nothing but ſmall Beer, yet for all this the wounded Prince died within two days; the *Spaniard* ſlipt away, and ſo ſcaped hanging. And whileſt I opened the body in the ſight of the Phyſicians and Chirurgeons to embalm him, the ſigns and accidents of the wound did evidently and plainly appear to be as we had pronounced before.

What wounds may be cured onely by lint, or by tents and Water.

And there be alſo other jugling Companions of this Tribe, who promiſe to cure all wounds with Lint, or Tents, either dry or macerated in Oil or Water, and bound to the wound, having murmured over ſome charm or other, who have had ſometimes good ſucceſs, as I can witneſs. But the wounds upon which trial was made were ſimple ones, which onely required union, or cloſing for to perfect the cure. So verily the bones of Beaſts when they be broke, grow together by the onely benefit of Nature. But when the affect ſhall be compound by diverſity of Symptoms, as a wound with an ulcer, inflammation, contuſion and fracture of a bone, you muſt hope for no other from Tents, or Lints, nor Charms, than death. Therefore the common ſort, who commit themſelves to theſe Impoſtors to be cured, do not only injure themſelves, but alſo hurt the Common-wealth, and the common profit of the Citizens; for whoſe good and Juſtice ſake a prudent Magiſtrate ought to deprive Impoſtors of all freedom in a free and Chriſtian Commonweal.

Witches, Conjurers, Diviners, Soothſayers, Magicians, and ſuch like, boaſt of curing many Diſeaſes; but if they do or perform any thing in this kind, they do it all by ſleights, ſubtilties, and forbidden Arts, as Charms, Conjurations, Witcheries, Characters, Knots, Magical Ligatures, Rings, Images, Poyſons, Laces tied acroſs, and other damnable tricks, with which they pollute, pervert, and defame the prime and ſacred Art of Phyſick, and that with the danger of mens lives. Who certainly are to be baniſhed by the Laws of our Countrey, eſpecially ſeeing it is decreed in *Moſes* Law, *Let none be found among you that uſeth witchcraft*, or a regarder of Times, or a marker of the flying of Fowls, or a Sorcerer, or a Charmer, or that conſulteth with Spirits, or a Soothſayer, or that asketh counſel at the dead; for all that do ſuch things are abomination to the Lord, and becauſe of theſe abominations the Lord thy God doth caſt them out before thee. But the miracles of our Lord Jeſus Chriſt the Son of God, and of his Saints and Apoſtles in curing Diſeaſes beyond Nature and all Art, are of another kind, which we ought to believe ſo firmly and conſtantly, that it ſhould be counted an impiety for a Chriſtian to doubt of them. All holy Writings are full of theſe; as to give ſight to the blind, hearing to the deaf, power to go to thoſe ſick of the Palſie, to drive forth Devils, to cure the Leproſie, to give fruitfulneſs to Women, to raiſe the Dead, and perform by the Holy Ghoſt other Miracles which exceed the condition and Law of Nature; whom here we earneſtly intreat to free and protect us from unclean Devils, and the Spirits of Diabolical deceit, and to give us the mind that we may will and be able always to aſpire to Heaven, and faſten the hope, ſafety, and anchor of all our Fortunes in God alone. *Amen.* *Deut.* 18.

The End of the Firſt Book.

BOOK

BOOK II.

Of Living Creatures, and of the Excellency of Man.

The difference of brute Beasts

BEfore I come to speak of the Anatomy of Mans Body, I have thought fit to say a little of the Nature of brute Beasts. There is between Beasts a great deal of difference by Nature; for of these some are hardy and bold, others fearful; some wild and savage, others tame; some walking in herds, others wandring alone; some covered and defended with shels and scales, as the Crocodile, the Tortois, and many kinds of Fish; others have stings and prickles.

The Horse hath his hard and strong hoofs, his Crest (as being a generous Beast) beset with a thick and harsh Mane. The defence of the magnanimous Lion are his Teeth, his crooked Paws and Tail. Bulls are formidable by their Horns. The Boar by his Tusks standing out, as it were natural Hunting-spears. The Hare being a timorous Creature, is naked and unarmed; but in recompence thereof Nature hath made her nimble and swift of foot. For what the more noble and couragious Beasts have in Arms, is supplied in the fearful by nimbleness and celerity. Infinite are the other endowments of brute Beasts, and such as can hardly be imagined or described. For, if we diligently search into their Nature, we shall observe the impressions and shadows of many Vertues, as of Magnanimity, Prudence, Fortitude, Clemency, and Docility: for they entirely love one another, follow those things that are good, shun those that are hurtful, and gather and lay up in store those things that are necessary for Life and Food. Lastly, They give undoubted presages of the Weather and Air. They have taught men many things, and are of a most exquisit and quick sense; of rare Art in Vocal Musick, prudent and careful for their young, and faithful Lovers of their Native Soil. They are religiously observant of the Rights of Friendship and Chastity. They have their Weapons whereby they are prepared both to invade and to defend themselves being invaded. They submit themselves to the Discipline of Man, practise and imitate his Speech, and mutually prattle and chant one to another. They have a kind of Weal-publick amongst themselves, and know how to preserve their present welfare, and to depel the contrary, being in this their own Counsellors, and not tutored by Man. Yea, Man is beholden to them for the knowledge of many wholsom things. The consideration of which bred so great a doubt amongst the ancient Philosophers, that it was a question amongst them, Whether Beasts had use of Reason, or no? Therefore also the wise *Solomon* sends us for examples of parsimony and diligence unto the Ant or Pismire; and *Esaias* in exprobration of the People of *Israel* for their ingratitude and rebellion against God, sends them to the Ox and Ass; for they do not onely know, but reverence their Masters.

Some shadow of Vertue in Beasts.

Lib.8. Cap.27. But from whence is the knowledge of these Medicins wherewith the Art of Physick is so richly adorned, but from brute Beasts? as *Pliny* affirmeth. The infallible vertue of the Herb *Dictamnus*, in drawing Darts out of the flesh, was taught us by the Hart, who wounded with the Huntsman's Darts or Arrows, by means hereof draws out the Weapons which remain sticking in her. Which is likewise practised by the Goats of *Candy*, as *Aristotle* writeth. The wonderful effect which *Celandine* hath upon the sight, was learnt by the practice of Swallows, who have been observed with it to have besmeared, and so strengthened the eyes of their young. Serpents rub their eye-lids with Fennel, and are thought by that means to quicken and restore the decaying sight of their eyes. The Tortois doth defend and strengthen her self against the biting of Vipers, by eating of Savory. Bears, by eating of Pismires, expel that Poison that they have contracted by their use of Mandrakes. And for correction of that drowsiness and sloth which grows upon them by their long sleep in their Dens, they eat the herb of *Aron* (i.) Cuckopint. But the Art they use in the inticing and catching of Pismires is very pretty: they go softly to the holes or hills of the Pismires, and there lay themselves all their length upon the ground, as if they were dead, hanging out their Tongue wet with their foam, which they draw not again into their mouth before they feel them full of Pismires, which are enticed by the sweetness of the foam: And having taken this as a purging Medicine, they expel by the guts those ill humors wherewith they were offended. We see that Dogs give themselves a Vomit by eating a kind of Grass, which is from thence called Dog-grass. Swine, when they find themselves sick, will hunt after Smalt, or River-Lobsters. Stockdoves, Blackbirds, and Partridges, purge themselves by Bay-leaves. Pigeons, Turtles, and all sorts of Pullen disburden themselves of gross humours by taking of Pellitory of the Wall. The Bird *Ibis* (being not much unlike the Stork) taught us the use of Clysters. For when he finds himself oppressed with a burden of hurtful humours, he fills his Bill with Salt Water, and so pnrgeth himself by that part by which the Belly is best discharged. The invention of the way of removing the Cataract of the eye we must yield unto the Goat, who by striking by chance against the thorny bushes, pulls off the Cataract which hinders the sight, and covers the ball of the eye, and so recovers his sight. The benefit of Phlebotomy we owe unto the *Hippopotamus* or River-horse, being a kind of Horse, and the Inhabitant of the River *Nilus*; who being a great devourer, when he finds himself surcharged with a great deal of bloud, doth by rubbing his thigh against the sharp Sands on the Bank side, open a Vein, whereby the superfluous bloud is discharged, which he stoppeth likewise when it is fit, by rowling himself in the thick mud. The Tortois having chanced to eat any of the flesh of a Serpent, doth make Origanum and Marjoram her Antidote. The Ancients found help from brute Beasts, even against the dreadful and non-sparing force of Lightning; for they were of opinion that the Wings of an Eagle were never struck with Lightning, and therefore they put about their heads little wreaths of these Feathers

The craftiness of Bears.

The Bird *Ibis* the first Inventer or Shewer of Clysters.

The invention of removing a Cataract.

The invention of phlebotomy.

A preservative against Thunder.

Feathers. They were perſuaded the ſame thing of the Seal, or Sea-Calf, and therefore were wont to encompaſs their bodies with his Skin, as a moſt certain ſafeguard againſt Lightning. It were a thing too long and laborious to ſpeak of all thoſe other muniments of life and health (obſerved here and there by *Ariſtotle* and *Pliny*) which we have learnt of brute Beaſts. I will therefore end this Chapter, after that I have firſt added this; That we are beholden to Beaſts not onely for the skill of curing Diſeaſes, and of preſervation of Health, but for our Food, our Rayment, and the Ornament and Beautifying of our Bodies.

Of the Faculty of brute Beaſts in Preſaging.

THe firſt knowledge and skill of Prognoſtication, and obſervation of Weather by the Air, was firſt delivered unto us from Beaſts of the Land and Water, and from Fowl. For we ſee in daily obſervation, that it is a ſign of change of Weather when Lambs and Rams do but at one another with their Horns, and playing wantonly do kick, and keep up their heels. The ſame is thought to be preſaged when the Ox licks himſelf againſt the hair, and on the ſudden fills the Air with his lowing, and ſmells to the ground, and when he feeds more greedily than he uſed to do. But if the Piſmires in great multitudes fetch their prey ſo haſtily, that they run and tumble one upon another in their narrow paths, it is thought a ſign of rain; As is alſo the buſie working of Moles, and the Cats rubbing and ſtroking of her head and neck, and above her ears with the bottom of her feet. Alſo when Fiſhes play and leap a little above the Water, it is taken for a ſign of rain. But if the Dolphins do the ſame in the Sea, and in great companies, it is thought to preſage a ſudden ſtorm and tempeſt. Whereby the Mariners fore-warned, uſe all care poſſible for the ſafety of themſelves and their Ships, and, if they can, caſt Anchor. And it is ſufficiently known what the louder croaking of Frogs than ordinary portends.

What the butting of Rams ſignifies.

Preſages of Rain.

The ſign at Sea of a ſtorm at hand.

But the faculty of Birds in this kind of preſaging, is wonderful. If Cranes flie through the Air without noiſe, it is a ſign of fair Weather; and of the contrary if they make a great noiſe and fly ſtraglingly. As alſo if Sea-Fowl fly far from the Sea, and light on the Land. The cry or ſcriech-ing of Owls portends a change of the preſent Weather, whether foul or fair. *Plutarch* ſaith, that the loud cawing of the Crow betokens Winds and Showrs, as alſo when he flaps his ſide with his wings. Geeſe and Ducks, when they dive much, and order, and prune, and pick their Feathers with their Beaks, and cry to one another, fore-tell rain; and in like manner Swallows, when they fly ſo low about the Water that they wet themſelves and their wings. And the Wren, when he is obſerved to ſing more ſweetly than uſual, and to hop up and down. And the Cock when he chants, or rather crows preſently after the ſetting of the Sun. And Gnats and Fleas, when they bite more then ordinary. If the Heron ſoar aloft into the Air, it betokeneth fair Weather; if on the contrary he fly cloſe by the Water, rain. If Pigeons come late home to the Dove-houſe, it is a ſign of rain. If Bats fly in the Evening, they fore-ſhew wet Weather. And laſtly the Crocodile lays her Eggs in that place which muſt be the bounds of the overflowing of the River *Nilus*; and therefore he that firſt meets with theſe Eggs, tells the reſt of the Countrey People, and ſhews how high the flood will riſe, and what inundation it will make upon their Grounds: A thing moſt worthy of admiration, that in this Monſter there ſhould be that ſtrong faculty of preſaging.

The Crocodile by laying her eggs ſhews the bounds of the River *Nilus*.

Of the Induſtry of Fiſhes.

MAny Sea-fiſhes, when they feel a tempeſt coming, do gravel or baleſt themſelves, to the end they may not be toſſed up and down at the pleaſure of the waves. Others, when the fury of the Sea is at the height, hide themſelves in the holes of Rocks. But in that they ſwim againſt the ſtream, they do it for this cauſe and reaſon, that the force of the ſtream and the flood may not take from them, and ſtrike off their ſcales, and that their gills may not fill with water which would hinder their ſwimming, and intercept their reſpiration. As by the ſame advice Cranes fly againſt the Wind; whereas if they ſhould fly down the Wind their Feathers would be diſplaced and broken, and they would not be able to fly.

How Fiſhes provide for their ſafety againſt a ſtorm.

How they ſwim againſt the ſtream.

Of the Induſtry of Birds in the building of their Neſts.

THe induſtry of Birds in the building of their Neſts is ſuch, that it doth far exceed the Art and Skill of all Maſons and Architects, from whence it is become a Proverb, *That men know, and can do all things but make Birds Neſts.* They are built within with Wool and Feathers, and ſuch kind of ſoft things, which are as a kind of a Pallet for the young ones. Swallows build their Neſts in a round form, that they may be the more firm, and leſs ſubject to be hurt by any things that ſhall ſtrike againſt them, and likewiſe more capacious. They chuſe their matter out of Dirt and Chaff, (interlacing it with many Straws) as it were, their Plaſter or Lime. Thoſe that build in Trees do make choice of the ſoundeſt Boughs, as if they meant to have them as a ſure foundation for the building which they ſhould erect thereon. The Cock and the Hen do by turns ſit over their Eggs, and likewiſe fetch their meat, interchanging each others labour; neither do they ever forſake their young, before they are able to get their own living. I had at my houſe a great number of Sparrows Neſts in earthen Pots; and when the young ones begun to wax pretty big, and to be covered with Feathers, I made the whole Neſt be taken down and ſet upon the ground, that I and my friends might delight our ſelves in beholding the care of the old ones in the feeding of their young; for they feed them every one in order, skipping none, neither will they (to the wrong of the reſt) give one two parts, although he gape, and be importunate for it; dividing moſt juſtly to every one his own ſhare, according to the exact rule of diſtribution. And oftentimes for experiment, I would make trial with a ſtrange Sparrow of the ſame age, laid near, or put among the reſt of the young ones, whether the old ones would feed the ſtranger, as if it were legitimate. But this as a ſtranger and a Baſtard they would ſuffer to ſtarve, ſkipping it when it gaped after the meat. And in like manner Lambs and young Kids do in the Fields, in the midſt of a great Flock, run every one to his own Dam; who being moſt certainly able to diſtinguiſh between the Legitimate and a Baſtard, will not ſuffer her ſelf to be ſuckt, but by her own young.

Of what things Birds build their Neſts.

In what ſhape.

With what care Sparrows feed their young.

Of

Of the Industry of Spiders.

How the Spiders weave.

THe Spider spins her Web with wonderful Artifice, hanging and fastening it to every tack, or stay that is nigh, drawing of his thread, and running upwards and downwards, and every way. And although the diligence of the Chamber-maid beats down and mars this pendulous and new-begun work, yet her seat and her hold the Spider keeps still; neither doth she, nor will she desist from the work she hath begun, but in a very short time weaves a great deal more unto the ruines of her former work, than can be unweaved again with much labour. So that from hence all Cloth and Linnen Weavers, all Embroiderers and workers with the Needle (you will easily think) have learnt their Arts, if either you observe the exactness of the weaving, the fineness of the thread, or the continuation and indissoluble knitting together of the whole Web; for, being abrupt, and troubled with no ends of threds at all, it resembles a thin membrane, anointed with a kind of glew, whereby when the prey is entangled, the Spider runs presently in, and as it were draws her nets and infolds, and takes the captive after the manner of Huntsmen. If this were not daily seen with our eyes, it would be thought fabulous.

How they catch their prey.

Of Bees.

Bees chuse themselves a King.

I Cannot pass in silence the great industry of Bees: For having established a kind of Weal-publick, they make election of a King, who is such a one, as in procerity of body, and excellency of feature exceedeth all the rest. He is remarkable by his short wings, his streight legs, his grave gate; and in stead of a Diadem or Regal Crown, either he hath no sting, or else doth not use it, which is the Artillery of the rest. He never goeth unattended out of the Hive, but alway, environed with a Princely Retinue, the rest of his Train following after, neither goes he at any time abroad, but upon urgent affairs which concerns the whole State. His progress is fore-warned by the voice and sound of Trumpets, and as it were with singing, and they all draw nigh. Every one gets as near to his person as he can, and when he is weary with flying, they all bear him up with their own bodies.

Their pitching their tents. Their obsequies for their dead King.

On what place soever he alighteth, there they forthwith pitch their Tents. If he chance to die, they go not abroad to feed, but stand all mourning round about the corpse; then carry him out of the Hive, and (as it were follow his Hearse and bury him: and lastly, having with solemnity performed all the several rites and obsequies, they chuse themselves another King, for without a King they cannot live. He then taketh care of all things, having his eye every where, whilest that the rest intend the performance of the work. And supervising all, giveth them encouragement, and chastiseth negligence. For their time of going forth for food, they chuse a clear and fair day; for they have a natural faculty of presaging of the Weather. They are such observers of Justice and equity, that never, either with their sting, or by any other way, do they molest any Creature, neither do they exercise and prepare their Spears against any, but for the safeguard of themselves and their Hives.

Their justice.

Of the Care of Bees.

THey manage and order their affairs in this manner; in the day-time they appoint before their Gates a Station of Watchmen and Guarders. In the night they rest from their labours, so long, till that one (who is appointed to this charge) by one or two hums, as by the sound of a Trumpet, rouzeth all the rest. Then come they together to observe what is the state of the Weather, which if they foresee will be fair, then abroad go they into the Fields and Pastures. Some therefore bring into the Hive little fascicles of Flowers on their thighs; others water in their mouth, and others a dewy moisture gathered on their bodies. These are met by others, who receive their burdens, which they dispose in their due and proper places. Those that are sent out into the Fields for food, are the youngest and the smallest: and therefore if the wind chance to rise any thing high, they expect until it cease, and that the force and violence thereof be over. But if it continue violent, then do they ballast themselves with a little stone, flying close by the ground to prevent their being driven to and fro by the wind. They are exceeding diligent in all their business, and do punish the sloth of the Lazy oftentimes with death. Some of them are the Builders, others polish the Building, and the rest bring in their Materials.

Their watch.

Their divers imployments.

The building in their arched Hives is with wonderful artifice, being made with two doors, one to come in, and the other to go out at. They have all things alike, lest that the inequality, either of their food or labour, should give occasion of dissension. Their care is, that their houses may shew both state and handsomness. Idle Drones, born for nothing but to eat, and consume the fruits of their labours, they chase from their Hives. Those that chance to lose their stings are utterly disabled, and in a short time their guts come out that way, and they die. They bring to the Owners wonderful increase of Wax and Honey.

They punish Sloth with banishment.

Aristomachus a diligent observer of Bees.

Aristomachus the Philosopher doth boast, that for fifty eight years together, he had with great care been a nourisher of Bees, onely that he might better attain to the knowledge of their state and condition.

Of Pismires and Ants.

NEither truly is the industry, diligence, and experience of the Pismire less worthy of admiration than that of the Bees. Insomuch as that *Solomon* bids the sluggard to take an example of diligence from the Pismire. Truly, if experience did not witness it, it would seem incredible, that so small a Creature should be able to store up such abundance of Corn, to dispose and manage her affairs in that good order that we see she doth. *Pliny* saith, that they have among them the form of a well-governed and well-ordered Common-weal. For how pretty a sight is it to see them when they seize upon a grain they have a mind to carry away, how they set to it, and lift it with head and shoulders, And how, lest the Corn which they carry to their Store-house, should put forth and grow, they bite it at one end. If it be so big that they cannot carry it into their little hole, they divide it in the middle. If it be dampish, they lay it out to dry in the Sun and open Air. When the Moon is at the full they follow their work in the night; when she doth not shine, they take their rest, whereby they shew themselves to have some knowledge of heavenly things. *Pliny* affirmeth

Lib. 11. *&* 30.

Wonderful care.

firmeth that they have their ſet Fairs and Markets, whither they come in great companies, and where they uſe to eſtabliſh Leagues of Amity and Friendſhip one with another. And when one marks them well, would he not think that they were in conference one with another, and that they did diſcourſe among themſelves of their buſineſs? Do we not ſee that the often trampling of their little feet doth wear a path even upon hard flint ſtones?

From whence we may note, what in all kind of things is the affect of the aſſiduity. They ſay alſo that they perform the rites of burial one unto another, after the manner of men. What words ſhall I uſe (ſaith *Plutarch*) to expreſs ſufficiently the diligence and induſtry of the Piſmires? There is not among all the great things in Nature, a ſight of greater wonder than theſe: For in the Piſmires are ſeen the marks of all Vertues. Their great meetings argue that they maintain a kind of Friendſhip. There is nothing but may be attained by diligence.

Their alacrity in the undergoing of their labours, ſeem to ſhew their fortitude and magnanimity; and laſtly, they are eminent examples of Temperance, Providence, and Juſtice. Their mutual Charity appeareth in this, that if one of them that is not loaden meets another (in one of their narrow paths) that is, he will give him the way, that he may the better go on in his intended journey. They ſay, that the firſt entrance into their hole is not ſtreight, but full of many diverticles and crooked paths, which in the end will bring you to three little Cells; in one of which they have their Conventicles, in the other they lay up their Proviſions; and in the third they bury the carkaſſes of their dead. This doth *Plutarch* ſpeak concerning Piſmires. The forms of all Vertues expreſt in Piſmires.

Of Silk-Worms.

WIth the Induſtry of theſe Creatures I ſhall not unfitly join that of the Silk-Worm, of whoſe pains and care, both in the making of their Neſts, and the ſpinning of their thred and bottoms (wherewith Kings are ſo magnificently adorned) Philoſophers have written very ſtrange things.

And who can chuſe but wonder at thoſe great endowments of Skill and Knowledge, and that exceeding induſtry (the Mother of ſo much Wealth) in the little Body of ſo ſmall a Creature? The providence therefore of God doth not onely appear in this, that he hath adorned each Creature with a peculiar and proper endowment, but in this eſpecially, that on the leaſt Creatures of all, he hath beſtowed the greater portion of Skill, Induſtry, and Ingenuity, to ſupply their defect of bodily ſtrength. Diligence the Mother of Wealth.

Of the love of Beaſts one towards another, and to their Young.

PLutarch writeth, That all kind of Creatures bear a ſingular love, and have a kind of care of thoſe that are generated of them, and the induſtry of Partridges this way is much commended; for during the time that their young ones are weak and unable to fly, they teach them to lie upon their backs, and to hide themſelves among the clods on the ground, that ſo being almoſt of the ſame colour, they may not be diſcerned by the Falconer. But if notwithſtanding they ſee any body coming, and that he is near them, they do with a hundred dodges and ſtoopings of themſelves, as if they were weary with flying, entice him away from their young to follow after them, and when they have their purpoſe, they then, as if they had recovered ſome freſh ſtrength, fly quite away: Who can but wonder at this, both affection and ſubtilty? The induſtry of Partridges in preſerving their Young.

In *Florida*, part of the *Weſt-Indies*, they have a Beaſt, which for the variety and deformity of it I cannot paſs over in ſilence; the Natives call it *Succarath*, the Cannibals *Su*. It keeps for the moſt part about the Rivers, and the Sea-ſhore, and lives by prey. When he perceiveth that he is purſued by the Huntſman, he gets his young ones upon his Back, and with his Tail, which is very long and broad, he covereth them, and ſo flying, provideth both for his own and their ſafety; neither can he be taken by any other way but by Pits, which thoſe ſavage men uſe to dig in the places near which he is to run, into which at unawares he tumbles headlong.

This Picture of him here, I drew out of *Thevets* Coſmography.

How Hares provide for themſelves and their Young, for fear of Hunters.

Neither are thoſe things leſs wonderful that are reported of Hares, for when they would go to their ſeat, they ſever their young, and commit them to the truſt of divers places, it may be two acres aſunder one from another, leſt peradventure a Huntſman, a Dog, or any Man ſhould chance to come that way, and they might be in danger to be loſt at once. And then after they have traced up and down, hither and thither, and every way, that the Dogs may not trace them, nor the Huntſman prick them, they take a leap or two, and leap into their forms.

Nor inferior to this is the craft of the Hedg-hog; for when the Fox purſueth him, and is now at his heels, he rowls himſelf up in his prickles like a Cheſnut in the outward ſhell, ſo that every part being rounded and encompaſſed with theſe ſharp and dangerous pricks, he cannot be hurt; and ſo ſaves himſelf by this trick. For his young he provides in this manner:

The care of the Hedg-hog to provide for her Young.

In the time of Vintage he goes to the Vines, and with his feet he ſtrikes off the Boughs and the Grapes, and then rowling his body makes them ſtick upon his prickles, and ſo doth (as it were) take his burden upon his back, and then returns to his hole; you would think that the Grapes did move of themſelves; the prey he divides between himſelf and his young.

Of the affection of Birds, and of Dogs towards their Maſters.

The Piety of Storks.

THe young Stork provides for the old, which is diſabled by age; and if any one of their equals come to any miſchance that he is not able to flie, they will give him their aſſiſtance, and bear him on their backs and wings. And therefore this affection and piety towards the old one, and (as it were) brotherly love towards their equals, is commended in the Stork.

The Hen in any kind of danger gathers her Chickens under her wings, and (as it were) with that guard, defends them as well as ſhe can. For their ſake ſhe expoſeth her ſelf to the cruelty of the fierceſt Beaſts; and will flie in the eyes of a Dog, a Wolf, or a Bear, that by chance offers to meddle with her Chickens.

The fidelity of Dogs.

But who is there that doth not admire the fidelity and love of Dogs towards their Maſters, whereby they recompence them for their keeping? A Dog will never forſake his Maſter, no, if he be never ſo hardly uſed. For there is no man can find a ſtick hard enough to drive that Dog clean away from him which hath once taken a love to him. There is no kind of Creature that doth more certainly and readily remember his Maſter; he will know the voice of all the houſhold, and of thoſe which frequent the houſe. There cannot be a truſtier Keeper (as *Cicero* himſelf ſaith) than a Dog is; I ſpeak not of their faculty of ſmelling, whereby they follow their Maſters by the foot, and find them; neither do I ſpeak of thoſe infinite examples of the fidelity of Dogs, which were too long to rehearſe.

Doves free from adultery.

Pigeons, as well the Cock as the Hen, although they are all very venereous, yet they know no adultery; yea, and the Hen will bear with the frowardneſs of the Cock, neither will ſhe ever leave him, but reconciling him unto her by her officious diligence, bring him to his wonted dalliance and kiſſes; neither is the love of either of them leſs towards their Young.

Turtles never couple twice.

There is the like mutual bond of love between Turtles; for if one of them die, the ſurviver never ſolicits Hymen more, neither will he ever chuſe other ſeat than a dry withered Bough.

Of the Lamprey.

LEſt that the heat of affection may ſeem to lie quenched under the Waters, let us by one example, (it were an infinite thing to ſpeak of all) ſee in what kind of mutual love the Creatures of the Water come ſhort of thoſe of the Land. The Lamprey of all the Creatures of this kind doth worthily bear the praiſe for its piety towards thoſe of whom it was generated, its affection towards thoſe that are generated of her; for firſt ſhe breeds Eggs within her, which in a ſhort time after are ſpawned. But ſhe doth not as ſoon as her young ones are formed and procreated, bring them ſtraight-way forth into the light after the manner of other Fiſhes that bring forth their Young alive, but nouriſheth two within her, as if ſhe brought forth twice, and had a ſecond brood. Theſe ſhe doth not put forth before they are of ſome bigneſs, then ſhe teacheth them to ſwim and to play in the Water, but ſuffers them not to go far from her; and anon gapes and receives them by her mouth into her bowels again, ſuffering them to inhabit there, and to feed in her belly ſo long as ſhe thinks fit.

The Savage or Brute Beaſts may be made tame.

Coſmograph. Tom. 2. lib. 19. cap. 7.

THevet reporteth, that the Emperour of the *Turks* hath at *Caire* (it was once called *Memphis*) and at *Conſtantinople*, many ſavage Beaſts kept for his delight, as Lions, Tigers, Leopards, Antilopes, Camels, Elephants, Porcupines, and many other of this kind. Theſe they uſe to lead about the City to ſhew. The Maſters of them are girt with a Girdle hung about with little Bells, that by the noiſe of theſe Bells the people may be fore-warned to keep themſelves from being hurt by theſe Beaſts. But in hope of reward, and of gifts, they ſhew them to Ambaſſadors of ſtrange Nations, before whom they make theſe Beaſts do a thouſand very delightful tricks, and in the interim they play their Countrey Tunes and Muſick upon their Pipes and other Inſtruments, and make many ſports in hope of gain.

That Fiſhes alſo may be tamed.

BUt it is far more wonderful that the Creatures of the Water ſhould be made tame, and be taught by the Art of Man. Among which the chiefeſt are held to be the Eel. The ſame things alſo are reported of the Lamprey. For, we have it recorded, that *Marcus Craſſus* had a Lamprey in his Fiſh-pool that was ſo tame and ſo well taught, that he could command her at his pleaſure. Therefore as a domeſtical and tame Beaſt he gave her a name, by which, when he called her, ſhe would come. And when this Lamprey died, he mourned for her in black, as if ſhe had been his daughter. Which when his Colleague *Cneus Domitius* objected to him by way of reproach, he replying told him, That he had buried three Wives, and had mourned for none of all them three.

Of

Of the ſtrength, piety, docility, clemency, chaſtity, and gratitude of Elephants.

AMong the Beaſts of the Field, there is none more vaſt, more ſtrong, or more to be feared than the Elephant. His ſtrength is ſufficiently ſhewn by thoſe towred Caſtles of armed men which he carries, and fiercely ruſheth with into the Battail. The *Roman* Souldiers, being otherwiſe of undaunted ſpirits, yet in that battail which they fought againſt *Pyrrhus*, being terrified with the vaſt-

neſs and immanity of theſe Bodies, which they had never before ſeen, preſently turned their backs and fled; which notwithſtanding, it is a wonderful thing what Stories Natural Philoſophers tell of the Vertues of the Elephant.

Lib.8.cap.1. *Pliny* writeth, that an Elephant cometh very near to the underſtanding that Men have, and that he hath a rude kind of knowledge of Language; that his facility and obſequiouſneſs is wonderful; that his memory in the performance of his wonted duties, is no leſs wonderful. And for

The Religion of the Elephant. Religion (*Plutarch* ſaith) that they pray unto the Gods, and ſprinkle and purge themſelves with ſalt water; and that with great reverence they worſhip the Sun at his riſing, lifting their trunks up towards Heaven for want of hands. *Pliny* addeth, that they do with the like reverence worſhip the Moon and the Stars. For it is related in the Hiſtory of the *Arabians*, that at a New Moon the Elephants go by Troops down unto the Rivers, and there waſh themſelves with water; and being thus purged, kneel down and worſhip the Moon, and then return to the Woods; the eldeſt going firſt, and the other following after according to their age. *Plutarch* reporteth, that it hapned once, that among the Elephants which were taught at *Rome*, againſt the Panegyrick Shows, there was one that was ſomething dull, and not ſo docile as the reſt, which made him be deſpiſed by his fellows, and often beaten by his Maſter: But that this Elephant, that he might ſupply by diligence what he wanted in wit, was often-times obſerved in the night, by the light of the Moon, to be practiſing and conning what he learnt of his Maſter in the day time. For they were wont to be taught to make Letters, and alſo to preſent Garlands to the Spectators, and other ſuch like tricks. But they can never be brought to go aboard a Ship, to be carried over the Sea into any ſtrange Land, unleſs their Maſter give them his word to aſſure them that they ſhall return again to their own native ſoil. They never hurt any one that doth not firſt provoke them. They never gender but in private, out of ſight; an argument of their modeſty.

Plin.lib.8. c.5.

Of the Lion, the Ichneumon, and thoſe other Beaſts which are not eaſily terrified.

The providence of the Lion in his going. THe Lion when he goes, hath his claws always clutched, and (as it were) put up in their ſheaths, not onely becauſe he would leave no mark in his feet, whereby he may be traced and ſo taken, but becauſe by continual walking he ſhould wear off, and blunt the points of his Claws. Bulls when they fight, charge one another with their horns, and like valiant Souldiers provoke and animate one another to the Battail.

The Ichneumon ſeems to imitate the moſt valiant Souldier in his preparation and acceſs to battail; for he bedawbs himſelf with mud, and doth (as it were) buckle and make tite his Armour, eſpecially when he is to encounter with the Crocodile; who although he be a vaſt Beaſt, is put to flight by this little Creature. And this truly hath been obſerved to be by the ſingular Providence of Nature, that the moſt vaſt Creatures are terrified by the leaſt things, and ſuch from whence there can ariſe no danger; ſo they ſay, the Elephant doth ſtartle at the grunting of a Hog, and the Lion at the crowing of a Cock; although it be reported of the Lion, that no fear can make him turn his face. Theſe kind of fears, terrors, and affrightments, ariſing upon light and moſt ridiculous occaſions, we find as well in the ancient as modern Hiſtories of our Times, to have diſperſed and put to flight mighty Legions of Souldiers, and moſt potent Armies.

The greateſt are terrified by the leaſt.

Of Cocks.

Cocks are Kingly and martial Birds. COcks are Kingly Birds, and therefore Nature hath adorned them with a Comb, as with a Princely Diadem; and whereſoever they come, their magnanimity and courage makes them Kings. They fight with their Beaks and their Spurs, and with their martial voice they fright the Lion, who is otherwiſe the King of Beaſts.

Of Conies.

Conies have taught us undermining. COnies have taught us the Art of undermining the Earth, whereby the moſt lofty Cities and Structures reaching to the very Skies, are by taking away their foundation levelled with the ground.

Marcus Varro writes, that in *Spain* there was a Town, and that no mean one, which ſtanding on a ſandy ground, was ſo undermined by a company of Conies, that all the Houſes tumbling and falling down to the ground, the Inhabitants were fain to depart and ſeek new dwellings.

Of Wolves.

The deceits and ambuſhes of Wolves. MEn have learnt the Arts of waging War from the Wolves, for they come out by Troops, and lie in ambuſh near the Towns which they have appointed, and then one of them runs unto the Town and provokes the Dogs. And making, as if he run away, incites the Dogs to follow him, until he hath gotten them unto the place where their ambuſh lieth, which on a ſudden appeareth and ruſheth out upon them. And ſo they kill and eat all, or as many of the Dogs as they are able to catch.

Of the Fox.

The craft of the Fox. IN ſubtilty and craft the Fox exceedeth all other Beaſts: When in the chaſe the Dogs are at his heels, he berays and bepiſſes his tail, and ſwings it in the face and eyes of the Dogs that follow him, and ſo blinding them, in the mean time gets ground of them. To fetch the Hens down from their Perch, he hath this device; he ſhakes and ſwings his tail upwards and downwards, as if he meant to throw it at them; which they fearing tumble down, and he takes up one of them for his prey. His warineſs when he paſſes over a River that is frozen, is wonderful; for he goes ſoftly to the bank, and lays his ear to liſten if he can hear the noiſe of the Water running under the Ice: For, if he can, back he goes, and will not venture to paſs over. The knowledge of which thing he could never meerly by his ſubtilty and craft attain unto, but that of neceſſity he muſt have ſome faculty of reaſoning joined with it; which by diſcourſe, and by proving one thing by another, arrives at this concluſion: Whatſoever is liquid and maketh a noiſe, is in motion; whatſoever liquid

The Fox ſeems to reaſon with himſelf. His *Sorites.*

liquid is in motion, is not concrete and frozen; that which is not concrete and frozen, is liquid; whatsoever is liquid, will not bear a heavier body; whatsoever will not bear a heavier body, cannot with safety be adventured on; and therefore back again must I go, and not pass over this River.

That men are taught by Beasts to polish and to whet their weapons, and to lie in ambush.

SOuldiers are careful to keep their Weapons from rust, and therefore they carry them to the Armourers to be polished. But in this care, many Beasts are nothing inferiour unto them; for Boars whet their tusks against they fight. And the Elephant knowing that one of his teeth is doubled with digging at the roots of Trees to get meat, keepeth the other sharp, and touches nothing with it, preserving it for his combat with the *RHINOCEROT* his Enemy. But the craft of

The craft of the Rhinocerot about to fight with the Elephant.

the Rhinocerot is very remarkable, that being in continual enmity with the Elephant, at the time when he prepares for the battel, he whets his horn againſt a Rock, as it were with a Whetſtone; nor (if he can chuſe) will he ſtrike any other part of the Elephant but the belly, becauſe he knows that part of the Elephant is ſo tender, that it may be eaſily pierced. This Beaſt is in length equal to the Elephant, but in height he is inferiour unto him, by reaſon of the ſhortneſs of his feet; he is of a paliſh yellow colour, and full of many ſpots.

Of Swine.

SWine, if in the Woods, they hear any one of the ſame Herd with them crying out, they ſtrait make a ſtand; and marſhalling their Forces, haſte all, as if they had been warned by the ſound of a martial Trumpet, to the aſſiſtance of their fellows.

Of the Fiſhes Scarus *and* Anthia.

The love of Fiſhes one to another.

PLutarch reports of the *Scari*, that when one of them chances to ſwallow a hook, and be taken, the reſt of the ſame kind come to his reſcue, and ſhearing the line with their teeth, ſet him at liberty. But the readineſs of the *Anthiæ* to the mutual aſſiſtance of one another, is yet more manifeſt; for by caſting the line upon which the hook hangeth on their back, with the ſharpneſs of their Fins they cut it aſunder, and ſo ſet free themſelves and their captived fellows.

Of the Pilot-*fiſh.*

THere is a great kindneſs between the Pilot-fiſh and the Whale; For, although in bulk of body the Whale ſo far exceed him, yet he leads the Whale, and goes always before him as his Pilot, to keep him from running himſelf into any ſtraight or muddy place, whence he might not eaſily get out. And therefore the Whale always follow him, and very willingly ſuffers himſelf to be led by him, it being for his own good. And, in like manner, he gets into the Whales mouth, and there lodging himſelf, ſleeps when he ſleeps, and leaves him not either by day or night.

The Whales Pilot or Guide

Of Cranes.

Cranes order themſelves in ranks.

CRanes when they are to take a long journey into ſome Countrey croſs the Seas, put their company in ſo good order, that no Captain can put his Souldiers in better. For before they ſtir out of any place, they have (as it were) their Trumpets to call them together, and encourage them to flie. They come together, and then flie up on high that they may ſee afar off, chuſing a Captain whom they are to follow. They have their Serjeants to take care of their ranks, and keep their nightly Watches by turns. *Plutarch* tells us, that the Crane, which is appointed to ſtand Sentinel for all the reſt, holds a ſtone in her foot, to the end, that if ſhe chance to give way to Nature and ſleep, ſhe may be awaked by the noiſe of the falling ſtone. The Leader, lifting up his head, and ſtretching out his long neck, looks about him far and wide, and gives warning to the reſt, of any danger that may befal them. The ſtrongeſt lead the way, that they may the better with the flapping of their wings break the force of the Air, and this they do by turns. And that they may the eaſilier prevail againſt the force and oppoſition of the Winds, they diſpoſe their company into a Wedge in the form of the Greek letter Δ, or a triangle; and being skilful in the Stars, they fore-ſee when tempeſts are coming, and fly down to the ground to keep themſelves from the injury of the approaching ſtorm.

The Sentinel Crane.

Of Geeſe.

The care of Geeſe that their gagling do them no harm.

THe Geeſe of *Sicily* do with great warineſs take care, that by their keeking and their noiſe, they do not expoſe themſelves to the rapacity of Birds of prey: for *Plutarch* ſaith, that when they are to fly over the hill *Taurus*, for fear of the Eagles that are there, they hold ſtones in their mouths to keep themſelves from gagling, until that they come unto a place where they may be ſecure.

Of Dragons.

The craft of Dragons fighting againſt the Elephant.

NEither are the Dragons leſs crafty; for thus do they overcome thoſe vaſt and otherwiſe invincible Beaſts the Elephants. They lie in ambuſh, and ſuddenly ſet upon the Elephants when they fear no ſuch matter, and involve their legs with the twines of their tail, in ſuch ſort, that they are not able to go forward, and ſtop their noſtrils with their heads, ſo that they cannot fetch their breath; they pull out their eyes, and whereſoever they find the skin moſt tender there they bite and ſuck the bloud until they make them fall down dead. *Pliny* ſaith, that there are Dragons found in *Æthiopia* of ten cubits long, but that in *India* there are Dragons of an hundred foot long, that fly ſo high that they fetch Birds, and take their prey even from the midſt of the Clouds.

Lib.8. c.11,12.

Of the Fiſh called the Fiſherman.

The craft of the Fiſherman-fiſh in taking her prey.

THis fiſh is called the Fiſherman, becauſe he hunts and takes other Fiſhes, which he doth almoſt by the ſame cunning which the Cuttel uſes; for he hath hanging at his throat a certain bag, like the Wattels of a Turkey-Cock, This when he liſteth he caſteth out, and layeth before the little Fiſhes for a bait, and then by little and little draws it up again, until he catch for food the little Fiſhes ſeiſing upon it as a prey.

Of

Of the Cuttel Fiſh.

WOnderful is the craft of the Cuttel-fiſhes, for they carry a bladder at their neck full of a black Juice or Ink, which they pour forth as ſoon as they feel themſelves taken, that ſo they may blind the eyes of the Fiſhermen, as *Plutarch* ſaith, and as *Ariſtotle* witneſſeth, they with their long fangs do not onely hunt and take little Fiſhes, but oftentimes alſo Mullets. The craft of the Cuttel to ſave her ſelf. *Lib.9. de Hiſt. Animal.c.37.*

Of the Arms or Weapons of brute Beaſts.

BRute Beaſts are naturally ſo furniſhed with Arms that they have no need to get, make, or borrow in any other place.

And ſome of them nevertheleſs are ſo furniſhed with ſuch Arms, that they captivate thoſe which hold them Priſoners; an example of this is the *Torpedo*, which doth not onely hurt by touch, but alſo by the Net being between, he breaths ſuch a quality from him as ſtupifies the hands of the Fiſhermen, ſo that they are forced to let go their Nets, and ſo let him go; moreover if it touch a Ship it makes it ſtay. *Thevet* writes, that the *Perſian* Bay towards *Arabia*, nouriſhes a Fiſh equal in length and thickneſs to a Carp, on every ſide encompaſſed with ſharp and ſtrong pricks, like our Porcupine, with which he fights againſt all kinds of Fiſh. If a man chance but to be lightly hurt either with theſe, or his teeth, he will die within 24 hours. *Coſmogr. tom.1. lib.10.c.10.*

Of the Fiſh Utelif.

HE ſaith moreover, that as he was carried by force of tempeſt through the Atlantick Ocean, he ſaw this Fiſh, having (as it were) a Saw in his forehead of three foot long, and four fingers broad, armed on each ſide with ſharp ſpikes; they call it *Utelif* in their Countrey ſpeech.

Of the Fiſh Caſpilly.

THere is another Fiſh to be ſeen in the *Arabian* Gulf which the *Arabians* call *Caſpilly*; it is two foot long, and many broad; it hath a skin not much unlike a Dog-fiſh, but armed with ſpikes; one whereof he carries in his forehead a foot and half broad; in ſharpneſs and force of cutting not much ſhort of a graver or chiſſel: with this weapon, when ſhe is oppreſt with hunger, ſhe aſſails the firſt Fiſh ſhe meets, neither doth ſhe give over before ſhe carry her as a prey whither ſhe pleaſe, as *Thevet* ſaith he hath ſeen. *Tom.1. lib.5. cap.2.*

Of Crabs.

CRabs and Lobſters, though in the quantity of their body they be but ſmall, yet they uſe their forked Claws before, not onely in feeding, but alſo in defending themſelves, and aſſailing others.

Of the docility of Beaſts, and firſt of the Dog.

BEaſts are apt to learn thoſe things which men deſire, whereby they ſhew themſelves not wholly void of reaſon. For Dogs, Apes, and Horſes, learn to creep through the Juglers Hoops, and riſe on their hinder feet, as though they would dance. *Plutarch* tells that a Jugler had a Dog which would repreſent many things upon the Stage befitting the occaſion and argument of the Play; amongſt the reſt, he exceeded all admiration in that, that taking a ſoporifick Medicin, he excellently feigned himſelf dead; for firſt, as taken with a giddineſs in his head he begun to tremble, then preſently fell down, and lying on the ground, as it were contracted his dying members, and laſtly, as if truly dead he waxed ſtiff; and moreover ſuffered himſelf diverſly to be fitted according to divers parts of the Theatre, the Fable ſo requiring. But when he, by thoſe things that were ſaid and done, knew it was time to riſe, he firſt begun to move his Legs by little and little, as if he had been wakened from a ſound ſleep; then preſently with his head a little lifted up, he looked this way and that way, to the great admiration of all the beholders; and finally roſe up, and went familiarly and chearfully to him he ſhould. Than which ſight the Emperour *Veſpaſian* (who was then preſent in *Marcellus* his Theatre) never ſaw any which more delighted him. The wonderful docility of Dogs. A ſpectacle full of admiration and truth.

Of the Ape.

AN Ape is a ridiculous Creature, and which makes men much ſport in imitating their actions. There hath been ſeen an Ape which would pipe and ſing, and beſides, dance and write, and endeavour to perform many other things proper to men. I remember I ſaw in the Duke of *Somes* houſe a great and curſt Ape, who becauſe he much troubled many, had his hands cut off, who ſuffering himſelf to be cured, when the wound was cicatrized, he grew more mild and docile. Wherefore cloathed in a green Coat, and girt over his loins with a Girdle, he carried hanging thereat a Caſe of Spectacles, a pair of Knives, and a Childs Handkerchief. He was committed to the charge of the Maſter-Cook to teach, becauſe he had taken up his lodging in the Chimney-corner, he was taught many tricks and feats. If at any time he ſwerved from his doctrin and precepts, in a trice the whip was upon his back and loins, and much was abated of his daily allowance; for, as *Perſius* ſaith, The belly is the Maſter of Arts, and Sharpner of Wit. By theſe means he profited ſo in a ſhort time, that he much exceeded all the Apes of his time in the glory of his Wit; and there was none counted more skilful in leaping and dancing to the Pipe, running up a Pole, and nimbly leaping through his Maſters Legs. To conclude, he performed all the actions of a ſtrong Ape, and very reverendly carried up Diſhes with the Waiters and Servingmen, and made clean the Diſhes and Platters by licking, and did much other drudgery, ſo that he was commonly called Maſter *John Do-all*. At Dinner and Supper ſitting in a Chair, he ſaid Grace, and caſting his eyes up towards Heaven, and rouled them this way and that way, and ſmote his Breſt with the ſtumps of his hands with much lamentation, and imitated Prayer by the gnaſhing or beating together of his teeth. He would turn up his tail to any *Gal. lib.1. de uſu partium.*

that

that offended him, for his Coat ſcarce covered half his buttock, leſt he ſhould have defiled it) he made much other paſtime, always going upright by reaſon of the cutting away of his hands, unleſs at any time through wearineſs he were forced to ſit on his Buttocks.

Of the Camel.

Camels both tame and wild

THe *Camel* is a very domeſtical and gentle Beaſt, and which is eaſily tamed and taught all kind of obedience and ſervice; although ſome of them are cruel, wild, and troubleſom by biting and ſtriking ſuch as they meet, no leſs then untamed Horſes. There is no need to houſe them

The eaſie and not chargeable keeping of Camels.

in the night, for they may be left in the plain fields in the open and free air, feeding upon the Graſs and Trees, and cropping the tops of Thiſtles, neither in the morning do they any whit the worſe undergo or carry their burdens. They are not put to carry burdens before they be four years old. The *Arabians* geld them young, that they may enjoy their labour the longer; neither being

gelt,

gelt, do they rage for Love or deſire of Venery. At the putting in of the Spring they endure hunger and thirſt for eight days together; they are ſo dutiful, that at the beck of the Turkiſh Slaves, or but touched on the neck with a Twig, they preſently kneel on the ground to take up their burden, neither do they lift themſelves up before they find that they have a ſufficient load laid upon them. Thoſe that have but one bunch upon their back are of *Africk*, but ſuch as have two bunches are of *Aſia* or *Scythia*. Thoſe kind of Camels that are the bigger, are uſed to carry packs, but the leſſer are uſed to ride upon, as our Horſes are. They love nothing ſo well as Beans, and yet they live content with four handfuls of Beans for a day. The greateſt wealth of the *Arabians* conſiſts in Camels, and ſo they eſtimate their riches, not by the quantity of Silver or Gold, but by the number of Camels. The *Turkiſh* Emperour (*Thevet* being the reporter) made a Captain over the herds of his Camels, giving him a great troop of African and Chriſtian Slaves, that they might be the better looked unto. I have heard it reported (ſaith *Thevet*) by certain *Arabian*, *African*, and *Jewiſh* Merchants who were preſent, at that time when *Sultan Selim*, the firſt of that name, beſieged *Caire* in *Ægypt*, (which in former times was called *Memphis*) that there then was in that Emperours Army ſixty thouſand Camels, beſides a mighty company of Mules.

Camels know when they have a ſufficient load.

Camels both to carry burdens, and to ride upon.

A mighty troop of Camels.

Of ravenous Birds.

BUt let us take view of Falconers teaching ravenous Birds, how with ſwift wings carried aloft into the Air, they may ſeize upon other Birds, and caſt them down dead to the ground; in performance whereof, they often too freely ſoar up to the Clouds, ſo that they carry themſelves out of the Falconers ſight, with a deſire to Sun themſelves, neglecting in the mean time their deſigned prey.

The diligence of Falconers in training up their Hawks.

The Heron when ſhe ſees her ſelf kept under, and below the Falcon, carried up by his ſtrong wings with a marvellous ſwiftneſs, with her Beak, which is long and ſharp, hid under her wings, and turned upwards, ſhe receives the Falcon blinded with the heat of fight, and deſire of prey, careleſly flying down and ruſhing upon him; ſo that he often ſtrikes him through the gorge, ſo that oft-times they both fall down dead to the ground. But if the Falcon without harm eſcape the deceits by Art, and the happy turning of his body, and the Heron be not caſt down, the Faulconer calling her back with never ſo loud a voice, yet by ſetting up her Feathers ſhe dares her to the pretended fight.

The fight of the Heron and Falcon.

That Birds have taught us Muſical Tunes.

THe Nightingales are ſweet and excellent ſingers, tuning their notes with infinite quaverings, and diverſities of ſounds, ſo prettily and ſweetly, that humane induſtry can ſcarce equal the ſweetneſs thereof, by ſo many muſical Inſtruments; ſo that we ſay, he ſings like a Nightingale, who varies his voice with much variety. In which thing Birds much excel men, becauſe they have that admirable ſweetneſs of ſinging from Nature it ſelf without any labour of learning; which men can ſcarce attain to in any School of Muſick, by having their ears a thouſand times pluckt by the hands of a curſt Maſter.

To ſing like a Nightingale.

That Beaſts know one anothers voice.

BEaſts know one another by their voice, ſo that they may ſeem to talk and to laugh together, whileſt fluttering with their ears, they pluck in their noſes with a pleaſant aſpect of their eyes; and as ſpeech is given to men, ſo Birds have their natural voice, which is of the ſame uſe to them, as ſpeech is to us. For all Birds of the ſame Species, as men of the ſame Countrey, chant and chirp to one another, when men underſtand not the ſpeech of other men, unleſs of the ſame Nation. Wherefore the *Scythian* Tongue is no more profitable to one living in *Egypt*, than if he were dumb; nor the *Egyptians* underſtand it no more than if they were deaf. Wherefore an *Egyptian* is dumb and deaf to a *Scythian*. This thoſe which travel well underſtand, how many dangers, how many troubles they undergo becauſe they cannot expreſs their minds, and require things neceſſary for life. Wherefore to the aſſiſtance of this unprofitable Tongue, we are compelled to call the reſt of the Members, and to abuſe the geſtures of the Head, Eyes, Hands, and Feet. Truly the condition of brute Beaſts is not ſo miſerable, ſeeing that all of the ſame kind whereſoever they be, may anſwer each other with a known voice. Truly, if any ſhould hear a *German*, *Briton*, *Spaniard*, *Engliſhman*, *Polonian* and *Greek*, ſpeaking amongſt themſelves in their Native Tongues, not underſtanding any of them, he could ſcarce diſcern, and certainly judge, whether he heard the voice of Men or of Beaſts.

The Voice to Beaſts is of the ſame uſe, as Speech is to Men.

We are as ill as deaf, when we hear an unknown Language.

That Birds may counterfeit Mans voice.

LInets, Larks, Pies, Rooks, Daws, Crows, Stares, and other ſuch like Birds, ſpeak, ſing, whiſtle, and imitate the voices of Men and other Creatures. In this Parrats excel all other, being wondrous skilful imitaters of mens voices; and very merry, but ſpecially when they have drank a little Wine.

Parrats are wonderful imitaters of Mans voice.

Plutarch reports that there was a Barber at *Rome* who kept a Pie in his ſhop, which ſpoke exceeding well, and that of her own accord, none teaching her, when ſhe firſt heard men talking together; ſhe imitated the voice or cry of all Beaſts ſhe heard, as alſo the ſound of Drums, and the ſound of Pipes and Trumpets; to conclude, there was nothing which ſhe did not endeavour to imitate. There have been Crows that have ſpoken and articulately ſung Songs and Pſalms, and that of ſome length. To which purpoſe the Hiſtory of *Macrobius* is notable; for he tells that there was one amongſt thoſe who went forth for luck ſake to meet with *Auguſtus Cæſar*, returning from the War againſt *Antonius*, who carried a Crow which he had taught plainly to pronounce this ſalutation, *Salve Cæſar Imperator Auguſtiſſime*, that is, *God ſave thee, O moſt ſacred Emperour Cæſar.*

A talking Pie.

Lib. 2. Saturn. cap. 4.

Cæſar

Cæſar taken with the novelty of this ſpectacle, bought this obſequious Bird with a thouſand pieces of Silver. *Pliny* and *Valerius* have reckoned up amongſt prodigies, Oxen and Aſſes that have ſpoken. I omit infinite other things recorded by the Ancients, *Plato*, *Ariſtotle*, *Pliny*, *Plutarch*, and other Philoſophers of great credit, of the docility of Beaſts, and their admirable felicity of underſtanding. Which things, if untrue, theſe learned men would never have recorded in Writing, leſt ſo they might brand with vanity (than which nothing is more baſe) the reſt of their Writings to poſterity in all enſuing Ages.

Of the Sympathy and Antipathy of Living Creatures amongſt themſelves.

HAving briefly deſcribed the underſtanding of brute Beaſts, it ſeems not impertinent to ſet down ſome things more worthy of knowledge, happening unto them by reaſon of Sympathy and Antipathy; that is, mutual agreement and diſagreement, which happens not onely to them living, but alſo dead, by a certain hidden property, through occaſion whereof ſome deſire, others ſhun, and others proſecute one another even to death. In teſtimony whereof, the Lyon the King of Beaſts excelling all other in courage and magnanimity, fears the Cock, for he is not onely terrified by his preſence, but alſo by his crowing being abſent. So an Elephant fears an Hog; but he is ſo afraid of Mice and Rats, that he will not touch the meat that is given him, if he ſmell that it hath been defiled with ſuch Creatures. There is deadly hatred between the Elephant and Rhinocerot; yet when the Elephant is furious and angry, he becomes quiet and calm at the ſight of a Ram. A Horſe is ſo afraid of a Camel, that he cannot endure his ſight. The Dog hates the Wolf, the Hart flies the Dog. The Snake flies from and fears a naked man, and follows him being clothed. There is deadly hatred between the Aſpis and Ichneumon; for he when he hath rouled himſelf in the clay, dries himſelf in the Sun, and ſo being covered over (by doing thus divers times) as it were with ſhells or armour, he enters into combat, ſtretching out his Tail, and preſenting his Back, until he get opportunity to choak his adverſary by leaping and faſtening on her Jaws, by which ſtratagem he alſo kills the Crocodile, The green Lizard is a capital enemy to the Serpent, but moſt friendly to Man, as *Eraſmus* witneſſeth by many Hiſtories concerning that matter, in his Dialogue of Sympathy and Antipathy. There is a great deal of hatred between a Man and a Wolf, which is moſt manifeſt by this, that if the Wolves firſt ſee a Man, his Voice is taken away, and his intended cry hindered. If the Weaſel intend to ſet upon the Aſpis that moſt venemous Serpent, ſhe arms her ſelf by eating Rue, as a moſt certain Antidote. The Ape fears the Torpedo, as *Eraſmus* manifeſts by a pleaſant Hiſtory in the forementioned Dialogue; where alſo he pretily ſhews the deadly hatred between the Serpent called Areus and the Toad. The like hate is between the Owl and Crows, ſo that the Owl dares not go out, fly abroad, or ſeek her food unleſs by night. The Water or River Fowl are afraid of the Falcon, that if they but hear her bells, they had rather be killed with ſtaves and ſtones, then take wing to flie into the air. So the Lark yields her ſelf to be taken by a Man, leſt ſhe fall into the Talons of the Hobby. The Caſtril, or Merlin, is naturally a terrour to Hawks, ſo that they both ſhun his voice and preſence.

The Lion fears a Cock.

A Horſe fears a Camel.

What Fowl fear the Falcon.

The Kites are all at perpetual enmity with the Crows, wherefore the Crow always gets away the Kites proviſion. All kind of Pullen fear the Fox. The Chicken fears neither a Horſe nor an Elephant; but, ſcarce hatched, it preſently runs away at the voice or ſight of a Kite, and hides it ſelf under the Hens Wings. The Lamb and Kid flie from the Wolf when they firſt ſee him, neither doth Death give an end to that hatred, but it ſupervives their Funeral. An experiment whereof (they ſay) is, that if one Drum be headed with Wolves skins and another with Sheeps, and beaten up together, you ſhall ſcarce hear the ſound of the Drum covered with Sheep skins. And beſides, if you ſtring one Harp with Strings made of Sheeps guts, and another with Strings of Wolves guts, you cannot bring it to paſs by any Art, to make them agree and go in one Tune. It is reported from the experiments of many men, that if a Wolves head be hanged up on high in the place where Sheep are, that they will not touch the Graſs, how good and freſh ſoever it be, nor reſt quiet in any place, but tumultuouſly run up and down, until all ſuch kind of terrour be taken away. The hate betwixt Mice and Weaſels appears by this, that if you mix never ſo little of the brains of a Weaſel in the Rennet, with which you crudle your Cheeſe, the Mice will never gnaw or touch that Cheeſe. The Linnet doth ſo hate the Bird *Florus*, that both their blouds put into one veſſel cannot be mixed together. A Wolves head hung up in a Dove-houſe, drives away Poll-Cats and Weaſels. The Panther and Hyæna burn with ſo great hatred, that if both their skins be laid one againſt the other, the Panthers will ſhed the hair, the hairs of the Hyæna remaining entire and not moved; which thing, they ſay, happens to the Feathers of other Birds, if any one chance to tie them up in a bundle with the Eagles. Let theſe ſuffice for ſome few examples of many, of the Antipathy amongſt Beaſts. But of the Sympathy and conſent of Beaſts amongſt themſelves, I think needleſs to write any thing, being it is ſufficiently known to all, that one Jay aſſociates another, and the cruel Bears agree amongſt themſelves; and Beaſts of ſame ſpecies do wonderfully conſent one with another.

The Enmity between the Kites and Crows.

The diſcord between the Lamb and Wolf is not ended by Death.

How to make Cheeſe that Mice will not gnaw.

That Man excells all Beaſts.

I Now think it fit to aſſay to write of that excellency of Man over Beaſts, which I have ſo long intended. Neither would I that Epicures, and other, too much natural and materiate Philoſophers, ſo take thoſe things I have written of the endowments of Beaſts, as though we ſhould think there were no difference between Man and Beaſt. I had no ſuch meaning, no ſuch intention; but onely that man ſhould not become too ſtately, or too ingrate in leſs acknowledging God to be the Author of ſo many benefits with which he abounds. For whatſoever we have largely ſpoken of Beaſts, yet there is no compariſon between Beaſts and Man; for there is too great a difference between them. For Mans mind is adorned with Religion, Juſtice, Prudence, Magnanimity, Faith, Piety, Modeſty, Clemency, Fortitude, and other Vertues as Lights which ſhine much more bright in Man than

than Beasts. For they are sometimes all in some one Man, each whereof are thought great in Beasts. For seeing that Man is made to the Image of God, it cannot be, how much soever he defile himself with the pollution of Vices, that he can so obscure that inbred light, but that always some beam of the Divine Wisdom will be inherent and shine in him. But although by collation to some Beasts, he may seem a defective and weak Creature; yet no fortitude nor strength of Beasts can be so great as to equal the fortitude of Man. For God hath engraven in Man the Character of his Divine Virtue, by the assistance whereof, he might have all Beasts under and obedient to him. And though by that we have formerly said, Beasts may seem to have a certain shadow of reason, yet that small light is not fit for many and divers uses, but there is onely given them so much providence as should be sufficient for them and the preservation of their bodies. But men have Reason given them to crop or gather the Fruits of Eternal Life, (as *Lactantius* saith) whereby it comes to pass, that Man onely, amongst so many Creatures, hath sense and understanding of Divine things. Which *Cicero* thought to be known by that, because Man onely had a certain knowledge of God in his mind. Wherefore he was enriched by God with Reason, Speech, and Hands, as helps for the performance of all his Actions; moreover by his singular and almost divine Wit he easily excells all brute Beasts. For first, Reason being his guide, he invented things necessary for life, fitly imposed names on the things invented befitting their Natures, framed Letters and Characters, invented all Liberal Arts and Handy-crafts, and found means to measure the Land and Sea. He hath observed and drawn into an Art the spaces of the Celestial Globe, the distinctions of the Stars; the changes and orders of Days and Nights, of Times and Seasons; the rising and setting of Stars, and their power and effects over these lower Bodies. Lastly, He records in writing to perpetual memory that which concerns his own Nature, or the Nature of other things, the Precepts and Ordinances of Life and Manners; by which singular gift, we can now confer with *Socrates*, *Plato*, *Aristotle*, and other Philosophers of ancient Times, as if they were living.

Man bears Gods Image.

Man hath given names to things.

What benefit Man hath by reason of his native Nakedness and Ignorance.

But as Mans Body is by Nature naked and unarmed, so is his Mind like a smooth Table in which nothing is painted, nothing graven; but for help of his Nakedness he hath Hands, and for supply of his Ignorance, Reason and Speech. And by these three being, as it were, the Ministers of infinite variety of things, he clothes and defends his Body with all things needful, and enriches his Mind with the knowledge of Arts and Sciences. Now if he had certain Weapons born with him, he should use them onely; if he should be born skilful in any Art, he would meddle with none else. Therefore, because it was more expedient to use all sorts of Weapons with the Hand, and be skilful in all Arts; therefore he must be born wanting and ignorant of all. *Aristotle* very wittily called the Hand the Instrument of Instruments; in imitation of which speech, one may rightly affirm, that Reason is the Art of Arts: for as the Hand in worth exceeds the other Instruments, because it can make, handle, and fit them for use; so Reason and Speech, though names of no Art, yet comprehend and encrease all Arts. Therefore Man, seeing he hath his Mind instructed by Art, that is, by Reason, it is fit he should have his Body defended with a Weapon or Instrument, that is, the Hand; which in agility and excellency should excel all other Instruments. For so Man hath his Hands in stead of all Weapons, which he may use in War and Peace, as the Instruments of all Arts; he wants not the Bulls Horns, the Boars Tusks, the Horses Hoofs, nor, to conclude, any Arms of any other Beast. For by the benefit of his Hands he can handle other Arms far more profitable and safe; as a Lance, Sword, Spear, Halberd; but Man also can use at some distance the Bow, Sling, and Hand-gun, when the Horn and the Hoof cannot be used but near at hand. But some may say, a Lion exceeds a Man in swiftness of Foot; what then? is Man therefore inferiour to him? no, for by the means of his Hands, and the guidance of his Reason he bridling and riding upon a Horse, out-runs the Lion, and being Victor follows him to and again as he himself pleases, or vanquished flies away; and from the Horses back, as from a Tower, wounds the Lion with what Weapons he pleases. To conclude, Man is abundantly provided with means to defend himself from the violence of all other Beasts. For this purpose he doth not onely harness himself as with brazen Walls, but also makes Ditches and Bulwarks, he makes by the ministry of his Hands all kind of Weapons, weaves himself Garments, casts into the Water and draws forth Nets to catch Fish; and to conclude, he performs all things to his own contentment, and having that priviledge granted him by God, he rules over all the Earth; all things which lie hid in the bowels of the Earth, which go, or creep upon the Earth, which swim in the Sea, and flie through the Air, or are any where shut up in the compass of the Skie, are in Mans dominion.

Gal. cap. 4. lib. 1. de usu partium.

As the Hand is the Instrument of Instruments, so Reason is the Art of Arts.

Man under God is the King and Emperour of the World.

How wonderful God hath shewed himself in making Man.

Gods Deity and Providence hath principally shewed it self in the Creation of Man; neither his so admired Light hath so shone in the production of other Creatures, seeing that God would have them to live and have their being onely for Mans sake, that they might serve him. Therefore Man is, if we diligently consider all his endowments, a certain Pattern and Rule of the Divine Majesty and (if I may so say) Artifice. For being made to Gods Image, he is as it were his Coin, exceeding the capacity of all humane understanding. Which seemed a just reason to the ancient Philosophers that he should be called *Microcosmos*, or a little World, because the particles of all things contained in the compass of Heaven and Earth, are contained in his Mind and Body, that in the mean time I may in silence pass over his Soul, more great and noble than the whole World.

Man is the end of all Mundane things.

Man a little World, yea almost a great World.

Why

Why Nature hath not given Man the faculty of Presaging.

Man is not obnoxious to the Air and Stars.

THis seems the reason, that Men by the instinct of Nature do not foresee the future seasons and dispositions of the Heaven and Air; because, seeing they have received certain sparks of prudence from God, by whose care and guidance they are led to the knowledge of things by no deceitful but certain judgment, being not obnoxious to the conditions and changes of Times and Seasons, as Beasts are: Wherefore knowing all these airy changes to be placed under them, that is to say, their minds; according as occasion serves and their minds desire, they give themselves to mirth when the air is wet, stormy, and dark; and on the contrary in a clear and fair season, to a serene and grave meditation of things sublime and full of doubt. But Beasts accommodating themselves to that disposition of the Air which is present and at hand, are lively or sad, not from any judgment, as Men, but according to the temper and complexion of their bodies following the inclinations of the Air, and of the humours one while diffused, another while contracted. Neither ought we to

One Man will counterfeit the voices of infinite varieties of Beasts.

blame Man, because he can imitate the voice of Beasts, but rather much commend him, that he can infinitely wrest and vary one thing, that is, his Voice; for Men can bark like Foxes and Dogs; grunt like Hogs, whet and grind their teeth like Boars, roar like Lions, bellow like Bulls, neigh like Horses, knack their teeth like Apes, howl like Wolves, bray like Asses, bleat like Goats and Sheep, mourn like Bears, Pigeons, and Turtles, keek and gaggle like Geese, hiss like Serpents, cry like Storks, caw like a Crow, and crow like a Cock, clock like Hens, chatter as Swallows and Pies, sing like Nightingales, croak like Frogs, imitate the singing of Wasps and humming of

The power of Musick.

Bees, mew like Cats. The singing of Birds scarce seems to merit the name of Musical, compared to the Harmony of Men, fitted and tuned with infinite variety of Voices. For with this they possess the Ears of Kings and Princes, provoke and temper their wrath, and carry mens minds beyond themselves, and transform them into what habits they please. But if those cruel Beasts have any humanity, they owe it all to Man: For he tames Lions, Elephants, Bears, Tigers, Leopards, Panthers, and such other like.

That Man may attain unto the knowledge of all Voices and Tongues.

THe docility of Mans Wit is so great, and facility of the body obeying that divine gift of Wit, such, that he is not onely able to learn to speak the Tongues of divers Nations differing in so

Man not onely the imitater, but the interpreter of the Voices of Beasts and Birds.

many peculiar Languages; and not onely to imitate and counterfeit the voices of all Beasts though so much different from Man, which many flattering and jugling Companions, followers of other mens Tables will do; but also be able to know and understand both what they pretend and signifie. In confirmation of which thing, they cite the Philosopher *Apollonius* most famous in this kind of Study and Knowledge, He walking on a time amongst a company of his Friends through the Field, and seeing a Sparrow come flying and chirping much to divers other Sparrows sitting upon a Tree, is reported to have said to those which were with him, That Bird which came flying hither, told the other in her Language, that an Ass laded with Corn was fallen down at the City Gate, and had shed the Wheat upon the ground. Wherefore *Apollonius*, and all his friends which were with him went thither to see whether it were so, and found that it was so as he had told them, and observed that the Sparrows, moved thereto by the coming of the other, were eating up the grains of Corn shed on the ground.

But for Crows and Pies artificially taught to counterfeit mens Voices, it is too small a thing, that for that cause they should contend with men. For they have quickly babled all they have learnt with longer cost and labour, tediously singing still the same song, and whatsoever they prate they do it without Sense, Understanding, or any Reason for what they say. But Man always contemplating somewhat more high, still thinks of greater things than these present, and never rests. But

The unquenchable desire of Learning in Man.

burning with an infinite and endless desire of Knowledge, he doth not onely covet to know those things which appertain to food and cloathing, but by casting his eyes towards Heaven, and by the light of his mind, he learns and understands things Divine. Which is so certain an Argument of the celestial original of our Soul, that he which considers those things, can no ways doubt, but that we have our minds seasoned by the universal Divine Understanding. But now it is time for us to set upon the Description of the Body, the habitation and fit Instrument of all the Functions of the Divine Mind.

Of the Crocodile.

A tame Crocodile.

PLutarch reports of the Crocodile (whose Figure is here delineated) that being tamed, and taught by Man, he doth not onely hear Mans Voice, and answers to his call, but suffers himself to be handled, and opening his throat, lets his teeth be scratched and wiped with a Towel. How small a part of Physick is that which Beasts are taught by Nature? Certainly nothing in comparison of Man, who by the study and practice of a few years, can learn at his fingers ends all the parts of Physick; and practise them not onely for his own, but also for the common good of all men. But why cannot Beasts attain unto the knowledge of Physick so well as Men? I think, because so great Art as Physick is, cannot be attained unto by the dull capacities of Beasts.

But



But for that I have written of the Religion of Elephants, if I muſt ſpeak according to the truth of the matter, we cannot ſay, they worſhip God, or have any ſenſe of the Divine Majeſty. For how can they have any knowledg of ſublime things, or of God, ſeeing they wholly following their food, know not how to meditate on celeſtial things? Now for that they behold and turn themſelves to the Moon by night, and to the Sun in the morning, they do not that as worſhipping, or for that they conceive any excellency or divinity in the Sun; but becauſe Nature ſo requiring and leading them, they feel their bodies to rejoyce in that light, and their entrails and humors to move and ſtir them to it. Therefore when we attributed Religion to Elephants, we ſaid it rather popularly, than truly, and more that we might exhort men to the Worſhip of God, than that we thought Elephants had any knowledge of Divine Worſhip implanted in their minds.

In what ſenſe we ſaid, Elephants had Religion.

The end of the Second Book.

BOOK III.

Of the Anatomy of Mans Body.

IFollowing the cuſtom and the manner of ſuch as before me have written of Anatomy, will firſt, (that I may make the minds of the Readers more attentive and deſirous of theſe ſtudies) declare how neceſſary it is, and alſo how profitable; and then ſhew the order to be obſerved in it, before I come to the particular deſcription of mans body.

The neceſſity of the knowledg of Anatomy.

Furthermore, how Anatomy may be defined, and the manner of the definition of the parts. For the firſt, the knowledg of Anatomy ſeems in my judgment very neceſſary to thoſe that deſire to excel, or attain to perfection of Phyſick; that is, whereby they may be able to preſerve the preſent health of the body, and the parts thereof, and drive away diſeaſes. For how can either Phyſician or Chirurgeon preſerve health by the uſe of the like things, which conſiſts in the temperament, conformation and natural union of the parts; or expel the diſeaſe which hurts thoſe three, by the like uſe of their contraries, unleſs he ſhall know the nature and compoſure of the body, and underſtand, as by the rule of this knowledg, how much it ſwerves from the nature thereof? Wherefore it is excellently ſaid of *Hippocrates*, that the Phyſician, called to cure the ſick Patient, ought diligently to conſider, whether thoſe things that are in him, or appear to be in him, be like or unlike, that is, whether the Patient be like himſelf and his own nature in all his parts and functions, temperature, compoſure and union; that he may preſerve thoſe which are yet contained in the bounds of nature, and reſtore thoſe that are gone aſtray. Which thing *Galen* hath alſo confirmed, ſpecially where he ſaith, He muſt well know the nature and ſtructure, or compoſure of the bones, who takes upon him to reſtore them broken or diſlocated to themſelves and their proper ſeats or places. Moreover, ſeeing that healing doth not only conſiſt in the knowledg of the diſeaſe, but as well in preſcribing fit medicines, and like application of them to the body and the parts thereof, all which by their natural diſſimilitude, do require unlike medicines, according to *Galens* opinion: I prethee tell me, Who can perform this, which is ignorant of the deſcription of the whole and the parts thereof, taught by Anatomy? We may ſay the like of the Apothecary, who ignorant of the ſituation of the parts in the body cannot apply Emplaiſters, Ointments, Cataplaſms, Fomentations, Epithemes, bags to the fit places, as to the ſutures of the skull, to the Heart, Liver, Stomach, Spleen, Reins, Womb, or Bladder. For example: Let us imagine the Liver to be troubled with a hot diſtemperature, but on the contrary, the ſtomach with a cold (which commonly happens, ſeeing the Liver hotter than ought to be, ſends up many vapours to the head; from whence cold humours fall into the ſtomach) if hot things to be applied to the ſtomach by the Phyſicians preſcription, be by the Apothecary, making no difference, applied, to both the ſtomach and neighbouring liver, (which may chance, if he be ignorant, that the ſtomach bends ſomewhat to the left ſide under the breaſt-blade; but the liver ſo takes up the right ſide of the body, that with a great part thereof, it covers almoſt all the ſtomach) will he not be much offend by increaſing the hot diſtemper of the liver, and not thereby giving eaſe, or help to the diſeaſe? Shall not, by this his ignorance, the Patient be fruſtrated of his deſire, the Phyſician of his intent, and the Medicine of its effect? By theſe examples I think it moſt manifeſt, that the Anatomical knowledg of the parts of the body is exceeding neceſſary to all Phyſicians, Chirurgeons, and Apothecaries, who will practiſe Phyſick with any praiſe, to the glory of God, and the benefit and good of man, for whoſe ſake we have writ theſe things, and illuſtrated them by figures, ſubjecting the parts to the eye, and fitly put them in their proper places.

Initio lib. de Offic. Medici.

Lib. de oſſibus.

1. de loc. affectis, & lib. 3. Meth.

Why, when the liver is hot the ſtomach is commonly cold.

The knowledg of Anatomy, is commodious four manner of ways.

But Anatomy is commodious four manner of ways: The firſt is, becauſe thus we are led to the knowledg of God the Creator, as by the effect to the cauſe; for, as we read in St. *Paul*, The inviſible things of God are made manifeſt by the viſible. The ſecond is, that by means hereof we know the nature of mans body, and the parts thereof, whereby we may more eaſily and certainly judge and determine of ſickneſs and health. The third is, that by the knowledg of the body and its parts, and together therewith it affections and diſeaſes, we may prognoſticate what is to come, and foretel the events of diſeaſes. Laſtly, the fourth is, that, conſidering the nature of the diſeaſed part, we may fitly preſcribe medicines, and apply them in their due place.

There is a threefold method.

Now we muſt declare in what order Anatomy may be fitly delivered; but firſt we muſt obſerve, there is a threefold method: The firſt is called of Compoſition, being very commodious for the teaching of Arts, which *Ariſtotle* hath uſed in his Works of Logick, and natural Philoſophy, the order and beginning taken from the leaſt and moſt ſimple, to the more compound. The ſecond of Diviſion, fit for the inventing or finding out of Sciences. *Galen* hath followed this order in his Books of Anatomical Adminiſtrations, and of the uſe of the parts. The third of Definition, which ſheweth the nature and eſſence of things, as appears by *Galen* in his Book *de Arte Parva*. And becauſe this order doth alſo proſecute the diviſions, therefore it is commonly accuſtomed to be comprehended in the compaſs of the ſecond. Therefore I will follow this in my Anatomical Treatiſe, dividing mans body into its parts, which I will not only ſubject to the eye in the way of knowing them, but alſo to the mind in the faithful underſtanding them. For, I will adjoyn thoſe things that are delivered of them by *Galen* in his Book of Anatomy-Adminiſtrations, with thoſe which he hath taught in his Books of the uſe of the parts. For there he fitly lays the parts of mans body before our eyes, to the ſenſe. But here he teaches to know them, not to ſee them; for he ſhews why, and for what uſe, they are made, Having briefly handled theſe things,

The Authors intent.

we

we muſt declare what Anatomy is; that, as *Cicero* ſaith out of *Plato*'s *Phædro*, it may be underſtood of what we diſpute. And becauſe we attain that by definition (which is a ſhort and plain ſpeech, conſiſting of the *Genus* and Difference of the things defined, being the eſſential parts, by which the nature and eſſence of the thing is briefly and plainly explained) firſt we define Anatomy, then preſently explain the particular parts of the definition.

What Anatomy is.

Wherefore Anatomy (if you have regard to the name) is a perfect and abſolute diviſion, or artificial reſolution of mans body into its parts, as well general as particular, as well compound as ſimple. Neither may this definition ſeem illegitimate; ſpecially amongſt Phyſicians and Chirurgeons. For, ſeeing they are Artizans humiliated to the ſenſe, they may uſe the proper and common qualities of things for their eſſential differences and forms. As on the contrary, Philoſophers may refuſe all definitions as ſpurious, which conſiſt not of the next *Genus*, and the moſt proper, and eſſential differences. But ſeeing that, through the imbecillity of our underſtanding, ſuch differences are unknown to us, in their places we are compelled, in defining things, to draw into one many common and proper accidents, to finiſh that definition which we intend: which for that cauſe we may more truly call a deſcription, becauſe for the matter and eſſential form of the thing, it preſents us only the matter adorned with certain accidents. This appears by the former definition, in which *Diviſion* and *Reſolution* ſtand for the *Genus*, becauſe they may be parted into divers others, as it were into *ſpecies*. That which is added over and beſides, ſtands in place of the difference, becauſe they ſeparate and make different the thing it ſelf from all other rath and unartificial diſſections. We muſt know, an artificial diviſion, is no other than a ſeparation of one part from another, without the hurt of the other, obſerving the proper circumſpection of each of them; which if they periſh or be defaced by the diviſion, it cannot be ſaid to be artificial. And thus much may ſuffice for the parts of the definition in general.

How a definition differs from a deſcription.

For as much as belongs to the explication of each word; we ſaid, *of Mans body*, becauſe as much as lies in us, we take care of, preſerve the health, and depel the diſeaſes thereof: By which it may appear that mans body is the ſubject of Phyſick, not as it is mans, or conſiſts of matter and form, but as it is partaker of health and ſickneſs.

The ſubject of Phyſick.

We underſtand nothing elſe by part, according to *Galen*, than ſome certain body, which is not wholly disjoyned, nor wholly united with other bodies of their kinds; but ſo, that, according to his opinion, the whole be compoſed therewith, with which in ſome ſort it is united, and in ſome kind ſeparated from the ſame, by their proper circumſcription. Furthermore by the *parts in general*, I underſtand the head, breaſt, belly, and their adjuncts. By the particular parts of thoſe, I underſtand, the ſimple parts, as the ſimilar, which are nine in number, as a griſtle, bone, ligament, membrane, tendon, nerve, vein, artery, muſculous fleſh; ſome add fibers, fat, marrow, the nails, and hairs; other omit them as excrements: But we muſt note that ſuch parts are called ſimple, rather in the judgment of the ſenſe, than of reaſon. For if any will more diligently conſider their nature, they ſhall find none abſolutely ſimple, becauſe they are nouriſhed, have life and ſenſe, either manifeſt or obſcure, which happens not without a nerve, vein, and artery.

Gal. lib. 1. *de uſu part.* lib. 1. Meth. 1

The ſimilar parts are nine.

But if any ſhall object, that no nerve is communicated to any bone, except the teeth; I will anſwer, that nevertheleſs the bones have ſenſe by the nervous fibers, which are communicated to them by the *Perioſteum*, as by whoſe mediation the *Perioſteum* is connext to the bones, as we ſee it happens to thoſe membranes, which involve the bowels. And the bones, by this benefit of the animal ſenſe, expel the noxious and excrementitious humors from themſelves into the ſpaces between them, and the *Perioſteum*, which, as indued with a more quick ſenſe, admoniſheth us, according to its office and duty, of that danger which is ready to ſeiſe upon the bones, unleſs it be prevented. Wherefore we will conclude according to the truth of the thing, that there is no part in our body ſimple, but only ſome are ſo named and thought, according to the ſenſe; although alſo otherwiſe ſome may be truly named Simple, as according to the peculiar and proper fleſh of each of their kinds. Thoſe parts are called Compound, which are made or compoſed by the mediation, or immediately of theſe ſimple, which they term otherwiſe organical, or inſtrumental; as an arm, leg, hand, foot, and others of this kind.

How the bones come to feel.

The compound or organical parts.

And here we muſt obſerve, that the parts are called ſimple and ſimilar, becauſe they cannot be divided into any particles but of the ſame kind; but the compound are called diſſimilar from the quite contrary reaſon. They are called inſtrumental and organical, becauſe they can perform ſuch actions of themſelves, as ſerve for the preſervation of themſelves and the whole; as the eye of it ſelf, without the aſſiſtance of any other part, ſeeth, and by this faculty defends the whole body, as alſo it ſelf. Wherefore it is called an inſtrument or organ, but not any part of it, as the coats, which cannot of it ſelf perform that act. Whereby we muſt underſtand, that in each inſtrumental part we muſt diligently obſerve four proper parts. One by which the action is properly performed, as the Cryſtalline himor in the eye. Another, without which the action cannot be performed, as the nerve and the other humors of the eye. The third, whereby the action is better and more conveniently done, as the tunicles and muſcles are. The fourth, by which the action is preſerved, as the eye-lids and circle of the eye. The ſame may be ſaid of the hand, which is the proper inſtrument of holding; for it performs this action, Firſt, by the muſcle, as the principal part; Secondly, by the ligament, as a part without which ſuch action cannot be performed; Thirdly, by the bones and nails, becauſe by the benefit of theſe parts, the action is more happily performed; Fourthly, by the veins, arteries and skin, for that by their benefit and uſe, the reſt, and ſo conſequently the action it ſelf is preſerved.

Four particles to be obſerved in each organical part.

But we muſt conſider, that the inſtrumental parts have a fourfold order. They are ſaid to be of the firſt order, which are firſt and immediately compoſed of the ſimple, as only the authors of ſome one action, of which kinds are the muſcles and veſſels. They are of a ſecond, which conſiſt of theſe firſt ſimple, and others beſides, as the fingers. They are counted of the third rank, which

Four ſorts of inſtrumental parts.

are compoſed of parts of the ſecond order, and ſome beſides, as the hand taken in general. The fourth order is the moſt compoſed, as the whole body, the organ and inſtrument of the Soul. But you muſt obſerve, that when we ſay, the muſcles and veſſels are ſimple parts, we refer you to the ſenſe and ſight, and to the underſtanding comparatively to the parts which are more compound; but if any conſider their eſſence and conſtitution, he ſhall underſtand they are truly compound, as we ſaid before. Now it remains, that we underſtand, that in each part, whether ſimple or compound, nine things are to be conſidered; as, ſubſtance, quantity, or magnitude, figure, compoſition, number, connexion, (by which name, we alſo underſtand the original and inſertion) temperature, action and uſe; that by the conſideration of theſe things, every one may exerciſe the Art of Phyſick, in preſerving health, curing diſeaſes, or foreſeeing their events and ends.

Nine things to be conſidered in each part.

But alſo we muſt note, that of the organical parts, there be three, by whoſe power the body is governed; which for that cauſe they call regent and principal, becauſe they govern all the reſt; they are the Liver, Heart, and Brain. But they are called principal, not only, becauſe they are neceſſary for life, (for the ſtomach, wind-pipe, lungs, reins, bladder, and ſuch like parts perhaps are equally as neceſſary for life;) but becauſe from each of theſe three, ſome force, power and faculty, or alſo matter neceſſary for the whole body, flow over all the body, when no ſuch thing proceeds from the reſt of the parts. For from the Liver a matter fit for nouriſhment is diſtributed by the veins through all the body; from the Heart the vital force, diffuſed by the arteries, imparts life to the whole body; from the Brain by the nerves a power or faculty is carried through all the parts of the body, which gives them ſenſe and motion.

Why the three principal parts are ſo called.

Galen would have the Teſticles to be of this kind, not for the neceſſity of the individual, or peculiar body, but for the preſervation of the *Species* or kind. And moreover, in his Book *de Semine*, comparing the Teſticles with the Heart, he makes them the more noble by this reaſon, that by how much it is better to live well and happily, than ſimply and abſolutely to live, by ſo much the Teſticles are more excellent than the heart; becauſe with them we may live well and pleaſantly, but with this ſimply live; as we ſee by the example of Eunuchs, and ſuch as are gelt, by which the Teſticles ſeem rightly to be accounted amongſt the principal parts; for Nature ſeeing it deſired, that this its work ſhould be immortal, for the attaining of that immortality which it intends, frames thoſe parts, like as prudent founders of a City, who do not only procure to furniſh their City with many Inhabitants, ſo long as they are in building it, but alſo that it may remain in the ſame ſtate and condition for ever, or at leaſt for many ages. And yet notwithſtanding of ſo many Cities built in the firſt memory of man, there remains none, whoſe fame and ſtate, together with the Builders name, is not decayed and periſhed. But this humane work of nature, ſtands yet ſecure for theſe many thouſand of years, and ſhall endure hereafter; becauſe it hath found a way, by which every one may ſubſtitute another in his place before he depart. Hence it is, that all Creatures have members fit for generation, and pleaſures inſerted in thoſe members, by which they might be enticed to mutual embraces and copulations. But the mind, which hath dominion over thoſe members, hath an incredible deſire of propagating the iſſue; by which alſo brute Beaſts incited, deſire to propagate their kinds for ever. For ſeeing that Nature underſtands, all theſe her works conſidered particularly by themſelves, are frail and mortal, it hath done what it could to recompence that fatal neceſſity of dying, by a perpetual ſucceſſion of Individuals.

Lib. de arte medica.

The uſe and function of the parts ſerving for generation.

Hitherto we may ſeem to have abundantly ſhewed what neceſſity of knowledge in Anatomy belongs to all Artizans in Phyſick, and alſo what order is to be obſerved in the ſame; and laſtly, how it is defined, and the reaſon of the parts of the definition. Wherefore it remains that we proſecute what we have taken in hand; which is, that we ſhew and declare how to know all and every the parts of mans body, how many, and what they be, and to underſtand wherefore they be. For although the true knowledge of Anatomy may be perfected by the ſight of the eye, and touching and handling each part with the hand, yet nevertheleſs the labour of deſcribing Anatomy is not unprofitable. For by reading, ſuch as have often exerciſed themſelves in the diſſecting of mens bodies, may refreſh and help their memories; and ſuch as have not, may make plain and eaſie the way to the underſtanding of Diſſections.

CHAP. I.

The diviſion or partition of mans Body.

BY reaſon the partition of mans body can hardly be underſtood, if the diſtinction of the proper faculties of the ſoul be not underſtood, for whoſe cauſe the body enjoys that form (which we ſee) and diviſion into divers Inſtruments: Therefore I thought good in few words to touch that diſtinction of the faculties of the ſoul, for the better underſtanding of the partition of the body, which we intend. Wherefore the ſoul, the perfection of the body, and beginning of all its functions, is commonly diſtinguiſhed, and that in the firſt and general diviſion, into three faculties, which are, the Animal, Vital and Natural. But the Animal is divided into the principal, ſenſitive and motive: Again, the Principal is diſtinguiſhed into the imaginative, reaſonable and memorative: And the Senſitive into ſeeing, hearing, ſmelling, taſting, and touching: But the Motive into progreſſive and apprehenſive. And the Vital is divided into the dilative and contractive faculty of the heart and arteries, which we know or underſtand by the pulſifick faculty. But the Natural is parted into the nutritive, auctive, and generative faculties; which three perform their parts by the help and miniſtry of five other faculties, which are, the attractive, retentive, concoctive, aſſimilative and expulſive.

What the Soul is and with how many faculties it is endued.

After

After the self-same manner, the organ or instrument of the soul, to wit, man's body, at the first division is distinguished into three parts, which from their office they call Animal, Vital and Natural. These again, according to the sub-division of the subalternal faculties, are divided particularly into other parts; so that any one may know the organ of each faculty, by the property of the function. For, while other Anatomists divide man's body into four universal and chief parts, they distinguish from the three first, those which they call the Extremities; neither do they teach, to what rank of the three prime parts each Extremity should be reduced. From whence many difficulties happen in reading the writing of Anatomists; for shunning whereof, we will prosecute, as we have said, that distinction of man's body, which we have touched before.

All the parts mans body are distinguished into three.

Wherefore, as we said before, man's body is divided into three principal and general parts, Animal, Vital, and Natural. By the Animal parts, we understand, not only the parts pertaining to the head, which are bounded with the crown of the head, the collar-bones, and the first *Vertebra* of the breast, but also the extremities, because they are organs and instruments of the motive-faculty; *Hippocrates* seems to have confirmed the same; where he writes, Those who have a thick and great head, have also great bones, nerves, and limbs. And in another place he saith, those who have great heads, and, when they stoop, shew a long neck, such have all their parts large, but chiefly the Animal. Not for that *Hippocrates* would therefore have the head the beginning and cause of the magnitude and greatness of the bones and the rest of the members; but that he might shew the equality, and private care, or government of Nature, being most just and exact in the fabrick of man's body, as, if she hath well framed the head, it should not be unlike that she idly or carelesly neglected the other parts which are less seen. I thought good to dilate this passage, lest any might abuse that authority of *Hippocrates*, and gather from thence, that not only the bones, membranes, ligaments, grisles, and all the other animal parts, but also the veins and arteries depend on the head as the original. But if any observe this our distinction of the parts of the body, he will understand, we have a far other meaning.

What parts are here called Animal.

Lib. 6. Epid.

By the Vital parts, we understand only the heart, arteries, lungs, wind-pipe, and other particles annexed to these. But by the Natural, we would have all those parts understood which are contained in the whole compass of the *Peritonæum* or Rim of the body, and the processes of the *Erythroides*, the second coat of the Testicles. For as much as belongs to all the other parts, which we call Containing; they must be reckoned in the number of the Animal, which notwithstanding, we must thus divide into principal, sensitive, and motive; and again, each of these in the manner following: For first, the principal is divided into the Imaginative, which is the first and upper part of the brain, with its two ventricles, and other annexed particles, into the reasoning, which is a part of the brain, lying under the former, and (as it were the top thereof with its third ventricle; into the Memorative, which is the *cerebellum* or after-brain, with a ventricle hallowed in its substance. Secondly, The Sensitive is parted into the visive, which is in the eyes; the auditive in the ears; the smelling, in the nose; the tasting, in the tongue and palat; the active, or touching which is in the body, but most exquisite in the skin which invests the palms of the hands. Thirdly, the motive is divided into the Progressive, which intimates the legs; and the Comprehensive, which intimates the hands. Lastly, into simply-motive, which are three parts, called bellies, for the greatest part terminating and containing; for the Vital, the instrument of the faculty of the heart, and dilatation of the arteries, are the direct or streight fibers, but of the Constrictive the transverse; but the three kinds of fibers together, of the Pulsifick: Or, if you please, you may divide them into parts serving for Respiration, as are the lungs and weazon, and parts serving for vital motion, as are the heart and arteries, furnished with these fibers, which we formerly mentioned. The division of the natural parts remains, which is into the nourishing, active, and generative, which again, are distributed into attractive, universal and particular retentive, concoctive, distributive, assimilative, and expulsive. The attractive, as the gullet and upper orifice of the ventricle; the retentive, as the *Pylorus*, or lower passage of the stomach; the concoctive, as the body of the ventricle, or its inner coat; the distributive, as the three small guts; the expulsive, as the three great guts; we may say the same of the Liver; for that draws by the mesaraick and gate-veins, retains by the narrow orifices of the veins dispersed through the substance thereof; it concocts by its proper flesh; distributes by the hollow vein, expels by the spleen, bladder of the gall, and kidneys. We also see the parts in the Testicles divided into as many functions; for they draw by the preparing vessels; retain by the various crooked passages; in the same vessels they concoct the seed by the power of their proper substance and faculty; they distribute by the ejaculatory, at the glandules called *Prostatæ*, and the horns of the womb, supplying the place of prostates: Lastly, they expel or cast forth by the prostates, horns, and adjoyning parts. For as much as belongs to the particular attraction, retention, concoction, distribution, assimilation of each part, that depends of the particular temper, and, as they term it, occult property of each similar and simple part. Neither do these particular actions differ from the universal, but that the general are performed by the assistance of the three sorts of fibers; but the special, by the several occult property of their flesh, arising from their temperature, which we may call a specifick property. Now in the composition of man's body, Nature principally aims at three things. The first is, to create parts necessary for life, as are the heart, brain, and liver. The second, to bring forth other for the better and more commodious living, as the eyes, nose, ears, arms and hands. The third is, for the propagation and renewing the *species* or kind, as the privy parts, testicles and womb. And this is my opinion, of the true distinction of man's body, furnished with so many parts, for the performance of so many faculties; which you, if you please, may approve and follow. If not, you may follow the common and vulgar, which is, into three bellies or capacities, the upper, middle, lower, (that is, the head, breast, and lower belly) and the limbs or joints. In which, by the head we do not understand all the Animal parts, but only those which are from the crown

What parts are called Vital.

The division of the animal parts.

The division of the vital parts.

The division of the natural parts.

The vulgar division of mans body.

of the head to the first *vertebra* of the neck, or to the first of the back; if, according to the opinion of *Galen*, *Lib. de Ossibus*, where he makes mention of *Enarthrosis* and *Arthrodia*, we reckon the neck amongst the parts of the head. By the breast, whatsoever is contained from the collar bones to the ends of the true and bastard, or short ribs, and the midriff. By the lower belly, the rest of the trunk of the body, from the ends of the ribs to the share-bones; by the limbs, we understand the arms and legs. We will follow this division in this our Anatomical Discourse, because we cannot follow the former in dissecting the parts of mans body, by reason the Animal parts are mutually mixed with the Vital and Natural: And first of the lower belly.

The Figure shewing the fore-parts of the body.



A The hairy Scalp, call'd τετιχωτὸς.
b the forehead, call'd *Frons*, μέτωπον.
c The temples call'd *tempora*, κρόταφοι.
From *b* to *d*, the compass of the face.
e The greater or inward corner of the eys, call'd *Canthus internus.*
f the lesser or external angle of the eye, call'd *Canthus externus.*
* The lower eye-brow, which is immoveable, *Palpebra.*
g The cheek-ball call'd *mala*, μῆλα.
h the cheek-puff, call'd *bucca*, γιάθος.
i The ridg of the nose call'd *Nasus externus*, ῥὶν.
k the nostrils call'd *nares*, μυκτῆρες.
l the outward ear, *auris externa.*
m The mouth made of the two lips, *Os.*
n The chin call'd *mentum*, γένειον.
o The neck, *collum*, αὐχὴν, and τράχηλος.
From *o* to *e* the pillar of the neck, *truncus* and ὄλμος.
p p The hollow of the neck called *jugguli*, σφαγαὶ.
q q The Patel bones, *claves*, κλεῖδες.
r The chest, *pectus*, στέρνον.
ſ The right breast.
ſſ The left breast: to this Region we apply cordial *Epithemations* moist and dry.
tt The nipples of the breasts, *papillæ*, θῆλαι.
u The trench of the heart which the Ancients called καρδία; The Latines *scrobiculus cordis.* This part is anointed for the mouth of the stomach.
From u to E. the lower belly, γαστὴρ.
X The *Epigastrium* or upper part of the lower belly.
y y The *Hypochondria* or *Præcordia.*
* The outward Liver-remedies are applied to this place.
z The region of the navil, called *umbilicalis*, or the middle part of the lower belly.
A The navil, *umbilicus.* The root of the belly, ὄμφαλος.

BB The sides, *Latera* πλευραὶ, and in our Author, *Lumbi, seu Lumbaris regio.* C *Hypogastrium*, the water-course *Aqualiculus*, the lower part of the lower belly, ἧτρον. DD The flanks called *Ilia*, and νεφροῖνες. E. The groins called *pubes* or *pecten*, κλεὶς καὶ ἥβη. F F The Lesk called *inguen*, where those tumors which are called *bubones.* G The Yard with the fore-skin, *penis cum præputio.* H The stones or testicles with the cod or *scrotum.* II The shoulders, *humeri*, ἐπωμίδες. KK The arms, *Brachia*, βράχιονα. L The bowt of the arm, called *Gibber*, ἀγκὼν. M The outside of the lower part of the arm, clled *cubitus*, πῆχυς. N The wrist called *Brachiale*, καρπὸς. O The after-wrist *postbrachiale*, μεταμάρπιον. P The palm called *Palma*, or *vola manus.* Θέναρ. Φ The back of the hand, *dorsum manus*, ὑπόθεναρ. Q Q The fore and middle part of the thigh, where we apply cupping-glasses to bring down womens courses, μηρὸν. RR The knee, *genu*, γόνυ. S S The leg, *tibia*, κνήμη. T T The calf of the leg, *sura*, γαστροκνήμιον. V V The instep, *tarsus.* XX The top of the foot, *Dorsum pedis*, ῥὶς ποδὸς. Y Y The inner ankles, σφυρὸν. Z Z The outward ankles. α α The toes of the feet. Ϛ The place under the inner ankle, where the vein called *Saphena* is opened.

Why the belly is not bony.

Nature would not have this lower belly bony, because the ventricle might be more easily dilated by meat and drink, children might grow the better, and the body be more flexible. It is convenient we begin our Anatomical Administration from this; because it is more subject to putrefaction than the rest, both by reason of its cold and moist temperature, as also by reason of the feculent excrements therein contained. Yet before we go any further, if the Anatomical Administrations must

muſt be performed in publick, the body being firſt handſomly placed, and all the Inſtruments neceſſary for Diſſection made ready, the belly muſt be divided into its parts: Of which ſome contain, and other ſome are contained.

They are called containing, which make all that capacity which is terminated by the *Peritoneum* or rim of the belly. The upper part whereof is bounded by *Galen* within the compaſs of the direct muſcles, and by a general name is called *Epigaſtrium*, or the upper part of the lower belly. That again is divided into three parts, that is, into that which is above the navil, and which carries the name of the whole; into that which is about the navil, and is called the umbilical or middle part; and laſtly, into that which is below the navil, called the *Hypogaſtrium*, or the lower part of the lower belly. The diviſion of the lower belly.

The Figure of the back-parts of a man.



A The fore-part of the head, *ſynciput*, ἔρεγμα.
B The top or crown of the head, *vertex*, κορυφή.
C The hinder part of the head, *occiput*, κοτὶς ὀπίσθιον.
From D to D the face, *facies*, πρόσωπον.
E The eye-brows, *ſupercilia*, ὀφρῦς.
F The upper eye-lid, βλέφαρον.
G The tip of the noſe, called *globulus naſi*.
H The back-part of the neck called *cervix*, αὐχὴν, and the nuke or nape of the neck. There is a hollowneſs at the top of this *cervix*, where we apply Seatons.
I The back-part of the ſhoulder top called *axilla*, ὦμος.
K K The ſhoulder-blades, *ſcapulæ*, ὠμοπλάται.
1 2 3 On this place we ſet Cupping-glaſſes.
4 5 6 7 The back, *dorſum*, νῶτος.
8 9 The ridge, *ſpina dorſi*, ῥάχις.
L The arm-hole, *ala*, μασχάλη.
* The elbow, *gibber brachii*.
M M M M the ſides, *latera*.
N N The loins, *lumbi*, or the region of the kidneys, ὀσφύς.
O O The place of the hips, *coxendices*, where we apply remedies for the Sciatica.
P The place of the holy bone, or *Os ſacrum*, where we apply remedies in the diſeaſe of the right gut.
Q The place of the rump or *Coccyx*.
R R The buttocks, *nates*, πλῶνες.
S S The back part of the thigh, *femur*.
T T The ham, *poples*, ἰσχύς.
V V The calf of the leg, *ſura*.
X X The foot, or *parvus pes*, πούς.
Y Y The outer ankle, *malleolus externus*.
Z Z The heel, *calx*, or *calcaneus*, πτέρνα.
a a The ſole of the foot, *planta pedis*, κοῖλον τοῦ ποδός.
b The inſide of the lower part of the arm called *ulna*, κώνυξ.
c The outſide of the ſame, *cubitus*, πῆχυς.
d d the wriſt, *carpus*. *e e* The back-part of the hand, *dorſum manus*. *g* The fore-finger, *index*, δείκτης. *h* The thumb, *pollex*, ἀντίχειρ. *i* The middle-finger, *medius*, μέσος. *k* The ring-finger, *annularis*, *medicus*, ἰατρικός. The little-finger, *auricularis minimus*, ὠτίτης.

In every of which three parts there be two lateral or ſide-parts to be conſidered, as in the *Epigaſtrium*, the right and left *Hypocondria*, which are bounded above and below, in the compaſs of the midriff, and the ſhort-ribs. In the umbilical the two *Lumbares* (ſome call them *Latera* ſides) which, on both ſides from the loweſt parts of the breaſt, are drawn to the flanks or hanch-bones; in the *Hypogaſtrium*, the two *Ilia*, or flanks bounded with the hanch and ſhare-bones. Neither am I ignorant, the *Ilia*, or flanks, which the Greeks call Λαγόες, ſignifie all the empty parts, from the ends of the ribs, even to the hanch-bones, whereupon they alſo call them Κενεῶνες, as if you ſhould ſay, empty-ſpaces, becauſe they are not encompaſſed with any bone. Yet I thought good, that this doctrine of dividing the belly ſhould be more diſtinct, to call the parts which are on each ſide the navel, *Lumbares*, and thoſe on the lower part of the lower belly, *Ilia*, flanks. But we muſt obſerve, that the Ancients have been ſo diligent in deciphering the containing parts, that as exactly as might be, they deſigned the bowels contained in the belly, which being divers, lie in ſundry places; for the greater portion of the liver lies under the right *Hypocondrium*, under the left almoſt all the ventricle and ſpleen. Under the *Epigaſtrium* the lower orifice of the ventricle, and the The *Hypocondria*.

ſmaller

ſmaller portion of the liver; in the *Lumbares*, or ſides, in the right and upper part the right kidney; in the lower part towards the flank, the blind gut; in the middle part thereof the collick aud empty guts. In the upper part of the left ſide lies the Kidney, in the middle part, the reſt of the empty and colick guts. Under the region of the navel, lies the girdle or upper part of the kall, the colick-gut thruſting it ſelf alſo through that way. Under the *Ilia*, or flanks, the right and left, lie the greater part of the gut, *Ileon*, the horns of the women big with child, and the ſpermatick veſſels in men and women. Under the *Hypogaſtrium* in the lower part lies the right, or ſtrait gut, the bladder, womb, and the reſt of the kall.

A moſt certain note of the part affected by the place where the pain is.

If we know, and well underſtand theſe things, we ſhall more eaſily diſcern the parts affected by the place of the pain; and cure it by fit application of remedies, without the hurting of any part. The diſtinction of ſuch places, and the parts in thoſe places, as ſeeming moſt profitable, I have thought good to illuſtrate by the placing the two precedent figures, in which thou haſt deciphered, not only the foreſaid parts, containing and contained, but alſo of the whole body, and many other things which may ſeem to conduce to the knowledge of the mentioned parts.

CHAP. II.

Of the containing parts of the Epigaſtrium, *and the preparation to Anatomical Adminiſtration.*

The containing parts of the belly.

THe containing parts of the *Epigaſtrium*, are the *Epidermis*, or thin outward skin; the true skin; the fleſhy or fatty Pannicle, the eighth muſcle of the *Epigaſtrium*, with their common coat, the rim of the belly, the five vertebra's of the loins, all the holy-bone, the hanch-bone, ſhare-bone, the white-line and midriff. Of theſe parts, ſome are common to the whole body, as the three firſt; the other, proper to the parts contained in the *Epigaſtrium* taken in general. Which that you may ſee in their order, firſt you muſt cut round about the navel, to the upper *ſuperficies* of the muſcles, that ſo we may keep it, till ſuch time, as occaſion ſhall offer it ſelf, to ſhew the umbilical veſſels lying in that place, which are one vein, two arteries, and the *Urachus* (if it be there.) Which being done, you muſt draw a ſtrait line from the cheſt, over the breaſt-blade, even to the ſhare-bone, which may divide the common-containing parts, even to the white line.

Then preſently it will be convenient to draw two other lines a-croſs or overthwart, of the like depth on each hand, from the circumference of the navel, even to the ſides, that ſo on each part we may draw the skin more commodiouſly from the parts lying under it; the ſight of which otherwiſe it would hinder. Theſe things being done, the skin muſt be divided from the parts lying under it from the deſigned circumference left about the navel. We muſt teach how the skin is two-fold, true and falſe, and render a reaſon of the name, which we will every where do, as far as the thing will ſuffer, and it ſhall lie in our power. And in doing or examining theſe things, it will be convenient diligently to enquire into the nine things mentioned in the Preface. We will begin with the skin, becauſe that part is firſt obvious to our ſenſes.

CHAP. III.

Of the utmoſt Skin or Cuticle.

The skin two-fold.

From what parts the skin cannot be ſeparated.

THe skin being the firſt part, and ſpred over all the body, is twofold, that is, the true, and baſtard skin: The true is called by the *Greeks Derma*, which may almoſt every where be pulled from the parts lying under it, which it inveſts, except in the face, ears, the palms of the hands, ſoles of the feet, fingers, and privities, where it ſticks ſo cloſe that it cannot be ſeparated.

The baſtard skin (which firſt of all we will declare, becauſe it firſt preſents it ſelf to our ſight) is by the *Greeks* called *Epidermis*, becauſe it covers the true skin, they term it commonly the Cuticle. The ſubſtance of it is excrementitious, and (as it were) a certain dry flouring, or production of the true skin. That it draws not its ſubſtance from the Seed, is apparent by this, that as it is eaſily loſt, ſo it is eaſily repaired, which happens not in parts truly ſpermatical. This outmoſt thin skin, or Cuticle, may two manner of ways be made apparent; by it ſelf, and ſeparated from the other, as by burning with fire, or ardent heat of the Sun (in ſome delicate bodies, and ſuch as are not accuſtomed to be converſant in Sun-ſhine.) The quantity in thickneſs is very ſmall, but the extent is moſt large, becauſe it covers all the skin. The figure of it is round, and long, like thoſe parts which it inveſts. The compoſure of it is obſcure; yet becauſe this Cuticle is the excrement of the true skin, we ſay it hath its matter from the excrementitious ſuperfluity of the Nerves, Veins, Arteries and ſubſtance of the true skin.

The matter of the Cuticle.

The quantity.

The figure.

The compoſure.

The number.

The temperature.

The uſe.

It is in number one, like as the true skin which it outwardly covers, that it might be a *medium* between the object and fixed faculty of Touching, diffuſed over all the true skin, which every where lies under it. For the temperature, by the common conſent of Phyſicians, it is in the midſt of all exceſs; for, that ſeeing it is the *medium* between the object and faculty, if it ſhould be hotter, colder, moiſter, or drier, it would deceive the faculty by exhibiting all objects, not as they are of themſelves, but as it ſhould be; no otherwiſe than as to ſuch as look through red or green ſpectacles, all things appear red or green. Wherefore for this reaſon it was convenient the Cuticle ſhould be void of all ſenſe. It hath no action in the body, but it hath uſe; for it preſerves and beautifies the true skin, for it ſeems to be given by the ſingular indulgence of nature, to be a muniment and ornaments to the true skin. This Providence of Nature, the induſtry of ſome Artizans, (or rather Curtizans) doth imitate; who, for to ſeem more beautiful, do ſmooth and poliſh it.

By

By this you may understand, that not all the parts of the body have action, yet have they their use, because, according to *Aristotle*'s opinion, Nature hath made nothing in vain. Also you must note, that this thin skin or Cuticle being lost, may every where be regenerated, unless in the place which is covered with a scar. For here the true skin being deficient, both the matter and former faculty of the Cuticle is wanting. Why the Cuticle cannot be restored in scars.

CHAP. IV.

Of the true Skin.

THe true skin, called by the *Greeks Derma*, is of a Spermatick substance: Wherefore being once lost, it cannot be restored as formerly it was. For in place thereof comes a scar, which is nothing else but flesh dried beyond measure. It is of sufficient thickness, as appears by the separating from the flesh. The substance. Magnitude.

But for the extent thereof, it encompasses the whole body, if you except the eyes, ears, nose, privities, fundament, mouth, the ends of the fingers where the nails grow, that is, all the parts by which any excrements are evacuated. The figure of it is like the Cuticle, round and long, with its productions, with which it covers the extremities of the parts. Figure.

It is composed of nerves, veins, arteries, and of a proper flesh and substance of its kind, which we have said to be spermatical, which ariseth from the process of the secundine, which lead the spermatick vessels even to the navel; in which place each of them into parts appointed by Nature, send forth such vessels as are spred abroad and diffused from the generation of the skin. Which also, the similitude of them both, that is, the skin and membrane *Chorion*, do argue. For as the *Chorion* is double, without sense, encompassing the whole Infant, lightly fastned to the first coat, which is called *Amnios*; so the skin is double, and of it self insensible (for otherwise the nerves were added in vain from the parts lying under it) ingirting the whole body, lightly cleaving to the fleshy Pannicle. But if any object, That the Cuticle is no part of the true skin, seeing it is wholly different from it, and easily to be separated from it, and wholly void of sense: I will answer, These Arguments do not prevail. For, that the true skin is more crass, thick, sensible, vivid and fleshy, is not of it self, being rather by the assistance and admixture of the parts, which derived from three principal it receives into its proper substance; which happens not in the Cuticle. Neither, if it should happen, would it be better for it, but verily exceeding ill for us, because so our life should lye fit and open to receive a thousand external injuries, which encompass us on every side, as the violent and contrary access of the four first qualities. Composure. The skin of it self is void of sense. The number.

There is only one skin, as that which should cover but one body; the which it every-where doth, except in those I formerly mentioned. It hath connexion with the parts lying under it by nerves, veins and arteries, with those subjacent parts put forth into the skin investing them, that there may be a certain communion of all the parts of the body amongst themselves. Connexion.

It is cold and dry in its proper temper, in respect of its proper flesh and substance, for it is a spermatical part. Yet, if any consider the sinews, veins, arteries, and fleshy threds which are mixed in its body, it will seem temperate, and placed (as it were) in the midst of contrary qualites, as which hath grown up from the like portion of hot, cold, moist and dry bodies. The use of the skin is to keep safe and sound the continuity of the whole body, and all the parts thereof, from the violent assault of all external dangers; for which cause it is every where indued with sense, in some parts more exact, in others more dull, according to the dignity and necessity of the parts which it ingirts, that they might all be admonished of their safety and preservation. Lastly, it is penetrated with many pores, as breathing-places, as we may see by the flowing out of sweat, that so the arteries in their *diastole* might draw the encompassing air into the body, for the tempering and nourishing of the fixed inbred heat, and in the *systole* expel the fuliginous excrements, which in Winter, suppresst by the cold air encompassing us, makes the skin black and rough. We have an argument and example of breathing through these, by drawing the air in by transpiration, in women troubled with the Mother, who without respiration live only for some pretty space by transpiration. Use. The reason why the skin is blacker and rougher in Winter.

CHAP. V.

Of the fleshy Pannicle.

AFter the true skin, follows the Membrane, which Anatomists call the fleshy Pannicle, whose nature that we may more easily prosecute and declare, we must first shew what a Membrane is, and how many ways the word is taken; then, wherefore it hath the name of the fleshy Pannicle. A Membrane therefore is a simple part, broad and thin, yet strong and dense, white and nervous, and the which may easily, without any great danger, be extended and contracted. Sometimes it is called a Coat, which is, when it covers and defends some part. This is called the Pannicle; because in some parts it degenerates into flesh, and becomes musculous, as in a man from the collar-bones, to the hair of the head, in which part it is therefore called the broad muscle, whereas in other places it is a simple Membrane, here and there intangled with the fat lying under it, from whence it may seem to take or borrow the name of the fatty Pannicle. But in Beasts (whence it took that name, because in those a fleshy substance maketh a great part of this Pannicle) it appears manifestly fleshy and musculous over all the body, as you may see in Horses and Oxen, that by that means being moveable, they may drive and shake off their flies, and other troublesome things, What a Membrane is. Why it is sometimes called a coat, sometimes the fleshy and fatty Pannicle. Why beasts have this Pannicle wholly fleshy or musculous.

things, by their ſhaking and contracting their backs. Theſe things conſidered, we ſay, the fleſhy Pannicle in its proper body, is of a nervous or membranous ſubſtance, as that which hath its original from the coat *Amnios* (which is next to the Infant) dilated near to the navel, and ſtretched forth for the generation of this Pannicle; in which thing I think good to note, that as the membranes *Chorion* and *Amnios* naturally interwoven with ſmall nervous fibers, encompaſs and inveſt the child as long as it is contained in the womb; ſo the skin and the fleſhy Pannicle, knit together by ſuch like bands, engirt the whole body.

The ſubſtance.

The magnitude & figure.

Number.

Compoſure.

Therefore the fleſhy Pannicle is equal in magnitude and like in figure to the true skin, but that it lies under it, and is contained in it, in ſome places mixt with the fat, in others increaſed by the fleſh interwoven with it, and in ſome other is only a ſimple Membrane.

The compoſition of it is ſuch, as the ſight of it preſents to our eye, that is, of veins, arteries, nerves, and the proper fleſh, ſome whites mixed and interlaced with fat, and ſometimes with muſculous fleſh. It is but one, by reaſon of the uſe we ſhall preſently ſhew; it is ſituated between the skin and fat, or common coat of the muſcles, annexed to theſe, and the other parts lying under it, by the veins, nerves and arteries, aſcending from theſe inward parts, and implanting themſelves into the ſubſtance thereof, and then into the true skin.

The temperature.

The uſe.

The temperature thereof is diverſe, according to the variety of the parts interwoven with it. The uſe of it is, to lead, direct and ſtrengthen in their paſſage, the veſſels which are diſſeminated into the true skin, and the whole ſuperficies of the body. But in Beaſts it hath another commodity, that is, it gives a ſhaking or trembling motion to their skin and back, for that cauſe which we formerly touched.

CHAP. VI.

Of the Fat.

The fat is rather an excrement than a part.

The ſubſtance.

The efficient cauſe of fat.

THe Fat coming near the condition of an excrement, rather than of a part (as we ſaid, when we treated of the ſimilar parts) is of an oily ſuſtance, bred of the airy and vaporous portion of the blood, which ſweating through the pores of the coats, or mouths of the veſſels, becomes concrete about the membranes, and nerves, and cold bodies, and turns into fat by the coldneſs of the place. Whereby we may know, that cold, or a more remiſs heat, is the efficient cauſe of fat, which is manifeſt by contemplation, not only of creatures of divers kinds, but alſo by thoſe of the ſame ſpecies and ſex, if ſo be that the one be colder than the other.

The quantity.

The compoſure.

The ſite.

By which we may underſtand, that the fat is the more or leſs in quantity, according to the different temper of the whole body, and of its particular parts. For its compoſition, it conſiſts of that portion of the blood which we formerly mentioned, intermixt with certain membranes, nervous fibers, veins and arteries. The greateſt part of it lies between the fleſhy Pannicle, and the common coat of the Muſcles. * Otherwiſe it is diffuſed over all the body, in ſome places more, in ſome leſs, yet is always about the nervous bodies, to which it delights to cleave. Moſt Anatomiſts enquire whether the fat lie above or beneath the fleſhy Pannicle. But me-thinks, this queſtion is both impertinent and idle; being we often ſee the fat to be on both ſides. (*a*) It is of a middle temper between heat and cold, being it ariſeth of the more airy portion of the blood; although it may ſeem cold in reſpect of the efficient cauſe, that is, of cold by which it concretes. For the reſt, moiſture is predominant in the fat. (*b*) The uſe thereof is, to moiſten the parts which may become dry by long faſting, vehement exerciſe, or immoderate heat; and beſides, to give heat, or keep the parts warm. Although it do this laſt rather by accident, than of its own nature, as heated by exerciſe, or by ſome ſuch other chance; it heats the adjacent parts, or may therefore be thought to heat them, becauſe it hinders the diſſipation of the native and internal heat; like as cold heats in Winter, whereby the bellies are at that time the hotter. I know, ſome learned Phyſicians of our time ſtiffly maintained, that the fat was hot; neither did they acknowledge any other efficient cauſe thereof, than temperate heat, and not cold. But I think it beſt to leave the more ſubtil agitation of theſe queſtions to natural Philoſophers. But we muſt note, (*c*) that at the joynts which are more uſually moved, there is another ſort of fat, far more ſolid and hard, than that which we formerly mentioned, often found mixed with a viſcid and tough humor like the white of Eggs, that ſo it might be ſufficient for a longer time to moiſten theſe parts, ſubject to be hurt by drineſs, and to make them ſlippery, and ſo fitter for motion; in imitation whereof they uſually greaſe hard bodies, which muſt be in frequent motion, as Coach-wheels and Axletrees. And there is another kind of fat, which is called *Sebum*, ſeam, in one thing differing from the ordinary fat, that it is much drier; the moiſter and ſofter portion of the fat being diſſipated by the raging heat of the place. For it is found principally about the (*d*) Midriff, where there are many windings of arteries and veins; and it is alſo about the reins, loins, and *baſis* of the heart. The fat is waſted by long faſting; is dried and hardened by vehement exerciſe, and immoderate heat. Hence it is, that it is much more compact in the palms of the hands, and ſoles of the feet, about the eyes and heart, ſo that it reſembles the fleſh in denſity and hardneſs; becauſe by the continual motion and ſtrong heat of theſe parts, the thinner portion being diſſipated and diffuſed, the more groſs and terreſtrial remains.

* I was preſent at the opening of a Body, *Feb.* 1630. in which the fat in the lower part of the lower belly was in thickneſs above eight inches, upon the breaſt between four and five inches: which I thought good to remember in this place, both for the rarity of the thing, as alſo becauſe it was increaſed by report, and the place miſtaken; ſome ſaying the *Omentum* or Kall was ſo thick, which was falſe; for it did not much exceed the quantity of that part, in other fat men.

(*a*) The Temper. (*b*) The uſe. (*c*) The ſolider fat or ſeam. (*d*) In what parts, and for what cauſe the fat is more denſe.

CHAP.

CHAP. VII.

Of the common Coat of the Muſcles.

NExt under the fat, appears a certain coat, ſpread over all the muſcles, and called the common coat of the muſcles; it is of a nervous ſubſtance, as all other membranes are. The quantity and breadth thereof is bounded by the quantity of the muſcles which it involves, and fits it ſelf to, as that, which encompaſſes the muſcles of the *Epigaſtrium*, is of equal largeneſs with the ſame muſcles. The figure of it is round: it is compoſed of veins, nerves, arteries, and its peculiar fleſh conſiſting of three ſorts of fibers; the beginning of it is from the *Periоſteum*, in that part where the bones give ligaments to the muſcles; or, according to the opinion of others, of the nervous and ligamentous fibers of the muſcles, which riſing up, and diffuſed over the fleſhy *ſuperficies* thereof, are united for the generation of this coat. But this membrane ariſing from the *Periоſteum* (as every membrane which is below the head, takes its original from the *Periоſteum* either primarily, by the interpoſition of no *medium*, or ſecondarily) is ſtretched over the muſcles by their Tendons. But if any object, that this membrane, pluck'd from the belly of the muſcle, may ſeem to end in a ligament: I will anſwer, that it is the condition of every nervous part, ſo to bind or faſten it ſelf to another part of his own kind to ſtay, ſo that it can ſcarce be pluck'd from thence. We ſee the proof hereof in the *Peritonæum* or rim in the *Epigaſtrium*, or lower part of the lower belly. That which covers the muſcles of the *Epigaſtrium*, is but one, unleſs you had rather part it into two, the right and the left diſtinguiſhed by the interpoſition of *Linea Alba*, or White-Line. It is ſituate betwixt the fat and the muſcles; for it is faſtened above and below to theſe parts with fibers, which in ſmalneſs and fineneſs exceed the Spiders web. But by its veſſels, it participates with the three principal parts, and is of a cold and dry temper. The uſe of it is, to contain the muſcles in their natural union, and to keep them, as much as in it lies, from putrefaction, which may happen to them from *pus* or matter, which is often caſt forth of the ſimilar parts into the empty ſpaces and diſtances of the muſcles. Wherefore going about to ſeparate the fat of the *Epigaſtrium* (where you muſt begin the diſſection of mans body) you muſt have a care that you hurt it not with your knife, but that, before you touch the muſcles, ſee you artificially take it away, that you may the more eaſily ſeparate the muſcles, lying under it, diſtinguiſhed by a manifeſt ſpace at the White-Line, which is made by the meeting together of the proper coats of all thoſe muſcles.

The ſubſtance.
The quantity.
The compoſure.
The original.
The number.
The ſite.
The uſe.
What the White-line is.

CHAP. VIII.

What a Muſcle is, and how many differences there be thereof.

A Muſcle is the inſtrument of voluntary motion; and ſimple voluntary motion is performed ſix manner of ways, upwards, downwards, forwards, backwards, to the right hand, and to the left; but the compound one way, which is circularly, the which is performed by the continual ſucceſſion of the motion of the muſcles ingirting the part. Such a motion Falconers uſe when they ſtretch forth their hand, and lure their Hawk. We have ſome parts, which have motion without a muſcle, but that motion is not voluntary; ſuch parts be, the heart, ſtomach, guts, both the bladders, (that is, that of the gall, and that of the urine) and divers other which have the motions of attraction, expulſion, and retention, by the means of the three ſorts of fibers; for they draw by the right, expel by the tranſverſe, and retain by the oblique. The differences of muſcles, which are many and diverſe, are taken from their ſubſtance, original, inſertion into the part which they move, form or figure, holes or openings, magnitude, colour, ſite, kind of fibers, their conjugation or connexion, heads, bellies, tendons, oppoſition in action and office. Some in ſubſtance are nervous, venous, arterious; becauſe they have manifeſt nerves, veins, and arteries; as the Midriff, the Intercoſtal, or Epigaſtrick muſcles, and many more, and that for their difference from other muſcles, into which neither nerve, nor vein, or arteries are manifeſtly inſerted, although ſecretly they admit them all for ſenſe and motion, life, and nouriſhment; ſuch are the muſcles of the wriſt, the wormy muſcles of the hands and feet; for if there be any nerves obſerved in them, they are very ſmall. Some had rather make the difference of muſcles thus, that ſome of them are fleſhy, ſome nervous, others membranous. From their original; ſome ariſe from the bones, as thoſe which move the hands, arms and legs; others from griſles, as the muſcles of the throat; others, from membranes which inveſt the tendons, as the wormy muſcles of the hands and feet; others, from ligaments, as the extenders of the fingers; others, from other muſcles, as the two lower muſcles of the Yard which proceed from the Sphincter muſcle of the ſundament. Others have no original, as, the membrane, which we call the fleſhy Pannicle, aſſumes fleſh in certain places, and degenerates into a muſcle; ſuch are the *Cremaſter*, or hanging muſcles of the teſticles, the large muſcles of the face; and if you pleaſe, the midriff as that which is compoſed of two coats; the one, encompaſſing the ribs and the *Peritonæum*, hath fleſh in the midſt between the two membranes. And moreover, ſome muſcles have their original from one only bone, as thoſe which bend and extend the cubit; others ariſe of many bones, as the oblique deſcending, the Dorſal, and many muſcles of the neck, which ariſe together from many ſpondyls, and ſides of ſpondyl. There be others, according to the opinion of ſome men, both from the bones and griſles of the *Pubis* at the right or direct muſcles of the *Epigaſtrium*, yet by their favour I think otherwiſe. Becauſe by the Anatomical and received axiom, A muſcle is there thought to take his beginning, from whence he receives a nerve; but theſe muſcles take a nerve from the intercoſtal muſcles,

What a muſcle is.
How the circular motion is performed.
From whence the differences of muſcles are drawn.
Differences of muſcles from their ſubſtance.
Differences of muſcles from their original.
Where a muſcle hath its original.

Differences of muſcles from their inſertion.

muſcles, wherefore their original ought to be referr'd to the ſides of the breaſt-blades, as ſhall be ſhewed in due place. From their inſertion ariſe theſe differences; ſome are inſerted into a bone, as thoſe which move the head, arms, and legs; others into a griſle, as thoſe of the Throtle, eye-lids, noſe, and the oblique aſcendent muſcles of the *Epigaſtrium*; ſome into a bone and griſle both, as the right muſcles of the *Epigaſtrium* and the midriff: Some into the skin, as the muſcles of the lips; others into the coats, as the muſcles of the eyes; others into ligaments, as the muſcles of the yard. But theſe differences following may be drawn both from their inſertion and original. For ſome muſcles ariſing from many parts, are inſerted into ſome one part, as divers of thoſe which move the arm and the ſhoulder, which ariſing from many ſpondyls, are inſerted into the bone of the ſhoulder, and the ſhoulder-blade. Others ariſe from one part, and inſert themſelves into more, as, thoſe which ariſe from the bottom of the ſhoulder-blades are extended and inſerted into ſome eight or nine of the upper ribs, to help reſpiration; and the benders and extenders of the fingers and toes: Others, ariſing from many bones, are inſerted into as many, as ſome of thoſe which ſerve for reſpiration, to wit, thoſe which we call the hinder Saw-muſcles, and the *Semiſpinatus*, which ſends a tendon into all the ribs. Others have their original from many bones, and end in griſles of the ſeven ribs, as thoſe two which lie under the *Sternon*. Moreover, alſo theſe differences of muſcles may be drawn from the original and inſertion, that ſome proceed from bones, and are inſerted into the next bone, to help and ſtrengthen the motion thereof, as the three muſcles of the hip; Others ariſe from an upper bone, and are not inſerted into the next, but into ſome other, as the long muſcles. Some are named from the part they move, as the temporal muſcles, becauſe they move the temples: Others from their office, as the grinding muſcles; becauſe they move the skin as a Mill, to grind aſunder the meal. From their form or figure; becauſe ſome are like Mice, other like Lizards which have their legs cut off; for that they imitate in their belly, body, or tendon, the belly or tail of ſuch creatures; and from whence the name of *Muſculus* and *Lacertus* are divided. Such are thoſe which bend the wriſt, and which are faſtened to the bone of the leg, and which extend the foot; others are triangular, as that which lifts up the arm, called *Epomis* or *Deltoides*, and that which draws the arm to the breaſt, called the pectoral muſcle. Others quadrangular, as the *Rhomboides*, or Lozenge-muſcle of the ſhoulder-blade, and the two hindſom-muſcles ſerving for reſpiration, and two of the wriſts which turn down the hand; others conſiſt of more than four angles, as the oblique deſcending, and that muſcle which joyns it ſelf to it from the ſhoulder-blade; others are round and broad, as the midriff; others circular, as the Sphincter-muſcle of the fundament and bladder; others are of a pyramidical figure, as the ſeventh muſcle of the eye, which compaſſes the optick nerve in beaſts, but not in men; others have a ſemicircular form, as that which ſhuts up the eye, ſeated at the leſſer corner thereof; others reſemble a Monk's cowl, or hood, as the *Trapezius* of the ſhoulder-blade. Beſides, others at their firſt original are narrow, but broad at their inſertion; as the Saw-muſcle of the ſhoulder, and the tranſverſe of the *Epigaſtrium*; others are quite contrary, as the three muſcles of the hip; others keep an equal breadth or bigneſs in all places, as the intercoſtal muſcles and thoſe of the wriſt; others are long and ſlender, as the long muſcle of the thigh; others are long and broad, as the oblique deſcending muſcles of the *Epigaſtrium*; others are directly contrary, as the Intercoſtal, which are very narrow. From their perforations; for ſome are perforated, as the midriff, which hath three holes, as alſo the oblique and tranſverſe of the *Epigaſtrium*, that ſo they may give paſſage forth to the preparing ſpermatick veſſels, and to the ejaculatory veſſels, the coat *Erythroides* aſſociating and ſtrengthening them; others are not perforated. From their magnitude; for ſome are moſt large, as the two muſcles of the hip; others very ſmall, as the eight ſmall muſcles of the neck, and the proper muſcles of the Throtle, and the wormy muſcles; others are of an indifferent magnitude. From their colour; for ſome are white and red, as the temporal muſcles, which have Tendons coming from the midſt of their belly; others are livid, as the three greater muſcles of the calf of the leg, which colour they have by the admixtion of the white, or tendinous nervy coat with the red fleſh; for, this coat by its thickneſs darkning the colour of the fleſh, ſo that it cannot ſhew its redneſs and freſh colour, makes it ſeem of that livid colour. From their ſituation; for ſome are ſuperficiary, as thoſe which appear under the skin and fat; others deep in, and hid, as the ſmooth and four twin muſcles; ſome are ſtretched out, and (as it were) ſpred over in a ſtrait and plain paſſage, as the muſcles of the thigh which move the leg, except the Ham-muſcle; others oblique, as thoſe of the *Epigaſtrium*; otherſome tranſverſe, as the tranſverſe of the *Epigaſtrium*; where you muſt obſerve, that although all the fibers of the muſcles are direct, yet we call them oblique and tranſverſe, by comparing them to the right muſcles, as which by the concourſe of the fibers make a ſtrait or acute angle.

Differences of muſcles taken from their figure.

Differences from their perforations.

From their magnitude.

From their colour.

From their ſite.

From their Fibers.

From the ſorts of fibers; for ſome have one kind of fiber, yet the greateſt part enjoy two ſorts running ſo up and down, that they either are croſſed like the letter X, as happens in the pectoral and grinding muſcles; or elſe do not concur, as in the *Trapezii*. Others have three ſorts of fibers, as the broad muſcle of the face.

From their Connexion.

From their coherence or connexion, or their texture of nervous fibers; for ſome have fibers ſomewhat more diſtant and remote immediately at their original, than in other places, as you may ſee in the muſcles of the buttocks: Others in their midſt and belly, which by reaſon thereof in ſuch muſcles is more big or tumid, their head and tail being ſlender, as happens in moſt of the muſcles of the arm and leg, in which the denſe maſs of fleſh interwoven with fibers, disjoyns the fibers in ſo great a diſtance; in otherſome the fibers are more diſtant in the tail, as in the greater Saw-muſcle ariſing from the bottom of the ſhoulder-blade; in others, they are equally diſtant through the whole muſcle, as in the muſcles of the wriſt, and between the ribs.

From their Head.

From their head; for in ſome it is fleſhy, interwoven with few fibers, as in the muſcles of the buttocks; in others it is wholly nervous, as in the moſt broad muſcle common to the arm and ſhoulder-blade, and in the three muſcles of the thigh proceeding from the tuberoſity of the huckle-

huckle bone; in ſome it is nervous and fleſhy, as in the internal and external muſcle of the arm. Beſides, ſome have one head, others two; as the bender of the elbow, and the external of the leg; others three, as the three-headed muſcle of the thigh, But we muſt note, that the word nerve or ſinew is here taken in a large ſignification, for a ligament, nerve and tendon, as *Galen* ſaith (*Lib. de Oſſibus*;) and moreover we muſt obſerve, that the head of a muſcle is one while above, another while below, otherwhiles in the midſt, as in the midriff, as you may know by the inſertion of the nerve, becauſe it enters the muſcle by its head.

From their belly alſo, there be ſome differences of muſcles taken; for ſome have their belly immediately at their beginning, as the muſcles of the buttocks; others at their inſertion, as the midriff; others juſt at their head, as thoſe which put forth the calf of the leg; in others it is ſomewhat further off, as in thoſe which draw back the arm, and which bend the leg; in others, the belly extends even from the head unto the tail, as in the intercoſtal muſcles, and thoſe of the wriſt; in others, it is produced even to their inſertion, as in thoſe of the palms of the hands and ſoles of the feet; ſome have a double belly diſtinguiſhed by a nervous ſubſtance; as thoſe which open the mouth, and thoſe which ariſe from the root of the lower of proceſs of the ſhoulder-blade. From their belly.

Moreover the differences of muſcles are drawn alſo from the tendons; for ſome have none, at leaſt which are manifeſt, as the muſcles of the lips, and the ſphincter-muſcles, the intercoſtal, and thoſe of the wriſt; others have them in part, and want them in part, as the midriff; for the midriff wants a tendon at the ends of the ſhorter ribs, but hath two at the firſt *Vertebra* of the loins in which it is terminated; others have a tendon indeed. But ſome of theſe move with the bone, ſome not, as the muſcles of the eyes; and beſides, ſome of theſe have broad and membranous tendons, as the muſcles of the eyes, and *Epigraſtium*, except the right muſcles; in others they are thick and round, as in the benders of the fingers; in others they are leſs round, but more broad than thick, ſuch is the tendon ariſing from the twin muſcles, and *Soleus* of the leg; others have ſhort tendons, as the muſcles which turn down the hand; otherſome long, as thoſe of the palms of the hands, and ſoles of the feet; beſides, others produce tendons from the end of their belly, which tendons are manifeſt; others from the midſt, as the temporal muſcles. From their tendons.

Beſides, alſo others diffuſe many tendons from their belly, as in the hands the benders of the fingers, and extenders of the feet. Otherſome put forth but one, which ſometimes is divided into many, as thoſe which bend the third articulation of the foot; otherwhile many muſcles by their meeting together make one tendon, as the three muſcles of the calf of the leg, and thoſe which bend the cubit and leg. All tendons have their original, when the nerves and ligaments diſperſed through the fleſhy ſubſtance of a muſcle, are by little and little drawn and meet together, until at laſt carried to the joynt, they are there faſtned for the fit bending and extenſion thereof. From the contrariety of their actions; for ſome parts have contrary muſcles, benders and extenders, other have none; for the cods and fundament have only lifters up. From their function; for ſome are made for direct motions, as thoſe which extend the fingers and toes; others for oblique, as the Supinators of the hand, and the Pronators; others perform both, as the pectoral muſcle, which moves the arm obliquely upward and downward, as the upper and lower fibers are contracted; and alſo out-right, if all the fibers be contracted together, which alſo happens to the *Deltoides* and *Trapezius*. I have thought it good to handle particularly theſe differences of muſcles, becauſe that by underſtanding them, the prognoſtick will be more certain, and alſo the application of remedies to each part; and if any occaſion be, either to make inciſion, or ſuture, we may be more certain, whether the part affected, be more or leſs nervous. From their action. From their function.

CHAP. IX.

Of the parts of a Muſcle.

HAving declared the nature and differences of a muſcle, we muſt note that ſome of the parts thereof are compound and univerſal, others ſimple or particular. The compound are the head, belly, and tail. The ſimple are ligaments, a nerve, fleſh, a vein, artery, and coat. For the compound parts; by the head, we underſtand the beginning and original of a muſcle, which is one while ligamentous and nervous, otherwhiles alſo fleſhy. By the belly, that portion which is abſolutely fleſhy: By the tail we underſtand a tendon conſiſting partly of a nerve, partly of a ligament promiſcuouſly coming forth from the belly of the muſcle. For as much as belongs to the ſimple, which are ſix in number, three are called proper, and three common. The proper are a ligament from a bone, a nerve proceeding from the brain, or ſpinal marrow, and fleſh compact by the concretion of blood. The common are a vein from the liver or trunk ariſing from thence; an artery proceeding from the heart, a coat produced by the nervous and ligamentous fibers ſpreading over the *ſuperficies* of the muſcle. But for the ſimple uſe of all ſuch parts, the nerve is (as it were) the principal part of a muſcle, which gives it ſenſe and motion, the ligament gives ſtrength, the fleſh contains the nervous and ligamentous fibers of the muſcle, and ſtrengthens it, filling up all the void ſpaces; and alſo, it preſerves the native humidity of theſe parts, and cheriſheth the heat implanted in them; and, to conclude, defends it from all external injuries; for, like a fan, it oppoſeth it ſelf againſt the heat of the Sun; and is a garment againſt the cold; and is as a cuſhion in all falls and bruiſes; and as a buckler of defence againſt wounding-weapons. The vein nouriſhes the muſcle, the artery gives it life, the coat preſerves the harmony of all the parts thereof, leſt they ſhould be any ways disjoyned or corrupted by purulent abſceſſes breaking into the empty or void ſpaces of the muſcles; as we ſee it hapneth in a Gangrene, where the corruption hath invaded this membrane, by the breathing out of the more acid matter or filth. The compound and ſimple parts of a muſcle. What uſe each ſimple particle hath in a muſcle.

CHAP. X.

A more particular inquiſition into each part of a Muſcle.

The nature of a ligament.

HAving gone thus far, it remains, that we more particularly inquire into each part of a Muſcle, that (if it be poſſible) nothing may be wanting to this Diſcourſe. Wherefore a ligament properly ſo called, is a ſimple part of mans body, next of a bone and griſle, the moſt terreſtrial, dry, hard, cold, white; taking its original immediately, or by the interpoſition of ſome *medium* from the bones or griſles (from whence alſo the muſcles have their beginning) whereby it comes to paſs, that a ligament is void of ſenſe, unleſs it receive a nerve from ſome other place; for ſo the ligaments which compoſe and ſtrengthen the tongue and yard, are partakers of ſenſe, and it inſerts it ſelf into the bone and griſle, that ſo it may bind them together, and ſtrengthen and beautifie the whole joint or connexion; (for theſe three be the principal uſes of a ligament) then diffuſing it ſelf into the membranes and muſcles to ſtrengthen thoſe parts. A nerve, to ſpeak properly, is alſo a ſimple part of our body, bred and nouriſhed by a groſs and phlegmatick humour, ſuch as the brain, the original of all the nerves, and alſo the Spinal marrow endued with the faculty of feeling, and oftentimes alſo of moving. For there be divers parts of the body which have nerves, yet are deſtitute of all voluntary motion, having the ſenſe only of feeling, as the membranes, veins, arteries, guts, and all the entrails. A nerve is covered with a double cover from the two membranes of the brain, and beſides alſo with a third proceeding from the ligaments which faſten the hinder part of the head to the *Vertebra's*, or elſe from the *Pericranium*. We underſtand no other things by the fibers of a nerve, or of a ligament, than long and ſlender threds, white, ſolid, cold, ſtrong, more or leſs, according to the quantity of the ſubſtance, which is partly nervous and ſenſible, partly ligamentous and inſenſible. You muſt imagine the ſame of the fleſhy fibers in their kind; but of theſe threds ſome are ſtrait for attraction; others oblique, for retention of that which is convenient for the creature; and laſtly, ſome tranſverſe, for expulſion of that which is unprofitable. But when theſe tranſverſe threds are extended in length, they are leſſened in bredth; but when they are directly contracted, they are ſhortned in length. But when they are extended all together as it were, with an unanimous conſent, the whole member is wrinkled as contracted into it ſelf: as on the contrary it is extended when they are relaxed. Some of theſe are beſtowed upon the animal parts, to perform voluntary motions; others upon the vital to perform the agitation of the heart and arteries; others upon the natural for attraction, retention, and expulſion. Yet we muſt obſerve, that the attraction of no ſimilar part is performed by the help of the foreſaid fibers or threds, but rather by the heat implanted in them, or by the ſhunning of emptineſs, or the familiarity of the ſubſtance. The fleſh alſo is a ſimple and ſoft part, compoſed of the pure portion of the blood inſinuating it ſelf into the ſpaces between the fibers, ſo to inveſt them for the uſes formerly mentioned. This is (as it were) a certain wall and bulwark againſt the injuries of heat and cold, againſt all falls and bruiſes, as it were, a certain ſoft pillow or cuſhion yielding to any violent impreſſion. There be three ſorts of fleſh; one more ruddy, as the muſculous fleſh of perfect creatures, and ſuch as have blood; for the fleſh of all tender and young things having blood, as Calves, and alſo of all ſorts of fiſh, is whitiſh, by reaſon of the too much humidity of the blood. The ſecond kind is more pallid, even in perfect creatures having blood, ſuch is the fleſh of the heart, ſtomach, weaſon, guts, bladder, womb. The third is belonging to the entrails, or the proper ſubſtance of each entrail, as that which remains of the liver (the veins, arteries and coat being taken away) of the bladder, of the gall, brains, kidneys, milt: Some add a fourth ſort of fleſh which is ſpongy, and that they ſay is proper to the tongue alone.

The threefold uſe of a ligament.

What a nerve is.

What we mean by the nervous and ligamentous fibers.

By what power the ſimilar parts principally draw or attract.

What, and of how many ſorts the fleſh is.

What a vein is.

A vein is the veſſel, pipe or channel of the blood, or bloody matter; it hath a ſpermatick ſubſtance, conſiſts of one coat compoſed of three ſorts of fibers.

What an artery is.

An artery is alſo the receptacle of blood, but that ſpirituous and yellowiſh, conſiſting in like manner of a ſpermatick ſubſtance: But it hath two coats with three ſorts of fibers, the utmoſt whereof is moſt thin, conſiſting of right fibers, and ſome oblique: But the inner is five times more thick and denſe than the utmoſt, inverwoven with tranſverſe fibers; and it doth not only contain blood and ſpirit, but alſo a ſerous humor, which we may believe, becauſe there be two emulgent arteries as well as veins.

Why an artery is more thick and denſe than a vein.

But the inner coat of an artery is therefore more thick, becauſe it may contain blood which is more hot, ſubtil, and ſpirituous; for the ſpirit, ſeeing it is naturally more thin and light, and in perpetual motion, would quickly fly away, unleſs it were held in a ſtronger hold. There is other reaſon for a vein, as that which contains blood, groſs, ponderous, and ſlow of motion. Wherefore if it had acquired a denſe and groſs coat, it could ſcarce be diſtributed to the neighbouring parts: God, the maker of the Univerſe, foreſeeing this, made the coats of the veſſels contrary to the conſiſtence of the bodies contained in them. The *Anaſtomoſis* of the veins and arteries, that is to ſay, the application of the mouths of the one to the other, is very remarkable, by benefit of which they mutually communicate and draw the matters contained in them, and ſo alſo transfuſe them by inſenſible paſſages, although that *Anaſtomoſis* is apparent in the vein and artery that meet together at the joynt and bending of the arm, which I have ſometimes ſhewed in the Phyſick Schools, at ſuch times as I there diſſected Anatomies.

The mutual *Anaſtomoſis* of the veins and arteries.

Where it is manifeſt.

From whence a muſcle hath its beginning or head.

But the action or function of a muſcle is either to move or confirm the part according to our will into which it is implanted; which it doth when it draws it ſelf towards its original, that is to ſay, its head. But we define the head by the inſertion of the nerve, which we underſtand by the manner of the working of the muſcle.

CHAP.

CHAP. XI.

Of the muſcles of the Epigaſtrium, *or lower Belly.*

NOw ſeeing that we have taught what a muſcle is, and what the differences thereof are, and what ſimple and compound parts it hath, and what the uſe, action and manner of action in each part is; it remains that we come to the particular explication of each muſcle, beginning with thoſe of the lower belly, as thoſe which we firſt meet withal in diſſection.

Eight muſcles of the *Epigaſtrium.*

Theſe are eight in number, four oblique, two on each ſide, two right or direct, one on the right, another on the left ſide; and in like manner two tranſverſe. All theſe are alike in force, magnitude and action, ſo mutually compoſed, that the oblique deſcendant of one ſide, is conjoyned with the other oblique deſcendant on the other ſide, and ſo of the reſt.

We may add to this number the two little ſupplying or aſſiſting muſcles, which are of a *Pyramidal* form, and ariſe from the ſhare-bone, above the inſertion of the right muſcles: Of the oblique muſcles of each ſide the one aſcends, the other deſcends, whereupon it comes to paſs, that they are called the oblique deſcendant and aſcendant muſcle. Thoſe oblique which we firſt meet with, are the deſcendant, whoſe ſubſtance is partly ſanguine, partly ſpermatick; for they are fleſhy, nervous, ligamentous, veinous, arterious and membranous. Yet the fleſhy portion is predominant in them, out of which reſpect *Hippocrates* is wont to expreſs the muſcles by the name Fleſhes; their greatneſs is indifferent between the large and the ſmall muſcles; their figure is three ſquare. They are compoſed of the fore-mentioned parts, they are two in number; their ſite is oblique, taking their beginning from the touching of the great ſaw-muſcle, and from the ſixth and ſeventh true ribs, or rather from the ſpaces between the ſix lower ribs, and rather on the forepart of the muſcles, than of the ribs themſelves; from whence ſhunning the *Vertebra's* of the loins, the fleſhy parts of them are terminated in the external and upper eminency of the haunch-bone, and the membranous end in the lower eminency of the ſhare-bone and the white-line. Yet *Columbus* diſſenting from this common deſcription of the oblique muſcles. thinks that they are only terminated in the white-line, and not in the ſhare-bone. For (ſaith he) wherefore ſhould they be inſerted into the ſhare-bone which is not moved? But becauſe it would be an infinite labour and trouble to ſet down at large the ſeveral opinions of all Authors of Anatomy; I have thought it ſufficient for me to touch them lightly by the way. Their connexion is with the oblique aſcendant lying under them, and with the direct or right. Their temperament is twofold, the one hot and moiſt, by reaſon of the belly and fleſhy portion of them; the other cold and dry, in reſpect of their ligamentous and tendinous portion. Their action is to draw the parts into which they are inſerted towards their original, or elſe to unite them firmly. Yet each of theſe privately and properly draws the hip in an oblique manner towards the *Cartilago Scutiformis*, or breaſt-blade. Then follow the oblique aſcendant, who have the ſame ſubſtance, quantity, figure, compoſure, number and temper the deſcendant have. They are ſituate between the deſcendant and tranſverſe with whom they have connexion, eſpecially by the veſſels which are brought from the parts beneath. All the fleſhy parts ariſe from the rack-bones of the haunch to the ends of the baſtard-ribs, which they ſeem to admit above and below, being fleſhy even to the fourth, and then becoming membranous, they take their way to the white-line, with a double *aponeuroſis*, which paſſes through the right muſcles above and below, as we may plainly ſee from the navel downwards. In their fleſhy part they draw their original from the ſpine of the haunch-bones a little lower than the deſcendant end in their fleſhy part. But for their membranous parts, they ariſe before from the ſhare-bone, but behind from the ſpondyls of the holy-bone, and *Vertebra's*, of the loins obliquely aſcending upwards to the white-line, into which they are terminated by an *aponeuroſis* or membranous tendon (which ſeems to penetrate the right muſcle upwards and downwards, eſpecially under the navel) but by their fleſhy part at the ends of all the baſtard ribs, which they ſeem to receive above and below. And becauſe theſe muſcles are terminated in the white-line, they have alſo another uſe, yet ſuch as is common to all the muſcles of the *Epigaſtrium*, that is, to preſs down the guts. Their action is (if they perform it together) to draw and dilate the breaſt; but if their actions be ſeparate, they draw the cheſt to the hip with an oblique motion. After theſe follow the right muſcles, ſo called, becauſe they deſcend according to the length of the body, and becauſe they have right or ſtrait fibers.

The oblique deſcendant.
Their ſubſtance.
Their greatneſs and figure.
Their compoſure and ſite.
Their connexion.
Their temperament.
Their action.
The oblique aſcendant.
Their ſite and connexion.
Their action.
The right muſcles of the *Epigaſtrium.*

We will ſay nothing (to ſhun prolixity, which in all other places we will avoid) of their ſubſtance and other conditions, which they have common with the fore-mentioned muſcles. They are ſituate in the eminenteſt or extuberating region of the belly, bounding the *Epigaſtrium* taken in general, (or the ſuperficiary belly;) they are divided by the manifeſt intercourſe of the white-line, even to the navel, in which place they ſeem to be united even to the place of their inſertion. They draw their original not from the ſhare-bone, as ſome would have it, but according to the inſertion of their nerves from the ſides of the *Cartilago Scutiformis*, and the ends of the ſixth, ſeventh and eighth ribs; but they end in the ſhare-bone, where they make a common tendon ſufficiently ſtrong and ſhort. *Sylvius*, *Veſalius* and *Columbus* think they ariſe from the ſhare-bone, becauſe they cannot be inſerted into that bone, becauſe it is unmoveable. You may perceive in theſe muſcles certain nervous and tranſverſe interſections, oftentimes three in number for the ſtrength of theſe muſcles, (of which *Galen* makes no mention, although they may be ſeen in Apes.) And alſo in the inner ſide of theſe muſcles you may ſee four veins, and as many arteries, of which ſome creep upwards, others run downwards. The upper, called the Mamillary, deſcend from the Axillary by the ſide and lower parts of the *Sternon*, the ſlenderer portions thereof being diſtributed by the way to the *Mediaſtinum*, and about the fourth and fifth rib to the dugs, from whence they take their name.

Their ſite.
Original.

The meeting together of the Epigaſtrick and mamillary veins and arteries.

That which remains breaking out by the ſides of the breaſt-blade, inſerts it ſelf into thoſe muſcles, creeping along, even almoſt to the navel; in which place they are manifeſtly united (that is, the veins with the veins, and arteries with the arteries) with the Epigaſtrick, which aſcend from the upper part of the Iliack; on each ſide under the ſaid muſcles, until they meet with theſe four mamillary veſſels. That you may find the concourſe of the veins and arteries about the navel, you muſt follow both the upper and the lower ſomewhat deep into the fleſh, preſſing the blood on both ſides from above downwards, and from below upward, until you ſhall find the exoſculation of theſe veſſels, which will appear by this, That the blood will flow from this into that, and from that into this; otherwiſe you can ſcarce perceive it, by reaſon of the ſmalneſs of ſuch veſſels which want blood. But that by the benefit of ſuch concourſe of the veſſels, the matters may be communicated and tranſported both from the womb to the dugs, and again from the dugs to the womb, appears in Nurſes who want their courſes, when the milk comes into their dugs; and on the contrary loſe their milk when their courſes flow plentifully. Otherwiſe to what purpoſe ſhould there be ſuch concourſe between the veſſels of the paps and womb? for there are veins and arteries diffuſed to the ſides of the womb from the root of the Epigaſtricks; for indeed the Epigaſtricks which in their aſcent meet with the mamillary, go not to the womb, though they be next to them, and ariſe from the ſame trunk with the Hypogaſtrick vein of the womb. The action of theſe muſcles is, to move or draw near together the parts of the Hypogaſtrium to the *Præcordia*, or Hypochondries. Their uſe, in *Columbus* opinion, is, to draw the breaſt downwards, ſo to dilate it. At the end of theſe, nature hath produced two other ſmall muſcles from the upper part of the ſhare-bone, of a triangular figure, for the ſafety of the thick and common tendon of the right muſcles; whereupon they are called *Succenturiati*, or Aſſiſters.

Their action.

Their uſe.

The firſt figure of the lower Belly.

ABCD *The upper, lower, and lateral parts of the* Peritonæum.

EE *The White-line from the griſle of the breaſt-bone, called the breaſt-blade, to the commiſſure or meeting of the ſhare-bones.*

F *The griſle of the breaſt-bone,* Cartilago enſi-formis, *or the breſt-blade.*

G *The navel, which, all the muſcles being taken away, muſt be kept for the demonſtration of the Umbilical veſſels.*

HH *The productions of the* Peritonæum, *which contain the ſeminary veſſels on either ſide.*

** *The hole which giveth way to the ſeminary veſſels of men.*

II *A vein and an artery from the* Epigaſtrick, *which being carried upward under the right muſcles, do here hang down, and are diſtributed into the lower part of the* Abdomen.

KK *A vein and an artery, from the internal mammary, proceeding from under the bone of the breaſt, are carried downward through the right muſcles, and are diſſeminated into the upper part of the* Abdomen.

1 2 *The place wherein the right muſcles ariſe, which being here cut off, do hang down, that their veſſels may the better be ſeen.*

FIG. I

FIG. II.



3,4. *The* Anaſtomoſis, *or inoculation of the foreſaid veſſels, making the conſent of the* Abdomen *and the noſe, and of the womb with the breaſts, as ſome think.* LL *Branches of veins running into the ſides of the* Peritonæum. N *The place of the Haunch-bone bared, to which the oblique and tranſverſe muſcles do grow.*

The Pyramidal or aſſiſting muſcles.

The tranſverſe muſcles of the *Epigaſtrium.*

Some (moved with I know not what reaſon) would have theſe two ſmall muſcles to help the erection of the yard. *Columbus* thinks they ſhould not be ſeparated from the right, and that they only are the fleſhy beginnings of the right. But on the contrary, *Fallopius* manifeſtly proves them different and ſeparate from the right, and ſhews their uſe. The tranſverſe remain to be ſpoken of, ſo called by reaſon of their fibers, which make right angles with the fibers of the right muſcles.

They

They have a quadrangular figure ſituate upon the greateſt part of the *Peritonæum*, to which they ſtick ſo cloſe that they ſcarce can be ſeparated. They take their original from the production of the loins, the eminency of the haunch-bone, the tranſverſe productions of the *Vertebra*'s of the loins, and the ends of the baſtard-ribs; contrary to the opinion of many, whom the inſertion of the nerve convinces, but they end in the White-line, as all the reſt do. Their figure and ſite.

Their action is to paſs the guts, eſpecially for the expulſion of excrements. Their action.

But all the eight recited muſcles, beſide their proper uſe, have another common; that is, they ſtand for a Defence or Bulwark, for all the parts lying under them, and ſerve for the ſtrengthening of the voice, as experience ſhews in thoſe who ſound Trumpets and Cornets. The common uſe and action of the eight muſcles of the *Epigaſtrium*.

Therefore theſe muſcles do equally on every ſide preſs the belly; but the midriff, the intercoſtal muſcles aſſiſting it, doth drive from above downwards, from which conſpiring contention follows the excretion of the excrements by the fundament; but unleſs the midriff ſhould aſſiſt, theſe muſcles would preſs the excrements no more downwards, than upwards to the mouth.

Although to this excretion of the excrements, it is not ſufficient that the Epigaſtrick, Midriff, and intercoſtal muſcles preſs the belly, but the muſcles of the throttle muſt be alſo ſhut. For the mouth being open, the excrements never go well forth; becauſe the vapors do paſs out of the mouth, which being reſtrained and driven to the midriff, by ſtretching it powerfully thruſts down the excrement. Wherefore Apothecaries when they give glyſters, bid the Patient to open his mouth, that the glyſter may eaſily go up, which otherwiſe would ſcarcely go up, the mouth being ſhut; becauſe ſo, we ſhould have no place empty in us, into which the glyſter might be admitted. Why when the mouth is open, the excrements go more ſlowly forth.

Of the White-line, and Peritonæum or Rim of the Belly.

THe White-line is nothing elſe, than the bound and extremities of the muſcles of the *Epigaſtrium*, diſtinguiſhing the belly in the midſt into two parts, the right and left. It is called White, both of its own colour, and alſo for that no fleſhy part lies under it, or is placed above it. It is broader above the navel, but narrower below, becauſe the right muſcles do there grow into one. Now we muſt treat of the coat or membrane, *Peritonæum* or rim of the belly; it is ſo called, becauſe it is ſtretched over all the lower belly, and particularly over all the parts contained in the ventricle, to which alſo it freely lends a common coat. It hath a ſpermatick ſubſtance, as all other membranes have; the quantity of it in thickneſs is very ſmall, (for it is almoſt as thin as a Spiders web) yet differing in divers places in men and women; for men have it more thick and ſtrong below the navel, that ſo it may contain the extenſion of the ſtomach, often ſtretched beyond meaſure with meat and drink. On the contrary, women have it ſo thick and ſtrong below their navel, that it ſeems double, that ſo they may more eaſily endure the diſtention of their womb, cauſed by the child contained in it. But above the navel, men and women have the *Peritanæum* of an equal ſtrength, for the ſelf ſame reaſon. The longitude and latitude of it is known by the circumſcription of the belly. What the White-line is. What the *Peritonæum* is. The ſubſtance and quantity.

The figure is round and ſomewhat long; it puts forth ſome productions, like finger-ſtalls, both for the leading and ſtrengthening the ſpermatick veſſels, and the eremaſter muſcles of the teſticles, and, beſides it, the ejaculatory veſſels; as alſo to impart a coat to the teſticles, and all the natural parts. The figure.

It is compoſed of ſlender, membranous and nervous fibers, certain ſmall branches of veins and arteries concurring with them, which it receives for life and nouriſhment from the adherent parts. The compoſition.

This membrane is one in number, and beſides every where one and equal, although *Galen* would have it perforated in that place where the ſpermatick veſſels deſcend to the teſticles: But, in truth, we muſt not think that a hole, but rather a production, as we ſaid before. The number. *Lib. de ſem.*

The later Anatomiſts have obſerved, the coat *Peritonæum* is doubled below the navel, and that by the ſpaces of theſe reduplications the umbilical arteries aſcend to the navel.

It is ſituate near the natural parts, and compaſſes them about, and joyned by the coat, which it gives them, as alſo on the ſides, it is joyned to the *Vertebra's* of the loins, from whoſe ligaments (or rather *Perioſteum*) it takes the original: On the lower part, it cleaves to the ſhare-bone, and on the upper to the midriff, whoſe lower part it wholly inveſts; on the fore or outer part it ſticks ſo cloſe to the tranſverſe muſcles, that it cannot be pluck'd from them but by force, by reaſon of the complication and adheſion of the fibers thereof with the fibers of the proper membrane of theſe muſcles; which membrane in *Galen*'s opinion proceeds from this *Peritonæum*, ſo that it is no marvel that we may more eaſily break than ſeparate theſe two coats. It is of temperature cold and dry, as all other membranes. The ſite and connexion. *Lib. 6. Meth.*

It hath many uſes, the firſt whereof is, to inveſt and cover all the parts of the lower belly, eſpecially the kall, leſt it ſhould be ſqueezed by great compreſſures and violent attempts into the empty ſpaces of the muſcles, as it ſometimes happens in the wounds of the *Epigaſtrium*, unleſs the lips of the Ulcer be very well united; for then appears a tumor about the wound by the guts and kall thruſting without the *Peritonæum* into thoſe ſpaces of the muſcles; from whence proceeds cruel pain. Uſe.

Another uſe is, to the further caſting forth of the excrements by preſſing the ventricle and guts on the foreſide, as the midriff doth above, as one ſhould do it by both his hands joyned together.

The third uſe is, it prohibits the repletion of the parts with flatulency after the expulſion of the excrements, by ſtraitning and preſſing them down,

The fourth and laſt is, that it contains all the parts in their ſeat, and binds them to the backbone, principally that they ſhould not fly out of their places by violent motions, as by leaping, and falling from on high.

Laſtly, we muſt know, that the rim is of that nature, that it will eaſily dilate it ſelf, as we ſee in Dropſies, in women with child, and in tumors againſt nature.

CHAP. XIII.

Of the Epiploon, Omentum, or Zirbus, that is the Kall.

The ſubſtance, magnitude, figure.

After the containing parts, follow the contained, the firſt of which is the *Epiploon*, (or Kall) ſo called, becauſe it (as it were) ſwims upon all the guts. The ſubſtance of it is fatty and ſpermatick, the quantity of it for the thickneſs is diverſe, in divers men, according to their temperament. The latitude of it is deſcribed by the quantity of the guts. It is in figure like a purſe, becauſe it's double. It is compoſed of veins, arteries, fat, and a membrane, which ſliding down from the gibbous part of the ventricle, and the flat part of the gut *Duodenum* and Spleen over the guts, is turned back from the lower belly to the top of the Colon. It is one as we ſaid covering the guts. It hath its chief connexion with the firſt *Vertebra's* of the Lions, from which place in Beaſts it ſeems to take a Coat, as in men from the hollow part of the Spleen, and gibbous of the ventricle, and depreſſed part of the *Duodenum*; from whence doubled, it is terminated in the fore and higher part of the Colick-gut. Which moved *Galen* to write, that the upper part of the membrane of the Kall was annexed to the ventricle; but the lower, to the laxer part of the Colick-gut. From the Veſſels of which parts it borrows his, as alſo the nerves, if it have any. The temper of it in lean bodies is cold and dry, becauſe their Kall is without fat; but in fat bodies it is cold and moiſt by reaſon of the fat. The uſe of it is two-fold: The firſt is to heat and moiſten the guts, and help their concoction, although it do it by accident, as that which through the denſity of the fat, hinders the cold air from piercing in, and alſo forbids the diſſipation of the internal heat. Another uſe is, that, in want of nonriſhment in times of great famine, ſometimes it cheriſhes, and (as it were) by it dew preſerves the innate heat, both of the ventricle and neighbouring parts, as it is written by *Galen*. Moreover, we muſt obſerve, that in a rupture or relaxation of the *Peritonæum*, the Kall falls down into the *Scrotum*, from whence comes that rupture we call *Epiplocele*. But in women that are ſomewhat more fat, it thruſts it ſelf between the bladder and the neck of the womb, and by its compreſſion hinders, that the ſeed comes not with full force into the womb, and ſo fruſtrates the conception. Beſides, when by a wound or ſome other chance, any part of it be defective, then that part of the belly which anſwers to it, will afterwards remain cold and raw, by reaſon of the fore-mentioned cauſes.

The compoſure.

The connexion.

Lib. Anatom. adminiſt.

The temper.

The uſe two-fold.

Lib. 4. de uſu partium.

A cauſe of fruſtrating conception.

The ſecond Figure of the lower Belly.

A A, B B. *The inner part of the* Peritonæum, *cut into four parts, and ſo turned backward.*

B *The upper* B. *ſheweth the implantation of Umbilical vein into the liver.*

C *The navel ſeparated from the* Peritonæum. *From* D *to the upper* B *the Umbilical veins.*

E E *The forepart of the ſtomach blown up, neither covered by the liver nor kall.*

F F *A part of the* Gibbous *ſide of the liver.*

G *Veſſels diſſeminated through the* Peritonæum.

* *The Breaſt-blade.*

H *The bottom of the bladder of urine.*

I *The connexion of the* Peritonæum *to the bottom of the bladder.*

K K K K *The kall covering the guts.*

M N *Veſſels and ſinews embracing the bottom of the ſtomach.*

O *The meeting of the veſſels of both ſides; ſo that* M N *and* O *ſhew the ſeam which* Ariſtotle *mentions*, 3 Hiſt. & 4. de part. Anim. *where he ſaith, That the kall ariſes and proceeds from the midſt of the belly.*

P P *Branches of veſſels running alongſt the bottom of the ſtomach.*

Q Q Q Q *Certain branches of the veſſels diſtributed to the upper membrane of the* Omentum, *and compaſſed with fat.*

a a *The two Umbilical arteries going down by the ſides of the bladder to a branch of the great artery.*

b *The ligament of the bladder which is ſhewed for the* Urachus.

CHAP.

CHAP. XIV.

Of the Ventricle or Stomach.

NOw we muſt ſpeak of the ſtomach; the receptacle of the food neceſſary for the whole body, the ſeat of appetite, by reaſon of the nerves diſperſed into its upper orifice, and ſo into its whole ſubſtance. The ſubſtance thereof is rather ſpermatick than ſanguine, becauſe that for one fleſhy membrane, it hath two nervous: The quantity or magnitude of the ventricle is diverſe, according to the various magnitudes of bodies, and gluttony of men. The figure of it is round and ſomewhat long, like a Bag-pipe. The ſtomach is compoſed of two proper coats, and one common from the *Peritonæum*, together with veins, ſinews, and arteries; the innermoſt of its proper coats is membranous, woven with right fibers, for the attraction of meats; it is extended and propagated even to the mouth thereof, whereby it comes to paſs that the affections of one part may eaſily be communicated to the other by ſympathy or conſent. This coat hath its original from the membranes of the brain which accompany the nerves deſcending from the the third and fourth conjugation to the mouth thereof. And in like ſort from other productions deſcending by the paſſages of the head, from whence alſo another reaſon may be drawn from that, which they commonly bring from the nerves of the ſixth conjugation; why in wounds of the head, the ſtomach doth ſo ſoon ſuffer by conſent with the brain? The exterior or outer is more fleſhy and thick, woven with oblique fibers, to retain and expel. It draws its original from the *Pericranium*, which aſſoon as it comes to the gullet, takes unto it certain fleſhy fibers. There be nerves ſent into the ſtomach from the ſixth conjugation of the brain, as it ſhall be ſhewed in its proper place. Veins and arteries are ſpread into it from the *Gaſtrica*, the *Gaſtrepiploides*, the *Coronaria* and Splenick, from the ſecond, third and fourth diſtribution of the *Vena-porta*, or Gate-vein; and the third of the deſcendent artery to the natural parts, aſſoon as it paſſes forth of the midriff.

What the ventricle is. The ſubſtance. The magnitude. The figure. The compoſure. The cauſe of the conſent of the mouth and ſtomach.

It is one in number, The greater part of it is ſituated on the left ſide, between the Spleen, the hollowneſs of the liver and the guts, that, aſſiſted by the heat of ſuch neighbouring parts, it may more chearfully perform the concoction of the meat. Neither am I ignorant that *Galen* hath written, that a great part of the ſtomach lies on the left ſide. But Inſpection it ſelf and Reaſon, makes me derogate from *Galen*'s authority: for, becauſe there is more empty ſpace on the left ſide, by reaſon the Spleen is leſs than the Liver, it was fit it ſhould lie more on the left ſide. The more proper connexion of it is with the gullet and guts, by its two orifices; with the brain, by its nerves; with the liver and ſpleen, by its veins; with the heart by it arteries; and with all the natural parts by its common membrane.

The number. *Lib. de uſu partium.* The connexion.

The temper of the ventricle in men of good habit, is temperate, becauſe it is almoſt compoſed of the equal commixture of ſanguine and ſpermatick parts; or according to *Galen*'s opinion, it is cold of it ſelf, and by the parts compoſing it; and hot by the vicinity of the bowels. But in ſome it is hotter, in others colder, according to the diverſe temper and complexion of divers bodies. That ſtomach is to be thought well tempered, that powerfully draws down the meat and drink, and embraces and retains them ſo drawn, until by concoction and elixation, they ſhall be turned into a juyce like cream (which the *Greeks* call *Chylos*;) and laſtly, which doth ſtrongly ſend from it, and repel the excrements of this firſt concoction.

The temper. *Lib. 9. Meth.*

The ſtomach is known to be hotter by this, that it better concocts and digeſts coarſe and hard meats, as Beef, hard Eggs, and the like, than ſoft meats eaſie of digeſtion, which it corrupts and turns into belchings. For ſo a young Chicken, is ſooner burnt than well roaſted at a great fire. The ſtomach which is colder, deſires much meat, but is ſlow in concocting them, eſpecially if they be cold and hard of digeſtion, which for that cauſe quickly turn ſower. The action of a well conditioned ſtomach is twofold, one common, another proper. The common is to attenuate, mix and digeſt the meats taken in at the mouth, for the nutrition of it ſelf and the whole body, after the liver hath performed its duty, which before it be done, the ventricle only enjoys the ſweet pleaſure of the *Chylus*, and comforts it ſelf againſt the impurity of the adjacent parts, whereof it is called the work-houſe of concoction. Its firſt action is to attract, retain, and aſſimilate to it ſelf that which is convenient; but to expel whatſoever ſhall be contrary, either in quantity or quality, or in the whole ſubſtance.

Notes of a hot ſtomach. The action twofold.

It hath two orifices, one above, which they commonly call the ſtomach and heart, the other lower, which is called the *Pylorus*, or lower mouth of the ſtomach. The upper bends to the left ſide near the back-bone; it is far more large and capacious than the lower, that ſo it may more commodiouſly receive meats half-chewed, hard and groſs. which Gluttons caſt down with great greedineſs; it hath an exquiſite ſenſe of feeling, becauſe it is the ſeat of the appetite, by reaſon of the nerves incompaſſing this orifice, with their mutual imbracings; whereby it happens that the ventricle in that part is endued with a quick ſenſe, that perceiving the want and emptineſs of meat, it may ſtir up the creature to ſeek food. For albeit nature hath beſtowed four faculties on other parts, yet they are not ſenſible of their wants, but are only nouriſhed by the continual ſucking of the veins, as Plants by juyce drawn from the earth.

The two orifices of the ſtomach.

This orifice is ſeated at the fifth *Vertebra* of the cheſt, upon which they ſay it almoſt reſts. Yet I had rather ſay, that it lies upon the twelfth *Vertebra* of the cheſt, and the firſt of the loins; for in this place the gullet perforates the midriff, and makes this upper orifice. The lower orifice bends rather to the right ſide of the body, under the cavity of the liver. It is far ſtraiter than the upper, leſt any thing ſhould paſs away before it be well attenuated and concocted; and it doth that by the help or aſſiſtance of, as it were, a certain ring, like to the ſphincter muſcle of the fundament, which ſome have thought a glandule made by the tranſpoſition of the inner and fleſhy membrane

The ſite. The glandulous ring of the *Pylorus*.

membrane of the ventricle into that which is the outer of the guts. I know *Columbus* laughs at this glandulous ring, but any one that looks more attentively, ſhall perceive that *Pylorus* is glandulous. The ſtomach in its lower and inner ſide, hath many folds and wrinkles, which ſerve to hold and contain the meats, until they be perfectly concocted. In the ventricle, we obſerve parts gibbous and hollow; the hollow is next to the liver and midriff; the gibbous is towards the guts. Now we muſt note that the ventricle, when it is much reſolved or looſed, may ſlide down even to the navil near the bladder, the which we have obſerved in ſome bodies diſſected after their death.

The falling down of the ſtomach.

The third and fourth Figures.



The firſt figure ſhews the fore-ſide of the ſtomach and gullet.

A *ſheweth the orifice of the gullet cut from the throat.*

B *the ſtrait and direct courſe of the gullet from* A *to* B.

C *how the gullet above the firſt rack-bone of the cheſt, from* B *to* C *inclineth to the right hand.*

D *his inclination to the left hand, from* C *to* D.

E E *the two glandules called the Almonds, ſet cloſe to the gullet in the end of the throat, called alſo* Pariſtmia, Antiades, Tonſillæ, *and* Salviares glandulæ.

F F *another glandulous body in the midſt of the gullet, about the fifth rack-bone, from which place the gullet gives place to the great artery, ſomewhat declining to the right ſide:* Væſalius, *lib.* 5. *c.* 3. *and* Columbus, *c.ult. l.* 9. *write, that thoſe glandules are filled with a certain moiſture, with which the gullet is moiſtened that the meats may ſlide down more eaſily into the ſtomach, as through a ſlippery paſſage. No otherwiſe than the* Glandulæ proſtatæ, *filled with a kind of groſs and oily moiſture, ſmooth the paſſage of the urine, that ſo it may flow through it, with a more free and leſs troubled courſe.* G *the connexion of the gullet with the ſtomach, where the upper orifice of the ſtomach is faſhioned.* H *the lower orifice of the ſtomach called* Pylorus. I K *the upper part of the ſtomach at* I. *the lower at* K LL *the foreſide of the ſtomach.* P *the gullet called* Duodenum. T V *the right and left nerves of the ſixth pair, encompaſſing about the gullet and the uppermoſt left orifice of the ſtomach.*

The ſecond Figure ſheweth the back-parts of the Ventricle and Gullet.

A EE FF G H P TV *ſhew the like parts as in the former. From* C *to* D *the inclination of the ſtomach to the left hand.* M N O *the back-ſide of the ſtomach.* M *ſheweth the prominence of the left ſide.* N *of the right.* O *ſheweth the dock or impreſſion, where it reſteth upon the rack-bones.* Q R *the paſſage of the bladder of the gall into the* Duodenum *at* R. S *a glandulous body growing under the* Duodenum, *bearing up the veſſels.* X Y *a nerve on the left ſide creeping up to the top of the ſtomach, and ſo running out to the liver.*

CHAP. XIV.

Of the Guts.

Their ſubſtance.

THe Guts the inſtruments of diſtribution and expulſion, are of the ſame ſubſtance and compoſure with the ſtomach, but that the ſite of the coats of the ſtomach is contrary to thoſe of the guts. For that which is the innermoſt coat of the ſtomach, is the outermoſt of the guts, and ſo on the contrary.

Figure.

The figure of the guts is round, hollow and capacious, ſome more, ſome leſs, according to the diverſe bigneſs.

Their number.

But for the quantity of the guts, ſome are ſmall, ſome great, more or leſs, according to the varieties of bodies. But they are ſix in number: For there be three ſmall; the *Duodenum*, the *Jejunum*, or empty gut, and the *Ileon*. Three great, the Blind, the Colick, and the Right-gut. All which have had their names for the following reaſons; the firſt, becauſe it is extended the length of twelve fingers, like another ſtomach, without any turning or winding; of which greatneſs it is found in great bodied men, ſuch as were more frequently to be met withal in *Galen*'s time, than in this time of ours; in which, this gut is found no longer than ſeven, eight or nine fingers at the moſt. The cauſe of this length is, that there may be a free paſſage to the Gate-vein, coming out of the liver, as alſo the artery and nerve which run into it. For ſeeing that this

The *Duodenum*.

gut

gut may ſometimes riſe to the top of the liver, it would poſſeſs the ſpace under the bladder of the gall (with which it is often tinctured) if it had any revolutions that way, which is the paſſage for ſuch like veſſels. Others give another reaſon of this figure, which is, That there ſhould be nothing to hinder the eaſie and fit diſtribution of the perfectly concocted *Chylus* to the liver.

The ſecond is called *Jejunum*, or the empty-gut, not becauſe it is abſolutely ſo, but becauſe it contains little in compariſon of the other. There is a triple cauſe of this emptineſs, the firſt the multitude of the meſeraick veins and arteries which are about it, whereupon there is a greater and quicker diſtribution of the *Chylus*. The ſecond is the vicinity or neighbourhood of the liver, ſtrongly drawing the *Chylus* contained in it; the third is the flowing down of the Cholerick humor from the bladder of the gall into it, which ever and anon by its acrimony cleanſes away the filth, and by continual flowing ſolicites it to expulſion. The third is called *Ileon*, becauſe it lies between the *Ilia*, or flanks; it differs nothing from the reſt in ſubſtance and magnitude, but in this one thing, that there is more matter contained in it than in the reſt, by reaſon of the paucity of the veſſels terminated in it, that it is no marvel that there can be no exact demonſtration made of them. The fourth is called *Cæcum*, or the blind, becauſe it hath but one paſſage to ſend out and receive in the matter. This gut hath a long and ſtrait production, which, according to the opinion of ſome (though altogether erroneous) often falls down into the *Scrotum* in the rupture, or relaxation of the rim of the belly; for, that production in the lower belly ſtrongly ſticks to the *Peritonæum*, or rim, which hinders ſuch falling down. But *Galen* ſeems by ſuch a blind-gut to have meant this long and narrow production; and certainly, ſo thinks the common ſort of Anatomiſts; but here *Veſalius* juſtly reprehended *Galen*. Wherefore *Sylvius* that he might free *Galen* of this fault, would have us by the blind-gut to underſtand the beginning of the colick-gut. The fifth is called *Colon* (or colick-gut) becauſe it is greater and more capacious than the reſt. The ſixth and laſt, the right-gut, by reaſon of the rightneſs or ſtraitneſs of the paſſage. This, in Beaſts, eſpecially, hath a certain fatneſs in it to make the paſſage ſlippery, and leſt the guts ſhould be exulcerated in the paſſage, by the ſharpneſs of hard and acrid excrements.

The Jejunum. *Ileon.* *Cæcum.* *Colon.* *Rectum.*

The ſite of theſe guts is thus: The *Duodenum* upon the back-bone bends to the right hand; the *Jejunum* poſſeſſes a great part of the upper umbilical region, and diffuſes it ſelf into both ſides with windings, like to thoſe of the gut *Ileum*, even to the flanks. The gut *Ileon* is ſituate at the lower part of the umbilical region, going with many turnings and winding, even to the hollowneſſes of the holy bone, above the bladder and ſide parts of the *Hypogaſtrium*, they call the flanks.

Their ſite.

The blind bends to the right hand, a little below the kidney, above the firſt and fourth *Vertebræ* of the loins. The Colon or colick-gut is crooked or bent, in the form of a *Scythian*-bow, filling all the ſpace from the blind-gut, below the right kidney, even to the hollowneſs of the liver, and then it goes by the gibbous part of the ſtomach above the ſmall-guts, even to the hollowneſs of the Spleen; from whence ſliding under the left kidney, with ſome turnings, it is terminated upon the *Vertebra's* of the loins.

By all which turnings and windings of the colick-gut, it is eaſie to diſtinguiſh the pain of the Stone of the kidneys, which remain fixt in one certain place, from the colick wandring through thoſe crooked paſſages we mentioned. The right-gut tends with an oblique ſite towards the left hand, upon the holy-bone even to the very fundament. They have all one and a common connexion; for they are all mutually joyned together by their coats, becauſe there is but one way from the gullet even to the fundament; but they are joyned to the principal parts by their nerves, veins and arteries.

The diſtinction between the colick and the ſtone in the kidneys. *Their connexion.*

But a more proper connexion is that, where the *Duodenum* on the upper part of it, is joyned with the *Pylorus*; but on the lower part to the *Jejunum*, and the parts lying under it, by the coat of the *Peritonæum*. The *Jejunum*, or empty-gut, is joyned to the *Duodenum* and *Ileon*. The *Ileon*, with the empty blind-guts. The blind with the *Ileon* and *Colon*, and with the right ſide of the back-bone where it is tied more ſtraitly. The *Colon* with the blind and right-guts, and in his middle part, with the kidneys and gibbous part of the ſtomach; whereby it comes to paſs, that being diſtended with wind in the colick, it over-turns and preſſes the ſtomach, and ſo cauſes vomiting.

Why vomiting happens in the colick.

Laſtly, the right-gut is annexed with the colick-gut and fundament. At the end whereof there is a muſcle faſtned, of figure round and circular, called the *Sphincter*, ariſing from the lower *Vertebra's* of the holy bone and rump; by the benefit of which, as of a door or gate, the excrements are reſtrained at our will, leſt man born for all honeſt actions, without all ſhame, in every time and place, ſhould be forced every where to eaſe his belly. For ſuch as have loſt the benefit of this muſcle by the Palſie, have their excrements go from them againſt their wills. There is a body ſituate at the end of the right-gut, and of a middle ſubſtance between the skin and fleſh, as it were ariſing from the mixture of them both, like the extremities of the lips, of the ſame uſe with the *Sphincter*, but that it is not altogether ſo powerful. But there are alſo certain veins ſituate about it called the Hæmorrhoidal; of which we will ſpeak in their place.

The Sphincter muſcles of the fundament. *Gal. lib. 5. de uſu partium. cap. 14.*

Beſides, there are two other muſcles that deſcend to the end of this gut, being broad and membranous on each ſide, one ariſing from the ſide and inner parts of the ſhare and hip-bones, which inſerted above the *Sphincter* pull up the fundament falling down, wherefore they are called *Levatores Ani*, or the lifters up of the fundament. Wherefore when as either they are too weak, or reſolved, or the fundament oppreſſed with the weight of flegmatick, ſalt, cholerick and ſharp humors, the gut is ſcarce reſtored into its place, that there is need of the help of the fingers for that purpoſe.

Levatores Ani.

The guts follow the temper of the ſtomach. Their action is the diſtributing the *Chylus* by the meſeraick veins (which of duty belongs to the three ſmall guts) and the receiving the excrements of the *Chylus*, and retention of them, till a fit time of expulſion, which belongs to the third quarter. Beſides, theſe ſmall guts finiſh up the work of concoction, begun in the ſtomach, although

The action of the guts.

though they be not altogether made for that uſe. But nature is often accuſtomed to abuſe the parts of the body for ſome better uſe.

Their fibers. But we muſt note, that for the compoſure of the guts, they have only tranſverſe fibers, for expulſions ſake, unleſs that at the beginning of the *Colon*, and the end of the right gut, you may ſee certain right fibers added to the tranſverſe to ſtrengthen them, leſt theſe guts ſhould chance to be broken and torn by the paſſage of hard excrements, and the laborious endeavour of expulſion, (ſpecially in brute beaſts.)

The fifth figure, of the lower Belly.

A *The breaſt-blade,* Cartilago Enſiformis.

BB *The rim, with the midriff and broken ribs bent outwards.*

C C *The gibbous part of the liver.*

D *A ligament tying the liver to the midriff.*

E *Part of the umbilical vein.*

F F *The ſtomach fill'd full of meat.*

G *A part of the ſpleen.*

H *The blind-gut of the late Writers, for the Ancients took the top of the* Colon *for it.*

I *The beginning of the great or thick guts.*

I *And ſo to* K, *ſheweth the paſſages of the colick-gut from the right kidney to the liver. And ſo the colick and the ſtone on this ſide are in one place, and therefore hardly diſtinguiſhed.*

K *to* L *The ſame colick-gut lieth under the whole bottom of the ſtomach, which is the reaſon that thoſe which are troubled with the colick caſt ſo much.*

L *to* M *The paſſage of the* Colon *from the ſpleen to the ſhare-bone, by the left kidney, a way which maketh the pain of the ſtone and the colick on the left ſide, very hard to diſtinguiſh.*

N *The* Colon *ending in the right gut.*

O *The beginning of the right gut, unto the bladder.*

P Q *The ſunken or fallen ſide of the* Colon *at* P, *and his chambers or cells at* Q R S T. *the leſſer guts eſpecially lying under the navel.*

a a *The two umbilical arteries.*

b *The bottom of the bladder.* * *The connexion of the bladder and the* Peritonæum.

How the guts become fit to retain. But if any ask, how they have retention, being they want oblique fibers; he may know, that the *fæces* are retained in the right-gut, by the force of the *Sphincter*-muſcle, but oft-times in the blind, by their hardneſs and abundance, whereby they ſtick in the paſſage; but in the reſt, by reaſon of their conformation into many windings and turnings.

Their length. The length of the guts, is ſeven times more than the length of the whole body: to this length they have windings, leſt the nouriſhment ſhould quickly ſlide away, and leſt men ſhould be with-drawn by gluttony from action and contemplation. For ſo we ſee it comes to paſs in moſt Beaſts, which have one gut, ſtretched ſtrait out from the ſtomach to the fundament; as in the Lynx, and ſuch other Beaſts of inſatiable gluttony, always, like Plants, regarding their food.

CHAP. XV.

Of the Meſentery.

The ſubſtance. Magnitude. Figure. Compoſure. After the guts follows the Meſentery, being partly of a fatty, and partly of a ſpermatick ſubſtance. The greatneſs of it is apparent enough, although in ſome it be bigger, and in ſome leſſer, according to the greatneſs of the body. It is of a round figure, and not very thick. It is compoſed of a double coat ariſing from the beginning and root of the *Peritoneum.* In the the midſt thereof, it admits nerves from the Coſtal of the ſixth Conjugation; veins from the *Vena Porta*, or gate-vein; arteries from the deſcendent artery, over and beſides a great quantity of fat and many glandulous bodies, to prop up the diviſion of the veſſels ſpread over it, as alſo to moiſten their ſubſtance.

Number. It is in number one, ſituate in the middle of the guts, from whence it took its name.

The connexion. Yet ſome divide it into two parts, to wit, into the *Meſeræum*, that is, the portion interwoven with the ſmall guts, and into the *Meſo-colon* which is joyned with the great. It hath connexion by its veſſels, with the principal parts, by its whole ſubſtance with the guts, and in ſome ſort with the kidneys, from whoſe region it ſeems to take its coats.

The temper. It is of a cold and moiſt temper, if you have reſpect to his fatty ſubſtance; but if to the reſt of the parts, cold and dry.

The

The action and use of it is, to bind and hold together the guts, each in his place, lest they should rashly be folded together, and by the Meseraick-veins (which they term the hands of the liver) carry the *Chylus* to the liver. The action and use.

In which you must note, that all the meseraick veins come from the liver, as we understand by the dissection of bodies; although some have affirmed, that there be some veins serving for the nourishment of the guts, no ways appertaining to the liver, but which end in certain glandulous bodies, dispersed through the mesentery, of whose use we will treat hereafter. All the meseraick veins come from the liver.

CHAP. XVI.

Of the Glandules in general, and of the Pancreas, *or Sweet-bread.*

A Glandule is a simple part of the body; sometimes of a spongy and soft substance, sometimes of a dense and hard. Of the soft Glandules are the *Tonsillæ* (or Almonds, like in substance to blanched Almonds,) the *Thymus*, *Pancreas*, *Testicles*, *Prostatæ*. But the dense and hard are the *Parotides*, and other like. The Glandules differ amongst themselves in quantity and figure, for some are greater than other some, and some are round, and others plain, as the *Thymus* and *Pancreas*. Substance of the glandules. Quantity and figure.

Others are compounded of veins, nerves, arteries, and their proper flesh, as the Almonds of the ears, the milky glandules in the breasts and the testicles. Others want nerves, at least which may be seen, as the *Parotides*, the axillary, or those under the arm-holes, and others. The number of glandules is uncertain, by reason of the infinite multitude and variety of sporting nature. You shall find them always in those places, where the great divisions of vessels are made, as in the middle ventricle of the brain, in the upper part of the chest, in the mesentery, and other like places. Composition. Number.

Although othersome be seated in such places, as nature thinks needful to generate and cast forth of them a profitable humor to the creature; as the Almonds at the root of the tongue, the kernels in the dugs, the spermatick vessels in the *scortum*, and at the sides of the womb; or where Nature hath decreed to make emunctories for the principal parts, as behind the ears, under the arm-holes, and in the groins. The connexion of glandules is not only with the vessels of the parts concurring to their composition, but also with those, whose division they keep and preserve. They are of a cold temper, wherefore Physicians say, the blood *recrudescere*, i.e. to become raw again in the dugs, when it takes upon it the form of milk. But of these some have action, as the Almonds, which pour out spattle useful for the whole mouth, the dugs milk, the testicles seed; others, use only, as those which are made to preserve, under-prop and fill up the divisions of the vessels. Besides this, we have spoken of glandules in general, we must know, that the *Pancreas*, is a glandulous and flesh-like body, as that which hath every where the shape and resemblance of flesh. It is situate at the flat end of the liver, under the *Duodenum*, with which it hath great connexion, and under the gate-vein, to serve as a Bulwark both to it and the divisions thereof, whilst it fills up the empty spaces between the vessels themselves, and so hinders, that they be not pluck'd asunder, nor hurt by any violent motion, as a fall or the like. Connexion. Temper. Action and use. The substance of the *Pancreas*. The site.

CHAP. XVII.

Of the Liver.

HAving gone thus far, order of dissection now requires, that we should treat of the distribution of the gate-vein; but, because it cannot well be understood unless all the nature of the liver from whence it arises, be well known, therefore putting it off to a more fit place, we will now speak of the liver. Wherefore the liver (according to *Galen*'s opinion, *lib. de Form. fœtus*) is the first of all the parts of the body, which is finished in conformation. It is the shop and author of the blood, and the original of the veins; the substance of it is like the concrete mud of the blood, the quantity of it is diverse, not only in bodies of different, but also of the same species; as in men amongst themselves, of whom one will be gluttonous and fearful, and another bold, and temperate or sober; for he shall have a greater liver than this, because it must conceive and concoct a greater quantity of *Chylus*: yet the liver is great in all men, because they have need of a great quantity of blood for the repairing of so many spirits, and the substantifick moisture, which are resolved and dissipated in every moment by action and contemplation. But there may be a twofold reason given, why such as are fearful have a larger liver. The first is, because in those the vital faculty (in which the heat of courage and anger resides) which is in the heart, is weak; and therefore the defect of it must be supplied by the strength of the natural faculty. For thus nature is accustomed to recompence that which is wanting in one part, by the increase and accession of another. The other reason is, because cold men have a great appetite; for by *Galen*'s opinion *In arte parva*, coldness increases the appetite; by which it comes to pass that they have a greater quantity of *Chylus*, by which plenty the liver is nourished and grows larger. Some Beasts, as Dogs and Swine, the liver divided into five or more Lobes, but a man hath but one Lobe, or two or three at the most; and these not so much distinguished, as which cherish the upper and hollow region of the ventricle, with embracing to help forward the work of concoction. Therefore the liver is almost content with one Lobe, although it is always rent with a small division, that the umbilical vein piercing into the roots and substance of it, may have a free passage; but also oftentimes there is, as it were, a certain small Lobe of the liver, laid under that umbilical vein, as a cushion. What the liver is. The substance and quantity. Why Cowards have great livers.

The

The figure. The figure of the liver is gibbous; riſing up and ſmooth towards the midriff; towards the ſtomach is the *ſimous* or hollow ſide of it ſomewhat unequal, and rough by reaſon of the diſtance of the Lobes, the original of the hollow-vein, and the ſite of the bladder of the gall.

The compoſure. The veſſels. The compoſition of the liver is of veins, nerves, arteries, the coat and proper ſubſtance thereof which we call the groſs and concrete blood, or *Parenchyma*. Veins and arteries come to it from the navil; but nerves immediately from theſe which are diffuſed over the ſtomach according to *Hippocrates*; yet they penetrate not very deep into its ſubſtance; for it ſeems not to ſtand in need of ſuch exact ſenſe, but they are diſtributed upon the coat and ſurface thereof, becauſe this part made for diſtribution over the whole body, keeps to it ſelf no acrid or malign humor; for the perception of which it ſhould need a nerve, although the coat inveſting it, ſends many nervous fibers into its ſubſtance, as is apparent by the taking away of the coat from a boiled liver; we muſt think the ſame of the other entrails. The coat of the liver is from the *Peritonæum*, waxing ſmall from the umbilical vein,

The number and ſite. The connexion. when it divides it ſelf for the generation of the gate and hollow veins, as is obſerved by *Galen*, *Lib. de format. Fœtus*. The liver is only one, ſituate in the greater part on the right ſide, but with the leſſer part on the left, quite contrary to the ſtomach. Its chief connexion is with the ſtomach and guts, by the veins and membranes of the *Peritonæum*; by the hollow vein and artery, with the heart; by the

The temper. nerve with the brain; and by the ſame ligatures with all the parts of the whole body. It is of a hot and moiſt temper, and ſuch as have it more hot, have large veins and hot blood; but ſuch as have it

The action. cold, have ſmall veins, and a diſcoloured hew. The action of the liver is the converſion of *Chylus* into the blood, the work of the ſecond concoction. For although the *Chylus* entring into the meſeraick veins, receive ſome reſemblance of blood, yet it acquires not the form and perfection of blood, before

The ligaments. it be elaborate, and fully concoct in the liver. It is bound and tied with three ſtrong ligaments, two on the ſides in the midſt of the baſtard ribs, to bear up its ſides, and the third more highand ſtrong, deſcending from the blade, to ſuſtain its proper part, which with its weight would preſs the lower orifice of the ſtomach, and ſo cauſe a falling or drawing down of the ſternon and collar-bone. And thus much may ſuffice for its proper ligaments, for we before-mentioned its common; the veins, arteries, nerves, and coat of the *Peritonæum*, by which it is knit to the loins and other natural parts. But we muſt note, that beſides theſe three proper ligaments, the liver is alſo bound with others to the baſtard-ribs; as *Sylvius* obſerves in his Anatomical obſervations, and *Hollerius* in his Practice, *c. de Plurit.*

CHAP. XVIII.

Of the Bladder of the Gall.

The ſubſtance greatneſs and figure thereof. NOw we muſt come to the bladder of the gall, which is of a nervous ſubſtance, and of the bigneſs of a ſmall pear; it is of figure round, with the bottom more large, but the ſides and mouth more narrow and ſtrait. It is compoſed of a double coat, one proper, conſiſting of three ſorts of fibers, the other from the *Peritonæum*. It hath a vein from the *Porta* or gate-vein, and an artery from that which is diffuſed into the liver, and a nerve from the ſixth conjugation. It is

The compoſition. Number and connexion. but one, and that hid on the right ſide under the greater lobe of the liver, it is knit with the touching of its own body, and of the paſſages and channels made for the performance of its actions with the liver; and in like manner with the *Duodenum*, and not ſeldom with the ſtomach alſo, by another paſſage; and to conclude, to all the parts by its veins, nerves, arteries, and common coat. It is of a cold

Temper. Action. temper, as every nervous part is. The action of it, is to ſeparate from the liver the cholerick humor, and that excrementitious, but yet natural, by the help of the right fibers, for the purifying of the blood, and by the oblique fibers, ſo long to keep it being, until it begin to become troubleſom in quantity, or quality, or its whole ſubſtance, and then by the tranſverſe fibers, to put it down into the *Duodenum* to provoke the expulſive faculty of the guts. I know, *Fallopius* denies the texture of ſo many

The channels of the Gall. fibers, to be the miniſter of ſuch action to the gall. But *Veſalius* ſeems ſufficiently to have anſwered him. The bladder of the gall hath divers channels: for coming with a narrow neck, even to the beginning of the gate-vein, it is divided into two paſſages, the one whereof ſuffering no diviſion, is carried into the *Duodenum*, unleſs that in ſome it ſend another branch into the bottom of

Lib. 2. de Temper. the ſtomach, as is obſerved by *Galen*; which men have a miſerable and wretched life, being ſubject to cholerick vomitings, eſpecially when their ſtomachs are empty, with great pains of their ſtomach and head, as is alſo obſerved by *Galen*, cap. 74. *Artis Med.* The other, coming out of the body of the liver, divides its ſelf into two or three paſſages, again entring the ſubſtance of the liver, is divided with infinite branches, accompanying ſo many branches of the gate-vein through the ſubſtance of the liver, that ſo the blood unleſs it be moſt elaborate and pure, may not riſe into the hollow-vein, all which things Diſſection doth manifeſtly teach.

The ſixth Figure of the Bladder of the Gall.

FIG. II

M *The* Pylorus *joyned to the* Duodenum.

N *The* Duodenum *joyned to the* Pylorus.

P *Shews the bottom of the bladder of the gall.*

QQ *The holes of the bladder of the gall diſperſed through the liver, betwixt the roots of the hollow and gate-veins.*

R *The root of the gate-vein in the liver.*

S *The root of the hollow-vein in the liver.*

a *The concourſe or meeting of the paſſages of choler into one branch.*

b *The neck of the bladder into which the paſſage is inſerted,*

c *The paſſage of the gall into the* Duodenum

num. d *The* Duodenum *opened to manifeſt the* Porus Biliaris. i. e. *an Artery going to the hollow part of the Liver, and the bladder of the Gall.* f *A ſmall Nerve belonging to the Liver and the bladder of Gall, from the rib branch of the ſixth pair,* g g *The Ciſtick Twins from the Gate-veins.*

CHAP. XIX.

Of the Spleen or Milt.

BUt becauſe we cannot well ſhew the diſtribution of the Gate-vein, unleſs the Spleen be firſt taken away and removed from its ſeat: therefore before we go any further, I have thought good to treat of the Spleen. Therefore the Spleen is of a ſoft, rare, and ſpongious ſubſtance (whereby it might more eaſily receive and drink up the dregs of the bloud from the Liver) and of a fleſh more black than the Liver. For it reſembles the colour of its muddy bloud, from which it is it is generated. It is of an indifferent greatneſs, but bigger in ſome than in other-ſome, according to the diverſe temper and complexion of men. It hath, as it were, a triangular Figure, gibbous on that part, it ſticks to the Ribs and Midriff, but hollow on that part next the Stomach. It is compoſed of a Coat, the proper Fleſh, a Vein, Artery, and Nerve. The membrane comes from the *Peritonæum*, the proper fleſh from the *fæces* or dregs of bloud, or rather of the natural melancholy humour, with which it is nouriſhed. The fourth branch of the *Vena Porta* or Gate-vein, lends it a Vein; the firſt branch of the great Deſcendent Artery, preſently after the firſt entrance without the Midriff, lends it an Artery. But it receives a Nerve from the left Coſtal, from the ſixth conjugation on the inner part, by the roots of the ribs; and we may manifeſtly ſee this Nerve, not onely diſperſing it ſelf through the Coat of the Liver, but alſo penetrating with its Veſſels the proper Fleſh thereof, after the ſelf ſame manner, as we ſee it is in the Heart and Lungs. It is one in number, ſituate on the left ſide between the Stomach and the Baſtard-ribs, or rather the Midriff which deſcends to the roots. For it oft-times cleaves to the Midriff on its gibbous part by a Coat from the *Peritonæum*, as alſo on the hollow part to the Stomach, both by certain Veins which ſends it into the Ventricle, as alſo by the Kall. It hath connexion, either primarily or ſecondarily, with all the parts of the Body by theſe its Veſſels.

The Subſtance. Magnitude. Figure. Compoſition. Number and Site. Connexion.

It is of a cold and dry temper; the action and uſe of it is to ſeparate the Melancholick humor, which being feculent and droſſie, may be attenuated by the force of many Arteries diſperſed through its ſubſtance. For by their continual motion and native heat, which they carry in full force with them from the Heart, that groſs bloud puts off its groſsneſs, which the Spleen ſends away by paſſages fit for that purpoſe, retaining the ſubtler portion for its nouriſhment. The paſſages by which it purges it ſelf from the groſsneſs of the melancholy bloud, are a Vein aſcending from it into the Stomach to ſtir up the appetite by its ſourneſs, and ſtrengthen the ſubſtance thereof by its aſtriction; and alſo another Vein, which ſometimes from the Spleen-branch, ſometimes from the Gate-vein, plainly under its orifice, deſcends to the Fundament, there to make the Hæmorrhoidal Veins.

Temper and uſe.

CHAP. XX.

Of the Vena Porta *or Gate Vein, and the diſtribution thereof.*

THe Gate-vein, as alſo all the other Veins is of a ſpermatick ſubſtance, of a manifeſt largeneſs, of a round and hollow Figure, like to a Pipe or Quill. It is compoſed of its proper Coat, and one common from the *Peritonæum*. It is onely one, and that ſituate in the ſimous or hollow part of the Liver, from whence it breaks forth (or rather out of the Umbilical Vein) into the midſt of all the Guts with which it hath connexion, as alſo with the Stomach, Spleen, Sphincter of the Fundament, and *Peritonæum*, by the Coat which it receives from thence. It is of a cold and dry temper. The action of it is to ſuck the *Chylus* out of the Ventricle and Guts, and ſo to take and carry it to the Liver, until it may carry back the ſame turned into bloud for the nutriment of the Stomach, Spleen, and Guts. This Gate-vein coming out of the ſimous part of the Liver, is divided into ſix branches, that is, four ſimple, and two compound again divided into many other branches; The firſt of the ſimple aſcends from the fore-part of the trunk of the bladder of the Gall by the paſſage of the Choler (and are marked with g g) with a like Artery for life and nouriſhment, and this diſtribution is known by the name of *Cyſticæ Gemellæ*, or Cyſtick Twins. The ſecond called the *Gaſtrica* or Stomach Vein, ariſing in like manner from the forepart of the Trunk, is carried to the *Pylorus* and the ſimous or back part of the Stomach next to it.

The Subſtance and Figure. Compoſition. Number and Site. Temper and Action. Diviſion thereof into 6 branches, of which, four ſimple. 1. *Cyſticæ Gemellæ.* 2. *Gaſtrica.*

The third is called *Gaſtrepiplois*, the Stomach and Kall-Vein, which coming from the right ſide of the gate-vein goes to the gibbous part of the ſtomach next to the *Pylorus* and the right ſide of the kall.

3. *Gaſtrepiplois.*

The fourth going forth from behind on the right hand of the Gate-vein, aſcends above the root of the Meſeraick branch even to the beginning of the Gut *Jejunum* along the Gut *Duodenum*, from whence it is called *Inteſtinalis*, or the Gut-vein. And theſe are the four ſimple Branches. Now we will ſpeak of the compound.

4. *Inteſtinalis.*

The firſt is ſplenick, which is divided after the following manner. For in its firſt beginning and upper part, it ſends forth the *Coronalis*, or Crown-vein of the Stomach, which by the back-part of the Stomach aſcends into the upper and hollow part thereof; to which place, as ſoon as it arrives, it is divided again into two branches, the one whereof climbs up even to its higher orifice, the other deſcends down to the lower, ſending forth by the way other branches to the fore and back parts of the Stomach. Theſe engird and on every ſide encompaſs the Body or the Ventricle, for which cauſe they are named the Crown-veins.

Two compound. I. *Ramus Splenicus*, ſending forth, 1. *Coronalis.*

I have ſometimes obſerved this coming forth of the Trunk, a little above the orifice of the ſplenick branch. But this ſame ſplenick branch on its lower part, produces the branch of the Hæmorrhoidal Veins, which deſcending to the Fundament above the left ſide of the Loins, diffuſes a good portion thereof into the leaſt part of the Colick Gut, and the right Gut, at the end whereof it is often ſeen to be divided into five Hæmorrhoidal Veins, ſometimes more, ſometimes leſs.

2. *Hæmorrhoidalis Interna.*

Silvius writes that the Hæmorrhoidal branch deſcends from the Meſenterick: and truly we have ſometimes obſerved it to have been ſo. Yet it is more ſutable to Reaſon, that it ſhould deſcend from the Splenick, not onely for that we have ſeen with our eyes that it is ſo, but alſo becauſe it is appointed by Nature for the evacuation of the excrementitious melancholick humor. But this ſame ſplenick branch out of the middle almoſt of its upper part, produces the third branch going to the gibbous part of the Stomach and the Kall; they term it the greater, middle, and left *Gaſtrepiplois*. But on the lower part towards the Spleen, it produces the ſimple *Epiplois* or Kall-vein, which it diffuſes through the left ſide of the Kall. Moreover from its upper part, which touches the Liver, it ſends forth a ſhort branch called *Vas breve*, or *Venoſum*, to the upper orifice of the Ventricle for ſtirring up the appetite.

3. *Gaſtrepiplois major ſiniſtra.*

4. *Epiplois ſimplex.*

5. *Vas breve ſeu Venoſum.*

Lib. 4. de uſu Partium.

We have oftentimes and almoſt always obſerved, that this Vein-veſſel, which *Galen* calls *Vas Breve*, comes from the very body of the Spleen, and is terminated in the midſt of the Stomach on the left ſide, but never pierces both the Coats thereof. Wherefore it is ſomewhat difficult to find, how the melancholy juice can that way be poured, or ſent, into the capacity of the Stomach. Now the ſplenick branch, when it hath produced out of it thoſe five fore-mentioned branches, is waſted and diſperſed into the ſubſtance and body of the ſpleen.

II. *Ramus meſenterius* divided into three Parts.

Then follows another compound branch of the *Vena Porta*, called the Meſenterick, which is divided into three parts; the firſt and laſt whereof goes to the Blind-gut, and to the right and middle part of the Colick gut, divided into an infinite multitude of other branches. The ſecond and middle is waſted the *Ileon*, as the third and greater in the *Jejunum* or Empty-gut. It is called Meſenterick, becauſe it is diffuſed over all the Meſentery, as the Splenick is in the Spleen. And thus much we have to ſay of the diviſion of the Gate-vein, the which if at any time thou ſhalt find to be otherwiſe than I have ſet down, you muſt not wonder at it, for you ſhall ſcarce find it the ſame in two bodies, by reaſon of the infinite variety of particular Bodies, which (as the Philoſophers ſay) have each their own, or peculiar gifts; Our judgment is the ſame of other diviſions of the Veſſels. Yet we have ſet down that which we have moſt frequently obſerved.

CHAP. XXI.

Of the Original of the Artery, and the diviſion of the Branch deſcending to the Natural Parts.

THeſe things being thus finiſhed and conſidered, the Guts ſhould be pulled away; but ſeeing that if we ſhould do ſo, we ſhould diſturb and loſe the diviſion of the Artery deſcending to the Natural Parts; therefore I have thought it better to handle the diviſion thereof, before the Guts be pluckt away. Therefore we muſt ſuppoſe, according to *Galens* opinion, that as all the Veins come from the Liver, ſo all Arteries proceed from the Heart. This preſently at the beginning is divided into two branches, the greater whereof deſcends downwards to the Natural Parts upon the Spine of the Back, taking its beginning at the fifth *Vertebra* thereof from whence it goes into the following Arteries. The firſt, called the Intercoſtal, runs amongſt the intercoſtal Muſcles, and the diſtances of the Ribs and Spinal Marrow, through the perforation of the Nerves on the right and left hand from the fifth true, even to the laſt of the Baſtard Ribs.

The original of Arteries. The diviſion of the great deſcendent Artery, is into theſe;

1. *Arteria intercoſtalis.*

This in going this progreſs makes ſeven little branchings, diſtributed after the forementioned manner, and going forth of the trunk of the deſcendent over againſt each of the intercoſtal Muſcles.

2. *Phrenica.*

The ſecond being parted into two, goes on each ſide to the Midriff, whence it may be called, or expreſſed by the name of the *Diaphragmatica*, or *Phrenica*, (*i.*) the Midriff Artery. The third being of a large proportion, ariſing from the upper part of the Artery, preſently after it hath paſſed the Midriff, is divided into two notable branches, whereof one goes to the Stomach, Spleen, Kall, to the hollow part of the Liver and the Gall; the other is ſent forth to the Meſentery and Guts after the ſame manner, as we ſaid of the Meſeraick Vein, wherefore it is called the *Cœliaca*, or Stomach Artery. But we muſt note, all their mouths penetrate even to the innermoſt Coat of the Guts, that by that means they may the better and more eaſily attract the *Chylus* contained in them.

3. *Cœliaca.*

The fourth carried to the Reins, where it is named the Reignal or Emulgent, becauſe it ſucks fit matter from the whole maſs of bloud.

4. *Emulgent.*

The fifth is ſent to the Teſticles with the preparing Spermatick-veins, whence alſo it is named the ſpermatick Artery, which ariſes on the right ſide, from the very Trunk of the deſcendent Artery; that it may aſſociate the ſpermatick Vein of the ſame ſide, they run one above another, beneath the hollow Vein; wherefore we muſt have a great care whileſt we labour to lay it open, that we do not hurt and break it.

5. *Spermatica.*

The ſixth going from the fore and upper part of this deſcendent Artery, deſcends with the Hæmorrhoidal Veins to the Fundament; preſently from his beginning, ſending forth certain branches alongſt the Colick Gut, which by *Anaſtomoſis* are united with other branches of the *Cœliacal* Artery; for whoſoever ſhall look more attentively, he ſhall often obſerve that Veins are ſo united amongſt themſelves, and alſo Arteries, and ſometimes alſo the Veins with the Arteries. For *Anaſtomoſis* is a communion and a communicating of the Veſſels amongſt themſelves by the application of their mouths, that ſo by mutual ſupplies they may eaſe each others defect. But they call this the lower Meſeraick Artery.

6. *Hæmorrhoidalis ſeu meſenterica inferior.*

The

The ſeventh proceeding from the trunk with ſo many branches as there be *Vertebra's* in the loins, goes to the loins, and the parts belonging to them, that is the ſpinal marrow of that part, and other parts encompaſſing theſe *Vertebraes*, whereupon it is ſtiled the *Lumbaris*, or Loin-Artery. 7. *Lumbaris.*

The Seventh Figure of the lower Belly.



AA *The Midriff turned back with the ribs of the* Peritonæum.
BB *The Cave or hollow part of the Liver; for the Liver is lifted up that the hollow part of it may be better ſeen.*
C *The leaſt ligament of the Liver.*
D *The Umbilical Vein.*
E *The hollowneſs of the Liver, which giveth way to the Stomach.*
F *The left orifice of the Stomach.*
GG *Certain knubs or knots, and impreſſions in the hollow part of the Liver.*
H *The bladder of Gall.*
I *The Gate-vein cut off, and Branches which go to the bladder of Gall.*
K *A nerve from the Liver coming from the ſtomachical nerve.*
L *An Artery common to the Liver and Bladder of Gall.*
M *A nerve common alſo to them both, coming from the right* coſtal *nerve of the ribs.*
N *The paſſage of the Gall the Guts cut off.*
OO *The hollow of the fore-parts of the Spleen.*
P *The line where the Veſſels of the Spleen are implanted.*
Q *The trunk of the hollow vein.*
R *The trunk of the great Artery.*
S *The* Cœliacal *Artery cut off.*
TV *The Kidneys yet wrapped in their membrane.*
XY *The fatty veins called* Venæ adipoſæ.
a b *The Emulgent Veins with the Arteries under them.*
cc dd *The Ureter from either kidney to the bladder.*
ef *The Spermatical Veins to the Teſticles; the right from the hollow Vein, the left from the Emulgent.*
gg *Veins coming from the Spermatical to the* Peritonæum. h i *The ſpermatical Arteries.* k *The lower meſenterical Artery.* l *The Aſcending of the great Artery above the hollow Vein, and the diviſion of it, and the hollow Vein into two trunks.* m *The Artery of the loins called* Lumbaris. n *The holy Artery called* Sacra. o *A part of the right gut.* p *The bladder of Urine.* * *The connexion of the Bladder with the* Peritonæum. q *A part of the Veſſels which lead the ſeed from the Teſticles is here reflected.* r ſ *The* Scrotum *or Cod, that is, the skin that inveſts the Yard and Teſticles.* t *The fleſhy Pannicle or membrane which is under the Cod.* u *The Coat which is proper to the Teſticles with his Veſſels.* x *A part of the Yard excoriated or flayed, and hanging down.*

The eighth maketh the Iliack Artery, untill ſuch time as it departs from the *Peritonæum* where the Crural Arteries take their original. This Iliack Artery ſends many divarications towards the Holy bone where it takes its beginning, and to the places lying near the Holy bone, which, becauſe they run the ſame courſe as the Iliack Veins, for brevities ſake we will let paſs further mention of them till we come to treat of the Iliack Veins. 8. *Iliaca.*

CHAP. XXII.

Of the diſtribution of the Nerves to the Natural parts.

IT remains that before the bowels be taken away, we ſhew the Nerves ſent to the entrails and Natural parts, that as wiſe and provident men we may ſeem to have omitted nothing. Firſt we muſt know that theſe Nerves are of the ſixth Conjugation, which deſcend as well to the ſtomach all alongſt the Gullet, and the ſides thereof, as thoſe at the roots of the ribs on both ſides within. But when they are paſſed through the Midriff, thoſe which are diſtributed amongſt the Natural parts follow the turnings of the Veins and Arteries, but ſpecially of the Arteries. Wherefore if you have a mind to follow this diſtribution of the Nerves, you muſt chiefly look for it in thoſe places, in which the Artery is diſtributed amongſt the Guts above the Loins. The Original of the Nerves which are carried to the Natural parts.

Theſe Nerves are but ſmall, becauſe the parts ſerving for nutrition, needed none but little Nerves for the performance of the third duty of Nerves, which is in the diſcerning and knowing of what is troubleſom to them. For unleſs they had this ſenſe, there is nothing would hinder, but theſe bowels, neceſſary for life, being poſſeſſed with ſome hurtful thing, the Creature ſhould preſently fall down dead; but we have this benefit by this ſenſe, that as ſoon as any thing troubles and vellicates the bowels, we being admoniſhed thereof, may look for help in time. Their Magnitude and Uſe.

And beſides, if they were deſtitute of this ſenſe, they might be gnawn, ulcerated, and putrified by the raging acrimony of the excrements falling into, and ſtaying in them; but now (by means hereof) as ſoon as they find themſelves pricked or plucked, preſently by the expulſive faculty they endeavour to expel that which is troubleſom, and ſo free themſelves of preſent and future dangers.

CHAP. XXIII.

The manner of taking out the Guts.

WHen the Guts are to be taken out, you muſt begin with the right Gut. And you muſt divide it, being firſt ſtraitly tied in two different places, at a juſt diſtance about four fingers from the end, with a ſharp knife between two ligatures. Then you muſt ſhew its proper Coats and Fibres, and that common one which it hath from the *Peritonæum*. This being done, you muſt in like manner bind the trunk of the Gate-vein as neer the original as you can; that ſo all his branches being in like manner tied, there may be no fear of effuſion of bloud: you muſt do the like with the Cœliack Artery at the left Kidney, and in the lower Meſenterick, which deſcends to the right Gut with Hemorrhoidal Veins. This being done pull away the Guts even to the *Duodenum*, which being in like manner tied in two places, which ought to be below the inſertion of the *Porus Cholagogus*, or paſſage of the Gall, that you may ſhew the oblique inſertion thereof into that Gut; for the obliquity of its inſertion is worth obſervation, as that which is the cauſe that the Gall cannot flow back into its bladder by the compreſſion of this Gut from below upwards. Then all theſe windings of the Guts may be taken away from the body.

CHAP. XXIV.

The Original and Diſtribution of the deſcendent Hollow Vein.

The original of the Hollow Vein. It is divided into two Trunks.

BEcauſe the reſt of the natural parts, do almoſt all depend upon the deſcendent Hollow Vein, therefore before we go any further, we will ſhew its Original and Diſtribution. We ſaid before that all Veins proceeded from the Liver, but yet in divers places. For the Gate-vein goes out of the hollow part, and the Hollow Vein out of the gibbous part of the Liver, which going forth like the body of a Tree, is divided into two great branches; the leſſer of which goes to the Vital and Animal parts, and the extremities of theſe parts, as we ſhall ſhew in their place. The greater, deſcending from the back part of the Liver above the *Vertebraes* of the Loins to the parts beneath, goes in the manner following. The firſt diviſion thereof is to the membranes of the Reins, which come from the *Peritonæum*. Wherefore there it produces the *Venæ adipoſæ*, or fatty Veins, ſo called, becauſe they bring forth a great quantity of fat in thoſe places; Of theſe fatty Veins there is a diverſe original; for the right doth oftentimes ariſe from the right emulgent, becauſe it is higher; but the leſs comes from the very trunk of the Hollow Vein, becauſe the emulgent on that ſide is lower; and you ſhall ſcarce ſee it otherwiſe.

The diviſion of the greater branch of the Hollow Vein.

1. *Adipoſa.*

2. *Emulgens.*

The ſecond, being the Kidney or Emulgent Veins, go to the Reins, which, at their entrance, or a little before, is divided into two branches, like as the Artery is, the one higher, the other lower, and theſe again into many other through the ſubſtance of the Kidneys, as you may learn better by Ocular Inſpection than by Book. They are thick and broad, that the ſerous humour may without impediment have freer paſſage. Their original is different; for the right emulgent oftentimes comes forth of the Hollow Vein ſomewhat higher than the left; that ſeeing their office and duty is to purge the maſs of bloud from the cholerick and ſerous humour, that if any part thereof ſlide by the one, it may not ſo ſcape, but fall as it were into the other. Which certainly would not have happened if they had been placed the one juſt oppoſite to the other. For the ſerous or wheyiſh humour would have ſtaid as equally ballanced, or poiſed, by reaſon of the contrariety of the action, and traction or drawing thereof. But we muſt remember, that in diſſecting of Bodies, I hove oftentimes found in ſuch as have been troubled with the Stone, ſeven emulgent Veins, and ſo many Arteries; four from the left ſide coming from divers places, of which the laſt came from the Iliack; three from the right hand likewiſe in divers places.

3. *Spermatica.*

The third diviſion is called the Spermatick or Seed Vein, it goes to the Teſticles; the original thereof is thus; that the right ariſes on the fore-part of the trunk of the Hollow Vein; but the left moſt commonly from the emulgent. Beſides, you ſhall ſometimes find that theſe have companions with them, to the right emulgent; but to the left, another from the Hollow Vein; in ſome but on one ſide, in others on both. But alſo I have ſometimes obſerved the left emulgent to proceed from the Spermatick or Seed Vein.

4. *Lumbaris.*

The fourth, becauſe it goes to the Loins, is called *Lumbaris*; which in his original and inſertion is wholly like the Artery of the Loins. But there are four *Lumbares* or Loin Veins on each ſide, that is, one in each of the four ſpaces of the five *Vertebraes* of the Loins.

5. *Iliacæ*, which are divided into,

1. *Muſculoſæ.*

2. *Sacræ.*

The fifth diviſion makes the *Iliacæ*, until, paſſing through the *Peritonæum*, they take the names of Crural Veins: Theſe are firſt divided into the Muſculous, ſo called, becauſe they go to the oblique aſcendent and tranſverſe Muſcles, and to the *Peritonæum*. Sometimes they have their original from the end of the Trunk. And the ſame *Iliacæ* are divided into the *Sacræ*, or Holy; which go the ſpinal marrow of the Holy bone through thoſe holes, by which the Nerves generated of this marrow, have their paſſage.

Thirdly,

Thirdly, The *Iliacæ* are divided into the *Hypogaſtricæ*, ſo called becauſe they are diſtributed to all the parts of the *Hypogaſtrium*, or lower part of the lower belly, as to the right Gut, the muſcles thereof, the muſculous skin (in which place they often make the external Hemorrhoidal, ordained for the purging of ſuch bloud as offends in quantity, as thoſe other, [that is, the inward Hemorrhoidal] which deſcend from the right Gut from the Gate-vein by the ſpleenick branch, ſerves for cleanſing that which offends in quality,) to the Bladder and the neck thereof, even to the end of the Yard, to the Womb, and even to the neck of the Womb and utmoſt part of the Privities, from whence it is likely the Courſes break forth in Women with Child and Virgins. But this ſame Vein alſo ſends a portion without the *Epigaſtrium* by that perforation which is common to the Share and Haunch-bones, which, ſtrengthened by the meeting of the other internal Crural Vein, deſcends even to the Ham; but in the mean time, by the way, it is communicated to the muſcles of the Thigh, called *Obturatores*, and other parts within. 3 *Hypogaſtricæ, which produce the Hæmorrhoidales externæ.*

Fourthly, The *Iliacæ* produce the *Epigaſtricæ*, which on both ſides from below aſcend according to the length of the right muſcles, ſpreading alſo by the way ſome branches to the oblique and tranſverſe muſcles, and alſo to the *Peritonæum*. 4 *Epigaſtricæ.*

Fifthly, Theſe *Iliacæ* produce the *Pudendæ*, or Veins of the Privities; becauſe they go in Women to their Privities, and in men to the Cods; where they enter that fleſhy Coat filled with Veins, and going to the skin of the Yard they take their beginning under the *Hypogaſtricæ*. 5. *Pudendæ.*

CHAP. XXV.

Of the Kidneys or Reins.

NOw follow the Kidneys, which that they may be more eaſily ſeen, (after that you have diligently obſerved their ſituation) you ſhall deſpoil of their fat, if they have any about them, as alſo of the membrane they have from the *Peritonæum*. Firſt, You ſhall ſhew all their conditions, beginning at their ſubſtance.

The Nineth and Tenth Figure of the Veſſels of Seed and Urine.

FIG. XX.

FIG.



The firſt Figure ſheweth the fore-ſide, the ſecond the hinder-ſide.

a a a 1 *The fore-part of the right kidney.*

b b b 2 *The back part of the left kidney.*

c 1 *The outſide.*

d d 1 2 *The inner ſide.*

e e 1 2 *The two cavities whereinto the emulgent veſſels are inſerted.*

f f 1 2 *The trunk of the hollow vein.*

g g 1 2 *The trunk of the great Artery.*

h i 1 2 *The emulgent vein and artery.*

k k 1 2 *The right fatty vein.*

l 1 *The left fatty vein.*

* 1 *The Cœliacal artery.*

m n 1 2 *The Ureters.*

o p q 1 2 *The right ſpermatick vein which ariſeth near* p, *the left near* q.

r 1 *The place where the arteries of the ſeed ariſe.*

ſ 1 2 *Small branches diſtributed from the ſpermatical veins to the* Peritonæum.

t 1 2 *The ſpiry varicous body, called* Varicoſum Vas pyramidale.

u 1 2 *The* Paraſtatæ *or* Epididymis.

x 1 *The Teſticle yet covered with its coat.*

y 1 2 *The place where the leading veſſel called* vas deferens, *doth ariſe.* α 1 2 *The deſcent of the ſame leading veſſel.* β 1 2 *The revolution of the ſame leading veſſel.* γ 1 2 *The paſſage of the ſame veſſel reflected like a recurrent nerve.* δ 2 *The meeting of the ſame leading veſſels.* ε 1 2 *The Bladder of Urine; the firſt Figure ſheweth it open, the ſecond ſheweth the back parts.* ζ, ζ 1 *The ſmall bladder of the ſeed opened.* ηη 2 *The Glandules called* Glandulæ Proſtatæ. θ 1 *The Sphincter muſcle of the Bladder.* ιι 1 2 *The two bodies which make the ſubſtance of the Yard.* κκ 1 *The veſſels which go unto the Yard and neck of the Bladder.* λ 1 *The paſſage which is common to the Urine and Seed, cut open.* Ψ 2 *The implantation of the Ureters into the Bladder.*

The ſubſtance of the Kidneys is fleſhy, denſe, and ſolid, leſt they ſhould be hurt by the ſharpneſs of the Urine. Their magnitude is large enough, as you may ſee. Their figure is ſomewhat long and *Their Subſtance.*

Magnitude. Figure. and round, almoſt reſembling a ſemicircle, and they are lightly flatted above and below. They are partly hollow and partly gibbous; the hollow lies next the hollow Vein, and on this ſide they receive the emulgent Veins and Arteries, and ſend forth the Ureters; their gibbous part lies towards the loins.

Compoſition. They are compoſed of a coat coming from the *Peritonæum*; their own peculiar fleſh, with the effuſion of bloud about the proper Veſſels, (as happens alſo in other entrails) generates a ſmall Nerve, which ſpringing from the Coſtal of the ſixth Conjugation, is diffuſed to each Kidney on his ſide into the coat of the Kidney it ſelf, although others think it always accompanies the Vein and Artery.

But *Fallopius*, that moſt diligent Author of Anatomy hath obſerved that this Nerve is not onely oftentimes divaricated into the coat of the Kidneys, but alſo pierces into their ſubſtance.

Number. Site. They are two in number, that if the one of them ſhould by chance be hurt, the other might ſupply thoſe neceſſities of Nature for which the Kidneys are made. They lie upon the loins at the ſides of the great Veſſels, on which they depend by their proper Veins and Arteries, and they ſtick to them as it were, by a certain ſecond coat, leſt that they might be ſhaken by any violent motions. Wherefore we may ſay that the Kidneys have two coats, one proper adhering to their ſubſtance, the other, as it were, coming from the *Peritonæum* on that part they ſtick to it. The right Kidney is almoſt always the higher, for thoſe reaſons I gave, ſpeaking of the original of the emulgent Veſſels. *Columbus* ſeems to think the contrary; but ſuch like controverſies may be quickly decided by the Eye.

Connexion. They have connexion with the principal Veſſels by the Veins, Nerves, and Arteries; by the Coats with the Loins and other parts of the lower Belly, but eſpecially with the Bladder by the Ureters.

Temper. Action. They are of a hot and moiſt temper, as all fleſhy parts are. Their action is to cleanſe the Maſs of the Bloud from the greater part of the ſerous and cholerick humour. I ſaid the greater part, becauſe it is needful that ſome portion thereof ſhould go with the alimentary bloud to the ſolid parts, to ſerve in ſtead of a vehicle, leſt otherwiſe it ſhould be too thick.

Their Strainer. Beſides, you muſt note, that in each Kidney there is a cavity bounded by a certain membrane, encompaſſed by the diviſion of the emulgent Veins and Arteries through which the Urine is ſtrained partly by the expulſive faculty of the Kidneys, partly by the attractive of the Ureters which run through the ſubſtance of the Kidneys on the hollow ſide, no otherwiſe than the *Porus cholagogus* through the body of the Liver.

CHAP. XXVI.

Of the Spermatick Veſſels.

Ureters. NOw we ſhould have ſpoken of the Ureters, becauſe, as we ſaid before, they are paſſages derived from the Kidneys to carry the Urine to the Bladder. But, becauſe they cannot be diſtinguiſhed and ſhewed, unleſs by the corrupting and vitiating the ſite of the ſpermatick Veſſels, therefore I have thought it better to paſs to the Explication of all the ſpermatick parts.

And firſt of all you muſt gently ſeparate them, (that ſo the Declaration of them may be more eaſie and manifeſt) and that from the coat which comes from the *Peritonæum*, and the fat which inveſts them even to the Share-bone, having diligently conſidered their ſite, before you ſeparate them.

Their Subſtance. Quantity. Then you ſhall teach that the ſubſtance of theſe Veſſels is like to that of the Veins and Arteries. Their quantity is ſmall in thickneſs, but of an indifferent length, by reaſon of the diſtance of their original from the Teſticles. They are longer in Men than in Women, becauſe theſe have their Teſticles hanging without their Belly, but Women have them lying hid within their Belly.

Figure and Compoſure. Their figure and compoſure is wholly like the figure and compoſition of the Veins and Arteries, except in this one thing, that from that place where they go forth of the great capacity of the *Peritonæum*, they are turned into many intricate windings, like crooked ſwoln Veins, even to the Teſticle; That the ſpermatick matter in that one Tract, which yet is no other than bloud, may be prepared to concoction, or rather be turned into Seed in theſe Veſſels, by the irradiation of the faculty of the Teſticles.

Number. Theſe Veſſels are ſix in number, four preparing, and two ejaculatory, of which we will ſpeak hereafter. Therefore on each ſide there be two preparing Veſſels, that is, a Vein and an Artery, ariſing as we told you when we ſpoke of the diſtribution of the hollow Vein.

Site. They are inſerted into the Teſticles through that coat which we call *Epididymis*, others *Dartos*. Their ſite is oblique above the Loins and Flanks, whileſt they run down between the ends of the Share and Haunch-bone, they are knit to the parts lying under them, both by certain Fibers which they ſend from them, as alſo by the membrane they have from the *Peritonæum*. They have like temperature as the Veins and Arteries have. Their action is to carry bloud to the Teſticles for generating of Seed.

CHAP. XXVII.

Of the Teſticles, or Stones.

Their Subſtance. Magnitude and Figure. Compoſition. THe Teſticles are of a Glandulous, white, ſoft and looſe ſubſtance, that ſo they may the more eaſily receive the ſpermatick matter: their magnitude and figure equal, and reſemble a ſmall Pullets Egg ſomewhat flatted; their compoſure is of Veins, Arteries, Coats, and their proper fleſh. Their Veins and Arteries proceed from the ſpermatick Veſſels, their Nerves, from the ſixth Conjugation, by the roots of the Ribs, and out of the Holy-bone. They are wrapped in four Coats, two whereof are common, and two proper. The common, are the *Scrotum* or skin

skin of the Cods, proceeding from the true skin; and the fleshy Coat, which consists of the fleshy Pannicle in that place receiving a great number of Vessels, through which occasion it is so called. The proper Coats are first the *Erythrois* arising from the process of the *Peritonæum*, going into the *Scrotum* together with the spermatick Vessels, which it involves and covers; this appears red both by reason of the Vessels, as also of the Cremaster-muscles of the Testicles; then the *Epididymis* or *Dartos* which takes its original of the membrane of the spermatick preparing Vessels. The flesh of the Testicles, is as it were, a certain effusion of matter about the Vessels, as we said of other entrails. But you must observe, that the *Erythrois* encompasses the whole Stone, except its head, in which place it strikes to the *Epididymis*, which is continued through the whole substance of the Testicle. This *Epididymis* or *Dartos* was therefore put about the Stones, because the Testicles of themselves are loose, spongious, cavernous and soft, so that they cannot safely be joined to the spermatick Vessels, which are hard and strong. Wherefore Nature, that it might join extreams by a fit *Medium*, or mean, formed this Coat *Epididymis*. This is scarce apparent in Women by reason of its smalness. The two forementioned common Coats, adhere or stick together by the Vessels not onely amongst themselves, but also with the *Erythrois*. You must besides observe, the Cremaster-muscles are of the said substance with other muscles, small and thin, of an oblique and broad figure, arising from the membrane of the *Peritonæum*, which (as we said before) assumes flesh from the flanks. Their composition is like other muscles. They are two, on each side one. They are situate from the ends of the Flanks even to the Stones. They have connexion with the process of the *Peritonæum* and Testicles. Their temper is like that of other muscles. Their action is to hang and draw up the Testicles towards the Belly, whence they are called hanging muscles. The Testicles are most commonly two in number, on each side one; sometimes there be three, sometimes one alone; as it happens also in the Kidneys, for some have but one Kidney. They lie hid in the *Scrotum* at the very roots of the Share-bone, connexed to the principal parts of their Vessels, with the neck of the Bladder and Yard; but by their Coats they adhere to the parts from whence they have them. They are of a cold and moist temper, because they are glandulous; although they may be hot by accident, by reason of the multitude of the Vessels flowing thither. Those whose Testicles are more hot, are prompt to Venery, and have their Privities and adjacent parts very hairy; and besides, their Testicles are very large and compact. Those on the contrary that have them cold, are slow to Venery, neither do they beget many children, and those they get, are rather female than male; their Privities have little hair upon them, and their Testicles are small, soft, and flat. The action of the Testicle is to generate Seed, to corroborate all the parts of the Body, and by a certain manly irradiation to breed or increase a true masculine courage. This you may know by Eunuchs, or such as are gelt, who are of a womanish nature, and are oftentimes more tender and weak than Women. As *Hippocrates* teaches by example of the *Scythians*, *Lib. De Aere, Locis & Aquis.*

The Coat *Erythrois.*

The *Epididymis*, or *Dartos.*

The Cremaster muscles.

Temper.

Action.

CHAP. XXVIII.

Of the Varicous Bodies or Parastates, *and of the ejaculatory Vessels, and the glandulous or* Prostates.

THe Varicous *Parastatæ* are nervous and white bodies, like as the nerves, wound and close woven amongst themselves; they are stretched even from the top to the bottom of the Testicles, from whence presently by their departure they produce the *Vasa ejaculatoria*, or leading Vessels. But unless we do very well distinguish their names, they shall scarce shun confusion. For that which I call *Parastatæ*, that is, as it were the head of the Testicle, being, as it were, like another Stone, is called *Epididymis* by *Galen*, *l.* 1. *De Semine*. But I, by the example and authority of many Anatomists, understand by the *Epididymis* the proper Coat of the Testicles, of which thing I thought good by the way to admonish you of. Their Action is, by their crooked passages to hinder the Seed from departing out of the preparing into the leading Vessels, before it shall be most perfectly laboured and concocted in these Vessels by the power and force of the Testicles. For in the first windings the bloud looks pure, but in the last it is not so red, but somewhat whitish. For Nature commonly doth thus delay the matter in its passage, either by straitness or obliquity, which it desires to make more perfect and elaborate by any new concoction; this we may learn by the foldings of the *Rete mirabile*, the windings in the Guts, the wrinkles in the bottom of the Stomach, the straitness of the *Pylorus*, the Capillary Veins dispersed through the body of the Liver; Certainly Nature hath intended some such thing in the making of the spermatick Vessels. Their quantity is visible, and figure round, tending somewhat to sharpness. They are composed of Veins, Nerves, and Arteries, which they enjoy from the Vessels of the Testicles, from the *Epididymis*, or the Coat, from the *Peritonæum*, and their proper substance. Their temper is cold and dry. They be two in number, one to each Testicle. But these Varicous bodies are called *Parastatæ*, Assisters, because they superficially assist, and are knit to the Testicles according to their length, or long ways. Out of the *Parastatæ* proceed the *Vasa ejaculatoria*, or leading Vessels, being of the same substance as their Progenitors, that is, solid, white, and as it were nervous. Their quantity is indifferent, their figure round and hollow, that the Seed may have a free passage through them, yet they seem not to be perforated by any manifest passage, unless by chance in such as have had a long *Gonorrhœa*. They have like temper as the *Parastates*, between which and the *Prostates* they are seated, immediately knit with them both, as both in the Coat, and the other Vessels with the parts from whence they take them.

Their Substance.

Here the Author speaks otherwise than *Galen*.

Their Action.

Their Quantity, Figure and Composure.

Their temper and number.

Vasa ejaculatoria, the ejaculatory or leading Vessels.

But we must note, that such like Vessels coming out of the *Parastates* ascend from the bottom of the Stones even to the top, in which place meeting with the preparing Vessels, they rise into the Belly by the same passages, and bind themselves together by nervous fibres, even to the inner capacity

capacity of the belly; from whence turning back, they forſake the preparing, that ſo they may run to the bottom of the Share-bone, into the midſt of two glandulous bodies, which they call *Proſtates* ſituate at the neck of the bladder, that there meeting together, they may grow into one paſſage,

The Tenth Figure, wherein thoſe things ſhewed in the former Figure, are more exactly ſet forth.



a a *A part of the Midriff, and of the* Peritonæum *with the ribs broken.*
bb cc *The convex or gibbous part of the liver marked with* bb, *the hollow or concavous part with* cc.
d e *The right and left ligaments of the Liver.*
f *The trunk of the gate-vein.*
g *The trunk of the hollow vein.*
h l *The fatty veins, both left and right.*
i *The aſcent of the great Artery above the hollow vein, and the diviſion thereof.*
k *The* Cœliacal *Artery.*
m n *The emulgent Veſſels.*
oo pp *The fat tunicles or coats torn from both the Kidneys.*
qq *The Ureters that go unto the Bladder.*
t u *The right ſpermatical Vein which ariſeth near to* u.
x y *The double original of the left ſpermatical Vein.*
x *From the Emulgent.*
y *From the hollow vein.*
α *The original of the ſpermatical Arteries.*
ß *Certain branches from the ſpermatick Arteries which run unto the* Peritonæum. γ *The paſſage of the ſpermatical Veſſels through the productions of the* Peritonæum, *which muſt be obſerved by ſuch as uſe to cut for the Rupture.* δ *The ſtiry bodden Hidie's entrance into the teſticle, it is called* Corpus varicoſum pyramidale. ε *The* Paraſtatæ. ζ *The Stone or Teſticle covered with his inmoſt coat.* η *The deſcendent of the leading Veſſel called* Vas deferens. V V *The Bladder.* * *The right Gut.* ξ *The Glandules, called* Proſtatæ, *into which the leading Veſſels are inſerted.* ρ *The muſcle of the Bladder.* σ τ υ *Two bodies of the Yard,* σ *and* τ *and* υ *his Veſſels.* Φ χ *The coat of the Teſticle.* ⏚ ω *The muſcle of the Teſticle* ⏚, *his Veſſels* ω.

For thus of three paſſages, that is of the two leading Veſſels, and one paſſage of the Bladder, there is one common, one in men for the caſting forth of Seed and Urine. A Caruncle riſing like a Creſt at the beginning of the neck of the Bladder, argues this uniting of the paſſages, which receiving this ſame paſſage which is ſufficiently large, is oft-times taken by ſuch as are ignorant in Anatomy for an unnatural Caruncle, then eſpecially when it is ſwollen through any occaſion. Theſe leading Veſſels are two in number, on each ſide one. Their action is to convey the Seed made by the Teſticles to the Proſtates, and ſo to the neck of the Bladder, ſo to be caſt forth at the common paſſage. But if any ask whether that common paſſage made by the two leading Veſſels between the glandulous Bodies be ſo obvious to ſenſe or no: We anſwer, it is not manifeſt, though reaſon compel us to confeſs that that way is perforated by reaſon of the ſpermatick, groſs, and viſcous matter carried that way. But peradventure the reaſon why that paſſage cannot be ſeen, is, becauſe in a dead carkaſs all ſmall paſſages are cloſed and hid, the heat and ſpirits being gone; and the great appear much leſs, by reaſon all the perforations fade, and fall into themſelves. Yet certainly theſe paſſages muſt needs be very ſtrait even in a living Man, ſeeing that in a dead they will not admit the point of a needle. Wherefore we need not fear, leſt in ſearching, whileſt we thruſt the *Catheter* into the Bladder, it penetrate into the common paſſage of the leading Veſſels which runs within the Caruncle, unleſs peradventure by ſome chance, as a *Gonorrhœa*, or ſome great *Phlegmon*, it be much dilated beſides Nature. For I have ſometimes ſeen ſuch paſſages ſo open, that they would receive the head of a Spathern; which thing ſhould admoniſh us, that in ſearching we take great care that we do not raſhly hurt this Caruncle; for being ſomewhat raſhly handled with a *Catheter*, it caſts forth bloud, eſpecially if it be inflamed. But alſo the concourſe of the ſpirits flowing with great violence together with the Seed, much helps forward ſuch ejaculation thereof performed through theſe ſtrait paſſages by the power of the imaginative faculty in the Act of Generation.

Their Number and Action.

This Caruncle muſt be obſerved and diſtinguiſhed from a *Hyperſarcoſis* or fleſhy excreſcence.

After the leading Veſſels, follow the *Proſtatæ*, being glandulous Bodies of the ſame ſubſtance and temper that other Glandules are. Their quantity is large enough, their figure round, and ſomewhat long, ſending forth on each ſide a ſoft production of an indifferent length. They are compoſed of Veins, Nerves, Arteries, a coat (which they have from the neighbouring parts) and laſtly their proper fleſh, which they have from their firſt conformation. They are two in number, ſituate at the root of the neck of the Bladder, ſomewhat ſtraitly bound or tied to the ſame, to the leading

The *Proſtatæ*. Their quantity and figure.

Number and ſite.

Veſſels

Veſſels, and the parts annexed to them. But always obſerve, that every part which enjoys nouriſhment, life, and ſenſe, either firſt or laſt, hath connexion with the principal parts of the Body, by the intercourſe of the Veſſels which they receive from thence. An Anatomical Axiom.

The uſe of the Proſtates is to receive in their proper body the ſeed laboured in the Teſticles, and to contain it there, until it be troubleſom either in quantity or quality, or both. Beſides, they contain a certain oily and viſcid humour in their glandulous body, that continually diſtilling into the paſſage of the Urine, it may preſerve it from the acrimony and ſharpneſs thereof. But we have obſerved alſo on each ſide other Glandules, which *Rondeletius* calls *Appendices Glanduloſæ*, glandulous dependences to ariſe from theſe Proſtates, in which alſo there is ſeed reſerved. Their uſes. *Rond. in method. ad morbos.*

CHAP. XXIX.

Of the Ureters.

NOw it ſeems fit to ſpeak of the Ureters, Bladder, and parts belonging to the Bladder. Therefore the Ureters are of a ſpermatick, white, denſe, and ſolid ſubſtance, of an indifferent bigneſs in length and thickneſs. Their Figure is round and hollow. They are compoſed of two Coats, one proper conſiſting of right and tranſverſe Fibres which comes from the emulgent Veins and Arteries; the other common, from the *Peritonæum*; beſides, they have Veins, Nerves, and Arteries, from the neighbouring parts. The ſubſtance, magnitude, figure and compoſure of the Ureters.

They be two in number, on each ſide one; they are ſituate between the Kidnies (out of whoſe hollow part they proceed) and the Bladder. But the manner how the Ureters inſert or enter themſelves into the Bladder, and the *Porus Cholagogus* into the *Duodenum*, exceeds admiration; for the Ureters are not directly but obliquely implanted near the orifice of the Bladder, and penetrate into the inner ſpace thereof; for within they do, as it were, divide the membrane, or membranous Coat of the body of the Bladder, and inſinuate themſelves into that, as though it were double. But this is opened at the entrance of the Urine, but ſhut at other times, the cover, as it were falling upon it, ſo that the humour which is fallen into the capacity of the Bladder, cannot be forced or driven back; no not ſo much as the Air blown into it can come this way out, as we ſee in Swines Bladders blown up and filled with Air. Number and Site.

For we ſee it is the Air contained in theſe which fills them thuss neither can it be preſſed forth but with extraordinary force.

For as this Skin or Coat turned in by the force of the humour gives way, ſo it being preſſed out by the body contained within, thruſts its whole body into the paſſage as a ſtopple; like to this, is the inſertion of the *Porus Cholagogus* into the Guts.

The Ureters have connexion with the above-mentioned parts, with the muſcles of the Loins, upon which they run from the Kidneys to the Bladder. Connexion.

Wherefore nothing hinders, but that the ſtone ſliding through the Ureters into the Bladder, may ſtupifie the Thigh as much as it did when it was in the Kidney. They are of a cold and dry temper.

Their uſe is, to ſerve as paſſages or channels, for carrying the Urine into the Bladder. Temper and uſe.

CHAP. XXX.

Of the Bladder.

THe Bladder is of the ſame ſubſtance that the Ureters, that is, nervous, that ſo it may be the more eaſily dilated. The ſubſtance

It is of a large proportion, in ſome bigger, in ſome leſs, according to the difference of Age and habit of body. It is of a round Figure, and as it were, Pyramidal. Figure.

It is compoſed of two Coats, one proper, which is very thick and ſtrong, compoſed of the three ſorts of Fibres, that is, in the inner ſide of the direct, without of the tranſverſe, and in the midſt of the oblique. The other common Coat coming from the *Peritonæum*, hath Veins and Arteries on each ſide one, from the *Hypogaſtrick* Veſſels above the Holy bone; alſo it hath Nerves on each ſide from the ſixth conjugation mixt with the Nerves of the Holy bone. For theſe Nerves deſcend from the Brain even to the end of the Holy bone. Compoſition.

It is but one, and that ſituate in men in the lower belly upon the right Gut, and below the Share-bone; but in Women between the Womb and that bone, to which it cleaves with his membranous ligaments, as it doth to the Yard by its neck, and to the right gut by its common Coat and proper Veſſels. It is of a cold and dry temper.

The uſe and action thereof is by the Fibers continually to draw the Urine, and contain it as long as need requires, and then to expel it by the neck, partly by compreſſion either of it ſelf, or rather to the muſcles of the *Epigaſtrium* and Midriff; becauſe this motion, ſeeing it is voluntary, cannot be performed unleſs by a muſcle which the Bladder wants; partly by the dilatation and relaxation of the Sphincter muſcle compoſed of tranſverſe Fibers, like the Sphincter of the Fundament, after the ſame manner to ſhut up the orifice of the Bladder, that the Urine flow not out againſt our will. But the Bladder, as it fills, is dilated; but as it is emptied, it is contracted like a purſe. You may eaſily obſerve this muſcle in a Sows bladder: it is ſtretched from the orifice of the Bladder, and beginning of the Urinary paſſage even to the Privities in Women; but in Men it is terminated in the *Peritonæum* as ſoon as it hath left the right Gut. Beſides, this muſcle is thus far Temper, uſe or action. The ſphincter of the Bladder.

ſtretched

ſtretched forth, that the Urine by its compreſſion ſhould be wholly preſſed out of the Bladder, which by too long ſtay would by its acrimony do ſome harm. This is the common opinion of Anatomiſts concerning the Sphincter of the Bladder, which nevertheleſs *Fallopius* allows not of. For (ſaith he) if this muſcle ſhould be ſituate beneath the glandulous bodies, the Seed in copulation could never be caſt forth without ſome ſmall quantity of Urine. Wherefore he thinks that this muſcle is ſituate above the *Proſtates*, and that it is nothing elſe but the beginning of the neck of the Bladder, which becomes more fleſhy whileſt it is woven with tranſverſe fibers.

The Eleventh Figure of the Bladder and Yard.

AB 1 2 3 4 5 7 9 *The two bodies which make the Yard.*
CC 2 3 *The place where theſe two bodies do firſt ariſe.*
D 1 2 3 4 5 7 9 *The Nut of the Yard, called* Glans Penis.
EE 4 5 *The fungous and red ſubſtance of the bodies of the Yard.*
F 4 5 *The mutual connexion of the bodies of the Yard, and the nervous outward ſubſtance of the ſame, compaſſing round about the former fungous ſubſtance.*
G 1 2 3 4 5 7 9 *The paſſage of the Urine, or common Pipe, running under the Yard all along his length.*
HI 1 2 *The firſt pair of Muſcles of the Yard, which in the firſt Figure do yet grow to it, but in the ſecond they hang from their original.*
KL 1 2 *The ſecond pair of Muſcles of the Yard, in the firſt Figure, growing; in the ſecond, hanging from their inſertion.*
M 1 2 *The Sphincter of the right Gut.*
N 3 7 8 9 *The round Sphincter-muſcle of the bladder.*
OO *A Membrane which is over the holes of the Share-bone.*



P 2 *A round Ligament from the meeting of the Share-bones on the head of the thigh.* Q 3 7 8 *The body of the Bladder.* RR 3 7 *The* Proſtatæ, *which into Seed when it is perfectly laboured, is led.* SS 3 8 *Portions of the Ureters.* TT*3 *Portions of the Veſſels which lead down the ſeed.* VV 7 8 *The Umbilical Arteries.* X 7 8 *The Ligament of the Bladder called* Urachus. Y 7 8 *The Navel or Umbilicus.* Z 7 8 *The Umbilical Vein.* aa 7 *The Vein and Artery of the Yard.* b 5 *The Artery diſtributed through the body of the Yard.*

The neck of the Bladder.

For the neck of the Bladder: it differs nothing in ſubſtance, compoſure, number, and temper from the Bladder, but onely in quantity, which is neither ſo large, nor round in Figure, but ſomewhat long together with the Yard, repreſenting the ſhape of the letter S. It is placed in men at the end of the right Gut and *Peritonæum*, riſing upwards even to the roots of the Yard, and with it bending it ſelf downwards; in Women it is ſhort, broad, and ſtreight, ending at the orifice of the neck of the Womb between the nervous bodies of the *Nymphæ*.

The connexion and uſe thereof.

In men it hath connexion with the Bladder, the ejaculatory Veſſels, the right Gut and Yard, but in Women onely with the neck of the Womb and Privities. The uſe of it is in Men to caſt forth Seed and Urine, in Women onely Urine. But we muſt note that the Share-bones muſt be divided and pulled aſunder in that part where they are joined, that ſo you may the more exactly obſerve the ſituation of theſe parts. Beſides you muſt note, that by the *Peritonæum*, we underſtand nothing elſe, in Men and Women, than that ſpace which is from the Fundament to the Privities, in which the ſeam is called *Taurus*.

CHAP. XXXI.

Of the Yard.

The ſubſtance, quantity and figure of the Yard.

NOw follows the declaration of the privy parts of Men and Women; and firſt we will treat of Mens. The Yard is of a ligamentous ſubſtance, becauſe it hath its original from bones; it is of an indifferent magnitude in all dimenſions, yet in ſome bigger, in ſome leſs; the Figure of it is round, but yet ſomewhat flatted above and beneath.

Compoſure.

It is compoſed of a double Coat, Nerves, Veins, Arteries, two Ligaments, the paſſage of the Urine, and four Muſcles. It hath its Coats both from the true Skin, as alſo from the fleſhy Pannicle; but the

the Veins and Arteries from thoſe of the lower part of the lower belly which run on the lower part of the Holy-bone into the Yard, as the ſeminary Veſſels run on the upper part.

The ligaments of the Yard proceed on both ſides from the ſides and lower commiſſure of the Share-bones; wherefore the Yard is immediately at his root furniſhed with a double ligament; but theſe two preſently run into one ſpongy one. The paſſage of the Urine ſituate in the lower part of the Yard, comes from the neck of the Bladder between the two ligaments. The ligaments

For the four Muſcles, the two ſide-ones compoſing or making a great part of the Yard, proceed from the inward extuberancy of the Hip-bone, and preſently they are dilated from the original, and then grows leſs again. The two other lower ariſe from the Muſcles of the Fundament, and accompany the Urinary paſſage the length of the *Peritonæum* until they enter the Yard; but theſe two Muſcles cleave ſo cloſe together, that they may ſeem one, having a triangular Form. The Muſcles.

The action of theſe four Muſcles in the act of generation is, they open and dilate this common paſſage of Urine and Seed, that the Seed may be forcibly or violently caſt into the Field of Nature; and beſides, they then keep the Yard ſo ſtiff that it cannot bend to either ſide. Their Action.

The Yard is in number one, and ſituate upon the lower parts of the Share-bone, that it might be more ſtiff in erection. It hath connexion with the Share-bone and neighbouring parts, by the particles of which it is compoſed. It is of a cold and dry temper. The action of it is to caſt the Seed into the Womb, for preſervation of mankind.

The head of it begins where the tendons end; this head from the Figure thereof is called *Glans* and *Balanus*, that is, the Nut; and the skin which covers the head, is called *Præputium*, that is, the foreskin. The fleſh of this *Glandule* is of a middle nature between the glandulous fleſh and true skin. But you muſt note that the ligaments of the Yard, are ſpongy contrary to the condition of others, and filled with groſs and black bloud. But all theſe ſtirred up by the delight of deſired pleaſure, and provoked with a venereal fire, ſwell up and erect the Yard. The Nut. The *Præputium*, or Foreskin.

CHAP. XXXII.

Of the Spermatick Veſſels and Teſticles in Women.

NOw we ſhould treat of the Privy parts in Women, but becauſe they depend upon the neck and proper body of the Womb, we will firſt ſpeak of the Womb, having firſt declared what difference there is between the ſpermatick Veſſels and Teſticles of Men and Women. Wherefore we muſt know that the ſpermatick Veſſels in Women do nothing differ from thoſe in Men in Subſtance, Figure, Compoſure, Number, Connexion, Temper, Original, and Uſe; but onely in Magnitude and Diſtribution; for Women have them more large and ſhort. In what the ſpermatick Veſſels in Women differ from thoſe in Men.

It was fit they ſhould be more large, becauſe they ſhould not onely convey the matter fit for generation of Young and nouriſhment of the Teſticles, but alſo ſufficient for the nouriſhment of the Womb and Child; but ſhorter, becauſe they end at the Teſticles and Womb within the belly in Women. Where you muſt note, that the preparing ſpermatick Veſſels, a little before they come to the Teſticles, are divided into two unequal branches, of which the leſſer, bended after the ſame manner, as we ſaid in Men, goes into the head of the Teſticle, through which it ſends a ſlender branch into the Coats of the Teſticles for life and nouriſhment, and not onely into the Coats, but alſo into leading Veſſels. But the bigger branch deſcends on each ſide by the upper part of the Womb between the proper Coat and the common, from the *Peritonæum*, where it is divided into divers branches. By this difference of the ſpermatick Veſſels, you may eaſily underſtand why Women caſt forth leſs Seed than Men. Why Womens ſpermatick Veſſels are larger, but ſhorter then Mens.

For their Teſticles, they differ little from Mens but in quantity; for they are leſſer, and in Figure more hollow and flat, by reaſon of their defective heat which could not elevate or lift them up to their juſt magnitude. Their compoſure is more ſimple; for they want the *Scrotum* or Cod, the fleſhy Coat, and alſo, according to the opinion of ſome, the *Erythroides*; but in place thereof they have another from the *Peritonæum* which covers the proper Coat, that is, the *Epididymis* or *Dartos*. *Silvius* writes, that Womens Teſticles want the *Erythroides*; yet it is certain, that beſides their peculiar Coat *Dartos*, they have another from the *Peritonæum*, which is the *Erythroides*, or, as *Fallopius* calls it the *Elythroides*, that is as much as the *Vaginalis*, or ſheath. But I think that this hath ſprung from the miſunderſtanding that place in *Galen*, where he writes that Womens Teſticles want the *Epididymis*. For we muſt not underſtand that to be ſpoken of the Coat, but of the Varicous Paraſtates (as I formerly ſaid.) They differ nothing in number, but in ſite; for in Men they hang without the belly at the Share-bone above the *Peritonæum*; Women have them lying hid in their belly, near the bottom at the ſides of the Womb, but yet ſo as they touch not the body of the Womb. In what their Teſticles differ from Mens. *Lib. 14. de uſu Partium.* Site.

But theſe Teſticles are tied to the Womb, both by a Coat from the *Peritonæum*, as alſo by the leading Veſſels deſcending to the Horns of the Womb; but to the reſt of the body, by the Veſſels and the Nerves ariſing from the Holy-bone and Coſtal Nerves. They are of a colder Temper than Mans. The ejaculatory, or leading Veſſels in Women differ thus from Mens; they are large at the beginning, and of a Veiny conſiſtence, or ſubſtance, ſo that you can ſcarce diſcern them from the Coat *Peritonæum*, then preſently they become nervous, and wax ſo ſlender, that they may ſeem broken or torn, though it be not ſo; but when they come nearer to the Horns of the Womb, they are again dilated; in their own conditions, they agree with Mens, but that they are altogether more ſlender and ſhort. They have a round figure, but more intricate windings than Mens; I believe that theſe windings might ſupply the defect of the Varicous Paraſtates. They are Connexion. Temper. Their ejaculatory Veſſels. Why they have more intricate windings.

Their Site. are ſeated between the Teſticles and Womb; for they proceed out of the head of the Teſticle, then preſently, armed with a Coat from the *Peritonæum*, they are implanted into the Womb by its horns.

The Twelfth Figure of the Womb.

The Firſt Figure.

A *The bottom of the Womb laid open without any membrane.*

BB *The Neck of the Womb turned upward.*

CD *A part of the bottom of the Womb like the Nut of the Yard, ſwelling into the upper part of the Neck of the Womb, in the middle whereof the orifice appeareth.*

EE *A membrane knitting the Womb to the* Peritonæum, *and holding together the Veſſels thereof.*

F *The left Teſticle.*

G *The ſpermatical Vein and Artery.*

H *A part of the ſpermatical Veſſels reaching unto the bottom of the Womb.*

I *One part of the Veſſels coming to the Teſticles.*

* *A Veſſel leading the Seed unto the Womb.*

K *The Coat of the Teſticle with the implication of the Veſſels.*

L *The cavity of the Bladder opened.*

M *The inſertion of the Ureters into the Bladder.*

N *The Ureters cut from the Kidnies.*

O *The inſertion of the Neck of the Bladder into the Lap or Privity.*



The Second Figure.

a a *The ſpermatical Vein and Artery.* b b *Branches diſtributed to the* Peritonæum *from the ſpermatical Veſſels.* c *The bottom of the Womb.* d *The neck of the Womb.* e *Certain Veſſels running through the inſide of the Womb, and the neck thereof.* f f *Veſſels reaching to the bottom of the Womb produced from the ſpermatical Veſſel.* g g *The leading Veſſel of the Seed called* Tuba, *the Trumpet.* h h *A branch of the ſpermatical Veſſel compaſſing the Trumpet.* i i *The Teſticles.* k k *The lower ligaments of the Womb, which ſome call the Cremaſters or hanging Muſcles of the Womb.* l *The Lap or Privity in which the Cremaſters do end.* m *A portion of the neck of the Bladder.*

The Third Figure.

a a *The ſpermatical Veſſels.* b b *A branch from theſe ſpermatical Veſſels to the bottom of the Womb.* c *The body or bottom of the Womb.* d *The neck of the ſame.* e *The neck of the Bladder ending into the neck of the Womb.* f f *The Teſticles.* g g *The leading Veſſels, commonly (though not ſo well) called the Ejaculatory Veſſels.* h h *The diviſion of theſe Veſſels, one of them determining into the horns at double* k k. i i *The other branch ending in the neck, by which Women with child avoid their ſeed.* k k *The Horns of the Womb.*

The Fourth Figure.

AB *The boſom of the bottom of the Womb, at whoſe ſides are the Horns.* CD *A line like a ſuture or ſeam, a little diſtinguiſhing that boſom.* EE *The ſubſtance of the bottom of the Womb, or the thickneſs of his inner Coat.* F *A protuberation or ſwelling of the Womb in the middle of the boſom.* G *The orifice of the bottom of the Womb.* HH *The Coat or ſecond Cover of the bottom of the Womb, coming from the* Peritonæum. IIII *A portion of the Membranes which tie the Womb.* KK *The beginning of the neck of the Womb.* L *The neck of the Bladder inſerted into the neck of the Womb.* m *The* Clitoris *in the top of the Privity.* n *The inequality of the Privity where the* Hymen *is placed.* o *The hole or paſſage of the Privity in the cleft.* p *The ſkinny caruncle of the Privity.*

CHAP.

CHAP. XXIII.

Of the Womb.

THe Womb is a part proper onely to Women, given by nature in ſtead of the *Scrotum*, as the neck thereof, and the annexed parts in ſtead of the Yard; ſo that if any more exactly conſider the parts of generation in Women and Men, he ſhall find that they differ not much in number, but onely in ſituation and uſe. For that which man hath apparent without, that Women have hid within, both by the ſingular providence of Nature, as alſo by the defect of heat in Women, which could not drive and thruſt forth thoſe parts, as in men. The Womb is of a nervous and membranous ſubſtance, that it may be more eaſily dilated and contracted, as need ſhall require. Wherein the Privy parts in Women differ from thoſe in Men.

The magnitude thereof is divers, according to the diverſity of Age, the uſe of Venery, the flowing of their Courſes, and the time of Conception. The Womb is but ſmall in one of unripe Age, having not uſed Venery, nor which is Menſtruous; therefore the quantity cannot be rightly defined. The ſubſtance and magnitude of the Womb.

The figure of the Womb is abſolutely like that of the bladder, if you conſider it without the productions, which *Herophilus* called Horns, by reaſon of the ſimilitude they have with the horns of Oxen at their firſt coming forth. It conſiſts of ſimple and compound parts. The ſimple are the Veins, Arteries, Nerves, and Coats. The Veins and Arteries are four in number, two from the preparing ſpermatick Veſſels, the two other aſcend thither from the *Hypogaſtrick*, after this manner. Figure. The horns of the Womb. Compoſure. The Veins and Arteries.

Firſt, Theſe Veſſels before they aſcend on each ſide to the Womb, divide themſelves into two branches, from which otherſome go to the lower part of the Womb, otherſome to the neck thereof, by which the menſtruous bloud, if it abound from the Conception, may be purged.

Nerves come on both ſides to the Womb, both from the ſixth Conjugation, deſcending by the length of the back-bone, as alſo from the holy bone, which preſently united and joined together, aſcend and are diſtributed through the Womb, like the Veins and Arteries. Nerves.

The utmoſt or common Coat of the Womb proceeds from the *Peritonæum*, on that part it touches the holy bone; but the proper it hath from the firſt conformation, which is compoſed of the three ſorts of Fibers, of the right on the inſide of the attraction of both ſeeds; the tranſverſe without to expel, if occaſion be; the oblique in the midſt, for the due retention thereof. The Coats.

The Womb admits no diviſion, unleſs into the right and left ſide, by an obſcure line or ſeam, ſuch as we ſee in the *ſcrotum*, but ſcarce ſo manifeſt; neither muſt we after the manner of the Ancients, imagine any other Cells in the Womb. For by the Law of Nature, a Woman at one birth can have no more than two. An Argument hereof is, they have no more than two Dugs. If any chance to bring forth more, it is beſides Nature, and ſomewhat monſtrous, becauſe Nature hath made no proviſion of nouriſhment for them. No Cells in the Womb.

Nature hath placed the Womb at the bottom of the Belly, becauſe that place ſeems moſt fit to receive the ſeed, to carry and bring forth the Young. It is placed between the Bladder and right Gut, and is bound to theſe parts much more ſtraitly by the Neck than by the Body thereof; but alſo beſides, it is tied with two moſt ſtrong ligaments on the ſides and upper parts of the Sharebone, on which it ſeems to hang; but by its common Coat from the *Peritonæum*, chiefly thick in that place, it is tied to the Hollow bone, and the bones of the Hanch and Loins. The ſite.

By reaſon of this ſtrait connexion, a Woman with child feeling the painful drawings back, and as it were, convulſions of thoſe ligaments, knows her ſelf with child. It of a cold and moiſt temper, rather by accident than of it ſelf. The action thereof is to contain both the ſeeds, and to cheriſh, preſerve, and nouriſh it ſo contained, until the time appointed by Nature; and alſo beſides, to receive and evacuate the menſtruous bloud. The compound parts of the Womb are the proper Body and Neck thereof. That Body is extended in Women big with child, even to the Navel, in ſome higher, in ſome lower. The temper and action.

In the inner ſide the *Cotyledones* come into our conſideration, which are nothing elſe than the orifices and mouths of the Veins ending in that place. They ſcarce appear in Women, unleſs preſently after child-bearing, or their menſtrual purgation; but they are apparent in Sheep, Goats, and Kine, at all times like Wheat-corns, unleſs when they are with young; for then they are of the bigneſs of haſel nuts: but then alſo they ſwell up in Women, and are like a rude piece of fleſh of a finger and a half thick, which begirt all the natural parts of the Infant ſhut up in the Womb; out of which reſpect this ſhapeleſs fleſh, according to the opinion of ſome, is reckoned amongſt the number of Coats inveſting the Infant, and called *Chorion*, becauſe as in Beaſts the *Chorion* is interwoven with Veins and Arteries, whence the umbilical Veſſels proceed, ſo in Women this fleſhy lump is woven with Veins and Arteries, whence ſuch Veſſels have their original. Which thing, how true and agreeable to reaſon it is, let other men judge. The *cotyledones*. *Columbus* juſtly reproved.

There is one thing whereof I would admoniſh thee, that as the growth of the *Cotyledones* in Beaſts are not called by the name of *Chorion*, but are onely ſaid to be the dependents thereof; ſo in Women ſuch ſwollen *Cotyledones* merit not the name of *Chorion*, but rather of the dependences thereof.

This Body ends in a certain ſtraitneſs which is met withall, in following it towards the Privities, in Women which have born no children, or have remained barren ſome certain time, for in ſuch as are lately delivered you can ſee nothing but a cavity and no ſtraitneſs at all. This ſtraitneſs we call the proper orifice of the Womb, which is moſt exactly ſhut after conception, eſpecially until the Membrane, or Coats encompaſſing the Child be finiſhed and ſtrong enough to contain the ſeed that it flow not forth, nor be corrupted by entrance of the air; for it is opened to ſend forth the Seed, and in ſome the Courſes and ſerous humours which are heaped up in the Womb in the time of their being with Child The orifice of the Womb. The proper orifice of the Womb is not always exactly ſhut, in Women with Child.

The neck of the Womb.

From this orifice the neck of the Womb taking its original, is extended even to the Privities. It is of a muſculous ſubſtance, compoſed of ſoft fleſh, becauſe it might be extended and contracted, wrinkled, and ſtretched forth, and unfolded, and wreſted, and ſhaken at the coming forth of the child, and after be reſtored to its former ſoundneſs and integrity. In proceſs of age it grows harder, both by uſe of venery, and alſo by reaſon of age, by which the whole body in all parts thereof becomes dry and hard. But in growing and in young Women it is more tractable and flexible for the neceſſity of Nature.

Its Magnitude. Compoſition.

The magnitude is ſufficiently large in all dimenſions, though diverſe, by reaſon of the infinite variety of bodies. The figure of it is long, round, and hollow. The compoſition is the ſame with the Womb, but it receives not ſo many Veſſels as the Womb; for it hath none but thoſe which are ſent from the *Hypogaſtrick* Veins by the branches aſcending to the Womb. This neck on the inſide is wrinkled with many creſts, like the upper part of a Dogs mouth, ſo in copulation to cauſe greater pleaſure by that inequality, and alſo to ſhorten the act.

Number and Site.

It is onely one, and that ſituate between the neck of the bladder and the right Gut, to which it cloſely ſticketh, as to the Womb by the proper orifice thereof, and to the Privities by its own orifice; but by the Veſſels to all the parts from whence they are ſent.

Temper.

It is of a cold and dry temper, and the way to admit the ſeed into the Womb, to exclude the Infant out of the Womb, as alſo the menſtrual evacuation. But it is worth obſervation, that in

No *Hymen*.

all this paſſage there is no ſuch Membrane found as that they called *Hymen*, which they feigned to be broken at the firſt coition. Yet notwithſtanding *Columbus*, *Fallopius*, *Wierus*, and many other learned men of our time think otherwiſe, and ſay, that in Virgins a little above the paſſage of the Urine, may be found and ſeen ſuch a nervous Membrane, placed overthwart, as it were, in the middle way of this neck, and perforated for the paſſages of the courſes. But you may find this falſe by experience; it is likely the Ancients fell into this errour through this occaſion, becauſe that in ſome a good quantity of bloud breaks forth of theſe places at the firſt copulation.

The thirteenth Figure, ſhewing the parts of Women different from thoſe in Men.



A B C D *The* Peritonæum *reflected or turned backward, above and below.*

E F *The gibbous part of the Liver* E, *the cave or hollow part* F.

G *The trunk of the Gate Vein.*

H *The hollow Vein.*

I *The great Artery.*

K *The roots of the* Cœliacal *Artery which accompanieth the Gate Vein.*

L M *The fatty Vein going to the Coat of the Kidneys.*

N O *The fore-part of both the Kidneys.*

T V *The Emulgent Veins and Arteries.*

a a *The right Ureter at the loweſt* a, *cut from apart which, near to* b, *ſticketh yet to the bladder, becauſe the bottom of the bladder is drawn to the left ſide.*

c *The left Ureter inſerted into the Bladder near to* r.

d d *The Spermatick Vein which goeth to the left teſticle marked with* i.

e e *The Spermatick Vein which goeth to the left teſticle with* i *alſo.*

f *The trunk of the great Artery from whence the ſpermatical Arteries do proceed.*

g h *The ſpermatical Arteries.*

i i *The two teſticles.*

l l *A branch which from the ſpermatick Veſſels reacheth unto the bottom of the Womb.*

m m *The leading Veſſel of the Seed which* Fallopius *calleth the* Tuba *or trumpet, becauſe it is crooked and reflected.*

n *A branch of the ſpermatick Veſſel compaſſing the leading Veſſel.* o o *A Veſſel like a Worm which paſſeth to the Womb, ſome call it* Cremaſter. p *The bottom of the Womb, called* Fundus Uteri. q *A part of the right Gut.* r ſ *The bottom of the Bladder whereto is inſerted the left Ureter, and a Vein led from the neck of the Womb near unto* r. t *the neck of the Bladder.* u *The ſame inſerted into the Privity or Lap.* x *A part of the neck of the Womb above the Privity.* y y *Certain skinny Caruncles of the Privities, in the midſt of which is the ſlit, and on both ſides appear little billocks.*

The Figures belonging to the Dugs and Breſts.

α α *The Veins of the Dugs which come from thoſe, which deſcending from the top of the ſhoulder, are offered to the Skin.* β *The Veins of the Dugs derived from thoſe which through the arm-hole are led into the hand.* γ *The body of the Dug or Breſt.* δ δ *The Kernels and fat between them.* ε ε *The Veſſels of the Dugs deſcending from the lower part of the neck called* Jugulum, *under the Breſt-bone.*

From

But it is more probable that this happens by the violent attrition of certain Veſſels lying in the inward *ſuperficies* of the neck of the Womb, not being able to endure without breaking ſo great extention as that nervous neck undergoes at the firſt coition. For a Maid which is marriageable, and hath her genital parts proportionable in quantity and bigneſs to a Mans, ſhall find no ſuch effuſion of bloud, as we ſhall ſhew more at large in our Book of Generation. From whence the blood proceeds that breaks forth in ſome Virgins at the firſt coition.

This neck ends at the Privities, where its proper orifice is: which privy parts we muſt treat of, as being the productions and *appendices* of this neck. This *Pudendum* or Privity is of a middle ſubſtance, between the fleſh and a nerve; the magnitude is ſufficiently large, the figure round, hollow, long. It is compoſed of Veins, Arteries, Nerves, deſcending to the neck of the Womb, and a double Coat proceeding from the true Skin and fleſhy Pannicle; both theſe Coats are firmly united by the fleſh coming between them; whereupon it is ſaid that this part conſiſts of a muſculous Coat. It is one in number, ſituate above the *Peritonæum*. It hath connexion with the Fundament, the neck of the Womb and Bladder, by both their peculiar orifices.

It hath a middle temper, between hot and cold, moiſt and dry. It hath the ſame uſe as a mans *Præputium* or fore-skin, that is, that together with the *Nymphæ* it may hinder the entrance of the air, by which the Womb may be in danger to take cold. The lips of the Privities called by the *Greeks* Πτερυγώματα, by the *Latines Alæ*, contain all that region which is inveſted with hairs; and becauſe we have fallen into mention of theſe *Nymphæ*, you muſt know that they are, as it were, productions of the muſculous skin, which deſcend on both ſides from the upper part of the Share-bone downwards, even to the orifice of the neck of the bladder, oft-times growing to ſo great a bigneſs, that they will ſtand out like a Mans Yard. Wherefore in ſome they muſt be cut off in their young years, yet with a great deal of caution, leſt if they be cut too raſhly, ſo great an effuſion of bloud may follow, that it might cauſe either death to the Woman, or barrenneſs of the Womb, by reaſon of the refrigeration by the too great effuſion of bloud. The later Anatomiſts, as *Columbus* and *Fallopius*, beſides theſe parts, have made mention of another Particle, which ſtands forth in the upper part of the Privities, and alſo of the urinary paſſage, which joins together thoſe Wings we formerly mentioned. *Columbus* calls it *Tentigo*; *Fallopius Cleitoris*, whence proceeds that infamous word *Cleitorizein*, (which ſignifies impudently to handle that part.) But becauſe it is an obſcene part, let thoſe which deſire to know more of it, read the Authors which I cited. *Alæ.* Πτερυγώματα. *Cleitoris, Tentigo.*

CHAP. XXXV.

Of the Coats containing the Infant in the Womb, and of the Navel.

THe Membranes or Coats containing the Infant in the Womb of the Mother, are of a ſpermatick and nervous ſubſtance, having their matter from the ſeed of the Mother. But they are nervous, that ſo they may be the more eaſily extended, as it ſhall be neceſſary for the Child. They are of good length and bredth, eſpecially near the time of deliverance, they are round in figure like the Womb. Their ſubſtance, magnitude, figure, and compoſure.

Their compoſition is of Veins, Arteries, and their proper ſubſtance. The Veins and Arteries are diſtributed to them (whether obſcurely or manifeſtly, more or fewer) from the Womb by the *Cotyledones*, which have the ſame office, as long as the Child is contained in the Womb, as the Nipples or Paps of the Nurſes after it is born. For thus the Womb brings the *Cotyledones*, or Veins degenerating into them through the Coats like certain Paps to the Infant ſhut up in them.

Theſe Coats are three in number, according to *Galen*; one called the *Chorion*, Secundine, or After-birth; the other *Allantoides*, the third *Amnios*. I find this number of Coats in Beaſts but not in Women, unleſs peradventure any will reckon up in the number of the Coats the *Cotyledones*, ſwollen up and grown into a fleſhy maſs, which many skilful in Anatomy do write; which opinion notwithſtanding we cannot receive as true. I could never in any place find the *Allantoides* in Women with child, neither in the Infant born in the ſixth, ſeventh, eighth, or in the full time, being the nineth Moneth, although I ſought it with all poſſible diligence, the Midwives being ſet apart, which might have violated ſome of the Coats. The number.

But thus I went about this buſineſs: I divided the dead body of the Mother croſswiſe upon the region of the Womb, and taking away all impediments which might either hinder, or obſcure our diligence, with as much dexterity as was poſſible, we did not onely draw away that Receptacle or Den of the Infant from the inward ſurface of the Womb, to which it ſtuck by the *Cotyledones*, but we alſo took away the firſt Membrane which we called *Chorion*, from that which lies next under it, called *Amnios*, without any rending and tearing; for thus we poured forth no moiſture, whereby it might be ſaid, that any Coat made for the containing of that humour, was rent or torn. And then we diligently looked, having many Witneſſes and Spectators preſent, if in any place there did appear any diſtinction of theſe two Membranes, the *Allantoides* and *Amnios*, for the ſeparating the contained humours, and for other uſes which they mention.

But when we could perceive no ſuch thing, we took the *Amnios* filled with moiſture on the upper ſide, and having opened it, two ſervants holding the apertion, that no moiſture might flow out of it into the circumference of the *Chorion*, or Womb, then preſently with Spunges we drew out by little and little all the humidity contained in it, the Infant yet contained in it, which was fit to come forth, that ſo the Coat *Amnios* being freed of this moiſture, we might ſee whether there were any other humour contained in any other Coat beſides. But having done this with ſingular diligence and fidelity, we could ſee no other humour, nor no other ſeparation of the Membranes beſides.

He ſhews by three ſeveral reaſons that there is no *Allantoides*.

So that from that time I have confidently held this opinion, that the Infant in the Womb is onely wrapped in two Coats, the *Chorion* and *Amnios*. But yet not ſatisfied by this experience, that I might yet be more certain concerning this *Allantoides*, having paſſed through the two former Coats, I came to the Infant, and I put a quill into its Bladder, and blew it up as forcibly as I could, ſo to try if by that blowing I might force the Air into that Coat which we queſtioned, as ſome have written. But neither thus could I drive any Air from hence through the Navel into the controverted Coat, but rather I found it to fly out of the Bladder by the Privities. Wherefore I am certainly perſuaded that there is no *Allantoides*. Moreover I could never find, nor ſee, in the Navel, that paſſage called the *Urachus*, which they affirm to be the beginning and original of the Coat *Allantoides*. But if it be granted that there is no ſuch Coat as the *Allantoides*, what diſcommodity will ariſe hereof? ſpecially ſeeing the Sweat and Urine of the Infant may eaſily, and without any diſcommodity be received, collected, and contained in the ſame Coat, by reaſon of the ſmall difference which is between them. But if any object that the Urine by its ſharpneſs and touching will hurt the Infant: I will anſwer, There can be no ſo great ſharpneſs in the Urine of ſo ſmall an Infant; and that, if there be any, it is tempered by the admixture of the gentle vapour of Sweat.

Beſides, If you conſider or have regard to the uſe of ſuch an humour (which is to hold up the Child, leſt by its weight it break the ties, by which it is bound to the Womb;) we ſhall find no humour more fit for this purpoſe than this ſerous, as which by its thickneſs is much more fit to bear up a weight, than the thin and too liquid Sweat. For ſo we ſee the Sea or Salt-water carries greater weights without danger of drowning than freſh Rivers do. Wherefore I conclude that there is no need that the Urine ſhould be kept and contained in one Coat, and the Sweat in another. The Ancients who have writ otherwiſe, have written from obſervations made in Beaſts. Wherefore we make but onely two Coats, the *Chorion* and *Amnios*; the one of which, ſeeing it contains the other, they both ſo encompaſs the Child, that they veſt it on every ſide.

Fallopius in ſome ſort ſeems to be of this opinion; for he onely makes two Coats, the *Chorion* and *Amnios*; but he thinks the Infant makes the Water into a certain part of the *Chorion*, as you may perceive by reading of his Obſervations. Both theſe Coats are tied between themſelves by the intercourſe of moſt ſlender nervous Fibers, and ſmall Veſſels penetrating from the outer *Chorion* to the inner *Amnios*. Wherefore unleſs you warily handle theſe Coats, you may eaſily tear the *Amnios* in ſeparating it. They are of the ſame temper with other Membranes. Their uſe is different; for the *Chorion* is made both for the preſervation of the Veſſels which it receives from the Womb for the generating of the umbilical Veins and Arteries, as alſo to keep whole and ſafe the parts which it inveſts.

Their temper and uſe.

But the *Amnios* is to receive and contain the excrementitious and ſerous humours, which the Child ſhut up in the Womb is accuſtomed to evacuate. But this Coat is very thin and ſoft, but ſtrong and ſmooth, leſt by its touch it might hurt the Infant, whereupon it is called the Lambskin Coat.

CHAP. XXXV.

Of the Navel.

What the Navel is.

The Navel is the center of the body.

The Figure and Compoſure.

Lib. de format. fœtus in utero.

There is onely one Vein in a Childs Navel, but no *Urachus*

THe Navel follows theſe Coats: It is a white body, ſomewhat reſembling the wreathen Cord, or Girdle of the *Franciſcan* Friers, but that it hath not the knots ſtanding ſo far out, but onely ſwelling in certain places, reſembling a knot, onely lifted up on one ſide; it ariſes and takes its original from a fleſhy maſs, which we expreſſed by the name of ſwelling *Cotyledones*, and goes into the midſt of the lower Belly of the Infant, yea verily into the midſt of the whole Body, whoſe root it is therefore ſaid to be. For even as a Tree by the root ſucks nouriſhment from the Earth, ſo the Infant in the Womb draws its nouriſhment by the Navel. The greatneſs of it in breadth and thickneſs, equals the bigneſs of the little finger. But it is a foot and a half long, ſo that children are brought forth with it encompaſſing their middle, neck, arms, or legs. The Figure of it is round. It is compoſed of two Arteries, one Vein, and two Coats. It hath theſe Veſſels from that great multitude of capillary Veins and Arteries, which are ſeen diſperſed over the *Chorion*. Wherefore the Vein entring in at the Navel, penetrates from thence into the hollow part of the Liver, where divided into two, according to *Galen*'s opinion, it makes the Gate and Hollow Veins. But the Arteries carried by themſelves the length of the Navel, caſt themſelves into the *Iliacæ*, which they make, as alſo all other, that from thence the Vital ſpirit may be carried by them over all the Infant. It hath its two Coats from the *Chorion*.

But ſeeing they are mutually woven and conjoined without any *medium*, and are of a ſufficient ſtrength and thickneſs over all the Navel, they may ſeem to make the Infants external Skin and fleſhy Pannicle. I know very many reckon two umbilical Veins, as alſo Arteries, and the *Urachus*, by, or through which the Urine flows into the Coat *Allantoides*. But becauſe this is not to be found in Women, but onely Beaſts, I willingly omit it, becauſe I do not intend to mention any parts, but ſuch as belong to humane bodies. Yet, if there be any which can teach me, that theſe parts, which I think proper to brute Beaſts, are to be found in Women, I will willingly confeſs that to his credit, from whom I have reaped ſuch benefit.

The other things that may be required concerning the Navel, as of its number, ſite, connexion, temper, and uſe, may eaſily appear by that we have ſpoken before. For we have apparently ſet down the uſe, when we ſaid the Navel was made for that purpoſe, that the Infant may be nouriſhed by it, as the Tree by the root, by reaſon of the continuation of the Veſſels thereof, with the preparing ſpermatick Veſſels made by God for that purpoſe: To whom be honour and glory for ever and ever. *Amen.*

The End of the Third Book.

BOOK IV.

Treating of the Vital parts contained in the CHEST.

The PREFACE.

HAving finiſhed the firſt Book of our Anatomy, in explanation of the Natural Parts contained in the lower Belly: Now Order requires that we treat of the Breſt; that ſo the parts in ſome ſort already explained (I mean the Veins and Arteries) may be diſpatched after the ſame order and manner, without interpoſition of any other matter,

And beſides alſo, that we may the more exactly and chearfully ſhew the reſt of the parts which remain, as the Head and Limbs, knowing already the original of thoſe Veſſels which are diſperſed through them. To this purpoſe we will define what the Cheſt *is, and then we will divide it into its parts. Thirdly, in theſe we will conſider which parts contain, and which are contained; that ſo we may more happily finiſh our intended Diſcourſe.*

CHAP. I.

What the Thorax or the Cheſt is; into what parts it may be divided, and the nature of theſe parts.

THe *Thorax*, or Cheſt, is the middle Belly, terminated or bounded above with the Collar bones, below with the Midriff, before with the *Sternon* or Breſt, behind with the twelve *Vertebraes* of the Back, on both ſides, with the true and Baſtard Ribs, and with the intercoſtal and intercartilagineous Muſcles. Nature hath given it this ſtructure and compoſition, leſt that being a defence for the Vital parts againſt external injuries, it ſhould hinder reſpiration; which is no leſs needful for the preſervation of the native heat diffuſed by the vital ſpirits, and ſhut up in the Heart, as in the Fountain thereof, againſt internal injuries, than the other forementioned parts againſt the external. For if the Cheſt ſhould have been all bony, verily it had been the ſtronger, but it would have hindred our reſpiration or breathing, which is performed by the dilating and contracting thereof. Wherefore leſt one of theſe ſhould hinder the other, Nature hath framed it, partly bony and griſly, and partly fleſhy. Some render another reaſon hereof, which is, That Nature hath framed the Cheſt, that it might here alſo obſerve the order uſed by it in the Fabrick of things, which is, that it might conjoin the parts much diſagreeing in their compoſure, as the lower Belly, altogether fleſhy, and the Head all bony, by a medium partaker both of the bony and fleſhy ſubſtance; which courſe we ſee it hath obſerved in the connexion of the Fire and Water, by the interpoſition of the Air; of the Earth and Air, bythe Water placed between them.

The containing parts of the Cheſt.

Why Nature hath made the Cheſt partly bony, partly griſly.

The Cheſt is divided into three parts, the upper, lower, and middle,; the collar-bones contain the upper, the Midriff the lower, and the *Sternon* the middle. The *Sternon* in *Galen*'s opinion is compoſed of ſeven bones, I believe by reaſon of the great ſtature of the people that lived then. Now in our times you ſhall oft find it compact of three, four, or five bones, although we will not deny, but that we have often obſerved it (eſpecially in young bodies) to conſiſt of ſeven or eight bones.

The number of the bones of the *Sternon*.

Wherefore thoſe who have fewer bones in number in their *Sternon*, have them larger, that they might be ſufficient to receive the ribs, This is the common opinion of the *Sternon*. Yet *Fallopius* hath deſcribed it far otherwiſe; wherefore let thoſe who deſire to know more hereof, look in his Obſervations.

At the lower part of the *Sternon* there is a griſle called commonly *Furcula*, and *Malum granatum*, or the Pomegranate, becauſe it reſembles that fruit; others call it *Cartilago ſcutiformis*, that is, the Breſt-blade.

Cartilago ſcutiformis, the Breſt-blade.

It is placed there, to be (as it were) a Bulwark or defence to the mouth of the Stomach, endued with moſt exquiſit ſenſe; and alſo that it ſhould do the like to that part of the Midriff which the Liver bears up in that place ſituate above the orifice of the Ventricle by the ligament coming between, deſcending from the lower part of the ſame griſle into the upper part of the Liver.

The common people think that this Griſle ſometime falls down. But it ſo adheres, and is united to the bones of the *Sternon*, that the falling thereof may ſeem to be without any danger, although oft-times it may be ſo moiſtned with watery and ſerous humidities, with which the orifice of the Stomach abounds, that (as it were) ſoaked and drunk with theſe, it may be ſo relaxed, that it may ſeem to be out of its place; in which caſe it may be preſſed and forced by the hand into the former place and ſeat, as alſo by applying outwardly, and taking inwardly aſtringent and drying Medicins to exhauſt the ſuperfluous humidity.

This Griſle at its beginning is narrow, but more broad and obtuſe at its end, ſomewhat reſembling the round or blunt point of a Sword, whereupon it is alſo called *Cartilago Enſiformis*, or the Sword-like griſle. In ſome it hath a double, in others a ſingle point.

In old people it degenerates into a Bone. Now becauſe we make mention of this Griſle, we will ſhew both what a Griſle is, and how many differences thereof there be, that henceforward as often as we ſhall have occaſion to ſpeak of a Griſlle, you may underſtand what it is.

What a Griſle is. A Griſle is a ſimilar part of our bodies, next to a Bone moſt terreſtrial, cold, dry, hard, weighty, and without ſenſe, differing from a Bone in drineſs onely, the which is more in a Bone. Wherefore a Griſle being loſt, cannot be regenerated, like as a Bone, without the interpoſition of a *Callus*.

The differences thereof. The differences of theſe are almoſt the ſame with Bones, that is, from their conſiſtence, ſubſtance, greatneſs, number, ſite, figure, connexion, action, and uſe. Omitting the other for brevity ſake, I will onely handle thoſe differences which ariſe from ſite, uſe, and connexion. Therefore Griſles either adhere to the Bones, or of, and by themſelves make ſome part, as the Griſles of the Eye-lids called *Tarſi*, of the *Epiglottis*, and Throttle. And others which adhere to Bones, either adhere by the interpoſition of no *medium*, as thoſe which come between the Bones of the *Sternon*, the Collar-bones, the Share and Haunch-bones, and others; or by a ligament coming between, as thoſe which are at the ends of the Baſtard Ribs to the *Sternon* by the means of a Ligament, that by thoſe Ligaments being ſofter than a Griſle, the motions of the Cheſt may be more quickly and ſafely performed. The Griſles which depend on Bones, do not onely yield ſtrength to the Bones, but to themſelves, and the parts contained in them, againſt ſuch things as may break and bruiſe them. The Griſles of the *Sternon*, and at the ends of the Baſtard Ribs, are of this ſort.

Their twofold uſe. By this we may gather, that the Griſles have a double uſe, one to poliſh and levigate the parts to which that ſlippery ſmoothneſs was neceſſary for performance of their duty; and for this uſe ſerve the Griſles which are at the Joints, to make their motions the more nimble. The other uſe is to defend thoſe parts upon which they are placed, from external injuries, by breaking violent aſſaults, by ſomewhat yielding to their impreſſion, no otherwiſe than ſoft things oppoſed againſt Cannon-ſhot. We will proſecute the other differences of Griſles in their place, as occaſion ſhall be offered and required.

CHAP. II.

Of the containing and contained parts of the Cheſt.

The diviſion of the Cheſt into its parts. THe containing parts of the Cheſt are both the Skins, the fleſhy Pannicle, the Fat, the Breſts, the common Coat of the Muſcles, the Muſcles of that place, the fore-mentioned Bones, the Coat inveſting the Ribs, and the *Diaphragma* or Midriff. The parts contained are the *Mediaſtinum* the *Pericardium* or Purſe of the heart, the Heart, the Lungs and their Veſſels. Of the Containing parts, ſome are common to all the Body, or the moſt part thereof, as both the Skins, the fleſhy Pannicle and Fat. Of which being we have ſpoken in our firſt Book, there is no need now further to inſiſt upon: Others are proper to the Cheſt, as its Muſcles (of which we will ſpeak in their place) the Breſts, the fore-mentioned Bones, the Membrane inveſting the Ribs, and the *Diaphragma* or Midriff.

We will treat of all theſe in order, after we have firſt ſhewed you the way how you may ſeparate the Skin from the reſt of the Cheſt. Putting your Knife down even to the perfect diviſion of the Skin, you muſt draw a ſtraight line from the upper part of the lower Belly, even to the Chin; then draw another ſtraight line, overthwart at the Collar-bones even to the Shoulder-blades; and in the places between the Collar-bones: (if you deſire to ſhun prolixity) you may at once ſeparate both the Skins, the fleſhy Pannicle, the Fat, and common Coat of the Muſcles; becauſe theſe parts were ſhewed and ſpoken of in the diſſection of the lower Belly.

Yet you muſt reſerve the Breſts in diſſecting of the Bodies of Women; wherefore from the upper parts of the Breſts, as artificially as you can, ſeparate onely the Skin from the parts lying under it, that ſo you may ſhew the Pannicle which there becometh fleſhy and muſculous, and is ſo ſpred over the neck and parts of the Face, even to the roots of the hairs.

CHAP. III.

Of the Breſts or Dugs.

Their ſubſtance. THe Breſts, as we ſaid, when we ſpoke of the Nature of Glandules, are of a glandulous ſubſtance, white, rare, or ſpongious; in Maids and Women that do not give ſuck, they are more ſolid, and not ſo large.

Magnitude. Figure. Compoſure. Wherefore the bigneſs of the Dugs is different, although of a ſufficient magnitude in all. Their Figure is round, ſomewhat long, and in ſome ſort Pyramidal, their compoſure is of the Skin, the fleſhy Pannicle, Glandules, Fat, Nerves, Veins, and Arteries, deſcending to them from the *Axillaris* under the *Sternon*, betwixt the fourth and fifth, and ſometimes the ſixth of the true Ribs.

And there they are divided into infinite Rivulets by the interpoſition of the Glandules and Fat, by which fit matter may be brought to be changed into the Milk by the faculty of the Dugs.

Which Glandules have Nerves, and which have none. We will ſpeak no more of the Nature of the Glandules or Kernels, as having treated of them before; onely we will add this, that ſome of the Glandules have Nerves, as thoſe of the Breſts, which they receive from the parts lying under them, that is, from the intercoſtal, by which it comes to paſs, that they have moſt exquiſite ſenſe. Others want a nerve, as thoſe which ſerve only for diviſion of the veſſels, and which have no action, but only uſe.

They be two in number, on each ſide one, ſeated at the ſides of the *Sternon* upon the fourth, fifth, and ſixth true ribs.

Their connexion. Wherefore they have connexion with the mentioned parts with their body, but by their veſſels with all other parts, but eſpecially with the womb by the reliques of the mamillary veins and arteries,

teries, which deſcend down at the ſide of the Breſt-blade; in which place theſe Veins inſinuating themſelves through the ſubſtance of the Muſcles, are a little above the Navel conjoined with the *Epigaſtricks*, whoſe original is in ſome ſort oppoſite to the *Hypogaſtricks*, which ſend forth branches to the Womb. By the meeting of theſe it is more likely that this commerce ſhould ariſe, than from other, and thoſe almoſt capillary branches, which are ſometimes ſeen to deſcend to the Womb from the *Epigaſtrick*. How the breſts and womb communicate each with other.

They are of a cold and moiſt temper; wherefore they ſay, that the bloud by being converted into Milk, * becomes raw, flegmatick, and white, by the force of the proper fleſh of the Dugs. Their action is to prepare nouriſhment for the new-born Babe, to warm the Heart from whence they have received heat, and to adorn the Breſt. Their temper * *Recrudeſcit.* Their action and uſe.

By this you may know that ſome Glandules have action, others uſe, and ſome both. At the top of the Dugs there are certain hillocks, or eminencies called Teats or Nipples, by ſucking of which the Child is nouriſhed through certain ſmall and crooked paſſages, which though they appear manifeſt to the ſight, whileſt you preſs out the milk by preſſing the Dug, yet when the milk is preſſed out, they do not appear, nor ſo much as admit the point of a Needle, by reaſon of the crooked ways made by Nature in thoſe paſſages for this uſe, that the Milk being perfectly made, ſhould not flow out of its own accord againſt the Nurſes Will. For ſo the Seed is retained and kept for a certain time in the Proſtates. The Nipples.

CHAP. IV.

Of the Clavicles or Collar-bones, and Ribs.

IF we ſhould handle theſe parts after the common order, we ſhould now treat of the Muſcles of the Cheſt which move the Arm, and ſerve for reſpiration, and which firſt offer themſelves to our ſight.

But for that they cannot be fitly ſhewed, unleſs we hurt the Muſcles of the Shoulder-blade and Neck, therefore I think it better to defer the explanation of theſe Muſcles, until ſuch time as I have ſhewed the reſt of the contained and containing parts, not onely of the Cheſt, but alſo of the Head, that having finiſhed theſe we may come to a full demonſtration of all the reſt of the Muſcles, beginning with thoſe of the Head, which we firſt meet with, and ſo proſecuting the reſt even to the Muſcles of the Feet, as they ſhall ſeem to offer themſelves more fitly to diſſection, that ſo, as much as lies in us, we may ſhun confuſion.

Wherefore to return to our propoſed task; after the aforeſaid Muſcles, come the Collar-bones, *Sternon*, and Ribs.

But that theſe parts may be the more eaſily underſtood, we muſt firſt know what a Bone is, and whence the differences thereof are drawn.

Therefore a Bone is a part of our Body moſt terreſtrial, cold, dry, hard, wanting all manifeſt ſenſe, if the Teeth be excepted. What a Bone is.

I ſaid [manifeſt ſenſe,] that you may underſtand that the parts have a double ſenſe of Touching, the one manifeſt, ſuch as reſides in the Fleſh, Skin, Membranes, Nerves, Teeth, and certain other parts; the other obſcure, yet which may ſuffice to diſcern the helping and hurting tactile qualities, ſuch ſenſe the Bowels and Bones have; for very ſmall Fibers of the Nerves are diſſeminated to theſe parts by mediation of their Coat, or Membrane, I ſay, ſo ſmall that they can ſcarce be diſcerned by the eyes, unleſs (as *Galen* ſaith) by plucking ſuch Coats away from the parts. A double ſenſe. *Lib.* 1. *de Locis affectis.*

But it is no marvail, if Nature would have theſe parts in like manner to have ſuch ſmall Veins, contrary to the Lungs and moſt part of the Muſcles, onely to yield ſo much nouriſhment to the part, as ſhould be needful; for ſeeing the ſubſtance of the Bones is cold, hard, denſe and ſolid, it waſtes the leſs. Why the Bones have ſuch ſmall Veins.

Wherefore they need not ſo much bloud for their nouriſhment, as the hot and ſoft parts; and beſides the leſſer Bones have neither Veins or Arteries, but draw fit nouriſhment, onely by the force of the attractive faculty implanted in them.

The differences of Bones are taken from many things, as from their *Apophyſes*, *Epiphyſes*, Griſles, Necks, Heads, Solidity, Cavity, Eminencies, Marrow, Conſiſtence, Bigneſs, Number, Figure, Site. We will proſecute all theſe as they ſhall offer themſelves in the demonſtration of the Bones; to which doctrine we will give a beginning at the Clavicles or Collar-bones. Whence the difference of Bones may be taken.

The Clavicles are two very hard and ſolid Bones, without any great or notable cavity, ſituate on each ſide betwixt the ſide and upper part of the *Sternon* and top of the Shoulder-blade, for the ſtrength and ſtability of theſe parts, whence they take the name of *Clavicule* Clavicles, (from the *Greek* Κλεὶς, which ſignifies a Key, or any other Bar or faſtning of a Door.) They carry the ſhape of a Surgeons Levatory. The Clavicles or Collar-bones.

But you muſt note that the Clavicles ſeem to be faſtned to the *Sternon* by the mediation of a griſly bone, Moreover the ſpace and cavity contained within the Collar-bones, is called by the Latines *jugulum*, by the French the Upper *Furcula*, becauſe the Jugular Veins paſs that way; it ſticks to the Upper Proceſs of the Shoulder by a Griſle, which *Galen* calls the ſmall Griſle-bone, although it be nothing elſe but a production of the *Os juguli*. *Lib.* 13. *de uſu Part. cap.* 13.

For the *Sternon*, which we ſaid is framed of divers Bones, as ſometimes 3, ſometimes 4, 5, 6, 7, and ſometimes 8; you muſt note they are very ſpongy and full of pores, and of a far ſofter conſiſtence than the Collar-bones, wherefore more ſubject to corruption; beſides, they are mutually joined by interpoſition of Muſcles. Their uſe is to be as a ſhield to defend the Vital parts.

The Ribs are 24 in number, on each ſide 12, ſeven of theſe are called true or perfect Ribs, becauſe The Ribs.

cauſe they make a circle, at the one end joined to the *Sternon*, on the other to the *Vertebraes*; the other are called Baſtard, or ſhort Ribs, becauſe they fall ſhort in their way, and come not to the *Sternon*; but they are faſtned on the fore-ſide of the *Sternon* by Griſles and Ligaments, but on the back-part to the tranſverſe *Vertebraes* of the Back-bone, and to the ſides of the ſaid *Vertebraes*. But the ſhort Ribs are onely knit to the *Vertebraes*, wherefore that part of the *Vertebraes* is called the roots of the Ribs.

Their Conſiſtence.

The exterior, or fore-part of the Baſtard or ſhort Ribs, is griſly, that they ſhould not be broken, and that they might be the eaſier lifted up in the diſtenſions of the Stomach filled with meat. They are of a conſiſtence ſufficiently hard, yet more towards their root than at the *Sternon*, where they come nearer together, and are more hardly broken; they are ſmooth both within and without, but in the midſt they have ſome ſign of being double, or hollow, to receive the Veins and Arteries, which nouriſh their bony ſubſtance; they are faſhioned like a Bow; their uſe is the ſame with the *Sternon*, and beſides, to carry and ſtrengthen the Muſcles ſerving for reſpiration.

CHAP. V.

The Anatomical adminiſtration of the Sternon.

THe Coat inveſting the Ribs, which the common Anatomiſts call *Pleura*, is the laſt of the containing parts of the Cheſt, which becauſe it lies hid in the inner part thereof, it cannot be ſhewn unleſs by pulling aſunder of the *Sternon*; wherefore we muſt now ſhew the manner of opening the *Sternon*, that hereby they may not violate the original or inſertion of any of the Muſcles. Wherefore firſt you muſt underſtand, that he which will ſhew in their proper place their original and inſertion of the pectoral Muſcles, of the *Maſtoides*, of the two Muſcles of the Bone *Hyois*, of the Muſcles *ſubclavii*, and *intercartilaginei*, ought firſt of all to ſeparate all the pectoral Muſcles from the *Sternon*, and the Griſles from the true Ribs; then to cut the Ligaments, next the Bones themſelves, even from the ſixth true Rib to the Clavicles.

And then ſhewing the *Mediaſtinum* ſtretched under the *Sternon* all the length thereof, he muſt ſeparate the *Sternon* with his Knife, and bend it up to the Clavicles, and there cut it, reſerving together with it the four Muſcles, that is, the two *Maſtoides*, and the two moving the Bone *Hyois*, becauſe they either wholly, or for the moſt part, ariſe from the *Sternon*.

Laſtly, The Clavicles being ſomewhat thruſt upwards, the Griſles muſt on each ſide be turned outward toward the Arm; that ſo the containing parts of the Cheſt may not lie onely open to view, and be eaſily ſhewed, but alſo the Muſcles may be contained in their place, until they come to be ſhewed in their order.

And becauſe the Collar-bones muſt be lifted up very high, that the recurrent nerves may be more eaſily ſeen, and the diſtribution of the Veins and Arteries, the two ſmall Subclavian Muſcles, one on each ſide muſt be ſhewn by the way, who have their original from the inner and fore-part of the Clavicles and an oblique deſcent to the *Sternon*, towards the griſle of the firſt rib.

For the Clavicles cannot be thus ſeparated, but that theſe Muſcles muſt be violated and ſpoiled. Alſo you may divide the *Sternon* in the midſt, that you may ſhew the inward pectoral Muſcles whole having ſeparated the Muſcles which ariſe from the upper part. All which things being performed as they ought, we muſt come to the Coat inveſting the Ribs, and then to the *Mediaſtinum*, as ariſing from it.

CHAP. VI.

Of the Pleura, *or Coat inveſting the Ribs.*

What the membrane inveſting the ribs is.

THe *Tunica Subcoſtalis*, or Coat inveſting the Ribs, being the laſt of the containing parts of the Cheſt, is a large and a broad membrane anſwerable in proportion of uſe and action to the *Peritonæum* of the lower Belly. For as the *Peritonæum* generally and particularly covers all the natural parts, binding and holding them in their places, ſo this Coat inveſts all the Vital parts in general, becauſe it is ſtretched over all the inſide of the Cheſt, but in particular whileſt it gives each a Coat from it ſelf.

Its original.

It hath its original from the *Perioſteum* (or, as others will have it, from the *Pericranium*) inveſting the *Vertebraes* of the Cheſt at the roots of the Ribs. Wherefore it ſticks very faſt to the Ribs, ſcarce to be ſeparated, as alſo to all the parts bounding the Cheſt, and contained in it.

Veſalius reprehends *Galen*, becauſe he ſaid, that this was double on both ſides; yet *Columbus* defends *Galen*, and verily it is ſeen to be double in the inner part of the Cheſt, under the Ribs and the Muſcles of the Ribs, that in that ſpace there may be way for the Veins, Arteries, and Nerves.

Whether, as there is a twofold Pleuriſie, ſo alſo a double *Pleura*.

Some have made it twofold, and divided it into the internal and external; as thoſe which have made two ſorts of Pleuriſies, the true and baſtard; placing the external above the Ribs and intercoſtal Muſcles; but the internal under the Ribs, Muſcles, *Diaphragma*, and *Sternon*.

But we to ſhun ambiguity, intend onely to proſecute thoſe things which are manifeſt to the eyes; wherefore we ſay, that the Ribs are lined on the inſide with a double Coat; One which immediately and firmly ſticks to them on every ſide called the *Perioſteum*, which is common to them and other Bones. The other which lies upon that *Perioſteum*, and on the inſide inveſts all the Ribs, whence is it called the *Subcoſtalis tunica*. The ſubſtance, temper, and compoſure, are the ſame, as in other membranes.

The

The magnitude in length, as alſo the Figure, is the ſame with the compaſs of the inner part of the Cheſt; the thickneſs of it, is very little. The Coat is commonly called the *Pleura*, from the name of the part which it covers or lines, (for the *Greeks* call the Ribs Πλεῦρα,) and in like manner that which happens betwixt the *Perioſteum* and this *Pleura*, is called either a true or baſtard Pleuriſie. The Magnitude and Figure.

CHAP. VII.

Of the Mediaſtinum.

NOw we muſt ſpeak of the parts contained in the Cheſt, ſeeing we have already handled the containing: beginning with the *Mediaſtinum*, as being a part which in diſſection firſt preſents it ſelf to our ſight. The *Mediaſtinum* is of the ſame ſubſtance, thickneſs, compoſure, number, temper, as the *Pleura*. For the ſubſtance of the *Mediaſtinum* is membranous, and though it be ſtretched all the length of the Cheſt, yet it is of a ſmall thickneſs, receiving Veins, Nerves and Arteries from all the parts to which it is knit, like as the *Pleura* doth; but eſpecially from the Mammillary Veſſels, deſcending under the *Sternon*. The Subſtance and Magnitude.

It is in number one, but it is made of two Membranes produced from the Subcoſtal: for this aſcending on each ſide by the hollowneſs of the Cheſt to the *Sternon*, and then at right Angles, is reflected to the bodies of the *Vertebraes*, whence the *Pleura* hath it original.

In that reflection there is ſo much diſtance between each Membrane as may be ſufficient to receive two fingers. For otherwiſe, ſeeing that they cannot penetrate through the Heart, it was fit each ſide of the *Pleura* ſhould turn to the *Pericardium*, that ſo they might arrive at the appointed place without offence. Neither yet is that ſpace void and empty, but woven with many ſmall nervous Fibers. *Columbus* adds, that that place is often filled with a certain humour beſides Nature, which you may draw out, or evacuate, by opening the *Sternon*.

Yet I would gladly learn of *Columbus* by what ſigns we may know that ſuch an humour is contained there. For the Figure, the *Mediaſtinum* with the *Pleura* on each ſide, repreſents the Figure of a Leather Bottle, whoſe flat ſide is the *Mediaſtinum*, whoſe other ſide the *Pleura*; the bottom that part of the *Pleura* which is next the Midriff; the mouth the upper part of the *Pleura* at the firſt Ribs. We ſhewed the ſite and connexion of the *Mediaſtinum*, when we declared its original. The Figure.

The uſe thereof is to ſeparate the Vital parts (as it were) into two Cels, the right and left, that if peradventure it happen that the one be hurt, the Creature may live by the benefit of the other. The Uſe.

And it hath another uſe, which is, to prop and hold up the *Pericardium*, that it fall not upon the Heart with its weight, but toſſed with the motions of the Heart and Cheſt, it may move to this or that ſide.

CHAP. VIII.

Of the Diaphragma *or Midriff.*

ALthough the Midriff may ſeem to be accounted rather a part containing than contained, yet for commodities ſake, we have deferred the demonſtration thereof till now. Therefore, it is a Muſcle round and long, terminating the lower part of the Cheſt. What the Midriff is.

It is of the ſame ſubſtance, compoſition, and temper, as the Muſcles of the *Epigaſtrium*; it is made of two Coats, the lower whereof is from the *Peritonæum*, and the upper from the *Pleura*. Which getting to them fleſh, but not there, but in their circumference, by the benefit of the bloud brought thither by the Veins and Arteries diſtributed through it, turn into a Muſcle; whoſe middle is nervous and membranous, but the extremities by which it is inſerted, one while fleſhy, as in that part next to the Baſtard-Ribs; another while tendonous, as where it touches the firſt and ſecond *Vertebraes* of the Loins, for it ends in them by two Tendons manifeſt enough. It is one in number, interpoſed with an oblique ſite betwixt the Natural and Vital parts. It hath connexion with the lower part of the *Sternon* and Short-ribs, and the two firſt *Vertebraes* of the Loins, but by its Coats and Veſſels with the parts from whence it received them. Its ſubſtance, compoſition, &c. Connexion.

The extent thereof is equal to the compaſs of the lower part of the Cheſt. The length of it is from the Breſt-blade, even to the firſt and ſecond *Vertebra* of the Loins. The thickneſs is diverſe, for it is far thicker in its fleſhy extremity than in its nervous original. Quantity.

The action thereof is to help the expulſion of the Excrements by the mutual aſſiſtance of the *Epigaſtrick* Muſcles: but the chief uſe is for reſpiration, of which it is one of the prime inſtruments. This partition the Ancients called *Phrenes*, becauſe the inflammation thereof cauſed like ſymptoms, as the inflammation of the Brain, by reaſon of the large Nerves on each ſide one, which come to it directly and primarily from the third, fourth, and fifth *Vertebraes* of the neck. This Muſcle differs from other Muſcles, eſpecially in figure. It is perforated in three places, to give way or paſſage to the aſcendent Hollow-vein, to the Artery, *Aorta*, and the Gullet. Action. Why the *Diaphragma* was called *Phrenes*.

CHAP.

CHAP. VI.

Of the Lungs.

Their Substance. Quantity. The Lobes thereof.

THe Lungs are of a ſoft ſubſtance and fleſhy, rare and like a Sponge, of a various colour pamered; their quantity is ſufficiently large, for moſt commonly they are divided into four lobes, disjoined with a manifeſt and viſible diviſion, on each ſide two, whereby they may be the more eaſily opened and contracted, and the Air may the better enter.

Beſides alſo in large bodies, who have a very great Cheſt, there is found a fifth lobe, ariſing from the ſecond lobe of the right ſide, as a cuſhion or bolſter to bear up the Hollow Vein aſcending from the Midriff to the Heart.

In little Men who have a ſhorter Cheſt, becauſe the Heart is ſo near as to touch the *Diaphragma*, this lobe is not ſeen, yet it is always found in Dogs.

Figure. The Lungs repreſent the figure or ſhape of an Oxes foot or hoof; for like it they are thicker in their baſis, but ſlenderer in their circumference, as you may ſee in blowing them up by the weazon,

Compoſition. with your mouth or a pair of bellows. They are compounded of a Coat coming from the *Pleura* which on each ſide receives ſufficient number of Nerves from the ſixth conjugation; and alſo of the *Vena arterioſa* coming from the right Ventricle of the Heart, and the *Arteria venoſa* from the left, as ſhall be ſhewed in the Anatomy of the Heart; beſides the *Aſpera arteria* or Weazon coming from the Throat; and laſtly, its own fleſh, which is nothing elſe than the concretion of cholerick Bloud poured out like foam about the diviſions of the foreſaid Veſſels, as we have ſaid of other parts.

The body of the Lungs is one in number, unleſs you will divide it into two, by reaſon of the variety of its ſite, becauſe the Lobe of the Lungs ſtretched forth into the right and left ſide do almoſt involve all the Heart, that ſo they may defend it againſt the hardneſs of the bones which are about it, they are tied to the Heart chiefly at its baſis, but to the roots of the ribs, and their *Vertebraes* by the Coat it hath from thence; but by the Veſſels to theſe parts from whence they proceed. But oftThe ſticking of the Lungs to the Ribs. times preſently from the firſt and natural conformation they are bound to the circumference of the Ribs by certain thin and membranous productions which deſcend from thence to the Lungs, otherwiſe they are tied to the Ribs by the *Pleura*.

Their nouriſhment. The nouriſhment of the Lungs is unlike to the nouriſhment of other parts of the Body; for you cannot find a part equally rare, light, and full of air, which may be nouriſhed with bloud equally thin and vaporous. In temper they incline more to heat than to cold, whether you have regard to their compoſure of cholerick bloud, or their uſe, which is to prepare and alter the air, that it hurt not the Heart by its coldneſs. The Lungs is the inſtrument of Voice and Breathing by the Weazon or Wind-pipe. For the Lobes are the inſtruments of Voice, and the Ligaments of Reſpiration. But the *Larinx* or Throttle, is the chief inſtrument of the Voice; for the Weazon firſt prepares the Voice for the Throttle, in which it being in ſome meaſure formed, is perfected in the Palate of the Mouth, as in the upper part of a Lute, or ſuch like Inſtrument, by the help of the *Gargareon* or *Uvula*, as a certain quill to play withall.

But as long as one holds his breath he cannot ſpeak, for then the Muſcles of the *Larinx*, Ribs, the *Diaphragma*, and the *Epigaſtrick* Muſcles are preſſed down, whence proceeds a ſuppreſſion of the Vocal matter, which muſt be ſent forth in making or uttering a Voice.

Why the Lungs are light. Nature would have the Lungs light for many reaſons; the firſt is, That ſeeing they are of themſelves immoveable, they might be more obſequious and ready to follow the motion of the Cheſt; for when it is ſtraitned, the Lungs are ſtraited and ſubſide with it; and when it is dilated, they alſo are dilated, and ſwell ſo big, that they almoſt fill up all the upper capacity thereof.

Another cauſe is, That by this their rarity they might more eaſily admit the entring air at ſuch times as they have much or ſudden neceſſity, as in running a Race.

And laſtly, That in Pleuriſies and other purulent abſceſſes of the Cheſt, the *Pus* or matter poured forth into the capacity of the Cheſt, may be ſuckt in by the rare ſubſtance of the Lungs, and by that means the ſooner ſent forth and expectorated,

The uſe of reſpiration or breathing. The uſe of Reſpiration is to cool and temper the raging heat of the Heart. For it is cooled in drawing in the breath by the cool air, and in ſending out thereof by avoiding the hot fuliginous vapour. Therefore the Cheſt performs two contrary motions, for whileſt it is dilated it draws in the encompaſſing the air, and when it is depreſſed, it expels the fuliginous vapour of the Heart; which any one may eaſily perceive by the example of a pair of Smiths Bellows.

CHAP. X.

Of the Pericardium, *or Purſe of the Heart.*

Whence it hath its matter. THe *Pericardium* is (as it were) the houſe of the Heart, which ariſing at the baſis thereof (either the Ligaments of the *Vertebraes* ſituate there, or elſe the Veſſels of the Heart yielding it matter) is of a nervous, thick and denſe ſubſtance without any Fibers. It retains the Figure of the Heart, and leaves an empty ſpace for the Heart to perform its proper motion. Wherefore the bigneſs of the *Pericardium* exceeds that of the Heart.

It conſiſts of a double Coat, one proper, of which we have ſpoken; another common, coming from the *Pleura*; and alſo of the Veins, Arteries, and Nerves; the Veſſels partly coming from the Mamillary, partly from the *Diaphragma*, chiefly there where it touches it; the Nerves come on each ſide from the ſixth conjugation.

It

It is onely one, placed about the Heart, and annexed to it at the baſis thereof by its Membranes, to the original of the Lungs, and the *Vertebraes* lying under them, and by the Veſſels to the parts from whence it received them. It is of a cold and dry temper, as every Membrane is. Number and connexion.

The uſe thereof is to cover the Heart, and preſerve it in its native humidity, by certain natural moiſture contained in it, unleſs you had rather ſay, that the moiſture we ſee contained in the *Pericardium*, is generated in it after death by the condenſation and concretion of the ſpirits. Although this ſeems not very likely, becauſe it grows and is heaped up in ſo great quantity in living bodies, that it hinders the motion of the Heart, and cauſes ſuch palpitation, or violent beating thereof, that it often ſuffocates a man. Uſe.

For this Palpitation happens alſo to hearty and ſtout men, whoſe hearts are hot, but bloud thin and wateriſh, by reaſon of ſome infirmity of the Stomach or Liver; and this humour may be generated of vapours which on every ſide exhale into the *Pericardium* from the bloud boiling in the Ventricles of the Heart, where kept in by the denſity thereof, they turn into yellowiſh moiſture; as we ſee it happens in an Alembeck. From whence the matter of the watery humour contained in the *Pericardium*.

Nature would have the *Pericardium* of a denſe and hard conſiſtence, that by the force thereof the Heart might be kept in better ſtate; for if the *Pericardium* had been bony, it would have made the Heart like Iron by the continual attrition; on the contrary, if it had been ſoft and fungous, it would have made it ſpongy and ſoft like the Lungs. The Conſiſtence.

CHAP. XI.

Of the Heart.

THe Heart is the chief Manſion of the Soul, the Organ of the Vital Faculty, the beginning of Life, the Fountain of the Vital Spirits, and ſo conſequently the continual nouriſher of the Vital Heat, the firſt living and laſt dying; which becauſe it muſt have a natural motion of it ſelf, was made of a denſe, ſolid, and more compact ſubſtance than any other part of the Body. What the Heart is, and of what ſubſtance.

The fleſh thereof is woven with three ſorts of fibers, for it hath the right in the inner part deſcending from the baſis into the point, that they might dilate it, and ſo draw the bloud from the Hollow Vein into the receptacles thereof, and the breath or air from the Lungs by the *Arteria venoſa*; it hath the tranſverſe without, which paſs through the right at right angles, to contract the Heart, and ſo drive the Vital Spirits into the great Artery *Aorta*, and the cholerick bloud to the Lungs by the *Vena arterioſa* for their nouriſhment; It hath the oblique in the midſt to contain the air and bloud drawn thither by the fore-mentioned Veſſels, until they be ſufficiently elaborate by the Heart. The three ſorts of Fibers of the Heart.

All theſe Fibers do their parts by contracting themſelves towards the original, as the right from the point of the Heart towards the Baſis, whereby it comes to paſs, that by this contraction of the Fibers the Heart dilated becomes ſhorter, but broader, no otherwiſe than it is made more long and narrow by the contraction of the tranſverſe: but, by the drawing of the oblique, it is leſſened in that part which looks towards the *Vertebraes*, which chiefly appears in the point thereof.

It is of an indifferent bigneſs, but yet in ſome bigger, in ſome leſs, according to the diverſe tempor of cold or hot men, as we noted in the Liver. The Magnitude.

The figure thereof is pyramidal, that is, it is broader in the baſis, and narrower at his round point. Figure.

It is compoſed of the moſt denſe fleſh of all the body, by the effuſion of bloud at the diviſions and foldings of the Veſſels, and there concrete, as it happens alſo to the other entrails. For the bloud being there a little more dried than that which is concrete for the making of the Liver, turns into a fleſhy ſubſtance more denſe than the common fleſh, even as in hollow Ulcers, when they come to cicatrize. Compoſition.

It hath the Coronal Veins and Arteries, which it receives either on the right ſide from the Hollow Vein, or on the left from the Baſis at the entrance of the Artery *Aorta*. You cannot by your eye diſcern that the Heart hath any other Nerves than thoſe which come to it with the *Pleura*. The proper Veſſels.

Yet I have plainly enough obſerved others in certain Beaſts which have great hearts, as Swine; they appeared ſeated under the fat which covers the Veſſels and Baſis of the heart, leſt the humid ſubſtance of theſe parts ſhould be diſſolved and diſſipated by the burning heat of the Heart. Whereby you may perceive that the heat of the Heart is different from the Elementary heat, as that which ſuffers fat to grow about this entrail, where otherwiſe it doth not concrete, unleſs by cold, or a remiſs heat, which thing is chiefly worth admiration. The Nerves.

The Heart is one alone, ſituate moſt commonly upon the fourth *Vertebra* of the Cheſt, which is in the midſt of the Cheſt. Yet ſome think that it inclines ſomewhat to the left ſide, becauſe we there feel the motion or beating thereof; but that happens by reaſon of its left Ventricle, which being it is filled with many Spirits, and the beginning of the Arteries, it beats far more vehemently than the right. It required that ſeat by the decree of Nature, becauſe that region is the moſt ſafe and armed, and beſides it is here on every ſide covered (as it were with the hands of the Lungs. Number and Site.

It hath connexion with the fore-mentioned *Vertebraes*, but by the parts compoſing it, with thoſe parts from whence it hath them; with the Lungs by the *Vena arterioſa* and the *Arteria Venoſa*; and laſtly, with all the parts of the body by the Arteries which it ſends to them all. Connexion.

It is of a hot and moiſt temper, as every fleſhy part is. The action thereof is, firſt to prepare the bloud in its right Ventricle, for the fit nouriſhment of the Lungs; for from hence it is that *Galen* ſaith the right Ventricle was made for the neceſſity of the Lungs. Secondly to generate the Vital Spirits in its left Ventricle for the uſe of the whole body. But this Spirit is nothing elſe than a Temper and Action. What the Vital Spirit is.

certain

certain middle ſubſtance between Air and Bloud, fit to preſerve and carry the native heat, wherefore it is named the Vital, as being the Author and preſerver of life. In the inner parts of the heart there preſent themſelves to our conſideration, the Ventricles, and the parts contained in the Ventricles and between them; ſuch are the *Valvulæ*, or Valves, the Veſſels and their Mouths, their diſtribution into the Lungs, the Wall or Partition, and the two productions or Ears of the Heart; which becauſe they are doubtful, whether they may be reckoned amongſt the external or internal parts of the Heart, I will here handle in the firſt place.

The *Auriculæ cordis*, or Ears of the Heart.

Therefore theſe *Auriculæ* or Ears, are of a ſoft and nervous ſubſtance, compact of three ſorts of Fibers, that ſo by their ſoftneſs they might the more eaſily follow the motions of the Heart, and ſo break the violence of the matter entering the Heart with great force when it is dilated. For otherwiſe by their violent and abundant entrance they might hurt the Heart, and (as it were) overwhelm and ſuffocate it; but they have that capacity which we ſee given by Nature, that ſo they might (as it were) keep in ſtore the Bloud and Air, and then by little and little draw it forth for the uſe of the neceſſity of the Heart. But if any enquire if ſuch matters may be drawn into the Heart by the onely force of the *Diaſtole*, *ad fugam vacui*, for avoiding of emptineſs; I will anſwer, That that drawing in, or attraction, is cauſed by the heat of the Heart, which continually draws theſe matters to it, no otherwiſe then a Fire draws the adjacent Air, and the flame of a Candle the Tallow which is about the wiek for nouriſhments ſake. Whileſt the Heart is dilated it draws the air, whileſt it is drawn together, or contracted, it expels it. This motion of the Heart is abſolutely natural, as the motion of the Lungs is animal. Some add a third cauſe of the attraction of the Heart, to wit, the ſimilitude of the whole ſubſtance. But in my judgment, this rather takes place in that attraction which is of bloud by the *Venæ coronales* for the proper nouriſhment of the Heart, than in that which is performed for attraction of matters for the benefit of the whole Body.

Their magnitude and number.

Theſe Ears differ in quantity, for the right is far more capacious than the left, becauſe it was made to receive a greater abundance of matter. They are two in number, on each ſide one, ſituate at the baſis of the Heart: The greater at the entrance of the Hollow Vein into the Heart, the leſs at the entrance of the veinous and of the great Artery, with which parts they have both connexion.

Their uſe.

We have formerly declared what uſe they have, that is, to break the violence of the matters, and beſides to be ſtays or props to the *Arteria venoſa* and great Artery, which could not ſuſtain ſo rapid and violent a motion as that of the Heart, by reaſon of their tenderneſs of ſubſtance.

Of the Ventricles of the Heart.

The partition between the Ventricles of the Heart.

THe Ventricles are in number two, on each ſide one, diſtinguiſhed with a fleſhy partition ſtrong enough, having many holes in the ſuperficies, yet no where piercing through.

The right of theſe Ventricles is the bigger, and encompaſſed with the ſofter and rarer fleſh; the left is the leſſer, but is engirt with a threefold more denſe and compact fleſh; for the right Ventricle was made for a place to receive the bloud brought by the hollow Vein, and for diſtributing of it, partly by the *Vena arterioſa* into the lungs for their nouriſhment, partly into the left Ventricle by ſweating through the wall or partition, to yield matter for the generation of the Vital ſpirits.

Why the right Ventricle is more capacious and leſs compact.

Therefore becauſe it is needful there ſhould be ſo great a quantity of this bloud, it was likewiſe fit that there ſhould be a place proportionable to receive that matter. And becauſe the bloud which was to be received in the right Ventricle was more thick, it was not ſo needful that the fleſh to contain it ſhould be ſo compact; but on the contrary, the arterious bloud and vital ſpirit have need of a more denſe receptacle, for fear of waſting, and leſt they ſhould vaniſh into air; and alſo leſs room, that ſo the heat being united, might become the ſtronger, and more powerfully ſet upon the elaboration of the bloud and ſpirits.

The action of the right Ventricle.

Therefore the right Ventricle of the Heart is made for preparation of the bloud appointed for the nouriſhment of the Lungs, and the generation of the vital ſpirits, as the Lungs are made for the mitification or qualifying of the Air. Which works were neceſſary if the Phyſical Axiom be true, *That like is nouriſhed by like*, as the rare and ſpongious Lungs with more ſubtil bloud; the ſubſtance of the Heart groſs and denſe, with the veinous bloud, as it flows from the Liver, that is groſs.

The action of the left Ventricle.

And it hath its Coronal Veins from the hollow Vein, that it might thence draw as much as ſhould be ſufficient.

But the left Ventricle is for the perfecting of the vital ſpirit, and the preſervation of the native heat.

Of the Orifices and Valves of the Heart.

The uſes of the four orifices of the Heart.

THere be four Orifices of the Heart, two in the right, and as many in the left Ventricle; the greater of the two former gives paſſage to the Vein, or the bloud carried by the hollow Vein to the Heart; the leſſer opens a paſſage to the *Vena arterioſa*, or the cholerick bloud carried in it for the nouriſhment of the Lungs.

The larger of the two other makes a way for the diſtribution of the Artery *Aorta*, and the vital ſpirit through all the Body; but the leſſer gives egreſs and regreſs to the *Arteria venoſa*, or to the air and fuliginous vapours. And becauſe it was convenient that the matters ſhould be admitted into their proper Ventricles by theſe orifices, by the *Diaſtole*, to wit, into the right Ventricle by the greater orifice, and into the left by the leſſer; and becauſe on the contrary it was fit that the matters ſhould be expelled by the *Syſtole* from their Ventricles, by the fore-mentioned orifices.

The Valves.

Therefore Nature to all theſe orifices hath put eleven Valves, that is to ſay, ſix in the right Ventricle, that there might be three to each orifice; five in the left, that the greater orifice might have three and the leſſer two, for the reaſon we will preſently give.

How they differ.

Theſe Valves differ many ways: Firſt in action; for ſome of them carry in matter to the Heart, others

others hinder that which is gone out, that it come not back again. Secondly, they differ in ſite: For thoſe which bring in, have membranes without, looking in; thoſe which carry out, have them within looking out. Thirdly, in figure; for thoſe which carry in, have a Pyramidal figure, but thoſe which hinder the coming back again, are made in the ſhape of the Roman Letter C. Fourthly, in ſubſtance; for the former for the moſt part are fleſhy, or woven with fleſhy fibers into certain fleſhy knots ending towards the point of the heart: The later are wholly membranous. Fifthly; they differ in number: for there be only five which bring in, three in the right ventricle at the greater orifice, and two in the left at the leſſer orifice; thoſe which prohibit the coming back, are ſix in each ventricle, three at each orifice. Laſtly, they differ in motion: for the fleſhy ones are opened in the *Diaſtole*, for the bringing in of blood and ſpirit, and contrariwiſe are ſhut in the *Syſtole*, that they may contain all, or the greater part of that they brought in. The membranous on the contrary are opened in the *Syſtole* to give paſſage forth to the blood and ſpirits over all the body, but ſhut in the *Diaſtole*, that that which is excluded might not flow back into the heart. But you ſhall obſerve that Nature hath placed only two Valves at the orifice of the *Arteria venoſa*, becauſe it was needful that this orifice ſhould be always open, either wholly, or certainly a third part thereof; that the air might continually be drawn into the heart by this orifice in Inſpiration, and ſent forth by Exſpiration in the contraction of the heart. Whereby we may gather this, that there is but one third part of that air we draw into the heart in breathing, ſent forth again in the form of vapor in Exſpiration, becauſe Nature would have but one third part of the orifice to lye open for its paſſage out. Therefore the Exſpiration or breathing out, and the *Syſtole* of the heart and arteries, is ſhorter than the Inſpiration, ſo that we may truly ſay, that the Inſpiration, or drawing the breath in, is equally ſo long as the Exſpiration is together with the reſt, which is in the midſt between the two motions.

Action. Site. Figure. Subſtance. Number. Motion.

Why there be only two Valves at the orifice of the *Arteria venoſa*.

CHAP. XII.

Of the diſtribution of the Vena arterioſa, *and the* Arteria venoſa.

HAving hitherto ſhewed the original of the veſſels of the heart, we muſt now ſpeak of their diſtribution. The *Vena arterioſa*, or the arterious vein; and the *Arteria venoſa*, or the veinous artery, each proceeding out of his proper ventricle, that is, the right and left, are divided into two large branches; one of which goes to the right, and the other to the left hand, the one lying croſs-ways over the other, the vein always riding over the artery, as you may underſtand better by the ſight of your eyes, than by reading of Books. Theſe branches at their entrance of the Lungs are divided into two other large branches, and each of them go to his peculiar Lobe of the Lungs; and theſe again run almoſt into infinite other branches, diſperſed in the places over the Lungs.

The artery always lies under the vein.

Theſe veſſels have acquired their names by reaſon of that Tranſmutation of conſiſtence, whereby the compoſure of a vein degenerates into an artery, and that of an artery into a vein, for the commodity of life. For this is a miracle of prudent Nature to change the coats of the veſſels of the Lungs; producing a vein which in its body ſhould imitate an artery, and an artery which ſhould repreſent a vein: For if the *Vena arterioſa* ſhould have retained its proper conſiſtence, the arterious blood which is carried by it from the Heart to nouriſh the Lungs, might by reaſon of its ſubtilty penetrate through, and flow away by reaſon of the rarity of the veinous texture: And ſo Nature ſhould never have attained her conceived end, that is, to nouriſh the Lungs, by reaſon of the continual motion of their contraction and dilatation.

A twofold reaſon why the vein was made arterious, or like an artery.

For nouriſhment cannot be aſſimilated to the part, unleſs it be put and cleave to it. Wherefore it was fit, that Nature ſhould make the body of this vein ſolid, that it might be immoveable, unſhaken and ſtubborn (in reſpect of a vein which by its ſoftneſs would have been too obſequious and yielding to the agitation of the Lungs) that ſo it might have nouriſhment, which might be diffuſed into all parts thereof, and which might neither be drawn by its *Diaſtole*, nor driven back into the heart by its *Syſtole*. But the artery hath the conſiſtence of a vein, that by that veinous ſoftneſs according to the neceſſity of Nature, it might be the more readily contracted and dilated, to bring the air in, and carry the vapours forth of the heart. Here we meet with a difficulty, which is, by what way the blood is carried out of the right and left ventricle of the heart.

Wky the artery was made like a vein.

Galen thinks that there be certain holes in the partition made for that purpoſe; and verily there are ſuch, but they are not perforated. Wherefore *Columbus* hath found out a new way, which is, that the blood is carried to the Lungs by the *Vena arterioſa*, and there attenuated; and carried from thence together with the air by the *Arteria venoſa* to the left ventricle of the heart; this he writes, truly very probably. *Botallus*, in his Treatiſe *de Catarrho*, hath found out a third way, to wit, a vein, which he calls *Arteriarum nutrix*, that is, the nurſe of the arteries, which creeps a little above the coronal to the right ear of the heart, and then goes into the left ear thereof. But yet I am very much afraid, that this vein obſerved by *Botallus*, is that veſſel obſerved by *Fallopius*, whereby the *Vena arterialis* is joyned to the *Aorta*, and by which all the vital blood is carried for the forming and nouriſhment of the Lungs while the Infant is yet in the womb. Of which alſo *Galen* makes mention, but it had lain hid from his time to this day, but that *Fallopius* raiſed up the memory of it again.

By what way blood may paſs out of the right into the left ventricle.

The vein called the Nurſe of the arteries. *Fallop. initio obſer. Arteriarum. Gal. l. 15. de uſu partium, cap. 6.*

CHAP. XIII.

The Diſtribution of the aſcendent Hollow-vein.

Gal. lib de ſorm. fœtus. The greater deſcendant branch of the hollow vein.

THe hollow vein riſing out of the gibbous part of the liver, and reſembling (according to *Galen*) the body of a Tree, is divided into two notable branches, but not of a like bigneſs. For the greater, by the hind-part of the liver upon the back-bone, and by the way, receives certain other branches from the ſubſtance of the liver, which enter not into the great trunk with the reſt. You may often ſee this deſcendent branch even to the back-bone, upon which it lies in this its deſcent, covered with the ſubſtance of the liver, ſo that it may ſeem that branch proceeds not from that common trunk together with the aſcendent, although indeed it always doth. But the leſſer branch aſcends to the upper parts, and is diſtributed after this manner following: For firſt ariſing into the midriff, it beſtows two ſmall veins upon it, on each ſide one, which from that part are called *Phrenicæ*. But from thence when it arrives at the right ear of the heart, it makes the *Coronales*, the Coronal or Crown-veins, which compaſs the *baſis* of the heart in manner of a crown. Thirdly, entring ſomewhat more deeply into its right ear, in its greater part it produces the *Vena arterioſa*. Fourthly, lifted up above the heart, on the right ſide it produces the vein *Azygos* or *ſine pari* (that is, without a fellow) which deſcending to the fourth rib, (reckoning from above downwards) nouriſheth the intercoſtal muſcles, and alſo the membranes of the eight lower ribs, on both ſides, ſending a branch into each of the muſcles at the lower part of the rib, which may be ſufficient for their nouriſhment. Beſides alſo oftentimes, eſpecially in little men, this vein *Azygos* nouriſhes all the ſpaces between all the ribs by the like branches, which it ſends in the ſame manner to the four ribs. Moreover alſo, this *Azygos* ſometime, though but ſeldom, is found double, that is, on each ſide one. Here you muſt chiefly obſerve, that this vein, after it hath nouriſhed the ſpaces between the lower ribs, in its remainder deſcends under the *Diaphragma*, and is joyned on the left ſide to the Emulgent vein; by which it is manifeſt how an Abſceſs may be critically evacuated by the urine, in a Pleuriſie. But this ſame *Azygos* is more depreſſed on the right ſide, and meets with the *Venæ lumbares*, but eſpecially with one of them which goes down to the thigh, whereby *Fallopius* gathers, that it is very convenient in the beginnings of Pleuriſies, to open the *Vena poplitis*, the vein of the ham. Fifthly, above the *Azygos* (when it is wanting there) it ſends forth the branch called *Intercoſtalis* to the other ſpaces between the upper ribs; although this is ſometimes ſeen to come from the *Axillaris*, which *Sylvius* calls the *Subclaviæ*. Sixthly, it brings forth the *Mammariæ*, ſo called, becauſe in their greater part they run to the dugs between the fourth and fifth ribs, for the uſes formerly mentioned, men and women have on each ſide one of theſe coming from the *Subclaviæ*. They are ſometimes found to proceed by a certain common orifice from the hollow vein, before it be divided into the *ſubclavian* branches, but it is rather in beaſts than in men; theſe veins deſcending by the ſides of the *Sternon*, yield nouriſhment to the two inner muſcles of the cheſt, to the ſeven intercoſtal muſcles of the true ribs, to the *Sternon* it ſelf, and to its ligaments and griſtles, as alſo to the *Mediaſtinum* and the upper part of the right muſcles, and the adjacent parts. Seventhly, it produces the *Cervicalis*, which on both ſides through the holes of the productions of the *Vertebra's* of the neck, aſcends to the head, ſending many ſmall branches into the ſpinal marrow through the holes by which the nerves paſs; and alſo into the membranes, ligaments, griſtles, bones, and neighbouring muſcles. Eighthly, the *Muſculoſa*, or muſculous, which alſo ariſing out of the *Subclaviæ*, is divided into two other branches: The one whereof goeth upon the breaſt to the paps nouriſhing the fore-moſt muſcles; wherefore in a baſtard-pleuriſie, cupping-glaſſes may be fitly applied in this place.

The upper branch of the hollow vein is the leſs.

Venæ phrenicæ Coronales.

Vena Arterioſa.

Vena Azygos, or ſine pari.

This *Azygos* ſometimes two.

How the matter of a pleuriſie may be evacuated by urin.

Intercoſtalis.

Mammaria.

Cervicalis.

Muſculoſa.

In what place cupping-glaſſes may be fitly applied in a baſtard pleuriſie.

The other branch deſcends to the upper muſcles of the cheſt, but ſpecially to that which is called *Latiſſimus*. The Tenth is the *Axillaris*. The Eleventh the *Humeralis*, of which we will treat in their place. The Twelfth and laſt is the *Jugularis* properly ſo called, which is twofold, the internal and external. The internal being the leſſer, doth preſently on both ſides from this very beginning aſcend by the ſides of the *Aſpera Arteria*, or weazon, even to the mouth and skull, yielding nouriſhment to the parts by which it paſſes, as to the next membranes and nerves. But when it comes to the *baſis* of the *Cranium*, it is divided into two branches; the greater whereof going back along the *baſis* of the *Cranium* to the hind-part thereof, ſending a branch to the long muſcle ſituate upon the *œſophagus*, it enters the *Cranium* with the ſmall *Carotides* through the hole of the nerves of the ſixth conjugation, where they become one common veſſel. The leſſer ſending a ſlip to the organ of hearing by the hole called *Cæcum* (or the Blind) alſo enters the *Cranium*, and is ſpent in the thicker *meninx* near to the hole of the third and fourth conjugation of nerves. The external Jugular vein being greater and fairer, moſt commonly ſimple, yet ſometimes double, either preſently at his beginning, or a little after, aſcends ſuperficially on both ſides of the neck, between the broad muſcle, or fleſhy pannicle, being there eaſie to be diſcerned, and other muſcles ſituate at the ſides of the neck, into which, as alſo into the skin, it ſends certain branches for nouriſhment.

Axillaris.

Humeralis.

Jugularis interna, externa.

Into what parts the *Jugularis interna* goes.

Into what parts the *Jugularis externa* goes.

The Figure of the hollow vein, whole and freed from the reſt of the body.



A *The trunk of the hollow vein. The lower* A A, *at this place of the liver, is ſeated the left part of the vein, and diſtributeth branches to the left ſide.*

B *ſheweth how the trunk of the hollow vein in the cheſt (to give way to the heart) is curved or bowed to the right hand.*

Betwixt A *and* B, *that part of the hollow vein which is betwixt the gibbous ſide of the liver and the midriff.*

C *The left midriff-vein called* Phrenica ſiniſtra, *from which ſurcles do run in a man unto the purſe of the heart; for the midriff and it, do grow together.*

D *The orifice of the hollow vein which groweth unto the heart.*

E *The crown-vein called* Coronaria, *which like a crown compaſſeth the* baſis *of the heart, and ſprinkleth his ſurcles on the outſide thereof as far as to the cone or point.*

FF *The trunk of the vein* Azygos *or* non-paril, *deſcending along the right ſide of the rack-bones unto the loins.*

G G *The lower intercoſtal veins, to the branches of the vein* Azygos, *which go unto the diſtances betwixt the ribs, and afford ſurcles unto the muſcle which lie upon the ribs and the rack-bones, and the membranes of the cheſt.*

H *The diviſion of the hollow vein into two ſubclavian trunks near the* Jugulum *under the breaſt-bone.*

II *The ſubclavian branch tending on either ſide unto the arm, called by ſome* Axillaris. K *The upper intercoſtal vein which commonly ſendeth three ſlips unto the diſtances of the upper ribs, unto which the firſt intercoſtal vein ſent no branches.* L L *The deſcending mammary vein: This deſcendeth under the breaſt-bone unto the right muſcles of the* Abdomen, *and affordeth ſurcles to the diſtances of the griſtles of the true ribs, to the* Mediaſtinum, *the muſcles that lie upon the breaſt and the skin of the* Abdomen. M *The conjunction of the mammary with the* Epigaſtrick *vein aſcending about the navel under the right muſcles.* N *The vein of the neck called* Cervicalis, *aſcending towards the skull, which alloweth ſurcles to thoſe muſcles that lie upon the neck.* O *The vein called* Muſcula, *which is propagated with many ſurcles into the muſcles that occupy the lower parts of the neck and the upper parts of the cheſt.* P Thoracica ſuperior, *the upper cheſt-vein which goeth to the muſcles lying upon the cheſt, to the skin of that place, and to the dugs.* Q *The double* Scapularis, *diſtributed into the hollow part of the ſhoulder-blade and the neighbour muſcles; ſo alſo betwixt* P *and* R *ſometimes ſmall veins do reach into the glandules that are in the arm-holes.* R Thoracica inferior *running downward along the ſides of the cheſt; and eſpecially diſtributed into the muſcle of the arm called* Latiſſimus. S *The inner Jugular vein which entreth into the skull after it hath beſtowed ſome ſurcles upon the rough artery.* T *The external Jugular vein.* V *The diviſion of this vein under the root of the ear.* X *A branch of the external Jugular which goeth into the inſide of the mouth, and is diverſly divided into the parts therein contained.* Y *the exterior branch diſtributed near the* Fauces *into the muſcles of the chops, and the hole skin of the head.* Z *a portion of the branch,* y *reaching unto the face.* a æ *The vein of the fore-head.* a *A portion of it creeping through the temples,* æ * *A propagation that goeth unto the skin of the Nowl or* Occiput. a a *The vein called* Cephalica *or the external vein of the arm which others call* Humeraria. b Muſcula ſuperior, *a propagation of the* Cephalica *vein which goeth unto the backward muſcles of the neck. Betwixt* b *and* d *on the backſide iſſueth a branch from the* Cephalica *which paſſeth unto the outſide of the blade, and a portion thereof runneth betwixt the fleſh and the skin.* d d *A vein from the* Cephalica *which attaineth unto the top of the ſhoulder, and is conſumed into the muſcle that elevateth or lifteth up the arm, and into his skin.* e e *A ſmall vein from the* Cephalica *diſperſed through the skin and the muſcles of the arm.* f *The diviſion of the* Cephalica *into three parts.* g *The firſt branch runneth deep unto the muſcles which ariſe out of the external protuberation of the arm.* h *The ſecond branch which goeth to make the* median *vein.* i i *The third branch running obliquely above the wand and the outſide of the arm.* k *From his branch certain circles are divided into the skin, the chief whereof is marked with* k. l *The third branch at the wriſt which is joyn-*

ed at l, *with the branch of the* Basilica *marked with* x. m *The* Basilica *which on the right hand is called* Hepatica, *on the left hand* Lienaris. n o *A branch of the* Basilica *going to the heads of the muscles of the cubit at* n, *and to the muscles themselves at* o. P *A notable branch of the* Basilica *running obliquely, and bestowing surcles upon the muscles that issue from the external protuberation. This branch descendeth together with the fourth nerve.* q *Division of the* Basilica *into two branches, and that which is noted with* q, *is ever accompanied with an artery.* ſ *A branch of this vein bestowed upon the arm.* t *A branch of the* Basilica *which together with the branch of the* Cephalica *marked with* h, *makes the* mediana *or middle vein marked with* a. u *A branch of the* Basilica *going to the inner head of the arm.* xx *A branch issuing out of the former that creepeth along unto the wrist, and toward the little finger conjoyning it self with a branch of the* Cephalica. y *A vein running out unto the skin at the outside of the cbuit. Upper* z *a propagation issuing out of a branch of the* Basilica *marked with* t; *lower* z, *A branch of the* Basilica x, *going to the inside of the arm.* α *The* median *or common vein.* β *The partition of the* median *vein above the wrist. This division should have been made above* γ. γ *The external branch of the partition which goeth to the outside of the head.* δ *From which issueth a small branch to the inside.* ε *The internal branch under* ε, *which toward the middle and the ring finger is especially disposed.* ϛ, *The vein of the thumb dispersed into the mountainet or hillock, which is conjoyn'd with the branch noted with* δ. ζ *The trunk of the hollow-vein from which issue branches unto the parts seated under the liver.* η *The fatty vein called* Adipoſa ſiniſtra, *which goeth unto the fat of the kidneys.* θ ι *The two Emulgents which lead whey-blood unto the kidneys.* λμ *The two ſpermatical veins leading the matter of the seed unto the testicles.* Ν *The beginning of the bodden vessel called* Vas varicoſum. ξ *The veins of the loins called* Lumbares, *which are sent in the knots or knees to the rack-bones, to the marrow of the back, to the muscles that lie upon the loins, and to the* Peritonæum. ο *The bifurcation of the hollow vein into the Iliack branches, which bifurcation is not unlike* ^. ϖ Muſcula ſuperior, *a transverse branch going to the muscles of the* Abdomen, *and to the* Peritonæum. ρ σ *The division of the left Iliack vein, into an inner branch at* ρ, *and an utter at* σ. τ Muſcula media, *the utter propagation of the branch* ρ. *Distributed through the muscles of the* coxa *and the skin of the buitock.* υ *An inner propagation of the same branch* ρ, *which goeth unto the holes of the holy-bone.* ΦΦ *The vein called* Sacra, *which goeth unto the upper holes of the holy-bone.* χψ *The vein* Hypogaſtrica *distributed to the bladder, to the muscles of the fundament, and the neck of the womb.* ω *A vein arising from the utter branch marked with* σ, *which is joyned with some branches of the internal vein, near the holes or perforations of the share-bone.* 31 *A vein which when it is passed the share-bone, distributeth one branch into the cup of the* coxendix, *and to the muscles of that place.* ϰ *Another small branch which runneth under the skin at the inside of the thigh.* χ *The congress or meeting of the fore-said vein, with a branch marked with* char. 2. *and distributed into the leg.* 1 *The* Epigaſtrick *vein, a propagation of the utter branch* σ *perforating the* Peritonæum, *whereto, as also the muscles of the* Abdomen, *and the skin it offereth branches, the chief branch of this vein is joyned with the descending mammary above the navel at* M. Δ Pudenda *an inner propagation of the branch.* σ *Running overthwart unto the privities.* ☉ ρ Saphæna *or the ancle-vein or the inner branch of the crural trunk, which creepeth through the inside of the leg under the skin unto the tops of the toes.* A *The first interior propagation of the* Saphæna *offered to the groin.* Ξ *The utter propagation thereof divided to the foreside or outside of the thigh.* Π *The second propagation of the* Saphæna *going to the first muscle of the leg.* Σ *The third propagation of the* Saphæna *going to the skin of the whirl-bone, and unto the ham.* Φ *The fourth propagation of the* Saphæna *dispersing his muscles forward and backward.* Ψ *Branches from this unto the foreside of the inward ankle, to the upper part of the foot, and to all the toes.* Ω Iſchias minor, *called also* Muſcula interior *the utter branch of the crural trunk divided into the muscles of the* coxendix, *and to the skin of that place.* 1 2 *And this also may be called* Muſcula. 1 *The exterior and lesser which passeth into some muscles of the leg.* 2 *The interior, greater, and deeper unto the muscles of the thigh.* 3 4 *The vein called* Poplitea, *made of two crural veins divided under the knee.* 5 *From this, a surcle is reached upward unto the skin of the thigh,* 6 *but the greater part runs by the bent of the knee under the skin as far as the heel.* 7 *Also to the skin of the outward ankle.* 8 *The vein called* Suralis, *or calf-vein, because it runneth unto the muscles that make the calf of the leg.* 9 *The division of the Sural-vein into an exterior trunk* 9, *and an interior* 14. 10 11 *The division of the exterior trunk under the knee into an external branch, which along the brace attaineth unto the muscles of the foot,* 11 *and an internal.* 12 13 14 *Which descending along the outside of the leg to the upper of the foot is cloven into divers branches, and in the back of the foot mixeth it self with* Poplitea, *or the ham-vein* 20. 15 *The interior branch of the Sural-vein which runneth into the back-side of the leg.* 16 *A branch hereof descending to the inside of the heel, and the great toe, and is divided into divers surcles.* 17 Iſchias major *issuing out of the internal trunk at* 14, *and running through the muscles of the calf.* 18 *A propagation hereof is derived unto the upper part of the foot, and affording two surcles to every toe.* 19 *The remainder of the inner inner trunk, behind the inner ankle approacheth to the bottom of the foot, and is consumed into all the toes.* 20 *The commixtion of the vein* Poplitea *with the small or calf-branch at* 13.

Where the external Jugular-vein may be fitly opened in the inflammations of the parts of the mouth.

But when it arrives to the basis of the lower part of the head, it is divided into more branches, one whereof is carried to the muscles of the bone *Hyois*, the *Larinx*, the tongue and the lower part of the tongue (in which place it is commonly opened in the Squinances, and other inflammations of the mouth) and to the coat of the nose. Another is carried to the *Dura mater*, passing on both sides through a hole, situate under the bone *mastoides*; and besides, ascending to the bone of the back-part of the skull, it comes obliquely to the upper part of the future *Lambdoides*, where these branches meeting together, pass into the reduplication of the *Dura mater*, dividing the fore-part of the brain, that so, joyned and united, they may make the *Torcular*; the third ascendent is distributed upon the back-part and basis of the lower jaw, to the lips, the sides of the nose, and the muscles thereof; and in like manner to the greater corner of the eyes, to the fore-head and other partr of the face, and at length by meeting together of many branches, it makes in the fore-head of the vein which is called *vena recta*, or *vena frontis*, that is, the fore-head vein. The

Vena recta.

fourth

fourth aſcending by the glandules behind the ears, after it hath ſent forth many branches to them, is divided into two others, one whereof paſſing before, and the other behind the ear, are at length ſpent in the skin of the head. The fifth and laſt wandring over all the lower part of the head going to the back-part thereof, makes the *Vena pupis*, which, extended the length of the head by the ſagittal ſuture, at length goeth ſo far, that it meets with the *Vena frontis*, which meeting is the cauſe, that a vein opened in the fore-head, is good in griefs of the hinder-part of the head, and ſo on the contrary. But we muſt obſerve, that in the *Cranium* of ſome, the *Vena pupis* by one or more manifeſt paſſages, ſends ſome portion thereof to the inner part of the head, ſo that the *Vena pupis* being opened, may make revulſion of the matter which cauſeth the internal pains of the head.

Vena pupis.

CHAP. XIV.

The diſtribution of the Nerves, or Sinews of the ſixth Conjugation.

BEcauſe the diſtribution of the Arteries cannot be well ſhewed, unleſs we violate thoſe nerves which are carried over the cheſt, therefore before we ſhew the diſtribution of the arteries, we will, as briefly as we can, proſecute the diſtribution of theſe nerves.

Three pair of nerves of the ſixth conjugation.

Now the ſixth conjugation brings forth three pair of nerves; for paſſing out of the skull, as it comes down to the cheſt, it by the way ſends forth ſome branches to certain muſcles of the neck, and to the three aſcendent muſcles of the *Larinx* on each ſide of the *Sternon*, and upon the clavicles. Then the remainder deſcending into the cheſt, is divided on each ſide into theſe three pair. The firſt pair makes the *Ramus coſtalis*. The ſecond, the *Ramus recurrent*. The third pair, the *Ramus ſtomachicus*. The *Ramus coſtalis*, or coſtal branch, is ſo called, becauſe deſcending by the roots of the ribs, even to the holy bone, and joyning themſelves to theſe which proceed from each of the *Vertebra's* of the ſpine, they are carried to all the natural parts.

Ramus Coſtalis.

The *Recurrens*, or recurrent, is alſo ſo called, becauſe as it were ſtarting up from the cheſt, it runs upward again: But theſe two recurrent nerves do not run back from the ſame place; but the right from below the artery, called by ſome the Axillary, by others Subclavian, and the left from beneath the great artery, deſcending to the natural part. But each of them on each ſide aſcending along by the weazon, even to the *Larinx*, and then they inſinuate themſelves by the wings of *Cartilago ſcutiformis*, and *Thyroides* into the proper muſcles, which open and ſhut the *Larinx*.

Recurrens.

An anatomical *Axiome.*

By how much the nerves are nearer the original, to wit, the brain, or ſpinal-marrow, they are by ſo much the ſofter. On the contrary, by how much they are further abſent from their original, they are ſo much the harder and ſtronger, which is the reaſon that nature would have theſe recurrent nerves to run back again upwards, that ſo they might be the ſtronger to perform the motions of the muſcles of the *Larinx*. But the *Stomachicus* or ſtomach-branch is ſo called, becauſe it deſcends to the ſtomach or ventricle. For this branch deſcending on both ſides by the ſides of the gullet, ſends many branches from it into the inner ſubſtance of the lungs, into the coat thereof, into the *Pericardium* and heart, and then coming into the upper orifice of the ſtomach, it is ſpent in many branches, which folded after divers manners and ways, chiefly makes that mouth or ſtomach, which is the ſeat of the animal appetite (as they term it) and hunger, and the judger of things convenient or hurtful for the ſtomach. But from thence they are diverſly diſſeminated over all the body of the ventricle.

Why Nature would have the vocal nerves recurrent.

Ramus Stomachicus.

Moreover the ſame branch ſends forth ſome ſmall braaches to the liver and bladder of the gall, giving each part by the way, ſo much ſenſe as ſhould be ſufficiently neceſſary for it. Here you muſt note, the ſtomach branch deſcends on each ſide one, knit to the gullet, and by the way they divide themſelves into two branches, each of which goes to the oppoſite ſide, that it may there joyn it ſelf to the nerve of that ſide. To which purpoſe, the right is carried above the gullet, the left below it; ſo that theſe two ſtomatick become four, and again theſe four preſently become two.

CHAP. XV.

The diviſion of the Arteries.

THe artery ariſing forth of the left ventricle of the heart, is preſently (the two coronal arteries being firſt ſpread over the ſubſtance of the heart) divided into two unequal branches. The greater whereof deſcends to the lower parts, being diſtributed, as we formerly mentioned in the third Book, Chap. 22. The leſſer aſcending to the upper parts, is again divided into two other unequal branches, the leſſer of which aſcending towards the left ſide, ſends forth no artery from it, until it arrive at the rib of the cheſt, where it produces the Subclavian artery, which is diſtributed after the manner following.

The left branch of the aſcendent artery is leſs than the right.

The diſtribution of the left ſubclavian artery into the,

1. *Intercoſtalis.*

2. *Mammaria.*

3. *Cervicalis.*

Firſt, it produces the intercoſtal, and by it imparts life to the three intercoſtal muſcles of the four upper ribs, and to the neighbouring places.

Secondly, It brings forth the mammillary branch, which is diſtributed as the mammillary vein is.

Thirdly, the *Cervicalis*, which aſcends along the neck by the tranſverſe productions to the *Dura mater*, being diſtributed as the *Vena Cervicalis* is.

The Figure of the Arteries.



A *The orifice of the great Artery, or the beginning thereof, where it iſſueth out of the heart.*

B Coronaria, *ſo called, becauſe like a Crown it compaſſeth the baſis of the heart.*

C *The diviſion of the great artery into two trunks,* V *i.*

D *The left ſubclavian, climbing obliquely upward unto the ribs.*

E *The upper intercoſtal artery, or a branch which beſtoweth four propagations unto the diſtances of the lower rib.*

F *The neck-artery which through the tranſverſe proceſſes of the rack-bones of the neck attaineth to the ſcull, beſtowing ſurcles unto the marrow and his neighbour muſcles.*

G *The left mammary artery running under the breaſt-bone, and to the navil. It diſtributeth the ſurcles to the* Mediaſtinum, *the muſcles of the breaſt, and of the* Abdomen.

H Muſcula, *or a branch attaining to the backward muſcles of the neck.*

I *The* Scapular-*arteries which go unto the hollowneſs of the blade, and of the muſcles that lie thereon.*

K Humeraria *which climbeth over the top of the ſhoulder.*

L Thoracica ſuperior, *ſprinkled unto the forward muſcles of the cheſt.*

M Thoracica inferior; *which paſſing along the ſides of the cheſt, attaineth to the broad muſcles of the arm.*

N *The axillary artery running out into the arm, and affording branches unto the muſcles thereof.*

O *A branch reaching to the outſide of the cubit lying deep.*

PP *branches to the joynt of the cubit with the arm.* Q *The upper branch of the artery running along the* Radius, *and offering ſurcles to the thumb, the fore-finger, and the middle-finger.* R *A ſurcle creeping unto the outſide of the hand, and led betwixt the firſt bone of the thumb, and that of the after-wriſt, ſupporteth the fore-finger where we uſe to feel the pulſe.* S *the lower branch of the artery running along the* Ulna, *and communicating ſurcles to the little finger, the ring-finger, and the middle finger.* * *A little branch unto the muſcles about the little finger* T *The diſtribution of the upper and lower branches into the hand and the fingers.* V *The trunk of the great artery aſcending to the* Jugulum, *and the diviſion thereof in that place into* X Y Z. X *the left* Carotis, *or ſleepy artery.* Y Subclavian dextra, *divided into branches, as the right is divided.* Z Carotis dextra, *called alſo* Apoplectica *and* Lethargica. a *The diviſion of the left* Carotis *in the chops.* b *The exteriour branch of that diviſion going into the face, the temples, and behind the ears.* c *The inner branch going to the throttle, the chops, and the tongue.* d *The diviſion hereof at the* baſis *of the ſkull, into two branches which enter the* ſinus *of the* Dura mater. e *A propagation of the branch* b, *unto the muſcles of the face.* f *The diſtribution of the branch* b, *under the root of the ear.* g *The forebranch hereof creeping up the temples.* h *The back-branch running on the back-ſide of the ear under the ſkin.* i *The trunk of the great Artery, deſcending unto the ſpondils of the back.* kkk *the lower* intercoſtal *arteries which go unto the diſtances of the eight lower ribs, from which are offered ſurcles to the marrow, and to the muſcles that grow to the back and to the cheſt.* l *the artery of the midriff called* Phrenica *or* Diaphragmatica. ξ Meſenterica ſuperior, [*but you muſt note, that above* ξ *the trunk of the* Cœliacal *artery is taken away, leſt the multitude of letters in ſo ſmall a Table ſhould breed obſcurity.*] θ ν *The right and left Emulgents running from the* Aorta *or great artery unto the kidneys.* ιι νν *The ſpermatical arteries on either ſide going to the teſticles.* λ *the lower meſenterical artery on the left, below* μ *running eſpecially into the colick-gut on that ſide.* μμ *The arteries calld* Lumbares, *which run overthwart and like knees, affording ſurcles to the muſcles that grow to the loins, and to the* Peritonæum. μ *The lower* Muſcula ſuperior *running into the ſides of the* Abdomen *and the muſcles.* νν *The bifurcation of the great artery, into two* Iliack *trunks; and at the ſides, but ſomewhat inward, are branches which make thoſe that are called* Sacræ. T *The diviſion of the left* Iliack *trunk into an inner branch at* ξ, *and an utter at* Φ. ξ *The inner* Iliack *branch.* o Muſcula inferior, *the utter propagation of the inner branch going unto the muſcles which cover the branch-bone and the* Coxendix. ϖ Hypogaſtrica, *the inner propagation of the*

the

the inner branch going to the bladder, the yard, and the neck of the womb. ϟ *The umbilical artery.* ♃ *The remainder of the branch* ξ, *aſſuming an addition from the utter branch, near* Φ, *and ſo falling through the hole of the ſhare-bone into the leg.* τ Epigaſtrica, *it aſcendeth upward unto the right muſcle of the* Abdomen, *and about the navel is joyned with the mammary artery.* υ Pudenda, *it creepeth overthwart the ſhare-bone.* Φ *The* Crural *trunk without the* Peritonæum. χ Muſcula cruralis exterior, *going into the fore-muſcles of the thigh.* ϟ Muſcula cruralis interior, *going unto the muſcles of the inſide of the thigh.* ω *The conjunction of this artery with the branches.* Γ Poplitea, *going to the muſcles on the back-ſide of the thigh.* ΔΔ *Which communicateth ſmall branches to the joynt of the knee, and the muſcles that make the calf of the leg.* ⊙ *The diviſion of the* Crural *artery under the ham into three branches.* Λ Tibiæa exterior, *it accompanieth the brace-bone, and is conſumed into the muſcles.* Ξ *The chief part of the* crural *artery.* Σ *The upper and backer* Tibiæa. ΠΦ *The lower and backer* Tibiæa *running unto the upper ſide of the foot at* Φ. Ψ *A propagation of the* crural *artery going to the inner and upper ſide of the foot, and ſprinkling a branch unto the ankle.* Ω *A propagation unto the lower part of the foot which affordeth ſtir-cles to each toe.*

Fourthly, paſſing out of the cheſt, from the back-part of the cheſt, it ſends forth the *muſculoſa*, whereby it gives life to the hind-muſcles of the neck, even to the back-part of the head. 4. *Muſculoſa.*

Fifthly, having wholly left the cheſt, it ſends forth the two *Humeraria*, or ſhoulder-arteries, the one whereof goes to the muſcles of the hollow part of the ſhoulder-blade, the other to the joynt of the arm and muſcles ſituate there, and the gibbous part of the ſhoulder-blade. 5. *Humeraria duplex.*

Sixthly and laſtly, it produces the *Thoracica*, which is alſo twofold; for the one goes to the fore-muſcles of the cheſt, the other to the *Latiſſimus*, as we ſaid of the vein, the remnant of it makes the *Axillaris* of that ſide. 6. *Thoracica duplex.*

The other greater branch likewiſe aſcending, by the right ſide, even to the firſt rib of the cheſt, makes alſo the ſubclavian of that ſide, which, beſides thoſe diviſions it makes on this ſide, like thoſe of the left ſide, hath alſo another which makes the right and left *Carotides*, or ſleepy arteries, which aſcending undivided with a nerve of the ſixth conjugation and the internal jugular vein, by the ſides of the *Aſpera Arteria*, or wind-pipe, when they come to the *Pharinx*, they are divided on each ſide into two branches, the one internal, the other external. The internal and greater is ſent to the *Pharinx*, *Larinx*, and tongue; then entring into the head by the long hole and back-part of the upper jaw, it ſends many branches to the noſe, eyes, the inſide of the temporal muſcles, and to the *Craſſa menynx*, or *Dura mater*: The remainder of this branch going by the ſide-holes of the ſame, that it might there make the *Plexus admirabilis*, as we ſee. And then it is ſpent upon the *baſis* of the brain abundantly diffuſed over the *tenuis meninx*, or *Pia mater*, and then the membrane or *Plexus Choroides*. The external or leſſer branch of the ſleepy arteries goes to the cheeks, the temples, and behind the ears; laſtly, it ſends a branch into the long muſcle of the neck with which the internal Jugular-vein inſinuates it ſelf into the *Dura mater*, entring by the hole of the nerves of the ſixth conjugation.

The diſtribution of the right ſubclavian artery.

The *Carotides*, or ſleepy arteries.

Their diviſion.

The diſtribution of the internal branch of the ſleepy arteries.

To what parts the external branch of the ſleepy artery arrives.

But we muſt note, that there be more veins in a mans body, than arteries; and beſides, that the veins are far thicker. For there is no need for preſerving the native heat in the parts themſelves, either of ſo many, or ſo large inſtruments of that kind. Therefore you may often find veins without arteries, but never arteries without veins.

But we underſtand, that an artery is companion to a vein, not only when it touches it, or adheres to it by common membranes, as uſually it happens: but alſo when it is appointed together with the vein for the uſe of the ſame part.

CHAP. XVI.

Of the Thymus.

THe *Thymus* is a glandule, of a ſoft, rare, and ſpongious ſubſtance, of large bigneſs, ſituate in the furtheſt and higheſt part of the cheſt, amongſt the diviſions of the ſubclavian or Jugular veins and arteries, as yet contained in the cheſt, for this uſe; that it might ſerve theſe veſſels for a defence againſt the bony hardneſs of the cheſt; and beſides, that, as it were by this prop or ſtay, the diſtributions of theſe veſſels might become the ſtronger; for ſo we ſee that nature hath provided for others, eſpecially ſuch as are the more noble and worthy. This glandule appears very large in beaſts and young men, but in ſuch as have attained to full growth it is much leſs, and ſcarce to be ſeen.

What the *Thymus* is.

The uſe.

The magnitude.

CHAP. XVII.

Of the Aſpera Arteria, *the rough Artery or Weazon.*

THe *Aſpera Arteria*, or Weazon, ſeeing it is the inſtrument of voice and reſpiration, is of a griſtly, ligamentous, and wholly various ſubſtance. For if had been one rough and contined body with the *Larinx* or throttle, it could not be neither dilated nor compreſſed; opened, nor ſhut; neither could it order the voice according to our deſire.

The ſubſtance.

The

The Figure of the Aſpera Arteria, *or Weazon.*

FIG. 1.



A *The orifice of the great artery, cut from the heart.*
aa *The coronal arteries of the heart.*
BCD *The diviſion of the great artery into two trunks; the deſcending* C, *the aſcending* D.
E *The left axillary, or ſubclavian artery.*
F *The right axillary or ſubclavian artery.*
G *The right* Carotis *or ſleepy artery.*
H *The left* Carotis.
I *The trunk of the rough artery or weazon.*
KL *The diviſion of the rough artery into two branches, of which the right goes into the right, and left in the left ſide of the lungs; which branches are again ſubdivided into many other.*
M *The head of the rough artery called the* Larinx *or* Throttle.
NN *Certain glandules or kernels at the root of it.*
OO *The right and left nerves of the ſixth and ſeventh conjugation.*
P *A revolution of ſmall branches of the right nerve to the right* Axillary Artery.
QQ *The right recurrent nerve.*
R *A revolution of ſmall branches of the left nerve unto the deſcending of the great artery.*
SS *The left recurrent nerve.*

Compoſure. It is compoſed of veins from the internal Jugular, of arteries ariſing from the *Carotides*, and of nerves, proceeding from the recurrent branch of a double membrane, of which the external comes from the *Peritonæum*; the internal, which is the ſtronger and woven with the right fibers, from the inner coat of the mouth, the which is common with the inner coat of the *œſophagus* or gullet. And alſo it conſiſts of round griſles, yet not drawn into a perfect circle, compoſed in manner of a channel, and mutually joyned together in order, by the ligaments that proceed from their ſides and ends.

Why the back part of the weazon is ligamentous. Theſe ſame ligaments perfect the remnant of the circle of this *Aſpera Arteria*, on that part next the gullet, which is thought to be done to this end; that that ſoftneſs of a ligament, might then give place, when we ſwallow harder and greater gobbets of meat. Of the two ſorts of ligaments which are annexed to the griſtles of the weazon, ſome tie and faſten together the rings or circles which give means both to it and theſe circles to be drawn in length; otherſome bring theſe griſtles into a perfect circle, which alſo yield them means of dilatation. Theſe ligaments cover the inner ſuperficies, but the griſtles are placed without, to reſiſt the incurſion of external injuries.

Why the forepart is griſtly. But we muſt note, that by this communion of the inner coats of the weazon and gullet, we reap this benefit in the commodiouſneſs of the action, that one of theſe parts being depreſſed, the other is lifted up, like a rope running in a wheel or pully. For thus whileſt the gullet is depreſt to ſwallow any thing, the weazon is lifted up; and on the contrary, when the ſtomach riſes up in vomiting, the weazon is depreſt.

The number and ſite. The diviſion of the weazon through the lobes of the lungs. It is only one, and that ſeated between the *Larinx*, (from which it takes its beginning,) and the lungs in which it ends; firſt dividing it ſelf into two large branches, the right and the left; and beſides, each of theſe entring into the ſubſtance of the lungs, is again divided into two others; to each of the lobes one; and, to conclude, theſe be ſubdivided into infinite others, through the ſubſtance of the lobes.

All theſe branches are griſtly even to the ends. They are ſituate between the ends of the *Arteria venoſa*, and the *Vena arterioſa*, that the entrance of air into the heart by the *Arteria venoſa*, might be ſpeedier; as alſo the paſſage out of the vapour, by the *Vena arterioſa*, Thus it hath connexion with theſe in the ends, or utmoſt parts thereof, but by the other parts compaſſing it, with the members from whence it takes them.

The temper and action. The temperament thereof is cold and dry. The action is to carry the air to, and vapours from the lungs; that by dilating, but this by preſſing the griſtles together.

CHAP.

CHAP. XVIII.

Of the Gullet.

THe *Oeſophagus*, or Gullet, which is the paſſage of the meat and drink, is of a middle ſubſtance between fleſh and ſinews, becauſe it conſiſts of one nervous membrane, and another fleſhy. The nervous is placed the innermoſt, and is continued to the inner coat of the mouth even to the lips, (whereby it comes to paſs, that the lips tremble in diſeaſes which are ready to be judged by a critical vomiting) and to the inner part of the *Aſpera Arteria*; it conſiſts of right Fibers for the attraction of the meat, which we ſee is ſometimes ſo quick and forcible in hungry people, that they have ſcarce time to chaw it, before they find it, to be pluck'd down, as it were, with hand, The fleſhy coat placed without is woven with tranſverſe fibers, to haſten the going of the meat into the ſtomach, and for expulſion in vomitting and breaking of wind. Theſe two coats are continued with the two coats of the ſtomach, and have the like ſite. Beſides, the gullet hath theſe parts compoſing it, as a vein from the gate and hollow aſcendent vein; a nerve from the ſixth Conjugation, an artery from that which creeps alongſt the bottom of the ſtomach with the *Vena Gaſtrica*, or elſe from the arteries aſcending the hollow part thereof; but alſo, beſides all theſe veſſels, it may have a third coat from the membrane inveſting the ribs, or *Pleura*. The magnitude of the gullet is large enough, yet ſome be bigger, ſome leſs, according to the varieties of bodies. The figure of it is round, that ſo it might be more large to ſwallow meat, and leſs ſubject to offence. It is placed between the back-bone and weazon from the roots of the tongue even to the ſtomach. But as it deſcends alongſt the back-bone, when it comes to the fourth *Vertebra* of the cheſt, it turns to the right ſide, to give way to the great Artery *Aorta*, and the deſcendent artery; then it turns to the left ſide to the ſtomach, or mouth of the ventricle. Nature hath faſtened it to the *Diaphragma* with ſtrong membranous ties, leſt that, if it had lain upon the artery, it ſhould have hindered the paſſage of the vital ſpirit to the lower parts. It is only one, and that tied to the fore-mentioned parts, both by its veſſels and membranes. It is of temper rather cold than hot, as all thoſe parts, which are more nervous than fleſhy, are. The action thereof is to draw and carry down the meat, and to caſt forth ſuch things by vomit as trouble the ſtomach. Here you muſt note, that whileſt we ſwallow down, the gullet is drawn downwards, and the weazon upwards, which is the cauſe that we cannot ſup and blow, ſwallow and breathe, together at the ſame inſtant; which we muſt think to happen by Gods ſingular providence, to whoſe name be glory for everlaſting. *Amen.*

The ſubſtance.

Attractive force thereof.

The compoſure.

The magnitude.

The Figure, Site.

Temper and action.

Why we cannot ſup and blow at one time.

The End of the Fourth Book.

BOOK

BOOK V.

Of the Animal parts contained in the Head.

CHAP. I.

A general deſcription of the Head.

HAving hitherto declared two general parts of mans body, that is, the natural and vital, it is now fit to betake our ſelves to the laſt, that is, the animal, beginning with the head.

Wherefore we will firſt define the head, then divide it into its parts; thirdly, deſcribe each of theſe parts; fourthly, demonſtrate them after the order they offer themſelves to our ſight in diſſection.

What the head is. Why ſeated in the higheſt place.

The head therefore is the ſeat of the ſenſes, the palace and habitation of reaſon and wiſdom, from whence, as from a fountain, infinite actions and commodities ariſe. It is ſeated above the reſt of the body, that the animal ſpirit from thence, as from a Tower, may govern and moderate the whole body, and perform all actions according to the preſcript of nature. By the head we underſtand all that which is contained from the crown of the head to the firſt *Vertebra* of the neck.

The figure.

The beſt figure of the head is round, lightly flatted on each ſide, *extuberating* ſomething to the fore and hind-part thereof. For from hence is taken an argument of the goodneſs of the ſenſes; on the contrary, thoſe which are exactly round, or acuminate, and ſharp towards the top, are not thought good. The head is divided into the face, forehead, temples, the forepart, the crown, and hind-part.

The diviſion thereof.

By the face we underſtand, whatſoever is contained between the eye-brows and the lower part of the chin. By the forehead, all the ſpace from the eye-brows even to the coronal ſuture. By the temples, whatſoever is hollowed from the leſſer corner of the eye, even to the ears. By the forepart of the head, whatſoever runs in length from the top of the forehead, or the coronal ſuture, even to the ſuture *Lambdoides*, and on each ſide to the *Oſſa petroſa*, the ſtony bones, or ſcaly ſutures. By the crown we ſignifie a certain point exquiſitely in the midſt of the ſagittal ſuture, which is ſufficiently known. By the *Occiput* or hind-part of the head, that which is terminated by the ſuture *Lambdoides* and the firſt *Vertebra* of the neck.

The containing parts of Head.

Of all theſe parts there be ſome ſimple, ſome compound; beſides, ſome are containing, ſome contained. Of the containing, ſome are common to all the parts of the head, as the skin, the fleſhy pannicle, and *pericranium*; others are proper to certain parts, as the fleſhy pannicle to the neck, face, forehead, and skin covering the *cranium*, the common coat of the muſcles to the fat and face; the skull and both the *Meninges* to the brain.

The parts contained.

The parts contained, are the ſubſtance of the brain, the four ventricles, and the bodies contained in them, the nerves, the mammillary proceſſes; the *Plexus Choroides* or *Rete admirabile*; the *Glandula baſilaris*, and others, of which we will ſpeak hereafter.

We muſt now ſpeak of the containing parts beginning with the skin; for the order of teaching requires, that we take our *Exordium* from the more ſimple; but firſt we will ſay ſomething of the hair.

What the hair is. The uſe thereof.

The hair is nothing elſe than an excrement generated and formed of the more groſs and terrene portion of the ſuperfluities of the third concoction, which could not be waſted by inſenſible tranſpiration. The benefit of it is, that conſuming the groſs and fuliginous, or ſooty excrements of the brain, it becomes a cover and ornament for the head.

This hair of the head and eye-brows have their original from the firſt conformation of the infant in the womb, the reſt of the hairs of the body ariſe and grow forth as the body grows and becomes more dry, of which ſort are the hairs which cover the chin, arm-holes, groins, and other parts of our bodies.

CHAP. II.

Of the muſculous skin of the Head (commonly called the hairy ſcalp) and of the Pericranium.

What the hairy ſcalp is.

THe skin which covers the skull, and is covered with the hair, is far more fleſhy, thick, hard, and dry than any other part of the body, eſpecially which wants hair. The skin hath almoſt the like condition of quality as thoſe parts have, which it doth ſimply cover, but is as it were, loſt in them, or grown into one with them, as in the lips and forehead with the fleſhy pannicle, wherefore it is there called muſculous; in other places it adheres to the grittles, as on the ſides of the noſtrils and corners of the eyes, whereupon it is there called griſtly.

Its connexion.

It hath connexion with the *Pericranium*, becauſe joyned to it, it receives nerves from the firſt and ſecond *Vertebra* of the neck, and from the third conjugation of the brain, which are diſſeminated through all its ſubſtance, whereby it comes to paſs, that the wounds, contuſions and impoſthumes, that happen in or upon this skin, are not to be neglected.

The

The * *Pericranium*, (but I ſuppoſe it ſhould be the *Perioſteum*) is a moſt thin membrane, which next and immediately covers all the bones of the body, and this on the head is called by a peculiar name the *Pericranium*, by reaſon of the excellency of the *Cranium* or skull; in other bones it is termed the *Perioſteum:* And as the *Pericranium* takes its original from the *Craſſa meninx*, propagating it ſelf by certain ſtrings or threds ſent forth by the ſutures and holes of the skull, ſo all other membranes of the body have their original either from this *Pericranium*, or *Craſſa meninx*, ſending forth their productions, as well by the holes or paſſages of the head, as by thoſe of the ſpinal marrow or back-bone it ſelf even to the holy bone.

* Our Author (with *Falleptus* and *Laurentius*) confounds the *Pericranium* and *Perioſteum*: but *Veſalius*, *Bauhinus* and *Bartholinus* diſtinguiſh them, making the *Pericranium* thin and ſoft, and the *Perioſteum* moſt thin and nervous, and of moſt exquiſite ſenſe.

Of which this is an argument; for in what part ſoever of the body a membrane is hurt, preſently the hurt or ſenſe thereof comes to the *Craſſa meninx*. For ſo thoſe who have but their little toe hurt, when they ſneeze or cough, perceive an increaſe of their pain, by the paſſage thereof to the brain.

Why the wounds thereof muſt not be neglected.

* The uſe of this *Pericranium* is to cover the skull; and to give notice of things hurtful, by the power of the quick ſenſe which it is endued withal, and the *Perioſteum* doth the like in other bones. Beſides, it ſuſtains and faſtens by the ſutures the *Craſſa meninx* to the skull; leſt it ſhould fall by reaſon of its weight upon the *Pia mater*, and ſo hurt it, and hinder the pulſation of the brain and arteries that are plenteouſly ſpread through both the *Meninges*. Wherefore the *Pericranium* hath moſt ſtrait connexion with the *Craſſa meninx*, becauſe it takes the original from thence.

The *Pericranium* and *Perioſteum* of the ſame nature.

Whence all the membranes proceed.

We muſt think the ſame of the other membranes of the body, which thing is very notable in the ſolution of the continuity of the membranes.

Why when any membranous part is hurt in any part of the body, the head is affected by conſent.

CHAP. III.

Of the Sutures.

* The uſe of the *Pericranium*.

THe Sutures do ſew or faſten together the bones of the skull; theſe be five in number. Three, are true and legitimate; two, falſe and ſpurious. The Coronal, the firſt of the true Sutures, is ſeated in the forepart of the head, deſcending downwards overthwart the forepart of the head to the midſt of the temples; it is ſo called, becauſe *Corollæ*, that is, wreaths, crowns, or garlands are ſet upon that place.

Their uſe and number.

The ſecond is called the *Sagittalis*, or right ſuture, as that, which running through the crown, divides the head into two equal parts, as with a ſtrait line, running the length of it from the coronal to the *Lambdoides* or hind-ſuture.

But this third Suture *Lambdoides* is ſo called, becauſe it repreſents the capital Greek Letter *Lambda* Λ. You muſt underſtand this deſcription of the ſutures, not as always, but as for the greater part, to be thus. For there be ſome skulls that want the foremoſt ſuture, otherſome the hind, and ſometimes ſuch as have none of the true ſutures, but only the falſe and ſpurious. And alſo you ſhall ſometimes find the ſagittal to run to the noſe.

Some skulls want ſutures.

And oft-times there be three or four ſutures in the back-part of the head, ſo that indeed the number of the ſutures is not certain. Which alſo we find obſerved by *Cornelius Celſus*, where he writes, that *Hippocrates* was deceived by the ſutures by chance; for that he conjectured, that the bones of the back-part of the head, were broken; becauſe his Probe, thruſt to the roughneſs of the ſecond ſuture *Lambdoides*, ſtaid as at a cleft made in the bone by a ſtroke. *Celſ. lib. c. 40.*

The other two are called the falſe, ſtony and ſcaly ſutures, by reaſon they are made by a ſcaly conjunction of the bones, but not by a toothed ſaw or comb-like connexion. But if any ask, Why the head conſiſts not of one bone, that ſo it might be the ſtronger? I anſwer, It is, that ſo it might be the ſafer both from internal and external injuries. For the skull, being, as it were, the tunnel of the chimney of this humane fabrick, to which all the ſmoaky vapours of the whole body aſcend, if it had been compoſed of one bone, theſe vapours ſhould have had no paſſage forth.

Why the skull conſiſts of divers bones.

Wherefore the groſſer vapours paſs away by the ſutures, but the more ſubtil by the pores of the skull; ſome have their ſutures very open, but others on the contrary very cloſe.

Therefore nature hath otherwiſe compendiouſly provided for ſuch as want ſutures: For it hath made one or two holes, ſome two fingers breadth from the *Lambdoides*, through which the *Vena pupis* enters into the skull, and they are of that largeneſs, that you may put a points tag into them, that the vapours may have free paſſage forth, otherwiſe there would be danger of death; thus Nature hath been careful to provide for man againſt internal injuries; And in like manner againſt external; for it hath made the head to conſiſt of divers bones, that when one is broken, the other may be ſafe, the violence of the ſtroke being ſtaid in the diviſion of the bones.

In what bodies and by what mean, the *vena pupis* ſometimes enters into the parts within the skull.

Whereby you may know, that if the skull chance to be broken in the oppoſite ſide to that which received the blow, that it happens either by reaſon of the defect of ſutures, or elſe becauſe they are unperfect, and too firmly cloſed; otherwiſe it is impoſſible ſuch fractures ſhould happen by reaſon of the ſeparation of the bones, which breaks the violence of the blow that it can go no further.

In what men one part of the head, being ſtricken, the oppoſite is broken.

And certainly, as it is rare to find a skull without ſutures, ſo it is rare to find ſuch kind of fractures. Therefore Chirurgeons muſt diligently obſerve the ſutures and ſite of them, leſt they be deceived, and take them for fractures, or unawares apply a Trepan to them, whence by breaking the veins, arteries and nervous fibers by which the internal parts communicate with the external, there may enſue increaſe of pain, a violent defluxion of blood upon the *Craſſa meninx*, and the falling thereof upon the brain, (the fibers being broken by which it ſtuck to the *Pericranium*) and ſo conſequently a deadly interception of the pullion of the brain.

Why we muſt not apply a Trepan to the ſutures.

CHAP.

CHAP. IV.

Of the Cranium, *or Skull.*

What the *Cranium* is.

THe *Cranium*, or Skull covering the brain like an Helmet, is compoſed and conſiſts of ſeven bones; of which ſome are more denſe, thick and hard than otherſome. The firſt is the *Os Occipitis*, or nowl-bone ſeated in the back-part of the head, more hard and thick than the reſt, becauſe we want hands and eyes behind, whereby we may keep or ſave our ſelves from falling.

Why the nowl-bone is harder than the reſt.

This bone is circumſcribed, or bounded by the ſuture *Lambdoides*, and the * *Os baſilare*. The eminencies, and, as it were, heads of this bone are received into the firſt *Vertebra*; for upon this the head is turned forwards and backwards, by the force of fourteen muſcles and ſtrong ligaments, which firmly tie theſe heads of the nowl-bone in the cavities of this firſt *Vertebra*.

* My Author means by the *Os baſilare* in this place the wedg-bone: but ſome Anatomiſts make it a *Synonyma* of this *Os occipitis*.

The ſecond bone of the skull is in the fore-part, and is called the *Os coronale*, or *Os frontis*, the fore-head-bone; it hath the ſecond place in ſtrength and thickneſs. It is bounded by the coronal ſuture, and the ends of the wedg-bone: In this fore-head bone there is often found a great cavity under the upper part of the eye-brows, filled with a glutinous, groſs, viſcid and white matter or ſubſtance, which is thought to help to elaborate the air for the ſenſe of ſmelling.

The forehead-bone, next to the nowl-bone is harder than the reſt.

Chirurgeons muſt take ſpecial notice of this cavity; becauſe when the head chances to be broken in that place, it may happen, that the fracture exceeds not the firſt table; wherefore being ignorant of this cavity, and moved with a falſe perſwaſion that they ſee the brain, they may think the bone wholly broken, and ſo preſs the *Meninges*, whereupon they will dilate the womb, and apply a Trepan and other inſtruments to lift up the ſecond table of the bone, without any need at all, and with the manifeſt danger of the life of the Patient.

A cavity to be obſerved in the forehead-bone.

The third and fourth bones of the skull, are the *Oſſa parietalia*, or *Bregmatis*, having the third place of denſity and thickneſs; although this denſity and thickneſs be different in divers places of them. For on the upper part of the head, or crown (where that ſubſtance turns not to a bone in children, until they have all their teeth, ſo that it feels ſoft in touching, and through it you may feel the beating of the brain) theſe bones are very tender, ſo that oft-times they are no thicker than ones nail, that ſo the moiſt and vapourous excrements of the brain, ſhut up where the greater portion of the brain reſides, may have a freer paſſage by the brains *Diaſtole* and *Syſtole*. Theſe two ſquare bones are bounded above with the ſagittal ſure, below with the ſcaly, on the fore-part with the coronal, and on the hind-part with the *Lambdoides*.

Oſſa parietalia & Bregmatis.

Oſſa petroſa, or the ſcaly-bone.

The fifth and ſixth bones of the skull, are the two *Oſſa petroſa*, ſtony or ſcaly bones, which are next to the former in ſtrength. They are bounded with the falſe or baſtard-ſuture, and with part of the *Lambdoides*, and wedg-bone.

Os ſphenoides, or the wedg-bone.

The ſeventh is the *Os ſphenoides*, *baſilare*, or *Cuneiforme*, that is, the wedg-bone. It is called *Baſilare*, becauſe it is (as it were) the *baſis* of the head. To this the reſt of the bones of the head are fitly faſtned in their places. This bone is bounded on each ſide with the bones of the forehead, the ſtony bones, and bones of the nowl and palat. The figure repreſents a Bat, and its proceſſes her wings.

Os Ethmoides, or *Cribroſum*.

There is beſides theſe another bone at the *baſis* of the forehead-bone, into which the mammillary proceſſes end; the Greeks call it ἠθμοειδὲς, the Latines, *Cribroſum* and *Spongioſum*, the ſpongy-bone; becauſe it hath many holes in it not perforated in a direct paſſage, as in a ſive, but winding and anfractuous, that the air ſhould not by the force of attraction, preſently leap or aſcend into the brain, and affect it with its qualities, before it be elaborated by its lingring in the way. There are beſides alſo, ſix other little bones lying hid in the ſtony bones at the hole or auditory-paſſage; on each ſide three, that is to ſay, the *Incus* or Anvil, the *Malleolus* or Hammer, and the *Stapes* or ſtirrop, becauſe in their figure they repreſent theſe three things; the uſe of theſe we will declare hereafter.

The three bones of the Auditory-paſſage.

But alſo in ſome skulls there are found ſome diviſions of bones, as it were collected fragments, to the bigneſs almoſt of ones thumb, furniſhed and diſtinguiſhed by their proper commiſſures, or ſutures, which thing is very fit to be known to a Chirurgion in the uſe of the Trepan.

By what means a Chirurgion may conjecture that there are extraordinary ſutures in certain places of the skull.

Verily he may give a conjecture hereof, whilſt he ſeparates the *Pericranium* from the skull, for the *Pericranium* is with greater difficulty pluck'd away from the ſutures, becauſe the *Craſſa meninx* hath ſtraiter connexion therewith by his nervous fibers ſent forth in ſuch places. The skulls in women are ſofter and thinner than in men, and in children more than in women, and in young men more than in men of a middle age. Alſo the *Æthiopians* and Black-moors, as alſo all the people inhabiting to the South, have their skulls more hard and compoſed with fewer ſutures.

The skulls of ſuch as inhabit the Southern countreys, are more hard and denſe.

Therefore, as it is written by *Hippocrates*, ſuch as have their skulls the ſofter, the ſymptomes in fractures, are more dangerous and to be feared in them. But the skull by how much the ſofter it is, by ſo much it more eaſily and readily yields to the perforating Trepan. Moreover in ſome skulls, there be bunches ſtanding out beſides nature, made either round or cornered, which the Chirurgeon muſt obſerve for two cauſes; the firſt is for the better conſideration of a blow or fracture. For in theſe bunches or knots, the ſolution of the continuity cannot be, if it ſeem to be ſtretched in length, but that the wound muſt penetrate to the inner parts. For in a round body there can be no long wound, but it muſt be deep, by the weapon forced the deeper; becauſe as a round body touches a plain but only in *puncto*, in a prick or point: So whatſoever falls only lightly or ſuperficially upon it, touches a point thereof. But on the contrary, a long wound muſt be upon a plain ſurface, which may be but only ſuperficial.

We muſt obſerve the extuberances beſides nature, which are in ſome skulls.

Another cauſe is, becauſe ſuch bunches change the figure and ſite of the ſutures. And the Chirurgeon muſt note, that the skull hath two tables, in the midſt whereof the *Diploe* is; which is a ſpongy ſubſtance into which many veins and arteries, and a certain fleſhineſs are inſerted, that the skull ſhould not be ſo heavy, and that it might have within it ſelf proviſion for the life thereof; and laſtly, that there might be freer paſſage out for the fuliginous vapours of the brain.

The ſite and ſubſtance of the *Diploe*.

The

The upper table is thicker, denſer, ſtronger and ſmoother than the lower. For this as it is the ſlenderer, ſo it is the more unequal, that it may give place to the internal veins and arteries, (which make a manifeſt impreſſion into the ſecond table on the inſide thereof) from which branches enter into the skull by the holes which contain the eyes. Which thing faſtens the *Craſſa meninx* to the skull, and is therefore very worthy to be obſerved.

For in great Contuſions, when no fracture and fiſſure appears in the skull, by reaſon of the great concuſſion or ſhaking of the brain, theſe veſſels are often broken, whence happens a flux of blood between the skull and membranes, and laſtly death. But it is fit the Chirurgeon take good heed to the tender and ſoft ſubſtance of the *Diploe*, that when he comes to it, having paſſed the firſt table, he may carefully uſe his Trepan, leſt by leaning too hard, it run in too violently, and hurt the membranes lying underneath it, whence convulſion and death would follow. To which danger I have found a remedy, by the happy invention of a Trepan, as I will hereafter more at large declare in handling the wounds of the head.

There may be a deadly rupture of the veſſels of the brain without any fracture of the skull.

Caution to be had in the uſe of the Trepan.

CHAP. V.

Of the Meninges, that is, the two Membranes called Dura mater *and* Pia mater.

THe *Craſſa meninx* is one of the firſt and principal membranes of the body; it goes forth by the ſutures and holes of the nerves that proceed out of the skull; and it paſſes forth by the bone *Ethmoides* perforated for that purpoſe, to carry ſmells to the brain, and purge it of excrementitious humors. This ſame *Craſſa meninx* inveſts the inner coat of the noſe; alſo it paſſes forth of the great hole through which the ſpinal marrow paſſes, veſted with this *Craſſa meninx*, with all the nerves and membranes. For which cauſe if any membrane in the whole body be hurt, by reaſon of that continuation which it hath with the *Meninges*, it ſtraight communicates the hurt to the head by conſent.

Why the bone *Ethmoides* is perforated.

The *Craſſa meninx* is thicker and harder than all other membranes in the body; whereupon it hath got the name of the *Dura mater*; beſides alſo, it begirts, produces and defends the other membranes.

The conſiſtence of the *Craſſa meninx*.

The uſe of it is to involve all the brain, and to keep it when it is dilated, that it be not hurt by the hardneſs of the skull. For the courſe of nature is ſuch, that it always places ſome third thing of a middle nature, betwixt two contraries. Alſo the *Craſſa meninx* yields another commodity, which is, that it carries the veins and arteries, entring the skull for a long ſpace. For they inſinuate themſelves into that part, where the duplicate or folded *Meninges* ſeparate the brain from the *Cerebellum*, and ſo from thence they are led by the ſides of the *Cerebellum*, until they come (as it were) to the top thereof; where being united, they inſinuate themſelves into that other part of the *Craſſa meninx*, where, in like manner being duplicated and doubled, it parts the brain at the top into the right and left. Theſe united veins run in a direct paſſage even to the forehead, after the manner of the ſagittal ſuture: They have called this paſſage of the mutually infolded veins, the *Torcular* or Preſs, becauſe the blood which nouriſhes the brain, is preſſed and drops from thence by the infinite mouths of theſe ſmall veins. Therefore alſo here is another uſe of the *Craſſa meninx*, to diſtinguiſh the brain by its duplication, being it thruſts it ſelf deep into its body, into two parts, the fore and hind, and preſently to ſeparate the ſame into the right and left; that one part being hurt, the other may remain ſafe and ſound, performing its duty to the creature, as we ſee in ſome that have the Palſie. *Columbus* obſerved that this *Meninx* was double, and verily I have found it true by my own ſight.

The uſe.

What the *Torcular* is.

One part of the brain being hurt, the other keeps the creature alive.

The other *Meninx* or membrane of the brain, called *Pia mater*, is moſt ſlender, interchaſed with divers veins and arteries, for its own and the brains nouriſhment and life. This doth not only involve the brain, as the *Craſſa meninx* doth, but alſo more deeply penetrate in the anfractuous paſſages thereof, that it may every where joyn and bind it to it ſelf, not eaſily to be drawn from thence, by many ſmall fibers, whereby it deſcends even to the cavities of the ventricles thereof. Wherefore you muſt ſee it abſolutely in the ſite, as we have mentioned, and not pluck it away unleſs with the ſubſtance of the brain.

The conſiſtence of the *Pia mater*.

Theſe membranes when they are hurt or afflicted, cauſe grievous and moſt bitter torment and pain; wherefore I dare ſay, that theſe membranes are rather the authors of ſenſe, than the brain it ſelf, becauſe in diſeaſes of the brain, as in the Lethargy, the part affected is troubled with little or no ſenſe of pain.

The ſenſe of the *Meninges*.

CHAP. VI.

Of the Brain.

NOw followeth the brain, the beginning of the nerves and voluntary motion, the inſtrument of the firſt and principal faculty of the Soul, that is, the Animal and Rational. Man hath this part in greater plenty than any other Creature, for it almoſt fills the whole skull. But if it ſhould have filled it all, the brain could not be moved, that is, dilated and contracted in the skull. It is of a cold and moiſt Temperature. The laudable temper of the brain is known by the integrity and perfection of the internal and external ſenſes; the indifferency of ſleep and waking, the maturity or ripeneſs of judgment, and conſtancy of opinions, from which, unleſs it meets with better and more probable, it is not eaſie to be moved.

What the brain is.

The quantity.

Temper.

The firſt Figure of the Head, as it appears when the skull is taken away.
The ſecond Figure ſhewing the brain, the skull and Dura mater *being taken off.*

A A B B *The* Dura meninx, *or thick membrane.*
C C C *The third* Sinus *of this membrane.*
D D *The courſe of the veins as they run through the membrane or the ſecond vein of the brain.*
E E *The firſt vein of the brain.*
F F F *Certain ſmall veins which perforate the skull, and reach to the* Pericranium, *or skull-skin.*
G G G *Fibers of the* Dura meninx *paſſing through the coronal ſuture, which fibers make the* Pericranium.
H H *Fibers paſſing through the ſagittal ſuture.*
I I *Others paſſing through the Lambdal ſuture.*
K *A knub which uſeth to grow to the* Sinus *of the skull.*
L *A cavity in the forehead-bone.*
M *The skull.*
N *The* Pericranium *or skull-kin.*

FIG. I.



II.



Figure 2.

A A A *A part of the* Craſſa meninx *dividing the brain.*
B B *The third* Sinus *of the ſame craſs membrane opened.*
C C *The beginning of the veſſels out of the third* Sinus *into the* Pia mater.
D D D *The propagation or branches of theſe veſſels.*
E E E *The* Pia mater, *or thin* meninx, *immediately compaſſing the brain.*
F F F *Certain veſſels running through the convolutions or branches of the brane.*
G G G *Certain branches of veins running through the ſides of the* Dura meninx. H H H *The thick membrane reflected downward.*

You ſhall know the brain is more hot, by the quickneſs of the ſenſes and motions of the body, by ſhortneſs of ſleep, the ſudden conceiving of opinions, and change of them, by the ſlippery and failing memory, and laſtly, by eaſily receiving hurt from hot things, as the Sun and Fire. Such as have a cold brain, are ſlow to learning, and to conceive other things, but they do not eaſily put away their once conceived opinions. They have ſlow motion to action, and are ſleepy. Thoſe who have a dry brain, are alſo ſlow to learn, for you ſhall not eaſily imprint any thing in dry bodies, but they are moſt conſtant retainers of thoſe things they have once learned; alſo the motions of their bodies are quick and nimble. Thoſe who have a moiſt brain do eaſily learn, but have an ill memory, for with like facility as they admit the ſpecies of things and imprint them in their minds, do they ſuffer them to ſlide and ſlip out of it again. So clay doth eaſily admit what character or impreſſion ſoever you will, but the parts of this clay, which eaſily gave way to this impreſſion, going together again, mixes, obliterates and confounds the ſame. Therefore the ſenſes proceeding from a cold brain are dull, the motions ſlow, the ſleep profound.

The action. The action of the brain is to elaborate the animal ſpirit and neceſſary ſenſe ſerving the whole body, and to ſubject it ſelf as an inſtrument to the principal faculties, as to reaſon. The brain is twofold, the fore and hind. The hind by reaſon of its ſmallneſs is called the *Cerebellum*, (the little or after-brain.) But the fore by reaſon of its magnitude, hath retained the abſolute name of the brain. Again, this fore-brain is twofold, the right and the left, parted by that depreſſion which we formerly mentioned, of the *Meninges* into the body of brain. But this diviſion is not to be here ſo abſolutely taken, as though the brain were exactly divided, and ſeparated into ſo many parts; but in the ſenſe we ſay the liver and the lungs are divided a pretty way, whereas at their Baſis they have one continued body. The outward ſurface of the brain is ſoft, but the inward hard, callous and very ſmooth; when on the contrary, the outward appears indented and unequal with many windings, and creſted, as it were, with many worm-like foldings.

Number.

CHAP.

CHAP. VII.

Of the Ventricles and Mammillary Proceſſes of the Brain.

FOr the eaſie demonſtration of the Ventricles of the Brain, it is convenient you cut away a large portion thereof, and in your cutting, obſerve the blood ſweating out of the pores of it. But beſides, it is fit you conſider the ſpongy ſubſtance by which the excrements of the brain are heaped up, to be preſently ſtrained out, and ſent away by the hollow paſſage. In the ſubſtance of the brain you muſt obſerve four ventricles, mutually conjoyned by certain paſſages, by which the ſpirits endued with the *ſpecies* of things ſenſible, may go from one into another The firſt and two greater, one on each ſide are placed in the upper brain. The third is under them in the middle part of the brain. The fourth and laſt at the foreſide of the *Cerebellum*, towards the beginning of the ſpinal marrow. The two foremoſt are extended the length way of the brain in the form of a ſemicircle, whoſe horns look or bend outwards. They are ſpacious and large, becauſe it was meet the ſpirits contained there together with their excrements, ſhbuld be there purified and cleanſed; but in other ventricles, the pure and already elaborate ſpirits are only received. Theſe ventricles are white and ſmooth in their inner ſuperficies; but, that on each ſide they have an extuberancy at the midſt of the ſemi-circle, ſituate at the baſis of the pillar of the middle ventricle towards the noſe under the *Septum lucidum*, or clear partition, ſevering or parting in ſunder theſe two ventricles.

The ſubſtance of the brain is porous, and ſweats forth blood.

The four ventricles thereof.

The magnitude of the upper ventricles of the brain.

The *Septum lucidum*, or clear or thin partion, is nothing elſe than a portion of the brain indifferently ſolid, but very clear, that ſo through this partition the animal ſpirits contained in theſe two Ventricles, may mutually paſs and be communicated, and yet no other groſſer ſubſtance may pierce the thin denſity thereof.

The *Septum lucidum*.

The third Figure repreſents the Cerebellum *with the wormy Proceſſes ſeparated from it.*



AB *The right and left part of the After-brain.*
CD *The* Anterior *and* Poſterior *regions of the middle part of the After-brain.*
E *The* Anterir *wormy proceſs.*
F *The* Poſterior *wormy proceſs.*
GG *In this place the After-brain did grow to the ſpinal marrow.*
H *The cavity in the ſpinal marrow maketh the fourth ventricle.*
IK *The* Anterior *and* Poſterior *proceſſes of the bain, called* Vermi-formes, *or the wormy proceſſes.*

Wherefore it is not to be feared, that the water contained in one of the ventricles may paſs to the other through this partition, as I have oft-times obſerved to the great admiration of the ſpectators in the dead bodies of ſuch as died of the Palſie, in which I have found the ventricle of that ſide which was taken with the Palſie much dilated, according to the quantity of the water contained therein, the other being either wholly empty and without any; or certainly no fuller than in any other, dead through any other occaſion. For ſome affirm, that there is a certain kind of wateriſh moiſture always to be found in the ventricles, which may be made by the condenſation of the animal ſpirits by the force of the deadly cold. But theſe two firſt ventricles of the brain go into one common paſſage, as both the bellows of a fornace, whereby the ſpirit inſtructed with the ſpecies of things, goes into the under or middle ventricle from the former. In theſe ſame firſt ventricles, the *Plexus choroides* is to be conſidered, and in like manner the paſſage by which the groſſer excrements are driven or ſent into the pituitary glandule.

Why the Palſie of one ſide is not preſently communicated to the other.

This *Plexus choroides* is nothing elſe, but a production of the *Pia mater* diverſly folded with the mutual implication of veins and arteries woven in the form of a net. Theſe veſſels are of magnitude and capacity ſufficient, both to yield life and nouriſhment to that particle to which they are faſtened, as alſo for the generation of the animal ſpirits, as which take fit matter from the veins ſtretched forth into the ſame *Plexus*, the hind-artery and vein *Torcular*; and alſo from the air entring into the brain by the mammillary proceſſes. But the mammillary proceſſes are certain common ways for conveyance of the air and ſmells, into the brain, and carrying of excrements from the brain.

The *Plexus choroides*.

For thus in them who have the Catarrh and *Coriza*, or Poſe, neither the air, nor ſmells can penetrate into the brain; when frequent ſneezings enſue, the brain ſtrongly moving it ſelf to the expulſion of that which is troubleſome to it. But of the excrements of the brain, whether bred there, or proceeding from ſome other part, ſome are of a fumid and vaporous nature, which breathe inſenſibly through the ſutures of the ſkull; others are groſs and viſcid, of which a great part is expelled by both theſe productions, or through each of them. For thus in the Poſe you may ſee ſome who have one of their noſtrils ſtopt, the other running, and ſome who have both obſtructed. The moſt proper benefit of the two firſt ventricles of the brain is to entertain the Phantaſie, as in a convenient ſeat and habitation, ſeeing the mind there eſtimates and diſpoſes in order the ſpecies of things brought in from the external ſenſes, that ſo it may receive a true judgment of them from reaſon, which reſides in the middle ventricle.

The *Proceſſus Mammillares*.

The uſe of the upper ventricles of the brain,

The fourth and fifth Figure of the Brain.

Figure 5.

R R R *The lower* ſuperficies *of the callous body reflected.*

S T V *The* triangular *ſurface of the* Fornix *or Arch.*

X X *The lower part of the partition of the Ventricle continuated with the arch.*

Y Y *The upper part of the partition continued with the callous body.*

Figure 6.

A A A *The lower ſurface of the arch.*

B C *Two corners of the arch, by which it is continuated with the ventricles.*

D E *The right and left ventricles.*

F G *Arteries climbing up from the ſleepy arteries through the lower ſide of the ventricles, for the forming of that complication of the veſſels, which is called* Plexus choroides.

H *A veſſel iſſuing out of the fourth* Sinus *under the arch, and paſſing into the third ventricle.*

I K L *The diviſion of this veſſel, a part whereof goeth to the right ventricle at* K, *and another to the left at* L.

M N *The* Plexus choroides *made of the artery* F G, *and the veſſel* H.

O O *Small veins paſſing through the ventricles of the brain, produced from the veſſels* K *and* L.

P *Other veins ariſing from the ſame, diſperſed without the ventricles into the* Pia mater.

Q *A paſſage from the third ventricle unto the Baſon, or* Tunnel.

R S *Canales, or* Sinus, *graven or furrowed in the ſubſtance of the ventricles; in which the phlegm is led along to the orifice of the foreſaid paſſage marked with* Q.

FIG. V.

VI

The ſixth Figure of the Brain.

Figure 10.

A A *Parts of the ſpinal marrow cut from the brain.*

B C *The places where this marrow did grow unto the brain.*

D E *The teſticles.*

F G *The buttocks.*

H *The Pine glandule.*

From I *to* K *A part of the third ventricle going to the fourth, under the teſticles.*

K L M N *A part of the fourth ventricle which is engraven in the marrow.*

O *The top of the fourth ventricle.*

P *The place where the ſpinal marrow goeth out of the ſkull.*





XII.

Figure 11.

A B *Parts of the optick nerves.*

C D *The ſleepy arteries.* E *The Baſon or Tunnel hanging down.* F *A hole or perforation of the* Dura meninx, *through which the Tunnel reacheth unto the glandule.* G G *Parts of the ſecond conjugation of ſinews.*

Figure 12.

A *The glandule.* B *The Baſon or Tunnel, called* Pelvis *or* Infundibulum. C D E F. *The four holes through which the phlegmatick excrement iſſueth.*

The

The third ventricle is ſeated between the hindermoſt extremities of the former ventricles, and the laſt ventricle of the *Cerebellum*. In this, ſix parts preſent themſelves to our conſideration, that is, the *Pſalloides* or Arch, the *Conarium* or pine glandule, the buttocks, worm-like productions, the baſon and paſſage which is from this middle into the laſt and hindmoſt ventricle. The *Pſalloides* or Arch, is nothing elſe, but the cover of the middle ventricle, reſembling a roof, born up with three ſtays or pillars, the one whereof is extended to the noſe under the *Septum lucidum*; the two other on each ſide one, look toward the back-part of the brain. This is the reaſon of this figure which is outwardly convex, and inwardly concave, to wit, that there might be free ſpace for that motion which the animal ſpirit inwardly produces, and beſides, that it might more eaſily ſuſtain the burthen of the brain lying upon it. For an arched figure is the moſt convenient of all other to ſuſtain a weight.

The ſeat of the third ventricle of the brain.

The parts to be conſidered in it.

What the *Fornix*, or arch is, and the uſe thereof.

The *Conarium*, or Pine-glandule is a ſmall glandule of the ſame ſubſtance with the brain, round and ſomewhat long, like a Pine-apple, from whence it hath the name: This glandule is ſeated over againſt a ſmall hole which deſcends to the loweſt ventricle. It hath this uſe, to ſtrengthen the diviſion of the veſſels led thither with the production of the *Pia mater* for the generation of the animal ſpirits, and the life and nouriſhment of the brain.

What the *Conarium* or pine-glandule is.

The *Nates*, or buttocks, are ſubjected, or placed, under this glandule, that is, bodies of a ſolid and white ſubſtance drawn out in length like a childs buttocks, eſpecially in Beaſts, and chiefly in a ſheep. Theſe buttocks have ſuch a ſolid ſubſtance, that ſo they may keep open and free the paſſage, or channel, that runs down from the middle to the lower ventricle, by means of which the brain participates with the *Cerebellum*.

What the *Nates* or Buttocks are.

The Worm is a production of the *Cerebellum*, or after-brain, to wit, a portion of the ſame being in the top, or beginning, and as it were in the entrance thereof, being like many little circles, or wheels mutually knit together by ſlender membranes; and it is ſo called becauſe it reſembles thoſe thick white worms which are found in rotten wood. It doth, as it were, perform the office of a Porter to the formerly mentioned paſſage, that it may give way and entrance into the *Cerebellum*, to a neceſſary quantity of ſpirits, when need requires; leſt that, if they ſhould ruſh with a ſudden violence into the *Cerebellum*, they might confound the imprinted notions of things to be remembred.

What the worm is.

The *Pelvis*, or Baſon, is a paſſage appointed for the carrying away of the groſs excrements by the palat; and is ſo called, becauſe it hath the ſimilitude and uſe of a baſon, or tunnel; it deſcends from the third ventricle into the glandule which is ſeated between the proceſſes of the wedg-bone called the ſaddle thereof, as you may perceive by putting in a ſpathern. Now there remains the laſt of the ſix parts propoſed to our conſideration in the third ventricle, that is, the channel or paſſage, running from this third ventricle into the fourth, for the uſe formerly mentioned.

Here the *Pelvis* or Baſon is confounded with the Tunnel.

This channel deſcending in its original from the baſon, goes from thence under the buttocks into the laſt ventricle, the *Meninges* being perforated; which, that you may ſhew, it is fit you put the end of a Spathern through it. The benefit of a third ventricle, is, that it may be as a Tribunal or Judgment-ſeat, to the reaſoning faculty, when the mind will draw concluſions from things ſeen.

The Channel from the third into the fourth ventricle.

The fourth ventricle ſeated in the place we formerly mentioned; it is leſs than the reſt, but more ſolid; leſs as that which was not to receive the ſpirit before it was purified, and cleanſed from all impurities; but more ſolid, that it might contain it the ſafer. The uſe thereof is, to be as a treaſury and ſtore-houſe of the opinion, and judgments which reaſon ſhall decree, that when need requires, we may fetch and draw them from thence as laid up in ſtore. I know *Galen* and the *Greek* Phyſicians have not ſo diſtinguiſhed in places, the three forementioned faculties; but have written, that they all are all over-confuſed through the whole ſubſtance of the brain, which opinion alſo *Fernelius* in his *Pathologia* hath renewed. Yet I had rather follow this opinion, as commonly received and celebrated by the *Arabian* Phyſicians.

The mammillary proceſſes are the inſtruments and paſſages of Smelling, being of the ſame ſubſtance with the brain, and like nerves, which run out from the hind-horns of the upper or foremoſt ventricles of the brain to the *Ethmoides* and ſpongy bones of the noſe, that hence they may receive the diverſe kind of ſmells, and carry them into the brain. But although they be like nerves, yet they are not accounted nerves, becauſe they go not out of the skull.

The uſe of the Mammillary proceſſes.

CHAP. VIII.

Of the ſeven Conjugations of the Nerves of the Brain, ſo called, becauſe they always ſhew the nerves conjugated and doubled; that is, on each ſide one.

THe nerves are the ways and inſtruments of the animal ſpirit and faculty, as of which thoſe ſpirits are vehicles, as long as they are contained in the brain; they conſiſt of the only and ſimple marrowy ſubſtance of the brain, or ſpinal marrow. But paſſing forth of the brain, the have another membranous ſubſtance which involves them, joyned with them from the two membranes of the brain; and according to the opinion of ſome Anatomiſts, they have alſo a third from the ligaments, drawn as well from divers others, as from theſe by which they are tied to the *Vertebra's*; yet this opinion ſeems abſurd to me, ſeeing ſuch a membrane, as that which is inſenſible, wholly repugns the condition of a nerve, which is to give ſenſe to the parts to which it is inſerted.

What a nerve or ſinew is.

Its ſubſtance.

Whether the nerve have a third membrane from the ligaments of the *Vertebra's*.

The magnitude of the nerves is different, according to the diverſe neceſſity of ſenſe incident to the parts into which they are inſerted. Their figure is round, and long, like to a Conduit-pipe to carry water in; the membranes of the brain, with which the nerves are covered, being dilated and ſtretched over them, after the ſame manner that the proceſſes of the *Peritonæum* involves the

Their magnitude.

Their figure.

ſpermatick veſſels, with which they go down to the teſticles, and take life and nouriſhment by the capillary veins and arteries, which deſcend to them with the membranes.

Their uſe.

They are made for this uſe, that they may impart ſenſe to the ſenſitive parts, and motion to thoſe that are fit to be moved.

Their number.

All the nerves deſcend from the brain either mediately, or immediately; their number is ſeven and thirty pair, or conjugations; whereof ſeven have their original immediately from the brain, the other thirty from the ſpinal marrow.

The firſt conjugation of the nerves.

The firſt Conjugation of the nerves of the brain is thicker than all the reſt, and goes to the eyes, to carry the viſive ſpirit to them. Theſe ariſing from divers parts of the brain, in the middle way before they go out of the skull meet together croſs-wiſe, like the Iron of a Mill (which is faſtned in the upper ſtone) going into one common paſſage with their cavities not viſible to the eye; that ſo the ſpirits brought by thoſe two nerves may be communicated, and they are mutually joyned and meet together ſo, that being driven back from one eye they may flie back into the other. An argument whereof may be drawn from ſuch as aim at any thing, who ſhutting one of their eyes ſee more accurately; becauſe the force of the neighbouring ſpirits united into one eye, is more ſtrong than when it is diſperſed into both. This conjugation, when it comes into the glaſſie humor, is ſpent in the ſtructure of the net-like coat which contains this humor on the back-part.

The ſeventh Figure ſhewing the eighth Conjugation of the Nerves of the Brain.

FIG. I.



FIG. II.



AA 1 2 *The brain.* BB 1 2 *the After-brain.*

CC 1 2 *The ſmelling of the brain, which ſome call the Mammillary proceſſes.*

D 1 *The beginning of the ſpinal marrow out of the baſis of the brain.*

F 1 2 *A part of the ſpinal marrow when it is ready to iſſue out of the skull.*

F 1 2 *The mammillary proceſſes which ſerve for the ſenſe of Smelling.*

GG 1 2 *The optick nerves.*

H 1 *The coition or union of the optick nerves.*

II 1 2 *The coat of the eye whereinto the optick nerves are extended.*

KK 1 2 *The ſecond pair of the ſinews ordained for the motion of the eyes.*

LL 1 2 *The third pair of ſinews, or, according to the moſt Anatomiſts, the leſſer root of the third pair.*

MM 1 2 *The fourth pair of ſinews, or the greater root of the third pair.*

N 2 *A branch of the third conjugation derived to the muſculous skin of the fore-head.*

O 2 *A branch of the ſame to the upper jaw.*

PP 2 *Another into the coat of the noſtrils.*

Q 2 *Another into the temporal muſcles.*

R 2 *A branch of the fourth conjugation crumpled like the tendril of a vine.*

S 2 *A branch of the ſame reaching unto the upper teeth, and the gums.*

T 2 *Another of the ſame to the lower-jaw.*

V 2 *A ſurcle of the branch* T, *to the lower lip.*

XX 2 *Another ſurcle from the branch* T, *to the roots of the lower teeth.*

YY 2 *The aſſumption of the nerves of the fourth conjugation unto the coat of the tongue.*

Z 1 2 *The fourth pair are vulgarly ſo called which are ſpent into the coats of the palat.*

a 1 2 *The fifth pair of ſinews which belong to the hearing.*

Φ *The* Auditory-*nerve, ſpread abroad into the cavity of the ſtony-bone.*

* *A hard part of the fifth conjugation above, the* * *which may be counted for a diſtinct nerve.* b 1 2 *A ſmall branch derived from this harder part of the firſt pair.* c 1 2 *A lower branch from the ſame original.* d 1 2 *This nerve is commonly aſcribed to the fifth pair; but indeed is a diſtinct conjugation, which we will call the Eighth, becauſe we would not interrupt the order of other mens accounts.* e 1 2 *The ſixth pair of ſinews.* f 2 *A branch from them divided to the neck, and the muſcles couched thereupon.* g 2 *Another branch to the muſcles of the* Larinx, *or throttle.* h 1 2 *The ſeventh pair of ſinews.* i 1 *The union of the ſeventh pair with the ſixth.* l 2 *A propagation of the ſeventh pair to thoſe muſcles which ariſe from the Appendix called* Stiloides. m 2 *Surcles from the ſeventh conjugation to the muſcles of the tongue, the bone* Hyois, *and the Larinx.* o p q 1 *Three holes; through the hole* o *the phlegm iſſueth out of the third ventricle of the brain to the tunnel; and at* p q *is the paſſage of the* Soporary *arteries to the ventricles of the brain.*

The ſecond Conjugation.

The ſecond conjugation goes into many parts, at its paſſing forth of the skull; and in the bottom of the circle of the eye it is diſtributed into the ſeven muſcles moving the eyes.

The third conjugation.

The third is twofold, in the paſſage out of the skull, it is likewiſe divided into many branches of

of which ſome are carried to the temporal muſcles, into the *Maſſeteres*, or grindling muſcles, into the skin of the face, forehead and noſe; Otherſome are ſent into the upper part of the cheek, and the parts belonging to it, as into the teeth, gums, and the muſcles of the upper lip; and thoſe which are called the round, which incompaſs the mouth on the inſide; the laſt are waſted in the coat of the tongue, to beſtow upon it the ſenſe of taſting.

The fourth conjugation is much ſmaller, and is almoſt wholly waſted upon the coat of the Palat of the mouth, to endue it alſo with the ſenſe of taſting. The fourth conjugation.

The fifth as its original, and having not as yet paſſed forth of the skull, is divided into two, and ſends the greater portion thereof to the hole of the ear, or paſſage of hearing, that it may ſupport the auditory faculty; and it ſends forth the other leſſer portion thereof to the temporal muſcles by the paſſage next to it; by which the ſecond conjugation paſſes forth. The fifth conjugation.

The ſixth being the greateſt next to the firſt, paſſing entire forth of the skull, imparts ſome ſmall branches to certain muſcles of the neck and throttle, and then deſcending into the cheſt, it makes the recurrent nerves; and diſperſed over all the parts of the two lower bellies, it paſſes even to the bladder and teſticles, as we ſhewed in the former Book. The ſixth conjugation.

The ſeventh inſerted and ſpent upon the muſcles of the bone *Hyois*, the tongue, and ſome of the throttle, to give them motion; it paſſes forth of the skull by the hole of the nowl-bone at the extuberancies thereof. The ſeventh conjugation.

CHAP. IX.

Of the Rete Mirabile, *or wonderful Net, and of the Wedge-bone.*

THe Animal ſpirit is made of the vital, ſent from the heart by the internal ſleepy arteries to the brain. For it was requiſite, that it ſhould be the more elaborate, becauſe the action of the animal is more excellent than that of the vital: Nature hath framed a texture of arteries in many places running croſs one another, in the form of a Net divers times doubled; (whereupon it had the name of the wonderful Net) that ſo the ſpirit by longer delay in theſe Labyrinthian or Maze-like turnings, might be perfectly concocted and elaborated, and attain to a greater fitneſs to perform the animal functions. The exiſtence of the animal ſpirit. What the *Rete mirabile* is.

This wonderful Net ſituate at the ſides of the *Apophyſes clinoides*, or productions of the wedg-bone, is two-fold; that is, divided by the pituitary glandule, which is ſituate between the ſaid *Apophyſes clinoides*, having the wedg-bone lying under them, next to the *Craſſa meninx*, being perforated on the right and left ſide, next to which lye bones as a rare as a ſponge even to the palat, by which the phlegm is purged by the mouth and noſe; and there-hence, I think, that ſpattle flows, which ſuch as have a moiſt brain, continually ſpit out of their mouth. The ſite and number.

The eighth Figure of the Brain.

FIG. I.



II

A *The brain.*
B *The* Cerebellum, *or after-brain.*
C *A proceſs of the Brain, but not that is called* Mammillaris.
DD *The marrow of the back as it is yet within the skull.*
E *The* Mammillary *proceſs or inſtrument of ſmelling,*
F *The optick nerve.*
G *The coat of the eye into which the optick nerve is ſpread.*
H *The nerve that moveth the eye or the ſecond pair.*
I *The third conjugation, or the harder and leſſer branch of the nerves of the third conjugation brought forward.*
K *The fourth conjugation or the greater and thicker nerve of the third pair bending downward.*
L *A branch of the nerve marked with* I, *which goeth to the fore-head.*
M *Another branch of the nerve* I, *reaching to the upper jaw.*
NN *A nerve proceeding from the branch* I, *intexed or woven with the coat of the noſe.*
O *The nerve of the temporal muſcle iſſuing from the branch* I.
P *A nerve contorted of the nerves* K *and* b.
Q *A nerve proceeding from the branch* K, *to the ſockets of the upper teeth.*
R *A nerve creeping from the nerve* K *to the lower jaw.*

S *A ſurcle of the branch* R, *offered to the lower lip.* TT *Other ſurcles from the branch* R, *attaining to the lower teeth.* V V *A branch of the nerve* K, *diffuſed into the coat of the tongue.* XX *The fourth pair of ſinews which go into the coat of the palat.* Y *The fifth pair of ſinews which are the nerves of hearing.* a *The membrane of the ear, unto which that fifth nerve goeth.* b c *Two ſmall branches of the fifth conjugation uniting themſelves with the nerve* P. d *The eighth conjugation or a nerve of the fifth pair attaining unto the face.* e e *The ſixth pair of nerves.* f *A branch from the nerve* e, *reaching to the muſcles of the neck.* g *Small branches derived unto the throttle, or* Larinx. h *The bifurcation of the nerve into two branches,* iii *An inner branch hanging to the rack-bones, and ſtrengthening the* intercoſtal *nerves, and is therefore called* intercoſtalis. k k *Surcles of the utter branch going to the heads of the muſcles, to the breaſt-bone, and to the collar-bones.* l m *Branches of the right nerve* l, *making the right recurrent nerve.* m n *The inſertion of the recurrent ſinews into the muſcles of the* Larinx. o p *Branches of the left nerve making the left recurrent ſinew* p. q q *Branches from the ſixth conjugation going to the coat of the lungs.* r *Small nerves of the heart, and of the purſe thereof called the* Pericardium, *as alſo ſome approaching to the coats of the lungs.* ſ *Nerves on either ſide ſent to the ſtomach.* t *The right ſtomach-nerve going to the left oriſice of the ſtomach.* u u *The left ſtomach-nerve going to the right oriſice of the ſtomach.* x *A nerve from the branch* u, *paſſing into the hollowneſs of the liver.* y *The nerve belonging to the right ſide of the kell.* z *The nerve belonging to the colick-gut.* α *A nerve creeping to the gut called* duodenum, *and the beginning of the* jejunum, *or empty gut.* β *A nerve implanted in the right ſide of the bottom of the ſtomach.* γ *A nerve belonging to the liver and bladder of gall.* δ *A nerve reaching to the right kidney.* ε *A branch reaching to the* Meſenterium *and the guts.* ζ *A branch ſprinkled to the right part of the bladder.* η *A branch going through the left part of the kell.* θ *Surcles derived to the colick-gut and the kell.* ι *Small branches inſerted into the Spleen.* λ λ *A nerve approaching to the left ſide of the bottom of the ſtomach.* μ *A branch belonging to the left ſide of the* Meſentery *and the guts.* ν *A branch which attaineth to the left kidney.* ξ *Small nerves creeping through the left ſide of the bladder.* ο *The ſeven pair of ſinews.* π *A branch derived from the ſixth conjugation to the muſcles which ariſe from the proceſs called* Styloides. ρ *A branch of the ſeventh conjugation which goeth to the muſcles of the tongue, of the bone* Hyois, *and of the throttle, or* Larynx. ς *A conjunction or coition of the ſixth and ſeventh pair into one nerve.*

What the *Apophyſes clinoides* are.

Theſe *Apophyſes clinoides* are certain productions of the *Os baſilare*, or wedg-bone (called the ſaddle thereof) between which, as I ſaid, the pituitary glandule lies with part of the wonderful Net.

Whether the *Rete mirabile* differs from the *Plexus choroides.*

There is a great controverſie amongſt Anatomiſts concerning this part; for, *Veſalius* denies that it is in man, *Columbus* admits it; yet he ſeems to confound it with the *Plexus choroides.* Truly, I have obſerved it always after the manner, as *Sylvius* alledges againſt *Veſalius.* It remains, that we recite the perforations of the skull, becauſe the knowledg of theſe much conduces to the underſtanding of the inſertions of the veins, arteries and nerves.

CHAP. X.

Of the holes of the inner Baſis of the Skull.

IN the firſt place are reckoned the holes of the bone *Ethmoides*; then thoſe of the Optick-nerves. Thirdly, of the nerves moving the eyes. Fourthly, of that portion of the nerves of the fourth conjugation which go to the temporal muſcles. Fifthly, are reckoned thoſe holes ſcarce viſible, ſituate under the pituitary glandule, by which the ſpittle is evacuated. Sixthly, that hole which is in the wedg-bone made for the entrance into the internal ſleepy Arteries, compoſing the wonderful Net, and then paſſing into the brain by a great Slit. That perforation which we reckon in the ſeventh place is commonly double, made for the entrance of one of the branches of the internal Jugular-vein. The eighth hole is ſomewhat long, of an oval figure, by which, part of the third conjugation, and all the fourth conjugation paſſes forth. The ninth are the auditory paſſages. The tenth are very ſmall holes, and give way to the vein and artery going to the auditory paſſage, above the *foramen cæcum.* In the eleventh place are reckoned the perforations which yield paſſage forth to the ſixth pair of nerves, to part of the ſleepy arteries, and of the internal jugular. In the twelfth, thoſe which yield a way out to the ſeventh conjugation. The great hole of the nowl-bone through which the ſpinal marrow paſſes, is reckoned the thirteenth. The fourteenth is that which moſt commonly is behind that great hole, by which the Cervical veins and arteries enter in.

CHAP. XI.

Of the perforations of the external Baſis of the Brain.

THere is a hole on each ſide at the eye-brows, by which paſſes a ſmall nerve from the third conjugation coming out of the cavity of the orb of the eye, and going by the forehead bone to the eye-brows, that it may give motion to the two muſcles of the upper eye-brow and forehead. Yet oftentimes the hole is but to be ſeen on one ſide, often-times there is a cleft in ſtead thereof, other-whiles it is not perforated nor cleft at all. The ſecond is the perforation of the greater corner of the eye, by which a portion of the nerves of the third conjugation deſcends to the coat of the noſe; in this hole the *Glandula Lacrymalis* is ſeated. The third is ſeated under the eye, that it may give way to the other portion of the nerves of the third conjugation going to the part of the face, and the teeth of the upper jaw. The fourth is at the beginning of the palat, amongſt the cutting and ſhearing-teeth, through which a vein, an artery, and the coat of the palat paſſes out. In the fifth order, are reckoned the perforations of the palat, by which the nerves deſcend from the fourth conjugation, to give or cauſe the taſte. In the ſixth order are ranked

ed

ed the holes of the palat ſerving for the reſpiration, and the flegm falling from the brain by the noſtrils. And there is a cleft under the yoke-bone aſcending into the orb of the eye, by which there is a way, as well for the nerves of the third conjugation to the temporal muſcles, as alſo for certain veins and arteries. But alſo, there is noted another hole at the mammillary proceſs, which is not perforated in the judgment of the ſenſe. Beſides, there is thought to be another at the hind root of the ſame proceſs, by which a certain ſmall vein paſſes from the Jugular to the *Torcular*. But I have only noted theſe three paſſages by the way, becauſe there is ſo much variety in them, that nothing can be certainly ſaid of them.

CHAP. XII.

Of the Spinal Marrow, or Pith of the Back.

What the ſpinal marrow is.

THe ſpinal marrow is like a river running from the fountain of the Brain. This ſends nerves for ſenſe and motion to all the neigbouring parts under the head, ſpreading its branches as from the body of a tree. Theſe branches, as we ſhall hereafter ſhew, are on each ſide thirty. This ſame ſpinal marrow is covered with the two membranes inveſting the brain, diſtinguiſhed by no diſtance of place, as in the Brain. But alſo it hath another membrane added to theſe, being very hard and denſe, which keeps it from being broken and violated by the violent bending of the body forwards and about. The diſeaſes of this marrow do almoſt cauſe the like ſymptomes, as the diſeaſes of the brain; for they hurt the ſenſe and motion of all the parts lying beneath them; as, for example, If any of the *Vertebra's* of the back-bone be moved out of their place, there follows a diſtortion or wreſting aſide of the marrow; but then eſpecially if it happen that one of the *Vertebra's* be ſtrained, ſo ſharp and bitter a compreſſion urges the marrow by reaſon of the bony body of the *Vertebra*, that it will either rend it, or certainly hinder the paſſage of the ſpirit by it. But by theſe ſame holes of the *Vertebra's* the veins and arteries go to the ſpinal marrow for to give life and nouriſhment to it, as the nerves by them paſs forth into all the lower parts of the body.

The coats of the ſpinal marrow.

The diſeaſes from the hurting of the ſpinal marrow.

Figure 1. *Sheweth the form of the ſpinal marrow properly ſo called, with its membranes, and the nerves proceeding from it.*

Figure 2. *The ſpinal marrow naked and bare, together with its nerves, as moſt part of Anatomiſts have deſcribed it.*

The tenth Figure of the Spinal Marrow.



A *The beginning of the ſpinal marrow where it falls out of skull.*

B *The thickneſs thereof in the ſpondyls or rack-bones of the loins.*

C *The diviſion thereof into ſtrings, or hairy threds.*

D *The ſeven nerves of the neck.*

From D *to* E, *or from* 7 *to* 19 *ſhew the nerves of the back.*

From E *to* F *The nerve of the loins.*

From F *to* G *The nerves of the* Os ſacrum, *or holy-bone.*

H *The end of the marrow.*

I K L *Do ſhew how the nerves do iſſue from the marrow in ſtrings.*

M M *The knots of the ſinews made of the conjunction of thoſe ſtrings.*

N O *The membranes that inveſt the marrow.*

Figure 2.

A *The beginning of the ſpinal marrow in the skull.*

3 4 5 6 7 *Theſe Characters ſhew (according to* Veſalius *opinion) how the conjugation of the nerves of the brain do take their original skull.*

B *From the marrow remaining yet without the egreſs of the ſpinal marrow out of the ſkull.*

C *The cords or ſtrings whereinto it is divided.*

D 7 *The marrow of the neck and ſeven pair of ſinews.*

E 19 *Twelve pair, or conjugations, of nerves proceeding from the marrow of the cheſt.*

F 24 *The marrow of the loins, and five pair of ſinews.*

G 30 *The marrow of the holy-bone, and ſix pair of ſinews.*

H *The extremity, or end of the ſpinal marrow.*

The end of the Fifth Book.

BOOK VI.

Treating of the Muſcles and Bones, and the other Extreme parts of the Body.

The PREFACE.

PEradventure ſome may wonder that I have ended my Fifth Book of Anatomy, before I have fully deſcribed all the parts of the Head, the which ſeemed, as it were, only appointed for that purpoſe. Therefore I muſt yield a reaſon of this my intention. I have a deſire, in one Treatiſe, and, as it were, at one breath, to proſecute the Anatomy of the Muſcles. *Wherefore, becauſe the parts of the Head not yet deſcribed, principally conſiſt of the Muſcles, therefore I deſired to comprehend them together with this ſame deſcription of the extreme parts of the body; beginning at the upper part of the face; to wit, the eyes: But having firſt deſcribed the bones of the face, without the knowledg of which it is impoſſible to ſhew the original and inſertion of the Muſcles. We have formerly noted, that by the face is meant whatſoever lies from the eye-brows even to the chin. In which there is ſuch admirable induſtry of Nature, that of the infinite multitude of men you cannot find two ſo like, but that they may be diſtinguiſhed by ſome unlikeneſs in their faces; alſo, it hath adorned this part with ſuch exquiſite beauty, that many have died by longing to enjoy the beauty deſired by them. This ſame face albeit it little exceeds half a foot, yet it indicates and plainly intimates by the ſudden changes thereof, what affections and paſſions of hope, fear, ſorrow and delight poſſeſs our minds; and what ſtate our bodies are in, ſound, ſick, or neither. Wherefore ſeeing the face is of ſo much moment, let us return to the Anatomical deſcription thereof: Which that we may eaſily and plainly perform, we will begin with the bones thereof; whereby, as we formerly ſaid, the original and inſertion of the Muſcles may be more certain and manifeſt to us.*

The deſcription of the bones being unknown, it muſt neceſſarily follow that the original and inſertion of the Muſcles muſt be ſo alſo.

The endowments of the face.

The Countenance is the bewrayer of the will.

CHAP. I.

Of the Bones of the Face.

Bones in each orb of the eye.

THe bones of the face are ſixteen or ſeventeen in number. And firſt, there be reckoned ſix about the orbs of the eyes, that is three to each orb, of which one is the bigger, another leſſer, and the third between both; each of theſe touch the forehead-bone in their upper part. Beſides, the greater is joyned with a ſuture to the proceſs of the ſtony-bone, and ſo makes the *Zygoma*, that is, the *Os Jugale*, or Yoke-bone, framed by Nature for preſervation of the temporal muſcle. The leſſer is ſeated at the greater corner of the eye, in which there is a hole perforated to the noſe, and in this is the glandule in which the *Ægilops* doth breed. The middle is in the bottom, or inner part of the orb, very ſlender, and as it were of a membranous thinneſs: Then follow the two bones of the noſe which are joyned to the fore head-bone by a ſuture, but on the foreſide between themſelves by harmony. But on the back and hind-part with two other bones, on each ſide one, which deſcending from the bone of the forehead (to which alſo they are joyned by a ſuture) receive all the teeth. Theſe two in *Galens* opinion are ſeldom found ſeparated. But theſe are the thickeſt of all the bones of the face hitherto mentioned, knit by a ſuture with the greateſt bone of the orb, on the back part with the wedge-bone, on the inner ſide with the two little inner bones of the palat, which on the inſide make the extremity thereof, whereby it comes to paſs, that we may call theſe bones the hinder, or inner bones of the palat. They reckon one of theſe bones the eleventh, and the other the twelfth-bone of the head; theſe two little bones on their ſides next to the winged productions of the wedg-bone, receive on each-ſide one of the nerves of the fourth conjugation, which, in the former Book, we ſaid were ſpent upon the membrane of the palat.

What the *zygoma* is, and what uſe it hath.

The *Ægilops*.

The two bones of the noſe.

The two inner bones of the palat.

The two bones of the jaw.

And in *Galen*'s opinion there be other two in the lower jaw, joyned at the middle of the chin; although ſome think it but one bone, becauſe by the judgment of ſenſe there appears no diviſion or ſeparation therein. But you may ſee in children how true this their ſuppoſition is, for in men of perfect growth it appears but one bone; theſe two are reckoned for the thirteenth and fourteenth bones. Now theſe two bones making the lower jaw, have in their back-part on each ſide two productions, as they lie to the upper jaw, the one of which repreſents the point of a Sword, and is called the *Corone:* Thee other is obtuſe and round; which is inſerted into the cavity ſeated at the root of the proceſs of the ſtony-bone, near to the paſſage of the ear.

Two productions on each ſide of the lower jaw.

The Luxation of the lower jaw.

This may be ſtrained to the fore-part by violent gaping, by retraction of the muſcles ariſing from the wing-like proceſſes, and ending at the lower angles of the broader part of the ſame jaw.

The lower jaw filled with a marrowy humor.

This jaw is hollow, as alſo the upper, eſpecially in the back-part, being filled with a white and glutinous humor, conducing to the growth of the teeth. This humor hath its matter from the blood brought thither by the veſſels, veins, arteries and nerves from the third Conjugation entring here by a paſſage large enough. Whereby it comes to paſs, that this part is not only nouriſhed and lives, but alſo the teeth receive ſenſe by the benefit of the nerves entring thither with the

the vein and artery: by ſmall holes to be ſeen at the lower roots of the teeth; and thence it is that a beating pain may be perceived in the Tooth-ach, becauſe the defluxions may be by the arteries; or rather becauſe the humor flowing to the roots of the teeth, may preſs the artery in that place: Beſide alſo you may ſee ſome appearance of a nervous ſubſtance in the root of a tooth newly pluck'd out.

How the teeth feel.
Why the teeth have a beating pain.

But alſo you muſt conſider, that this jaw from its inner capacity produces at the ſides of the chin two nerves of a ſufficient magnitude, over againſt the lower Dog-teeth, and the firſt of the ſmaller grinding teeth, as I have noted in the deſcription of nerves of the third conjugation. I have thought good to put thee in mind of theſe, that when thou ſhalt have occaſion to make inciſion in theſe places, thou mayeſt warily and diſcreetly handle the matter, that theſe parts receive no harm.

The nerves of the lower jaw muſt be obſerved.

There remains another bone ſeated above the palat, from which the griſtly partition of the noſe ariſes, being omitted of all the Anatomiſts, for as much as I know. Now therefore that you may the better remember the number of the bones of the face, I will here make a repetition of them.

The bone of the noſe above the palat, or the partition of the noſe.

There are ſix of the orbs of the eyes, at each three. The ſeventh and eighth we may call the Naſel, or Noſe-bones. The ninth and tenth the Jaw-bones. The eleventh and twelfth are called the inner bones of the palat. The thirteenth and fourteenth, the bones of the lower Jaw. The partition of the noſe may reckoned the fifteenth.

Now it remains, having ſpoken of theſe bones, that we treat of the Teeth, the Eye-brows, the Skin, the fleſhy pannicle, the muſcles; and laſtly, the other parts of the Face.

CHAP. II.

Of the Teeth.

The teeth are bones.

THe teeth are of the number of the bones, and thoſe which have the moſt, have thirty two, that is, ſixteen above, and ſo many below; of which in the forepart of the mouth there are four above, and as many beneath, which are called *Inciſorii*, cutting or ſhearing teeth, to cut in ſunder the meat, and they have but one root. To theſe are joyned two in each jaw, that is, on each ſide of the other one, which are called the *Canini dentes*, Dog-teeth, becauſe they are ſharp and ſtrong like Dogs-teeth; theſe alſo have but one root, but that is far longer than the other have.

The ſhearing-teeth.

The Dog-teeth.

Then follow the *Molares*, or grinders, on each ſide five; that is, ten above, and as many below, that they may grind, chaw, and break the meat, that ſo it may be the ſooner concocted in the ſtomach; for ſo they vulgarly think, that meat well chawed is half concocted; thoſe grinders which are faſtned into the upper jaw, have moſt commonly three roots, and oft-time four. But theſe which are faſtned into the lower, have only two roots, and ſometimes three, becauſe this lower jaw is harder than the upper, ſo that it cannot be ſo eaſily hollowed, or elſe becauſe theſe teeth being fixed and firmly ſeated, needed not ſo many ſtays as the upper, which, as it were, hang out of their ſeats. The ſhearing-teeth cut the meat, becauſe they are broad and ſharp; the Dog-teeth break it becauſe they are ſharp pointed and firm: but the Grinders being hard, broad and ſharp, chaw and grind it aſunder, But if the Grinders had been ſmooth, they could not fitly have performed their duty; for all things are chawed and broken aſunder more eaſily by that which is rough and unequal.

The grinding teeth.

Why the upper grinding teeth have more roots.

The uſe of the teeth.

Wherefore they ſharpen their Milſtones when they are ſmoother than they ſhould be, by picking them with a ſharp Iron. The teeth are faſtened in the Jaws by *Gomphoſis*, that is, as a ſtake or nail, ſo are they fixed into the holes of the jaws; for they adhere ſo firmly thereto in ſome, that when they are pluck'd out, part thereof follows together with the tooth; which I have often obſerved to have been alſo with great effuſion of blood. This adheſion of the teeth faſtned in the jaws, is beſides ſtrengthned with a ligament, which applies it ſelf to their roots together with the nerves and veſſels. The teeth differ from the other bones, becauſe they have action whilſt they chaw the meat; becauſe being loſt they may be generated, and for that they grow as long as the party lives; for otherwiſe by the continual uſe of chawing, they would be worn and waſted away by one another. You may perceive this by any that have loſt one of their teeth; for that which is oppoſite to it becomes longer than the reſt, becauſe it is not worn by its oppoſite. Beſides alſo, they are more hard and ſolid than the reſt of the bones, and indued with a quick ſenſe by reaſon of the nerves of the third conjugation which inſert themſelves into their roots; for if you rub or grind a tooth newly puck'd out, you may ſee the remains of the nerve; they have ſuch quick ſenſe, that with the tongue they might judg of taſtes. But how feel the teeth, ſeeing they may be filled without pain? *Fallopius* anſwers, that the teeth feel not in their upper or exterior part, but only by a membrane which they have within. And the teeth have another uſe, eſpecially the fore-teeth, which is, they ſerve for diſtinct and articulate pronuntiation; for thoſe that want them faulter in ſpeaking, as alſo ſuch as have them too ſhort, or too long, or ill-ranked. Beſides children ſpeak not diſtinctly before they have their fore-teeth. And muſt note, that the Infant as yet ſhut up in its Mothers womb hath ſolid and bony teeth; which you may perceive by diſſecting it preſently after it is born.

The teeth are faſtned in the jaws by *Gomphoſis*.

The faſtening of the teeth into the jaw is to be obſerved.

Wherein the teeth differ from the other bones.

For what uſe the teeth have ſenſe.

The foreteeth help for the articulation of the voice.

But even as there are two large cavities in the forehead-bone at the eye-brow, filled with a viſcous humour, ſerving for the ſmelling; and in like manner, the air ſhut up in the mammillary proceſſes is for hearing: So in the jaws, there be two cavities furniſhed with a viſcid humor for the nouriſhment of the teeth.

CHAP.

CHAP. III.

Of the Broad Muſcle.

NOw we ſhould proſecute the containing parts of the face; to wit, the skin, the fleſhy pannicle and fat; but, becauſe they have been ſpoken of ſufficiently before, I will only deſcribe the fleſhy pannicle, before I come to the diſſection of the eye, that we may the more eaſily underſtand all the motions performed by it, whether in the face or forehead.

Firſt, that you may more eaſily ſee it, you muſt curiouſly ſeparate the skin in ſome part of the face. For unleſs you take a good head you will pluck away the fleſhy pannicle together with the skin, as alſo this broad muſcle to which it immediately adheres, and in ſome places ſo cloſely and firmly, as in the lips, eye-lids, and the whole forehead, that it cannot be ſeparated from it. Nature hath given motion, or a moving force, to this broad muſcle, that whilſt it extends or contracts it ſelf, it might ſerae to ſhut and open the eye. It will be convenient to ſeparate the muſcle thus freed from the skin, beginning from the fore-part of the clavicles even to the chin, aſcending in a right line, and shen turning back as far as you can; for thus you ſhall ſhew how it mixes it ſelf with the skin and muſcles of the lips.

There are no particular Muſcles appointed to ope n and ſhut the eye, for that is the broad muſcle only.

When thou ſhalt come to the eyes, thou ſhalt teach how the eye is ſhut and opened by this one muſcle, becauſe it is compoſed of three ſorts of fibers; although by the opinion of all who hitherto have written of Anatomy, thoſe actions are ſaid to be performed by the power of two muſcles appointed for that purpoſe; one of which is at the greater corner on the upper part, the other reſembling a ſemicircle at the leſſer corner, from whence extending it ſelf to the middle of the griſtle *Tarſus*, it meets with the former ending there; but they are in part extended over all the eye-lid, whereby it cometh to paſs, that it alſo in ſome ſort becometh moveable. But although in publick diſſections, theſe two muſcles are commonly wont to be ſolemnly ſhewed, after the manner I have related; yet I think, that thoſe which ſhew them, know no more of them than I do. I have grounded my opinion from this, that there appears no other muſculous fleſh in theſe places, to thoſe which ſeparate the fleſhy pannicle, or broad muſcle, than that which is of the pannicle it ſelf, whether you draw your Inciſion-knife from the forehead downwards, or from the cheek upwards.

Divers reaſons to that purpoſe.

Beſides, when there is occaſion to make inciſion on the eye-brows, we are forbidden to do it tranſverſe, leſt this broad muſcle falling upon the eye, make the upper eye-lid unmoveable; but, if ſuch a cut be received accidentally, we are commanded preſently to ſtitch it up; which is a great argument, that the motion of the upper eye-lid is not performed by its proper muſcles, but wholly depends, and is performed by the broad muſcle, Now if theſe ſame proper muſcles which we have deſcribed ſhould be in the upper eye-lid, it ſhould be meet (becauſe when one of the muſcles is in action, the other, which is its oppoſite or Antagoniſt, reſts or keeps holy-day) that when that which is ſaid to open the eye is employed, the oppoſite thereof reſting, the upper eye-lid ſhould be drawn towards its original, as we ſee it happens in Convulſions; becauſe the operation of a muſcle is the collection of the part which it moves towards its original.

Why you muſt take heed of making a tranſverſe inciſion upon the eye-brows.

The action of a muſcle.

Therefore ſeeing ſuch a motion or collection appears not any where in the eye-lid, I think it therefore manifeſt, that all the motion of this upper eye-lid depends upon this broad muſcle, and that it alone is the author of the motion thereof.

The original of the broad muſcle.

The original of this broad muſcle is from the upper part of the *Sternon*, the clavicles, the ſhoulder-blades, and all the ſpines of the *vertebra's* of the neck: But it is inſerted into all theſe parts of the head which want hair, and the whole face, having divers fibers from ſo various original, by the benefit of which it performs ſuch manifold motions in the face (for it ſo ſpreads it ſelf over the face, that it covers it like a vizard) by reaſon of the variety of the original and the production of the divers fibers of this muſcle. But I have not in the deſcription of this muſcle proſecuted thoſe nine conditions, which in the firſt Book of my Anatomy I required in every part, becauſe I may ſeem to have ſufficiently declared them in the deſcription of the muſcles of the *Epigaſtrium*. Wherefore hence forward you muſt expect nothing from me in the deſcription of the Muſcles beſides their original, inſertion, action, compoſition, and the deſignation of their veſſels.

The inſertion, and reaſon why we expreſs ſo many motions with the face.

CHAP. IV.

Of the Eye-lids, and Eye-brows.

What the eye-brows are.

BEcauſe we have fallen into mention of the eye-lids, and eye-brows, and becauſe the order of Diſſection alſo requires it, we muſt tell you what they are, of what they conſiſt, and how, and for what uſe they were framed by Nature. Therefore the eye-brows are nothing elſe, than a rank of hairs ſet in a ſemicircular form upon the upper part of the orb of the eye, from the greater to the leſſer corner thereof, to ſerve for an ornament of the body, and a defence of the eyes againſt the acrimony of the ſweat falling from the forehead.

Their uſe.

What the eye-lids are.

Their compoſure and uſe.

But the eye-lids on each ſide two, one above, and another below, are nothing elſe than as it were certain ſhuttings appointed and made to cloſe and open the eyes when need requires, and to contain them in their orbs. Their compoſure is of a muſculous skin, a griſtle and hairs ſet like a pale at the ſides of them to preſerve the eyes when they are open, chiefly againſt the injuries of ſmall bodies, as motes, duſt, and ſuch like. Theſe hairs are always of equal and like bigneſs, implanted at the edges of the griſtly part, that they might always ſtand ſtrait and ſtiff out. They

are

are not thick, for ſo they ſhould darken the Eye. The Griſle in which they are faſtned is encompaſſed with the *Pericranium* ſtretched ſo far before it produce the *Conjunctiva*. It was placed there, that when any part thereof ſhould be drawn upwards or downwards by the force of the broad Muſcle, or of the two proper Muſcles, it might follow entirely and wholly by reaſon of its hardneſs. They call this ſame Griſle, eſpecially the upper, *Tarſus*. The upper and lower Eye-lid differ in nothing, but that the upper hath a more manifeſt motion, and the lower a more obſcure: for otherwiſe Nature ſhould have in vain encompaſſed it with a Muſculous ſubſtance. What the *Tarſus* is.

CHAP. V.

Of the Eyes.

THe Eyes are the Inſtruments of the faculty of Seeing, brought thither by the viſive ſpirit of the Optick Nerves, as in an *Aquæ-ductl*. They are of a ſoft ſubſtance, of a large quantity, being bigger or leſſer, according to the bigneſs of the body. They are ſeated in the head, that they might over-look the reſt of the body, to perceive and ſhun ſuch things as might endanger or endamage the body; for the action of the Eyes is moſt quick, as that which is performed in a moment, which is granted to none of the other ſenſes. Wherefore this is the moſt excellent ſenſe of them all. For by this we behold the Fabrick and Beauty of the Heavens and Earth, diſtinguiſh the infinite varieties of colours, we perceive and know the Magnitude, Figure, Number, Proportion, Site, Motion, and reſt, of all bodies. The Eyes have a pyramidal Figure whoſe Baſis is without, but the Cone or point within at the Optick Nerves. Nature would have them contained in a hollow circle, that ſo by the profundity and ſolidity of the place they might be free from the incurſions of bruiſing and hurtful things. What the Eyes are. Their ſite. The quickneſs and excellency of their action. Figure.

They are compoſed of ſix Muſcles, five Coats, three Humours, and a moſt bright Spirit, (of which there is a perpetual afflux from the Brain) two Nerves, a double Vein, and one Artery, beſides much fat; and laſtly, a Glandule ſeated at the greater angle thereof, upon that large hole which on both ſides goes to the Noſe, and that, leſt that the humours falling from the Brain ſhould flow by the Noſe into the Eyes, as we ſee it fares with thoſe whoſe Eyes perpetually weep or water by reaſon of the eating away of this Glandule, whence that affect is called the *Fiſtula lacrymalis*, or weeping Fiſtula. Compoſition. *Glandula Lacrymalis.* *Fiſtula Lacrymalis.*

But there is much fat put between the Muſcles of the Eye, partly that the motion of the Eyes might be more quick in that ſlipperineſs of the fat, as alſo that the temper and complexion of the Eyes, and chiefly of their nervous parts, might be more conſtant and laſting, which otherwiſe by their continual and perpetual motion would be ſubject to exceſſive drineſs. For Nature for the ſame reaſon hath placed Glandules flowing with a certain moiſture near thoſe parts which have perpetual agitation. Why fat is placed about the Eyes.

CHAP. VI.

Of the Muſcles, Coats, and humours of the Eye.

THere are ſix Muſcles in the Eye, of which four perform the four direct motions of the Eye: they ariſe from the bottom of the Orb, and end in the midſt of the Eye, encompaſſing the Optick Nerve. When they are all moved with one endeavour, they draw the Eye inwards. But if the upper onely uſe its action, it draws the Eye upwards; if the lower, downwards; if the right, to the right ſide; if the left, to the left ſide. The number ſite, and action of the Muſcles.

The two other Muſcles turn the Eye about; the firſt of which being the longer and ſlenderer, ariſes almoſt from the ſame place from which that Muſcle ariſes which draws the Eye to the right ſide to the greater corner. But when it comes to the utmoſt part of the inner angle, where the *Glandula lacrymalis* is ſeated, it ends in a ſlender Tendon, there piercing through the middle Membrane which is there, as through a Ring; from whence it preſently going back, is ſpent in a right angle towards the upper part of the Eye, betwixt the inſertions of thoſe two Muſcles, of the which one draws the Eye upwards, the other directly to the outward corner, as it is obſerved by *Fallopius*, or rather, which I remember, I have always obſerved, they turn between the Muſcles which move the Eye upwards, and to the inner corner.

This fifth Muſcle when it is drawn in towards its beginning, ſo draws the eye with its circular tendon that it carries it to the greater corner.

The ſixth Muſcle is contrary to that, for that it hath its original from the lower part of the orb at a ſmall hole, by which a Nerve of the third conjugation paſſes forth; and being that it is moſt ſlender, whileſt it aſcends tranſverſly to the outward corner, it involves the eye ſo alſo, that it is inſerted in it by a ſmall Tendon, ſo that the Tendons of them both are often-times taken but for one. That thou mayeſt truly and accurately obſerve this anatomical deſcription of the Eye, the Eye muſt not be pluckt out of its orb, but rather the orb it ſelf muſt be broken and ſeparated.

For thus thou ſhalt certainly and plainly ſee the fore-mentioned original of the Muſcles. For the five Coats, the firſt which is firſt met with in diſſection, comes from the *Pericranium*, and is extended over all the white of the Eye even to the *Iris* or Rainbow. The duty of it is to ſtrengthen, bind, and contain the Eye in its orb, wherefore it had the name *Conjunctiva*; others call it *Adnata*, or *Epipophycos*. The five coats of the Eye. 1. *Conjunctiva*, or *Adnata*.

The ſecond is called the *Cornea*, becauſe it reſembles a Horn in colour and conſiſtence; this

2. *Cornea*, or the Horny Coat. coat differs and varies from it ſelf; for in the fore-part, as far as the *Iris* goes, it is clear and perſpicuous, but thick and obſcure in the hind part, by reaſon of the diverſe poliſhing. On the fore-part it is denſe; that it may preſerve and contain the Cryſtalline and wateriſh humour, but withall tranſparent, ſo to give the object a free paſſage to the Cryſtalline. It hath its original from the *Craſſa Meninx*, proceeding forth from the inner holes of the orb of the eye, for it compaſſes the eye on every ſide.

3. *Uvea*, or the Grapy Coat. The third is called *Uvea* or Grapy Coat, becauſe in the exteriour part it repreſents the colour of black Grape; it ariſes from the *Pia Mater*, and encompaſſes all the Eye, except the *Pupilla* or Apple of the Eye, for here being perforated, it adheres to the horny Coat by the Veins and Arteries which it communicates to it for life and nouriſhment. But when it arrives at the *Iris*, then forſaking the *Cornea*, it deſcends deep in the Eye, and in ſome ſort is turned about the Cryſtalline humour, to which alſo it moſt firmly adheres, ſo bounding the wateriſh humour, and alſo prohibiting that the Albugineous humour do not overwhelm the Cryſtalline. This grapy Coat is, as it were, died on the inſide with divers colours, as black, brown, blue, or green like a Rainbow, and that for theſe enſuing benefits.

Why the Grapy Coat reſembles divers colours. The firſt is, if that it had been tinctured with one colour, all objects would have appeared of the ſame colour, as it comes to paſs when we look through green or red Glaſs. But it muſt be coloured, that ſo it may collect the ſpirits diſſipated by the Sun and Seeing.

Table 3. Fig. 1. *Sheweth the Membrane and humors of the Eye, by lines drawn after the manner of a true Eye.*
F. 2. *Sheweth the horny coat with a portion of the optick nerve.*
Fig. 3. *Sheweth the ſame divided by a tranſverſe ſection.*
Fig. 4. *Sheweth the* Uvea, *or grapy coat, with a portion of the Optick Nerve.*
Fig. 5. *The Grapy Coat of a Mans Eye.*
Fig. 6. *The Horny, Grapy, and the Choroides.*
Fig. 7. *The interiour ſuperficies of the Grapy Coat.*
Fig. 8. *The poſterior part of the Horny Coat, together with the ſaid Net Coat ſeparated from the Eye.*
F. 9. *The coat of the vitreous or glaſſie humor called* Hyaloides.
Fig. 10. *The humours joined together.*
Fig. 11. *The former part of the Cryſtalline.*
Fig. 12. *The Cryſtalline humour covered yet with his Coat.*
Fig. 14. *The Cryſtalline of a Mans Eye.*
Fig. 15. *His Coat.*
Fig. 16. *The watery humour diſpoſed upon the Cryſtalline round about.*
Fig. 17. *The hairy proceſſes beamingly ſprinkled through the fore-ſide of the Coat of the Glaſſie humour.*
Fig. 18. *The fore-ſide of the Glaſſie humour.*
Fig. 19. *The place of the Watery humour.*
Fig. 20. *The Glaſſie humour containing or comprehending the Cryſtalline.*

The Explication of the firſt Figure by it ſelf.
a *The Cryſtalline humour.*
b *The Glaſſie humour.*
c *The Watery humour.*
d *The utmoſt Coat called* Adnata.
e *The dark part of the Horny Tunicle, which is not tranſparent.*
f *The Grapy Coat called* Retiformis.
h *The coat of the glaſſie humour called* Hyaloides.
i *The coat of the Chryſtalline.*
k k *The hairy proceſſes, called* Proceſſus ciliares.
l *The impreſſion of the Grapy coat where it departeth from the thick coat.*
m *The horny coat, a part of the thick coat.*
n n *The fat betwixt the Muſcles.*
o *The Optick Nerve.*
p *The* Dura meninx.
q *The* Pia Mater, *or thin* Meninx.
r r *The Muſcles.*

The explication of the other 19. Fig. together.
a 2 4 8 *The Optick Nerve.*
b 2 4 *The thin* Meninx *cloathing the Nerve.*
c 2 3 *The thick* Meninx *cloathing the Nerve.*
d 8 *The poſterior part of the horny coat.*
e 8 *The coat called* Retina *gathered together on an heap*
f 2 3 *The Rain-bow of the Eye.*
g 2 3 *The leſſer circle of the Eye, or the* Pupilla.
h 2 3 *Veſſels diſperſed through the* Dura meninx.
i 3 6 *The Grapy coat, but* i *in* Fig. 3. *ſheweth how the Veſſels do join the hard Membrane with the Grapy coat.*
k 6 *The horny or hard Membrane turned over.*
l l 3 4 *Certain fibers and ſtrings of Veſſels, whereby the Grapy coat is tied to the Horny.*
m m 4 5 *The impreſſion of the Grapy coat where it recedeth or departeth from the horny coat.*
n n 4 5 6 7 *The* Pupilla, *or Apple of the Eye.*
o o 7 *The ciliar or hairy proceſſes.*
p 7 *The beginning of the Grapy coat made of a thin Membrane dilated, but* p *in* Fig. 17. *ſheweth the Ciliar proceſſes ſprinkled through the fore-part of the Glaſſie humour,*
r 9 *The*

The Figure of the Eye.



19 The boſom or depreſſion of the Glaſſie humour receiving the Cryſtalline. ſ 12 15 *The bredth of the Coat of the Cryſtalline.* t 12 13 14 16 *The poſterior part of the Cryſtalline humour, which is ſpherical or round.* u 11 14 20 *The fore-part of the ſame Cryſtalline depreſſed.* x 10 20 *The amplitude of the Glaſſie humour.* y 10 16 19 *The amplitude of the watery humour.* z 19 *The place where the glaſſie humour is diſtinguiſhed from the watery, by the interpoſition of the* Hyaloides, *or Coat of the Glaſſie humour.* α 10 16 *The place where the grapy Coat ſwimmeth in the watery humour.* β 18 *The cavity or depreſſion of the Glaſſie humour which remaineth when the Cryſtalline is exempted or taken from it.* δ 19 *The cavity or depreſſion of the Watery humour made by the ſame means.*

Thirdly, It was convenient it ſhould be planted with infinite variety of colours for the preſervation of the ſight. For as the extreme colours corrupt and weaken the ſight, ſo the middle refreſh and preſerve it, more or leſs, as they are nearer or further remote from the extremes. It was fit it ſhould be ſoft, that ſo it might not hurt the Cryſtalline humour upon whoſe circumference it ends; and perforated in the part objected to it, leſt by its obſcurity it ſhould hinder the paſſage of the objects to the Cryſtalline, but rather that it might collect by its blackneſs, as a contrary, the great, and as it were, diffuſed variety of colours, no otherwiſe than we ſee the heat is ſtrengthened by the oppoſition of cold; ſome call this Coat *Choroides*, becauſe it is woven with many Veins and Arteries, like the Coat *Chorion* which involves the infant in the Womb.

Now follows the fourth Coat called *Amphibleſtroides* or *Reti-formis*, the Net-like Coat, becauſe proceeding from the Optick Nerve dilated into a Coat, it is woven like a Net with Veins and Arteries which it receives from the grapy Coat, both for the life and nouriſhment both of it ſelf, alſo of the Glaſſie humour which it encompaſſes on the back-part. The principal commodity of this Coat is, to perceive when the Cryſtalline humour ſhall be changed by objects, and to lead the viſive ſpirit inſtructed or furniſhed with the faculty of Seeing, by the mediation of the Glaſſie humour even to the Cryſtalline, being the principal inſtrument of Seeing. It is ſofter then any other Coat, leſt the touch of it ſhould offend that humour. Wherein thou wilt admire the ſingular order of Nature, which as in other things it paſſes not from one extreme to another, unleſs by a *Medium*; ſo here it hath not fitted the hard horny Coat to the ſoft humours, but by interpoſition of divers *media* of a middle conſiſtence. For thus, after the harder Coats *Adnata* and *Cornea*, it hath placed the grapy Coat; by ſo much ſofter than theſe two, as the Net-like Coat is ſofter than it, that thus it might paſs from extreme to extreme, as it were, by theſe degrees of hardneſs and ſoftneſs.

4. *Amphibleſtroides* or *Reti-formis*, Net-like Coat.

An Anatomical Axiom.

The fifth and laſt Coat is called *Arachnoides*, becauſe it is of the conſiſtence of a Spiders Web. And we may well reſemble this Coat to that skin of an Onion which exceeds the other in clearneſs, whiteneſs, and thinneſs. This *Araneoſa* or Cobweb-like Coat encompaſſes the Cryſtalline humour on the fore-ſide, peradventure that ſo it might defend it, as the chief inſtrument of Seeing, if the other humours ſhould at any time be hurt. It hath its original from the excrementitious humidity of the Cryſtalline humour, hardned into that Coat by the coldneſs of the adjacent part; abſolutely like the thin skin which encompaſſes the white of an Egg.

5. *Arachnoides, ſive Araneoſa*, the Cobweb Coat.

The firſt humour of the Eye is called *Aqueus*, or Wateriſh, from the ſimilitude of Water; it is ſeated between the tranſparent part of the horny Coat, the portion of the Cryſtalline humour lying towards the Apple of the Eye, and that reflection of the grapy Coat which comes from the *Iris* to the circumference of the Cryſtalline humour, that filling the empty ſpace it may diſtend the *Cornea*, and ſo hinder the falling thereof upon the Cryſtalline which would ſpoil the ſight; as alſo that by its moiſture it might hinder the drying of the Cryſtalline humour. Peradventure it is made of the whayiſh humour ſweating out of the Veſſels of the Coats, having their orifices for the moſt part in that place where this wateriſh humour reſides. The ſecond humour and middlemoſt in ſituation is called the Cryſtalline, becauſe it imitates Cryſtal in the brightneſs and colour; if ſo be, that we may attribute any colour to it. For indeed it was fit, that none of the three humours ſhould be tinctured with any colour, as thoſe which would be the inſtruments of Sight, leſt they might beguile us in ſeeing, as red and green ſpectacles do; for, that is true which we have read written by the Philoſopher, That the ſubject or matter, appointed for the reception of any form, ſhould want all impreſſion thereof. Hence Nature hath created a formleſs Matter, the humours of the Eyes without colours, Wax without any Figure, the Mind without any particular knowledge of any thing, that ſo they might be able to receive all manner of Forms. The figure of the Cryſtalline humour is round, yet ſomewhat flatted on the fore-ſide, but yet more flatted behind, that ſo the objects might be the better retained in that, as it were plain figure, and that they might not fly back as from a Globe, or round body, in which they could make but ſhort ſtay; leſt it might be eaſily moved from its place by the force of any thing falling or hitting againſt it, becauſe that body which is exactly round touches not a plain body, but onely in a point or prick. Half this humour ſwims in the Glaſſie humour, that ſo it may be nouriſhed from it by tranſpoſition of matter; or rather (ſeeing it is encompaſſed on every ſide with the fifth Coat, that the matter cannot eaſily be ſent from the one into the other) by the benefit of the Veſſels produced even unto it as well by the Net-like Coat as by the Grapy; but it is filled with a bright ſpirit on the fore-part, which lies next to the wateriſh humour, and the ſpace of the Apple of the Eye.

The three humours of the Eye.

1. *Aqueus*, or Watery.

2. *Cryſtallinus*, or Cryſtalline.

A Philoſophical Axiom.

Of which thing this is an argument, that as long as a man remains alive, we ſee the Eye every way full and ſwollen, but lank and wrinkled when he is dead; beſides alſo, one of the Eyes being ſhut, the *Pupilla* of the other is dilated by the ſpirit compelled to fly thither. And alſo for the ſame cauſe the horny Coat is wrinkled in very old men, and the *Pupilla* is ſtraitned by the wrinkles ſubliding into themſelves, which is the cauſe that they ſee little or not at all; for by Age and ſucceſs of Time the humour is conſumed by little and little, the implanted ſpirit vaniſhes away, and ſmaller quantity of ſpirits flow from the Brain, as from a Fountain which is alſo exhauſted. The

Gal. cap. 5. lib. 10. de uſu Part.

horny Coat at his original, that is, in the parts next the *Iris*, ſeemeth to be very nigh the Cryſtalline humour, becauſe all the Coats in that place mutually cohere as touching one another; but as it runs further out to the *Pupilla*, ſo it is further diſtant from the Cryſtalline. Which you may eaſily perceive by Anatomical diſſection, and the operation of touching or taking away a Catarrhact: for whereas a Catarrhact is ſeated between the horny Coat and Cryſtalline humour, the needle thruſt in, is carried about upwards, downwards, and on every ſide through a large and free ſpace, neither touching the horny Coat nor Cryſtalline humour, by reaſon theſe bodies are ſevered by a good diſtance filled with ſpirit and a thin humour. The uſe of it is, that it may be like a Looking-glaſs to the faculty of Seeing carried thither with the viſive ſpirit.

In what place a Catarrhact or a Suffuſion breeds.

3. *Vitreus ſeu Albugineus*, that is Glaſſie, or like the white of an Egg.

The third and laſt humour is the *Vitreus*, the Glaſſie, or rather Albugineous humour; called ſo, becauſe it is like molten Glaſs, or the white of an Egg. It is ſeated in the hind-part of the Cryſtalline humour, that ſo it may in ſome ſort break the violence of the ſpirit flowing from the Brain into the Cryſtalline humour, no otherwiſe than the watery humour is placed on the fore-ſide of the Cryſtalline to hinder the violence of the light and colours entering that way. This Glaſſie humour is nouriſhed by the Net-like Coat.

The Veins of the Eye.

We have formerly ſpoken ſufficiently of the Nerves of the Eye: Wherefore it remains that we ſpeak of the Veins. Some of theſe are internal, carried thither with the Coats of the Veſſels of the Brain; otherſome external ſtretched over the external parts of the Eye, as the Muſcles and Coat *Adnata*; and by theſe Veins inflammations and redneſs often happen in the external parts of the Eye: for which the *Vena pupis* muſt be opened, and Cupping-glaſſes and Horns muſt be applied to the nape of the Neck and ſhoulders: as, in the internal inflammations of the Eye, the Cephalick-Vein muſt be opened to avert and evacuate the morbifick humour.

What Veins may be opened in what inflammations of the Eyes.

CHAP. VII.

Of the Noſe.

THe Noſe is called in Greek *Ris*, becauſe the excrements of the Brain flow forth by this paſſage; thou maiſt underſtand it hath divers ſubſtances by compoſition. The quantity, figure and ſite are ſufficiently known to all. But it is compoſed of the Skin and Muſcles, Bones, Griſles, a Membrane or Coat-nerves, Veins, and Arteries. The Skin and Bones, both contained and containing, have formerly been explained, as alſo the Nerves, Veins, and Arteries. The Griſles of the Noſe are ſix in number; the firſt is double, ſeparating both the noſtrils in the top of the Noſe extended even to the Bone *Ethmoides*. The ſecond lies under the former. The third and fourth are continued to the two outward Bones of the Noſe. The fifth and ſixth being very ſlender, and deſcending on both ſides of the Noſe, make the wings or moveable parts thereof. Therefore the uſe of theſe Griſles is, that the Noſe moveable about the end thereof, ſhould be leſs obnoxious to external injuries, as fractures, and bruiſes; and beſides, more fit for drawing the air in, and expelling it forth in breathing. For Nature for this purpoſe hath beſtowed four Muſcles upon the Noſe, on each ſide two, one within and another without.

The Griſles of the Noſe.

The Muſcles thereof.

The External taketh its original from the Cheek, and deſcending obliquely from thence, and after ſome ſort annexed to that which opens the upper lip, is terminated into the wing of the Noſe, which it dilates.

The Internal going on the inner ſide from the Jaw-bone, ends at the beginning of the Griſles that make the Wings, that ſo it may contract them. The Coat which inwardly inveſts the Noſtrils and their paſſages, is produced by the Sive-like Bones from the *Craſſa meninx*, as the inner Coat of the Palat, Throttle, Weazon, Gullet, and inner Ventricle; that it is no marvail, if the affects of ſuch parts be quickly communicated with the Brain. This ſame Coat on each ſide receives a portion of a Nerve from the third Conjugation, through the hole which deſcends to the Noſe by the great corner of the Eye.

The temper, action, and uſe.

The Noſe in all the parts thereof is of a cold and dry temper. The action and profit thereof is to carry the air, and oft-times ſmells to the mamillary proceſſes, and from thence to the four Ventricles of the Brain, for the reaſons formerly ſhewed. But becauſe the mammillary proceſſes being the paſſages of the Air and Smells are double, and for that one of theſe may be obſtructed without the other, therefore Nature hath alſo diſtinguiſhed the paſſage of the Noſe with a griſly partition put between, that when the one is obſtructed, the air by the other may enter into the Brain for the generation and preſervation of the animal ſpirit. The two holes of the Noſe at the firſt aſcend upwards, and then downwards into the Mouth, by a crooked paſſage, leſt the cold air or duſt ſhould be carried into the Lungs. But the Noſe was parted into two paſſages, as we ſee, not onely for the forementioned cauſe, but alſo for helping the reſpiration and vindicating the Smell from external injuries; and laſtly, for the ornament of the Face.

Why the Noſe was parted in two.

CHAP. VIII.

Of the Muſcles of the Face.

Their number

NOw we muſt deſcribe the Muſcles of the Face pertaining as well to the Lips as to the lower Jaw. Theſe are 18 in number, on each ſide nine, that is, four of the Lips, two of the upper, and as many of the lower. But there belong five to the lower Jaw. The firſt of the upper Lip being the longer and narrower, ariſing from the Yoke-bone, deſcends by the corner

ner of the mouth to the lower lip, that ſo it may bring it to the upper lip, and by that means ſhut the mouth. The other being ſhorter and broader, paſſing forth of the hollowneſs of the cheek, or upper Jaw (by which a portion of the nerves of the third conjugation deſcends to theſe two Muſcles, and other parts of the face) ends in the upper part of the ſame upper lip, which it compoſes together with the fleſhy pannicle and skin, and it opens it by turning up the exterior Fibers towards the Noſe, and ſhuts it by drawing the internal inwards towards the Teeth.

The firſt of the lower lip being the longer and ſlenderer, entering out of that region which is between the external perforation of the upper Jaw (through which, on the inner part of the ſame, a Nerve paſſeth forth to the ſame Muſcles) and the Muſcle *Maſſeter* (of which hereafter,) then aſcending upwards by the corner of the Mouth, it ends in the upper lip, that ſo it may draw it to the lower.

The other broader and ſhorter, begins at the lower part of the chin, and the hollowneſs thereof, and ends at the lower lip which it makes, opening it within and without, by its internal and external Fibers, as we alſo ſaid of its oppoſite. And that I may ſpeak in a word, Nature hath framed three ſorts of Muſcles for the motion of the Mouth; of which ſome open the Mouth, others ſhut it, and other ſome wreſt it and draw it awry: but you muſt note, that when the Muſcles of one kind jointly perform their functions (as the two upper which we deſcribed in the firſt place, on each ſide one, which draw the lower lip to the upper, and the Muſcles oppoſite to them) they make a right or ſtreight motion; but when either of them moves ſeverally, it moves obliquely, as when we draw our mouth aſide. But theſe Muſcles are ſo faſtned and fixed to the skin, that they cannot be ſeparated; ſo that it is no great matter whether you call it a muſculous skin, or a skinny Muſcle: (Which alſo takes place in the palms of the hands, and ſoles of the feet:) but theſe Muſcles move the lips, the upper Jaw being not moved at all.

CHAP. IX.

Of the Muſcles of the lower Jaw.

WE have ſaid theſe Muſcles are five in number, that is, four which ſhut it, and one which opens it, and theſe are alike on both ſides. The firſt and greater of theſe four Muſcles which ſhut the Jaw is called *Crotophita* or Temporal Muſcle: it ariſes from the ſides of the forehead, and *Bregma*-bones, and adhering to the ſame and the ſtony-bone, it deſcends under the yoke-bone, from whence it inſerts it ſelf to the proceſs of the lower Jaw, which the *Greeks* call *Corone*, that it may draw it directly to the upper, ſo to ſhut the Mouth. Their number. The Temporal Muſcle.

But you muſt note that this Muſcle is tendinous even to his Belly, and that it fills and makes both the Temples. It is more ſubject to deadly wounds than the reſt, by reaſon of the multitude of Nerves diſperſed over the ſubſtance thereof, which becauſe they are near their original, that is, the Brain, they infer the danger of ſudden death by a Convulſion, which uſually follows the affects of this Muſcle, but alſo in like manner it cauſes a Fever, the Phrenſie and *Coma*. Why the wounds of the Temporal Muſcle are deadly.

The Figure of the chief Muſcles of the Face.

FIG. II.

A *The Muſcle of the Fore-head and the right Fibers thereof.*
B *The Temporal Muſcle.*
α β γ *His ſemicircular original.*
D *The Muſcle of the upper lip.*
G *The Yoke-bone under which the Temporal Muſcles paſs.*
I *The Maſſeter, or Grinding Muſcle.*
K *The upper Griſle of the Noſe.*
M *A Muſcle forming the Cheeks.*
N *The Muſcle of the lower lip.*
O *A part of the fifth Muſcle of the lower Jaw called* Digaſtricus, *that is, double-bellied.*
Q R *The firſt Muſcle of the Bone* Hyoides, *growing unto the rough Artery.*
S *The ſecond Muſcle of the Bone* Hyoides *under the Chin.* T *The third Muſcle of the Bone* Hyoides *ſtretched to the Jaw.* T K *The ſeventh Muſcle of the Head, and his inſertion at* T. V V *The two venters of the fourth Muſcle of the Bone* Hyoides. Φ *The place where the Veſſels paſs which go to the Head, and the Nerves which are ſent to the Arm.*

Therefore that it ſhould be leſs ſubject or obvious to external injuries, Nature hath, as it were, made it a retiring place in the Bone, and fortified it with a Wall of Bone raiſed ſomewhat higher about it. The other Muſcle almoſt equal to the former in bigneſs, being called the *Maſſeter*, or Grinding Muſcle makes the Cheek; it deſcends from the loweſt part of the greateſt Bone of the Orb (which bends it ſelf, as it were, back, that it may make part of the Yoke-bone) and inſerts it ſelf into the lower Jaw, from the corner thereof to the end of the root of the proceſs *Corone*, that ſo it may draw this Jaw forward and backward, and move it like a Hand-Mill. The *Maſſeter* or Grinding Muſcle.

Wherefore Nature hath compoſed it of two ſorts of Fibers, of the which ſome from the Neck (the Cheek in that place under the Eyes ſtanding ſomewhat out like an Apple ariſing from the concourſe of the greater Bones of the Orb and upper Jaw) deſcend obliquely to the corner and

hinder part of the lower Jaw, that it may move it forwards. Otherſome ariſe from the lower part of the ſame Yoke-bone, and deſcending obliquely interſect the former Fibers after the ſimilitude of the letter X, and inſert themſelves into the ſame lower Jaw at the roots of the proceſs *Corone*, that ſo they might draw it back: Truly by reaſon of theſe contrary motions, it is likely this Muſcle was called the *Maſſeter*, or Grinder.

The Round Muſcle.

The third which is the round Muſcle, ariſes from all the Gums of the upper Jaw, and is inſerted into all the Gums of the lower, inveſting the ſides of all the Mouth with the Coat, with which it is covered on the inſide, being otherwiſe covered on the outſide with more fat then any other Muſcle. The action thereof is, not onely to draw the lower Jaw to the upper, but alſo as with a ſhovel to bring the meat diſperſed over all the Mouth under the Teeth, no otherwiſe than the Tongue draws it in.

The leſſer Muſcle of the lower Jaw.

The fourth being ſhorter and leſs than the reſt ariſing from all the hollowneſs of the winged proceſs of the Wedge-bone, is inſerted within into the broadeſt part of the lower Jaw, that ſo in like manner it may draw the ſame to the upper. This is the Muſcle through whoſe occaſion we ſaid this lower Jaw is ſometimes diſlocated.

The Figure of the Muſcles of the lower Jaw.

FIG. III.

A *A hole in the fore-head bone in the brim of the ſeat of the Eye, ſending a ſmall Nerve of the third pair to the Muſcles of the fore-head and the upper eye-brow.*
B *The temporal Muſcle.*

The fifth and laſt Muſcle.

The fifth and laſt Muſcle of the lower Jaw iſrom the proceſs *Styloides* of the Stony bone, aſcends to the fore-part of the Chin, near to the connexon of the two bones of this Jaw, to draw this Jaw downwards from the upper in opening the Mouth. This Muſcle is ſlender and tendinous in the midſt, that ſo it might be ſtronger, but it is fleſhy at the ends. All theſe Muſcles were made by the ſingular Providence of Nature, and engraffed into this part for the performance of many uſes and actions, as biting aſunder, chawing, grinding and ſevering the meat into ſmall particles, which the tongue by a various and harmleſs motion puts under the teeth. Thus much I thought good to ſay of the parts of the Face, as well containing as contained.

The uſe of theſe mentioned Muſcles.

CHAP. X.

Of the Ears and Parotides, *or Kernels of the Ears.*

The nature and compoſition of the ears.

THe Ears are the Organs of the ſenſe of Hearing. They are compoſed of the skin, a little fleſh, a griſle, veins, arteries, and nerves. They may be bended or folded in without harm, becauſe being griſly, they eaſily yield and give way; but they would not do ſo if they ſhould be bony, but would rather break. That lap at which they hang Pendants and Jewels, is by the Ancients called *Fibra*, but the upper part *Pinna*. They have been framed by the Providence of Nature into two twining paſſages like a Snails ſhell, which as they come nearer to the *foramen cæcum* or blind hole, are the more ſtraitned, that ſo they might the better gather the air into them, and conceive the differences of ſounds and voices, and by little and little lead them to the Membrane.

What the *Fibra* and *Pinna* are.

The figure and reaſon thereof.

This Membrane which is indifferently hard, hath grown up from the Nerves of the fifth conjugation, which they call the Auditory. But they were made thus into crooked windings, leſt the ſounds ruſhing in too violently ſhould hurt the ſenſe of Hearing. Yet for all this, we oft find it troubled and hurt by the noiſe of Thunder, Guns, and Bells. Otherwiſe alſo, leſt that the air too ſuddenly entering, ſhould by its qualities, as Cold, cauſe ſome harm; and alſo that little creeping things and other extraneous Bodies, as Fleas and the like, ſhould be ſtaid in theſe windings and turnings of the ways, the glutinous thickneſs of the cholerick Excrement, or Ear-wax, hereunto alſo conducing, which the Brain purges and ſends forth into this part, that is, the auditory paſſage framed into theſe intricate Mæanders.

For what uſe the Ear-wax ſerves.

For what uſe the membrane ſtretched under the Auditory paſſage ſerves.

What ſound is

But that we may underſtand how the Hearing is made, we muſt know the ſtructure of the Organ, or Inſtrument thereof. The Membrane which we formerly mentioned to conſiſt of the Auditory Nerve, is ſtretched in the inſide over the Auditory paſſage, like as the head of a Drum. For it is ſtretched and extended with the Air, or Auditory Spirit implanted there, and ſhut up in the cavity of the mamillary proceſs and *foramen cæcum*, that ſmitten upon by the touch of the external air entering in, it may receive the object, that is, the ſound, which is nothing elſe than a certain quality ariſing from the Air, beaten or moved by the colliſion and conflict of one or more bodies.

Such a colliſion is ſpred over the Air, as the Water which by the gliding touch of a Stone produces many circles and rings, one as it were riſing from another. So in Rivulets running in a narrow Channel, the Water ſtrucken, and as it were, beaten back in its courſe againſt broken, craggy and ſteep Rocks,

Rocks, wheels about into many turnings: this colliſion of the beaten air flying back divers ways from arched and hollow-roofed places, as Dens, Ciſterns, Wells, thick Woods, and the like, yields and produces a double ſound, and this reduplication is called an *Echo*. Wherefore the Hearing is thus made by the air, as a *medium*; but this air is two-fold, that is, External and Internal. The cauſe of an echo.

The Figure of the Ears and Bones of the Auditory paſſage.

Tab. 10. *Sheweth the Ears and the divers internal parts thereof.*

Fig.1. *Sheweth the whole external Ear, with a part of the Temple-bone.*

Fig.2. *Sheweth the left Bone of the Temple divided in the midſt by the inſtrument of Hearing, whereabout on either ſide there are certain paſſages here particularly deſcribed.*

Fig. 3. and 4. *Sheweth the three little bones.*

Fig.5. *Sheweth a portion of the bone of the Temples which is ſeen near the hole of Hearing divided through the midſt, whereby the Nerves, Bones, and Membranes may appear, as* Veſalius *of them conceiveth.*

Fig.6. *Sheweth the Veſſels, Membranes, Bones and Holes of the Organ of Hearing, as* Platerus *hath deſcribed them.*

Fig. 7. and 8. *Sheweth the little Bones of the Hearing of a Man and of a Calf, both joined and ſeparated.*

Fig.9. *Sheweth the Muſcle found out by* Aquapendens.

For the particular Declaration ſee *Dr. Crooks Anatomy*, pag.577.

The exteriour is that which encompaſſes us, but the interiour is that which is ſhut up in the cavity of the mamillary proceſs and *foramen cæcum*, which truly is not pure and ſole air, but tempered and mixed with the auditory ſpirit. Thence proceeds the noiſe or beating of the Ears when vapors are there mixed with the air in ſtead of the ſpirits, whereby their motion is perturbed and confuſed. But neither do theſe ſuffice for hearing; for Nature for the more exact diſtinction of ſounds hath alſo made the little bones, of which one is called the *Incus* or Anvil, another the *Malleolus* or hammer, the third the *Stapes* or Stirrop, becauſe the ſhape thereof reſembles a *German* Stirrop. Alſo it may be called *Deltoides*, becauſe it is made in the ſhape of the Greek Letter Δ. The three bones of the auditory paſſage.

They are placed behind the Membrane; wherefore the Anvil and Hammer moved by the force of the entrance of the external air, and beating thereof againſt that Membrane, they more diſtinctly expreſs the difference of ſounds, as ſtrings ſtretched within under the head of a Drum. As for example; Theſe bones being more gently moved repreſent a low ſound to the common ſenſe and faculty of Hearing, but being moved more vehemently and violently, they preſent a quick and great ſound. To conclude, according to their diverſe agitation, they produce divers and different ſounds. Their uſe. Whence the difference of ſounds.

The Glandules ſhould follow the Ears in the order of Anatomy, as well thoſe which are called the emunctories of the Brain, that is, the *Parotides*, (which are placed, as it were, at the lower part of the Ears) as theſe which lie under the lower Jaw, the Muſcles of the Bone *Hyoides*, and the Tongue, in which the *Scrophulæ*, and other ſuch cold abſceſſes breed. It ſhall here ſuffice to ſet down the uſe of all ſuch like Glandules.

Therefore the *Parotides* are framed in that place by Nature, to receive the virulent and malign matter ſent forth by the ſtrength of the Brain, by the Veins and Arteries ſpred over that place. The reſt ſerve to ſtrengthen the diviſion of the Veſſels, to moiſten the Ligaments and Membranes of the Jaw, leſt they ſhould be dried by their continual motion. Their other conditions and uſes are formerly handled in our firſt Book of Anatomy.

CHAP.

CHAP. XI.

Of the Bone Hyoides, *and the Muſcles thereof.*

The reaſon of the name. THe ſubſtance of the Bone *Hyoides* is the ſame with that of other Bones. The figure thereof imitates the Greek Letter υ from whence it took the name, (as alſo the name ὑψιλοειδὲς; And from the Letter λ it is in like ſort called λαμβδοειδὲς; by ſome it is ſtiled *os Gutturis*, and *os Linguæ*, that is, the Throat-bone and Tongue-bone.

The compoſition. The compoſition thereof conſiſts of many Bones joined into one by the interpoſition of Griſles.

The ſite. This Bone is bigger in Beaſts and compoſed of more Bones, and that not onely by the intercourſe of Griſles, but alſo of Ligaments. It is ſeated with its baſis (being gibbous on the fore-part for conſtancy, and arched on the inſide that it might receive and contain the root of the Tongue) upon the upper part of that Griſle of the Throttle, which is called *Scutiformis*, or Shield-like, (for this ſeems to prop it up by the ſtrength of two proceſſes riſing at the baſis thereof) and the root of the Tongue. From this baſis it ſends forth two horns to the ſides of the Tongue on each ſide one, which in men are tied to the Appendix *Styloides* by Ligaments ſent from it ſelf. Contrary than it is in Beaſts, who have it of many Bones; united, as we ſaid,, by the intercouſe of Ligaments even to the

The temper and uſe. root of the *Styloides*. Wherefore this Bone hath connexion with the fore-mentioned parts, and other hereafter to be mentioned. It hath the ſame temper as other bones have. The uſe of it is, to miniſter Ligaments to certain Muſcles of the Tongue, and inſertion as well to the two foremoſt and upper Muſcles of the Throttle, as to its own, of which we will now treat.

The Muſcles of the bone *Hyoides*. The Muſcles of the Bone *Hyoides*, according to the opinion of ſome, are eight, one each ſide four; of which there be two, one of which *Galen* refers to the common Muſcles of the *Larinx* or Throttle; and the other to thoſe which move the Shoulder-blade upwards. Howſoever it be, the firſt of the four before-mentioned ariſes from the Appendix *Styloides*, and paſſing over the nervous ſubſtance of the Muſcle opening the lower Jaw, is inſerted into the horns of the Bone *Hyoides*. This Muſcle is very thin, yet ſomewhat broad, the which in that reſpect may eaſily be cut, unleſs you have a care in ſeparating the Muſcle which opens the lower Chap. The ſecond aſcends obliquely from the upper part of the Shoulder-blade near the production thereof called *Coracoides*, to the beginnings of the horns of the ſaid Bone *Hyoides*. This is round and nervous in the midſt that ſo it might be the ſtronger, as that is which we formerly ſaid opens the lower Jaw; and it is referred by *Galen* amongſt thoſe which move the Shoulder-blade upwards. The third ariſes from the upper part of the *Sternon*, and is inſerted at the root and baſis of the Bone *Hyoides*; yet *Galen* refers it to the common Muſcles of the *Larinx*; whoſe opinion takes place rather in Beaſts than in Man, ſeeing in Man this Muſcle cannot be found either to proceed, or be inſerted into the Throttle, as it is in Beaſts. The

The action of theſe Muſcles. fourth and laſt deſcends within from the Chin to the root of the Bone *Hyoides*. The firſt of theſe Muſcles with its Companion or Partner, moves the Bone *Hyoides* upwards, the ſecond downwards, the third backwards, and the fourth forwards. I would declare whence theſe Muſcles have their Veſſels, had I not abundantly ſatisfied that thing, when I treated of the diſtribution of the Nerves, Veins and Arteries.

CHAP. XII.

Of the Tongue.

What kind of fleſh the Tongue hath. THe Tongue is of a fleſhy, rare, looſe, and ſoft ſubſtance; it enjoys fleſh of a different kind from the reſt of the fleſh, as chiefly appears when you cut it from the firſt original of the Muſcles thereof; which thing hath moved ſome, that they have made a fourth kind of fleſh proper to the Tongue and different from the reſt, *viz.* the Fibrous Muſculous, and that of the Bowels.

The quantity. The quantity thereof is ſuch, that it may be contained in the Mouth, and eaſily moved to each part

The figure. thereof. The Figure of it is triangular, which it rather expreſſes in the baſis, which is at the root of the Bone *Hyoides*, than in its point, or fore-part, where from a triangle it becomes more dilated.

Compoſure. It is compoſed of a Membrane (which it hath from that which lines all the inſide of the Mouth,)

The Nerves. Muſcles four, Nerves two on each ſide, the one whereof is ſent from the third conjugation, into the coat thereof; the other, from the ſeventh is ſent into the muſculous ſubſtance even to the end thereof for motions ſake; ſo that thoſe ſenſifick Nerves from the third conjugation, onely give to judge of Taſtes, compoſe the Coat, and touch or enter not the fleſh. Beſides, it is compoſed of Veins and Arteries on each ſide one, which it receives from the external Jugular and *Carotides*, running manifeſtly to the end thereof on the lower ſide, that ſo they might be eaſily opened in the diſeaſes of the Mouth and Throttle; they commonly term theſe the *Venæ nigræ*, or black Veins.

The Muſcles of the Tongue. The Muſcles of the Tongue are abſolutely ten, on each ſide five. The firſt narrow at the beginning, and broader at the end, deſcends into the upper ſide of the Tongue from the Appendix *Styloides*, and together with its Co-partner draws it upwards. The ſecond hath its original within from the lower Jaw, about the region of the Grinding Teeth, and is inſerted into the lower ſide of the Tongue, the which with its Partner draws it downward. The third proceeds from the inner part of the Chin, and goes to the root of the Tongue, that when need requires, it may put it forth of the Mouth. The fourth, the greateſt and broadeſt of them all, compoſed of all ſorts of Fibers, paſſeth forth from the baſis of the bone *Hyoides*, and ends at the lower part of the Tongue, which with its Companion plucks it back into the mouth. The fifth and laſt moſt uſually ariſes from the upper part of the horns of the bone *Hyoides*, and goes to the roots of the Tongue between the two firſt, that

it

it may move it to the ſides of the Mouth. The temper thereof, as of all other fleſh, is hot and moiſt. The firſt action and commodity thereof is, to be the Organ of the ſenſe of Taſting, wherefore it was made fungous and ſpongy, that by reaſon of the rarity of it, it might more eaſily admit the taſtes conjoined with the ſpettle as a vehicle, Another to be an inſtrument to diſtinguiſh the voice by articulate ſpeech, for which it was made moveable into each part of the Mouth. The third is to be a help to chaw and ſwallow the meat. For which cauſe it is like a ſcoop or diſh with which we throw back the Corn into the Mill, which hath ſcaped grinding. And becauſe, when the Tongue is drie, it is leſs nimble and quick to perform its motions, as appears by thoſe which can ſcarce ſpeak by reaſon of thirſt, or a burning Fever: therefore Nature hath placed very ſpongy glandules at the roots thereof, on each ſide one, which like ſponges ſuck and receive, both from the Brain and other places, a wateriſh and ſpettely humour, with which they humect and make more glib, not onely the Tongue, but alſo the other parts of the Mouth, as the Throat and Jaws; theſe glandules are called the *Tonſillæ*, or Almonds of the Throat.

The temper, action, and manifold uſe of the tongue.

The uſe of the glandules placed at the roots of the tongue.

CHAP. XIII.

Of the Mouth.

THE Mouth is that capacity, which, bounded with the Cheeks and Lips contains within its Precincts the Teeth, Tongue, and the beginning of the Throttle and Gullet. Therefore the uſe of the Mouth is to contain the Tongue, and ſerve it in the fitter performance of its actions; and although many parts hereof have been formerly handled, as the Lips, Teeth, Jaws, Tongue, Almonds, and paſſages of the Palat coming from the Noſe, yet it remains that we declare what the Palate, the *Gargareon* or Uvula, the *Pharinx*, and *fauces* or Chops, are. The Palat (or, as it is commonly called, the Roof of the Mouth) is nothing elſe but the upper part of the Mouth bounded with the Teeth, Gums, and upper Jaw. In which place the Coat common to the whole Mouth, is made rough with divers wrinkles, that the meats put up and down between the Tongue and the Palat might be broken and chawed more eaſily by that inequality and roughneſs. If any would find find the Nerves, which deſcend into the Palate from the fourth Conjugation, let him ſeparate that Coat, and caſt it from the fore to the hind-part of the Mouth; for ſo he ſhall find them at the ſides and hind-parts of the bones of the Palate, which incompaſs the Palat, and at the beginning of the inner holes of the Mouth, which deſcend from the Noſe, and region of the productions of the Wedg-bone called the Saddle. Theſe holes or paſſages are open, that we may breath the better when we ſleep, and that when the Noſe is not well, the excrements which ſeek their paſſage by it, may be eaſilier drawn away by the Mouth. This ſame Coat is woven with nervous Fibers, that like the Tongue it may judge of Taſtes; theſe Fibers compoſe a Coat that hath a middle conſiſtence betwixt ſoft and hard. For if it ſhould have been any harder, like a Bone or Griſle, it would have been without ſenſe; but if ſofter, hard, acid and ſharp meats would have hurt it.

What it is.

The uſe.

What the Palat is.

The Nerves thereof.

Why the holes of the Palat are open.

What kind of Coat the Palat hath.

CHAP. XIV.

Of the Gargareon, *or Uvula.*

BY the *Gargareon* we underſtand a fleſhy and ſpongy body, in ſhape like a Pine-Apple, hanging directly down at the further end of the Palat and baſis of the bone *Ethmoides*, where the two holes of the Palat come from the Noſe, above the entrance of the Throttle. This little body is ſituate in this place to break the violence of the air drawn in by breathing and that by delay it might in ſome ſort temper and mitigate it by the warmneſs of the Mouth. Beſides, that it might be as it were the *Plectrum*, or quill of the Voice, ſo to diffuſe the fuliginous vapour ſent forth in breathing, that it may be diſperſed over all the mouth, that reſounding from thence it may be articulate, and by the motion of the Tongue diſtinguiſhed and formed into a certain Voice. Which uſe is not ſmall; when we ſee by experience, that ſuch as have this particle cut away, or eaten, or corrupted by any accident, have not onely their Voice vitiated and depraved, but ſpeak ill-favouredly, and, as they ſay, through the Noſe; and beſides, in proceſs of time they fall into a Conſumption by reaſon of the cold air paſſing down before it be qualified. This ſame patricle is alſo a means to hinder the duſt from flying down through the Weazon into the Lungs. By the *Pharinx* and *Fauces* is meant the inner and back-part of the mouth, ſet or placed before the entrance of the Throttle and Gullet; being ſo called, becauſe that place is narrow and ſtrait, that as it were by theſe ſtraits, the air drawn in by the mouth might be forced down by the Throttle, and the meat into the Gullet.

What the *Gargareon* or Uvula is.

The ſite and manifold uſe thereof.

The diſcommodities that enſue the loſs of the Uvula.

What the *Pharinx* and *Fauces* are.

CHAP. XV.

Of the Larinx, *or Throttle.*

FIrſt we muſt ſhew what is meant by the *Larinx* and Throttle, then proſecute the other conditions of it after our accuſtomed manner. Therefore by the *Larinx* we underſtand nothing elſe in this place than the Head and extremity of the rough Artery, or Weazon, which comes nearer to griſly ſubſtance, than to any other. The quantity thereof is ſufficiently large, yet

What is meant by the *Larinx*.

The magnitude, figure, and compoſure.

yet diverſe according to the diverſity of bodies. It reſembles in ſhape the head of a *German* pipe. The compoſure of it conſiſts of 18 Muſcles, on each ſide nine, which as they are like in quantity, ſo alſo in ſtrength and action; of three Griſles, Veins, Arteries, and Nerves, as we ſhewed when we ſpoke of the diſtribution of the Veſſels; as alſo of a double Coat, the one external, the other internal, as we ſhewed when we ſpoke of the Weazon.

The deſcription of the three Griſles of the *Larinx*.

Theſe three Griſles are joined together by certain Ligaments and Muſcles; the foremoſt Griſle, which alſo is the greater, is called by the *Greeks* θυρεοειδὴς, in Latin commonly *Scutiformis*, that is ſhield-like, becauſe it reſembles a ſhield. The ſecond, being the hinder and middle in magnitude, wants a Name, wherefore it is called the *innominata*, or nameleſs Griſle. The laſt and leaſt, which notwithſtanding may be parted into two, ſo lies upon the edges of the other, that it reſembles the mouth of an Oil-pot, or a Pitcher, whereupon the *Greeks* call it *Arytenoides*.

Whence the infinite variety of Voices proceed.

Theſe Griſles thus fitted amongſt themſelves utter a diſtinct Voice, by the benefit of the *Epiglottis*, or After-tongne; and alſo of the Muſcles opening and ſhutting, dilating and compreſſing them, whence proceed infinite varieties of Voices. For thus when they are opened and dilated, they yield a heavy or dull ſound; when they are ſhut or drawn together, a quick or ſharp ſound; and to conclude, they make it infinite ways different according to the infinite variety of the dilatation, or conſtriction thereof.

The Muſcles of the *Larinx*.

Therefore, becauſe it was fit theſe Griſles ſhould be moveable, eſpecially the *Arytenoides* and *Thyroides*, Nature hath put to them on

Their number

each ſide nine Muſcles, of which three are common, and ſix proper. The firſt of the common lying hid under the third Muſcle of them that move the bone *Hyoides*, ariſes from the root of the ſame bone, and by an oblique deſcent inſerts it ſelf at the baſis of the ſhield-like Griſle, to dilate it upwards and downwards. The ſecond aſcends obliquely from the inner part of the *Sternon* according to the length of the Weazon (whence it is called *Bronchius*) to the bottom and ſides of the ſame ſhield-like Griſle, that it may open and dilate it with its wings. This Muſcle is ſeen from the firſt original thereof, even a great part of the way ſtraitly to cohere with the third Muſcle of the Bone *Hyoides*; therefore under each of the Muſcles there is a glandulous body ſpred about the fore and upper part of the Weazon, on that place where it applies it ſelf to the Throttle; this body although it reſemble

A notable Hiſtory.

a fleſhy ſubſtance, yet it is a glandule: which being pluckt away by a certain Emperick taking upon him to cure the Kings-evil, cauſed a defect of Voice on one ſide, becauſe he pulled away the recurrent Nerve lying upon the glandule as it goes to the Throttle, as *Galen* reports, *Lib. de Locis Affectis*. The third and laſt ariſes from the parts of the *Vertebraes* of the Neck lying tranſverſly upon the ſides of the Gullet, and ends at the wings and ſides at the ſhield-like Griſle, that it may tie it more ſtraitly to the ſecond Griſle. But theſe three are called common Muſcles, becauſe they take their original from ſome other place than the Throttle, that ſo they may be inſerted into ſome part thereof; for they are called the proper Muſcles which ariſe from the Throttle it ſelf, which we have ſaid to be ſix on each ſide: the firſt of which ariſing from the fore-part of the ſecond Griſle, makes a circle under the baſis of the ſhield-like Griſle; whileſt aſcending obliquely to the baſis thereof, it is afterwards inſerted in a part of it, ſo to ſtrengthen and dilate it. The ſecond in like manner ariſing from the ſecond Griſle, from that place where it adheres to the firſt, it runs obliquely croſſing the firſt to the inner and forepart of the Griſle *Thyroides* near to the baſis thereof, that it may join it to the ſecond. The third from the hind-baſis of the ſecond Griſle aſcends directly to the baſis of the third Griſle *Arytenoides*, that with the ſecond Muſcle it may open and ſhut it. The fourth aſcends from the ſides of the ſecond Griſle, near the original of the ſecond Muſcle, to the ſides of the *Arytenoides*, that with the ſecond Muſcle it may open and ſhut it. The fifth ariſes from the inner middle of the ſhield-griſle, and ends in the fore-part of the *Arytenoides* at the inſertion of the fourth Muſcle, that ſo it may preſs down the ſaid Griſle.

Whence the Muſcles of the Throttle have their Nerves.

The ſixth and laſt aſcends by the hind-baſis of the *Arytenoides* to the fore-baſis of the ſame, to preſs it down. But you muſt note that all ſuch Muſcles as ariſe from below upwards, receive branches from the recurrent, but eſpecially thoſe who open and ſhut the Griſle *Arytenoides*. But the ſite, temper, connexion, and uſe of the Throttle may eaſily be known by that we have ſaid before: Although it be a thing very full of difficulty to ſearch out and demonſtrate all the conditions of the organical parts, by reaſon of the diverſity of their compoſition. Wherefore henceforward concerning the ſubſtance, temper, and other circumſtances of ſuch parts as we ſhall omit, you may have recourſe to thoſe things which we have written in the Demonſtration of the ſimple and ſimilar parts, of which theſe organical are compoſed; as if any ſhould ask, of what temper the *Larinx* is, you ſhall anſwer, of a cold, dry, hot, and moiſt, becauſe it conſiſts both of

The *Epiglottis*, or After-Tongue.

a griſly and fleſhy ſubſtance. He which reckons up all the parts of the Mouth, muſt not omit that griſly and membranous body which ariſes from the roots of the Tongue, which that it might be more quick for motion, that is, whereby it might be more eaſily erected and depreſſed (for thoſe things which are more ſoft do continually ſlide away, but thoſe which are too hard cannot be bended) it was convenient it ſhould be neither too hard, nor too ſoft, that it might be erected whileſt we breath, but depreſſed when we ſwallow. It is a principal inſtrument of the Voice, for it cannot be well articulated unleſs the way were ſtrait. Therefore it ſtraitens that way, and the paſſage of the griſles of the Throttle, but eſpecially the *Arytenoides*; it is always moiſt by a certain Native and Inbred Humidity; wherefore, if it happen to be dried by a Fever, or any other like accident, the Speech is taken away. It is bound on both ſides by the common membrane of the Mouth to the ſides of the *Arytenoides* even to the back-part thereof, that ſo like a Cover it may open and ſhut the orifice of the Throttle, that none of the meat and drink in ſwallowing may

Of potable things ſomewhat always falls upon the Lungs.

fall into the Weazon, in ſuch abundance as may hinder the egreſs and regreſs of the air. For we muſt not think that this body doth ſo cloſely ſhut the orifice of the Throttle, but that ſome ſmall quantity of moiſture always runs down by the inner ſides, as the walls thereof, to moiſten the Lungs; otherwiſe *Eclegmaes* ſhould be of no uſe in the diſeaſes of the Cheſt. And becauſe that this little body is partaker of voluntary motion, therefore according to the opinion of ſome there-

there are four Muſcles beſtowed upon it, two which may open it, and two that ſhut it, on each ſide one. The opening Muſcles deſcend from the root of the bone *Hyoides*, and in their inſertion, growing into one, they are terminated in the root of this body, that is, the *Epiglottis* in the back part thereof. The ſhutting Muſcles (in thoſe Creatures where they are found) ariſe on the inſide between the Coat and Griſle thereof. Truly I could never obſerve and find theſe four Muſcles in a man, though I have diligently and earneſtly ſought for them, but I have always obſerved them in Beaſts. Therefore ſome have boldly affirmed that this little body in ſwallowing lies not upon the orifice of the Throttle, unleſs when it is preſſed down by the heavineſs of ſuch things as are to be ſwallowed; but that at all other times by reaſon of the continual breathing it ſtands upright, the Throttle being open. There remain as yet to be conſidered, two ſmall boſoms or cavities, or rather fiſſures which Nature hath hollowed in the very Throttle under the *Epiglottis*, on each ſide one, that if by chance any of the meat or drink ſhould fall, or ſlip aſide in the *Larinx*, it might be there ſtaid and retained. Beſide that, the Air too violently entering, ſhould be in ſome ſort broken by theſe clifts or chinks, no otherwiſe then the bloud and ſpirit entering into the heart through the *Auriculæ*, or Ears thereof.

The Muſcles of the *Epiglottis*.

The uſe of the cavities or fiſſures of the Throttle.

CHAP. XVI.

Of the Neck and the parts thereof.

FIrſt we will define what the Neck is, then proſecute the parts thereof, as well proper as common, eſpecially thoſe of which we have not as yet treated. For it were ſuperfluous to ſpeak any more of the Skin, the fleſhy Pannicle, the Veins, Arteries, Nerves, Gullet, Weazon and Muſcles aſcending and deſcending to the parts into which they are inſerted alongſt the Neck; wherefore you muſt not expect, that we ſhould ſay any thing of the Neck, more than to deſcribe the *Vertebræ* or Rack-bones, being the proper parts thereof, and the Ligaments, as well thoſe proper to the Neck, as thoſe which it hath in common with the head; and laſtly, the Muſcles, as well thoſe it hath in common with the Head and Cheſt, as thoſe of its own. Therefore the Neck is nothing elſe than a part of the Head, which is contained between the Nowl-bone and the firſt *Vertebra* of the back. First in the Neck, the *Vertebraes* muſt be conſidered, and we muſt ſhew what they have proper and peculiar, and what common amongſt themſelves, that we may the more eaſily ſhew the original and inſertion of the Muſcles growing out of them and ending in them. The Neck conſiſts of ſeven *Vertebræ*, or Rack-bones; in which you muſt conſider their proper body; and then the holes by which the Spinal-marrow paſſes; thirdly, the *Apophyſes* or proceſſes of the *Vertebra*; fourthly, the holes through which the Nerves are diſſeminated into other parts from the Spinal marrow, and beſides the perforations of the tranſverſe productions by which the Veins and Arteries, which we call *Cervicales*, aſcend alongſt the Neck; and laſtly, the connexion of theſe ſame *Vertebræ*, or Rack-bones. For the firſt, By the body of the *Vertebra*, we underſtand the fore-part thereof upon which the Gullet lies. For the hole, that is not always the largeſt in thoſe *Vertebræ* which are nigheſt the Head; but it is always encompaſſed with the body of the *Vertebræ*, and beſides with three ſorts of proceſſes, except in the firſt Rack-bone, that is right, tranſverſe and oblique. By right, we underſtand thoſe extuberancies in the Rack-bones of the Neck which are hollowed directly in the upper part of them, and riſe up creſted on each ſide to ſuſtain and receive the baſis of the Rack-bone which is ſet upon it. By the oblique proceſſes, we underſtand the bunchings out by which theſe Rack-bones are mutually knit together by *Ginglymos*; theſe are ſeated between the tranſverſe proceſſes. By the tranſverſe, we underſtand the protuberations next the body, which divide the *Vertebra* or Rack-bone in a ſtraight line. Theſe proceſſes are perforated, that they may give way to the before deſcribed Veins and Arteries, which entering the Spinal marrow by the holes of the Nerves nouriſh the Rack-bones and parts belonging to them. Beſides, you muſt note, that the perforations of the Rack-bones of the Neck, by which the Nerves proceed from the Spinal marrow to the outward parts, are under the tranſverſe proceſs, that is growing or made by the upper and lower *Vertebra*, contrary to all other which are in the reſt of the Rack-bones. For the connexion of the Rack-bone, you muſt know, that all the *Vertebræ* of the Spine have ſix connexions, two in their own bodies, and four in their oblique proceſſes. By the two firſt connexions they are ſo mutually articulated in their own bodies, that each are joined with other both above and below. But by the four other by their oblique aſcendent and deſcendent proceſſes on each ſide two, they are ſo mutually inarticulate, that as the fourth Rack-bone of the Neck by its oblique aſcendent proceſſes, is received of the deſcendent proceſſes of the third Rack-bone, ſo it receives the oblique aſcendent proceſſes of the firſt, by its oblique deſcendents, for always the oblique aſcendents are received, and the deſcendents receive. Yet we muſt except the firſt Rack-bone of the Neck which is contained with four connexions by his lower oblique proceſſes, and by its upper by which it receives the oblique proceſſes of the Nowl-bone, and of the ſecond Rack-bone. The ſecond *Vertebra*, or Rack-bone, muſt alſo be excepted, which is holden by five connexions, that is to ſay, four by its oblique proceſſes, and the fifth by its own body, by which it is knit to the body of the third *Vertebra*. But we muſt note, that whereas Nature hath not given a Spine to the firſt Rack-bone, yet it hath given it a certain bunch or extuberancy in ſtead thereof; in like manner, ſeeing it makes no common paſſage with the ſecond *Vertebra*, for the paſſing forth of the Nerve, it is perforated at its ſides of the body, and it is made very thin on the fore-ſide, as if it were without body, that it might receive the fore-proceſs raiſed in the upper body of the ſecond Rack-bone, which *Hippocrates* calls the Tooth, to which the principal Ligament of the Head is faſtned, which deſcends within from the hind-part of the Head under the *Apophyſes Clinoides*, or proceſſes of the Wedge-bone.

What the Neck is.

What to be conſidered in the *Vertebræ* of the Neck.

Which be the right proceſſes of the *Vertebræ*.

Which the Oblique.

Which the Tranſverſe.

The connexions of the *Vertebræ* of the Neck.

The Proceſs called the Tooth.

And

By what articulation the head is bended backwards and forwards.

And by this articulation the head is bended forwards and backwards, as it is moved to the ſides by the articulation of the firſt Rack-bone with the ſecond. That proceſs is bound by two ligaments, the firſt of which being greater and broader is external, comprehending in the compaſs thereof all the upper articulation, aſcending from the Rack-bones to the Head, or rather deſcending from the Head to them, as any other Ligament going from one bone to another. The other is the ſtronger, and alſo encompaſſes the articulation mixing it ſelf with the Griſle, which by its interpoſition binds together all the Rack-bones, the firſt excepted, as you may ſee in pulling aſunder the Rack-bones of a Swine; and the whole Spine, or Rack-bone is tied together, and compoſed throughout with ſuch Ligaments.

Table. 2 . { Figure 1. *Sheweth all the Rack-bones of the Back knit together.*
{ Figure 2. *Sheweth the fore and upper face of the Neck, &c.* See Dr. *Crook*, p. 398.

From A *to* B *the ſeven* Vertebraes *of the Neck.*
From C *to* D *the twelve* Vertebraes *of the Cheſt.*
From E *to* F *the five Rack-bones of the Loins.*
From G *to* H *the* Os ſacrum, *or Holy Bone conſiſting, commonly, of ſix* Vertebræ.
From I *to* K *the Bone* Coccyx, *or the Rump-bone, according to the late Writers.*
L L *The bodies of the* Vertebræ.
M *The Tranſverſe proceſſes of the* Vertebræ.
N *The deſcendent proceſſes.*
O O *The aſcendent proceſſes.*
P P *The backward proceſſes.*
Q Q *The holes that are in the ſides of the* Vertebræ, *through which the Nerves are tranſmitted.*
R R *A griſly Ligament betwixt the* Vertebræ.
A 2 3 4 *The hole whereout the marrow of the Back iſſueth.*
B 2 3 *The cavity which admitteth the root of the ſecond Rack-bone.*
C 3 4 *A cavity or* Sinus *in the ſame place cruſted over with a Griſle.*
D 2 *A prominence in the outward region of the* Sinus.
E F 2 3 *The* Sinus, *or cavity of the firſt Rack-bone which admitteth the two heads of the Nowl-bone.*
G G 2 3 4 *The tranſverſe proceſs of the firſt* Vertebra. H 1 *The hole of this tranſverſe proceſs.* I 3 *The* Sinus *which together with the cavity of the Nowl-bone marked with* E, *maketh a common paſſage prepared for the Nerves.* K 3 4 *A rough place where the Spine of the firſt Rack is wanting.* L L 4 *Two cavities of the firſt Rack receiving the two bunches of the ſecond Rack marked with* M N. M N 5 6 *The two bunches of the ſecond Rack which fall into the cavities of the firſt.* O 7 *The Appendix or Tooth of the ſecond Rack.* P 5 *A knub of this Appendix cruſted over with a Griſle.* Q 6 *The back ſide of the Tooth.* R 6 *The* Sinus *or cavity of the ſame, about which a tranſverſe Ligament is rouled, containing the ſaid Tooth in the cavity of the firſt Rack.* S T 6 *Certain cavities at the ſides of the Tooth whence the roots iſſue of the fore-branch of the ſecond pair of ſinews.* V 5 *The point of the Tooth.* X 3 *An aſperity or roughneſs, where is a hole, but not thrilled through.* Y 6 *A cavity of the ſecond Rack, which together with the cavity marked with* Z, *maketh a hole through which the Nerves do iſſue.* Z 4 *The* Sinus *of the firſt Rack.* a 5 6 7 *The double ſpine of the ſecond Rack.* b 5 6 7 *The tranſverſe proceſs of the ſecond Rack.* c 7 *The hole of the ſaid tranſverſe proceſs.* d 6 7 *The deſcending proceſs of the ſecond Rack, whoſe cavity is marked with* d, *in the ſixth Figure.* e 6 7 *The place where the body of the ſecond Rack deſcendeth downward.* f g g 8 *The lower ſide of the body of the third Rack at* f, *the two eminent parts of the ſame at* g g. h i 8 *The aſcending proceſſes.* l m 8 *The two deſcending proceſſes.* n o p q 8 *The tranſverſe proceſſes.* r 8 9 *The Spine or backward proceſs.* ſ t 8 *The two tops of the Spine.* u 9 *The deſcending proceſs of the third Rack.* x 9 *The aſcending proceſs.* y *The tranſverſe proceſs of the third Rack.* α 8 9 *The hole of this tranſverſe proceſs.* β 9 *The upper hollowed part of the body of the third Rack.* δ 9 *The* Sinus *or cavity which maketh the lower part of a hole through which the conjugations of the Nerves are led.* ε 7 *The upper part of the ſame hole.*

FIG. 1



The *Vertebræ* of the Holy-bone.

The Holy-bone is compoſed of four *Vertebræ* (or rather of five or ſix, as in the Figure above) beſides the Rump-bone, it receives, and holds faſt the *Oſſa Ilium*, or Hanch-bones, and is as a Baſis to all the Rack-bones placed above it, whereby it comes to paſs that the Rack-bones from the Head to the Holy-bone grow ſtill thicker, becauſe that which ſupports ought to be bigger than that which is ſupported. There is a certain moiſture, tough and fatty, put between the Rack-bones, as alſo in other joints to make them glib and ſlippery, that ſo they may the better move. Whileſt this motion is made, the Rack-bones part one from another.

The

The commodities or uſes of the Spine are ſaid to be four. The firſt is, That it is as it were, the ſeat and foundation of the compoſure and conſtruction of the whole body, as the Carcaſs is in a Ship. The ſecond, That it is a way or paſſage for the marrow. The third is, Becauſe it contains and preſerves the ſame. The fourth is, That it ſerves for a Wall or Bulwark to the entrails, which lie and reſt upon it on the inſide. And, becauſe we have fallen into mention of Ligaments, it will not be amiſs to inſert in this place that which ought to be known of them. Firſt therefore, we will declare what a Ligament is, then explain the divers acceptions thereof; and laſtly, proſecute their differences. The manifold uſes of the Back-bone.

Therefore a Ligament is nothing elſe than a ſimple part of Mans Body, next to a Bone and Griſle the moſt terreſtrial, and which moſt uſually ariſes from the one or other of them either mediately or immediately, and in the like manner ends in one of them, or in a Muſcle, or in ſome other part; whereby it comes to paſs, that a Ligament is without bloud, dry, hard, cold, and without ſenſe, like the parts from whence it ariſes, although it reſemble a Nerve in whiteneſs and conſiſtence, but that it is ſomewhat harder. What a Ligament is. Why it is without ſenſe.

A Ligament is taken either generally, or more particularly; in general, for every part of the body, which ties one part to another, in which ſenſe the skin may be called a Ligament, becauſe it contains all the inner parts in one union. So the *Peritonæum* comprehending all the natural parts, and binding them to the Back-bone: ſo the Membrane inveſting the Ribs, (that is, the *Pleura*) containing all the Vital parts; thus the Membranes of the Brain, the Nerves, Veins, Arteries, Muſcles, Membranes; and laſtly, all ſuch parts of the Body which bind together, and contain other, may be called Ligaments, becauſe they bind one part to another; as the Nerves annex the whole Body to the Brain, the Arteries faſten it to the Heart, and the Veins to the Liver. But to conclude, the name of a Ligament more particularly taken, ſignifies that part of the Body which we have deſcribed a little before. What parts may be called Ligaments in a general ſignification.

The differences of Ligaments are many, for ſome are membranous and thin; others broad, otherſome thick and round, ſome hard, ſome ſoft, ſome great, ſome little, ſome wholly griſly, others of a middle conſiſtence between a Bone and Griſle, according to the nature of the motion of the parts which they bind together in quickneſs, vehemency, and ſlowneſs. We will ſhew the other differences of Ligaments, as they ſhall preſent themſelves in diſſection. The differences of Ligaments properly ſo called.

CHAP. XVII.

Of the Muſcles of the Neck.

THe Muſcles of the Neck, as well proper as common, are in number twenty, or elſe twenty two, that is, ten or eleven on each ſide; of which, ſeven onely move the Head, or the firſt *Vertebra* with the Head; the other three or four, the neck it ſelf. Of the ſeven which move the Head, and with the head the firſt *Vertebra*, ſome extend and erect it, others bend and decline it, others move it obliquely, but all of them together in a ſucceſſive motion move it circularly: and the like judgment may be of the Muſcles of the Neck. Their number

But before I can come to the deſcription of their original and inſertion, I muſt admoniſh thee, that the two Muſcles of the Shoulder-blade muſt firſt be taken away by diſſection; that is, the *Trapezius* or Table-muſcle, and the *Rhomboides*, or Square-muſcle; whoſe original and inſertion that we may the better demonſtrate, (or rather the action by which we ſeek that original and inſertion) they muſt be pulled up, beginning at their inſertion, which is at the Shoulder-blade (as ſhall be ſhewed in the proper place, turning them up towards their original, that is, to the Spine. Beſides, the leſs *Rhomboides*, the hinder and upper (called alſo the *Dentatus* or toothed-Muſcle) muſt be raiſed from its oriignal, which is at the three lower Rack-bones of the Neck and the firſt of the Back, and turned up to its inſertion, which is at three ſpaces of the lower ribs nigh to the hind and upper angle of the Shoulder-blade, as ſhall be ſhewed in fit place hereafter. Theſe Muſcles thus raiſed up, the four Muſcles which erect and extend the Head, muſt be taken away, and then thoſe two which move it obliquely; and laſtly, one which bends or declines: for thus Anatomical order requires. Yet, if you think good, you may, not hurting the other, firſt of all cut away that which is called the *Maſtoides*, which declines or bends the Head. For theſe four which lift up and extend the Head, the firſt from the figure of the Spleen is called the *Splenius*, it aſcends from the five upper ſpines of the Back, and the four lower of the Neck, and is obliquely inſerted at the back-part of the Head, and the Mamillary proceſs, whence you may raiſe it towards its original. The ſecond by reaſon of its compoſure is called *Complexus*; this paſſing from the third, fourth, and fifth tranſverſe proceſs of the Back, and often from the firſt of the Neck: aſcends directly to the back-part of the Head, encompaſſing the lower and ſide-part of the Neck, you may eaſily take it up, if you begin at the ſpine, and ſo go forward to the tranſverſe proceſſes and mamillary proceſſes of the Nowl-bone. This *Complexus* may be divided into two or three Muſcles, but that with ſome difficulty, by reaſon of its folded texture. The third and fourth, which be two of the eight little Muſcles, being four on each ſide, do aſcend ſomewhat obliquely, the firſt truly from the whole ſide of the ſecond *Vertebra*. The ſecond from the whole ſide of the proceſs of the firſt *Vertebra*, which it hath in ſtead of a Spine; they aſcend to the back-part of the Head, juſt againſt the Spine; theſe two Muſcles by the conſent of all Anatomiſts, are called right or direct Muſcles, onely moving the head, theſe truly muſt not be plucked from the places of their original, nor inſertion, but onely bound by a ſtring put under them, that ſo they may be the more eaſily ſhewed. On each ſide follow two oblique Muſcles, one whereof onely moves the Head; the other primarily the firſt *Vertebra*, but ſecondarily and by accident the Head it ſelf. For the firſt, contrary to the The *Splenius*. The *Complexus*. The *Recti*, or two right Muſcles.

opinion of ſome, it ariſes from the tranſverſe proceſs of the firſt Rack-bone, and then is inſerted, above the inſertion of the firſt right Muſcle: the which in like manner you muſt lift up, by ſomething put underneath it, but not ſeparate it. The other entering forth of the Spine of the ſecond *Vertebra*, is inſerted at the proceſs of the firſt, contrary to the original of the precedent, although ſome think otherwiſe. It will be convenient in the like manner, onely to lift up this with a ſtring, and not pluck him from its place, that ſo you may ſee how all theſe make a perfect triangle. The action of this Muſcle is contrary to the action of the precedent, as the contrariety of its original and inſertion ſhew.

The Fourth Figure of the Muſcles. This Figure ſheweth the cavities of the middle and lower Bellies, the Bowels being taken out, but moſt part of the Bones and Muſcles remaining.



AB *The firſt Muſcle bending the neck, called* Longus.
C C *The ſecond bender of the neck, called* Scalenus.
DDDD *The outward* intercoſtal *Muſcles.*
EEEE *The inner* intercoſtal *Muſcles.*
FFF *The ſecond Muſcle of the Cheſt, called* ſerratus major.
G *The firſt Muſcle of the Shoulder-blade, called* ſerratus minor, *ſeparated from his original.*
H *The firſt Muſcle of the Arm called* Pectoralis, *ſeparated from his original.*
I *The ſecond Muſcle of the Arm, called* Deltoides.
K *The Bone of the Arm without fleſh.*
L *The firſt Muſcle of the Cubit, called* Biceps.
M *The ſecond Muſcle of the Cubit called* Brachicus.
N *The Clavicle, or Collar-bone, bent backward.*
O *The firſt Muſcle of the Cheſt, called* Subclavius.
P *The upper proceſs of the Shoulder-blade.*
Q *The firſt Muſcle of the Head, called* obliquus inferior.
R *The ſecond Muſcle of the Head, called* Complexus.
S *The fourth Muſcle of the Shoulder-blade, called* Levator.
TV *The two Bellies of the fourth Muſcle of the bone* Hyois. XX aa *The fifth Muſcle of the back whoſe original is at* aa. YY bb cc *The ſixth Muſcle of the Thigh, called* Pſoæ, *whoſe original is at* cc, *and tendon at* bb. ZZ *The ſeventh Muſcle of the thigh.* d *The Holy-bone.* ooo *The holes of the Holy-bone, out of which the Nerves do iſſue.* e *A portion of the fifth Muſcle of the thigh ariſing frrm the Share-bone.* f *The Share-bone bared.* k *The nineth Muſcle of the thigh or the firſt* circumactor.

Which may be truly called the proper Muſcle of the Neck.

Wherefore when the firſt oblique moves the Head obliquely forward, the ſecond pulls it back by the firſt *Vertebra*; this, with his aſſociate of the other ſide, may be truly termed the proper Muſcles of the Neck, becauſe they belong to no other part; whereas it is contrary in other Muſcles. But we muſt note, that the Head (according to *Galen*'s opinion) hath two motions, one directly forwards and backwards, as appears in beckning it forwards, and caſting it backwards; the other circular.

The two motions of the Head.

The firſt in *Galen*'s opinion is performed by the firſt *Vertebra* moved upon the ſecond; the ſecond by the Head moved upon the firſt *Vertebra*; for which he is reproved by the later Anatomiſts, who teach that the Head cannot be turned round, or circularly upon the firſt *Vertebra*, without putting it out of joint.

The *Maſtoidtus.*

For the laſt which bends the Head, it aſcends from the upper and ſide-part of the *Sternon*, and the next part of the clavicle, obliquely to the *Apophyſis Maſtoides*, or mamillary proceſs of the hind part of the Head, whence it is called the *Maſtoideus*. You may divide this by reaſon of its manifold original rather into two, than into three Muſcles. But it had been better that the Head might have been moved every way, equally backwards and to the right and left ſides; but thus it would often have been ſtrained to our great damage and danger of life; neither could there have been ſuch facility of motion without a looſneſs of the joint. Therefore Nature had rather beſtow upon the Head an harmleſs faculty of fewer motions, than one furniſhed with more variety, but with a great deal more uncertainty and danger. Wherefore it hath made this juncture not lax or looſe, but ſtiff and ſtrong.

After

After the ſhewing of theſe Muſcles, we muſt come to three or four of the Neck, of which number, two (which ſome reduce to one) extend, another bends, and the laſt moves ſide ways; and all of them with a motion ſucceeding each other turn it about, as we ſaid of the Muſcles of the Head. The firſt of theſe which extend, taking its original from the ſix tranſverſe proceſſes of the ſix upper Rack-bones of the Back or rather from the root of the oblique, aſcends directly to the Spine of the ſecond *Vertebra* of the Neck, and the oblique proceſs thereof; ſome ſome call it the *Tranſverſarius*; that is, the tranſverſe Muſcle. This, if you deſire to take it away, it is beſt firſt to ſeparate it from the Spine, then to turn it upwards to the tranſverſe proceſſes; unleſs you had rather draw it a little from its Partner and Companion, in that place where their originals are diſtinct, ſeeing it is the laſt and next to the Bones. The *Tranſverſarius.*

The Fifth Figure of the Muſcles. In which ſome Muſcles of the Head, Cheſt, Arms, and Shoulder-blade are deſcribed.

I *The proceſs of the Shoulder-blade, called the top of the Shoulder.*

O *The fourth Muſcle of the Arm, or* the greater round Muſcle, *to which* Fallopius *his right Muſcle is adjoined, which ſome call the* leſſer round Muſcle.

Q Q *The ſixth Muſcle of the Arm, or the upper* Blade-rider.

X *The ſecond Muſcle of the ſhoulder-blade, or the* Levator, *or Heaver.*

Z *The ſecond Muſcle of the Cheſt, or the* greater Saw-muſcle.

Y *The fifth Muſcle of the Cheſt, or Muſcle called* Sacro-lumbus.

α β *His place wherein he cleaveth faſt to the longeſt muſcle of the back.*

γ γ *The tendons of the Muſcle obliquely inſerted into the Ribs.*

Δ Δ *The firſt pair of the Muſcles of the head, or the ſplinters.*

Ch 8 9 *Their length, whoſe beginning is at* 8, *and inſertion at* 9.

10 11 *The ſides of this Muſcle.*

12 *That diſtance where they depart one from the other.*

13 *The two Muſcles called* Complexi, *near their inſertion.*

Φ *The ſecond Muſcle of the back, or the* Longeſt *Muſcle.*

Ω *The fourth Muſcle of the Back, or the* Semi-ſpinatus.

δ *The Shoulder-blade bare.*

ρ *A part of the tranſverſe Muſcle of the* Abdomen.

Marvel not if you find not this diſtinction of their original ſo plain and manifeſt, for it is commonly obſcure. For the Muſcle *Spinatus*, as it moſt commonly comes to paſs, ariſing from the roots of the ſeven upper Spines of the Back, and the laſt of the neck, is inſerted into other Spines of the Neck, ſo that it might eaſily be confounded with the former by *Galen*. The third bends the Neck, and ariſing within from the Body of the five upper *Vertebræ* of the Back (though with a very obſcure original, ſpecially in lean Bodies) it aſcends under the Gullet alongſt the Neck, even to the Nowl-bone, into whoſe inner part it is obſcurely inſerted. Wherefore it is likely that it helps not onely to bend the Neck but alſo the Head. This Muſcle is made of oblique Fibers proceeding from the body of the *Vertebræ*, all the way it paſſes to the tranſverſe proceſſes of the other *Vertebra*. But it ſeems with its co-partner which is oppoſite to it, to make a certain hollow path upon the bodies of the *Vertebræ*, to the Gullet, and it is called the Long Muſcle. The fourth and laſt, which we ſaid moves the Neck to one ſide, is called *Scalenus* from the figure thereof; it aſcends from the hinder and upper part of the firſt rib of the Cheſt, inſerting it ſelf into all the tranſverſe proceſſes of the Neck by its Fibers, which as it were for the ſame purpoſe, it hath ſufficiently long, that it may faſten it ſelf from the furtheſt and loweſt proceſs of the Neck into the firſt or higheſt thereof. The paſſage of the Nerves through this to the Arm makes this Muſcle ſeem double, or divided into two. For The *Spinatus.* The *Longus.* The *Scalenus.*

the Veins and Arteries pertaining to the Neck, they have been declared in the proper Chapters of the diſtribution of the Veſſels; it remains that you note, All theſe Muſcles receive Nerves from the *Vertebræ*, whence they ariſe.

The Sixth Figure of the Muſcles; Shewing ſome of the Muſcles of the Head, Back, Cheſt, Shoulder-blade and Arm.

A D *The ſecond pair of the Muſcles of the Head, or the two* Complexi, *the firſt part is at* A D.

B C *The ſecond part;* E F *The third part riſing up under* G, *and inſerted at* F.

G *The fourth part of this Muſcle, or the right muſcle of the Head according to* Fallopius, *which* Veſalius *made the fourth part of the ſecond.*

G G *(Betwixt the Ribs) the external* intercoſtal *muſcles.*

L *The original of the two muſcles of the Back.*

M *His tendons at the Rack-bone of the neck.*

The upper O, *the fourth muſcle of the Arm, or the* greater round *muſcle.*

O O *the lower, The ſixth muſcle of the Cheſt, or the* Sacrolumbus *hanging from his original.*

Q *The ſixth muſcle of the Arm or the upper* Blade-rider *inverted.*

V *The third ligament of the joint of the Arm.*

X *The fourth muſcle of the Shoulder-blade or the* Heaver.

Z *The ſecond muſcle of the Cheſt, or the* greater Saw-muſcle.

Ξ *The three muſcles of the neck called* Tranſverſalis.

Π *The Fourth muſcle of the neck called* Spinatus.

Σ *The firſt muſcle of the Back, or the* Square muſcle.

Φ *The two muſcles of the Back, or the* Longeſt; *whoſe original is at* L, *and his tendons at the* Vertebræ *at* M M.

Ω *The fourth muſcle of the back called* Spinatus.

∂ *The back of the Shoulder-blade flayed.*



The Seventh Figure of the Muſcles; Shewing ſome Muſcles of the Head and Cheſt, the Trapezius, *or Table-muſcle being taken away: as alſo of the Blade and Arm.*



A *The prominent part of the fourth Muſcle of the Cheſt called* Serratus poſticus ſuperior.

Δ *The firſt muſcle of the head called* Splenius,

E E *The inſertion of the muſcle of the head, called* Complexus,

I *The Coller bone bared.*

M *The back-part of the ſecond Muſcle of the Arm called* Deltois.

ξ H *His backward original.*

θ *His implantation into the Arm.*

N N *The fourth muſcle of the Arm called* Latiſſimus,

S μ *His original from the Spines of the Rack-bones, and from the holy-bone.*

π *The connexion of this Muſcle with the Haunch-bone, which is led in the inſide from* μ *to* π.

ω *The place where it lieth upon the lower angle of the Baſis of the Shoulder-blade.*

O *The four Muſcles of the Arm, called* Rotundus major.

e *Some Muſcles of the Back do here offer themſelves.*

P *The fifth Muſcle of the Arm, called* Super-ſcapularis inferior.

Q *The ſixth Muſcle of the Arm called* Super-ſcapularis Superior.

S *The beginning of the third Muſcle of the Arm called* Latiſſimus.

V *The third muſcle of the Blade called* Rhomboides.

Φ X *His original from the Spines of the Rack-bones.*

⏚ ω *His inſertion into the Baſis of the Shoulder-blade.*

χ *The fourth muſcle of the Blade called* Levator.

* *A part of the oblique deſcendent muſcle of the* Abdomen.

the Veins and Arteries pertaining to the Neck, they have been declared in the proper Chapters of the diſtribution of the Veſſels; it remains that you note, All theſe Muſcles receive Nerves from the *Vertebræ*, whence they ariſe.

The Sixth Figure of the Muſcles; Shewing ſome of the Muſcles of the Head, Back, Cheſt, Shoulder-blade and Arm.

A D *The ſecond pair of the Muſcles of the Head, or the two* Complexi, *the firſt part is at* A D.

B C *The ſecond part;* E F *The third part riſing up under* G, *and inſerted at* F.

G *The fourth part of this Muſcle, or the right muſcle of the Head according to* Fallopius, *which* Veſalius *made the fourth part of the ſecond.*

G G *(Betwixt the Ribs) the external* intercoſtal *muſcles.*

L *The original of the two muſcles of the Back.*

M *His tendons at the Rack-bone of the neck.*

The upper O, *the fourth muſcle of the Arm, or the* greater round *muſcle.*

O O *the lower, The ſixth muſcle of the Cheſt, or the* Sacrolumbus *hanging from his original.*

Q *The ſixth muſcle of the Arm or the upper* Blade-rider *inverted.*

V *The third ligament of the joint of the Arm.*

X *The fourth muſcle of the Shoulder-blade or the* Heaver.

Z *The ſecond muſcle of the Cheſt, or the* greater Saw-muſcle.

Ξ *The three muſcles of the neck called* Tranſverſalis.

Π *The Fourth muſcle of the neck called* Spinatus.

Σ *The firſt muſcle of the Back, or the* Square muſcle.

Φ *The two muſcles of the Back, or the* Longeſt; *whoſe original is at* L, *and his tendons at the* Vertebræ *at* M M.

Ω *The fourth muſcle of the back called* Spinatus.

∂ *The back of the Shoulder-blade flayed.*



The Seventh Figure of the Muſcles; Shewing ſome Muſcles of the Head and Cheſt, the Trapezius, *or Table-muſcle being taken away: as alſo of the Blade and Arm.*



A *The prominent part of the fourth Muſcle of the Cheſt called* Serratus poſticus ſuperior.

Δ *The firſt muſcle of the head called* Splenius,

E E *The inſertion of the muſcle of the head, called* Complexus,

I *The Coller bone bared.*

M *The back-part of the ſecond Muſcle of the Arm called* Deltois.

ξ H *His backward original.*

θ *His implantation into the Arm.*

N N *The fourth muſcle of the Arm called* Latiſſimus,

S μ *His original from the Spines of the Rack-bones, and from the holy-bone.*

π *The connexion of this Muſcle with the Haunch-bone, which is led in the inſide from* μ *to* π.

ω *The place where it lieth upon the lower angle of the Baſis of the Shoulder-blade.*

O *The four Muſcles of the Arm, called* Rotundus major.

e *Some Muſcles of the Back do here offer themſelves.*

P *The fifth Muſcle of the Arm, called* Super-ſcapularis inferior.

Q *The ſixth Muſcle of the Arm called* Super-ſcapularis Superior.

S *The beginning of the third Muſcle of the Arm called* Latiſſimus.

V *The third muſcle of the Blade called* Rhomboides.

Φ X *His original from the Spines of the Rack-bones.* ⏚ ω *His inſertion into the Baſis of the Shoulder-blade.* χ *The fourth muſcle of the Blade called* Levator. * *A part of the oblique deſcendent muſcle of the* Abdomen.

The Eighth Figure of the Muſcles, eſpecially thoſe of the Cheſt, Head, and Shoulder-blade; the Trapezius Latiſſimus, *and* Rhomboides, *being taken away.*

A *The fourth Muſcle of the Cheſt, or the upper and hinder Saw-muſcle.*

B *The five Muſcles of the Cheſt, or the lower and hinder Saw-muſcle.*

ab *A membranous beginning of the Muſcle of the* Abdomen, *deſcending obliquely down from the Spine of the back.*

C *The firſt Muſcle extending the Cubit at* c, *his original is from the neck of the Arm, and from the lower Baſis of the Blade at* d.

E *The Original of the fourth Muſcle of the Bone* Hyois *from the Blade.*

GG *The Outward Intercoſtal Muſcles.*

I *The Clavicle or Collar-bone bared.*

N *The Upper, the ſecond Muſcle of the Arm called* Deltois, *char.* 4, 5. *the beginning of this Muſcle.*

N *The third Muſcle of the Arm or the broad Muſcle ſeparated.*

O *The fourth Muſcle of the Arm or the lower* Super-ſcapularis, *or blade-rider.*

1 2 3 *Char. his original at the Baſis of the Shoulder-blade at* 12, *and his inſertion into the joint of the Arm at* 3.

Q *The ſixth Muſcle of the Arm or the upper* Super-ſcapularis.

X *The fourth Muſcle of the Blade, called* Levator, *or the Heaver.*

Z *The ſecond Muſcle of the Cheſt, or the greater Saw-muſcle.*

7 7 Char. *the Ribs.*

F *The ſixth Muſcle of the Cheſt, or the Muſcle called* Sacrolumbus.

E Λ *The firſt Muſcle of the Head, or the Splinter.*

E E *The ſecond Muſcle of the Head, or the inſertion of the Muſcles called* Complexi.

Φ *The ſecond Muſcle of the Back, or the Longeſt Muſcle.* Ω *The fourth Muſcle of the Back, called* Semi-ſpinatus.

The Nineth Figure of the Muſcles, ſhewing the Muſcles of the Head and Neck.



A B *The third pair of the Muſcles of the Head, called* Recti Majores.
C *The Mammillary proceſs.*
D *The tranſverſe proceſs of the firſt Rack-bone.*
E *The proceſs of the ſecond Rack-bone of the Neck.*
F G *The fourth pair of Muſcles of the Head, called* Recti Minores.
H I *The fifth pair of Muſcles of the Head, called* Obliqui Superiores.
K L *The ſixth pair of Muſcles of the Head, called* Obliqui Inferiores.
X *The fourth pair of Muſcles of the Shoulder-blade.*
Λ *The ſecond Muſcle of the Neck called* Scalenus, *which* Fallopius *maketh the eighth Muſcle of the Cheſt.*
Π *The fourth Muſcle of the Neck, called* Spinatus.
Σ *The firſt Muſcle of the Back, called* Quadratus.
Φ *The ſecond Muſcle of the Back, called* Longiſſimus.
a *The* Sinus, *or boſom of this Muſcle, whereby it giveth way unto the third Muſcle of the Back, called* Sacer.
b *His Original.*
ϒ *The third Muſcle of the Back, called* Sacer.
γ *His Original.*
δ *His End.*
Ω *The fourth Muſcle of the Back, called* Semiſpinatus.
ε *His upper end under the fourth Muſcle of the Neck.*

CHAP. XVIII.

Of the Muſcles of the Cheſt and Loins.

WE muſt now ſpeak of the Muſcles both of the Cheſt which ſerve for reſpiration, as alſo of the Loins. But firſt we muſt know that the hind part of the Cheſt, called the *Metaphrenum*, or Back, conſiſts of twelve *Vertebræ*, the Loins of five, all which differ not from the *Vertebræ* of the Neck, but that they are thicker in their bodies than theſe of the Neck; neither are they leſſer in holes, neither have they their tranſverſe proceſſes perforated or parted in two, as the Rack-bones of the Neck have. Beſides, each of theſe Rack-bones alone by it ſelf, on each ſide in the lower part thereof, makes a hole, through which a Nerve hath paſſage from the Spinal-marrow to the adjacent parts; when on the contrary in the *Vertebræ* of the Neck, ſuch holes or paſſages are not made, but by meeting together of two of them. In what the *Vertebræ* of the Neck and Loins agree and diſagree.

Concerning the proceſſes of the Rack-bones of the Cheſt, whether tranſverſe, right or oblique they differ nothing from theſe of the Neck (I mean even to the tenth) but that the tranſverſe ſeeing they are not perforated, as we ſaid before, do as it were ſuſtain the Ribs, being ſtraitly bound to them with ſtrong Ligaments both proper and common; but after the tenth *Vertebra* of the Back, the two other of the Back, and all thoſe of the Loins are different, not onely from thoſe of the Neck, but alſo from the ten firſt of the Back, by reaſon of their oblique proceſſes, becauſe from the eleventh (which is received, as well by that which is above it, as that under it, for the ſtrength of the whole Back, and the eaſier bending thereof without fear of fracture or diſlocation) the above-mentioned proceſſes of the lower Rack-bones, which were wont to receive, are received; as, on the contrary, they receive, which are wont to be received. They differ beſides from all the fore-mentioned, by reaſon of their Spines, becauſe from the eleventh they by little and little do look upwards, contrary to the former.

But if any ask how the tenth *Vertebra* of the Back may be termed the midſt of the Spine, ſeeing the whole Spine conſiſts of twenty four *Vertebræ?* He may know that this may be true, as thus; If the ſix Bones of the Holy-bone, and the fourth of the Rump (being more griſly than bony) be numbred amongſt the Bones of the Spine; for then from the ſetting on of the head to the eleventh Rack-bone of the Back are ſeventeen in number, and ſo many from thence downwards. How the tenth *Vertebra* of the Back, may be ſaid to be the middle of the Spine.

But let us return to the Muſcles of the Cheſt ſerving for reſpiration. Firſt you muſt know that theſe Muſcles are fourſcore and nine, that is, on each ſide forty four, alike in ſtrength, thickneſs, ſite, and action; and one beſides in the midſt which they call the *Diaphragma*, or Midriff. Of theſe forty four, there are twenty two which dilate the Cheſt in drawing in the breath; that is, the *Sub-clavius*, The number of the Muſcles of the Cheſt. The Muſcles dilating the Cheſt.

clavius, the *Dentatus*, or *Serratus major* in the opinion of ſome, both the *Rhomboides* or *Serrati poſtici*; the oblique aſcendent of the lower Belly, the eleven *Intercoſtales*, and the ſix *Intercartilaginei externi*.

The Muſcles contracting the Cheſt.

On the contrary, as many contract the Breſt in expiration; to wit, the *Sacrolumbus*, the oblique deſcendent, the Right and Tranſverſe of the lower Belly, the inner Triangular, the ſix *Intercartilaginei*, and the eleven inner *Intercoſtales*. Of theſe twenty two dilating the cheſt, the firſt from the ſite is called the *Subclavius*, for it deſcends obliquely from the inner and fore-part of the *Clavicula* or Coller-bone, into the Griſle of the firſt Rib, even to the *Sternon*, and dilates it. The ſecond is the *Serratus major*, the greater Saw-muſcle ariſing according to the opinion of ſome from the whole *Baſis* of the Shoulder-blade on the inſide, and it is tranſverſly inſerted into the nine upper Ribs, producing certain toothed, or Saw-like proceſſes, running further to the Bones of the Rib than to the Spaces between them, or Intercoſtal Muſcles, whereupon it hath the name of the Saw-muſcle; yet ſome have referred this Muſcle to them of the Shoulder-blade. The third deſcends from the three lower Spines of the Neck, and the firſt of the Back, by means of a membranous and moſt thin ligament, into the three or four upper Ribs, running further into their Spaces or Intercoſtal Muſcles, than into the Ribs themſelves, whereupon it is called *Serratus poſterior & ſuperior*, that is, the hinder Saw-muſcle. The fourth in like manner aſcends by means of a membranous and thin ligament from the three upper Spines of the Loins, and the two laſt of the Cheſt, or Back, into three or four of the lower, or laſt of the Baſtard-ribs, ſent forth further into them or their Bones, than into the Intercoſtal Muſcles poſſeſſing the ſpaces between them, wherefore it is called *Serratus poſterior & inferior*, the hinder and lower Saw-muſcle. Moreover theſe two laſt Muſcles have been called by a common name from their figure the *Rhomboides*, that is, the ſquare Muſcles. The fifth which we ſaid was the aſcendent of the *Epigaſtrium*, hath already been ſufficiently deſcribed in his place. The eleven *Intercoſtales externi*, or external Intercoſtal muſcles deſcend obliquely from the back part of the lower ſide of the upper Rib, into the fore part of the upper ſide of the Rib lying next under, after a quite contrary manner to the ſix *Intercartilaginei*, who having like original and inſertion amongſt the Griſles, as the Intercoſtal amongſt the Ribs, deſcend obliquely from the fore-part backwards. And thus much of the Muſcles dilating the Cheſt in inſpiration.

The *Subclavius* is the firſt of the Muſcles dilating the Cheſt.

Serratus major.

Serratus poſterior and *Superior.*

The oblique aſcendent of the lower Belly.

The eleven *Intercoſtales externi.*

Six Intercartilaginei.

But the firſt of the other Muſcles, being as many in number, which contract the Cheſt in expiration, ariſing from the Holy-bone, and the oblique proceſſes of the Loins, aſcends (firmly and confuſedly adhering with the *Muſculus ſacer*, or Holy-muſcle, which we ſhall deſcribe hereafter) to the roots of the twelve Ribs, imparting in the aſcent a ſmall tendon to each of them, by which it draws theſe Ribs towards the tranſverſe proceſſes; and by reaſon of its original, it is called *Sacrolumbus*, that is, the Holy-loin-Muſcle.

The *Sacrolumbus* the firſt of thoſe which contract the Cheſt.

The oblique deſcendent, the right and tranſverſe of the *Epigaſtrium.*

The ſecond, third, and fourth, which we ſaid were the oblique deſcendent, right, and tranſverſe of the *Epigaſtrium*, have been formerly deſcribed in their place.

Triangulus Muſculus.

But, by the way, you muſt note that theſe three Muſcles of the *Epigaſtrium*, help expiration rather by accident than of themſelves, to wit, by driving back the Midriff towards the Lungs by the entrails, which alſo they force upwards, by drawing the parts into which they are inſerted towards their original. The fifth, which we call the *Triangulus*, or Triangular, may be called the *Compreſſor* of the Griſles, which proceeding from the inner-ſides of the *Sternon*, goes to all the Griſles of the true Ribs; this is more apparent under the *Sternon* in Beaſts than in Men, though it be not very obſcure in them neither.

Intercoſtales interni.

For the internal Intercoſtal Muſcles, in my judgment, they ariſe, from the lower ſides of the upper Rib, and deſcending obliquely from the fore-part backwards, are inſerted into the upper ſide of the rib next under it; ſo that they may follow the production of the Fibers of the external *Intercartilaginei*; as the ſix Internal *Intercartilaginei*, follow the ſite of the external Intercoſtal, proceeding from behind forwards; wherefore as well the Intercoſtal, as the *Intercartilaginei*, every where interſect each other, after the ſimilitude of the Letter X. I know ſome have written that the Internal Muſcles (whether Intercoſtal or *Intercartilaginei*) aſcend from the upper ſide of the lower Rib, forwards and backwards.

Intercartilaginei interni.

Muſcles always receive their Nerves in their heads.

But if this were true, it would follow, that theſe Muſcles admitted their Nerves in their Tail, and not in their Head, ſeeing the Nerve always goes under the Rib, and not above it,

The Midriff.

The laſt Muſcle of the Cheſt, that is, the *Diaphragma*, or Midriff, is ſufficiently deſcribed before; wherefore it remains, we deſcribe the Muſcles of the Loins. Theſe are ſix in number, on each ſide three, equal in thickneſs, ſtrength, and ſituation; one of theſe bends, and the other two extend the Loins; it is called by reaſon of the figure, the *Triangulus* or Triangular, which bends the Loins; it aſcends from a great part of the hind-ſide of the haunch-bone into the tranſverſe proceſſes of the loins, and the laſt of the Cheſt, on the in-ſide, for which cauſe it is made of Fibers, ſhort, long, and indifferent, anſwering to the nearneſs or diſtance of the ſaid proceſſes. The firſt of the extenders is called *Semi-ſpinatus*, becauſe even to the middle of its body it takes the original from the Spines of the Holy-bones and Loins, this with its oblique Fibers aſcends from all the ſaid Spines to the tranſverſe proceſſes, as well of the Loins as Cheſt. The other is called *Sacer*, the Holy-muſcle, becauſe it takes its original from the Holy-bone, or the ſides thereof; it aſcends with its oblique Fibers to the Spines of the Loins, and of the eleven lower Rack-bones of the Cheſt.

The Muſcles of the Loins. They are three pair.

Triangulus.

Semi-ſpinatus.

Sacer.

CHAP. XIX.

Of the Muſcles of the Shoulder-blade.

NOw we muſt deſcribe the Muſcles of the extreme parts, and firſt of the Arm, taking our beginning from thoſe of the Shoulder-blade. But firſt, that we may the better underſtand their deſcription, we muſt obſerve the nature and condition of the Shoulder-blade.

There-

Therefore the Blade-bone on that part which lies next unto the Ribs is ſomewhat hollowed; wherefore on the other ſide it ſomewhat bunches out. It hath two Ribs, one above, another below; by the upper, is meant nothing elſe than a border or right line, which looking towards the Temples is extended from the exterior angle thereof under the Collar-bone even to the proceſs *Coracoides* which this Rib produces in the end thereof: By the lower, the under-ſide which lies towards the lower belly and the ſhort Ribs. The deſcription of the Blade bone, or Shoulder-blade.

Beſides, in this Shoulder-blade we obſerve the Baſis, Head, and Spine. By the *Baſis* we underſtand the broader part of the Shoulder-blade, which looks towards the Back-bone. By the Head we underſtand the narrower part thereof, in which it receives the head of the Arm in a cavity, indifferently hollow, which it produces both by it ſelf, as alſo by certain Griſles which there faſtned, encompaſs that cavity. This kind of cavity is called *Glene*. The Baſis of the Blades. The head of the Shoulder-blade.

This receives and contains the Bone of the Arm by a certain ſtrong ligament encompaſſing and ſtrengthening the Joint, which kind of ligament is common to all other Joints: this ligament ariſes from the bottom of the cavity of the Shoulder-blade, and circularly encompaſſes the whole Joint, faſtning it ſelf to the head of the Arm; there are alſo other ligaments beſide this, which encompaſs and ſtrengthen this articulation. By the Spine is meant a proceſs, which ariſing by little and little upon the gibbous part of the blade, from the *baſis* thereof where it was low and depreſt, becomes higher until it ends in the *Acromion* or upper part thereof. Nature hath made two productions in this Bone (that is to ſay, the *Acromion* from the Spine, and the *Coracoides* from the upper ſide) for the ſtrengthening of the articulation of the Arm and Shoulder-blade, that is, leſt the Arm ſhould be eaſily ſtrained upward or forwards; beſides, it is faſtned to the clavicle by the proceſs *Acromion*. The Spine of the Blade. The proceſſes. *Acromion* and *Coracoides*. The Muſcles of the Shoulder-blade.

The Muſcles which move the Shoulder-blade are ſix in number, of which four are proper, and two common. The firſt of the four proper ſeated in the fore-part, aſcends from the bones of five or ſix of the upper Ribs to the *Coracoides*, which it draws forwards, and is called *Serratus minor*, *i.e.* the leſſer Saw-muſcle; which that you may plainly ſhew, it is fit you pull the pectoral Muſcle from the Collar-bone, almoſt to the middle of the *Sternon*. The other firſt oppoſite againſt it is placed on the fore-ſide, and draws its original from the three lower ſpines of the Neck, and the three upper of the Cheſt, from whence it extends it ſelf, and ends into all the griſly *baſis* of the Shoulder-blade, drawing it backwards; It is called the *Rhomboides*. The third from its Action is called the *Levator*, or the Heaver, or lifter up, ſeated in the upper part, it deſcends from the tranſverſe proceſſes of the four firſt *Vertebræ* of the Neck into the upper angle and ſpine of the Blade. The fourth called *Trapezius* or the Table-muſcle, is ſeated in the back-part, and is membranous at the original, but preſently becomes fleſhy: it ariſes from almoſt all the back part of the head, from all the ſpines of the Neck, and the eight upper *Vertebræ* of the Cheſt, and then is inſerted by his nervous part, almoſt into the whole baſis of the blade, extending it ſelf above the Muſcle thereof, even to the midſt of the Spine, where being fleſhy it is inſerted even to the *Acromion*, the upper part of the Clavicle, and in ſome ſort to the upper rib. This Muſcle hath a three-fold action, by reaſon of its triple original. The firſt is to draw the Shoulder-blade towards its original, that is, to the Nowl and Spine of the Neck; the other is to draw it towards the Back, becauſe of the contraction of the middle or tranſverſe Fibers, which lead it directly thither; and the other to draw it downwards by reaſon of the original it hath from the fifth, ſixth, ſeventh, and eighth Spine of the *Vertebræ* of the Cheſt. *Serratus minor*. *Rhomboides*. *Levator*. *Trapezius*.

But we muſt note that theſe divers actions are not performed by this Muſcle, by the aſſiſtance of one onely Nerve, but by more, which come into it by the Spinal marrow, by the holes of the *Vertebræ* as well of the Neck as the Cheſt, from whence it takes the original. For the two other which are the common Muſcles of the Blade, and Arm, or Shoulder, we will deſcribe them with the Muſcles of the Shoulder, or Arm: for one of theſe which is called the *Latiſſimus*, that is, the broadeſt, aſcends from the Holy-bone to the Shoulder-blade and Arm. *Latiſſimus*.

The other, named the *Pectoralis*, comes from the *Sternon* and Collar-bone to the Shoulder-blade and Arm. *Pectoralis*.

CHAP. XX.

The deſcription of the Hand taken in general.

NOw it befits us to deſcribe in order the Muſcles of the Arm; but firſt we muſt know what it is that we call the Arm. But ſeeing that cannot fitly be underſtood, unleſs we know what the hand is, ſeeing that the Arm is a part of the Hand, therefore firſt we muſt define what a Hand is, and then divide it into its parts. Therefore the hand is taken two manner of ways, that is, generally and ſpecially.

The Hand generally taken, ſignifies all that which is contained from the joining of the Arm to the Shoulder-blade, even to the ends of the fingers. But in particular it ſignifies onely that which is comprehended from the furtheſt bones of the cubit, or the beginning of the wriſt, to the very fingers ends. What is meant by the Hand in general.

Therefore the hand in general is an inſtrument of inſtruments, made for to take up and hold any thing. It is compoſed of three great parts, that is, of the Arm, Cubit, and Hand, vulgarly and properly ſo called; but the hand taken thus in particular is again divided in three other parts, the *Carpus* or *Brachiale*, the Wriſt; the *Metacarpium* or *Poſtbrachiale*, the After-wriſt, and the Fingers: all theſe parts (ſeeing each of them are not onely organical parts, but alſo parts of organical parts) are compoſed of all, or certainly of the moſt of the ſimilar parts; that is, of both the Skins, the fleſhy Pannicle, the fat Veins, Arteries, Nerves, Muſcles, or Fleſh, Coats both common and proper, Bones, Griſles and Ligaments: all which we will deſcribe in their order.

But

The differences of the hand from the ſite thereof.

But firſt I think good to admoniſh you of the differences of the hand taken from the ſite thereof, and theſe differences are ſix in number, the fore, the hind, the internal, the external, the upper and lower ſide, or part thereof.

By the fore, we mean that part which looks directly from the Thumb to the Shoulder; by the hind, we underſtand the part oppoſite to it, which from the little finger looks towards the baſis of the Shoulder-blade. By the inſide, we ſignifie that part which lies next to the ſides of the body, when the Hand retains it natural ſite; by the outſide, the part oppoſite to it. The upper and lower ſide you may know by the very naming thereof.

Why the hand is divided into ſo many Fingers.

The Hand properly ſo called, is divided into five Fingers, that ſo it may hold and take up bodies; of all figure, as round, triangular, ſquare, and the like, and gather up the leaſt bodies with the Fingers ends, as Needles, Pins, and ſuch like.

Why the nails are added to the ſoft fleſh of the Fingers.

Nature hath beſtowed two Hands upon us, that ſo they may help each other, each moving to each ſide. But for the taking up and holding of ſmall bodies, it was fit that the Fingers of their own nature ſoft, ſhould be armed with Nails, that conſiſting of ſoft fleſh and a hard nail, they might ſerve for all actions; for the nail is a ſtay to the ſoft fleſh, which otherwiſe would turn away in meeting with an hard body; the uſe of the Nails is to ſcratch, ſhave, and pull off the skin, to rend, pinch, and pluck aſunder ſmall bodies. They have not bony hardneſs, that ſo they might not break but bend.

Why the nails grow continually.

Yet other Creatures have hard Nails to ſerve them in ſtead of Weapons. Their figure is round, becauſe ſuch a figure is leſs obnoxious to external injuries; and, by reaſon they are ſubject to wearing, they grow continually.

Nature hath placed fleſh on the inner and ſide part of the Fingers, ſo to preſs more ſtraitly the things they once take hold of; ſo, that beholding them cloſe together we can hold Water that it may not run out. The length of the Fingers is unequal, that when they are opened and ſtretched forth, they make as it were, a circular figure; for ſo it comes to paſs, that the hand can hold all bodies, but eſpecially round.

It remains that we proſecute the diſtribution of the Veins, Arteries, and Sinews, which run over all the parts of the Hand taken in general and particular, whereby we may more commodiouſly hereafter handle all the proper parts thereof.

CHAP. XXI.

The diſtribution of the Subclavian Vein, and firſt of the Cephalica *vr* Humeraria.

TWo large Veins deſcend from the Subclavian, the one from the lower ſide, the other from the higher. Yet ſometimes, and moſt uſually, both theſe proceed from the ſame common orifice, as in men of a low ſtature in the Arm. The one of theſe is called the *Axillaris*, the other the *Humeraria* or *Cephalick*; therefore this *Cephalick* paſſing forth of the *Subclavian* runs ſuperficially along the fore-ſide, between the Muſcle *Deltoides*, and the tendon of the pectoral Muſcle, and deſcends in the midſt between the common Coat of the Muſcles and the fleſhy Pannicle, even to the bending of the cubit, where in lean bodies it is plainly to be ſeen, whereas in fat bodies it is hardly to be perceived, being as it were buried in abundance of fat. This Vein having in its deſcent ſent forth ſome ſmall branches, both to the skin, as alſo to certain Muſcles over which it runs, is divided into two, a little above the outward protuberation of the Arm. One of the branches into which it is divided deſcending obliquely to the fore-part of the cubit, a little below the bending of the cubit, it meets and is united with the like branch in the ſame place, as ſhall be ſhewn hereafter.

The Cephalick Vein.

The Median Vein.

How by opening the Median Vein you may draw more or leſs bloud from the Head or Liver.

That which ariſes from this concourſe, is called the Median Vein, becauſe it ariſes from two branches, and is ſeated between them. They uſually open this Median Vein in the diſeaſes of the Head and Liver, which require Phlebotomy; but if it ſhall not be ſufficiently manifeſt, when you judge it muſt be opened, for a general evacuation of the whole body; you may cut one of theſe branches by whoſe concourſe it is made, which you ſhall think the fitter, and becauſe each branch draws from the next parts, according to the ſtraightneſs of the Fibers, rather than from the oppoſite ſide; if you would evacuate the Head and Liver equally by opening either of theſe branches, it is convenient that opening that branch (for example) which comes from the Cephalick, you preſently lay your Thumb upon it, until you ſuppoſe you have drawn a juſt quantity of bloud from the Liver by the *Baſilica* or Liver-vein; which done, you may take off your Thumb and ſuffer the bloud to follow freely, by the open branch of the Cephalick, until you have drawn as much bloud as you ſhall judge requiſite, otherwiſe you will draw it but from one part, to wit, the Head. So you ſhall evacuate it onely from the Liver, if you open the branch which comes from the *Baſilica*, and concurs to the generation of the Median.

Moreover, when there is need to open the *Baſilica*, and it ſhall be no where conſpicuous, the Cephalick or Median being eaſie to be diſcerned at the ſame time, you may in ſtead thereof open the Median, or if it be not to be found, the Cephalick, preſſing but the trunk thereof with your Thumb, as we ſaid before, leſt the Head ſhould be evacuated in ſtead of the Liver. You may do the ſame in the *Baſilica*, if when there ſhall be neceſſity to open the Cephalick, it ſhall not appear. Moſt of thoſe which at this day open a Vein, in ſtead of the Median, open that branch of the *Baſilica* which aſcends together with the Cephalick to make the Median. But you muſt underſtand that the Median deſcends between the two bones of the cubit, even to the end thereof; and then divided into many branches, it is at length ſpent on the back of the hand behind the Thumb, the fore and middle Fingers, or the After-wriſt. Sometimes it runs back into the following branch, and

and then at the Wriſt it departs from it, to be beſtowed upon the fore-mentioned parts. The other branch of the Cephalick, which we may call the fore and outward Cephalick, deſcending directly down to the midſt of the Wand, thence wanders overthwart into the hind part of the Arm, where increaſed with a branch from the *Baſilica*, it is diſtributed over all the back of the hand, which with the Median it nouriſheth. But the branches of theſe Veins do ſo run through the fore-named parts, that by the way they yield them neceſſary proviſion.

CHAP. XXII.

The Deſcription of the Axillary Vein.

THe Axillary ariſing at the inſertion of the pectoral muſcle, or a little higher, after it hath produced the two *Thoracicæ*, it is divided under the tendon of that Muſcle into two fair branches, that is to ſay, into the inner deep Axillary, and the skin or outward Axillary. The deep or inner having ſtill for his Companion in his deſcent, the Axillary Artery, and the Nerves of the third conjugation, after it hath produced the ſmall external muſculous of the Arm, it goes into the bending of the elbow, where running ſomewhat deep with the Artery and Nerve into the Muſcles of the cubit, it is divided into three other branches, of which one deſcending with the Wand, ſlides under the ring into the inner ſide of the hand, and hath beſtowed two ſmall branches on the Thumb, two others on the fore, and one upon the middle finger, ſo that all of them aſcend by the ſides of theſe fingers, the other deſcending with the Artery, as the former alongſt the cubit ſends branches to the reſt of the fingers, like as the former. The third goes on the fore-ſide between the two bones even to the wriſt, and the ſquare Muſcle. The axillary is divided into the deep Axillary, and outward Axillary

But you muſt note that the Veins of which we now treat, do not onely make theſe diviſions mentioned by us, but infinite others beſides, as well in the parts which they go to, as alſo in the inner Muſcles of the hand which they nouriſh.

And thus much of the internal and deep axillary Vein. For the external or skin-axillary (which firſt appears under the skin, eſpecially in lean bodies, a little above the inward production of the arm) it is divided in that place into two branches, the one whereof deſcending to the bending of the Arm meets, and is united with the Cephalick branch, ſooner or later, that ſo it may produce the Median, as we formerly mentioned.

The other branch having ſent forth many ſhoots of a different length and thickneſs, as well into the skin, as into the other neighbouring parts, deſcending alongſt the lower ſide of the bone of the cubit, properly ſo called, is at length ſpent upon the fore and outward Cephalick branch, which we ſaid deſcended alongſt the Wand; and thus united, they run over all the hand, where in the right hand, between the middle and fore-finger, they make the *Salvatella*; but in the left, in the ſame place they produce the *Splenitica*. The *Salvatella* and *Splenitica*.

But always remember, (if in diſſection you find any thing otherwiſe than we have delivered it) that the diſtribution of the Veſſels is ſo various, (eſpecially in the hands) that there can no certain rule be delivered thereof.

CHAP. XXIII.

The Diſtribution of the Axillary Artery.

THe Axillary Artery from the firſt original, which is preſently after the the two *Thoracicæ* deſcending between the Muſcle called *Biceps*, or the two-headed Muſcle, and the *Brachicus*, with the deep Axillary Vein, diſtributes a large branch amongſt the outward Muſcles of the Arm, which extend the cubit, and is ſpent in the external Muſcles of the ſame, which ariſe without from the productions of the Arm.

And this is called the *Ramus Muſculus* or muſculous branch, as alſo the Vein that accompanies this Artery. Then this Artery when it comes to the bending of the Cubit, thruſting it ſelf into the Muſcles bending the Fingers, communicates certain branches to the parts pertaining to the de-articulation of the Cubit with the Shoulder, and other parts there ſituate, as it did in the upper parts, by which it deſcended hither. Verily it may be a general Rule, that every Veſſel ſends or beſtows certain portions thereof by the way to all the parts by which it paſſes. But if you ſhould ask, why I have not proſecuted theſe productions? I would anſwer, I never intended to handle other then large and fair branches of Veſſels, by raſh inciſion of which, there may happen danger of death or a diſeaſe. For it would be both an infinite and needleſs buſineſs to handle all the divarications of the Veins, Arteries, and Nerves. Therefore this Artery ſunk into theſe Muſcles, when it comes almoſt to the midſt of the Cubit; preſently, or a little after it is divided into two large branches, the one of which alongſt the Wand, and the other alongſt the Cubit, is carried into the hand on the inſide under the Ring. For both theſe branches are diſtributed and ſpent upon the hand after the ſame manner as the branches of the internal axillary Vein, that is, having ſent by the way ſome little ſhoots into the parts by which they paſs, at the length the branch which deſcends by the Wand of the remainder thereof, beſtows two ſprigs upon the Thumb, on each ſide one, and two in like manner on the fore-finger, and one on the middle; the other which runs alongſt the Ell, performs the like office to the little and the middle or Ring-finger, as you may ſee by diſſection. An Anatomical Axiom.

CHAP.

CHAP. XXIV.

Of the Nerves of the Neck, Back, and Arm.

The 7 pair of Nerves of the Neck.

NOw we ſhould handle the ſinews of the Arm, but becauſe theſe proceed from the Nerves of the Neck and Back; I think it fit therefore to ſpeak ſomething of them in the firſt place.

The firſt pair.

Therefore from the Neck there proceeds ſeven pair of Nerves, the firſt of which proceeds from the Nowl-bone, and the firſt *Vertebra* of the Neck; as alſo of the firſt pair of the Back from the laſt *Vertebra* of the Neck, and the firſt of the Cheſt. But all theſe Nerves, divided into two or more branches of the firſt pair (that is to ſay, on each ſide) go, the one to the ſmall right Muſcle, aſcending from the firſt Rack-bone of the Neck to the Nowl-bone, the other to the long Muſcle on the fore-ſide of the Neck.

The ſecond pair.

The branches of the ſecond pair are diſtributed, ſome with a portion which they receive from the third pair over all the skin of the head; the two others go as well to the Muſcles, which are from the ſecond *Vertebra* to the back-part of the head; and from the ſame to the firſt *Vertebræ*, as alſo to the long Muſcle before-mentioned.

The third pair.

One of the third pair of ſinews is communicated to the Head, as we ſaid before, but others to the Muſcles which extend, or erect the Head and the Neck; there is alſo one of theſe diſtributed into the neighbouring ſide-Muſcle and part of the long.

The fourth pair.

The Nerves of the fourth pair go, one to the Muſcles as well of the Neck as the Head, and to the broad Muſcle; the other, after it hath ſent ſome portion thereof into the long Muſcle and the ſide-

The fifth pair.

Muſcles of the Neck; it deſcends with a portion of the fifth and ſixth pair to the Midriff. One of the branches of the fifth pair is beſtowed on the hind Muſcles of the Neck and Head, the other upon the long-Muſcle and Midriff; the third is communicated to the *Levatores* or Heaving-Muſcles of the Arm and Shoulder.

The ſixth pair.

One of the Nerves of the ſixth pair goes to the hind-Muſcles of the Neck and Head, another to the Midriff, the third with a portion of the ſeventh pair of the Neck, and of the firſt and ſecond of the Cheſt go to the Arms, and heaving-Muſcles of the Shoulder-blade.

The ſeventh pair.

One of the branches of the ſeventh pair runs to the broad-Muſcle, and to the neighbouring Muſcles both of the Neck and Head; another, increaſed with a portion of the fifth and ſixth pair of the Neck, and a third joined to the ſecond and third pair of the Cheſt deſcending into the Arm, go to the Hand.

But you muſt note that the Muſcles which take their original from many *Vertebræ*, whether from above downwards, or from below upwards, admit Nerves not onely from the *Vertebræ* from whence they take their original, but alſo from them which they come near in their deſcent, or aſcent.

The 12 pair of Nerves of the cheſt.

There paſs twelve Conjugations of Nerves from the Rack-bones of the Cheſt.

The firſt pair.

The firſt entering forth from between the laſt Rack-bone of the Neck and the firſt of the Cheſt, is divided (that is, on each ſide each Nerve from his ſide) into two or more portions, as alſo all the reſt. Therefore the branches of this firſt Conjugation go ſome of them to the Arms, as we ſaid before, others to the Muſcles, as well theſe of the Cheſt, as others ariſing there, or running that way.

The ſecond pair.

The branches of the ſecond Conjugation are diſtributed to the ſame parts, that theſe of the firſt were.

The other pairs.

But the branches of all the other Conjugations even to the twelfth, are communicated, ſome to the intercoſtal Muſcles running within under the true ribs even to the *Sternon*, and under the Baſtard-ribs even to the right and long Muſcles; and the coſtal Nerves of the ſixth Conjugation are augmented by meeting theſe intercoſtal branches by the way as they deſcend by the roots of the Ribs. Other particles of the ſaid Nerves are communicated to the Muſcles as well of the Cheſt as Spine, as the ſame Muſcles paſs forth, or run alongſt by the *Vertebræ*, from whence theſe Nerves have either their original or paſſage forth.

The Nerves which are carried to the Arms.

Having thus therefore ſhewed the original of the ſinews of the Arm, it remains that we ſhew their number and diſtribution.

Their number is five or ſix; proceeding from the fifth, ſixth, and ſeventh *Vertebra* of the Neck, and the firſt and ſecond of the Cheſt. The firſt of which not mixed with any other from the fifth *Vertebra* of the Neck, goes to the Muſcle *Deltoides*, and the skin which covers it.

The other four or five when they have mutually embraced each other, not onely from their firſt original, but even to the ſhoulder, where they free themſelves from this convolution, are diſtributed after the following manner.

The firſt and ſecond deſcending to the Muſcle mentioned a little before, and thence ſometimes even to the Hand, is by the way communicated to the Muſcle *Biceps*, and then under the ſaid Muſcle it meets, and is joined with the third Nerve. Thirdly, It is communicated with the longeſt Muſcle of the cubit, in the bending whereof it is divided into two branches deſcending alongſt the two bones of the cubit, until at laſt born up by the fleſhy pannicle it is ſpent upon the skin and inner ſide of the hand.

The third lower than this, is firſt united with the ſecond, under the Muſcle *Biceps*, and then ſtraightway ſeparated from it, it ſends a portion thereof to the Arm which lies under it, and to the skin thereof; laſtly, at the bending of the cubit on the fore-ſide, it is mingled with the fifth pair.

The fourth the largeſt of all the reſt, coming down below the third branch under the *Biceps* with the internal Axillary Vein and Artery, is turned towards the outward and back-part of the Arm, there to communicate it ſelf to the Muſcles extending the cubit, and alſo to the inner skin

of

of the arm, and the exterior of the cubit; the remainder of this branch when in its deſcent it hath arrived at the joynt of the cubit, below the bending thereof it is divided into two branches, the one whereof deſcending alongſt the cubit, is ſpent on the outſide of the wriſt; the other aſſociating the wand, is on the outſide in like manner in two branches, beſtowed upon the thumb, and in as many upon the fore-finger, and by a fifth upon the middle finger, though more obſcurely.

The fifth branch being alſo lower than the reſt, ſliding between the muſcles bending and extending the cubit, when it comes behind the inner protuberation of the cubit (in which place we ſaid before the third branch meets with this) it is communicated to the internal muſcles of the ſame, and then divided into three portions, one of which on the outſide alongſt the middle of the cubit, goes in two ſprigs to the little finger, and ſo many to the middle finger, and one to the ring-finger; the other two, the one without, and the other within the ring, go to the hand: where after each of them hath beſtowed what was requiſite on the muſcles of the hand, they are waſted into other five ſmall portions, of which theſe which are from that portion which deſcends without the ring, ſend two ſprigs to the little, two to the fore, and one to the middle finger, but thoſe which come from that which paſſes under the ring, by ſuch a diſtribution communicates it ſelf to other fingers, as two ſprigs to the thumb, two to the fore, and one to the middle-finger. The ſixth the loweſt, and laſt, runs between the skin and fleſhy pannicle, by the inner protuberation of the arm, and then is ſpent upon the skin of the cubit.

CHAP. XXV.

The deſcription of the Bone of the Arm, and the muſcles which move it.

BEcauſe we cannot perfectly demonſtrate the original of the muſcles of the arm, (eſpecially of the two arm-muſcles) not knowing the deſcription of this bone; firſt therefore we will deſcribe it, then return to the original of the muſcles ariſing from thence. The bone of the arm is the greateſt of all the bones in the body, except the thigh-bone; it is round, hollow and filled with marrow, with a great appendix, or head, on the top thereof, having an indifferent neck, to which it is knit by *Symphyſis*, for appendices are no otherwiſe united to their bones. In the lower part thereof it hath two proceſſes, or protuberations, one on the foreſide, another on the hind, between which ſwellings there is a cavity like to half the compaſs of a wheel, about which the cubit is moved. The extremity of this cavity ends in two holes, of which one is the more external, the other more internal: Theſe cavities receive the heads of the cubit, that is, the fore, or internal, receives the fore proceſs when the arm is bended inwards; but the external or hinder, the exterior as it is extended.

The greatneſs and figure. The appendix of the arm. The proceſſes of the arm.

For the head of the arm, it hath a double connexion, the one with its own neck by *Symphyſis*; that is, a natural union of the bones without any motion; the other with the lightly ingraven cavity of the ſhoulder-blade, which we call *Glene*, by that kind of de-articulation which is called *Arthrodia*: This connexion is made firm and ſtable by the muſcles deſcending into the arm from the ſhoulder-blade, as alſo by the proper ligaments deſcending from the circle and brow of the cavity of the *Acromion* and *Coracoides* to this head of the arm; this ſame head of the arm is, as it were, more cleft and open on the inner-ſide, than on the foreſide, that ſo it may give way to one of the ligaments coming from the ſhoulder-blade to the muſcle *Biceps*. Foraſmuch as belongs to the lower end of the bone of the arm (which we ſaid hath two proceſſes;) we may ſay that it is faſtened to the bones of the cubit by two ſorts of articulation; that is, by *Ginglymos*, with the Ell or proper bone of the cubit; and by *Arthrodia*, with the *Radius*, or Wand, which in a lightly ingraved cavity receives the fore proceſs of the arm, and is turned about it for the motion of the hand. The hinder proceſs is chiefly added for the ſafety and preſervation of the veins, arteries and nerves.

Theſe things thus ſhown, it is worth our labour to know the figure of the arm it ſelf, as it lies between the fore-mentioned appendices and proceſſes; that, in the caſe of a fracture, we may know how conveniently to reſtore it; therefore firſt we muſt underſtand, that this bone is ſomewhat bended and hollowed on the inſide under the cleft of the head thereof, but bunching out on the out and fore-ſide.

The figure of the arm.

Wherefore ſeeing it muſt be moveable forwards and backwards, upwards and downwards, Nature for the performance of ſo many motions hath furniſhed it with eight muſcles, which are ſix proper and two common with the ſhoulder-blade. Of which number, two move it forwards, two backwards, two upwards, two downwards. Which muſt not be underſtood ſo, as that theſe two muſcles ſhould move it directly forwards, inclining neither upwards nor downwards; and the other two ſhould move it ſo upwards, as it ſhould incline neither forwards nor backwards; but thus, That it cannot be moved neither to this nor that part, unleſs by the help and proper action of this, or that muſcle. Thus therefore, if the pectoral with his aſſociate perform their duty; or action, the arm is always moved forwards, as it is lifted up by the action of the *Deltoides*, and his companion, and ſo of the reſt.

The eight muſcles thereof.

But to come to the original and inſertion of theſe muſcles; the one of theſe two which move the arm forwards called by reaſon of his original, the Pectoral, ariſing from more than half of the Collar-bone; and almoſt all the *Sternon*, and the ſixth, ſeventh and eighth rib, goes up and faſtens it ſelf to the *Coracoides*, by a membrane or a membranous tendon ſufficiently ſtrong (for which cauſe it is ſaid to be common to the ſhoulder and arm) and it goes into the arm between the muſcles *Deltoides* and *Biceps* with a ſtrong tendon compoſed of fibers croſſing each other, of which ſome deſcend from the Collar-bone, and the upper part of the *Sternon*, others aſcend from the lower original hereof; that is, from the ſixth, ſeventh and eighth ribs; and although the action of this muſcle be diverſe by

The original and inſertion of the pectoral muſcle.

reaſon of the diverſity of its fibers ariſing from divers places, yet always it draws the arm forwards, whether it be moved upwards, downwards, or to the breaſt; the other which is his companion, deſcends from the whole lip or brow of the ſimous, or hollow part of the blade, which it fills in the fore-part of the arm near the head thereof. For the two *Levatores*, or the lifters up of the arm, the
The *Deltoides.* firſt named *Deltoides*, deſcends almoſt from half the clavicle, the proceſs *Acromion*, and all the ſpine of the ſhoulder-blade into the fore-ſide of the arm, the breadth of four fingers below the joynt. It hath divers actions according to the diverſity of the fibers, as alſo every muſcle hath; yet howſoever it is contracted, whether by the fibers from the clavicle alone, or by the ſpinal alone, or by both at once, it always lifts and heaves the arm upwards. The other which is his Aſſociate deſcends from the gibbous part of the ſhoulder-blade, contained between the upper rib thereof, and the
The *Epomis*, or *Scapularis.* ſpine between the proceſſes *Acromion* and *Coracoides*, to the neck of the arm; and this we will call the *Epomis* or *Scapularis*; that is, the ſhoulder-muſcle. But the firſt and larger of the two muſcles, which draw the arm backwards, ariſes from the greateſt part of the utter lip of the gibbous part of the ſhoulder-blade, which is under the ſpine thereof, and lying upon the blade it ſelf, it goes into the hind-part of the arm above the neck thereof. The other which is contiguous to it, and his partner in working, but leſſer, paſſes from the upper and exterior part of the lower rib of the ſhoulder-blade, and thence, as it were, in ſome ſort extending it ſelf upon the gibbous part thereof, near unto that rib, it goes into the arm. This muſcle ſeems to be the ſame with the former, being fleſhy without, even above the top of the ſhoulder. One and the leſſer of theſe two which draw downwards, enters out from the ſtait line of the lower rib of the blade, and goes into the lower part of the arm about the neck thereof. The other called the *Latiſſimus*, or broadeſt, aſcends from the ſpines of the holy-bone of the loins, and often alſo from the nine lower of the cheſt, by the lower corner of the ſhoulder-blade into which it is inſerted by a membranous tendon, as alſo it is into the inner part of the arm near the neck by another ſtrong tendon; whereupon this muſcle is called a common muſcle of the ſhoulder and arm. But when this muſcle happens to be wounded, the arm cannot eaſily be ſtretched forth, or lifted up.

Table 24. *Sheweth the Brain together with the After-brain, the Spinal Marrow and the Nerves of the whole Body.*

A *That part of the brain that is next the noſtrils.*
B *That part which is at the ſide of ventricles.*
C *The back part of the brain.*
D *The* Cerebellum *or After-brain.*
E *The mammillary proceſs in the right-ſide.*
F *The original of the optick-nerve.*
G *Their conjunctions.*
H *The coat into which the optick-nerve is extended.*
I *The ſecond pair of the ſinews of the brain.*
K *The leſſer root of the third conjugation.*
L *The thick root of the ſame conjugation according to the common opinion.*
M *The fourth conjugation of the ſinews.*
N *The leſſer root of the fifth pair.*
O *The bigger root of the ſame pair.*
P *The ſmall membrane of the ear which they call the* Tympany.
Q *The lower branch of the bigger root of the fifth conjugation.*
S *The ſixth pair of ſinews.*
T *The ſeventh pair.*
V *The beginning of the ſpinal marrow out of the middle of the baſis of the brain.*
X *The right ſinew of the midriff cut off.*
Y *A branch from the fifth pair creeping to the top of the ſhoulder.*
Z *The firſt nerve of the arm, from whence there goeth a branch to the skin.*
A *The ſecond nerve of the arm, and a branch therefrom into the firſt muſcle of the cubit.*
B *The third nerve of the arm, and a branch going to the skin on the out-ſide.*
C *A branch from the third nerve to the ſecond muſcle of the cubit.*
D *The congreſs, or meeting, of the ſecond nerve with the third.*
E *A ſmall branch from the third nerve to the ſecond muſcle of the* Radius.
F *The diſtribution of the ſecond nerve into two branches.*
* *The leſſer branch of this diviſion lengthened out to the skin as far as the thumb.* a *The place of the ſpinal*

nal marrow, where it iſſueth out of the brain, 1 2 3, &c. *Thirty pair of nerves ariſing from the ſpinal marrow are here noted by their Char. that is to ſay, ſeven of the neck, twelve of the cheſt, five of the loins, and ſix of the holy-bone.* b *The thicker branch of the ſecond nerve divided into two parts.* c *Branches of the the third nerve ſprinkled here and there.* d *Nerves from the third pair to the thumb, the fore-finger and the middle-finger.* ee *The fourth nerve of the arm.* f *The paſſage hereof through the inſide of the ſhoulder.* g *A tripartition of this branch where it toucheth the cubit.* hh *A branch diſtributed from the fourth nerve to the outward skin of the cubit.* i *The upper branch of the diviſion of the fourth nerve.* kk *A branch of* i, *reaching it to the outſide of the hand.* ll *The lower branch of the diviſion of the fourth nerve paſſing through the back-ſide of the cubit.* m *The fifth nerve of the arm.* n *Branches of this nerve diſperſed here and there.* oo *A branch of the fifth nerve, reaching to the inſide of the hand and the fingers.* p *A ſurcle of the branch* o, *derived to the outſide of the hand and fingers,* q q *The ſixth nerve of the arm and the courſe thereof under the skin.* r r *The intercoſtal nerves there cut off where they are together with the ribs reflected forward.* ſ ſ *Branches on each ſide running backward.* t t *Nerves attaining unto the cheſt.* u u *The commixtion of the nerves* r r *with the deſcending branch of the ſixth conjugation of the brain.* xx *Nerves from the loins led unto this place.* y *A branch going to the teſticles here cut off.* z *A nerve reaching to the firſt muſcle of the thigh.* c *The firſt nerves of the leg.* α β *A ſurcle of the former nerve derived to the skin at* α, *and inſerted into the muſcles at* β γ, *the ſecond nerve of the leg.* δ δ δ *A nerve from the former, allowed unto the skin as low as to the foot, and paſſing along the inſide of the leg.* ε *A branch of the ſecond nerve running unto the muſcles.* ζ *The third nerve of the leg.* η *A ſurcle thereof unto the skin.* θ *Another ſurcle unto the muſcles.* ι ι *The fourth nerve of the leg.* κ κ *The* anterior *propagation of the nerves proceeding from the holy-bone.* λ *The end of the ſpinal marrow.* μ *A branch from the fourth nerve inſerted into the muſcles ariſing from the* Coxendix, *or hip-bone.* ν *Another branch going to the skin of the thigh on the back-ſide.* ξ *A propagation derived to the fourth muſcle of the leg, and to the skin of the knee.* o o *Nerves attaining to the heads of the muſcles of the foot.* π ρ *The diviſion of the fourth crural nerve into two trunks* σ *a branch from the trunk* ϖ *diſperſed into the outward skin of the leg.* τ *A ſurcle of the trunk* ϖ, *derived to the muſcles.* υ *Another ſurcle to the skin of the leg on the fore-ſide.* Φ *A branch of the trunk* ρ, *to the skin of the inſide of the leg, and of the foot,* χ *A ſurcle of the trunk* ρ, *to the hind-moſt skin of the leg.* ψ *A branch of the whole trunk* ρ, *led along to the forward part of the leg and the foot.* ω *The deſcent of the trunk* ρ *into the foot.*

CHAP. XXVI.

The deſcription of the Bones of the Cubit and the Muſcles moving them.

AFter theſe Muſcles, follow thoſe which bend and extend the Cubit, but becauſe their inſertion cannot be fitly demonſtrated, unleſs the bones of the cubit be firſt deſcribed; therefore firſt of all, we will delineate the bones themſelves. But verily, leſt this doubtful word *Cubit* ſhould cauſe obſcurity; firſt, we muſt note, that it hath a threefold ſignification, for oft-times it is uſed for all that part of the hand which lies between the arm and wriſt, oft-times for the lower bone of this part, ſometimes for the upper part of this bone, which is turned within the orb, or cavity of the arm (no otherwiſe than a cord in the wheel of a Pulley) and this is called the *Olecranon*. Here truly we uſe this word *Cubit* in the firſt ſignification. Wherefore, we ſay, the cubit is compoſed of two bones, the one of which we call the *Radius*, or Wand, or the leſſer *Focile* of the arm; the other we properly call the Cubit, or Ell. Theſe two bones ſtick together at their ends being firmly bound together by ſtrong ligaments; but the middle-parts of them are a pretty way diſtant from each other, and chiefly towards their lower ends, for the better ſituation and paſſage of the muſcles and veſſels from the inner ſide to the exterior, as ſhall be ſhewed in fit place. The wand hath two *Epiphyſes*, or Appendices, the one at the upper end, the other at the lower. The upper is round and hallowed on the ſurface like a Baſon, it receives the fore proceſs of the bone of the arm, bound to the ſame by ſtrong ligaments, deſcending as well from the proceſs of the arm, as the *Olecranon* into the circumjacent parts of this appendix of the wand. This connexion is made for this uſe, that we may turn our hand upwards and downwards by the cubit turned and twined about this proceſs. But the lower appendix of this wand is hollowed on the inſide, that ſo it might more commodiouſly receive the bones of the wriſt; but gibbous without, that it might be ſafer: Now this wand is ſofter and thicker at the lower end, but leſſer and harder above, where on the inſide it hath a ſwelling out, whereby to receive the muſcle *Biceps*: Beſides, on the out-ſide of the middle thereof it is ſomewhat gibbous and round, ſo to become more ſafe from the injuries of external bodies; but it is hollowed or bended on the inſide, for the better taking and holding any thing in the hand. But that ſide which which lies next to the Ell is flatted for the fitter original and ſeat of the Muſcles; laſtly, it is ſeated upon the bone of the Cubit, or Ell, juſt againſt the thumb. But the Ell, or bone of the cubit properly and particularly ſo called, hath in like manner two appendices, the one above, the other beneath. The upper, which alſo is the greater, is fitted to the orb of the arm in which it goes to and again for the extenſion and bending of the arm, no otherwiſe than a rope runs in a pulley, but that it turns not abſolutely and perfectly round, which is cauſed by the two proceſſes of unequal bigneſs, the which are therefore ſtayed in the holes or cavities of the bone of the arm, the greater proceſs which we called *Olecranon* is letted by the exterior hole, that ſo the extenſion of the arm can be no further, but the leſſer proceſs by the inner hole, makes the bending thereof the leſs perfect. The compoſure of theſe bones is by *Ginglymos*, and it is ſtrengthned not only by common ligaments coming from the muſcles, which move the bones themſelves, but alſo by proper liga-

What is meant by the cubit.

What the *Olecranum* is.

The two bones of the cubit.

The two appendices of the wand.

The figure and ſite of the wand.

The appendices of the bone of the cubit.

ments, deſcending from the proceſſes of the arm and the lips of the holes and cavities ſtanding about the appendix of the cubit. The other lower and leſſer appendix is in ſome ſort hollow on the inſide for the fitter receiving the bones of the wriſt, but the outſide is round, and ends in a point, which is called by the Greeks *Styloides*. But now this Ell (contrary in this to the wand) is thicker towards the arm, but ſlenderer towards the wriſt. And beſides, in the thicker part thereof, it is hollowed or bended towards the inſide, and in the ſame place is gibbous or bunching forth on the outſide: but it is round and ſtrait, unleſs on that ſide which lies next the wand: For the reſt, it is hollow and full of marrow like the wand. The ſite of the *Radius*, or wand, is oblique, but that of the cubit or ell, is right, that the arm might be the better and more eaſily moved; becauſe the motion by which the arm is extended and bended, is according to a right line, but that by which the inſide of the hand is turned upwards and downwards, is performed obliquely and circularly. Wherefore it was expedient, that the wand ſhould be oblique, and the cubit ſtrait; for the cubit-bone is appointed for to extend and bend the arm, but the wand to perform the wheeling and turning about thereof; and this is the cauſe that it was fitting, there ſhould be a different connexion of theſe bones with the arm. Theſe things were fitting to be ſpoken concerning the nature of theſe bones, that in the cure of fractures we may work the more ſafely and happily, taking indication from that which is agreeable to nature: Wherefore now it remains, that we come to the deſcription of the muſcles which are ſeated in the arm, the cubit-bone or ell. Theſe are four in number, two extending it, and two bending it. The firſt of the benders is called *Biceps*, by reaſon of its two heads, the one whereof deſcends from the *Coracoides*, the other from the lip of the cavity of the ſhoulder-blade by the fiſſure or cleft of the head of the bone of the arm. Theſe two heads under the neck of this arm becoming fleſhy, are firmly united at the belly and midſt of the arm, and thus united, are at the length implanted by a ſtrong tendon to the inner protuberation of the wand. The other is called the *Brachiæus*, by reaſon of the ſtrait coherence thereof with the bone of the arm; this faſtened under the *Biceps*, deſcends obliquely on the back and upper part of the bone of the arm into the top of the wand and the inner ſide of the ell. But the firſt of the extenders is called the *Longus*, or long-muſcle; this deſcends from the lower rib of the ſhoulder, and cleaving to the bone of the arm, goes thither (faſtened, and as it were always ſtraitly joyned with his fellow-muſcle, ſpecially near the cubit) wherefore you ſhall preſently hear. The other, termed the *Brevis*, or ſhort muſcle, being the companion of the long, deſcends on the hind-part of the neck of the bone of the arm, as it were growing to, and lying under the former long-muſcle, ſo that making one common broad tendon outwardly fleſhy, inwardly nervous, they are inſerted into the *Olecranum*, ſo by mutual aſſiſtance to extend the cubit.

The figure of the cubit bone or ell.

The muſcles moving the cubit.

The *Biceps*, or two-headed muſcle.

The *Brachiæus*.

The *Longus*.

The *Brevis*.

CHAP. XXVII.

The Deſcription of the Bones of the Wriſt, After-wriſt and Fingers.

What the hand properly ſo called is.

WE ſaid before, that the hand taken more particularly, and properly, is divided into the wriſt, after-wriſt, and fingers; and that the hand in this ſignification is bounded by the ends of the bones of the cubit and fingers. All the parts of the wriſt, which it hath common with the after-wriſt, have been already alſo plentifully explained: This only remains to be noted, that the skin as well of the hands as of the feet, is of a middle nature between pure fleſh, and pure skin; no otherwiſe than that which covers the forehead, but that this which covers the palms of the hands, and ſoles of the feet, is unmoveable: But it is moſt thick, eſpecially on the feet, leſt it ſhould be eaſily offended by continual going. Beſides the common parts, the wriſt is compoſed of eight ſmall bones mutually knit together in a certain order, and by *Diarthroſis* with the two bones of the cubit, but mutually and amongſt themſelves by *Synarthroſis*, by interpoſition of griſtles and ligaments as well common, that is, coming from the muſcles, as proper, deſcending always from the upper to the lower. But theſe ſame bones are ſome leſs than otherſome; beſides, they are hard, and without marrow, gibbous on the outſide for the ſecurity and comelineſs of the hand, but hollow on the inſide for to give way to the tendons going into the fingers. Theſe bones are diſpoſed in two ranks, the firſt rank contains only three, but the ſecond five. The three of the firſt rank are thus arrayed, or placed, that one of them may receive the appendix *Styloides*, of the cubit; the other the ell and the wand together; and the third may be received by the wand. But three of the five bones of the ſecond order ſuſtain the four bones of the after-wriſt, and are knit to the ſame by *Synarthroſis*; after which manner of connexion they are joyned to the bones of the firſt rank; the fourth ſuſtains the firſt bone of the thumb, to which alſo it is co-articulate by *Synarthroſis*; the fifth and laſt is ſeated on the inſide againſt the ell, chiefly above that bone of the firſt order, which receives the appendix *Styloides* of the cubit: This is leaſt and weakeſt of them by reaſon of its griſtly ſubſtance, which makes the ring with certain ligaments running from one of the inner ſides of the wriſt to the other.

What the *Annulus* or ring is.

This ring is placed there, as well for the preſervation of the ſinews, veins and arteries paſſing under it (leſt when we lean upon our hand and wriſt, theſe parts ſhould be hurt by compreſſion) as alſo for the commodity of the action of the muſcles bending the finger, which in the performance of their action and the contracting themſelves, might deform the hand by their paſſing forth of the cavity of the wriſt. For what attraction ſoever is made by ſtrings, if it be free, and not hindred, is according to a ſtrait line.

The bones of the after-wriſt.

Now follow the bones of the ſecond part of the hand, or of the after-wriſt. Theſe are four in number, gibbous without, but arched within, or hollow in the middle; for, hence is the palm of the

the hand, or certainly the greater part thereof; their ends next the fingers are somewhat remote from each other, that in these clifts the muscles *Interosses* might find a place and seat. But these ends have each an appendix, as you may perceive in the Sceleton of a Child. But you must note, that by the first bone of the wrist, or after-wrist, we mean that which is in the fore-side of the hand, that is to say, that in the wrist which lies under the thumb, and that in the after-wrist, which is seated under the fore-finger, as those which keep in order the fingers; which exceed the rest in necessity and dignity.

The Figure of the Bones of the Hand. The first sheweth the inside of the right-hand, and the second shews the back-side of the same.



The Character 1 2 3 4 5 6 7 8 *shew the eight bones of the wrist.*
A 1 2 *The first bone of the after-wrist, lying under the thumb.*
I II III IIII *The four other bones of the after-wrist annexed to the fingers.*
BC *The two bones of the thumb.*
DEF 1 2 *The three bones of the fore-finger which are the same in the other fingers.*
M 1 2 *A little bone sometimes fastned outwardly at the joynt of the eighth bone of the wrist.*
N 1 *A process of the eighth bone of the wrist, swelling out into the ball of the hand.*
O 1 *A process of the fifth bone of the wrist, from which a ligament proceeds.* P 2 *An appendix of the bones of the wrist, by which they are articulated to the after-wrist.* Q 2 *Another appendix which with its head entereth into the cavity of the finger.* R 1 2 *The space between the bones of the after-wrist.* S 1 2 *Two little seed-bones set on the inside and outside of the first joynt.* T 1 *Two seed-bones in the first of the four-fingers.* V V 1 *One seed-bone in the second and third joynt of the fingers.*

After these follow the fifteen bones of the fingers; that is, three in each, which are hollow and fistulous, full of a thin and liquid marrow, and not of gross and thick, as in the arm and thigh, They are outwardly gibbous, but inwardly hollow and flat for the fitter seat of the tendons ascending alongst the fingers on the inside even to the upper joynt. The which that Nature might the better strengthen and preserve, it hath produced from the lips of the inner cavities of these bones a membranous and strong ligament, which running over-thwart from one side to the other, doth so straitly close the tendons to their bones, that they cannot go forth of their places, or incline to either side. They are connexed on the out-side, that they might be more fit to hold any thing. But for the first bones of the four fingers and thumb, four are joyned together with so many bones of the after-wrist by *Synarthrosis*, for the bones of the after-wrist are moved by no manifest motion; the fifth is knit to the second rank of the bones of the wrist, therefore that bone cannot be attributed to the after-wrist, as some have written, seeing it hath manifest motion and is knit by *Diarthrosis*, but the bones of the after-wrist are only fastned by *Synarthrosis*. For the second and third rank of bones of the fingers, they are knit the second to the first, and the third to the second by *Diarthrosis* and *Arthrodia*, because, besides the manifest motion they have, they receive each other by a superficiary cavity; as those of the first rank, the bones of the after-wrist; and those of the second rank, them of the first; and those of the third, them of the second. And all the bones of the fingers are larger and thicker at their basis, but smaller towards the ends; and they are bound by ligaments especially proper, which (as we said formerly) descend from the first to the second; so that the last bones, seeing they have not to whom to communicate their nerves, make and produce nails thereof: Wherefore the nails are generated by the fibers of the ligaments, and the excrement of the tendons which are terminated at the bottom of the nails. Now remain the *Ossa Sesamoidea*, or seed-bones: These are nineteen in number in the inner joynts of each of the hands, and as many in each foot, *viz.* Two in the first joynt of the four fingers, and in the second of the thumb, and one in each of the rest. For the inner side of the joynts, you may for the most part observe one in each of them; yet in the second joynt of the thumb there be two above the two tendons, which are somewhat gristly.

The bones of the fingers.

Whence the nails are generated.

The *Ossa Sesamoidea*, or seed-bones.

They are made for this use, that they may firm and strengthen the joynts, so that the bones of the fingers may not be turned awry, or thrust forth of their places by strong and violent motions, as it sometimes happens in the whirlbone of the knee. They are called *Sesamoidea*, from the resemblance they have to the seed of *Sesamum*, which is somewhat long and flat.

Their use.

CHAP. XXVIII.

Of the Muſcles, which ſeated in the cubit, move the Wand, and with it the hand.

The muſcles of the cubit.

NOw we muſt deſcribe the muſcles of the formerly deſcribed parts; that is, thoſe which are ſeated in the cubit, which are carried to the inſide of the hand, and thoſe which are called the *Interoſſes*. Now the muſcles of the cubit are fourteen, ſeven external, and ſeven internal; two of the ſeven external do primarily twine or turn up the Wand; and ſecondarily, or by accident, turn the palm of the hand upwards, whereupon they have called them *ſupinatores*, or turnes up of the hand; two extend the wriſt, whereupon they are named *Carpi-tenſores*, or the wriſt-extenders; two the fingers, whence they are ſtiled *Digitum-tenſores*, or finger-ſtretchers; to conclude, the ſeventh and laſt is termed *Abductor*, or *Obliquator externus*.

The *Supinatores.*

The *Carpitenſores.*

The *Digitumtenſores.*

The *Obliquator externus.*

The firſt of the two *Supinatores* is called the long, or longeſt, becauſe it deſcends from the outſide of the arm above the proceſſes thereof, and is inſerted by a round and ſtrong tendon into the lower appendix. The other deſcends obliquely from the outward and upper proceſs of the arm, and is inſerted at the third part of the wand by a membranous and fleſhy tendon before, and on the inſide thereof. The upper of the two extenders of the wriſt, deſcending above the wand from the external and upper proceſs of the arm, is inſerted by two tendons into the firſt and ſecond bone of the after-wriſt, which ſuſtain the fore and middle-fingers.

The firſt of the *Supinatores.*

The ſecond.

The upper of the *Carpitenſores.*

The lower.

The other and lower, deſcending from the ſame place as the former, above the cubit, is inſerted into the fourth bone of the after-wriſt which bears up the little-finger. Theſe muſcles whilſt they move alone, that is, each with his Antagoniſt, to wit, the wriſt-benders, they move obliquely, upwards or downwards, the whole hand properly ſo called. The firſt and greater of the extenders of the fingers, or finger-ſtretchers, ariſing from the *Olecranum*, or bone of the cubit, deſcends ſuperficiarily between the two bones of the cubit even to the wriſt, in which place it is divided into four tendons, which paſſing under the ring ſeated there, end (each diſtinguiſhed by a common ligament above the bone of the after-wriſt) in the laſt joynts of the four fingers, adhering nevertheleſs firmly to the bones, which are above theſe joynts.

The greater of the *Digitumtenſores.*

The leſſer.

The other, which is the leſſer, ariſing almoſt in the middle of the wand, goes obliquely to the thumb, into which it is inſerted by two tendons: The one thicker, which is inſerted into the root thereof, and draws it from the other fingers; the other ſlenderer continued even to the upper joynt thereof, and by its action extending the thumb.

The *Obliquator* or *Abductor externus.*

The ſeventh, which is the *Abductor* or *Obliquator*, is ſeated at the hind-part of the hand; that is, towards the little finger: We have often found this divided into two, yea verily we have found it trifide, or divided into three, this year in three or four bodies; one portion thereof went to the lower ſide of the ring-finger with two tendons, the other in like manner to the middle and fore-fingers, and the third to the thumb.

And for all that it is thus divided, yet ſome have taken and accounted it for one muſcle, becauſe it hath one original and action, which is, to draw the fingers backwards; ſome have added to this the extender of the thumb, by reaſon of their common original; and thus of four muſcles they have made one, divided into ſeven tendons, diſtributed, as is formerly ſhewed. But when the *Obliquator* of the ring-finger is wanting, as it often happens, the extender of the finger ſupplies that defect by certain productions of tendinous ſtrings. But ſome alſo have written, that this muſcle which we ſaid hath ſeven tendons, is only a production of the deep fore-muſcle, which ſhould be ſent through the ſpace between the bones of the cubit; yet I had rather make it a muſcle of it ſelf, by reaſon of its ſtrait adheſion with the bones of the arm and wand. And let thus much ſuffice for the external muſcles of the cubit, which you may comprehend in the number of ſeven, as we have done; or in ſix, if you take away one of the four; or in nine, if you had rather reſolve it into four with *Galen*; or in eight, if you divide this muſcle only into three. For in very deed the *Abductor* or *Obliquator* of the ring-finger is not often found in men.

The muſcles of the inner part of the cubit.

Now muſt we come to the inner muſcles of the cubit, the firſt of which compaſſes the skin of the palm of the hand, whence it is called the *Palmaris*. The ſecond and third joyned by the communion of their action turn down or prone the wand, and conſequently the hand, ſo that the palm looks towards the feet, whereupon they are called *Pronatores*.

The fourth and fifth joyned alſo in affinity of action bend the wriſt, wherefore they are named *Carpi-flexores*, wriſt-benders. The ſixth and ſeventh are appointed to bend the firſt, ſecond, and third joynts of the fingers, wherefore they are termed *Digitum-flexores*, *Finger-benders*. For their original; the *Palmaris*, the leaſt and uppermoſt of them all, deſcends fleſhy from the hind-proceſs of the inner arm, and a little after ending in a long ſlender tendon, it is ſpent in the skin of the palm of the hand even to the roots of the finger. For it was neceſſary that the skin ſhould ſtraitly cohere with the ſubjacent parts, not only for the fitter taking or comprehenſion of any thing, leſt that skin in holding ſhould be wrinkled and drawn away from the palm and fingers, and ſo be an impediment; but beſides, that the hand might have a more exact ſenſe to diſtinguiſh of hot, cold, moiſt, dry, ſmooth, equal, rough, ſoft, hard, great, little, and ſuch other qualities.

The *Palmaris.*

The *Pronatores.*

Then follow the two *Pronatores*, of which one called the round, comes obliquely from the inner ſide of the hind-proceſs of the arm almoſt to the middle of the wand, to which it adheres by a membranous and fleſhy tendon, even to the place appointed for inſertion. The other, ſquare three or four fingers broad, yet ſomewhat ſlender, ſeated within under all the muſcles which deſcend on the inſide to the wriſt or fingers, upon the ends of the bones of the cubit, aſcends tranſverſe from below the ell, unto the top of the wand, where it ends in a membranous tendon. Both the *Carpi-flexores*, or wriſt-benders, ariſe from the hind, but inner proceſs, and deſcend obliquely, (the one

The *Carpi-flexores.*

more

more, or leſs than the other) the one alongſt the ell, but the other alongſt the wand; and that which deſcends alongſt the ell, is inſerted into the eighth bone of the wriſt, which we ſaid made part of the ring; the other which follows the wand is inſerted with his greater part into the bone of the wriſt, and with the reſt into the firſt bone of the after-wriſt which ſuſtains the fore-finger.

Now remain the *Digitum-flexores*, or finger-benders, which becauſe they lye upon one another, the upper is called the *Sublimis*, but the lower the *Profundus*. The *Sublimis*, or upper, ariſing from the inner part of the hind proceſs of the arm, and from the upper part of the ell and wand, deſcends between the two bones of the cubit, even to the wriſt and ring; divided into four tendons it is inſerted into the ſecond de-articulation of the four fingers, which it bends by the force of this his proper inſertion; as alſo the firſt, as well by the power of the common ligament, as by certain fibers coming from it, which it ſends thither by the way in its paſſage. But theſe four tendons near unto this their inſertion are divided into two, ſo to give paſſage and add ſtrength to the tendons of the deep muſcles deſcending into the third and laſt joynt of the fingers. *The Digitum-flexores.* *The Sublimis Digitum-flexor.*

But this ſame *Profundus* or deep muſcle ariſing from the upper and inner parts of the ell and wand, deſcends between theſe two bones under the *Sublimis*, alſo undivided even to the wriſt, where it is divided into five tendons which it brings forth under the common ligament, and the diviſions of the tendons of the *Sublimis* even to the laſt joynt of the fingers, which they bend, by this their proper inſertion, as alſo of the bones of the firſt and ſecond joynts of the fingers by the means of the common ligament and fibrous productions which they beſtow upon them by the way. Beſides theſe fore-mentioned, there is ſeen alſo a certain membranous ligament which engirts the tendons in the compaſs of the fingers. *The Profundus Digitum-flexor.*

CHAP. XXXIX.

Of the Muſcles of the inſide of the Hand.

THE muſcles of the inſide of the hand are ſeven in number; the firſt is called *Thenar*, becauſe it makes the greater part of the palm; the ſecond from the ſite is called the *Hypothenar*; the third the external *Abductor* of the thumb. The four other are called by reaſon of their figure the *Lumbrici*, or wormy-muſcles, or the *Abductores*, or drawers of the four fingers to the thumb. Now the firſt, called *Thenar*, thicker than the reſt, ariſes from all the bones of the after-wriſt, taking its beginning from that bone which bears up the ring-finger, whence aſcending alongſt the vital line even to the end thereof at the firſt bone of the after-wriſt ſuſtaining the fore-finger, it is at length inſerted into the laſt joynt of the thumb by the longeſt fibers, but by the middle and ſhorteſt fibers almoſt into all the inner parts of the firſt bones of two joynts, and by reaſon of this, the thumb is drawn to the other fingers, and from them again by his lower original. *The number of the muſcles of the inſide of the hand.* *The Thenar.*

Some divide this muſcle into three, by reaſon of his diverſe actions, making the firſt to ariſe from the root of the bone of the after-wriſt which bears up the ring-finger; but the other from that middle bone of the after-wriſt which ſuſtains the middle-finger; but of the third, from the upper end of that bone which under-props the fore-finger; and that the inſertion of them all, is, as we formerly mentioned. But the former opinion likes me better, both for ſhunning confuſion, and abbreviating the doctrine of the number of muſcles.

The *Hypothenar* ariſes from the fourth bone of the after-wriſt, and that bone of the wriſt which ſuſtains it, and then with its longeſt fibers, it is inſerted into the ſecond joynt of the ring-finger, and by the ſhorteſt into the firſt, through which occaſion, as alſo in reſpect of its two-fold action, ſome have divided it into two, that the one of them might lead it from the reſt, and the other might draw it to the thumb. *The Hypothenar.*

The third the external *Abductor* of thumb, deſcends from the firſt bone of the after-wriſt, into the firſt and ſecond joynt of the thumb; wherefore ſome have divided it into two. The *Lumbrici*, or four external *Abductores*, of the fore-fingers, ariſe from a membrane, inveſting and binding together the tendons of the *Digitum-flexores*, or finger-benders, and at length on the ſides towards the thumb even by a ſmall tendon, running even to the ſecond joynt of the four-fingers. *The external Abductor of the thumb.* *The Lumbrici.*

Now the *Interoſſes* of the after-wriſt, remain to be ſpoken of; theſe are ſix, two in each of the ſpaces between the fingers, one internal, the other external, of which the internal deſcending with oblique fibers from the ſide of the firſt bone of the after-wriſt, goes alſo into the ſides of the fingers, that ſo it may the more cloſely bind together the bones of the after-wriſt, whoſe action is manifeſted, when we thruſt our fingers into a ſtrait glove, or when we bend our hand. Some think that it helps alſo the drawing of the fingers towards the thumb. The external aſcends alſo by oblique fibers from the ſides of the ſecond bone of the after-wriſt, to the firſt joynts of the fingers, interſecting the internal, which we now deſcribed after the manner of the letter X, for to extend the palm of the hand, and help the drawing away of the fingers of the thumb. *The Interoſſei.*

Here concluding the deſcription of the muſcles of the whole hand taken in general, you ſhall note that they are thirty nine in number, that is, eight appointed to move the arm; four ſet to move the cubit, in general; ſeven ſeated on the out-ſide of the cubit, and as many on the inſide in the ſame cubit, moving the wand, and with it the hand; ſeven on the inſide of the hand: And laſtly, the ſix *Interoſſes*. Some increaſe this number, ſaying, there are nine on the external part of the cubit, and eleven on the inſide of the hand. *The number of the muſcles of the whole taken in general.*

CHAP.

CHAP. XXX.

A deſcription of the Leg taken in general.

After the hand follows the deſcription of the leg. Wherefore to take away all doubtfulneſs, we will firſt define the leg; then divide it into the parts more and leſs compound; thirdly, we will proſecute all things common to all theſe parts; fourthly, thoſe which are peculiar to each; and then, God willing, we will give an end to our Anatomy.

The diverſe acception of the leg. The thigh. The leg or ſhank. The foot.

Now this word *Crus*, or Leg, is uſed two manner of ways, that is, either generally or ſpecially, and ſpecially again after two ſorts, that is, either abſolutely and ſimply ſo, or with an adjunct. It is ſimply taken for all that which is between the knee and foot. But with an adjunct for the greater bone thereof. But the leg taken in general, is the inſtrument of going, containing all whatſoever is from the hips, to the very ends of the toes. It is divided into three great parts, that is to ſay, the thigh, the leg, or ſhank, and the foot. By the thigh, we mean, that which lies between the hip and the knee. By the leg, properly ſo called, or ſhank, that which is contained between the knee and the foot. By the foot, all from thence to the ends of the toes.

The diviſion of the foot. The inſtep. The top of the foot. The toes.

Again, they divide the foot into three parts; that is, the *Tarſus* or inſtep, the *Pedion* or top of the foot, and the *Digiti pedum*, or toes. We underſtand by the inſtep, that which is contained in the firſt ſeven bones, which anſwers in proportion to the wriſt of the hand. By the top of the foot, that which is comprehended in the five following bones, which is anſwerable to the after-wriſt. That which remains, we call the toes. But becauſe all theſe parts have other common and proper parts, we will only follow the diſtribution of the veins, arteries and nerves; ſeeing we have ſufficiently explained the reſt, when we deſcribed the containing parts of the body in general.

CHAP. XXXI.

A deſcription of the Crural-vein.

The beginning of the crural-vein. The two branches thereof.

The Crural-vein begins then, when the hollow-vein, paſſing forth of the *Peritonæum*. and ſtretched to the hanch-bone, and the ſides of the *Pubis* in the groin, is firſt divided into two large branches, the one of which deſcends on the inſide, alongſt the bones of the whole leg, together with the artery and nerve; the other runs down outwardly and ſuperficially alongſt the leg, between the fat lying under the skin, and the muſcles even to the foot, and is ſpent in the skin thereof. This, becauſe it is always apparent and manifeſt, is called properly by the Greeks *Sapheia*, but commonly *Saphena*.

By what veins the matter cauſing thoſe tumors called *Bubones* flow down.

This vein, by the way, preſently at its original is divided into two branches, the one internal, the other external; of which the internal is ſpent upon the *Bubones*, and other glandules of that place and the skin, and by this branch come the defluxions called *Bubones*; the other branch is waſted in the fore and utter skin of the upper part of the thigh; then a little lower, that is, about the breadth of three or four fingers, it is gathered again into one branch made of many little ones, which is ſpent in the fore and hind-skin of this thigh. Thirdly, a little below the middle of the thigh, it is again divided into two other branches, of which the one goes into the skin on the fore-ſide, and the other on the hind-ſide. Fourthly, it is diſtributed by two other ſmall ſprigs into the skin, on the four and hind part of the knee; which often-times are not found, eſpecially when the *Poplitea*, or ham-vein, is ſomewhat larger than ordinary. Fifthly, a little below the knee, it produces two other branches, lying upon each other in their paſſage out into the fore and hind-skin of that place. You muſt note, that branch which runs into the skin of the hind-part, is carried by certain other ſprigs, which it produces into a branch of the *Poplitea* paſſing forth of the two twin-muſcles. Sixthly, in the bigger part of the calf of the leg, it is divided into two other branches, which in like manner are diſtributed into the skin, as well in the fore-ſide as the back-ſide of the leg.

Where, and in what diſeaſes, the *Sapheia* muſt be opened.

At length, after many diviſions, which for brevity ſake I omit, when it arrives at the fore and inner ſide of the ankle (where it is commonly opened in the diſeaſes of the parts below the midriff which require blood-letting) it is parted into two other branches, the leſſer of which deſcends to the heel; the other in many ſprigs is ſpent upon the skin of all the upper and lower parts of the foot and toes.

To what places, and by how manifold diviſions the internal branch of the crural vein goes. *Iſchiadica vena.* *Muſcula vena.* *Poplitea vena.*

The ſecond branch of this crural-vein, which we ſaid deſcends within together with the artery and nerve, even into the foot, is divided; firſt, piercing ſomewhat deep in, it produces four divarications; one internal, deſcending below the original of the *Saphia*, into the muſcle called *Obturator externus*, and into certain other external muſcles. The three other run outwardly, the firſt towards the huckle-bone, by which the *Iſchias* is made, the two other into the four muſcles of the thigh, neither are theſe ſprigs far remote from one another. Secondly, all that branch is divided into two other branches, the one above, the other below, an artery always accompanying it; the lower of which is ſpent upon many of the hinder-muſcles of the thigh ending nigh the ham. The upper, beſides, that it beſtows many branches upon the fore and inner-muſcles of the thigh; deſcending to the ham, it produces the *Poplitea*, or ham-vein, made ſometimes of two branches, the one proceeding from above, and the other from below. This *Poplitea* deſcending by the bending of the ham, is ſpent one while upon the skin of the calf of the leg, another while upon the knee; otherwhiles increaſed with branches of the *Sapheia*, it goes on the out-ſide of the ankle to the skin, on the upper-ſide of the foot, and ſometimes on the lower.

Thirdly, a little below the original of the ham-vein, and under the bending of the knee, it brings

brings forth the *Suralis*, which is beſtowed upon the muſcle of the *Sura*, or calf of the leg, and upon the skin of the inner ſide thereof, and of the foot, continued ſometimes even to the inner part of the great toe. *Suralis vna.*

Fourthly, under the head of the hinder appendix of the bones of the leg, it produces between theſe two bones, another vein, which nouriſhing the fore-muſcle of the leg, is conſumed upon the foot.

Fifthly and laſtly, it brings forth the *Iſchiadica major*, or greater *Iſchias*, which is divided into two branches of an unequal bigneſs; the larger whereof, from his original deſcending alongſt the inner part of the leg-bone, inſinuates it ſelf under the muſcles of the calf, between this and the heel, into the ſole of the foot, upon which it is waſted, divided into ten ſmall ſprigs, two for each toe; the other being the leſſer deſcending alongſt the *Perone*, or ſhin-bone, is conſumed between it and the heel, yet ſometimes it is produced, not only even to the muſcle the *Abductor* of the toes, but alſo by five ſurcles, even to the fourth toe, and the ſides of the middle toe. *Iſchiadica major.*

CHAP. XXXII.

The Diſtribution of the Crural Artery.

THe Crural Artery ariſing from the ſame place whence the Crural vein proceeded, and deſcending with the internal Crural Vein, is diſtributed as followeth:

Firſt, into the muſcle of the thigh, which ſpreading it ſelf through the muſcles thereof meets with the utmoſt *hypogaſtrica*, deſcending with the vein through the common hole of the huckle and ſhare-bone, and is joyned with it *Arteria muſcula.*

Secondly, when it arrives at the ham, between the *Condyles*, or proceſſes of the leg, it ſends two branches into the knee.

Thirdly, a little after it produces another branch, which it ſends to the exterior muſcles of the leg; and when it arrives at the middle of the leg, it is divided into two branches, between the Twin-muſcles and *Soleus*, the one internal, the other external; the internal, ſome ſurcles communicated by the way to the parts by which it paſſes, but ſpecially to the joynt of the ankle, ſtretches it ſelf over the ſole of the foot, between the lower extremity thereof and heel; whither when it arrives, it is divaricated into five ſurcles, of which it beſtows two on the great toe, two on the next, and one on the middle toe. The external deſcending in like manner to the ſole of the foot, between the *Fibula* and the heel, beſides other ſprigs, which it may ſpread by the way, it produces one without on the joynt of the ankle, another in the muſcle, the *Abductor* of the toes; to the wriſt and back of the foot. But the remainder is divided into five portions, of which two are ſent to the fourth, and two to the little toe, and one to the middle.

CHAP. XXXIII.

Of the Nerves of the Loins, Holy-bone and Thigh.

THere ariſe five Conjugations of Nerves from the Loins, divided into external and internal branches; the external are diſſeminated into the *Rachitæ*, or chin-muſcles, the muſcles *Semiſpinatus* and *Sacer*, and skin lying over them. The internal are ſent into the oblique aſcendent and tranſverſe-muſcle of the lower belly, into the *Peritonæum*, into the loin and cheſt-muſcles ariſing there, but after a different manner; for ſome are abſolutely carried thither, as the nerves of the firſt conjugation of the loins, and oftentimes alſo of the ſecond, but that ſometimes they ſend a ſmall ſprig to the teſticles, when the coſtal have ſent none thither; but ſome lower are partly diſtributed there, and partly ſent ſome other way; for the greater portions, firſt united amongſt themſelves, then preſently with the portion of thoſe of the holy-bone, go into the thigh, as we ſhall ſhew in the diſtribution of the nerves of the holy-bone. The five conjugations of the nerves of the loins. Where the teſticles have their nerves.

Now from the holy-bone, proceed ſix conjugations of nerves, reckoning that for the firſt which proceeds from the laſt *Vertebra* of the loins, and firſt of the Holy-bone, and that the ſixth which proceeds from the loweſt part of the holy-bone, and the firſt of the Rump. Theſe Conjugations of nerves are divided into external and internal branches. The conjugation of the nerves proceeding through the holy-bone.

The leſſer external paſſing forth by the external and hinder holes of the holy-bone, are diſtributed into the parts properly belonging thereto, to wit, the muſcles and skin thereof; for every nerve by the Law of Nature, firſt and always yields to the neighbouring parts, that which is needful, then preſently to others as much as it can. An Anatomical axiom.

Wherefore if thou wouldſt know whence each part hath his veſſels at the next hand, that is, the veins, arteries, and nerves, thou muſt remember the ſite of each part, and the courſe of the veſſels, and to conſider this, that the veins and arteries, as ſpeedily and conveniently as they can, inſinuate themſelves into the parts, ſometimes at the head or beginning, ſomewhiles by the middle or extremes thereof, as there is occaſion.

But a nerve principally enters a muſcle at the head thereof, or at leaſt not far from thence, but never by the tail, whereby it may eaſily be underſtood by what branch of each vein, artery, and nerves, each part may have nouriſhment, life and ſenſe. The other internal branches of the foreſaid conjugations go, eſpecially the four uppermoſt united from their original with the three lowermoſt of the loins, into all the legs, as you ſhall preſently hear. But the two lower are conſumed upon the muſcles called *Levatores Ani*, the *Sphincter*-muſcle of the ſame place; beſides,

upon

upon the muſcles of the yard, and neck of the bladder in men, but in women upon the neck of the womb and bladder.

For theſe parts admit another in their bottom from the coſtal nerve, being of the ſixth conjugation of the brain: Theſe thus conſidered, let us come to the nerves of the thigh, which (as we ſaid) from their firſt original, as it were compacted and compoſed of the greater portion of the three inner and lower branches of the loins, and the four upper of the holy-bone, are divided in the thigh into four branches, of which the firſt and higher deſcending from above the *Peritonæum*, to the little *Trochanter*, is waſted upon the inward and ſuperficiary muſcles of the thigh, and the skin which covers them a little above the thigh.

The ſecond, deſcending with the crural vein and artery by the groin, is divided into two branches like as the vein, the one internal, the other external; of which the internal deſcending with the vein and artery is ſent into the inner and deep muſcles of the thigh, ending above the knee. But the external deſcending ſuperficially with the *Saphæa*, even into the foot, gives branches by the way to the skin which covers it.

The third ſeated under theſe former, paſſing by the hole common to the ſhare and hanch-bone, ſends certain branches to the groins, to the muſcles called *Obturatores*, to the *Tricipites*, and ſometimes to the muſcles of the yard, and ends at the midſt of the thigh.

The fourth, which is the thickeſt, ſolideſt, and hardeſt of all the nerves in the body, deſcending wholly from the productions of the holy-bone, and deſcending outwardly, between the lower part of the ſame bone, and the *Os Ilium*, or hanch-bone to the thigh, beſtows certain ſprigs to the hind-muſcles thereof proceeding from the protuberation of the *Iſchium*, or huckle-bone, and in like ſort it gives other ſome to the skin of the buttocks, and alſo to the skin covering the forementioned muſcles.

A little after, it is parted into two branches deſcending undivided even to the bending of the knee, they both are communicated by divers ſurcles of the muſcles of the leg; yet ſo as the leſſer produces another branch from the reſt of the portion thereof deſcending on the fore-part of the leg, alongſt the ſhin-bone unto the top of the foot, where it is divided into ten ſurcles ſcarce apparent to the ſight, two running to each of the toes. The other greater, deſcending in like manner in the remainder of its portion by the hind-part of the leg into the ſole of the foot, caſts it ſelf with the veins and arteries between the heel and leg bone, where firſt divided into two branches, each of which preſently parted into five, ſend two ſprigs to the ſides of the toes. And theſe are the moſt notable and neceſſary diſtributions of the veſſels and nerves; we purpoſely omit others which are infinite, and of which the knowledg is impertinent.

CHAP. XXXIV.

Of the proper parts of the Thigh.

HAving explained the common parts of the leg in general: Now we muſt come to the proper, beginning at the thigh. The proper parts of the thigh, are muſcles, bones and ligaments. But becauſe the demonſtration of the muſcles is ſomewhat difficult, if we be ignorant of the deſcription of the bones from whence they ariſe, and into which they are inſerted; therefore we judg it worth our labour, firſt to ſhew the bones, and the dearticulation of theſe of the thigh; beginning with thoſe bones which are knit with the upper part of the holy-bone.

Of how many bones the *Oſſa Ilium* conſiſt.

And they are two in number, on each ſide one, commonly called the *Oſſa Ilium*; each of theſe is compoſed of three bones; of which one is the upper, another the lower and anterior, and the third the middle, and after a manner the poſterior. The upper by a particular name is called the *Os Ilium*, the hanch-bone, and it is the largeſt and biggeſt, having a griſtly Appendix in the compaſs thereof, even to the connexion it hath with the other neighbouring bones, whoſe upper part we term the right line thereof; but the *baſis*, which is adjoyned to it by *Symphyſis*, we call the lip, or brow thereof, becauſe it ſtands both ſomewhat out and in, after the manner of the brow.

What the *Os Ilium* ſtrictly taken is.

What the line, lip, brow and rib of the *Os Ilium* are.

But that which lies between the *baſis* and ſtrait line, we name the Rib; this ſame upper bone hath two hollow ſuperficies, the one internal, the other external. The connexion thereof by *Symphyſis*, is twofold, the one with the upper part of the holly-bone; the other, with that bone we called the middle, and after ſome ſort the poſterior; which taking its beginning from the narrower part of the *Os Ilium*, makes that cavity in which the head of the thigh is received; this cavity the *Greeks* call *Cotyle*, the *Latins Acetabulum*, and it is ended by the ſide of the hole common to it, and the ſhare-bone; this middle, and in ſome ſort poſterior-bone, is called properly and particularly the *Os Iſchii*, or huckle-bone, and contains nothing elſe but the fore-mentioned cavity; but, that on the hinder and lower part thereof, it brings forth a proceſs, which adjoyns it ſelf to the ſhare-bone at the lower part of the common hole, in which place it appears very rough and unequal, and it is called the Tuberoſity of the huckle-bone, at whoſe extremity alſo it brings forth a little head ſomewhat reſembling the proceſs of the lower jaw called *Corone*.

The *Os Iſchium*, or huckle-bone.

The third bone named *Os pubis*, or the ſhare-bone, ſtretches it ſelf even to the higheſt part of the *Pecten*, where meeting with the like bone of the other ſide, it is united to it by *Symphyſis*, after which manner alſo, all theſe three bones are united. It is reported, that this bone opens in women in their travel, yet hitherto I can find no certainty thereof.

The *Os pubis* or ſhare-bone.

You may perceive a manifeſt ſeparation of theſe three bones in the *Sceleton* of a child; for in thoſe who are of more years, the griſtles which run between theſe connexions turn into bones.

Now follows the thigh-bone, the biggeſt of all the bones of the body; it is round, and ſo bended, that it is gibbous on the exterior and fore-part thereof, that ſo it might be the ſafer from

The deſcription of the thigh-bone.

external

external injuries; but on the hind and inner part, it is hollow, or sinous, like to the back of an Ass, whereby the Muscles might have a more commodius original and insertion.

That sinous part a little below the midst thereof, is divided into two lines, the one whereof goes to the internal tuberosity, the other to the external of the lower appendix of the same thigh. These are chiefly to be observed, because the oblique fibers of the vast muscles, thence take their original.

Besides, this bone hath two appendices in the ends thereof, as easily appears in a childs thigh; the upper appendix makes the round head of the thigh it self, which (as every other appendix) seated upon a long neck, is received in the cavity of the hanch-bone, by *Enarthrosis*; it is stayed and fastned there by two sorts of ligaments, of which the one is common, proceeding from the muscles, which descend from above, about the neck thereof; the other is proper, which is two-fold, that is, one membranous and broad, proceeding from the whole cavity of the orb, or cup, descending about all the head of the thigh, above the neck thereof; the other thick and round, descending from the second cavity of the *Cotyle* it self, which is extended, even to the common hole at the top of the head thereof. The two Appendices of the thigh-bone.

Besides, under this head, that bone hath two processes, the one great and thick, the other little and short. The two processes of the thigh-bone make the two *Trochanters*.

The greater seated in the hind-part, is called the great *Trochanter*; the lesser situate in the inner part, is named the little *Trochanter*.

But you must note, that the greater *Trochanter*, on the higher and hind-part thereof, which looks towards the head of this bone, makes a certain small *sinus*, or bosom, into which the Twin-muscles and others, whereof we shall hereafter speak, are implanted; we must also consider the multitude of holes encompassing this neck, between the head and the two *Trochanters*; which yield a passage to the vessels, that is, the veins, arteries and nerves, into the marrow of the bone it self, whence the marrow it self becomes partaker of sense, especially on that part which is covered with a coat, and the bone lives and is nourished. Whence the marrow becomes partaker of sense.

The Figure of the Thigh Bone.



A 1 2 *The head of the thigh going into the cup of the hip-bone.*

B 2 *A* Sinus *in the head of the thigh, into which is inserted a round ligament.*

C 1 2 *The conjunction of the appendix of the thigh with the bone it self.*

D 1 2 3 *The neck of the thigh.*

E F *The two lower heads of the thigh.*

G 1 2 *The conjunction of the lower appendix.*

H 1 12 *A* Sinus *betwixt the two heads of the thigh.*

K 2 *A part of the lower head of the thigh, from whence the first muscle of the foot doth proceed.*

L 2 *Another part from whence the second and first muscles arise.*

M 2 *Another part to which the tendon of the fifth muscle of the thigh is infixed.*

N 1 2 *A* Sinus *of the outward side of the head for the fourth muscle of the leg.*

O 2 *A* Sinus *of the inside through which the tendons do pass.*

P 2 *A protuberation at which the said tendons are reflected.*

Q 2 *The upper process of the thigh, and betwixt* Q *and* D *is the* Sinus.

R 1 2 *The union of the process with the thigh.*

S S 2 *A rough line from the impression of the external processes.*

T 1 *The anterior impression of the internal processes. & betwixt* T *and* V, *another impression higher than the former.*

V 1 2 *The fourth impression in the top of the process* X 3. *Four* X *shew the four appendices of the thigh,* Y 3 *Three* Y *shew the three heads of the thigh.* Z Z 3 *Two processes of the thigh.* a 1 *The interior process of the thigh.* b 1 *The conjunction of the process with the thigh.* c c 2 *A line descending obliquely from the inner process.* d d 2 *A line running through the length of the thigh.* e 2 *The largeness of the thigh in this part.* f 1 *A roughness from which the eighth muscle issueth.* g h 5 *A knub of the whirl-bone going in-*

to

to the Sinus *marked with* I, *which is betwixt the heads of the thigh.* i 5 *A* Sinus *fitted for the inner head of thigh.* k 5 *A* Sinus *agreeing with the external head of the thigh.* l 5 *The lower aſperity or roughneſs.* m 4 *The foreſide of the pattel or whirl-bone, rough and unequal.*

The other Appendix of the thigh, that is, the lower, is the greateſt and thickeſt; riſing, as it were, with two heads, which are divided by two cavities, the one ſuperficiary, and on the foreſide, whereby it receives the whirl-bone of the knee; the other deep, and on the back-part, by which it receives the griſtly, and, as it were, bony-ligaments, proceeding from the eminency, which is ſeen, between the two cavities of the upper Appendix of the bone of the Leg, which *Hippocrates lib. de Fracturis*, calls in his tongue *Diaphyſis*.

CHAP. XXV.

Of the Muſcles moving the thigh.

Their number. THE muſcles of the thigh are juſt fourteen in number; that is, two bend it, whereupon they are called *Flexores*, or benders; three extend it, whereupon they are called *Tenſores*, extenders; three move it inwards, driving the knee outwards, and drawing the heel inwards, as when we croſs our legs; yet ſome make theſe three one, and call it the *Triceps*, or three-headed muſcle. Six ſpread it abroad, and dilate it, as happens in the act of Venery.

Four of theſe are called *Gemini*, or Twins, by reaſon of the ſimilitude of their thickneſs, original inſertion, and action; the two other are called *Obturatores*, becauſe they ſtop the hole which is common to the ſhare and back-bone.

The two *Flexores.* Now one of the two *Flexores*, being round, deſcends on the inſide with fibers of an unequal length from all the tranſverſe proceſſes of the loins, above the hind-commiſſure of the hanch and ſhare-bones, and is inſerted into the little *Trochanter*; the other broader and larger from the original paſſes forth of the whole lip, and inner brow of the hanch-bone, and filling the inner cavity thereof, is inſerted above the fore-part of the head of the thigh, into the little *Trochanter* by a thick tendon, which it with the fellow muſcle lately deſcribed, produces even from the fleſhy part thereof, wherefore you need to take no great pains in drawing, or plucking them away.

The three *Tenſores.* The three *Tenſores*, or Extenders, make the buttocks, of which the firſt being the thicker, larger, and external, ariſing from the rump, the holy-bone, and more than half of the exterior and hinder lip of the hanch-bone, is inſerted by oblique fibers, ſome four fingers breadth from the great *Trochanter* at the right-line, which we ſaid, reſembled an Aſſes back.

The ſecond, which is the middle in bigneſs and ſite, deſcends from the reſt of the hip, and from the fore and outward rib of the hanch-bone, and, above the midſt of the bone, is inſerted into the upper part of the great *Trochanter*, by a triangular inſertion above the upper and exterior part thereof.

The third being leſſer, ſhorter and thinner, lying hid under theſe former, proceeds from the middle of the external ſurface of the hanch-bone; and then is inſerted into the greater part of the right line of the great *Trochanter*.

Theſe three muſcles have a great and large original, but a narrow inſertion, as it were, by oblique fibers.

Three *Intromoventes.* Then follow thoſe three muſcles which move the thighs inwards, ſtraiten and croſs them, ſo that the knee ſtands forwards, or outwards, but the heel is drawn inwards, as you may underſtand by their inſertion, although ſome think otherwiſe. But theſe three muſcles by their original, partly fleſhy, and partly membranous, ariſe from the upper and fore-part of the circumference of the ſhare-bone, and thence are inſerted into the hind-line of the huckle-bone, ſome higher than otherſome; for the leſſer and ſhorter ſtays at the roots of the little *Trochanter*, the middle deſcends a little deeper, the third with the longeſt of his fibers, deſcends even to the midſt of the line.

This, if it be ſo, that is, theſe muſcles proceeding from the fore and upper part, to be inſerted into the hinder-line of the huckle-bone, whilſt they alone perform their action, and draw the thighs together, they will turn them outwards, juſt ſo as when we put them a-croſs, but they will not draw one heel to another, and put the heel outwards, for ſuch like motion is performed by the inner vaſt muſcle of the thigh, moving the leg. Now follow the ſix which move the buttocks.

The movers of the buttocks. The firſt and higher of the *Quadragemini*, or the four Twin-muſcles, paſſes forth of the commiſſure of the holy-bone, with the bone of the rump, or rather, from the loweſt extream of the holy-bone, and thence it is inſerted into the cavity of the great *Trochanter* by a tendon of a ſufficient largeneſs.

The ſecond proceeding from the hollow part, or fiſſure, which is between the extremity of the huckle-bone, and the tuberoſity or ſwelling out of the ſame, is inſerted in like manner into the cavity of the great *Trochanter*.

The third aſcends from the inner part of the ſwelling out of the huckle-bone, a little above, between the two *Trochanters*, into the cavity of the greater of them.

The fourth and laſt, the loweſt and broadeſt of them all, proceeds from all the exterior protuberancy of the huckle-bone, and thence is inſerted into the great *Trochanter*, and theſe four muſcles lie hid under the thick and more eminent part of the buttocks; wherefore, that you may the better ſhew them, they muſt be turned up towards their original.

The two *Obturatores.* The two *Obturatores* remain to be ſpoken of, that is, the internal and external, both which ariſe from the circuit and circumference of the hole which they ſtop, which, as we ſaid, is common to the ſhare and huckle-bone, but the internal aſcends to the exterior root of the great *Trochanter*, by

by the middle fiſſure between the upper part of the protuberancy of the huckle-bone, and the ſpine which ſtands up in the hinder baſis of the hanch-bone.

But the external proceeds from the exterior cavity, and the middle ſpace between the tuberoſity of the huckle-bone, and cavity thereof, and is inſerted into the lower part into the cavity of the great *Trochanter*, together with the *Quadragemini*.

If you would plainly ſee the exterior *Obturator*, you muſt either cut off the beginning of the three-headed muſcle, or handſomely pluck it away, and then extend it, and turn it up; the internal is eaſily diſcerned when the bladder is taken away.

CHAP. XXXVI.

Of the Bones of the Leg or Shank.

THoſe which would deſcribe the muſcles of the leg, ought firſt to deſcribe the bones thereof, beginning at the *Rotula*, or whirl-bone of the knee. What the *Patella* or whirl-bone of the knee is.

This bone is griſtly on the out-ſide, and round in compaſs, but on the inner and middle part after ſome ſort gibbous, but ſomewhat flatted at the ſides, that ſo it may be fitlier applied to the joynt of the knee, and fitted within the anterior cavity of the two appendices of the thigh, and the upper and fore-moſt of the leg.

The uſe thereof is to ſtrengthen the joynt of the knee, and to hold the leg at his due extent, ſo that it may not be bended ſo far forwards, as it is backwards. The uſe thereof.

The bones of the leg are two; the one thicker, called by the particular and proper name, the *Os Tibiæ*, or leg-bone; the other which is leſſer, is termed *Perone*, or *Fibula*, but commonly the leſſer *focile*, (and in Engliſh it may be termed the ſhin-bone) The thicker being hollow and marrowy, is ſeated in the inner part of the leg, having two proceſſes, the one bigger, the other leſs. What, and how many bones the leg hath. The leg bone.

The bigger ſeated on the upper-part of the bone, and conjoyned to it by *Symphyſis*, makes two ſuperficial and ſide cavities disjoyned by an indifferent riſing; wherefore this bone is connext to the bone of the thigh by *Ginglymos*. For in the cavities thereof it receives the lower and hinder protuberances of the appendix of the thigh-bone, but the middle eminency thereof, is received by it between the two protuberances thereof.

This joynt is ſtrengthned, not only by the force of the tendons, or muſcles ending there, but alſo of three ſtrong ligaments; of which, one proceeds from all the external; another from all the internal parts of that connexion; the third, which we out of *Hippocrates*, called *Diaphyſis*, from the diſtance or ſpace between them. The other proceſs of the leg-bone, which we called the leſs, ſeated in the lower part thereof, makes, as it were, a double cavity, whereby it receives the *Aſtragalus*, or paſtern-bone; but on the inſide it makes the ankle, as the *Perone* makes it without: Between theſe ankles the *Aſtragalus* is received on the ſides, and turned as the nut in a Croſs-bow, as often as there is need to bend or extend the foot. Beſides, this ſame leg-bone, being triangular, hath three eminencies made in the ſhape of an Aſſes back; the ſharper deſcends alongſt the fore-part, called by the Greeks *Anticnemion*; the ſecond reſides on the inner-part; and the third on the outer: All theſe muſt be diligently obſerved, and chiefly, that on the fore-part; becauſe it is as a guide and rule to a Chirurgeon in the well-ſetting of a broken leg. What *Diaphyſis* is. The *Perone*, or ſhin-bone, is ſeated, as it were, on the out-ſide, and as behind the leg-bone; it hath alſo two appendices hollow on the inſide, but gibbous on the out. This bone by the upper of theſe is faſtned and inſerted under the inner, and in ſome ſort the hinder appendix of the leg-bone, ſo that it is in no ſort articulated with the thigh, but ſerves only inſtead of a leaning-ſtock. But by the lower, this ſame bone is not only received in the loweſt part of the leg, or ankle, or paſtern-bone, but alſo receives part thereof, which is joyned on the ſame ſide with the heel, eſpecially then when we bend our foot outwards. The *Perone*, *fibula*, or ſhin-bone.

This bone is faſtned to the fore-mentioned bones by *Synarthroſis*, but bound by ſtrong ligaments proceeding from the ſame bones, and mutually ſent from one to another, or, if you had rather, from the upper into the lower, as we ſaid in the arm. But this ſame *fibula*, or ſhin-bone is alſo triangular, having three lines; of which one ſtands outwards, and another on the foreſide, and the third behind.

CHAP. XXXVII.

Of the Muſcles of the Legs.

ALL the motions of the leg, are performed by eleven muſcles, of which there be ſix on the fore-ſide, and five on the hind. But of theſe, ſome move the leg only, as thoſe which take their original from the bone of the thigh; others truly move the leg, but with the thigh, as thoſe which ariſe above the thigh, that is, from the hanch, huckle and ſhare-bones. Their number.

The firſt of theſe on the fore-ſide, called the long, but commonly the *Sutorius* (or Tailor-muſcle, by reaſon of its action) it ariſes from the lower and fore-extremity of the ſpine or appendix of the hanch-bone, and deſcending obliquely above the other muſcles, is inſerted by a large and membranous tendon, in the fore and inner part of the leg under the knee; the action thereof is to croſs the legs, but being firſt bended by the muſcles preſently to be treated of, it helps alſo the three-headed muſcle in the performance of the fore-mentioned action. The *Longus*.

The ſecond of theſe four muſcles is termed the *Membranoſus*, or membranous, becauſe it is wholly ſuch, unleſs at the original where it deſcends fleſhy from the root and baſis of the above-mentioned ſpine of the hanch-bone, and that obliquely with its membranous and broad tendon The *Membranoſus*.

(mixed with the common coat of the muſcle) into the outward part of the leg, which it moves outwards, as alſo the thigh with the four twin-muſcles; for, as we have in another place obſerved, of two oblique motions concurring in one, is made a right motion; and beſides, almoſt all the motions of the body are thus performed; the muſcles which perform ſuch motions are placed and oppoſed in an oblique ſite, as may be perceived by the motions and ſite of the muſcles of the hand taken in general.

The *Rectus.* The third, called the *Rectus*, or Right (becauſe it deſcends above the *Crureus*, alongſt the right fore-line of the thigh, between the two vaſt muſcles) comes forth between the extremity of the appendix of the hanch-bone and cavity thereof, with a very ſtrong ligament, and then is inſerted into the fore-part of the leg, paſſing over the midſt of the whirl-bone of the knee; it extends the leg, with the three following, but by accident it may help the bending of the thigh.

The two *vaſti.* The fourth and fifth are called *Vaſti*, vaſt or huge muſcles, by reaſon of their largeneſs, the one of theſe is internal, the other external: They both ariſe with right fibers, from their original, but with oblique at their inſertion, by reaſon whereof they both ſeem to have a compound action from a right and oblique motion; the right helping for the extenſion of the leg, but the oblique to draw one knee to another, or to disjoyn both the knees; the internal comes by its right fibers from the root of the little *Trochanter*, but by its oblique from the inner deſcendent line of the thigh. The external paſſes forth by its right fibers from the root of the great *Trochanter*, but by the oblique from the external deſcendent line of the ſame bone. But all theſe fibers are in certain places ſo mixed with the *Crureus*, that they cannot be ſeparated unleſs you violate the one of them; they go into the leg (each on his ſide) above the whirlbone of the knee alongſt the ſides of the right muſcle, with which it makes an unſeparable tendon, as you ſhall preſently hear.

The *Crureus.* The ſixth and laſt of theſe fore-muſcles called *Crureus*, or thigh-muſcle (by reaſon of the ſtrait and firm adheſion, which it hath with the thigh-bone, which is by ſome called *Crus*) from the ſpace between the two *Trochanters* deſcends under the right muſcles, and two vaſt muſcles into the fore-part of the thigh, even to the whirl-bone of the knee. But we muſt note, that theſe four laſt muſcles make a common thick and broad tendon, with which they cover the *Patella*, or whirl-bone, and all the fore dearticulation of the knee, that they cannot be ſeparated without tearing; wherefore we muſt think, that this tendon ſerves the knee for a ligament: Now all theſe muſcles performing their action together, extend the leg. The five hind-muſcles follow to be ſpoken of; of which three ariſe from the tuberoſity of the huckle-bone, going into the inner part, the fourth from the middle of the *Pubis* called *Biceps*, that is, the two-headed muſcle into the outſide of the Leg. Of the internal, one paſſing from the fore-mentioned

The three internal. tuberoſity, deſcends ligamentous even into the midſt of the thigh, and then becoming fleſhy, is inſerted by its tendon, after the manner we formerly mentioned.

The other being ſlender, paſſing forth alſo from the ſame place, with its tendon, is inſerted with the tendon of the long-muſcle, and ends in the inner part of the leg, which with its companion, it draws inwardly, and brings to the other, which ſame thing it performs in the thigh, by the help of the three-headed muſcle.

The third being the inner, or hinder, deſcends from the middle part of the ſhare-bone, with a broad and ſlender ligament, and is inſerted with a round tendon, into the inner part of the leg after the manner of the fore-mentioned.

The *Biceps*, or two-headed muſcle. The fourth called *Biceps* takes one of the two heads, of which it conſiſts, from the laſt mentioned tuberoſity, the other from the outer line of the thigh, but is inſerted into the external part of the leg, as we formerly ſaid.

The *Popliteus* or ham-muſcle. The fifth and laſt called the *Popliteus* deſcends obliquely fleſhy from the external condyle or knot of the thigh, into the inner and hinder part of the leg, at the joyning thereof to the ſhin-bone; the action thereof is, to draw the leg, after a manner inwards.

CHAP. XXXVIII.

Of the Bones of the Foot.

THe order of Anatomy requires, that we now proſecute the muſcles moving the foot; but becauſe we ſhould in vain deliver their inſertion, the diſpoſition and condition of the bones of the foot not being firſt known, therefore it firſt behoves us, to ſet forth their deſcription. Therefore the bones of the foot are ſix and twenty in number, diſtinguiſhed into three ranks; that is, the bones of the *Tarſus*, or inſtep, are ſeven; thoſe of the *Pedium*, the after-wriſt, or back of the foot five; and thoſe of the toes, fourteen. Of the ſeven bones of the inſtep, there are four named, and three unnamed. The firſt of the named immediately following the bones of the leg, is called *Aſtragalus*, the paſtern or ankle bone. This hath three connexions, one, as we ſaid before, in the upper and broader part, with the bones of the leg, of which it is received; the other in the lower and hind-part, by which it receives the upper and inner proceſs of the bone of the heel; the third on the fore-ſide, by which it is received in the cavity of the *Os Naviculare*, or *Scaphoides*, that is, the boat-like bone. By the firſt connexion the foot is extended and bended; by the ſecond it is moved with the heel to the ſides: The two firſt connexions are by *Diarthroſis*, the laſt by *Synarthroſis*. But it is ſtrengthned by ſtrong and broad ligaments, deſcending and aſcending from one bone into another; alſo they are ſtrengthned by membranes, muſcles and tendons, deſcending to the foot, above and under theſe joynts. But this bone hath three proceſſes, as three feet, faſtned to the bone of the heel; of which the firſt and leaſt is under the out-ankle; the bigger (which *Galen* ſaith, makes a round head, faſtned on a long neck) looks towards the fore-part of the foot, over againſt the great toe, and the next toe to it; the middlemoſt is at the heel, behind the leg-bone.

Their number. The bones of the inſtep. The *Aſtragalus* its three connexions and their uſe.

Its three proceſſes.

The

The Figure of the bones of the foot properly ſo called.
Figure 1 *and* 2 *ſhew the bones of the right foot faſtned together, their upper face and their neather face.*
Figure 3 4 5 *and* 6 *ſhew the upper, lower, inner and outer ſides of the* Talus, *or Paſtern.*
Figure 7 8 9 *ſhew the ſame ſides of the heel.*
Figure 10 *and* 11 *ſhew the forward and backward ſide of the boat-bone.*
Figure 12 13 *ſhew the fore and back-part of the wriſt made of four bones.*

A B C D 3 5 6 *The protuberation of the* Talus *joyned to the appendix of the leg-bone, and of this protuberation four ſides.*
E E 3 *A* Sinus *inſculped in the protuberation of the* Talus.
F F 3 *Two bunching parts of the* Taſus.
G 3 *The inner ſide of the protuberation of the* Talus *cruſted over with a griſtle, joyned to the inner ankle.*
H 6 *The outward* Sinus *of the protuberation of the* Talus *covered over with a griſtle receiving the inner ankle.*
I 5 *A rough* Sinus *of the* Talus, *receiving a griſtly ligament from the inner ankle.*
K 6 *A* Sinus *of the* Talus, *receiving a griſtly ligament from the outward ankle.*
L M 5 6 *Two* Sinus *in the hinder part of the* Talus.
N 3 4 5 6 *The neck of the* Talus, *or Paſtern-bone.*
O 3 4 5 6 *The head of the* Talus *going under the* Sinus *of the Boat-bone.*
P 7 8 9 *The head of the heel cruſted over with a griſtle, and going under the* Sinus *of the* Talus, *or the Paſtern-bone.*
Q 4 *A large* Sinus *of the* Talus, *receiving the head of the heel.*
R 7 8 9 *A* Sinus *of the heel whereto the lower part of the head of the* Talus *is joyned.*
S 4 *The lower power of the head of the* Talus *going into the* Sinus *of the heel.* T T 4 *A ſharp* Sinus *of the heel receiving a griſtly ligament from the Paſtern-bone.* X Y Z 2 *The place of the heel.* Y Z 2 Y 8 Z 9 *A proceſs of the heel made for the production of muſcles.* a b 7 8 9 *From* a *to* b *the diſtance of the upper part of the heel.* c 8 9 *The hinder-part of the heel.* d 2 8 *The inner ſide of the heel.* e 8 *The place where the tendons that run to the bottom of the foot are reflected.* f 7 8 *The utter ſide of the heel.* g 1 7 9 *Here the tendons of the ſeven and eight muſcles of the foot are ſtretched out.* h 7 *The fore-part of the heel which is joyned to the Paſtern-bone.* i 7 *That part of the heel which is joyned to the Cube-bone.* k 11 *The* Sinus *of the Boat-bone, receiving the head of the* Talus. l m n 10 *Three ſurfaces of the Boat-bone lightly prominent, which are articulated to the bones of the wriſt.* o p 11 *The upper part of the Boat-bone regarding the top of the foot.* q r 10 *and* q 11. *His lower part.* q 10 11 *A* Sinus *through which the ſixth muſcle of the foot is led.* ſ t u 13 *The plain ſurfaces of the three inner bones of the wriſt whereby they are articulated to the Boat-bone.* x 13 *A ſhallow* Sinus *of the Cube-bone whereby it is articulated to the heel.* α β 12 *The plate of the Cube-bone to which that bone of the after-wriſt is joyned which ſupporteth the laſt toe ſave one.* γ 12 13 *the place of the Cube-bone where the third Bone of the Wriſt is articulated.* δ 12 13 *That part of the cube-bone which reſpecteth the outſide of the foot.* ε 12 13 *The ſurface of the cube-bone in the upper part of the foot.* ζ 2 13 *That part of the cube-bone which regardeth the earth.* ϰ 2 *A* Sinus *of the Cube-bone at which the tendon of the ſeventh muſcle of the foot is reflected.* B 13 *A proceſs of the third bone of the wriſt whereinto the fifth muſcle of the foot is inſerted.* ι 12 *The place of the inner-bone of the wriſt to which that bone of the after-wriſt which ſuſtaineth the great is coupled.* ϰ 12 *The place of the ſecond bone of the wriſt whereto the bone of the after-wriſt that ſupporteth the fore-toe is articulated.* λ 12 *The place of the third bone of the wriſt, whereto that bone of the after-wriſt which ſupporteth the middle-toe is articulated.* μ 1 2 *A ſmall bone whereby that bone of the after-wriſt which ſuſtaineth the little toe is joyned unto the cube-bone.* ν ν 1 2 *The diſtances betwixt the bones of the after-wriſt.* ξ ξ 1 2 *The heads of the bones of the after-wriſt, which enter into the boſoms of the toes.* ϖ 2 *A proceſs of the bone of the after-wriſt wherein the tendon of the ſeventh muſcle of the foot is implanted.* ρ 2 *a proceſs of the bone of*

the after-wriſt, which ſuſtaineth the little toe, which proceſs receiveth the tendon of the muſcle of the foot. 5 T υ 1 2 *The three bones of the fore-toe.* ♃ ω 2 *Two ſeed-bones placed under the bone of the after-wriſt which ſuſtaineth the great toe.* * 2 *Under* X, *a ſeed-bone ſet to the ſecond joynt of the great toe.* Γ 1 2 *The* Talus *or Paſtern.* Δ 1 2 *The heel.* ☽ 1 2 *The boat-bone.* Λ Ξ 1 2 *The bones of the toes.* Φ X 1 2 *Two bones of the great toe,* I III III IV V 1 *The five bones of the after-wriſt.*

I paſs over in ſilence many other things; as, the ſmoothneſs and aſperity, or roughneſs of the bone, which I had rather you ſhould learn by ocular Inſpection, than by Book. The ſecond bone lying under this is called the *Calcaneum*, or heel-bone, being the biggeſt of all the bones of the foot, upon which all the body relies when we go. It hath two upper proceſſes, the one great, the other little. The great is received in the hind and outer proceſs of the *Aſtragalus*; the leſſer is received on the inſide in the third proceſs of the ſame bone, the which we ſaid had a round head faſtned to a long neck. Beſides, it is round on the hind-part, and much diſ-joyned from the leg-bone, but on the fore and longer part, it is knit by *Synarthroſis* to the die-bone, whoſe lower and inner part it ſeems to receive; the ſuperficies thereof is wholly unequal, and riſing up with many ſwellings. On the inner ſide, it makes, as it were, a channel, ſo to give way, as well to the veſſels as tendons going to the ſole of the foot and toes. Laſtly, we muſt conſider the holes by which the veſſels paſs into that bone to give it nouriſhment; by reaſon of which veſſels the fracture of this heel-bone, is very dangerous, becauſe of the preſſing and contuſion of the veſſels; as *Hippocrates* ſhews. For the ligaments of this heel, or heel-bone, they are ſuch, as thoſe of the *Aſtragalus*, to wit, tendons, membranes and ligaments properly ſo called, coming from one bone to another. The third bone of the foot is named *Scaphoides*, or Boat-like, from the reſemblance it hath to a Boat, for on that part which looks towards the Paſtern-bone, it is hollow; but on that part which is next the three *Innominata*, or nameleſs bones (which it ſuſtains, and of which it is received, as it in the cavity thereof receives the head of the *Aſtragalus*) it is gibbous like the bottom of a Boat The connexions thereof are by *Synarthroſis*, and they are ſtrengthned by the fore-mentioned ligaments: This ſame bone is arched on the upper part, but ſomewhat hollowed or flatted below; the inner part ends in a point, like the prow of a ſhip, but the outer obtuſe like the ſtern of a ſhip. The fourth bone of thoſe which have names, is called *Cuboides*, from the reſemblance of a Die; although that ſimilitude be very obſcure. On the fore-part it ſuſtains the toes, which by a certain proportion to the fingers of the hand, may be called the ring and little toes; but it is ſuſtained on the hind-part, with the back-part of the heel; on the inner ſide it is joyned with the Boat-like bone, and that nameleſs bone which ſuſtains the middle toe; on the out-ſide it produces a riſing like the back of an Aſs, which on the lower part is extended tranſverſly all the length thereof; at the two ſides of this eminency, or riſing, there are two ſmall cavities, in form of a channel.

The firſt and the greater of the *Oſſa innominata*, or nameleſs bones, ſuſtains the great toe; the leſſer and ſecond, the next toe thereto; the third and middle in bigneſs, the middle toe. Theſe three bones are arched on their upper part, but ſomewhat hollowed below. They are knit to the three fore-mentioned bones by *Synarthroſis*, of which they are received; but on the hind-part with the Boat-like bone which they receive. Now we muſt come to the bones of the ſecond rank, that is, of the *Pedium*, or back of the foot; theſe are five in number, bearing up the five bones of the toes. They are ſomewhat gibbous on the upper part, but hollow below; each of them hath two proceſſes at the end thereof, by the lower and firſt of which they receive the three nameleſs and die-bone, but by the upper made into a round head, they are received of the firſt bones of the toes. Their connexions, whether with the toes, or bones of the inſtep, are by *Synarthroſis*. The ligaments as well proper as common are ſuch, as we ſaid of the former. The bones of the third order now remain to be ſpoken of, which, we ſaid, makes the toes; and they are fourteen, two of the greater toe, but three of each of the other toes. The firſt is ſomewhat longiſh, but the reſt are very ſhort, except that of the great toe, all of them on the upper ſide are round and convex; but on the lower ſomewhat hollow, and plain-wiſe, that the tendons which bend them, may paſs more ſtaitly and ſafely without inclining to either ſide, even to their furtheſt joynts; although ſuch paſſages are much helped by the membranous and common ligament, which riſing from the ſides of theſe bones, involves theſe tendons, as we mentioned in the fingers. To conclude, each of theſe bones, the laſt excepted, have a double connexion by *Diarthroſis*, they are all unequal in their bigneſs, that is, thick at their beginning (where they receive the heads of the precedent bones, upon which they move as a door upon the hinges) and ſo they grow ſmaller towards the ends; but by their ends, they are received of the following bones: At their ends they riſe into two eminencies on their ſides, diſtinguiſhed by a cavity between them, through which occaſion they are far thicker at their ends, than in their middle. The Ligaments by which their connexions are faſtned, are ſuch as the former. The *Oſſa ſeſamoidea* or ſeed-bones of the feet, are like in number and ſite to thoſe of the hands. But this is to be noted, that thoſe ſeed-bones which are in the firſt Articulation are ſomewhat bigger than the reſt, and they are round and longiſh on the out-ſide, but ſmooth and hollow on the inſide, ſeated between two cavities, encompaſſed by three riſings, of which two are on the ſides, and the third in the midſt of the extremity of the firſt bone of the *Pedium*, which chiefly bears up the great toe. To conclude, before we come to ſpeak of the Muſcles, we muſt obſerve, that the foot was made for two commodities. The firſt is, to ſtay and bear the whole body, when we ſtand, for which cauſe Nature ſet not the great toe contrary to the other, as it placed the thumb on the hand. The other is for apprehenſion, or taking hold of; wherefore Nature framed and made the foot, and theſe moveable and joynted in the toes, as in the fingers of the hand. Beſides alſo, for that we muſt go upon our feet, Nature hath made them in ſome places hollow on the lower ſide, and in other ſome plain in a triangular figure, that ſo our feet may carry us over every ſoil, plain, mountainous, equal and unequal, through all parts of the world.

The deſcription of the *Calcaneum* or *Calx*.

Why a fracture of the heel is ſo dangerous. *Hippocrates, Sect. 3. lib. de fracturis.*

The *Os Scaphoides*, or Boat-like bone.

The *Os Cuboides* or Die-bone.

The *Oſſa innominata* or nameleſs bones.

The bones of the foot or *Pedium*.

The bones of the toes.

The ſeed-bones of the foot.

The twofold uſe of the feet.

CHAP.

CHAP. XXXIX.

Of the Muſcles moving the Foot.

THe muſcles of the leg moving the foot are abſolutely nine, three in the fore-part, and ſix in the hind. Two of three fore-muſcles bend the foot, when they joyntly perform their action; but when ſeverally, each draws it to his ſide; the third chiefly extends the toes, for otherwhiles it ſeems by its ſlenderer and longer tendon (which exceeds not that bone of the *Pedium*, which ſuſtains the little toe) to help alſo to bend the foot. Their number.

The firſt is called *Peronæus*, becauſe it deſcends alongſt the bone *Perone*. The other the *Tibiæus anticus*, for that it deſcends along the *Os Tibiæ*, or bone of the leg. The third from its action is called the *Digitum-tenſor*, or Toe-ſtretcher. For their original, the *Peronæus* which ſeems to have two heads, deſcends from the upper appendix of the *Perone*, or ſhin-bone by its firſt head, but by the other from the middle of the ſame bone from the fore-ſide into the hind, as the ſuperficies ſhews which paſſes between the fore and outward line of the ſaid bone; but after it arrives at the lower and hinder appendix of the ſame bone, behind the outer ankle, it produces two tendons, which by the guidance of the ligaments, as well proper as common, go the thicker under the ſole of the foot, ending in the die-bone, and that bone of the *Pedium* which ſuſtains the great toe; the leſſer goes on the out-ſide to the die-bone; and the laſt and leaſt bone of the *Pedium* which bears up the little toe, ſometimes a ſlender portion thereof is produced even to the ſide of the little toe, extending and drawing it from the reſt. *Muſculus Peronæus.*

The *Tibiæus anticus* or fore-leg muſcle proceeding from the upper and outer appendix of the leg-bone deſcends above the ſurface of the ſame bone, which is between the four and outer-line to which it adheres, as alſo to that ſurface even to the midſt, from which place it produces one tendon, which deſcending on the fore and loweſt part, ends on the out-ſide into two of the nameleſs bones, that is, into the firſt which is the thicker, and into the middle-moſt; but beſides, by a ſlender portion thereof, it is extended into the firſt and greater bone of the *Pedium*, ſo to extend the great toe, drawing it inwards to the other foot. And this muſcle with the precedent bends the foot, if they both perform their parts at once; but if ſeverally, each draws the foot towards his ſide. *Tibiæus anticus.*

The third, which is the *Digitum-tenſor*, or Toe-ſtretcher, is twofold; the one takes its original from the top of the leg, and running alongſt the ſhin-bone, and paſſing under the ring, carries it ſelf into the foot, in which it ends by five tendons going to all the joynts of the toes, and by a ſixth at that bone of the *Pedium* which ſuſtains the little toe, whereby (as we formerly ſaid) it helps the bending of the foot. The other deſcends into the midſt of the ſhin-bone, and ſomewhat faſtned thereto, by one tendon paſſing under the ring, it goes to the great toe. But you muſt note, that all theſe tendons have nervous, ligamentous, and fleſhy fibers ſo ſeparated from each other, that they can equally alone perform their function, as if they were more diſtinct muſcles. And we muſt think the ſame of the reſt which have diſtinct tendons preſently from their fleſhy part. The Toe-ſtretcher is two-fold.

The ſix hind-muſcles follow: of which the two firſt are called the *Gemelli*, or Twins, by reaſon of the ſimilitude of their thickneſs, original, inſertion and action. The third is called the *Plantaris*, becauſe it is ſpent upon the ſole of the foot, as the *Palmaris* upon the palm of the hand. The fourth is termed the *Soleus*, or ſole-muſcle, by reaſon of the reſemblance it hath to the fiſh of that name. The fifth the *Tibiæus poſticus*, or hind-leg muſcle, which deſcends alongſt the back-part of the leg-bone. The ſixth and laſt the *Digitum-flexor*, or Toe-bender, equivalent to the deep muſcle of the hand. Some make but one muſcle of this, and the *Tibiæus poſticus*, which produces three tendons; others had rather make three, as thus, that one ſhould be the *Tibiæus*, the other the bender of four toes, the third the bender of the great toe. The ſix hind muſcles.

Now for the two *Gemilli*, or Twins, the one is internal, the other external; the internal paſſes forth from the root of the inner Condyle of the thigh; but the external from the external Gondyle; and from this their original preſently becoming fleſhy, eſpecially on the out-ſide, they meet together a little after in their fleſhy parts, and with the *Soleus* they make the thick and great tendon at the midſt of the leg, which from thence is inſerted into the back-part of the heel; in this very tendon, breed painful kibes. The action thereof is, to help our going by putting forth the foot, whilſt it draws the heel towards its original. The two *Gemelli* or Twin-muſcles. In what place the kibes breed.

The *Plantaris* the leaſt and ſlendereſt of them all, paſſes forth fleſhy from the outward head of the leg-bone, and from thence the ſpace of ſome four fingers breadth it ends in a ſtrong and ſlender tendon, which it ſends between the twin and ſole muſcles to the ſole of the foot, there to produce a membrane which covers the ſole of the foot, and a muſcle equivalent to the upper bender of the hand. The *Plantaris.*

The *Soleus*, or ſole-muſcle, the thickeſt of them all, and ſeated under the Twin-muſcles, deſcends from the Commiſſure of the leg and ſhin-bones, and about the midſt of the leg, after it hath mixed his tendon with that of the twin-muſcles, it runs into the foreſaid place that it may extend the foot for the foreſaid uſe. The *Soleus.*

The *Tibiæus poſticus* deſcends from the hinder appendix of the leg and ſhin-bones, and adhering to them almoſt as far as they go, by a ſtrong tendon, being, as it were, bony at the end thereof it is inſerted into the Boat-like bone, and the two firſt nameleſs bones; ſo to help the oblique extenſion of the foot. The *Tibiæus poſticus.*

The laſt being the *Digitum-flexor*, or Toe-bender, is two-fold; for one ariſes from the leg-bone, in that place where the *Poplitæus* ends, and inſerted into that ſame bone, it goes even to the back-ſide of the inner ankle, and from thence into the joynts of four of the toes. The other draws his original from almoſt the middle of the ſhin-bone, and ſomewhat inſerted into it, it goes by the The *Digitum-flexor* twofold.

heel and paſtern-bone to the great toe, mixed with the precedent; their action is to bend the firſt joynt of the toes, rather by the force of the common ligament, than by the ſmall portion of the tendon which ends there. But it is their action to bend the laſt dearticulation of the toes by their proper inſertion.

CHAP. XL.

Of the Muſcles moving the toes of the Feet.

Their number.

NOw follow the muſcles moving the toes; theſe are eight in number, one on the upper, and ſeven on the lower ſide. The firſt proceeds from the paſtern, heel, and die-bones below the external ankle, or the ligament of theſe bones with the leg-bone; and obliquely ſtretched to the top of the foot, is parted into five ſmall tendons to the ſides of the five toes, ſo to draw them outwards towards it original, whereupon it is called the *Abductor* of the toes, and alſo *Pedioſus*, becauſe it is ſtretched over the *Pedium*, or back of the foot.

The *Abductor* of the toes or *Pedioſus*.

The *Flexor ſuperior*.

The firſt of the ſeven of the lower ſide called the *Flexor ſuperior*, or upper-bender, ariſes from the heel; and ſtretched alongſt the foot under the ſtrong membrane (which from the heel is ſtraitly faſtned to the extremity of the bones of the *Pedium*, to ſtrengthen the parts contained under it) is inſerted by four tendons, at the ſecond joynt of the four toes which it bends. Here you muſt note, that near the inſertion thereof, this muſcle divides it ſelf, like that muſcle of the hand which is called *Sublimis*, that ſo it may give way to the deep, which (as we ſaid) deſcends alongſt the fingers, to which a certain common membranous ligament adjoyns it ſelf, which involves and faſtens it to the bone all alongſt the lower part of the fingers, even to the laſt dearticulation.

The muſcle equivalent to the *Thenar*.

The ſecond equivalent to that muſcle of the hand which is called *Thenar*, ſeated on the inner ſide of the foot, ariſes from the inner and hollow part of the heel and paſtern-bones, and ends in the ſide, and inner part of the great toe, which it draws from the reſt inwards: This may be divided into two or three muſcles, as the *Thenar* of the hand, to draw the great toe to the reſt, as much as need requires, juſt as we ſaid of the hand. The third anſwerable to that of the hand which is named the *Hypothenar*, paſſes from the outer part of the heel, and aſcending by the ſides of the foot, it is in like manner inſerted into the ſide of the little toe, ſo to draw it from the reſt; to which ſame action, a certain fleſh contained under the ſole of the feet may ſerve, which is ſtretched even to theſe toes, that alſo it may ſerve to hollow the foot.

The four *Lumbrici*.

The four *Lumbrici*, or wormy-muſcles follow next, which from the membrane of the deep toe-bender, are inſerted into the inner and ſide part of the four toes, ſo to draw them inwards by a motion contrary to that which is performed by the *Pedioſus*.

The deſcription of the upper and lower *Interoſſes*.

The *Interoſſes* or bone-bound muſcles of the *Pedium* or back of the foot, remain to be ſpoken of: Theſe are eight in number, four above and as many below, different in their original, inſextion and action: For the upper, becauſe they draw the foot outwards with the *Pedioſus*, ariſe from the fore and inner part of that bone of the *Pedium*, which bears up the little toe (and ſo alſo the reſt each in its order) are inſerted into the outward and fore-part of the following bone. The lower, on the contrary, paſs from the four and outer part of that bone of the *Pedium*, which bears up the great toe (and ſo each of the reſt in its order) but are inſerted into the inner and upper part of the following bone, ſo with the wormy-muſcles to draw it inwards, or to hollow the foot outwards, or to flat the foot, as we ſaid of the *Interoſſes* of the hand.

CHAP. XLI.

An Epitome, or brief recital of the bones of a mans Body.

The bones of the skull fourteen.

THe whole head which hath the leaſt, conſiſts of ſixty bones; but that which hath moſt, of ſixty three; that is, fourteen of the *Cranium* or skull, fourteen or ſeventeen of the face, and thirty two teeth: Of the bones of the skull there be eight containing, and ſix contained; the containing are, the *Os frontis*, or forehead-bone, the nowl-bone, the two bones of the *Synciput*, the two ſtony-bones, the wedg-bone, and the ſive-like or ſpongy-bone. But the contained are ſix, ſhut up in the cavity of the ears, the anvil, hammer and ſtirrop.

The bones of the face fifteen.

For the bones of the face, there are ſix within or about the orb of the eye, that is, on each ſide three; two bones of the noſe, two leſſer jaw-bones, and two bigger, which are always in beaſts ſeen diſtinguiſhed by a manifeſt difference, but it is ſo rare in men, that I have not found it as yet; therefore theſe only are diſtinguiſhed by manifeſt difference, two which contain all the upper teeth, the two inner of the palate, the two of the lower jaw in children; and laſt of all the *Os Criſtæ*, whence the middle griſtle or partition of the noſe ariſes.

The teeth thirty two.

The two and thirty teeth are equally diſtributed in the upper and lower jaws; and of theſe there be eight ſhearers, four fangs or dog-teeth, and twenty grinders.

The bone *Hyoides*.

And there is another bone at the root of the tongue called *Os Hyoides*, always compoſed of three bones, ſometimes of four.

The bones of the ſpine thirty four.

Now follow the bones of the ſpine, or back-bone, which are juſt four and thirty, that is, ſeven of the neck, twelve of the cheſt, five of the loins, ſix of the holy-bone, and four of the rump. Beſides, there are two bones of the throat, or collar-bones.

Two collar-bones.

The ribs twenty four.

The ribs are twenty four, that is, fourteen true, and ten baſtard ribs.

The bones of the *Sternon* three.

The bones of *Sternon*, or breaſt-bone moſt frequently three, otherwhiles ſeven, as ſometimes in young bodies.

The bones of the whole arm ſixty two.

Hence coming to the arm there are reckoned ſixty two, beginning with the ſhoulder-blade; as

there

there are two ſhoulder-blades, two arm-bones, four bones of the cubit, that is, two ell-bones, and two wands, ſixteen of the wriſt, eight of the after-wriſt, and thirty of the fingers; into this number alſo come the *Seſamoidea*, or ſeed-bones, of which ſome are internal, and theſe always twelve at the leaſt, although ſometimes there may be more found, a great part of which rather merit the name of griſtles, than bones; there are others external, if we believe *Sylvius*.

The firſt ſheweth the fore-part of the Sceleton of a man, &c.

The Declaration of theſe three Figures put into one.

A 3 *The coronal ſuture called in Greek* στεφανιαία.

B 2 3 *The ſuture like the letter* λ, *called* λαμβδοειδὴς.

C 2 *The ſagittal ſure called* ὀβελιαῖα.

D 2 3 *The ſcale-like* Conjunction *called* λεπιδοειδὴς.

α 2 3 Os verticis, *or* Syncipitis, *the bone of the* Synciput, *called* Os βρέγματος.

1 3 *The forehead bone, that is* μετώπη.

γ 2 3 *The bone of the nowl or* ἰνίς.

δ 2 3 *The bones of the temples or* μεθιαφῶν.

ε 3 *An appendix in the temple-bone like a bodkin*, σπιλοειδὴς.

ζ 1 2 3 *A proceſs in the temple-bone like the teat of a dug, called therefore* Mammillaris *and* μαστοειδὴς.

E 2 3 *The wedg-bone*, σφηνοειδὲς.

η 3 *The ſtony part of the ſkull.*

θ 3 *A proceſs of the wedg-bone much like the wing a Bat, and therefore called* πτερυγοειδὴς.

Now remain the bones of the leg, which (if we reckon the *Oſſa Ilium*, on each ſide three, as in young bodies it is fit it ſhould) they are ſixty ſix, beſides the ſeed-bones, that is to ſay, two hannch-bones, two ſhare-bones, two huckle-bones, two thigh-bones, two whirl-bones of the knees, four of the leg, that is, two leg-bones, and two ſhin-bones. Fourteen of the inſtep, as two heel, two paſtern, boat-like, two die, and ſix nameleſs bones. Ten of the *Pedium*, or back of the foot, that is, five in each foot, and twenty eight of the toes; and as many ſeed-bones in the feet, as the hands enjoy. But I have thought good to add theſe Figures for the better underſtanding of what hath been ſpoken hereof. The bones of the whole leg ſixty ſix.

The

The ſecond and third Figure ſheweth the brck-ſide of the Sceleton. and the lateral part of the Sceleton.

F 1 2 3, *The yoke-bone,* ζύγπμα. G 1 3 *The lower jaw.* IKLMN 1 2 3 *The back or the ſpine* ῥαχίς. *From* I *to* K *the neck,* τραχηλος. *From* K *to* L *the rack-bones of the cheſt. From* L *to* M *the rack-bones of the loins. From* M *to* N *the holy-bone,* ἱερὸν. N *The rump-bone,* κόκκυξ. O 1 3 *The breaſt-bone,* στέρνον. P 1 3 *The ſword-like griſtle of the breaſt,* ξιφοειδὴς. *Char.* 1 3, *as far as to* 12, *in all, three Tables, ſhew the twelve ribs of the cheſt,* πλευραί. Q 1 *The clavicles or collar-bones,* κλεῖδες. R 1 2 3 *The ſhoulder-blade,* ὠμοπλάτες. λ 1 2 3 *The upper pooceſs of the ſhoulder-blade, or the top of the ſhoulder, called* ἀκρώμιον. μ 1 3 *The lower proceſs of the ſhoulder-blade, called* ἀγκωνοειδὴς. S 1 2 *The bone of the arm, called* Humerus, *and* βραχίων. TV 1 2 3. *The cubit* πῆχυς. X 1 2 3 *The wand, or the upper bone of the cubit, called* κερκὶς. Y 1 2 3 *The ell or lower-bone of the cubit, called* πῆχυς. ν 3 *The proceſs of the cubit,* ὠλένοκρανον. ξ 1 3 *The proceſs like a bodkin, or probe, called* στυλοειδὴς. ZZ 1 2 3 *The wriſt,* καρπός. ΓΓ 1 3 *The after-wriſt,* μετακάρπιον. ΔΔΔ 1 *The fingers* δάκτυλοι. Θ 1 2 3 *The bones joyned to the ſides of the holy-bone, on each ſide diſtinguiſhed, as it were, into three parts.* ο 1 2 3 *The firſt part called the hanch-bone,* Os Ilium, λαγόνων. ϖ 1 2 3 *The ſecond part of the bone of the* Coxendix, ἰσχίον. ρ 1 2 3 *The third part of the ſhare-bone,* Os pubis, ἴβυς. σ 1 2 3. *A griſtle going between the conjunction of the ſhare-bones.* Λ 1 2 3 *The thigh,* μηρὸς. τ 1 2 3 *The greater outward proceſs of the thigh called* Rotator, τροχαντὴρ μέγας. υ 1 2 3. *His leſſer and inner proceſs.* Ξ 1 2 3 *The whirl-bone of the knee,* Patella Rotutula, ἐπιμύλις. Π Σ 1 2 3 *The leg,* κνήμη. Φ 1 2 3 *The inner and greater bone of the leg,* περόνιον. Ψ 1 2 3 *The utter and ſmaller bone of the leg, called the Brace-bone,* Fibula, περόνη. Φ 1 2 3 *The proceſs of the leg, or the inner ankle, called* Malleolus internus. X 1 2 *The proceſs of the brace of the outward ankle, both of them are called in Greek* σφυρὸν. Ω 1 2 3 *The bone called the Cock-all,* Talus, ba liſta, Os ἀστράγαλος. a 2 *The heel* Calx, πτέρνα. *b* 1 3 *The bone called* Os Naviculares, σκαφοειδὲς. cc 1 2 3 *The wriſt of the foot called* Tarſus, *conſiſting of four bones,* ταρσὸς. d e f 1 2 3 *Three inner bones of the wriſt of the foot called by ſome* χαλκοειδῆ. g 1 2 3 *The utter bone of the wriſt of the foot like a Die, called* κυβοειδὲς. h h 1 2 3 *The after-wriſt of the feet called* Pedium, *by ſome* μεταταρσος. ii 2 3 *The toes of the foot.* k 1 2 3 *The ſeed bones of the foot, called* officula ſeſamina, σησαμοειδῆ.

This

This Figure ſheweth the Sceleton *of the bones and griſtles of a Woman, that it may appear all her bones are in proportion leſſer than the bones of a man. But in this Figure, only thoſe parts are marked with letters wherein a Woman differeth from a Man in her bones and griſtles.*

A *The ſagittal ſuture deſcending into the noſe, and dividing the forehead-bone, which is ſometimes found in women, very rarely in men, but always in infants.*

BB *The cheſt ſomewhat depreſſed before, becauſe of the paps.*

CC *The collar bones not ſo much crooked as in men, nor intorted ſo much upward.*

D *The breaſt-bone perforated ſometimes with a hole much like the form of a heart, through which the veins do run outward, from the mammillary veins unto the paps.*

E *The griſtles of the ribs, which in women are ſomewhat bony, becauſe of the weight of the dugs.*

F *A part of the back reflected, or bent backward above the loins.*

G G *The compaſs of the hanch-bones running more outward, for the womb to reſt upon, when a woman is with child.*

HH *The lower proceſſes of the ſhare-bones, bearing outward, that the cavity marked with* K, *might be larger.*

I *The Anterior commiſſure or conjunction of the ſhare-bones filled up with a thick griſtle, that in the birth they might better yield ſomewhat for natures neceſſity.*

K *A great and large cavity circumſcribed by the bones of the Coxendix and the holy-bone.*

L *The rump or* coccyx, *curved backward to give way in the time of the birth.*

M *The thigh bones by reaſon of the largeneſs of the foreſaid cavity, have a greater diſtance betwixt them above, whence alſo it is that Womens thighs are thicker than Mens.*

CHAP. XLII.

An Epitome of the names and kinds of compoſure of the Bones.

BEcauſe it is as neceſſary for a Chirurgeon to know the manner of ſetting and repairing broken bones, as to put them in their places when they are diſlocated, or out of joynt; but ſeeing neither of them can be underſtood when the natural connexion of the bones is not known; I have thought it a work worth my labour, briefly to ſet down, by what and how many means the bones are mutually knit and faſtned together. The univerſal compoſure and ſtructure of all the bones in a mans body is called by the Greeks *Sceletos*. But all the bones are compoſed after two ſorts, that is, by *Arthroſis*, an Articulation or joynt, and by *Symphyſis* a natural uniting or joyning together. There are many other kinds of both theſe ſorts. For there are two kinds of Articulation, that is, *Diarthroſis*, or De-articulation, and *Synarthroſis*, or Co-articulation; which differ as thus, De-articulation is a compoſition of the bones with a manifeſt and viſible motion; Co-articulation hath a motion of the bones, yet not ſo manifeſt, but more obſcure. But theſe two, do again admit a ſubdiviſion into other kinds. For *Diarthroſis*, contains under it *Enarthroſis*, *Arthrodia*, and *Ginglymos*. Now *Enarthroſis* or Inarticulation is a kind of Dearticulation, in which a deep cavity receives a thick and long head, ſuch a compoſition hath the thigh-bone with the huckle-bone.

What the *Sceletos* is.

Two ſorts of Articulation.

What *Diarthroſis* and *Synarthroſis* are.

Three ſorts of *Diarthroſis*.

What *Enarthroſis* is.

Arthrodia is when a lightly engraven cavity admits a ſmall and ſhort head; ſuch a connexion is that of the arm-bone with the ſhoulder-blade; of the firſt *Vertebra* with the ſecond. The Greeks have diſtinguiſhed by proper names theſe two kinds of cavities and heads; for they call the thick and long head *Cephale*, that is, a head abſolutely; but the leſſer they term *Corone*, or *Coronon*, which the Latins call *Capitulum*, a little head. But they call a deep cavity *Cotyle*, and a ſuperficiary one *Glene*. The third ſort called *Ginglymos*, is when the bones mutually receive, and are received one of another; as when there is a cavity in one bone, which receives the head of the oppoſite bone, and alſo the ſame bone hath a head which may be received in the cavity of the oppoſite bone; ſuch a compoſure is in the cubit-knee, that is in the connexion of the thigh-bone. And thus much of Dearticulation and the three kinds thereof.

What *Arthrodia*.

What *Cephale* is.

What *Cotyle* is.

What *Glene* is.

What *Ginglymos*.

Synarthroſis, or Coarticulation, another kind of juncture, hath alſo three kinds thereof (*Gal. lib. de Oſſibus*) to wit, *Sutura*, *Gomphoſis* and *Harmonia*.

Three kinds of *Synarthroſis*.

Suture

What a *Suture* is.
What *Gomphoſis* is.
What *Harmonia* is.

Suture is a compoſition of the bones after the manner of ſewing things together, example whereof appears in the bones of the skull. *Gomphoſis* is when one bone is faſtened in another as a pin is faſtened in a hole, after which manner the teeth are faſtened in their ſockets in both the jaws. *Harmony* is when the bones are compoſed by the interpoſition of a ſimple line, after which manner many bones of the noſe and face are joyned together.

Hitherto we have ſpoken of the firſt conſtruction of the bones by articulation and the kinds thereof; now it follows we treat of *Symphyſis*.

What *Symphyſis* is.

Symphyſis or growing together, as we formerly ſaid, is nothing elſe, than natural union of the bones; ſuch union is made two manner of ways, that is, either by interpoſition of no other thing; after which ſort, in ſucceſs of time the bones of the lower jaw grow together, which formerly in children were manifeſtly diſtinguiſhed, or by the mediation of ſome *medium*; but that happens three manner of ways, by interpoſition of three ſeveral *Media*, as firſt of a griſtle, which kind of union the Greeks call *Syncondroſis*, after which manner the ſhare-bones grow together, and alſo ſome *Appendices* in young bodies; ſecondly, of a ligament, and it is named by the Grecians *Synneuroſis*, the name of a nerve being taken in the largeſt ſenſe; for ſometimes it is uſed for a tendon, otherwhiles for a ligament, otherwhiles for a nerve, properly ſo called, and which is the author of ſenſe and motion. But this *Symphyſis*, or union, hath place by *Synneuroſis*, or interpoſition of a nerve, in certain bones of the *Sternon* and hanch.

Syncondroſis.

Synneuroſis. The things ſignified by the word *Nerve.*

Synſarcoſis.

Thirdly, the bones grow into one by interpoſition of fleſh, called in Greek *Synſarcoſis*; thus the fleſh of the gums faſtens the teeth, and makes them immoveable. But if ſome be leſs pleaſed with this diviſion, by reaſon of the obſcurities in which it ſeems to be involved, this following expreſſion comes into my mind, which I was firſt admoniſhed of by *German Cortin* Doctor of Phyſick, which if you well obſerve it, is both blameleſs and more eaſie for your underſtanding.

An Epitome or brief recital of all the Muſcles of mans body.

As I have formerly reckoned up the bones, ſo here, I have decreed to recite the muſcles of mans body. Wherefore in the face we firſt meet with the broad or skin-muſcle ariſing from the fleſhy pannicle, and covering the whole neck, and almoſt all the face. Then follow four pertaining to the upper eye-lids. In the orbs of the eyes lie fourteen, that is, ſeven in each orb, of which four are called right, two oblique, and one pyramidal. Then ſucceed four of the noſe, two external, on each ſide one, and two internal; theſe draw it together, and the other open it. After theſe come the ten muſcles of the lower jaw, of which two are called the *Crotaphitæ*, or temporal; two *Maſſeteres* or grinders; two round (which ſeem to me rather to pertain to the lips, than to this jaw;) two little ones hid in the mouth, ariſing from the winged proceſs of the wedg-bone; two openers of the mouth being nervous or tendinous in their midſt. Then follow the eight muſcles of the lips, that is, four of the upper, and as many of the lower, ſhutting and opening the mouth. The tongue with his ten muſcles hid, as it were, in the den of the mouth. Wherefore the muſcles of the whole face are fifty one. In the four part of the neck are found the muſcles of the bone *Hyoides* and throttle: Now eight muſcles hold the bone *Hyoides* as equally ballanced; of which there are two upper ariſing from the chin, two on the ſides from the proceſs *Styloides*, perforated in their midſt, through which the two openers of the mouth in that part nervous do paſs; two ariſe from the *Sternon*, and laſtly, two from the upper rib of the ſhoulder-blade to the *Coracoides*, which alſo in their midſt are nervous, in which place the two *Maſtoidei* lye upon them.

The bones which as pillars ſuſtain the Fabrick of the whole Body; are either

- *United mutually by* Symphyſis, *or union; by which they are ſo conjoyned that there is no diſſimilar, nor heterogeneous body, at leaſt which may be diſcerned, interpoſed between them. Such union appears in the two bones of the lower jaw at the chin, in the bones of the* Sternon, *the hanch with the huckle-bones, and the ſhare-bones between themſelves; of this union there are no more kinds, for by this it cometh to paſs, that the bones which were more and diſtinct meet together by interpoſition of one* Medium, *to wit, a griſtle, which now indeed, is no griſtle, but is turned into a bone.*
- *Or Conjoyned by that which they call* Arthrodia, *or Articulation, as when they ſo concur and are bound together, that ſome Heterogeneous ſubſtance may be noted betwixt them, but the bones thus compoſed are knit two manner of ways; that is,*
  - *Either more looſly as by* Diarthroſis *that is a kind of Articulation not very ſtrait, as by which it might have opportunity to perform diverſe motions: Of this Compoſition or Articulation of bones there are three kinds; as,*
    - Enarthroſis, *when the head of a bone is wholly received in the cavity of another, and hid therein, as the thigh-bone is joyned with the huckle-bone.*
    - Arthrodia, *when in a lightly engraven and not much depreſſed cavity the head of another bone is not wholly hid, but onely received in part thereof; ſo that, unleſs Nature had otherwiſe provided a ſufficient receptacle for the head of this bone (as by the ligaments of the neighbouring muſcles) it would otherwiſe have been in perpetual danger of diſlocation. Thus the arm-bone is faſtened to the ſhoulder-blade.*
    - Ginglymos, *when the bones mutually receive each other; ſuch like compoſition hath the cubit and arm-bone.*
  - *Or more ſtraitly, as by* Synarthroſis *when the bones are more ſtraitly knit, ſo that they can perform no motions in the body. Of this Articulation there are alſo three kinds, that is,*
    - Gomphyſis, *as when one bone ſo receives another as a pin is faſtned in the hole made by a piercer; thus the teeth are faſtned in the jaws.*
    - Sutura, *like a Saw, or teeth of a Comb; as the bones of the skull are mutually knit together; or as Scales, or Tiles are laid, after which manner the ſtony-bones are faſtned to thoſe of the* Sinciput.
    - Harmonia, *which is by interpoſition of a ſimple-line, which parts bones abutting one upon another, as the bones of the noſe.*

The

The Throttle compoſed of three griſtles hath eighteen or twenty muſcles; of which ſix or eight are common, and twelve proper; Of the common there are two above, two below, and two at the ſides of the firſt griſtle; to which we may add thoſe two which ſerve for the opening of the *Epiglottis*, which are always found in great four-footed Beaſts for to preſs down the *Epiglottis*. The eighteen muſcles of the *Larinx*.

The proper are twelve, which almoſt all of them come from the ſecond griſtle, ſo to be inſerted into the firſt and third, of which ſome are before, others behind the *Thyroides*. Beſides, theſe are the *Maſtoidei* which bend the head.

But in the back part of the neck there are twelve muſcles alſo appointed for to move the head, ſo that in all there are fourteen muſcles ſerving for the motion of the head, the two fore *Maſtoidei*, and the twelve hind-muſcles, that is to ſay, the two *Splenii*, two *Complexi*, four right, and ſo many oblique, which are very ſhort, ſo that they paſs not beyond the firſt and ſecond *vertebra*. The head is moved by fourteen muſcles.

The neck hath eight muſcles, of which two are called the long, lying before upon the bodies of the *Vertebræ*; the two *Scaleni*, whichare at the ſides; the two *Spinati*, which run alongſt the ſpine; the two tranſverſe, which go to the tranſverſe proceſs of the cheſt. The eight muſcles of the neck.

The cheſt hath eighty one muſcles, of which ſome are on the fore-part, ſome on the hind, others on the ſides; they are all combined and coupled together, except the midriff. Now of theſe there are the two *Subclavii*; the two great ſaw-muſcles which proceed from the baſis of the ſhoulder-blade; the four little *Rhomboides*, or ſquare-muſcles, that is, two above, and two below; the two *Sacrolumbi*, the two binders of the griſtles within the cheſt. The muſcles of the cheſt eighty one.

Beſides, there are twenty and two external, and as many internal intercoſtal muſcles, twenty four *Intercartilaginei*, that is, twelve external, and as many internal; ſo that the intercoſtal, and *Intercartilaginei*, are ſixty eight, which with the twelve before mentioned, make the numbr of eighty muſcles. Add to theſe the midriff being without an aſſociate, and you ſhall have the number formerly mentioned, to wit, eighty one. But alſo, if you will add to theſe the muſcles of the lower belly, I will not much gain-ſay it, becauſe by accident they help inſpiration and exſpiration.

Wherefore of the eight muſcles of the *Epigaſtrium*, there are four oblique, of which two are deſcendent, and ſo many aſcendent; two right, to which you may add the two aſſiſting or pyramidal muſcles which come from the ſhare-bone, if it pleaſe you to ſeparate them from the head of the right muſcles. The eight muſcles of the lower-belly.

There are ſix or eight Muſcles of the Loins, of which two bend the Loins, which are the triangular; the two *Semiſpinati*; two *Sacri*; two are in the midſt of the back, which for that cauſe we may call the *Rachitæ*, or Chine-muſcles. Now, that hereafter we may ſeverally and diſtinctly ſet down the muſcles of the extreme parts, we will come to the privities. The ſix or eight of the loins.

Where for the uſe of the teſticles, there are two muſcles called the *Cremaſteres*, or hanging-muſcles. At the root of the yard, or *Peritonæum*, there are four others, partly for the commodious paſſing of the urin and ſeed, and partly for erecting the yard. The *Sphincter*-muſcle is ſeated at the neck of the bladder. The two cremaſters of the teſticles.

At the end of the right gut are three muſcles, two *Levatores Ani*, or lifters up of the fundament, and one *Sphincter* or ſhutting-muſcle. Now let us proſecute the muſcles of the extremities or limbs. But it will be ſufficient to mention only the muſcles of one ſide, becauſe ſeeing theſe parts of the body are double, thoſe things which are ſaid of the one may be applied to the other. The three of the fundament.

Wherefore the muſcles of the arm, beginning with theſe of the ſhoulder-blade, at the leaſt, are forty two, for there are four of the ſhoulder-blade: Of the arm properly or particularly ſo called, ſeven or eight; and there are three, four or five proper muſcles of the cubit; that is, appointed for the performance of the motions thereof; in the inner part of the cubit are ſeven, and as many in the outer; but thoſe of the hand are reckoned thirteen at leaſt. The muſcles of the arm in general forty two.

The four of the ſhoulder-blade are the *Trapezius*, reſembling a Monks Cowl, which moves it upwards and downwards, and draws it backwards; the ſecond is the *Levator*, or lifter up; the third the great *Rhomboides* lying under the *Trapezius*; the fourth, the leſſer ſaw-muſcle, which is inſerted into the *Caracoides*. The arm is moved forwards, backwards, upwards, downwards and circularly.

The pectoral muſcle ariſing from the clavicle, breaſt-bone, and neighbouring ribs, draw it forwards; the *Humilis*, or low-muſcle, coming from the lower-rib of the ſhoulder-blade draws it backwards; the *Deltoides* upwards, and the *Latiſſimus* downwards, and ſomewhat backwards. But the three ſeated about the ſhoulder-blade move it about, or circularly.

The *Epomis* or *Scapularis* upwards; the *Superſcapularis*, which may ſeem two, backwards and downwards; the *Subſcapularis* which is in the cavity of the ſhoulder-blade, forwards, ſo that by a certain viciſſitude and ſucceſſion of action, they move it circularly. Two muſcles bend the cubit, the one named *Biceps*, or two-headed, and the other *Brachiæus* or the arm-muſcle; but one, two or three muſcles extend it; for, if you have reſpect to the original, this muſcle hath two or three heads, but one only inſertion.

In the inſide of the cubit are ſeven muſcles, one *Palmaris*, two wriſt-benders, two *Pronatores*, one ſquare, another in ſome ſort round; two finger-benders, and one *Abductor*, or drawer aſide. Theſe fourteen internal and external muſcles of the cubit, do not indeed move the cubit, but only ſeated there move the wand, and with it the hand. Theſe are the thirteen muſcles of the hand; the *Thenar* which may not only be divided into two, but into ſix, not only by the divers actions it performs, but alſo by the branches divided by a manifeſt ſpace between them; the ſecond is called the *Hypothenar*, which lies under the little finger, as the *Thenar* doth under the thumb; the third is the *Abductor* of the thumb; then follow the four *Lumbrici* and ſix *Interoſſes*, although eight may be obſerved.

The whole leg hath at the leaſt fifty muſcles, for we reckon there are fourteen muſcles in the thigh, there are eleven made for the uſe of the leg; there are nine ſeated in the leg, three before, and ſix behind, which ſerve for the uſe of the foot and toes; in the foot are ſeated ſixteen. Therefore of the fourteen muſcles ſerving the thigh to bend it, one called the *Lumbaris*, the other ariſing from the cavity of the hanch-bone; but the three which make the buttocks and the *Triceps* or three-headed The muſcles of the leg in general fifty.

headed muſcle, (which if you pleaſe, you may divide into three) extend it. Beſides theſe, the four twin-muſcles, and two *Obturatores*, of which the one is internal, and the other external, turn the thigh about. The leg hath eleven; that is, the long, the membranous, the four *Poſtici*, or hind-muſcles (three of which come from the huckle-bone, but the other from the commiſſure of the ſhare-bone) the right, the two vaſt, the *Cruræus* or leg-muſcle, and the *Popliteus*, or ham-muſcle. Theſe ſeated in the leg for the uſe of the foot and toes, are three fore, and ſix hind-muſcles: Two of the fore bend the foot, one of which is called the *Tibiæus anticus*, the other *Peronæus*, which you may divide into two. The third the bender of the toes, although it alſo partly bend the foot, to which alſo the bender of the thumb may be revoked. One of the hind is the toe-bender, others extend the foot; and are in this order: Two twins, one *Plantaris*, one *Soleus*, one *Tibiæus poſticus*, and the great bender of the toes, to which may be revoked the bender of the thumb. Of the ſixteen ſeated in the foot, one is above, ſeated on the back of the foot, which we call the *Abductor* of the toes; another, in the ſole of the foot; to wit, the little bender of the toes, which goes to the ſecond joynt of the toes alongſt the inſide of the foot; the other lends his help to the great toe, which you call the *Abductor* of the thumb, another is ſeated on the outſide for the uſe of the little toe. To theſe are added the four *Lumbrici*, beſides the eight *Interoſſes*, or if you had rather ten. And thus much may ſuffice for the enumeration of the muſcles.

The Figure of the muſcles, when the Skin with its Veins, the Fat, and all the fleſhy membranes are taken away; that part of the fleſhy Membrane excepted, which takes upon it the nature of a muſcle, as being conjoyned with the muſcles.

a *The muſcle of the fore-head.*
b *the temporal muſcle.*
c *the muſcle ſhutting the eye-lid.*
d *the muſcle opening the wings of the noſe.*
e *the fore-part of the yoke-bone.*
f *the muſcle of the upper lip, tending to the noſe.*
g *the beginning of the maſſeter or grinding muſcle.*
h *the broad muſcle conſiſting of a fleſhy membrane.*
i k *the beginning thereof which riſes immediately from the collar-bone, and the top of the ſhoulder.*
l *that part thereof which bends forwards to* l.
m *the muſcle which lifts up the arm.*
n *the pectoral muſcle.*
o *the membranous part of this muſcle which is joyned to the nervous part of the firſt muſcle of the* Abdomen, *or belly.*
q q *the fleſhy portion thereof, from the ſixth and ſeventh ribs, and the inſertion thereof.*
r *the muſcle drawing down the arm.*
ſ *the oblique deſcending muſcle of the lower belly.*
t t t *the inſertion of the great ſaw-muſcle.*
u u *the* Linea alba, *or white-line, at which the two oblique deſcendent muſcles meet, covering the whole belly.* x *the yard, the ſkin being taken away.* y *the veſſels of ſeed.*

α *the teſticles wrapped in the fleſhy membrane.* β *the fore-muſcle bending the cubit.* γ γ *the hind muſcle bending the cubit.* δ *the muſcle extending the cubit.* ε *the two-headed muſcle extending the wriſt.* ζ *the muſcle producing the broad tendon on the back of the hand.* ζ *his tendon.* η *the muſcle turning up the wand.* θ *the upper muſcle flatting the wand.* ι *the ſecond of the arm-benders, whoſe beginning is* κ *and tendon* λ. ο *a portion of the muſcle, whereof one part yields tendons to the wriſt, the other to the thumb.* ϖ *the fleſhleſs articulation of the thumb.* ρ *a muſcle inſerted into the wriſt, lying near to the following muſcle.* σ *a muſcle divided into two tendons, the one whereof is inſerted into the firſt joynt of the thumb, the other into the following.* τ *the firſt muſcle of the thigh, whoſe head is at* υ, *and tendon at* Φ, *and inſertion at* χ. ψ *the end of the ſecond muſcle of the thigh.* ω *the end of the third muſcle of the thigh.* 1 *the ſixth muſcle of the leg; his beginning at* 2, *almoſt wholly membranous at* 3 .4 *the ninth muſcle of the leg.* 5 *the eighth of the leg.* 6 *a portion of the ſixth and ſeventh of the thigh.* 7 *the glandules of the groins.* 8 *the eighth of the thigh.* 9 *the ſecond of the leg.* 11 *the innermoſt of the ankle.* 12 *the ſixth muſcle of the foot, his original* 13. 14 *and* 15 *the ſeventh of the foot.* 16 *the tendon of the muſcle lifting up the great toe.* 17 *the muſcles extending the four other toes.* 18 *the abductor of the great toe,* 19 *a tranſverſe ligament.* 20 *a tendon of the ninth muſcle of the foot.* 21 *the firſt muſcle.* 22 *the fourth muſcle of the foot.* 23 *the tendon of the third muſcle.* 24 *a muſcle bending the third bone of the four leſſer toes.*

The end of the ſixth Book.

BOOK VII.

Of TUMORS *against* NATURE *in General.*

CHAP. I.

What a Tumour against Nature, vulgarly called an Impoſtume, is; and what be the differences thereof.

IN Impoſthume, commonly ſo called, is an affect againſt Nature, compoſed and made of three kind of Diſeaſes; diſtemperature, ill Conformation, and Solution of Continuity, concurring to the hindering or hurting of the Action. An humour, or any other matter, anſwering in proportion to a humour, aboliſhing, weakning, or depraving of the office, or function of that part or body in which it reſides, cauſeth it. What an Impoſtume vulgarly ſo called is. The material cauſes of Impoſtumes, or unnatural tumours.

The differences of Impoſtumes are commonly drawn from five things, Quantity, Matter, Accidents, the Nature of the part, which they affect or poſſeſs; and laſtly, their efficient cauſes. I have thought good for the better underſtanding of them, to deſcribe them in this following Scheme.

A Table of the differences of Tumors.

The differences of Impoſtumes are drawn principally from five things; that is,

- *From their Quantity, by reaſon whereof* Impoſtumes *are called*
  - *Great, which are comprehended under the General name of Phlegmons, which happen in the fleſhy parts, by* Galen, lib. de Tumor. contra Naturam, & lib. 2. ad Glauconem.
  - *Indifferent, or of the middle ſort, as* Fellons.
  - *Small, as thoſe which* Avicen *calls* Bothores, i.e. *Puſhes and Puſtules, all kind of Scabs and Leproſies; and laſtly, all ſmall breakings out.*
- *From their Accidents, as*
  - *Colour, from whence Impoſtumes are named, white, red, pale, yellow, blue or black, and ſo of any other colour.*
  - *Pain, hardneſs, ſoftneſs, and ſuch like; from whence they are ſaid to be painful, not painful hard, ſoft, and ſo of the reſt.*
- *From the matter, of which they are cauſed and made, which is either*
  - *Natural,*
    - *Hot, and that either*
      - *Sanguin, from whence a true* Phlegmon.
      - *Cholerick, from whence a true* Eryſipelas.
    - *Cold, and that either*
      - *Phlegmatick, from whence a true* Oedema.
      - *Melancholick, from whence a perfect* Scirrhus.
  - *Or,*
  - *Not Natural, which hath exceeded the limits of its natural goodneſs, from whence illegitimate Tumours, therefore*
    - *of a ſanguine humour,*
      - *Carbuncles, Gangrenes, eating-Ulcers, Sphacels are cauſed.*
    - *of a cholerick humour,*
      - *Of the groſſer, the eating* Herpes; *of the ſubtiler, the* Herpes miliaris *is made.*
    - *of a phlegmatick humour.*
      - *Watery and flatulent Impoſtumes, the Kings-evil, knots and all phlegmatick ſwellings and excreſcences.*
    - *of a melancholick humour.*
      - *The exquiſite or perfect* Scirrhus, *hardneſſes, and all ſort of cancerous Tumors.*
- *From the condition and nature of the parts which they poſſeſs, from whence the* Ophthalmia, *that is, a Phlegmon of the eyes.* Parotis, *a tumour near the ears.* Paronychia, *or a Whitlow, at the roots of the nails; and ſo of the reſt.*
- *From the efficient cauſes, or rather the manner of doing. For ſome Impoſtumes are ſaid to be made by defluxions, others by congeſtion; thoſe are commonly hot, and the other commonly cold, as it ſhall more manifeſtly appear by the following chapter.*

CHAP. II.

Of the general cauſes of Tumours.

THere are two general Cauſes of Impoſtumes, Fluxion, and Congeſtion: Defluxions are occaſioned, either by the part ſending, or receiving; the part ſending diſcharges it ſelf of the humours, becauſe the expulſive faculty reſident in that part is provoked to expel them; moved thereto, either by the troubleſomneſs of their Quantity or Quality. The part receiving, draws and receives occaſion of heat, pain, weakneſs, (whether natural or accidental) openneſs of the paſſages, and lower ſituation. After what manner tumours againſt Nature are chiefly made.

The cauſes of heat, in what part ſoever it be, are commonly three, as, all immoderate motion (under which frictions are alſo contained;) external heat, either, from Fire, or Sun; and the uſe of acrid Meats and Medicins. The cauſes of Heat.

The cauſes of Pain are four, the firſt is a ſudden and violent invaſion of ſome intemperate thing, by means of the four firſt qualities; the ſecond is, ſolution of continuity, by a Wound, Luxation, Fracture, Contuſion, or Diſtenſion; the third, is the exquiſit ſenſe of the part, for you feel no pain in cutting a bone, or expoſing it to cold or heat; the fourth is, the attention, as it were, of the Animal Faculty; for the mind, diverted from the actual cauſe of pain, is leſs troubled, or ſenſible of it. Four cauſes of Pain.

Two cauſes of weakneſs.

A part is weak, either by its Nature, or by ſome Accident: by its Nature, as the Glandules and the Emunctories of the principal parts; by Accident, as if ſome diſtemper, bitter pain, or great defluxion have ſeized upon it, and wearied it, for ſo the ſtrength is weakned, and the paſſages dilated. And the lowneſs of ſite yields opportunity for the falling down of humours.

Two cauſes of congeſtion.

The cauſes of congeſtion are two principally, as the weakneſs of the concoctive faculty, which reſides in the part, (by which the aſſimilation into the ſubſtance of the part of the nouriſhment flowing to it, is fruſtrated) and the weakneſs of the expulſive faculty; for, whileſt the part cannot expel ſuperfluities, their quantity continually increaſes.

And thus often times cold Impoſtumes, have their original from a groſs and tough humour, and ſo are more difficult to cure.

Laſtly, All the cauſes of Impoſtumes may be reduced to three; that is, the primitive or external; the antecedent or internal; and the conjunct or containing: as we will hereafter treat more at large.

CHAP. III.

The ſigns of Impoſthumes or Tumours in general.

The principal ſigns of tumours are drawn from the eſſence of the part.

BEfore we undertake the cure of Tumors, it is expedient to know their kinds and differences, which knowledge muſt be drawn from their proper ſigns, the ſame way, as in other Diſeaſes. But becauſe the proper and principal ſigns of tumours are drawn from the eſſence of the part they poſſeſs, we muſt firſt know the parts, and then conſider what their eſſence and compoſition are.

We are taught both by Skill in Anatomy, and the obſervation of the depraved Function, eſpecially when the affected part is one of thoſe which lie hid in the Body; for we know whether or no the external parts are affected with a Tumour againſt Nature, by comparing that with his Natural, which is contrary. For comparing the ſound part with the diſeaſed, we ſhall eaſily judge whether it be ſwollen or no.

But becauſe it is not ſufficient for a Chirurgeon only to know theſe general ſigns (which are known even to the vulgar) he muſt attentively obſerve ſuch as are more proper and near. And theſe are drawn from the difference of the matter and humours, of which the tumours conſiſt.

Lib. 2. ad Glauc. & 13. Method.

For this, *Galen* teaches, That all differences of Tumours ariſe from the nature and condition of the matter which flows down and generates the Tumour; alſo they are known by ſuch accidents as happen to them, as colour, heat, hardneſs, ſoftneſs, pain, tenſion, reſiſtance.

The proper ſigns of a ſanguin tumour, of a phlegmatick, of a melancholick, of a cholerick.

Wherefore pain, heat, redneſs, and tenſion, indicate a ſanguine humour; coldneſs, ſoftneſs, and no great pain, Phlegm; tenſion, hardneſs, the livid colour of the part, and a pricking pain by fits, Melancholy; and yelloviſh and pale colour, biting pain without hardneſs of the part, Choler.

The knowledge of tumors by their motion and exacerbation. *Lib. 2. Epidem.*

And beſides, Impoſtumes have their periods and exacerbations following the nature and motion of the humours of which they are generated. Wherefore by the motion and fits it will be no difficult matter to know the kind of the humor; for as in the Spring, ſo in the Morning the bloud is in motion; as in the Summer, ſo in the midſt of the Day, Choler; as in Autumn, ſo in the Evening, Melancholy; as in Winter, ſo in the Night the exacerbation of Phlegm are moſt predominant. For *Hippocrates* and *Galen* teach, that the Year hath Circuits of Diſeaſes, ſo that the ſame proportion of the exceſs and motion of humours, which is in the Four Seaſons of the Year, is alſo in the Four Quarters of each Day.

The begining of an Impoſtume. The increaſe. The ſtate.

Impoſtumes which are curable have Four Times; their beginning, increaſe, ſtate, and declination; and we muſt alter our Medicins according to the variety of theſe Times. We know the beginning by the firſt ſwelling of the part; The increaſe, when the ſwelling, pain and other accidents do manifeſtly increaſe and enlarge themſelves; The ſtate when the foreſaid ſymptoms increaſe no more, but each of them, becauſe at their height, remain in their ſtate immoveable, unleſs the very matter of the tumour degenerate, and change it ſelf into another kind of humour; The Declination, when the ſwelling, pain, fever, reſtleſsneſs, are leſſened. And from hence the Chirurgeon may preſage what the end of the tumour may be; for tumours are commonly terminated four manner of ways, if ſo be that the motion of the humours cauſing them be not intercepted, or they without ſome manifeſt cauſe do flow back into the body.

Therefore firſt they are terminated by inſenſible tranſpiration or reſolution; ſecondly, by ſuppuration when the matter is digeſted and ripened; thirdly, by induration, when it degenerates into a Scirrhus, the thinner part of the humour being diſſolved; the fourth, which is the worſt of all, by a Corruption and Gangrene of the part, which is, when overcome with violence, or the abundance or quality of the humour, or both, it comes to that diſtemper, that it loſes its proper action.

The ſigns of a tumor to be terminated by reſolution.

It is beſt to terminate a tumour by reſolution, and the worſt by corruption; ſuppuration and induration are between both, although that is far better than this. The ſigns by which the Chirurgeons may preſage that an Impoſtume may be terminated by reſolving, are the remiſſion or ſlacking of the ſwelling, pain, pulſation, tenſion, heat, and all other accidents, and the unaccuſtomed livelineſs and itching of the part; and hot Impoſtumes are commonly thus terminated, becauſe the hot humour is eaſily reſolved, by reaſon of its ſubtilty.

The ſigns of ſuppuration.

Signs of ſuppuration are the intenſion or increaſe of pain, heat, ſwelling, pulſation, and the fever; for according to *Hippocrates*, Pain and the Fever are greater when the matter is ſuppurating, than when it is ſuppurated.

The Chirurgeon muſt be very attentive to know and obſerve when ſuppuration is made, for the purulent matter oft-times lies hid (as *Hippocrates* ſaith) by reaſon of the thickneſs of the part lying above or over it.

The ſigns of an Impoſtume degenerating into a Scirrhous hardneſs, are the diminution of the

tumour

tumour and hardneſs remaining in the part. The cauſes of the hardneſs not going away with the ſwelling, are the weakneſs of Nature, the groſsneſs and toughneſs of the humour, and unskilfulneſs of the Chirurgeon, who by too long uſing reſolving things hath occaſioned, that the more ſubtil part of the humour being diſſolved, the reſt of the groſſer nature like earthy dregs remains concrete in the part. For ſo Potters Veſſels dried in the Sun, grow hard. But the unskilful Chirurgeon may occaſion a Scirrhous hardneſs by another means, as by condenſating the skin, and incraſſating the humours by too much uſe of repercuſſives. But you may perceive an Impoſtume to degenerate into a Gangrene thus, if the accidents of heat, redneſs, pulſation and tenſion ſhall be more intenſe than they are wont to be in ſuppuration, if the pain preſently ceaſe without any manifeſt cauſe; if the part wax livid or black; and laſtly, if it ſtink.

The ſigns and cauſes of a tumor terminated in a Scirrhus.

The ſigns of a Gangrene at hand.

But we ſhall treat of this more at large when we come to treat of the Gangrene and *Sphacelus*. A ſudden diminution of the tumour, and that without manifeſt cauſe, is a ſign of the matter fallen back, and turned into the body again, which may be occaſioned by the immoderate uſe of refrigerating things. And ſometimes much flatulency mixed with the matter, although there be no fault in thoſe things which were applied.

Of diſappearance of a tumor, and the ſigns thereof.

Fevers and many other malign Symptoms; as Swoundings and Convulſion, by tranſlation of the matter to the noble parts, follow this flowing back of the humour into the body.

CHAP. IV.

Of the Prognoſtick in Impoſtumes.

TUmors ariſing from a melancholy, phlegmatick, groſs, tough, or viſcous humour, ask a longer time for their cure, than thoſe which are of bloud or choler. And they are more difficultly cured which are of humours not natural, than thoſe which are of humours yet contained in the bounds of Nature.

Cold tumors require a longer cure.

For thoſe humours which are rebellious, offend rather in quality than in quantity, and undergo the divers forms of things diſſenting from Nature, which are joined by no ſimilitude or affinity with things Natural, as Suet, Poultis, Honey, the dregs of Oil and Wine; yea and of ſolid bodies, as Stone, Sand, Coal, Straws; and ſometimes of living things, as Worms, Serpents, and the like Monſters.

Tumors made of matter nor natural, are more difficultly cured.

The tumours which poſſeſs the inner parts and noble entrails, are more dangerous and deadly, as alſo thoſe which are in the joints, or near to them. And theſe tumors which ſeize upon great Veſſels, as Veins, Arteries, and Nerves, for fear of great effuſion of bloud, waſting of the ſpirits and convulſion. So Impoſtumes of a monſtrous bigneſs are often deadly by reaſon of the great reſolution of the ſpirits cauſed by their opening. Thoſe which degenerate into a *Scirrhus*, are of long continuance and hard to cure, as alſo thoſe which are in hydropick, leprous, ſcabby and corrupt bodies, for they often turn into malign and ill-conditioned Ulcers.

Hippo. Aph. 8. ſect. 6.

CHAP. V.

Of the general Cure of Tumors againſt Nature.

THere be three things to be obſerved in the cure of Impoſtumes. The firſt is the eſſence thereof; the ſecond, the quality of the humour cauſing the Impoſtume; the third, the temper of the part affected. The firſt Indication drawn from the Eſſence, that is, from the greatneſs or ſmalneſs of the Tumor, varies the manner of curing, for the Medicins muſt be increaſed or diminiſhed according to the greatneſs of the Tumor. The ſecond, taken from the nature of the humour alſo changes our counſel, for a *Phlegmon* muſt be otherwiſe cured than an *Eryſipelas* and an *Oedema*, than a *Scirrhus*; and a ſimple Tumor, otherwiſe than a compound. And alſo you muſt cure after another manner a Tumor coming of an humour not natural, than that which is of a natural humour; and otherwiſe that which is made by congeſtion, than that which is made by defluxion. The third Indication is taken from the part in which the Tumor reſides; by the nature of the part we underſtand its temperature, conformation, ſite, faculty, and function.

What muſt be conſidered in undertaking the cure of tumors.

What we muſt underſtand by the nature of the part.

The temperature indicates that ſome Medicins are convenient for the fleſhy parts, as thoſe which are more moiſt; others for the nervous, as more dry; for you muſt apply ſome things to the Eye, and others to the Throat; one ſort of things to theſe parts which by reaſon of their rarity are eaſily ſubject to defluxion, another to thoſe parts which by their denſity are not obnoxious to it.

But we muſt have good regard to the ſite of the part, as if it have any connexion with the great Veſſels, and if it be fit to pour forth the matter and humour when it is ſuppurated.

Galen by the name of Faculty underſtands the uſe and ſenſe of the part. This hath a manifold indication in curing, for ſome parts are principal, as the Brain, Heart, and Liver; for their vertue is communicated to the whole body by the Nerves, Arteries, and Veins.

What we muſt underſtand by the faculty of the part.

Others truly are not principal, but yet ſo neceſſary that none can live without them, as the Stomach. Some are endued with a moſt quick ſenſe, as the Eye, the Membranes, Nerves, and Tendons; wherefore they cannot endure acrid and biting Medicins. Having called to mind theſe indications, the indication will be perfected by theſe three following intentions, as if we conſider the humour flowing down, or which is ready to flow; the conjunct matter, that is, the humour impact in the part; the correction of accidents; yet ſo that we always have care of that which is moſt urgent and of the cauſe. Therefore firſt repercuſſives muſt be applied for the antecedent matter, ſtrong or weak, having regard to the Tumour as it is then, onely excepting ſix conditions of Tumors; the

What we muſt conſider in performing the Cure.

What things diſſwade us from uſing repercuſſives.

firſt is, if the matter of the tumour be venenate: the ſecond, if it be a critical abſceſs: the third, if the defluxion be near the noble parts: the fourth, if the matter be groſs, tough, and viſcid: the fifth, when the matter lies far in, that is, flows by the Veins which lies more deep: the ſixth, when it lies in the Glandules. But if the whole body be plethorick, a convenient diet, Purging, and Phlebotomy, muſt be appointed, frictions and bathes muſt be uſed. Ill humours are amended by diet and purging. If the weakneſs of the part receiving draw on a defluxion, it muſt be ſtrengthened.

If the part be inferiour in its ſite, let the Patient be ſo ſeated, or laid, that the part receiving, as much as may be, may be the higher. If pain be the cauſe of defluxion, we muſt aſſwage it by things mitigating it. If the thinneſs, or lightneſs of the humour cauſe a defluxion, it muſt be inſpiſſate by Meats and Medicins. But for the matter contained in the part, becauſe it is againſt Nature, it requires to be evacuate by reſolving things, as Cataplaſms, Ointments, Fomentations, Cupping-glaſſes; or by evacuation, as by ſcarifying, or ſuppurating things, as by ripening and opening the Impoſtume. Laſtly, For the conjunct accidents, as the Fever, Pain, and ſuch like, they muſt be mitigated by aſſwaging, mollifying and relaxing Medicins, as I ſhall ſhew more at large hereafter.

CHAP. VI.

Of the four principal and general Tumours, and of other Impoſtumes which may be reduced to them.

What tumors may be reduced to a Phlegmon. Which to an *Eryſipelas*. Which to an *Oedema*.

THE principal and chief Tumours which the abundance of humours generate, are four; a *Phlegmon*, *Eryſipelas*, *Oedema*, and *Scirrhus*: innumerable others may be reduced to theſe, diſtinguiſhed by divers names according to the various condition of the efficient cauſe and parts receiving. Wherefore a *Phygethlum*, *Phyma*, Fellon, Carbuncle, Inflammation of the Eyes, Squincy, *Bubo*, and laſtly, all ſorts of hot and moiſt tumours may be reduced to a Phlegmon. The *Herpes miliaris*, the eating *Herpes*, Ring-worms, and Tetters, and all Impoſtumes brought forth by choler, are contained under an *Eryſipelas*. *Atheromata*, *Steatomata*, *Melicerides*, the *Teſtudo* or *Talpa*, *Ganglion*, Knots, Kings-Evils, Wens, Watery Ruptures, the *Aſcites* and *Leucophlegmatia* may be reduced to an *Oedema*, as alſo all flatulent tumours, which the abundance of corrupt Phlegm produces.

Which to a *Scirrhus*.

In the kindred of the *Scirrhus* are reckoned a Cancer, Leproſie, Warts, Corns, a *Thymus*, a *Varix*, *Morphew* black and white, and other Impoſtumes ariſing from a Melancholy humour.

Now we will treat of theſe Tumors in particular, beginning with a Phlegmon.

CHAP. VII.

Of a Phlegmon.

What a true Phlegmon is. A Phlegmon one thing, and a phlegmonous Tumour another.

A Phlegmon is a general name for all Impoſtumes, which the abundance of inflamed bloud produces. That is called a true Phlegmon, which is made of laudable bloud, offending onely in quantity. But a Baſtard Phlegmon, or a phlegmonous Impoſtume hath ſome other, and proper name; as a Carbuncle, Fellon, Gangrene, Sphacel, and the like malign Puſtules. So when there is a conflux of divers humors into one tumor, divers kinds of phlegmonous Impoſtumes called by divers names, according to the more abundant humour, ariſe; as if a ſmall portion of Phlegm ſhall be mixed with a greater quantity of bloud, it ſhall be called an *Oedematous Phlegmon*; but if, on the contrary, the quantity of phlegm be the greater, it ſhall be named a phlegmonous *Oedema*, and ſo of the reſt; always naming the tumour, from that which is predominant in it.

Therefore we muſt obſerve that all differences of ſuch tumours ariſe from that, either becauſe the bloud cauſing it offends only in quantity; which if it do, it cauſes that tumor which is properly called a Phlegmon; if in quality, it makes a phlegmonous tumour, becauſe the matter thereof is much departed from the goodneſs of bloud.

But bloud is ſaid to offend in quantity, either by admixture of ſome other matter, as Phlegm, Choler, or Melancholy, from whence proceed *Oedematous*, *Eryſipelous*, and *Scirrhous* Phlegmons; or by corruption of its proper ſubſtance, from whence Carbuncles and all kinds of Gangrenes; or by concretion, and when Nature is diſappointed of its attempted and hoped for ſuppuration, either by default of the Air, or Patient, or by the errour of the Phyſician; and hence oft-times happen *Atheromaes*, *Steatomaes*, and *Melicerides*. Although theſe things be ſet down by the Ancients, of the ſimple and ſimilar matter of the true Phlegmon; yet you muſt know, that in truth there is no Impoſtume, whoſe matter exquiſitely ſhews the Nature of one, and that ſimple humour, without all admixture of any other matter; for all humours are mixed together with the bloud yet from the plenty of bloud predominating, they are called Sanguine, as if they were of bloud alone.

Wherefore if any tumours reſemble the nature of one ſimple humour, truly they are not of any natural humour, but from ſome humour which is corrupt, vitiated and offending in quality; for ſo bloud by aduſtion degenerates into Choler and Melancholy.

Gal. lib. de Tumoribus, &c. ad Glauc. Hippoc. lib. de Vuln. cap. Gal. lib. de Tumor. præter naturam.

Therefore a true Phlegmon is defined by *Galen*; A tumor againſt Nature, of laudable bloud, flowing into any part in too great a quantity.

This tumour, though moſt commonly it be in the fleſh, yet ſometimes it happens in the Bones, as *Hippocrates* and *Galen* witneſs.

A Phlegmon is made and generated thus: when bloud flows into any part, in too great a quantity; firſt the greater Veins and Arteries of the part affected are filled, then the middle, and laſtly, the ſmalleſt and capillary; ſo from thoſe thus diſtended, the bloud ſweats out of the pores and ſmall paſſages like dew, and with this the void ſpaces which are between the ſimilar parts are

firſt

firſt filled, and then with the ſame bloud all the adjacent parts are filled, but eſpecially the fleſh, as that which is moſt fit to receive defluxions, by reaſon of the ſpongious rarity of its ſubſtance; but then the nerves, tendons, membranes, and ligaments, are likewiſe ſtuffed full; whereupon a Tumour muſt neceſſarily follow, by reaſon of the repletion which exceeds the bounds of Nature; and from hence alſo are Tenſion and Reſiſtance; and pain alſo happens at the ſame time, both by reaſon of the tenſion and preternatural heat.

The cauſe of a beating pain in a Phlegmon

And there is a manifeſt pulſation in the part, ſpecially whileſt it ſuppurates, becauſe the Veins, Arteries, and Nerves, are much, being they are not onely heated within by the influx of the fervid humour, but preſſed without by the adjacent parts. Therefore ſeeing the pain comes to all the foreſaid parts becauſe they are too immoderately heated and preſſed, the Arteries, which are in the perpetual motion of their *ſyſtole & diaſtole*, whileſt they are dilated, ſtrike upon the other inflamed parts, whereupon proceeds that beating pain.

Hereunto add; The Arteries, then filled with more copious and hot bloud, have greater need to ſeek refrigeration by drawing in the encompaſſing air; wherefore they muſt as of neceſſity, have a conflict with the neighbouring parts which are ſwollen and pained. Therefore from hence is that pulſation in a Phlegmon which is defined by *Galen*, An agitation of the Arteries, painful and ſenſible to the Patient himſelf; for otherwiſe as long as we are in health, we do not perceive the pulſation of the Arteries. *Com. ad Aph. 21. Sect. 7.*

Wherefore theſe two cauſes of pulſation, or a pulſifick pain in a Phlegmon, are worthy to be obſerved, that is, the heat and abundance of bloud contained in the Veſſels and Arteries (which more frequently than their wont incite the Arteries to motion, that is, to their *ſyſtole* and *diaſtole*) and the compreſſion and ſtraitning of the ſaid Arteries, by reaſon of the repletion and diſtention of the adjacent parts, by whoſe occaſion the parts afflicted and beaten by the trembling and frequent pulſation of Arteries are in pain.

Another kind of Pulſation in a Phlegmon.

Hence they commonly ſay, that in the part affected with a Phlegmon, they feel, as it were, the ſenſe or ſtroke of a Mallet or Hammer ſmiting upon it. But alſo, beſides this pulſation of the Arteries, there is, as it were, another pulſation with itching from the humours whileſt they putrefie, and ſuppurate, by the permixtion, motion, and agitation of vapours thereupon ariſing.

The cauſe of heat in a Phlegmon is bloud, which whileſt it flows more plentifully into the part, is as it were, trodden or thruſt down, and cauſes obſtruction, from whence neceſſarily follows a prohibition of tranſpiration and putrefaction of the bloud, by reaſon of the preternatural heat. But the Phlegmon looks red by reaſon of the bloud contained in it, becauſe the humour predominant in the part ſhines through the skin.

CHAP. VIII.

Of the Cauſes and Signs of a Phlegmon.

The Primitive cauſes of a Phlegmon. The Antecedent and Conjunct.

THE Cauſes of a Phlegmon are of three kinds; for ſome are primitive, ſome antecedent, and ſome conjunct. Primitive are falls, contuſions, immoderate labour, frictions, application of acrid ointments, burnings, long ſtaying, or labouring in the hot Sun, a diet inconſiderate, and which breeds much bloud. The antecedent Cauſes are, the great abundance of bloud, too plentifully flowing in the Veins. The conjunct, the collection or gathering together of bloud impact in any part.

The ſigns of a Phlegmon.

The ſigns of a Phlegmon are, ſwelling, tenſion, reſiſtance, feveriſh heat, pain, pulſation, (eſpecially while it ſuppurates) redneſs, and others, by which the abundance of bloud is ſignified.

And a little Phlegmon is often terminated by reſolution, but a great one by ſuppuration; and ſometimes it ends in a Scirrhus, or a tumour like a Scirrhus; but otherwhiles in a Gangrene, that is, when the faculty and native ſtrength of the part affected, is over-whelmed by the greatneſs of the defluxion, as it is reported by *Galen*. The Chirurgeon ought to conſider all theſe things, that he may apply and vary ſuch Medicins as are convenient for the nature of the Patient, and for the time and condition of the part affected. *Gal. de Tum.*

CHAP. IX.

Of the Cure of a true Phlegmon.

What kind of Diet muſt be preſcribed in a Phlegmon.

THE Chirurgeon in the cure of a true Phlegmon muſt propoſe to himſelf four intentions. The firſt of Diet; This, becauſe a Phlegmon is a hot affect and cauſes a Fever, muſt be ordained of refrigerative and humecting things, with the convenient uſe of the ſix things Not-natural, that is, Air, Meat and Drink, Motion and Reſt, Sleep and Waking, Repletion and inanition, and laſtly, the paſſions of the mind. Therefore let him make choice of that air which is pure and clear, not too moiſt, for fear of defluxion, but ſomewhat cool; let him command Meats which are moderately cool and moiſt, ſhunning ſuch as generate bloud too plentifully, ſuch will be Broths not too fat, ſeaſoned with a little Borage, Lettuce, Sorrel, and Succory: let him be forbidden the uſe of all Spices, and alſo of Garlick and Onions, and all things which heat the bloud, as are all fatty and ſweet things, as thoſe which eaſily take fire. Let the Patient drink ſmall Wine, and much allayed with Water: or, if the Fever be vehement, the Water of the Decoction of Licoris, Barly, ſweet Almonds, or Water and Sugar; always having regard to the ſtrength, age, and cuſtom of the Patient.

For if he be of that age, or have ſo led his life that he cannot want the uſe of Wine, let him uſe it, but altogether moderately. Reſt muſt be commanded; for all bodies wax hot by motion, but let him chiefly have a care that he do not exerciſe the part poſſeſſed by the Phlegmon for fear of a new defluxion. Let his ſleep be moderate; neither, if he have a full body, let him ſleep by day, eſpecially preſently after meat. Let him have his belly ſoluble, if not by Nature, then by Art, as by the frequent uſe of Clyſters and Suppoſitories. Let him avoid all vehement perturbations of mind; as hate, anger, brawling; let him wholly abſtain from Venery.

How to divert the defluxion of humours.

This manner of diet thus preſcribed, we muſt come to the ſecond ſcope, that is, the diverſion of the defluxion, which is performed by taking away its cauſe, that is, the fulneſs and illneſs of the humours. Both which we may amend by purging and bloud-letting, if the ſtrength and age of the Patient permit.

The pain muſt be aſſwaged.

But if the part receiving be weak, it muſt be ſtrengthened with thoſe things which by their aſtriction amend the openneſs of the paſſages, the violence of the humour being drawn away by Cupping-glaſſes, Frictions, Ligatures. But if pain trouble the part, which is often the occaſion of defluxion, it muſt be mitigated by Medicins aſſwaging pain.

The third ſcope is, to overcome the Conjunct Cauſe. That we may attain to this, we muſt enter into the conſideration of the tumour, according to its times, that is, the beginning, increaſe, ſtate, and declination. For from hence the indications of variety of Medicins muſt be drawn. For in the beginning we uſe repercuſſives to drive away the matter of the Phlegmon flowing down, as the White of an Egg, Oxycrate, the Juices or Waters of Houſleek, Plantain, Roſes, Cataplaſms of Henbane, Pomgranate, Pills, Balauſties, Bole Armenick, *Terra ſigillata*, Oyl of Roſes, Quinces, Myrtils, Poppies.

When we muſt uſe repercuſſives.

Of theſe ſimples variety of compound Medicins ariſes. This may be the form of a Cataplaſm. ℞ *far. hordei* ʒ ij. *ſucci ſemper-vivi plantag. an.* ʒ iij. *pul. malicorii, balauſtiorum & roſar. an.* ʒ ij. *ol. myrtill. & roſar. an.* ʒ i. *fiat Cataplaſma.* Another, ℞ *Plantag. ſolani, hyoſcyam. an. m.* ij. *caudæ equin. tapſi barb. centinodiæ, an. m.* i. *coquantur perfectè in oxycrato, piſſentur, trajiciantur, addendo pulveris myrtil. nuc. cupreſſi. & roſ. rub. an.* ʒ iij. *farin. fab.* ʒ ij. *olei roſar. & cydon. an.* ʒ i ſs. mix them and make a Cataplaſm to the form of a liquid Pultis. And you may uſe this liniment, by dipping linen clothes in it, and applying to the part; ℞ *ol. nymph. & roſar. an.* ʒ iij. *aq. roſ. ſolani & plantag. an.* ʒ ij. *aceti* ʒ iij. *albumin. ovorum n.* iij. *fiat linimentum.* Alſo *ung. roſatum & ung. album, camphor. Raſis* are good to apply to it, as in like manner, *Emp. Diacalcitheos* diſſolved in Vinegar, and Oyl of Roſes and alſo *Populeon* may be uſed. In the increaſe, you muſt have care of the humour flowing down, and of that which already impacted in the part, did formerly fall down. Therefore repercuſſives muſt be tempered and mixed with diſcuſſing Medicins, but ſo, that they may carry the chief ſway, as, ℞ *Fol. malvæ, abſinth. plantag. an. m.* iij. *coquantur in oxycrato, contundantur, trajectis add. farinæ fabarum & hordei an.* ʒ i. *pul. roſar. rub. & Abſinth. an.* ʒ i. *ol. roſar. & chamæm. an.* ʒ. i. *fiat Cataplaſma ad formam Pultis ſatis liquidæ.* Another, ℞ *farinæ hord.* ʒ iij. *farinæ ſem. lini & fænugræci. an.* ʒ i. *coquantur in aqua communi addendo ſub. finem pul. myrtil. roſar. & chamæm. an.* ʒ ſs. *axungiæ anſeris & olei roſar. an.* ʒ i. *miſce, fiat Cataplaſma.*

What local Medicins we muſt uſe in the increaſe.

What in the ſtate.

But in the ſtate, the repercuſſives and diſcuſſives ought to be alike with ſome anodyns, or mitigating Medicins, if it be painful, as, ℞ *Rad. Altheæ* ʒ iv. *malvæ, parietar. an. m.* ij. *coquantur ſub cineribus, addendo farin. fabar. & lentium an.* ʒ ij. *pulveris cham. & meliloti an.* ʒ ß. *olei cham. & roſar. an.* ʒ i. *axungiæ gal.* ʒ ij. *fiat Cataplaſma.* Another, ℞ *Micæ panis triticei aquâ calidâ macerati* ℔ ß. *pulveris roſar. rub. & abſinth. ana* ʒ vj. *olei aneth. & mellis com. an.* ʒ ij. *Miſce omnia ſimul & fiat Cataplaſma ad formam Pultis ſatis liquidæ*; which is of chief uſe when there is pain.

What in the declination.

But when the violence of pain and other ſymptoms are aſſwaged, it is likely that the Phlegmon is come to determination. Wherefore then we muſt uſe more powerful and ſtrong diſcuſſives, and onely then; beginning with the more gentle, leſt the ſubtiler part of the humour being diſſolved, the groſſer, remaining in the part, ſhould grow hard, as, ℞ *Mal. biſmal. an. m.* iij. *coquantur, addendo farinæ hordei* ʒ ij. *mellis com.* ʒ i. *ol. chamæm. & melilot. an.* ʒ ß. *fiat Cataplaſma.* Or, ℞ *Rad. cum Brion. & Cucumer. agreſt. an.* ʒ ij. *florum chamæm. & melilot. ana m.* iij. *coquantur in hydromelite addendo farinæ, ſem. lini, & fænugræc. an.* ʒ ij. *ol. aneth. axungiæ anſer. & anat. an.* ʒ i. *fiat Cataplaſma.* And this Plaiſter following may here find place:

℞ *Diachyl. mag.* ʒ ij. *Empl. de melilot.* ʒ i. *olei aneth. & chamæmel.* ʒ ß. diſſolve them all together and make a Medicin for your uſe. Or, ℞ *Empl. de mucag. & oxycr. an.* ʒ ij. *Empl. Diachyl. Ireat.* ʒ i. *olei liliorum & chamæmel. quantum ſatis eſt*, and make thereof a ſoft Emplaiſter.

The correction of the accidents.

The fourth ſcope of curing a Phlegmon conſiſts in correction of the accidents which accompany it; of which, Pain is the principal.

The diſcommodities of pain.

Wherefore the Chirurgeon muſt be diligent to aſſwage it; for beſides, that it weakens the ſtrength, and debilitates and depraves the function, it alſo cauſes defluxions by drawing the bloud and ſpirits to the part affected.

Medicins aſſwaging pain.

According to the variety of Pain there muſt be variety of Medicins, as, ℞ *Micæ panis albi in lacte tepido macerati* ℔ ſs. *vitell. ovorum* iij. *ol. roſar.* ʒ ij. *croci* ʒ ß. *fiat Cataplaſma.* Or, ℞ *Florum chamæm. & melil. an. p.* iij. *farinæ ſem. lini, & fænugræc. an.* ʒ i. *fiat Cataplaſma Pultis ſatis liquidæ.* Or, ℞ *Mucagin. rad. altheæ & fænugr. an.* ʒ iij. *ol. roſar. & aneth. an.* ʒ i. *farin. ſem. lini. quantum ſatis, ut inde formetur Cataplaſma ſatis molle.*

Narcotick Medicins.

But if the pain remain, and yield not to theſe remedies, we muſt flie to ſtronger; making of Narcoticks or Stupefactives, but with care leſt we benum or dead the part; as, ℞ *Fol. hyoſcyami & papav. ſub. cineribus coctorum an.* ʒ iij. *adipis ſuillæ & ol. roſ. an* ʒ. i. *croci* ʒ ij. *fiat Cataplaſma:* or, ℞ *Fol. cicutæ & ſolani furioſi, an.* ʒ iv. *coquantur ſub cineribus, piſſentur, & trajiciantur addendo unguent. popul. & ol. roſar. an* ʒ i. *farin. fænugræc. quantum ſatis erit, ut inde formetur Cataplaſma ad formam Pultis liquidæ.*

CHAP.

CHAP. V.

The Cure of an ulcerated Phlegmon.

BUt it often happens that the humour is ſo impact in the part, that it cannot be repreſſed, and ſo groſs, that it cannot be diſcuſſed; which we may know by the greatneſs of the heat and ſwelling, by the bitterneſs of the pricking pain, the fever, and pulſation, and heavineſs. The ſigns of a Phlegmon turning to an Abſceſs.

Wherefore laying aſide all hope of diſcuſſing, we muſt come to the Suppuratives. For which purpoſe *Galen* foments the ſwollen part with Water or Oyl being Warm, or with both of them; and then applies this following Cataplaſm. *Lib. 2. ad Glau. cap. 7.*

℞ *Farinæ triticivel micæ panis* ℥ iv. *ol. com.* ℥ iij. *aquæ com. quantum ſufficit. fiat Cataplaſma.* Or, ℞ *Rad. lilior. alb. & althææ, an.* ℥ iij. *fol. malvæ parietar. & ſenecionis, ana. m.* i. *coquantur in hydromelite, piſſentur trajectis adde farin. ſem. lini* ℥ ij. *axungiæ ſuillæ, ol. liliorum, an.* ℥ ß. *fiat Cataplaſma.* Or, ℞ *Malvæ, biſmalv. violar. an. m.* i. *caricarum ping. n.* x. *paſſul.* ℥ ij. *coquantur in aq. com. tuſis, & trajectis, adde mellis com.* ℥ ij. *ung. baſilicon. & butyri recent. ana* ℥ i. *fiat cataplaſma.* You may profitably uſe for the ſame purpoſe, *Empl. Diachylon magnum*, or *Baſilicon.* Or, ℞ *Empl. Diachyl. mag.* ℥ iij. *ung. baſilicon.* ℥ i. *ol. liliorum* ℥ ß. Of theſe mixed together make a Medicin for the foreſaid uſe. Suppurative Medicins.

When the heat, pain, fever, and other accidents ſhall remit, when the tumour hath a ſharp head, when by the preſſing of your finger you find the humour to flow, as it were, to and fro, then you may know that it is ripe. The ſigns of *Pus*, or matter

Wherefore without any further delay the tumor muſt be opened, leſt the matter too long ſhut up, corrode the adjacent parts, and the Ulcer become ſinuous and fiſtulous.

For this uſually happens, eſpecially then, when the matter is venenate or malign, or when the ſwelling is near a Joint, or at the Fundament, or ſuch like hot and moiſt places.

For by the decree of *Hippocrates* we ſhould anticipate the maturation of ſuch Tumours by opening. *Hip. lib. de Fiſtula.*

They may be opened with an Inciſion-knife, or Cauſtick, and that either actual, or potential. For if the Patient ſhall be heartleſs and leſs confident, ſo that he either cannot, or will not endure any Inſtrument, you muſt make way for the matter by a Potential Cautery. You may alſo do the buſineſs by another ſlight, as thus:

Thruſt the point of a ſharp Knife or Lancet through a braſs Counter, that it may ſtand faſt in the midſt thereof; then cover it diligently with ſome Emplaiſter or Cataplaſm, that neither the Patient nor ſtanders by perceive the deceit: then laying on the Plaiſter, as if that you would make a paſſage for the matter by that means; but when you have fitted the point to the part where it is fit to open the Tumor, ſo guide the Counter with your fingers, that you may preſently make an impreſſion into the Tumor ſufficient for excluding the matter. I have here expreſſed three delineations of ſuch Inſtruments, that you may uſe theſe, either bigger, leſſer, or indifferent, as occaſion ſhall ſerve.

B *Counters with the points of Knives or Lancets put through them.*



A *Shews the Counter or piece of Silver.*
B *Shews the point of the Lancet.*

But there are ſeven things which muſt be diligently conſidered in opening all ſorts of Impoſtumes. The firſt is, That you put your Knife to that part of the Abſceſs which is the ſofter, and yields to the impreſſion of your fingers, and where it riſes into a head or point. The ſecond is, That you make choice of that place for diſſection which is the loweſt, that ſo the contained impurity may the more readily flow out, and not ſtay in the paſſage. The third is, That it be made according to the wrinkles of the skin, and the right Fibers of the Muſcles lying next under the skin. The fourth is, That you turn your Knife from the larger Veſſels and Nerves worth ſpeaking of. The fifth is, That the matter contained in them be not evacuated too abundantly at once in great Abſceſſes, leſt thereby the ſtrength be dejected, the ſpirits being much waſted together with the unprofitable humour. The ſixth is, That the affected part be handled as gently as you can. The ſeventh is, That after the opening, when the matter is evacuated, the Abſceſs be cleanſed, filled with fleſh, and laſtly, conſolidated and cicatrized. But ſeeing that commonly after ſuch ſections ſome part of the Tumour remains, all the contained humour being not wholly ſuppurated, the Chirurgeon may perceive that this is an implicit affect, that is, a Tumour and Ulcer. But the Cure thereof muſt be ſo, that you take away the Tumour before the Ulcer; for the Ulcer cannot be healed before the part be reſtored to its nature. Therefore the Suppuratives formerly preſcribed muſt be uſed, and the Ulcer muſt be dreſſed for two or three days with this following Medicin. What the cure muſt be after the opening of the abſceſs.

Other

Other Inſtruments for opening Abſceſſes.



Rings in which little Knives lie hid, fit for to open Abſceſſes.

The Delineation of a Trunk or hollow Inſtrument going with a Spring.

A *Shews the thicker Pipe.*
B *Shews another, which enters and is faſtned in the other by a Screw.*
C *The point of the Inſtrument looking out.*
D *The ſpring which forces the Inſtrument.*

Deterſive Medicins.

℞. *Vitellum unius ovi, terebinth. Venetæ, & ol. Roſar. an.* ℥ ß, *fiat medicamentum.* Then you muſt ſeek to cleanſe it by this following Medicin.

unguentum de Apio.

℞ *Mellis roſar.* ℥ i. *Syrupi roſar. & tereb. Venet. an.* ℥ i ß. *far. hordei* ℥ ij. *fiat medicamentum ad uſum.* For this very purpoſe there is a ſingular Deterſive made of *Apium* or Smallage, of which this is the deſcription.

℞ *Succi apii, plantag. beton. an.* ℥ i. *Mellis commun.* ℥ v. *terebinth. Venet.* ℥ iv. *farin. Hordei & Orobi, an.* ʒ ij. *pulveris Aloes, rad. Ireos florent. myrrhæ, an.* ℥ i. *coquatur mel cum ſuccis, quibus conſumptis addantur farinæ, & pulveres, & miſceantur omnia ad formam unguenti.* But if you would cleanſe it more powerfully, you may uſe *Unguentum Apoſtolorum*, or *Unguentum Aureum* and *Ægyptiacum* mixed according to the ſcope you conceive in your minds; when the Ulcer ſhall ſeem ſufficiently cleanſed, it ſhall be filled with fleſh, and cicatrized after the manner we ſhall declare in the proper treatiſe of the Cure of Ulcers.

CHAP. XI.

Of Fevers and the Cures of thoſe Fevers which accompany Phlegmons.

The Fever of a Phlegmon. What a Fever is.

AMongſt the *Symptoms* which moſt uſually accompany Phlegmons, and afflict all the body of the Patient, Fevers are the chief; that is, hot and dry diſtempers kindled in the heart, and thence by the Arteries ſent over all the body; yet thoſe which uſually follow this kind of Tumours, are *Ephemeræ*, that is, Diary, unputrid *Synochi*; of whoſe nature and order of Cure I will here briefly relate what I have learnt from my Maſters, that is, Doctors of Phyſick, as I have been converſant with them in the practice of my Art.

What an *Ephemera*, or Diary is.

The *Ephemera*, or Diary [that is, of one day] is a hot and dry diſtemperature kindled in the vital ſpirits. It hath that name, becauſe by its own nature it tarries not above the ſpace of one day, or twenty four hours, by reaſon it is kindled in a ſubtile eaſily diſſipable matter.

The cauſes thereof.

The efficient cauſes of this Fever are wearineſs, hunger, and drunkenneſs, anger, fury, ſorrow, watching, great and piercing cold, Aduſtion, Bathes, and manner of living inclining more to heat then ordinary; applying, uſing or drinking of acrid Medicins, as Poiſons, or of hot Meats, or drinks; to conclude, all the efficient cauſes common to all Fevers, putrefaction onely excepted, which properly appertains to putrid Fevers.

Aphoriſm 55. *lib.* 4.

For a *Bubo* alſo, which is a Phlegmon of the Glandules, cauſes a Diary, as *Hippocrates* ſhews. All Fevers proceeding from the Tumours of the Glandules are evil, the Diary excepted. Which *Aphoriſm* muſt be underſtood warily and with that diſtinction which *Galen* gives in his Commentary, where he ſaith; It is not onely to be underſtood of Tumours riſing in the Glandules without occaſion, that is, without any evident and manifeſt cauſe; for otherwiſe Fevers that thence take their

original, though not Diary, yet are not all evil, as we learn by Buboes in Children, and the venereous Buboes, which happen without inflammation or corruption of the Liver; for ſuch commonly have no malign Fever accompanying them, which thing is worthy a Chirurgeons obſervation.

The common ſigns of a Diary are, a moderate and vaporous heat feeling gentle to the hand, a Pulſe ſwift and frequent, ſometimes great and ſtrong, as when the Diary is cauſed by anger; ſometimes little, if the Fever proceed from ſorrow, hunger, cold, crudity; for other reſpects equal and ordinary. The ſigns of a Diary.

The moſt certain ſigns are, if the Fever come upon one not by little and little, but ſuddenly, and that from external and evident cauſe; no loathing of Meat, no cauſleſs wearineſs, no deep ſleep, yawning, great pain, reſtleſsneſs, ſhaking, nor cold going before; and laſtly, no other troubleſom ſymptom preceding. We here make no mention of the Urin, becauſe moſt frequently they reſemble the Urins of ſound bodies; for in ſo ſhort a time as Diaries endure, there cannot ſo great a perturbation be raiſed in the bloud that there may be ſigns thereof found in the Urine. A Diary is ended in one fit, which by the proper nature of this Fever laſts but one day, although ſometimes otherwiſe it is extended to three or four days ſpace; and then it eaſily degenerates into a Putrid, eſpecially any errour of the Patient, Phyſician, or thoſe which attend him, concurring therewith, or if the external things be not rightly fitted. Why in a Diary the Urin is like to thoſe in health.

This Fever is terminated either by inſenſible tranſpiration, or by the moiſture of the skin, or by a ſweat natural, gentle, and not ill ſmelling; to this Diary we may refer the unputrid *Synochus* generated of bloud not putrid, but onely heated beyond meaſure. For uſually there ariſes a great heat over all the body, by means of the bloud immoderately heated; whence the Veins become more tumid, the Face appears fiery, the Eyes red and burning, the Breath hot, and to conclude, the whole habit of the body more full, by reaſon of that ebullition of the bloud, and the diffuſion of the vapours thence ariſing over all the body: Whence it is that this kind of *Synochus* may be called a vaporous Fever. To this Children are incident; as alſo all ſanguin bodies, which have no ill humours. The cure of this and the *Ephemera*, or Diary is the ſame; becauſe it may ſcarce ſeem different from the *Ephemera* in any other thing, than that it may be prolonged for three or four days. Wherefore whatſoever we ſhall ſay for the cure of the *Ephemera*, may be applied to the *Synochus*, bloud-letting excepted, which in an unputrid *Synochus* is very neceſſary. The unputrid *Synochus*.

Now the cure of a Diary-Fever conſiſts in the decent uſe of things Not natural, contrary to the cauſe of a diſeaſe; wherefore Baths of warm and natural Water are very profitable, ſo that the Patient be not Plethorick, nor ſtuffed with excrements, nor obnoxious to Catarrhs and Defluxions, becauſe a Catarrh is eaſily cauſed and augmented by the humours diffuſed and diſſolved by the heat of a Bath; therefore in this caſe we muſt eſchew frictions, and anointing with warm oil, which things notwithſtanding, are thought very uſeful in theſe kind of Fevers, eſpecially when they have their original from extreme labour, by attriction of the skin, or a *Bubo*. Let this be a general rule, that to every Cauſe whence this Fever proceeded, you oppoſe the contrary for a remedy; as to labour, reſt; to watching, ſleep; to anger and ſorrow, grateful ſociety of Friends, and all things repleniſhed with pleaſant good will; and to a *Bubo*, the proper cure thereof. The cure of a Diary Fever.

Wine moderately tempered with Water according to the cuſtom of the ſick Patient, is good and profitable in all cauſes of this Fever, except he be pained in his head, or that the Fever drew its original from anger, or a *Bubo*; for in this laſt caſe eſpecially, the Patient muſt abſtain wholly from Wine, until the inflammation come to the ſtate, and begins to decline. This kind of Fever often troubles Infants; and then you muſt preſcribe ſuch Medicins to their Nurſes, as if they were ſick, that ſo by this means their Milk may become Medicinable. Alſo it will be good to put the Infant himſelf into a Bath of natural and warm Water, and preſently after the Bath to anoint the ridg of the Back and Breſt with Oil of Violets. But if a Phlegmon poſſeſs any inward part, or otherwiſe by its nature be great, or ſeated near any principal Bowel, ſo that it may continually ſend from it either a putrid matter or exhalation to the heart, and not onely affect it by a quality of preternatural heat by the continuity of the parts, thence will ariſe the putrid *Synochus*, if the bloud by contagion putrefying in the greater Veſſels, conſiſts of one equal mixture of the four humours. This Fever is thus chiefly known: it hath no exacerbations, or remiſſions, but much leſs intermiſſions; it is extended beyond the ſpace of twenty four hours, neither doth it then end in vomit, ſweat, moiſture, or by little and little inſenſible tranſpiration, after the manner of intermitting Fevers or Agues; but remains conſtant, until it leaves the Patient for altogether: it commonly happens not, unleſs to thoſe of a good temper and complexion, which abound with much bloud, and that tempered by an equal mixture of the four humours. It commonly endures not long, becauſe the bloud by ſome peculiar putrefaction degenerating into Choler or Melancholy, will preſently bring forth another kind of Fever, to wit, a Tertian or continued Quartan. The uſe of Wine in a Diary. How a putrid *Synochus* is cauſed.

The cure of this Fever (as I have heard of moſt learned Phyſitians) chiefly conſiſts in bloud-letting. For by letting of bloud the fulneſs is diminiſhed, and therefore the obſtruction is taken away, and laſtly the putrefaction. And ſeeing that in this kind of Fever there is not onely a fault of the matter, by the putrefaction of the bloud, but alſo of the Temper by exceſs of heat; certainly Phlebotomy helps not onely, as we ſaid, the putrefaction, but alſo the hot diſtemper. For the bloud in which all the heat of the creature is contained, whileſt it is taken away, the acrid and fuliginous excrements exhale and vaniſh away with it, which kept in, increaſe the Feveriſh heat. Moreover the Veins, to ſhun emptineſs, which Nature abhors, are filled with much cold air in ſtead of the hot bloud which was drawn away, which follows a cooling of the habit of the whole body, yea, and many by means of Phlebotomy have their Bellies looſed, and ſweat, both which are much to be deſired in this kind of Fever. Phlebotomy neceſſary in a putrid *Synochus*.

This moved the ancient Phyſicians to write, that we muſt draw bloud in this diſeaſe, even to the fainting of the Patient. What benefit we may reap by drawing bloud even to fainting.

Yet

Yet becauſe thus, not a few have poured out their lives together with their bloud, it will be better and ſafer to divide the evacuations, and draw ſo much bloud at ſeveral times, as the greatneſs of the diſeaſe ſhall require, and the ſtrength of the Patient may bear.

Why we muſt give a Clyſter preſently after bloud-letting.

When you have drawn the bloud, forthwith inject an emollient and refrigerative Clyſter; leſt that the Veins emptied by Phlebotomy may draw into them the impurity of the Guts; but thoſe Clyſters which cool too much, rather bind the belly than looſe it. The following day the Morbifick matter muſt be partly evacuated by a gentle Purge, as a bole of *Caſſia*, or *Catholicon*; then muſt you appoint Syrups which have not onely a refrigerative quality, but alſo to reſiſt putrefaction, ſuch as the Syrup of Limmons, Berberies, of the Juice of Citrons, of Pomegranats, Sorrel and Vinegar; let his diet be abſolutely cooling and humecting, and alſo ſlender; for the native heat much debilitated by drawing of great quantity of bloud cannot equal a full diet. Therefore it ſhall ſuffice to feed the Patient with Chicken and Veal Broths made with cooling Herbs; as Sorrel, Lettuce, and Purſlan. Let his drink be Barly Water, Syrrup of Violets mixed with ſome pretty quantity of boiled Water, *Julepum Alexandrinum*, eſpecially if he be troubled with ſcouring or laſk. But the Phyſitian muſt chiefly have regard to the fourth day: for if then there appear any ſigns of concoction in the excrethe *Criſis* muſt be expected on the ſeventh day, and that either by a looſeneſs of the belly, or an abundance of Urin, by Vomits, Sweats, or Bleeding Therefore we muſt then do nothing but commit the whole buſineſs to Nature.

When Syrrups profitable in this caſe.

Why a ſlender Diet muſt be uſed after letting much bloud.

When drinking of Water is permitted in a putrid *Synochus*.

But for drinking cold Water, which is ſo much commended by *Galen* in this kind of Fever, it is not to be ſuffered before there appear ſigns of concoction; moreover in the declining of the Diſeaſe, the uſe of Wine will not be unprofitable to help forwards Sweats.

CHAP. XII.

Of an Eryſipelas, *or Inflammation.*

The definition of an *Eryſipelas*.

HAving declared the cure of a Phlegmon, cauſed by laudable bloud; we muſt now treat of thoſe Tumors which acknowledge Choler the material cauſe of their generation, by reaſon of that affinity which intercedes between Choler and Bloud. Therefore the Tumors cauſed by natural Choler, are called *Eryſipelata*, or Inflammations; theſe contain a great heat in them, which chiefly poſſeſſes the skin, as alſo oftentimes ſome portion of the fleſh lying under it. For they are made by moſt thin and ſubtle bloud (which upon any occaſion of inflammation eaſily becomes Cholerick) or by bloud and Choler, hotter then is requiſite, and ſometimes of choler mixed with an acrid ſerous humour.

Gal. cap. 2. lib. 14. Meth. med. & 2. ad Glauc.

That which is made by ſincere and pure choler, is called by *Galen*, a true and perfect *Eryſipelas*. But there ariſe three differences of *Eryſipelaes*, by the admixture of choler with the three other kinds of humours. For if it being predominant be mixed with bloud, it ſhall be termed *Eryſipelas Phlegmonodes*; if with Phlegm, *Eryſipelas œdematodes*; if with Melancholy, *Eryſipelas Scirrhodes*. So that the former and ſubſtantive word ſhews the humour bearing dominion, but the latter or adjective that which is inferiour in mixture. But if they concur in equal quantity, there will be thereupon made *Eryſipelas Phlegmone*, *Eryſipelas œdema*, *Eryſipelas ſcirrhus*.

Two kinds of *Eryſipelaes*.

Galen acknowledges two kinds of *Eryſipelaes*, one ſimple and without an ulcer, the other ulcerated. For choler drawn and ſevered from the warmneſs of the bloud, running by its ſubtilty and acrimony unto the skin, ulcerates it; but reſtrained by the gentle heat of the bloud, as a bridle, it is hindered from piercing to the top of the skin, and makes a tumour without an ulcer. But of unnatural choler are cauſed many other kinds of cholerick tumors, as the *Herpes*, *Exedens*, and *Miliaris*: and laſtly, all ſorts of tumors which come between the *Herpes* and *Cancer*. You may know *Eryſipelas* chiefly by three ſigns, as by their colour, which is yellowith red; by their quick ſliding back into the body at the leaſt compreſſion of the skin, the cauſe of which is the ſubtlety of the humour and the outward ſite of it under the skin, (whereupon by ſome *Eryſipelas* is called a Diſeaſe of the Skin;) laſtly, by the number of the Symptoms, as Heat, Pulſation, Pain. The heat of an *Eryſipelas* is far greater than that of a Phlegmon, but the pulſation is much leſs; for as the heat of the bloud is not ſo great as that of choler, ſo it far exceeds choler in quantity and thickneſs; which may cauſe compreſſion and obſtruction of the adjacent Muſcle.

Gal. lib. 2. ad Glauc. Hip. Apho. 79. Sect. 7. Aph. 25. Sect. 16. Aph. 43. Sect. 3.

For Choler eaſily diſſipable by reaſon of its ſubtlety quickly vaniſhes, neither doth it ſuffer it ſelf to be long contained in the empty ſpaces between the Muſcles; neither doth an *Eryſipelas* agree with a Phlegmon in the propriety of the pain. For that of an *Eryſipelas* is pricking and biting without tenſion or heavineſs; yet the primitive, antecedent, and conjunct cauſes are alike of both the tumors. Although an *Eryſipelas* may be incident to all parts, yet principally it aſſails the Face, by reaſon of the rarity of the skin of that place, and the lightneſs of the cholerick humour flying upwards. It is ill when an *Eryſipelas* comes upon a wound or ulcer, and although it may come to ſuppuration, yet it is not good; for it ſhews that there is obſtruction by the admixture of a groſs humour, whence there is ſome danger of eroſion in the parts next under the skin.

It is good when *Eryſipelas* comes from within outwards, but ill when from without it retires inward. But if an *Eryſipelas* poſſeſs the Womb it is deadly, and in like manner if it ſpread too far over the face, by reaſon of the ſympathy of the membranes of the Brain.

CHAP.

CHAP. XIII.

Of the Cure of an Eryſipelas.

FOr the cure of an *Eryſipelas* we muſt procure two things, to wit, Evacuation and Refrigeration. But becauſe here is more need of cooling, than in a Phlegmon, the chief ſcope muſt be for Refrigeration. Which being done, the contained matter muſt be taken away and evacuated with moderately reſolving Medicines. We muſt do four things to attain unto theſe forementioned ends. Firſt of all, we muſt appoint a convenient manner of Diet, in the uſe of the ſix things not natural; that is, we muſt incraſſate, refrigerate, and moiſten, as much as the nature of the Diſeaſe and Patient will ſuffer, much more than in a Phlegmon; then we will evacuate the antecedent matter by opening a Vein, and by Medicines purging choler; and that by cutting the Cephalick Vein, if there be a portion of the bloud mixed with choler, if the *Eryſipelas* poſſeſs the face, and if it be ſpread much over it. *Gal.* 14. *Meth.* Four things to be performed in curing an *Eryſipelas.*

But if it ſhall invade another part, although it ſhall proceed of pure choler, Phlebotomy will not be ſo neceſſary, becauſe the bloud which is as a bridle to the Choler being taken away, there may be danger, leſt it become more fierce; yet if the body be plethorick, it will be expedient to let bloud, becauſe this, as *Galen* teacheth, is oft-times the cauſe of an *Eryſipelas*. It will be expedient to give a Clyſter of refrigerating and humecting things before you open a Vein; but it belongs to a learned and prudent Phyſitian to preſcribe Medicines purging choler. In what *Eryſipelas* it is convenient to let bloud, in what not.

The third care muſt be taken for Topick, or local Medicins, which in the beginning and increaſe muſt be cold and moiſt, without any either drineſs or aſtriction, becauſe the more acrid matter by uſe of aſtringent things being driven in, would ulcerate and fret the adjacent particle. What Topick Medicins are fit to be uſed in the beginning of an *Eryſipelas.*

Galen and *Avicen* much commend this kind of remedy; Take fair Water ℥ vj. of the ſharpeſt Vinegar ℥ i, make an Oxycrate, in which you may wet linnen clothes and apply to the affected part and the circumjacent places, and renew them often. Or, ℞ *Succi ſolani, plantag. & ſempervivi, an.* ℥ ij. *aceti* ℥ ß. *Mucaginis ſem. Pſyllii* ℥ ij. *ſucci hyoſcyami* ℥ i. *Miſce.* But if it the *Eryſipelas* be upon the face, you muſt uſe the Medicin following,

℞ *Unguent. Roſ.* ℥ iv. *ſucci plantagin. & ſempervivi, an.* ℥ i. *trochiſc. de Camphora* ℥ ß, *aceti parum*; let them be mixed together and make a liniment. But if the heat and pain be intolerable, we muſt come to narcotick Medicins. As, ℞ *Succi hyoſcyami, ſolani, cicutæ, an.* ℥ i. *album ovorum n* ij. *aceti* ℥ ß, *opii & Camphor. an. gra.* iv. *croci* ϑ ß, *Mucaginis ſem. pſyll. & fænigr. extractæ in aq. roſ. & plantag. an* ℥ i. *o!. de papav.* ℥ ij. *fiat linimentum, addendo ung. refrigerantis Gal. comphor. q. ſatis ſit.* Yet we muſt not uſe ſuch like Medicins too long, leſt they cauſe an extinction of the native heat and mortification of the part.

Wherefore ſuch Narcotick Medicins muſt be uſed with regard of place, time, and ſuch other circumſtances. Therefore we may three manner of ways underſtand when to deſiſt from uſing Narcotick or Stupefactive Medicins. The firſt is when the Patient in the affected part feels not ſo much heat, pricking and pain, as before. The ſecond is, when the part feels more gentle to the touch than before. The third, when the fiery and pallid colour begins by little and little to wax livid and black; for then muſt we abſtain from Narcotick, and uſe reſolving and ſtrengthening things, whereby the part may be revived and ſtrengthened by recalling the native heat; As, ℞ *Farinæ hordei & Orobi, an.* ℥ ij. *farinæ ſem. lini* ℥ i ß, *coquantur in Hydromelite vel oxycrato, addendo pulv. roſarum & chamæmel, an.* ℥ ß. *ol. anethi & chamæm. an.* ℥ i. *fiat cataplaſma.* Or you may uſe this following fomentation, ℞ *Rad. Altheæ* ℥ ij. *fol. malvæ, biſmal. pariet. abſinthii, ſalviæ, an.* m. i. *flor. chamæm. meliloti, roſar. rub. an.* m. ij. *coquantur in æquis partibus vini & aquæ, & fiat fotus cum ſpongia.* After the fomentation, you may apply an Emplaiſter of *Diachylon Ireatum*, or *Diapalma* diſſolved in Oyl of Chamomile and Melilote, and ſuch other like. The fourth Intention which is of the correction of accidents, we will perform by thoſe means which we mentioned in curing a Phlegmon, by varying the medicaments, according to the judgment of him which undertakes the Cure. What caution muſt be had in the uſe of Narcotick Medicins. Reſolving and ſtrengthening Medicins.

CHAP. XIV.

Of the Herpes; *that is, Tetters, or Ring-worms, or ſuch like.*

HErpes is a tumour cauſed by pure choler ſeparated from the reſt of the humours, that is carried by its natural lightneſs and tenuity even to the outer or ſcarf-skin, and is diffuſed over the ſurface hereof. *Galen* makes three ſorts of this tumour. For if perfect choler of an indifferent ſubſtance, that is, not very thick, cauſe this tumour, then the ſimple *Herpes* is generated, obtaining the name of the *Genus*; but if the humour be not ſo thin, but compounded with ſome ſmall mixture of Phlegm, it will raiſe little bliſters over the skin like to the ſeeds of Millet, whence it was that the Ancients called this Tumour the *Herpes Miliaris*. But if it have any admixture of Melancholy, it will be an *Herpes exedens*, terrible by reaſon of the eroſion, or eating into the Skin and Muſcles lying under it. What a *Herpes* is, what be the kinds thereof. *Gal. 2. ad Glauconem.* What the *Herpes miliaris* is. What the *exedens.*

There are abſolutely three intentions of curing; The firſt is to appoint a Diet juſt like that we mentioned in the cure of an *Eryſipelas*; The ſecond is to evacuate the antecedent cauſe, by Medicins purging the peccant humour, for which purpoſe oft-times Clyſters will ſuffice, eſpecially if the Patient be ſomewhat eaſie by Nature, and if the Urin flow according to your deſire; for by this a great part of the humour may be carried into the bladder; The third ſhall be to take away the conjunct cauſe by Local Medicins ordained for the ſwelling and ulcer: Therefore the Chirurgeon Three intentions in curing *Herpes.*

A rule for healing Ulcers conjoined with tumours.

rurgion ſhall have regard to two things, that is, the reſolving of the tumour, and the drying up of the Ulcer; for every Ulcer requires drying, which can never be attained unto, unleſs the ſwelling be taken away. Therefore becauſe the chiefeſt care muſt be to take away the tumour, which if it be performed, there can be no hope to heal the ulcer; he ſhall lay this kind of medicine to diſſolve and dry, as, ℞ *Ceruſæ & tuthiæ prepar. an.* ℥ j. *ol. roſ. & adipis capon. an.* ℥ ij. *corticis pini uſti, & loci* ʒ ſ, *ceræ quantum ſatis, fiat unguentum.* Or, ℞ *Farin. hord. & lent. an.* ℥ ij. *coquantur in decocto corticis mali granati, balauſt. plantag. addendo pulveris roſar. rub. abſinth. an.* ʒ ſ, *olei Myrtillor. & mellis com. an.* ℥ vj. *fiat unguentum, ut artis eſt.* But for an *Herpes Miliaris* theſe muſt chiefly be uſed, ℞ *Pulv. gallarum, malicurii, balauſt. boli armeni an.* ʒ i. *aquæ roſ.* ℥ iij. *aceti acerrimi* ʒ i. *axungiæ anſer. & olei Myrtillor. an.* ℥ i ſ, *terebinth.* ʒ i. *fiat unguentum ad uſum.* I have often found moſt certain help in *unguentum emulatum cum Mercurio*, for it kills the Puſtules, and partly waſtes the humour contained in them. Yet if the Ulcer not yet neither yields, but every day diffuſes it ſelf further and further, you ſhall touch the edges and lips thereof with ſome acrid medicin, as *Aqua fortis*, Oil of Vitriol, or ſuch like, for by this kind of remedy, I have oft-times healed fretting Ulcers, which ſeemed altogether incurable.

The force of *unguentum emulatum cum Mercurio.*

Medicines fit for reſtraining eating and ſpreading Ulcers.

CHAP. XV.

Of Fevers, which happen upon Eryſipelous Tumors.

A vulgar deſcription of an intermitting Tertian Fever.

AS Fevers ſometimes happen upon Inflammations, and Eryſipelaes, which favour of the humour whereof they proceed, that is, Choler: Therefore ſeeing it is peculiar to Choler, to move every third day, it is no marvail if great Inflammations bring with them Tertian Fevers, or Agues, which have their Fit every third day; for it is called an Intermitting Tertian which comes every other day.

The cauſes of Tertian Fevers.

The primitive cauſes in general are ſtrong exerciſes, eſpecially in the hot Sun, the uſe of heating and drying either Meats or Medicins, great abſtinence joined with great labour, care, ſorrow; the antecedent cauſes are the plenty of choler in the body, and hot and dry diſtemperature either of the whole Body, or of the Liver onely: the conjunct cauſe is the putrefaction of the cholerick humour lying in ſome plenty without the greater Veſſels, in the habit of the Body.

The ſigns of an intermitting Tertian.

The Signs, a ſhaking or ſhivering, like as when we have made water in a cold Winter morning, a great pricking, ſtretching or ſtiffneſs, as if there were pins thruſt into us over all our bodies, by reaſon of the acrimony of the cholerick humour driven uncertainly and violently over all the body, and the ſenſible membranous and nervous particles at the beginning of the Fit; then preſently the heat becomes acrid, the Fever kindled like a Fire in dry Straw; the Pulſe is great, quick and equal, the Tongue dry, the Urine yellowiſh, red and thin. The Symptoms are watchings, thirſt, talking idly, anger, diſquietneſs and toſſing the body at the leaſt noiſe or whiſpering. Theſe Fevers are terminated by great Sweats. They are incident to cholerick young Men, ſuch as are lean, and in Summer; after the Fit oft-times follow cholerick Vomiting and yellowiſh Stools. After the Fit there follows an abſolute intermiſſion retaining no reliques of the Fever, until the approach of the following Fit, becauſe all the cholerick matter by the force of that Fit and Nature, is eaſily caſt out of the body, by reaſon of its natural levity and facility; whereas in Quotidians there is no ſuch thing, as which after the Fit always leave in the body a ſenſe and feeling of a certain inequality by reaſon of the ſtubbornneſs of the Phlegmatick humour and dulneſs to motion. The Fit commonly uſes to endure 4,5,or 6 hours, although at ſome time it may be extended to 8 or 10. This Fever is ended at 7 Fits, and uſually is not dangerous, unleſs there be ſome errour committed by the Phyſitian, Patient, or ſuch as attend him. Tertians in Summer are ſhorter, in Winter longer.

The Symptoms.

Why Tertians have an abſolute ceſſation of the Fever at the end of each fit.

Wherefore the beginning of the Fit is accompanied with ſtiffneſs, or ſtretching, the ſtate with ſweat, whereupon, if the Noſe, Lips, or Mouth, break forth into pimples, or ſcabs, it is a ſign of the end of the Fever, and of the power of nature which is able to drive the conjunct cauſe of the diſeaſe from the center to the habit of the body; yet theſe pimples appear not in the declining of all Tertians, but onely then, when the cholerick humour cauſing the Fever ſhall reſide in the Stomach, or is driven thither from ſome other part of the firſt region of the Liver. For hence the ſubtler portion thereof, carried by the continuation of the inner Coat to the Mouth and Noſe, by its acrimony eaſily cauſes Pimples in theſe places. The Cure is performed by Diet, and Pharmacy.

The diet of ſuch as have a Tertian

Therefore let the Diet be ſo ordered for the ſix things not natural, that it may incline to refrigeration and humectation, as much as the digeſtive faculty will permit, as Lettuce, Sorrel, Gourds, Cucumbers, Mallows, Barly, Creams, Wine much allaid with Water, thin, ſmall, and that ſparingly, and not before ſigns of concoction ſhall appear in the Urine; for at the beginning he may not uſe Wine, nor in the declining, but with theſe conditions which we have preſcribed.

When ſuch as have a Tertian may uſe Wine.

The time of feeding the Patient.

But for the time of feeding the Patient, on that day the Fit is expected, he muſt eat nothing for three hours before the Fit, leſt the Aguiſh heat lighting on ſuch Meats as yet crude, may corrupt and putrifie them; whence the matter of the Fever may be increaſed, (becauſe it is as proper to that heat to corrupt all things, as to the native to preſerve and vindicate from putrefaction) the Fit lengthened, and Nature called away from the concoction and excretion of the Morbifick humour; yet we may temper the ſeverity of this Law by having regard to the ſtrength of the Patient; for it will be convenient to feed a weak Patient not onely before the Fit, but alſo in the Fit it ſelf; but that onely ſparingly, leſt the ſtrength ſhould be too much impaired.

When to purge the Patient.

Now for Pharmacy; It muſt be conſidered, whether the ſtrength of the Patient be ſufficient, if the humours abound; for then you may preſcribe *Diaprunum ſimplex*, *Caſſia* newly extracted, the decoction of Violets, of Citrin Myrobalanes, Syrups of Violets, Roſes, of Pomegranats and Vinegar. But if the powers of the Patient languiſh, he muſt not onely not be purged, but alſo muſt not draw bloud

bloud too plenteouſly, becauſe Cholerick men ſoon faint, by reaſon of the facile and eaſie diſſipation of the ſubtile humors and ſpirits; beſides, ſuch as are ſubject to Tertian Fevers do not commonly abound with bloud, unleſs it be with cholerick bloud, which muſt rather be renewed, or amended by cooling and humecting things, than evacuated. Yea verily, when it is both commodious and neceſſary to evacuate the body, it may be attempted with far more ſafety by ſuch things as work by inſenſible tranſpiration, which provoke Sweats, Vomit, or Urin, by reaſon of the ſubtlety of the cholerick humour, than by any other. Alſo the frequent uſe of emollient Clyſters made with a decoction of Prunes, Jujubes, Violets, Bran and Barley, will profit much. If the Patient fall into a *Delirium*, or talk idlely by reaſon of the heat and drineſs of the head, with a particular exceſs of the cholerick humor, the head muſt be cooled by applying to the Temples and Fore-head, and putting into the Noſe Oil of Violets, Roſes, or Womans Milk. Let the feet and legs be bathed in fair and warm Water, and the ſoles of the feet be anointed with Oil of Violets, and ſuch like.

In the declining, a Bath made of the branches of Vines, the leaves of Willows, Lettuce, and other refrigerating things boiled in fair Water, may be profitably uſed three hours after meat eaten ſparingly.

When the time is fit to uſe a Bath.

But I would have you ſo to underſtand the Declination, or declining, not of one particular Fit, but of the Diſeaſe in general, that the humours already concocted, allured to the skin by the warmneſs of the Bath, may more eaſily and readily breath forth: he which otherwiſe ordains a Bath at the beginning of the Diſeaſe, will cauſe a conſtipation in the skin and habit of the body, by drawing thither the humours peradventure tough and groſs, no evacuation going before.

What kinds of evacuations are moſt fit in a Tertian.

Alſo it will be good after general purgations to cauſe ſweat by drinking White Wine, thin and well tempered with Water; but Urin by a decoction of Smallage and Dill. Certainly Sweat is very laudable in every putrid Fever, becauſe it evacuates the conjunct matter of the Diſeaſe, but chiefly in a Tertian, by reaſon that choler by its inbred levity eaſily takes that way, and by its ſubtlety is eaſily reſolved into ſweat. But that the ſweat may be laudable it is fit it be upon a critical day, and be fore-ſhewed by ſigns of concoction agreeable to the time and manner of the Diſeaſe. Sweats when as they flow more ſlowly are forwarded by things taken inwardly and applied outwardly; by things taken inwardly, as with white Wine, with a decoction of Figs, Raiſins ſtoned, Graſs, Roots, and the like opening things; but by things outwardly applied, and Sponges dipped in a decoction of hot Herbs (as Roſemary, Thyme, Lavender, Marjerom, and the like) applied to the Groins, Armholes, and Ridge of the Back.

Sudorificks;

You may for the ſame purpoſe, fill two Swines bladders with the ſame decoction, or elſe Stone-bottles, and put them to the feet, ſides, and between the thighs. Then let this be the bound of Sweating, when the Patient begins to wax cold, that is, when the Sweat feels no more hot, but cold.

When bloud muſt be let.

But by the conſent of all, bloud muſt not be letten after the third Fit, but preſently at the beginning of the Fever, according to the opinion and preſcription of *Galen*; for ſeeing this Fever for the moſt part is terminated at ſeven Fits, if you ſtay until the third Fit be paſt, the Fever will now be come to its State; but *Hippocrates* forbids us to move any thing in the ſtate, leſt Nature then buſied in concocting the Diſeaſe, be called from its begun enterpriſe.

Aphor. 29. Sect. 2.

CHAP. XVI.

Of an Oedema, *or cold Phlegmatick Tumor.*

HItherto we have treated of hot Tumors, now we muſt ſpeak of cold; Cold Tumors are onely two, an *Oedema*, and a *Scirrhus*. And for all that *Hippocrates* and the Ancients uſed the the word *Oedema* for all ſorts of Tumors in general; yet by *Galen* and thoſe Phyſicians which ſucceeded him, it hath been drawn from that large and general ſignification, to a more ſtrait and ſpecial, onely to deſign a certain *ſpecies* or kind of Tumor.

Gal. lib. de tum. præter natur.

What an *Oedema* is.

Wherefore an *Oedema* is a ſoft, lax, and painleſs Tumor, cauſed by collection of a Phlegmatick humour.

The differences of *Oedema*.

The Ancients made eight differences of Tumors proceeding of Phlegm: The firſt they termed a true and lawful *Oedema* proceeding from natural Phlegm; from unnatural Phlegm by admixtion of another humour they would have three ſorts of Tumors to ariſe; as that, by mixture of bloud, ſhould be made an *Oedema Phlegmonodes*, and ſo of the reſt.

By how many ways Phlegm becomes not natural.

Beſides, when they perceived natural Phlegm either puffed up by flatulency, or to flow with a wateriſh moiſture, they called ſome *Oedemaes* flatulent, others wateriſh; but alſo when they ſaw this ſame Phlegm often to turn into a certain Plaiſter-like ſubſtance, they thought that hence proceeded another kind of *Oedema*, which they expreſſed one while by the name of *Atheroma*, another while by *Steatoma*, and ſometimes by *Melicerides*, as laſtly, they called that kind of *Oedema* which is cauſed by putrid and corrupt Phlegm, *Scrophule*. For we muſt obſerve that Phlegm ſometimes is natural, and offends onely in quantity; whence the true *Oedema* proceeds: otherwhiles it is not natural, and it becomes not natural, either by admixtion of a ſtrange ſubſtance, as Bloud, Choler, or Melancholy, whence ariſe the three kinds of *Oedemaes* noted formerly by the way; or by the putridneſs and corruptions of its proper ſubſtance, whence the *Strumæ* and *Scrophulæ* proceed; or by concretion, whence Kernels and all kinds of Wens, *Ganglia*, and Knots; or by reſolution, whence all flatulent and wateriſh Tumors, as the *Hydrocele*, *Pneumatocele*, and all kinds of Dropſies.

The Cauſes.

The cauſes of all *Oedemaes* are the defluxion of a Phlegmatick, or flatulent humour into any part, or the congeſtion of the ſame made by little and little in any part, by reaſon of the imbecillity thereof in concocting the nouriſhment, and expelling the excrement.

The Signs.

The ſigns are a colour whitiſh and like unto the skin, a ſoft Tumor, rare and lax by reaſon of the plentiful

plentiful moiſture with which it abounds, and without pain, by reaſon this humour infers no ſenſe of heat, nor manifeſt cold; when you preſs it with your finger the print thereof remains, becauſe of the groſsneſs of the humour and ſlowneſs to motion. *Oedemaes* breed rather in Winter than in Summer, becauſe Winter is fitter to heap up Phlegm; they chiefly poſſeſs the Nervous and Glandulous parts, becauſe they are bloudleſs, and ſo cold and more fit by reaſon of their looſneſs to receive a defluxion; for the ſame cauſe, bodies full of ill humours, ancient, and not excerciſed, are chiefly troubled with this kind of Tumor.

The Prognoſticks.

How *Oedemaes* are terminated.

An *Oedema* is terminated ſometimes by reſolution, but oftner by concretion; ſeldomer by ſuppuration, by reaſon of the ſmall quantity of heat in that humour.

A Symptomatical *Oedema*, as that which follows upon a Dropſie, or Conſumption, admits no cure unleſs the Diſeaſe be firſt taken away.

The intentions of curing *Oedemaes*.

The general cure is placed in two things, that is, in evacuation of the conjunct, and matter prohibiting the generation of the antecedent. We attain to both, chiefly by four means.

The firſt truly by ordaining a fit manner of living and preſcribing moderation in the uſe of the ſix things not natural. Wherefore we muſt make choice of ſuch air as is hot, dry, and ſubtle; we muſt preſcribe Wine of a middle Nature for his drink, let the Bread be well baked, let meats be appointed which may generate good bloud, and theſe rather roſted than boiled. Let all fruits be forbidden, as alſo Broths and Milk-meats; let him eat ſuch Fiſh as are taken in Stony Rivers; the Patient ſhall obſerve mediocrity in feeding, but principally ſobriety in drinking, for fear of crudities; after meat let him uſe digeſtive Powders, or common Dridge Powder; if his belly be not naturally looſe, let it be made ſo by Art.

The Diet.

Exerciſe.

Let the Patient uſe exerciſe before meat, ſo by little and little to ſpend this humour, and reſtore the native heat. Let him ſleep little, becauſe much ſleep breedeth cold humours; let him avoid grief and ſadneſs. And if he be of a weak body, let him abſtain from Venery, leſt by another weakning by the uſe of Venery added to his preſent infirmity, he fall into an incurable coldneſs, from whence a greater meaſure of crudity will ariſe. Otherwiſe, if the body be ſtrong and luſty, by ſuch exerciſes, and the moderate uſe of Venery, it will be the more dried and heated.

What to be obſerved in the uſe of Venery.

For ſo that ſentence of *Hippocrates* is to be underſtood; That Venery is a cure for Phlegmatick Diſeaſes, as *Galen* in his Commentaries tells us. The Phyſician may perform the ſecond intention by turning his counſel to that part, from whence the Spring of Phlegmatick humour flows. For if the infirmity ariſe from the Stomach, or from any other part, the part from whence it comes muſt be ſtrengthened; if from the whole habit of the body, let attenuating, penetrating, and opening Medicins be preſcribed. We perform the third intention by evacuating the humour impact in the part with local Medicins varied according to the four times of the Tumor.

6. Epid. ſect. 5. ſen. 23.

Lib. 2. ad Glaue. cap. 3.

A Rowler.

For *Galen*, in the beginning and increaſe, preſcribeth a fomentation of *Oxyceratum* uſed with a Sponge. But if ſo be that the *Oedema* be upon the Arm or Leg, a repelling Rowler is very good, that is, ſuch an one as is brought from below upwards. So theſe Medicins following are very fit for the ſame purpoſe, ℞ *Lixivii ex cineribus ſarmentorum, & caulium, an.* ℥ iv. *Tartari & Aluminis an.* ℥ ſ. *aceti* ℥ ij. mix all together and make a decoction, wherein wet Sponges and foment the place. Alſo you may uſe the following Cataplaſm, ℞ *Farinæ hordei* ℥ iv. *coquantur in Lixivio communi, addendo pulveris nucis cupreſſi, corticum granatorum, balauſti, an* ℥ i. *Myrrhæ, Aloes, alum. an.* ℥ ſ. *olei Myrtill.* ℥ ij. *fiat Cataplaſma.* In the ſtate and declination, you muſt uſe drying and reſolving Medicins, as, *Nucum cupreſſi, granat. ſumach. balauſti, an.* ℥ i. *Salviæ, origan. calament. Hyſſopi, meliſſæ, an. m.* i. *abſinthii, plantag. caudæ equ. tapſ. barb. centinod. an. m. ſſ. alum. tartar. & ſalis com. an.* ℥ i. *coquantur cum lixivio*; foment it with a Sponge, then preſently apply this following Cataplaſm. ℞ *Rad. Brioniæ* ℥ ij. *abſinth. plantag. centin. chamæm. meliloti peleg. an. m. ſſ. coquantur in hydromelite, piſtentur, trajiciantur, addendo pulveris roſ. rub. chamæm. melil. an.* ℥ i. *fiat Cataplaſma.*

What caution to be had in application of Emplaiſters.

Laſtly, You may here with good ſucceſs uſe reſolving Emplaiſters and Ointments, firſt heating, or chafing the part by friction or fomentations, as well moiſt as dry; otherwiſe Emplaiſters will ſcarcely do their duty, by reaſon of the great coldneſs of the part, being not ſufficient of it ſelf to aſſimilate the nouriſhment, or to expel the ſuperfluous and unprofitable humour. Let a fomentation be made with white Wine, in which Sage, Roſemary, Thyme, Lavender, Chamomile and Melilot flowers, red Roſes, Orris roots, *Stœchas*, and ſuch like have been boiled, with a little Vinegar added thereunto. Quench hot Bricks in the ſame decoction, and apply them wrapped in linnen cloths to the affected part, for ſo vapours will breath forth, which hath an attenuating, piercing, reſolving and ſtrengthening faculty. But you may, in ſtead of the Bricks, fitly apply Hogs or Ox bladders, filled half full with the foreſaid decoction, and that hot. The frictions muſt be made of hot linnen cloths, for ſo the native heat together with the bloud and ſpirits is recalled to the part, and fuliginous humours contained under the skin are reſolved, whereby the ſtrength of the part is in ſome part recovered.

CHAP. XVII.

Of the Cure of flatulent and Wateriſh Tumours.

In what place Flatulencies may be gathered.

I Formerly declared that not onely flatulent and wateriſh Tumors were comprehended under this word *Oedema*, but alſo ſuch as are bred of congealed Phlegm, as *Atheromata*, *Steatomata*, and *Melicerides*, Flatulent or windy Tumors are cauſed by vapour and wind kept in or contained ſometimes under the skin, ſomewhiles under the Membranes, as the *Perioſteum* and *Pericranium*, whereupon enſues cruel torment by reaſon of the diſtention of thoſe parts which are indued with moſt exquiſit ſenſe. Sometimes the Entrails, as the Stomach and Guts are ſwollen and ſtretched out with wind, as in a Tympany.

They

They in this differ from a true and legitimate *Oedema*, that when you lay your finger upon them and take it off again, there remains no ſign of the preſſure thereof, becauſe they are diſtent by vapour and not by humour, for the vapour being preſſed returns ſpeedily again, as you may perceive by balls or bladders filled with wind. In what flatulent tumours differ from a true *Oedema*.

The cauſe of ſuch tumours is the weakneſs of the native heat, not being able eaſily to reſolve and waſte the Phlegm by which the windy Tumours are raiſed: for ſo the morning Sun (which in ſome ſort reſembles our native heat) cannot reſolve the miſts diſperſed in the air; which at noon it eaſily reſolves into pure air. Alſo after the ſame manner our weaker heat ſtirs up vapours from that Phlegm it could not diſſolve, which vapours are the matter of inflammations, or ſwellings. But oft-times although the native heat be ſufficiently powerful, yet becauſe the humour lieth deep, or is kept by the thickneſs of ſome Membrane, Tendon, or Ligament, the ſtirred up vapour cannot exhale, whereby it comes to paſs, that increaſed by little and little it cauſes a Tumour. The cauſes of flatulent tumours.

The ſigns of ſuch a Tumour are a certain renitency or reſiſtance, perceived by preſſing it with your finger; and ſometimes a noiſe, as if you ſmite upon a Drum, eſpecially if much wind be contained therein, ſuch as are often gathered together in the hollowneſs of the belly, and in the ſpaces between the larger Muſcles. The Tumour is neither red, nor hot, but rather cold and white, as in an *Oedema*. It often poſſeſſeth the joints, and eſpecially the knees, and it is very difficult to be reſolved. If ſuch flatulency be gathered together in the Guts, it cauſeth the Wind Colick, in which ſometimes the diſtenſion is ſo great, that Death enſues by reaſon of the renting or tearing the Coats of the Guts. The ſigns of ſuch tumours.

CHAP. XVIII.

Of the Cure of a flatulent and wateriſh Tumour.

WE ſhall chiefly and principally cure flatulent and wateriſh Tumours by three means. Firſt, by the ſame diet which we preſcribed in an *Oedema*; then by ſtrengthening the parts appointed for concoction, as the Stomach and Liver, chiefly by the temperate uſe of Aromatick things, as *Diacuminum*, *Diacalamentha*, *Aromaticum*, *Caryophyllatum*, *Aromaticum Roſatum*, and the like, to be preſcribed according to the good liking of the Phyſitian which over-ſees the Cure; laſtly by taking away of the conjunct matter by hot, drying, and attenuating Medicins which they call Carminative, that ſo the part being rarified, the humour and flatulency therein may be diſcuſſed and diſſipated. But remedies of this nature muſt be varied according to the variety of the parts; for ſome things are fit to be applied to the Stomach, others to the Guts, others to the Joints, and others to the fleſhy parts: for the Colick you muſt inject carminative Clyſters, let reſolving *Sacculi* or Bags be applied, and Cupping-glaſſes faſtened to the Navel; if an outward part be affected, we uſe fomentations, liniments, chiefly if pain torment, as alſo Cataplaſms and Emplaiſters, as ℞ *Florum chamæm. melil. roriſmarini, roſar. rub. an. p.* i. *abſinthii* ij. *hyſſopi, an.* m. let them be boiled in Lye, adding a little Vinegar for a fomentation to be uſed with Sponges. Diet. Things ſtrengthening the parts. Medicins evacuating the conjunct matter.

Galen foments the part with Roſe-vinegar and a little Salt put thereto, and would have a Sponge dipped therein to lie ſomewhat long upon the part, ℞ *Olei chamæm. aneth. rut. & liliorum, an.* ℥ ß. *ceræ albæ* ℥ vj. *aq. vitæ* ℥ i. let them all be mixed together and make a liniment, with which anoint the part after the fomentation. ℞ *Farinæ fabar. orobi, an.* ℥ iij. *coquantur in decoctio pulegii, origani, calamenth. ſalviæ, addita pulverum chamæm. & melilot. an. m.* ß. *furfur farinæ. fab. & orobi, an.* ℥ ij. *coquantur cum lixivio communi, addendo terebinth.* ℥ iij. *oleor. aneth. & rut. an.* ℥ ij. make an emplaiſter for the foreſaid uſe. *Galen*'s fomentation.

The Emplaiſter of *Vigo*, with *Mercury*, and without, is very good for the ſame purpoſe. But you muſt note, that ſuch Medicins muſt be applied to the part actually hot, and the ſame heat muſt be contained and renewed by putting about it linen Clothes, Bricks, Bottles, and ſuch like hot things.

The humour and flatulency which were kept ſhut up in the part being reſolved, the part muſt be ſtrengthened, leſt now and then it receive or generate the like matter. That may be done by the following fomentation and cataplaſm. ℞ *Nucum cupreſſi, corticum granat. ſumach. berberis, balauſt. an.* ℥ i. *caudæ equin. arnogloſſ. tupſi barb. abſinth. ſalviæ, roriſm. lavendul. m. ſſ. flor. chamæm. melil. roſar. anthos. an. p.* i. *alum. ſalis com. an.* ℥ i. *bulliant omnia in æquis partibus aquæ fabrorum & vini auſteri*, make bags for a fomentation, or uſe the decoction for the ſame purpoſe with a Sponge. ℞ *Farinæ fab. hordei & lupin. an.* ℥ ij. *terebinth. commun.* ℥ iv. *pulv. radicis ireos, maſtic. an.* ℥ ß. *mellis com.* ℥ ij. ß. of the aforeſaid Decoction as much as ſhall ſuffice, ſo to make a Cataplaſm to the form of a Poultis liquid enough; let it be applied hot to the affected part having uſed the fomentation before. Corroborating Medicins.

The ſigns of a wateriſh tumour are the ſame as of a flatulent; but over and beſides it ſhines and at the preſſing with your Fingers, there is heard a noiſe of murmur as of a bladder half filled with Water. The ſigns of a wateriſh tumour.

Therefore the wateriſh tumour if it ſhall not yield to the fore-mentioned reſolving Medicins, the way muſt be opened with an Inciſion-Knife, after the ſame manner, as we mentioned in a Phlegmon. For often-times this kind of remedy muſt be neceſſarily uſed, not onely by reaſon of the contumacy of the humour which gives no place to the reſolving Medicins, but alſo becauſe it is ſhut up in its proper ciſt or bag, the thickneſs of which fruſtrates the force of the reſolving Medicins, neither ſuffers it to penetrate into the humour. As I ſome years ago found by experience in a Maid of 7 years old; which troubled with a *Hydrocele*, or wateriſh Rupture, to whom, when I had raſhly applied to diſſolve it with reſolving Medicins of all ſorts, at length I was forced to open it with my knife, not only to evacuate the contained matter, but alſo that I might pluck out the bag, which unleſs it were cut up by the root, would be a mean to cauſe a relapſe. *John Altine* Doctor of Phyſick called me to this buſineſs. *James Guillemeau* the Kings Chirurgeon over-ſaw the Cure. Why a wateriſh tumour muſt be opened with an inſtrument. A Hiſtory.

CHAP. XIX.

Of an Atheroma, Steatoma, and Meliceris.

In what an *Atheroma*, *Steatoma*, and *Meliceris* differ.

ALthough theſe tumours may be thought to be comprehended under one *genus* with the other *Oedematous* tumours, yet they differ as thus; that is, their matter is ſhut up in its bladder, or bag, as it were in a peculiar Cell. But their difference amongſt themſelves is thus; the matter of the *Steatoma*, as the name ſignifieth, is like unto Tallow [for Στεαρ in *Greek* ſignifieth Tallow or Seam] yet it oft-times is found ſtuffed with other divers hard bodies, ſtony, bony, or callous, like unto the claws an Hen. For *Philoxenus* reports that he ſometimes ſaw Flies in a *Steatoma* at the opening thereof, and ſuch other like things wholly diſſenting from the common matter of Tumours. The matter contained in an *Atheroma*, is like to pap, with which they feed little Children. A *Meliceris* contains matter reſembling Honey in colour and conſiſtence; theſe tumours appear and riſe without any inflammation going before them. Thus you ſhall know theſe tumours, a *Steatoma* is harder than the other two, neither yields it to the preſſure of your finger; but when it once yields, it doth not ſpeedily and eaſily return to its former Figure, becauſe the matter is more groſs; it is of the ſame colour as the skin, without pain, and of a longiſh Figure. The *Meliceris* yields to the touch, as being a looſe and ſoft body, and as it is eaſily diſpoſed and diffuſed, ſo it quickly returns to its former place and tumour. It differs from the *Atheroma* in figure and ſubſtance. For it is more globous and of a ſubtiler and more ſhining matter, beſides alſo it takes up a large ſpace, and is more obſequious to the touch, and, for the reſt, without pain. As for the manual operation of the Chirurgeon in their cure, it ſeems to be of no great conſequence of what ſort the matter is, whether reſembling Tallow, Honey, or Pap, for there is one ſimple manner of operation, which is, that you pluck away the contained humour, as alſo the receptacle in which it is contained. Yet you muſt note ſuch tumours, ſometimes as it were hanging in the ſurface of the skin, are eaſily to be moved this way, and that way; but otherſome again deeper faſtned firmly cohere with the adjacent bodies, and theſe require an exquiſite hand, and alſo induſtry, for fear of a great flux of bloud and convulſion by cutting a Vein. There are many other kinds of tumours, as the *Teſtudo* or Mole, the *Nata*, the *Glandula*, *Nodus*, *Botium*, *Lupia*, which as in matter (for they are all of a thick, clammy, and viſcous Phlegmatick humour) ſo alſo in kind they agree with an *Atheroma*, *Steatoma*, and *Meliceris*. But alſo in theſe for the moſt part, when they are opened you may ſee bodies of all ſorts far different from the common matter of tumours, as Stones, Chalk, Sand, Coals, Snails, Straws, or Awns of Corn, Hey, Horn, Hairs, Fleſh, both hard and ſpongeous, Griſles, Bones, whole Creatures as well living as dead.

Of Chirurgery to be uſed to theſe tumours.

What the cauſe may be, that we ſometimes find *Inſecta* in theſe tumours.

The generation of which things (by the corruption and alteration of humours) ſhall not make us much to admire it, if we conſider, that as Nature, of all Seeds and Elements of the whole great World, hath made Man, the Microcoſm or little World, that he might be, as it were the lively Image of that greater World; ſo in him, it being never idle in us, would have all the kinds of all motions and actions to ſhew themſelves, as long as matter for generation is not wanting. But becauſe there is little, or rather no mention of theſe tumours amongſt the Ancients, we will briefly ſhew the opinions of the later Writers concerning them.

What the *Teſtudo* or *Talpa* is.

Now they ſay, the *Teſtudo* is a tumour contrary to Nature, ſoft, diffuſed, vaulted or arched like a Tortois, ſometimes it ariſes in the head in form of a Mole, and then it is called a Mole.

What the *Nata* is.

The *Nata* is a great and fleſhy tumour, not in ſhape unlike a Melon, or rather the fleſh of a mans Buttocks, whence it may ſeem to have had the name, unleſs we had rather ſay, It had it, becauſe it more uſually breeds upon the buttocks, than upon any other part of the body.

What a *Glandula*.

The *Glandula* takes it denomination from an Acorn, called *Glans* in Latine, the which it ſomewhat reſembles in the compaſs and form of the tumour; or elſe becauſe it moſt commonly breeds in the Glandules or Emunctories of Mans body.

What *Nodus*.

The *Nodus*, or knot, is a round tumour, hard and immoveable, named from a rope tied on a knot. *Guido Cauliacenſis* affirms Knots commonly to grow into nervous bodies; but at this time they more uſually ariſe on the bones of ſuch as have the French Diſeaſe.

CHAP. XX.

Of the Cure of Lupiæ, *that is, Wens, or Ganglions.*

What a *Ganglion* is.

A Wen or *Ganglion*, is a tumour ſometimes hard, ſometimes ſoft, yet always round, uſing to breed in dry, hard, and nervous parts. And ſeeing that ſome of the tumours mentioned before in the former Chapter, ſtick immoveable to the part to which they grow, becauſe they are contained in no ciſt, or bag; otherſome are moved up and down by the touch of your Fingers, becauſe they are contained in a bag or bladder; it commonly comes to paſs that Wens have their bladder wherein to contain them; and therefore we think fit, the rather more freely and particularly to treat of their Cure, becauſe they are more difficultly cured, eſpecially where they are inveterate and of long ſtanding.

The cauſes.

The primitive cauſes of theſe are dull blows, fallings from high places, ſtrains, and other ſuch like occaſions. But the antecedent and conjunct cauſes are the ſame with thoſe of an *Atheroma*, *Meliceris*, and *Steatoma*.

Signs.

The deſcription formerly ſet down, will furniſh you with the ſigns by which you may know when they are preſent; certainly from very ſmall beginnings they grow by little and little to a

great

great bigneſs, in the ſpace of ſix or ſeven years, ſome of them yield much to the touch, and almoſt all of them are without pain.

You may hinder ſuch as are beginning and firſt growing from increaſe, by ſomewhat a ſtrong and frequent rubbing with your fingers. For ſo their bag or bladder, together with the skin, wax thin, and the contained humour grows hot, is attenuated, and reſolved. But if ſo you nothing prevail, you muſt lie upon them with your whole hand, or a flatted piece of Wood, as heavy as you can, until ſuch time as the ciſt, or bag, be broken by your impreſſion; Then apply and ſtrongly bind unto it a Plate of Lead, rubbed over with Quickſilver; for I have many times found by experience, that it hath a wonderful force to reſolve and waſte the ſubject humour. But if the Wen be in ſuch a place in which you can make no ſtrong impreſſion, as in the Face, Cheſt, Belly, and Throat, let there be applied an Emplaiſter which hath a reſolving force, ſuch as this following hath: ℞ *Gummi ammon. bdellii. galban. an.* ʒ iij. *liqueſiant in aceto, & trajiciantur per ſetaceum, addendo olei liliorum & lauri, an.* ʒ i. *aqu. vitæ parum, pulveris ireos, ſalis ammon. ſulphur. vivi, vitrioli Romani, an.* ʒ ß. Let them be incorporated together, and make an Emplaiſter according to Art. But if the Tumor cannot be thus reſolved, it muſt be opened with a Knife, or Cautery. And after the Eſchar is removed, and the bag waſted by *Ægyptiacum*, *Mercury*, and the like, the ulcer muſt be cleanſed, repleniſhed with Fleſh, and cicatrized.

Their Cure at the beginning.

Plates of Lead rubbed with Quickſilver.

A reſolving Plaiſter.

Things to waſte or conſume the bag.

Sometimes Wens grow to ſo great a maſs that they cannot be cured by the deſcribed remedies, wherefore they muſt be taken away by the root, by your Hand and Inſtrument, if ſo be that there be no danger by reaſon of their greatneſs, and ſo that they adhere not too cloſely to the adjacent parts, and if they be not too nigh to the greater Veins and Arteries, for it will be better in ſuch a cauſe to let them alone. This ſhall be your way to cut them off, or take them away. A ſmall Inciſion muſt be made, even to the bladder or bag, by which thruſt in a Probe of a fingers thickneſs, hollowed in the midſt, round at the end, and as long as need ſhall require; then draw it many times about between the skin and the bag, even to the root of the Wen, that ſo the skin may be divided long ways, then it will be requiſite to make another Inciſion overthwart, ſo that they may interſect each other like a Croſs; then preſently draw the skin from the bladder, from the corners of the Wen towards the root, and that with your finger covered with a fine linnen cloth, or elſe with a Razor, if need require.

The manner to take away Wens.

But you muſt obſerve, that in a Wen there are always certain Veſſels which are ſmall in the beginning, but much increaſed in proceſs of time, according to the increaſe of the Wen, whereof they are, as it were, the roots; wherefore if any *Hæmorrhagie*, or flux of bloud happen, let it be ſtopped by binding the Veſſels at their heads and roots, or make a ſtrait ligature at the roots of the Wen, with a piece of Whipcord, or with a many times doubled thred, and let the ends hang forth until it fall away of its own accord. Neither will it be ſufficient to have cut away all this Tumor, but alſo it will be fit to cut away a portion of the skin, wherewith the tumor was covered, and onely to leave ſo much as ſhall ſuffice to cover the part; then with a Needle and Thred draw together the lips of the inciſion, but in the interim let tents be put into the bottom of the ulcer until it be perfectly cleanſed, and the reſt of the Cure be Workman-like performed, even to the cicatrizing thereof.

A Hiſtory.

The Chirurgeon *Collo*, and I, uſing this method, in the preſence of Maſter Dr. *Violanius* the Kings Phyſician, took away a Wen from Martial *Collard* the Maior of *Burbon*, it hanged at his neck, as big as a Mans head, and it weighed eight pounds; which made it ſo troubleſom and burdenſom to him, that he was forced to carry it bound up in a Towel as in a Scrip.

What Wens to be cured by ligature.

Which dangerous to cure.

Verily, if theſe kind of Tumors have a ſlender root and broad top, they muſt be ſtraitly tied, and ſo cut off, But it is very difficult and full of dangerous chance, to take away ſuch Wens as are ſeated in the Neck near unto the Jugular Veins, thoſe under the Arm-holes, in the Groins, and ſuch as are under the Ham; by reaſon of the deadly force of ſuch ſymptoms as may thence ariſe. We can onely conjecture, not certainly ſay, what kind of matter may be contained in them. We can onely know of what ſort it is, when by inciſion it is preſented to our ſight. Yet in ſuch as are very hard, and do much reſiſt the Touch, there are often found matters, which in conſiſtence may be reſembled to little Stones or Pebles.

A Hiſtory.

The matter of a Wen is ſometimes taken for a *Cancer*.

I being on a time called to open the body of a great Lady, found in one of her Breſts a body which might equal the bigneſs of an Hens Egg, hard, and compact like a rough Peble; it was held, whileſt ſhe lived, both by the Phyſicians and the Chirurgeons, to be a *Cancer*, becauſe this hardneſs was very painful to her when it was but gently preſſed down.

Another Hiſtory.

How you may know a Wen from a *Cancer*.

But alſo ſome few years agon, I, being called to the Cure of a very honeſt Woman, which was troubled with the ſame diſeaſe, ſtrongly withſtood the Phyſicians and Chirurgeons, affirming it to be a *Cancer*, for the tumor had taken no deep root, the habit of the part was not changed from the native colour, the Veins about it were not ſwollen, neither was there any other convincing ſign of a *Cancer*. For this ſame Woman had her Courſes at their due and uſual time, and was well-liking, and had a good colour in her face and body, was free from all ſort of pain, unleſs when you preſſed down the part affected. Beſides, thenceforward the Tumor grew not at all, no other evil accident befel her, yea verily ſhe lives merrily, and well both in body and mind.

CHAP. XXI.

Of a Ganglion *more particularly ſo called.*

What a *Ganglion* properly ſo called is.

The cauſes.

THere are alſo certain ſmall Tumors of the kind of *Dupiæ*, or Wens, which grow on divers parts of the body, but chiefly on the wriſts of the hands, and ankles of the feet, being called by a more particular name *Ganglia*; they appear on the top of the skin, neither do they ever lie deep. The cauſe of them is either the imbecillity of a nerve or tendon, got by wreſting, extenſion, a blow, labour, or other ſuch like cauſe. Through which occaſion the alimentary juice which

flowed to theſe parts, ſeeing it can neither be concocted, nor aſſimilated into the proper ſubſtance, is converted into an humour of the like nature cold, and groſs, which in continuance of time heaping it ſelf up by little and little about the Fibers, and the very ſubſtance of the tendon concretes into a tumor.

What *Ganglia* may not be cured with Iron Inſtruments.

It is not fit to uſe any Iron Inſtrument to theſe *Ganglia* which poſſeſs the tendons and joints, but onely apply *Ammoniacum* and *Galbanum* diſſolved in Vinegar and *Aqua Vitæ:* as, ℞ *Gummi ammon. & ſagapeni in aqua vitæ diſſolutorum, an.* ʒ i. *coquantur ſuper cineres calidos ad formam emplaſtri, ſub finem adde ſulphuris vivi ſubtiliter pulveriſati* ʒ ß. *fiat empl. ad uſum.* Alſo the Emplaiſter of *Vigo* with double *Mercury* would be good for the ſame purpoſe.

The tumor ſoftned by theſe remedies, muſt be wrought, rubbed, or preſſed, ſo long, until the bladder or bag be broken under your finger, which I have divers times done; then it will be expedient preſently to apply and bind hard thereunto a plate of Lead rubbed with Quickſilver, which may waſte and conſume the remainder of the tumor.

Sometimes there are *Ganglia* ſeen hanging by a ſmall root, as it were a ſtring; wherefore they muſt be tied with a ſtring at the root, and every day twitched harder and harder, till ſuch time as they fall off. The reſt of the cure may be eaſily performed by the common rules of Art.

CHAP. XXII.

Of the Strumæ *or* Scrophulæ, *that is, the Kings Evil.*

What the *Scrophulæ* or Kings Evil is.

THe *Scrophulæ* are œdematous tumors ariſing in the glandulous parts, as the Breſts, Arm-holes Groins, but chiefly in the glandules of the neck. They appear either one or many, according to the quantity of that matter from whence they proceed, commonly contained in their proper ciſt, a bag, as *Atheromaes*, *Steatomaes*, and *Melicerides* are.

Their material cauſe. How they differ from other glandulous tumors.

They are made of a groſs, cold, viſcid, and phlegmatick matter with ſome admixture of Melancholy. They differ from other glandulous tumors; firſt in number, for moſt uſually there appear many of them united together, ſpringing from ſomewhat a deeper root than glandulous tumors do; ſome of them are moveable, otherſome woven with the neighbouring nerves, remaining unremoveable.

Ganglia appear fewer in number, and are without pain; but *Scrophulæ* often-times are painful, eſpecially when they wax hot by putrefaction; ſo that ſometimes they degenerate into cancerous Ulcers, not to be touched by Inſtruments nor acrid Medicins.

Phlegmatick, melancholick, and gluttonous perſons, and ſuch as are accuſtomed to feed on cold and moiſt nouriſhments, as fiſh and cold water, and lead a ſedentary and idle life, are ſubject to the *Scrophulæ*.

Their cure by Diet.

They are cured by a moſt ſlender Diet, for ſo the native heat by want of nouriſhment turned upon the material cauſe of ſuch like tumors, waſtes it.

Emollient and reſolving Medicins.

And they are cured by purging off the ſuperfluous humours, and alſo by application of emollient reſolving and ſuppurating Topick Medicins, after this following manner. ℞ *Mucaginis alth. fænugr. & ficum ping. an.* ʒ ij. *olei liliorum, & chamæm. an.* ʒ i. *pinguedinis anſeris & axungiæ porci* ʒ ß. *Terebinth. Ven.* ʒ i ß. *ammoniaci, & galbani in aceto diſſolutorum, an.* ʒ i. *ceræ novæ quantum ſatis, fiat cerotum ſecundum artem ad modum Diachyli magni.*

The Ointment for the *French* Diſeaſe, and the Emplaiſter of *Vigo* with *Mercury*, are excellent for this purpoſe, eſpecially, if we continue ſo long until the Patient come to Salivation, for ſo nature will disburden it ſelf of the humour generating the *Scrophulæ*, which I have ſometimes tried with happy ſucceſs. ℞ *Emplaſtri diachyl. alb. & mag. ceroti æſopi deſcriptionis Philagrii, an.* ʒ ij. *Terebinth. claræ* ʒ i. *olei liliorum parum, fiat emplaſtrum ſatis molle.* But if the *Scrophulæ* cannot by this means be reſolved,

Suppuratives.

but, as it oft-times happens, tend to ſuppuration, you muſt uſe Suppuratives, as ℞ *Rad. alth. & lilior. an.* ʒ iij. *coquantur in aqua communi, piſtentur, trajectis adde capitum alliorum ſub cineribus coctorum* ʒ iij. *olei liliorum, & ping. anſeris & anatis, an.* ʒ i. ß. *farinæ ſeminis lini quantum ſatis; formetur cataplaſma.*

A Note to be obſerved in opening *Scrophulous* tumors.

Here we muſt admoniſh the Chirurgeon that he open not the *Scrophulæ*, before that all the contained humour be fully and perfectly turned into *pus*, or matter, otherwiſe the reſidue of the humour will remain crude, and will ſcarce in a long time be brought to maturation; which precept muſt be principally obſerved in the *Scrophulæ*, and alſo ſometimes in other abſceſſes, which come to ſuppuration.

Natural heat the cauſe of ſuppuration.

For we muſt not, as ſoon as any portion of the contained humours appear converted into *pus*, procure and haſten the apertion. For that portion of the ſuppurated humour cauſes the reſt ſooner to turn into *pus*, which you may obſerve in inanimate bodies. For fruits which begin to periſh and rot, unleſs we preſently cut away the putrifying part, the reſidue quickly becomes rotten: there is alſo another reaſon, the native heat is the efficient cauſe of ſuppuration; it therefore (the Sore being opened) diminiſhed and weakned by reaſon of the diſſipation of the ſpirits, evacuated together with the humour, will cauſe the remaining portion of the humour not to ſuppurate, or that very hardly, and with much difficulty. Yet if the tumefied part be ſubject, by its own nature, to corruption and putrefaction, as the Fundament; if the contained matter be malign, or critical, it will be far better to haſten the apertion.

The Chirurgical manner of curing *Scrophulæ*.

There is alſo another way of curing the *Scrophulæ*, which is performed by the hand. For ſuch as are in the neck, and have no deep roots, by making Inciſion through the skin, are pulled and cut away from thoſe parts with which they were intangled. But in the performance of this work, we take eſpecial care that we do not violate or hurt with our inſtrument the Jugular Veins, the ſleepy Arteries, or recurrent Nerves. If at any time there be danger of any great efflux of bloud, after they are plucked from the skin, they muſt be tied at their roots, by thruſting through a needle and thred, and then by binding the thred ſtrait on both ſides, that ſo bound they may fall off by themſelves by little without any danger. The remainder of the Cure may be performed according to the common rules of Art.

CHAP.

CHAP. XXIII.

Of the Fever which happens upon an œdematous Tumour.

HAving ſhewed all the differences of œdematous Tumors, it remains, that we briefly treat of the Symptomatical Fever, which is ſometimes ſeen to happen upon them. This therefore retaining the motion of the humour by which it is made, is commonly of that kind, which they name intermitting Quotidians. Now the fit of a Quotidian comes every day, and in that repetition continues the ſpace of eighteen hours; the reſidue of the day it hath manifeſt intermiſſion. How an intermitting Quotidian happens upon œdematous tumors.

The primitive cauſes of this Fever, are the coldneſs and humidity of the air encompaſſing us, the long uſe of cold meats and drinks, and of all ſuch things as are eaſily corrupted, as Summer Fruits, crude Fiſhes, and laſtly, the omiſſion of our accuſtomed exerciſe. The cauſe of a Quotidian Fever.

The antecedent cauſes are, a great repletion of humors, and theſe eſpecially phlegmatick. The conjunct cauſe is Phlegm putrefying in the habit of the body, and firſt region thereof without the great Veins.

The ſigns of this Fever are drawn from three things; as firſt Natural, for this Fever or Ague chiefly ſeizes upon thoſe which are of a cold and moiſt temper, as Old Men, Women, Children, Eunuchs, becauſe they have abundance of Phlegm; and it invades Old Men by its own nature, becauſe their native heat being weak, they cannot convert their meats, then taken in a ſmall quantity, into laudable bloud, and the ſubſtance of the parts. But it takes children by accident, not of it ſelf, and their own nature, for Children are hot and moiſt; but by reaſon of their voracity or greedineſs, and their violent, inordinate, and continual motion after their plentiful feeding, they heap up a great quantity of crude humours, fit matter for this Fever, whereby it comes to paſs, that fat children are chiefly troubled with this kind of Fever, becauſe they have the paſſages of their bodies ſtrait and ſtopped, or becauſe they are ſubject to Worms, they are troubled with pain, by corruption of their meat; whence ariſeth a hot diſtemper by putrefaction, and the elevation of putrid vapours, by which the heart being moleſted, is eaſily taken by this kind of Fever. The Signs. How children come to be ſubject to Quotidian Fevers.

From things not Natural, the ſigns of this Fever are thus drawn. It chiefly takes one in Winter, and the Spring, in a cold and moiſt region, in a ſedentary and idle life, by the uſe of meats, not onely cold and moiſt, but alſo hot and dry, if they be devoured in ſuch plenty, that they overwhelm the native heat.

For thus Wine, although it be by faculty and Nature hot and dry, yet taken too immoderately, it accumulates phlegmatick humours, and cauſes cold Diſeaſes. Therefore Drunkenneſs, Gluttony, Crudity, Baths, and Exerciſes preſently after meat, being they draw the meat as yet crude into the Body and Veins; and to conclude, all things cauſing much phlegm in us, may beget a Quotidian Fever. But by things contrary to Nature, becauſe this Fever uſually follows cold Diſeaſes, the Center, Circumference and Habit of the Body being refrigerated. How phlegmatick humors happen to be generated by hot and dry meats.

The ſymptoms of this Fever are, the pain of the mouth of the Stomach, becauſe that phlegm is commonly heaped up in this place, whence follows a vomiting or caſting up of phlegm; the Face looks pale, and the mouth is without any thirſt, often-times in the fit it ſelf; becauſe the Stomach flowing with phlegm, the watery and thinner portion thereof continually flows up into the mouth and tongue, by the continuity of the inner coat of the ventricle common to the gullet and mouth. The Symptoms of Quotidians.

It takes one with coldneſs of the extreme parts, a ſmall and deep pulſe, which notwithſtanding in the vigour of the Fit, becomes more ſtrong, great, full, and quick. Juſt after the ſame manner, as the heat of this Fever at the firſt touch appears mild, gentle, moiſt, and vaporous; but at the length it is felt more acrid, no otherwiſe than fire kindled in green wood, which is ſmall, weak, and ſmoky at the firſt; but at length when the moiſture, being overcome, doth no more hinder its action, it burns and flames freely. The manner of the pulſe and heat in a Quotidian.

The Patients are freed from their fits with ſmall ſweats, which at the firſt Fits break forth very ſparingly, but more plentifully when the *Criſis* is at hand; the Urin at the firſt is pale and thick, and ſometimes thin, that is, when there is obſtruction. But when the matter is concoct, as in the ſtate, it is red: if at the beginning of the Fit they caſt up any quantity of phlegm by vomit, and that Fit be determinated in a plentiful ſweat, it ſhews the Fever will not long laſt; for it argues the ſtrength of Nature, the yielding and tenuity of the matter flying up, and the excretion of the conjunct cauſe of the Fever. Critical Sweats. The Urin.

A Quotidian Fever is commonly long, becauſe the Phlegmatick humor being cold and moiſt by Nature, is heavy and unapt for motion; neither is it without fear of a greater Diſeaſe, becauſe oft-times it changes into a burning or Quartan Fever, eſpecially if it be bred of ſalt Phlegm, for ſaltneſs hath affinity with bitterneſs, wherefore by aduſtion it eaſily degenerates into it, ſo that, it need not ſeem very ſtrange if ſalt phlegm by aduſtion turn into choler, or melancholy. Thoſe who recover of a Quotidian Fever, have their digeſtive faculty very weak; wherefore they muſt not be nouriſhed with ſtore of meats, nor with ſuch as are hard to digeſt. In a Quotidian, the whole body is filled with crude humors, whereby it comes to paſs, that this Fever oft-times laſts ſixty days. But have a care you be not deceived, and take a double Tertian for a Quotidian, becauſe it takes the Patient every day as a Quotidian doth. Verily it will be very eaſie to diſtinguiſh theſe Fevers by the kind of the humour, and the propriety of the ſymptoms and accidents; beſides, Quotidian commonly take one in the evening, or the midſt of the night, as then when our bodies are refrigerated by the coldneſs of the air cauſed by the abſence of the Sun. Wherefore then the cold humours are moved in us, which were bridled a little before by the preſence and heat of the Sun. But, on the contrary, double Tertians take one about Noon. The ſhortneſs and gentleneſs of the Fit, the plentiful ſweat breaking forth, the matter being concocted, cauſes us to think the Quotidian ſhort and ſalutary. Why Quotidians are oft-times long. Into what Diſeaſes a Quartan uſually changes. How to diſtinguiſh a Quotidian from a double Tertian.

The Cure is performed by two means; to wit, Diet, and Pharmacy. Let the Diet be ſlender and attenuating, let the Patient breathe in a clear air moderately hot and dry; let his meats be Diet.

bread

bread well baked, Cock or Chicken broths, in which have been boiled the roots of Parſley, Sorrel and the like.

When the uſe of ſpiced and ſalted meats are fit.

Neither at ſometimes will the uſe of hot meats, as thoſe which are ſpiced and ſalted, be unprofitable, eſpecially to ſuch as have their ſtomach and liver much cooled. Let him eat Chickens, Mutton, Partridge, and ſmall Birds, River-fiſhes, and ſuch as live in ſtony Waters, fried or boiled, rear Eggs, and ſuch like. Theſe Fruits are alſo good for him, Raiſins, ſtewed Prunes, Almonds and Dates. Let his drink be ſmall white Wine mixed with boiled Water. Moderate Exerciſes will be good, as alſo frictions of the whole Body: Sleep taken at a fitting time, and proportioned to waking, ſo that the time of Sleep fall not upon the time of the Fit, for then it hurts very much, for calling the heat to the inner parts, it doubles the raging of the feveriſh heat inwardly in the Bowels.

When Sleep is hurtful.

For the Paſſions of the Mind, the Patient muſt be merry, and comforted with a hope ſhortly to recover his health. It ſeems not amiſs to ſome, at the coming of the Fit to put the feet and legs into hot Water, in which Chamomil, Dill, Melilot, Marjerom, Sage, and Roſemary have been boiled.

Medicins.

The Medicins ſhall be ſuch Syrups as are called digeſtive and aperitive, as Syrup of Wormwood, Mints, of the five opening Roots, *Oxymel* with a decoction of Chamomil, Calamint, Melilot, Dill and the like, or with common decoctions. The Purgatives ſhall be *Diaphœnicon*, *Electuarium*, *Diacarthami*, *Hiera picra*, Agarick, Turbith, of which you ſhall make Potions with the Waters of Mints, Balm, Hyſſop, Sage, Fennel, Endive, or the like; *Pilulæ aureæ* are alſo good. Theſe Purgatives ſhall ſometimes be given in form of a Bole with Sugar, as the Phyſitian being preſent ſhall think moſt fit and agreeable to the nature of the Patient.

Care muſt be had of the Stomach. Vomits.

About the ſtate of the Diſeaſe, you muſt have a care of the Stomach, and principally of the mouth thereof, as being the chief ſeat of Phlegm; wherefore it will be good to anoint it every other day with Oil of Chamomil mixed with a little white Wine, as alſo to unlade it by taking a Vomit of the Juice of Radiſh, and much *Oxymel*, or with the decoction of the Seeds and Roots of *Aſarum* and Chamomil; and Syrup of Vinegar will be very good, eſpecially at the beginning of the Fit, when Nature and the humours begin to move; for an inveterate Quotidian, though you can cure it by no other remedy, nothing is thought to conduce ſo much as one dram of old Treacle taken with Sugar in form of a Bole, or to drink it diſſolved in *Aqua vitæ*.

The uſe of Treacle in an inveterate Quotidian.

CHAP. XXIV.

Of a Scirrhus, *or an hard Tumor proceeding of Melancholy.*

What a true and legitimate *Scirrhus* is. What an illegitimate *Scirrhus* is.

HAving ſhewed the nature of Tumors cauſed by Bloud, Choler, and Phlegm, it remains we ſpeak of theſe, which are bred of a Melancholick humour: of theſe there are ſaid to be four differences. The firſt is of a true and legitimate *Scirrhus*, that is, of an hard Tumor endued with little ſenſe, and ſo commonly without pain, generated of a natural melancholick humour. The ſecond is, of an illegitimate *Scirrhus*, that is of an hard Tumor inſenſible, and without pain, of a melancholick humour concrete by too much reſolving and refrigerating. The third is of a cancrous *Scirrhus* bred by the corruption and aduſtion of the melancholick humour. The fourth of a phlegmonous, Eryſipelous or Oedematous *Scirrhus*, cauſed by Melancholy mixed with ſome other humor. The cauſe of all theſe kinds of Tumors is a groſs, tough, and tenacious humor concrete in any part. But the generation of ſuch a humor in the body happens either of an ill and irregular diet, or of the unnatural affects of the Liver or Spleen, as obſtruction; or by ſuppreſſion of the *Hæmorrhoids*, or Courſes.

The Signs.

The ſigns are hardneſs, renitency, a blackiſh colour, and a dilation of the Veins of the affected part with blackiſhneſs, by reaſon of the abundance of the groſs humour. The illegitimate, or baſtard *Scirrhus* which is wholly without pain and ſenſe, and alſo the cancerous, admit no cure; and the true legitimate ſcarce yield to any.

Prognoſtick.

Thoſe which are brought to ſuppuration, eaſily turn into Cancers and Fiſtulaes; theſe tumors though in the beginning they appear little, yet in proceſs of time they grow to a great bigneſs.

CHAP. XXV.

Of the Cure of a Scirrhus.

Diet.

THe Cure of a *Scirrhus* chiefly conſiſts of three heads. Firſt, The Phyſician ſhall preſcribe a convenient Diet, that is, ſober and moderate feeding, tending to humidity, and indifferent heat; for his manner of life, let it be quiet and free from all perturbation of anger, grief and ſadneſs, as alſo abhorring the uſe of Venery. The ſecond is placed in the evacuation of the antecedent matter, as by Phlebotomy, if need require, and by purging, by procuring the *Hæmorrhoids* in men, and the Courſes in Women; let Purgations be preſcribed of *Diacatholicon*, *Hiera*, *Diaſenna*, Polypody, *Epithymum*, according to the mind of the learned Phyſician. The third conſiſts in the convenient uſe of Topick Medicins, that is, emollient at the beginning, and then preſently reſolving, or rather ſuch as are mixed both of reſolving and emollient faculties, as *Galen* teaches; for by the uſe of onely emollient things there is danger of putrefaction, and a *Cancer*; and onely of reſolving there is fear of concretion, the ſubtiler part being reſolved, and the groſſer ſubſiding.

Lib. 2. ad. Glauconem.

Emollients.

The emollient ſhall be thus: ℞ *Rad. althæ. lib. ſ. rad. liliorum* ℥ iij. *coquantur in aqua com. piſtentur, trajiciantur per ſetaceum, addendo olei chamæm. & lilior. an.* ℥ ij. *æſipi humid.* ℥ ſ. *emplaſtri diachyl. alb. cum oleo liliorum diſſoluti* ℥ iij. *ceræ albæ quantum ſit ſatis, fiat cerotum.* Or, ℞ *Gummi ammoniaci, galb. bdellii, ſtyracis liquidæ in aceto diſſolutorum, an.* ℥ i. *diachyl. mag.* ℥ i. ſ. *olei liliorum, & axungiæ anſeris.*

anſeris, an. ℥ i. *ceroti æſip. deſcriptione Philagr.* ℥ ij. *liqueſcant omnia ſimul, ceræ quantum ſit ſatis, ut inde fiat cerotum ſatis molle.* When you have ſufficiently uſed emollient things, fume the tumour with ſtrong Vinegar and *Aqua Vitæ* poured upon a piece of a Milſtone, Flint, or Brick, heated very hot; for ſo the mollified humour will be rarified, attenuated, and reſolved; then ſome while after renew your emollients, and then again apply your reſolvers to waſte that which remains, which could not be performed together, and at once; for thus *Galen* healed a Scirrhus in *Circilius* his Son. Goats dung is very good to diſcuſs Scirrhous tumours; but the Emplaiſter of *Vigo* with a double of *Mercury* is effectual above the reſt, as that which mollifies, reſolves, and waſtes, all tumours of this kind.

Lib. ad Glauc. The efficacy of the Empl. of *Vigo* with *Mercury.*

CHAP. XXVI.

Of a Cancer *already generated.*

A *Cancer* is an hard tumour rough and unequal, round, immoveable, of an aſh or livid colour, horrid by reaſon of the Veins on every ſide, ſwollen with black bloud, and ſpread abroad to the ſimilitude of the ſtretched-out legs and claws of a Crab. It is a tumour hard to be known at the firſt, as that which ſcarce equals the bigneſs of a Chick, or *Cicer:* after a little time it will come to the greatneſs of a Haſel-nut, unleſs peradventure provoked by ſomewhat too acrid Medicins

What a *Cancer* is.

The Figure of the Crab, *called* Cancer *in Latine.*



it ſuddenly increaſe; being grown bigger, according to the meaſure of the increaſe, it torments the Patient with pricking pain, with acrid heat, the groſs bloud reſiding in the Veins growing hot, and inferring a ſenſe like the pricking of Needles, from which notwithſtanding the Patient hath oft-times ſome reſt. But becauſe this kind of tumour by the Veins extended and ſpread about it like claws and feet, being of a livid and aſh-colour, aſſociated with a roughneſs of the skin and tenacity of the humour, repreſents, as it were, the toothed claws of the Crab, therefore I thought it not amiſs to inſert (as before) the Figure of the Crab, that ſo the reaſon both of the name and thing might be more perſpicuous.

The nature of the pain.

The reaſon of the name.

CHAP. XXVII.

Of the Cauſes, Kinds, and Prognoſticks of a Cancer.

HEre we acknowledge two Cauſes of a *Cancer*, the antecedent and conjunct. The antecedent cauſe depends upon the default of irregular diet, generating and heaping up groſs and feculent bloud; by the morbifick affection of the Liver diſpoſed to the generation of that bloud, by the infirmity or weakneſs of the Spleen in attracting and purging the bloud, by the ſuppreſſion of the Courſes, or Hæmorrhoids, or any ſuch accuſtomed evacuation. The conjunct cauſe is that groſs and melancholick humour ſticking and ſhut in the affected part, as in a ſtrait. That melancholick bloud which is more mild and leſs malign, onely increaſed by a degree of more fervid heat, breeds a not ulcerated *Cancer*, but the more malign and acrid cauſes, an ulcerated. For ſo the humour which generateth Carbuncles, when it hath acquired great heat, acrimony, and malignity, corrodes, and ulcerates the part upon which it alights. A *Cancer* is made more fierce and raging by meats inflaming the bloud, by perturbations of the mind, anger, heat, and Medicins too acrid, oily, and emplaſtick, unfitly applied, both for time and place.

The cauſes of a *Cancer.*

The cauſes of a not ulcerated *Cancer.*

Amongſt the ſorts or kinds of *Cancers*, there be two chiefly eminent, that is, the ulcerated or manifeſt *Cancer*, and the not ulcerated or occult. But of *Cancers* ſome poſſeſs the internal parts, as the Guts, Womb, Fundament; others the external, as the Breſts; alſo there is a recent, or late bred *Cancer*, and alſo an inveterate one. There is one ſmall, another great, one raging and malign, another more mild. Every *Cancer* is held almoſt incurable, or very difficult to be cured, for it is a Diſeaſe altogether malign, to wit, a particular Leproſie. Therefore, ſaith *Actius*, a *Cancer* is not eaſily ſtaid, until it hath eaten even to the innermoſt of the part which it poſſeſſes. It invades Women

The ſorts and differences of *Cancers.*

Actius lib. 6. The parts moſt ſubject to *Cancers.*

Women more frequently than Men, and thoſe parts which are lax, rare, fungous, and glandulous, and therefore opportune to receive a defluxion of a groſs humour, ſuch are the Breſts, and all the emunctories of the noble parts. When it poſſeſſes the Breſt it often cauſes inflammation to the Armholes, and ſends the ſwelling ever to the glandules thereof, whereupon the Patients do complain that a pricking pain even pierces to their hearts. But this ſame pain alſo runs to the clavicles, and even to the inner ſide of the ſhoulder-blades and blades. When it is increaſed, and covers the noble parts, it admits no cure but by the hand; but in decayed bodies, whoſe ſtrength fail, eſpecially if the *Cancers* be inveterate, we muſt not attempt the Cure, neither with Inſtrument, nor with Fire, neither by too acrid Medins, as potential Cauteries; but we muſt onely ſeek to keep them from growing more violent, and from ſpreading further, by gentle Medicins, and a palliative Cure. For thus, many troubled with a *Cancer*, have attained even to old age. Therefore *Hippocrates* admoniſhes us, that it is better not to cure occult or hidden *Cancers*, for the Patients cured (ſaith he) do quickly die, but ſuch as are not cured live longer.

What *Cancers* one muſt not undertake truly to cure.

CHAP. XXVIII.

Of the Cure of a Cancer *beginning, and not yet ulcerated.*

A *Cancer* beginning, is oft hindered from increaſing, before it faſten its roots; but when it hath once increaſed, it admits no cure but by iron, as that which contemns by reaſon of the malignity and contumacy, the force of all Medicins. *Galen* affirms he cured a *Cancer* not ulcerated. Now that Cure is performed by Medicins, purging Melancholy; by Phlebotomy, when the ſtrength and age of the Patient may well endure it; by ſhunning all things which may breed ill and fæculent bloud. The diſtemper of the Liver muſt firſt be corrected, the Spleen, as alſo the part affected; in Men the Hæmorrhoides, in Women their Courſes muſt be procured.

Lib. 2. ad Glauc.

Therefore thick and muddy Wines, Vinegar, brown Bread, cold Herbs, old Cheeſe, old and ſalted Fleſh, Beef, Veniſon, Goat, Hare, Garlick, Onions and Muſtard; and laſtly, all acrid, acid, and other ſalt things, which may by any means incraſſate the bloud, and inflame the humours, muſt be eſchewed. A cooling and humecting diet muſt be preſcribed; Faſting eſchewed, as alſo Watchings; immoderate Labours, Sorrow, Cares, and Mournings; let him uſe Ptiſans, and in his Broths boil Mallows, Spinace, Lettuce, Sorrel, Purſlain, Succory, Hops, Violets, Borrage and the four cold ſeeds. But let him feed on Mutton, Veal, Kid, Capon, Pullet, young Hares, Partridges, Fiſhes of Stony Rivers, rear Eggs; and uſe white Wine but moderately for his drink.

Diet.

The part affected with the *Cancer* muſt be gently handled, and not over-burdened by over-hard or heavy things, or by too ſolid or fat Emplaiſters; on the contrary, gentle and mitigating Medicins muſt be uſed; applying alſo at certain times ſuch things as reſiſt venom, or poiſon, as Treacle and Mithridate. Aſſes Milk is exceeding fit to aſſwage the acrimony of the cancerous humour. Therefore it muſt not onely be taken inwardly, but alſo applied outwardly to the cancerous Ulcer, making thereof a fomentation.

How to handle the cancerous part.
Antidotes.
Aſſes Milk.

CHAP. XXIX.

Of the Cure of an ulcerated Cancer.

AN Ulcerated *Cancer* hath many ſigns common with that which is not ulcerated, as the roundneſs of the tumour, the inequality, roughneſs, and pain; to the judgment of the eye the tumour ſeems ſoft, but it is hard to the touch; the Ulcer is filthy, with lips, thick, ſwollen, hard, knotty, turned out, and ſtanding up, having a horrid aſpect, and caſting forth ichorous, filthy, and Carion-like filth, ſometimes black, ſometimes mixed with rotten filth, and otherwhiles with much bloud. This kind of Ulcer is malign, rebellious and untractable, as that which contemns mild remedies, and becomes more fierce by acrid and ſtrong; the pain, fever, and all the ſymptoms being increaſed, from whence the powers are dejected, the waſting and conſumption of the body follows, and laſtly, death. Yet if it be ſmall, and in a part which may ſuffer amputation, the body being firſt purged, and bloud drawn, the ſtrength of the Patient not diſſuading, it will be convenient to uſe the hand, and to take hold of, and cut away whatſoever is corrupt, even to the quick, that no fear of contagion may remain or be left behind. The amputation finiſhed, the bloud muſt not be preſently ſtopped, but permitted to flow out in ſome meaſure, yea verily preſſed forth all about it, that ſo the Veins ſwollen with black and melancholy bloud may be disburdened. When you have taken a ſufficient quantity of bloud, the place muſt be ſeared with an actual cautery. For that will ſtrengthen the part affected, draw forth the venenate quality, and alſo ſtay the defluxion. Then muſt you apply mitigating Medicins, and procure the falling away of the Eſchar. To conclude, that which remains muſt be performed according to the cure of other Ulcers. Now we know and underſtand, that all the *Cancer* is cut away, and all the malignity thereof extinct, when the Ulcer caſts forth laudable matter, when that good fleſh begins to grow by little and little, like to the grains of a Pomegranate, the pricking pain, and all the ſymptoms being aſſuaged. Yet the cure of an ulcerated *Cancer* which ſhall poſſeſs the lips, may be more happily and mildly performed, no cauſtick Medicin being applied after ſection, ſo alſo that ſcarce any deformity will be left when it is cicatrized. Which new and never formerly tried, or written of way, as far as I know, I found and performed in a man of fifty years old. Doctor *John Altine*, a moſt learned Phyſitian being called to Counſel, *James Guillemeau*, and Maſter *Euſtachius* the King's Chi-

The Signs.

How and where a *Cancer* may be cut away.
What to be obſerved in cutting away a *Cancer*.
The benefit of applying a cautery after amputation of the *Cancer*.
Signs that a *Cancer* is well taken away.

Chirurgeons, and *John le Jeune* the Duke of *Guiſe* his moſt worthy Chirurgeon being preſent.

A new and obſervable way of taking away a *Cancer* from the lip.

The way is this; The *Cancer* muſt be thruſt through the lips on both ſides, above and below with a needle and thred, that ſo you may rule and govern the *Cancer* with your left hand, by the benefit of the thred (leſt any portion thereof ſhould ſcape the inſtrument in cutting) and then with your Sizers in the right hand, you may cut it off all at once; yet it muſt be ſo done, that ſome ſubſtance of the inner part of the lip which is next to the teeth may remain (if ſo be that the *Cancer* be not grown quite through) which may ſerve, as it were, for a foundation to generate fleſh to fill up the hollowneſs again. Then when it hath bled ſufficiently, the ſides and brinks of the Wound muſt be ſcarified on the right and left ſides, within and without, with ſomewhat a deep ſcarification, that ſo (when we would draw together the ſides and lips of the Wound, by that manner of ſtitching which is uſed in an hare-lip) we may have the fleſh more pliant and tractable to the needle and thred. The reſidue of the Cure muſt be performed juſt after the ſame manner as we uſe in hare-lips, of which we ſhall treat hereafter.

CHAP. XXX.

Of the Topick Medicins to be applied to an ulcerated and not ulcerated Cancer.

Repelling Medicins.

WE at the beginning uſe repercuſſive Medicins, ſuch as are the juices of Nightſhade, Plantain, Henbane, Lettuce, Sorrel, Houſleek, Water, Lentil, or Ducks-meat, Knot-graſs, Pomegranates, and the like. Alſo *oleum roſarum Omphacinum*, the powders of Sumach, Berberies, Litharge, Ceruſe, Burnt-lead, *Tutia*, Quick-ſilver, and the like. Of which you may compoſe Fomentations, Liniments, Ointments, Cataplaſms, Emplaiſters. *Emplaſtrum Diacalcitheos* diſſolved with juice of Nightſhade, and Oil of Roſes is very fit for not ulcerated *Cancers*. *Pompholix*, or *Tutia* waſhed in juice of Nightſhade, or Plantain, is very good for ulcerated *Cancers*. Beſides, this following Medicin is very commendable.

℞ *Litharg. & ceruſ. an.* ℥ i. *terantur in mortario plumb. cum oleo roſar. donec reducantur ad conſiſtentiam linimenti vel unguenti*; and there may be uſe of a reſolving and repercuſſive Ointment, as, ℞ *plumbi uſti loti pomphol. thuris an.* ʒ ij. ℈ *abſinth. pontic.* ʒ ℈. *olei roſarum* ℥ iij. *ceræ* ʒ vj. *ſucci ſolani, quantum ſufficit ad unguenti craſſitudinem.* They very much commend *Theodoricks* Emplaiſter to aſſwage the pain of ulcerated *Cancers*.

Theodoricks Emplaiſters.

℞ *Olei roſ. ceræ alb. an.* ʒ ij. ℈. *ſucci granat. & ſolani, an* ʒ ij. *ceruſæ lotæ* ℥ i. *plumbi uſti, loti, & tuthiæ præpar. an.* ℥ ℈. *thuris maſtich. an.* ʒ ij. *fiat empl. molle.* This following Ointment I have often uſed with good ſucceſs.

℞ *Theriac. veter.* ʒ i. *ſucci cancrorum* ℥ ß. *ſucci lactucæ & olei roſar. an.* ℥ i. ß. *vitel. ovorum ſub cinerib. cocti.* ij. *camphor.* ʒ ß. *piſtentur omnia in mortario plumb. & fiat unguentum.*

℞ *Spum. argent. axungiæ porci recentis ceræ alb. an.* ℔ ß. *olei boni* ℥ viij. *vitel. ovorum aſſat.* iv. *fiat ununguent. ſervetur uſui.* And when you will uſe it, mix it with a little Ointment of Roſes. I have alſo mitigated great pain by applying Leaches to an ulcerated *Cancer*, in that part where the torment was moſt vehement, by disburdening the part of ſome portion of the malign humour; which ſame thing I have done by application of young Whelps, or Pigeons, or Chickens, cut long-ways, and preſently applied to the ulcer, and now and then changed as ſoon as their heat ſeems diſſolved; and others applied for their natural heat in an Anodyne or mitigating Medicin. *John Baptiſta Theodoſius* in his Epiſtles writes, that a cataplaſm of the herb *Eryſimum*, or Cadlock, being beaten, is very good to be applied to a *Cancer* not ulcerated; but if the *Cancer* be ulcerated, he boils this ſame herb in *Hydromel*, and ſo by injection and lotions cleanſes the ulcer and mitigates the pain. If the *Cancer* affect the Womb, the Patient feels the pricking of the pain in the groin above the *pecten*, and in the Kidneys, and is often troubled with a difficulty of making water; but when it is ulcerated, it pours forth filth, or matter, exceeding ſtinking and carion-like, and that in great plenty, the filthy vapour of which carried up to the heart, and brain, cauſes often ſwounding. Now to mitigate the pains of ſuch like places, the following Medicins are of good uſe.

Leaches.

The application of Whelps, Chickens, &c.

Epiſt. 21.

The Eſtate of *Eryſimum*.

The ſigns of the *Cancer* in the Womb.

℞ *Mucag. ſemin. lini, fœnugr. extracti. in aqua roſar. & plantaginis quod ſatis eſt.* Of this being warm make a Fomentation.

℞ *Rad. Althææ* ℔ ß. *coquatur in hydromelite, piſtetur & trajiciatur, addendo ol. roſar. parum, fiat Cataplaſma.* Alſo you ſhall make divers peſſaries according to the different kind of pain; alſo make injections of the juice of Plantain, Knot-graſs, Lettuce, Purſlain, mixed together, and agitated or laboured in a Leaden Mortar with a little Oil of Roſes; for this kind of Medicin is commended by *Galen* in every kind of ulcerated *Cancers*. Alſo this following Water is very profitable, and often proved by me. ℞ *Stercoris bubuli* ℔ iv. *herbæ Roberti plantag. ſempervivi, hyoſcyami, portulac. lactuc. endiv. an. m.* i. *cancros fluviatiles, num.* xij. Let them be all beaten together and diſtilled in a Leaden Alembick, keep the liquor for uſe, and with it make often injection into the part, or if the ſite of the part will permit, let the cancerous ulcers be waſhed therewith, and pledgets of lint ſteeped therein, be applied and renewed ever and anon; for ſo the acrimony and force of the inflammation is retunded, and the pain aſſwaged. *Galen* beats into powder River Crabs burnt; the powder mixed with Ointment of Roſes is moſt profitably applied upon lint to cancerous Ulcers.

Lib. 9. Simpl.

Lib. 4. de comp. med. ſecundum gen.

It will be very convenient to put into the neck of the Womb the following Inſtrument made of Gold or Silver, whereby the cancerous filth may have free and ſafe paſſage forth, and the filthy and putredinous Vapours may more eaſily breathe forth. Therefore let it be hollow quite through, ſome five or ſix fingers long, and about the bigneſs of ones thumb, at the upper end perforated with many holes whereby the filth may have paſſage forth. Let the outer or lower end be ſome two fingers thick in the circumference, make it with a neat ſpring, that may hold that end open,

open, more or leſs, according to the Phyſicians mind; let there be two ſtrings or laces put unto it, by which being tied before and behind to the rowler, with which the Woman ſhall girt her loins, the Device may be kept from falling, as you may ſee in the following Figure.

A Vent made like a Peſſary, for the Womb affected with a cancerous Ulcer.



A *Shews the upper end perforated with five or ſix holes.*
B *The lower end.*
C *That part of the end which is opened by the ſtring, which is marked with the letter* D.
E E *The ſtrings or laces.*

Lib. 6. ſimp. Plates of Lead A Hiſtory.

Neither is that remedy for not ulcerated *Cancers* to be contemned, which conſiſts of a Plate of Lead beſmeared with Quick-ſilver; for *Galen* himſelf teſtifies that Lead is a good Medicin for malign and inveterate Ulcers. But *Guido Cauliacenſis* is a witneſs of ancient credit and learning, that ſuch Plates of Lead rubbed over with Quick-ſilver, to ſuch malign Ulcers as contemn the force of other Medicins, are, as it were, Antidotes to waſte and overcome their malignity and evil nature. This kind of remedy, when it was preſcribed by that moſt excellent Phyſician *Hollerius*, who commanded me to apply it to the Lady of *Montigni*, Maid of Honour to the Queen-mother, troubled with a *Cancer* in her left Breſt, which equalled the bigneſs of a Walnut, did not truly throughly heal it, yet notwithſtanding kept it from further growth. Wherefore at length growing wearyof it, when ſhe had committed her ſelf to a certain Phyſician, boldly promiſing her quick help, ſhe tried, with loſs of her life, how dangerous and diſadvantagious the cure of a *Cancer* was, which is undertaken according to the manner of healing other ulcers; for this Phyſitian, when he had caſt away this our Medicin, and had begun the cure with mollifying, heating and attractive things, the pain, inflammation, and all the other ſymptoms increaſing, the tumor grew to that bigneſs, that being the humour drawn thither could not be contained in the part it ſelf, it ſtretched the breſt forth ſo much, that it broke it in the middle, juſt as a Pomgranate cleaves when it comes to its full maturity; whereupon an immoderate flux of bloud followed, for ſtaying whereof he was forced to ſtrew cauſtick powders thereon; but by this means the inflammation and pain becoming more raging, and ſwoundings coming upon her, ſhe poor Soul in ſtead of her promiſed health, yielded up her Ghoſt in the Phyſicians boſom.

CHAP. XXXI.

Of the Fever which happeneth in Scirrhous Tumors.

Why a Quartan happens upon Scirrhous tumors.

Such a Fever is a Quartan, or certainly coming near unto the nature of a Quartan, by reaſon of the nature of the Melancholick humour of which it is bred. For this ſhut up in a certain ſeat in which it makes the tumour, by communication of putrid vapours heats the heart above meaſure, and enflames the humours contained therein, whence ariſes a Fever. Now therefore a Quartan is a Fever coming every fourth day, and having two days intermiſſion.

The primitive cauſes thereof are theſe things which increaſe Melancholick humours in the body, ſuch as the long eating of Pulſe, of coarſe and burnt Bread, of ſalt Fleſh and Fiſh, of groſs Meats, as Beef, Goat, Veniſon, old Hares, old Cheeſe, Cabbadge, thick and muddy Wines, and other ſuch things of the ſame kind.

The antecedent cauſes are, heaped up plenty of Melancholick humours, abounding over all the body. But the conjunct cauſes are Melancholick humours putrefying without the greater Veſſels, in the ſmall Veins, and habit of the body.

The ſigns.

We may gather the ſigns of a Quartan Fever from things which they call natural, not natural, and againſt nature. From things natural; for a cold and dry temper, old age, cold and fat, Men, having their Veins ſmall, and lying hid, their Spleen ſwollen and weak, are uſually troubled with Quartan Fevers.

Why they are frequent in Autumn.

Of things not natural; this Fever or Ague is frequent in Autumn, not onely becauſe, for that it is cold and dry, it is fit to heap up Melancholick humours; but chiefly by reaſon that the humours by the heat of the preceding Summer are eaſily converted into aduſt Melancholy, whence far worſer and more dangerous Quartans ariſe, than of the ſimple Melancholick humour: to conclude, through any cold or dry ſeaſon in a region cold and dry, men that have the like Temper eaſily

eaſily fall into Quartains; if to theſe a painful kind of life full of danger and ſorrow doth accrew.

Of things contrary to Nature, becauſe the fits take one with painful ſhaking, inferring, as it were, the ſenſe of breaking or ſhaking the bones; further it taketh one every fourth day with an itching over the whole body, and oft-times with a thin skurf and puſtules, eſpecially on the legs; the pulſe at the beginning is little, ſlow, and deep, and the urin alſo is then white and wateriſh, inclining to ſomewhat a dark colour.

In the declination when the matter is concocted, the urin becomes black, not occaſioned by any malign ſymptom or preternatural exceſs of heat (for ſo it ſhould be deadly) but by excretion of the conjunct matter. The fit of the Quartain continues twenty four hours, and the intermiſſion is forty four hours. It often takes its original from an obſtruction, pain and *Scirrhus* of the Spleen, and of the ſuppreſſing of the Courſes and Hæmorrhoides.

Quartains taken in the Summer are for the moſt part ſhort, but in the Autumn long, eſpecially ſuch as continue till Winter. Thoſe which come by ſucceſſion of any diſeaſe of the Liver, Spleen, or any other precedent diſeaſe, are worſe than ſuch as are bred of themſelves, and commonly end in a Dropſie. But thoſe which happen without the fault of any bowels, and to ſuch a Patient as will be governed by the Phyſician in his Diet, infer no greater harm, but free him from more grievous and long diſeaſes, as Melancholy, the Falling-ſickneſs, Convulſion, Madneſs; becauſe the Melancholy humor, the author of ſuch diſeaſes, is expelled every fourth day by the force of the fit of the Quartain. Prognoſtick. From what diſeaſes a Quartain frees one.

A Quartain Feaver, if there be no errour committed, commonly exceeds not a year; for otherwiſe ſome Quartains have been found to laſt to the twelfth year, according to the opinion of *Avicen*: The Quartain beginning in Autumn is oft-times ended in the following Spring; the Quartain which is cauſed by aduſt blood, or choler, or ſalt-flegm, is more eaſily and ſooner cured, than that which proceeds from aduſt melancholy humor; becauſe the melancholy humor, terreſtrial of its own nature, and harder to be diſcuſſed than any other humor, is again made by aduſtion (the ſubtiler parts being diſſolved and the groſſer ſubſiding) more ſtubborn, groſs, malign, and acrid. The cure is wholly abſolved by two means, that is, by Diet and Medicines. The diet ought to be preſcribed contrary to the cauſe of the Feaver in the uſe of the ſix things not natural, as much as lies in our power. Wherefore the Patient ſhall eſchew Swines fleſh, flatulent, viſcid and glutinous meats, fenny Fowls, ſalt meats and Veniſon, and all things of hard digeſtion. The uſe of white Wine indifferent hot and thin, is convenient to attenuate and incide the groſs humor, and to move urin and ſweat; yea verily at the beginning of the fit, a draught of ſuch Wine will cauſe vomiting, which is a thing of ſo great moment, that by this one remedy many have been cured. Yet if we may take occaſion and opportunity to provoke vomit, there is no time thought fitter for that purpoſe than preſently after meat; for then it is the ſooner provoked, the fibers of the ſtomach being humected and relaxed, and the ſtomach is ſooner turned to vomiting, whereupon follows a more plentiful, happy, and eaſie evacuation of the Phlegmatick and Cholerick humor, and leſs troubleſome to Nature: And of all the crudities with which the mouth of the ventricle abounds in a Quartain, by reaſon of the more copious afflux or the Melancholick humor, which by his qualities cold and dry diſturbs all the actions and natural faculties. Moreover, exerciſes and frictions are good before meat; ſuch paſſions of the mind are as contrary to the cauſe from which this Feaver takes his original, are fit to be cheriſhed by the Patient, as Laughter, Jeſting, Muſick, and all ſuch like things full of pleaſure and mirth. At the beginning the Patient muſt be gently handled and dealt withal, and we muſt abſtain from all very ſtrong medicines, until ſuch time as the diſeaſe hath been of ſome continuance. For this humour, contumacious at the beginning, when as yet Nature hath attempted nothing, is again made more ſtubborn, terreſtrial and dry, by the almoſt fiery heat of acrid medicines. If the body abound with blood, ſome part thereof muſt be taken away by opening the Median or Baſilick-vein of the left arm, with this caution, that if it appear more groſs and black, we ſuffer it to flow more plentifully; if more thin, and tinctured with a laudable and red colour that we preſently ſtay it. The matter of this Feaver muſt be ripened, concocted and diminiſhed with the Syrups of *Epithymum* of *Scolopendrium*, of Maiden-hair, Agrimony, with the waters of Hops, Bugloſs, Borage, and the like. I ſincerely proteſt, next unto God, I have cured very many Quartains by giving a portion of a little Treacle diſſolved in about ſome two ounces of *Aqua vitæ*, alſo ſometimes by two or three grains of Musk diſſolved in Muskadine, given at the beginning of a particular fit towards the general declination of the diſeaſe after general purgations, the humor and body being prepared, and the powers ſtrong: And certainly an inveterate Quartain can ſcarce ever be diſcuſſed, unleſs the body be much heated with meats and medicines. Therefore it is not altogether to be diſproved, which many ſay, that they have driven away a Quartain by taking a draught of Wine every day aſſoon as they came forth of their beds, in which ſome leaves of Sage had been infuſed all the night. Alſo it is good a little before the fit to anoint all the ſpine of the back with Oyls heating all the nervous parts, ſuch as are the Oyl of Rue, Walnuts, of the Peppers, mixing therewith a little *Aqua vitæ*; but for this purpoſe, the Oyl of *Caſtoreum* which hath been boiled in an Apple of *Coliquintida*, the Kernels taken out, upon hot coals, to the conſumption of the half part, mixing therewith ſome little quantity of the Powders of Pepper, Pellitory of *Spain*, and *Euphorbium*, is excellent. Certainly, ſuch like Inunctions are good, not only to mitigate the vehemency of the terrible ſhaking, but alſo to provoke ſweats; for becauſe by their humid heat they diſcuſs this humor being dull and rebellious to the expulſive faculty; for the Melancholy is, as it were, the droſs and mud of the blood. Therefore, if on the contrary, The Quartain Feaver ſhall be cauſed by aduſt choler, we muſt hope for and expect a cure by refrigerating and humective medicines, ſuch as Sorrel, Lettuce, Purſlane, broths of the decoctions of Cucumbers, Gourds, Mellons, and Pompions. For in this caſe, if any uſe hot medicines, he ſhall make this humor moſt obſtinate by the reſolving of the ſubtiler parts. Thus *Trallianus* boaſts that he hath cured Diet. How much vomiting prevails to cure a Quartain. Medicines. What Quartains muſt be cured with refrigerating things.

theſe kinds of Quartain Feaver by the only uſe of refrigerating *Epithemaes* being often repeated a little before the beginning of the fit. And this is the ſum of the cure of true and legitimate intermitting Feavers; that is, of thoſe which are cauſed by one ſimple humor, whereby the cure of thoſe which they call Baſtard intermitting Feavers, may be eaſily gathered and underſtood; as which are bred by a humor impure, and not of one kind, but mixt or compoſed by admixture of ſome other matter; for example, according to the mixture of divers humors Phlegmatick and Cholerick, the Medicins muſt alſo be mixt, as if it were a confuſed kind of Feaver of a Quotidian and Tertian, it muſt be cured by a medicine compoſed of things evacuating flegm and choler.

What baſtard Agues are, and how they muſt be cured.

CHAP. XXXII.

Of an Aneuriſma, *that is, the dilatation, or ſpringing of an Artery, Vein, or Sinew.*

What it is.

AN *Aneuriſma* is a ſoft tumor yielding to the touch, made by the blood and ſpirit poured forth under the fleſh and muſcles, by the dilatation or relaxation of an Artery. Yet the Author of the definitions, ſeems to call any dilatation of any veinous veſſel by the name of an *Aneuriſma*. *Galen* calls an *Aneuriſma*, an opening made of the *Anatomiſts* of an Artery. Alſo an *Aneuriſma* is made when an Artery that is wounded cloſeth too ſlowly, the ſubſtance which is above it being in the mean time agglutinated, filled with fleſh and cicatrized, which doth not ſeldom happen in opening of Arteries unskilfully performed and negligently cured; therefore *Aneuriſma's* are abſolutely made by the *Anaſtomoſis*, ſpringing, breaking, *Eroſion*, and wounding of the arteries. Theſe happen in all parts of the body, but more frequently in the throat, eſpecially in women after a painful travail. For when as they more ſtrongly ſtrive to hold their breath, for the more powerful expulſion of the birth, it happens that the artery is dilated and broken, whence follows an effuſion of blood and ſpirits under the skin. The ſigns are, a ſwelling one while great, another ſmall, with a pulſation and a colour not not varying from the native conſtitution of the skin. It is a ſoft tumor, and ſo yielding to the impreſſion of the fingers, that if it peradventure be ſmall, it wholly vaniſheth, the arterious blood and ſpirits flying back into the body of the artery, but preſently, aſſoon as you take your fingers away, they return again with like celerity. Some *Aneuriſma's* do not only when they are preſſed, but alſo of themſelves, make a ſenſible hiſſing, if you lay your ear near to them, by reaſon of the motion of the vital ſpirit ruſhing with great violence through the ſtraitneſs of the paſſage.

In what parts they chiefly happen.

Prognoſtick.

Wherefore in *Aneuriſma's* in which there is a great rupture of the artery, ſuch a noiſe is not heard, becauſe the ſpirit is carried through a larger paſſage. Great *Aneuriſma's* under the arm-pits, in the groins and other parts wherein there are large veſſels, admit no cure. becauſe ſo great an eruption of blood and ſpirit often follows upon ſuch an Inciſion, that death prevents both art and cure.

A Hiſtory.

Which I obſerved a few years ago in a certain Prieſt of St. *Andrews* of the Arches, Mr. *John Maillet*, dwelling with a chief Preſident *Chriſtopher de Thou*. Who having an *Aneuriſma* at the ſetting on of the ſhoulder about the bigneſs of a Wall-nut, I charged him, he ſhould not let it be opened, for if he did, it would bring him into manifeſt danger of his life, and that it would be more ſafe for him to break the violence thereof with double clothes ſteeped in the juice of Night-ſhade and Houſleek, with new and wheyey cheeſe mixt therewith: Or with *Unguentum de Bolo*, or *Emplaſtrum contra rupturam*, and ſuch other refrigerating and aſtringent medicines, if he would lay upon it a thin plate of Lead, and would uſe ſhorter breeches, that his doublet might ſerve to hold it too, to which he might faſten his breeches inſtead of a ſwathe, and in the mean time he ſhould eſchew all things which attenuate and inflame the blood, but eſpecially he ſhould keep himſelf from all great ſtraining of his voice. Although he had uſed his diet for a year, yet he could not ſo handle the matter but that the tumor increaſed; which he obſerving goes to a Barber, who ſuppoſing the tumor to be of the kind of vulgar Impoſthumes, applies to it in the evening a Cauſtick cauſing an Eſchar ſo to open it. In the morning ſuch an abundance of blood flowed forth from the tumor being opened, that he therewith aſtoniſhed, implores all poſſible aid, and bids that I ſhould be called to ſtay this his great bleeding, and he repented that he had not followed my direction. Wherefore I was called, but when I was ſcarce over the threſhold, he gave up his ghoſt with his blood. Wherefore I diligently admoniſh the Chirurgeon that he do not raſhly open *Aneuriſma's*, unleſs they be ſmall, in an ignoble part, and not indued with large veſſels, but rather let him perform the cure after this manner: Cut the skin which lies over it until the artery appear, and then ſeparate it with your knife from the particles about it, then thruſt a blunt and crooked needle with a thred in it under it; bind it, then cut it off, and ſo expect the falling off of the thread of it ſelf, whiles Nature covers the Orifices of the cut artery with the new fleſh, then the reſidue of the cure may be performed after the manner of ſimple wounds. The *Aneuriſma's* which happen in the internal parts are incurable. Such as frequently happen to thoſe who have often had the unction and ſweat for the cure of the French diſeaſe, becauſe being ſo attenuated and heated therewith, that it cannot be contained in the receptacles of the artery, it diſtends it to that largeneſs as to hold a mans fiſt: Which I have obſerved in the dead body of a certain Taylor, who by an *Aneuriſma* of the arterious vein ſuddenly whilſt he was playing at Tennis fell down dead, the veſſel being broken; his body being opened, I found a great quantity of blood poured forth into the capacity of the cheſt, but the body of the artery was dilated to that largeneſs I formerly mentioned, and the inner coat thereof was bony. For which cauſe within a while after I ſhewed it to the great admiration of the beholders in the Phyſicians School, whilſt I publickly diſſected a body there; whilſt he lived, he ſaid he felt a beating and a great heat over all his body the force of the pulſation of all the Arteries, by the occaſion whereof he often ſwounded. Dr. *Sylvius* the Kings Profeſſor of Phyſick at that time forbad him the uſe of Wine, and wiſhed him to uſe boiled water for his drink, and

Aneuriſma's muſt not raſhly be opened.

How they muſt be cured.

Thoſe of the inward parts incureable.

A Hiſtory.

and Curds and new Cheeſes for his meat, and to apply them in form of Cataplaſms upon the grieved and ſwoln part. At night he uſed a Ptiſan of Barley meal and Poppy-ſeeds, and was purged now and then with a Clyſter of refrigerating and emollient things, or with Caſſia alone, by which medicines he ſaid he found himſelf much better. The cauſe of ſuch a bony conſtitution of the Arteries by *Aneuriſmaes* is, for that the hot and fervid blood firſt dilates the coats of an artery, then breaks them; which when it happens, it then borrows from the neighbouring bodies, a fit matter to reſtore the looſed continuity thereof.

This matter, whilſt by little and little it is dried and hardned, it degenerates into a griſtly or elſe a bony ſubſtance, juſt by the force of the ſame material and efficient cauſes, by which ſtones are generated in the reins and bladder. For the more terreſtrial portion of the blood is dried and condenſed by the power of the unnatural heat contained in the part affected with an *Aneuriſma*; whereby it comes to paſs, that the ſubſtance added to the dilated and broken artery is turned into a body of a bony conſiſtence. In which the ſingular providence of Nature, the Hand-maid of God, is ſhewed, as that which, as it were, by making and oppoſing a new wall or bank, would hinder and break the violence of the raging blood ſwelling with the abundance of the vital ſpirits; unleſs any had rather to refer the cauſe of that hardneſs to the continual application of refrigerating and aſtringent medicines. Which have power to condenſate and harden, as may not obſcurely be gathered by the writings of *Galen*. But beware you be not deceived by the fore-mentioned ſigns; for ſometimes in large *Aneuriſmaes* you can perceive no pulſation, neither can you force the blood into the artery by the preſſure of your fingers, either becauſe the quantity of ſuch blood is greater than which can be contained in the antient receptacles of the artery, or becauſe it is condenſate and concrete into clods, whereupon wanting the benefit of ventilation from the heart, it preſently putrefies: Thence enſue great pain, a Gangrene, and mortification of the part, and laſtly, the death of the creature.

Lib. 4. cap. ult. de præſ. ex pulſu.

A Caution in the knowing *Aneuriſmats.*

The end of the Seventh Book.

BOOK VIII.

Of particular Tumors againſt Nature.

The PREFACE.

BEcauſe the cure of Diſeaſes muſt be varied according to the variety of the temper, not only of the body in general, but alſo of each part thereof; the ſtrength, figure, form, ſite, and ſenſe thereof being taken into conſideration: I think it worth my pains, having already ſpoken of Tumors in general, if I ſhall treat of them in particular, which affect each part of the body, beginning with thoſe which aſſail the head. Therefore the Tumor either affects the whole head, or elſe only ſome particle thereof, as the Eyes, Ears, Noſe, Gums, and the like. Let the Hydrocephalos *and* Phyſocephalos *be examples of thoſe Tumors which poſſeſs the whole head.*

CHAP. I.

Of an Hydrocephalos *or watry Tumor which commonly affects the heads of Infants.*

THe *Greeks* call this Diſeaſe *Hydrocephalos*, as it were a Dropſie of the head, by a wateriſh humor; being a diſeaſe almoſt peculiar to Infants newly born. It hath for an external cauſe the violent compreſſion of the head by the hand of the Midwife, or otherwiſe at the birth, or by a fall, contuſion, and the like. For hence comes a breaking of a vein, or artery, and an effuſion of the blood under the skin. Which by corruption becoming whayiſh, laſtly degenerateth into a certain wateriſh humor. It hath alſo an inward cauſe, which is the abundance of ſerous and acrid blood, which by its tenuity and heat ſweats through the pores of the veſſels, ſomtimes between the muſculous skin of the head, and the *Pericranium*; ſometimes between the *Pericranium* and the skull; and ſometimes between the skull and membrane called *Dura mater*, and otherwhiles in the ventricles of the brain.

What it is. The cauſes.

Differences by reaſon of place.

The ſigns of it, contained in the ſpace between the muſculous skin and the *Pericranium*, are a manifeſt tumor without pain, ſoft, and much yielding to the preſſure of the fingers. The ſigns when it remaineth between the *Pericranium* and the skull, are for the moſt part like the fore-named, unleſs it be that the Tumor is a little harder, and not ſo yielding to the finger, by reaſon of the parts between it and the finger: And alſo there is ſomewhat more ſenſe of pain. But when it is in the ſpace between the skull and *Dura mater*, or in the ventricles of the brain, or of the whole ſubſtance thereof, there is a dulneſs of the ſenſes, as of the ſight and hearing; the tumor doth not yield to the touch, unleſs you uſe ſtrong impreſſion, for then it ſinketh ſomewhat down, eſpecially in Infants newly born; who have their skulls almoſt as ſoft as wax, and the junctures of their ſutures lax, both by nature, as alſo by accident, by reaſon of the humor contained therein moiſtening and relaxing all the adjacent parts; the humor contained here lifts up the skull ſomewhat more high, eſpecially at the meetings of the ſutures; which you may thus know, becauſe the tumor being preſſed, the humor flies back into the ſecret paſſage of the brain.

Signs.

To conclude, the pain is more vehement, the whole head more ſwollen, the fore-head ſtands ſomewhat further out, the eye is fixt and immoveable, and alſo weeps by reaſon of the ſerous humor ſweating out of the brain.

A Hiſtory. *Veſalius* writes, that he ſaw a Girl of two years old, whoſe head was thicker than any mans head by this kind of Tumor, and the skull not bony, but membranous, as it uſeth to be in Abortive-births, and that there was nine pound of water ran out of it.

Abucraſis tells, that he ſaw a Child whoſe head grew every day bigger by reaſon of the watery moiſture contained therein, till at length the Tumor became ſo great, that his neck could not bear it neither ſtanding nor ſitting, ſo that he died in a ſhort time. I have obſerved and had in cure four children troubled with this diſeaſe, one of which being diſſected after it died, had a brain no bigger than a Tennis-Ball. But of a Tumor and humor contained within under the *Cranium*, or skull, I have ſeen none recover, but they are eaſily healed of an external Tumor.

Therefore whether the humor lye under the *Pericranium*, or under the muſculous skin of the head, it muſt firſt be aſſailed with reſolving medicines, but if it cannot be thus overcome, you muſt make an Inciſion, taking heed of the Temporal Muſcle, and thence preſs out all the humor, whether it reſemble the waſhing of fleſh newly killed, or blackiſh blood, or congealed or knotted blood, as when the tumor hath been cauſed by contuſion; then the wound muſt be filled with dry lint, and covered with double boulſters; and laſtly, bound with a fitting ligature.

CHAP. II.

Of a Polypus, *being an eating Diſeaſe in the Noſe.*

The reaſon of the name. THe *Polypus* is a tumor of the noſe againſt Nature, commonly ariſing from the *Os Ethmoides*, or ſpongy-bone. It is ſo called, becauſe it reſembles the feet of a Sea-*Polypus* in figure, and the fleſh thereof in conſiſtence. This tumor ſtops the noſe, intercepting and hindring the liberty of ſpeaking and blowing the noſe. *Celſus* ſaith, the *Polypus* is a caruncle of excreſcence one while white, another while reddiſh, which adheres to the bone of the noſe, and ſometimes fills the noſtrils hanging towards the lips, ſometimes it deſcends back through that hole, by which the ſpirit deſcends from the noſe to the throttle; it grows ſo that it may be ſeen behind the *Uvula*, and often ſtrangles a man by ſtopping his breath. There are five kinds thereof; the firſt is, a ſoft membrane, long and thin like the relaxed and depreſſed *Uvula*, hanging from the middle griſtle of the noſe, being filled with a phlegmatick and viſcid humor. This in exſpiration hangs out of the noſe, but is drawn in and hid by inſpiration; it makes one ſnaffle in their ſpeech, and ſnort in their ſleep. The ſecond hath hard fleſh, bred of melancholy blood without aduſtion, which obſtructing the noſtrils, intercepts the reſpiration made by that part. The third is fleſh hanging from the griſtle, round and ſoft, being the off-ſpring of phlegmatick blood. The fourth is a hard tumor, like fleſh, which when it is touched, yields a ſound like a ſtone; it is generated of melancholy blood dried, being ſomewhat of the nature of a *Scirrhus* confirmed, and without pain. The fifth is, as it were, compoſed of many cancrous Ulcers ſpread over the tranſverſe ſurface of the griſtle.

Lib. 6. cap. 8.

The differences hereof.

Which of them admit no manual operation. Of all theſe ſorts of *Polypi* ſome are not ulcerated, others ulcerated, which ſend forth a ſtinking and ſtrong ſmelling filth. Such of them as are painful, hard, reſiſting, and which have a livid, or leaden colour, muſt not be touched with the hand, becauſe they favour of the nature of a *Cancer*, as into which they often degenerate; yet by reaſon of the pain which oppreſſes more violently, you may uſe the Anodyne medicines formerly deſcribed in a *Cancer*, ſuch as this following.

An Anodyne. ℞ *Olei de vitell. ovorum* ℥ ij, *Litharg. auri, & Tuthiæ præp. an.* ℥ i, *ſucci plat. ſolani an.* ℥ i ß, *Lapid. hæmatit. & camphoræ, an.* ℥ ß. Let them be wrought a long time in a leaden Mortar, and ſo make a medicine to be put into the noſtrils. Thoſe which are ſoft, looſe, and without pain, are ſometimes curable, being plucked away with an Inſtrument made for that purpoſe, or elſe waſted by actual cauteries put in through a pipe, ſo that they touch not the ſound part; or by potential cauteries, as *Egyptiacum* compoſed of equal parts of all the ſimples with Vitriol, which hath a faculty to waſte ſuch like fleſh. *Aqua fortis* and Oyl of Vitriol have the ſame faculty, for theſe take away a *Polypus* by the root; for if any part there remain, it will breed again. But cauteries and acrid medicines muſt be put into the noſtrils with this caution, that in the mean time cold repelling and aſtringent medicines be applied to the noſe and parts about it to aſſwage the pain, and hinder the inflammation. Such as are *Unguentum de bello*, and *Unguentum nutritum*, white of Eggs beaten with Roſe-leaves, and many other things of the like nature.

Why it muſt be taken clear away.

CHAP. III.

Of the Parotides, *that is, certain ſwellings about the Ears.*

What it is. THe *Parotis* is a tumor againſt Nature, affecting the glandules and thoſe parts ſeated behind and about the Ears, which are called the Emunctories of the brain; for theſe becauſe they are looſe and ſpongy, are fit to receive the excrements thereof. Of theſe ſome are critical, the matter of the diſeaſe ſomewhat digeſted being ſent thither by the force of Nature. Others Symptomatical, the excrements of the brain increaſed in quantity, or quality, ruſhing thither of their own accord. Such abſceſſes often have great inflammations joyned with them, becauſe the biting humor which flows thither is more vitiated in quality than in quantity. Beſides alſo, they often cauſe great pain, by reaſon of the diſtention of the parts indued with the moſt exquiſite ſenſe, as alſo by reaſon of a nerve of the fifth Conjugation ſpread over theſe parts; as alſo of the neighbouring membranes of the brain, by which means the Patient is troubled with head-ach, and all

The differences. Their ſigns and ſymptoms.

his

his face becomes ſwoln. Yet many times this kind of Tumor uſeth to be raiſed by a tough, viſcous, and groſs humor.

This diſeaſe doth more grievouſly afflict young men than old; it commonly brings a Feaver and watching. It is difficult to be cured, eſpecially, when it is cauſed by a groſs, tough, and viſcid humor, ſent thither by the *Criſis*. Prognoſtick.

The cure muſt be performed by diet, which muſt be contrary to the quality of the humor in the temper and conſiſtence of the meats. If the inflammation and redneſs be great, which indicate abundance of blood, Phlebotomy will be profitable, yea very neceſſary. But here we muſt not uſe the like judgment, in application of local medicines, as we do in other tumors, as *Galen* admoniſheth us; that is, we muſt not uſe repercuſſives at the beginning, eſpecially, if the abſceſs be critical; for ſo we ſhould infringe or fore-ſlow the endeavours of Nature forcibly freeing it ſelf from the morbifique matter. But we muſt much leſs repel, or drive it back, if the matter which hath flowed thither be venenate, for ſo the reflow thereof to the noble parts would prove mortal. Wherefore the Chirurgeon ſhall rather aſſiſt Nature in attracting and drawing forth that humor. Yet if the defluxion ſhall be ſo violent, if the pain ſo fierce, that thence there may be fear of watchings, and a Feaver, which may deject the powers; *Galen* thinks, it will be expedient with many reſolving medicines to mix ſome repelling. Wherefore at the beginning let ſuch a Cataplaſm be applied. The cure. *Lib. 3. de comp. med. ſec. Locos. Hip. aph. 21. lib. 1.*

℞ *Far. hord. & ſem. lin. ana* ℥ ij, *coquantur cum mulſo aut decocto cham. addendo but. recen. & olei cham. ana* ℥ i, *fiat cataplaſma.* And the following Oyntment will alſo be good. Gentle reſolving medicines.

℞ *But. recen.* ℥ ii, *olei cham. & lilior. an* ℥ i, *unguen. de Althea* ℥ ß, *ceræ parum:* Make an Oyntment to be applied with moiſt and greaſie wool, to mitigate the pain; alſo ſomewhat more ſtrong diſcuſſing and reſolving medicines will be profitable; as,

℞ *Rad. Altheæ & bryon. an.* ℥ ij, *fol. rutæ, puleg. orig. an. m.* i, *flo. chamæm. melil. an. p.* i, *coquantur in hydromelite, piſtentur, trajiciantur, addendo farin. fænugræc. orobi. an.* ℥ i, *pul. Ireos, cham. melilot. an.* ℥ ij. *olei aneth. rutac. an.* ℥ i, *fiat cataplaſma.* But if you determine to reſolve it any more, you may uſe *Emplaſtrum Oxycroceum* and *Melilot-plaiſter.* If the humor doth there concrete and grow hard, you muſt betake you to the medicines which were preſcribed in the Chapter of the *Scirrhus*; but if it tend to ſuppuration, you ſhall apply the following medicine. Stronger reſolvers.

℞ *Rad. liliorum & ceparum ſub cineribus coct. an.* ℥ iij. *Vitell. ovor. num.* ii, *axung. ſuilla & unguent. baſilicon, an.* ℥ i, *farr. ſem. lini* ℥ i ß, *fiat cataplaſma.* But if the matter do ſo require, let the tumor be opened as we have formerly preſcribed. A ripening medicine.

CHAP. IV.

Of the Epulis, *or over-growing of the fleſh of the Gums.*

THe *Epulis* is a fleſhy excreſcence of the gums between the teeth, which is by little and little oft-times increaſed to the bigneſs of an Egg, ſo that it both hinders the ſpeech and eating; it caſts forth ſalvious and ſtinking filth, and not ſeldom degenerates into a *Cancer*, which you may underſtand by the propriety of the colour, pain, and other accidents; for then you muſt by no means touch it with your hand. But that which doth not torment the Patient with pain, may be pluck'd away; and let this be the manner thereof. What it is. The Symptomes.

Let it be tied with a double thred, which muſt be ſtraiter twiched until ſuch time as it fall off; when it ſhall fall away, the place muſt be burnt with a cautery, put through a trunk or pipe, or with *Aqua fortis*, or oyl of *Vitriol*, but with great care that the ſound parts adjoyning thereto be not hurt; for if ſo be that it be not burnt, it uſually returns. The Chirurgical cure.

I have often by this means taken away ſuch large tumors of this kind, that they hung out of the mouth in no ſmall bigneſs, to the great diſfiguring of the face, which when as no Chirurgeon durſt touch, becauſe the fleſh looked livid, I ventured upon, becauſe they were free from pain; and by taking them away and cauterizing the place, I perfectly healed them: not truly ſuddenly, and at once; for although I burnt the place after diſſection, yet nevertheleſs they ſprung up again, becauſe a certain portion of the bone and ſockets in which the teeth ſtand faſtned, were become rotten. I have often obſerved ſuch like fleſh by continuance of time to have turned into a griſtly and bony ſubſtance. Wherefore the cure muſt be begun as ſpeedily as may be; for being but little, and having faſtened no deep roots, it is more eaſily taken away, being then only filled with a viſcid humor, which in ſucceſs of time is hardened, and makes the taking away thereof more difficult. Why the cure muſt not be deferred.

CHAP. V.

Of the Ranula.

THere is oft-times a tumor under the tongue, which takes away the liberty of pronuntiation or ſpeech; wherefore the Greeks call it *Batrachium*, the Latins *Ranula*, becauſe ſuch as have this diſeaſe of the tongue, ſeem to expreſs their minds by croaking rather than by ſpeaking. The Reaſon why it is ſo called.

It is cauſed by the falling down of a cold, moiſt, groſs, tough, viſcid, phlegmatick matter, from the brain upon the tongue, which matter in colour and conſiſtence reſembles the white of an Egg, yet ſometimes it looks of a citrin or yellowiſh colour. The Cauſe.

That you may ſafely perform the cure, you muſt open the Tumor rather with a Cautery of hot Iron, than with a Knife, for otherwiſe it will return again. The manner of opening it muſt be thus. You ſhall get a bended hollow and perforated Iron-plate with a hole in the midſt, and making the Patient to hold open his mouth, you ſhall ſo fit it, that the hole may be upon the part The Cure.

which muſt be opened. Then there you muſt open it with an hot Iron, for ſo you ſhall hurt no part of the mouth which is whole; but when you are ready to burn it, by thruſting your thumb under the Patients chin, you may ſomewhat elevate the Tumor whereby you may open it with more certainty; when it is opened, you muſt thruſt out the matter contained therein, and then waſh the Patients mouth with ſome Barly-water, Honey, and Sugar of Roſes; for ſo the Ulcer will be ſafely and quickly healed.

The Delineation of the Iron-plate, and crooked actual Cautery.



CHAP. VI.

Of the ſwelling of the Glandules, or Almonds of the Throat.

Why the glandules are called Almonds. Their uſe.

NAture at the jaws near the roots of the tongue, hath placed two glandules oppoſite to one another; in figure and magnitude like to Almonds, whence alſo they have their name; their office is to receive the ſpittle falling down from the brain, both leſt that the too violent falling down of the humor ſhould hinder the tongue in ſpeaking, as alſo, that the tongue might always have moiſture, as it were, laid up in ſtore, leſt by continual ſpeaking, it ſhould grow dry and fail. For thus this ſpittle being conſumed by feaveriſh heats, the Patients are ſcarce able to ſpeak, unleſs they firſt moiſten their tongue by much waſhing their mouth.

The cauſe of their tumor.

Theſe glandules, becauſe they are ſeated in a hot and moiſt place, are very ſubject to inflammations; for there flows into theſe oft-times together with the blood, a great quantity of crude, phlegmatick and viſcous humors, whence ariſes a Tumor; which is not ſeldom occaſioned by drinking much, and that vaporous Wine; by too much Gluttony, and ſtaying abroad in the open air.

Symtomes.

Swallowing is painful and troubleſome to the Patient, and commonly he hath a Feaver. Oft-times the neighbouring muſcles of the throttle and neck are ſo ſwoln together with theſe glandules, that (as it uſually happens in the *Squinzy*) the paſſage of the breath and air is ſtopped, and the Patient ſtrangled.

Cure.

We reſiſt this imminent danger by purging and blood-letting, by applying Cupping-glaſſes to the neck and ſhoulders, by frictions and ligatures of the extreme parts, and by waſhing and gargling the mouth and throat with aſtringent Gagariſms. But if they come to Suppuration, you muſt with your Inciſion-knife make way for the evacuation of the *Pus*, or matter; but, if on the contrary, theſe things performed according to art, defluxion be increaſed, and there is preſent danger of death by ſtopping and intercepting the breath, for the ſhunning ſo great and imminent danger, the top or upper part of the *Aſpera arteria* or Weazon muſt be opened, in that place where it uſes to ſtand moſt out; and it may be done ſo much the ſafer, becauſe the jugular veins and arteries are furtheſt diſtant from this place, and for that this place hath commonly little fleſh upon it. And that the Inciſion may be the fitlier made, the Patient muſt be wiſhed to bend his head back, that ſo the artery may be the more eaſily come to by the Inſtrument; then you ſhall make an Inciſion overthwart way with a crooked knife between two rings (not hurting nor touching the griſtly ſubſtance) that is to ſay, the membrane which ties together the griſtly rings, being only cut; you ſhall then judge that you have made the Inciſion large enough, when you ſhall perceive the breath to break out by the wound; the wound muſt be kept open ſo long, until the danger of ſuffocation be paſt; and then it muſt be ſowed up not touching the griſtle: But if the lips of the wound ſhall be hard and callous; they muſt be lightly ſcarrified, that ſo they may become bloody for their eaſie agglutination and union, as we ſhall ſhew more at large in the cure of Hare-lips. I have had many in cure, who have recovered, that have had their weazon together with the griſtly rings thereof cut with a great wound, as we ſhall note when we ſhall come to treat of the cure of that wounds of that part.

Extreme diſeaſes muſt have extreme remedies.

How you muſt open the weazon.

CHAP. VII.

Of the Inflammation and Relaxation in the Uvula *or* Columella.

What the *uvula* is, and what the uſe thereof.

THe *Uvula* is a little body, ſpongy, and ſomewhat ſharpened to the form of a Pine-apple, hanging even down from the upper and inner part of the palat, ſo to break the force of the air drawn in, in breathing, and carried to the lungs; and to be as a quill to form and tune the voice. It often grows above meaſure by receiving moiſture falling down from the brain, becoming ſharp by little and little from a broader and more ſwoln *Baſis*. Which thing cauſes

The cauſe of the ſwelling thereof.

many

many ſymptomes; for by the continual irritation of the diſtilling humor the cough is cauſed, which alſo hinders the ſleep, and intercepts the liberty of ſpeech; as alſo, by hindering reſpiration, the Patients cannot ſleep, unleſs with open mouth: They are exerciſed with a vain endeavouring to ſwallow (having, as it were, a morſel ſticking in their jaws) and are in danger of being ſtrangled. Symptomes.

This diſeaſe muſt be reſiſted and aſſailed by purging, bleeding, cupping, taking of clyſters, uſing aſtringent Gargles, and a convenient diet; but if it cannot thus be overcome, the cure muſt be tried by a cauſtick of *Aqua fortis*, which I have divers times done with good ſucceſs. But if it cannot be ſo done, it will be better to put to your hand, than through idleneſs to ſuffer the Patient to remain in imminent and deadly danger of ſtrangling: yet in this there muſt very great caution be uſed; for the Chirurgeon ſhall not judge the *Uvula* fit to be touched with an inſtrument, or cauſtick, which is ſwoln with much inflamed, or black blood, after the manner of a *Cancer*; but he ſhall boldly put to his hand, if it be longiſh, grow ſmall by little and little into a ſharp, looſe and ſoft point; if it be neither exceeding red, neither ſwoln with too much blood, but whitiſh and without pain. Therefore that you may more eaſily and ſafely cut away that which redounds and is ſuperfluous, deſire the Patient to ſit in a light place, and hold his mouth open; then take hold of the top of the *Uvula* with your Sizzers, and cut away as much thereof as ſhall be thought unprofitable. Otherwiſe you ſhall bind it with the inſtrument here-under deſcribed. The invention of this Inſtrument is to be aſcribed to *Honoratus Taſtellanus*, that diligent and learned man, the Kings Phyſician ordinary, and the chief Phyſician of the Queen-mother. Which alſo may be uſed in binding of *Polypi*, and warts in the neck of the womb. The Cure. The Cure by Chirurgery.

The Delineation of Conſtrictory-rings, fit to twitch or bind the Columella, *with a twiſted thread.*



A *Shews the ring, whoſe upper part is ſomewhat hollow.*
B *A double waxed thread, which is couched in the hollowneſs of the ring, and hath a running, or looſe knot upon it.*
C *An Iron rod, into the eye whereof the forementioned double thread is put, and it is to twitch the* Columella, *when as much thereof is taken hold of, as is unprofitable, and ſo take it away without any flux of blood. When you would ſtraiten the thread, draw it again through the Iron-rod, and ſo ſtrain it as much as you ſhall think good, letting the end of the thread hang out of the mouth. But every day it muſt be twitched harder than other, until it fall away by means thereof, and ſo the part and Patient be reſtored to health. I have delineated three of theſe Inſtruments, that you may uſe which you will, as occaſion ſhall be offered.*

A Figure of the Speculum oris, *by which the mouth is held and kept open whilſt the Chirurgion is buſied in the cutting away, or binding the* Uvula.



But if an eating Ulcer ſhall aſſociate this relaxation of the *Uvula*, together with a flux of blood, then it muſt be burnt and ſeared with an hot Iron, ſo thruſt into a Trunk, or Pipe, with an hole in it, that ſo no ſound part of the mouth may be offended therewith.

A

A hollow Trunk with a hole in the ſide, with the hot Iron inſerted, or put therein.



CHAP. VIII.

Of the Angina, *or Squinzy.*

What it is. THe Squinancy, or Squincy, is a ſwelling of the jaws, which hinders the entring of the ambient air into the weazon, and the vapours and the ſpirit from paſſage forth, and the meat alſo from being ſwallowed. There are three differences thereof. The firſt torments the Patient with great pain, no ſwelling being outwardly apparent, by reaſon the Morbifick humor lies hid behind the almonds or glandules of the *Vertebræ* of the neck, ſo that it cannot be perceived, unleſs you hold down the tongue with a Spatula, or the *Speculum oris*, for ſo you may ſee the redneſs and tumor there lying hid. The Patient cannot draw his breath, nor ſwallow down meat nor drink: his tongue (like a Grey-hounds after a courſe) hangs out of his mouth; and he holds his mouth open, that ſo he may the more eaſily draw his breath; to conclude, his voice is, as it were, drown'd in his jaws and noſe; he cannot lie upon his back, but lying is forced to ſit, ſo to breathe more freely: And becauſe the paſſage is ſtopt, the drink flies out at his noſe; the eyes are fiery and ſwoln, and ſtanding out of their orb. Thoſe which are thus affected are often ſuddenly ſuffocated, a foam riſing about their mouths.

The differences.

The firſt kind.

The Symptoms.

The ſecond kind. The ſecond difference is ſaid to be that, in which the tumor appears inwardly, but little or ſcarce any thing at all outwardly, the tongue, glandules and jaws, appearing ſomewhat ſwoln.

The third. The third, being leaſt dangerous of them all, cauſes a great ſwelling outwardly, but little inwardly.

The cauſes. The cauſes are either internal or external. The external are a ſtroak, ſplinter, or the like thing ſticking in the throat, or the exceſs of extreme cold or heat. The internal cauſes are a more plentiful defluxion of the humors either from the whole body or the Brain, which participate of the nature, either of blood, choler, or flegm, but ſeldom of Melancholy. The ſigns by which the kind and commixture may be known, have been declared in the general Treatiſe of Tumors. The Squincy is more dangerous, by how much the humor is leſs apparent within and without. That is leſs dangerous which ſhews it ſelf outwardly, becauſe ſuch an one ſhuts not up the ways of the meat, nor breath. Some die of a Squincy in twelve hours, others in two, four or ſeven days. Thoſe (ſaith *Hippocrates*) which ſcape the Squincy, the diſeaſe paſſes to the lungs, and they die within ſeven days; but if they ſcape theſe days, they are ſuppurated; but alſo often-times this kind of diſeaſe is terminated by diſappearing, that is, by an obſcure reflux of the humor into ſome noble part, as into the lungs (whence the *Empyema* proceeds) and into other principal parts, whoſe violating brings inevitable death; ſometimes by reſolution, otherwiſe by ſuppuration.

Hip. ſect. 3. prog. 2. Aphor. 10. ſect. 5.

The way of reſolution is the more to be deſired; it happens when the matter is ſmall, and that ſubtle; eſpecially, if the Phyſician ſhall draw blood by opening a vein, and the Patient uſe fitting Gargariſms. A critical Squincy divers times proves deadly, by reaſon of the great falling down of the humor upon the throttle, by which the paſſage of the breath is ſuddenly ſhut up. Broths muſt be uſed made with Capons, and Veal ſeaſoned with Lettuce, Purſlain, Sorrel, and the cold Seeds.

Diet. If the Patient ſhall be ſomewhat weak, let him have potched Eggs, and Barly Creams, the Barly being ſomewhat boiled with Raiſons in Water and Sugar, and other meats of this kind. Let him be forbidden Wine, inſtead whereof he may uſe *Hydromelita*, and *Hydroſacchara*, that is, drinks made of Water and Honey, or Water and Sugar; as alſo Syrups of dried Roſes, of Violets, Sorrel and Limmons, and others of this kind. Let him avoid too much ſleep. But in the mean time the Phyſician muſt be careful of all, becauſe this diſeaſe is of their kind, which brook no delays. Wherefore

Cure. let the *Baſilica* be preſently opened, on that ſide the tumor is the greater; then within a ſhort time ter the ſame day, for evacuation of the conjunct matter, let the vein under the tongue be opened; let Cupping-Glaſſes be applied, ſometimes with Scarification, ſometimes without, to the neck and ſhoulders, and let frictions and painful ligatures be uſed to the extreme parts. But let the humor impact in the part be drawn away by Clyſters and ſharp Suppoſitories. Whilſt the matter is in

Repelling Gargariſms. defluxion, let the mouth without delay be waſhed with aſtringent Gargariſms to hinder the defluxion of the humor, leſt by its ſudden falling down it kill the Patient; as it often happens, all the Phyſicians care and diligence notwithſtanding. Therefore let the mouth be frequently waſhed with Oxycrate, or ſuch a Gargariſm; ℞ *Pomorum ſylveſt. nu.* iiij. *ſumach, Roſar. rub. an. m. ſſ. herber.* ʒ ii. let them be all boyled with ſufficient quantity of water to the conſumption of the half, adding thereunto of the Wine of four Pomgranats, ʒ iiij, of *Diamoron* ʒ ij, let it be a little more boyled, and make a gargle according to Art. And there may be other Gargariſms made of the waters of Plantain, Night-ſhade, Verjuyce, Julep of Roſes, and the like. But if the matter of the defluxion ſhall be Phlegmatick, Alum, Pomgranat-pill, Cypreſs-nuts, and a little Vinegar may be ſafely added. But

on

on the contrary, Repercuſſives muſt not be outwardly applied, but rather Lenitives, whereby the external parts may be relaxed and rarified, and ſo the way be open either for the diffuſing or reſolving the portion of the humor. You ſhall know the humour to begin to be reſolved, if the Feaver leave the Patient, if he ſwallow, ſpeak, and breathe more freely, if he ſleep quietly, and the pain begin to be much aſſwaged. Therefore then Nature's endeavour muſt be helped by applying reſolved medicines, or elſe by uſing Suppuratives inwardly and outwardly, if the matter ſeem to turn into *Pus*. Therefore let Gargariſms be made of the roots of Marſh-mallows, Figs, Jujubes, Damask-prunes, Dates, perfectly boyled in water. The like benefit may be had by Gargariſms of Cows-milk with Sugar, by Oyl of Sweet-almons, or Violets warm, for ſuch things help forward Suppuration and aſſwage pain; let ſuppurating Cataplaſms be applied outwardly to the neck and throat, and the parts be wrapped with wool moiſtned with Oyl of Lilies. When the Phyſician ſhall perceive that the humor is perfectly turned into *Pus*, let the Patients mouth be opened with the *Speculum oris*, and the abſceſs opened with a crooked and long Inciſion-knife; then let the mouth be now and then waſhed with cleanſing Gargles; as ℞ *Aquæ hordei lib. ſſ. mellis roſ. & ſyr. roſar. ſic. an.* ℥ i, *fiat gargariſma.* Alſo, the uſe of *ænomel*, that is, Wine and Honey, will be fit for this purpoſe. The Ulcer being cleanſed by theſe means, let it be cicatrized with a little Roch-Alum added to the former Gargariſms.

Ripening Gargariſms.

Detergent Gargariſms.

The Figure of an Inciſion-knife, opened out of the haft, which ſerves for a ſheath thereto.

CHAP. IX.

Of the Bronchocele, *or* Rupture *of the Throat.*

THat which the French call *Goetra*, that the Greeks call *Bronchocele*, the Latins *Gutturis Hernia*, that is, the Rupture of the throat. For it is a round tumor of the throat, the matter whereof coming from within outwards, is contained between the skin and weazon; it proceeds in women from the ſame cauſe as an *Aneuriſma*.

The reaſon of the name.

But this general name of *Bronchocele* undergoes many differences; for ſometimes it retains the nature of *Melicerides*, other-whiles of *Steatoma's*, *Atheroma's* or *Aneuriſma's*; in ſome there is found a fleſhy ſubſtance having ſome ſmall pain; ſome of theſe are ſmall, others ſo great, that they ſeem almoſt to cover all the throat; ſome have a ciſt, or bag, others have no ſuch thing; all, how many ſoever they be, and what end they ſhall have, may be known by their proper ſigns; theſe which ſhall be curable, may be opened with an actual or potential cautery, or with an Inciſion-knife. Hence, if it be poſſible, let the matter be preſently evacuated; but if it cannot be done at once, let it be performed at divers times, and diſcuſſed by fit remedies; and laſtly, let the ulcer be conſolidated and cicatrized.

The differences.

The Cure.

CHAP. X.

Of the Pleuriſie.

THe Pleuriſie is an inflammation of the membrane, inveſting the ribs, cauſed by ſubtile and cholerick blood; ſpringing upwards with great violence from the hollow vein into the *Azygos*, and thence into the intercoſtal veins, and is at length poured forth into the empty ſpaces of the intercoſtal muſcles, and the mentioned membrane. Being contained there, if it tend to ſuppuration, it commonly, infers a pricking pain, a Feaver, and difficulty of breathing. This ſuppurated blood is purged and evacuated one while by the mouth; the lungs ſucking it, and ſo caſting it into the weazon, and ſo into the mouth; otherwhiles by urin, and ſometimes by ſtool.

What it is.

Of a Pleuriſie coming to ſuppuration.

But if nature, being too weak, cannot expectorate the purulent blood poured forth into the capacity of the cheſt, the diſeaſe is turned into *Empyema*, wherefore the Chirurgeon muſt then be called, who beginning to reckon from below upwards, may make a vent between the third and fourth true and legitimate ribs; and that muſt be done either with an actual or potential cautery, or with a ſharp knife drawn upwards, towards the back, but not downwards, leſt the veſſels ſhould be violated which are diſſeminated under the rib. This apertion may be ſafely and eaſily performed by this actual cautery; it is perforated with four holes, through one whereof there is a pin put higher or lower, according to the depth and manner of your Inciſion: Then the point thereof is thruſt through a plate of Iron perforated alſo in the midſt, into the part deſigned by the Phyſician, leſt the wavering hand might peradventure touch, and ſo hurt the other parts not to be meddled withal. The ſame plate muſt be ſomewhat hollowed, that ſo it might be more eaſily fitted to the gibbous ſide, and bound by the corners on the contrary ſide with four ſtrings. Wherefore I have thought good here to expreſs the figures thereof.

Of the change thereof into an *Empyema*.

Of the aperti-on of the ſide in an *Empye-ma*.

The Figure of an actual Cautery, with its Plate fit to be uſed in a Pleuriſie.



But if the Patient ſhall have a large body, cheſt and ribs, you may divide and perforate the ribs themſelves with a Trepan; howſoever the apertion be made, the *pus*, or matter, muſt be evacuated by little and little at ſeveral times; and the capacity of the cheſt cleanſed from the purulent matter by a detergent injection of vi. ounces of Barley-water, and ℥ ii, Honey of Roſes, and other the like things mentioned at large in our cure of Wounds.

CHAP. XI.

Of the Dropſie.

What the Dropſie is.

THe Dropſie is a Tumor againſt nature by the abundance of wateriſh humor, of flatulencies, or Phlegm, gathered one while in all the habit of the body, otherwhiles in ſome part and that eſpecially in the capacity of the belly between the *Peritonæum* and entrails. From this diſtinction of places and matters, there ariſe divers kinds of Dropſies. Firſt, that Dropſie which fills that ſpace of the belly, is either moiſt or dry. The moiſt is called the *Aſcites*, by reaſon of the ſimilitude it hath with a leather-bottle, or *Borachio*, becauſe the wateriſh humor is contained in that capacity, as it were in ſuch a veſſel.

The differences thereof.

The dry is called the *Tympanites*, or Tympany, by reaſon the belly ſwollen with wind ſounds like a *Tympanum*, that is, a Drum. But when the whole habit of the body is diſtended with a phlegmatick humor, it is called *Anaſarca* or *Leucophlegmatia*. In this laſt kind of Dropſie the lower parts firſt ſwell, as which by reaſon of their ſite are moſt ſubject to receive defluxions, and more remote from the fountain of the native heat; wherefore if you preſs them down, the print of your finger will remain ſometime after; the Patients face will become pale and puffed up, whereby it may be diſtinguiſhed from the two other kinds of Dropſie. For in them firſt the belly, then by a certain conſequence the thighs and feet do ſwell. There are beſides alſo particular Dropſies, contained in the ſtrait bounds of certain places, ſuch are the *Hydrocephalus* in the head; the *Bronchocele* in the throat; the *Pleurocele* in the cheſt; the *Hydrocele* in the *Scrotum*, or cod; and ſo of the reſt. Yet they all ariſe from the ſame cauſe, that is, the weakneſs or defect of the altering or concocting faculties, eſpecially of the liver, which hath been cauſed by a *Scirrhus*, or any kind of great diſtemper, chiefly cold, whether it happen primarily, or ſecondarily by reaſon of ſome hot diſtemper diſſipating the native and inbred heat, ſuch a Dropſie is incurable; or elſe it comes by conſent of ſome other higher or lower part; for if in the lungs, midriff, or reins, there be any diſtemper, or diſeaſe bred, it is eaſily communicated to the gibbous part of the liver, by the branches of the hollow vein, which run thither. But if the miſchief proceed from the ſpleen, ſtomach, meſentery, guts, eſpecially the *jejunum* and *Ileum*, it creeps into the hollow ſide of the liver by the meſeraick veins, and other branches of the *Vena porta* or gate-vein. For thus ſuch as are troubled with the *Aſthma*, Ptiſick, Spleen, Jaundiſe, and alſo the Phrenſie, fall into a Dropſie.

The Symptomes.

The cauſes.

How divers diſeaſes turn into Dropſies.

Laſtly, All ſuch as have the menſtrual or hæmorrhoidal blood ſuppreſſed or too immoderately flowing contrary to their cuſtom, either overwhelms, diminiſheth or extinguiſheth the native heat; no otherwiſe than fire, which is ſuffocated by too great a quantity of wood; or dieth and is extinguiſhed for want thereof. We muſt look for the ſame from the excrements of the belly or bladder, caſt forth either too ſparingly or too immoderately: Or by too large quantity of meats too cold and raſhly devoured without any order. To conclude, by every default of external cauſes through which occaſion, errour may happen in diet or exerciſe.

The ſigns of an *Aſcites*.

The *Aſcites* is diſtinguiſhed from the two other kinds of Dropſies, both by the magnitude of the efficient cauſe, as alſo by the violence of the Symptoms, as the dejected appetite, thirſt, and ſwelling of the *Abdomen*. And alſo when the body is moved or turned upon either ſide, you may hear a ſound as of the joggling of water in a veſſel half full. Laſtly, the humor is diverſly driven upwards or downwards, according to the turning of the body and compreſſion of the *Abdomen*: It alſo cauſeth various Symptoms by preſſure of the parts to which it floweth. For it cauſeth difficulty of breathing and the cough by preſſing of the midriff; by ſweating through into the capacity of the cheſt, it cauſeth like Symptoms as the *Empyema*. Beſides alſo the Patients often ſeem, as it were, by the ebbing and flowing of the wateriſh humor, one while to be carried to the skies, and another whiles to be drowned in the water, which I have learn'd not by reading of any author, but by the report of the Patients themſelves. But if theſe wateriſh humors be fallen down to the lower parts, they ſuppreſs the excrements of the guts and bladder by preſſing and ſtraitning the paſſages. When the Patient

The Symptomes.

lies

lies on his back, the tumor ſeems leſs, becauſe it is ſpread on both ſides: On the contrary, when he ſtands or ſits, it ſeems greater, for that all the humor is forced or driven into the lower belly, whence he feels a heavineſs in the *Pecten* or ſhare. The upper parts of the body fall away by defect of the blood fit for nouriſhment in quality and conſiſtence, but the lower parts ſwell by the flowing down of the ſerous and wateriſh humor to them. The pulſe is little, quick, and hard with tention.

This diſeaſe is of the kind of Chronical or long diſeaſes; wherefore it is ſcarce, or never cured, eſpecially in thoſe who have it from their Mothers womb, who have the action of their ſtomach depraved; and thoſe who are cachectick, and old; and laſtly, all ſuch as have the natural faculty languiſhing and faulty. Prognoſticks.

On the contrary, young and ſtrong men, eſpecially if they have no feaver, and finally all who can endure labour, and thoſe exerciſes which are fit for curing this diſeaſe, eaſily recover; principally if they uſe a Phyſician, before the water which is gathered together do putrefie and infect the bowels by its contagion.

CHAP. XII.

Of the cure of the Dropſie.

THe beginning of the cure muſt be with gentle and mild medicines; neither muſt we come to a *Paracenteſis*, unleſs we have formerly uſed and tried theſe. Therefore, it ſhall be the part of the Phyſician to preſcribe a drying diet, and ſuch medicines as carry away water, both by ſtool and urine, *Hippocrates* ordains this powder for Hydropick perſons. ℞ *Canthar. ablatis capitib. & aliis* ʒʃ *comburantur in furno, & fiat pulvis*; of which adminiſter two grains in white wine; for, nature, helped by this, and the like remedies, hath not ſeldom been ſeen to have cured the Dropſie. But that we may haſten the cure, it will be available to ſtir up the native heat of the part by application of thoſe medicines which have a diſcuſſing force; as bags, baths, ointments, and Emplaiſters. Let bags be made of dry and harſh Bran, Oats, Salt, Sulphur, being made hot; or, for want of them, of Sanders or Aſhes often heated. *Hip. lib. 4. de acut. & lib. de intern.* Bags.

The more effectual baths are Salt, Nitrous, and Sulphurous waters, whether by nature or art, that is, prepared by the diſſolution of Sal, Nitre, and Sulphur; to which if Rue, Marjoram, the leaves of Fennel, and tops of Dill, of *Stœchas*, and the like, be added, the buſineſs will go better forwards. Let bags be made of the oyl of Rue, Dill, Bays, and Squills, in which ſome *Euphorbium*, Pellitory of *Spain*, or Pepper, have been boiled. Let Plaiſters be made of Frankincenſe, Myrrh, Turpentine, *Coſtus*, Bayberries, Engliſh Galengal, Honey, the dung of Oxen, Pigeons, Goats, Horſes, and the like, which alſo may be applied by themſeves. If the diſeaſe continue, we muſt come to *Sinapiſms* and *Phœnigms*, that is, to rubrifying and veſicatory medicines. When the bliſters are raiſed, they muſt be anointed again, that ſo the water may by little and little flow ſo long until the humor be exhauſted, and the Patient reſtored to health. Baths. Liniments. Emplaiſters. Veſicatories.

Galen writes, the Husbandmen in *Aſia*, when they carried wheat out of the Countrey into the City in Cars, when they would ſteal away and not be taken, hide ſome ſtone-jugs fill'd with water in the midſt of the Wheat; for that will draw the moiſture through the jugs into it ſelf, and increaſe both the quantity and weight. When certain pragmatical Phyſicians had read this, they thought that Wheat had force to draw out the water, ſo that if any ſick of the Dropſie ſhould be buried in a heap of Wheat, it would draw out all the water. *Gal. lib. de facul. natur. 1.*

But if the Phyſician ſhall profit nothing by theſe means, he muſt come to the exquiſitly chief remedy, that is, to *Paracenteſis*. Of which becauſe the opinions of the ancient Phyſicians have been diverſe, we will produce and explain them. Divers opinions of *Paracenteſis*, or opening of the belly.

Thoſe therefore which diſallow *Paracenteſis*, conclude it dangerous for three reaſons: The firſt, becauſe by pouring out the contained water, together with it, you diſſipate and reſolve the ſpirits, and conſequently the natural, vital, and animal faculties. Another opinion is, becauſe the liver wanting the water by which formerly it was born up, thence-forward hanging down by its weight, depreſſeth and draweth downwards the midriff and the whole cheſt, whence a dry cough, and a difficulty of breathing proceed. The third is, becauſe the ſubſtance of the *Peritonæum*, as that which is nervous, cannot be pricked or cut without danger, neither can that which is pricked or cut, be eaſily agglutinated and united, by reaſon of the ſpermatick and bloodleſs nature thereof. *Eraſiſtratus* moved by theſe reaſons, condemned *Paracenteſis* as deadly: Alſo, he perſwaded that it was unprofitable, for theſe following reaſons; *viz.* Becauſe the water poured forth, doth not take away with it the cauſe of the Dropſie, and the diſtemper and hardneſs of the liver, and of the other bowels, whereby it comes to paſs that by breeding new waters they may eaſily again fall into the Dropſie. And then the Feaver, the thirſt, the hot and dry diſtemper of the bowels, all which were mitigated by the touch of the included water, are aggravated by the abſence thereof, being poured forth; Which thing ſeemeth to have moved *Avicen* and *Gordonius* that he ſaid none, the other ſaid very few, lived after the *Paracenteſis*: But the refutation of all ſuch reaſons is very eaſie. Reaſons againſt it. *Eraſiſtratus* his reaſons againſt it.

For, for the firſt; *Galen* infers that harmful diſſipation of ſpirits, and reſolving the faculties happens, when the *Paracenteſis* is not diligently, and artificially performed. As in which the water is preſently poured forth; truly, if that reaſon have any validity, Phlebotomy muſt ſeem to be removed far from the number of wholſome remedies, as whereby the blood is poured forth, which hath far more pure and ſubtil ſpirits, than thoſe which are ſaid to be diffuſed and mixed with the Dropſie-waters. But that danger which the ſecond reaſon threatens ſhall eaſily be avoided; the Patient being deſired to lie upon his back in his bed, for ſo the liver will not hang down. But for the third reaſon, the fear of pricking the *Peritonæum*, is childiſh: For thoſe evils which follow upon wounds of the nervous parts, happen by reaſon of the exquiſite ſenſe of the part, which in the *Peritonæum* ill affected and altered by the contained water, is either none or very ſmall. But reaſon Reaſons for it.

and

and experience teach, many nervous parts, alſo the very membranes themſelves being far removed from a fleſhy ſubſtance, being wounded admit cure; certainly much more the *Peritonæum*, as that which adheres ſo ſtraitly to the muſcles of the *Abdomen*, that the diſſector cannot ſeparate it from the fleſh, but with much labour. But the reaſon which ſeems to argue the unprofitableneſs of *Paracenteſis* is refelled by the authority of *Celſus*. I, ſaith he, am not ignorant that *Eraſiſtratus* did not like *Paracenteſis*; for he thought the Dropſie to be a diſeaſe of the Liver, and ſo that it muſt be cured; and that the water was in vain let forth, which, the liver being vitiated, might grow again. But firſt, this is not the fault of this bowel alone, and then although the water had his original from the liver, yet unleſs the water which ſtayeth there contrary to Nature be evacuated, it hurteth both the liver, and the reſt of the inner parts, whilſt it either increaſeth their hardneſs, or at the leaſt keepeth it hard, and yet notwithſtanding it is fit the body be cured. And although the once letting forth of the humor profit nothing, yet it makes way for medicines, which while it was there contained, it hindered. But this ſerous, ſalt, and corrupt humor is ſo far from being able to mitigate a feaver and thirſt, that on the contrary it increaſeth them. And alſo it augmenteth the cold diſtemper, whilſt by its abundance it overwhelms and extinguiſheth the native heat. But the authority of *Celius Aurelianus* that moſt noble Phyſician, though a Methodick, may ſatisfie *Avicen* and *Gordonius*. They, ſaith he, which dare avouch that all ſuch as have the water let out by opening their belly have died, do lie; for we have ſeen many recover by this kind of remedy: But if any died, it hapned either by the default of the ſlow or negligent adminiſtration of the *Paracenteſis*. I will add this one thing which may take away all errour or controverſie; we unwiſely doubt of the remedy when the Patient is brought to that neceſſity, that we can only help him by that means.

Lib. 3. *cap.* 21.

Lib. de morb. Ch. cap. de Hydrope.

The places of the apertion muſt be divers according to the parts chiefly affected.

Now muſt we ſhew how the belly ought to be opened. If the Dropſie happen by fault of the liver, the ſection muſt be made on the left ſide; but if of the ſpleen, in the right: for if the Patient ſhould lie upon the ſide which is opened, the pain of the wound would continually trouble him, and the water running into that part where the ſection is would continually drop, whence would follow a diſſolution of the faculties. The ſection muſt be made three fingers breadth below the navel, to wit, at the ſide of the right muſcle, but not upon that which they call the *Linea Alba*; neither upon nervous parts of the reſt of the muſcles of the *Epigaſtrium*; that ſo we may prevent pain and difficulty of hearing. Therefore we muſt have a care that the Patient lye upon his right ſide, if the Inciſion be made in the left, or on the left, if in the right. Then the Chirurgion both with his own hand, as alſo with the hand of his ſervant aſſiſting him, muſt take up the skin of the belly, with the fleſhy pannicle lying under it, and ſeparate them from the reſt; then let him divide them ſo ſeparated with a ſection even to the fleſh lying under them; which being done, let him force as much as he can the divided skin upwards towards the ſtomach, that when the wound, which muſt preſently be made in the fleſh lying there-under, ſhall be conſolidated, the skin, by its falling therein, may ſerve for that purpoſe; then therefore let him divide the muſculous fleſh and *Peritonæum* with a ſmall wound, not hurting the kall or guts.

The manner of making apertion.

Then put into the wound a trunk, or golden, or ſilver crooked pipe, of the thickneſs of a Gooſe-quill, and of the length of ſome half a finger. Let that part of it which goes into the capacity of the belly have ſomething a broad head, and that perforated with two ſmall holes, by which a ſtring being faſtened, it may be bound ſo about the body, that it cannot be moved, unleſs at the Chirurgeons pleaſure. Let a ſponge be put into the pipe, which may receive the dropping humor; and let it be taken out when you would evacuate the water; but let it not be poured out all together, but by little and little for fear of diſſipation of the ſpirits, and reſolution of the faculties, which I once ſaw happen to one ſick of the Dropſie. He being impatient of the diſeaſe and cure thereof, thruſt a Bodkin into his belly, and did much rejoyce at the pouring forth of the water, as if he had been freed from the humor and the diſeaſe, but died within a few hours, becauſe the force of the water running forth, could by no means be ſtaid, for the Inciſion was not artificially made. But it will not be ſufficient to have made way for the humor by the means afore-mentioned, but alſo the external orifice of the pipe muſt be ſtopped and ſtrengthened by double clothes, and a ſtrong ligature, leſt any of the water flow forth againſt our wills. But we muſt note, that the pipe is not to be drawn out of the wound, before as much water ſhall be iſſued forth as we deſire, and the tumor requireth; for once drawn forth, it cannot eaſily be put in again, and without force and pain be fitted to the lips of the wound, becauſe the skin and fleſhy pannicle cover it by their falling into the wound of the fleſh or muſcle. But whilſt the water is in evacuation, we muſt have a diligent care of feeding the Patient, as alſo of his ſtrength; for if that fail, and he ſeem to be debilitated, the effuſion of the water muſt be ſtayed for ſome days, which at the length performed according to our deſire, the wound muſt be ſo conſolidated that the Chirurgeon beware it degenerate not into a Fiſtula.

A Hiſtory.

A caution for taking out the pipe.

The Figure of a Pipe in form of a Quill, to evacuate the water in Dropſies.



Another manner of evacuating the water after the apertion.

Others perform this buſineſs after another manner; for, making an Inciſion, they thruſt through the lips of the wound with a needle and thred; but they take up much of the fleſhy ſubſtance with the needle, leſt that which is taken up ſhould be rent and torn by the forcible drawing of the lips together. Then the thred it ſelf is wrapped up and down over both ends of the needle, ſo thruſt through, as is uſually done in a hare-lip, that ſo the lips of the wound may ſo cloſely cohere, that not a drop of water may get out againſt the Chirurgeons will. Sometimes ſuch as are cured and healed of the Dropſie, fall into the Jaundiſe, whom I uſually cure after this manner.

A medicine for the Jaundiſe.

℞. *ſterc. anſer.* ℥ ij. diſſolve it in ℥ iij, *vini. alb. coletur*: Make a Potion, and let it be given two hours before meat.

CHAP.

CHAP. XIII.

Of the tumor and relaxation of the Navel.

THe *Exomphalos* or ſwelling of the navel, is cauſed by the *Peritonæum*, either relaxed or broken; for by this occaſion oft-times the guts, and oft-times the kall, fall into the ſeat of the navel, and ſometimes ſuperfluous fleſh is there generated; otherwiſe, this tumor is as an *Aneuriſma* by too great a quantity of blood poured forth in that place: Otherwiſe by a flatulent matter, and ſometimes by a wateriſh humor. If the humor be occaſioned by the kall, the part it ſelf will retain his proper colour, that is, the colour of the skin; the tumor will be ſoft and almoſt without pain, and which will recide without noiſe, either by the preſſure of your fingers, or of it ſelf when the Patient lieth on his back; but tumor cauſed by the guts, is more unequal, and when it is forced in by the preſſure of your fingers, there is ſuch a noiſe heard, as in the *Enterocele*; but if the tumor proceed of ſuperfluous fleſh it will be harder and more ſtubborn, not eaſily retiring into the body, although the Patient lie upon his back, and you preſs it with your fingers.

The divers cauſes thereof.

Signs hereof occaſioned by the kall.

By the guts.

By Fleſh.

The tumor is ſofter which proceeds of wind, but which will not retire into the body, and ſounds under your nail like a taber. If the ſwelling be cauſed by a wateriſh humor, it hath all things common with the flatuous tumor, except that it is not ſo viſible and without noiſe. If it be from effuſion of blood, it is of a livid colour; but if the effuſed blood ſhall be arterial, then there are the ſigns of an *Aneuriſma*. Wherefore when the tumor is cauſed by the guts, kall, wind or a wateriſh humor, it is cured by Chyrurgery; but not if it proceed from a fleſhy excreſcence or ſuffuſion of blood. The tumor of the navel proceeding from the kall and guts, the Patient muſt lie upon his back to be cured; and then the kall and guts, muſt with your fingers be forced into their due place: Then the skin with which the tumor is circumſcribed muſt be taken up with your fingers, and thruſt through with a needle, drawing after it a double twined and ſtrong thred; then it muſt be ſcarified about the ſides, that ſo it may be the eaſier agglutinated. Then muſt it be thruſt through with a needle three or four times, according to the manner and condition of the diſtention and tumor. And ſo twitch it ſtrongly with a thred, that the skin which is ſo bound may at length fall off together with the ligature. But alſo you may cut off the skin ſo diſtended even to the ligature, and then cicatrize it, as ſhall be fit. A flatulent tumor of the navel ſhall be cured with the ſame remedies, as we ſhall hereafter mention in the cure of a windy rupture, but the watery may be poured forth by making a ſmall incition. And the wound ſhall be kept open ſo long, untill all the water be drained forth.

By wind.

By a wateriſh humor.

By bruiſed blood.

Which may be cured by Chirurgery, which not.

The cure by Chirurgery.

CHAP. XIV.

Of the Tumors of the Groins and Cods called Herniæ, *that is, Ruptures.*

THe ancient Phyſicians have made many kinds of Ruptures, yet indeed there are only three to be called by that name, that is, the *Inteſtinalis*, or that of the guts; the *Zirbalis*, or that of the kall; and, that which is mixed of them both. The other kinds of Ruptures have come into this order, rather by ſimilitude, than any truth of the thing; for in them the gut or kall do not forſake their places.

There are only three ſorts of Ruptures.

The Greeks have given to all theſe ſeveral names, both from the ſeat of the tumor, as alſo from their matter. For thus they have called an unperfect rupture which deſcends not beyond the groins, nor falls down into the cods, *Bubonocele:* but the compleat which penetrates into the cod, if it be by falling down of the gut, *Enterocele:* if from the kall, *Epiplocele*; if from them both together, they name it *Entero-epiplocele:* but if the tumor proceed from a wateriſh humor, they term it *Hydrocele:* if from wind, *Phyſocele*; if from both, *Hydro-phyſocele*; if a fleſhy excreſcence ſhall grow about the teſticle, or in the ſubſtance thereof, it is named *Sarcocele.* If the veins interwoven, and divaricated divers ways, ſhall be ſwoln in the cod and teſticles, the tumor obtains the name of a *Cirſocele.* But if the humors ſhall be ſhut up or ſent thither, the name is impoſed upon the tumor, from the predominant humor, as we have noted in the beginning of our Tractate of Tumors. The cauſes are many, as, all too violent motions, a ſtroke, a fall from a high place, vomiting, a cough, leaping, riding upon a trotting horſe, the ſounding of trumpets, or ſackbuts, the carrying or lifting up of a heavy burthen, racking, alſo the too immoderate uſe of viſcid and flatulent meats; for all ſuch things may either relax or break the *Peritonæum*, as that which is a thin and extended membrane. The ſigns of a *Bubonocele* are a round tumor in the groin, which preſſed, is eaſily forced in. The ſigns of an *Enterocele* are a hard tumor in the cod, which forced, returneth back and departeth with a certain murmur and pain; but the tumor proceeding of the kall, is lax and feels ſoft like wool, and which is more difficultly forced in, than that which proceeds from the guts, but yet without murmuring and pain; for the ſubſtance of the guts, ſeeing it is one, and continued to it ſelf, they do not only mutually ſucceed each other, but by a certain conſequence do, as in a dance, draw each other, ſo to avoid diſtention, which in their membranous body cannot be without pain, by reaſon of their change of place from that which is natural, into that againſt nature: None of all which can befal the kall, ſeeing it is a ſtupid body, and almoſt without ſenſe, heavy, dull, and immoveable. The ſigns that the *Peritonæum* is broken, are the ſudden increaſe of tumor, and a ſharp and cutting pain; for when the *Peritonæum* is only relaxed, the tumor groweth by little and little, and ſo conſequently with ſmall pain; yet ſuch pain returns ſo often, as the tumor is renewed by the falling down of the gut, or kail, which happens not to the *Peritonæum* being broken: for the way being once open, and paſſable to the falling body, the tumor is renewed without any diſtention, and ſo without any pain to ſpeak of.

Bubonocele.

Enterocele and *Epiplocele.*

Hydrocele.

Phyſocele.

Sarcocele.

Cirſocele.

The cauſes.

The ſigns.

The reſt of the ſigns ſhall be handled in their places. Sometimes it happens that the guts and kall, do firmly adhere to the proceſs of the *Peritonæum*, that they cannot be driven back into their proper ſeat. This ſtubborn adheſion happens by the intervention of the viſcid matter, or by means of ſome excoriation cauſed by the rude hand of a Chirurgeon, in too violently forcing of the gut, or kall, into their place. But alſo, too long ſtay of the gut in the cod, and the neglect of wearing a Truſs, may give occaſion to ſuch adheſion. A perfect and inveterate Rupture by the breaking of the proceſs of the *Peritonæum* in men of full growth, never, or very ſeldom admits of cure. But you muſt note, that by great Ruptures of the *Peritonæum*, the guts may fall into the cod, to the bigneſs of a mans head, without much pain and danger of life, becauſe the excrements, as they may eaſily enter, by reaſon of the largeneſs of the place and Rupture, ſo alſo they may eaſily return.

What Rupture is uncureable.

CHAP. XV.

Of the Cure of Ruptures.

To what Ruptures children are ſubject.

BEcauſe children are very ſubject to Ruptures, but thoſe truly not fleſhy or varicous, but watry, windy, and eſpecially of the guts, by reaſon of continual and painful crying and coughing: Therefore in the firſt place we will treat of their cure. Wherefore the Chirurgeon, called to reſtore the gut which is faln down, ſhall place the child, either on a table, or in a bed, ſo that his head ſhall be low, but his buttocks and thighs higher; then ſhall he force with his hands by little and little, and gently, the gut into the proper place; and ſhall foment the groin with the aſtringent Fomentation, deſcribed in the falling down of the womb. Then let him apply this remedy: ℞ *Præſcript. decoctionis quantum ſufficit, farinæ hordei & fabarum, an.* ℥ i, *pulver. Aloes, Maſtithes, Myrtill. & Sarcocc. an.* ℥ ſ, *Boli Armeni* ℥ ij. Let them be incorporated and made a Cataplaſm according to art. For the ſame purpoſe he may apply *Emplaſtrum contra Rupturam:* but the chief of the cure conſiſts in folded Clothes, and Truſſes, and Ligatures artificially made, that the reſtored gut may be contained in its place, for which purpoſe he ſhall keep the child ſeated in his cradle for thirty or forty days, as we mentioned before; and keep him from crying, ſhouting, and coughing; *Aetius* bids, ſteep paper three days in water, and apply it made in a ball to the groin, the gut being firſt put up; for that remedy by three days adheſion will keep it from falling down. But it will be, as I ſuppoſe, more effectual, if the paper be ſteeped not in common, but in the aſtringent water, deſcribed in the falling down of the womb. Truly I have healed many by the help of ſuch remedies, and have delivered them from the hands of the Gelders, which are greedy of childrens teſticles, by reaſon of the great gain they receive from thence. They by a crafty cozenage, perſwade the Parents, that the falling down of the gut into the cod, is uncurable: Which thing, notwithſtanding experience convinceth to be falſe, if ſo be the cure be performed according to the fore-mentioned manner, when the *Peritonæum* is only relaxed, and not broken: for the proceſs thereof by which the gut doth fall as in a ſteep way, in progreſs of time and age is ſtraitned and knit together, whilſt alſo in the mean time the guts grow thicker.

An aſtringent Cataplaſm.

Ser. 1. *c.* 24.

The craft and covetouſneſs of Gelders.

Another way to cure Ruptures.

A certain Chirurgeon who deſerveth credit, hath told me that he hath cured many children, as thus, He beats a Loadſtone into fine powder, and gives it in pap, and then he anoints with honey the groin, by which the gut came out, and then ſtrewed it over with fine filings of Iron. He adminiſtred this kind of remedy for ten or twelve days: The part for other things being bound up with a Ligature and Truſs as was fitting. The efficacy of this remedy ſeemeth to conſiſt in this; that the Loadſtone by a natural deſire of drawing the Iron which is ſtrewed upon the groin, joyns to it the fleſhy and fatty particles interpoſed between them, by a certain violent impetuoſity, which on every ſide preſſing and bending the looſneſs of the *Peritonæum*, yea verily adjoyning themſelves to it, in proceſs of time by a firm adheſion intercept the paſſage and falling down of the gut or kall; which may ſeem no more abhorring from reaſon, than that we behold the Loadſtone it ſelf through the thickneſs of a table, to draw Iron after it any way. The ſame Chirurgeon affirmed, that he frequently and happily uſed the following medicine. He burnt into aſhes in an oven red Snails, ſhut up in an earthen pot, and gave the powder of them to little children, in pap; but to thoſe which were bigger in broth.

The reaſon of this cure.

Another medicine.

But we muſt deſpair of nothing in this diſeaſe, for the cure may happily proceed in men of full growth, as of forty year old, who have filled the three dimenſions of the body, as this following relation teſtifies.

A notable Hiſtory.

There was a certain Prieſt in the Pariſh of St. *Andrews*, called *John Moret*, whoſe office was to ſing an Epiſtle with a loud voice as often as the ſolemnity of the day, and the thing required. Wherefore ſeeing he was troubled with the *Enterocele*, he came to me, requiring help, ſaying, he was troubled with a grievous pain, eſpecially then, when he ſtretched his voice in the Epiſtle. When I had ſeen the bigneſs of the *Enterocele*, I perſwaded him to get another to ſerve in his place; ſo having gotten leave of M. *Curio*, Clerk and Deacon of Divinity, he committed himſelf unto me: I handled him according unto art, and commanded him he ſhould never go without a Truſs; and he followed my directions. When I met him ſome five or ſix years after, I asked him, How he did? he anſwered, Very well, for he was wholly freed from the diſeaſe, with which he was formerly troubled; which I could not perſwade my ſelf of, before that I had found that he had told me the truth, by the diligent obſervation of his genitals. But ſome ſix months after, he dying of a Pleuriſie, I came to *Curio*'s houſe where he died, and deſired leave to open his body, that I might obſerve whether Nature had done any thing at all in the paſſage through which the gut fell down: I call God to witneſs, that I found a certain fatty ſubſtance about the proceſs of the *Peritonæum* about the bigneſs of a little Egg, and it did ſtick ſo hard to that place, that I could ſcarce pull it away without the rending of the neighbouring parts. And this was the ſpeedy cauſe of his

We muſt never deſpair in diſeaſes, if ſo be Nature be aſſociated by Art.

his cure. But it is moſt worthy of obſervation and admiration, that Nature but a little helped by art, healeth diſeaſes which are thought incurable. The chief of the cure conſiſts in this, that we firmly ſtay the gut in its place, after the ſame manner as theſe two Figures ſhew.

The Figure of a man broken on one ſide, wearing a Truſs whoſe Bolſter muſt have three Tuberoſities, two on the upper, and one on the lower part; and there muſt be a hollowneſs between them in the midſt, that they may not too ſtraitly preſs the ſhare-bone, and ſo cauſe pain. The manner of ſuch a Truſs, I found out not long ago, and it ſeemed better and ſafer than the reſt for to hinder the falling down of the gut and kall.

A *Shews the ſhoulder-band which is tied before and behind to the girdle of the Truſs.*
B *The Truſs.*
C *The Cavity left in the midſt of the Tuberoſities.*

Another Figure of a Man having a Rupture on both ſides, ſhewing by what means, with what kind of and what ſhoulder-band he muſt be bound on each groin.

A *ſheweth the ſhoulder-band divided in the midſt for the putting through of the head.*
B *The Truſs, with two Bolſters, between which is a hole for putting through the yard. The form of both Bolſters ought to be the ſame with the former.*

In the mean time we muſt not omit diet. We muſt forbid the uſe of all things, which may either relax, dilate, or break the proceſs of the *Peritonæum*, of which I have already treated ſufficiently. Sometimes, but eſpecially in old men, the guts cannot be reſtored into their place, by reaſon of the quantity of the excrements hardned in them: In this caſe they muſt not be too violently forced, but the Patient muſt be kept in his bed; and, lying with his head low, and his knees higher let the following Cataplaſms be applied.

℞ *Rad. alth. & lil. ana* ℥ ij. *Seminis lini & fænugr. an.* ℥ ß, *fol. malvæ, & viol. pariet. an. m.* ſ. Let them be boiled in fair water, afterwards beaten, and drawn through a ſearſe, adding thereto of new Butter without Salt, and Oyl of Lilies as much as ſhall ſuffice. Make a Cataplaſm in the form of a liquid Pultis. Let it be applied hot to the cod, and bottom of the belly; by the help of this remedy when it had been applied all night, the guts have not ſeldom been ſeen of themſelves, without the hand of a Chirurgeon, to have returned into their proper place. The windineſs being reſolved, which hindered the going back of the excrements into another gut, whereby they might be evacuated and expelled. But if the excrements will not go back thus, the flatulencies, yet reſiſting undiſcuſſed, an emollient and carminative clyſter is to be admitted, with a little Chymical Oyl of Turpentine, Dill, Juniper, or Fennil. Clyſters of Muſcadine, Oyl of Walnuts, and *Aqua vitæ*, and a ſmall quantity of any the aforeſaid Oyls, are good for the ſame purpoſe. A Cataplaſm to ſoften the excrements. Chymical oyl.

It often happens that the guts cannot yet be reſtored, becauſe the proceſs of the *Peritonæum* is not wide enough. For when the excrements are fallen down with the gut into the cod; they grow hard by little and little, and increaſe by the acceſs of flatulences cauſed by reſolution, which cauſe ſuch a tumor as cannot be put up through that hole, by which a little before it fell down: Whereby it happens that by putrefaction of the matter there contained, come inflammations, and a new acceſs of pain; and laſtly, a vomiting and evacuation of the excrements by the mouth, being hindered from the other paſſage of the fundament. They vulgarly call this affect *Miſerere mei.* That you may help this ſymptom, you muſt rather aſſay extreme remedies, than ſuffer the Patient to die by ſo filthy and loathſom a death. And we muſt cure it by Chirurgery, after this manner following. We will bind the Patient lying on his back, upon a table or bench; then preſently make an Inciſion in the upper part of the cod, not touching the ſubſtance of the gut; then we muſt have a ſilver Cane or Pipe, of the thickneſs of a Gooſe-quil, round and gibbous in one part thereof, but ſomewhat hollowed in the other, as is ſhewed by this following Figure.

The Figure of the Pipe or Cane.

The Chirurgical cure by the Golden tie.

We muſt put it into the place of the Inciſion, and put it under the production of the *Peritonæum* being cut together with the cod, all the length of the production, that ſo with a ſharp knife we may divide the proceſs of the *Peritonæum*, according to that cavity ſeparated from the guts there contained, by the benefit of the Cane in a right line not hurting the guts. When you have made an indifferent Inciſion, the guts muſt gently be put up into the belly with your fingers, and then ſo much of the cut *Peritonæum* muſt be ſowed up, as ſhall ſeem ſufficient, that by that paſſage made more ſtrait, nothing may fall into the cod after it is cicatrized.

But if there be ſuch abundance of excrements hardned, either by the ſtay or heat of inflammation, that that Inciſion is not ſufficient to force the excrements into their place, the Inciſion muſt be made longer, your Cane being thruſt up towards the belly: So that it may be ſufficient for the free regreſs of the guts into the belly. Then ſow it up as is fit, and the way will be ſhut up againſt the falling down of the gut or kall; the proceſs of the *Peritonæum* being made more ſtrait, by reaſon of the future; for the reſt, the wound ſhall be cured according to Art. But before you undertake this work, conſider diligently whether the ſtrength of the Patient be ſufficient, neither attempt any thing before you have foretold, and declared the danger to the Patients friends.

CHAP. XVI.

Of the Golden Ligature, or the Punctus Aureus, *as they call it.*

IF the Rupture will not be cured by all theſe means, by reaſon of the great ſolution of the continuity of the relax'd or broken *Peritonæum*, and the Patient by the conſent of his friends there preſent, is ready to undergo the danger in hope of recovery; the cure ſhall be attempted by that which they call the *Punctus aureus*, or Golden tie.

For which purpoſe a Chirurgeon which hath a skilful and ſure hand, is to be imployed, He ſhall make an Inciſion about the ſhare-bone, into which he ſhall thruſt a Probe like to the Cane, a little before deſcribed; and thruſt it long-ways under the proceſs of the *Peritonæum*, and by lifting it up, ſeparate it from the adjoyning fibrous, and nervous bodies, to which it adheres; then preſently draw aſide the ſpermatick veſſels, with the *Cremaſter*, or hanging muſcle of the teſticle; which being done, he ſhall draw aſide the proceſs it ſelf, alone by it ſelf: And he ſhall take as much thereof as is too lax, with ſmall and gentle mullets, perforated in the midſt, and ſhall with a needle, having five or ſix threds, thruſt it through as near as he can to the ſpermatick veſſels, and Cremaſter muſcles. But the needle alſo muſt be drawn again in to midſt of the remnant of the proceſs, taking up with it the lips of the wound; then the thred muſt be tied on a ſtrait knot, and ſo much thereof muſt be left after the Section, as may be ſufficient to hang out of the wound. This thred will of it ſelf be diſſolved by little and little by putrefaction: Neither muſt it be drawn out before that Nature ſhall regenerate and reſtore fleſh into the place of the ligature, otherwiſe all our labour ſhall be ſpent in vain.

And laſtly, Let the wound be cleanſed, filled with fleſh, and cicatrized, whoſe callous hardneſs may withſtand the falling of the gut or kall.

Another manner thereof.

There are ſome Chirurgeons who would perform this Golden Ligature after another manner. They cut the skin above the ſhare-bone where the falling down commonly is, even to the proceſs of the *Peritonæum*, and they wrap once or twice about it, being uncovered, a ſmall Golden Wire, and only ſtraiten the paſſage as much as may ſuffice to amend the looſneſs of this proceſs, leaving the ſpermatick veſſels at liberty; then they twiſt the ends of the wire twice or thrice with ſmall mullets, and cut off the remnant thereof; that which remains after the cutting, they turn in,

left

leſt with the ſharpneſs they ſhould prick the fleſh growing upon it. Then leaving the Golden Wire there, they cure the wound like to other ſimple wounds, and they keep the Patient ſome fifteen or twenty days in his bed, with his knees ſomething higher, and his head ſomething lower.

Many are healed by this means; others have fallen again into the diſeaſe by reaſon of the ill twiſting of the wire.



A *Shews a crooked needle having an eye not far from the point, through which you may put the Golden Wire.*

B B *The Golden Wire put through the eye of of the needle.*

C *The Mullets or Pincers, to cut away the waſte or ſuperfluous ends of the wire.*

D *The ſpring of the Mullets.*

E *The Mullets to twiſt the ends of the wire together.*

There is alſo another manner of this Golden tie, which I judge more quick and ſafe, even for that there is no external body left in that part after the cure. Wherefore they wrap a leaden wire inſtead of the golden, which comes but once about the proceſs of the *Peritonæum*, then twine it as much as need requires; that is, not too looſly, leſt it ſhould leave way for the falling down of the body, neither too ſtraitly, leſt a Gangrene ſhould come by hindering the paſſage of the ſpirits and nouriſhment. The ends thereof are ſuffered to hang out; when in the proceſs of time, this contraction of the *Peritonæum* ſeems callous, then the wire is untwiſted and gently drawn out. And the reſt of the cure performed according to Art. But let not the Chirurgeon thruſt himſelf upon his work raſhly, without the advice of the Phyſician, for it divers times comes to paſs, that the teſticles are not as yet fallen down into the cod by the too great ſluggiſhneſs of Nature, in ſome of a pretty growth; but remains long in the groins, cauſing a tumor with pain, which thing may make a good Chirurgeon believe that it is an *Enterocele*. Therefore whilſt he labours by repelling medicines and truſſes to force back this tumor, he increaſeth the pain, and hinders the falling down of the teſticles into the cod. I obſerved this not long ago in a Boy, which an unskilful Chirurgion had long, and grievouſly troubled, as if he had a rupture: For when I had obſerved that there was but one ſtone in the cod, and knew the Boy was never gelt; I bid them caſt away the Plaiſters and Truſſes, and wiſh'd his Parents that they ſhould ſuffer him to run and leap, that ſo the idling ſtone might be drawn into the cod, which thing by little and little, and without pain, had the event as I foretold.

The third manner thereof.

A thing to be noted.

A Hiſtory.

That the reaſon of this affect may be underſtood, we muſt know that man differs from a woman, only in efficacy of heat; but it is the nature of ſtrong heat to drive forth, as of cold to keep in. Hence it is that the ſtones in men hang forth in the cod, but in women they lie hid in the lower belly. Therefore it happens that in ſome males more cold by Nature, the teſticles are ſhut up ſome certain time, until at length they are forc'd down into the cod by youthful heat. But that we may return to our former Treatiſe of the Cod, although that way of curing Ruptures wants not pain and danger, yet is ſafer than that which is performed by gelding, which by the cruelty thereof expoſes the Patient to manifeſt danger of death. For the Gelders while they fear leſt when the cure is finiſhed, the relaxation may remain, pull with violence the proceſs of the *Peritonæum* from the parts to which it adheres, and together with it a nerve of the ſixth conjugation which runs to the ſtones; they offer the ſame violence to the ſpermatick veſſels; by which things enſue great pain, convulſion, efflux of blood, inflammation, putrefaction, and laſtly death, as I have obſerved in many whom I have diſſected, having died a few days after their gelding. Although ſome eſcape theſe dangers, yet they are deprived of the faculty of generation for all their life after;

for performance whereof, Nature hath beſtowed the teſticles, as parts principally neceſſary for the conſervation of mankind. Through which occaſion *Galen* hath not feared to prefer them before the heart, becauſe the heart is the beginning of life, but the teſticles of a better life; for it is far more noble to live well, than ſimply and abſolutely to live; therefore Eunuchs degenerate into a womaniſh nature; for they remain without beards, their voice is weak, their courage fails them, and they turn cowards; and ſeeing they are unfit for all human actions, their life cannot but be miſerable. Wherefore I will never ſubſcribe to the cutting out of the Stones, unleſs a *Sarcocele* or Gangrene invade them, But that the way of performing the *Punctus aureus* may be better known, I have thought good (in the foregoing page) to ſet down the Inſtruments, by which this operation is performed, before your view.

Lib. de arte medica.

Lib. de ſem.

Another more eaſie and ſafe way to reſtore the Gut and Kall.

Lib 3. *cap.* 33. THeodorick and *Guido* have invented another way of performing this operation. They put back into their places the gut and kall being fallen down, the Patient being ſo placed, that his thighs are high and his head is ſomewhat low; then they draw aſide the lower portion of the production of the *Peritonæum*, and alſo the ſpermatick veſſels, and cremaſter-muſcle to the *Iſchium*; then by applying a cauſtick fitted to the age and diſeaſe, they burn the other part of the proceſs, directly perpendicular to the ſhare-bone, where the gut did fall down. Then they pull off the Eſchar thus made with a knife even to the quick, then they apply another cauſtick in the ſame place, which may go even to the bone, then procure the falling of this Eſchar made on the foreſaid proceſs. And afterwards they heal the Ulcer which remains; which preſently contracting ſomewhat a thick *Callus*, ſo keeps up the guts and kall, that it binds them from falling down into the cod. This way of reſtoring the gut and kall, though it be ſafer and more facile; yet the Chirurgeon muſt not attempt it, if the guts or kall ſtick ſo faſt, agglutinated to the proceſs of the *Peritonæum*, that they cannot be ſevered, nor put back into their places (for from the guts ſo burnt and violated, greater miſchief would enſue) if by the broken and too much dilated proceſs, the bodies thereby reſtrained, make an exceeding great tumor by their falling down; if the teſticle yet lying in the groin as in a *Bubonocele*, a kind of *Enterocele* being not yet deſcended in the *Scotum*, or cod, if the Patients be not come to ſuch age, as they can keep themſelves from ſtirring, or hold their excrements while the operation is performed.

CHAP. XVIII.

Of the cure of other kinds of Ruptures.

EPiplocele is the falling down of the kall into the groin or cod; it hath the ſame cauſes as an *Enterocele*. The ſigns have been explained. It is not ſo dangerous, nor infers a conſequence of ſo many evil ſymptoms, as the *Enterocele* doth, yet the cure is the ſame with the other.

What a *Hydrocele* is. *Hydrocele* is a wateriſh tumor in the cod; which is gathered by little and little between the membranes encompaſſing the teſticles, eſpecially the *Dartes* and *Erythroides*; it may be called a particular Dropſie, for it proceeds from the ſame cauſes, but chiefly from the defect of native heat.

The ſigns. The ſigns are a tumor encreaſing ſlowly without much pain, heavy, and almoſt of a glaſſie clearneſs, which you may perceive by holding a candle on the other ſide; by preſſing the cod above, the water flows down, and by preſſing it below, it riſes upwards, unleſs peradventure in too great a quantity it fills up the whole capacity of the cod, yet it can never be forced or put up into the belly as the kall or guts may, for oft-times it is contained in a ciſt or bag; it is diſtinguiſhed from a *Sarcocele*, by the ſmoothneſs and equality thereof.

The Cure. The cure muſt firſt be tried with reſolving, drying and diſcuſſing medicines, repeated often before, and in the Chapter of the Dropſie; this which follows I have often tried and with good ſucceſs.

A medicine to draw forth the contained matter. ℞ *Ung. comitiſſæ, & deſiccat. rub. an* ℥ ij, *malaxentur ſimul*, and make a medicine for your eaſe. The water by this kind of remedy is digeſted and reſolved, or rather dried up, eſpecially if it be not in too great quantity. But if the ſwelling, by reaſon of the great quantity of water, will not yield to thoſe remedies, there is need of Chirurgery; the cod and membranes wherein the water is contained, muſt be thruſt through with a Seton, that is, with a large three-ſquare pointed Needle, thred with a skean of Silk; you muſt thruſt your Needle preſently through the holes of the Mullets made for that purpoſe, not touching the ſubſtance of the teſticles. The skean of thred muſt be left there, or removed twice or thrice a day, that the humor may drop down, and be evacuated by little and little. But if the pain be more vehement by reaſon of the Seton, and inflammation come upon it, it muſt be taken away, and neglecting the proper cure of the diſeaſe, we muſt reſiſt the ſymptoms.

Some Practitioners uſe not a Seton, but with a Razor, or Inciſion-knife, they open the lower part of the cod, making an Incilion ſome half fingers breadth long, penetrating even to the contained water; always leaving untouched the ſubſtance of the teſticles and veſſels, and they keep the wound open, until all the water ſeems evacuated; truly by this only way the cure of a watery rupture whoſe matter is contained in a ciſt, is ſafe, and to be expected; as we have ſaid in our Treatiſe of Tumors in general.

What a *Pneumatocele* is. The *Pneumatocele*, is a flatulent tumor in the cod, generated by the imbecillity of heat reſiding in the part.

The Cure. It is known by the roundneſs, levity, renitency and ſhining. It is cured by preſcribing a convenient diet, by the application of medicines which reſolve and diſcuſs flatulencies, as the ſeeds of Annis, Fennel, Fenugreek, *Agnus Caſtus*, *Rue*, *Origanum*, and other things ſet down by *Avicen* in his Treatiſe of Ruptures. I have often uſed, with good ſucceſs for this purpoſe, *Emplaſtrum Vigo-*

nis

nis cum Mercurio; and *Emplaſtrum Diacalcitheos*, diſſolved in ſome good Wine, as Muſcadine with Oyl of Bays.

A *Sarcocele* is a Tumor againſt Nature, which is generated about the ſtones by a ſcirrhous fleſh. Groſs and viſcid humors breed ſuch kind of fleſh, which the part could not overcome and aſſimilate to it ſelf; whence this over-abundance of fleſh proceeds like as Warts do. *Varices*, or ſwoln veins often aſſociate this tumor; and it increaſes with pain. It is known by the hardneſs, aſperity, inequality and roughneſs. It cannot be cured but by amputation, or cutting it away; but you muſt diligently obſerve, that the fleſh be not grown too high, and have already ſeized upon the groin; for ſo nothing can be attempted without the danger of life. What a *Sarcocele* is. The Signs. Prognoſticks.

But if any man think, that he in ſuch a caſe may ſomewhat eaſe the Patient by the cutting away of ſome portion of the ſame ſoft fleſh, he is deceived. For a *Fungus* will grow, if the leaſt portion thereof be but left, being an evil far worſe than the former; but if the tumor be either ſmall or indifferent, the Chirurgeon taking the whole tumor, that is, the teſticle tumified through the whole ſubſtance, with the proceſs incompaſſing it, and adhering thereto on every ſide, and make an inciſion in the cod, even to the tumor; then ſeparate all the tumid body, that is, the teſticle from the cod: Then let him thruſt a needle with a ſtrong thred in it, through the midſt of the proceſs, above the region of the ſwoln teſticle; and then preſently let him thruſt it the ſecond time through the ſame part of the proceſs; then ſhall both the ends of the thred be tied on a knot, the other middle portion of the *Peritonæum* being comprehended in the ſame knot. This being done, he muſt cut away the whole proceſs with the teſticle comprehended therein. But the ends of the thred, with which the upper part of the proceſs was bound, muſt be ſuffered to hang ſome length out of the wound, or inciſion of the cod. Then a repercuſſive medicine ſhall be applied to the wound and the neigbouring parts with a convenient ligature. And the cure muſt be performed as we have formerly mentioned. The Cure.

The *Cirſocele* is a tumor of veins dilated, and woven with a various and mutual implication about the teſticle and cod, and ſwelling with a groſs and melancholy blood. The cauſes are the ſame as thoſe of the *Varices*. But the ſigns are manifeſt. What a *Cirſocele* is.

To heal this tumor, you muſt make an Inciſion in the cod, the bredth of two fingers to the *Varix*. Then put under the varicous vein, a needle having a double thred in it, as high as you can, that you may bind the roots thereof: Then let the needle be again put after the ſame manner about the lower part of the ſame vein, leaving the ſpace of two fingers between the ligatures. But before you bind the thred of this loweſt ligature, the *Varix* muſt be opened in the midſt, almoſt after the ſame manner as you open a vein in the arm to let blood: That ſo this groſs blood cauſing a tumor in the cod, may be evacuated as is uſually done in the cure of the *Varices*. The wound that remains ſhall be cured by the rules of Art after the manner of other wounds; leaving the threds in it, which preſently fall away of themſelves. To conclude then, it being grown callous, eſpecially in the upper part thereof, where the vein was bound, it muſt be cicatrized; for ſo afterwards blood cannot be ſtrained or run that way. The Cure.

Hernia Humoralis is a tumor generated by the confuſed mixture of many humors in the cod, or between the tunicles which involve the teſticles, often alſo in the proper ſubſtance of the teſticles. It hath like cauſes, ſigns and cures as other tumors. While the cure is in hand, Reſt, Truſſes, and fit Rowlers to ſuſtain and bear up the teſticles, are to be uſed. *Hernia Humoralis.*

CHAP. XVIII.

Of the falling down of the Fundament.

WHen the muſcle called the *Sphincter* which ingirts the fundament is relaxed, then it comes to paſs that it cannot ſuſtain the right gut. This diſeaſe is very frequent to children by reaſon of the too much humidity of the belly; which falling down upon that muſcle mollifieth and relaxeth it, or preſſeth it down by an unaccuſtomed weight, ſo that the muſcles called *Levatores Ani*, or the lifters up of the fundament, are not ſufficient to bear up any longer. A great Bloody-flux gives occaſion to this effect. A ſtrong endeavour to expel hard excrements, the *Hæmorrhoids*, which ſuppreſſed do over-load the right gut, but flowing relax it: Cold, as in thoſe which go without breeches in Winter, or ſit a long time upon a cold ſtone, a ſtroke or fall upon the holy-bone, a Palſie of nerves which go from the Holy-bone to the muſcles the lifters up of the fundament: the weight of the ſtone being in the bladder. The cauſes.

That this diſeaſe may be healed, we muſt forbid the Patient too much drinking, too often eating of Broth, and from feeding on cold Fruits. For local medicines the part muſt be fomented with an aſtringent decoction made of the rinds of Pomegranats, Galls, Myrtles, Knotgraſs, Shepherds-purſe, Cypreſs Nuts, Alum, and common Salt boiled in Smiths-water, or Red-wine. After the Fomentation, let the gut be anointed with Oyl of Roſes or Myrtles, and then let it be gently put by little and little into its place, charging the child, if he can underſtand your meaning, to hold his breath. When the gut ſhall be reſtored, the part muſt be diligently wiped, leſt the gut fall down again by reaſon of the ſlipperineſs of the unction. Then let the powder preſcribed for the falling down of the Womb be put into the fundament as far as you can: Then you muſt ſtraitly bind the loins with a ſwathe, to the midſt whereof behind let another be faſtned which may be tied at the *Pubes* coming along the *Peritonæum*, ſo to hold up the fundament the better to contain it in its place, a ſpunge dipt in the aſtringent decoction. The Patient, if he be of ſufficient age to have care of himſelf, ſhall be wiſhed when he goes to ſtool, that he ſit upon two pieces of wood being ſet ſome inch aſunder, leſt by his ſtraining he thruſt forth the gut together with the excrement; but if he can do it ſtanding, he ſhall never by ſtraining thruſt forth the gut. The cure.

But if the gut cannot by the preſcribed means be reſtored to its place, *Hippocrates* bids that the *Hippocrates* his cure.

the Patient hanging by the heels be ſhaken; for ſo the gut by that ſhaking will return to his place: But the ſame *Hippocrates* wiſheth to anoint the fundament, becauſe that remedy having a drying faculty, hath alſo power to reſolve the flatulent humors without any acrimony, by reaſon of which the gut was the leſs able to be contained in his place.

CHAP. XIX.

Of the Paronychia.

What the *Paronychia* is.

THe *Paronychia* or *Panaris* is a tumor in the ends of the fingers, with great inflammation, coming of a malign and venemous humor, which from the bones by the *Perioſteum* is communicated to the tendons and nerves of that part which it affecteth, whereof cruel ſymptoms do follow, as pulſifick pain, a Feaver, reſtleſneſs, ſo that the affected through impatiency of the pain are variouſly agitated like thoſe tormented with Carbuncles: For which cauſe *Guido* and *Johannes de Vigo* judge this diſeaſe to be mortal; wherefore you muſt provide a skilful Phyſician for the cure of this diſeaſe, which may appoint convenient diet, purging and blood-letting. In the mean time the Chirurgeon ſhall make way for the virulent and venenate matter, by making inciſion in the inner part of the finger, even to the bone alongſt the firſt joynt thereof; for *Vigo* ſaith, there is not a preſenter remedy, if ſo be that it be quickly done, and before the mutaration of the matter; for it vindicates the finger from the corruption of the bone and nerves, and aſſwages pain, which I have often and happily tried immediately at the beginning, before the perfect impreſſion of the virulency.

Lib. cap. 4. tract.

But the wound being made, you muſt ſuffer it to bleed well, then preſently let him dip his finger in ſtrong and warm Vinegar, in which ſome Treacle being diſſolved may draw forth the virulency. But to appeaſe the pain, the ſame remedies muſt be applied to the affected part as are uſed in Carbuncles, as the leaves of Sorrel, Henbane, Hemlock, Mandrake roaſted under the Embers, and beaten in a Mortar with new *Unguentum Populeon*, or Oyl of Roſes, or new Butter without Salt: For ſuch like medicines alſo help forward ſuppuration; whilſt by their coldneſs, they repreſs the extraneous heat affecting the part; and ſo ſtrengthen the native heat, being the author of ſuppuration: Which reaſon moved the ancient Phyſicians to uſe ſuch medicines in a Carbuncle; but if by reaſon of the fearfulneſs of the Patient, or unskilfulneſs of the Chirurgeon, no inciſion be made, a Gangrene and Sphacel ſhall poſſeſs the part, it remains that you cut off with your cutting Mullets as much of the part as ſhall be corrupt, and perform the reſt of the cure according to Art. Yet it doth not ſeldom happen, that there may be no need to cut off ſuch a finger, becauſe it being corrupted together with the bone by little and little, diſſolves into a purulent, or rather ſanious or much ſtinking filth. But in this affect there is often cauſed an Eſchar by the aduſtion of putredinous heat, and ſuperfluous fleſh indued with moſt exquiſite ſenſe groweth underneath it, which muſt in like manner be cut off with the Mullets, that the part may receive comfort, the pain being aſſwaged by the copious effuſion of blood.

CHAP. XX.

Of the ſwelling of the Knees.

Gal. com. ad ſent. 1. ſer. 4. lib. 6. Epid. Gal. com. ad ſent. 67. ſect. 2. prog.

AFter long and dangerous diſeaſes there oftentimes ariſe tumors in the knees, and alſo in Plethorick bodies, and ſuch as have evil juyce after labours and exerciſe. This kind of diſeaſe is frequent, becauſe the humor eaſily falls into the part which hath been heated by labour. But if ſuch tumor follow long diſeaſes, they are dangerous and difficult to cure, and therefore not to be neglected; for bitter pain accompanieth them, becauſe the humor falling thither, diſtends the membranes, which being many, involve the part; beſides that, this humor participateth of a certain virulent and malign quality, whether it be cold or hot, when it hath ſettled into thoſe parts, being ſuch as we find in the pains of the joynts, and in the bitings of venemous Creatures.

The Cure.

For the cure, if the tumor be cauſed by blood, let a ſlender and refrigerating diet be appointed, and Phlebotomy for the revulſion of the antecedent cauſe; divers local medicines ſhall be uſed, according to the variety of the four times. But for to aſſwage the pain, *Anodynes*, or mitigating medicines ſhall be appointed: Of all which we have ſufficiently treated in the Chapter of the cure of a Phlegmon.

And becauſe theſe parts are of exact ſenſe, if there be neceſſity to open the tumor, yet muſt we not do it raſhly, or unconſiderately, for fear of pain and evil accidents.

This kind of tumor is oft-times raiſed by wind contained there; in which caſe the Chirurgeon muſt be very provident, that he be not deceived with the ſhew of flowing of the humor, which he ſeems to perceive by the preſſures of his fingers, as if there were matter and humor contained therein, and ſo be brought to open the tumor. For the wind breaking forth inſtead of the humor, cauſeth evil ſymptoms by reaſon of the Section raſhly made in a part ſo ſenſible.

But if wateriſh humors ſhall tumefie the part, the body ſhall firſt be purged with medicines purging flegm: And then inciding, attenuating, rarifying, diſcuſſing, and very drying local medicines ſhall be uſed.

Of which we have abundantly ſpoken in the Chapter of the *Oedema*. Yet this humor divers times lies deep between the whirl-bone and the joynt, which cauſeth it that it cannot be diſcuſſed and reſolved by reaſon of the weakneſs of the part, and defect of heat, ſo that the adventitious humor often moves and excludes the bones from their ſeat. As I have obſerved it to have happened to many.

In

In which caſe, Irrigations of red Wine, falling ſomething high whereby the force of the Medicine may enter and more eaſily penetrate, are much commended.

CHAP. XXI.
Of the Dracunculus.

It is not as yet ſufficiently known what *Dracunculi* are.

I Cannot chuſe but explain in this place thoſe things which may be ſpoken of that kind of tumor againſt Nature, which by the Ancients is called *Dracunculus*. The matter and reaſon of theſe hath been variouſly handled by divers Authors, ſo that hitherto we have nothing written of them, to which we may by right and with good reaſon adhere as a firm foundation of their eſſence.

For firſt, for *Galen*'s opinion, *Lib. 6. de Loc. affect. cap.* 3. The generation, ſaith he, of thoſe hairs which are evacuated by the urin is worthy no leſs admiration than the *Dracunculi*, which, as they ſay, in a certain place of *Arabia* breed in the legs of men, being of a nervous nature, and like Worms in colour and thickneſs.

Lib. 4. cap. ult.

Therefore ſeeing I have heard many who have ſaid they have ſeen them, but I my ſelf never ſaw them, I cannot conjecture any thing exactly neither of their original nor eſſence.

Paulus Ægineta writes, that the *Dracunculi* are bred in *India*, and the higher parts of *Egypt*, like Worms in the muſculous parts of mans body, that is, the arms, thighs and legs, and alſo creep by the intercoſtal muſcles in children with a manifeſt motion.

The cure out of *Ægineta*.

But whether they be creatures indeed, or only have the ſhape of creatures, they muſt be cured with a hot fomentation, by which the *Dracunculus* raiſed to a juſt tumor, may put forth it ſelf, and be pluck'd away piece-meal with the fingers: Alſo ſuppurating Cataplaſms may be applied, compoſed of Water, Honey, Wheat and Barley-meal.

Avicen being various, having no certainty whereon to reſt, inclineth one while to this, and another while to that opinion: For now he ſpeaketh of the *Dracunculi*, as of creatures, then preſently of a matter and humor ſhut up in a certain place; for the reſt, he rightly delivers the cure and eſſence of this diſeaſe, as we ſhall afterwards ſhew.

Cap. 21. lib. 4. ſent. 3. tract. 3.

Aetius ſaith, the *Dracunculi* are like Worms, and that they are found ſometimes great, ſometimes ſmall, and that their generation is not unlike to that of flat Worms, which are bred in the guts, for they move under the skin, without any trouble, but in proceſs of time, the place becomes ſuppurate about the end of the *Dracunculus*. The skin openeth, and the head thereof is thruſt forth.

Lib. 14. cap. ult.

But if the *Dracunculus* be pulled, it cauſeth great grief; eſpecially, if it be broken by too violent pulling. For that which is left cauſeth moſt vehement pain. Wherefore that the creature may not run back, the arm muſt be bound with a ſtrong thred, and this muſt be done every day, that the *Dracunculus* going forward by little and little, may be intercepted by this binding, but not broken off.

The cure out of *Aetius*.

The place muſt be bathed with *Aqua mulſa*, and oyl in which Wormwood or Southernwood hath been boyled, or ſome other of thoſe medicines which are preſcribed for the Worms of the belly.

But if the *Dracunculus* going forward of its one accord, may be eaſily drawn forth, we muſt do nothing elſe: But if it be turned to ſuppuration, we muſt not leave off the Cataplaſms, the *Aqua mulſa*, and anointing with oyl: It was uſual with him after the taking away of the Cataplaſms, to apply *Emplaſtrum è Baccis Lauri*: But when it is come to ſuppuration, the skin muſt be opened long-ways, and the *Dracunculus* ſo laid open muſt be taken away, but the skin muſt be filled with lint, and the reſt of the ſuppurative cure uſed, ſo that the creature being ſuppurated and drawn forth, the wound may be incarnated and cicatrized.

Tractat. 7. c. 34.

The cure out of *Rhaſis*.

Rhaſis writeth, that when the part is lifted up into a bliſter, and the vein haſteneth its egreſs, it is good for the Patient to drink the firſt day half a dram of *Aloes*, the next day a whole dram, the third day two drams; and in like manner the place affected muſt be fomented with *Aloes*, for ſo that which lies hid will break forth: That which ſhall come forth muſt be rolled in a pipe of Lead, which may equal the weight of a dram, ſo that it may hang down, for the vein drawn by the weight will come more forth; and when that which ſhall come forth is grown much and long, it muſt be cut off, but not by the root, but ſo that a portion thereof may remain and hang forth, to which the leaden Pipe may be faſtened, for otherwiſe it would withdraw its ſelf into its skin and its lurking hole, and ſo cauſe a putrid and malignant Ulcer.

Therefore we muſt gently meet with this diſeaſe, and the vein muſt be drawn by little and little out of the Body, until it be all come forth, that no worſe thing happen: But if by chance it ſhall happen that as much of the vein as ſhall be come forth ſhall be cut off by the roots, then the Ulcer muſt be opened long-ways with an Inciſion-knife, and that ſo that whatſoever remains thereof may be wholly taken away. Then for ſome days the part muſt be anointed with butter until whatſoever of ſuch a ſubſtance adheres, being conſumed with putrefaction ſhall flow away. Then the Ulcer muſt be cured with ſarcotick things.

His opinion of them.

Therefore *Rhaſis* thus in the ſame Text expreſſeth the ſame thing by divers names, and armed with Iron and Lead, he comes to the cure thereof, as if he meant to encounter with ſome fierce Beaſt.

Soranus his opinion.

Soranus the Phyſician, who lived in the times of *Galen*, was of a quite contrary opinion, as *Paulus Ægineta* in the place being before cited, relates of him; as who denies the *Dracunculus* to be a living-creature, but only a condenſation of a certain ſmall nerve, which ſeems both to the Phyſician and Patients to have ſome motion under the skin.

Wherefore *Soranus* ſeems to have come nearer the truth than the reſt, but yet not ſo, as throughly to underſtand, and know the Eſſence of this Diſeaſe, as we ſhall demonſtrate hereafter.

Manardus

Epiſt. 2. lib. 7. *Manardus* writes, that the *Dracunculi* are generated of evil and unlaudable blood, groſs, hot, and melancholick; or of aduſt phlegm very much dried.

Gorræus a moſt learned Phyſician of our time, *Lib. de Definitionib. medic.* denies any of our Phyſicians to be able to ſay any thing of the *Dracunculi*, becauſe it is a diſeaſe ſo unfrequent in theſe our Regions, that it is ſcarce ever met withal in practice.

The Author of the Introduction, and Medicinal Definitions, defines the *Dracunculus* to be a diſeaſe very like the *Varices*; then cauſing great pain, when increaſing by little and little, it begins to be moved: Therefore to be cured after the ſame manner, and by the ſame method of Section and Inciſion, as the *Varices* are. Which thing ſeems chiefly to have moved *Guido* to refer this kind of diſeaſe to the *Varices* in his Tractate of Impoſthumes, becauſe it hath the ſame cauſe, and is healed with the ſame remedy as the *Varices*.

But ſeeing that divers names have been impoſed upon this diſeaſe by ſeveral Writers, yet they have all expreſſed it by the name of a Vein, for it is called by *Avicen* and *Guido*, *Vena Medeñ*, becauſe it is a diſeaſe frequent in the City *Medina*: by *Albucraſis*, *Vena Civilis*. *Haliabas* hath called it *Vena Famoſa*; others have called it *Vena Cruris*, or the Leg-vein. Truly, the contrariety of ſo many opinions repugnant not only amongſt themſelves, but alſo with themſelves, eaſily argueth how little certainty they had of the eſſence of this diſeaſe, who have written of it unto us: To which alſo this may be added, that none of the later Phyſicians have written any thing thereof. For although *Jacobus Dalechampius*, a man moſt converſant in every part of Phyſick, hath written much of this matter in his Book of the *French* Surgery which he ſet forth ſome years ago: Yet he hath left us no ampler teſtimony of his induſtry, than that he was very diligent in collecting the writings of the Ancients concerning this thing, interpoſing no judgment of his own, the better to aſſure us of a thing ſo controverted.

But my modeſty cannot ſo contain me, but that I ſhall chuſe rather to undergo the cenſure of being thought too daring, than (as much as in me lieth) to ſuffer this queſtion of the *Dracunculi*, to remain longer ambiguous and undecided. Therefore for the preſent, I will thus order it, that refuting the opinions of the Ancients, I may ſtrengthen by certain reaſons, my opinion of the eſſence and cure of this diſeaſe.

Aetius opinion confuted. *Tract. 3. ſerm. 1. cap. 40.* For firſt, that *Dracunculi* are no living things, nor like unto Worms, nor of like generation as the flat Worms of the belly, which was the opinion of *Aetius*, is eaſie to diſprove both by his Writings, as alſo by Reaſon it ſelf. For he writes, that the broad Worm which he calls *Tænia*, is, as it were, a certain *Metamorphoſis*, or Tranſmutation, of the inner tunicle of the ſmall guts into a quick living and moveable body.

But no man ever ſaid, neither will he confeſs that the *Dracunculi* hath the material cauſes of their beginning from the tunicle of the vein, in which they are cloſed, or from the fibers of a nervous body, to which often they are adjoyned; but much leſs from the skin under which they lie, may they draw the material cauſes of their original.

Moreover, neither can there be any generation of Worms, nor of any other living Creatures whatſoever, who have their original from putrefaction, unleſs by the corruption of ſome matter, of whoſe better and more benign part, Nature by the force of the vital heat, produceth ſome animate body, as *Ariſtotle* teacheth. Wherefore to produce this effect, it is fit the matter ſhould have ſuch a diſpoſition to putrefaction as is required for the generation of ſuch a creature as they would make the *Dracunculus* to be: It is fit the helping cauſes ſhould concur as aſſiſtant to the principals in the action. And it is meet the place ſhould be opportune or fit. *4 Meteorolog.*

Natural Melancholick humors is moſt unapt to putrefie. Stink, an unſeparable companion to putrefaction.

But there may be many cauſes found which may give life to the *Dracunculi*; for by the common conſent of all thoſe who have written of them, their generation proceeds from an humor melancholick, terreſtrial and groſs, which by its qualities both by the firſt coldneſs and drineſs, as alſo by the ſecond, that is Acidity, is not only thought moſt unfit of all others for putrefaction, but alſo is is judged to reſiſt putrefaction, as that which is cauſed by heat and ſuperfluous humidity. Beſides, if the material cauſe of this diſeaſe ſhould be from a humor putrefying and turning by putrefaction into ſome living creature, it was fit there ſhould be ſtench alſo, as being an unſeparable accident of putrefaction; for thus, the excrements in the guts of which the Worms are generated, do ſmell or ſtink.

Therefore that which exhales from their bodies who are troubled with the *Dracunculi*, ſhould be ſtinking, as it happens to thoſe ſick of the *Pthiriaſis* or *Lowſie-evil*. But none of thoſe who have delivered the accidents or ſymptoms of the *Dracunculi* are found to have made mention hereof; but of the efficient cauſe whereby ſo great heat may be raiſed in the places next under the skin, by the efficacy whereof ſuch a creature may be formed of a matter melancholick and moſt unapt to putrefie, as they make the *Dracunculus* to be, who feign our bodies to be fruitful Monſters; eſpecially ſeeing the ſurface of the body is continually ventilated by the ſmall arteries ſpread under the skin, as alſo by the benefit of inſenſible Tranſpiration, and breathed with the coolneſs of the air incompaſſing us. But now the material and efficient cauſes being defective, or certainly very weak, for the generation of ſo laborious an effect; what coadjutory cauſe can yield aſſiſtance? Can the humidity of meats; for thoſe bodies which are fed with warm and moiſt meats, as Milk, Cheeſe, Summer-fruits, uſually breed Worms, as we are taught by experience in children.

What things uſually breed worms.

But on the contrary *Avicen* in the place before cited writeth, that meats of a hot and dry temper chiefly breed this kind of diſeaſe, and that it is not ſo frequent to moiſt bodies, and ſuch as are accuſtomed to the Bath, moiſt meats and Wine moderately taken. But whether may the condition of the air of thoſe Regions in which it is, as it were, an Endemial diſeaſe, confer any thing to the generation of ſuch creatures? Certainly, for this purpoſe in a cloudy, warm and thick air, ſuch as uſeth to be at the beginning of the Spring when all the places reſound with Frogs, Toads, and the like creatures bred of putrefaction.

But on the contrary, *Jacobus Dalechampius* by the opinion of all the Phyſicians that have written of the *Dracunculi*, writes, that this diſeaſe breeds in the dry and Sun-burnt Regions of *India* and *Arabia*; but if at the leaſt that part of our body which is next under the skin ſhould have any opportunity to ingender and nouriſh ſuch creatures, they may be judged to have written that the *Dracunculus* is a living creature, with ſome probability. But if there be no opportunity for generation in that place, nor capacity for the nourithment of ſuch like creatures as in the guts, if that Region of the body be breathed upon with no warmneſs and ſmothering heat, if it be defiled with none of thoſe groſs excrements, as the guts uſually are, but only by the ſubtiller exhalation, which have an eaſie and inſenſible tranſpiration by the pores of the skin, which may ſeem to be a juſt cauſe of ſo monſtrous and prodigious an effect: But we ſhall little profit with theſe engines of reaſon unleſs we caſt down at once all the Bulwarks, with which this old opinion of the *Dracunculi* may ſtand and be defended. *Cap. 83. Chir. Gallic.*

For firſt they ſay, Why have the ancients expreſſed this kind of diſeaſe by the name of a living thing, that is, of a *Dracunculus* or little Serpent? I anſwer, becauſe in Phyſick, names are often impoſed upon diſeaſes rather by ſimilitude than from the truth of the thing; for the confirmation whereof, the examples of three diſeaſes may ſuffice, that of the *Cancer*, *Polypus*, and *Elephas*. For theſe have thoſe names, not becauſe any Crab, Polypus, or living Elephant may breed in the body by ſuch like Diſeaſes, but becauſe this by its propagation into the adjacent parts repreſents the feet and claws of a Crab; the other repreſents the fleſh of the Sea-Polypus in its ſubſtance; and the third, becauſe ſuch as have the Leproſie, have their skin wrinkled, rough, and horrid with ſcales and knots, as the skin of a living Elephant. So truly, this diſeaſe of which we now enquire ſeems by good right to have deſerved the name *Dracunculus*, becauſe in its whole conformation, colour, quality and production into length and thickneſs it expreſſeth the image of a Serpent. But, whence, will they ſay, (if it be without life) is that manifeſt motion in the matter? We reply, that the humor, the cauſe of this diſeaſe is ſubtil and hot, and ſo runs with violence into the part whence it may ſeem to move. But when the *Dracunculi* are ſeparated, why do they put their heads, as it were, out of their holes? We anſwer, In this the Ancients have been very much deceived; becauſe after the Suppuration, the Ulcer being opened, ſome nervous body being laid bare, thruſt forth and ſubjected it ſelf to the ſight, which by the convulſive and ſhaking motion, might expreſs the crooked creeping of a Serpent. But they will ſay, pain happens not unleſs to things indued with ſenſe and life, but this *Dracunculus* when he is drawn too violently, eſpecially if he be broken, thereby will cauſe extreme pain: We do anſwer, that the concluſion doth not follow, and is of no conſequence; for theſe pains happen not, unleſs when the unprovident Surgion draws or pulls inſtead of the *Dracunculus* ſome nervous or membranous body ſwoln and repleat with aduſt humor, whence there cannot but be great pain, that part being pull'd which is the author of ſenſe. But it is childiſh, to ſay that the *Dracunculus* feels, for that it cauſeth ſharp pains to the living body in which it is. Therefore that at laſt we may determine ſomething of the nature, eſſence, and generation of theſe *Dracunculi*, I dare boldly affirm, it is nothing elſe but a tumor and abſceſs bred from the heat of the blood in a venenate kind. Such blood driven by the expulſive faculty through the veins to the external parts, eſpecially the limits, that is, the arms and legs, cauſeth a tumor round and long often ſtretched from the joynt of the ſhoulder even to the wriſt, or from the groin even to one of the ankles with tenſion, heat, renitency, pricking pain, and a feaver. But this tumor is ſome while ſtretch-forth ſtrait, otherwhiles into oblique and crooked tumors, which hath been the cauſe that many, taken with this kind of diſeaſe, and having their limbs ſo infolded as with the twinings of a Serpent, would ſay, they had a Serpent. I have thus much to ſay of the *Dracunculi*, eſpecially of thoſe of our own Country.

Why they are called *Dracunculi*.

For the cure, it is not unlike to the cure of a Phlegmon ariſing from a Defluxion; for here alſo in like manner the remedies muſt be varied according to the four times of the diſeaſe, and the ſame rule of diet, Phlebotomy and purging muſt be obſerved, which is before preſcribed in the cure of a Phlegmon.

The Cure.

The mention of the *Dracunculi* calls to my memory another kind of Abſceſs, altogether as rare. This our *French* men name *Cridones*, I think *a Crinibus*, i. from hairs: It chiefly troubles children, and pricks their back like thorns. They toſs up and down being not able to take any reſt. This diſeaſe ariſeth from ſmall hairs which are ſcarce of a pins length, but thoſe thick and ſtrong. It is cured with a fomentation of water more than warm, after which you muſt preſently apply an oyntment made of hony and wheaten flower; for ſo theſe hairs lying under the skin are allured and drawn forth; and being thus drawn, they muſt be plucked out with ſmall mullets. I imagine this kind of diſeaſe was not known to the ancient Phyſicians.

So the *Malum pilare* in *Ariſtotle, cap.* 11. *lib.* 7. *hiſt. animal.*

The end of the Eighth Book.

THE

BOOK IX.

Of Wounds in general.

CHAP. I.

What a Wound is, what the kinds and differences thereof are, and from whence they may be drawn or derived.

What a wound properly is.

A Wound is a ſolution of Continuity, cauſed by a ſtroke, fall, or bite, newly done, bloody, and with putrefaction and filth. They alſo call it a new ſimple Ulcer; for the ſolution of Continuity happens to all parts of the body; but according to the diverſity of parts, it hath divers names amongſt the Greeks. For in the fleſh it is called *Helcos*, in the bone *Gatagma*, in the nerve *Spaſma*, in the ligament *Thalaſma*, in the veſſels *Apoſpaſma*, in the muſcles *Regma*; and that ſolution of Continuity, which happens in the veſſels, their mouths being open, is termed *Anaſtomoſis*; that which happens by eroſion, *Aneuroſis*; that which is generated by ſweating out and tranſcolation, *Diapedeſis*. That theſe may be the more eaſily underſtood, I have thought good to deſcribe them in the following Table.

Divers appellations of wounds according to the varieties of the parts.

A Table of the differences of Wounds.

- The Differences of Wounds are drawn or taken,
  - From the nature of the parts in which they are made or happen. But theſe parts are
    - Either ſimilar, and theſe
      - Either ſoft, as the { Glandules, Fleſh, Fat, Marrow.
      - Or hard, as { A Bone, A Griſtle.
      - Of a middle conſiſtence, as the { Membranes, Ligaments, Fibers, Veſſels, Nerves, Veins, Arteries.
    - Or Organical, and theſe either
      - Principal, as the { Brain, Heart, Liver, to which ſome add the Womb and Teſticles.
      - Or ſerving the principal as, { The Weaſon, Lungs, Gullet, Stomach, Guts, Bladder.
      - Or neither, as { The Ears, Noſe, Feet, Hands, and other of the ſame kind.
  - From their proper eſſence, from whence they are called,
    - Simple wounds { When there is no complication of any other diſeaſe or ſymptom, beſides.
    - Or compound, { When there is a complication of ſome one or more diſeaſes, which unleſs they be taken away, we muſt not hope for to cure the wound.
  - From their quantity according to which they are called, { Great, Indifferent, Little, Long, Broad, Deep, Short, Narrow, Superficiary.
  - From their Figure, according to which they are named, { Strait, Oblique, Cornered.

CHAP. II.

Of the cauſes of Wounds.

Divers denominations from their cauſes.

ALL things which may outwardly aſſail the body with force and violence, may be counted the cauſes of wounds; which are called green, and properly bloody. Theſe things are either animate, or inanimate, as the bitings and prickings of Beaſts. The inanimate, as the ſtroke of an Arrow, Sword, Club, Gun, Stone, a Dagger, and all ſuch like things.

From the variety of ſuch like cauſes, they have divers names: For thoſe which are made by ſharp and pricking things are called Punctures: Thoſe cauſed by cutting things, are called Wounds or Gaſhes; and thoſe which are made by heavy and obtuſe things are named Contuſions, or wounds with contuſions.

CHAP.

CHAP. III.

Of the Signs of Wounds.

WOunds are firſt known by ſight, and by the ſigns drawn from thence. The Chirurgeon ought firſt and chiefly, to conſider, what wounds are curable, and what not; what wounds will ſcarce admit of cure, and what may be eaſily cured; for it is not the part of a prudent Chirurgeon, to promiſe cure in a deadly or dangerous and difficult wound; leſt he may ſeem to have killed him, whom not the unſufficiency of the Art, but the greatneſs of the wound hath ſlain. A caution for making reports of Wounds.

But when the Wound is dangerous, but yet without deſpair of recovery, it belongs to him to admoniſh the Patients friends which are by, of the preſent danger, and doubtful ſtate of the Wound, that if Art ſhall be overcome by the greatneſs thereof, he ſhall not be thought ignorant of the Art, neither to have deceived them.

But as this is the part and duty of a good and prudent Chirurgeon, ſo it is the trick of a cheating and jugling Knave, to enlarge ſmall wounds, that ſo he may ſeem to have done a great cure, when it is nothing ſo. A jugling cheating Chirurgeon.

But it is agreeable to reaſon, that the Chirurgeon profeſſing the Diſeaſe eaſie to be cured, will think himſelf in credit bound by ſuch promiſes and his duty, and therefore ſeek all means for the quick recovery of the Patient; leſt that which was of its own nature ſmall, may by his negligence become great. Therefore it is expedient he ſhould know what Wounds are to be accounted great.

This (as *Galen* ſaith) is three ways to be known; The firſt is by the magnitude and principality of the part affected; for thus the wounds of the Brain, Heart, and of the greater Veſſels, though ſmall of themſelves, yet are thought great. Then from the greatneſs of the ſolution of continuity; for which cauſe Wounds may be judged great, in which much of the ſubſtance of the part is loſt in every dimenſion, though the part be one of thoſe which are accounted ſervile. Then from the malignity; through which occaſion the Wounds of the joints are accounted great, becauſe for the moſt part they are ill conditioned. *Lib.4. Meth. cap.6.1.* Wounds are called Great, out of three reſpects.

CHAP. IV.

Of Prognoſticks to be made in Wounds.

THoſe Wounds are thought dangerous, wherein any large Nerve, Vein, or Artery are hurt. From the firſt there is fear of Convulſion, but from the other large effuſion of the veinous, or arterious bloud, whence the powers are debilitated; alſo theſe are judged evil, which are upon the Arm-pits, Groins, Legs, Joints, and between the Fingers; and likewiſe thoſe which hurt the head or tail of a Muſcle. What wounds are dangerous.

They are leaſt dangerous of all other which wound onely the fleſhy ſubſtance. What leaſt dangerous.

But they are deadly which are inflicted upon the Bladder, Brain, Heart, Liver, Lungs, Stomach, and ſmall Guts. What deadly. *Hipp. aphor.19. Lib.6.*

But if any Bone, Griſle, Nerve, or portion of the Cheek, or Prepuce, ſhall be cut away, they cannot be reſtored.

Contuſed wounds are more difficult to cure than thoſe which are from a ſimple ſolution of continuity; for before you muſt think to heal them up, you muſt ſuppurate and cleanſe them, which cannot be done in a ſhort time. Why round Wounds are difficult to heal.

Wounds which are round and circular are ſo much the worſe, for there can be no unity unleſs by an angle, that is, a meeting together of two lines, which can have no place in round Wounds, becauſe a circular figure conſiſts of one oblique line. Beſides, Wounds are by ſo much thought the greater, by how much their extreams and lips are the further disjoined, which happens to round Wounds. Contrary to theſe are cornered Wounds, or ſuch as are made alongſt the fibers, as ſuch as may be healed.

Wounds may be more eaſily healed in young men than in old, becauſe in them Nature is more vigorous, and there is a greater plenty of fruitful, or good bloud, by which the loſs of the fleſh may be the better and more readily reſtored, which is ſlowlier done in old bodies, by reaſon their bloud is ſmaller in quantity and more dry, and the ſtrength of nature more languid.

Wounds received in the Spring, are not altogether ſo difficult to heal as thoſe taken in Winter or Summer. For all exceſs of heat and cold is hurtful to them, it is ill for a Convulſion to happen upon a Wound, for it is a ſign that ſome Nervous body is hurt; the Brain ſuffering together therewith, as that which is the Original of the Nerves. A tumor coming upon great Wounds is good; for it ſhews the force of nature is able to expel that which is harmful, and to eaſe the wounded part. *Hipp. lib. de ulcer. Hipp. aph. 66. lib. 5.*

The organical parts wholly cut off, cannot again be united: becauſe a vital part once ſevered and plucked from the trunk of the body, cannot any more receive influence from the heart as from a root without which there can be no life. The looſed continuity of the Nerves, Veins, Arteries, and alſo the Bones, is ſometimes reſtored, not truly, and, as they ſay, according to the firſt intention, but by the ſecond, that is, by repoſition of the like, but not of the ſame ſubſtance. The firſt intention takes place in the fleſhy parts by converting the Alimentary bloud into the proper ſubſtance of the wounded part. But the ſecond, in the ſpermatick in which the loſt ſubſtance may be repaired by interpoſition of ſome heterogeneous body, which Nature, diligent for its own preſervation, ſubſtitutes in place of that which is loſt: for thus the body, which reſtores and agglutinates, is no Bone but a *Callus*, whoſe original matter is from an humour ſomewhat groſſer than that, from whence the Bones have their original and beginning. What a *Callus* is, and whence it proceeds.

This humour, when it ſhall come to the place of the fracture, agglutinateth the ends of the Bones together, which otherwiſe could never be ſo knit by reaſon of their hardneſs. The Bones of Children are more eaſily and ſpeedily united by reaſon of the pliantneſs of their ſoft and tender ſubſtance. Small and contemptible wounds often prove mortal. Laſtly, We muſt here admoniſh the Chirurgeon that ſmall Wounds, and ſuch as no Artiſan will judge deadly, do divers times kill by reaſon of a certain occult and ill diſpoſition of the

Aphor. 1. *Sect.* 1. wounded, and encompaſſing bodies; for which cauſe we read it obſerved by *Hippocrates*, that it is not ſufficient for the Phyſician to perform his duty, but alſo external things muſt be rightly prepared and fitted.

CHAP. V.

Of the Cure of Wounds in general.

The general Indication of Wounds.

THe Chirurgeon ought for the right cure of Wounds to propoſe unto himſelf the common and general indication: that is, the uniting of the divided parts, which indication in ſuch a caſe is thought upon and known even by the vulgar: for that which is disjoined deſires to be united, becauſe Union is contrary to Diviſion. But by what means ſuch Union may be procured, is onely known to the skilful Artiſan. Therefore we attain unto this chief and principal Indication by the benefit of Nature as it were the chief Agent, and the work of the Chirurgeon as the ſervant of Nature. And unleſs Nature ſhall be ſtrong, the Chirurgeon ſhall never attain to his conceived and wiſhed for end: therefore that he may attain hereto, he muſt perform five things; the firſt is, that if there be any ſtrange body, as pieces of Wood, Iron, Bones, bruiſed Fleſh, congealed Bloud, or the like, whether they have come from without, or from within the Body, and ſhall be by accident faſtned or ſtuck in the Wound, he muſt take them away, for otherwiſe there is no Union to be expected.

Five things neceſſary for uniting Wounds.

Another is, that he join together the lips of the Wound, for they cannot otherwiſe be agglutinated and united. The third is, that he keep cloſe together the joined lips. The fourth, that he preſerve the temper of the wounded part; for the diſtemper remaining, it is impoſſible to reſtore it to its unity. The fifth is, that he correct the accidents, if any ſhall happen, becauſe theſe urging, the Phyſician is often forced to change the order of the Cure.

All ſtrange and external Bodies muſt be taken away, as ſpeedily as is poſſible, becauſe they hinder the action of Nature intending Unity, eſpecially if they preſs or prick any Nervous Body or Tendon, whence pain or an abſceſs may breed in any principal part, or other ſerving the principal.

Yet if by the quick and too haſty taking forth of ſuch like Bodies there be fear of cruel pain or great effuſion of bloud, it will be far better to commit the whole work to Nature than to exaſperate the Wound by too violent haſtening.

For Nature by little and little will exclude, as contrary to it, or elſe together with the *Pus*, what ſtrange Body ſoever ſhall be contained in the wounded part. But if there ſhall be danger in delay, it will be fit the Chirurgeon fall to work quickly, ſafely, and as mildly as the thing will ſuffer: for effuſion of bloud, Swooning, Convulſion, and other horrid ſymptoms, follow upon the too rough and boiſtrous handling of Wounds, whereby the Patient ſhall be brought into greater danger than by the Wound it ſelf.

Therefore he may pull out the ſtrange Bodies, either with his fingers or with inſtruments fit for that purpoſe: but they are ſometimes more eaſily and ſometimes more hardly pulled forth, according as the Body infixed is either hard or eaſie to be found or pulled out Which thing happens according to the variety of the figure of ſuch like Bodies, according to the condition of the part it ſelf, ſoft, hard, or deep, in which theſe bodies are faſtned more ſtraitly or more looſly; and then for fear of inferring any worſe harm, as the breaking of ſome Veſſel: but how we may perform this firſt intention, and alſo the expreſſion of the inſtruments neceſſary for this purpoſe, ſhall be ſhewn in the particular Treatiſe of Wounds made by Gun-ſhot, Arrows, and the like.

Ligatures and Sutures for to conjoin and hold together the lips of Wounds.

But the Chirurgeon ſhall attain to the ſecond and third ſcope of curing Wounds by two and the ſame means, that is, by Ligatures and Sutures: which notwithſtanding before he uſe he muſt well obſerve whether there be any great flux of Bloud preſent, for he ſhall ſtop it if it be too violent, but provoke it if too ſlow, (unleſs by chance it ſhall be poured out into any capacity or belly) that ſo the part freed from the ſuperfluous quantity of Bloud may be leſs ſubject to inflammation. Therefore the lips of the Wound ſhall be put together, and ſhall be kept ſo joined by Suture and Ligatures: Not truly of all, but onely of thoſe which both by their nature and magnitude, as alſo by the condition of the parts in which they are, are worthy and capable of both the remedies. For a ſimple and ſmall ſolution of continuity, ſtands onely in need of the Ligature which we call Incarnative, eſpecially if it be in the Arms or Legs, but that which divides the Muſcles tranſverſly, ſtands in need of both Suture and Ligature; that ſo the lips which are ſomewhat far diſtant from each other, and as it were, drawn towards their beginning and ends may be conjoined.

If any portion of a fleſhy ſubſtance by reaſon of ſome great Cut, ſhall hang down, it muſt neceſſarily be adjoined and kept in the place by Suture. The more notable and large Wounds of all the parts, ſtand in need of Suture, which do not eaſily admit a Ligature, by reaſon of the figure and ſite of the part in which they are, as the Ears, Noſe, Hairy-ſcalp, Eye-lids, Lips, Belly, and Throat.

Three ſorts of Ligatures.

There are three ſorts of Ligatures, by the joint conſent of all the Ancients. They commonly call the firſt a Glutinative or Incarnative, the ſecond Expulſive, the third Retentive. The Glutinative or Incarnative is fit for ſimple, green and yet bloudy Wounds. This conſiſts of two ends, and muſt ſo be drawn, that beginning on the contrary part of the Wound, we may ſo go upwards, partly croſſing it, and going downwards again, we may cloſely join together the Lips of the Wound. But let the Ligature be neither too ſtrait, leſt it may cauſe inflammation or pain; nor too looſe, leſt it be of no uſe, and may not well contain it.

What an Incarnative Ligature is.

What an Expulſive.

The expulſive Ligature is fit for ſanious and fiſtulous Ulcers, to preſs out the filth contained in them. This is performed with one Rowler, having one ſimple head; the beginning of binding muſt be taken from the bottom of the *Sinus*, or boſom thereof, and there it muſt be bound more ſtraitly, and ſo by little and little going higher, you muſt remit ſomething of that rigour even to the mouth of the Ulcer, that ſo (as we have ſaid) the ſanious matter may be preſſed forth.

The

The Retentive Ligature is fit for ſuch parts as cannot ſuffer ſtrait binding; ſuch are the Throat, Belly, as alſo all parts oppreſſed with pain, for the part vexed with pain, abhorreth binding. The uſe thereof, is to hold to local Medicins. It is performed with a Rowler, which conſiſts ſomewhiles of one, ſomewhiles of more heads. All theſe Rowlers ought to be of Linnen, and ſuch as is neither too new, nor too old, neither too coarſe nor too fine. Their bredth muſt be proportionable to the parts to which they ſhall be applied; the indication of their largeneſs being taken from their Magnitude, Figure, and Site. As we ſhall ſhew more at large in our Tractates of Fractures and Diſlocations.

What the retentive.

What the rowlers muſt be made of.

The Chirurgeon ſhall perform the firſt ſcope of curing Wounds, which is of preſerving the temper of the wounded part, by appointing a good order of Diet by the preſcript of a Phyſician, by uſing univerſal and local Medicins. A ſlender, cold and moiſt Diet muſt be obſerved, until that time be paſſed, wherein the Patient may be ſafe and free from accidents which are uſually feared. Therefore let him be fed ſparingly, eſpecially if he be plethorick; he ſhall abſtain from Salt and ſpiced Fleſh, and alſo from Wine: if he ſhall be of a cholerick or ſanguine nature, in ſtead of Wine he ſhall uſe the Decoction of Barley or Liquorice, or Water and Sugar. He ſhall keep himſelf quiet, for Reſt is (in *Celſus*'s opinion) the very beſt Medicin. He ſhall avoid Venery, Contentions, Brawls, Anger, and other perturbations of the mind. When he ſhall ſeem to be paſt danger, it will be time to fall by little and little to his accuſtomed manner and diet of life. Univerſal remedies are Phlebotomies and Purging, which have force to divert and hinder the defluxion, whereby the temper of the part might be in danger of change.

Why and how the temper of the wounded part muſt be preſerved.

For Phlebotomy it is not always neceſſary, as in ſmall Wounds and Bodies, which are neither troubled with ill humours, or Plethorick: But it is onely required in great Wounds, where there is fear of Defluxion, Pain, *Delirium*, Raving and unquietneſs; and laſtly, in a Body that is Plethorick, and when the Joints, Tendons, or Nerves are wounded. Gentle purgations muſt be appointed, becauſe the humours are moved and enraged by ſtronger; whence there is danger of defluxion and inflammation: wherefore nothing is to be attempted in this caſe without the advice of a Phyſician.

In what wounds bloud letting is not neceſſary.

The Topick and particular Medicins are Agglutinative, which ought to be endued with a drying and aſtrictive quality, whereby they may hold together the lips of the Wound and drive away defluxion, having always a regard to the nature of the part, and the greatneſs of the diſeaſe. The Simple Medicins are *Olibanum*, *Aloes*, *Sarcocolla*, *Bole Armenick*, *Terra ſigillata*, *Sanguis Draconis*, Common and Venice Turpentine, Gum, *Elemni*, Plantane, Horſetail, the greater Comfry, *Parina Volatilis*, and many other things of this kind, which we ſhall ſpeak of hereafter in our *Antidotary*.

What Medicins are to be judged agglutinative.

The fifth ſcope of healing Wounds, is the correction of thoſe Symptoms or Accidents which are accuſtomed to follow Wounds, which thing verily makes the Chirurgeon have much to do; for as he is often forced to omit the proper cure of the Diſeaſe, ſo to reſiſt the accidents and ſymptoms, as Bleeding, Pain, Inflammation, a Fever, Convulſion, Palſie, Talking idly, or Diſtraction, and the like. Of which we ſhall treat briefly and particularly, after we have firſt ſpoken of Sutures as much as we ſhall thing fitting for this place.

CHAP. VI.

Of Sutures.

What wounds ſtand in no need of a Suture.

When Wounds are made alongſt the Thighs, Legs, and Arms, they may eaſily want Sutures, becauſe the Solution of continuity is eaſily reſtored by Ligatures, but when they are made overthwart, they require a Suture, becauſe the fleſh and all ſuch like parts being cut are drawn towards the ſound parts; whereby it comes to paſs that they part the further each from other: wherefore that they may be joined and ſo kept, they muſt be ſewed, and if the Wound be deep, you muſt take up much fleſh with your Needle; for if you onely take hold of the upper part, the Wound is onely ſuperficially healed: but the matter ſhut up, and gathered together in the bottom of the Wound, will cauſe abſceſſes and hollow Ulcers: Wherefore now we muſt treat of making of Sutures.

The firſt manner of Suture. The form of your Needle.

The firſt called *Interpunctus*, leaves the diſtance of a fingers bredth, and therefore is fit for the green Wounds of the fleſhy parts, which cannot be cured with a Ligature, and in which no heterogeneous or ſtrange body remains. It is performed after this manner. You muſt have a ſmooth Needle with a Thred in it, having a three-ſquare point, that ſo it may the better enter the Skin, with the head of it ſomewhat hollowed, that the Thred may lie therein; for ſo the Needle will the better go through. You muſt alſo have a little Pipe with a hole or window in the end, which you muſt hold and thruſt againſt the lip of the Wound, that it be not moved to the one ſide or other, whileſt you thruſt through the Needle: And that we may ſee through that window when the Needle is thruſt through, and alſo draw it together with the thred, and withall hold the lip of the Wound in more firmly, that it follow not at the drawing forth of the Needle and Thred. Having thus pierced the lips of the Wound, tie a knot, near to which cut off the Thred, leſt that if any of it be left below the knot, it may ſo ſtick to the Emplaiſters that it cannot be plucked and ſeparated from them without pain, when they are taken off. But you muſt note the firſt ſtitch muſt be thruſt through the midſt of the Wound, and then the ſecond muſt be in that ſpace which is between the midſt and one of the ends; but when you have made your ſtitches, the lips of the Wound muſt not be too cloſely joined, but a little ſpace muſt be left open between them, that the matter may have free paſſage forth, and inflammation and pain may be avoided: otherwiſe, if they ſhall be cloſely joined together without any diſtance between, a tumor after ariſing when the matter ſhall come to ſuppuration, the lips will be ſo much diſtended that they may eaſily be broken by the ſtiffneſs of the Thred. But you muſt neither take hold of too much nor too little fleſh with your Needle;

The form of the Pipe with a window in it

for too little will not hold, and too much cauſeth pain and inflammation. And beſides, leaves an ill-favoured ſcar. Yet in deep Wounds ſuch as are thoſe which are made in the thicker Muſcles, the Needle muſt be thruſt home, that ſo it may comprehend more of the fleſhy ſubſtance, leſt the Thred drawn away by the weight of the fleſh not taken hold of, may be broken. But oft-times Wounds are ſeen made in ſuch places, as it would be needful the Chirurgeon ſhould have a crooked Needle and Pipe, otherwiſe the Suture will not ſucceed according to his deſire. Wherefore I have thought good to ſet forth both their figures, that you may uſe either as occaſion ſhall ſerve.

The Figures of Pipes with Feneſtels in them, and Needles fit for Sutures.



The ſecond means of Suture.

The ſecond Suture is made juſt after the ſame manner as the Skinner ſows their Fells or Furs. And the Guts muſt be ſowed with this kind of Suture (if they ſhall be at any time wounded) that the Excrements come not forth by the Wound.

The third manner of Suture.

The third Suture is made by one or more Needles having Thred in them, thruſt through the Wound, the Thred being wrapped to and again at the head and the point of the Needle, as Boys uſe to faſten their Needle, for fear of loſing it, in their Caps or Cloths. This kind of Suture is fit in the curing and healing of Hare-lips, as we ſhall ſhew you hereafter expreſſed by a Figure.

The fourth kind of Suture termed *Gaſtroraphia*.

The fourth kind of Suture is termed *Gaſtroraphia*, invented for the reſtoring and uniting the great Muſcles of the *Epigaſtrium*, or lower Belly, cut with a great wound together with the *Peritonæum* lying under them. The manner whereof we ſhall ſhew in due place.

The fifth kind called the Dry Suture.

The fifth kind is called the dry Suture, which we uſe onely in the Wounds of the face, which alſo we will deſcribe in its proper place.

CHAP. VII.

Of the Flux of Bloud, which uſually happens in Wounds.

The ſigns of bloud flowing from an Artery.

OFt-times great bleeding follows upon Wounds, by reaſon of ſome Veſſel cut, broken, or torn, which there is need to heal and help diligently, becauſe the bloud is the treaſure of Nature, without which life cannot conſiſt. The Bloud which floweth from an Artery, is thus known. It is more ſubtile, it runs forth as it were leaping, by reaſon of the vital ſpirit contained together with it in the Arteries. On the contrary, that which floweth from a Vein is more groſs, black, and ſlow. Now there are many ways of ſtanching bloud.

The firſt way of ſtaying bleeding.

The firſt and moſt uſual is that, by which the lips of the Wound are cloſed, and, unleſs it be ſomewhat deep, are contained by Medicins which have an aſtringent, cooling, drying, and glutinous faculty: As *Terræ ſigill. Boli Armeni, ana* ℥ ß. *Thuris, Maſticis, Myrrhæ, Aloes, ana* ʒ ij. *Farinæ volat. molend.* ℥ i. *Fiat pulvis qui albumine ovi excipiatur.* Or, R. *Thuris & Aloes, ana partes æquales.* Let them be mixt with the White of an Egg, and the Down of a Hare, and let the pledgets be dipped in theſe Medicins, as well thoſe which are put unto the Wound, as thoſe which are applied about it. Then let the Wound be bound up with a double cloth and fit ligature, and the part be ſo ſeated as may ſeem the leaſt troubleſom and moſt free from pain.

The 2. manner of ſtanching it

But if the Bloud cannot be ſtaid by this means, when you have taken off all that covereth it, you ſhall preſs the Wound and the orifice of the Veſſel with your Thumb, ſo long until the bloud ſhall be concrete about it, into ſo thick a clot as may ſtop the paſſage.

The 3. way by binding of the Veſſels.

But if it cannot be thus ſtaid, then the Suture (if any be) muſt be opened, and the mouth of the Veſſel towards the original or root, muſt be taken hold of, and bound with your Needle and Thred, with as great a portion of the fleſh as the condition of the part will permit. For thus I have ſtaid great bleedings, even in the amputation of members, as I ſhall ſhew in fit place. To perform this Work we are often forced to divide the skin which covereth the wounded Veſſel. For if the Jugular Vein or Artery be cut, it will contract and draw it ſelf upwards and downwards. Then the Skin it ſelf muſt be laid open under which it lieth, and thruſting a Needle and Thred under it, it muſt be bound as I have often done. But before you looſe the knot, it is fit the fleſh ſhould be grown up, that it may ſtop the mouth of the Veſſel, leſt it ſhould then bleed.

An admonition.

The 4. way by Eſchatoricks.

But if the condition of the part ſhall be ſuch as may forbid this comprehenſion, and binding of the Veſſel; we muſt come to *Eſcharoticks*, ſuch as are the powder of burnt *Vitriol*, the powder of Mercury, with a ſmall quantity of burnt Allum; and Cauſticks which cauſe an Eſcar. The falling away of which muſt be left to Nature, and not procured by Art, leſt it ſhould fall away before that the orifice of the Veſſel ſhall be ſtopt with the fleſh or clotted bloud.

The 5. way by cutting off the Veſſels.

But ſometimes it happens that the Chirurgeon is forced wholly to cut off the Veſſel it ſelf,

that

that thus the ends of the cut Veſſel withdrawing themſelves, and ſhrinking upwards and downwards, being hidden by the quantity of the adjacent and incompaſſing parts, the flux of the bloud, which was before not to be ſtaid, may be ſtopped with leſs labour. Yet this is an extreme remedy and not to be uſed, unleſs you have in vain attempted the former.

CHAP. VIII.

Of the pain which happens upon Wounds.

Pain weakens the body, and cauſes defluxions.

THe pains which follow upon Wounds ought to be quickly aſſwaged, becauſe nothing ſo quickly dejects the powers, and it always cauſes a defluxion, of how good ſoever a habit and temper the body be of; for Nature ready to yield aſſiſtance to the wounded part, always ſends more humours to it than are needful for the nouriſhment thereof, whereby it comes to paſs that the defluxion is eaſily increaſed, either by the quantity, or quality, or by both.

Divers Anodynes or medicins to aſſwage pain.

Therefore to take away this pain, the author of defluxion, let ſuch medicins be applied to the part as have a repelling and mitigating faculty; as ℞ *Olei Myrtili, & Roſarum, ana* ʒ ij. *Ceræ alb.* ʒ i. *Farinæ hordei,* ʒ ß. *Boli armeni, & terræ ſigillat, ana* ʒ vj. Melt the Wax in the Oils, then incorporate all the reſt, and according to Art, make a Medicin to be applied about the part: or, ℞ *Emplaſt. Diacalcith.* ʒ iv. *Olc. Roſar. & aceti, ana* ʒ ß. *liquefiant ſimul*, and let a Medicin be made for the fore-mentioned uſe. Irrigations of Oil of Roſes and Myrtils, with the white of an Egg, or a whole Egg added thereto, may ſerve for lenitives, if there be no great inflammation; Rowlers and double cloths moiſtened in Oxycrate, will be alſo convenient for the ſame purpoſe. But the force of ſuch Medicins muſt be often renewed, for when they are dried, they augment the pain. But if the pain yield not to theſe, we muſt come to narcotick Medicins, ſuch as are the Oil of Poppy, of Mandrake, a Cataplaſm of Henbane and Sorrel, adding thereto Mallows and Marſh-mallows, of which we ſpoke formerly in treating of a Phlegmon.

Laſtly, We muſt give heed to the cauſe of the pain, to the kind and nature of the humour that flows down, and to the way which nature affects: for according to the variety of theſe things, the Medicins muſt be varied, as if heat cauſe pain, it will be aſſwaged by application of cooling things; and the like reaſon obſerved in the contrary: If Nature intend ſuppuration, you muſt help forwards its indeavours with ſuppurating Medicins.

CHAP. IX.

Of Convulſion by reaſon of a Wound.

What a Convulſion is.

A Convulſion is an unvoluntary contraction of the Muſcles (as of parts moveable at our pleaſure) towards their original, that is, the Brain and Spinal Marrow, for by this the convulſed member or the whole body (if the Convulſion be univerſal) cannot be moved at our pleaſure. Yet motion is not loſt in a Convulſion as it is in a Palſie, but it is onely depraved: and becauſe ſometimes the Convulſion poſſeſſeth the whole body, otherwhiles ſome part thereof, you muſt note that there are three kinds of Convulſions in general.

Three kinds of an univerſal Convulſion.

The firſt is called by the Greeks *Tetanos*, when as the whole body grows ſtiff like a ſtake that it cannot be moved any way.

The ſecond is called *Opiſthotonos*, which is when the whole body is drawn backwards.

The third is termed *Emproſthotonos*, which is when the whole body is bended or crooked forwards.

Three cauſes of a Convulſion.

A particular Convulſion is, when as the muſcle of the Eye, Tongue, and the like parts which is furniſhed with a Nerve, is taken with a Convulſion, Repletion, or Inanition, Sympathy or conſent of pain cauſe a Convulſion.

Cauſes of Repletion.

Abundance of humours cauſe Repletion, dulling the body by immoderate eating and drinking, and omiſſion of Exerciſe, or any accuſtomed evacuation, as ſuppreſſion of the Hemorrhoids and Courſes: for hence are ſuch like excrementitious humours drawn into the Nerves, with which they being repleat and filled are dilated more than is fit, whence neceſſarily becoming more ſhort, they ſuffer Convulſion. Examples whereof appear in Leather, and Lute or Viol ſtrings, which ſwollen with moiſture in a wet ſeaſon are broken by repletion.

Cauſes of Inanition.

Immoderate Vomitings, Fluxes, or Bleedings, cauſe Inanition or Emptineſs; wherefore a Convulſion cauſed by a Wound, is deadly: as alſo by burning Fevers. For by theſe and the like cauſes, the inbred and primogenious humidity of the Nerves is waſted, ſo that they are contracted like Leather which is ſhrunk up, by being held too near the fire, or as Fiddle-ſtrings which dried with Summers heat, are broken with violence; ſuch a Convulſion is incurable: For it is better a Fever follow a Convulſion, than a Convulſion a Fever; as we are taught by *Hippocrates*, ſo that ſuch a Fever be proportional to the ſtrength of the convulſifick cauſe, and the Convulſion proceed from Repletion; for the abundant and groſs humour cauſing the Convulſion is digeſted and waſted by the feveriſh heat. *Aph. 26. ſect. 2.*

Cauſes of Convulſion by conſent of pain.

The cauſes of a convulſion by reaſon of pain, are either the puncture of a Nerve, whether it be by a thing animal, as by the biting of a venemous Beaſt; or by a thing inanimate, as by the prick of a Needle, Thorn, or Pen-knife; or great and piercing cold, which is hurtful to the Wounds, principally of the nervous parts; whereby it comes to paſs, that by cauſing great and bitter pain in the Nerves they are contracted towards their original, that is, the Brain, as if they would crave ſuccour from their parents in their diſtreſſed eſtate. Beſides alſo, an ill vapour carried to the Brain from ſome putrefaction ſo vellicateth it, that contracting it ſelf, it alſo contracteth together with it all the Nerves and Muſcles; as we ſee it happeneth in thoſe which have the Falling-Sickneſs. By which it appears that not onely the Brain it ſelf ſuffereth together with the Nerves, but alſo the Nerves with the Brain.

Signs of a convulſion.

The ſigns of a Convulſion are, difficult, painful, and depraved motions,

motions, either of ſome part or of the whole body, turning aſide of the Eyes and whole Face, a contraction of the Lips, a drawing in of the Cheeks as if one laughed, and an univerſal Sweat.

CHAP. X.

The cure of a Convulſion.

The cauſe of a Convulſion by Repletion.

THe Cure of a Convulſion, is to be varied according to the variety of the convulſive Cauſe, for that which proceeds from Repletion muſt be otherwiſe cured, than that which is cauſed by an inanition; and that which proceeds of Pain, otherwiſe than either of them. For that which is cauſed by Repletion is cured by diſcuſſing and evacuating Medicins; as by Diet conveniently appointed, by purging, bleeding, digeſtive local Medicins, Exerciſe, Frictions, Sulphureous Baths and other things appointed by the preſcription of ſome learned Phyſician which ſhall overſee the cure, which may conſume the ſuperfluous and excrementitious humors that poſſeſs the ſubſtance of the Nerves and habit of the Body. The local remedies are Oils, Unguents, and Liniments, with which the Neck, Back-bone, and all the contracted parts ſhall be anointed. The Oils are, the Oil of Foxes, Bays, Cammomil, Worms, Turpentine, of *Coſtus*, of *Caſtoreum*: The Ointments are, *Unguentum Arragon, Agrippæ, de Althæa, Martiatum.* This may be the form of a Liniment; ℞ *Olei chamæm. & Laurin. ana* ℥ ij. *Olei Vulp.* ℥ i. *Unguenti de Althæa & Marti. an.* ℥ ß. *Axungiæ Vulpis*, ℥ i. *Aquæ vitæ* ℥ i. ß. *Ceræ quantum ſufficit.* Make a Liniment for your uſe. Or, ℞ *Olei Lumbric. de Spica & de Caſtoreo an.* ℥ iij. *Axung. hum.* ℥ i. *Sulphuris vivi*, ℥ ß. *Ceræ quantum ſufficit.* Make a Liniment. Or, ℞ *Unguenti Martiati, & Agrip. an.* ℥ iij. *Olei de Terebinth.* ℥ i. ß. *Olei Salviæ*, ℥ ß. *Aquæ vitæ* ℥ i. *Ceræ* ℥ i. ß. *fiat linimentum.* But this diſeaſe is cured by ſlender Diet, and Sweating, with the Decoctions of *Guaiacum*, becauſe by theſe remedies the groſs, tough, and viſcid excrements, which are in fault, are digeſted,

The cure of a Convulſion cauſed by inanition.

A Convulſion proceeding of Inanition is to be cured by the uſe of thoſe things which do wholſomly and moderately nouriſh. And therefore you muſt preſcribe a Diet conſiſting of Meats full of good nouriſhment, as Broths, and Cullices of Capons, Pigeons, Veal, and Mutton, boiling therein Violet and Mallow leaves. Conſerves muſt be ordained, which may ſtrengthen the debilitated powers, and humect the habit of the body; ſuch as are the Conſerves of Bugloſs, Violets, Borage, and Water Lillies. The following Broth will be profitable, ℞ *Lactucæ, Bugloſ. & portul. an. M.* i. *quatuor ſeminum frigid. major. an.* ℥ ß. *ſeminis Barberis*, ℥ i. Let them all be boiled with a Chicken, and let him take the Broth every morning. If thirſt oppreſs him, the following Julep will be good. ℞ *Aquæ roſar.* ℥ iv. *aquæ viol.* ℔ ß. *ſaccari albiſſimi* ℥ vi. *fiat Julep, utatur in ſiti.* If the Patient be bound in his body, emollient and humecting Clyſters ſhall be appointed, made of the decoction of a Sheeps head and feet, Mallows, Marſh Mallows, Pellitory of the Wall, Violet leaves, and other things of the like faculty. Or that the remedy may be more ready and quickly made, let the Clyſters be of Oil and Milk. Topick remedies ſhall be Liniments and Baths. Let this be the example of a Liniment, ℞ *Olei Viol. & Amygdal. dulc. an.* ℥ ij. *Olei Lilior. & Lumbric. an.* ℥ i. *Axungiæ porci recentis*, ℥ iij. *Ceræ novæ quantum ſufficit*, *fiat Linimentum*, with which let the whole ſpine and part affected be anointed: This ſhall be the form of an emollient and humecting bath. ℞ *Fol. Malvæ, Biſmalvæ, Pariet. ana M.* vj. *Seminis Lini & fœnug. an.* ℔ ß. *coquantur in aqua communi, addendo Olei Lilior.* ℔ ix. Make a Bath: into which let the Patient enter when it is warm. When he ſhall come forth of the Bath, let him be dried with warm cloths, or reſt in his bed avoiding ſweat. But if the Patient be able to undergo the charge, it will be good to ordain a Bath of Milk, or Oil alone, or of them equally mixt together.

An Emollient Liniment for any Convulſion.

An Emollient and humecting Bath.

CHAP. XI.

Of the Cure of a Convulſion by Sympathy and pain.

The Cure of a Convulſion by a puncture or bite.

A Convulſion which is cauſed both by conſent of pain and communication of the affect, is cured by remedies which are contrary to the dolorifick cauſe. For thus if it proceed from a puncture or venemous bite, the wound muſt be dilated and enlarged by cutting the skin, that ſo the venenate matter may flow forth more freely, for which purpoſe alſo Medicins which are of a thin and liquid conſiſtence, but of a drying and digeſtive faculty ſhall be poured in, to call forth and diſſove the virulency, as Treacle and Mithridate diſſolved in *Aqua vitæ*, with a little of ſome Mercurial Powder; for this is a noble antidote. Alſo Cupping-glaſſes and ſcarifications will be good. Laſtly, the condition of all dolorifick cauſes, ſhall be oppugned by the oppoſition of contrary remedies; as if pain by reaſon of a pricked nerve or tendon, ſhall cauſe a Convulſion, it muſt preſently be reſiſted by proper remedies, as Oil of Turpentine, of *Euphorbium*, mixt with *Aqu. vitæ*, and alſo with other remedies appropriated to punctures of the nerves. If the pain proceed from exceſs of cold, becauſe cold is hurtful to the brain, the ſpinal marrow, and nerves; the Patient ſhall be placed in a hot air, ſuch as that of a Hot-houſe or Stove; all the ſpine of his back and convulſed parts muſt be anointed with the hot liniments above mentioned: for that is much better than ſuddenly to expoſe him from the conceived convulſifick cauſe to a moſt ſhot fire or warm bath. In the mean time the Chirurgeon muſt take diligent heed, that as ſoon as the ſign of the Convulſion to come, or already preſent, or at hand, do ſhew themſelves, that he put a ſtick between the Patients teeth, leſt they be faſt locked up by the pertinacious contraction of the Jaws, for many in ſuch a caſe have bit off their Tongues, for which purpoſe he ſhall be provided of an inſtrument called *Speculum Oris*, which may be dilated and contracted according to your mind by the means of a ſcrew, as the following figures demonſtrate; the one preſenting it open and ſomewhat twined up, and the other as it is ſhut.

A worthy *Altxipharmacum* or Antidote.

You muſt hinder the locking of the teeth.

The

The Figure of a Speculum Oris, *to open the Teeth when they are locked or held faſt together.*



CHAP. XII.

Of the Palſie.

THe Palſie is the reſolving or mollification of the nerves, with privation of ſenſe and motion, not truly of the whole Body, but of the one part thereof, as of the right or left ſide. And ſuch is properly named the Palſie: for otherwiſe and leſs properly the reſolution of ſome one member is alſo called the Palſie: for when the whole body is reſolved, it is an Apoplexy. Therefore the Palſie ſometimes takes half the body, otherwhiles the upper parts, which are between the Navel and the Head, otherwhiles the lower which are from the Navel to the Feet; ſometimes the Tongue, Gullet, Bladder, Yard, Eyes; and laſtly, any of the particles of the body. What a Palſie is. The differences thereof.

It differs from a Convulſion in its whole nature. For in a convulſion, there is a contention and contraction of the part, but in this a reſolving and relaxation thereof: beſides, it commonly happeneth that the ſenſe is either aboliſhed or very dull, which uſually remains perfect in a Convulſion. There are ſome which have a pricking, and as it were great pain in the part. How it differs from a Convulſion.

The cauſes are internal or external; the internal are humours obſtructing one of the Ventricles of the Brain, or one ſide of the ſpinal marrow, ſo that the animal faculty, the worker of Senſe and Motion, cannot by the nerves come to the part to perform its action. The external cauſes are a fall, blow, and the like injuries, by which oft-times the joints are diſlocated, the ſpinal marrow wreſted aſide, and conſtrictions and compreſſions of the *Vertebræ* ariſe, which are cauſes that the animal ſpirit cannot come to the Organs in its whole ſubſtance. But it is eaſie by skill in Anatomy perfectly to underſtand by the reſolved part the ſeat of the morbifick cauſe, for when there is a Palſie properly ſo called, that is, when the right or left ſide is wholly ſeized upon, then you may know that the obſtruction is in the brain, or ſpinal marrow; but if the parts of the head be untoucht, either of the ſides being wholly reſolved, the fault remains in the original of the ſpinal marrow; if the arms be taken with this Diſeaſe, we may certainly think that the matter of the Diſeaſe lies hid in the fifth, ſixth, and ſeventh *Vertebra* of the neck. But if the lower members languiſh, we muſt judge the Paralytick cauſe to be contained in the *Vertebræ* of the Loins and Holy-bone. Which thing the Chirurgeon muſt diligently obſerve that he may always have recourſe to the original of the Diſeaſe. The Palſie which proceeds from a nerve cut, or exceedingly bruiſed, is incurable, becauſe the way to the part by that means is ſhut againſt the animal ſpirit. Old men ſcarce or never recover of the Palſie, becauſe their native heat is languid, and they are oppreſſed with abundance of excrementitious humours; neither doth an inveterate Palſie which hath long poſſeſt the part, neither that which ſucceeds an Apoplexy, yield us any better hope of cure. It is good for a Fever to come upon a Palſie, for it makes the diſſipation of the reſolving and relaxing humour, to be hoped for. When the member affected with the Palſie is much waſted, and the oppoſite, on the contrary, much increaſed in quantity, heat, and colour, it is ill: for this is a ſign of the extreme weakneſs of the afflicted part, which ſuffers it ſelf to be defrauded of its nouriſhment, all the proviſion flowing to the ſound or oppoſite ſide. The Cauſes. It is good for a Fever to happen upon a Palſie.

CHAP. XIII.

Of the Cure of the Palſie.

IN the cure of the Palſie we muſt not attempt any thing, unleſs we have firſt uſed general remedies, Diet and Purging; all which care lieth upon the learned and prudent Phyſician. The Decoction of *Guaiacum* is very fit for this purpoſe, for it procures ſweat and attenuates, digeſts and drieth up all the humidity with relaxeth the nerves: but when ſweat doth not flow, it ſhall not The decoction of *Guaiacum* is good for a Palſie.

be

Things actually hot good for to be applied to paralytick members.

be unprofitable to put about the reſolved members, bricks heated red hot in the fire and quenched in a decoction of Wine, Vinegar, and reſolving herbs, or alſo ſtone Bottles, or Ox and Swine bladders, half filled with the ſame decoction; for ſuch heat which is actual reſuſcitateth and ſtrengtheneth the heat of the part, which in this Diſeaſe is commonly very languid: Then the Patient ſhall go into a Bathing-tub, which is vailed or covered over, juſt as we have deſcribed in our Treatiſe of Baths, that ſo he may receive the vapour of the following decoction. ℞ *Fol. Salviæ, Lavend. Lauri major. Abſinth. Thym. Angelicæ, Rutæ, ana M.* ß. *Florum Chamæm. Melil. Anethi, Anthoſ. ana* P. ij. *Baccar. Laur. & Juniper. Conquaſſatur. ana* ℥ i. *Caryophyl.* ℥ ij. *Aquæ fontanæ & Vini albi, ana* ℔ iv. Let them be all put in the Veſſel mentioned in the Treatiſe lately deſcribed for uſe. The Patient ſhall keep himſelf in that Bathing-tub, as long as his ſtrength will give him leave, then let him be put into his bed well covered, where he ſhall ſweat again, be dried, and reſt. Then let him be preſently anointed with the following Ointment, which *Leonellus Faventius* much commends: ℞ *Olei Laurini & de Terebinth. ana* ℥ iij. *Olei Nardini & petrolei, ana* ℥ i. *Vini malvatici,* ℥ iv. *Aquæ vitæ* ℥ ij. *Pyrethri, Piperis, Sinap. Granor. Junip. Gummi hederæ, anacard. Laudani puri, an.* ℥ i. ß. *Terantur & miſceantur omnia cum Oleis & Vino: bulliant in vaſe duplici uſque ad Vini conſumptionem, facta forti expreſſione, adde Galbani, Bdellii, Euphorbii, Myrrhæ, Caſtorei, adipis Urſi, Anatis, Ciconiæ, an.* ℥ ij. Make an Ointment in form of a Liniment, adding a little Wax if need ſhall require. Or you ſhall uſe the following remedy approved by many Phyſicians: ℞ *Myrrhæ & Aloes, Spicæ nardi, Sanguinis draconis, thuris, opoponacis, Bdellii, Carpobalſami, amomi, ſarcocollæ, croci, maſtic. gummi arabici, ſtyrac. liquidæ, ladani, caſtorei, ana* ℥ ij. *Moſchi,* ℈ i. *Aquæ vitæ,* ℥ i. *Terebinthinæ venetæ, ad pondus omnium, pulveriſabuntur pulveriſanda & gummi cliquabuntur cum aqua vitæ & aceti tantillo.* And let them all be put in fit Veſſels, that may be diſtilled in *Balneo Mariæ*, and let the Spine of the Back, and paralytick limbs be anointed with the liquor which comes from thence. I have often tried the force of this following Medicin: ℞ *Rad. Angel. Ireos floren. gentian. cyperi, ana* ℥ i. *Calami aromat. Cinam. Caryophyl. nucis Moſch. macis, ana* ℈ ij. *Salviæ major. Iuæ arthriticæ, Lavend. roriſm. ſatureiæ, puleg. calament. mentaſtri, ana M.* ß. *florum. chamæm. melil. hyperic. anthos, ſtœchad. ana* P. i. *Conciſa omnia contundantur, & in Aqua vit. & Vini malvat. an.* ℔ ij. *infundantur.* And let them be diſtilled in *Balneo Mariæ*, like the former, let the affected parts be moiſtned with the diſtilled liquor, of which alſo you may give the Patient a ſpoonful to drink in the morning with ſome Sugar. For thus the Stomach will be heated, and much phlegm contained therein as the fewel of this diſeaſe, will be conſumed.

Leo Faventius his Ointment.

An approved Ointment for the Palſie.

A diſtilled Water, good to waſh them outwardly, and to drink inwardly.

Exerciſes and frictions. Chymical Oil.

You muſt alſo appoint Exerciſes of the affected parts, and frequent and hard frictions, with hot linen cloths, that the native heat may be recalled, and the excrements contained in the parts digeſted: you may alſo uſe the Chymical Oyls of Roſemary, Thyme, Lavender, Cloves, Nutmegs; and laſtly, of all Spices, the manner of extracting whereof, we ſhall hereafter declare in a peculiar Treatiſe.

CHAP. XIV.

Of Swooning.

What Swooning is. Three cauſes of Swooning.

SWooning is a ſudden and pertinacious defect of all the powers, but eſpecially the vital; in this, the Patients lie without motion or ſenſe, ſo that the Ancients thought that it differed from Death onely in continuance of time. The cauſe of Swooning, which happens to thoſe that are Wounded, is Bleeding, which cauſeth a diſſipation of the ſpirits: or Fear, which cauſeth a ſudden and joint retirement of the ſpirits to the heart. Whence follows an intermiſſion of the proper duty, as alſo of of the reſt of the faculties, whileſt they being thus troubled, are at a ſtand. Alſo Swooning happens by a putrid and venenate vapour, carried to the Heart by the Arteries, and to the Brain by the Nerves; by which you may gather, that all Swooning happens by three cauſes. The firſt is, by diſſipation of the ſpirits and native heat, as in great bleeding. And then by the oppreſſion of theſe ſpirits by obſtruction, or compreſſion, as in Fear, or Tumult; for thus the ſpirits fly back haſtily from the ſurface and habit of the body, unto the Heart and Center. Laſtly, By Corruption, as in bodies filled with humours, and in poiſonous Wounds. The ſigns of Swooning are paleneſs, a dewy and ſudden ſweat ariſing, the failing of the pulſe, a ſudden falling of the body upon the ground without ſenſe and motion, a coldneſs poſſeſſing the whole body, ſo that the Patient may ſeem rather dead than alive. For many of theſe who fall into a Swoon die, unleſs they have preſent help.

The cure of Swooning cauſed by diſſipation of ſpirits. The cure of Swooning cauſed by a venenate air. The cure of Swooning cauſed by oppreſſion and obſtruction.

Therefore you ſhall help them, if when they are ready to fall, you ſprinkle much cold water in their face, if that the ſwooning happen by diſſipation of the ſpirits; or if they ſhall be ſet with their faces upwards upon a bed, or on the ground, as gently as may be; and if you give them bread dipt in Wine to hold and chew in their mouths. But if it be cauſed by a putrid vapour and poiſonous air, you ſhall give them a little Mithridate or Treacle in *Aqua vitæ* with a Spoon, as I uſually do to thoſe which have the Plague, or any part affected with a Gangrene, or Spacel. But if the Patients cannot be raiſed out of their Swoons, by reaſon of the pertinacious oppreſſion and compreſſion of the ſpirits about the Heart, you muſt give them all ſuch things as have power to diffuſe, call forth, and reſuſcitate the ſpirits, ſuch as are, ſtrong Wines to drink, ſweet Perfumes to ſmell: You muſt call them by their own name loud in their ear, and you muſt pluck them ſomewhat hard by the hairs of the Temples and Neck. Alſo rub the Temples, Noſtrils, Wriſts, and Palms of the Hands with *Aqua vitæ*, wherein Cloves, Nutmegs, and Ginger have been ſteeped.

CHAP.

CHAP. XV.

Of Delirium (i. e.) *Raving, Talking idly, or Doting.*

DOting or Talking idly, here is uſed for a ſymptom which commonly happeneth in Fevers cauſed by a wound, and inflammation; and it is a perturbation of the fanſie and function of the mind, not long induring. Wherefore ſuch a doting happens upon Wounds by reaſon of vehement pain, and a fever, when as the nervous parts, as the joints, ſtomach, and midriff, ſhall be violated. What a ſymptomatical *Delirium* is. The cauſes thereof.

For the Ancients did therefore call the Midriff *Phrena*, becauſe when this was hurt, as if the mind it ſelf were hurt, a certain phrenzie enſues; that is, a perturbation of the animal faculty, which is imployed in ratiocination, by reaſon of the community which the *Diaphragma* hath with the Brain, by the Nerves ſent from the ſixth conjugation, which are carried to the ſtomach. Therefore Doting happens by too much bleeding, which cauſeth a diſſipation of the ſpirits, whereby it happens that the motions and thoughts of the mind err, as we ſee it happens to thoſe who have bled much in the amputation of a member. And it happens by the puncture of a venemous Beaſt, or from Seed retained or corrupted in the Womb, or from a Gangrene or Sphacel, from a venenate and putrid air carried up to the Brain, or from a ſudden tumult and fear. Laſtly, What things ſoever with any diſtemper, eſpecially hot, do hurt and debilitate the mind These may cauſe Doting by the afflux of humours, ſpecially cholerick, by diſſipation, oppreſſion or corruption of the ſpirits. Therefore if it ſhall proceed from the inflammation of the Brain, and *Meninges* or Membranes thereof; after Purging and Bloudletting by the preſcription of a Phyſician, the hair being ſhaved or cut off, the head ſhall be fomented with Roſe Vinegar, and then an Emplaiſter of *Diacalcitheos*, diſſolved in Oil and Vinegar of Roſes, ſhall be laid thereupon. Sleep ſhall be procured with Barly creams, wherein the ſeeds of white Poppy have been boiled, with Broths made of the decoction of the cold ſeeds of Lettuce, Purſlain, Sorrel, and ſuch like. Cold things ſhall be applied to his Noſtrils, as the ſeeds of Poppy gently beaten with Roſe-water and a little Vinegar. Let him have merry and pleaſant Companions that may divert his mind from all cogitations of ſorrowful things, and may eaſe and free him of cares, and with their ſweet intreaties may bring him to himſelf again. But if it happen by default of the ſpirits, you muſt ſeek remedy from thoſe things which have been ſet down in the Chapter of Swooning. Why the Brain ſuffers with the Midriff. The Cure.

The End of the Nineth Book.

BOOK X.

Of the Green and Bloudy WOUNDS *of each Part.*

CHAP. I.

Of the kind or differences of a broken Skull.

NOw that we have briefly treated of Wounds in general, that is, of their differences, ſigns, cauſes, prognoſticks and cure, and alſo ſhewed the reaſon, of the accidents and ſymptoms which uſually follow and accompany them, it remains that we treat of them as they are incident to each part, becauſe the cure of Wounds muſt be diverſly performed according to the diverſity of the parts. Now we will begin with the Wounds of the Head. Therefore the head hath the hairy ſcalp lightly bruiſed without any wound, otherwhiles it is wounded without a Contuſion, and ſometimes it is both contuſed and wounded: but a fracture made in the skull, is ſometimes ſuperficiary, ſometimes it deſcends even to the *Diploe*, ſometimes it penetrates through the two Tables, and the Meninges, into the very ſubſtance of the Brain; beſides the Brain is oft-times moved and ſhaken with breaking of the internal Veins, and divers ſymptoms happen when there appears no Wound at all in the head: of all and every of which we will ſpeak in order, and add their cure, eſpecially according to the opinion of the divine *Hippocrates*. He in his Book *Of the Wounds of the Head*, ſeems to have made 4 or 5 kinds of fractures of the Skull. The firſt is called a Fiſſure or Fracture, the ſecond a Contuſion or Colliſion, the third is termed *Effractura*, the fourth is named *Sedes*, or a ſeat; the fifth (if you pleaſe to add it) you may call a Counterfiſſure, or as the Interpreter of *Paulus* calls it, a *Reſonitus*. As when the bone is cleft on the contrary ſide, to that which received the ſtroke. There are many differences of theſe five kinds of a broken Skull. For ſome fractures are great, ſome ſmall, and others indifferent: ſome run out to a greater length or bredth, others are more contracted; ſome reſide onely in the ſuperficies, others deſcend to the *Diploe*, or elſe pierce through both the Tables of the Skull; ſome run in a right line, others in an oblique and circular; ſome are complicated amongſt themſelves, as a Fiſſure is neceſſarily and always accompanied with a Colliſion or Contuſion, and others are aſſociated with divers accidents, as pain, heat, ſwelling, bleeding, and the like. Sometimes the Skull is ſo broken, that the Membrane lying under it, is preſſed with ſhivers of the Bone, as with pricking Needles. Somewhiles none of the bones fall off. All which differences are diligently to be obſerved, becauſe they force us to vary cure, and therefore for the help of memory, I have thought good to deſcribe them in the following Table. The differences of a broken head. The kinds of a broken skull out of *Hippocrates*. Differences from their quantity. Differences from their figure. From their complication.

A Table

A Table of the Fractures of the Skull.



Another Table of the differences of a fractured Skull.



CHAP.

CHAP. II.

Of the cauſes and ſigns of a broken Skull.

THe cauſes of a broken Skull are external, as a fall, a blow, or ſtroak with any kind of Weapon, ſharp, obtuſe, heavy, hard, the bitings of Beaſts, and many other things of the like kind. The external cauſes.
But the ſigns by which we come to know that the Skull is broken, are of two kinds; for ſome of them are found out by the reaſoning and diſcourſe of the mind, other by the ſenſe, as thoſe which lay open the Wound to the Eye and Hand.

The Rational ſigns ſhew by theſe things which have happened upon the thing it ſelf, whether it be, and of what ſort it is. For you may know the Skull is broken, if the Patient ſhall fall down with the ſtroak, or if he ſhall fall headlong from a high place upon ſome hard thing. If for ſome time after the ſtroak he ſhall lie without ſpeaking, ſight, and hearing; if he ſhall have felt and feel much pain, ſo that he is often forced to put his hand to the Wound. But alſo the Weapon is to be conſidered, that is, whether if it be heavy, obtuſe, pricking, or ſharp. Alſo we muſt conſider with what and how great ſtrength the ſtroak was given, and with how great anger, and from what diſtance the Weapon fell. Alſo we muſt conſider whether the Patient received the blow with his Head unarmed and naked; whether he fell into a Swoon preſently after the blow; whether when he came to himſelf, he was in his right ſenſes; whether his eyes were blinded; whether he were troubled with a giddineſs or dizineſs, and whether he bled at the noſe, mouth, ears, or eyes; and laſtly, whether he vomited. For *Hippocrates* writes, that thoſe who have their Brain cut, muſt neceſſarily have a Fever and vomiting of Choler to enſue thereupon, which *Galen* confirming in his Commentary, ſaith that the ſame happens alſo when the Wound comes to the Membranes of the Brain. Rational cauſes. *Aphor. 50. ſect. 6.*

Alſo a dull ſound as from a broken Veſſel coming from the Skull, (the Hairy ſcalp and *Pericranium* being taken off) and it being lightly ſmitten upon with an iron Probe, is ſaid to be a ſign of a fracture thereof, as it is recorded by *Paulus Ægineta*. Truly all theſe ſigns make a great conjecture, or rather aſſuredneſs that the Skull is wounded, and the Brain hurt, as which cannot happen unleſs the bone be broken, as *Celſus* hath written. Yet many have had their Skulls broken, who had no ſuch ſign immediately after the blow, but this is very ſeldom. But I do not think fit amongſt ſo many ſigns, here to omit that which is ſet down by *Guido*. If any (ſaith he) will know in what place the Skull is broke, let the Patient hold faſt between his fore-teeth one end of a Lute ſtring or thred, and the Chirurgeon hold the other in his hand, then let him lightly touch or play upon the ſtring with his fingers; for in the very inſtant of the ſound or ſtroke, the Patient will be certainly admoniſhed, or perfectly perceive the part of the Skull that is broken, and as overcome and forced by this ſenſe of pain, will by lifting up of his hand make demonſtration thereof. As yet I have not been able to find the truth hereof by experience, although I have made trial of it in many. Wherefore I cannot ſay any thing certainly of this ſign, as neither of that which is mentioned by *Hippocrates* in *Coais Præſ.* In ſuch as you doubt whether the bones of the Skull be broken or not, you muſt judge by giving them the ſtalk of the Aſphodil to chaw on both ſides of their jaws, but ſo that you bid them withall obſerve, whether they perceive any bone to crackle or make a noiſe in their heads; for thoſe which are broken ſeem to make a noiſe. *Lib. 8. cap 4.* *Hippocrates* and *Guido's* conjectural ſigns of a broken skull.

But paſſing over theſe things, now let us come to thoſe ſigns which may be obvious to our ſenſes.

CHAP. III.

Of the ſigns of a broken Skull, which are manifeſt to our ſenſe.

THoſe ſigns are here ſaid to be manifeſt to ſenſe, which when the bone is bared, manifeſt the Wound to our Eyes, Fingers, and Probe. But if the hairs ſtand upon one end in the Wound, you may know the bone is broke, becauſe the hair which yields to the violence of the blow, cannot be ſo cut, the bone which reſiſts the ſtroak being not violated, as it is obſerved by *Hippocrates*; wherefore we may by the ſight of this one thing, before any inſpection of the Wound it ſelf, ſuſpect by a probable conjecture, that the Skull is broken, and perſuade the beholders or ſtanders by ſo much. Senſible ſigns of a broken skull before the dividing of the skin. *Lib. de Vulner. cap.*

Moreover we may, before we have cut the skin acroſs, or laid bare the bone, give a gueſs by our feeling, whether the Skull be broken or no, if we by preſſing down our fingers near the Wound ſhall perceive the bone either to ſtand up, or be preſſed down otherwiſe than it ſhould naturally be.

The skin being cut croſs-wiſe, and the bone laid bare, if the fracture be not obvious to the eye, you muſt trie with your Probe, which muſt neither be too thin nor too ſharp, leſt by falling into ſome natural cranies, it may cauſe us to ſuſpect without any cauſe that the bone is broken; neither let it be too thick, leſt the little clifts may deceive you. If when your Probe comes to the bone it meets with nothing but that which is ſmooth and ſlippery, it is a ſign that it is whole. What Probe muſt be uſed in ſearching for a fracture.

But on the contrary, if you find it any thing rough, ſpecially where there is no ſuture, it ſhews the bone is broken. But let the Chirurgeon conſider, that the fractures are not ſeldom upon the ſutures; and that the ſutures have not always one and their natural ſite, as alſo it often comes to paſs that the broken clift, or cut bone, can neither be perceived by your ſight nor inſtrument: wherefore if you think there is any ſuch thing, by the rational ſigns above mentioned; anoint the place with Writing Ink and Oil, and ſo you ſhall find the crack or clift, by the means we ſhall ſhew you hereafter.

When you are certain of the fracture, then you muſt diligently conſider the greatneſs of the Diſeaſe, and apply Medicins ſpeedily. Verily when a fracture chances to light upon any ſuture, the

Lib. 5. Epid. in Autonomus of Omilum, Hippocrates was deceived by the futures.

the diſeaſe is hard to be known, unleſs the fracture be very great, becauſe the ſutures by their clifts and roughneſs reſemble fractures; wherefore *Hippocrates* ſaith, that he was deceived by them. Now having briefly delivered the differences and ſigns of a broken Skull, it is time to come to the ſeveral kinds thereof, with a Fiſſure.

CHAP. IV.

Of a Fiſſure, being the firſt kind of a broken Skull.

Upon what occaſion the hairy ſcalp muſt be cut.

IF the Chirurgeon by the fore-mentioned ſigns ſhall know that the Skull is broken, or crackt, and if the Wound made in the muſculous skin ſhall not be thought ſufficient for ordering the Fiſſure, then muſt he ſhave off the hair, and cut with a Razor or Inciſion-knife, the muſculous Skin with the *Pericranium* lying under it in a triangular or quadrangular figure to a proportionable bigneſs, always ſhunning as much as in him lies, the ſutures and temples; neither muſt he fear any harm to enſue hereof; for it is far better to bare the Bone by cutting the Skin, than to ſuffer the kind and nature of the Fracture to remain unknown by a too religious preſervation of the skin; for the skin is cured without any great ado, though pluckt off to no purpoſe.

Celſus.

Hippocrates.

For it is much more expedient (in *Hippocrates* opinion) to cure Diſeaſes ſafely and ſecurely, though not ſpeedily, than to do it in a ſhorter time with fear of relapſe and greater inconveniencies. Let this diſſection be made with a Razor or ſharp Knife, and if there be any Wound made in the skin by the Weapon, let one of your Inciſions be made agreeable thereto.

A Razor, or Inciſion-Knife.

The manner how to pull the hairy ſcalp from the broken Skull.

Now therefore the muſculous skin together with the *Pericranium* muſt be divided, and cut with a ſharp Razor preſſed and guided with a ſtrong and ſteddy hand; then it muſt be ſo pluckt from the bone or skull lying under it, that none thereof remain upon the bone; for if it ſhould be rent or torn with the Trepan, it would cauſe vehement pain with inflammations. You muſt begin to pull it back at the corners of the lines croſſing each other with right angles, with this Chiſſel whoſe figure you ſee here expreſſed.

A Chiſſel or Inſtrument to pull back or ſeparate the Pericranium *from the Skull.*

Then you muſt fill all the Wound with Bolſters of fine ſoft lint, that ſo the lips may be kept further aſunder. But you ſhall apply upon it Medicins fit to ſtanch bloud. But if it ſo come to paſs that the bloud flows forth ſo violently, that it can be ſtaid by no means, the Veſſel it ſelf muſt be bound, after this manner.

The manner to bind a Veſſel in caſe of too much bleeding. A Hiſtory.

Firſt thruſt through the muſculous skin on the outſide with a needle and thred, then thruſt the needle back again, then tie the thred on a knot on the out-ſide, but firſt put ſome lint rolled up to the bigneſs of a Gooſe-quill between the thred and the hairy ſcalp on both ſides thereof, leſt the ſtrait twitching of the thred which may ſerve to ſtay the bleeding, may cut and tear the skin, or cauſe pain: then muſt you raiſe his head ſomewhat higher.

I have lately tried, and performed this upon a certain Coach-man, who, thrown from the Coach upon his head on a pavement of Free-ſtone, exceedingly bruiſed the hinder part of the *Bregma*, for which cauſe it was fit to open the muſculous skin, with a croſs Inciſion, both that the congealed bloud might be preſſed out, as alſo that the fracture (if there were any) might be obſerved. But an Artery being cut in performance hereof, when as the Chirurgeon, who was there preſent, could not ſtay the bloud leaping out with violence; and the Coachman already had loſt ſo great a quantity thereof, that his ſtrength was ſo much decayed that he could not ſtir himſelf in his Bed, or ſcarce ſpeak: I being called, ſhewed them by experience, that whereas aſtringent Medicins were uſed before to no purpoſe, it was better to ſtay the bleeding by binding the Veſſel, than to let the Patient die for a childiſh fear of pricking him.

A way to find a fracture in the Skull, when it preſents not it ſelf to the view at the firſt.

A ſign that both the Tables are broken.

But that we may return to our former matter, the Chirurgeon ſhall the next day conſider, with what kind of fracture the bone is hurt; and if no ſigns of hurt appear to the eyes, nor be perceived with your fingers and probe, yet ſome of the rational ſigns may cauſe one to have a conjecture that there is a fracture: Then you muſt anoint, as we told you before, the bared bone with Writing Ink, and a little Oil of Roſes, that the cleft or crack may be died or coloured therewith, if that there be any there. Then the next dreſſing you muſt dry the bone with a linnen cloth, and ſcrape off the Ink and Oil with ſcraping Inſtruments made for the purpoſe, if any part thereof ſhall be ſunk into the bone, for if there be any crack, it will be black: Wherefore you muſt continue ſcraping until no ſign of the Fiſſure remain, or elſe until you come even to the *Dura Mater*. But that he may be more certain whether the Fiſſure pierce through both the Tables of the ſkull, he muſt bid the Patient, that

ſtopping

ſtopping his Noſe and Mouth he ſtrive to breath with a great indeavour. For then bloudy matter, or *ſanies*, will ſweat through the Fiſſure: For the breath driven forth of the Cheſt, and prohibited paſſage forth, ſwells and lifts up the ſubſtance of the Brain, and the *Meninges*, whereupon that frothy humidity and *ſanies* ſweats forth. Therefore then the bone muſt be cut, even to the *Dura Mater*, with a *Radula*, and other ſcraping Inſtruments fit for that purpoſe, yet ſo as you hurt not the Membrane; but if the Fiſſure ſhall be ſomewhat long, it will not be convenient to follow it all the extent thereof, for Nature will repair and reſtore the reminant of the Fiſſure by generating a *Callus*; beſides alſo, the Chirurgeon according to *Celſus* opinion, muſt take away as little of the bone as he can, becauſe there is nothing ſo fit to cover the Brain as the Skull. Therefore it ſhall ſuffice to make a paſſage, whereby the bloud and *ſanies* may paſs and be drawn forth, leſt that matter being ſuppreſt, may corrupt the bone, and cauſe an inflammation in the Brain. But the broken Bone muſt be taken forth within three days, if it be poſſible, eſpecially in Summer, for fear of inflammation. Yet I have often taken forth with a Trepan, and with Scrapers the bones of the Skull, after the ſeventeenth day, both in Winter and Summer, and that with happy ſucceſs. Which I have the rather noted, leſt any ſhould at any time ſuffer the wounded to be left deſtitute of remedy, for it is better to try a doubtful remedy than none. Yet the By-ſtanders ſhall be admoniſhed and told of the danger, for many more die, who have not the broken bones of the Skull taken out, than thoſe that have.

A ſign that both the Tables are broken.

You may uſe the Trepan after the tenth day.

But the Inſtruments with which the wounded or cleft bones may be cut out, are called *Scalpri*, or *Radulæ*, of which I have cauſed divers ſorts to be here decyphered, that every one might take his choice according to his mind, and as ſhall be beſt for his purpoſe. But all of them may be ſcrued into one handle, the figure whereof I have exhibited.

Radulæ *or* Scalpri, (i.) *Shavers or Scrapers.*



Radulæ *of another form, for the better cutting of the greater Bones.*



To conclude, When the Skull ſhall be wounded or broken with a ſimple Fiſſure, the Chirurgeon muſt think he hath done ſufficient to the Patient, and in his Art, if he ſhall divide the bone, and dilate the Fiſſure, or clift, with the deſcribed Inſtruments, though he have uſed no Trepan, although the Fiſſure pierce through both the Tables. But if it doth not exceed the firſt Table, you muſt ſtay your ſcrapers as ſoon as you come to the ſecond, according to the opinion of *Paulus*: but if the bone ſhall be broken and ſhivered into many pieces, they ſhall be taken forth with fit Inſtruments, uſing alſo a Trepan, if need ſhall require, after the ſame manner as we ſhall ſhew you hereafter.

It is ſufficient in a ſimple fiſſure to dilate it with your *Scalpri* onely and not to Trepan it.

CHAP. V.

Of a Contuſion, which is the ſecond ſort of Fracture.

What an *Ecchymoſis* is.

AN *Ecchymoſis*, that is, effuſion of bloud, preſently concreting under the muſculous Skin, without any Wound, is oft cauſed by a violent contuſion. This Contuſion if it ſhall be great, ſo that the Skin be divided from the Skull, it is expedient that you may make an Inciſion, whereby the bloud may be evacuated and emptied. For in this caſe you muſt wholly deſiſt from ſuppurative Medicins (which otherwiſe would be of good uſe in a fleſhy part) by reaſon that all the moiſt things are hurtful to the Bones, as ſhall be ſhewn hereafter.

How a Contuſion of the Skull muſt be cured.

Different cures of a depreſſed Skull.

Such like Contuſions more frequently happen in Children, being eaſily perceived by the ſoftneſs and inundation of the contuſed part: forth of which oft-times when I have opened them with my Inciſion-Knife, ſerous clotted and blackiſh bloud hath iſſued. The reſidue of the Cure is perfected by moderate compreſſion of the part, and drying Medicins. Moreover the Skull of a Child may be preſſed down by a great Contuſion, even as we ſee it happens in thin Veſſels of Braſs, Lead, or Pewter, for oft-times by the preſſure of your finger, they are ſo dented in, that the print thereof remains; yet ſometimes they fly back of themſelves, and again acquire their former plainneſs and equability, which alſo happens in the bones of Children, Women, and ſuch as are ſoft, humid, and phlegmatick. But if the Bones do not ſpring back of themſelves, you muſt apply a Cupping-glaſs with a great flame; withall command the Patient to force his breath up as powerfully as he can, keeping his mouth and noſe cloſe ſhut; for thus there will be hope to reſtore the depreſſed Bone to its place, by the ſpirits forced upwards to the Brain and Skull, by the powerful attraction of the Cupping-glaſs. But if ſo be that the Bone cannot by this means be reſtored, then you muſt make an Inciſion in the skin, and faſten ſuch a Trepan as you ſee here delineated, into the depreſt or ſetled part of the Bone, and ſo pull it directly upwards; juſt as we ſee Coopers raiſe the ſtaves of their Caſk when they are ſunk too much in.

But if the Bone ſhall be too ſtrong, thick, and denſe, ſo that this Inſtrument will not ſerve to pluck it forth; then you muſt perforate the Skull in the very center of the depreſſion, and with this threefold Inſtrument or Levatory, put into the hole, lift up and reſtore the Bone to its natural ſite; for this ſame Inſtrument is of ſtrength ſufficient for that purpoſe. It is made with three feet, that ſo it may be applied to any part of the head which is round; but divers heads may be fitted to the end thereof, according as the buſineſs ſhall require, as the Figure here placed doth ſhew.

A three-footed Levatory.



But if at any time it comes to paſs that the Bone is not totally broken or depreſt, but onely on one ſide; it will be fit ſo to lift it up, as alſo to make a vent for the iſſuing out of the filth, to divide the Skull with little Saws like theſe which you ſee here expreſſed; for thus ſo much of the bone as ſhall be thought needful, may be cut off without compreſſion, neither will there be any danger of hurting the Brain or Membrane with the broken bone.

The

The figures of Saws fit to divide the Skull.



But if by ſuch ſigns as are preſent, and ſhall appear, we perceive or judge that the contuſion goes but to the ſecond Table, or ſcarce ſo far, the baring or taking away of the bone muſt go no farther than the contuſion reaches, for that will be ſufficient to eſchew and divert inflammations and divers other ſymptoms. And this ſhall be done with a ſcaling or Deſquamatory Trepan (as they term it) with which you may eaſily take up as much of the bone as you ſhall think expedient: And I have here given you the figure thereof.

A Deſquamatory, or Scaling Trepan.



A Delineation of other Levatories.

A A. *Shews the point or tongue of the Levatory, which muſt be ſomewhat dull, that ſo it may be the more gently and eaſily put between the* Dura Mater *and the Skull, and this part thereof may be lifted up ſo much by the head or handle taken in your hand, as the neceſſity of the preſent operation ſhall require.*

B *Intimates the body of the Levatory, which muſt be four ſquare, leſt the point or tongue put thereon ſhould not ſtand faſt, but the end of this body muſt reſt upon the ſound bone, as on a ſure foundation.*

The uſe thereof is thus, Put the point or tongue under the broken or depreſſed bone, then lift the handle up with your hand, that ſo the depreſſed bone may be elevated.

C *Shews the firſt Arm of the other Levatory, whoſe crooked end muſt be gently put under the depreſſed bone.*

D *Shews the other Arm, which muſt reſt on the ſound bone, that by the firm ſtanding thereof, it may lift up the depreſſed bone.*

CHAP. VI.

Of an Effracture, or depreſſion of the Bone, being the third kind of Fracture.

What a Contuſion is.

What an Effracture is.

The cauſe of Effractures.

The Cure.

BEfore I come to ſpeak of an Effracture, I think it not amiſs to crave pardon of the courteous and underſtanding Reader, for this reaſon eſpecially, that as in the former Chapter, when I had determined and appointed to ſpeak of a Contuſion, I inſerted many things of a Depreſſion; ſo alſo in this Chapter of an Effracture, I intend to intermix ſomething of a Contuſion; we do not this through any ignorance of the thing it ſelf; for we know that it is called a Contuſion when the bone is depreſt and cruſht, but falls not down. But an Effracture is when the bone falls down, and is broken by a moſt violent blow. But it can ſcarce come to paſs, but that the things themſelves muſt be confounded and mixt, both as they are done, and alſo when they are ſpoken of; ſo that you ſhall ſcarce ſee a Contuſion without an Effracture, or this without that. Therefore the bones are often broken off and driven down with great and forcible blows, with clubs whether round or ſquare, or by falling from a high place directly down, more or leſs according to the force of the blow, kind of Weapon and condition of the Part receiving the ſame: Wherefore you muſt be provided with diverſity of remedies and inſtruments to encounter therewith. Wherefore admit the bone is preſſed down, and ſhivered into many pieces, now for that theſe ſplinters need not be taken out with a Trepan, you may do the buſineſs with Levatories made and neatly faſhioned for that purpoſe; ſuch as theſe, which here are expreſt.

A Levatory.

But we muſt have ſpecial care, leſt that in pulling and taking out of theſe ſcales and ſplinters we hurt the membranes. Theſe ſcales are ſometimes very rough and prickly, ſo that they cannot touch the *Meninges* without offence; but ſomewhiles the buſineſs is ſo intricate, that they cannot be taken out, unleſs by enlarging the fracture. Wherefore in this caſe, if there be a ſpace ſo large, as that the ends of theſe mullets may enter, you may eaſily ſhear off ſo much of the bone as ſhall be neceſſary and requiſite for the taking away of theſe ſcales without any aſſiſtance of the Trepan, which I have done very often, and with good ſucceſs; for the operation performed by theſe Mullets is far more ſpeedy and ſafe than that with the Trepan; and in the performance of every operation, the chief commendation is given to ſafeneſs and celerity.

Cutting Mullets, commonly called Roſtra Pſittaci, *or Parrots Beaks.*



Moreover I have thought good here to give you the Figures of Chiſels, Scrapers, Pincers, together with a leaden Mallet, becauſe ſuch Inſtruments are not onely very neceſſary to take forth the ſcales of bones which are broken, but alſo to plain and ſmooth thoſe which remain whole.

The

The Figures of Serapers, Pincers, a leaden Mallet, &c.



But here you muſt note, that a Trepan or Levatory, muſt never be applied to a bone quite broken, leſt the membranes lying under it be hurt by the compreſſion thereof. Therefore you muſt apply them to a ſound bone, but as near as you can to the Fracture, ſo that you take away as little of the Skull as is poſſible, leſt the Brain deſpoiled of its bony cover, take ſome harm thereby. Neither Effractures, nor yet Fiſſures, if they be of ſome length, muſt be followed to their ends; but think your ſelf well, if you have made a paſſage for the iſſuing forth of the *ſanies* or filth, and have drawn forth that bone which pricked the membranes. For Nature is accuſtomed by generating a *Callus* to ſoulder, or unite the bones of the Skull, as it alſo doth thoſe of the other parts; as we have read it written by *Hippocrates* and *Galen*; for which purpoſe, it hath by ſingular providence repleniſhed both the tables of the Skull, with a certain alimentary and bloudy matter, that with this as with marrow it might repair the loſs and defect of the bone.

Hipp. lib. de vuln. cap. Gal. lib. 6. meth. cap. ult.

A Hiſtory. The truth hereof was lately manifeſted in the ſervant of Maſter *Grolo*, who had an Effracture on the coronal bone by a grievous blow given him with the foot of a Mule; which when I underſtood, I divided the muſculous skin with a three-cornered ſection in that place, with an intent to apply a Trepan there; wherefore the day following, the bone being bored, and when I thought to draw it forth, yea verily endeavoured to pluck it forth, being already divided with the Trepan, I perceived a fearful production of an Effracture, by the moveableneſs of the bone ſhaking under my hand, for it reached from the midſt of the Fore-head to the leſſer corner of the Eye. Wherefore omitting both my determination, and endeavour to pull it forth, I thought I ſhould do ſufficiently for the Patient if I ſhould onely raiſe up the bone which was depreſt, for ſo it did not trouble the *Craſſa Meninx* by preſſing it and the matter and filth were let forth by a paſſage made with a Saw. So that in concluſion, he recovered perfectly, but that he loſt one of his Eyes which was adjoining to the Fracture.

CHAP. VII.

Of a Seat, being the fourth kind of a broken Skull.

What a Seat is. HIppocrates calls a Seat that kind of Fracture of the Skull, when the Weapon ſo falls upon the Skull, that the Fracture retaining the print thereof, is neither ſtretched forth any further, nor contracted to any leſs ſpace.

The Cure. And ſeeing there be many forms hereof, they all (whether they ſhall be ſuperficiary, or ſhall pierce even to the *Diploe*, or elſe paſs through both the Tables, whether it be with any loſs of the bony ſubſtance, whether it run long ways, or elſe be but ſhort, or otherwiſe are dilated to ſome bredth or elſe be but narrow; whether they ſhall be done with a cut, or with a prick with a Dagger, Stylet-to, Lance, or other kind of Weapon, whether they ſhall have this or that accident joined with them, I ſay all of them, how many and various ſoever they be) ought and muſt be cured by ſome of the formerly deſcribed Inſtruments and means. Yet this muſt be noted which as yet we have not remembred, that if it happen by a violent ſtroak and great wound, that a portion of the bone is wholly ſo cut off that it is clean ſevered from the reſt of the Skull, and hang onely by the *Pericranium* and the muſculous skin; yet you muſt not pluck it from the *Pericranium*, and caſt it away as unprofitable, but reſtore it to its proper ſeat and place, ſo by the force of Nature, to be glewed by a *Callus*, as *Celſus* hath obſerved.

Lib. 8. cap. 4.

A Hiſtory. I have tried the truth of this experiment in Captain *Hydron*, not very long ago. He had the middle part of the *Os Coronale*, of the bredth and length of three fingers, ſo cut with a ſharp Sword that it ſtuck not to the reſt of the bone; but ſcarce adhering to the *Pericranium* and muſculous skin lay turned down over his face, ſo that the *Dura Mater* was plainly ſeen; wherefore I prepared to pluck it from the skin, and caſt it away, but that I remembred *Hippocrates* Precept, where he bids, that the Brain ſhould not be robbed of its cover and left bare. Wherefore firſt of all I wiped away the bloud which was fallen upon the *Dura Mater*, whoſe motion you might plainly ſee, then I reſtored the portion of the bone to its place, and faſtned it on the upper ſide with a Suture conſiſting of three ſtitches; and that the reſidue of the matter might have paſſage forth, I filled the places between each ſtitch with lint: by this means, he by the mercy of God recovered, though at the ſame time he received many other large wounds in his body; which is a certain experiment, that we muſt caſt away no part of the Skull nor of the *Pericranium*, no not of the muſculous skin, unleſs neceſſity urge, therefore much leſs to leave the Brain naked and deſpoiled of its coverings.

CHAP. VIII.

Of a Reſonitus, *or Counter-Fiſſure, being the fifth kind of Fracture.*

What a *Reſonitus* is.

SOmetimes the Fracture is made in the part oppoſite to that which received the blow; as if the right ſide be ſtruck, the left is cloven; this kind of Fracture is very dangerous, becauſe we cannot find it out by any certain ſign, as it is written by *Hippocrates*, *Lib. de Vuln. Capitis*. Wherefore if at any time the Patient die of ſuch a Fracture, the Chirurgeon muſt be pardoned.

Lib.6.cap.90.

And although *Paulus Ægineta* laugh at this kind of Fracture, and thinks that it cannot happen to a mans head, as that which is hard and full, as it happens in empty Glaſs Bottles, yet I have ſometimes ſeen and obſerved it.

In whom this fracture may take place in divers bones of the skull.

Neither is their reaſon of any validity, who think Nature therefore to have framed the Head of many bones knit together by ſutures; leſt the fracture of the one ſide, ſhould be ſtretched to the other. For peradventure this may take place in ſuch as have expreſs ſutures, ſeated and framed according to Nature. But it takes no place in ſuch as either want them, or have them not ſeated according to Nature, or have them very cloſe and ſo defaced that it may ſeem one Bone grown together of many; This ſhall be made manifeſt by recital of the following Hiſtory.

A Hiſtory.

A ſervant of *Maſſus* the Poſt-maſter, had a grievous blow with a ſtone upon the right *Bregma*, which made but a ſmall wound, yet a great Contuſion and Tumor. Wherefore that it might more plainly appear, whether the Bone had received any harm, and alſo that the congealed bloud might be preſſed forth, the wound was dilated, the skin being open by *Theodore Hereus* the Chirurgeon, who as he was a skilful workman, and an honeſt man, omitted nothing which Art might do for his cure. When he had divided the skin, the bone was found whole, although it was much to be feared that it was broken, becauſe he fell preſently to the ground with the blow, vomited, and ſhewed other ſigns of a fractured skull; ſo it happened that he died on the one and twentieth day of his ſickneſs. But I being called to learn, and ſearch how he came by his death, dividing the skull with a Saw, found in the part oppoſite to the blow, a great quantity of *ſanies*, or bloudy matter, and an Abſceſs in the *Craſſa Meninx*, and alſo in the ſubſtance of the very Brain, but no ſutures but the two ſcaly ones. Therefore that is certain which is now confirmed by the authority of *Hippocrates*, as alſo by reaſon and experience, that a blow may be received on the one ſide, and the bone may be fractured on the oppoſite, eſpecially in ſuch as have either no ſutures, or elſe ſo firmly united and cloſed, that they are ſcarce apparent.

The *Reſonitus* may be in the ſame bone of the skull.

Neither is it abſurd, that the part oppoſite to that which received the ſtroak, of the ſame bone and not of divers bones may be cloven, and in thoſe men who have their skulls well made, and naturally diſtinguiſhed and compoſed with ſutures; and this both was, and is the true meaning of *Hippocrates*. That this may be the better underſtood, we muſt note that the oppoſite part of the ſame bone may be underſtood two manner of ways. Firſt, When the fracture is in the ſame ſurface of the ſmitten bone, as if that part of one of the bones of the *Bregma*, which is next to the Lambdal ſuture be ſmitten, and the other part next to the Coronal ſuture be cloven. Secondly, When as not the ſame ſuperficies and table which receives the blow, but that which lies under it is cleft, which kind of fracture

A Hiſtory.

I obſerved in a certain Gentleman, a Horſeman of Captain *Stempans* Troop; He in defending the breach of the Wall of the Caſtle of *Hiſdin*, was ſtruck with a Muſquet bullet upon the *Bregma*, but had his Helmet on his head, the bullet dented in the Helmet but did not break it, no nor the muſculous skin, nor skull, for as much as could be diſcerned, yet notwithſtanding he died apoplectick upon the ſixth day after.

But I being very deſirous to know what might be the true cauſe of his death, dividing his skull, obſerved that the ſecond Table was broken, and caſt off ſcales and ſplinters, wherewith as with Needles the ſubſtance of the Brain was continually pricked, the firſt and upper table being whole for all this: I afterwards ſhewed the like example to *Capellanus* and *Caſtellanus*, the King and Queens chief Phyſicians, in the expedition of *Roan*.

Why *Hippocrates* ſet down no way to cure a *Reſonitus*.

The manner to know when the skull is fractured by a *Reſonitus*.

But *Hippocrates* preſcribes no method of curing this fifth kind of fracture, by reaſon he thinks it cannot be found out by any circumſtance, whence it happens that it is for the moſt part deadly: Yet muſt we endeavour to have ſome knowledge and conjecture of ſuch a fracture, if it ſhall at any time happen. Wherefore having firſt diligently ſhaven away the hair, we muſt apply an Emplaiſter of Pitch, Tar, Wax, Turpentine, the Powder of *Iris*, or Flower-de-luce roots and Maſtich; now if any place of the head ſhall appear more moiſt, ſoft, and ſwollen, it is ſomewhat likely that the bone is cleft in that place, ſo that the Patient, though thinking of no ſuch thing, is now and then forced to put his hand to that part of the skull. Confirmed with theſe and other ſigns formerly mentioned, let him call a Council of learned Phyſicians; and fore-tell the danger to the Patients friends which are there preſent, that there may no occaſion of calumny remain, then let him boldly perforate the skull, for that is far better than forſake the Patient ready to yield to the greatneſs of the hidden diſeaſe, and ſo conſequently to die within a ſhort while after. There are four ſorts or conditions of fractures, by which the Chirurgeon may be ſo deceived, that when the skull is broken indeed, yet he may think there is no fracture. The firſt is when the bone is ſo depreſſed, that it preſently riſes up into its true place and native equability. The ſecond is when the Fiſſure is onely capillary. The third is when the bone is ſhaken on the inſide, the utter ſurface nevertheleſs remaining whole, for aſmuch as can be diſcerned. The fourth is, when the bone is ſtricken on the one ſide, and cleft on the other.

CHAP.

CHAP. IX.

Of the moving, or concuſſion of the Brain.

BEſides the mentioned kinds of Fractures by which the Brain alſo ſuffers, there is another kind of affect beſides Nature, which alſo aſſails it by the violent incurſion of a cauſe in like manner external; they call it the commotion or ſhaking of the Brain, whence Symptoms like thoſe of a broken skull enſue. Falling from aloft upon a ſolid and hard body, dull and heavy blows, as with Stones, Clubs, Staves, the report of a piece of Ordnance, or crack of Thunder, and alſo a blow with ones hand. *Gal. lib. 2. de comp. medic. cap. 6. & com. ad Aph. 58. ſect. 7.*

Thus as *Hippocrates* tells, that beautiful Damoſel the daughter of *Nerius*, when ſhe was twenty years old, was ſmitten by a Woman, a friend of hers playing with her, with her flat hand upon the fore-part of the head, and then ſhe was taken with a giddineſs, and lay without breathing, and when ſhe came home, ſhe fell preſently into a great Fever, her head aked, and her face grew red. The ſeventh day after, there came forth ſome two or three ounces of ſtinking and bloudy matter about her right Ear, and ſhe ſeemed ſomewhat better, and to be at ſomewhat more eaſe. The Fever increaſed again, and ſhe fell into a heavy ſleepineſs, and loſt her ſpeech, and the right ſide of her face was drawn up, and ſhe breathed with difficulty, ſhe had alſo a convulſion and trembling, both her tongue failed her, and her eyes grew dull, on the nineth day ſhe died. *Lib. 5. Epidem.* But you muſt note, that though the head be armed with a Helmet, yet by the violence of a blow the Veins and Arteries may be broken, not onely theſe which paſs through the ſutures, but alſo thoſe which are diſperſed between the two Tables in the *Diploe*, both that they might bind the *Craſſa Meninx* to the skull, that ſo the Brain might move more freely, as alſo that they might carry the alimentary juice to the Brain wanting Marrow, that is, bloud to nouriſh it, as we have formerly ſhewed in our Anatomy. The Veſſels of the brain broken by the commotion thereof.

But from hence proceeds the efflux of bloud running between the skull and membranes, or elſe between the membranes and brain; the bloud congealing there, cauſeth vehement pain, and the eyes become blind, Vomiting is cauſed, the mouth of the ſtomach ſuffering together with the Brain, by reaſon of the Nerves of the ſixth conjugation, which run from the Brain thither, and from thence are ſpread over all the capacity of the ventricle; whence becoming a partaker of the offence, it contracts it ſelf, and is preſently, as it were, overturned; whence firſt thoſe things that are contained therein are expelled, and then ſuch as may flow, or come thither from the neighbouring and common parts, as the Liver and Gall; from all which choler, by reaſon of its natural levity and velocity is firſt expelled, and that in greateſt plenty; and this is the true reaſon of that vomiting, which is cauſed and uſually follows upon fractures of the Skull and concuſſions of the Brain. Signs. *Celſus.* The cauſe of vomiting when the head is wounded.

Within a ſhort while after, inflammation ſeizes upon the membranes and brain it ſelf, which is cauſed by corrupt and putrid bloud proceeding from the veſſels broken by the violence of the blow, and ſo ſpread over the ſubſtance of the Brain. Such inflammation communicated to the Heart, and whole body by the continuation of the parts, cauſes a Fever. But a Fever by altering the Brain, cauſes Doting; to which if ſtupidity ſucceed, the Patient is in very ill caſe, according to that of *Hippocrates*; Stupidity and doting, are ill in a wound, or blow upon the Head. *Aph. 14. ſect. 9.* But if to theſe evils, a Sphacel, and corruption of the Brain enſue, together with a great difficulty of breathing, by reaſon of the diſturbance of the animal faculty, which from the Brain imparts the power of moving to the Muſcles of the Cheſt, the Inſtruments of Reſpiration; then death muſt neceſſarily follow.

A great part of theſe accidents appeared in King *Henry* of happy memory, a little before he died. A Hiſtory. He having ſet in order the affairs of *France*, and entered into amity with the neighbouring Princes, deſirous to honour the marriages of his Daughter and Siſter with the famous and noble exerciſe of Tilting, and he himſelf running in the Tilt-yard, with a blunt lance received ſo great a ſtroak upon his breſt, that with the violence of the blow, the vizour of his Helmet flew up, and the trunchion of the broken Lance hit him above the left Eye-brow, and the muſculous skin of the Fore-head was torn even to the leſſer corner of the left Eye, many ſplinters of the ſame Trunchion being ſtruck into the ſubſtance of the fore-mentioned Eye, the Bones being not touched or broken, but the Brain was ſo moved and ſhaken, that he died the eleventh day after the hurt. His Skull being opened after his death, there was a great deal of bloud found between the *Dura* and *Pia Mater*, poured forth in the part oppoſite to the blow, at the middle of the ſuture of the hind-part of the head; and there appeared ſigns, by the native colour turned yellow, that the ſubſtance of the Brain was corrupted, as much as one might cover with ones Thumb. Which things cauſed the death of the moſt Chriſtian King, and not onely the wounding of the Eye, as many have falſly thought. For we have ſeen many others, who have not died of far more grievous wounds in the Eye. What was the neceſſary cauſe of the death of King *Henry* the ſecond, of *France*.

The Hiſtory of the Lord *Saint-Johns* is of late memory: He in the Tilt-yard made for that time before the Duke of *Guiſes* houſe, was wounded with a ſplinter of a broken Lance, of a fingers length and thickneſs, through the vizour of his helmet, it entering into the Orb under the eye, and piercing ſome three fingers bredth deep into the head; by my help and Gods favour, he recovered, *Valeranus* and *Duretus* the Kings Phyſicians, and *James* the Kings Chirurgeon aſſiſting me. A Hiſtory.

What ſhall I ſay of that great and very memorable wound of *Francis* of *Lorain* the Duke of *Guiſe*? He in the fight of the City of *Bologne* had his head ſo thruſt through with a Lance, that the point entering under his right Eye by his Noſe, came out at his Neck between his Ear and the *Vertebræ*, the Head or Iron being broken and left in by the violence of the ſtroak, which ſtuck there ſo firmly, that it could not be drawn or plucked forth, without a pair of Smiths Pincers. But although the ſtrength and violence of the blow was ſo great, that it could not be without a fracture of the Bones, a tearing and breaking of the Nerves, Veins, and Arteries, and other parts; yet the generous Prince by the favour of God recovered. A Hiſtory.

By which you may learn, that many die of ſmall wounds, and other recover of great, yea, very large

Why ſome die of ſmall wounds, and others recover of great.

large and deſperate ones. The cauſe of which events is chiefly and primarily to be attributed to God, the Authour and Preſerver of Mankind; but ſecondarily to the variety and condition of Temperaments. And thus much of the commotion or concuſſion of the Brain; whereby it happens, that although all the Bone remains perfectly whole, yet ſome Veins broken within by the ſtroak, may caſt forth ſome bloud upon the membranes of the Brain, which being there concrete, may cauſe great pain, by reaſon whereof it blinds the Eyes; if ſo be that the place can be found againſt which the pain is, and when the Skin is opened, the bone look pale, it muſt preſently be cut out, as *Celſus* hath written. Now it remains that we tell you how to make your Prognoſticks, in all the forementioned Fractures of the skull.

CHAP. X.

Of Prognoſticks to be made in Fractures of the Skull.

Hip. de vul. cap.

WE muſt not neglect any Wounds in the Head, no not thoſe which cut or bruiſe but onely the hairy ſcalp, but certainly much leſs, thoſe which are accompanied by a fracture in the Skull, for oft-times all horrid ſymptoms follow upon them, and conſequently death it ſelf, eſpecially in bodies full of ill humours, or of an ill-habit, ſuch as are theſe which are affected with the *Lues Venerea*, Leproſie, Dropſie, Pthyſick, Conſumption: for in theſe, ſimple wounds are hardly or never cured; for union is the cure of wounds, but this is not performed unleſs by the ſtrength of Nature, and ſufficient ſtore of laudable bloud: but thoſe which are ſick of hectick Fevers and Conſumptions want ſtore of bloud, and thoſe bodies which are replete with ill humours, and of an ill habit, have no afflux or plenty of laudable bloud: but all of them want the ſtrength of Nature; the reaſon is almoſt the ſame in thoſe alſo which are lately recovered of ſome Diſeaſe.

Whether the wounds of children, or old people are better to heal.

Thoſe Wounds which are bruiſed are more difficult to cure, than thoſe which are cut. When the Skull is broken, then the continuity of the fleſh lying over it muſt neceſſarily be hurt and broken, unleſs it be in a *Reſonitus*. The bones of children are more ſoft, thin, and repleniſhed with a ſanguin humidity than thoſe of old men, and therefore more ſubject to putrefaction; Wherefore the Wounds which happen to the bones of children, though of themſelves and their own Nature they may be more eaſily healed, (becauſe they are more ſoft, whereby it comes to paſs, that they may be more eaſily agglutinated, neither is there fit matter wanting for their agglutination by reaſon of the plenty of bloud laudable both in conſiſtence and quality) than in old men, whoſe bones are drier and harder, and ſo reſiſt union, which comes by mixture, and their bloud is ſerous, and conſequently a more unfit bond of unity and agglutination; yet oft-times through occaſion of the ſymptoms which follow upon them, that is, putrefaction and corruption, which ſooner ariſe in a hot and moiſt body, and are more ſpeedily increaſed in a ſoft and tender, they uſually are more ſuſpected, and difficult to heal.

The Patient lives longer of a deadly fracture in the Skull in Winter than in Summer, for that the native heat is more vigorous in that time than in this; beſides alſo, the humours putrefie ſooner in Summer, becauſe then unnatural heat is eaſily inflamed, and more predominant, as many have obſerved out of *Hippocrates*.

Aph. 15. *ſect.* 1.

The Wounds of the Brain and of the *Meninges* or Membranes thereof are moſt commonly deadly, becauſe the action of the Muſcles of the Cheſt, and others ſerving for reſpiration, is divers times diſturbed and intercepted, whence death enſues. If a ſwelling happening upon a Wound of the head preſently vaniſh away, it is an ill ſign, unleſs there be ſome good reaſon therefore, as Bloud-letting,

Aph. 65. *ſect.* 5.

Purging, or the uſe of reſolving local Medicins, as may be gathered by *Hippocrates* in his Aphoriſms. If a Fever enſue preſently after the beginning of a wound of the head, that is, upon the fourth or ſeventh day, which uſually happens, you muſt juge it to be occaſioned by by the generating of *Pus* or

Aph. 47. *ſect.* 2.

Matter, as it is recited by *Hippocrates*. Neither is ſuch a Fever ſo much to be feared, as that which happens after the ſeventh day, in which time it ought to be terminated; but if it happen upon the tenth or fourteenth day with cold or ſhaking, it is dangerous, becauſe it makes us conjecture that there is putrefaction in the Brain, the *Meninges* or Skull, through which occaſion it may ariſe, chiefly if other ſigns ſhall alſo concur, which may ſhew any putrefaction, as if the wound ſhall be pallid and of a faint yellowiſh colour, as fleſh looks after it is waſhed.

Wounds which are dry, rough, livid, and black, are evil.

For as it is in *Hippocrates Aphoriſ.* 2. *Sect.* 7. It is an ill ſign if the fleſh look livid, when the bone is affected; for that colour portends the extinction of the heat, through which occaſion the lively or indifferently red colour of the part, faints and dies, and the fleſh thereabout is diſſolved into a viſcid *Pus* or filth.

Commonly another worſe affect follows hereon, wherein the wound becoming withered and dry, looks like ſalted fleſh, ſends forth no matter, is livid and black, whence you may conjecture, that the bone is corrupted, eſpecially if it become rough, whereas it was formerly ſmooth and plain, for it is made rough when *Caries* or corruption invades it; but as the *Caries* increaſes, it becomes livid and black, ſanious matter withall ſweating out of the *Diploe*, as I have obſerved in many: all which are ſigns that the native heat is decayed, and therefore death at hand; but if ſuch a Fever be occaſioned

The ſigns of a Fever cauſed by an *Eryſipelas*.

from an *Eryſipelas*, which is either preſent or at hand, it is uſually leſs terrible. But you ſhall know by theſe ſigns that the Fever is cauſed by an *Eryſipelas* and conflux of cholerick matter; if it keep the form of a Tertian, if the fit take them with coldneſs and end in a ſweat, if it be not terminated before the cholerick matter is either converted into *Pus*, or elſe reſolved; if the lips of the wound be ſomewhat ſwollen, as alſo all the face; if the eyes be red and fiery; if the neck and chaps be ſo ſtiff,

Why an *Eryſipelas* chiefly aſſails the face

that he can ſcarce bend the one, or open the other; if there be great exceſs of biting and pricking pain and heat, and that far greater than in a *Phlegmon*. For ſuch an *Eryſipelous* diſpoſition generated of thin and hot bloud, chiefly aſſails the face, and that for two cauſes.

The

The firſt is, by reaſon of the natural levity of the cholerick humour, the other becauſe of the rarity of the skin of theſe parts.

The cure of ſuch an affect muſt be performed by two means, that is, evacuation, and cooling with humectation. If choler alone cauſe this tumor, we muſt eaſily be induced to let bloud, but we muſt purge him with Medicins evacuating choler. If it be an *Eryſipelas Phlegmonodes*, you muſt draw bloud from the Cephalick Vein of that ſide which is moſt affected, always uſing advice of a Phyſician. Having uſed theſe general means, you muſt apply refrigerating and humecting things, ſuch as are the Juice of Nightſhade, Houſleek, Purſlane, Lettuce, Navel-wort, Water-Lentil, or Ducks-meat, Gourds, a Liniment made of two handfulls of Sorrel boiled in fair Water, then beaten or drawn through a ſearce, with ointment of Roſes or ſome *unguent. Populeon* added thereto will be very commodious. Such and the like remedies muſt be often and ſo long renewed until the unnatural heat be extinguiſhed. But we muſt be careful to abſtain from all unctuous and oily things, becauſe they may eaſily be inflamed, and ſo increaſe the Diſeaſe. Next we muſt come to reſolving Medicins; but it is good when any thing comes from within, to without; but on the contrary, it is ill when it runs from without inwards, as experience and the authority of *Hippocrates* teſtifie: If, when the bone ſhall become purulent, puſtules ſhall break out on the tongue by the dropping down of the acrid filth or matter by the holes of the palat upon the tongue, which lies under; now when this ſymptom appears, few eſcape. Alſo it is deadly when one becomes dumb and ſtupid, that is, Apoplectick by a ſtroak or wound on the Head; for it is a ſign that not onely the Bone, but alſo the Brain it ſelf is hurt. But oft-times the hurt of the Brain proceeds ſo far, that from corruption it turns to a Sphacel, in which caſe they all have not onely puſtules on their tongues, but ſome of them die ſtupid and mute, otherſome with a Convulſion of the oppoſite part; neither as yet I have obſerved any which have died with either of theſe ſymptoms, by reaſon of a wound in the Head, who have not had the ſubſtance of their Brain tainted with a Sphacel, as it hath appeared when their Skulls have been opened after their death.

The cure of an *Eryſipelas* on the face.

Why Oily things muſt not be uſed in an *Eryſipelas* of the Face. *Aph.* 25. *ſect.* 6.

Deadly ſigns in wounds of the head.

CHAP. XI.

Why, when the Brain is hurt by a Wound of the Head, there may follow a Convulſion of the oppoſite part.

MAny have to this day enquired, but as yet as far as I know it hath not been ſufficiently explained, Why a Convulſion in wounds of the Head ſeizes on the part oppoſite to the blow. Therefore I have thought good to end that Controverſie in this place. My reaſon is this, that kind of ſymptom happens in the ſound part by reaſon of emptineſs and dryneſs; but there is a twofold cauſe, and that wholly in the wounded part, of this emptineſs and dryneſs of the ſound or oppoſite part, to wit, pain, and the concourſe of the ſpirits and humours thither by the occaſion of the Wound, and by reaſon of the Pains drawing, and Natures violently ſending help to the affected part.

A Convulſion is cauſed by dryneſs.

A two-fold cauſe of Convulſifick dryneſs.

The ſound part exhauſted by this means both of the ſpirits and humours, eaſily falls into a Convulſion. For thus *Galen* writes; God the Creator of Nature hath ſo knit together the triple ſpirituous ſubſtance of our bodies, with that tie and league of concord, by the production of the paſſages, to wit, of Nerves, Veins, and Arthries, that if one of theſe forſake any part, the reſt preſently neglect it, whereby it languiſheth, and by little and little dies through defect of nouriſhment. But if any object that Nature hath made the body double for this purpoſe, that when one part is hurt, the other remaining ſafe and ſound, might ſuffice for life and neceſſity: but I ſay this Axiom hath no truth in the veſſels and paſſages of the body. For it hath not every where doubled the veſſels, for there is but one onely Vein appointed for the nouriſhment of the Brain, and the Membranes thereof, which is that they call the *Torcular*, by which when the left part is wounded, it may exhauſt the nouriſhment of the right and ſound part, and through that occaſion cauſe it to have a Convulſion by too much dryneſs. Verily it is true, that when in the oppoſite parts the Muſcles of one kind are equal in magnitude, ſtrength, and number, the reſolution of one part makes the convulſion of the other by accident; but it is not ſo in the Brain.

Lib. 4. *de uſu Partium.*

For the two parts of the Brain, the right and left, each by it ſelf performs that which belongs thereto, without the conſent, conſpiration, or commerce of the oppoſite part; for otherwiſe it ſhould follow that the Palſie properly ſo called, that is, of half the body, which happens by reſolution, cauſed either by mollification, or obſtruction, reſiding in either part of the Brain, ſhould infer together with it a Convulſion of the oppoſite part. Which notwithſtanding, daily experience convinceth as falſe. Wherefore we muſt certainly think, that in Wounds of the Head wherein the Brain is hurt, that Inanition and want of nouriſhment are the cauſes that the ſound and oppoſite part ſuffers a Convulſion.

Francis Dalechampius in his *French* Chirurgery renders another reaſon of this queſtion; That (ſaith he) the truth of this propoſition may ſtand firm and ratified, we muſt ſuppoſe that the Convulſion of the oppoſite part mentioned by *Hippocrates*, doth then onely happen, when by reaſon of the greatneſs of the inflammation in the hurt part of the Brain, which hath already inferred corruption, and a Gangrene to the Brain and Membranes thereof, and within a ſhort time is ready to cauſe a Sphacel in the Skull, ſo that the Diſeaſe muſt be terminated by death; for in this defined ſtate of the Diſeaſe, and theſe conditions, the ſenſe and motion muſt neceſſarily periſh in the affected part, as we ſee it happens in other Gangrenes, through the extinction of the native heat. Beſides, the paſſages of the animal ſpirit muſt neceſſarily be ſo obſtructed by the greatneſs of ſuch an inflammation or phlegmon, that it cannot flow from thence to the parts of the ſame ſide lying thereunder, and to the neighbouring parts of the Brain; and if it ſhould flow thither, it will be unprofitable to carry the ſtrength and faculty of ſenſe and motion, as that which is infected and changed by admixture of putrid and Gangrenous vapours. Whereby it cometh to paſs, that the wounded part deſtitute of ſenſe, is not ſtirred up to expel that which would be troubleſom to it, if it had ſenſe; wherefore neither are the Nerves thence ariſing ſeized upon, or contracted by a Convulſion.

Opinion of *Dalechampius.*

It furthermore comes to paſs, that becauſe theſe ſame Nerves are deprived of the preſence and comfort of the animal ſpirit, and in like manner the parts of the ſame ſide, drawing from thence their ſenſe and motion, are poſſeſſed with a Palſie; for a Palſie is cauſed either by the cutting or obſtruction of a Nerve, or the madefaction, or mollification thereof, by a thin and watery humour, or ſo affected by ſome vehement diſtemper, that it cannot receive the animal ſpirit.

But for the oppoſite part and the Convulſion thereof, it is known and granted by all, that a Convulſion is cauſed either by Repletion, which ſhorten the Nerves by diſtending them into bredth; or by Inanition, when as the native and primitive heat of the Nerves being waſted, their proper ſubſtance becoming dry, is wrinkled up and contracted; or elſe it proceeds from the vellication and acrimony of ſome vapour, or ſanious and biting humour, or from vehemency of pain. So we have known the Falling-ſickneſs cauſed by a venenate exhalation carried from the Foot to the Brain. Alſo we know that a Convulſion is cauſed in the puncture of the Nerve, when as any acrid and ſanious humour is ſhut up therein, the orifice thereof being cloſed; but in Wounds of the Nerves, when any Nerve is half cut, there happens a Convulſion by the bitterneſs of the pain.

But verily in the oppoſite part, there are manifeſtly two of theſe cauſes of a Convulſion; that is to ſay, a putrid and carion-like vapour, exhaling from the hurt and gangrenate part of the Brain; and alſo a virulent, acrid, and biting *ſanies* or filth ſweating into the oppoſite ſound part, from the affected and gangrenous; the malignity of which *ſanies*, *Hippocrates* deſirous to decipher, in reckoning up the deadly ſigns of a wounded head, hath expreſſed it by the word *Ichor*; and in his Book of Fractures he hath called this humour *Dacryodes & non Pyon*, [that is, *Weeping and not digeſted.*] Therefore it is no marvail, if the oppoſite and ſound part endued with exquiſite and perfect ſenſe, and offended by the flowing thereto of both the vaporous and ſanious matter, uſing its own force, contend and labour as much as it can, for the expulſion of that which is troubleſom thereto. This labouring or concuſſion is followed (as we ſee in the Falling-ſickneſs) by a Convulſion, as that which is undertaken in vain, Death being now at hand, and Nature over-ruled by the Diſeaſe. Thus (ſaith *Dalechampius*) muſt we in my judgment determine of that propoſition of *Hippocrates* and *Avicen.*

But he adds further, In Wounds of the Head which are not deadly, Practitioners obſerve that ſometimes the hurt part is taken with the Palſie, and the ſound with a Convulſion; otherwhiles on the contrary, the wounded part is ſeized by a Convulſion, and the ſound by a Palſie; otherwhiles both of them by a Convulſion or Palſie, and ſomewhiles the one of them by a Convulſion or Palſie, the other being free from both affects; the cauſes of all which belong not to this place to explain. Thus much *Dalechampius.*

CHAP. XII.

A Concluſion of the deadly ſigns in the Wounds of the Head.

The ſigns of a deadly wound from the depraved faculties of the mind.

From the habit of the body.

From the time that ſuch ſigns appear.

NOw that we may return to our former Diſcourſe; you may certainly fore-tell the Patient will die, when his reaſon and judgment being perverted, he ſhall talk idly, when his memory fails him, when he cannot govern his tongue, when his ſight grows dark and dim, his ears deaf, when he would caſt himſelf headlong from his Bed, or elſe lies therein without any motion; when he hath a continual Fever with a *Delirium*, when the Tongue breaks out in Puſtules, when it is chopt and become black by reaſon of too much drineſs, when the Wound grows dry and caſts forth little or no matter; when as the colour of the Wound which was formerly freſh, is now become like ſalted fleſh yellow and pale; when the Urin and other excrements are ſuppreſt; when the Palſie, Convulſion, Apoplexy; and laſtly, often ſwooning, with a ſmall and unequal pulſe invade him. All ſuch ſigns ſometimes appear preſently after the wound, otherwhiles ſome few days after; therefore when as the Brain is hurt and wounded by the violence of the Inciſion or Fiſſure, of the Contuſion, Compreſſion, Puncture, Concuſſion, or any other Fracture, the fore-mentioned ſigns appear preſently in the firſt days; but when they do not appear till many days after the blow, you may know that they riſe and appear, by reaſon of an inflammation and phlegmon in the Brain, occaſioned by the putrefaction of the bloud poured forth upon it.

Celſus lib. 8. cap. 4.

But we muſt obſerve this by the way, which alſo belongs to the Prognoſticks, that fleſh is eaſily regenerated and reſtored in all parts of the Head, except in that part of the Forehead which is a little above that which lies between the Eye-brows, ſo that it will be ulcerated ever after, and muſt be covered with a Plaſter. I believe that in that place there is an internal cavity in the Bone, full of air, which goes to the ſieve-like bones of the Noſe, by which the growth of fleſh may be hindered; or elſe that the bone is very denſe or compact in that place, ſo that there can ſcarce ſufficient Juice ſweat forth, which may ſuffice for the regeneration of fleſh; add hereunto a great conflux of excrements flowing to this ulcer, which ſhould otherwiſe be evacuated by the Eyes and Noſe, which hinder by that means the drineſs of the Ulcer, and conſequently the healing thereof.

Hence certainly it comes to paſs, that if you deſire the Patient thus affected to breath, ſhutting his mouth and noſe, the air or breath will come forth of the Ulcer with ſuch force, as it will eaſily blow forth a lighted Candle of an indifferent bigneſs held thereto. Which thing, I proteſt, I obſerved in a certain man, whom I was forced to trepan in that place, by reaſon the bone of the fore-head was broken and depreſſed.

CHAP. XIII.

Of ſalutary Signs in Wounds of the Head.

But on the contrary, theſe are ſalutary ſigns; when the Patient hath no Fever, is in his right mind, is well at the application or taking of any thing; ſleeps well, hath his Belly ſoluble, the Wound looks with a freſh and lively colour, caſts forth digeſted and laudable matter, the *Craſſa Meninx* hath its motion free and no way hindered.

When the Patients are out of danger.

Yet we muſt note, which alſo is obſerved by the Ancients, and confirmed by experience, that we muſt think none paſt danger, and free from all chance, until the hundredth day be paſt. Wherefore the Phyſician ought ſo long to have a care of his Patient, that is, to conſider how he behaves and governs himſelf in meat, drink, ſleep, venery, and other things.

The Patient muſt beware of cold.

But let the Patient diligently avoid and ſhun cold, for many when they have been cured of Wounds in the head, by careleſs taking cold have been brought into danger of their lives. Alſo you muſt know that the *Callus*, whereby the bones of the Skull are knit together, requires almoſt the ſpace of forty or fifty days to its perfect coagmentation and concretion. Though in very deed one cannot ſet down a certain number of days, by reaſon of the variety of bodies or tempers: for it is ſooner finiſhed in young men, and more ſlowly in old: and thus much may ſerve for prognoſticks. Now will we treat as briefly and perſpicuouſly as we can of the cure both in general and particular; wherefore beginning with the general, we will firſt preſcribe a convenient Diet, by the moderate uſe of the ſix things not natural.

CHAP. XIV.

Of the general cure of a broken Skull, and of the Symptoms uſually happening thereupon.

How the air ought to be.

The firſt cure muſt be to keep the Patient in a temperate air; and if ſo be that it be not ſuch of it ſelf and its own proper nature, it muſt be corrected by Art. As in Winter he muſt have a clear fire made in his chamber, leſt the ſmoak cauſe ſneezing and other accidents; and the windows and doors muſt be kept ſhut to hinder the approach of the cold air and wind. All the time the wound is kept open to be dreſt, ſome body ſtanding by ſhall hold a Chafingdiſh full of Coals, or a heated Iron bar over the wound, at ſuch a diſtance, that a moderate heat may paſs thence to the Wound; and the frigidity of the encompaſſing air may be corrected by the breathing of the diffuſed heat. For cold, according to the opinion of *Hippocrates*, is an Enemy to the Brain, Bones, Nerves, and ſpinal Marrow; it is alſo hurtful to Ulcers, by ſuppreſſing their excrements, which ſuppreſt do not onely hinder ſuppuration, but alſo by corroſion makes them ſinuous. Therefore *Galen* rightly admoniſheth us, to keep cold from the Brain, not onely in the time of trepaning, but alſo afterwards. For there can be no greater, nor more certain harm befal the fractured skull, than by admitting the air, by ſuch as are unskilful. For if the air ſhould be hotter than the Brain, then it could not thence be refrigerated; but if the Brain ſhould be laid open to the air in the midſt of Summer, when it is at the hotteſt, yet would it be refrigerated; and unleſs it were relieved with hot things, take harm. This is the opinion of *Galen*, whereby you may underſtand that many who have their Skulls broken, die more through default of skill in the curing, than by the greatneſs of the fracture.

Aphor. 18. *ſect.* 5.

Lib. 2. *de uſ. part. cap.* 2.

The Air though in Summer is colder than the Brain.

But when the Wound is bound up (with the Pledgets, Cloths, and Rowlers, as is fit) if the air chance to be more hot than the Patient can well indure, let it be amended by ſprinkling, and ſtrewing the chamber with cold Water, Oxycrate, the branches of Willows and Vine. Neither is it ſufficient to ſhun the too cold air, unleſs alſo you take heed of the over light, chiefly until ſuch time as the moſt feared and malign ſymptoms are paſt.

The diſcommodities of too much light.

For a too great light diſſipates the ſpirits, increaſes pain, ſtrengthens the Fever and Symptoms. *Hippocrates* wholly forbids Wine, therefore the Patient in ſtead thereof muſt drink Barley Water, fair Water boiled and tempered with Julep of Roſes, Syrup of Violets, Vinegar, and the like, Water wherein Bread crums have been ſteeped, Water and Sugar with a little juice of Limmons or Pomecitron added thereto, and ſuch like, as the ability and taſte of the Patient ſhall require. Let him continue ſuch drinks until he be free from malign ſymptoms, which uſually happen within fourteen days.

What his drink muſt be

Almonds increaſe the pain of the Head.

His meat ſhall be Pap, Ptiſan, ſhunning Almond-milks; (for Almonds are ſaid to fill the Head with vapours and cauſe pain) ſtewed Damask Prunes, Raiſins, and Currants ſeaſoned with Sugar, and a little Cinamon, (which hath a wonderful power to comfort the Stomach, and revive and exhilarate the ſpirits) Chickens, Pigeons, Veal, Kid, Leverets, Birds of the Fields, Pheaſons, Black-birds, Turtles, Partridges, Thruſhes, Larks, and ſuch like meats of good digeſtion, boiled with Lettuce, Purſlane, Sorrel, Borage, Bugloſs, Succory, Endive, and the like, are thought very convenient in this caſe. If he deſire at any time to feed on meats roaſted, he may; onely dipping them in Verjuice, in the acid juices of Oranges, Citrons, Limmons, or Pomegranates, ſometimes in one, and ſometimes in another, according to his taſte and ability. If any have a deſire to eat fiſh, he muſt make choice of Trouts, Gudgeons, Pikes, and like, which live in running and clear Waters, and not in muddy; he ſhall eſchew all cold Sallets and Pulſe, becauſe they fly up and trouble the head: it will be convenient after meat to uſe common Dridge Powder, or Anniſeed, Fennel-ſeed, or Coriander-comfits; alſo Conſerve of Roſes, or Marmalate of Quinces to ſhut up the orifice of the Ventricle, leſt the head ſhould be offended with vapours ariſing from thence.

What fiſh he may eat.

Children muſt eat often, but ſparingly, for Children cannot faſt ſo long as thoſe which are elder, becauſe their natural heat is more ſtrong, wherefore they ſtand in need of more nouriſhment: ſo alſo in Winter all ſorts of People require more plentiful nouriſhment, for that then their ſtomachs are more hot than in Summer.

Aphor. 13, & 14. *ſect.* 1.

When

Aphor. 15. *sect.* 2. When the fourteenth day is paſt, if neither a Fever, nor any thing elſe forbids, he may drink Wine moderately, and by little and little increaſe his diet, but that reſpectively to each ones nature, ſtrength, and cuſtom. He ſhall ſhun, as much as in him lies, ſleep on the day time, unleſs it happen that a *Phlegmon* ſeize upon the Brain or the *Meninges*. For in this caſe it will be expedient to ſleep on the day time; eſpecially from morning till noon, for in this ſeaſon of the day, as alſo in the Spring, bloud is predominant in the body, according to the opinion of *Hippocrates*. For it is ſo vulgarly known, that it need not be ſpoken, that the bloud when we are awake is carried into the habit and ſurface of the body; but on the contrary, by ſleep it is called into the noble parts, the Heart and Liver, Wherefore if that the bloud by the force of the Sun caſting his beams upon the Earth at his riſing is carried into the habit of the body, it ſhould again be more and more diffuſed by the ſtrength and motion of watching, the inflammation in the Brain and *Meninges* would be much increaſed. Wherefore it will be better, eſpecially then to ſtay by ſleep the violence of the bloud running into the habit of the body, when it ſhall ſeem to rage and more violently to affect that way. Watching muſt in like manner be moderate, for too much depraves the temper of the Brain and of the habit of the whole body; it cauſes crudities, pains, and heavineſs of the head, and makes the wounds dry and malign.

Why ſleep upon the day time is good for the brain being inflamed. *Lib.* 2. *Epidem.*

The diſcommodities enſuing immoderate watching. *Gal. Meth.* 18.

But if the Patient cannot ſleep by reaſon of the vehemency of the inflammation of the Brain and *Meninges*, *Galen* wiſhes to waſh, beſmear and anoint the head, noſe, temples, and ears with refrigerating and humecting things, for theſe ſtupefie and make drowſie the Brain and Membranes thereof, being more hot than they ought to be. Wherefore for this purpoſe let the temples be anointed with *Unguentum populeon*, or *Unguentum Roſatum* with a little Roſe-Vinegar or Oxycrate; let a Sponge moiſtned in the decoction of white or black Poppy-ſeed, of the rinds of the roots of Mandrages, of the Seeds of Henbane, Lettuce, Purſlane, Plantain, Night-ſhade, and the like. He may alſo have a Broath, or Barley-cream, into which you may put an emulſion made of the Seeds of white Poppy, or let him have a potion made with ℥ i. or ℥ i. ſ. of the Syrup of Poppy, with ʒ ij. of Lettuce water; Let the Patient uſe theſe things four hours after meat, to procure ſleep. For ſleep doth much help concoction, it repairs the efflux of the triple ſubſtance cauſed by Watching, aſſwageth pain, refreſheth the weary, mitigates anger and ſorrow, reſtores the depraved reaſon, ſo that for theſe reſpects it is abſolutely neceſſary that the Patient take his natural reſt.

Medicins procuring ſleep.

The commodities of ſleep.

If the Patient ſhall be Plethorick, let the plenitude be leſſened by bloud-letting, purging and a ſlender diet, according to the diſcretion of the Phyſician who ſhall over-ſee the Cure. But we muſt take heed of ſtrong purgations in theſe kinds of Wounds, eſpecially at the beginning, leſt the Fever, Inflammation, Pain, and other ſuch like ſymptoms be increaſed by ſtirring up the humours.

Lib. 4. *Meth.* Phlebotomy, according to *Galens* opinion, muſt not onely be made reſpectively to the plenty of bloud, but alſo agreeable to the greatneſs of the preſent diſeaſe, or that which is to come, to divert and draw back that humour which flows down, by a way contrary to that which is impact in the part; and which muſt be there evacuated, or drawn to the next. Wherefore for example, if the right ſide of the head be wounded, the Cephalick-vein of the right arm ſhall be opened, unleſs a great *Plethora* or plenitude cauſe us to open the *Baſilica*, or Median; yet if neither of them can be fitly opened, the *Baſilica* may be opened, although the body be not plethorick. The like courſe muſt be obſerved in wounds of the left ſide of the head; for that is far better by reaſon of the ſtraitneſs of the fibers, than to draw bloud on the oppoſite ſide; in performance whereof you muſt have diligent care of the ſtrength of the Patient, ſtill feeling his pulſe, unleſs the Phyſician be preſent, to whoſe judgment you muſt then commit all that buſineſs. For the pulſe is, in *Galens* opinion, the certaineſt ſhewer of the ſtrength. Wherefore we muſt conſider the changes and inequalities thereof, for as ſoon as we find it to become leſſer and more ſlow, when the fore-head begins to ſweat a little, when he feels a pain at his heart, when he is taken with a deſire to vomit or to go to ſtool, or with yawning, and when he ſhall change his colour and his lips look pale, then you muſt ſtop the bloud as ſpeedily as you can, otherwiſe there will be danger leſt he pour forth his life together with his bloud. Then he muſt be refreſhed with bread ſteeped in Wine, and put into his mouth, and by rubbing his temples and noſtrils with ſtrong Vinegar, and by lying upon his back. But the part ſhall be eaſed and freed from ſome portion of the impact and conjunct humour by gently ſcarifying the lips of the wound, or applying of Leeches. But it ſhall be diverted by opening thoſe Veins which are higheſt to the wounded part, as the *Vena Puppis*, or that in the midſt of the fore-head, or of the temples, or thoſe which are under the tongue; beſides alſo Cupping-glaſſes ſhall be applyed to the ſhoulder, ſometimes with ſcarification, ſometimes without; neither muſt ſtrong and long frictions with coarſe cloths of all the body, the head excepted, be omitted during the whole time of the Cure, for theſe will be available, though but for this; that is, to draw back and diſſipate by inſenſible tranſpiration the vapours which otherwiſe would aſcend into the head; which matters certainly in a body that lies ſtill and wants both the uſe and benefit of accuſtomed exerciſe, are much increaſed.

Lib. de cur. per ſanginis miſſ.

The uſe of Frictions.

But it ſhall be made manifeſt by this following and notable example, how powerful Bloud-letting is, to leſſen and mitigate the inflammation of the Brain, or the membranes thereof, in wounds of the head. I was lately called into the Suburbs of Saint *German*, there to viſit a young man twenty eight years old, who lodged there in the houſe of *John Martial* at the Sign of St. *Michael*. This young man was one of the houſhold-ſervants of Mr. *Doucador*, the Steward of the Lady *Admiral* of *Brion*. He fell down head-long upon the left *Bregma*, upon a marble pavement, whence he received a contuſed wound, without any fracture of the Skull, and being he was of a ſanguin temperature, by occaſion of this wound, a Fever took him on the ſeventh day with a continual *Delirium* and inflammation of phlegmonous tumour of the wounded *Pericranium*. This ſame tumor poſſeſſing his whole head and neck by continuation and ſympathy of the parts, was grown to ſuch a bigneſs, that his viſage was ſo much altered, that his friends knew him not, neither could he ſpeak, hear, or ſwallow any thing but what was very liquid. Which I obſerving, although I knew that the day paſt, which was the eighth day of his Diſeaſe, he had four Sawcers of bloud taken from him by *Germain Agace* Barber-ſurgeon of the

A Hiſtory.

the ſame Suburbs; yet conſidering the integrity and conſtancy of the ſtrength of the Patient: I thought good to bleed him again, wherefore I drew from him fourteen Sawcers at that one time; when I came to him the day after, and ſaw that neither the Fever nor any of the fore-mentioned ſymptoms were any whit remitted, or aſſwaged, I forthwith took from him four Saucers more, which in all made two and twenty; the day following when I had obſerved that the ſymptoms were no whit leſſened, I durſt not preſume, by my own onely advice, to let him the fourth time bloud, as I deſired. Wherefore I brought unto him that moſt famous Phyſician Doctor *Violene*, who as ſoon as he felt his pulſe, knowing by the vehemency thereof, the ſtrength of the Patient, and moreover conſidering the greatneſs of the inflammation and tumor which offered it ſelf to his ſight, he bid me preſently take out my Lancet and open a Vein. But I lingered on ſet purpoſe, and told him that he had already twenty two Saucers of bloud taken from him; then ſaid he, grant it be ſo, and though more have been drawn, yet muſt we not therefore deſiſt from our enterpriſe, eſpecially ſeeing the two chief Indications of bloud-letting yet remain, that is, the greatneſs of the Diſeaſe, and the conſtant ſtrength of the Patient. I being glad of this, took three Saucers more of bloud, he ſtanding by, and was ready to take more, but that he wiſhed me to defer until the afternoon; wherefore returning after dinner I filled two Saucers more, ſo that in all, this young man to his great benefit, loſt twenty ſeven Saucers of bloud at five times, within the ſpace of 4 days. Now the enſuing night was very pleaſing to him, the Fever left him about noon, the tumor grew much leſs, the heat of the inflammation was aſſwaged in all parts, except in his eye-lids, and the laps of his ears, which being ulcerated caſt forth a great quantity of *Pus* or matter. I have recited this hiſtory purpoſely to take away the childiſh fear which many have to draw bloud in the conſtant ſtrength of the Patient, and that it might appear how ſpeedy and certain a remedy it is, in inflammations of the head and brain.

The two chief Indications in bloud-letting.

Now to return from whence we digreſſed, you muſt note that nothing is ſo hurtful in fractures and wounds of the head, as Venery; not only at that time the diſeaſe is preſent, but alſo long after the cure thereof. For great plenty of ſpirits are contained in a ſmall quantity of ſeed, and the greateſt part thereof flows from the Brain; hence therefore all the faculties, but chiefly the Animal, are reſolved; whence I have divers times obſerved death to enſue in ſmall wounds of the head, yea when they have been agglutinated and united. All paſſions of the mind muſt in like ſort be avoided, becauſe they by contraction and diſſipation of the ſpirits cauſe great trouble in the body and mind. Let a place be choſen for the Patient as far from noiſe as can be, as from the ringing of Bells, beatings and knockings of Smiths, Coopers, and Carpenters, and from High-ways through which they uſe to drive Coaches; for noiſe increaſes pain, cauſes a Fever, and brings many other ſymptoms.

The diſcommodity of Venery in wounds of the head.

How hurtful noiſe is to the fractures of the skull.

I remember when I was at *Hiſdin* at the time that it was beſieged by the forces of *Charles* the fifth, that when the Wall was beaten with the Canon, the noiſe of the Ordnance cauſed grievous torment to all thoſe which were ſick, but eſpecially thoſe that were wounded on their heads, ſo that they would ſay, that they thought at the diſcharging of every Cannon that they were cruelly ſtrucken with ſtaves on that part which was wounded, and verily their wounds were ſo angered herewith, that they bled much, and by their pain and Fevers increaſed, were forced with much ſighing to breathe their laſt. Thus much may ſerve to be ſpoken of the cure in general: now we will out of the monuments of Ancients, treat of the particular.

A Hiſtory.

CHAP. XV.

Of the particular cure of wounds of the head, and of the muſculous Skin.

Of a ſimple wound of the fleſh and the skin.

LEt us begin with a ſimple wound, for whoſe cure the Chirurgeon muſt propoſe one onely ſcope, to wit, Union; for unleſs the wound pierce to the skull, it is cured like other wounds of the fleſhy parts of our bodies. But if it be compound, as many ways as it is complicate, ſo many Indications ſhew themſelves. In theſe, the chiefeſt care muſt be had of the more urgent order and cauſe.

Therefore if the wound ſhall be ſimple and ſuperficiary, then the hair muſt firſt be ſhaven away, then a Plaiſter applied made of the white of an Egg, Bole Armenic, and Aloes. The following day you muſt apply *Emplaſtrum de Janua*, or elſe *de gratia Dei*, until the wound be perfectly healed. But if it be deeper and penetrate even to the *Pericranium*, the Chirurgeon ſhall not do amiſs, if at the ſecond dreſſing he apply a digeſtive Medicin (as they call it) which may be made of Venice Turpentine, the yolks of Eggs, Oil of Roſes, and a little Saffron, and that ſhall be uſed ſo long, until the wound come to maturation; for then you muſt add Honey of Roſes and Barley flour to the digeſtive. Hence muſt we paſs to theſe Medicins, into whoſe compoſition no oily or unctuous body enters, ſuch as this; R *Terebinth. venetæ* ℥ ij. *ſyrupi roſar.* ℥ j. *pul. Aloes, Myrrhæ & Maſtich. an.* ℥ ß. Let them all be incorporated and made into an unguent, which ſhall be perfectly regenerated, then it muſt be cicatrized with this following Powder. R *Aluminis combuſti, corticis granatorum combuſt. an.* ℥ j. *Miſceantur ſimul & fiat pulvis:* but if the Wound be ſo large that it require a ſuture, it ſhall have ſo many ſtitches with a Needle as need ſhall ſeem to require.

A digeſtive Medicin.

A ſarcotick Medicin.

An Epulotick.

Whileſt I was at *Hiſdin*, a certain Souldier, by falling of the Earth whileſt he undermined, had the Hairy Scalp ſo preſſed down even to the *Pericranium*, and ſo wholly ſeparated from the beginning of the hind-part of his head, even to his fore-head, that it hung over his face. I went about the cure in this manner; I firſt waſhed all the Wound with Wine a little warmed, that ſo I might waſh away the congealed bloud mixed with the Earth, then I dried it with a ſoft linnen cloth, and laid upon it Venice Turpentine mixed with a little *Aqua Vitæ*, wherein I had diſſolved ſome *Sanguis Draconis*, Maſtich and Aloes; then I reſtored the hanging skin to its former place, and there ſtaid it with ſome ſtitches, being neither too ſtrait, nor too cloſe together, for fear of pain and inflammation, (which two chiefly happen whileſt the Wound comes to ſuppuration) but onely as much as ſhould

A Hiſtory.

What things we muſt obſerve in ſewing.

ſerve to ſtay it on every ſide, and to keep forth the air, which by its entrance doth much harm to Wounds: the lower ſides of the Wound I filled with ſomewhat long and broad tents, that the matter might have paſſage forth. Then I applied this following Cataplaſm to all the head. ℞ *Farinæ hord. & fabarum an.* ℥ vj. *olei roſati* ʒ iij. *aceti quantum ſufficit, fiat cataplaſma ad formam pultis*; this hath a faculty to dry, cool, repel, mitigate pain and inflammation, and ſtay bleeding.

When we muſt not let bloud in wounds.

I did not let him bloud, becauſe he had bled much, eſpecially at certain Arteries which were broken near his Temples; he being dreſſed after this manner grew well in a ſhort time. But if the wound be made by the biting of a wild Beaſt, it muſt be handled after another manner, as ſhall appear by this following Hiſtory.

A Hiſtory.

As many people on a time ſtood looking upon the Kings Lions, who were kept in the Tilt-yard at *Paris* for the delight of King *Henry* the Second, and at his charges, it happened that one of the fierceſt of them broke the things wherein he was tied, and leaping amongſt the Company, he with his paws threw to the ground a Girl of ſome twelve years old, and taking her head in his mouth, with his teeth wounded the muſculous skin in many places, yet hurt not the skull. She ſcarce at length delivered by the Maſter of the Lions from the jaws of Death and the Lion, was committed to the cure of *Rowland Claret* Chirurgeon, who was there preſent by chance at the ſame time: ſome few days after I was called to viſit her; ſhe was in a Fever, her head, ſhoulders, breſt, and all the places where the Lion had ſet his teeth or nails, were ſwollen; all the edges of the wound were livid, and did flow with a wateriſh, acrid, virulent, cadaverous, dark, green and ſtinking matter, ſo that I could ſcarce indure the ſmell thereof: ſhe was alſo oppreſt with pricking, biting, and very great pain,; which I obſerving, that old ſaying came into my mind, which is, That all Wounds made by the bitings of Beaſts, or of Men alſo, do ſomewhat participate of poiſon. Wherefore there muſt principally great care be had of the venenate impreſſion left in the Wounds by the nails and teeth, and therefore ſuch things muſt be applied, as have power to overcome poiſon. Wherefore I ſcarified the lips of the Wounds in divers places, and applied Leeches to ſuck out the venenate bloud, and eaſe the inflammation of the parts; then I made a Lotion of *Ægyptiacum* Treacle and Mithridate, after the following manner.

The bitings of Man and Beaſts are venenate.

Theriacal topick Medicins.

℞ *Mithrid.* ℥ i. *theriac.* ℥ ij. *ægyptiac.* ℥ ß. *diſſolvantur omnia cum aqua Vitæ, & Cardui ben.* Let the Wounds be fomented and waſhed with it warm; beſides alſo Treacle and Mithridate were put in all the Medicins which were either applied, or put into the Wound; and alſo of the ſame with the Conſerves of Roſes and Bugloſs diſſolved in the Water of Sorrel and *Carduus benedictus*, potions were made to ſtrengthen the heart, and vindicate it from malign vapours.

A Cordial Epithema.

For which purpoſe alſo this following *Epithema* was applied to the region of her heart. ℞ *Aquæ roſar. & nenuphar. an.* ℥ iv. *aceti ſcillitici* ℥ i. *corallorum, ſantalorum alborum & rubrorum, roſar. rub. pulveris, ſpodii. an.* ʒ i. *Mithridatii, Theriacæ, an.* ʒ ij. *flo. cordial. pulveriſatorum p.* ij. *croci* ʒ i. diſſolve them all together, make an Epitheme and apply it to the heart with a ſcarlet cloth or ſponge, and let it be often renued. Verily, ſhe dreſt after this manner, and the former remedies but once uſed, pain, inflammation, and all the malign ſymptoms were much leſſened; to conclude, ſhe recovered, but lingred, and was lean ſome two years after, yet at length ſhe was perfectly reſtored to her health and former nature. By which you may underſtand, that ſimple Wounds muſt be handled after another manner than theſe which have any touch of poiſon.

The cure of the hairy ſcalp when it is contuſed.

A repelling Medicin.

But now that we may proſecute the other affects of the hairy ſcalp; ſay that it is contuſed with a blow without a wound, that which muſt be firſt and always done, (that ſo the affect may better appear, and the remedies which are applied may take more effect) the hair muſt be ſhaven away, and at the firſt dreſſing a repelling Medicin applied, ſuch as this following *Oxyrhodinum.* ℞ *Ol. roſ.* ℥ iij. *album ovorum nu.* ij. *pulveris nucum cypreſſi, balauſt. alumin. rochæ. roſar. rub. an* ʒ i. Let them be all incorporated, and make a medicin for the former uſe; or in ſtead thereof you may apply the cataplaſm preſcribed before, conſiſting of *Farina hordei, fabarum, aceto & oleo roſaceo.* But ſuch Medicins muſt be often renued. When the pain and defluxion are appeaſed, we muſt uſe diſcuſſing Medicins for diſſipation of that humour which remains impacted in the part; ℞ *Emplaſtri de mucilagin.* ʒ ij. *oxicrocei, & emp. de meliloto, an.* ℥ i. *olei chamæm. & anethi. an.* ℥ ß. *malaxentur ſimul, & fiat emplaſtrum ad uſum dictum.* Such a fomentation will alſo be good. ℞ *Vini rub. lib.* iv. *lixivii, com. lib.* ij. *nuces cupreſſi contuſ. nu.* x. *pul. myrtillorum* ℥ i. *roſar. rub. abſinth. fol. ſalviæ, majoranæ, ſtœchados, florum chamæm. melil. an.* M. ß. *aluminis rochæ, radicis cyperi, calami aromatici an.* ℥ ß. *bulliant omnia ſimul*, and make a decoction to foment the grieved part. After ſomewhat a long fomenting it, whereby it may the better diſcuſs, dry and exhauſt the concrete humour, the head muſt be dried and more diſcuſſing things applied, ſuch as the Cerate deſcribed by *Vigo*, called *De Minio*; which hath an emollient and digeſtive faculty in this form. ℞ *Olei chamæm. lilior. an.* ℥ x. *olei maſtich.* ℥ ij. *pinguedinis vervecis lib.* i. *litharg. auri* ℥ viij. *minii* ℥ ij. *vini boni cyathum unum, bulliant omnia ſimul baculo agitando, primum quidem lento igne, mox vero luculentiore, donec tota maſſa colorem nigrum vel ſubnigrum contrahat; adde in fine coctu-*

A diſcuſſing Fomentation.

Ceratum de Minio.

ræ Terebinth. lib. ſ. pulveris maſtich. ℥ ij. *gum. elemi.* ℥ i. *ceræ quantum ſufficit, bulliant rurſus una ebullitione & fiat empl. molle.* But if the humour be not thus diſcuſſed, but onely grow ſoft, then the tumor muſt be quickly opened, for when the fleſh is inflamed and putrefied through occaſion of the contained humour, the bone under it putrefies alſo by the contagion of the inflammation and the acrimony of the matter falling upon the bone. When you have opened it, waſh away the filth of the Ulcer with this following deterſive Medicin. ℞ *Syrupi roſ. & abſinth. an.* ʒ j. *terebinth.* ʒ ß. *pul. ireos, aloes, maſtichis, myrrhæ, farinæ hordei, an.* ʒ ß. In ſtead hereof, if there be great putrefaction, *Ægyptia*, either by it ſelf, or mixt with an equal quantity of *Unguentum Apoſtolorum* may be put into the Ulcer. When the Ulcer is cleanſed, it will be time to uſe ſarcotick and cicatrizing Medicins.

Deterſive or cleanſing Medicins.

CHAP.

CHAP. XVI.

Of the particular cure of a Fracture or broken Skull.

IF the Skull be broken, ſo that it be needful to trepan it, or to elevate and lift it up, or ſcrape it away, the muſculous skin being cut, as we formerly noted, the *Pericranium* ſhall be plucked from the skull, as we ſaid before; which becauſe it can hardly be done without great pain, by reaſon of its exquiſite ſenſe and connexion with the Membranes of the Brain, we muſt labour to mitigate the pain for fear of inflammation and other accidents. Therefore the firſt dreſſing ended, and the corners of the Wound drawn each from other; at the ſecond dreſſing put to the Wound a Digeſtive (as they term it) made of the Yolk of an Egg and Oil of Roſes, but you muſt apply no humid thing to the bone, becauſe we deſire to keep it ſound and whole. For *Galens* opinion is, that bared bones muſt not be touched with unctuous things; but rather on the contrary, all dry things muſt be applied to them, which may conſume the ſuperfluous humidity. Therefore we muſt lay ſome lint and cephalick powders which we ſhall hereafter deſcribe, upon the bone we intend to preſerve, and muſt have diligent care that it be not offended either by the air, or touch of humid Medicins. You muſt in Trepaning have a ſpecial care of the *Craſſa Meninx*. For I have often obſerved a great quantity of bloud to have flowed from ſome broken Veſſel which adhered to the ſecond Table: neither muſt we preſently and forthwith ſtay ſuch bleeding, but ſuffer it to flow according to the plenitude and ſtrength of the Patient; for thus the Fever, and together therewith the reſt of the ſymptoms are diminiſhed. For the opinion of *Hippocrates*, in every green Wound it is good to cauſe often bleeding, except in the Bellies; for thus the vehemency of pain, inflammation and other accidents will be leſs troubleſom; alſo it is not amiſs too for old Ulcers to bleed much, for ſo they are freed from the burden of the impact humours. When you think it hath bled ſufficiently, it may be ſtanched with this following Medicin deſcribed by *Galen*.

Why the *Pericranium* hath ſuch exquiſite ſenſe.

Gal. 6. meth. The bones are offended with the application of humid things.

Lib. de ulcer.

℞ *Pulveris Aloes* ʒ ij. *thuris Maſtiches, an.* ʒ i ſ. *albumina ovorum nu.* ij. *agitentur ſimul cum pilis leporinis minutim inciſis, fiat medicamentum.* When the bleeding is ſtaid, you ſhall, for the aſſwaging of pain, drop upon the *Meninx* ſome Pigeons bloud, yet warm by opening a Vein under the Wing, then it ſhall be ſtrewed over with this following Powder: ℞ *Aloes, Thuris, Myrrhæ, Sanguinis draconis an.* ʒ i. *Miſce, fiat pulvis ſubtilis.* Alſo you may make an irrigation with Roſe Vinegar, or ſome repelling Medicin ſuch as is a Cataplaſm *ex farinis, & oleo roſaceo.* Which may be applied until the fourth day to aſſwage and mitigate pain.

Gal. 6. meth.

Vigo's Cerate will be of good uſe in this caſe, as that which in my opinion is moſt fit for fractures of the skull, becauſe it draws powerfully, reſolves and dries moderately, and by reaſon of the ſmell refreſhes the animal ſpirits, and ſtrengthens the Brain and Membranes thereof, as you may eaſily perceive by things which enter into the compoſition thereof. ℞ *Olei roſ. Omph. reſinæ pini, gummi Elemi, an.* ʒ ij. *Maſtiches* ʒ i ß. *pinguedinis vervecis caſtrati* ʒ ij. ſ. *foliorum beton. caprifol. anthos, an. M.* i. *ammoniaci* ʒ ß. *granorum tinctorum* ʒ x. *liquata pinguedine; terenda terantur, & ammoniacum ſimul cum aceto ſcillitico, eliquetur; deinde bulliant. omnia ſimul in lib.* ij. *vini boni, lento igne uſque ad conſumptionem vini, deinde exprimantur; cum expreſſione addantur terebinth. Ven.* ʒ iv. *ceræ albæ quantum ſufficit, fiat cerotum molle ad uſum prædictum.* Alſo let the neck, and all the Spine of the Back be anointed with a liniment, which hath force of mollifying the Nerves, leſt they ſhould ſuffer Convulſion; ſuch is this.

Vigo's Cerate good for a broken skull.

℞ *Rutæ, marrubii, roriſmar. ebulor. ſalviæ, herb. paralyſ. an. M. ſ. rad. Ireos, cyperi, baccarum lauri, an.* ʒ i. *florum chamæmelil. hyperici, an. M.* i. *piſtentur & macerentur omnia in vino albo per noctem, deinde coquantur in vaſe duplici cum oleo lumbricorum, liliorum, de terebinthina, axungiæ anſeris & hum. an.* ʒ ij. *uſque ad conſumptionem vini, poſtea colentur, & in colatura adde terebinth. venet.* ʒ iij. *aquæ vitæ* ʒ ſ. *ceræ quantum ſufficit. Fiat linimentum ſecundum artem.*

A liniment good againſt Convulſions.

But when the pain is aſſwaged, we muſt abſtain from all ſuch unctuous things, leſt they make the Wound become ſordid and malign, and putrefie the adjacent parts, and conſequently the *Craſſa Meninx* and Skull; for the integrity of all parts may be preſerved by their like, and ſuch are dry things in a fracture of the skull. Wherefore all humid and oily things muſt be ſhunned in the cure thereof, unleſs peradventure there ſhall be ſome need to mitigate pain, and bring the humour to ſuppuration.

Gal. 4. meth.

For, according to *Galen*, we are oft forced for a time to admit the proper cure of the diſeaſe, ſo to reſiſt the ſymptoms; furthermore *Hippocrates* would have us not to foment the Skull, no not with Wine; but if we do, to let it be but with very little. *Vidius* interprets that little to be, when there is fear of inflammation; for Wine if it be red, tart, and aſtringent, hath a repreſſing, refrigerating and drying faculty: for otherwiſe all Wine, although it heats and dries by its faculty, yet it actually humects and cools, both which are very hurtful in Wounds of the head, or a fractured skull, eſpecially when the bone is bare; for from too much cooling of the Brain there is fear of a Convulſion, or ſome other evil ſymptom. Wherefore let this be rarified, that is, we muſt not uſe humid and unctuous Medicins in Wounds of the head, except for curing of inflammation, or the mitigation of pain cauſed thereby. Therefore let the bared skull be ſtrewed with catagmatick and cephalick Powders, (being ſo called by the Ancients, for that they are convenient and good in fractures of the Skull and the reſt of the Bones;) for by their drineſs they conſume the ſuperfluous humidity, and by that means help Nature in the ſeparating of the broken bones, and the regenerating of fleſh. Such Powders uſually conſiſt of ſuch things as theſe enſuing; *Thus, Radix Iridos florent. farina hordei, & Ervi, pulvis Aloes Hepaticæ, Sanguis Draconis, Maſtiche, Myrrha, rad. Ariſtolochiæ, Gentianæ*; and generally all ſuch Simples as have a drying and an abſtergent faculty without biting; but you muſt not uſe theſe things before the pain, inflammation, and apoſtumation be paſt; that is, then, when the Membranes muſt be cleanſed, the bones ſcaled, and the fleſh generated. For the skull, by how much it is the drier, by ſo much it requires and more eaſily endures more powerful

How far humid things are good for a fractured skull.

Why Cephalick or Catagmatick Powders are good.

When to be uſed.

How to be mixed when they are to be applied to the *Meninges*.

and drier Medicins than the *Dura Mater* or *Pericranium*, as that which in quickneſs of ſenſe comes far ſhort of theſe two. Wherefore when you would apply the fore-mentioned cephalick Powders to the *Meninges*, they muſt be aſſociated and mixed with Honey, Syrup of Roſes, or of Wormwood, and ſuch other like, that ſo their too violently drying faculty may be allayed and tempered.

CHAP. XVII.

Why we uſe Trepaning in the Fractures of the Skull.

THere are four cauſes of this remedy: The firſt is to raiſe up the depreſt Bones, and take forth their fragments which preſs upon the *Meninges*, or alſo upon the ſubſtance of the Brain. The ſecond is, that the *ſanies* or matter may be evacuated, cleanſed, waſted, and dried up, which by the breaking of any veſſel is poured forth upon the Membranes, whereby they, and not they onely, but the Brain alſo is in a great danger of corruption. The third is, for the fitter application of Medicins, convenient for the wound and fracture. The fourth is, that ſo we may have ſomething whereby we may ſupply the defect of a repelling Ligature, and ſuch a one as may hinder defluxions; for ſuch a Ligature cannot take place here as it may in the other parts of the body, by reaſon of the ſphærical or round figure of the head, which doth not eaſily admit binding; and then the denſity and hardneſs of the interpoſed Skull is a means that the veſſels lying under it (by which uſually the defluxion comes) cannot eaſily be bound with a rowler ſufficiently to repel the running bloud. And the external Veſſels (to whom the force of the Ligature may come) cannot be bound without great pain, and danger of inflammation. For by ſuch a compreſſion the pulſation of the Arteries would be intercepted, and the efflux of the fuliginous excrements which uſeth to paſs through the ſutures of the Skull, would be ſuppreſt, by reaſon of the conſtriction of theſe ſutures.

Why a repelling Ligature cannot be uſed in fractures of the skull.

Beſides alſo, the bloud would thus be forced from the wounded part without, to within into the Membranes and Brain; when pain, inflammation, a Fever, Abſceſs, Convulſion, Palſie, Apoplexy, and laſtly Death it ſelf would enſue.

How the Patient muſt be placed when you Trepan him.

And theſe are the chief cauſes that Trepaning is neceſſary in fractures of the Skull, and not ſo in the fractures of other Bones.

But before you apply or put to your Trepan, the Patient muſt be fitly placed or ſeated, and a double cloth muſt be many times wrapped about his head, and then his head muſt be ſo laid, or preſſed upon a Cuſhion or Pillow, that when you come to your operation, it may not ſink down any further, but remain firm and ſteddy. Then you muſt ſtop the Patients Ears with Cotton-wool, that ſo he may not hear the noiſe made by the Trepan, or any other Inſtrument.

What to be done before the application of the Trepan.

But before you put to your Trepan, the bone muſt be pierced with an Inſtrument, having a three-ſquare point, that ſo it may be the more ſpeedily and certainly perforated. The point thereof muſt be no bigger than the pin of a Trepan, that ſo the Trepan which is forthwith to be applied may ſtand the more firm, and not to play to and again in too wide a hole.

The ſhape of this Inſtrument is not much different from a Gimblet, but that the point is three-ſquare, and not twined like a ſcrew, as you may perceive by this following figure.

A Gimblet or Piercer to perforate the Skull before the ſetting of the Trepan.



A *Shews the handle.*

B *The points which may be ſcrewed and fitted into the handle.*

CHAP.

CHAP. XVIII.

A Deſcription of Trepans.

TRepans are round Saws which cut the bone circularly, more or leſs according to their greatneſs; they muſt have a pin ſtanding in the middle a little further out than the teeth, ſo to ſtay and hold faſt the Trepan that it ſtir neither to this ſide nor that, until it be entered, and you have cut through the firſt table at the leaſt: then you muſt take forth the pin, leſt going quite through the bone, it may prick or hurt the *Craſſa Meninx*. Wherefore when you have taken forth the pin, you may ſafely turn it about until you have cut through both the tables; Your Trepans muſt alſo have a cap, or ſomewhat to engirt or encompaſs them, leſt no way hindred they cut more of the bone than we would, and in concluſion run into the *Meninx*. They muſt alſo be anointed with oil, that ſo they may cut more readily and gently; for thus Carpenters uſe to greaſe their Saws. But you muſt, during the time of the operation, often dip them in cold water, leſt the bone by attrition become too hot: for all hard ſolid bodies by quick and often turning about, become hot; but the bone made more hot and dry, is altered and changeth its nature, ſo that after it is cut more off, its ſcales and falls away. Now you muſt know that the bone which is touched with the Trepan or the Air, always caſts off ſcales: for the ſpeedier helping forwards whereof, you muſt ſtrew upon it powders made of Rocket, Briony, wild Cucumber, and *Ariſtolochia*-roots. When the bone is ſufficiently ſcaled, let this following powder be put upon it, which hath a faculty to cover the bone with fleſh, and to harden it with drineſs convenient to its kind. ℞ *Pulver. Ireos Illyricæ, Aloes Mannæ thuris, Myrrhæ Ariſtolochiæ, an.* ʒ i. Fleſh being by this means generated, let it be cicatrized by ſtrewing upon it the rinds of Pomegranates and Alum burnt.

The harm the bone receives by being heated with the Trepan.

What things haſten the ſcaling of the bone.

Neither ſhall the Chirurgeon forcibly take away theſe ſcales, but commit that whole work to Nature, which uſeth not to caſt them off before that it hath generated fleſh under them. For otherwiſe if he do any thing raſhly, he brings new corruption to the bone; as we ſhall more at large declare, when we come to treat of *Caries*, or rottenneſs of Bones.

The bone muſt not be forcibly ſcaled.

He which uſeth the Trepan, muſt conſider this, that the head is of a round figure, and alſo the Trepan cuts circularly, and therefore it is impoſſible to cut the bone ſo equally on every ſide, as if it were performed upon a plain body. Furthermore the thickneſs of the skull is not alike in all places, wherefore you muſt look and mark whether the Trepan go not more deep on one ſide than on the other, which you may do by meaſuring it now and then with a Pin or Needle, and if you find that it is cut deeper on one ſide than on the other, you muſt preſs down the Trepan more powerfully upon the oppoſite part.

A caution in Trepaning.

But ſeeing there are many ſorts of Trepans invented and expreſſed by many men, yet if you weigh and rightly conſider them all, you ſhall find none more ſafe, than that I invented and have here delineated. For it cannot pierce one jot further into the ſkull, than he pleaſes that uſes it, and therefore it cannot hurt either the *Meninges* or the Brain. An iron head or cover, ſtays it as a bar, that it can penetrate no further than you ſhall think it requiſite. This head or cover is to be drawn up and down, and ſet higher and lower, as he which uſes it ſhall think good, and ſo it will ſtay the Trepan that it ſhall not go a hairs bredth beyond your intended depth. So that henceforwards there ſhall be no Chirurgeon, howſoever ignorant in the performance of his Art, which by the benefit of ſuch a Trepan may not perform this operation without any danger, or fear of danger, of touching the *Dura Mater*, the hurting whereof, puts the life in jeopardy.

A ſafe and convenient Trepan.

The figure of our Trepan opened and taken in pieces.

The figure of the ſame Trepan fitted and put together.



A *Shews the whole handle or Brace of the Trepan.*
B *The Cover or Cap of the Trepan.*
C *The ferule.*
D D *The Screw-pins which hold and ſtay the ferule and Trepan.*
E *The Trepan without his pin.*
F *The Trepan furniſhed with its pin.*

A *Shews the Brace and Trepan fitted in every point.*
B *The place into which the Trepan is put and fitted.*
C C C *The upper end of the Trepan which is to be fitted and put into the Brain.*
D *The Trepan with its cover or cap upon it.*
E *The ferule.*
F *A ſcrew-pin by the twining whereof the Trepan is faſtned in the Brace.*
G *Another ſcrew-pin which faſtens the ferule cloſer to the Trepan.*
H *The three-ſquare point.*

In ſtead of the other Trepan ſet forth by the Author, I have thought fit to give you the figure of that Trepan that is here moſt in uſe, and the fitteſt therefore, as it is ſet forth by Dr. *Crook*.

A Terebellum *or Gimblet conſiſting of three branches.*



A Lentil-like cutting Scraper.

All theſe particulars of the Trepan taken aſunder, you may ſee united and fitted together in the other figure. But when you cannot bring out the bone which you have cut off with your Trepan, then you may take it forth with the *Terebellum* or Gimblet here expreſt, that is, ſcrewing the point thereof into the hole made by the three-ſquare pin; the handle of this inſtrument may alſo ſerve in ſtead of a Levatory. When with the Gimblet you have drawn or taken forth that part of the Skull which was cut away by the Trepan; if there ſhall be any ſharp ſplinters in the ſecond Table which may hurt and prick the *Meninx* when it is heaved up by the motion of the brain, they muſt be ſhaved away and planted with this Lentil-faſhioned ſcraper; being ſo called, becauſe it hath the head thereof faſhioned and ſmooth like a Lentil, leſt being ſharp it ſhould hurt and prick the membrane in the ſmoothing thereof.

The uſe of a Leaden Mullet.

But if by reaſon of the thickneſs the Skull cannot be cut with the Lentil-like Scraper, you may uſe the cutting Scrapers and a Mallet. The Mallet muſt be of Lead, that ſo it may ſhake the Brain as little as may be. But you muſt diligently with your Mullets take forth the ſharp ſplinters, and pieces of the Bone. But if the fractured part of the Skull be ſuch, that it will not admit that Section which is requiſite for the bared bone, as when the fracture is upon the temporal muſcle, or at the ſutures; then in the ſtead of one Trepan, two or three muſt be applied, if the neceſſity of the preſent caſe ſo require, and that within a very ſmall compaſs; but they muſt not be applied to the fractured part, but nigh thereto, as we ſhall ſhew more at large in the following Chapter. But the Trepans ſhall be applied ſo near to each other, that the ring of the ſecond may be joined with the ring of the firſt and third. But if a fracture ſhall happen to light upon a ſuture, then you muſt not apply a Trepan to it, but uſe two thereto on each ſide; he that ſhall do otherwiſe ſhall tear in ſunder the nervous and membranous fibers, and alſo the Veins and Arteries by which the *Dura Mater* is faſtned to the Skull, and yields matter to the *Pericranium*. He which ſhall apply one Trepan, that is, but upon one ſide of the ſuture, he ſhall not be able to get forth all the *ſanies* which is fallen down on both ſides by reaſon of the partition of the *Craſſa Meninx*, which lies between and riſes up by the ſuture of the skull.

Why a Trepan muſt not be applied to the ſutures.

Why two Trepans are to be uſed to a fractured ſuture.

To conclude, when for what cauſe ſoever we cannot make uſe of a Trepan, we may imploy this Inſtrument, if ſo be as much of the bone be bared as is needful. It is made in form of a pair of Compaſſes, and by means of a Screw may be opened, more or leſs, as you pleaſe. You as need ſhall require may change the points, and put other into their places, for they may be fitted to one ſide of the Compaſs with a Screw.

A pair of cutting Compaſſes to cut forth the Skull.



A *Shews the one leg of the cutting Compaſſes, which as you carry it about, cuts the skull.*

E *The Screw which faſtens the point to the leg of the Compaſſes.*

C C *Two different points which may be ſcrewed to the leg of the compaſſes, as need ſhall require.*

D *A great ſcrew which faſtens upon an Iron ſtring, alongſt which the one of the legs of the Compaſs running may be widened and ſtraitned as you pleaſe.*

A crooked Iron plate fit to ſuſtain and hold ſteddy one leg of the Compaſs upon the head.



Another pair of Compaſſes of the like nature and uſe, which may be widened and ſtraitned by a Screw.



Moreover it is fit that the one leg of ſuch cutting Compaſſes ſhould ſtand firm and ſteddy, whileſt the other is drawn circularly to cut. Wherefore it is fit you have an iron plate made full of little holes, wherein you may firmly ſtay that leg of the Compaſs, leſt it waver againſt your will; it is requiſite that this plate be crooked, (becauſe the head is round) that ſo it may be fitted to any part thereof.

CHAP. XIX.

Of the places of the Skull whereto you may not apply a Trepan.

FIrſt of all, you ſhall not apply a Trepan to a Bone that is ſo broken, that it is wholly, or in the greater part thereof, divided from the skull by the violence of the ſtroak, leſt by your weight and preſſing of the Trepan, you force it down upon the membrane. Secondly, you muſt not apply one to the fractured ſutures, for the reaſons mentioned in the former Chapter. Thirdly, nor to that part of the forehead which is a little above the eye-brows, for thoſe reaſons we gave you before in the twelfth Chapter. For there is in that place under the firſt Table of the Skull it ſelf, a large cavity repleniſhed with a certain white and tough humour, as alſo with a certain ſpirituous and airy ſubſtance, placed there by Nature, to prepare the air which aſcends to the Brain by the Noſtrils: unleſs the Chirurgeon obſerve and be mindful hereof, he may be deceived, ſuppoſing this cavity to be an Effracture of the Bone, and a depreſſion thereof. Fourthly, neither in the loweſt parts of the Skull, leſt the marrowy ſubſtance of the Brain, by reaſon of its weight, ſhould ſlide through the hole made by the Trepan. Fifthly, neither to the *Bregma*-bones of children, as thoſe which as yet have not acquired juſt ſolidity, to endure the impreſſion of a Trepan. Sixthly, nor to the temples by reaſon of the temporal muſcle, the cutting whereof, in the opinion of *Hippocrates*, cauſes convulſion of the oppoſite part. For being cut athwart it loſes its proper action, that is, to move and lift up the lower Jaw; but then the oppoſite temporal muſcle being whole and perfect, uſing its ſtrength, (his Antagoniſt ſuffering it, and not reſiſting or labouring any thing at all to the contrary) it draws the ſame Jaw to it, whereupon the mouth and all the parts of the face are drawn awry, and ſuffer a convulſion towards the ſound part, the other being reſolved according to *Hippocrates* his rule. For as often as the Muſcles of one kind are equal in number, magnitude, and ſtrength on each ſide, the reſolution of the one part, cauſes the convulſion of the other.

A bone almoſt ſevered from the skull muſt not be trepaned.

A notable cavity in the fore-head bone.

Lib. de Vul.

A rule out of *Hippocr.*

Neither doth this danger alone ariſe from the cutting of the temporal muſcle, but alſo another, which is, that this muſcle when we eat and ſpeak, is in perpetual motion, whereby it comes to paſs, that being once cut, it is ſcarce ever united again, beſide alſo the commiſſure or joyning together of the ſtony bones, lie under it. But by the ſecond caution we are forbid to trepan upon the ſutures; moreover alſo many Veins, Arteries, and Nerves are ſpread over the ſubſtance thereof, ſo that by cutting of them, there is danger of many and malign ſymptoms, as pain, inflammation, a Fever, a Convulſion not onely of the part it ſelf, but alſo of the whole body, whence laſtly death enſues. Wherefore let no Chirurgeon be ſo fool-hardy, as to attempt the cutting of this muſcle, ſo to trepan the bone which lies under it; rather let him apply his trepan above it, or on the ſide thereof, or as near to the affected part as I can, as I did in a Gentleman called *Monſieur de la Breteſche*. He in the triumphant entrance of King *Henry* the ſecond into the City of *Paris*, was ſo hurt with a ſtone, that the *Os Petroſum*, or ſcaly bone, was broken with the violence of the blow, and the temporal muſcle was vehemently contuſed, yet without any wound. I being called the next day (viewing the manner of the hurt, and the

What diſcommodities ariſe from cutting the temporal muſcles.

A Hiſtory.

the condition of the wounded part) thought good to bring ſome Phyſicians and Chirurgeons with me to conſult hereof, of whom when ſome thought it expedient preſently to divide the temporal muſcle, that baring the bone we might apply a Trepan, and ſo take forth the broken bones: I, on the contrary, began earneſtly to withſtand that opinion, citing that ſaying of *Hippocrates*, *ex libro de vulneribus Capitis*, wherein Chirurgeons are forbidden to cut ſuch muſcles, for fear of the fore-mentioned ſymptoms; alſo I cited experience, how that I had often obſerved all thoſe which had this muſcle cut died with a Convulſion; but that it ſhould be far better, that near above the fracture the bone ſhould be trepaned, not touching the temporal muſcle at all, if he could. When all of them at the laſt had inclined to my opinion, I preſently divided the muſculous skin which was over the upper part of the fracture with a three-cornered ſection: the day following, which was the third of his Diſeaſe, I trepaned him, and after I had done, ſome few days after, I took out ſome four ſplinters of the broken bone; and I put in a plain leaden pipe, by which (I wiſhing the Patient ever when I dreſt him to hold down his head, to ſtop his mouth and his noſe, and then ſtrive as much as in him lay to put forth his breath) much ſanious matter came forth, which was gathered between the Skull and *Craſſa Meninx*. Other filth which ſtuck more faſt, I waſhed out with a detergent decoction, injected with ſuch a Syringe as is here expreſt; and I did ſo much, God bleſſing my endeavours, that at length he recovered.

A plain leaden pipe for to carry forth the Sanies *gathered under the Skull.*

A little Syringe fit to make injections withall.

A Hiſtory.

The like chance and fortune befel *Monſieur de Pienne* at the ſiege of *Metz*. For he, as he fought at the breach of the Wall, had the bone of his temples broken with a ſtone ſtruck out of the adjacent Wall by a piece of Ordnance ſhot from the Emperours camp, he preſently fell down with the blow, and caſt bloud out of his mouth, noſe, and ears, with much vomiting, and remaining dumb, and as it were, ſenſleſs almoſt fourteen days, ſo that he knew none of the by-ſtanders. He had often palpitations, and convulſive twitchings, and his face was ſwollen. His fore-head bone was trepaned at the ſide of the temporal muſcle by the hand of *Peter Aubert* the Kings Chirurgeon: and although on the 25. day ſoft fleſh endued with exquiſite ſenſe grew out of the hole made with the Trepan, whoſe growth could not be hindered by Cathæretick Powders, yet at the length he recovered. The Ancients called this kind of growing fleſh, a *Fungus* [*i.* a Muſhrome] for that it is ſoft, and grows with a ſmall root and broad top like a Muſhrome: but it increaſes and decreaſes, according to the plenty of the flowing matter, and induſtry of the Chirurgeon hindering by art the growth thereof. This fleſh ſtinks exceedingly, they commonly call it *Ficus ſancti Fiacrii* [*i.* the Fig of S. *Fiacrye*.] This diſeaſe commonly hath its original after this manner. Even as in the bodies of trees from the excrements of nouriſhment, a certain half putrid, groſs and viſcous humour ſweats through the bark, and gathered together by little and little grows into a Muſhrom; ſo bloud melancholy both in temper and conſiſtence, ſprings from the broken veſſels of the skull and *Craſſa Meninx*, which alſo is ſent ſometimes by Nature for the neceſſary repairing the fleſh in theſe parts, whereupon a certain *Fungus* breeds, which in *Galens* opinion ſavours or partakes of the nature and condition of the parts to which it grows, though in general it be of the nature of malign Warts or Excreſcences. But for to take away ſuch *Fungi*, you muſt apply medicins which have a ſpecifick faculty to waſte ſuperfluous fleſh; ſuch are thoſe which ſtrongly dry, and gently waſte and eat, ſuch as this which follows. ℞ *Sabinæ* ℥ ij. *cereæ* ℥ i. *pulveriſentur ſimul, aſpergatur caro excreſcens.* Or elſe ℞ *Hermodactylorum combuſtorum* ℥ ß, make a powder for the ſame uſe. But if ſo be that this fungous fleſh come to ſuch growth, (as it often happens) as to equal the bigneſs of an Egg, it muſt be tied and ſtrait twitched cloſe to the root with a ſilken thred; and when it ſhall fall away by reaſon of this binding, the place muſt be ſtrewed with the fore-mentioned Powders, for ſo it will be more certainly cured than with more acrid Cathæreticks.

The generation of a *Fungus*.

CHAP. XX.

Of the corruption and Caries, *or rottenneſs of the Bones of the Head.*

Why when the Skull is broken, the bones ſometimes become foul or rotten.

THere ſometimes follows a corruption and Sphacel of the fractured bones of the Skull upon wounds of the Head; which happens, either becauſe they are touched by the air, which they are not ſenſible of, or for that the *ſanies* putrefying and detained under them, hath infected them with like putrefaction; or by the cure unskilfully handled, they by the raſh application of ſuppurating and oily Medicins becoming more moiſt, and ſo undergoing an unnatural change of their proper complexion and native temper, as we ſhall ſhew more at large when we ſhall treat of the reaſon of the *Caries* in the *Lues venerea*. We ſhall know this unnatural change and corruption, partly by ſight, that is, when from white they become to be yellowiſh, livid, and black; partly alſo by putting down a Probe, when as it meets with nothing ſmooth and ſlippery, but feels rough in many places, and beſides alſo when it enters and eaſily penetrates with a ſmall thruſting down into their ſubſtance, as if it were ſungous. Yet this laſt ſign may often deceive you, for I have divers times obſerved rotten bones, which being bare had long ſuffered the injury of the air, to become ſo hard, that a Trepan would ſcarce pierce them; for it is putrid humidity which makes the bones ſoft and fungous, but

The ſigns of foulneſs of the bone.

Corrupt bones are ſometimes hard.

but the air by drying them exhauſts this humidity, and laſtly dries it, whence follows ſuch contumacious hardneſs. This ſign will be far more certain, if the fleſh which is grown upon the bone be more ſoft than is fit, looſe, and have little or no ſenſe of feeling. You may correct and amend this corruption of the bone with cauteries as well actual as potential; or with powders of *Aloes*, *Gentian*, *Ariſtolochia*, *Centaury*, *Cortex pini*: as ℞ *Radic. Ireos*, *Flor. Ariſtolochiæ*, *an.* ʒ i. *centaur.* ʒ ij. *corticis pini* ʒ ℔, *Miſce & fiat pulvis ſubtiliſſimus oſſi inſpergendus*. But if it be much corrupted, it muſt be ſcraped forth with your *Scalpra*. And you muſt expect the falling or ſcaling of the corrupt bone from the ſound, and not forcibly procure it; for otherwiſe the ſound bone, which lies under it, being as yet covered with no fleſh growing over it, would be corrupted by the appulſe or touch of the air. Yet you ſhall by little and little gently move and ſhake rotten bones with your Probe, that ſo they may more eaſily ſcale, and with leſs trouble to Nature. But note by the way, that the ſcaling of the bone which hath environed the Trepan, is commonly performed in the ſpace of forty or fifty days. So long alſo will that cauſed by the unuſual appulſe or touch of the air, or application of a cautery, or the aſperſion of the Cephalick Powders; beſides alſo, in the ſame number of days broken bones may be united and joined together by a *Callus*, which is to them as a ſcar, yet ſometimes ſooner, ſomewhiles later, according to the variety of the ages, tempers, and habits of divers men. But if the *Caries* or *rottenneſs* can neither by theſe fore-mentioned remedies be overcome and amended, neither the looſed continuity agglutinated or united, you muſt give the Patient a vulnerary Potion; for hence I have found happy ſucceſs in many. But ſometimes not onely a certain portion of the bone is taken with a *Caries*, but alſo the whole is often ſeized upon with a ſphacel, and all falls out. For, in *Hippocrates* opinion, *Lib. de Vulneribus Capitis*, the bone of the Skull being broken, falls from the ſound more or leſs, according to the violence of the blow; which alſo is confirmed by experience. For which purpoſe I think good in this place to recite a Hiſtory, whereof I was an eye-witneſs, whileſt I ſerved as a Chirurgeon in *Piemont* under the Marſhal *de Montejan* (who was the Kings Lieutenant there.) It happened that a Lacquey of *Monſieur de Coulains* came to me to be cured; he had the *Bregma* bone of the left ſide broken with a Sword, neither yet did the fracture come to the ſecond Table; a few days after his recovery, the bone being agglutinated and united, it came to paſs that a company of *Gaſcoign* Souldiers (his Country-men) came to *Turin*, with whom one morning he eat plentifully Tripe fried with Onions and Spices, and drank a great quantity of ſtrong Wine. Whereupon he preſently fell into a continual Fever and loſt his Speech and underſtanding; his head ſwelled, his eyes looked red and fiery, and as though they would have ſtarted out of his head. Which things being conſidered, I let him bloud, having firſt (by the Phyſicians advice) given him a Clyſter, and applied to his head ſuch things as were fit; and alſo I laboured with Frictions and Ligatures of the extreme parts, to draw the humours downwards, yet for all this the part of the head which was formerly affected begun to apoſtumate; which being opened, there came forth a great quantity of matter, and at the length the muſculous skin and *Pericranium* ſinking down, both the Tables of the Skull became putrefied and rotten, as you might know by their blackneſs and ſtench. Now to take away this corruption, I applied at certain times actual cauteries, both to amend the corruption and ſeparate that which was altered: but mark, after ſome moneths ſpace, a great number of Worms came forth by the holes of the rotten bones from underneath the putrefied Skull; which moved me to haſten the ſeparation and falling away of the putrid bones. Which being done, upon the very *Craſſa Meninx*, which is more ſtrange, in that place which Nature had covered with fleſh, I obſerved three cavities of the largeneſs of ones thumb filled with Worms about the bigneſs of a points tag, with black heads, diverſly wrapped among themſelves. The bone which Nature ſeparated was of the bigneſs of the Palm of ones hand, ſo that it was ſtrange that ſo large a portion of the skull ſhould be caſt off by Nature, and yet the Patient not die thereof; for he recovered yet beyond all mens expectation, but after the agglutination of the wound the ſcar remained very hollow according to the decree of *Hippocrates*. For fleſh doth not eaſily grow upon a *Callus*, becauſe it is a thing ſtrange and ſuppoſititious by Nature: beſides, as a ſcar is a thing more denſe than the skin, ſo is a *Callus* than the bone, ſo that through the more compact ſubſtance thereof, the bloud can neither freely nor plentifully ſweat through for matter to regenerate fleſh. Hence it is that whereſoever any portion of the skull is wanting, you may there by putting to of your hand perceive and feel the beating of the brain, wherefore the Skull muſt needs be much weaker in that place. Now to help this infirmity, I wiſhed this Lacquey to wear a Cap made of thick Leather, ſo more eaſily to withſtand external injuries; and verily thereby he grew much better. Now I think good in this place to lay open the deceit and craft of ſome Impoſtors falſly ſtiling themſelves Chirurgeons, who when they are called to cure Wounds of the head, wherein any part of the skull is loſt, perſuade the Patient and his Friends that they muſt put a plate of Gold in the place of the skull which is wanting. Wherefore they hammer it in the preſence of the Patient, and turn it divers ways and apply it to the part, the better to fit it; but preſently after they ſlily convey it into their purſes, and ſo leave the Patient thus couzened. Others brag that they are able to put the dried rind of a Gourd in the place of a loſt bone, and faſten it on to defend the part; and thus they groſly abuſe thoſe which are ignorant in the Art. For this is ſo far from being done, that Nature will not ſuffer nor endure ſo much as an hair, or any other ſmall body to be ſhut up in a Wound when it is cicatrized; neither is the reaſon alike of a leaden bullet, which ſhot into the body lies there for many years without any harm to the Patient; for although lead have a certain familiarity with Mans Body, yet is at length (unleſs the denſity of the oppoſed fleſh, ligament, tendon, or ſome other ſuch like ſubſtance hinder) thruſt forth by Nature, impatient of all ſtrange bodies. And thus much of the rottenneſs and corruption of fractured bones; now muſt we ſpeak of the diſcommodities which befall the *Meninges* by Wounds whereby the Skull is broken.

The benefit of a vulnerary potion.

A Hiſtory.

A great falling away of a corrupt bone.

Aph. 45. *ſect.* 6.

The covetous craft of Impoſtors.

CHAP.

CHAP. XXI.

Of the diſcommodities which happen to the Craſſa Meninx *by fractures of the Skull.*

MAny diſcommodities chiefly happen to the *Craſſa Meninx* by a fracture of the skull, and raſh trepaning thereof; for it ſometimes chances to be cut and torn. Agglutination is a remedy for this diſeaſe, which *Hippocrates* wiſhes to be procured with the juice of *Nepeta*, [that is, of that Calamint, which ſmells like Penny-royal] mixed with Barley-flour. In ſtead whereof this following Powder having the like faculty, may take place.

Remedies for the lacerated *Meninx.*

℞ *Colophon* ʒ iij. *Myrrhæ, Aloes, Maſtiches, Sanguinis Dracon. an.* ʒ i. *croci, ſarcocollæ, an.* ʒ ß. *miſce & fiat pulvis ſubtilis.* But to purge the bloud and matter which is gathered and lies between the *Craſſa Meninx* and skull, you ſhall put in a Tent made of a rag twined up ſome four or five double, and ſteeped in Syrup of Roſes or Wormwood, and a little *Aqua Vitæ*; for thus you ſhall preſs down both the *Craſſa Meninx*, leſt lifted up by the accuſtomed and native pulſation of the Brain, it ſhould be hurt by the edges of the Skull, yet rough by reaſon of the ſharp ſplinters of the bone lately trepaned, and give freer paſſage forth for the matter there contained. But as oft as you ſhall dreſs the Patient, you ſhall renew the fore-mentioned Tent, untill all the matter be purged forth. And ſo often alſo you ſhall preſs down with this following Inſtrument the *Dura Mater*, and bid the Patient to ſtrive to put forth his breath, ſtopping his mouth and noſe, that ſo the matter may more eaſily be evacuated. This Inſtrument wherewith you ſhall hold down the *Dura Mater*, muſt have the end round, poliſht, and ſmooth, as it is here expreſt.

A fit Inſtrument to preſs and hold down the Dura Mater, *ſo to make way for the paſſage forth of the* Sanies *or Matter.*

A Sponge fit to foment withall.

And let there be laid upon the *Dura Mater* ſtrewed over with the formerly fore-mentioned Powder, a ſponge moiſtned and wrung forth of a drying decoction made of aromatick and cephalick things, ſuch as this which follows. ℞ *Fol. ſalviæ, majoran. betonicæ, roſar. rub. abſinth. Myrtil. florum chamæm. melil. ſtœchad. utriuſque an. M.* iij. ß. *rad. cyperi, calam. aromat. ireos, caryophyllatæ, angelicæ, an.* ʒ. ß. *bulliant omnia ſecundum artem cum aqua fabrorum & vino rubro, fiat decoctio ad uſum dictum.* An in ſtead hereof you may uſe Claret with a little *Aqua Vitæ*, that ſo the contained matter may be evacuated and dried up. A Sponge is fitter for this purpoſe to draw than a linnen rag, or any other thing, both becauſe it is good of it ſelf to draw forth the humidity, as alſo for that by its ſoftneſs it yields to the pulſation of the Brain. Then apply to the Wound and all the adjoining parts, an Emplaiſter of *Diacalcitheos* diſſolved with Vinegar or Wine, or Oil of Roſes, that ſo the Plaiſter may be the more cold and ſoft. For, in *Hippocrates* opinion, nothing which is any thing heavy or hard muſt be applied to the wounds of the head, neither muſt it be bound with too ſtrait or hard a ligature, for fear of pain and inflammation.

Lib. de vuln. cap.

Lib. de faſciis. The diſcommodities of too ſtrait binding of the head.

For *Galen* tells (as he had it from *Mantias*) that a certain man had loſt his eyes by inflammation and impoſtumation, ariſing for that an Apothecary had uſed too ſtrait a ligature to his head and face; for this ſtrait ligature ſo preſſed the ſutures, that the fuliginous vapours, which uſed to paſs through them and the pores of the skull, were ſtopped from paſſing that way; beſides, the beating of the Arteries was intercepted and hindered, by which means the pain and inflammation ſo increaſed, that his eyes were rent and broke in ſunder and fell forth of their orb. Wherefore *Hippocrates* rightly commends an indifferent ligature: alſo he fitly wiſheth us to let the Emplaiſters be ſoft which are applied to the head, as alſo the cloaths wherewith it is bound up to be of ſoft and thin Linnen, or of Cotton or Wool. When the Patient is in dreſſing, if there come much matter out of the Wound, you ſhall wiſh him if he can, to lie upon the wound, and now and then by fits to ſtrive to breathe, ſtopping his mouth and noſe, that ſo the brain lifted and ſwollen upwards, the matter may be the more readily caſt forth; otherwiſe ſuffer him to lie ſo in his bed, as he ſhall beſt like of, and ſhall be leaſt troubleſom to him. You may with good ſucceſs put upon the *Craſſa Meninx* Oil of Turpentine with a ſmall quantity of *Aqua Vitæ* and a little Aloes and Saffron finely powdered, to cleanſe or draw forth the *Sanies* or Matter, Or elſe, ℞ *Mellis roſar.* ʒ ij. *farinæ hord. pulver. aloes, maſtich. & Ireos florent. an.* ʒ ß. *Aqua Vitæ, parum*; let them be incorporated together and make a deterſive Medicin for the aforeſaid uſe.

What cloaths we muſt uſe.

How the Patient muſt lie in his bed.

Paulus lib. 6. cap. 90.

Sometimes alſo the *Craſſa Meninx* is inflamed after Trepaning, and ſwollen by a *Phlegmon*, that, impatient of its place, it riſes out of the hole made by the Trepan, and lifts it ſelf much higher than the skull, whence grievous ſymptoms follow. Wherefore to prevent death, of which then we ought to be afraid, we muſt enlarge the former hole with our cutting Mullets, that the matter contained under the Skull, by reaſon of whoſe quantity the membrane ſwells, may the more freely breathe and paſs forth, and then we muſt go about by the preſcript of the Phyſician to let him bleed again, to purge and diet him. The inflammation ſhall be reſiſted by the application of contrary remedies, as this following fomentation. ℞ *Sem. lini, althæ. fon. pſillii, roſ. rub. an.* ʒ i. *ſolani, plantag. an. M.* i. *bulliant in aqua tepida communi, ex qua fiat fotus.* Anodyne and repelling Medicins ſhall be dropped into his ears, when it is exceedingly ſwollen, that the tumor may ſubſide, you ſhall caſt upon it the meal or flour of Lentils, or Vine leaves beaten with Gooſe greaſe. With all which remedies, if the tumor do not vaniſh, and withall you conjecture that there is *Pus* or Matter contained therein, then you muſt open the *Dura Mater* with your inciſion-knife, holding the point upwards and outwards, for ſo the matter will be poured forth and the ſubſtance of the Brain not hurt nor touched. Many other Chirurgeons, and I my ſelf, have done this in many Patients with various ſucceſs. For it is better in deſperate caſes

Remedies for the inflammation of the *Craſſa Meninx.*

How we muſt open the *Craſſa Meninx* when it is impoſtumate.

to

to try a doubtful remedy than none at all; also it oft-times happens, whether by the violence of the contusion and blow, or concretion, or clotting of the bloud which is shed, or the appulse of the cold air, or the rash application of Medicins agreeing neither in temper nor complexion with the *Crassa Meninx*, or also by the putrefaction of the proper substance, that the *Dura Mater* it self becomes black. Of which symptom the Chirurgeon must have a great and special care.

The causes and remedies of the blackness of the *Dura Mater*.

Therefore that thou mayest take away the blackness, caused by the vehemency of the contusion, you shall put upon it oil of Eggs with a little *Aqua Vitæ*, and a small quantity of Saffron and Orris roots in fine powder, you shall also make a fomentation of discussing and aromatick things boiled in Water and Wine; and *Vigo*'s Cerat formerly described shall be applied. But if the harm come from congealed bloud, you shall withstand it with this following remedy. ℞ *Aqua vitæ* ℥ ij. *granor. tinctorum in tenuem pulverem tritorum* ʒ ij. ℈. *croci*, ℈ i. *Mellis rosat.* ʒ ij ℈. *sarcocol.* ʒ iij. *Leviter & simul bulliant omnia, & de colatura infundatur, quousque nigrities fuerit obliterata.* If this affect come by the touch of the air, it shall be helped with this following remedy. ℞ *Tereb. ven.* ℥ iij. *Melis ros.* ℥ ij. *Vitellum ov. unum, farin. hordei* ʒ iij. *croci* ℈ i. *sarcocol.* ʒ ij. *aq. vitæ* ʒ ij. *incorporentur simul, & bulliant paululum.* This remedy shall be used until the blackness be taken away, and the Membrane recover its pristin colour.

Remedies for contusion.

For congealed bloud.

For the hurt received by the air.

But if this affect proceed from the rash use of Medicins, it must be helped by application of things contrary. For thus the offence caused by the too long use of moist and oily Medicins, may be amended by using catagmatick and cephalick powders; but the heat and biting of acrid Medicins shall be mitigated by the contrary use of gentle things: for both humid and acrid things somewhat long used, make the part look black; that truly, by generating and heaping up filth; but this by the burning and hardning heat. But when such blackness proceeds from putrefaction, *John de Vigo* commends the following remedy. ℞ *Aqua Vitæ* ℥ ij. *mellis rosat.* ʒ ℈. But if the affect be grown so contumacious that it will not yield to this gentle remedy, then this following will be convenient. ℞ *Aqua Vitæ* ℥ iij. *mellis ros.* ℥ i. *pulver. Mercur.* ʒ ij. *unica ebullitione bulliant simul ad usum dictum.* Or, ℞ *Aq. vit.* ℥ i ℈. *syrup. absinth. & mellis rosat. an.* ʒ ij. *unguenti Ægyptiaci* ʒ i. ℈. *sarcocol. myrrhæ, aloes, an.* ʒ i. *vini albi boni & odoriferi,* ℥ i. *bulliant leviter omnia simul, colentur ad usum dictum.* But if the force of the putrefaction be so stubborn that it will not yield to these remedies, it will be helped with *Ægyptiacum* (made with Plantain Water in stead of Vinegar) used alone by it self, or with the powder of Mercury alone by it self, or mixt with the powder of Alum. Neither must we be afraid to use such remedies, especially in this extreme disease of the *Dura Mater*, for in *Galens* opinion the *Crassa Meninx*, after the skull is trepaned, delights in Medicins that are acrid, that is, strong, and very drying, especially if it have no *Phlegmon:* and this for two reasons; the first is, for that hard and dry bodies, such as membranous bodies are, be not easily affected, unless by strong Medicins; the other is, which must be the chief and prime care of the Physician, to preserve and restore the native temper of the part by things of like temper to it. But if the auditory passage not onely reaching to the hard membranes of the Brain, but also touching the Nerve which descends into it from the Brain, suffer most vehement Medicins, though it be placed so near; certainly the *Crassa Meninx* will endure them far more easily and without harm. But if by these means the putrefaction be not restrained, and the tumor be increased so much, that the *Dura Mater* rising far above the skull, remains unmovable, black and dry, and the Patients eyes look fiery, stand forth of his head and rowl up and down with unquietness and a phrensie, and these so many ill accidents be not fugitive, but constant; then know that death is at hand, both by reason of the corruption of the gangrene of a noble part, as also by extinction of the native heat.

What Medicins make the *Crassa Meninx* black.

Medicins against the putrefaction of the *Meninx*.

Why the *Crassa Meninx* easily endures acrid Medicins

Signs of death at hand.

CHAP. XXII.

Of the Cure of the Brain, being shaken, or moved.

WE have formerly declared the causes, signs, and symptoms of the concussion, or shaking of the Brain, without any wound of the musculous skin, or fracture of the bone; wherefore for the present I will treat of the Cure. Therefore in this case, for that there is fear that some Vessel is broken under the skull, it is fit presently to open the cephalick Vein, and let bloud be plentifully taken according to the strength of the Patient, as also respectively to the disease both which is present and like to ensue, taking the advice of a Physician. Then when you have shaved away the hair, you shall apply to the whole head and often renue the fore-mentioned Cataplasm, *Ex farinis, oleo rosaceo, oxymelite*, and other like cold and moist repelling Medicins. But you must eschew dry, and too astringent Medicins must be shunned, such as are *Unguentum de bolo* and the like; for they obstruct too vehemently, and hinder the passage forth of the vapours both by the sutures and the hidden pores of the skull. Wherefore they do not onely not hinder the inflammation, but fetch it when it is absent, or increase it when present. The belly shall be loosed with a Clyster, and the acrid vapours drawn from the head; for which purpose also it will be good, to make frictions from above downwards, to make straight ligatures on the extreme parts, to fasten large cupping-glasses with much flame to the shoulders and the original of the spinal marrow, that so the revulsion of the bloud running violently upwards to the brain, and ready to cause a Phlegmon, may be the greater. The following day it will be convenient to open the *Vena Puppis*, which is seated upon the Lambdal suture, by reason of the community it hath with the Veins of the brain, and shutting the mouth and nose to strive powerfully to breathe. For thus the membranes swell up, and the bloud gathered between them and the skull, is thrust forth, but not that which is shut up in the brain and membranes, of which if there be any great quantity, the case is almost desperate, unless Nature assisted with stronger force, cast it forth turned into *Pus*. But also after a few days the *Vena frontis* or fore-head Vein may be opened, as also the Temporal Arteries, and Veins under the Tongue, that the

What the concussion of the Brain is.

The opening of the *Vena Puppis*.

the conjunct matter may be drawn forth by ſo many open paſſages. In the mean ſpace the Patient muſt keep a ſpare diet, and abſtain from Wine, eſpecially until the 14. day, for that until that time the featful ſymptoms commonly reign. But repelling Medicins muſt be uſed until the 14. day be paſt, when we muſt come to diſcuſſing Medicins, beginning with the more mild, ſuch as is this following decoction. ℞ *Rad. Alth.* ℥ vj. *ireos, cypari, calam. arom. an.* ℥ ij. *fol. ſalviæ, majoran. betonic. flor. chamæm. melil. roſarub. ſtœchad. an. M.* ß. *ſalis com.* ℥ iij. *bulliant omnia ſimul ſecundum artem cum vino rub. & aquæ fabrorum, fiat decoctio.* Let the head be waſhed therewith twice a day with a Sponge. But yet when you do this, ſee that the head be not too much heated by ſuch a fomentation, or any ſuch like thing, for fear of pain and inflammation. Then you ſhall apply the Cerate of *Vigo* which hath power to diſcuſs indifferently, to dry, and draw forth the humours which are under the skull, and by its Aromatick force and power to confirm and ſtrengthen the Brain; it's thus deſcribed. ℞ *Furfuris bene triturati* ℥ iij. *farin. lentium* ℥ ij. *roſ. myrtillor. foliorum & granorum ejus, an.* ℥ i. *calam. aromat.* ℥ i. ß. *chamæmel. melil. M.* ß. *nuces cupreſſi num.* vj. *olei roſacei, & chamæm. an.* ℥ iij. *ceræ albæ* ℥ ij. ß. *thuris, maſtichis, an.* ℥ iij. *myrrhæ* ℥ ij. *in pulverem quæ redigi debent redactis, & liquefactis oleis cum cera, omnia miſceantur ſimul & fiat mixtura, quæ erit inter formam emplaſtri & ceroti.*

A diſcuſſing fomentation.

A caution in fomenting the head.

A deſcription of *Vigo*'s Cerate.

Vigo ſaith that one of the Duke of *Urbins* Gentlemen found the Urine hereof to his great good. He fell from his Horſe with his head downwards upon hard Marble, he lay as if he had been dead, the bloud guſht out of his noſe, mouth, and ears, and all his face was ſwollen, and of a livid colour; he remained dumb twenty days, taking no meat but diſſolved Gellies, and Chicken and Capon broths with Sugar; yet he recovered, but loſt his memory, and faltered in his ſpeech all his life after. To which purpoſe is that Aphoriſm in *Hippocrates*; Thoſe that have their Brain ſhaken by what cauſe ſoever, muſt of neceſſity become dumb; yea, alſo as *Galen* obſerves in his Commentary, loſe both their ſenſe and motion. That Cerate is not of ſmall efficacy, but of marvellous and admirable force, which could hinder the generating of an abſceſs, which was incident to the Brain by reaſon of the fall. Yet there be many men ſo far from yielding to reaſon, that they ſtifly deny that any impoſtumation can be in the Brain; and augmenting this errour with another, they deny that any who have a portion of the Brain cut off can recover, or riſe again; but the authority of ancient Writers and Experience, do abundantly refel the vanity of the reaſons whereon they rely. Now for the firſt, in the opinion of *Hippocrates*; If thoſe which have great pain in their heads have either *pus*, water or bloud flowing from their noſe, mouth, or ears, it helps their diſeaſe.

A Hiſtory.

Aph. 58. *ſect.* 7.

That there may be an abſceſs in the Brain. *Aph.* 10. *ſect.* 6.

Gal. lib. de inæqual. intemp. Rhaſ. cap. 4. *continent. Avicen cap. de exit. ſen.* 3. *lib.* 4. *cap.* 20.

But *Galen*, *Rhaſis*, and *Avicen*, affirm that *ſanies* generated in the Brain, disburdens it ſelf by the noſe, mouth, or ears; and I my ſelf have obſerved many who had the like happen to them.

A Hiſtory.

I was told by *Prothais Coulen*, Chirurgeon to *Monſieur de Langey*, that he ſaw a certain young man in the Town of *Mans*, who often uſed to ring a great Bell, he once hanging in ſport upon the rope, was ſnatcht up therewith, and fell with his head full upon the pavement; he lay mute, was deprived of his ſenſes and underſtanding, and was beſides hard bound in his Belly. Wherefore preſently a Fever and *Delirium*, with other horrid ſymptoms aſſailed him, for he was not trepanned becauſe there appeared no ſign of fracture in the skull: on the ſeventh day he fell into a great ſweat with often ſneezing, by violence whereof a great quantity of matter and *Pus* flowed forth of his ears, mouth, and noſe; then he was eaſed of all his ſymptoms, and recovered his health.

Lib. 8. *de uſu part. & com. ad Aph.* 18. *ſect.* 6.

Now for the ſecond, *Galen* affirms that he ſaw a Boy in *Smyrna* of *Ionia*, that recovered of a great wound of the Brain, but ſuch an one as did not penetrate to any of the ventricles. But *Guido* of *Cauliac* ſaith, he ſaw one which lived and recovered after a great portion of the Brain fell out by reaſon of a wound received on the hind part of his head. In the Year of our Lord 1538, while I was Chirurgeon to the Marſhal of *Montejan* at *Turin*, I had one of his Pages in cure, who playing at Quoits received a wound with a ſtone upon the right *Bregma* with a fracture, and ſo great an effracture of the bone, that the quantity of half a haſel Nut of the Brain came forth thereat. Which I obſerving, preſently pronounced the wound to be deadly; a Phyſician which was preſent, contradicted my opinion, affirming that ſubſtance was no portion of the Brain, but a certain fatty body. But I with reaſon and experience in the preſence of a great company of Gentlemen, convinced the pertinacy of the Man with reaſon; for that fat cannot be generated under the skull, for although the parts there contained be cold, yet becauſe they are heated by the abundance of the moſt hot and ſubtle animal ſpirits, and the heat of vapours riſing thither from all the body, they do not ſuffer fat to concrete about them. But with experience, for that in diſſecting of dead bodies, there was never any fat obſerved there; beſides alſo fat will ſwim on the top of water, but this ſubſtance as marrowy, caſt into the water preſently ſunk to the bottom.

Why fat cannot be generated under the skull.

Signs of a fatty ſubſtance.

Laſtly, Fat put to the fire becomes liquid and melts; but this ſubſtance being laid upon a hot iron became dry, ſhrunk up and contracted it ſelf like a piece of leather, but diſſolved not at all. Wherefore all thoſe which were preſent cried out, that my judgment was right of that ſubſtance that came forth of the skull. Yet though it was cut away, the Page recovered perfectly, but that he continued deaf all his life after.

CHAP. XXIII.

Of the Wounds of the Face.

Why we treat in particular of wounds of the Face.

HAving treated of the Wounds of the Head by their cauſes, ſigns, and cure, it follows that we now ſpeak of the wounds of the Face, if but for this, that when they are careleſly handled, they leave deformed ſcars in the moſt ſpecious and beautiful part of the body. The cauſes are the ſame which are incident to the skull, that is, external. But this may be added to the kinds nd differences of the wounds, that the life may be out of danger though any one whole part of the aFac(as the ear, eye, noſe, lip,) may be cut away by a wound, but not ſo in the Head or Skull.

Where-

Wherefore beginning at the Wounds of the eye-brows, we will proſecute in order the Wounds of the other parts of the face.

This is chiefly to be obſerved in wounds of the Eyebrows, that they are oft-times cut ſo overthwart, that the muſcles, and fleſhy pannicle which move and lift them up, are wholly rent and torn. In which caſe the eye-lids cannot be opened, and the eyes remain covered, and, as it were, ſhut up in the caſes of their lids; ſo that even after the agglutination of the Wound, if the Patient would look upon any thing, he is forced to hold up the eye-lids with his hand; with which infirmity I have ſeen many troubled, yet oft-times not ſo much by the violence of the Wound, as the unskilfulneſs of the Chirurgeon who cured them, that is, by the negligent application of the boulſters, an unfit ligature, and more unfit ſuture. In this caſe the skilful Chirurgeon, which is called to the Patient, ſhall cut off as much of the skin and fleſhy pannicle as ſhall ſerve the eye-lids, that ſo they may by their own ſtrength hold and keep open, without the help of the hand: then he ſhall ſew the Wound as is fit, with ſuch a ſtitch as the Furriers and Glovers uſe; and then he ſhall pour thereon ſome of the Balſom of my deſcription, and ſhall lay ſuch a Medicin to the neighbouring parts. ℞ *Olei roſar.* ℥ ß. *album ovor. nu.* ij. *boli armen. ſanguin. Drac. Maſtich. an.* ℥ j. *agitentur ſimul, fiat medic.* Then let the part be bound with a fitting ligature. Afterwards you ſhall uſe *Emplaſt. de gratia Dei, Empl. de Betonica, Diacalcitheos*, or ſome other like, until the Wound be cicatrized. But ſuch like, and all other Wounds of the Face may be eaſily healed, unleſs they either be aſſociated with ſome malign ſymptoms, or the Patients body be repleat with ill humours.

A thing to be obſerved in Wounds of the Eye-brows.

There ſometimes happen a quite contrary accident in Wounds of the Eye-brows, that is, when the eye-lids ſtand ſo up that the Patient is forced to ſleep with eyes open; wherefore thoſe which are ſo affected, are called by the *Greeks Lagophthalmi.* The cauſe of this affect is often internal, as a carbuncle, or other kind of abſceſs, as a blow or ſtroak. It ſhall be cured by a crooked or ſemicircular inciſion made above the eye-lids, but ſo, that the extremes of the ſemicircle bend downwards, that they may be preſſed down and joined as much as is needful to amend the ſtiffneſs of the eye-lid. But you muſt not violate the griſle with your Inſtrument, for ſo they could no more be lifted up; the reſidue of the cure muſt be performed as is fit.

Lagophthalmia is a quite contrary accident to the falling down of the Eye-lids.

CHAP. XXIV.

Of the Wounds of the Eyes.

WOunds of the Eyes are made by the violence of things pricking, cutting, bruiſing, or otherwiſe looſing the continuity. But the cure muſt always be varied according to the variety of the cauſes and differences. The firſt head of cure is, that if any ſtrange and heterogeneous body ſhall be fallen into the eyes, let it be taken forth as ſoon as you can, lifting and turning up the eye-lid with the end of a *Spatula.* But if you cannot diſcern this mote or little body, then put three or four ſeeds of *Clary*, or *oculus Chriſti* into the pained eye. For theſe ſeeds are thought to have a faculty to cleanſe the eyes and take out the motes, which are not faſtned deep in, nor do too ſtubbornly adhere to the membranes. For in this caſe you ſhall uſe this following Inſtrument, for herewith we open the eye-lids the further, putting it between them and the Eye, and alſo keeping the Eye ſteddy by gently preſſing it, that ſo with our mullets we may pull out the extraneous body; this is the figure of ſuch an Inſtrument.

The delineation of a Speculum Oculi, *fit to dilate and hold aſunder the Eye-lids, and keep the Eye ſteddy: it is ſo made, that it may be dilated and contracted according to the greatneſs of the Eyes.*



All ſtrange bodies taken out, let this medicin be put into the Eye. Take the ſtrains of a dozen Eggs, let them be beaten in a leaden Mortar, with a little Roſe-water, and ſo put into the Eye; but let this repercuſſive be laid upon the Eye and the neighbouring parts. ℞ *Albumin. ovor. nu.* iv. *pulver. aluminis rochæ combuſti* ℥ ij. *ſanguinis Draconis* ℥ j. *aquæ roſar. & plantag. an.* ℥ ij. *agitentur ſimul*, make a repercuſſive, which you may frequently uſe. Or elſe apply Cheeſe-curds well wrung, mixed with Roſe-water, the white of an Egg, and as much *acacia* as ſhall ſuffice. This which followeth doth more powerfully ſtay the flowing humour. ℞ *gum. arab. & tragac. an.* ℥ ij. *pſillii cydon. ſem. portul. plant. ſumach. an.* ℥ ij. *fiat mucag. cum aqua plantag. ſolan. & roſar. concinnetur collyrium*, of which you may drop ſome both within and about the Eye.

A repercuſſive to be put into the Eye.

Divers repercuſſives to be applied to the Eye.

But note, that all ſuch remedies muſt be applied warm, both that they may the better penetrate by their moderate heat, as alſo for that all actual cold things are hurtful to the eyes and ſight, becauſe they dull the ſight by incruſtating the viſive ſpirits. For I have known many who have become dull of ſight by the frequent uſing of Medicins actually cold to the eyes. I have on the contrary ſeen not a few, who have recovered with the fit uſe of ſuch like Medicins, who have had any part of their eye (ſo it were not the *pupilla* or apple of the eye) ſo pricked with a Needle or Bodkin, that much of the wateriſh humour ran forth thereat.

Things actually cold are hurtful to the Eyes.

The milk of a Woman which ſuckles a Girl (for that is reputed the cooler) mitigates pain and cleanſes, if it be milked out of the Dug into the eye; to which purpoſe alſo the bloud of Turtles, Pigeons,

Anodyne Medicins for the Eyes.

Pigeons or Chickens much conduces, being dropt into the eye by opening a Vein under their Wings. Alſo this following Cataplaſm aſſwageth pain and inflammation, and hinders defluxion, being applied to the eye and the adjacent parts. ℞ *Carnis pomorum ſub cinere calido decoctorum* ℥ v. *vitel. ovorum num.* iij. *caſſiæ fiſtulæ recenter extractæ* ℥ ß. *mucaginis pſillii, altheæ, & cydon. an.* ℥ j. *farin. hordei parum; incorporentur omnia ſimul, fiat cataplaſma.* Alſo Sheeps Lungs boiled in Milk and applied warm, and changed as they grow cold, are good to aſſwage pain. But if the too violent heat and pain ſhall not yield to ſuch Medicins, but require more vehement, then *Foliorum Hyoſcyami, m.* j. *ſub. cineribus coquatur, atque in mortario cum mucagine ſeminis pſillii, & cydonior. extracti. in aquis ſolani & plantag. piſtetur:* then let this Medicin be wrapped in a linnen cloth and applied to the Eyes and Temples. The mucilages of *Pſillium* or Flea-wort, and Quince-ſeed extracted in a decoction of Poppy-heads, and mixed with a little *Opium* and Roſe-water, are uſed for the ſame purpoſe. But when there is need of detergent and ſarcotick Medicins, then ℞ *Syrup. roſar. ſiccat.* ℥ j. *aq. fœnic. & rutæ, an.* ℥ ij, *aloes lotæ, olibani, an.* ℥ ß. mix them for the foreſaid uſe. The galls of Scates, Hares, and Partridges, diſſolved in Eye-bright and Fennil Water, are fit for cleanſing ſuch Wounds: as alſo this following *Collyrium.* ℞ *Aquæ hordei* ℥ j. *mellis deſpumati,* ℥ iij. *Aloes ter lotæ in aqua plantaginis & ſacchari cand. an.* ℥ j. *fiat collyrium.* Alſo this enſuing Medicin is very ſarcotick. ℞ *Mucagin. gummi olibani arabici, tragacanth. & ſarcocol. in aq. hordei extracti. an.* ℥ iij. *aloes ter lotæ in aq. roſar.* ℥ j. *ceruſ. uſtæ & lotæ, tutiæ præpar. an.* ℥ ß. *fiat collyrium.* But here you muſt note, that the coat *Adnata* often ſwells ſo much by reaſon of a wound, or ſome other injury, and ſtands ſo forth by the falling down of humours, acceſs and mixture of flatulencies, that it hides the whole *Pupilla*, and hangs forth of the eye-lids like as if it were an unnatural fleſhy excreſcence, and it loſes, the native colour, and looks very red, ſo that the Eye can neither be ſhut nor opened.

Narcoticks.

Detergent Medicins.

A ſarcotick Medicin for the eyes.

Wherewith a young Chirurgeon being deceived, determined to cut away this protuberancy of the *Adnata*, as though it had been ſome ſuperfluous fleſh, and then to waſte it with cathæretick Powders, had I not forbidden him, telling him of the certain danger of blindneſs which would thereupon befall the Patient. Wherefore I preſcribed a Fomentation of Chamomil, Melilote, Roſe-leaves, Wormwood, Rue, Fennil and Anniſeeds, boiled in Milk with the roots of Oris and Marigolds. Then I preſently added this following Fomentation, being more powerful and drying. ℞ *Nucis cupreſſi, gallar. balauſt. an.* ℥ j. *plantagin. abſinth. hippuris, flor. chamæm. roſar. rub. an. M* ß. *bulliant ſimul, cum aqua fabrorum, & fiat decoctum pro fotu cum ſpongia.* Beſides alſo you may apply a Cataplaſm made of Barley and Bean-flour, the Powders of Maſtick, Myrrhe, and Aloes, and ſome of the laſt deſcribed Decoction. The Tumour beginning to decline, I dropt the flowing Liquor into the Eye, which hath a very aſtringent, drying and ſtrengthening faculty. Roaſt a new laid Egg in Embers until it be hard, then pill off the ſhell, take forth the Yolk, and in place thereof put a ſcruple of Roman Vitriol in fine Powder, then put it in a linnen cloth and wring it hard forth into ſome clean thing, and drop thereof for ſome days into the Eye, with a little Smiths Water wherein Sumach and Roſe-leaves have been boiled. I have found by experience the certain force of this remedy; but if notwithſtanding there be a true fleſhy excreſcence upon the coat *Adnata*, it may be taken away by this following Powder. ℞ *Oſſis ſepiæ, & teſtæ ovorum calcinatæ an.* ℥ j. *fiat pulvis.* Calcined Vitriol, burnt Alum, and the like may be commodiouſly uſed to this purpoſe. Yet you muſt warily make uſe of all ſuch things, and always lay repercuſſives about the eye, that no harm enſue thereof. For divers times acrid humours fall down into the Eye with ſuch violence, that they break the horny coat, whereupon the humours of the Eye are poured out. Remember alſo, that in diſeaſes of the Eyes the Patient lie with his head ſomewhat high, and that he keep ſhut not onely the pained, but alſo the ſound Eye, becauſe reſt is always neceſſary for the grieved part. But one Eye cannot be moved without ſome motion of the other, by reaſon of the connexion they have by their optick and moving nerves, both the *Meninges* and the *Pericranium*, Veins and Arteries; which is the cauſe that when the one ſuffers, the other in ſome ſort partakes therewith.

A drying Fomentation.

A Medicin to conſume a fleſhy excreſcence without biting.

But if we cannot prevail by all theſe formerly preſcribed Medicins fit to ſtay the defluxion, then it remains that we apply a Seton to the Neck, for it is a ſingular remedy againſt inveterate defluxions into the Eyes. For we know by daily experience., that many who have had their ſight dulled by a long and great defluxion, ſo that they were almoſt blind, have by little and little recovered their former ſplendour and ſharpneſs of ſight, when matter once began to be evacuated by the Seton.

A Seton, a good remedy againſt inveterate defluxions into the eyes.

The truth hereof appeared in *Paul* the *Italian* Goldſmith, who dwelt near the *Auſtin-Friars*. For he having uſed many Medicins of divers Phyſicians and Chirurgeons in vain, when he was almoſt blind, he applying a Seton by mine advice, began by little and little to ſee better according to the quantity of the matter which was evacuated, until at length he perfectly recovered his ſight. But at laſt growing weary of the Seton which he had worn for a Year (although matter came daily forth thereof) yet he would have it taken forth and healed up; but this way of evacuation being ſhut up, and the humour beginning to flow into his eyes, ſo that he was in danger to become blind, he called me and made me again to apply the Seton in his Neck. Whereby recovering his former ſoundneſs and perfection of ſight, he yet wears the Seton.

A Hiſtory.

I alſo once freed by this kind of remedy, by appointment of the moſt learned Phyſician *Hollerius*, a certain young man of 20 years old, from the Falling-ſickneſs, who before had many fits thereof; the Ichorous humours, the feeders of this Diſeaſe, being by this means, as it is moſt probable, drawn away and evacuated.

A Seton good againſt the Falling-ſickneſs.

Wherefore ſeeing a Seton is of this uſe, I have thought good in this place to ſet down in Writing and by Figure, the manner of making thereof, for the behoof of young Practitioners: Wiſh the Patient to ſit on a low Stool, and to bend down his head, that ſo the skin and fleſhy pannicle may be relaxed; then muſt you with your fingers pluck up and ſever the skin from the muſcles, and

The manner of making a Seton.

A Figure of the Pincers, actual Cautery, and Needle, uſed in making a Seton.



and take hold of as much hereof as you can with your Pincers, not touching the Muſcles of the neck for fear of a Convulſion and other ſymptoms; you ſhall then twitch the skin which is held in the Pincers moſt hard, when you ſhall thruſt the hot Iron through the holes made in the midſt of them; that alſo the nerves being ſo twitched, the dolorifick ſenſe may the leſs come to the part. The wound muſt be made or burnt in long-ways, and not thwarting that ſo the matters may be the better evacuated by the ſtrait fibers. But the Cautery or hot Iron muſt have a three or elſe a four-ſquare point, and that ſharp that ſo it may the more eaſily and ſpeedily enter. Then keeping the Pincers immoveable, let him draw through the paſſage made by the Cautery a needle and thred with a three or four-doubled thred of Cotton [or rather a skean of Silk] moiſtned in the white of an Egg and Oil of Roſes; then after you have applied pledgets dipped in the ſame Medicin, bind up the part with a convenient ligature. The day following the neck muſt be anointed with Oil of Roſes, and the pledgets dipped in the former Medicin applied for ſome days after. But it will be convenient to moiſten the Seton with a digeſtive made of the yolk of an Egg and oil of Roſes until the Ulcer caſts forth much matter; then you ſhall anoint the Cotton thred with this following remedy. ℞ *Terebinth.ven.* ʒ iv. *ſyrupi roſat. & abſinthii an.* ʒ ß. *pulv. Ireos, diacrydii, agarici trochiſc. & Rhei, an.* ʒ ß. *incorporentur omnia ſimul & fiat medic.* Which you ſhall uſe ſo long as you intend to keep open the Ulcer. For it hath a faculty to draw the humors from the face, and cleanſe without biting.

I have found not long ſince by experience, that the apertion made with a long thick Triangular needle of a good length like to a large Pack-needle, is leſs painful than that which is performed with the actual cautery which I formerly mentioned. Wherefore I would adviſe the young Chirurgeon, that he no more uſe the aforeſaid actual cautery. I have here given you the Figure of the Needle.

The Figure of a Triangular Needle.



CHAP. XXV.

Of Wounds of the Cheek.

SEeing a Wound in the Cheek ſeems to require a Suture, it muſt have a dry ſuture (as they term it) leſt that the ſcar ſhould become deformed. For that deformity is very grievous to many, as to Women who are highly pleaſed with their beauties. Therefore you ſhall ſpread two pieces of new cloth of an indifferent fineneſs, and proportionable bigneſs with this enſuing Medicin. ℞ *Pulveris Maſtichini, Sanguinis Draconis, Thuris, farinæ volatilis, tragacanthæ contuſæ, gypſi, piſis, ſarcocollæ, an* ʒ ij. *picis nigræ,* ʒ j. ß. *albumina ovorum quæ ſufficiant, fiat medicamentum.* Apply the pieces of cloth ſpread with this, on each ſide of the Wound one, ſome fingers bredth aſunder, and let it alone till it be hard dried to the skin. Then you ſhall ſo draw them together with your Needle and thred, that the fleſh by their ſticking may alſo follow, and be mutually adjoined, as you may ſee it here expreſt. The Wound ſhall be agglutinated by this means, together with the uſe of fit Medicins, Pledgets, Ligatures. But all the Ligatures and ſtays which ſhall be uſed for that purpoſe, muſt be faſtned to the Patients night-lap.

The uſe of a dry ſuture.

How to make a dry ſuture.

But when the Wound is great and deep, and the lips thereof are much diſtant the one from the other, there can be no uſe of ſuch a dry ſuture. Wherefore you muſt uſe a three or four-ſquare Needle (that ſo it may the more readily and eaſily enter into the fleſh) being thred with a waxed thred; and with this you muſt thruſt through the lips of the Wound, and leave the Needle ſticking in the Wound, and then wrap the thred to and again over the ends thereof eight or ten times, juſt after that manner which Women uſe to faſten a Needle with thred in it upon their ſleeves, or Tailors to their hats or caps, that they may not loſe them.

A ſuture fit for hare-lips. The manner thereof.

The Needle thus faſtned ſhall be there until the perfect agglutination of the Wound; this kind of ſuture is uſed in the wounds of the lips, as alſo in hare-lips, for ſo we commonly call lips which are cleft from the firſt conformation in the Womb by the errour of the forming faculty. But ſuch a ſu-

What hare-lips are.

ture will help nothing to agglutination, if there lie or remain any skin between the lips of the wound; wherefore you ſhall cut away whatſoever thereof ſhall be there, otherwiſe you muſt expect no union. Other kind of ſutures are of no great uſe in wounds of theſe parts, for out of the neceſſity of eating and ſpeaking, they are in perpetual motion, wherefore a thred would cut the fleſh; for which reaſon you ſhall take up much fleſh with ſuch Needles mentioned in this laſt deſcribed kind of ſuture, as this following Figure ſhews.

The Figure of the ſuture fit for cloven or hare-lips; as alſo the delineation of the Needle about whoſe ends the thred is wrapped over and under, to and again.

A Hiſtory.

To this purpoſe I will recite a Hiſtory, to the end, that if any ſuch thing happen to come to your hands; you may do the like. A certain Gaſcoign in the battel of Saint *Laurence*, had his upper jaw cut overthwart even to his mouth, to the great disfiguring of his face. The wound had many worms in it, and ſtank exceedingly, becauſe he could get no Chirurgeon until three days after he was hurt. Wherefore I waſhed it with a decoction of Wormwood, Aloes, and a little *Ægyptiacum*, both to kill the Worms, and to fetch away all the putrid matter; I diſcuſſed the tumor with a diſſolving fomentation and cataplaſm, I joined together the lips of the Wound with the laſt deſcribed ſuture. But I applied this following Medicin to the whole part. ℞ *Terebinth. venetæ* ʒ vj. *gummi elemi* ʒ ij. *pulv. boli armeni, ſan. drac. Maſtiches, Myrrhæ, Aloes, an.* ʒ ß. *incorporentur ſimul, fiat medicamentum.* The wound was agglutinated within a few days, but that there remained a certain little hole at the joining of the lower Jaw with the upper, wherein you could ſcarce put the head of a pin; out whereof nevertheleſs much ſerous and thin moiſture flowed, eſpecially when he either eat or ſpake; which I have alſo obſerved in many others. But for ſtaying of this wateriſh humidity I dropped *Aqua fortis* into the bottom of the ulcer, and divers times put therein a little of the powder of burnt Vitriol. Thus by Gods grace he recovered and became whole.

A decoction good to waſh away putrefaction.

A ſmall hole remaining after the cure of great wounds.

CHAP. XXVI.

Of the Wounds of the Noſe.

How many ways the noſe may be hurt.

THe Noſe many ways ſuffers ſolution of continuity; as by a Wound, Fracture, and Contuſion, and it is ſometimes battered and broken on the upper part; which when it happens, you ſhall reſtore the depreſt bones to their native ſeat and figure, with the end of a *Spatula*, or fit ſtick wrapped about with Tow, Cotton, or a linnen rag. Then with pledgets dipped in an aſtringent Medicin compoſed *ex albumine ovi, Maſtich. bol. armen. ſanguin. drac. & alumine uſto*, and applied to the ſide of the Noſe, he ſhall labour to ſtrengthen the reſtored Bones, and then bind them with a convenient ligature, which may not preſs them too much, leſt the Noſe ſhould become flat, as it happens to many through the unskilfulneſs of Chirurgeons.

The cure of a broken Noſe.

The uſes of Pipes in broken Noſes.

Then muſt you put little Pipes into the Noſtrils, and theſe not exactly round, but ſomewhat flat and depreſt, tied to the night-cap on each ſide with a thred, leſt they ſhould fall out. By the help of theſe Pipes the Bones of the Noſe will be kept in their place, and there will be paſſage forth for the matter, and for inſpiration and exſpiration. But if all the Noſe, or ſome portion thereof ſhall be wholly cut off, we muſt not hope to reſtore it. But if the Noſe be ſo cut, that as yet it adheres to much of the adjacent fleſh, from whence it may receive life and

The Figure of Pipes to be put into the Noſtrils.



nou-

nouriſhment, then ſew it up. For the lower part of the Noſe, it may be ſhaken, depreſt and wreſted aſide, ſeeing it is griſly; but it cannot be broken, as the other which is of a bony Nature.

CHAP. XXVII.

Of the Wounds of the Tongue.

How many ways the continuity of the Tongue may be looſed.

THe Tongue may be ſo wounded, that either it may be wholly cut off and deprived of ſome portion of the ſubſtance, or onely ſlit long-ways, or athwart. The loſs of the ſubſtance cannot be repaired, becauſe every part ſeparated and pluckt from the living body, from whence it had life, ſpirit, and bloud, preſently dies. For, as Philoſophers ſay, *à privatione ad habitum non eſt regreſſus.* But when it is cut or ſlit long-ways or ſide-ways, it is eaſily reſtored by ſuture, if ſo be that the cloven part yet adhere to the living body from whence it may draw both matter and form of life. Therefore a careful ſervant ſhall ſtraitly hold with a ſoft and clean linnen cloth the body of the Tongue, leſt it ſhould ſlip away by reaſon of its ſlipperineſs, whileſt the Chirurgeon ſtitch it above and below; when he thinks he hath ſufficiently ſewed it, let him cut off the thred as near to the knot as he can, leſt being left too long it might be tangled with the teeth as he eats, and ſo cauſe a hurtful laceration or rending of the ſewed parts. In the mean time let the Patient eat Barley-Creams, Almond-Milks, Gellies, Culliſſes, and Broths, and the yolks of Eggs, and let him often hold in his mouth Sugar of Roſes and Syrup of Quinces; for ſuch things beſides their nouriſhing faculty, perform the part of an agglutinating and detergent Medicin. I have learned theſe things I have here ſet down, neither from my Maſters whom I have heard with attention, nor by reading of Books, but they have been ſuch as I have tried with happy ſucceſs in many; as in the ſon of Monſieur *de Marigny* Preſident of the Inquiſition, in *John Piet* a Carpenter dwelling in the Suburbs of Saint *German*.

The cure of a cloven tongue.

A Hiſtory.

But moſt apparently in a child of three years old, the ſon of the great Lawyer Monſieur *Covet*, who fell with his chin upon a ſtone, and ſo cut off a large piece of the end of his tongue, which chanced to be between his teeth; it hung but at a very ſmall fiber of fleſh, ſo that I had very little or no hope to agglutinate and unite it, which thing almoſt made me to pluck it quite away; yet I changed that determination by conſidering the loſs of the moſt noble action of ſpeaking, which would thereupon enſue, and weighing the providence of Nature often working wonders, and ſuch things as exceed the expectation of the Phyſician in curing Diſeaſes; I alſo thought thus with my ſelf, the fleſh of the Tongue is ſoft, looſe, fungous and ſpongy, neither is altogether ſpongy, neither is altogether obvious to the external injuries of the air; wherefore after that I had once or twice thruſt through the Needle and Thred upwards and downwards, and for the reſt ordered the Child to be uſed and dieted after the manner I lately mentioned, he grew well within a ſhort time, and yet remains ſo, ſpeaking well and diſtinctly.

Nature oft doth ſtrange things in the cure of Diſeaſes.

CHAP. XXVIII.

Of the Wounds of the Ears.

How many ways the unity of Ears may be violated.

THe Ears are ſometimes wholly cut off, ſometimes but in part, otherwhiles they are onely ſlit, ſo that the rent portion as yet adhering to the reſt, is joined with it in communion of life. In this laſt caſe it is fit to uſe a ſuture, but yet ſo that you touch not the Griſle with your Needle, for thence there would be danger of a Gangrene, which happens to many by fooliſh curing; therefore you ſhall take up and comprehend with your Needle onely the Skin, and that little fleſh which encompaſſes the Griſle. You ſhall perform the reſt of the cure with Pledgets and Ligatures artificially fitted, and ſhall reſiſt inflammation and other ſymptoms with fit Medicins. But you muſt take ſpecial care that no ſuperfluous fleſh grow in the auditory paſſage, which may hinder the hearing; wherefore you ſhall keep that paſſage free by ſtopping it with a piece of ſponge. But you ſhall procure agglutination and conſolidation of the griſly part (and therefore next to a bone moſt dry) with dry Medicins. But thoſe who have their Ears quite cut off, can do nothing but hide the deformity of their miſhap with a cap, ſtuffed with Cotton on that ſide.

How to ſew a wounded Ear.

CHAP. XXIX.

Of the Wounds of the Neck and Throat.

The differences of Wounds of the Neck and Throat.

THe Wounds of the Neck and Throat are ſomewhiles ſimple, as thoſe which onely uſe the continuity of the Muſcles; otherwhiles compound, ſuch as thoſe which have conjoined with them a fracture of the Bones, as of the *Vertebræ*, or hurt of the internal and external jugular Veins or ſleepy Arteries; ſometimes the *Trachea Arteria*, or Weazon, and the *Oeſophagus* or Gullet are wounded; ſometimes wholly cut off, whence preſent death enſues. Wherefore let not the Chirurgeon meddle with ſuch Wounds, unleſs he firſt foretel the danger of death, or the loſs of ſome motion to thoſe that are preſent. For it often happens that ſome notable nerve or tendon is violated by a wound in the neck, whence a Palſie enſues, and that abſolutely incurable, if the wound ſhall penetrate to the ſpinal marrow, alſo hurt therewith. Wounds of the Gullet and Weazon are difficultly cured, becauſe they are in perpetual motion; and chiefly of the latter, by reaſon it is griſly and without bloud. The wounds of the Gullet are known, by ſpitting of bloud,

The Palſie follows upon Wounds of the Neck.

Signs that the Gullet is wounded.

by the breaking forth of meat and drink by the wound; but if the Gullet be quite cut asunder, the Patient cannot swallow at all: for the cut parts are both contracted in themselves, the one upwards and the other downwards. But we know the Weazon is hurt by casting up bloud at the mouth with a continual cough, and by the coming forth of the breath or wind by the wound. The Wounds of the jugular Veins and sleepy Arteries, if they be great are usually deadly, because they cannot be straitly bound up, for you cannot bind the throat hard without danger of choaking or strangling the Patient. But for defect of a strait ligature in this case the flux of bloud proves deadly. If the recurrent Nerve of either side be cut, it makes the voice hoarse; if cut on both sides, it takes away the use of speech, by hurting those instruments which impart motion to the Muscles of the *Larinx*. For the cure, if the Wound be small, and not associated with the hurt of any notable vessel, nor of the Weazon and Gullet, it is speedily and easily cured; and if there shall be need, you shall use a suture, then you shall put therein a sufficient quantity of Venice Turpentine mixed with Bole-Armenick, or else some of my Balsam, of which this the Receipt. ℞ *Terebinth. venetæ* ℔ß *ff. gum. elemi* ℥ iv. *olei hypericonis* ℥ iij. *boli armen. & sang. draconis an.* ℥ j. *aqua vitæ* ℥ ij. *liquefiant simul omnia lento igne, & fiat Balsamum ut artis est, addendo pulveris ireos florent. aloes, masticbes, myrrhæ an.* ʒ j. I have done wonders with this Balsom in the agglutination of simple Wounds, wherein no strange body hath been. Now when you have put it in, lay upon it a plaister of *Diacalcitheos* dissolved in Oil of Roses and Vinegar, as that which hath power to repress the flowing down of humours, and hinder inflammation, or in stead thereof you may apply *Emp. de Gratia Dei*, or *Emp. de Janua*. But if the Jugular Veins and sleepy Arteries be cut, let the bleeding be staid, as we have shewed in a Chapter treating thereof. When the Weazon or Gullet are wounded, the Chirurgeon shall sew them up as neatly as he can; and the Patient shall not endeavour to swallow any hard thing, but be content to be fed with Gellies and Broths. When a Gargarism is needful, this following is very good. ℞ *Hordei M.* j. *florum rosar. p.* j. *passul. mund. jujubarum an.* ℥ ß. *glycyrrhizæ* ℥ j. *bulliant omnia simul, addendo mellis ros. & Julep. ros. an.* ℥ ij. *fiat Gargarisma, ut artis est.*

The faculty of *Diacalcitheos*.

The cure of the wounded Weazon and Gullet.

A Gargarism.

The manifold use thereof

With which being warm, the Patient shall moisten his mouth and throat, for it will mitigate the harshness of the part, asswage pain, cleanse and agglutinate, and make him breathe more freely. But that the Chirurgeon may not despair of, or leave any thing unattempted in such like wounds, I have thought good to demonstrate by some examples how wonderful the Works of Nature are, if they be assisted by Art.

A History.

A certain servant of Monsieur *de Champaigne* a Gentleman of *Anjou*, was wounded in the throat with a Sword, whereby one of the Jugular Veins was cut, together with his Weazon. He bled much and could not speak; and these symptoms remained until such time as the Wound was sewed up and covered with Medicins. But if Medicins at any time were more liquid, he, as it were, sucked them by the wound and spaces between the stitches, and presently put forth at his mouth that which he had sucked or drawn in. Wherefore more exactly considering with my self, the greatness of the Wound, the Spermatick, and therefore dry and bloudless nature unapt to agglutination of the affected part, but chiefly of the Weazon and Jugular Vein; as also for that the rough Artery is obnoxious to those motions which the Gullet performs in swallowing, by reason of the inner coat, which is continued to the coat of the Gullet, by which means these parts mutually serve each other with a reciprocal motion, even as the ropes which run to the wheel of a pulley; furthermore, weighing that the Artery was necessary for the breathing, and tempering the heat of the heart, as the Jugular Veins served for the nourishment of the upper parts; and lastly, weighing with my self the great quantity of bloud he had lost, which is, as it were, the Treasure of Nature, I told those which were present, that death was near and certainly at hand. And yet beyond expectation, rather by Divine Favour than our Art, he recovered his health.

A strange History.

Equally admirable is this History following. Two Englishmen walked out of the City of *Paris* for their Recreation to the Wood of *Vincenne*, but one of them lying in wait to rob the other of his money, and a massy chain of Gold which he wore, set upon him at unawares, cut his throat and robbed him, and so left him amongst the Vines which were in the way supposing he had killed him, having with his Dagger cut the Weazon and Gullet. This Murderer came back to the City; the other half dead, crawled with much ado to a certain Peasants house, and being dressed with such Medicins as were present, and at hand, he was brought to the City, and by his acquaintance committed to my care to be cured. I at the first, as diligently as I could, sewed up the Weazon which was quite cut asunder, and put the lips of the Wound as close together as I could; I could not get hold of the Gullet, because it was fallen down into the Stomach, then I bound up the Wound with Medicins, Pledgets, and fit Ligatures. After he was thus dressed, he begun to speak, and tell the name of the Villain the author of this fact, so that he was taken and fastned to the Wheel, and having his limbs broken, lost his wretched life, for the life of the innocent wounded man, who died the fourth day after he was hurt.

Another History.

The like hurt befel a certain German who lay at the house of one *Perots*, in the street of *Nuts*, he being frantick in the night cut his throat with a Sword; I being called in the Morning by his friends who went to see him, dressed him just after the same manner as I dressed the English man. Wherefore he presently recovered his speech, which before could not utter one syllable, freed from suspicion of the crime and prison the servant, who lying in the same Chamber with him, wrs upon suspicion committed to Prison, and confessing the thing as it was done, lived four days after the Wound, being nourished with Broths put into his Fundament like Clysters, and with the grateful vapour of comfortable things, as Bread newly drawn out of the Oven and soaked in strong Wine; I having thus by Art of Chirurgery made the dumb speak for the space of four days.

CHAP.

CHAP. XXX.

Of the Wounds of the Cheſt.

SOme Wounds of the Cheſt are on the fore-ſide, ſome behind, ſome penetrate more deep, others enter not into the capacity thereof, otherſome pierce even to the parts contained therein, as the *Mediaſtinum*, Lungs, Heart, Midriff, hollow Vein, and aſcendent Artery. Otherſome paſs quite through the body, whereby it happens that ſome are deadly, ſome not. The differences of wounds of the Cheſt.

You ſhall thus know that the wound penetrates into the capacity of the Cheſt, if that, when the Patients mouth and noſe be ſhut, the breath or wind break through the wound with a noiſe, ſo that it may diſſipate, or blow out a lighted Candle being held near it. If the Patient can ſcarce either draw, or put forth his breath, this alſo is a ſign that there is ſome bloud fallen down upon the *Diaphragma*. The ſigns.

By theſe ſigns you may know that the heart is wounded: If a great quantity of bloud guſh out, if a trembling poſſeſs all the members of the body, if the pulſe be little and faint, if the colour become pale, if a cold ſweat and frequent ſwooning aſſail him, and the extreme parts become cold, then death is at hand. Signs that the heart is wounded.

Yet when I was at *Turin*, I ſaw a certain Gentleman, who fighting a Duel with another, received a wound under his left breſt which pierced into the ſubſtance of his heart, yet for all that he ſtruck ſome blows afterward, and followed his flying enemy ſome two hundred paces until he fell down dead upon the ground; having opened his body I found a wound in the ſubſtance of the heart, ſo large as would contain ones finger; there was onely much bloud poured forth upon the Midriff. A Hiſtory.

Theſe are the ſigns that the Lungs are wounded, if the bloud comes foamy or frothy out of the wounds, the Patient is troubled with a cough, he is alſo troubled with a great difficulty of breathing and a pain in his ſide, which he formerly had not; he lies moſt at eaſe when he lies upon the wound, and ſometimes it comes ſo to paſs, that lying ſo, he ſpeaks more freely and eaſily, but turned on the contrary ſide, he preſently cannot ſpeak. Signs that the Lungs are wounded.

When the *Diaphragma* or Midriff is wounded, the party affected is troubled with a weight or heavineſs in that place, he is taken with a *Delirium*, or Raving, by reaſon of the ſympathy of the Nerves of the ſixth conjugation which are ſpread over the Midriff; difficulty of breathing, a cough and ſharp pain troubles the Patient, the Guts are drawn upwards; ſo that it ſometimes happens by the vehemency of breathing, that the Stomach and Guts are drawn through the wound into the capacity of the Cheſt, which thing I obſerved in two. Signs that the Midriff is wounded.

The one of theſe was a Maſon, who was thruſt through the midſt of the Midriff, where it is nervous, and died the third day following. I opening his lower belly, and not finding his ſtomach, thought it a monſtrous thing; but at length ſearching diligently, I found it was drawn into the Cheſt through the wound which was ſcarce an inch broad. But the ſtomach was full of wind, but little humidity in it. A Hiſtory.

The other was called Captain *Francis d' Alon* a Native of *Xantoign*, who before *Rochel* was ſhot with a Musket Bullet, entring by the breſt bone near to the ſword-like Griſle, and paſſing through the fleſhy part of the Midriff, went out at the ſpace between the fifth and ſixth baſtard ribs. The wound was healed up on the outſide, yet for all that there remained a weakneſs of the Stomach, whereupon a pain of the Guts like to the Colick took him, eſpecially in the Evening, and on the Night, for which cauſe he durſt not ſup but very ſparingly. But on the eighth moneth after, the pain raging more violently in his belly than it was accuſtomed, he died; though for the mitigating thereof *Simon Malmedy* and *Anthony du Val*, both learned Phyſitians, omitted no kind of remedy. The body of the deceaſed was opened by the skilful Chirurgeon *James Guillemeau*, who found a great portion of the Colick-gut ſwelled with much wind gotten into the Cheſt through the wound of the *Diaphragma*, for all it was ſo ſmall that you could ſcarce put your little finger in thereat. But now let us return from whence we digreſſed. Another Hiſtory.

We underſtand that there is bloud poured forth into the capacity of the Cheſt by the difficulty of breathing, the vehemency of the increaſing Fever, the ſtinking of the breath, the caſting up of bloud at the mouth, and other ſymptoms which uſually happen to thoſe who have putrified and clotted bloud poured out of the Veſſels into the Belly, infecting with the filthy vapour of the corrupt ſubſtance, the parts to which it ſhall come. But alſo, unleſs the Patient cannot lie upon his back, he is troubled with a deſire to vomit, and covets now and then to riſe, whence he often falls into a ſwound; the vital faculty which ſuſtains the body being broken and debilitated both by reaſon of the wound, and concrete or clotted bloud; for ſo putting on the quality of poiſon, it greatly diſſipates and diſſolves the ſtrength of the heart. Signs that there is bloud poured into the capacity of the Cheſt.

It is a ſign the ſpinal marrow is hurt, when a Convulſion or Palſie, that is, a ſudden loſs of ſenſe and motion in the parts thereunder, an unvoluntary excretion of the Urine and other excrements, or a total ſuppreſſion of them, ſeizes upon the Patient. When the hollow Vein and great Artery are wounded, the Patient will die in a ſhort time, by reaſon of the ſudden and abundant effuſion of the bloud and ſpirits, which intercepts the motion of the Lungs and Heart, whence the party dies ſuffocated. Signs that the Spine is wounded.

CHAP. XXXI.

Of the Cure of the Wounds of the Cheſt.

WE have read in *John de Vigo*, that it is diſputed amongſt Chirurgeons concerning the conſolidation of wounds of the Cheſt. For ſome think that ſuch wounds muſt be cloſed up, and cicatrized with all poſſible ſpeed, leſt the cold air come to the heart, and the vital ſpirits fly away and be diſſipated. Others on the contrary think that ſuch Wounds ought to be long kept open; *Vigo, tract. de Vulnerib. thorac. cap.* 10.

open; and alſo if they be not ſufficiently large of themſelves that then they muſt be enlarged by Chirurgery, that ſo the bloud poured forth into the capacity of the Cheſt may have paſſage forth, which otherwiſe by delay would putrefie, whence would enſue an increaſe of the Fever, a fiſtulous Ulcer, and other pernicious accidents. The firſt opinion is grounded upon Reaſon and Truth, if ſo be that there is little or no bloud poured forth into the capacity of the Cheſt. But the latter takes place where there is much more bloud contained in the empty ſpaces of the Cheſt. Which leſt I may ſeem raſhly to determin, I think it not amiſs to ratifie each opinion with a Hiſtory thereto agreeable.

A Hiſtory.

Whileſt I was at *Turin*, Chirurgeon to the Marſhal of *Montejan*, the King of *France* his General, I had in cure a Souldier of *Paris*, whoſe name was *Leveſque*, he ſerved under Captain *Renovart*. He had three wounds, but one more grievous than the reſt, went under the right breſt, ſomewhat deep into the capacity of the Cheſt, whence much bloud was poured forth upon the Midriff, which cauſed ſuch difficulty of breathing, that it even took away the liberty of his ſpeech; beſides through this occaſion he had a vehement Fever, coughed up bloud, and a ſharp pain on the wounded ſide. The Chirurgeon which firſt dreſſed him, had ſo bound up the wound with a ſtrait and thick ſuture, that nothing could flow out thereat. But I being called the day after, and weighing the preſent ſymptoms which threatned ſpeedy death, judged that the ſowing of the Wound muſt ſtraight be looſed, which being done, there inſtantly appeared a clot of bloud at the orifice thereof, which made me to cauſe the Patient to lie half out of his bed, with his head downwards, and to ſtay his hands on a Settle which was lower than the Bed, and keeping himſelf in this poſture, to ſhut his mouth and noſe that ſo his Lungs ſhould ſwell, the Midriff be ſtretched forth, and the intercoſtal Muſcles and thoſe of the *Abdomen* ſhould be compreſſed, that the bloud poured into the Cheſt might be evacuated by the wound; but alſo that this excretion might ſucceed more happily, I thruſt my finger ſomewhat deep into the Wound, that ſo I might open the orifice thereof being ſtopped up with the congealed bloud; and certainly I drew out ſome ſeven or eight ounces of putrefied and ſtinking bloud by this means. When he was laid in his Bed, I cauſed frequent injections to be made into the Wound of a decoction of Barley, with Honey of Roſes and red Sugar; which being injected, I wiſht him to turn firſt on the one, and then on the other, and then again to lie out of his bed as before: for thus he evacuated ſmall, but very many clots of blood, together with the liquor lately injected; which being done, the ſymptoms were mitigated, and left him by little and little. The next day I made another more detergent injection, adding thereto Wormwood, Centaury, and Aloes; but ſuch a bitterneſs did riſe up to his mouth, together with a deſire to caſt, that he could no longer endure it. Then it came into my mind that formerly I had obſerved the like effect of the like remedy in the Hoſpital of *Paris*, in one who had a fiſtulous ulcer in his Cheſt. Therefore when I had conſidered with my ſelf that ſuch bitter things may eaſily paſs into the Lungs, and ſo may from thence riſe into the Weazon and Mouth, I determined that thenceforwards I would never uſe ſuch bitter things to my Patients, for the uſe of them is much more troubleſome than any way good and advantagious. But at the length this Patient by this and the like means recovered his health beyond my expectation.

Why bitter things muſt not be caſt into the Cheſt.

Read the Hiſtory of *Maryllus* in *Galen*, *lib. 7. de Anatom. adminiſtra.*

But on the contrary, I was called on a time to a certain *German* Gentleman who was run with a Sword into the capacity of his Cheſt; the neighbouring Chirurgeon had put a great tent into the Wound at the firſt dreſſing, which I made to be taken forth, for that I certainly underſtood there was no bloud poured forth into the capacity of the Cheſt becauſe the Patient had no Fever, no weight upon the *Diaphragma*, nor ſpitted forth any bloud. Wherefore I cured him in few days by onely dropping in ſome of my balſom and laying a Plaiſter of *Diacalcitheos* upon the Wound. The like Cure I have happily performed in many others. To conclude, this I dare boldly affirm, that Wounds of the Cheſt by the too long uſe of tents degenerate into Fiſtulaes. Wherefore if you at any time ſhall undertake the cure of Wounds which penetrate into the capacity of the Cheſt, you ſhall not preſently ſhut them up at the firſt dreſſing, but keep them open for two or three days, but when you ſhall find that the Patient is troubled with none or very little pain, and that the Midriff is preſſed down with no weight, and that he breathes freely, then let the tent be taken forth, and the Wound healed up as ſpeedily as you can by covering it onely with lint dipped in ſome balſom which hath a glutinative faculty, and laid ſomewhat broader then the Wound; never apply liniments to Wounds of this kind, leſt the Patient by breathing draw them into the capacity of the Cheſt. Wherefore alſo you muſt have a care that the tent put into thoſe kinds of Wounds may be faſtned to the Pledgets, and alſo have ſomewhat a large head, leſt they ſhould be drawn (as we ſaid) into the capacity of the Cheſt; for if they fall in, they will cauſe putrefaction and death. Let *Emplaſt. Diacalcitheos*, or ſome ſuch like, be applied to the Wound. But if on the contrary, you know by proper and certain ſigns, that there is much bloud fallen into the ſpaces of the Cheſt, then let the orifice of the Wound be kept open with larger tents, until all the *ſanies* or bloudy matter, whereinto the bloud hath degenerated, ſhall be exhauſted. But if it happen at any time, as aſſuredly it ſometimes doth, that notwithſtanding the art and care of the Phyſician, the Wound degenerates into a *Fiſtula*, then the former evil is become much worſe. For *Fiſtulaes* of the Cheſt are ſcarce cured at any time, and that for divers cauſes. The firſt is, for that the muſcles of the Cheſt are in perpetual motion. Another is, becauſe they on the contrary inſide are covered onely with the membrane inveſting the ribs, which is without bloud. The third is, for that the Wound hath no ſtay, by means whereof it may be compreſſed, ſewed, and bound, whereby the lips being joined together, the Wound may at length be repleniſhed with fleſh and cicatrized.

What harm enſues the too long uſe of Tents.

No liniments muſt be uſed in wounds of the Cheſt.

Wounds of the Cheſt eaſily degenerate into a *Fiſtula*.

Why there flows ſuch plenty of matter out of wounds of the Cheſt.

But the reaſon why Wounds of the Cheſt do every day heap up and pour forth ſo great a quantity of matter, ſeems to be their vicinity to the heart, which being the fountain of bloud, there is a perpetual efflux thereof from thence to the part affected. For this is Natures care in preſerving the affected parts, that continually and abundantly without meaſure or mean it ſends all its ſupplies, that is, bloud and ſpirits to their aid. Add hereto that the affected parts by pain, heat, and continual motion of the Lungs and Midriff, draw and allure much bloud to themſelves. Such like

bloud

bloud defiled by the malignity and filth of the wound, is ſpeedily corrupted: whence it is that from the perpetual afflux of bloud, there is a continual efflux of matter or filth, which at the laſt brings a man to a conſumption; becauſe the ulcerated part like a ravenous Wolf conſumes more bloud by the pain, heat, and motion than can be miniſtred thereto by the heart. Yet if there be any hope to cure and heal the *Fiſtula*, it ſhall be performed (after the uſe of diet and phlebotomy, according to the preſcript of the Phyſician) by a vulnerary potion, which you ſhall find deſcribed when we treat of the *Caries* or rottenneſs of the bones. Wherefore you ſhall make frequent injections therewith into the *Fiſtula*, adding and mixing with it *Syrup. de roſis ſiccis* and *mel roſarum*. Neither do I, if the putrefaction be great, fear to mix therewith *Ægyptiacum*. But you muſt have a care to remember and obſerve the quantity of the injected liquor, that you may know whether it all come forth again after it hath performed its detergent office. For if any thereof remain behind in the corners and crooked paſſages, it hurts the part, as corrupted with the contagion thereof.

The cure of a *Fiſtula* in the Cheſt. When *Ægyptiacum* muſt be put into the injections.

The form of a Syringe fit to make injection, when a great quantity of liquor is to be injected into any part.



After the injected liquor is come forth, a Pipe of Gold, Silver, or Lead, ſhall be put into the fiſtulous ulcer, and it muſt have many holes in it, that ſo the filth may paſs forth at them; it muſt be faſt tied with ſtrings, that it may not fall into the capacity of the Cheſt. A great Sponge ſteeped in *Aqua Vitæ* and wrung forth again, ſhall be laid hot to the end or orifice thereof, both to hinder the entrance of the Air into the fiſtulous ulcer, as alſo to draw forth the filth there by its gentle heat; the which thing the Patient ſhall much further, if often-times both day and night he hold his breath, ſtopping his mouth and noſe, and lying upon the diſeaſed ſide, that ſo the *Sanies* may be the more forcibly evacuated; neither muſt we leave the putting in the pipe, before that this fiſtulous ulcer ſhall be almoſt dry, that is, whole; as when it yields little, or no matter at all, then it muſt be cicatrized. But if the orifice of this fiſtulous ulcer being in the upper part hinder the healing thereof, then by a chirurgical Section, a paſſage ſhall be made in the bottom, as we ſaid before in an *Empyema*.

The delineation of the Pipes with their Strings and Sponges.



The Reader muſt note that the Pipes which are fit for this uſe, need not have ſo many holes as theſe here expreſt; but onely two or three in their ends: for the fleſh growing and getting into the reſt, makes them that they cannot be plucked forth without much pain.

A Wound made in the Lungs admits cure, unleſs it be very large, if it be without inflammation; if it be on the skirts of the Lungs, and not on their upper parts; if the Patient contain himſelf from coughing much, and contentious ſpeaking, and great breathing: for the wound is enlarged by coughing, and thence alſo ariſes inflammation; the *Pus* and *Sanies* whereof, whilſt the lungs again endeavour to expel by coughing, by which means they are onely able to expel that which is hurtful and troubleſom to them, the ulcer is dilated, the inflammation augmented, the Patient waſtes away, and the Diſeaſe becomes inourable.

What wounds of the Lungs are curable.

The harm that enſues upon coughing, in Wounds of the Lungs.

There have been many *Eclegmaes* deſcribed by Phyſicians for to cleanſe the ulcer; which when the Patient uſeth, he ſhall lie on his back to keep them long in his mouth, ſo to relax the muſcles of the *Larinx*; for thus the Medicin will fall by little and little alongſt the coats of the Weazon, for if it ſhould fall down in great quantity, it would be in danger to cauſe coughing. Cows, Aſſes, or Goats-milk with a little Honey, leſt they ſhould corrupt in the ſtomach, are very fit remedies for this purpoſe; but Womans milk exceeds the reſt.

How *Eclegmata* muſt be ſwallowed.

But Sugar of Roſes is to be preferred before all other Medicins, in the opinion of *Avicen*, for that it hath a detergent, and alſo an aſtrictive and ſtrengthening faculty, than which nothing is more to be deſired in curing of Ulcers. When you ſhall think it time to agglutinate the cleanſed ulcer, you muſt command the Patient to uſe emplaſtick, auſtere, and aſtringent Medicins, ſuch as are *Terra ſigillata*, *bolus armenus*, *hypocyſtis*, *Plantain*, *Knot-graſs*, *Sumach*, *Acacia*, and the like, which the Patient ſhall uſe in his Broths and *Eclegmaes*, mixing therewith Honey of Roſes, which ſerving for a vehicle to the reſt, may carry away the impacted filth which hinders agglutination. But ſeeing an hective Fever eaſily follows upon theſe kinds of Wounds, and alſo upon the affects of the Cheſt and Lungs, it will not be amiſs to ſet down ſomewhat concerning the Cure thereof, that ſo the Chirurgeon may know to adminiſter ſome help to his Patient, whileſt a Phyſician is ſent for, to overcome this diſeaſe with more powerful and certain remedies.

The utility of Sugar of Roſes in ulcerated or wounded Lungs.

CHAP.

CHAP. XXXII.

Of the differences, cauſes, ſigns, and cure of an Hective Fever.

The reaſon of the name.

A Hective Fever is ſo called, either for that it is ſtubborn and hard to cure and looſe, as things which have contracted a habit, for *Hexis* in Greek ſignifies a habit; or elſe for that it ſeiſes upon the ſolid parts of our bodies called by the Greeks *Hexeis*; both which the Latin word *Habitus* doth ſignifie.

The differences thereof.

There are three kinds, or rather degrees of this Fever. The firſt is when the hectick heat conſumes the humidity of the ſolid parts. The ſecond is, when it feeds upon the fleſhy ſubſtance. The third and uncurable is, when it deſtroys the ſolid parts themſelves. For thus the flame of a Lamp firſt waſtes the Oil, then the proper moiſture of the Wiek. Which being done, there is no hope of lighting it again, what ſtore of Oil ſoever you pour upon it. This Fever very ſeldom breeds of it ſelf, but commonly follows after ſome other.

The Cauſes.

Wherefore the cauſes of a Hective Fever, are ſharp and burning Fevers not well cured, eſpecially if their heat were not repreſſed with cooling Epithems applied to the heart and *Hypochondria*. If cold Water was not fitly drunk. It may alſo ſucceed a Diary Fever which hath been cauſed and begun by ſome long great and vehement grief or anger, or ſome too violent labour, which any of a ſlender and dry body hath performed in the hot Sun. It is alſo oft-times cauſed by an ulcer or inflammation of the Lungs, an *Empyema* of the Cheſt, by any great and long continuing *Phlegmon* of the Liver, Stomach, Meſentery, Womb, Kidneys, Bladder, of the Guts *Jejunum* and *Colon*, and alſo of the other Guts, if the *Phlegmon* ſucceed ſome long *Diarrhœa*, *Lienteria*, or Bloudy-flux, whence a Conſumption of the whole body, and at laſt a Hectick Fever, the heat becoming more acrid, the moiſture of the body being conſumed.

The Signs.

This kind of Fever, as it is moſt eaſily to be known, ſo is it moſt difficult to cure; the pulſe in this Fever is hard, by reaſon of the drineſs of the Artery which is a ſolid part; and it is weak by reaſon of the debility of the vital faculty, the ſubſtance of the heart being aſſaulted. But it is little and frequent becauſe of the diſtemper and heat of the heart, which for that it cannot by reaſon of its weakneſs cauſe a great pulſe to cool it ſelf, it labours by the oftenneſs to ſupply that defect.

Why in hecticks the heat is more acrid after meat.

But for the pulſe, it is a proper ſign of this Fever, that one or two hours after meat the pulſe feels ſtronger than uſual; and then alſo there is a more acrid heat over all the Patients body. The heat of this flame laſts until the nouriſhment be diſtributed over all the Patients body; in which time the drineſs of the heart in ſome ſort tempered and recreated by the appulſe of moiſt nouriſhment, the heat increaſes no otherwiſe than Lime which a little before ſeemed cold to the touch, but ſprinkled and moiſtned with water grows ſo hot, as it ſmoaks and boils up. At other times there is a perpetual equality of heat and pulſe in ſmalneſs, faintneſs, obſcurity, frequency, and hardneſs, without any exacerbation, ſo that the Patient cannot think himſelf to have a Fever, yea, he cannot complain of any thing, he feels no pain, which is another proper ſign of an hectick Fever. The cauſe that the heat doth not ſhew it ſelf is, it doth not poſſeſs the ſurface of the body, that is, the ſpirits and humours, but lies as buried in the earthy groſsneſs of the ſolid parts. Yet if you hold your hand ſomewhat long, you ſhall at laſt perceive the heat more acrid and biting, the way being opened thereto by the skin, rarified by the gentle touch of the warm and temperate hand. Wherefore if at any time in theſe kind of Fevers the Patient feel any pain, and perceive himſelf troubled with an inequality and exceſs of heat, it is a ſign that the hectick Fever is not ſimple, but conjoined with a putrid Fever, which cauſeth ſuch inequality, as the heat doth more or leſs ſeize upon matter ſubject to putrefaction; for a hectick Fever of it ſelf is void of all equality, unleſs it proceed from ſome external cauſe, as from meat. Certainly if an Hippocratick face may be found in any diſeaſe, it may in this, by reaſon of the colliquation or waſting away the triple ſubſtance. In the cure of this Diſeaſe, you muſt diligently obſerve with what affects it is entangled, and whence it was cauſed. Wherefore firſt you muſt know whether this Fever be a Diſeaſe, or elſe a Symptom. For if it be ſymptomatical, it cannot be cured as long as the Diſeaſe, the cauſe thereof, remains uncured; as if an ulcer of the Guts occaſioned by a Bloudy-flix ſhall have cauſed it, or elſe a fiſtulous ulcer in the Cheſt, cauſed by ſome wound received on that part, it will never admit of cure, unleſs firſt the fiſtulous or dyſenterick ulcer ſhall be cured; becauſe the Diſeaſe feeds the Symptoms, as the Cauſe the Effect. But if it be a ſimple and eſſential hectick Fever, for that it hath its eſſence conſiſting in an hot and dry diſtemper, which is not fixed in the humours, but in the ſolid parts, all the counſel of the Phyſician muſt be to renew the body, but not to purge it; for onely the humours require purging, and not the defaults of the ſolid parts. Therefore the ſolid parts muſt be refrigerated and humected, which we may do by Medicins taken inwardly and applied outwardly.

The ſigns of a hectick joined with a putrid Fever.

The Cure.

A ſymptomatical hectick.

An eſſential hectick.

Things to be taken inwardly.

The things which may with good ſucceſs be taken inwardly into the body for this purpoſe, are Medicinal nouriſhments. For hence we ſhall find more certain and manifeſt good, than from altering Medicins, that is, wholly refrigerating and humecting without any manner of nouriſhment.

The benefit of Medicinal nouriſhments.

For by reaſon of that portion fit for nutriment which is therewith mixed, they are drawn and carried more powerfully to the parts, and alſo converted into their ſubſtance: whereby it comes to paſs that they do not humect and cool them lightly and ſuperficially, like the Medicins which have onely power to alter and change the body, but they carry their qualities more throughly even into the innermoſt ſubſtance. Of theſe things ſome are Herbs, as Violets, Purſlain, Bugloſs, Endive, Ducks-meat, or Water-lentil, Mallows, eſpecially when the belly ſhall be bound. Some are Fruits, as Gourds, Cucumers, Apples, Prunes, Raiſins, Sweet Almonds, and freſh or new Pine-Apple kernels; in the number of Seeds are the four greater and leſſer cold Seeds, and theſe new, for their native humidity, the Seeds of Poppies, Berberies, Quinces. The Flowers of Bugloſs, Violets, Water-lillies, are alſo convenient; of all theſe things let Broth be made with a Chicken, to be taken in the morning for eight or nine days, after the firſt Concoction.

For

For Meats; in the beginning of the Diſeaſe, when the faculties are not too much debilitated, he ſhall uſe ſuch as nouriſh much and long, though of hard digeſtion; ſuch as the extreme parts of Beaſts, as the feet of Calves, Hogs-feet not ſalted, the fleſh of a Tortois which hath lived ſo long in a Garden, as may ſuffice to digeſt the excrementitious humidity; the fleſh of white Snails, and ſuch as have been gathered in a Vineyard, of Frogs, River-Crabs, Eels taken in clear Water, and well cooked, hard Eggs eaten with the juice of Sorrel without Spices, Whitings and Stock-fiſh. For all ſuch things, becauſe they have a tough and glutinous juice, are eaſily put and glutinated to the parts of our body, neither are they ſo eaſily diſſipated by the Feveriſh heat. But when the Patient languiſheth of a long hectick, he muſt feed upon meats of eaſie digeſtion, and theſe boiled rather then roaſted; for boiled meats humect more, and roaſted more eaſily turn into choler. Wherefore he may uſe to eat Veal, Kid, Capon, Pullet, boiled with refrigerating and humecting herbs; he may alſo uſe Barly-creams, Almond-milks, as alſo Bread crummed and moiſtned with Roſe-water, and boiled in a decoction of the four cold Seeds with Sugar of Roſes; for ſuch a Panada cools the Liver, and the habit of the whole body, and nouriſheth withall. The Teſticles, Wings, and Livers of young Cocks, as alſo Figs and Raiſins. But if the Patient at length begin to loath and grow weary of boiled meats, then let him uſe roaſt, but ſo that he cut away the burnt and dried part thereof, and feed onely on the inner part thereof, and that moiſtned in Roſe-water, the juice of Citrons, Oranges, or Pomegranates. Let him abſtain from Salt and dry Fiſhes, and chuſe ſuch Fiſhes as live in ſtony Waters, for the exerciſe they are forced to undergo in ſhunning the Rocks beaten upon by the Waves. Aſſes milk newly milked and ſeaſoned with a little Salt, Sugar, Honey or Fennel, that it may not corrupt nor grow ſowre in the ſtomach; or Womans milk ſucked from the Dug by the Patient, to the quantity of half a pint, is much commended; verily Womans milk is the more wholſom, as that which is more ſweet and familiar to our ſubſtance, if ſo be that the Nurſe be of a good temper and habit of body. For ſo it is very good againſt the gnawings of the Stomach, and ulcers of the Lungs, from whence a Conſumption oft proceeds. Let your Milch Aſs be fed with Barly, Oats, Oak-leaves; but if the Patient chance to be troubled with the Flux of the Belly, you ſhall make the milk ſomewhat aſtringent by gently boiling it, and quenching therein Pebble-ſtones heated red hot. But for that all Natures cannot away with Aſſes milk, ſuch ſhall abſtain from it, as it makes to have acrid belchings, difficulty of breathing, a heat and rumbling in the *Hypochondria* and pain of the Head. Let the Patient temper his Wine with a little of the Waters of Lettuce, Purſlain, and Water-Lillies, but with much Bugloſs-Water, both for that it moiſtens very much, as alſo for that it hath a ſpecifick power to recreate the Heart, whoſe ſolid ſubſtance in this kind of Diſeaſe is grievouſly afflicted. And thus much of things to be taken inwardly.

The choice of meats.

How Aſſes milk muſt be uſed in a hectick.

Womans milk more wholeſom than Aſſes.

Theſe things which are to be outwardly applied, are inunctuous Baths, Epithems, Clyſters. Inunctions are divers, according to the various Indications of the parts whereto they are applied. For *Galen* anoints all the ſpine with cooling and moderate aſtringent things, as which may ſuffice to ſtrengthen the parts and hinder their waſting, and not let the tranſpiration; for if it ſhould be letted, the heat would become more acrid by ſuppreſſing the vapours. Oil of Roſes, Water-Lillies, Quinces, the mucilages of Gum-tragacanth and Arabick extracted into Water of Night-ſhade, with ſome ſmall quantity of Camphire, and a little Wax if need require: but on the contrary, the parts of the Breſt muſt be anointed with refrigerating and relaxing things; by refrigerating, I mean things which moderately cool, for cold is hurtful to the Breſt. But aſtringent things would hinder the motions of the Muſcles of the Cheſt, and cauſe a difficulty of breathing. Such inunctions may be made of Oil of Violets, Willows, of the Seeds of Lettuce, Poppies, Water-Lillies, mixing with them the Oil of Sweet Almonds to temper the aſtriction which they may have by their coldneſs. But you muſt have great care that the Apothecary for covetouſneſs in ſtead of theſe Oils newly made give you not old, rancid and ſalted Oils, for ſo in ſtead of refrigerating, you ſhall heat the part; Wine, Honey, and Oil, acquire more heat by Age; in defect of convenient Oils, we may uſe Butter well waſhed in Violet and Night-ſhade Water. The uſe of ſuch inunctions, is to cool, humect, and comfort the parts whereto they are uſed; they muſt be uſed Evening and Morning, chiefly after a Bath.

Things to be outwardly applied.

A caution in the choice of Oils.

Now for Baths, we preſcribe them either only to moiſten, and then plain warm Water wherein the Flowers of Violets and Water-lillies, Willow-leaves and Barly have been boiled, will be ſufficient; or elſe not onely to moiſten, but alſo to acquire them a fairer and fuller habit, and then you may add to your Bath the decoction of a Sheeps-head and Gather, with ſome Butter. But the Patient ſhall not enter into the Bath faſting, but after the firſt concoction of the Stomach, that ſo the nouriſhment may be drawn by the warmneſs of the Bath into the whole habit of the Body. For otherwiſe he which is ſick of a Conſumption, and ſhall enter the Bath with his Stomach empty, ſhall ſuffer a greater diſſipation of the triple ſubſtance, by the heat of the Bath, than his ſtrength is well able to endure. Wherefore it is fit thus to prepare the body before you put it into the Bath. The day before in the morning let him take an emollient Clyſter, to evacuate the excrements baked in the guts by the hectick dineſs; then let him eat to his dinner ſome ſolid meats about nine of the Clock, and let him about four of the Clock eat ſomewhat ſparingly, meats of eaſie digeſtion to his ſupper. A little after midnight let him ſup off ſome Chicken-broth, or Barly-cream, or elſe two rear Eggs tempered with ſome Roſe-water and Sugar of Roſes in ſtead of Salt. Some four or five hours after, let him enter into the Bath, thoſe things which I have ſet down being obſerved. When he comes out of the Bath, let him be dried and gently rubbed with ſoft linnen cloths, and anointed, as I formerly preſcribed, then let him ſleep, if he can, for two or three hours in his bed: when he wakes, let him take ſome Ptiſan or ſome ſuch like thing, and then repeat his Bath after the aforeſaid manner. He ſhall uſe this Bath thrice in ten days. But if the Patient be ſubject to crudities of the ſtomach, ſo that he cannot ſit in the Bath without fear of ſwooning, and ſuch ſymptoms, his ſtomach muſt be ſtrengthened with Oil of Quinces, Wormwood and Maſtich, or elſe with a cruſt of Bread toaſted and ſteeped in Muskadine, and ſtrewed over with the Powders of Roſes, Sanders, and ſo laid to the ſtomach, or behind near to the

The differences of Baths.

Why the Patients muſt not enter the Bath faſting.

How to prepare the body for the Bath.

Things ſtrengthening the Ventricle.

Epithems. the 13. *vertebra* of the back, under which place Anatomy teaches that the mouth of the ſtomach lies. Epithems ſhall be applied to the Liver and Heart, to temper the too acrid heat of theſe parts, and correct the immoderate drineſs by their moderate humidity. Now they ſhall be made of refrigerating and humecting things, but chiefly humecting; for too great coldneſs would hinder the penetration of the humidity into the part lying within. The Waters of Bugloſs and Violets, of each a quartern with a little white Wine, is convenient for this purpoſe. But that which is made of French Barly, the ſeeds of Gourds, Pompions, or Cucumers, of each three drams in the decoction, and mixed with much tempering with Oil of Violets, or of ſweet Almonds, is moſt excellent of all other. Let cloths be dipped and ſteeped in ſuch Epithems, and laid upon the part and renewed as oft as they become hot by the heat of the part. And becauſe in hectick bodies, by reaſon of the weakneſs of the digeſtive faculty, many excrements are uſually heaped up, and dried in the guts, it will be convenient all the time of the Diſeaſe to uſe frequently Clyſters made of the decoction of cooling and humecting Herbs, Flowers and Seeds, wherein you ſhall diſſolve *Caſſia*, with Sugar and Oil of Violets or Water-Lillies.

What a flux happening in a hectick Fever indicates. But becauſe there often happens very dangerous fluxes in a confirmed hectick Fever, which ſhew the decay of all the faculties of the body, and waſting of the corporeal ſubſtance, you ſhall reſiſt them with refrigerating and aſſiſting Medicins, and Meats of groſſer nouriſhment, as Rice, and Cicers; and application of aſtringent and ſtrengthening remedies, and uſing the decoction of Oats or parched Barly for drink. Let the Patient be kept quiet and ſleeping as much as may be, eſpecially if he be a child. For this Fever frequently invades children by anger, great and long fear, or the too hot milk of the Nurſe, over-heating in the Sun, the uſe of Wine, and other ſuch like cauſes; they ſhall be kept in a hot and moiſt air, have another Nurſe, and be anointed with Oil of Violets; to conclude, you ſhall apply Medicins which are contrary to the morbifick cauſe.

CHAP. XXXIII.

Of the Wounds of the Epigaſtrium *and of the lower Belly.*

How children be cured. THe Wounds of the lower Belly are ſometimes before, ſometimes behind, ſome onely touch the ſurface thereof, others enter in; ſome paſs quite through the Body, ſo that they often leave the Weapon therein; ſome happen without hurting the contained parts, others grievouſly offend theſe parts, the Liver, Spleen, Stomach, Guts, Kidneys, Womb, Bladder, Ureters, and great Veſſels, ſo that oft-times a great portion of the Kall falls forth. We know the Liver is wounded, when a great quantity of bloud comes forth of the Wound, when a pricking pain reaches even to the Sword-like griſle, to which the Liver adheres. Oft-times more choler is caſt up by Vomit, and the Patient lies on his Belly with more eaſe and content.

Their differences.

Signs of a wounded liver.

Signs that the Stomach and ſmaller Guts are wounded. When the Stomach or any of the ſmall Guts are wounded, the meat and drink break out at the Wound, the *Ilia* or flanks ſwell and become hard, the Hicket troubles the Patient, and oft-times he caſts up more choler, and grievous pain wrings his Belly, and he is taken with cold ſweats, and his extreme parts wax cold.

Signs to know when the greater Guts are wounded. If any of the greater Guts ſhall be hurt, the excrements come forth at the Wound: When the Spleen is wounded there flows out thick and black bloud, the Patient is oppreſſed with thirſt, and there are alſo the other ſigns which we ſaid uſe to accompany the wounded Liver. A difficulty of making water troubles the Patient whoſe reins are wounded, bloud is piſſed forth with the Urin, and he hath a pain ſtretched to his groins and the regions of the Bladder and Teſticles.

Signs that the Kidneys are hurt.

Signs that the Bladder is wounded. The Bladder or Ureters being wounded, the flanks are pained, and there is a Tenſion of the *Pecten*, or Share; Bloud is made inſtead of Urin, or elſe the Urin is very bloudy, which alſo divers times comes forth at the Wound. When the Womb is wounded, the bloud breaks forth by the Privities, and the ſymptoms are like thoſe of the Bladder.

Signs that the Womb is wounded. The Wounds of the Liver are deadly, for this part is the Work-houſe of the Bloud, wherefore neceſſary for life; beſides, by Wounds of the Liver the branches of the Gate or hollow Veins are cut, whence enſues a great flux of bloud not onely inwardly, but alſo outwardly, and conſequently a diſſipation of the ſpirits and ſtrength.

Prognoſticks. But the bloud which is ſhed inwardly amongſt the Bowels putrefies and corrupts, whence follows Pain, a Fever, Inflammation, and laſtly Death. Yet *Paulus Ægineta* writes that the lobe of the Liver may be cut away without neceſſary conſequence of death. Alſo the Wounds of the Ventricle and of the ſmall Guts, but chiefly of the *Jejunum*, are deadly; for many Veſſels run to the *Jejunum* or empty Gut, and it is of a very nervous and ſlender ſubſtance, and beſides it receives the cholerick humour from the bladder of the Gall. So alſo the Wounds of the Spleen, Kidneys, Ureters, Bladder, Womb, and Gall, are commonly deadly, but always ill, for that the actions of ſuch parts are neceſſary for life; beſides divers of theſe are without bloud and nervous, others of them receive the moiſt excrements of the whole body, and lie in the innermoſt part of the body, ſo that they do not eaſily admit of Medicins. Furthermore, all Wounds which penetrate into the capacity of the Belly, are judged very dangerous, though they do not touch the contained Bowels: for the encompaſſing, and new air entering in amongſt the Bowels, greatly hurts them, as never uſed to the feeling thereof; add hereto the diſſipation of the ſpirits which much weakens the ſtrength. Neither can the filth of ſuch Wounds be waſted away according to the mind of the Chirurgeon, whereby it happens they divers times turn into Fiſtulaes, as we ſaid of Wounds of the Cheſt, and ſo at length by collection of matter cauſe death. Yet I have dreſſed many, who by Gods aſſiſtance and favour have recovered of Wounds paſſing quite through their bodies.

Lib.6.cap.88.

A Hiſtory. I can bring as a witneſs the Steward of the Portugal Embaſſadour, whom I cured at *Melun* of a Wound made with a Sword ſo running through the body, that a great quantity of excrements came forth of the wounded Guts as he was a dreſſing, yet he recovered.

Not

Not long ago *Giles le Maiſtre*, a Gentleman of *Paris* was run quite through the body with a Rapier, ſo that he voided much blood at his mouth and fundament divers days together, whereby you know the guts were wounded; and yet he was healed in twenty days. In like ſort the wounds of the greater veſſels are mortal, by reaſon of the great effuſion of blood and ſpirits which enſues thereupon. Another Hiſtory.

CHAP. XXXIV.

The cure of Wounds of the lower Belly.

THe firſt cogitation in curing of theſe wounds ought to be, Whether they pierce into the capacity of the belly; for thoſe which paſs no further then the *Peritonæum* ſhall be cured like ſimple wounds which only require union. But thoſe which enter into the capacity muſt be cured after another manner. For oft-times the kall, or guts, or both, fall forth at them.

A gut which is wounded muſt be ſowed up with ſuch a ſeam as Furriers or Glovers uſe, as we formerly told you; and then you muſt put upon it a powder made of Maſtich, Myrrh, Aloes and Bole. Being ſowed up, it muſt not be put up boiſterouſly together and at once into its place; but by little and little, the Patient lying on the ſide oppoſite to the wound. As for example, the right ſide of the guts being wounded and falling out by the wound, the Patient ſhall lye on his left ſide, for the more eaſie reſtoring of the faln-down gut, and ſo on the contrary. If the lower part of the guts being wounded ſlide through the wound, then the Patient ſhall lye with his head low down, and his buttocks raiſed up by putting a pillow under them: If the upper part be hurt, then muſt he lye quite contrary, that the guts falling downwards, by ſuch a ſite, may give way to thoſe which are faln out through the wound. But often in this caſe, the guts having taken cold by the encompaſſing air, ſwell up and are diſtended with wind, the which you muſt diſcuſs before you put them into their place, with a Fomentation of the decoction of Camomil, Melilot, Aniſeeds, and Fennel, applied with a ſpunge, or contained in a bladder; or elſe with Chickens, or Whelps cut alive in the midſt and laid upon the ſwelling; for thus, they do not only diſcuſs the flatulency, but alſo comfort the afflicted part. But if the inflation cannot thus be diſcuſſed, the wound ſhall be dilated, that ſo the guts may return the more freely to their place. The cure of a wounded gut.

If the kall ſhall fall out, it muſt be ſpeedily reſtored to its place, for it is very ſubject to putrefie; for the fat, whereof for the moſt part it conſiſts, being expoſed to the air, eaſily loſes its native heat, which is ſmall and weak, whence a mortification enſues. Hence is that of *Hippocrates*; If the kall fall out, it neceſſarily putrefies. The Chirurgeon ſhall know whether it putrifies, or not, by the blackneſs and the coldneſs you may perceive by touching it; neither muſt you when it putrefies, preſently reſtore it to its place, for ſo the contagion of the putrefaction would ſpread to the reſt of the parts: But whatſoever thereof is putrefied ſhall be twitched and bound hard with a ſtring, and ſo cut off, and the reſt reſtored to his proper place; but its good after cutting of it away, to leave the ſtring ſtill hanging thereat, that ſo you may pluck and draw forth whatſoever thereof may by being too ſtrait bound, fall away into the capacity of the belly. Some think it better to let the kall thus bound to hang forth until that portion thereof which is putrefied fall away of it ſelf, and not to cut it off. But they are much deceived; for it hanging thus would not cover the guts, which is the proper place. The guts and kall being put up, if the wound be great and worth ſpeaking of, it muſt be ſowed with that ſuture which is termed *Gaſtroraphia*; but this kind of ſuture is thus made. The needle at the firſt putting in muſt only take hold of the *Peritonæum*, and then on the oppoſite ſide only of the fleſh, letting the *Peritonæum* alone, and ſo go along putting the needle from without inwards, and from within outwards, but ſo that you only take the muſculous fleſh and skin over it, and then only the *Peritonæum*, until you have ſowed up all the wound. He which doth otherwiſe ſhall undergo this danger, that whereas the coat *Peritonæum* is of it ſelf without blood, it being divided, or wounded, cannot of it ſelf be united to it ſelf, therefore it requires an intercourſe of fleſh: Otherwiſe unleſs it be thus united by the benefit of the fleſh intermixed therewith, there would remain an incurable tumor after the wound is cicatrized on the outſide. But that which we ſaid before, according to *Galen*'s mind, that all the wounds muſt be ſowed, it is not ſo to be taken, as if that the wound muſt be ſowed up to the very end; for in the lower part of the wound there muſt be left a certain ſmall vent by which the quitture may paſs forth, which being wholly cleanſed and exhauſted, the wound muſt be quite healed up. But the wounds which ſhall penetrate into the ſubſtance of the liver, ſpleen, ventricles, and other bowels, the Chirurgeon ſhall not ſuffer them to be without medicines, as if they were deſperate, but he ſhall ſpare neither labour nor care to dreſs them diligently. For doubtful hope is better than certain deſpair. The bladder, womb and right gut being wounded, detergent and agglutinative injections ſhall be put up by their proper paſſages. I have read nothing as yet in any Author of the wounds of the fat, for all of them refer the cure thereof to the wounds of the muſcles. Yet I will ſay this by the way, that wounds of the fat, how deep ſoever they be, if they be only ſimple, may be dreſſed without putting in of any tent, but only dropping in ſome of my Balſam, and then laying upon it plaiſter of *Gratia Dei*, or ſome ſuch like; for ſo they will heal in a ſhort time. The cure when the kall falls out. *Hip. Apo.* 58. *ſect.* 6. *Lib.* 6. *Meth. cap.* 4. The cure of the wounded fat.

CHAP. XXXV.

Of the Wounds of the Groins, Yard, and Teſticles.

WHen the groins and neigbouring parts are wounded, we muſt firſt conſider whether they pierce to within: And if they do penetrate, to what inward parts they come, whether to the bladder, the womb, or right gut; for theſe parts are ſuch near neighbours that oft-times they are all wounded with one blow. But for the wounds of the teſticles and genital parts, becauſe they are neceſſary inſtruments for the preſerving the *Species* by generation of a ſucceſſion of Individuals, and to keep all things quiet at home, therefore the Chirurgeon ought to be very diligent and careful for their preſervation. Wherefore if they ſhould chance at any time to be wounded, they ſhall be dreſſed, as we have formerly delivered, the medicines being varied according to the ſtate of the wound, and the appearing and happening ſymptoms; for it would be a thing of immenſe labour to handle all things in particular.

CHAP. XXXVI.

Of the Wounds of the Thighs and Legs.

Why wounds of the inſide o the thigh are oft-times deadly.

WOunds which have been received on the inſide of the thighs, have often cauſed ſudden death, if they have come to the vein *Saphena*, or the great artery, or the nerves, the aſſociates of theſe veſſels. But when they are ſimple, there is nothing which may alter the uſual manner of cure. Yet the Patient muſt be careful to lye in his bed; for the vulgar Italian Proverb is true, *La mano al petto, la gamba al letto*; that is, [The hand on the breaſt, and the leg on the bed.] But when they penetrate more deeply into the ſubſtance of the part, they bring horrid and fearful ſymptoms, as an inflammation, an abſceſs, from whence oft-times ſuch abundance of matter iſſues forth, that the Patient falls into an *Atrophia* and Conſumption. Wherefore ſuch wounds and ulcers require a careful and induſtrious Chirurgeon, who may fitly make Inciſions neceſſary for the corrupt parts, and calloſity of the fiſtulous ulcer. Some Chirurgeons have been ſo bold as to ſow together the end of the tendons of the ham, and of other joynts, when they have been quite cut aſunder. But I durſt never attempt it for fear of pain, convulſions, and the like horrid ſymptoms.

The large tendon of the heel hard to conſolidate.

For the wounds of that large tendon which is compoſed in the calf of the leg by the concourſe of three muſcles, and goes to the heel, I have obſerved that when it hath been cut with a Sword, that the wounds have been long and hard to cure; and beſides, when at the laſt they have been healed, as ſoon as the Patient hath got out of his bed, and endeavoured to go, they have grown ill and broke open again. Wherefore in ſuch like wounds let the Patient have a care, that he begin not to go, or too boldly to uſe his hurt leg before it be perfectly cicatrized, and the ſcar grown hard. Therefore that the Patient may be in more ſafety, I judge it altogether neceſſary, that he uſe to go with Crutches for a good while after the wound is perfectly healed up.

CHAP. XXXVII.

Of the Wounds of the Nerves and nervous parts.

Differences drawn from things wounded.

THe continuity of the nervous parts is divers ways looſed by the violent incurſion of external things; as by things which contuſe, batter, and grind in ſunder, as by the blow of a ſtone, cudgel, hammer, lance, bullet out of a Gun or Croſs-bow; by the biting of greater teeth; or the pricking of ſome ſharp thing, as a needle, bodkin, pen-knife, arrow, ſplinter; or the puncture of ſome venemous thing, as of a Sea-dragon; or the edge of ſome cutting thing, as a ſword or rapier; or of ſtretching things which violently tear aſunder the nervous bodies. Hence therefore it is, that of ſuch wounds ſome are ſimple, others compound; and the compound, ſome more compound than other. For of theſe ſome are ſuperficiary and ſhort, others deep and long; ſome run alongſt the nervous body, others run broad-ways; ſome cut the part quite aſunder, others only a portion thereof.

Their ſymptoms.

The ſymptoms which follow upon ſuch wounds are, vehement pain, and defluxion, inflammation, abſceſs, feaver, *delirium*, ſwooning, convulſion, gangrene, ſphacel; whence often death enſues by reaſon of that ſympathy which all the nervous parts have with the brain.

Why a puncture of a nerve is deadly.

Amongſt all the wounds of the nervous parts, there is none more to be feared than a puncture, or prick, nor any which cauſeth more cruel and dangerous ſymptoms. For by reaſon of the ſtraitneſs of the wound, medicines can neither be put in, nor the ſanious matter paſs forth; now the ſanious matter by long ſtay acquires virulency, whereby the nervous parts are tainted and ſwoln, ſuffer pain, inflammation, convulſions, and infinite other ſymptoms; of theſe the wounds are moſt dangerous, by which the nervous and membranous bodies are but half cut aſunder. For, the portion thereof which remains whole, by its drawing and contracting it ſelf towards the original, cauſeth great pain and convulſion by ſympathy. The truth hereof is evident in wounds of the head. as when the *Pericranium* is half cut, or when it is cut to apply a Trepan. For the cutting thereof infers far greater pain, than when it is cut quite aſunder. Wherefore it is ſafer to have the nervous body quite cut off, for ſo it hath no community, nor conſent with the upper parts, neither doth it labour, or ſtrive, to reſiſt the contraction of its ſelf; now this contrariety, and as it were fight, is the cauſe of pain; yet there ariſes another miſery from ſuch a wound, for the part whereinto the nerve which is thus cut inſnuder paſſes, thence forwards loſeth its action.

CHAP.

CHAP. XXXVIII.

Of the cure of Wounds of the nervous parts.

IT is the ancient Doctrine of the ancient Phyſicians, that the wounds of the nervous parts ſhould not preſently be agglutinated (which notwithſtanding the general and firſt indication, uſually taken from the ſolution of continuity, requires) but rather, chiefly if they be too ſtrait, that the punctures ſhould be dilated, by cutting the parts which are above them, and let them be kept long open that the filth may paſs freely forth, and the medicine enter well in. Yet I in many cures have not followed this counſel, but rather that which the common indication requires. A wound of the nervous parts indicated contrary to the general cure of wounds.

That cure is in freſh memory which I performed upon Monſieur *le Cocq*, a Proctor of the Spiritual Court, who dwelt in our *Ladies-ſtreet*; he gathering and binding up ſome looſe Papers, run a Pen-knife which was hid amongſt them, through his hand. Alſo one of his neighbours who went to ſpit a piece of Beef, thruſt the ſpit through the midſt of his hand: But I preſently agglutinated both their wounds, without any danger, dropping preſently in at the firſt dreſſing a little of my Balſom warm, and putting about it a repelling and aſtringent medicine, and by this means they were both of them healed in a ſhort time, no ſymptom thereupon happening. Yet I would not have the young Chirurgeon to run this hazard: For firſt, he muſt be well practiſed and accuſtomed to know the tempers and habit of men; for this manner of curing will not do well in a plethorick body, or in a body replete with ill humors, or indued with exquiſite ſenſe. Therefore in ſuch a caſe it will be ſafer to follow the courſe here ſet down. For wounds of the nerves do not only differ from other wounds, but alſo among themſelves in manner of curing. For although all medicines which draw from far, and waſte ſanious humors, may be reputed good for the wounds of the nerves; yet thoſe which muſt be applied to punctures, and to thoſe nerves which are not wholly laid open, ought to be far more powerful, ſharp and drying; yet ſo that they be not without biting, that ſo penetrating more deep, they may draw forth the matter, or elſe conſume and diſcuſs that which either lies about the nerves, or moiſtens their ſubſtance. On the contrary, when the ſinews are bared from fleſh and adjoyning particles, the ſtand in need but of medicines, which may only dry. Here you may furniſh your ſelves with ſufficient ſtore of medicines good for the nerves howſoever pricked. As ℞ *Terebinth. vin. & olei veteris an.* ℥ i. *Aquæ vitæ parum.* Or ℞ *olei Terebinth.* ℥ i. *Aquæ vitæ* ʒ i. *Euphor.* ℥ ß. Or, ℞ *radices Dracontiæ, Brioniæ, Valerianæ & Gentianæ exſiccatas, & in pulverem reductas, miſce cum decocto centauri, aut oleo, aut axungia veteri*; drop hereof warm into the wound as much as ſhall ſuffice. Or elſe put ſome Hogs, Gooſe, Capons, or Bears Greaſe, old Oyl, Oyl of Lilies, or the like, to *Galbanum*, pure Rozin, *opopanax* diſſolved in *Aqua vitæ* and ſtrong Vinegar. Or, ℞ *olei hypericonis ſambuci, & de euphorbio an.* ℥ i. *Sulphuris vivi ſubtiliter pulveriſati* ʒ ß, *gummi ammoni. bdellii an.* ʒ ii. *Aceti boni* ℥ ij. *Vermium terreſt. præparat.* ℥ i *bulliant omnia ſimul ad conſumptionem aceti.* Let as much hereof as ſhall ſuffice be dropped into the wound; then apply this following Cerate, which draws very powerfully. ℞ *Olei ſupra-ſcripti* ℥ i. *Terebinth. venet.* ℥ ß, *diachylonis albi cum gummi,* ℥ x. *ammoniac. bdellii in aceto diſſolutorum, an.* ʒ ij. *reſin. pini gum. elemi, picis navalis an.* ʒ v. *ceræ quod ſufficit, fiat ceratum ſatis molle.* We muſt uſe ſome whiles one, ſome whiles another of theſe medicines in punctures of the nerves with choice and judgment, according to their conditions, manner, depth, and the temperaments and habits of the wounded bodies. But if the pain yield not to ſuch remedies, but rather increaſe, with the inflammation of the affected part, a ſwelling of the lips of the wound, and ſweating forth of a ſerous, thin and virulent matter or filth, then you ſhall pour into it ſcalding Oyl, and ſhall touch three or four times not only the ſurface of the wound, but the bottom thereof with a rag dipped therein and tied to the end of *Spatula*. For this will take away the ſenſe from the nerve, tendon, or membrane, like as if they were burnt with a cautery, and ſo the pain will be eaſed. So in the moſt grievous pains of rotten teeth, the thruſting of an hot iron into their roots, or ſtopping them with cotton dipped in Oyl of Vitriol, or *Aqua vitæ*, gives moſt certain eaſe; for by burning the nerve which is inſerted into their roots, the ſenſe, and ſo conſequently, the pain is taken away. So alſo in malignant, gnawing, eating and ſpreading ulcers, which are always aſſociated with much pain, the pain ceaſes by applying an Eſcharotick, the powder of Alum or Mercury, or *Ægyptiacum* made ſomewhat more ſtrong than uſual. That the young Chirurgeon may be more ready for this practice and the uſe of the former medicines, I have thought good to inſert the following Hiſtory, both for the lateneſs of the thing, and pleaſing memory of the moſt laudable Prince.

Medicines fit for wounds of the nerves.

What wounds of the nerves muſt be burnt.

A certain Anodyne in pain of the teeth.

Why Eſcharoticks muſt be uſed to ſpreading ulcers.

Charles the ninth, the French King, being ſick of a Feaver, Monſieur *Chapellan* and *Caſtellan* his Phyſicians thought it fit he ſhould be let blood; for the performance whereof, there was called a Chirurgeon wondrous famous for that buſineſs; but when as he by chance had pricked a nerve inſtead of a vein, the King cried out, that he felt a mighty pain in that place. Then I bid, that the ligature ſhould ſtreight-ways be looſed, otherwiſe the arm would preſently be much ſwelled. But he going ſlowly about it, behold the arm began to ſwell with ſuch contraction, that he could not bend it, nor put it forth, and cruel pain moleſted not only the pricked particle; but all the whole member beſides. I forthwith laid upon the wound a plaiſter of *Baſilicon*, to hinder the agglutination thereof, and then I wrapped all the arm in a double linnen cloth dipped in Oxycrate, putting upon it an expulſive ligature, which beginning at the wriſt and ending at the top of the ſhoulder, might keep the blood and ſpirits from fear of defluxion and inflammation. This being thus performed, we went aſide to conſult what was neceſſary to be done, both to aſſwage the pain, as alſo to divert the other ſymptoms, which uſually happen upon punctures of the nerves. I being deſired, thus delivered my opinion, that in my mind, there were nothing better, then preſently to drop into the wound ſome Oyl of Turpentine warmed and mixed with a little *Aqua vitæ*. And then all the arm ſhouldbe be covered with a plaiſter of *Diacalcitheos* diſſolved in Vinegar and

A hiſtory.

A famous Hiſtory.

Oyl of Roſes, bound over and beſides with the expulſive ligature, which we formerly mentioned. For the Oyl and *Aqua vitæ* have a faculty to penetrate into the bottom of the wound, and to exhauſt and dry up the ſerous and virulent humor, which ſweats from the ſubſtance of the pricked nerve; and alſo to mitigate the pain by its actual heat. Furthermore, emplaiſter *Diacalcitheos* hath a faculty to diſſolve the humor which hath already fallen down into the arm, and to hinder the entrance and defluxion of any new matter. And the ligature is ſuch as by its moderate aſtriction would ſerve to ſtrengthen the muſcles, and to preſs out and repel the humors, which were fallen down into the upper part, and to prohibit that which is ready to fall down. Mine advice being approved of the Phyſicians both in word and deed, the pain was mitigated. But the humor ſtaid in the part, for the diſſolving and drying whereof, this following remedy was uſed. ℞ *far. hordei & orobi an.* ʒ ij. *flor. chamæm. & melilot. an.* p. ij. *butyr. recentis ſine ſale* ʒ i ſs. *Lixivii barbitonſoris quod ſufficit, fiat cataplaſma ad formam pultis.* By theſe remedies the King at laſt, after three months ſpace was perfectly healed, ſo that there remained no ſign of the depraved action in the part. But if at any time there ſhall be ſo great contumacy, that it will not yield to theſe means, but that there is imminent danger of a Convulſion; it will be better to cut it in ſunder, whether nerve, tendon, or membrane, than to expoſe the Patient to the danger of a deadly Convulſion; for thus indeed the peculiar action of that part will be loſt, but the whole body preſerved thereby; for ſo we had determined by common conſent, that if the pain which afflicted the King would not yield to the preſcribed remedies, either to pour in ſcalding Oyl, or elſe to cut the ſinew quite aſunder.

A diſcuſſing and drying cataplaſm.

A Hiſtory.

For the late and ſad memory of M^ris *Courtin* dwelling in the Street of *Holy-Croſs*, was in our minds, who of a vein not well opened in her arm fell into a Gangrene and total mortification of that whole part, of which ſhe died, becauſe ſhe was not dreſſed with the formerly mentioned medicines. Yet we muſt abſtain from theſe two powerful remedies, when the pricked nerve ſhall lye bare, for elſe the pain would be increaſed, and more grievous ſymptoms follow. Wherefore as I formerly wiſhed, more mild medicines muſt be applied, which may dry up the ſerous humor without biting acrimony; as ℞ *Terebinth. venet. in aq. roſ. lota* ʒ ij. *Boli armeni ſubtiliter pulveriſati,* ʒ ij. *Incorporentur ſimul.* Our Balſom alſo is excellent in this caſe, and this of *Vigo*'s which follows. ℞ *Olei roſar. omphacini* ʒ i ſs. *Olei de terebinth.* ʒ iij. *ſucci plant. ag.* ʒ ſs. *Semin. hypericonis aliquantulum contritim.* ſs. *Tutiæ præpar.* ʒ iij. *Calcis decies lotæ cum aqua plantagin.* ʒ ij. *antimonii* ʒ i. *ſevi hercini, & vitulini, an.* ℥ v. *vermium terreſtrium cum vino lotorum* ʒ i ſs. *Bulliant omnia ſimul dempta tutia in cyatho decoctionis hordei, ad conſumptionem aquæ & vini, colentur rurſumq; igni admoveantur, addendo tutiam, & fiat linimentum cum cera alba, &* ʒ ſs. *Croci.* This liniment aſſwages pains, and covers the bared nerves with fleſh. This cure of punctured nerves, may with choice and judgment, and obſerving the proportion of the parts, be transferred to the pricked tendons and membranes. But take this as a general and common rule, that all nervous bodies howſoever hurt, are to be comforted by anointing them with hot Oyls, ſuch as the Oyl of Bays, Lilies, of Worms, Sage, or ſome other ſuch like remedy being applied to their originals and more notable paſſages; as to the original of the ſpinal marrow, the arm-pits and groins. Neither do I think fit in this place to omit an effect which ſometimes happens to the large tendon of the heel, of which we formerly made mention. For it oft-times is rent or torn by a ſmall occaſion without any ſign of injury or ſolution of continuity apparent on the outſide, as by a little jump, the ſlipping aſide of the foot, the too nimble getting on horſe-back, or the ſlipping of the foot out of the ſtirrop in mounting into the ſaddle. When this chance happens, it will give a crack like a Coach-mans whip; above the heel, where the tendon is broken, the depreſſed cavity may be felt with your finger, there is a great pain in the part, and the party is not able to go. This miſchance may be amended by long lying and reſting in bed, and repelling medicines applied to the part affected in the beginning of the diſeaſe, for fear of more grievous ſymptoms, and then applying the Black-plaiſter, or *Diacalcitheos*, or ſome other ſuch, as need ſhall require; neither muſt we hereupon promiſe to our ſelves, or the Patient, certain or abſolute health. But on the contrary, at the beginning of the diſeaſe we muſt foretel that it will never be ſo cured, but that ſome reliques may remain, as the depreſſion of the part affected, and depravation of the action and going; for the ends of this broken or relaxed tendon by reaſon of its thickneſs and contumacy, cannot eaſily be adjoyned, nor being adjoyned, united.

An Anodyne and Sarcotick Balſom.

A general rule for all wounds of all nervous parts.

CHAP. XXXIX.

Of the Wounds of the Joynts.

Why wounds of the joynts are malignant.

BEcauſe the wounds of the Joynts have ſomething proper and peculiar to themſelves, beſides the common nature of wounds of the nerves, therefore I intend to treat of them in particular. Indeed they are always very dangerous, and for the moſt part deadly, by reaſon of the nervous productions and membranous tendons wherewith they are bound and ingirt, and into which the nerves are inſerted: Whereby it comes to paſs, that the exquiſite ſenſe of ſuch like parts will eaſily bring malign ſymptoms, eſpecially if the wound poſſeſs an internal, or, as they term it, a domeſtick part of them; as for example, the arm-pits, the bending of the arm, the inner part of the wriſt, and ham, by reaſon of the notable veins, arteries, and nerves of theſe parts, the looſed continuity of all which brings a great flux of blood, ſharp pain, and other malignant ſymptoms; all which we muſt reſiſt according to their nature and condition, as a flux of blood with things ſtaying bleeding, pain with anodynes. If the wound be large and wide, the ſevered parts ſhall be joyned with a ſuture, leaving an orifice in the lower part, by which the quitture may paſs forth. This following powder of *Vigo*'s deſcription muſt be ſtrewed upon the ſuture. ℞ *Thuris, ſang. draconis, boli armen. terræ ſigill. an.* ʒ ij. *Aloes, maſtich. an.* ʒ i. *Fiat pulvis ſubtilis.* And then the joynt muſt be wrapped about with a repercuſſive medicine compoſed of the whites of Eggs, a little oyl of Roſes, Bole, Maſtich, and Barley flower. If it be needful to uſe a Tent, let it be ſhort, and according to the wound thick,

The cure.

thick, leſt it cauſe pain, and moreover let it be anointed with the yolk of an Egg, oyl of Roſes, waſhed Turpentine and a little Saffron. But if the wound be more ſhort and narrow, it ſhall be dilated, if there be occaſion, that ſo the humor may paſs away more freely. You muſt reſt the part, and beware of uſing cold, relaxing, mollifying, humecting, and unctuous medicines, unleſs peradventure the ſharpneſs of the pain muſt be mitigated. For on the contrary, aſtringent and deſiccant medicines are good, as this following Cataplaſm. ℞ *furfur. macri, farin. hordei, & fabarum an.* ℥ iiij. *Florum chamæ. & melil. an.* m. ß *terebinth.* ℥ iij. *mellis communis* ℥ ij. *ol. myrt.* ℥ i. *Oxymelitis, vel lixivii com. quantum ſufficit; fiat cataplaſma ad formam pultis.* Or you may compoſe one of the Lees of Wine, Wheat-bran, the powder of Oaken-bark, Cypreſs-nuts, Galls and Turpentine, and ſuch like, that have an aſtringent, ſtrengthning and drying quality, and thereby aſſwaging pain, and hindering the deſluxion of humors. This following medicine is aſtringent and agglutinative. ℞ *terebinth. venet.* ℥ ij. *aq. vitæ parum, pulveris maſtich. aloes, myrrhæ, boli armen. an.* ℈ ij. And alſo our Balſam will be good in this caſe, if ſo be that you add hereto ſo much powder which dries without Acrimony, as occaſion ſhall ſerve: I admoniſhed you before to take heed of cold, and now again; for it is hurtful to all wounds and ulcers, but eſpecially to theſe of the nervous parts: Hence it is that many die of ſmall wounds in the Winter, who might recover of the ſame wounds though greater in the Summer. For cold, according to *Hippocrates*, is nipping to Ulcers, hardens the skin, and hinders them from ſuppuration, extinguiſheth natural heat, cauſes blackneſs, cold aguiſh fits, convulſions and diſtentions. Now divers excrements are caſt forth of wounds of the joynts, but chiefly albugineous, that is, reſembling the white of an Egg, and mucous, and ſometimes a very thin water, all which ſavour of the nature of that humor which nouriſheth theſe parts. For to every part there is appropriate for his nouriſhment and conſervation, a peculiar Balſam, which by the wound flows out of the ſame part; as out of the branches of the Vine, when they are pruned, their radical moiſture or juyce flows, whence alſo a *Callus* proceeds in broken bones. Now this ſame mucous, and albugineous humor, ſlow, and as it were frozen, flowing from the wounded joynts, ſhews the cold diſtemper of the parts, which cauſe pain, not to be orecome by medicines only potentially hot. Wherefore to correct that, we muſt apply things actually hot, as Beaſts and Swines bladder half full of a diſcuſſing decoction, or hot bricks quenched in Wines. Such actual heat helps Nature to concoct and diſcuſs the ſuperfluous humor impact in the joynts, and ſtrengthens them; both which are very neceſſary, becauſe the natural heat of the joynts is ſo infirm that it can ſcarce actuate the medicine, unleſs it be helped with medicines actually hot. Neither muſt the Chirurgeon have the leaſt care of the figure and poſture of the part, for a vicious poſture increaſes ill ſymptoms, uſes to bring to the very part though the wound be cured, diſtortion, numneſs, incurable contraction; which fault leſt he ſhould run into, let him obſerve what I ſhall now ſay: If the fore-part of the ſhoulder be wounded, a great boulſter muſt be under the arm-pit, and you muſt carry your arm in a ſcarf, ſo that it may bear up the lower part of the arm, that ſo the top of the ſhoulder may be elevated ſomewhat higher, and that ſo it may be thereby more ſpeedily and happily agglutinated and conſolidated. If the lower part be wounded, when fleſh begins to be generated, and the lips of the wound to meet, you muſt bid the Patient to move and ſtir his arms divers ways ever and anon; for if that be omitted or negligently done, when it is cicatrized, then it will be more ſtiff and leſs pliable to every motion; and yet there is a further danger leſt the arm ſhould totally loſe its motion. If the wound be upon the joynt of the elbow, the arm ſhall be placed and ſwathed in a middle poſture, that is, which neither too ſtraitly bows it, nor holds it too ſtiffly out; for otherwiſe, when it is cicatrized, there will be an impediment either in the contraction or extention. When the wound is in the wriſt or joynts of the fingers either externally or internally, the hand muſt be kept half ſhut, continually moving a ball therein. For if the fingers be held ſtrait ſtretched forth, after it is cicatrized, they will be unapt to take up or hold any thing, which is their proper faculty. But if after it be healed, it remain half ſhut, no great inconveniency will follow thereon: For ſo he may uſe his hand divers ways to his Sword, Pike, Bridle, and in any thing elſe. If the joynts of the hip be wounded, you muſt ſo place the Patient that the thigh-bone may be kept in the cavity of the huckle-bone, and may not part a hairs breadth there-from, which ſhall be done with linnen boulſters and ligatures applied as is fitting, and lying full upon his back. When the wound ſhall begin to cicatrize, the Patient ſhall uſe to move his thigh every way, leſt the head of the thigh-bone ſtick in the cavity of the huckle-bone without motion. In a wound of the knee, the leg muſt be placed ſtrait out, if the Patient deſire not to be lame: When the joynts of the feet and toes are wounded, theſe parts ſhall neither be bended in nor out, for otherwiſe he will not be able to go. To conclude, the ſite of the foot and leg, is quite contrary to that of the arm and hand.

An aſtringent and drying Cataplaſm.

Aphor. 20. *ſec.* 5.

What matter uſually flows from wounds of the joynts.

Why things actually hot muſt be applied to the wounded joynts.

Of the ſite and poſture of wounded joynts.

CHAP. XL.

Of the Wounds of the Ligaments.

THe wounds of the Ligaments, beſides the common manner of curing thoſe of the Nerves, have nothine peculiar, but that they require more powerful medicines, for their agglutination, deſiccation and conſolidating; both becauſe the ligamental parts are harder and drier, and alſo for that they are void of ſenſe. Therefore the foreſaid cure of nerves and joynts may be uſed for theſe wounds: For the medicines in both are of the ſame kind; but here they ought to be ſtronger and more powerfully drying. The Theory and cure of all the ſymptomes which ſhall happen thereupon, have been expreſſed in the Chapter of curing the wounds of the nervous parts, ſo that here we ſhall need to ſpeak nothing of them, for there you may find as much as you will. Wherefore here let us make an end of wounds, and give thanks to God the Author and giver of all good, for the happy proceſs of our labours: And let us pray that that which remains may be brought to a happy end, and ſecure for the health and ſafety of good people.

Ligaments more dry than nerves, and without ſenſe.

The end of the Tenth Book.

BOOK XI.

Of Wounds made by Gunſhot, other fiery Engines, and all ſorts of Weapons.

The PREFACE.

I Have thought good here to premiſe my opinion of the original, increaſe, and hurt of fiery Engines, for that I hope it will be an ornament and grace to this my whole Treatiſe: As alſo to intice my Reader, as it were with theſe junkets, to our following Banquet ſo much ſavouring of Gunpowder. For thus it ſhall be known to all whence Guns had their original, and how many habits and ſhapes they have acquired from poor and obſcure beginnings; and laſtly, how hurtful to mankind the uſe of them is.

Lib. 2. de inv. rerum. Polydore Virgil *writes, that a German of obſcure birth and condition was the Inventor of this new Engin which we term a Gun, being induced thereto by this occaſion. He kept a Mortar covered with a tile or ſlate, for ſome other certain uſes, a powder (which ſince that time for its chief and new known faculty, is named Gunpowder.) Now it chanced as he ſtruck fire with a ſteel and flint, a ſpark thereof, by accident fell into the Mortar, whereupon the powder ſuddenly catching fire, caſts the ſtone or tile which covered the Mortar up on high; he ſtood amazed at the novelty and ſtrange effect of the thing, and withal obſerved the formerly unknown faculty of the powder; ſo that he thought good to make experiment thereof in a ſmall Iron Trunk framed for that purpoſe according to the intention of his mind. When all things were correſpondent to his expectation, he firſt ſhewed the uſe of his Engine to the Venetians, when they warred with the Genoveſes about* Foſſa Clodia, *in the year of our Lord,* 1380. *Yet in the opinion of* Peter Meſſias, *this Invention muſt have been of greater antiquity; for it is read in the Chronicles of* Alphonſus XI. *King of* Caſtile, *who ſubdued the Iſles* Argezires, *that when he beſieged the chief Town, in the year of our Lord,* 1343. *the beſieged Moors ſhot, as it were, thunder againſt the Aſſailants, out of Iron Mortars. But we have read in the Chronicles written by* Peter *Biſhop of* Leons *of that* Alphonſus *who conquered* Toledo, *that in a certain Sea-fight fought by the King of* Tunis, *againſt the Mooriſh King of* Sivil, *whoſe part King* Alphonſus *favoured, the* Tunetans *caſt lightning out of certain hollow Engins or Trunks with much noiſe. Which could be no other, than our Guns, though not attained to that perfection of Art and Execution which now they have.*

Cap. 8. prim. par. var. lect.

I think the Deviſer of this deadly Engin hath this for his recompence, that his name ſhould be hidden by the darkneſs of perpetual ignorance, as not meriting for this his moſt pernitious Invention, any mention from Poſterity. Who the Inventer of Guns. *Yet* Andrew Thevet *in his Coſmography, publiſhed ſome few years agone, when he comes to treat of the* Suevi, *the Inhabitants of Germany, brings, upon the authority and credit of a certain old Manuſcript, that the German the Inventer of this Warlike Engine was by Profeſſion a Monk and Philoſopher, or Alchymiſt, born at* Friburg, *and nam'd* Conſtantine Anclzen. The reaſon of the name. *However it was, this kind of Engine was called* Bombarda (i.) *a Gun, from that noiſe it makes, which the Greeks and Latins according to the ſound call* Bombus; *then in the following ages, time, art and mans malicioufneſs, added much to this rude and unpoliſh'd invention. For firſt for the matter; Braſs and Copper, Metals far more tractable, fuſible, and leſs ſubject to ruſt, came as ſupplies to Iron. Then for the form; that rude and undigeſted Barrel, or Mortar-like maſs, hath undergone many forms and faſhions, even ſo far as it is gotten upon wheels, that ſo it might run not only from the higher ground, but alſo with more rapid violence to the ruine of mankind; when as the firſt and rude Mortars ſeemed not to be ſo nimbly traverſed, nor ſufficiently cruel for our deſtruction by the only caſting forth of Iron and fire. Hence ſprung theſe horrible Monſters of Canons, double Canons, Baſtards, Muſquets, Field-pieces; hence theſe cruel and furious Beaſts, Culverins, Serpentines, Baſiliſques, Sakers, Falcons, Falconets, and divers other names not only drawn from their figure and making, but alſo from the effects of their cruelty. Wherefore certainly I cannot ſufficiently admire the wiſdom of our Anceſtors, who have ſo rightly accommodated them with names agreeable to their natures; as thoſe who have not only taken them from the ſwifteſt Birds of prey, as Falcons, but alſo from things moſt harmful and hateful to mankind, ſuch as Serpents, Snakes, and Baſiliſques. That ſo we might clearly diſcern, that theſe Engines were made for no other purpoſe, nor with other intent, but only to be imployed for the ſpeedy and cruel ſlaughter of men; and that by only hearing them named we might deteſt and abhor them, as pernicious enemies of our lives. I let paſs other Engines of this Off-ſpring, being for their quantity ſmall, but ſo much the more pernicious and harmful, for that they nearer aſſail our lives, nay trayterouſly, and forthwith ſeiſe upon us not thinking nor fearing any ſuch thing; ſo that we can ſcarce have any means of eſcape; ſuch as Piſtols and other ſmall Hand-guns, which for ſhortneſs you may carry in your pocket, and ſo privily and ſuddenly taking them forth oppreſs the careleſs and ſecure.* The danger of Piſtols. *Fowling-pieces which men uſually carry upon their ſhoulders, are of the middle rank of theſe Engines, as alſo Muskets and Caleeveres, which you cannot well diſcharge unleſs lying upon a Reſt, which therefore may be called Breaſt-guns, for that they are not laid to the cheek, but againſt the breaſt, by reaſon of their weight and ſhortneſs: All which have been invented for the commodity of Footmen, and Light-horſemen. This middle ſort of Engine they call in Latin by a general name* Sclopus, *in imitation of the ſound, and the Italians who term it* Sclopetere; *the French call it* Harquebuſe, *a word likewiſe borrowed from the Italians, by reaſon of the touch-hole by which you give fire to the Piece, for the Italians call a hole* Buzio. *It is termed* Arcus (i.) *a Bow, for that at this preſent it holds the ſame place in Martial affairs, as the Bow did of old;*

and

and as the Archers formerly, ſo at this day the Musketiers are placed in front. From the ſame wretched Shop, and Magazine of Cruelty, are all ſorts of Mines, Countermines, Ports of fire, Trains, Fiery Arrows, Lances, Croſs-bows, Barrels, Balls of Fire, burning Fagots, Granats, and all ſuch fiery Engines and Inventions, which cloſely ſtuffed with fuel and matter for fire, and caſt by the Defendants upon the Bodies and Tents of the Aſſailants, eaſily take fire by the violence of their motion. Certainly a moſt miſerable and pernicious kind of Invention, whereby we often ſee a thouſand of heedleſs men blown up with a Mine by the force of Gunpowder; otherwhiles in the very heat of the Conflict you may ſee the ſtouteſt Souldiers, ſeiſed upon with ſome of theſe Fiery Engines, to burn in their harneſs, no water being ſufficiently powerful to reſtrain and quench the raging and waſting violence of ſuch fire cruelly ſpreading over the body and bowels. So it was not ſufficient to have Arms, Iron, and Fire to mans deſtruction, unleſs alſo that the ſtroke might be more ſpeedy, we had furniſhed them, as it were with wings, ſo to fly more haſtily to our own perdition, furniſhing Sithebearing Death with wings ſo more ſpeedily to oppreſs man, for whoſe preſervation, all things contained in the World were created by God. Verily when I conſider with my ſelf all the ſorts of warlike Engines, which the Ancients uſed, whether in the field in ſet Battels, as Bows, Darts, Croſs-bows, Slings; or in the aſſault of Cities, and ſhaking or overturning their Walls, as Rams, Horſes, Wooden-towers, Slings, and ſuch like; they ſeem to me certain childiſh ſports and games made only in imitation of the former. For theſe modern Inventions are ſuch as eaſily exceed all the beſt appointed and cruel Engines which can be mentioned or thought upon, in the ſhape, cruelty and appearance of their operations. For what in the World is thought more horrid or fearful than Thunder or Lightning? and yet the hurtfulneſs of Thunder is almoſt nothing to the cruelty of theſe infernal Engines; which may eaſily appear by comparing together both their effects. Man alone of all Creatures is not always killed by being touched with Thunder; but it immediately killeth all other things which are ſubject to be touch'd therewith. Nature beſtowing this honour upon him, ſeeing ſo many Creatures exceed him in ſtrength: For all things lye contrary to man; and man, unleſs he be overthrown with it, doth not die thereof. But theſe fire-ſpitting Engines do no more ſpare man, than they do other Creatures, and kill without difference from whence ſoever they come, whither ſoever they are carried, and howſoever they touch. There are many, but more are ſaid to be the remedies againſt Thunder; for beſide the charms whereby the ancient Romans did ſuppoſe they might be driven away, they never penetrate deeper into the ground than five foot, therefore ſuch as was fearful thought the deeper Caves the moſt ſafe. Of thoſe things which grow out of the earth, they do not touch the Bay-tree, and that was the cauſe that it was counted a ſign of Victory both in ancient and modern times. Wherefore Tiberius Cæſar, *otherwiſe a contemner of God and Religion, as he who indued with the Mathematical Sciences, thought all things governed by Fate, yet becauſe he exceedingly feared Thunder, he always carried a Laurel Wreath about his neck when the air was troubled, for that this kind of leaf is reported not to be touched with Thunder. Some report that he made him Tents of Seals skins, becauſe it toucheth not this kind of Creature of all thoſe things that live in the Sea, as neither the Eagle amongſt Birds, which for that is feigned to be* Jove's *Squire. But on the contrary, Charms, the victorious Bay, the Seal, or Sea-calf, the Eagle, or any ſuch thing, profits nothing againſt the violence of theſe fiery engines: No not a wall of ten foot thick will advantage. Laſtly, this argues the immenſe violence of braſen Canons above Thunder, for that Thunder may be diſperſed and driven away with the noiſe and ringing of Bells, the ſounding of Trumpets, the tinkling of braſen Kettles, yea alſo by the ſhooting of ſuch great Ordnance; to wit, the clouds, by whoſe colliſion and fight the Thunder is cauſed, being diſperſed by this violent agitation of the air, or elſe driven further to more remote parts of the skies. But their fury once provoked, is ſtayed by no oppoſition, appeaſed by no remedy. As there are certain ſeaſons of the year, ſo alſo there are certain Regions of the earth, wherein Thunder is ſeldom or never heard. Thunders are rare in Winter and Summer, and that for contrary cauſes; for that in Winter the denſe air is thickned with a thicker coat of clouds, and the froſty and cold exhalation of the earth extinguiſheth what fiery vapours ſoever it receives; which thing keeps* Scythia *and the cold Countreys about it free from Thunder. And on the contrary, too much heat preſerves* Egypt. *For hot and dry exhalations of the earth are condenſed into very thin, ſubtile, and weak clouds. But as the Invention, ſo alſo the harm and tempeſt of great Ordnance, like a contagious Peſtilence, is ſpread and rages over all the earth, and the skies at all times ſound again with their report. The Thunder and Lightning commonly gives but one blow or ſtroke, and that commonly ſtrikes but one man of a multitude: But one great Canon at one ſhot may ſpoil and kill a hundred men. Thunder, as a thing natural, falls by chance, one while upon a high Oak, another while upon the top of a Mountain, and ſomewhiles on ſome lofty Tower, but ſeldom upon Man. But this helliſh Engine, tempered by the malice and guidance of man, aſſails man only, and takes him for his only mark, and directs his bullets againſt him. The Thunder by its noiſe, as a Meſſenger ſent before, foretels the ſtorm at hand; but, which is the chief miſchief, this infernal Engine roars as it ſtrikes, and ſtrikes as it roars, ſending at one and the ſame time the deadly bullet into the breaſt, and the horrible noiſe into the ear. Wherefore we all of us rightfully curſe the Author of ſo pernicious an Engine; on the contrary, praiſe thoſe to the skies, who endeavour by words and pious exhortations to dehort Kings from their uſe, or elſe labour by writing and operation to apply fit medicines to wounds made by theſe Engines. Which hath moved me that I have written hereof almoſt with the firſt of the French. But before I ſhall do this, it ſeemeth not amiſs, (ſo to facilitate the way to the Treatiſe I intend to write of wounds made by Gunſhot) to premiſe two Diſcourſes, by which I may confute and take away certain erroneous opinions which have poſſeſſed the minds of divers; for that, unleſs theſe be taken away, the eſſence and nature of the whole diſeaſe cannot be underſtood, nor a fitting remedy applied by him which is ignorant of the diſeaſe.*

A compariſon of the ancient Weapons with the modern.

Pliny Lib. 2. cap. 59.

Plin. lib. 2. cap. 51.

Sueton. in Tiberio.

The wondrous force of great Ordnance.

Plin. lib. 2. cap. 50.

The firſt Diſcourſe which is dedicated to the Reader, refels and condemns, by reaſons and examples, the method of curing preſcribed by John de Vigo, *whereby he cauterizeth the wounds made by Gunſhot, ſuppoſing them venenate; and on the contrary proves the order of curing which is performed by ſuppuratives, to be ſo ſalutary and gentle, as that preſcribed by* Vigo *is full of errour and cruelty. The ſecond dedicated to the King, teaches that the ſame wounds are of themſelves void of all poyſon, and therefore that all their malignity depends upon the fault of the air, and ill humors predominant in the bodies of the Patients.*

The Arguments of the following Diſcourſes.

The

The firſt Diſcourſe wherein Wounds made by Gunſhot, are freed from being burnt, or cauterized, according to Vigo's *method.*

IN the year of our Lord, 1536. *Francis* the French King, for his acts in War and Peace ſtiled the Great, ſent a puiſſant Army beyond the Alps, under the Government and Leading of *Annas* of *Mommorancy* High Conſtable of *France*, both that he might relieve *Turin* with Victuals, Souldiers, and all things needful, as alſo to recover the Cities of that Province taken by the Marquis of *Guaſt* General of the Emperors Forces. I was in the Kings Army the Chirurgeon of Monſieur of *Montejan* General of the Foot. The Imperaliſts had taken the Straits of *Suze*, the Caſtle of *Villane*, and all the other paſſages; ſo that the Kings Army was not able to drive them from their Fortifications but by fight. In this conflict there were many wounded on both ſides with all ſorts of weapons, but chiefly with bullets. I will tell the truth, I was not very expert at that time in matters of Chirurgery; neither was I uſed to dreſs wounds made by Gunſhot. Now I had read in *John de Vigo*, that wounds made by Gunſhot were venenate or poiſoned, and that by reaſon of the Gunpowder; wherefore for their cure, it was expedient to burn or cauterize them with oyl of Elders ſcalding hot, with a little Treacle mixed therewith. But, for that I gave no great credit neither to the Author, nor remedy, becauſe I knew that cauſticks could not be poured into wounds, without exceſſive pain; I, before I would run a hazard, determined to ſee whether the Chirurgeons, who went with me in the Army, uſed any other manner of dreſſing to theſe wounds. I obſerved and ſaw that all of them uſed that method of dreſſing which *Vigo* preſcribes; and that they filled, as full as they could, the wounds made by Gunſhot with Tents and Pledgets dipped in this ſcalding Oyl, at the firſt dreſſing, which encouraged me to do the like to thoſe who came to be dreſſed of me. It chanced on a time, that by reaſon of the multitude that were hurt, I wanted this Oil. Now becauſe there were ſome few left to be dreſſed, I was forced, that I might ſeem to want nothing, and that I might not leave them undreſt, to apply a digeſtive made of the yolk of an egg, Oil of Roſes, and Turpentine. I could not ſleep all that night, for I was troubled in mind, and the dreſſing of the precedent day (which I judged unfit) troubled my thoughts; and I feared that the next day I ſhoud find them dead, or at the point of death by the poiſon of the wounds, whom I had not dreſſed with the ſcalding Oyl. Therefore I roſe early in the morning, I viſited my Patients, and beyond expectation, I found ſuch as I had dreſſed with a digeſtive only, free from vehemency of pain to have had good reſt, and that their wounds were not inflamed nor tumefied; but on the contrary, the others that were burnt with the ſcalding Oyl were feaveriſh, tormented with much pain, and the parts about their wounds were ſwoln. When I had many times tried this in divers others, I thought thus much, that neither I nor any other ſhould ever cauterize any, wounded with Gunſhot. When we firſt came to *Turin*, there was a Chirurgeon far more famous than all the reſt in artificially and happily curing wounds made by Gunſhot; wherefore I laboured with all diligence for two years time to gain his favour and love, that ſo at the length I might learn of him, what kind of medicine that was, which he honoured with the glorious title of Balſam, which was ſo highly eſteemed by him, and ſo happy and ſucceſsful to his Patients; yet could I not obtain it. It fell out a ſmall while after that the Marſhal of *Montejan* the Kings Lieutenant General there in *Piedmont* died; wherefore I went unto my Chirurgeon, and told him that I could take no pleaſure in living there, the favourer and *Mæcenas* of my ſtudies being taken away; and that I intended forthwith to return to *Paris*, and that it would neither hinder, nor diſcredit him to teach his remedy to me, who ſhould be ſo far remote from him. When he heard this, he made no delay, but preſently wiſhed me to provide two Whelps, one pound of Earth-worms, two pounds of Oyl of Lilies, ſix ounces of Venice Turpentine, and one ounce of *Aqua vitæ*. In my preſence he boiled the Whelps put alive into that Oyl, until the fleſh came from the bones; then preſently he put in the Worms, which he had firſt killed in White-wine, that they might ſo be cleanſed from the earthy droſs wherewith they are uſually repleat, and then he boiled them in the ſame Oyl ſo long, till they became dry, and had ſpent all their juyce therein: Then he ſtrained it through a towel without much preſſing; and added the Turpentine to it, and laſtly *Aqua vitæ*. Calling God to witneſs, that he had no other Balſam, wherewith to cure wounds made with Gunſhot, and bring them to ſuppuration. Thus he ſent me away as rewarded with a moſt precious gift, requeſting me to keep it as a great ſecret, and not to reveal it to any. When I came to *Paris*, I went to viſit *Silvius* the Kings Profeſſor of Phyſick, well known by name to all Scholars for his great Learning; he kept me long that ſo I might dine with him, and diligently enquires of me, if I had obſerved any new method of curing wounds made by Gunſhot, and Combuſtions, occaſioned by Gunpowder. Then I affirmed to him that Gunpower did not participate any thing of poyſon, for that none of thoſe things whereof it is compounded are poyſonous; which reaſon ought to free the whole compoſition from ſuſpicion of poyſon. And that experience confirmed this reaſon; for I had ſeen many Souldiers, who would drink a great quantity of this powder with Wine, becauſe they were perſwaded, that this drink would free them from malign ſymptoms when they were wounded; yet I give no credit to this perſwaſion; and laſtly, for that many without any harm, ſtrewed this powder upon rebellious Ulcers. For the Bullets, I affirm, that they cannot conceive ſuch heat as to become cauſtick. For if you ſhoot them out of a Gun againſt a hard ſtone, yet you may preſently take them up without any harm in your hands, though by ſtriking upon the ſtone, they ſhould become more hot. For the Combuſtions cauſed by Gunpowder, I obſerved no ſpecial nor peculiar remedy, which might make their cure different from other combuſtions. To which purpoſe I related this inſuing Hiſtory.

Lib. 1. de vulner. cap. 8.

What chance may do in finding out of remedies.

The deſcription of Oyl of Whelps.

Gunpowder not poyſonous.

Bullets ſhot out of a Gun do not burn.

A Hiſtory.

One of the Marſhal of *Montejan* his Kitchin-boys, fell by chance into a Caldron of Oyl, being even

even almoſt boiling hot; I being called to dreſs him, went to the next Apothecaries to fetch refrigerating medicines commonly uſed in this caſe: There was preſent by chance a certain old Countrey woman, who hearing that I deſired medicines for a Burn, perſwaded me at the firſt dreſſing, that I ſhould lay two raw Onions beaten with a little Salt; for ſo I ſhould hinder the breaking out of bliſters or puſtules, as ſhe had found by certain and frequent experience. Wherefore I thought good to try the force of her medicine upon this greaſie Scullion. I the next day found thoſe places of his body whereto the Onions lay, to be free from bliſters, but the other parts which they had not touched, to be all bliſtered.

A medicine hindering bliſtering in Burns or Scalds.

It fell out a while after, that a *German* of *Montejan* his Guard had his Flaſque full of Gunpowder ſet on fire, whereby his hands and face were grievouſly burnt: I being called, laid the Onions beaten, as I formerly told you, to the middle of his face, and to the reſt I laid medicines uſually applied to Burns. At the ſecond dreſſing I obſerved the part dreſſed with Onions quite free from bliſters and excoriation, the other being troubled with both; whereby I gave credit to the medicine. Beſides alſo, I laſtly told him this, that I had obſerved, that was the readieſt way to draw forth Bullets ſhot into the body, which ſets the Patient in the ſame poſture and ſite, as he was when he received his hurt. Which things when I had told him, together with many other handled at large in this Work, the good old man requeſted me to publiſh in print my opinions concerning theſe things, that ſo the erroneous and hurtful opinion of *Vigo* might be taken out of mens minds. To whoſe earneſt intreaty when I had aſſented, I firſt of all cauſed to be drawn and carved many Inſtruments fit to draw forth Bullets and other ſtrange bodes; then a ſhort while after I firſt publiſhed this Work in the year of our Lord, 1545. which when I found to be well liked and approved by many, I thought good to ſet it forth the ſecond time ſomewhat amended in the year, 1552. and the third time augmented in many particulars in the year, 1564. For I having followed many Wars, and detained as Chirurgeon in beſieged Cities, as *Mets* and *Heſden*, had obſerved many things under five Kings, whom I ſerved with diligence and content. I had learn'd many things from moſt expert Chirurgeons, but more from all learned Phyſicians, whoſe familiarity and favour for that purpoſe I always laboured to acquire with all diligence and honeſt arts; that ſo I might become more learned and skilful by their familiarity and diſcourſe, if there was any thing, eſpecially in this matter and kind of wounds, which was hid from me, or whereof I was not well aſſured. Of which number I have known very few, who have ſeen any thing in this kind of operation, either by ſtudy, or experience in Wars, have not thought that wounds made by Gunſhot ought to be dreſſed at the firſt with ſuppurative medicines, and not with ſcalding and cauſtick Oyl. For this I affirm, which then alſo I teſtified to this good man, that I have found very many wounds made in the fleſhy parts by Gunſhot, as eaſily cured as other wounds, which be made by contuſing things. But in the parts of the body where the Bullet meets with bones and nervous particles, both becauſe it tears and rends into ſmall pieces thoſe things which reſiſt, not only where it touches, but further alſo, through the violence of the blow, therefore it cauſeth many and grievous ſymptoms which are ſtubborn and difficult, and oft-times impoſſible to cure, eſpecially in bodies replete with ill humors, in an ill conſtitution of the Heaven and Air, ſuch as is hot, moiſt and foggy weather, which therefore is ſubject to putrefaction; and in like manner a freezing and cold ſeaſon, which uſes to mortifie the wounded parts not only of thoſe that are hurt with Bullets, but in like ſort with any other weapon; not only in bony and nervous particles, but alſo in muſculous. Whereby you may underſtand, that the difficulty of curing proceeds not from the venenate quality of the wounds; nor the combuſtion made by the Gunpowder, but the foulneſs of the Patients bodies, and the unſeaſonableneſs of the air.

A Hiſtory.

Wounds made by Gunſhot muſt be dreſſed with ſuppuratives.

The cauſes of difficulty in this cure.

For proof whereof, I will ſet down, that which I, not long agone, obſerved in a *Scotiſh* Nobleman the Earl of *Gordon*, Lord of *Achindon*, whom I cured at the appointment of the Queen-Mother. He was ſhot through both his thighs with a Piſtol, the bone being not hurt nor touched; and yet the two and thirtieth day after the wound he was perfectly healed, ſo that he had neither Feaver nor any other ſymptom which came upon the wound. Whereof there are worthy witneſſes, the Archbiſhop of *Glaſco*, the *Scotiſh* Ambaſſador, *Francis Brigart*, and *John Altine*, Doctors of Phyſick, as alſo *James Guillemeau*, the Kings Chirurgeon, and *Giles Buzet* a *Scotiſh* Chirurgeon, who all of them wondred that this Gentleman was ſo ſoon healed, no acrid medicine being applied. This I have thought good to recite and ſet down, that the Readers may underſtand, that I for thirty years ago had found the way to cure wounds made by Gunſhot, without ſcalding Oyl, or any other, more acrid medicine; unleſs by accident the illneſs of the Patients bodies, and of the air, cauſed any malign ſymptoms, which might require ſuch remedies beſides the regular and ordinary way of curing, which ſhall be more amply treated of in the following Diſcourſe.

A Hiſtory.

What makes Chirurgeons ſometimes uſe cauſticks in curing wounds made by Gunſhot.

Another Diſcourſe of theſe things, which King Charles *the Ninth, returning from the Expedition and Taking of* Rouen, *inquired of me concerning Wounds made by Gunſhot.*

FOr that it pleaſed your Majeſty one day, together with the Queen-Mother, the Prince of the *Rock upon Yon*, and many other Noblemen and Gentlemen, to inquire of me, What was the cauſe that the far greater part of the Gentlemen and common Souldiers which were wounded with Guns, and other warlike Engines, all remedies uſed in vain, either died, or ſcarce, and that with much difficulty recovered of their hurts, though in appearance they were not very great, and though the Chirurgeons diligently performed all things requiſite in their Art: I have made bold to premiſe this Diſcourſe to that Tractate which I determine to publiſh concerning wounds

The occaſion of writing this Diſcourſe.

Wounds made by Gunſhot; both to ſatisfie the deſires of the Princes and of many Gentlemen, as alſo the expectation they have of me, as being the Kings chief Chirurgeon (which place being given me by *Henry* II. *Charles* IX. a Son moſt worthy of ſuch a Father, had confirmed:) Neither make I any queſtion, but that many who too much inſiſt upon their own judgment, and not throughly conſider the things themſelves, will marvel, and think it far from reaſon; that I departing from the ſteps of my Anceſtors, and diſſenting wholly from the formerly received opinions, am far from their Tenents, who lay the cauſe of the malignity of wounds made by Gunſhot, upon the poyſon brought into the body by the Gunpowder, or mixed with the Bullets whilſt they are tempered or caſt. Yet for all this, if they will courteouſly and patiently weigh my Reaſons, they ſhall either think as I do, or at leaſt ſhall judge this my endeavour and pains, taken for publick good, not to be condemned nor contemned. For I ſhall make it evident by moſt ſtrong reaſons drawn out of the writings of the Ancients both Philoſophers and Phyſicians, and alſo by certain experiments of my own, and other Chirurgeons, that the malignity and contumacy which we frequently meet withal in curing wounds made by Gunſhot, is not to be attributed either to the poyſon carried into the body by the Gunpowder or Bullet, nor to burning imprinted in the wounded part by Gunpowder. Wherefore to come to our purpoſe, that opinion muſt firſt be confuted, which accuſeth wounds made by Gunſhot of poyſon, and we muſt teach, that there is neither any venenate ſubſtance, nor quality in Gunpowder: Neither, if there ſhould be any, could it empoyſon the bodies of ſuch as are wounded. Which that we may the more eaſily perform, we muſt examine the compoſition of ſuch powder, and make a particular inquiry of each of the ſimples, whereof this compoſition conſiſts, what eſſence they have, what ſtrength and faculties, and laſtly, what effects they may produce. For thus by knowing the ſimples, the whole nature of the compoſition conſiſting of them will be apparently manifeſt.

The argument of this Diſcourſe.

Gunpowder is not poyſonous.

The Simples which enter the compoſition of Gunpowder are only three, Charcoals of Sallow or Willow, or of Hemp-ſtalks, Brimſtone, and Salt-peter, and ſometimes a little *Aqua vitæ*. You ſhall find each of theſe, if conſidered in particular, void of all poyſon and venenate quality. For firſt in the Charcoal you ſhall obſerve nothing but drineſs, and a certain ſubtlety of ſubſtance, by means whereof it fires ſo ſuddenly, even as Tinder. Sulphur or Brimſtone is hot and dry, but not in the higheſt degree; it is often an oily and viſcid ſubſtance, yet ſo that it doth not ſo ſpeedily catch fire as the coal, though it retain it longer being once kindled, neither may it be ſo ſpeedily extinguiſhed. Salt-peter is ſuch, that many uſe it for Salt, whereby it is evidently apparent, that the nature of ſuch Simples is abſolutely free from all poyſon, but chiefly the Brimſtone (which notwithſtanding is more ſuſpected than the reſt.) For *Dioſcorides* gives Brimſtone to be drunk, or ſupped out of a rear Egg, to ſuch are Aſthmatick, troubled with the cough, ſpit up purulent matter, and are troubled with the yellow Jaundiſe. But *Galen* applies it outwardly to ſuch as are bitten by venemous Beaſts, to Scabs, Tetters and Leproſies. For the *Aqua vitæ*, it is of ſo tenuious a ſubſtance, that it preſently vaniſheth into the air, and alſo very many drink it, and it is without any harm uſed in trictions of the exterior parts of the body. Whence you may gather, that this powder is free from all manner of poyſon, ſeeing thoſe things whereof it conſiſts and is compoſed, want all ſuſpicion thereof. Therefore the German Horſe-men, when they are wounded with ſhot, fear not to drink off cheerfully half an ounce of Gunpowder diſſolved in Wine; hence perſwading themſelves freed from ſuch malign ſymptoms as uſually happen upon ſuch wounds; wherein whether they do right or wrong, I do not here determine. The ſame thing many French Souldiers forced by no neceſſity, but only to ſhew themſelves more couragious, alſo do without any harm; but divers with good ſucceſs uſe to ſtrew it upon Ulcers, ſo to dry them. Now to come to thoſe, who think that the venenate quality of wounds made by Gunſhot, ſprings not from the powder, but from the bullet wherewith ſome poyſon hath been commixt or joyned, or which hath been tempered or ſteeped in ſome poyſonous liquor: This may ſufficiently ſerve for a reply, that the fire is abundantly powerful to diſſipate all the ſtrength of the poyſon, if any ſhould be poured upon or added to the bullet. This much confirms my opinion which every one knows, the bullets which the Kings Souldiers uſed to ſhoot againſt the Towns-men in the ſiege of *Rouen*, were free from all poyſon; and yet for all that, they of the Town thought they were all poyſoned, when they found the wounds made by them, to be uncurable and deadly. Now on the other ſide, the Towns-men were falſly ſuſpected guilty of the ſame crime by the Kings Army, when as they perceived all the Chirurgeons labour in curing wounds made by the bullets ſhot from *Rouen*, to be fruſtrated by their contumacy and malign nature; each ſide judging of the magnitude and malignity of the cauſe, from the unhappy ſucceſs of the effect in curing. Even as among Phyſicians, according to *Hippocrates*, all diſeaſes are termed peſtilent, which ariſing from whatſoever common cauſe, kill many people; ſo alſo wounds made by Gunſhot, may in ſome reſpect be called peſtilent, for that they are more refractory and difficult to cure than others, and not becauſe they partake of any poyſonous quality, but by default of ſome common cauſe, as the ill complexions of the Patients, the infections of the air, and the corruption of meats and drinks. For by theſe cauſes wounds acquire an evil nature, and become leſs yielding to medicines. Now we have by theſe reaſons convinced of errour that opinion which held wounds made by Gunſhot for poyſonous: Let us now come to overthrow that which is held concerning their combuſtion.

Of what it is made.

Lib. 5. cap. 73. Lib. ſimp. cap. 36.

Bullets cannot be poyſoned.

As *Galen* notes *ad ſent. 20. & 21. ſect. 8. lib. 3. Epid.*

Firſt, it can ſcarce be underſtood how bullets which are commonly made of Lead, can attain to ſuch heat, but that they muſt be melted; and yet they are ſo far from melting, that being ſhot out of a Musket they will pierce through Armour and the whole body beſides, and yet remain whole, or but a little diminiſh'd. Beſides alſo, if you ſhoot them againſt a ſtone wall, you may preſently take them up in your hand without any harm, and alſo without any manifeſt ſenſe of heat; though their heat by the ſtriking upon the ſtone ſhould be rather increaſed, if they had any. Furthermore, a bullet ſhut into a barrel of Gunpowder, would preſently ſet it all on fire, if the bullet ſhould acquire ſuch heat by the ſhooting, but it is not ſo. For if any time the powder be fired

Woundsmade by Gunſhot are not burnt.

by

by ſuch an accident, we muſt not imagine that it is done by the bullet bringing fire with it, but by the ſtriking and colliſion thereof againſt ſome iron or ſtone that oppoſes or meets therewith, whence ſparks of fire proceeding as from a flint, the powder is fired in a moment. The like opinion we have of thatched houſes, for they are not fired by the bullet which is ſhot, but rather by ſome other thing, as linnen rags, brown paper, and the like, which rogues and wicked perſons faſten to their bullets. There is another thing which more confirms me in this opinion, which is, take a bullet of Wax, and keep it from the fire, for otherwiſe it would melt, and ſhoot it againſt an inch board, and it will go through it; whereby you may underſtand that bullets cannot become ſo hot by ſhooting, to burn like a cautery. But the orifices (may ſome ſay) of ſuch wounds are always black. This indeed is true, but it is not from the effect of heat brought thither by the bullet, but the force of the contuſion. Now the contuſion is exceeding great, both becauſe the bullet is round, and enters the body with incredible violence. Of which thoſe that are wounded will give you ſufficient teſtimony, for there is none of them, which thinks not preſently upon the blow, that as it were ſome poſt, or thing of the like weight, falls upon the affected member, whence great pain and ſtupidity poſſeſs the part, whereby the native heat and ſpirits are ſo much diſſipated, that a Gangrene may follow. But for the Eſchar which they affirm is made by the blow, and falls away afterwards, they are much miſtaken. For certain particles of the membranes are fleſh contuſed and torn by the violence of the bullet beguiles them; which preſently putrefying, and ſevered from the ſound parts by the power of nature and the ſeparating heat, which thing uſually happens in all great Contuſions. But for all that theſe ſo many and weighty reaſons may free the powder from all ſuſpicion of poyſon, and the bullet from all thought of burning; yet there are many who inſiſting upon Philoſophical Arguments raiſe new ſtirs. For (ſay they) the diſcharging a piece of Ordnance is abſolutely like Thunder and Lightning, which the rent and torn clouds caſt from the middle region upon the earth; wherefore the iron bullet which is ſhot out of the Canon muſt needs have a venenate and burning faculty. I am not ignorant that Lightning generated of a groſs and viſcous exhalation, breaking the cloud wherewith it is incompaſſed, never falls upon the earth, but brings fire with it, one while more ſubtile, another while more groſs, according to the various condition of the matter whence the exhalation hath ariſen. For *Seneca* writes that there are three ſeveral kinds of Lightning differing in burning, condition and plenty. One of them penetrates, or rather perforates by the tenuity of the matter of the object which it touches. The other with a violent impetuoſity breaks in ſunder, and diſſipates the objects, by reaſon it hath a more denſe, compact and forcible matter, like as Whirlwinds have. The third, for that it conſiſts of a more terreſtrial matter, burns what it touches, leaving behind it the impreſſion of the burning. Alſo I know that Lightning is of a peſtilent and ſtinking nature, occaſioned by the groſsneſs and viſcidity of the matter whereof it is; which matter taking fire, ſends forth ſo loathſom and odious a ſmell, that the very wild Beaſts cannot indure it, but leave their dens, if they chance to be touched with ſuch a Lightning. Beſides alſo we have read in the Northern Hiſtory of *Olaus Magnus*, that in ſome places after a Lightning, you ſhall find a whole Plain ſpread over with Brimſtone, which Brimſtone notwithſtanding is extinguiſhed, unprofitable, and of no efficacy. But grant theſe things to be thus, yet muſt we not therefore conclude, that the bullets of the great Ordnance carry poyſon and fire with them into the wounds. For though there be many things alike in Lightning and diſcharging great Ordnance, yet they have no ſimilitude either in matter or ſubſtance, but only in effects, whereby they ſhake, break in ſunder, and diſperſe the bodies which withſtand them: For Lightning and Thunder do it by means of fire, and oft-times of a ſtone generated in them, which is therefore termed, a Thunderbolt; but Ordnance by the bullet carried by the force of the air, more violently driving and forcing it forwards. Neither if any ſhould by more powerful Arguments force me to yield that the matter of Lightning and ſhooting of Ordnance are alike, yet will I not therefore be forced to confeſs that wounds made by Gunſhot are combuſt. For, according to *Pliny*, there are ſome Lightnings which conſiſting of a moſt dry matter, do ſhatter in ſunder all that withſtand them, but do not burn at all; others which are of ſomewhat a more humid nature, burn no more than the former, but only black ſuch things as they touch; laſtly, otherſome of a more ſubtile and tenuious matter, whoſe nature (as *Seneca* ſaith) we muſt not doubt to be divine, if but for this reaſon, that they will melt gold and ſilver, not harming the purſe; a ſword, not hurting the ſcabbard; the head of a lance, not burning the wood, and ſhed wine, not breaking the veſſel. According to which decree I can grant, that theſe Lightnings which break in ſunder, melt, and diſſipate, and perform other effects ſo full of admiration, are like in ſubſtance to the ſhot of great Ordnance; but not thoſe which carry with them fire and flame.

The reaſon why wounds made by Gunſhot look black.

The reaſons of our adverſaries refelled. *Quæſt. nat. l. 2. cap.* 49.

The ſtinking ſmell of Lightning.

Lib. 2. cap. 49.

The wonderful nature of ſome Lightning.

In proof whereof there comes into my mind a Hiſtory of a certain Souldier, out of whoſe thigh I remember I drew forth a bullet wrapped in the taffety of his breeches, which had not any ſign of tearing or burning. Beſides, I have ſeen many who not wounded, nor ſo much as touched, yet notwithſtanding have with the very report and wind of a Canon bullet, ſliding cloſe by their ears, faln down for dead, ſo that their members becoming livid and black, they have died by a Gangrene enſuing thereupon. Theſe and ſuch effects are like the effects of Lightning which we lately mentioned, and yet they bear no ſign nor mark of poyſon. From whence I dare now boldly conclude, that wounds made by Gunſhot are neither poyſoned, nor burnt. But ſeeing the danger of ſuch wounds in theſe laſt Civil-wars hath been ſo great, univerſal, and deadly to ſo many worthy perſonages and valiant men, what then may have been the cauſe thereof, if it were neither cumbuſtion, nor the venenate quality of the wound? This muſt we therefore now inſiſt upon and ſomewhat hardily explain. Thoſe who have ſpent all their time in the learning and ſearching out the myſteries of natural Philoſophy, would have all men think and believe, that the four Elements have ſuch mutual ſympathy, that they may be changed each into other; ſo that they not only undergo the alterations of the firſt qualities which are heat, coldneſs, drineſs and moiſture, but alſo the mutati-

A Hiſtory.

Why the wounds made by Gunſhot ſome few years agone were ſo deadly.

The cauſe of the tranſmutation of the Elements.

on

on of their proper substances by rarefaction and condensation. For thus the fire is frequently changed into air, the air into water, the water into air, and the water into earth; and on the contrary, the earth into water, the water into air, the air into fire; because these four first bodies have in their common matter enjoyed the contrary and fighting, yet first and principal, qualities of all.

* These Bellows here mentioned by the Author, are Balls made of Brass in form of a Pear, with a very small hole in their lesser ends: when you would fill them with water you must heat them very hot, and so the air which is contained in them will be exceedingly rarified, which by putting them presently into water will be condensate as much, & so will draw in the water to supply the place, *ne detur vacuum*. Then put them into fire, and it again rarifying the water into air will make them yield a strong continued and forcible blast. The cause of the report and blow of a Canon.

Whereof we have an example in the * Ball-bellows brought out of *Germany*, which are made of brass, hollow and round; and have a very small hole in them, whereby the water is put in, and so put to the fire; the water by the action thereof is rarified into air, and so they send forth wind with a great noise, and blow strongly assoon as they grow throughly hot. You may try the same with Chesnuts; which, cast whole and undivided into the fire, presently fly asunder with a great crack; because the watry and innate humidity turned into wind by the force of the fire, forcibly breaks his passage forth. For the air or wind raised from the water by rarefaction, requires a large place, neither can it now be contained in the narrow films, or skins of the Chesnut, wherein it was formerly kept. Just after the same manner Gunpowder being fired, turns into a far greater proportion of air according to the truth of that Philosophical Proposition, which saith, Of one part of earth, there are made ten of water; of one of water, ten of air; and of one of air, are made ten of fire. Now this fire, not possible to be pent in the narrow space of the Piece, wherein the powder was formerly contained, endeavours to force its passage with violence, and so casts forth the bullet lying in the way, yet so that it presently vanishes into air, and doth not accompany the bullet to the mark, or object, which it batters, spoils and breaks asunder. Yet the bullet may drive the obvious air with such violence, that men are often sooner touched therewith than with the bullet, and die by having their bones shattered and broken without any hurt on the flesh which covers them; which, as we formerly noted, it hath common with Lightning. We find the like in Mines, when the powder is once fired, it removes and shakes even Mountains of earth.

A History.

In the year of our Lord, 1562. a quantity of this powder which was not very great, taking fire by accident in the Arcenal of *Paris*, caused such a tempest that the whole City shook therewith, but it quite overturned divers of the neighbouring houses, and shook off the tiles and broke the windows of those which were further off; and to conclude, like a storm of Lightning, it laid many here and there for dead, some lost their sight, others their hearing, and othersome had their limbs torn asunder, as if they had been rent with wild Horses; and all this was done by the only agitation of the air into which the fired Gunpowder was turned. Just after the same manner as winds pent up in hollow places of the earth which want vents: For in seeking passage forth, they vehemently shake the sides of the earth, and raging with a great noise about the cavities, they make all the surface thereof to tremble; so that, by the various agitation one while up, another down, it overturns or carries it to another place. For thus we have read that *Megara* and *Ægina*, anciently most famous Cities of *Greece*, were swallowed up and quite over-turned by an Earthquake. I omit the great blusterings of the winds striving in the cavities of the earth, which represent to such as hear them at some distance, the fierce assailing of Cities, the bellowing of bullets, the horrid roarings of Lions, neither are they much unlike to the roaring reports of Canons. These things being thus premised, let us come to the thing we have in hand. Amongst things necessary for life, there is none causes greater changes in us than the air; which is continually drawn into the bowels appointed by nature, and whether we sleep, wake, or what else soever we do, we continual draw in and breath it out. Through which occasion, *Hippocrates* calls it Divine, for that breathing through this mundane Orb, it embraces, nourishes, defends and keeps in quiet peace all things contained therein, friendly conspiring with the Stars from whom a Divine vertue is infused therein. For the air diversly changed and affected by the Stars, doth in like manner produce various changes in these lower mundane bodies. And hence it is that Philosophers and Physicians do so seriously wish us to behold and consider the culture and habit of places, and constitution of the air, when they treat of preserving of health, or curing diseases. For in these the great power and dominion of the air is very apparent, as you may gather by the four Seasons of the year; for in Summer the air being hot and dry, heats and dries our bodies; but in Winter it produceth in us the effects of Winters qualities, that is, of cold and moisture; yet by such order and providence of nature, that although according to the varieties of Seasons our bodies may be variously altered, yet shall they receive no detriment thereby, if so be that the Seasons retain their seasonableness: From whence if they happen to digress, they raise and stir up great perturbations both in our bodies and minds; whose malice we can scarce shun, because they encompass us on every hand, and by the Law of Nature enter together with the air into the secret Cabinets of our Bodies both by occult and manifest passages. For who is he, that doth not by experience find both for the commodity and discommodity of his health, the various effects of winds, (wherewith the air is commixt) according as they blow from this or that Region, or quarter of the World. Wherefore seeing that the South-wind is hot and moist; the North-wind cold and dry; the East-wind clear and fresh; the West-wind cloudy, it is no doubt but that the air which we draw in by inspiration carries together therewith into the bowels the qualities of that wind which is then prevalent. Whence we read in *Hippocrates*, that changes of times, whether they happen by different winds, or vicissitude of Seasons, chiefly bring diseases; for northerly winds do condense, and strenghten our bodies, and make them active, well coloured and during, by resuscitating and vigorating the native heat. But southern winds resolve and moisten our bodies, make us heavy-headed, dull the hearing, cause giddiness, and make the eyes and body less agile; as the Inhabitants of *Narbon* find to their great harm, who are otherwise ranked among the most active people of *France*. But if we would make a comparison of the Seasons, and Constitutions of the year

The cause of an Earthquake.

How the air becomes hurtful.

Aphor. 17. *Sect.* 3.

by

by *Hippocrates* Decree, Draughts are more wholeſome and leſs deadly than rains; I judge, for that too much humidity is the mother of putrefaction, as you may learn by thoſe Countries which are blown upon by a wind from Sea. For in theſe fleſh which is kept for food, putrefies in the ſpace of an hour; and ſuch Ulcers as in other places are eaſily and quickly healed, do there by the conflux and collection of matter become inveterate and contumacious. Therefore as when the ſeaſons of the year ſucceſſively fall out agreeable to their nature, and when each ſeaſon is ſeaſonable, then either we are not ſick at all, or aſſuredly with leſs danger. So on the contrary, the perfect conſtitution and health of our bodies becomes worſe and decays, when the ſeaſons of the year are depraved and perverted in time and temper. Now ſeeing that theſe many years, the four ſeaſons of the year have wanted their ſeaſonableneſs, the Summer wanting his uſual heat, and the Winter its cold; and all things by moiſture and the dominion of the ſouthern winds have been humid and languid, I think there is none ſo ignorant in natural Philoſophy and Aſtrology, who will not think but that the cauſes of the malignity aud contumacy of thoſe diſeaſes which have ſo long afflicted all *France*, are to be attributed to the Air and Heavens. For otherwiſe, whence have ſo many peſtilent and contagious diſeaſes tyrannized over ſo many people of every age, ſex and condition? Whence have ſo many Catarrhs, Coughs, and heavineſſes of the head? So many Pleuriſies, Tumors, Small-poxes, Meaſſles and Itches, not admitting of digeſtion and remedies preſcribed by Art? Whence have we had ſo many venemous Creatures, as Toads, Graſhoppers, Caterpillers, Spiders, Waſps, Hornets, Beetles, Snails, Vipers, Snakes, Lizards, Scorpions, and Efts or Neuts, unleſs from exceſſive putrefaction which the humidity of the air, our native heat being liquid and dull, hath cauſed in us, and the whole Kingdom of *France*? Hence alſo proceeds the infirmity of our native heat, and the corruption of the blood and humors whereof we conſiſt, which the rainy Southwind hath cauſed with its ſultry heat. Wherefore in theſe laſt years I have drawn little blood, which hath not preſently ſhewed the corruption of its ſubſtance by the black or greeniſh colour, as I have diligently obſerved in all ſuch as I have bled by the direction of the Phyſicians, either for prevention of future, or cure of preſent diſeaſes. Whence it comes to paſs that the fleſhy ſubſtance of our bodies could not but be faulty both in temper and conſiſtence; ſeeing that the blood whence it is generated had drawn the ſeeds of corruption from the defiled air. Whence it fell out, that the wounds which hapned with loſs of ſubſtance could be ſcarce healed or united, becauſe of the depraved nature of the blood. For, ſo the wounds and ulcers of thoſe which are troubled with the Dropſie, whoſe blood is more cold or wholly wateriſh; ſo of leprous perſons, whoſe blood is corrupt; and laſtly, of all ſuch as have their bodies replete with ill juyce, or elſe are Cachectick, will not eaſily admit of cure. Yea aſſuredly, if but the very part which is hurt ſwerve from its native temper, the wound will not eaſily be cured. Therefore ſeeing all theſe things, both the putrefaction of the air, and depraved humors of the body, and alſo the diſtemper of the affected parts conſpired together to the deſtruction of the wounded; what marvel was it, if in theſe late Civil Wars, the wounds which were for their quantity ſmall, for the condition of the wounded part but little, have cauſed ſo many and grievous accidents, and laſtly death it ſelf? Eſpecially, ſeeing that the air which encompaſſeth us, tainted with putrefaction, corrupts and defiles the wounds by inſpiration and exſpiration, the body and humors being already diſpoſed, or inclined to putrefaction. Now there came ſuch a ſtink, which is a moſt aſſured ſign of putrefaction, from theſe wounds, when they were dreſſed, that ſuch as ſtood by could ſcarce endure it: Neither could this ſtink be attributed to the want of dreſſing, or fault of the Chirurgeon; for the wounds of the Princes and Nobility ſtunk as ill as thoſe of the common Souldiers. And the corruption was ſuch, that if any chanced to be undreſt for one day, which ſometimes hapned amongſt ſuch a multitude of wounded perſons, the next day the wound would be full of Worms. Beſides alſo, which furthermore argues a great putrefaction of humors, many had abſceſſes in parts oppoſite to their wounds, as in their left knee, when as the right ſhoulder was wounded; in the left arm, when as the right leg was hurt. Which I remember befel the King of *Navarre*, the Duke of *Nevers*, the Lord *Rendan*, and divers others. For all men had Nature ſo over-charged with abundance of vicious humors, that if it expelled not part thereof by Impoſthumes to the habit of the body, it certainly otherwiſe diſpoſed of it amongſt the inner parts of the body; for in diſſecting dead bodies, we obſerved that the Spleen, Liver, Lungs, and other Bowels were purulent, and hence it was that the Patients by reaſon of vapours ſent from them to the heart, were troubled with continual Feavers. But the liver and all the veinous parts being polluted, and ſo the generation of the laudable blood hindred, they languiſhed for want of fitting nouriſhment. But when the brain by vapours was drawn in to ſympathize with the reſt, they were moleſted with Ravenings and Convulſions. Wherefore if any thing ſucceeded unproſperouſly in ſo great malignancy of wounds, the Chirurgeon was not to be blamed, for that it were a crime to fight againſt God and the Air, wherein the hidden ſcourges of the divine Juſtice lye hid. Therefore if according to the mind of great *Hippocrates*, who commands to bring all contuſed wounds to ſuppuration, that ſo they may be healed, we endeavoured to cure with ſuch medicines wounds made with Gunſhot, and therefore contuſed; who can rightly be angry with us, if we performed it not ſo well, by reaſon of thoſe Putrefactions, Gangrenes and Mortifications which proceeded from the corrupt Air: For all that, we uſed not only ſuppuratives, but were oft-times forced to uſe other medicines; ſo long turning aſide from the cure of the diſeaſe, until we had orecome the ſymptoms which much indanger the Patient, and cuſtomarily happen upon ſuch wounds, as alſo upon thoſe which are made with a Sword, or any other kind of Weapon; as ſhall plainly appear in the following Treatiſe, to which it now ſeems high time that we betake our ſelves.

Fleſh quickly putrefies in maritime places.

In what bodies Ulcers and wounds are not eaſily cured.

An argument of great putrefaction of the humors.

All contuſed wounds muſt be brought to ſuppuration.

CHAP. I.

A diviſion of Wounds drawn from the variety of the wounded parts, and the Bullets which wound.

A diviſion of wounds from the variety of the wounded parts.

ALL wounds which are made in mans body by Gunſhot, whether ſimple or compound, are accompanied with contuſion, dilaceration, diſtemper and ſwelling. I ſay, all theſe poſſeſs either the noble parts, or ignoble, the fleſhy, nervous, or bony; ſome whiles with rending and tearing aſunder the larger veſſels, ſometimes without harming them. Now theſe wounds are only ſuperficiary, or elſe pierce deep and paſs quite through the Body. But there is alſo another diviſion of theſe wounds taken from the variety of the bullets wherewith they are made. For ſome bullets are bigger, ſome leſs, ſome between both; they are uſually made of Lead, yet ſometimes of Steel, Iron, Braſs, Tin, ſcarce any of Silver, much leſs of Gold. There ariſes no difference from their figure; for almoſt all kinds of wounds of this nature are round. From theſe differences, the Chirurgeon muſt take his Indications what to do, and what medicines to apply. The firſt care muſt be, that he think not theſe horrid and malign ſymptoms, which uſually happen upon theſe kinds of wounds, to ariſe from combuſtion, or poyſon carried with the bullet into the wounded part, and that for thoſe reaſons we have formerly handled at large. But rather let him judge they proceed from the vehemency of the contuſion, dilaceration and fracture, cauſed by the bullets, too violent entry into the nervous and bony bodies. For, if at any time the bullet ſhall only light upon the fleſhy parts, the wounds will be as eaſily cured, as any other wound uſually is, which is made with a contuſing and round kind of weapon, as I have often found by frequent experience, whilſt I have followed the Wars, and performed the part of a Chirurgeon to many Noblemen and common Souldiers, according to the counſel of ſuch Phyſicians as were there overſeers of the cure.

From the difference of bullets.

Wounds made by Gunſhot are uſually round.

CHAP. II.

Of the ſigns of Wounds made by Gunſhot.

Signs of wounds from their figure.

From their colour.

From the feeling of the blow.

From the bleeding.

From the heat of the wound.

Whence theſe wounds are ſo much contuſed.

WOunds made by Gunſhot are known by their figure, which is uſually round; by their colour, as when the native colour of the part decays, and inſtead thereof a livid, greeniſh, violet, or other colour ſucceeds; by the feeling or ſenſe of the ſtroke, when in the very inſtant of the receiving thereof, he feels a heavy ſenſe, as if ſome great ſtone, or piece of timber, or ſome ſuch other weighty thing had faln upon it; by the ſmall quantity of blood which iſſues out thereat, for when the parts are contuſed, within ſome ſmall while after the ſtroke they ſwell up, ſo that they will ſcarce admit a Tent, whence it is that the blood is ſtopped, which otherwiſe would flow forth of the orifice of the wound; by heat, which happens either by the violentneſs of the motion, or the vehement impulſion of the air, or the attrition of the contuſed parts, as the fleſh and nerves. Alſo you may conjecture that the wounds have been made by Gunſhot, if the bones ſhall be broken, and the ſplinters thereof by pricking the neighbouring bodies cauſe defluxion and inflammation. But the cauſe that the bullet makes ſo great a contuſion is, for that it enters the body without any points or corners, but with its round and ſpherical body, which cannot penetrate but with mighty force; whence it cometh to paſs that the wound looks black, and the adjacent parts livid: Hence alſo proceed ſo many grievous ſymptoms, as Pain, Defluxion, Inflammation, Apoſtumation, Convulſion Phrenſie, Palſie, Gangrene, and Mortification, whence laſtly Death enſues. Now the wounds do often caſt forth virulent and very much ſtinking filth, by reaſon of the great contuſion, and the rending and tearing of the neigbouring particles. A great abundance of humors flow from the whole body, and fall down upon the affected parts, which the native heat thereof being diminiſhed, forſakes, and preſently an unnatural heat ſeiſes upon it. Hitherto alſo tend an univerſal or particular repletion of ill humors, chiefly if the wounds poſſeſs the nervous parts, as the joynts. Verily neither a Stag with his horn, nor a flint out of a ſling can give ſo great a blow, or make ſo large a wound, as a leaden or iron bullet ſhot out of a Gun; as that which going with mighty violence, pierces the body like a Thunderbolt.

CHAP. III.

How theſe Wounds muſt be ordered, at the firſt dreſſing.

Strange bodies muſt firſt be pulled forth.

THe wound muſt forthwith be inlarged, unleſs the condition of the part reſiſt, that ſo there may be free paſſage forth, both for the *Sanies* or matter, alſo for ſuch things as are farced, or otherwiſe, contained therein; ſuch as are pieces of their Cloaths, Bombaſt, Linnen, Paper, pieces of Mail or Armour, Bullets, Hail-ſhot, ſplinters of Bones, bruiſed Fleſh, and the like, all which muſt be plucked forth with as much celerity and gentleneſs as may be. For preſently after the receiving of the wound the pain and inflammation are not ſo great, as they will be within a ſhort time after. This is the principal thing in performance of this work, that you place the Patient juſt in ſuch a poſture as he was in, at the receiving of the wound; for otherwiſe the various motion and turning of the muſcles will either hinder or ſtraiten the paſſage forth of the contained bodies. You ſhall, if it be poſſible, ſearch for theſe bodies with your finger, that ſo you may the more certainly and exactly perceive them. Yet if the bullet be entred ſomewhat deep in, then you ſhall ſearch for it with a round and blunt probe, leſt you put the Patient to pain; yet oftentimes you ſhall ſcarce by this means find the Bullet. As it happened to the Marſhal of *Briſſac* in the Siege of *Perpignan*, who was wounded in his right ſhoulder with a bullet, which the Chirur-

The manner how to draw them forth.

geons

geons thought to have entered into the capacity of his body. But I, wiſhing the Patient to ſtand juſt in the ſame manner as he did when he received the wound, found at length the place where the Bullet lay, by gently preſſing with my fingers, the parts near the wounds, and the reſt which I ſuſpected; as alſo by the ſwelling, hardneſs, pain and blackneſs of the part, which was the lower part of the ſhoulder near unto the eighth or ninth ſpondil of the back. Wherefore the bullet being taken forth by making inciſion in the place, the wound was quickly healed, and the Gentleman recovered. You ſhall obſerve this, and rather believe the judgment of your fingers, than of your Probe.

CHAP. IV.

A Deſcription of fit Inſtruments to draw forth Bullets and other ſtrange Bodies.

BOth the magnitude and figure of Inſtruments fit for drawing forth of bullets and other ſtrange bodies, are various according to the diverſity of the incident occaſions. For ſome are toothed, others ſmooth, others of another figure and bigneſs; of all which ſorts the Chirurgeon muſt have divers in a readineſs, that he may fit them to the bodies and wounds, and not the wounds and bodies to his Inſtruments.

The Delineation of ſuch like Inſtruments.

The ſtrait Cranes bill being alſo toothed, fit for drawing forth hail-ſtones, pieces of armour, ſplinter of bones and ſuch things as lye deep within.

The Ducks-bill.



This Ducks-bill hath a large, round and toothed cavity in the end, for ſo it more eaſily taketh hold of the Bullet when it lies amongſt much fleſh.

The crooked Cranes-bill, with teeth like a Saw.

A toothed Crows-bill.

Another Inſtrument fit for drawing forth of Bullets, which may be termed a Catch-bullet.



A *Shews the Trunk.*
B *Shews the rod, or ſtring, which opens and ſhuts the joynt.*
C *The joynt.*

Another Catch-bullet called a Lizards-noſe, made for drawing out of Bullets, which are ſomewhat flatted, by ſtriking upon a bone.

The Parrots-beak is made for drawing forth pieces of mail thruſt into the fleſh, or bones; and this is the figure thereof.

The Swans-bill opens with a ſcrew; you may with this dilate the wounds, and ſo put in a ſtrait Cranes-bil, as pincers to pluck forth ſtrange bodies. The figure of both are here expreſt.



A ſhews the ſcrew-pin. B *The hollowed part which receives the round part noted with* C, *which is opened and ſhut by the ſcrew.* DD *Falls or ſtays, which govern the running branch.*

But if theſe ſtrange bodies, eſpecially Bullets and Hail-ſhot, be not too deep in the wound, they may be taken forth with your Levatory, or elſe by the help of theſe Gimblets. Theſe Gimblets are ſcrewed into their pipes, or canes, and enter with their ſcrewed points into the Bullets, if that they be of Lead or Tin, and of no harder metal; and ſo being faſtned in them, bring them out with them.

The figure of the Gimblet, with his Pipe or Cane.

Beſides the Swans-bill which we lately mentioned, there are alſo other Inſtruments fit to dilate and open the wounds, therefore called Dilaters, by whoſe help the wound may be held open, that ſo the hidden bodies may be ſeen; for when you preſs together the two ends of this Inſtrument, the other two open and dilate themſelves. You may alſo uſe them in dilating divers other parts of the body, as the Noſtrils, Fundament, and ſuch like.

Dilaters.



The Inſtruments which follow are called Seton-needles, or Probes; whoſe uſe is, to draw through a Flamula, ſo to keep the wound open, that you may the better take forth any ſtrange body. Beſides alſo we uſe the ſame Needles to ſearch, or as it were to ſound the deepneſs of the wounds,

and

and to find out the bullets. For they cannot put one to much pain becauſe they have ſmooth and round ends. So alſo all Probes wherewith we ſearch for bullets, muſt have ſomewhat large, ſmooth and round ends. For ſeeing that the verges of the Wound meet together preſently after the hurt, if the Probes be too ſmall or ſlender, they will ſtick in the inequality of the fleſh, neither will they be able to come to the Bullet. But if they be ſharp and pointed, they will cauſe and renew the pain by pricking the fleſh they meet withal, and ſo hinder your intention of finding the Bullet: Now you muſt be furniſhed with theſe Inſtruments of a different length, according to the various thickneſs of the parts; for you cannot put any through the thigh but ſuch as are of a good length.

What Probes fit to ſearch theſe wounds.

Probes for to put flamula's through a Wound withal.



CHAP. IX.

What dreſſing muſt firſt be uſed, after the ſtrange bodies are pluck'd or drawn out of the Wound.

WHen the ſtrange bodies are drawn or pluck'd out of the wound, by thoſe means we have formerly recited, the chief of the cure muſt be to heal the contuſion, and amend the diſtemper of the air if it be hot and moiſt, that is, ſubject to putrefaction. This ſhall be done by medicines taken inwardly, applied outwardly, and put into the wound. Things to be inwardly uſed in diet and Pharmacy I leave to the judgment of learned Phyſicians; for the particular and topick medicines, (unleſs from the preſent conſtitution of the air, the condition of the wounded part, or from ſome other cauſe, there being a danger of a Gangrene) you muſt uſe ſuppuratives as you uſually do in contuſions; ſuch as are oyls of Whelps, and that which we call a Digeſtive; you muſt chiefly forbear ſuppuratives, when as the wounded part is of a nervous nature. For all nervous parts require drier medicines then fleſhy, as we have formerly delivered ſpeaking of wounds of the joynts; wherefore in wounds of the joynts and nervous parts you ſhall uſe more Venice Turpentine than oyl. *Laurentius Jolertus* the Kings Phyſician and Chancellor of the Univerſity of *Mompelier*, in a Treatiſe which he writ of wounds made with Gunſhot, forbids the uſe of Eſcharoticks both actual and potential, in theſe wounds, if ſimple; for that they induce pain, inflammation, a feaver, gangrene, and other deadly ſymptoms. Beſides alſo, an Eſchar will hinder ſuppuration, which is to be deſired in this kind of wounds, that ſo the contuſed fleſh may be ſevered from the ſound, leſt it be drawn to putrefaction by contagion. Which eaſily happens when an Eſchar is drawn, as a bar over it, for then the excrementitious humor remains longer in the part, and the putredinous vapours, hindred from paſſing forth, are increaſed, and carried from the leſſer veſſels to the bigger, and ſo over all the Body. Wherefore, when you ſuſpect putrefaction, letting alone ſuppuratives, uſe in the firſt place ſuch things as reſiſt putrefaction, as this following Oyntment. ℞ *Pulver. alumin. rochæ, viridis æris, vitrioli Romani, mellis roſat. an.* ℥ ij. *aceti boni quantum ſufficit, bulliant omnia ſimul ſecundum artem, & fiat medicamentum ad formam mellis.* This by reaſon of the heat and ſubtlety of the ſubſtance, hath a faculty to induce and attenuate the humors, as alſo to call forth the native heat drawn in and diſſipated by the violent and forcible entrance of the bullet into the body; furthermore alſo it corrects the venemous contagion of the virulent humor. Now this medicine ſhall be uſed, diſſolved in Vinegar or *Aqua vitæ*, and be put into the wound with tents or pledgets. The tents which ſhall be uſed at the firſt dreſſing muſt be ſomewhat long and thick, that by dilating the wound, they may make way for application of other remedies; otherwiſe you may make injection with a Syringe, that ſo it may penetrate the more powerfully. But this deſcribed *Ægyptiacum* ſhall be tempered according to the condition of the affected parts, for the nervous parts will be offended with it as being too acrid; but it may be qualified by admixture of oyl of Turpentine and Saint Johns-wort. Alſo we may well be without this *Ægyptiacum* when there is no ſuch peſtilent conſtitution of the air, as was ſeen in the late Civil Wars. After the uſe of *Ægyptiacum* you ſhall with emollient and lenitive medicines procure the falling away of the Eſchar, and ſuch a medicine is this following Oyl, being ſomewhat more than warm. ℞ *Olei violati lib.* iiij. *in quibus coquantur catelli duo nuper nati, uſque ad diſſolutionem oſſium, addendo vermium terreſtrium, ut decet præparatorium,* ℔ i. *Coquantur ſimul lento igne, deinde fiat expreſſo ad uſum, addendo terebinth. venet.* ℥ iij. *Aqua vitæ* ℥ i. This Oyl hath a wonderful force to aſſwage pain, to bring the wound to ſuppuration, and cauſe the falling away of the Eſchar. This enſuing Oyl is made more eaſily. ℞ *Olei ſeminis lini, & lilior. an.* ℥ iij. *Unguent. baſilic.* ℥ i. *Liquefiant ſimul & fiat medicamentum*: Put of this a ſufficient quantity into the wound; for this being applied indifferent hot, hath power to aſſwage pain, to ſoften and humect the orifice of the wound, and help forwards ſuppuration, which is the true manner of curing theſe kinds of wounds, accor-

A caution in the uſe of ſuppuratives.

Why Eſcharoticks muſt be eſchewed in theſe kinds, if they be ſimple.

How an Eſchar may cauſe putrefaction.

The deſcription of an *Ægyptiacum.*

How and when to temper this *Ægyptiacum.*

The oil of Whelps a digeſtive. Anodyne, and fit medicine to procure the falling away of an Eſchar.

ding to the rule of *Hippocrates*, which wiſhes every contuſed wound to be preſently brought to ſuppuration, for ſo it will be leſs ſubject to a Phlegmon; and beſides, all the rent and bruiſed fleſh muſt putrefie, diſſolve and turn to quitture, that new and good fleſh may be generated inſtead thereof. *Laurentius Iaubertus* much commends this following medicine, of whoſe efficacy, as yet I have made no trial. ℞ *Pulver. mercur. bis calcinati,* ℥ i. *Adipis porci recentis, vel butyri recentis,* ℥ viij. *Camphoræ in aqua vitæ diſſolutæ,* ʒ ij. *Miſce omnia ſimul, addendo tantillum olei liliorum, aut lini.* Experience taught him, and Reaſon alſo ſhews, that this kind of remedy is very commendable; for the powder of Mercury, if mixed with a groſs and humecting matter, doth in a ſhort ſpace turn the bruiſed fleſh into *Pus*, without cauſing any great pain. For the Camphire, whether it be hot or cold, in temper, it much conduces to that purpoſe, by reaſon of the ſubtlety of the parts whereof it conſiſts. For by means of this quality the medicines enter with more facility into the affected bodies, and perform their parts; beſides alſo, Camphire reſiſts Putrefaction. Some drop into the wound *Aqua vitæ*, wherein they have diſſolved ſome calcined vitriol. Which kind of remedy is not ſuppurative, but yet much reſiſts putrefaction, ſo that we may uſe it with good ſucceſs, when the weather is hot, moiſt and foggy. But when the wound is made very near at hand, it cannot but be burnt by the flame of the powder; in which, remedies uſed for burns, will be uſeful, not omitting ſuch as are fit for contuſions. But for thoſe parts which lye next the wound, you ſhall not, unleſs at the firſt dreſſing, apply refrigerating and aſtringent things, but rather emollient and ſuppurative. For thoſe things which have a refrigerating faculty, weaken the part, and hinder ſuppuration. For aſtringents conſtipate the skin, which is the cauſe, that, the putrid vapours ſhuts up and hindred from tranſpiration and paſſage forth, a Gangrene and Mortification eaſily ſeiſe upon the part. But if the contuſion be great, and diffuſe it ſelf more largely over the fleſh, the part muſt be much ſcarified; that ſo the contuſed and concrete blood, and therefore ſubject to putrefaction, may be evacuated. But for thoſe parts, which ſomewhat farther diſtant from the wound, encompaſs the contuſed fleſh, they require refrigerating and ſtrengthening medicines, ſo to hinder the falling down and ſettling of the humor in that part, which is this enſuing medicine. ℞ *pul. boli armen. ſanguin. Dracon. Myrrhæ, an.* ℥ i. *ſucci ſolan. ſempervivi, portulac. an.* ℥ i ß. *albumin* iiij. *ovorum. oxyrhodin. quantum ſufficit; fiat linimentum, ut decet.* You may uſe this and the like until the ſuſpected ſymptom be paſt fear. Neither muſt you have leſs care, of binding up and rolling the part, than of your medicines; for it doth not a little conduce to the cure, to bind it ſo fitly up as it may be without pain. The wound at the beginning of the cure, muſt be dreſſed but once in four and twenty hours, that is, until the wound be come to ſuppuration; but when the quitture begins to flow from it, and conſequently the pain and Feaver are increaſed, it ſhall be dreſt twice a day, that is, every twelve hours. And when the quitture flows more abundantly than uſual, ſo that the collection thereof is very troubleſome to the Patient, it will be requiſite to dreſs it every eight hours; that is, thrice a day. Now when as this abundant efflux is ſomewhat ſlaked, and begins to decreaſe, it will ſuffice to dreſs it twice a day. But when the Ulcer is filled with fleſh, and conſequently caſts forth but little matter, it will ſerve to dreſs it once a day, as you did at the firſt.

Lib. de ulcer.

The faculties of the powder of Mercury.

The force of calcined vitriol.

How wounds made by Gunſhot may be combuſt.

Scarification.

An Aſtringent repelling medicine.

The binding up.

How oft the wound muſt be dreſt in a day.

CHAP. VI.

How you ſhall order it at the ſecond dreſſing.

AT the ſecond and following dreſſings, unleſs you ſuſpect putrefaction, and a Gangrene, you ſhall only put into the wound ſome of the Oyls formerly deſcribed, adding to them the yolks of ſome eggs and a little Saffron; and uſe this medicine, until the wound come to perfect ſuppuration. Here you muſt note this, that theſe kinds of wounds are longer before they come to ſuppuration, than other wounds made by any other ſort of Weapon; both for that the bullet, as alſo the air which it violently carries before it, by much bruiſing the fleſh, on every ſide, diſſipates the native heat, and exhauſts the ſpirits of the part. Which things hinder digeſtion, and often cauſe the matter to ſtink, as alſo many other pernicious ſymptoms. Yet moſt uſually *Pus* or quitture appears within three or four days, ſooner and later according to the various complexion and temperament of the Patients bodies, and the condition of the ambient air in heat and cold. Then by little and little you muſt come to deterſives, adding to the former medicine ſome Turpentine waſhed in Roſe, Barley, or ſome other ſuch like water, which may waſh away the biting thereof. If the incompaſſing air be very cold, you may, to good purpoſe, add ſome *Aqua vitæ*; for by *Galen*'s preſcript, we muſt not uſe hot medicines in Winter, and leſs hot in Summer. Then in the next place uſe deterſives; as, ℞ *Aquæ decoctionis hordei quantum ſufficit, ſucci plantaginis, apii, agrimon. centaurei minoris, an.* ℥ i. *Bulliant omnia ſimul; in fine decoctionis adde terebinthinæ venetæ* ℥ iij. *Mellis roſat.* ℥ ij. *farin. hordei* ʒ iij. *Croci* ϑ i. Let them all be well mixed together and make a Mundificative of an indifferent conſiſtence. Or, ℞ *Succi clymeni, plantag. abſinth. apii, an.* ℥ ij. *Tereb. venet.* ℥ iiij. *Syrup. abſinth. & mellis roſ. an.* ℥ iij. *Bulliant omnia ſecundum artem poſtea colentur in colatura, adde pulver. aloes, maſtiches, Ireos Florent. far. hord. an* ʒ i. *Fiat Mundificativum ad uſum dictum.* Or, ℞ *Terebinth. venet. lotæ in aq. roſ.* ℥ v. *Olei roſ.* ℥ i. *Mellis roſ.* iij *myrrhæ, aloes, maſtich. ariſtoloch. rotundæ. an.* ʒ i ß. *Far. hord.* ʒ iij. *Miſce.* Make a Mundificative, which you may put into the wound with Tents, but ſuch as are neither too long, nor thick, leſt they hinder the evacuation of the quitture and vapours, whence the wounded part will be troubled with eroſion, pain, defluxion, inflammation, abſceſs, putrefaction; all which ſeverally of themſelves, as alſo by infecting the noble parts, are troubleſome both to the part affected, as alſo to the whole body beſides. Wherefore you ſhall put into the wound no Tents, unleſs ſmall ones, and of an indifferent conſiſtence; leſt (as I ſaid) you hinder the paſſing forth of the matter, or by their hard preſſing of the part, cauſe pain, and ſo draw on malign ſymptoms. But ſeeing Tents are uſed both to keep

Why wounds made by Gunſhot are ſo long before they come to ſuppuration.

Why Turpentine muſt be waſhed. *Gal. l. 3. Meth.*

A detergent medicine.

Why Tents muſt be neither too long nor thick.

keep open a wound so long, until all the strange bodies be taken forth, as also to carry the medicines, wherewithal they are anointed, even to the bottom of the wound: Now if the wound be sinuous and deep, that so the medicine cannot by that means arrive at the bottom and all the parts thereof, you must do your business by injections made of the following decoction. ℞ *aq. hord. lib.* iiij. *agrimon. centaur. minor. pimpinellæ, absinth. plantag. M.* ß. *Rad. aristoloch. rotund.* ʒ ß. *Fiat decoctio ad lib.* j. *in colatura expressa dissolve aloes hepatica* ʒ iiij. *Mellis ros.* ʒ ij. *Bulliant modicum.* Inject some of this decoction three or four times into the wound, as often as you dress the Patient; and if this shall not be sufficient to cleanse the filth, and waste the spongious, putrid and dead flesh, you shall dissolve therein as much *Ægyptiacum* as you shall think fit for the present necessity, but commonly you shall dissolve an ounce of *Ægyptiacum* in a pint of the decoction. Verily *Ægyptiacum* doth powerfully consume the proud flesh which lies in the capacity of the wound; besides also, it only works upon such kind of flesh. For this purpose, I have also made trial of the powder of Mercury and burnt Alum equally mixed together, and found them very powerful, even as sublimate, or Arsenick (but that these cause not such pain in their operation.) I certainly much wonder at the largeness of the Eschar which arises by the aspersion of these powders. Many Practitioners would have a great quantity of the injection to be left in the cavities of sinuous Ulcers, or wounds; which thing I could never allow of. For this contained humor causeth an unnatural tension in these parts, and taints them with superfluous moisture, whereby the regeneration of flesh is hindered; for that every Ulcer as it is an Ulcer, requires to be dryed, in *Hippocrates* opinion. Many also offend in the too frequent use of Tents; for as they change them every hour, they touch the sides of the wound, cause pain, and renew other malign symptoms; wherefore such Ulcers as cast forth more abundance of matter, I could wish rather to be dressed with hollow Tents, like those I formerly described to be put into wounds of the Chest. You shall also press a linnen boulster to the bottom of the wound, that so the parts themselves may be mutually condensed by that pressure and the quitture thrust forth; neither will it be amiss to let this boulster have a large hole fitted to the orifice of the wound and end of the hollow Tent and Pipe, that so you may apply a spunge for to receive the quitture, for so the matter will be more speedily evacuated and spent, especially if it be bound up with an expulsive ligature, beginning at the bottom of the Ulcer, and so wrapping it up to the top. All the the boulsters and rowlers, which shall be applied to these kinds of wounds, shall be dipped in Oxycrate or Red-Wine, so to strengthen the part, and hinder defluxion. But you must have a special care, that you do not bind the wound too hard, from hence will arise pain, hindering the passage forth of the putredinous vapours and excrements, which the contused flesh casts forth; and also fear of an *Atrophia*, or want of nourishment, the alimentary juyces being hindred from coming to the part.

When you must use injections.

An injection.

The quantity of *Ægyptiacum* to be used in an injection.

Why none of the injection must be left in the wound.

Hollow Tents or Pipes.

The manner of binding up the wound.

CHAP. VII.

By what means strange Bodies, left in at the first dressing, may be drawn forth.

IT divers times happens, that certain splinters of bones, broken and shattered asunder by the violence of the stroke, cannot be pulled forth at the first dressing, for that they either do not yield or fall away, or else cannot be found by the formerly described Instruments. For which purpose this is an approved medicine to draw forth that which is left behind. ℞ *Radic. Ireos Floren. panac. & capper. an.* ʒ iij. *Aristoloch. rotund. mannæ, thuris, an.* ʒ i. *In pollinem redacta, incorporentur cum melle rosar. & terebinth. venet. an.* ʒ ij. Or ℞ *Resin. pini siccæ* ʒ iij. *Pumicis combusti & extincti in vino albo, radic. Ireos, aristolochiæ, an.* ʒ ß. *Thuris* ʒ i. *Squamæ æris,* ʒ ij. *in pollinem redigantur, incorporentur cum melle rosato, fiat medicamentum.*

Two causes that make strange bodies hard to be taken forth.

CHAP. VIII.

Of Indications to be observed in this kind of Wounds.

THE Ulcer being cleansed and purged, and all strange bodies taken forth; Natures endeavours to regenerate flesh, and cicatrize it, must be helped forwards with convenient remedies, both taken inwardly, and applied outwardly. To which things we may be easily and safely carried by indications drawn, first from the essence of the disease, then from the cause; if as yet present it nourish the disease. For that which *Galen* says, *Lib.* 3. *Meth.* that no Indication may be taken from the primitive cause and time; must be understood of the time past, and the cause which is absent. And then from the principal times of the disease, the beginning, increase, state, and declination; for each of these four require their remedies. Others are taken from the temperament of the Patient, so that no Chirurgeon need doubt, that some medicines are fit for cholerick, others some for phlegmatick bodies. Hither refer the indication taken from the age of the Patient; also it is drawn from his diet, for no man must prescribe any slender diet to one who is always feeding, as to him who is accustomed to eat but once or twice a day. Hence it is that a diet consisting only of Panada's is more fitter for Italians than for French men; for we must give somewhat to custom, which is as it were another nature. Vocations and daily exercises, are referred to diet: For other things befit Husbandmen and Labourers, whose flesh is dense, and skin hardned by much labour, than idle and delicate persons. But of all other, have diligent regard of that indication which is drawn from the strength of the Patient; for we must presently, (all else being neglected) succour the fainting, or decaying strength; wherefore if it be needful to cut off a member that is putrefied, the operation must be deferred if the strength of the Patient be so dejected, that he cannot have it performed without manifest danger of his life. Also indication

The Indication which is drawn from the strength of the Patient is the chiefest of all other.

may

may be drawn from the incompaſſing air, under which alſo is comprehended that, which is taken from the ſeaſon of the year, region, the ſtate of the air and ſoil, and the particular condition of the preſent and lately by-paſt time. Hence it is we read in *Guido*, that wounds of the head are cured with far more difficulty at *Paris*, than at *Avignon*; where, notwithſtanding on the contrary, the wounds of the legs are cured with more trouble, than at *Paris*; the cauſe is, the air is cold and moiſt at *Paris*; which conſtitution ſeeing it is hurtful to the brain and head, it cannot but muſt be offenſive to the wounds of theſe parts. But the heat of the ambient air at *Avignon*, attenuates and diſſolves the humors, and makes them flow from above downwards. But if any object that experience contradicts this opinion of *Guido*, and ſay, that wounds of the head are more frequently deadly in hot Countreys; let him underſtand that this muſt not be attributed to the manifeſt and natural heat of the air, but to a certain malign and venenate humor, or vapour diſperſed through the air, and raiſed out of the Seas; as you may eaſily obſerve in thoſe places of *France* and *Italy* which border upon the *Mediterranean* Sea. An indication may alſo be drawn from the peculiar temper of the wounded parts, for the muſculous parts muſt be dreſſed after one, and the bony parts after another manner. The different ſenſe of the parts, indicates and requires the like variety of remedies; for you ſhall not apply ſo acrid medicines to the nerves and tendons, as to the ligaments which are deſtitute of ſenſe. The like reaſon alſo for the dignity and function of the parts needful for the preſervation of life; for oft-times wounds of the brain, or ſome other of the natural and vital parts, for this very reaſon that they are dehixed in theſe parts, divert the whole manner of the cure, which is uſually and generally performed in wounds. Neither that without good cauſe, for oft-times from the condition of the parts, we may certainly pronounce the whole ſucceſs of the diſeaſe; for wounds which penetrate into the ventricles of the brain, into the heart, the large veſſels, the cheſt, the nervous parts of the midriff, the liver, ventricles, ſmall guts, bladder, if ſomewhat large are deadly; as alſo thoſe which light upon a joynt in a body repleat with ill humors, as we have formerly noted. Neither muſt you neglect that indication which is drawn from the ſituation of the part, and the commerce it hath with the adjacent parts, or from the figure thereof; ſeeing that *Galen* himſelf would not have it neglected. But we muſt conſider in taking theſe forementioned Indications, whether there be a compoſition, or complication of the diſeaſes; for as there is one and that a ſimple indication, of one and that a ſimple diſeaſe, ſo muſt the indication be various of a compound and complicate diſeaſe. But there is obſerved to be a triple compoſition or complication of affects beſides nature: For either a diſeaſe is compounded with a diſeaſe, as a wound, or a phlegmon with a fracture of a bone; or a diſeaſe with a cauſe, as an ulcer with a defluxion; or a diſeaſe with a ſymptom, as wound with pain or bleeding. It ſometimes comes to paſs, that theſe three, the diſeaſe, cauſe and ſymptome, concur in one caſe or affect. In artificially handling of which, we muſt follow *Galen*'s counſel, who wiſhes in complicated and compounded affects, that we reſiſt the more urgent; then let us withſtand the cauſe of the diſeaſe; and laſtly that affect, without which the reſt cannot cannot be cured. Which counſel muſt well be obſerved; for in this compoſure of affects, which diſtracts the Emperick; on the contrary, the rational Phyſician hath a way preſcribed in a few and theſe excellent words, which if he follow in his order of cure, he can ſcarce miſs to heal the Patient. Symptoms truly as they are ſymptoms, yield no indication of curing, neither change the order of the cure; for when the diſeaſe is healed, the ſymptom vaniſhes as that which follows the diſeaſe, as a ſhadow follows the body. But ſymptoms do oftentimes ſo urge and preſs; that perverting the whole order of the cure, we are forced to reſiſt them in the firſt place, as thoſe which would otherwiſe increaſe the diſeaſe. Now all the formerly mentioned indications may be drawn to two heads; the firſt is, to reſtore the parts to its native temper; the other is, that the blood offend not either in quantity or quality; for when thoſe two are preſent, there is nothing which may hinder the repletion or union of wounds nor ulcers.

Why wounds of the head at *Paris*, and of the legs at *Avignon* are hard to be cured.

An indication to be drawn from the quick and dull ſenſe of the wounded part.

Gal.lib.7.Meth. & 2. ad Glauc.

Gal.l.7. Meth.

How and when we muſt take indication of curing from a ſymptome.

CHAP. IX.

What remains for the Chirurgeon to do in this kind of Wounds.

THe Chirurgeon muſt firſt of all be skilful, and labour to aſſwage pain, hinder defluxions, preſcribe a diet in thoſe ſix things we call not-natural, forbidding the uſe of hot and acrid things as alſo of Wine; for ſuch attenuate humors, and make them more aptfor defluxion. Therefore at the firſt let his diet be ſlender, that ſo the courſe of the humors may be diverted from the affected part; for the ſtomach being empty, and not well filled, draws from the parts about it, whereby it conſequently follows, that the utmoſt and remoteſt parts are at the length evacuated; which is the cauſe, that ſuch as are wounded, muſt keep ſo ſpare a diet for the next days following. Venery is very pernicious for that it inflames the ſpirits and humors far beyond other motions; whereby it happens that the humors waxing hot, are too plentifully carried to the wounded and over-heated part. The bleeding muſt not be ſtanched preſently upon receiving of the wound, for by the more plentiful efflux thereof, the part is freed from danger of inflammation and fulneſs. Wherefore if the wound bleed not ſufficiently at the firſt, you ſhall the next day open a vein, and take blood according to the ſtrength and plenitude of the Patient: for there uſually flows no great ſtore of blood from wounds of this nature; for that by the greatneſs of the contuſion and vehemency of the moved air, the ſpirits are forced in, as alſo I have obſerved in thoſe who have one of their limbs taken away with a Cannon bullet. For in the time when the wound is received; there flows no great quantity of blood, although there be large veins and arteries torn in ſunder thereby. But on the fourth, fifth, ſixth, or ſome more days after, the blood flows in greater abundance, and with more violence, the native heat and ſpirits returning into the part. The belly muſt be ſo qualified, that he may have at the leaſt one ſtool a day, either by Nature

Why ſuch as are wounded muſt keep a ſlender diet.

Why we muſt open a vein in ſuch as are wounded by Gunſhot.

ture, or Art; and if by Art, then rather with a Clyſter than purging medicines taken by the mouth, for that the agitation of humors, chiefly in the firſt days of the diſeaſe, is to be ſuſpected, leſt we increaſe the defluxion falling down upon the wounded part. Yet *Galen* writes that both the evacuations are here needful, that is, blood-letting and purging; though the Patient be neither plethorick, nor repleat with ill humors. But the care hereof muſt be committed to the judgment of the learned Phyſician; pain, if joyned with inflammation ſhall be mitigated, by anointing the parts near unto the wound with *unguent. nutritum*, compoſed with the juice of Plantain, Houſleek, Nightſhade, and the like. *Unguentum Diacalcitheos* deſcribed by *Galen* diſſolved with vinegar, oyl of Poppies and Roſes, is of no leſs efficacy; nor *unguent. de bolo*, nor divers other things of the ſame faculty, though properly no Anodynes, as thoſe which are not hot and moiſt in the firſt degree, but rather cold, but yet not ſo as to have any narcotick faculty. Now theſe forementioned things aſſwage pain, for that they correct the hot diſtemper, and ſtay the acrid and cholerick defluxions, whoſe violence is more than cold. After the uſe of repercuſſives, it will be good to apply this following Cataplaſm. ℞ *Micæ panis infuſæ in lacte vaccino* ℔ i ß. *Bulliant parum, addendo olei violacei, & roſar. an.* ʒ iij. *Vitell. ovorum nu.* iiij. *pulver. roſar. rub. flor. chamæm. & meliloti, an.* ʒ ii. *Farin. fabar. & hordei, an.* ʒ i. *miſce, fiat cataplaſma ſecundum artem.* Alſo in this caſe you may eaſily make a medicine, of bread-crums boiled in Oxycrate and oyl of Roſes. The cure of Tumors, if any aſſociate the wound, may be found in their proper place. Natures motion, whether to ſuppuration, or any ſuch thing, muſt ſtill be obſerved, and helped by the Phyſician and Chirurgeon, as the miniſters and ſervants thereof.

Gal. liò. 4. Meth. cap. 6.

Gal. liò. 1. de comp. Med. ſecund. Gen. c. 6.

An Anodyne and ripening Cataplaſm.

CHAP. X.

Of Bullets which remain in the body, for a long time after the Wound is healed up.

LEaden Bullets lye in ſome parts of the body ſome whiles ſeven, eight, or more years, ſo that they neither hinder the agglutination of the wound, neither doth any other ſymptom happen thereupon, as I have divers times obſerved; until at length by the ſtrength of Nature forcing them, and their proper weightineſs bearing them downwards, they ſhew themſelves in ſome lower part, by their ſwelling or bunching forth, and ſo muſt be taken forth by the hand of the Chirurgeon. For they ſay Lead hath a certain ſympathy and familiarity with mans body, chiefly the fleſhy parts thereof. Wherefore it neither putrefies it ſelf, nor cauſeth the fleſh to putrefie; beſides it hath an excellent faculty in cicatrizing old ulcers. But bullets of ſtone, iron, and of any other metal, are of another nature, for they cannot remain any long time in the body without hurt; for Iron will grow ruſty, and ſo corrode the neighbouring bodies, and bring other malign ſymptoms. Yet a Leaden bullet cannot remain any long time in nervous or noble parts without danger.

Why Leaden Bullets lye in the body ſo many years without doing any harm.

CHAP. XI.

How to correct the conſtitution of the Air, ſo that the noble parts may be ſtrengthened, and the whole body beſides.

BUt becauſe, as we have formerly told you, there are ſome times wherein even ſmall wounds made by Gunſhot prove deadly, not by their own fault, but the fault of the air; therefore alſo the Chirurgeon muſt have this care, that he correct the air with all diligence, and reduce it to a certain quality and moderation of ſubſtance, and ſtrengthen the noble parts and whole body beſides; which may be performed by the following medicines, which are to be taken inwardly and applied outwardly. In the morning, three hours before meat, let the Patient take ſome certain quantity, as the Phyſician ſhall think fit, of the Electuary *Diarrhodon Abbatis*, or *Aromaticum roſatum, triaſantalon, diamoſchum, lætificans Galeni*, or ſome ſuch other like. And you ſhall apply ſome ſuch Epitheme as is here deſcribed to the Heart and Liver. ℞ *Aquæ roſar.* ʒ iiij, *aquæ bugloſſæ, aceti boni, an.* ʒ ij. *coriandri præparati* ʒ ß. *caryophyll. cortic. citri an.* ʒ i. *Sant. rub.* ʒ ß. *coralli utriuſque* ʒ ß. *Camphoræ* ℈ i. *Croci* ℈ ß. *Pulver. diarrhod. abbat.* ʒ ii. *Theriacæ & Mithridat. an.* ʒ ß. *Pul. flo. chamæm. & melil. an.* ʒ iij. *miſce, fiat epithema.* Let it be applied warm by dipping a Scarlet cloth therein. You ſhall frequently put odoriferous and refrigerating things to the Patients noſe, to ſtrengthen the animal faculty; as, ℞ *Aquæ roſar. & aceti boni an.* ʒ iij. *caryophyllorum, nucis moſchat. cinamomi conquaſſatorum, & Theriacæ Galeni, an.* ʒ i. Let a linnen rag dipped herein, be now and then put to the Patients noſe; for the ſame purpoſe he ſhall carry a Pomander about him, and often ſmell thereto. As, ℞ *Roſ. rub. violar. an.* ʒ iij. *baccarum myrti, juniperi, ſantal. rub. an.* ʒ ij ß. *ſtyracis calamit.* ʒ ij. *aq. roſarum. quantum ſatis eſt: liquefiat ſimul cum ceræ albæ quod ſufficit, fiat ceratum ad comprehendendos ſupra-dictos pulveres cum piſtillo calido, & ducatur in pomum.* Or, ℞ *Rad. Ireos Florent. majoran. calam. aromat. ladani, benzoini, rad. cyperi caryophyl. an.* ʒ ij. *Moſchi. gra.* 4. *fiat pulvis cum gummi tragacanth. quod ſufficit.* Or elſe, ℞ *Ladani puri* ʒ i. *Benzoini* ʒ ß. *ſtyracis calamit.* ʒ vj. *Ireos flor.* ʒ ß. *Caryophyl.* ʒ iij. *majoran. roſ. rub. calami aromat. an.* ʒ ß. *in pollinem redigantur omnia, & bulliant cum aqua roſ. quantum ſufficit; colentur, colata, liquefiant cum juſta ceræ albæ quantitate, ſtyracis liquidæ* ʒ i. *Fiat ad modum cerati, & cum piſtillo fiat pomum, addita moſchi* ʒ i. Alſo you may corroborate the animal faculty by application of frontals, as alſo procure ſleep, and eaſe the pain of the head; as, ℞ *Aq. roſ.* ʒ ii. *olei roſ. & papav. an.* ʒ i ß. *aceti boni,* ʒ i. *trochiſ. de camphora.* ʒ ß *fit frontale.* Linnen rags dipped herein may be applied to the temples of the forehead, and often renewed, otherwiſe by their heat, drineſs, and hardneſs, they will cauſe watching inſtead of ſleep. Neither muſt you in the mean time bind the head too hard, leſt by intercepting and hindring the pulſation of the temporal Artery, you increaſe the pain of the head. You ſhall make a fire in the Patients Chamber of odoriferous woods, as Juniper, Bay-tree, the pruning or cuttings of Vines, Roſemary, and Orris roots. For the

Cordials to ſtrengthen the noble parts.

A cordial Epithem.

Pomanders.

Frontals to cauſe reſt, and ſtrengthen the animal faculty.

A ſweet water. the ſame purpoſe, you may ſprinkle the floor with ſweet water; if the Patient be able to undergo ſuch coſt. As, ℞ *majoranæ, menthæ, radic. cyperi, calami aromat. ſalviæ, lavendulæ, fœnicul. thymi, ſtœchad. flor. chamæm. melilot. ſatureiæ, baccarum lauri, & juniperi. an. M.* iij. *pulv. caryophyl. nucis Moſcat. an* ʒ i. *aquæ roſar. & vitæ, an. lib.* ij. *vini albi boni & odorifici. lib.* x. *bulliant omnia in balneo Mariæ ad uſumdictum.* You may alſo make perfumes to burn in his chamber: as thus, ℞ *carbonis ſalicis* ℥ viij. *ladani puri* ℥ ij. *thuris maſculi, ligni & baccarum Juniperi, an.* ℥ i. *xyloaloes, benjoini, ſtyracis calamit. an.* ℥ ß. *Nucis moſchatæ, ſantal. citrin. an.* ʒ iij. *caryophyll. ſtyracis liquidæ, an.* ʒ ij. *zedoariæ, calami aromat. an.* ʒ i. *gummi tragacanth. aqua roſar. ſoluti, quod ſit ſatis.* Make hereof perfumes in what faſhion you pleaſe. For the rottenneſs and corruption of bones, we will treat thereof hereafter in due place.

Perfumes to burn.

CHAP. XII.

Certain memorable Hiſtories.

HEre I think good for the benefit of young practitioners, to illuſtrate by examples the formerly preſcribed method of curing Wounds made by Gunſhot. The famous and moſt valiant Count of *Mansfelt*, Governor of the Dutchy of *Luxenbourg*, Knight of the Order of *Burgundy*, coming to the aid of the French King, was at the Battel of *Moncontour*; where in the conflict he received ſo great a wound at the joynt of the left arm with a Piſtol-bullet, that the bones were ſhivered and broken in ſo many pieces, as if they had been laid upon an Anvil and ſtruck with an hammer: Hence proceeded many malign ſymptoms, as cruel and tormenting pain, inflammation, a feaver, an œdematous and flatulent tumor of the whole arm even to the fingers ends, and a certain inclination to a Gangrene: Which to reſiſt, *Nicolas Lambert*, and *Richard Hubert*, the Kings Chirurgeons, had made many and deep ſcarifications. But when I came to viſit and dreſs him, by the Kings appointment, and had obſerved the great ſtench and putrefaction, I wiſhed that they would uſe lotions of *Ægyptiacum* made ſomewhat ſtronger than ordinary, and diſſolved in Vinegar, and *Aqua vitæ*, and do other things more largely ſpoken of in the Chapter of a Gangrene. For the Patient had alſo a *Diarrhœa*, or Flux, whereby he evacuated the purulent and ſtinking filth which flowed from his wound. Which how it might come to paſs we will ſhew at large, when we come to treat of the ſuppreſſion of the Urine. For this ſeemed very abſurd to many, becauſe that if this purulent humor flowed out of the arm into the belly, it muſt needs flow back into the veins, be mixed with the blood, and by its pernicious and contagious paſſage through the heart and liver, cauſe exceeding ill ſymptoms, and laſtly death. Indeed he often ſwounded by the aſcent of the filthy vapours raiſed from the Ulcer to the noble parts; which to reſiſt, I wiſhed him to take a ſpoonful of *Aqua vitæ* with ſome Treacle diſſolved therein. I endeavoured to repreſs the œdematous and flatulent Tumor poſſeſſing all the arm with ſtoups dipped in Oxycrate, to which was put a little Salt and *Aqua vitæ*; theſe ſtoups I ſtayed and held to the part with double cloaths, ſowed as ſtrait as I could. Such a compreſſion held the broken bones in their places, preſſed their *Sanies* from the Ulcers, and forced back the humors flowing to the part into the center of the body. If at any time I omitted this compreſſion, the Tumor was ſo increaſed, that I was in a great deal of fear, leſt the native heat of the part ſhould be ſuffocated. Neither could I otherwiſe bind up the arm by reaſon of the exceſſive pain which moleſted the Patient upon the leaſt ſtirring of the arm. There were alſo many Abſceſſes about his elbow and over all his arm beſides. For the letting forth of whoſe matter I was forced to make new Inciſions; which he endured very ſtoutly. At length I cured him with uſing a vulnerary potion, and by cleanſing the Ulcers, and correcting the putrefaction with *Ægyptiacum* diſſolved in Wine and honey of Roſes, and ſo poured into the Ulcers, and repreſſing the growth of proud fleſh, with the powder of burnt Alum, drying it after the deterſion with liniments. Now this I can truly affirm and profeſs, that, during the time of the cure, I took out above threeſcore ſplinters of bones, and thoſe neceſſarily, amongſt which there was one of the length of ones finger; yet by Gods aſſiſtance at length he became ſound in all things, but that he could not put forth, or draw in his arm.

The malign ſymptoms which uſually happen upon wounds made by Gunſhot.

Matter may flow from the wounded limbs into the belly.

A brief recital of the manner of the cure.

Not long after by the Kings command I went to ſee *Charles Philip* of *Croy*, Lord of *Auret*, the Duke of *Arſchots* Brother, not far from *Mounts* a City of *Henalt*. He kept his bed ſeven months by reaſon of a wound made by a bullet the ſpace of three fingers above his knee. When I came to him, he was afflicted with theſe ſymptoms, intolerable pain, a continual feaver, cold ſweats, watchings, excoriation of the hips by reaſon of his long lying upon them, his appetite dejected with much thirſt. He oft ſunk down as if he had the Falling-ſickneſs, had a deſire to vomit, and a continual trembling or ſhaking, ſo that he could not put one hand to his mouth without the aſſiſtance of the other: He ſwounded frequently by reaſon of the vapours aſcending to the noble parts. For the thigh-bone was broken long-ways, and ſide-ways with many ſplinters of bones, whereof ſome were plucked out; and others remained ſticking faſt in. He beſides alſo had an ulcer in his groin which reached to the midſt of his thigh, and many other ſinuous ulcers about his knee. All the muſcles of his thigh and leg were ſwoln with a flegmatick, cold and flatulent humor, ſo that almoſt all the native heat of thoſe parts ſeemed extinct. All which things being conſidered, I had ſcarce any hope to recover him, ſo that I repented my coming thither. Yet at length putting ſome confidence in his ſtrength, and prime of youth, I began to have better hopes. Therefore with his good liking, firſt of all, I made two Inciſions, ſo to let forth the matter, which lying about the bone did humect the ſubſtance of the muſcles. This had happy ſucceſs, and drew out a great quantity of matter; then I with a Syringe injected much *Ægyptiacum* diſſolved in Wine, and a little *Aqua vitæ* into theſe Inciſions, ſo to reſtrain and amend the putrefaction, repreſs the ſpongy, looſe, and ſoft fleſh, reſolve the œdematous and flatulent Tumor, aſſwage the pain, and ſtir up and ſtrengthen the native heat almoſt oppreſt by the abundance of excrementitious humors,

Horrid ſymptom occaſioned by a wound made by Gunſhot.

Inciſions wherefore made.

mors, ſo that it could ſcarcely aſſimilate any nouriſhment and adjoyn it to the parts. Then I fomented the affected part with Sage, Roſemary, Thyme, Lavender, Chamomile and Melilot-flowers, and Red-roſe leaves boiled in White-white, and Lye made of Oak-aſhes, adding thereto as much Salt and Vinegar as I judged requiſite. This Fomentation did attenuate and draw forth the morbifick humor. Now we uſed them long and often, ſo to waſte the humor more by drying up and breathing through the paſſages of the skin, more thereof than fell into the part. For this ſame purpoſe, we ordained that he ſhould uſe frictions with hot linnen clothes, and that theſe ſhould be made from above downwards, from below upward, and ſo on every ſide, and ſomewhat long withal: For a ſhort friction draws more humor into the part than it can reſolve: I wiſhed that each other day they ſhould lay bricks heated hot in the fire about his leg, thigh, and ſoal of his foot; but they were to be ſomewhat quenched, and ſprinkled with Wine and Vinegar, with a ſmall quantity of *Aqua vitæ*. Much waterish moiſture by this moiſt heat, did ſweat out of theſe parts, the tumor was leſſened, and the native heat by little and little reſtored. Then ſtoups dipped in Lye made of Oak aſhes, wherein Sage, Roſemary, Lavender, Salt and Cloves, were boiled, ſome *Aqua vitæ* added, were applied thereto; but the rowlers were ſo gently and artificially wrapped about, that he did eaſily endure them without any pain, and that with ſuch happy ſucceſs, that if they were omitted but one day, the tumor became very great. But thick linnen boulſters were laid upon the lower cavities of the Ulcer; that ſo the *Sanies*, or filth, might be more eaſily preſſed forth. But I had always a ſpecial care that the orifices of the Ulcers ſhould be kept open with hollow tents or pipes put therein: And ſometimes this following Cataplaſm was applied to reſolve the tumor. ℞ *Far. hord. fabar. & orobi, an.* ℥ vj. *Mellis com. & tereb. an.* ℥ ij. *flo. chamæm. melil. & roſ. rub. an.* ℨ ſ. *Pulv. rad. Ireos, Flor. cyper. Maſt. an.* ʒ iii. *Oxymel. ſemp. quantum ſufficit*; *fiat cataplaſma ad formam pultis ſatis liquidæ.* An *emplaſtrum de Vigo* without Mercury was applied thereto, whereby the pain was much aſſwaged, and the tumor leſſened: Yet were they not applied before the parts were throughly heated by the Fomentation, Frictions and Evaporations; for otherways this Emplaiſter could never have been activated, by reaſon of the exceſſive coldneſs of the affected parts. Neither did we omit catagmatick powders, fit for the taking, and drawing forth of broken bones. He uſed a vulnerary potion for fifteen days. Alſo beſides the particular frictions of the affected parts, I appointed other general frictions of the whole body, which was become very lean; for by theſe, blood together with the ſpirit was drawn to the parts, and the acrid, and fuliginous vapours were breathed forth. To conclude, his Feaver and pains being aſſwaged, his appetite reſtored, by feeding plentifully upon good meats according to his ſtrength, he in a ſhort time became more luſty; and laſtly, by the ſingular mercy of God, recovered his health perfectly, but that he could not very well bend his knee. I thought good to recite theſe things, not to glory or brag of the happy ſucceſs of thoſe Patients, which have recovered by means, and the favour of God; but that thus I may more fully and perfectly, by familiar examples, inſtruct young practicioners, in the operations of Chirurgery.

Wherefore I uſed Fomentations.

Mixed or round frictions, as they term them.

A medicated Lye.

A diſcuſſing Cataplaſm.

CHAP. XIII.

An Apology concerning Wounds made by Gunſhot.

THere lately came to my hands a Book written by a certain Phyſician, whereby he endeavours to diſprove and overthrow, that which I have hitherto writ, of the cure of wounds made by Gunſhot. Aſſuredly, if there were no other harm, but the loſs of my credit enſuing thereon, I would willingly hold my peace, and ſtop his mouth by modeſt ſilence. But ſeeing the ſafety of ſo many men lyes upon the judgment of this point, I have thought good to withſtand this errour, leſt it, to the great deſtruction of mankind, ſpread and diffuſe it ſelf any further. The uſe (ſaith he) of ſuppurative medicines, have killed many who have been but lightly wounded with Gunſhot; but acrid medicines, as *Ægyptiacum*, have killed more. Neither is the counſel of *Hippocrates* to be obſerved in curing this ſort of wounds, who bids that every contuſed wound be brought to ſuppuration. For ſeeing this is a new kind of wound, it requires new, and not anciently uſed, medicines. Now the temper of the air, changed from the natural conſtitution, ought not to indicate change of medicines; but much leſs muſt Thunder and Lightning be compared to the ſhooting of great Ordnance. Theſe are the chief heads of this his Book; which, becauſe they diſſent from the truth, and thoſe things I have formerly delivered, I have thought good here to confute. Firſt, ſeeing leaden Bullets which are uſually ſhot out of Guns are round, obtuſe and weighty, they cannot wound the body without contuſion and attrition: Now no contuſion can be cured without ſuppuration, not only according to the opinion of *Hippocrates*, but alſo of *Galen*, and all others, who have written of Phyſick. Neither muſt we invent new remedies, for theſe new kinds of wounds; for the Laws of the ſacred and divine Art of Phyſick, are not obnoxious to change, nor ſubject to the humor of men or times, as the Decrees of Kings and Emperours are. For theſe are ſtabliſhed with immutable neceſſity, which conſtancy neither conſuming time nor age, nor tyranny can pervert. Wherefore neither thoſe who with great praiſe are Phyſicians to Kings and Princes, I mean *Joubert* and *Potallus*, think it lawful for them to depart from the rules of *Hippocrates*. And this they not only do and follow in curing and doing the works of Art, but much and highly commend, confirm, and propound to be diligently obſerved by all in their Books, which they have publiſhed concerning the cure of theſe kinds of wounds. And yet theſe Phyſicians are ſuch, as, daily converſant in Armies and Kings-houſes, have healed and daily cure as many wounded by Gunſhot as this Phyſician our Antagoniſt hath ſeen in all his life. Neither only do theſe whom I have named thus cure theſe wounds, but almoſt all that dreſs ſuch kind of wounds do the like; ſo that, if there be nothing which may hinder, or indicate to the contray, they preſently apply ſuppuratives. And I wonder that he hath not obſerved how his neighbour *Doublet* the

The occaſion of writing this Apology.

The chief heads of our adverſaries Treatiſe.

All wounds made by Gunſhot are contuſed.

A ſuppurative medicine of tried efficacy.

the Emperick, cures deſperate wounds of this nature, with no other than a ſuppurative medicine, compoſed of Lard, the yolk of an Egg, Turpentine, and a little Saffron. In the year, 1538. there was at *Turin* whilſt I was Chirurgeon there to the Marſhal of *Montejan* the Kings Lieutenant General in *Piedmont*, a certain Chirurgeon wondrous famous for curing theſe wounds, and yet he uſed nothing elſe but the Oyl of Whelps, (the Deſcription whereof I at length obtained of him with much intreaty and expence;) and he uſed it not ſcalding hot, as ſome have imagined, but poured it ſcarce warm into their wounds, and ſo did mitigate their pain, and happily bring them to ſuppuration. Which afterwards almoſt all Chirurgeons, after they had got the Deſcription hereof, when I firſt publiſhed this Work, have uſed, and daily do uſe with happy ſucceſs.

The force of *Ægyptiacum* againſt putrefaction.

But in contemning and condemning *Ægyptiacum*, I think he hath no partaker; ſeeing there as yet hath been found no medicine more ſpeedy and powerful to hinder putrefaction, if beginning; or correct it, if preſent. Now theſe wounds often degenerate into virulent, eating, ſpreading and malign Ulcers, which caſt forth a ſtinking and Carion-like filth, whence the part gangrenates, unleſs you withſtand them with *Ægyptiacum*, and other acrid medicines, being greatly approved by the formerly named Phyſicians, and all Chirurgeons. But (ſaith he) this Unguent is poyſonous, and therefore hath been the death of many who have been wounded by Gunſhot. Verily if any diligently enquire into the Compoſition of this Oyntment, and conſider the nature of all and every the ingredients thereof, he ſhall underſtand that this kind of Unguent is far from poyſon; that on the contrary, it directly oppoſes and reſiſts all poyſon and putrefaction which may happen to a fleſhy part, through occaſion of any wound.

The force of the air in breeding and augmenting diſeaſes.

It is moſt falſe and diſſonant from the doctrine of *Hippocrates* to affirm, that the Seaſons of the year ſwerving from the Law of Nature, and the air, (not truly the ſimple and elementary) but that which is defiled and polluted by the various mixture of putrid and peſtilent vapours, (either raiſed from the earth, or ſent from above) make not wounds more malign and hard to cure at ſome times than they are at other ſome. For the air either very hot, or cold, drawn into the body by inſpiration or tranſpiration, generates a condition in us like its qualities. Therefore why may it not, when defiled with the putredinous vapours of bodies lying unburied after great Battels, and Shipwracks of great Armadoes, infect with the like quality our bodies and wounds?

A Hiſtory.

In the year, 1562. when the Civil Wars concerning Religion firſt begun in *France*, at *Pene*, a Caſtle lying upon the River *Lot*, many ſlain bodies were caſt into a Well, ſome hundred cubits deep: ſo ſtinking and peſtilent a vapour aroſe from hence ſome two months after, that many thouſands of people died all over the Province of *Agenois*, as if the Plague had been amongſt them, the pernicious Contagion being ſpread twenty miles in compaſs. Which none ought to think ſtrange, eſpecially ſeeing the putrid exhalations by the force of the winds may be driven and carried into divers and moſt remote Regions, diſperſed like the ſeeds of the Peſtilence; whence proceeds a deadly corruption of the ſpirits, humors and wounds, not to be attributed to the proper malignity or perverſe cure of wounds, but to be the fault of the air. Therefore *Francis Daleſchampe*, in his French Chirurgery, in reckoning up thoſe things which hinder the healing of Ulcers, hath not omitted that common cauſe which proceeds from the air defiled or tainted with the ſeeds of Peſtilence. For he had learn'd from his Maſter *Hippocrates*, that the mutations of times chiefly bring diſeaſes, and he had read in *Guido*, that this was the chief occaſion, that wounds of the head at *Paris*, and of the legs at *Avignion*, were more difficultly healed. Laſtly, even Barbers, and ſuch as have leaſt skill in Chirurgery know, that wounds eaſily turn into a Gangrene in hot and moiſt conſtitutions of the air. Wherefore when the wind is ſoutherly, the Butchers will kill no more fleſh than to ſerve them for one day. I have formerly declared the malignity of the wounds occaſioned by the air in the ſiege of *Rouen*, which ſpared none, no not the Princes of the Blood, who had all things which were requiſite for their health. Which cauſed me, made at length more skilful by experience, to uſe *Unguentum Ægyptiacum*, and medicines of the like faculty, inſtead of Suppuratives, to wounds during all that ſeaſon, that ſo I might withſtand the putrefaction and Gangrene which ſo commonly aſſailed them. But if the various motion of the Stars, can by their reflux ſend a Plague into the air, why then may it not by depravation of their qualities infect, and as by poyſoning corrupt both wounds and wounded bodies obnoxious to their changes, and that of the air? We learn'd long ſince by experience, that all pains, but principally of wounds, grow worſe in a rainy and moiſt ſeaſon, ſpecially becauſe in that ſoutherly conſtitution the air replete with thick and foggy vapours, cauſes the humors to abound in the body, which forthwith eaſily fall upon the affected parts, and cauſe increaſe of pain. But, ſaith our Adverſary, in the Battel at *Dreux*, and at S^t *Denis* which were fought in Winter, there died a great number of men who were wounded by Gunſhot: This I confeſs is true; but this I deny, that it was occaſioned by applying ſuppuratives or corroſives, but rather the vehemency and largeneſs of their wounds, and the ſpoil the bullet made in their members; but above all, by reaſon of the cold. For cold is moſt hurtful to wounds and ulcers, (as *Hippocrates* teſtifies) it hardens the skin, and cauſes a Gangrene. If this my Gentleman had been with me in the ſiege of *Metz*, he might have ſeen the legs of many Souldiers to have rotted, and preſently taken with a Gangrene to have faln away, by the only extremity of cold: If he will not believe me, let him make trial himſelf, and go Winter to the Chappel at Mount *Senis*, oneof the *Alpine* hills, where the bodies of ſuch as were frozen to death in paſſing that way are buried, and he ſhall learn and feel how true I ſpeak. In the mean time I think it fit to confute the laſt point of his Reprehenſion.

Hip. Aph. 1. *ſect.* 3.

In our ſecond Diſcourſe.

The power of the Stars upon the air and our bodies.

Aphor. 40. *ſect.* 5.

The ſimilitude between Thunder and great Ordnance, maintained.

He cavils for that I compared Thunder and Lightning with diſcharging of Pieces of Ordnance. Firſt, he cannot deny, but that they are alike in effects. For it is certain that the flame ariſing from Gunpowder ſet on fire, reſembles Lightning; in this alſo, that you may ſee it before you hear the crack or report. I judge, for that the eye almoſt in a moment perceives its objects; but the ear cannot but in ſome certain ſpace of time, and by diſtinct gradations. But the rumbling noiſe is like

in

in both, and certainly the Report of great Ordnance may be heard ſometimes at forty miles diſtance, whileſt they make any great battery in the beſieging of Cities. Beſides alſo, Iron Bullets catt forth with incredible celerity by the fired Gun-powder, throw down all things with a horrid force, and that more ſpeedily and violently by how much they reſiſt the more powerfully by their hardneſs. They report that Lightning melts the Money not hurting the Purſe; Now many by the onely violence of the air agitated and vehemently moved by ſhooting a piece of Ordnance, as touched with Lightning, have died in a moment; their bones being ſhivered and broken, no ſign of hurt appearing in the skin. The ſmell of Gun-powder when it is fired, is hurtful, fiery and ſulphurous, juſt like that which exhales or comes from bodies killed with Lightning. For men do not onely ſhun the ſmell, but alſo wild Beaſts leave their Dens if touched with Lightnings. Now the cruelty of great Ordnance makes no leſs ſpoil amongſt Buildings, nor ſlaughter amongſt Men and Beaſts, than Lightnings do, as we have formerly ſhewn by examples, not onely horrid to ſee, but even to hear reported, as of Mines, the Arcenal of *Paris*, the City of *Malines*. Theſe may ſeem ſufficient to teach, that Thunder and Lightning have a great ſimilitude with the ſhooting of great Ordnance, which notwithſtanding I would not have alike in all things. For they neither agree in ſubſtance nor matter, but onely in the manner of violent breaking aſunder the objects.

Now let us ſee and examine what manner of cure of Wounds made by Gun-ſhot our Adverſary ſubſtitutes for ours. For he would have ſuppuratives uſed and applied, yet ſuch as ſhould not be hot and moiſt in quality, or of an Emplaſtick conſiſtence, but hot and dry things. For (ſaith he) here is not the ſame reaſon as in Abſceſſes, where the Phyſician intends nothing but ſuppuration. But here becauſe a contuſion is preſent with the wound, this requires to be ripened with ſuppuratives, but the Wound to be dried. *Our Adverſaries method, and manner of cure reproved.*

Now to anſwer this objection, I will refer him to *Galen*, who will teach him the nature of ſuppuratives; from whom alſo he may learn that great regard is to be had of the Cauſe, and more urgent order in the Cure of Compound Diſeaſes; then would I willingly learn of him, whether he can heal a wound made by Gun-ſhot, not firſt bringing that which is contuſed to perfect maturity. If he affirm he can, I will be judged by whatſoever Practitioners he will, to judge how obſcure theſe things are. Whereby you may the better underſtand there is nothing more commodious than our *Baſilicon* and Oil of Whelps to ripen wounds made by Gun-ſhot, if ſo be that putrefaction, corruption, a Gangrene, or ſome other thing do not hinder. Then would he have *Oxycrate* poured into theſe wounds to ſtay their bleeding, which if it cannot ſo be ſtaid, he would have a Medicin applied conſiſting of the white of an Egg, Bole Armenick, Oil of Roſes and Salt. But I leave it to other mens judgment, whether theſe Medicins have power to ſtay bleeding if put into the wound; certainly they will make it bleed the more. For Vinegar ſeeing it is of a tenuious ſubſtance and biting, it is no doubt but that it will cauſe pain, defluxion and inflammation. To which purpoſe, I remember I put to ſtanch bleeding, for want of another remedy, a Medicin wherein was ſome Vinegar, into a Wound received by a Moor, an attendant of the Earl of *Roiſſy*, hurt with a Lance run through his arm before *Bologne* by an Engliſh Horſeman. But he comes again to me a little after, complaining and crying out that all his arm burnt like fire; wherefore I was glad to dreſs him again, and put another Medicin into his Wound, and laid an aſtringent Medicin upon the Wound, but poured it not therein. And then above all other remedies he extols his Balſam compoſed of Oil of Wax and Myrrh beaten together with the white of an Egg, which he ſaith is equal in operation to the natural Balſam of *Peru*. For he affirms, that this hath a faculty to conſume the excrementitious humidity of Wounds, and ſo ſtrengthens the part that no ſymptom afterwards troubles them. Yet he ſaith, this doth not ſo well heal and agglutinate theſe wounds, as it doth others which are cut. Verily it is ridiculous to think that contuſed Wounds can be healed after the ſame manner, as ſimple wounds may, which onely require the uniting of the looſed continuity. *Gal. lib. 9. ſimpl. 10. Method.* *Vinegar put into a wound doth not ſtay but cauſes bleeding. A Hiſtory.* *Balms are fit to heal ſimple but not contuſed Wounds.*

Therefore neither can theſe Balſams be fit remedies to heal Wounds made by Gun-ſhot, ſeeing by reaſon of their drineſs they hinder ſuppuration, which unleſs it be procured, the Patient cannot be healed. Wherefore ſuch things ought not to be put into Wounds of this nature, before they be ripened, waſhed and cleanſed from their filth. Yet can I ſcarce conceive where we ſhall be able to find out ſo many Chymiſts which may furniſh us with theſe things ſufficiently to dreſs ſo many wounded Souldiers as uſually are in an Army, or whence the Souldiers have ſufficient means to bear the charge thereof. Alſo that which he ſaith is abſurd, that the Balſams muſt be put into the Wounds without Tents; and preſently forgetting himſelf, he ſaith it will not be amiſs if there be a little and ſlender Tent put into the Wound, which may onely ſerve to hinder the agglutination thereof. But how can theſe Balſams come to the bottoms of Wounds without Tents, when as it is their chief property to carry Medicins even to the innermoſt parts of the Wounds, and always keep open a free paſſage for the evacuation of the quitture? But it is not worthy, that after he hath rejected *Unguentum Ægyptiacum*, he nevertheleſs bids to apply it, from the beginning until the contuſion come to perfect maturation, diſſolving it it in a decoction of the tops of Wormwood, S. *Johns* Wort, the leſſer Centory and Plantain, and ſo injecting it into the Wound. Beſides alſo a little after he gives another way of uſing it, which is, to boil a quantity of Honey of Roſes in Plantain Water, carefully ſkimming it, until it be boiled to the conſiſtence of Honey, and then to add as much *Ægyptiacum* thereto, and ſo to make an Ointment moſt fit to bring theſe Wounds to ſuppuration. But I leave it for any skilful in Chirurgery to judge, whether ſuch Medicins can be ſuppuratives, or whether they be not rather deterſives. Laſt of all, he writes, that theſe Wounds muſt be dreſt but every fourth day. And if there be a fracture of the bone joined with the Wound, then to move nothing after the firſt dreſſing until the eighth day after; then preſently in another place he ſaith, it will be good and expedient to drop ten or twelve drops of the formerly deſcribed Balſam every day into the Wound. Verily ſuch doctrin which neither agrees with it ſelf, nor the truth, cannot but much puſle a Novice and young practitioner in Chirurgery, who is not yet verſed in the Art, or the operations thereof. *Ægyptiacum howſoever made, is a cleanſer, not a ſuppurative.*

CHAP. XIV.

Another Apology againſt thoſe who have laboured with new Reaſons to prove that Wounds made by Gun-ſhot are poiſoned.

The occaſion of this Apology.

SOme few Moneths ago, I viſited a Patient together with ſome learned Phyſicians and skilful Chirurgeons. Now they, as it oft-times happens, in way of diſcourſe, begun to argue of the condition and quality of Wounds made by Gun-ſhot, and endeavoured to prove that they might be poiſoned, by five reaſons. Not truly through the occaſion of the Gun-powder, for they all confeſſed that it was free from poiſon, whether you have regard to its eſſence, or to its compoſition; but by the Bullet into which the poiſon may be transfuſed and incorporated. The firſt reaſon is, that Lead ſeeing it is of a rare and ſpongious nature, which the eaſineſs of melting and ſoftneſs argues, is very fit to drink and ſoak in what liquors ſoever you pleaſe. But methinks this concluſion is very weak; for in all mixtures made by Art, ſuch as this is whereof we ſpeak, there are two things to be conſidered; that is to ſay, the Matter of the things which enter into the mixture, and the Form. For the Matter, ſuch bodies muſt be either liquid, or ſoft, or friable; and laſtly, ſuch as may be broken and divided into ſmall particles, that ſo they may eaſily in all parts concur and be conjoined and united. But for their Form, there ought to be a certain affinity, conſent, and ſympathy. You may perceive this by Water and Oil; for each of them, though of a liquid ſubſtance, and ſuch may eaſily be mixed with divers other things, yet cannot they be mixed the one with the other, by reaſon of their antipathy of Forms. For thus Gold and Silver are ſo agreeing with Lead, that as oft as they are molten, Lead is mixed with them. But Braſs ſhuns Lead, as much as Gold and Silver fly Tin and white Lead. If therefore Braſs and Lead being melted cannot be mixed together, though contained under the ſame *Genus*, and common nature of Metals; how then can it be commixt with another thing diſtinct in the whole kind, much more in *Species* and Form, to wit, poiſon? Their ſecond reaſon is this; Iron (ſay they) which is more denſe, ſolid, and leſs porous, may receive ſome venenate ſubſtance and quality, as the Arrows of the Ancients which were dipped in poiſon, teſtifie; therefore muſt Lead much more be capable thereof. I anſwer, that the ſurface of Iron may be poiſoned, but not the inner part or ſubſtance by mixture therewith. But here the queſtion is of union, but not of anointing or inunction. The third reaſon is thus framed; though (ſay they) Lead caſts off and purges it ſelf from the droſs and unpure parts, yet that is no argument that it will not commix, or ſoak it ſelf in ſome ſtrange liquor or body; for thus Steel, being the moſt ſolid Iron, receives the temper which hardens it, by the artificial pouring upon it, or quenching it in liquors contrary thereto in their whole kind. I anſwer, that Steel admits into it by that quenching and tempering, none of the juices or liquors wherewith it is watered or quenched. For if that were neceſſary, it might be better and more eaſily performed, when the Metal is firſt caſt, than when it is beaten into Plates or Bars; which anſwer ſhall ſerve to confute their fourth reaſon; wherein they ſay, that Bullets may be made ſo poiſonous by the commixture of the juices of Monks-hood, Oleander, Crow-foot, and other ſuch like things which in their whole ſubſtance are contrary to ours, that the Wound which is made with them cannot but be poiſoned. But I on the contrary affirm, that mixture is onely of thoſe things, which may not onely be put, but alſo ſtick thereto, and be mutually united; but how can Water, or any other liquid juice ſo much as onely ſtick to Lead, as that which is a ſolid and firm body, it is ſo far from being united therewith? You may give more certain judgment hereof by experience, than by reaſon; wherefore let melted Lead be put into the foreſaid juices, or the like, then when the Lead is cold, weigh each of them ſeverally and you ſhall find, that both of them retain the ſame weight they formerly had. Which is a moſt certain argument, that neither the Lead hath mixed or united it ſelf with the juices, nor the juices loſt any part of their ſubſtance. Their fifth reaſon is thus; A Bullet ſhot out of a Gun againſt ſome hard ſtone, grows not ſo hot, but that you may preſently without any harm take it up in your hand. Therefore it is falſe, that the poiſon commixt and united with the Bullet can be diſſipated by the fire and flaſh of Gun-powder. The anſwer to this objection is eaſie. For when we ſay, that although the Bullet may be infected by poiſon perfectly commixt with the Lead, yet all the force of the poiſon would be diſſipated by the fire; we would have you thus to underſtand us, that we do not mean this of that fire which is made by the powder at the diſcharging of the Piece, but of that by force whereof the molten Lead is mixed and conjoined with the venenate juice, ſo to make one of many. For this fire exerciſing its force upon the venenate juices hindered by the intercourſe of no *Medium*, and that for ſome ſpace of time, and not for an inſtant, it may, if not conſume, yet much weaken their ſtrength. If there be any, who will not be ſatisfied by theſe reaſons, let him conſult, and read *Mathiolus*. There are (ſaith he) ſome in theſe later times wholly ignorant of things, who (if we may ſay the truth) have been ſo madly fooliſh, that they ſaid it was fit and requiſite to put Treacle and Mithridate, and ſuch like Antidotes amongſt Gold and Silver that was melted to make Cups, that ſo receiving the faculties of the Antidote they might reſiſt poiſon. But how abſurd and ridiculous their opinion is, let them judge, (for it needs no clearer reproof) who have but a little knowledge in natural things, but chiefly in Metals. Theſe are my Reaſons, theſe the Authorities of men excelling in Learning and Judgment, that confirm me in my ancient and former opinion, that Wounds made by Gun-ſhot do not partake of any venenate quality.

The reaſon of our Adverſary that the Bullets may be poiſoned, ſet down and confuted.

In Præfat. l. 6. Diaſcor.

CHAP.

CHAP. XV.

How Wounds made by Arrows differ from ſuch as are made by Gunſhot.

WOunds made by Arrows and Bolts ſhot out of Croſs-Bows, and ſuch like things, differ chiefly in two things, from thoſe which are made by Gun-ſhot. The firſt is, for that they are oft-times without contuſion, which the other never are. The other is, for that they oft-times are poiſoned. In both theſe reſpects their cure is different from the other. But the cure of theſe Wounds made by Arrows is different in it ſelf, by reaſon of the variety and divers ſorts of Darts or Arrows.

Wounds made with Arrows and ſuch like things, are often without contuſion. But are oft-times poiſoned.

CHAP. XVI.

Of the diverſity of Arrows and Darts.

ARrows and Darts are diffetent amongſt themſelves both in manner, and in form or figure, in number, making, faculty or ſtrength. In matter, for that ſome of them are of Wood, ſome of Reeds, ſome are blunt headed, others have piles or heads of Iron, Braſs, Lead, Tin, Horn, Glaſs, Bone. In figure, for that ſome are round, others cornered, ſome are ſharp-pointed, ſome barbed, with the barbs ſtanding either to the point, or ſhafts, or elſe acroſs, or both ways, but ſome are broad and cut like a Chiſſel. For their bigneſs, ſome are three foot long, ſome leſs. For their number, they differ in that, becauſe ſome have one head, others more. But they vary in making, for that ſome of them have the ſhaft put into the head, others the head into the ſhaft; ſome have their heads nailed to the ſhaft, others not, but have their heads ſo looſly ſet on, that by gentle plucking the ſhaft, they leave their heads behind them, whence dangerous Wounds proceed. But they differ in force, for that ſome hurt by their Iron onely, others beſides that, by poiſon, wherewith they are infected. You may ſee the other various ſhapes repreſented to you in this Figure.

The differences of Arrows. In matter. In ſign. In bigneſs. In number. In making. In force.

The Figure of divers ſorts of Arrows.



CHAP. XVII.

Of the difference of the wounded parts.

THe wounded parts are either fleſhy or bony; ſome are near the joints, others ſeated upon the very joints; ſome are principal, others ſerve them; ſome are external, others internal. Now in wounds where deadly ſigns appear, it is fit you give an abſolute judgment to that effect: leſt you make the Art to be ſcandalized by the ignorant. But it is an inhumane part, and much digreſſing from Art, to leave the Iron in the Wound; it is ſometimes difficult to take it out, yet a charitable and artificial Work. For it is much better to try a doubtful remedy than none at all.

You muſt not leave the weapon in the Wound.

CHAP. XVIII.

Of drawing forth Arrows.

YOu muſt in drawing forth Arrows ſhun Inciſions and Dilacerations of Veins and Arteries, Nerves and Tendons. For it is a ſhameful and bungling part to do more harm with your hand than the Iron hath done. Now Arrows are drawn forth two ways, that is, either by extraction, or impulſion. Now you muſt preſently at the firſt dreſſing pull forth all ſtrange bodies: which that you may more eaſily and happily perform, you ſhall ſet the Patient in the ſame poſture as he ſtood when he received his wound; and he muſt have alſo his Inſtruments in a readineſs, chiefly that which hath a ſlit pipe and toothed without, into which there is put a ſharp iron ſtile, like the Gimblets we formerly mentioned for the taking forth of Bullets; but that it hath no ſcrew at the end, but is larger and thicker, ſo to widen the Pipe, that ſo widened it may fill up the hole of the Arrows head whereinto the ſhaft was put, and ſo bring

The manner of drawing forth Arrows and ſuch weapons.

it forth with it, both out of the fleſhy as alſo out of the bony parts, if ſo be that the end of the ſhaft be not broken, and left in the hole of the head. That alſo is a fit Inſtrument for this purpoſe, which opens the other end toothed on the out-ſide, by preſſing together of the handle. You ſhall find the Iron or head that lies hid by theſe ſigns: there will be a certain roughneſs and inequality on that part, if you feel it up and down with your hand; the fleſh there will be bruiſed, livid, or black; and there is a heavineſs and pain felt by the Patient both there and in the Wound.

A delineation of Inſtruments fit to draw forth the heads of Arrows and Darts which are left in the Wounds without ſhafts.





A hooked Inſtrument fit for to draw forth ſtrange bodies, as pieces of Male, and ſuch other things as it can catch hold of, which may alſo be uſed in Wounds made by Gun-ſhot.

But if by chance either Arrows, Darts or Lances, or any winged head of any other weapon, be run through and left ſticking in any part of the Body, as the Thigh, with a portion of the ſhaft, or ſtaff ſlivered in pieces, or broken off; then it is fit the Chirurgeon with his cutting Mullets ſhould cut off the end of the ſtaff or ſhaft, and then with his other Mullets pluck forth the head, as you may ſee by this Figure.

CHAP. XIX.

How Arrows broken in a Wound may be drawn forth.

When to draw forth the weapon on the contrary ſide.

But if it chance that the weapon is ſo broken in the wound that it cannot be taken hold on by the formerly mentioned Mullets, then muſt you draw, or pluck it out with your Crane, or Crows-bill, and other formerly deſcribed Inſtruments. But if the ſhaft be broken near the head, ſo that you cannot take hold thereof with your Cranes-bill, then you ſhall draw it forth with your Gimblet, which we deſcribed before to draw forth Bullets; for if ſuch a Gimblet can be faſtned in Bullets, it may far better take hold of Wood. But if the head be barbed, as uſually the *Engliſh* Arrows are, then if it may be conveniently done, it will be very fitting to thruſt them through the parts. For if they ſhould be drawn out the ſame way they went in, there would be no ſmall danger of breaking or tearing the Veſſels and Nerves by theſe hooked barbs. Wherefore it is better to make a ſection on the other ſide whither the head tended, and ſo give it paſſage forth if it may be eaſily done; for ſo the Wound will be the more eaſily cleanſed and conſolidated.

A Delater hollowed on the inſide with a Cranes-bill to take hold on the barbed head.



When by the ſame way it went in.

But on the contrary, if the point tend to any bone, or have many muſcles or thick fleſh againſt the head thereof, as it happens ſometimes in the Thighs, Legs, and Arms, then you muſt not thruſt the head through, but rather draw it out the ſame way it came in, dilating the Wound with fit Inſtruments, and by skill in Anatomy ſhunning the larger Nerves and Veſſels. Therefore for this

purpoſe

purpoſe put a hollow Dilater into the Wound, and therewith take hold of both the barbs or wings of the head; and then take faſt hold of the head with your Cranes-bill, and ſo draw them forth all three together.

CHAP. XX.

What to be done when an Arrow is left faſtned or ſticking in a Bone.

BUt if the Weapon be ſo depact and faſtned in a Bone that you cannot drive it forth on the other ſide, neither get it forth by any other way than that it entered in by; you muſt firſt gently move it up and down, if it ſtick very faſt in; but have a ſpecial care that you do not break it, and ſo leave ſome fragment thereof in the bone; then take it forth with your Crows-bill, or ſome other fit Inſtrument formerly deſcribed. Then preſs forth the bloud, and ſuffer it to bleed ſomewhat largely, yet according to the ſtrength of the Patient and nature of the wounded part. For thus the part ſhall be eaſed of the fulneſs and illneſs of humours, and leſs moleſted with inflammation, putrefaction, and other ſymptoms which are cuſtomarily feared. When the Weapon is drawn forth, and the wound once dreſſed, handle it, if ſimple, as you do ſimple wounds; if compound, then according to the condition and manner of the complication of the effects; Certainly the Oil of Whelps, formerly deſcribed is very good to aſſwage pain. To conclude, you ſhall cure the reſt of the ſymptoms according to the Method preſcribed in our Treatiſe of Wounds in general, and to that we have formerly delivered concerning Wounds made by Gunſhot.

A Caution.

The benefit of bleeding in Wounds.

CHAP. XXI.

Of poiſoned Wounds.

IF theſe Wounds at any time prove poiſoned, they have it from their primitive cauſe, to wit, the impoiſoned Arrows or Darts of their Enemies. You may find it out both by the property of the pain, if that it be great and pricking, as if continually ſtung with Bees, for ſuch pain uſually enſues in Wounds poiſoned with hot poiſon, as Arrows uſually are: Alſo you ſhall know it by the condition of the wounded fleſh; for it will become pale and grow livid, with ſome ſigns of mortification. To conclude, there happen many and malign ſymptoms upon Wounds which are impoiſoned, being ſuch as happen not in the common nature of uſual Wounds. Therefore preſently after you have pluckt forth the ſtrange bodies, encompaſs the Wound with many and deep ſcarifications, apply ventoſes with much flame, that ſo the poiſon may be more powerfully drawn forth; to which purpoſe the ſucking of the Wound, performed by one whoſe mouth hath no ſoreneſs therein, but is filled with Oil, that ſo the poiſon which he ſucks may not ſtick nor adhere to the part, will much conduce. Laſtly, it muſt be drawn forth by rubefying, veſicatory, and cauſtick Medicins, and aſſailed by Ointments, Cataplaſms, Emplaiſters, and all ſorts of local Medicins.

The ſigns of poiſoned Wounds.

Remedies in poiſoned Wounds.

The End of the Eleventh Book.

BOOK XII.

Of CONTUSIONS and GANGRENES.

CHAP. I.

Of Contuſions.

A Contuſion, according to *Galen*, is a ſolution of continuity in the Fleſh or Bone, cauſed by the ſtroke of ſome heavy and obtuſe thing, or a fall from on high. The ſymptom of this Diſeaſe is by *Hippocrates* called *Peliosis*, and *Melaſma*, that is to ſay, blackneſs and blueneſs; the *Latins* term it *Sugillatum*. There are divers ſorts of theſe Sugillations or blackneſſes, according as the bloud is poured forth into the more inward or outward part of the body. The bloud is poured forth into the body, when any (for example) falls from an high, or hath any heavy weight falls upon him, as it often happens to ſuch as work in Mines, or are extremely wracked or tortured; and ſometimes by too loud and forcible exclamations. Beſides alſo, by a Bullet ſhot through the body, bloud is poured forth into the belly, and ſo often evacuated by the paſſages of the Guts and Bladder. The ſame may happen by the more violent and obtuſe blows of a hard Truncheon, Club, Stone, and all things which may bruiſe and preſs the bloud out of the Veſſels either by extending or breaking them. For which cauſes alſo the exteriour parts are contuſed, or bruiſed ſometimes with a Wound, ſometimes without, ſo that the Skin being whole, and as far as one can diſcern, untoucht, the bloud pours it ſelf forth into the empty ſpaces of the Muſcles, and between the Skin and Muſcles; which affect the Ancients have termed *Ecchymoſis*; *Hippocrates* calls it by a peculiar name *Nauſioſis*, for that in this affect the ſwollen Veins ſeem as it were to vomit, and verily do vomit or caſt forth the ſuperfluous bloud which is contained in them. From theſe differences of Contuſions are drawn the Indications of curing, as ſhall appear by the enſuing diſcourſe.

Gal. lib. de artis conſtitut. Sect. 2. lib. de fracturis.

Cauſes of Bruiſes and Sugillations.

Sect. 2. lib. de fract.

CHAP. II.

Of the general Cure of great and enormous Contuſions.

THe bloud poured forth into the body, muſt be evacuated by viſible and not viſible evacuation. The viſible evacuation may be performed by Bloud-letting, Cupping-glaſſes, Horns, Scarification, Horſleeches, and fit purgative Medicins; if ſo be the Patient have not a ſtrong and continual Fever. The not viſible evacuation is performed by reſolving and ſudorifick potions, baths, and a ſlender diet. Concerning Bloud-letting, *Galens* opinion is plain, where he bids, in a fall from an high place, and generally for bruiſes upon what part ſoever they be, to open a Vein, though the parties affected are not of a full conſtitution; for that, unleſs you draw bloud by opening a Vein, there may inflammations ariſe from the concrete bloud, from whence without doubt evil accidents may enſue. After you have drawn bloud give him four ounces of Oxycrate to drink; for that by the tenuity of its ſubſtance hinders the coagulation of the bloud in the Belly, or in ſtead thereof you may uſe this following Potion. ℞ *Rad. Gentianæ* ℥ iij. *bulliant in Oxycrato; in colatura diſſolve rhei electi* ℥ j. *fiat potio.* Theſe Medicins diſſolve, and caſt forth by ſpitting and vomit the congealed bloud, if any thereof be contained in the Ventricle or Lungs; it will be expedient to wrap the Patient preſently in a Sheeps skin, being hot and newly taken from the Sheep, and ſprinkled over with a little Myrrhe, Creſſes and Salt, and ſo to put him preſently in his Bed, and then cover him ſo that he may ſweat plentifully. The next day take away the Sheeps skin, and anoint the body with the following Anodyne and reſolving Unguent. ℞ *Unguent. de althæa* ℥ vj. *olei Lumbric. chamæm. anethi, an.* ℥ ij. *terebinth. venetæ,* ℥ iv. *farinæ fœnugræ. roſar. rub. pulveriſat. pul. myrtillorum, an.* ℥ j. *fiat litus ut dictum eſt.* Then give this potion which is ſudorifick, and diſſolves the congealed bloud. ℞ *Ligni guajaci,* ℥ viij. *radicis enulæ camp. conſolid. majoris, ireos Florent. polypod. querni, ſeminis coriandri, aniſi, an.* ℥ ß. *glycyrrhiz.* ℥ ij. *nepetæ, centaureæ, caryophyl. cardui benedict. verbenæ, an. m. ſ. aquæ fontanæ lib.* xij. Let them be all beaten and infuſed for the ſpace of twelve hours, then let them boil over a gentle fire until the one half be conſumed; let the Patient drink ſome half a pint of this drink in the morning, and then ſweat ſome hours upon it in his bed, and do this for ſeven or eight days. If any poor man light upon ſuch a miſchance, who for want of means cannot be at ſuch coſt, it will be good, having wrapped him in ſheet, to bury him up to the chin in Dung mixed with ſome hay or ſtraw, and there to keep him, untill he have ſweat ſufficiently. I have done thus to many with very good ſucceſs. You ſhall alſo give the Patient Potions made with ſyrups which have power to hinder the coagulation and putrefaction of the bloud; ſuch as ſyrup of Vinegar, or Lemmons, of the juice of Citrons and ſuch others to the quantity of an ounce diſſolved in Scabious, or *Carduus* Water. You may alſo preſently after the fall give this drink, which hath power to hinder the coagulation of the bloud, and ſtrengthen the bowels. ℞ *Rhei elect. in pul. redacti* ℈ j. *aquæ rubiæ majoris, & plantagin. an.* ℥ j. *theriacæ* ℥ ß. *ſyrupi de roſis ſiccis,* ℥ ß. *fiat potus.* Let him take it in the morning for four or days. In ſtead hereof you may make a potion of one dram of *Sperma ceti* diſſolved in Bugloſs or ſome other of the Waters formerly mentioned and half an ounce of ſyrup of Maiden-hair; if the diſeaſe yield not at all to theſe formerly preſcribed Medicins, it will be good to give the Patient for nine days, three or four hours before meat, ſome of the following Powder. ℞ *Rhei torrefacti, rad. rub. majoris, centaurei, gentianæ, ariſtolo. rotundæ, an.* ℥ ß. give ℥ j. hereof with ſyrup of Vinegar and *Carduus* Water. They ſay that the Water of Green Walnuts diſtilled by an Alembick, is good to diſſolve congealed and knotted bloud. Alſo you may uſe baths made of the decoction of the roots of Orris, Elecampane, Sorrel, Fennel, Marſh-mallows, Water-fern, or *Oſmund* the Water-man, the greater Comfrey, the ſeeds of Fænugreek, the leaves of Sage, Marjerom; the flowers of Camomile, Melilote, and the like. For a Warm Bath hath power to rarifie the skin, to diſſolve the clotted bloud, by cutting the tough, and mitigating the acrid humours, by calling them forth into the ſurface of the body, and relaxing the paſſages thereof; ſo that the rebellious qualities being overcome, there enſues an eaſie evacuation of the matter by Vomit or Expectoration, if it flote in the Stomach, or be contained in the Cheſt; but by Stool and Urin, if it lie in the lower parts; by ſweats and tranſpiration, if it lie next under the Skin. Wherefore Baths are good for thoſe who have a *Peripneumonia* or inflammation of their Lungs, or a Pleuriſie, according to the mind of *Hippocrates*, if ſo be that they be uſed, when the Fever begins to be aſſwaged; for ſo they mitigate pain, help forwards ſuppuration, and haſten the ſpitting up of the purulent matter. But we would not have the Patient enter into the Bath, unleſs he have firſt uſed general remedies, as Bloud-letting and Purging; for otherwiſe there will be no ſmall danger, leſt the humours diffuſed by the heat of the Bath, cauſe a new defluxion into the parts affected: Wherefore do not thou by any means attempt, to uſe this or the like remedy, having not firſt had the advice of a Phyſician.

Ad ſentent. 62. ſect. 3. lib. de Articulis.

A Potion to diſſolve and evacuate clotted bloud.

A hot Sheeps skin.

A diſcuſſing Ointment.

A Sudorifick Potion to diſſolve congealed bloud.

Syrups hindering putrefaction and congealing of bloud.

A drink for the ſame purpoſe.

A Powder for the ſame.

The diſtilled water of green Walnuts.

Baths.

Lib. 3. de Vict. acut. & lib. 3. de morb.

CHAP. III.

How we muſt handle Contuſions when they are joined with a Wound.

EVery great Contuſion forthwith requires Bloud-letting, or purging, or both; and theſe either for Evacuation or Revulſion. For thus *Hippocrates* in a contuſion of the heel, gives a Vomitory Potion, the ſame day, or elſe the next day after the heel is broken. And then if the Contuſion have a Wound aſſociating it, the defluxion muſt be ſtaid at the beginning with an Ointment made of Bole-Armenick, the White of Eggs and Oil of Roſes, and Myrtles, with the Powders of Red Roſes, Alum, and Maſtich. At the ſecond dreſſing apply a digeſtive made of the Yolk of an Egg, Oil of Violets and Turpentine. This following Cataplaſm ſhall be applied to the near parts to help for-

Sect. lib. fract.

forwards ſuppuration. ℞ *Rad. althææ, & lilii, an.* ℥ iv. *ſol. malv. violar. ſenecionis, an. M.* ß. *coquantur complete, & paſſentur per ſetaceum, addendo butyri recentis & olei viol. an.* ℥ iij. *farinæ volatilis quant. ſufficit; fiat cataplaſma ad formam pultis liquidæ.* Yet have a care in uſing of Cataplaſms, that you do not too much exceed, for too frequent and immoderate uſe of them makes wounds phlegmonous, ſordid, and putrid. Wherefore the Wound, after it is come to ſuppuration, muſt be cleanſed, filled with fleſh and cicatrized; unleſs happily the contuſed fleſh ſhall be very much torn, ſo that the native heat forſake it, for then it muſt be cut away. But if there be any hope to agglutinate it, let it be ſewed, and other things performed according to Art; but the ſtitches muſt not be made ſo cloſe together, as when the Wound is ſimple, and without contuſion; for ſuch Wounds are eaſily inflamed and ſwell up, which would occaſion either the breaking of the thred or fleſh, or tearing of the skin.

A ſuppurative Cataplaſm.

A Caution to be obſerved.

How contuſed Wounds muſt be ſewed.

CHAP. IV.

Of thoſe Contuſions which are without a Wound.

IF the Skin being whole and not hurt, as far as can be diſcerned, the fleſh which lies under it be contuſed, and the bloud poured forth under the Skin make an *Ecchymoſis*, then the Patient muſt be governed according to Art, until the malign ſymptoms, which commonly happen, be no more to be feared. Wherefore in the beginning draw bloud on the oppoſite ſide, both for evacuation and revulſion. The contuſed part ſhall be ſcarified with equal ſcarifications; then ſhall you apply Cupping-glaſſes, or Horns, both for evacuation of the bloud, which cauſes the tumour and tenſion in the part; as alſo to ventilate and refrigerate the heat of the part, leſt it turn into an Abſceſs. Neither muſt we, in the mean while omit gentle purging of the Belly. The firſt Topick Medicins ought to be aſtrictives, which muſt lie ſome ſhort while upon the part, that ſo the Veins and Arteries may be, as it were, ſtraitned and cloſed up, and ſo the defluxion hindered, as alſo that the part it ſelf may be ſtrengthened. This may be the form of ſuch a remedy, ℞ *Albumina ovorum nu.* iij. *olei myrtini & roſ. an.* ℥ j. *boli armeni, & ſang. drac. an.* ℥ ß. *nucum cupreſ. gallar. pul. alum. uſti, an.* ʒ ij. *incorporentur omnia addendo aceti parum, fiat medicamentum.* Then you ſhall reſolve it with a fomentation, cataplaſm, and diſcuſſing Emplaiſters.

Phlebotomy. Scarifying Cupping-glaſſes.

Aſtrictives how good in Contuſions.

After aſtrictives muſt follow diſcuſſives.

CHAP. V.

By what means the contuſed part may be freed from the fear and imminent danger of a Gangrene.

GReat Contuſions are dangerous even for this cauſe, for that a Gangrene and mortification ſometimes follow them; which *Hippocrates* teacheth to happen, when as the affected part is grown very hard and liquid. Wherefore when the part grows livid and black, and the native colour thereof, by reaſon of the efflux of the concrete bloud is almoſt extinct; chiefly to eaſe the part of that burden, Cupping-glaſſes and Horns ſhall be applied to the part it ſelf being firſt ſcarified with a Lancet, or elſe the following Inſtrument termed a *Scarificator*, which hath 18 little wheels ſharp and cutting like a Razor, which may be ſtraitned and ſlacked by the pins noted by *D* and *P*. This Inſtrument is to be commended for that it performs the operation quickly and gently, for it makes 18 Inciſions in the ſpace that you make one with a Lancet, or Knife.

Sect. 2. lib. de fract. The cauſe of a Gangrene.

The uſe of a *Scarificator.*

Then ſhall you foment the part with ſtrong Vinegar wherein the Roots of Radiſh, or of Dragons, Cuckow-pint, *Solomons* Seal, *Auripigmentum*, and the like, have been boiled; for ſuch acrid things do powerfully heat, reſolve, and draw the concrete bloud from the inner part of the body unto the Skin, which by its ſetling in the part affected, prohibits the entrance of the vital ſpirits, the preſervers of its integrity, yea alſo extinguiſheth the native heat of the ſame part. Now we muſt not uſe theſe things but with great diſcretion, leſt ſo we draw not onely that bloud which is poured forth of the Veſſels, but alſo the other which is contained in the Veſſels. Moreover alſo we muſt not uſe them, unleſs when the defluxion is ſtaid. For ſmall Contuſions (which *Galen* judgeth by the ſoftneſs of the contuſed part) it will be ſufficient to apply to diſcuſs them, Virgins-wax diſſolved and mixed with Cummin-ſeeds, Cloves, the Root of the black Briony, (which hath a wonderful faculty to diſcuſs all blackneſs and ſugillation:) for the ſame purpoſe, you may alſo apply Wormwood bruiſed, and ſo warmed in a diſh and ſprinkled over with a little white Wine. Alſo fry Wormwood with Oil of Camomil, Bran, the Powder of Cloves and Nutmegs, adding thereto a little *Aqua vitæ*; then put all in a linnen cloth, and apply it hot to the part. The following Emplaiſter doth powerfully diſcuſs congealed bloud.

A fomentation to diſcuſs and draw to the Skin.

Inſect. 2. lib. de fract.

A Scarificator.



A *Shews the Cover.* B *The Box, or Caſe.*

℞ *Picis nigræ* ℥ ij. *Gum. Elemi* ʒ j. ß. *ſtyracis liquidæ & terebinth. com. an.* ℥ ß. *ſulphuris vivi* ʒ j. *Liquefiant ſimul, fiat Empl.* and let it be ſpread upon Leather, and ſo applied.

A diſcuſſing Plaiſter.

CHAP. VI.

Of that ſtrange kind of Symptom which happens upon Contuſions of the Ribs.

Hip. ſect.3. lib. de art. ſent.58. & 65.

THe fleſh contuſed ſometimes by great violence, becomes mucous and ſwoln, or puffed up like Veal which the Butchers blow up, the Skin remaining whole. This is ſeen and happens chiefly in that fleſh which is about the ribs; for this being bruiſed either by a blow or fall, or renitency, or any other ſuch like cauſe; if you preſs it with your hand, a certain windineſs goeth out thereof with a ſmall whizzing, which may be heard, and the print of your fingers will remain, as in *œdemaes*. Unleſs you quickly make fit proviſion againſt this ſymptom, there is gathered in that ſpace, which the fleſh departing from the bones leaves empty, a certain purulent *ſanies*, which divers times fouls and corrupts the ribs. It will be cured, if the mucous tumor be preſently preſſed, and ſtraitly bound with ligatures, yet ſo, that you hinder not the breathing, when as the affect happens upon the Ribs and parts of the Cheſt. Then apply to the part a Plaiſter of *Oxycroceum*, or *Diachylon Ireatum* with the Emplaiſter *de meliloto*; alſo diſcuſſing fomentations ſhall be uſed. The cauſe of ſuch a tumour is a certain mucous flegm, ſeeing that Nature is ſo weak that it cannot well digeſt the nouriſhment, and aſſimilate it to the part, but leaves ſomething, as it were half concocted. No otherwiſe than the conjunctive coat of the eye is ſometime ſo lifted up, and ſwoln by a ſtroak, that it ſtarts, as it were, out of the orb of the eye, leaving ſuch filth, or matter, as we ſee thoſe which are blear-eyed to be troubled withall; becauſe the force and natural ſtrength of the eyes is become more weak, either by the fault of the proper diſtemperature, or the abundance of moiſture which flows thither, as it happens in thoſe tumours which are againſt Nature. For flatulencies are eaſily raiſed from a wateriſh and phlegmatick humour wrought upon by weak heat, which mixed with the reſt of the humour, the tumour becomes higher.

Remedies for a mucous and flatulent humour of the Ribs.

The cauſe.

CHAP. VII.

A Diſcourſe of Mumia, *or Mummy.*

Mummy a frequent and uſual Medicin in Contuſions.

The reaſon that the Author makes no mention there of amongſt his Medicins.

PEradventure it may ſeem ſtrange what may be the cauſe why in this Treatiſe of curing Contuſions or Bruiſes, I have made no mention of giving Mummy either in Bole or Potion to ſuch as have fallen from high places, or have been otherwiſe bruiſed; eſpecially ſeeing it is ſo common and uſual, yea the very firſt and laſt Medicin of almoſt all our practitioners at this day in ſuch a caſe. But ſeeing I underſtood, and had learnt from learned Phyſicians, that in uſing remedies, the Indication muſt always be taken from that which is contrary to the Diſeaſe, How could I? or how can any other give Mummy in this kind of Diſeaſe, ſeeing we cannot as yet know what Mummy is, or what is the nature and eſſence thereof? So that it cannot certainly be judged, whether it have a certain property contrary to the nature and effects of Contuſions. This, how it may have, I have thought good to relate ſomewhat at large; neither do the Phyſicians who preſcribe Mummy, nor the Authors that have written of it, nor the Apothecaries that ſell it, know any certainty thereof. For if you read the more ancient *Serapio* and *Avicen*, or the Modern *Matthiolus* and *Thevet*, you ſhall find quite different opinions. Ask the Merchants who bring it to us, ask the Apothecaries who buy it of them to ſell it to us, and you ſhall hear them ſpeak diverſly hereof, that in ſuch variety of opinions, there is nothing certain and manifeſt. *Serapio* and *Avicen* have judged Mummy to be nothing elſe but *Piſſaſphalthum*; now *Piſſaſphalthum* is a certain froth or foam riſing from the Sea, or Sea-waters; this ſame foam as long as it ſwims upon the Water is ſoft, and in ſome ſort liquid; but being driven upon the ſhore by force of tempeſt and working of the Sea, and ſticking in the cavities of the Rocks, it concretes into ſomewhat a harder ſubſtance than dried Pitch, as *Dioſcorides* ſaith. *Bellonius* ſaith, that Mummy is onely known to *Ægypt* and *Greece*. Others write that it is mans fleſh, taken from the Carcaſes of ſuch as are dead and covered over in the Sands in the Deſarts of *Arabia*; in which Countrey they ſay the Sands are ſometimes carried and raiſed up with ſuch force and violence of the Winds, that they overthrow and ſuffocate ſuch paſſengers as they meet withall; the fleſh of theſe, dried by the Sand and Wind, they affirm to be Mummy. *Matthiolus* following the more uſual and common opinion, writes that Mummy is nothing elſe than a liquor flowing from the Aromatick Embalments of dead Bodies, which becomes dry and hard. For underſtanding whereof you muſt know from all manner of antiquity, that the *Ægyptians* have been moſt ſtudious in burying and embalming their dead; not for that end, that they ſhould become Medicins for ſuch as live, for they did not ſo much as ſuſpect or imagine ſo horrid a wickedneſs; but either for that they held an opinion of the general Reſurrection, or that in theſe Monuments they might have ſomething whereby they might keep their dead friends in perpetual remembrance. *Thevet* not much diſſenting from his own opinion, writes that the true Mummy is taken from the Monuments and ſtony Tombs of the anciently dead in *Egypt*, the chinks of which Tombs were cloſed and cemented with ſuch diligence, the encloſed bodies embalmed with pretious Spices, with ſuch Art, for eternity; that the linnen veſtures which were wrapt about them preſently after their death, may be ſeen whole even to this day; but the bodies themſelves, are ſo freſh, that you would judge them ſcarce to have been three days buried. And yet in thoſe Sepulchres and Vaults from whence theſe Bodies are taken, there have been ſome Corps of two thouſand years old. The ſame, or their broken members are brought to *Venice* from *Syria* and *Egypt*, and thence diſperſed over all Chriſtendom. But according to the different condition of men, the matter of their embalments were divers; for the bodies of the Nobility or Gentry were embalmed with Myrrh, Aloes, Saffron, and other pretious Spices, and Drugs; but the bodies of the common ſort, whoſe poverty and want of means could not undergo ſuch coſt, were embalmed with *Aſphaltum* or *Piſſaſphaltum*.

The opinion of the *Arabians* concerning it.

Lib.4.cap.84. Another opinion of Mummy.

Another.

Now

Now *Mathiolus* ſaith, that all the Mummy which is brought into theſe parts, is of this laſt kind and condition. For the Noble-men and chief of the Province, ſo religiouſly addicted to the Monuments of their Anceſtors, would never ſuffer the bodies of their friends and kindred to be tranſported hither for filthy gain, and ſuch deteſted uſe, as we ſhall ſhew more at large at the end of this Work. Which thing ſometimes moved certain of our *French* Apothecaries, men wondrous audacious and covetous, to ſteal by night the bodies of ſuch as were hanged, and embalming them with Salt and Drugs, they dried them in an Oven, ſo to ſell them thus adulterated in ſtead of true Mummy. Wherefore we are thus compelled both fooliſhly and cruelly to devour the mangled and putrid particles of the carkaſſes of the baſeſt people of *Ægypt*, or of ſuch as are hanged, as though there were no other way to help or recover one bruiſed with a fall from a high place, than to bury Man by an horrid inſertion in their, that is, in Mans Guts. Now if this Drug were any way powerful for that they require, they might perhaps have ſome pretence for this their more than barbarous inhumanity. But the caſe ſtands thus, that this wicked kind of Drug, doth nothing help the diſeaſed, in that caſe, wherefore and wherein it is adminiſtred, as I have tried a hundred times; and as *Thevet* witneſſes, he tried in himſelf, when as he took ſome thereof by the advice of a certain *Jewiſh* Phyſician in *Egypt*, from whence it is brought; but it alſo infers many troubleſom ſymptoms, as the pain of the heart, or ſtomach, vomiting and ſtink of the mouth.

What our Mummy uſually is.

Mummy is no way good for contuſions.

I, perſuaded by theſe reaſons, do not onely my ſelf not preſcribe any hereof to my Patients, but alſo in conſultations, endeavour what I may, that it be not preſcribed by others. It is far better, according to *Galen*'s opinion, in *Method. med.* to drink ſome Oxycrate, which by its frigidity reſtrains the flowing bloud, and by its tenuity of ſubſtance diſſolves and diſcuſſes the congealed clots thereof. Many reaſons of learned Phyſicians (from whom I have learned this Hiſtory of Mummy) drawn from Philoſophy, whereby they make it apparent, that there can be no uſe of this or that Mummy in contuſions, or againſt flowing or congealed bloud, I willingly omit; for that I think it not much beneficial to Chirurgeons to inſert them here. Wherefore I judge it better to begin to treat of Combuſtions or Burns.

But hurtful, and how.

The effects of Oxycrate in Contuſions.

CHAP. VIII.

Of Combuſtions and their Differences.

ALl Combuſtions whether occaſioned by Gun-powder, or by ſcalding Oil, Water, ſome Metal, or what things ſoever elſe, differ onely in magnitude. Theſe firſt cauſe pain in the part, and imprint in it an unnatural heat. Which ſavouring of the fire, leaves that impreſſion, which the Greeks call *Empyreuma*. There are more or leſs ſigns of this impreſſion, according to the efficacy of the thing burning, the condition of the part burned, and ſtay upon the ſame. If the combuſtion be ſuperficiary, the skin riſes into puſtules and bliſters, unleſs it be ſpeedily prevented. If it be low or deep in, it is covered with an *Eſchar* or Cruſt, the burnt fleſh by the force of the fire turning into that cruſty hardneſs. The burning force of the fire, upon whatſoever part it falls, leaves a hot diſtemper therein, condenſates, contracts, and thickens the skin, whence pain proceeds; from pain there comes an attraction of humours from the adjacent and remote parts. Theſe humours preſently turn into wateriſh or ſerous moiſture, whileſt they ſeek to paſs forth, and are hindred thereof by the skin condenſated by the action of the fire, they lift it up higher, and raiſe the bliſters which we ſee. Hence divers Indications are drawn, whence proceeds the variety of Medicins for burns. For ſome take away the *Empyreuma*, that is, the heat of the fire, (as we term it) and aſſwage the pain; other hinder the riſing of bliſters, otherſome are fit to cure the ulcer, firſt to procure the falling away of the *Eſchar*, then to cleanſe, generate fleſh, and cicatrize it. Remedies fit to aſſwage pain, and take away the fiery heat, are of two kinds; for ſome do it by a cooling faculty, by which they extinguiſh the preternatural heat, and repreſs or keep back the bloud and humours, which flow into the parts by reaſon of heat and pain. Others endued with contrary faculties, are hot and attractive; as which by relaxing the skin, and opening the pores, reſolve and diſſipate the ſerous humours, which yield both begining and matter to the puſtules, and ſo by accident aſſwage the pain and heat. Refrigerating things are cold Water, the Water of Plantain, Nightſhade, Henbane, Hemlock; the juices of cooling Herbs, as Purſlane, Lettuce, Plantain, Houſleek, Poppy, Mandrake, and the like. Of theſe ſome may be compounded, as ſome of the fore-named juices beaten with the white of an Egg, Clay beaten and diſſolved in ſtrong Vinegar, Roch-Alum diſſolved in Water, with the Whites of Eggs beaten therein, Writing-Ink mixed with Vinegar, and a little Camphire, *Unguentum nutritium*, and alſo *Populeon* newly made. Theſe and the like ſhall be now and then renewed, chiefly at the firſt, until the heat and pain be gone. But theſe ſame remedies muſt be applied warm, for if they ſhould be laid, or put to cold, they would cauſe pain, and conſequently defluxion; beſides alſo, their ſtrength could not paſs, or enter into the part, or be brought into action; but ſo applied they aſſwage pain, hinder inflammation and the riſing of bliſters.

The reaſon and ſymptoms of Combuſtions.

The cauſe of the bliſters riſing upon Burns.

Variety of Medicins to take away the heat and aſſwage the pain

CHAP. IX.

Of hot and attractive Medicins to be applied to Burns.

AMongſt the hot and attractive things which by rarifying, drawing out, and diſſolving, aſſwage the pain and heat of combuſtions, the fire challenges the firſt place, eſpecially when the burning is but ſmall. For the very common people know and find by daily experience, that the heat of the lightly burnt part vaniſhes away, and the pain aſſwaged, if they hold the part which was burnt ſome pretty while to the heat of a lighted Candle or burning Coals, for the ſimi-

How fire may aſſwage the pain of burning.

litude

litude cauſeth attraction. Thus the external fire, whileſt it draws forth the fire which is internal and inuſt into the part, is a remedy againſt the diſeaſe it cauſed and bred. It is alſo an eaſily made and approved remedy, if they preſently after the Burn, apply to the grieved part raw Onions beaten with ſome Salt. Now you muſt note that this Medicin takes no place, if it be once gone into an ulcer, for it would increaſe the pain and inflammation; but if it be applied when the skin is yet whole and not excoriated, it doth no ſuch thing, but hinders the riſing of puſtules and bliſters. *Hippocrates* for this cauſe alſo uſes this kind of remedy in procuring the fall of the *Eſchar*. If any endeavour to gain-ſay the uſe of this remedy by that principle in Phyſick, which ſays, that Contraries are cured by Contraries, and therefore affirm that Onions, according to the authority of *Galen*, being hot in the fourth degree, are not good for combuſtions; let him know that Onions are indeed potentially hot, and actually moiſt, therefore they rarifie by their hot quality, and ſoften the skin by their actual moiſture, whereby it comes to paſs that they attract, draw forth, and diſſipate the imprinted heat, and ſo hinder the breaking forth of Puſtules. To conclude, the fire, as we formerly noted, is a remedy againſt the fire. But neither are diſeaſes always healed by their contraries (ſaith *Galen*) but ſometimes by their like; although all healing proceed from the contrary; this word *contrary*, being more largely and ſtrictly taken: for ſo alſo a Phlegmon is often cured by reſolving Medicins, which healeth it by diſſipating the matter thereof. Therefore Onions are very profitable for the burnt parts, which are not yet exulcerated or excoriated. But there are alſo many other Medicins good to hinder the riſing of bliſters, ſuch as new Horſe-dung fried in Oil of Wal-nuts or Roſes, and applied to the parts. In like manner the leaves of Elder or Dane-wort boiled in Oil of Nuts, and beaten with a little Salt. Alſo quenched Lime powdered and mixed with *Unguentum Roſatum*. Or elſe the leaves of Cuckow-pint and Sage, beaten together with a little Salt. Alſo Carpenters Glue diſſolved in Water and anointed upon the part with a feather, is good for the ſame purpoſe. Alſo thick Verniſh which Poliſhers or Sword-Cutlers uſe. But if the pain be more vehement, theſe Medicins muſt be renewed three or four times in a day and a night, ſo to mitigate the bitterneſs of this pain. But if if ſo be we cannot by theſe remedies hinder the riſing of bliſters, then we muſt preſently cut them as ſoon as they riſe, for that the humour contained in them, not having paſſage forth, acquires ſuch acrimony that it eats the fleſh which lieth under it, and ſo cauſeth hollow ulcers: So by the multitude of cauſes and increaſe of matter the inflammation groweth greater, not onely for nine days (as the common people prattle) but for far longer time; alſo ſomewhiles for leſs time, if the body be neither replete with ill humours, nor plethorick, and you have ſpeedily reſiſted the pain and heat by fit remedies. When the combuſtion ſhall be ſo great as to cauſe an *Eſchar*, the falling away muſt be procured by the uſe of emollient and humective Medicins, as of Greaſes, Oils, Butter with a little *Baſilicon*, or the following Ointment. ℞ *Mucagin. pſillii & cydon. an.* ℥ iv. *gummi trag.* ℥ ij. *extrahantur cum aqua parietaria, olei liliorum* ℥ ij. ß. *ceræ novæ q.ſ. fiat unguentum molle.* For ulcers and excoriations you ſhall apply fit remedies; which are thoſe that are without acrimony, ſuch as *Unguentum album camphoratum, deſiccativum rubrum, unguentum roſatum*, made without Vinegar, or *nutritum*, compoſed after this manner. ℞ *Lithargyri auri* ℥ iv. *ol. roſat.* ℥ iij. *ol. de papaver.* ℥ ij. ß. *ung. populeon.* ℥ iv. *camphoræ* ℥ j. *fiat unguentum in mortario plumbeo ſecundum artem.* Or Oil of Eggs tempered in a Leaden Mortar. Alſo unquenched Lime many times waſhed and mixed with *unguentum roſatum*, or freſh Butter without Salt, and ſome yolks of Eggs hard roaſted. Or ℞ *Butyri recent. ſine ſale, uſtulati, & colati* ℥ vj. *vitell. ovor.* iv. *ceruſ. lotæ in aqua plantag. vel roſar.* ℥ ß. *tuthiæ ſimiliter lotæ* ℥ iij. *plumbi uſti, & loti* ℥ ij. *Miſceantur omnia ſimul, fiat linimentum ut decet.* Or elſe, ℞ *cort. ſambuc. viridis, & olei roſat. an. lib.* j. *bulliant ſimul lento igne, poſtea colentur, & adde olei ovorum* ℥ iv. *pul. ceruſ. & tuthiæ præpar. an.* ℥ j. *ceræ albæ quantum ſufficit. fiat unguentum molle ſecundum artem.* But the quantity of drying Medicins may always be increaſed or diminiſhed, according as the condition of the Ulcer ſhall ſeem to require. The following remedies are fit to aſſwage pain, as the mucilages of Lin-ſeeds, of the ſeeds of *Pſillium*, or Flea-wort, and Quinces extracted in Roſe-water, or fair water, with the addition of a little Camphire; and leſt that it dry too ſpeedily, add thereto ſome Oil of Roſes. Alſo five or ſix yolks of Eggs mixed with the mucilages of Lin-ſeed, the ſeed of *Pſillium*, and Quinces often renewed, are very powerful to aſſwage pain. The Women which attend upon the people in the Hoſpital in *Paris*, do happily uſe this Medicin againſt Burns. ℞ *Lard. conſciſſi libram unam*; let it be diſſolved in Roſe-water, then ſtrained through a linnen-cloth, then waſh it four times with the Water of Henbane, or ſome other of that kind, then let it be incorporated with eight yolks of new laid Egs, and ſo make an Ointment. If the ſmart be great, as uſually it is in theſe kinds of Wounds, the Ulcer or Sores ſhall be covered over with a piece of Tiffany, leſt you hurt them by wiping them with ſomewhat a coarſe cloth, and ſo alſo the matter may eaſily come forth, and the Medicins eaſily enter in. Alſo you muſt have a care when the eye-lids, lips, ſides of the fingers, neck, the arm-pits, hams, and bending of the elbow are burnt, that you ſuffer not the parts to touch one the other, without the interpoſition of ſome thing; otherwiſe in continuance of time they would grow and ſtick together Therefore you ſhall provide for this, by fit placing the parts, and putting ſoft linnen rags between them. But you muſt note that deep combuſtions, and ſuch as cauſe a thicker *Eſchar*, are leſs painful than ſuch as are but onely ſuperficiary. The truth hereof you may perceive by the example of ſuch as have their limbs cut off, and ſeared and cauterized with an hot Iron: for preſently after the cauterizing is performed they feel little pain. For this great combuſtion takes away the ſenſe; the vehemency of the ſenſory or thing affecting the ſenſe, depriving the ſenſitive parts of their ſenſe: as we have formerly noted when we treated of Wounds and Pains of the Nerves. The falling away of ſuch *Eſchars* ſhall be procured by ſomewhat a deep ſcarification which may pierce even to the quick, that ſo the humours which lie under it may enjoy freer perſpiration, and emollient Medicins may the freelier enter in, ſo to ſoak, moiſten and ſoften the *Eſchar*, that it may at length fall away. The reſt of the Cure ſhall be performed by detergent and ſarcotick Medicins, adding to the former Ointments Metalline Powders, when the preſent neceſſity ſhall ſeem ſo to require. But we cannot

Beaten Onions good for Burns, and how.

Lib. 5. ſimpl.

How often in a day theſe muſt be dreſſed.

Medicins for an *Eſchar*.

A deſcription of *Nutritum*.

A remedy for Burns commonly uſed in the Hoſpital of *Paris*.

Why deep combuſtions are leſs painful than ſuperficiary.

juſtly

juſtly ſay in what proportion and quantity each of theſe may be mixed, by reaſon of that variety which is in the temper and conſiſtence of bodies, and the ſtubbornneſs and gentleneſs of Diſeaſes. After a Burn the Scar which remaineth is commonly rough, unequal, and ill-favoured: therefore we will tell you in our Treatiſe of the Plague, how it muſt be ſmoothed and made even.

I muſt not here omit to tell you, that Gun-powder ſet on fire doth often ſo penetrate into the fleſh, not ulcerating or taking off the skin, and ſo inſinuate and throughly faſten it ſelf into the fleſh by its tenuity, that it cannot be taken or drawn out thence by any remedies, no not by *Phœnigmes*, nor Veſicatories, nor Scarification, nor Ventoſes, nor Horns, ſo that the Prints thereof always remain, no otherwiſe than the marks which the *Barbarians* burn in their Slaves, which cannot afterwards be taken away or deſtroyed by any Art.

Marks or ſpots made in the face by corns of Gun-powder cannot be taken away.

CHAP. X.

Of a Gangrene and Mortification.

CErtainly the malign ſymptoms which happen upon Wounds, and the ſolutions of Continuity, are many, cauſed either by the ignorance or negligence of the Chirurgeon; or by the Patient, or ſuch as are about him; or by the malignity and violence of the Diſeaſe: but there can happen no greater than a Gangrene, as that which may cauſe mortification and death of the part, and oft-times of the whole body; wherefore I have thought good in this place to treat of a Gangrene, firſt giving you the definition, then ſhewing you the cauſes, ſigns, prognoſticks, and laſtly, the manner of the Cure. Now a Gangrene is a certain diſpoſition, and way to the mortification of the part, which it ſeizeth upon, dying by little and little. For when there is a perfect mortification, it is called by the Greeks *Sphacelos*, by the Latins *Syderatio*, our Countrey-men term it the Fire of S. *Anthony*, or S. *Marcellus*.

Gal. 2. ad Glauconem.

CHAP. XI.

Of the general and particular cauſes of a Gangrene.

THe moſt general cauſe of a Gangrene is, when by the diſſolution of the harmony and joint temper of the four firſt qualities, the part is made unapt to receive the Faculties, the Natural, Vital, and Animal Spirits, by which it is nouriſhed, lives, feels, and moves. For a part deprived by any chance of theſe, as of the light, languiſhes, and preſently dies. Now the particular cauſes are many: and theſe either primitive or antecedent. The primitive or external are combuſtions cauſed by things either actually or potentially burning; actually, as by Fire, ſcalding Oil, or Water, Gun-powder fired, and the like. But potentially by acrid Medicins, as Sublimate, Vitriol, potential Cauteries, and other things of the ſame nature: for all theſe cauſe a great inflammation in the part. But the ambient air may cauſe great refrigerations, and alſo a Gangrene, which cauſed *Hippocrates lib. de Aer.* to call great refrigerations of the Brain *Sphaceliſm*. Therefore the unadviſed and unfit application of cold and narcotick things, a fracture, luxation, and great contuſion, too ſtrait bandages, the biting of Beaſts, eſpecially of ſuch as are venemous, a puncture of the Nerves and Tendons, the wounds of the nervous parts and joints, eſpecially in bodies which are plethorick and replete with ill humours, great wounds whereby the Veſſels which carry life are much cut, whence an *Aneuriſma*, and laſtly, many other cauſes, which perturb that harmony of the four prime qualities which we formerly mentioned, and ſo infer a Gangrene.

The general cauſe of a Gangrene.

The particular cauſes.

Cold cauſeth a Gangrene.

CHAP. XII.

Of the Antecedent Cauſes of a Gangrene.

NOw the Antecedent or Internal and Corporeal cauſes of a Gangrene, are plentiful and abundant defluxions of humours, hot, or cold, falling into any part. For ſeeing the faculty of the part is unapt and unable to ſuſtain and govern ſuch plenty of humours, it comes to paſs that the native heat of the part is ſuffocated and extinct for want of tranſpiration. For the Arteries are hereby ſo ſhut or pent up in a Strait, that they cannot perform their motions of contraction and dilatation, by which their native heat is preſerved and tempered. But then the Gangrene is chiefly uncurable when the influx of humours firſt takes hold of the Bones, and inflammation hath its beginning from them. For in the opinion of *Galen*, all theſe kinds of affects which may befall the fleſh, are alſo incident to the bones. Neither onely a Phlegmon or Inflammation, but alſo a rottenneſs and corruption doth oft-times firſt invade and begin at the bones; for thus you may ſee many who are troubled with the Leproſie and French diſeaſe, to have their skin and fleſh whole and fair to look on, whoſe bones notwithſtanding are corrupt and rotten, and oft-times are much decayed in their proper ſubſtance. This miſchief is cauſed by a venemous matter, whoſe occult quality we can ſcarce expreſs by any other name than poiſon inwardly generated. Oft-times alſo there is a certain acrid and ſtinking filth generated in fleſh with a malign and old ulcer, with which if the bones chance to be moiſtned they become foul, and at length mortified: of which this ſaying of *Hippocrates* is extant, Ulcers of a years continuance, or longer, muſt neceſſarily foul the bone, and make the ſcars hollow. Whither alſo belongs this ſaying of the ſame party; An *Eryſipelas* is ill in the laying bare of a bone. But this flowing venenate and gangrenous matter is ſomewhiles hot, as in peſtilent Carbuncles, which in the ſpace of four and twenty hours by cauſing an *Eſchar*, bring the part to mortification: otherwhiles cold, as we ſee it divers times happens in parts which are poſſeſt with a Gan-

How defluxions cauſe a Gangrene.

An uncurable Gangrene.

Lib. de tumor. præter natur.

Aph. 5. ſect. 6.

A Gangrene by efflux of a cold matter.

Gangrene, no pain, tumor, blackneſs, nor any other precedent ſign of a Gangrene going before. For *John de Vigo* ſaith, that happened to a certain Gentlewoman of *Genoa* under his cure.

A notable Hiſtory.

I remember the ſame happened to a certain man in *Paris*, who ſupping merrily, and without any ſenſe of pain, went to bed, and ſuddenly in the night time a Gangrene ſeized on both his legs, cauſed a mortification without tumour, without Inflammation; onely his legs were in ſome places ſpred over with livid, black, and green ſpots, the reſt of the ſubſtance retaining his native colour: yet the ſenſe of theſe parts was quite dead, they felt cold to the touch; and if you did thruſt your Lancet into the skin no bloud came forth. A Council of Phyſicians being called, they thought good to cut the skin and fleſh lying under it, with many deep ſcarifications; which when I had done, there came forth a little black, thick, and as it were, congealed bloud; wherefore this remedy, as alſo divers other, proved to no purpoſe; for in concluſion, a blackiſh colour coming into his face and the reſt of his body, he died frantick. I leave it to the Readers judgment, whether ſo ſpeedy and ſuddenly cruel a miſchief could proceed from any other than a venenate matter; yet the hurt of this venenate matter is not peculiar, or by its ſelf. For oft-times the force of cold, whether of the encompaſſing air, or the too immoderate uſe of Narcotick Medicins is ſo great, that in few hours it takes away life from ſome of the members, and divers times from the whole body, as we may learn by their example who travel in great Snows, and over Mountains congealed, and hoared with Froſt and Ice. Hence alſo is the extinction of the native heat, and the ſpirits reſiding in the part, and the ſhutting forth of that which is ſent by Nature to aid or defend it. For when as the part is bound with rigid cold, and as it were frozen, they cannot get nor enter therein. Neither if they ſhould enter into the part, can they ſtay long there, becauſe they can there find no fit habitation, the whole frame and government of Nature being ſpoiled, and the harmony of the four prime qualities deſtroyed by the offenſive dominion of predominant Cold their Enemy; whereby it cometh to paſs, that flying back from whence they firſt came, they leave the part deſtitute and deprived of the benefit of nouriſhment, life, ſenſe, and motion.

Simple cold may cauſe a Gangrene.

A Hiſtory.

A certain *Briton* an Hoſtler in *Paris*, having drunk ſoundly after Supper, caſt himſelf upon a Bed; the cold air coming in at a Window left open, ſo took hold upon one of his legs, that when he waked forth of his ſleep, he could neither ſtand nor go. Wherefore thinking onely that his leg was numb, they made him ſtand to the fire; but putting it very nigh, he burnt the ſole of his foot without any ſenſe of pain, ſome fingers thickneſs; for a mortification had already poſſeſſed more than half his leg. Wherefore after he was carried to the Hoſpital, the Chirurgeon who belonged thereto, endeavoured by cutting away of the mortified leg to deliver the reſt of the body from imminent death; but it proved in vain, for the mortification taking hold upon the upper parts, he died within three days, with troubleſom belching and hicketing, raving, cold ſweat, and often ſwounding. Verily all that ſame Winter the Cold was ſo vehement that many in the Hoſpital of *Paris*, loſt the wings or ſides of their noſtrils, ſeized upon by a mortification without any putrefaction. But you muſt note that the Gangrene which is cauſed by cold, doth firſt and principally ſeize upon the parts moſt diſtant from the heart, the fountain of heat, to wit, the feet and legs; as alſo ſuch as are cold by nature, as griſly parts, ſuch as the Noſe and Ears.

What parts are uſually taken by a Gangrene proceeding of cold.

CHAP. XIII.

Of the Signs of a Gangrene.

THe ſigns of a Gangrene, which inflammation or a Phlegmon hath cauſed, are pain and pulſation without manifeſt cauſe, the ſudden changing of the fiery and red colour into a livid or black, as *Hippocrates* ſhews where he ſpeaks of the Gangrene of a broken heel. I would have you here to underſtand the pulſifick pain, not onely to be that which is cauſed by the quicker motion of the Arteries, but that heavy and pricking which the contention of the natural heat doth produce by raiſing a thick cloud of vapours from theſe humours which the Gangrene ſets upon. The ſigns of a Gangrene cauſed by cold, are, if ſuddenly a ſharp pricking and burning pain aſſaileth the part; for *penetrabile frigus adurit, (i.)* piercing cold doth burn: if a ſhining redneſs, as if you had handled Snow, preſently turn into a livid colour; if in ſtead of the accidental heat which was in the part, preſently cold and numbneſs ſhall poſſeſs it, as if it were ſhook with a Quartan Fever. Such cold, if it ſhall proceed ſo far as to extinguiſh the native heat, bringeth a mortification upon the Gangrene; alſo oft-times Convulſions and violent ſhaking of the whole body, are wondrous troubleſome to the Brain and the Fountains of life. But you ſhall know Gangrenes cauſed by too ſtrait bandages, by fracture, luxation, and contuſion, by the hardneſs which the attraction and flowing down of the humours hath cauſed, little pimples or bliſters ſpreading or riſing upon the skin by reaſon of the great heat, as in a combuſtion; by the weight of the part occaſioned through the defect of the ſpirits not now ſuſtaining the burden of the member; and laſtly from this, the preſſing of your finger upon the part, it will leave the print thereof as in an *œdema*; and alſo from this, that the skin cometh from the fleſh without any manifeſt cauſe.

Sect. 6. lib. de fractur.

What a pulſifick pain is.

Signs of a Gangrene proceeding from cold.

Signs of a Gangrene proceeding from ſtrait bandages, or ligatures, &c.

Now you ſhall know Gangrenes ariſing from a bite, puncture, *aneuriſma*, or wound in plethorick and ill bodies, and in a part indued with moſt exquiſite ſenſe, almoſt by the ſame ſigns as that which was cauſed by inflammation. For by theſe and the like cauſes, there is a far greater defluxion and attraction of the humours than is fit, when the perſpiration being intercepted, and the paſſages ſtopt, the native heat is oppreſſed and ſuffocated. But this I would admoniſh the young Chirurgeon, that when by the fore-mentioned ſigns he ſhall find the Gangrene preſent, that he do not defer the amputation, for that he finds ſome ſenſe or ſmall motion reſiding in the part. For oft-times the affected parts are in this caſe moved not by the motion of the whole Muſcle, but onely by means, that

Signs of a Gangrene occaſioned by a bite, puncture, &c.

that the head of the Muſcle is not yet taken with the Gangrene: which moving it ſelf by its own ſtrength, alſo moves its proper and continued tendon and tail though dead already; wherefore it is ill to make any delay in ſuch caſes.

CHAP. XIV.

Of the Prognoſticks in Gangrenes.

HAving given you the ſigns and cauſes to know a Gangrene, it is fit we alſo give you the Prognoſticks. The fierceneſs and the malignity thereof is ſo great, that unleſs it be moſt ſpeedily withſtood, the part it ſelf will die, and alſo take hold of the neighbouring parts by the contagion of its mortification: which hath been the cauſe that a Gangrene by many hath been termed an *Eſthiomenos*. For ſuch corruption creeps out like poiſon, and like fire eats, gnaws, and deſtroys all the neighbouring parts, until it hath ſpread over the whole body. For as *Hippocrates* writes, *Lib. de Vulner. capitis*; *Mortui & viventis nulla eſt proportio, (i.)* there is no proportion between the dead and living. Wherefore it is fit preſently to ſeparate the dead from the living; for unleſs that be done, the living will die by the contagion of the dead. In ſuch as are at the point of death, a cold ſweat flows over all their bodies: they are troubled with ravings, and watchings, belchings and hickettings moleſt them, and often ſwoundings invade them by reaſon of the vapours abundantly and continually raiſed from the corruption of the humours and fleſh, and ſo carried to the bowels and principal parts by the Veins, Nerves, and Arteries. Wherefore when you have foretold theſe things to the friends of the Patient, then make haſte to fall to your work.

Why a Gangrene is called *Eſthiomenos*.

The quick impatient of the dead.

CHAP. XV.

Of the general Cure of a Gangrene.

THe Indications of curing Gangrenes are to be drawn from their differences, for the cure muſt be diverſly inſtituted according to the eſſence and magnitude. For ſome Gangrenes poſſeſs the whole member, others onely ſome portion thereof; ſome are deep, other-ſome ſuperficial onely. Alſo you muſt have regard to the temper of the body. For ſoft and delicate bodies, as of Children, Women, Eunuchs, and idle perſons require much milder Medicins than thoſe who by Nature and Cuſtom, or Vocation of life are more ſtrong and hardy, ſuch as Huſbandmen, Labourers, Mariners, Huntſmen, Porters, and men of the like nature who live ſparingly and hardly. Neither muſt you have reſpect to the body in general, but alſo to the parts affected; for the fleſhy and muſculous parts are different from the ſolid, as the Nerves and Joints, or more ſolid, as the *Vertebræ*. Now the hot and moiſt parts, as the Privities, Mouth, Womb, and Fundament, are eaſilier and ſooner taken hold of by putrefaction, wherefore we muſt uſe more ſpeedy means to help them. Wherefore if the Gangrene be chiefly occaſioned from an internal cauſe, he muſt have a diet preſcribed for the decent and fitting uſe of the ſix things not Natural. If the body be plethorick, or full of ill humours, you muſt purge, or let bloud by the advice of a Phyſician. Againſt the aſcending up of vapours to the noble parts, the heart muſt chiefly be ſtrengthened with Treacle diſſolved in Sorrel or *Carduus* Water, with a bole of Mithridate, the Conſerve of Roſes and Bugloſs, and with Opiates made for the preſent purpoſe according to Art; this following Apozeme ſhall be outwardly applied to the region of the heart. ℞ *Aquæ Roſar. & nenuphar. an.* ℥ iv. *aceti ſcillitici,* ℥ j. *corallorum, ſantalorum alborum & rubrorum, roſar. rub. in pulver. redactarum, & ſpodii, an.* ℥ j. *mithrid. & theriacæ, an.* ℥ ij. ℔. *trochiſcorum de Caphura* ℥ ij. *flor. cardial. in pollin. redactarum, p.* ij. *croci* ℥ j. *Ex omnibus in pollinem redactis, fiat Epithema.* Which may be applied upon the region of the heart with a ſcarlet cloth or ſponge. Theſe are uſually ſuch as happen in the Cure of every Gangrene.

Various Indications of curing a Gangrene.

What parts ſooneſt taken hold by a Gangrene.

A cordial *Epithema*.

CHAP. XVI.

Of the particular Cure of a Gangrene.

THe cure of a Gangrene cauſed by the too plentiful and violent defluxion of humours ſuffocating the native heat, by reaſon of great Phlegmons is performed by evacuating and drying up the humours, which putrefie by delay and collection in the part. For this purpoſe Scarifications and Inciſions, great, indifferent, ſmall, deep, and ſuperficiary, according to the condition of the Gangrene, are much commended, that ſo the burdened part may enjoy the benefit of perſpiration; and the contained humours of diſſlation, or evacuation, of their ſooty excrements. Let Inciſions be made when the affect is great, deep in, and near to mortification. But Scarifications may be uſed when the part firſt begins to putrefie, for the greatneſs of the remedy muſt anſwer in proportion to that of the diſeaſe. Wherefore if it penetrate to the bones, it will be fit to cut the skin and fleſh with many and deep inciſions, with an Inciſion-knife made for that purpoſe; yet take heed of cutting the larger Nerves and Veſſels, unleſs they be wholly putrefied, for if they be not yet putrefied, you ſhall make your Inciſions in the ſpaces between them; if the Gangrene be leſs, we muſt reſt ſatisfied with onely ſcarifying it. When the Scarifications and Inciſions are made, we muſt ſuffer much bloud to flow forth, that ſo the conjunct matter may be evacuated. Then muſt we apply and put upon it ſuch Medicins as may by heating, drying, reſolving, cleanſing and opening, amend and correct the putrefaction, and by piercing to the bottom may have power to overcome the virulency already impact in the part. For this purpoſe, Lotions made

The cure of a Gangrene made by inflammation.

of the Lie of the Aſhes of Fig-tree, or Oak, wherein Lupins have been throughly boiled, are good. Or you may with leſs trouble make a Medicin with Salt-water, wherein you may diſſolve Aloes and *Ægyptiacum*, adding in the concluſion a little *Aqua vitæ*, for *Aqua vitæ* and calcined Vitriol are ſingular Medicins for a Gangrene. Or ℞ *Acet. opimi* ℔ j. *mel. roſ.* ʒ iv. *ſyrup. acetoſi* ʒ iij. *ſalis com.* ʒ v. *bulliant ſimul, adde aqua vitæ*, ℔. ſ. Let the part be frequently waſhed with this Medicin, for it hath much force to repreſs Gangrenes. After your Lotion, lay *Ægyptiacum* for a Liniment, and put it into the Inciſions, for there is no Medicine more powerful againſt putrefaction, for by cauſing an *Eſchar*, it ſeparates the putrid fleſh from the ſound. But we muſt not in this kind of affect expect that the putrid fleſh may of it ſelf fall from the ſound; but rather cut off with your Inciſion-knife, or Sciſſers, whatſoever thereof you can, and then put to it *Ægyptiacum* as oft as need ſhall require. The knowledge hereof may be acquired from the colour, ſmell, and ſenſibleneſs of the fleſh it ſelf. The deſcription of the *Ægyptiacum*, whoſe wondrous effects I have often tried in theſe cauſes, is this. ℞ *Floris æris, aluminis roch. mellis com. an.* ʒ iij. *aceti acerrimi* ʒ v. *ſalis com.* ʒ j. *vitrioli Rom.* ʒ ß. *ſublimati pul.* ʒ ij. *bulliant omnia ſimul ad ignem, fiat unguent.* If the force of the putrefaction in the part be not ſo great, a weaker *Ægyptiacum* may ſerve. When you have put in the *Ægyptiacum*, then preſently lay the following Cataplaſm thereupon. For it hinders putrefaction, reſolves, cleanſes and dries up the virulent *ſanies*, and by the dry ſubtlety of the parts penetrates into the member, ſtrengthens it, and aſſwages the pain. ℞ *Farin. fabar. hordei orobi, lent. lupin. an.* ℔ ſ. *ſal. com. mellis roſat. an.* ʒ iv. *ſucci abſinth. marrub. an.* ʒ j. ß. *aloes, maſtiches, myrrhæ, & aquæ vit. an.* ʒ ij. *oxymelitis ſimpl. quantum ſufficit; fiat Cataplaſma molle ſecundum artem*; Somewhat higher than the part affected, apply this following aſtringent, or defenſative, to hinder the flowing down of the humours into the part, and the riſing up of the vapours from the putrid part into the whole body. ℞ *Olei roſati, & myrtill. an.* ʒ iv. *ſucci plantag. ſolani, ſempervivi an.* ʒ ij. *album. ovorum* v. *boli armeni, terræ ſigillatæ ſubtiliter pulveriſatorum, an.* ʒ j. *oxycrati quantum ſufficit, miſce ad uſum dictum.* But theſe Medicins muſt be often renewed. If the grief be ſo ſtubborn, that it will not yield to the deſcribed remedies, we muſt come to ſtronger, to wit, Cauteries, after whoſe application *Galen* bids to put upon it the juice of a Leek with Salt beaten and diſſolved therewith, for that this Medicine hath a piercing and drying faculty, and conſequently to hinder putrefaction. But if you prevail nothing with Cauteries, then muſt you come to the laſt remedy and refuge, that is, the amputation of the part; for according to *Hippocrates*, to extream diſeaſes exquiſitly extreme remedies are beſt to be applied. Yet firſt be certain of the mortification of the part; for it is no little or ſmall matter to cut off a member without a cauſe.

The deſcription of an *Ægyptiacum.*

Aſtringents that may be uſed in cure of a Gangrene.

Gal. 2. ad Glauconem.

Aphor. 6. ſect. 11

Therefore I have thought it fit to ſet down the ſigns whereby you may know a perfect and abſolute mortification.

CHAP. XVII.

The ſigns of a perfect Necroſis, *or Mortification.*

A note concerning the unſenſibleneſs of the part.

You ſhall certainly know, that a Gangrene is turned into a Sphacel, or mortification, and that the part is wholly and throughly dead, if it look of a black colour, and be colder than ſtone to your touch, the cauſe of which coldneſs is not occaſioned by the frigidity of the air; if there be a great ſoftneſs of the part, ſo that if you preſs it with your finger it riſes not again, but retains the print of the impreſſion; if the skin come from the fleſh lying under it; if ſo great and ſtrong a ſmell exhale (eſpecially in an ulcerated Sphacel) that the ſtanders by cannot indure or ſuffer it; if a ſanious moiſture, viſcid, green or blackiſh, flow from thence; if it be quite deſtitute of ſenſe and motion, whether it be pulled, beaten, cruſhed, pricked, burnt, or cut off. Here I muſt admoniſh the young Chirurgeon, that he be not deceived concerning the loſs or privation of the ſenſe of the part. For I know very many deceived as thus; the Patients pricked on that part, would ſay, they felt much pain there. But that feeling is oft deceitful, as that which proceeds rather from the ſtrong apprehenſion of great pain which formerly reigned in the part, than from any faculty of feeling as yet remaining. A moſt clear and manifeſt argument of this falſe and deceitful ſenſe appears after the amputation of the member; for a long while after they will complain of the part which is cut away.

A wondrous ſymptom.

Verily it is a thing wondrous ſtrange and prodigious, and which will ſcarce be credited, unleſs by ſuch as have ſeen with their eyes and heard with their ears the Patients, who have many months after the cutting away of the Leg, grievouſly complained that they yet felt exceeding great pain of that Leg ſo cut off. Wherefore have a ſpecial care leſt this hinder your intended amputation; a thing pitiful, yet abſolutely neceſſary for to preſerve the life of the Patient and all the reſt of his body, by cutting away of that member which hath all the ſigns of a Sphacel and perfect mortification; for otherwiſe the neglected fire will in a moment ſpread over all the body, and take away all hope of remedy; for thus *Hippocrates* wiſheth, That Sections, Uſtions, and Terebrations muſt be performed as ſoon as need requires.

Sect. 7. lib. 6. Epidem.

CHAP. XVIII.

Where Amputation muſt be made.

The controverſie decided.

It is not ſufficient to know that Amputation is neceſſary, but alſo you muſt learn in what place of the dead part it muſt be done, and herein the wiſdom and judgment of the Chirurgeon is moſt apparent. Art bids to take hold of the quick, and to cut off the member in the ſound fleſh; but the ſame Art wiſheth us, to preſerve whole that which is ſound as much as in us lies.

I will ſhew thee by a familiar example how thou mayeſt carry thy ſelf in theſe difficulties. Let us ſuppoſe, that the foot is mortified even to the ankle; here you muſt attentively mark in what place you muſt cut it off. For unleſs you take hold of the quick fleſh in the amputation, or if you leave any putrefaction, you profit nothing by amputation, for it will creep and ſpread over the reſt of the body. It befits Phyſick, ordained for the preſervation of Mankind, to defend from the Iron or Inſtrument, and all manner of injury, that which injoyeth life and health. Wherefore you ſhall cut off as little of that which is ſound as you poſſibly can; yet ſo that you rather cut away that which is quick, than leave behind any thing that is periſhed, according to the advice of *Celſus*. Yet oft- *Lib. 7. cap. 33.* times the commodity of the action of the reſt of the part, and as it were a certain ornament thereof, changes this counſel. For if you take theſe two things into your conſideration they will induce you, in this propounded caſe and example, to cut off the Leg ſome five fingers bredth under the Knee. For ſo the Patient may more fitly uſe the reſt of his leg and with leſs trouble, that is, he may the better go on a wooden leg; for otherwiſe, if according to the common Rules of Art, you cut it off cloſe to that which is periſhed, the Patient will be forced with trouble to uſe three legs in ſtead of two.

For I ſo knew Captain *Francis Clark*, when as his foot was ſtricken off with an iron bullet, ſhot forth of a man of War, and afterwards recovered and healed up, he was much troubled and wearied with the heavy and unprofitable burden of the reſt of his leg, wherefore, though whole and ſound, he cauſed the reſt thereof to be cut off, ſome five fingers bredth below his Knee; and verily he uſed it with much more eaſe and facility than before in performance of any motion. We muſt do otherwiſe if any ſuch thing happen in the Arm; that is, you muſt cut off as little of the ſound part as you can. For the actions of the legs much differ from thoſe of the arms, and chiefly in this that the body reſts not, neither is carried upon the arms, as it is upon the feet and legs. An obſervable Hiſtory.

CHAP. XIX.

How the Section or Amputation muſt be performed.

THE firſt care muſt be of the Patients ſtrength: wherefore let him be nouriſhed with meats of good nutriment, eaſie digeſtion, and ſuch as generate many ſpirits; as with the yolks of Eggs, and Bread toſted and dipped in Sack or Muskadine. Then let him be placed as is fit, and drawing the Muſcles upwards towards the ſound parts, let them be tied with a ſtrait ligature a little above that place of the member which is to be cut off, with a ſtrong and broad fillet, like that which women uſually bind up their hair withall. This ligature hath a threefold uſe; the firſt is, that it hold the muſcles drawn up together with the skin, ſo that retiring back preſently after the performance of the work, they may cover the ends of the cut bones, and ſerve them in ſtead of bolſters or pillows when they are healed up, and ſo ſuffer with leſs pain the compreſſion in ſuſtaining the reſt of the body: beſides alſo by this means the Wounds are the ſooner healed and cicatrized; for, by how much more skin or fleſh is left upon the ends of the bones, by ſo much they are the ſooner healed and cicatrized. The ſecond is, for that it prohibits the flux of bloud by preſſing and ſhutting up the Veins and Arteries. The third is, for that it dulls the ſenſe of the part by ſtupefying it, the animal ſpirits by the ſtrait compreſſing being hindered from paſſing in by the Nerves. Wherefore when you have made your ligature, cut the fleſh even to the bone with a ſharp and well-cutting inciſion-knife, or with a crooked knife, ſuch as is here expreſſed. The Ligature of the part.

A crooked Knife fit for diſmembring, or a diſmembring Knife.

The Figure of ſuch a Saw.



Now you muſt note, that there uſually lies between the bones, a portion of certain muſcles which you cannot eaſily cut with a large inciſion or diſmembring knife; wherefore you muſt carefully divide it and ſeparate it wholly from the bone, with an inſtrument made neatly like a crooked Inciſion-knife. I thought good to advertiſe thee hereof; for if thou ſhouldeſt leave any thing beſides the bone to be divided by the Saw, you would put the Patient to exceſſive pain in the performance thereof; for ſoft things, as fleſh, tendons, and membranes, cannot be eaſily cut with a Saw. Therefore when you ſhall come to the bared bone, all the other parts being wholly cut aſunder and divided, you ſhall nimbly divide it with a little Saw about ſome foot and three inches long, and that as near to the ſound fleſh as you can. And then you muſt ſmooth the front of the bone which the Saw hath made rough. A Caution to be obſerved.

CHAP. XX.

How to ſtanch the bleeding when the member is taken off.

WHen you have cut off and taken away the member, let it bleed a little, according to the ſtrength of the Patient, that ſo the reſt of the part may afterwards be leſs obnoxious to inflammation and other ſymptoms; Then let the Veins and Arteries be bound up as ſpeedily and ſtraitly as you can; that ſo the courſe of the flowing bloud may be ſtopped and wholly ſtaid. Which may be done by taking hold of the Veſſels with your Crows-beak, whereof the Figure follows.

The Crows-beak fit for to draw the Veſſels forth of the fleſh, wherein they lie hid, that ſo they may be tied or bound faſt.



How to draw forth the Veſſels and bind them.

The ends of the Veſſels lying hid in the fleſh, muſt be taken hold of and drawn with this Inſtrument forth of the muſcles, whereinto they preſently after the amputation withdraw themſelves, as all parts are ſtill uſed to withdraw themſelves towards their originals. In performance of this work, you need take no great care, if you together with the Veſſels comprehend ſome portion of the neighbouring parts, as of the fleſh, for hereof will enſue no harm; but the Veſſels will ſo be conſolidated with more eaſe, than if they being bloudleſs parts ſhould grow together by themſelves. To conclude, when you have ſo drawn them forth, bind them with a ſtrong double thred.

CHAP. XXI.

How, after the bloud is ſtanched, you muſt dreſs the wounded member.

How the lips of the diſmembred part are to be joined together.

WHen you have the tied Veſſels, looſe your Ligature which you made above the place of amputation, then draw together the lips of the Wound with four ſtitches made acroſs, having taken good hold of the fleſh; for thus you ſhall draw over the bones that part of the skin and cut muſcles drawn upwards before the amputation, and cover them as cloſe as you can, that ſo the air may the leſs come at them, and that ſo the Wound may be the more ſpeedily agglutinated. But when we ſay, draw together the lips of the Wound with four ſtitches, you muſt not ſo underſtand it, as that you muſt endeavour to draw them ſo cloſe as to touch each other, for that is impoſſible; for the ſtitches would ſooner break out, and ſo the part would lie bare. Wherefore it will be ſufficient to draw them indifferent cloſe together, that ſo you may ſuffer the skin and fleſh thereunder to enjoy its former liberty which it poſſeſt before the drawing up; and ſo in fine, by Natures aſſiſtance, the Wound may be the more eaſily agglutinated.

CHAP. XXII.

How you muſt ſtop the bleeding, if any of the bound-up Veſſels chance to get looſe.

The Hæmorrhagy of ſmall Veſſels is not to be regarded.

THe buſineſs hitherto being performed as we ſaid, if peradventure it happen that any bandage of any of the Veſſels be unlooſed, then muſt you again bind the member with that kind of Ligature which you did before the amputation thereof. Or elſe which is better, more eaſie and leſs painful, let your ſervant take hold of the member with both his hands, preſſing his fingers ſtrait, ſtop the paſſage of the looſed Veſſel, for ſo he may ſtanch the bleeding. Then let the Workmaſter take a needle ſome four fingers long, ſquare, and having ſharp edges, drawing after it a three or four doubled ſtrong thred. With this let him bind the Veſſel after the following manner. Let him thruſt his Needle on the outſide into the fleſh, ſome half fingers bredth from the looſed Veſſel until he come to the end thereof, then let him put it about it, and bring it back again, but ſo that there be no more than the ſpace of a fingers bredth between the going in and coming forth of the Needle. In this ſpace let him put a linnen rag three or four times doubled, and thereupon bind ſomewhat ſtraight the two ends of the thred together. For ſo he ſhall hinder the knot from hurting the fleſh which lies under it in the bindings, and alſo add ſtrength thereto. For ſo the bound up orifice of the Veſſel will in ſhort ſpace be agglutinated to the adjoyning fleſh, and that ſo firmly, that there hath never been ſeen any one drop of bloud to have flowed from a Veſſel ſo bound up. But if the bloud which flows forth proceed from any ſmall Veſſel, you muſt not uſe this ſuture and ligature, nor make any ſuch great matter thereof, for it will quickly be ſtanched by the onely application of Aſtringents, preſently to be mentioned.

CHAP. XXIII.

How to perform the residue of the Cure of the amputated Member.

NOw must we shew what Medicins are fitting to be applied after the amputation of a member; which are Emplasticks, as those which exceedingly conduce to green Wounds. As, An emplastick Medicin.
℞ *Bol. arm.* ℥ iv. *farin. vol.* ℥ iij. *picis, resinæ, an.* ℥ ij. *pulverisentur omnia subtilissime & simul mixtis fiat pulvis*; herewith let the Wound be strewed, and lay thereupon dry Lint; but let the following repercussive or defensative be applied to the member. A repercussive
℞ *Albumen ovorum* vj. *boli arm. sang. drac. gypsi, terræ sigill. aloes, masticches, gallar. combust. an.* ℥ ij. *in pollinem redigantur omnia, & bene agitentur, addendo olei rosarum & myrtill. an.* ℥ j. *fiat defensativum ad formam mellis.* This ointment must be applied upon stoops dipped in Oxycrate, and that so that it may not onely cover the cut member, but also be spred further and cover the neighbouring parts; as when the Leg is cut off, it must be laid upon the joint, and spred higher than the Knee, some four fingers upon the Thigh, for it hath not onely a repercussive faculty, but it also strengthens the part, hinders the defluxion by tempering the bloud, asswaging pain, and hindering inflammation. It will also be good to moisten your double cloths and bandages in Oxycrate; then must you place the member in an indifferent posture upon a pillow stuffed with Oaten husks or chaff, Stags hair, or Wheat bran. It must not be stirred after the first dressing (unless great necessity urge) for four days in Winter, but somewhat sooner in Summer. For the ligatures wherewith the Vessels are bound, they must not be loosed, or otherwise taken away, before the mouths of the Vessels are covered with their glue or flesh, lest by too much haste you cause a new flux of bloud. This agglutination will be performed by applying refrigerating, astringent, and emplastick Medicins, such as this following powder. How to place the member and how often to dress it.
An emplastick Powder.
℞ *Boli arm. farin. hord. picis, res. gypsi, an.* ℥ iv. *Aloes, nucum cup. cort. granat. an.* ℥ j. *incorporentur omnia simul, fiat pulvis subtilis:* herewith let the whole Ulcer be strewed over for three or four days space; which being ended, let onely the seats of the Vessels be powdred therewith, and that for eight or ten days, so that we need no further doubt of the agglutination of the Vessels. In the mean space let the digestive be applied to the rest of the Ulcer until it be come to suppuration; for then you shall give over your digestive, and betake to your detersive and munditicative Medicins: As Detersives.
℞ *Terebinth. ven. lotæ in aqua vitæ* ℥ vj. *mellis ros. colati* ℥ iv. *succi plantag. Apii, centaur. minoris, an.* ℥ ij. *bulliant omnia simul usque ad consumptionem succorum, auferantur ab igne, addendo farinæ fab. & hord. an.* ℥ j. *theriac. Gal.* ℥ ß. *aloes, myrrhæ, aristoloch. an.* ℥ iij. *croci* ʒ j. *fiat mundificativum.* But seeing the case stands so that the Patients imagine they have their members yet entire, and yet do complain thereof (which I imagin to come to pass, for that the cut nerves retire themselves towards their original, and thereby cause a pain like to Convulsions; for as *Galen* writes in his Book, *De Motu Musculorum*, that contraction is the true and proper action of a Nerve and Muscle: and again, extension is not so much an action as a motion: now we must endeavour to give remedy to this symptom. Which may be done by anointing the spine of the back and all the affected part with the following Liniment, which is very powerful against Convulsions, the Palsie, Numness, and all cold effects of the nervous bodies. Why after dismembring the Patients complain of pain as if the part was yet remaining on.
An ointment for the spine of the back against all affects of the Nerves.
℞ *Salviæ, chamæpithyos, majoranæ, rorismar. menth. rutæ, lavendulæ, an. m.* j. *flor. chamæmel. melilot. summit. aneth. & hyperici, an. p.* ij. *baccarum lauri & juniperi, an.* ʒ ij. *radicis pyrethri* ʒ ij. *mastic. assæ odorat. an.* ʒ i. *terebinth. venet.* ℔ j. *olei lumbr. æneth. catell. an.* ℥ vj. *olei terebinth.* ℥ iij. *axung. hum.* ℥ ii. *croci* ʒ j. *vini albi odoriferi* ℔ j. *ceræ quantum sufficit, contundenda contundantur, pulverisanda pulverisentur, deinde macerentur omnia in vino per noctem, postea coquantur cum oleis & axungia prædictis in vase duplici, fiat linimentum secundum artem, in fine adde aquæ vitæ* ℥ iv. Besides, in dressing these wounds the Chirurgeon must use diligence to procure the falling away of the ends or scales of the bones which the Saw and the appulse of the Air never before coming hereto, have tainted; which may be done by applying to their ends actual Cauteries, that is, hot irons; in using of which you must have a special care that you touch not the sensible parts with fire; neither must the bones themselves be forcibly plucked off, but gently moved by little and little, so that you shall think that you and the Patient have exceedingly well performed your parts if they fall away at the thirtieth day after the Amputation. All these things being performed, you shall hinder the growth of proud flesh with the cathæreticks, such as are burnt Vitriol, the Powder of Mercury, and other things, amongst which is Alum burnt and powdered, which is excellent in these kinds of Wounds, whether by it self or mixed with others. You shall use these, and such like, even unto the perfect agglutination and cicatrization of the Wound, and you may of your self devise other things, such as these; as occasion shall offer it self. How to procure the falling away of the ends of the bones.
Cathæreticks.

CHAP. XXIV.

What just occasion moved the Author to devise this new form of remedy, to stanch the bloud after the amputation of a member, and to forsake the common way used almost by all Chirurgeons; which is by application of actual Cauteries.

VErily I confess, I formerly have used to stanch the bleeding of members, after amputation, after another manner than that I have a little before mentioned: Whereof I am ashamed, and aggrieved; But what should I do? I had observed my Masters, whose Method I intended to follow, always to do the like; who thought themselves singularly well appointed to stanch a flux of bloud, when they were furnished with various store of hot irons and caustick Medicins, which they would use to the dismembred part, now one, then another, as they themselves thought meet. Which thing cannot be spoken, or but thought upon without great horrour, much less acted. For this kind of remedy could not but bring great and tormenting pain to the Patient, Hot Irons not to be used.

ſeeing ſuch freſh wounds made in the quick and ſound fleſh, are endued with exquiſite ſenſe: Neither can any cauſtick be applied to nervous bodies, but that this horrid impreſſion of the fire will be preſently communicated to the inward parts; whence horrid ſymptoms enſue, and oft-times death it ſelf. And verily of ſuch as were burnt, the third part ſcarce ever recovered, and that with much ado, for that combuſt Wounds difficultly come to cicatrization; for by this burning are cauſed cruel pains, whence a Fever, Convulſion, and oft-times other accidents worſe than theſe. Add hereunto that when the eſchar fell away, oft-times a new hæmorrhage enſued, for ſtanching whereof they were forced to uſe other cauſtick and burning Inſtruments. Neither did theſe good men know any other courſe; ſo by this repetition, there was great loſs and waſte made of the fleſhy and nervous ſubſtance of the part: Through which occaſion the bones were laid bare, whence many were out of hope of cicatrization, being forced for the remainder of their wretched life, to carry about an ulcer upon that part which was diſmembred; which alſo took away the opportunity of fitting or putting to of an artificial leg or arm, in ſtead of that which was taken off. Wherefore I muſt earneſtly intreat all Chirurgeons, that leaving this old and too too cruel way of healing, they would embrace this new, which I think was taught me by the ſpecial favour of the ſacred Deity; for I learnt it not of my Maſters, nor of any other; neither have I at any time found it uſed by any: Onely I have read in *Galen* that there was no ſpeedier remedy for ſtanching of bloud than to bind the Veſſels (through which it flowed) towards their roots; to wit, the Liver and Heart. This precept of *Galen*, of binding and ſowing the Veins and Arteries in the new wounds, when as I thought it might be drawn to theſe which are made by the amputation of members, I attempted it in many; yet ſo, that at firſt in my budding practice thereof, I always had my Cauteries and hot Irons in a readineſs, that if any thing happened otherwiſe than I expected in this my new work, I might fetch ſuccour from the ancient practice; until at length confirmed by the happy experience of almoſt an infinite number of particulars, I bid eternally adieu to all hot Irons and Cauteries which were commonly uſed in this work. And I think it fit that Chirurgeons do the like. For Antiquity and Cuſtom in ſuch things as are performed by Art, ought not to have any ſway, authority or place contrary to reaſon, as they oft-times have in civil affairs; wherefore let no man ſay unto us, that the Ancients have always done thus.

Lib. 5. Meth.

CHAP. XXV.

The practice of the former precepts is declared, together with a memorable Hiſtory of a certain Souldier whoſe Arm was taken off at the Elbow.

A Hiſtory.

I Think it fit to confirm by an example, the preſcribed Method of curing a Gangrene and Mortification. Whileſt I was a Chirurgeon to the Marſhal of *Montejan* at *Turin*, a certain common Souldier received a Wound on his wriſt with a Musket-bullet, by which the bones and tendons being much broken, and the nervous bodies cruelly torn, there followed a Gangrene, and at length a Mortification even to the Elbow; beſides alſo an inflammation ſeized upon the middle part of his Cheſt, and there was as it were a certain diſpoſition to a Gangrene; whereby it followed, that he was painfully and dangerouſly troubled with belchings, hicketings, watchings, unquietneſs, and frequent ſwoundings, which occaſioned many Chirurgeons to leave him as deſperate. But it ſo fell out, that I (overcome by his Friends intreaty) undertook the cure of this wretched perſon, deſtitute of all humane help. Wherefore knowing the mortification by its ſigns, I cut off the Arm by the Elbow as ſpeedily as I could, making firſt the ligature, whereof I made mention; I ſay I took it off not with a Saw, but onely with an Inciſion-Knife, cutting in ſunder the ligaments which held the bones together, becauſe the ſphacel was not paſſed the joint of the Elbow. Neither ought this Section to be counted ſtrange, which is made in a joint; for *Hippocrates* much commends it, and ſaith that it is eaſily healed, and that there is nothing to be feared therein beſides ſwounding, by reaſon of the pain cauſed by cutting the common tendons and ligaments. But ſuch inciſion being made, the former ligature could not hinder, but much bloud muſt flow from thence, by reaſon of the large Veſſels that run that way; Wherefore I let the bloud to flow plentifully, ſo to disburden the part, and ſo afterwards to free it from the danger and fear of inflammation and a Gangrene; then preſently I ſtanched the bloud with an hot Iron, for as yet I knew no other courſe. Then (gently looſing the ligature) I ſcarified that part of the brawn of the Arm which was gangrenated, with many and deep inciſions, ſhunning and not touching the inner part, by the reaſon of the multitude of the large Veſſels and Nerves which run that way; then I preſently applied a Cautery to ſome of the Inciſions, both to ſtanch the bleeding, and draw forth the virulent *ſanies* which remained in the part. And then I aſſailed and overcame the ſpreading putrefaction, by putting and applying the formerly preſcribed Medicins; I uſed all ſorts of reſtrictive Medicins to ſtay the inflammation of the Cheſt; I alſo applied Epithemaes to the region of the heart, and gave him cordial potions and boles, neither did I deſiſt from uſing them until ſuch time as his belching, hicketing, and ſwoundings had left him. Whileſt I more attentively intended theſe things, another miſchief aſſails my Patient; to wit, Convulſions, and that not through any fault of him or me, but by the naughtineſs of the place wherein he lay, which was in a Barn every where full of chinks, and open on every ſide; and then alſo it was in the midſt of Winter, raging with Froſt and Snow and all ſorts of cold; neither had he any fire or other thing neceſſary for preſervation of life, to leſſen theſe injuries of the air and place: Now his joints were contracted, his teeth ſet, and his mouth and face were drawn awry, when as I pitying his caſe made him to be carried into the neighbouring Stable, which ſmoaked with much Horſe-dung; and bringing in fire in two Chafingdiſhes, I preſently anointed his neck and all the ſpine of his back, ſhunning the parts of the Cheſt, with liniments formerly deſcribed for Convulſions; then ſtraitway I wrapped him in a warm linnen cloth, and buried him even to the neck in hot dung, putting

Diſmembring at a joint.

Sect. 4. Lib. de Art.

Burying in hot horſe-dung helps Convulſions.

ting a little freſh ſtraw about him; when he had ſtaid there ſome three days, having at length a gentle ſcouring or flux of his belly, and plentiful ſweat, he begun by little and little to open his mouth and teeth, which before were ſet and cloſe ſhut. Having got by this means ſome opportunity better to do my buſineſs, I opened his mouth as much as I pleaſed, by putting this following Inſtrument between his teeth.

A Dilator made for to open the Mouth and Teeth by the means of a Screw in the end thereof.



Now drawing out the Inſtrument I kept his mouth open by putting in a Willow ſtick on each ſide thereof, that ſo I might the more eaſily feed him with meats ſoon made, as with Cows milk and rear Eggs, until he had recovered power to eat, the convulſion having left him. He by this means freed from the Convulſion, I then again begun the cure of his arm, and with an actual Cautery ſeared the end of the bone, ſo to dry up the perpetual afflux of corrupt matter. It is not altogether unworthy of your knowledge, that he ſaid, how that he was wondrouſly delighted by the application of ſuch actual cauteries, a certain tickling running the whole length of the arm by reaſon of the gentle diffuſion of the heat by the applying the cauſtick; which ſame thing I have obſerved in many others; eſpecially in ſuch as lay upon the like occaſion in the Hoſpital of *Paris*. After this cauterizing there fell away many and large ſcales of the bone, the freer appulſe of the air than was fit making much thereto; beſides when there was place for fomentation, with the decoction of red Roſe leaves, Wormwood, Sage, Bay-leaves, Flowers of Camomil, Melilote, Dill, I ſo comforted the part, that I alſo (at the ſame time by the ſame means) drew and took away the virulent *ſanies*, which firmly adhered to the fleſh and bones. Laſtly, it came to paſs, that by Gods, aſſiſtance theſe means I uſed, and my careful diligence, he at length recovered. Wherefore I would admoniſh the young Chirurgeon, that he never account any ſo deſperate, as to give him for loſt, content to have let him go with prognoſticks; for as an ancient Doctor writes, that as in Nature, ſo in Diſeaſes there are alſo Monſters.

A fomentation for a Convulſion.

Monſters or miracles in Diſeaſes.

The End of the Twelfth Book.

BOOK XIII.

Of Ulcers, Fiſtulaes, and Hæmorrhoides.

CHAP. I.

Of the Nature, Cauſes, and Differences of Ulcers.

HAving already handled and treated of the Nature, Differences, Cauſes, Signs and Cure of freſh and bloudy Wounds, Reaſon and Order ſeem to require that we now ſpeak of Ulcers; taking our beginning from the ambiguity of the name. For according to *Hippocrates*, the name of Ulcer moſt generally taken may ſignifie all or any ſolution of Continuity; in which ſenſe it is read that all Pain is an Ulcer. Generally, for a Wound and Ulcer properly ſo called; as appears by his Book *De Ulceribus*. Properly, as when he ſaith it is a ſign of death when an Ulcer is dried up through an *Atrophia*, or defect of nouriſhment. We have here determined to ſpeak of an Ulcer in this laſt and proper ſignification. And according thereto we define an Ulcer to be the ſolution of Continuity in a ſoft part, and that not bloudy, but ſordid and unpure, flowing with quitture, *ſanies* or any ſuch like corruption, aſſociated with one or more affects againſt Nature, which hinder the healing and agglutination thereof; or that we may give it you in fewer words according to *Galens* opinion; An Ulcer is a ſolution of Continuity, cauſed by Eroſion. The cauſes of Ulcers are either internal or external. The internal are through the default of humours peccant in quality rather than in quantity, or elſe in both, and ſo making eroſion in the skin and ſofter parts by their acrimony and malignity; now theſe things happen either by naughty and irregular diet, or by the ill diſpoſition of the entrails, ſending forth and emptying into the habit of the body this their ill diſpoſure. The external cauſes are, the exceſs of cold ſeizing

The diverſe acceptions of an Ulcer. *Sent. 34. ſect. 3. lib. de fract.*

Sect. 1. prog.

What an ulcer properly is.

Lib. de conſtit. Artis cap. 6.

The internal cauſes.

The external cauſes.

ſeizing upon any part, eſpecially more remote from the fountain of heat, whence follows pain, whereunto ſucceeds an attraction of humours and ſpirits into the part, and the corruption of theſe ſo drawn thither by reaſon of the debility or extinction of the native heat in that part, whence laſtly ulceration proceeds. In this number of external cauſes may be ranged, a ſtroke, contuſion, the application of ſharp and acrid Medicins, as Cauſticks, Burns, as alſo impure contagion, as appears by the virulent Ulcers acquired by the filthy copulation or too familiar converſation of ſuch as have the *French* Diſeaſe. How many and what the differences of Ulcers are, you may ſee here deſcribed in this following Scheme.

A Table of the Differences of Ulcers.

An Ulcer is an impure ſolution of continuity in a ſoft part, flowing with filth and matter or other corruption, whereof there are two chief differences; for one

- *Is ſimple and ſolitary without complication of any other affect againſt Nature, and this varies in differences, either*
  - *Proper, which are uſually drawn from three things, to wit,*
    - *Figure, whence one Ulcer is called*
      - *Round or Circular.*
      - *Sinuous, and variouſly ſpread.*
      - *Right or Oblique.*
      - *Cornered as Triangular.*
    - *Quantity, and that either according to their*
      - *Length; when an Ulcer is long, ſhort, indifferent.*
      - *Breadth; whence an Ulcer is broad, narrow, indifferent.*
      - *Profundity; whence an Ulcer is deep, ſuperficiary, indifferent.*
    - *Equality or Inequality; which conſiſts.*
      - *In thoſe differences of dimenſions whereof we laſt treated, I ſay in length, bredth, and profundity, wherein they are either alike or of the ſame manner, or elſe unlike and ſo of a different manner.*
  - *Or Common and accidental, and theſe drawn either*
    - *From their time; whence an Ulcer is termed new, old, of ſhort or long, cure and curation.*
    - *From their appearance; whence one is called an apparent Ulcer, another a hidden and occult Ulcer.*
    - *From their manner of generation; as if it be made by a heavy, bruiſing, cutting, pricking or corroding thing; whence a cut, torn and mixt Ulcer.*
    - *From their Site; whence an Ulcer before, behind, above, below in the head, tail, or belly of a Muſcle.*
    - *From that part it ſeizes upon; whence an Ulcer in the fleſh and skin, or feeding upon the griſtles or bones, ſuch as theſe of the Noſe, the Palat of the mouth, and Ears.*
    - *From other common accidents; whence a Telephian Ulcer, that is, ſuch an Ulcer as* Telephus *had. A Chironian, which needs the hand and art of* Chiron. *A Cancrous which reſembles a Cancer.*
- *Is Compound, and many and various ways complicated, as*
  - *With the cauſe whence an Ulcer*
    - *Is Cacochymick, Catarrhoick or venenate, that is, which a* Cacochymia *or Repletion of ill humours, a Catarrh, or poiſon cheriſhes or feeds.*
  - *With the Diſeaſe, as from*
    - *Diſtempers, whether ſimple or compound, whence an Ulcer is*
      - *Hot.*
      - *Cold.*
      - *Dry.*
      - *Moiſt.*
      - *Mixt.*
    - *Swelling or Tumour, whence a*
      - *Phlegmonous*
      - *Eryſipelous*
      - *Oedematous*
      - *Scirrhous*
      - *Cancrous*

      Ulcer.
    - *Solution of Continuity, or any other diſcommodity, whence a rough, callous, fiſtulous, cavernous, ſinuous Ulcer, with luxation, fracture, &c.*
  - *With the Symptom, whence a corroding, eating, painful, ſordid and virulent Ulcer.*
  - *With the cauſe and diſeaſe,*
    With the cauſe and Symptom,
    With the diſeaſe and Symptom,
    With the cauſe, diſeaſe and Symptom.

    Examples whereof may be taken from that we have formerly delivered.

CHAP.

CHAP. II.

Of the Signs of Ulcers.

THere are various signs of Ulcers according to their differences. For it is the sign of a putrid Ulcer, if it exhale a noisom, grievous, stinking and carion-like vapour, together with filthy matter. An eating Ulcer is known by the eating in, hollowness and wearing away of the part wherein it resides, together with the adjoining parts. A sordid Ulcer may be known by the grosness and viscidity of the excrements it sends forth, and by the loose and spongy softness, or the crusted inequality of the flesh which grows over it. A cavernous Ulcer, by the straitness of the orifice, and largeness and deepness of the windings within. A fistulous Ulcer, if to the last mentioned signs there accrew a callous hardness of the lips or sides of the Ulcer. A cancrous Ulcer is horrible to behold, with the lips turned black, hard and swollen; flowing with virulent and stinking corruption, and sometimes also with bloudy matter, together with the swelling and lifting up of the adjacent Veins. An untemperate, or as they term it, a distempered Ulcer, is such as is nourished by some great distemper, whether hot or cold, moist or dry, or compounded of these. An ill *natured or malign Ulcer is known by the difficulty of curing and rebellious contumacy to remedies appointed according to Art and Reason. We know a catarrhous Ulcer, if the matter which feeds it flow to it from some *varices* thereunto adjoining; or dilated, swollen and broken Veins, or from some entrail, or from the whole body being ill affected. An Apostematous Ulcer is perceived by the presence of any tumor against Nature, whose kind may be found out by sight and handling. *Telephian* Ulcers are such as affected *Telephus*; and *Chironian* (in whose cure *Chiron* excelled) are Ulcers which may be known by their magnitude, not much putrid, and consequently not sending forth any ill smell, not eating, not tormenting with pain, but having their lips swollen and hard, and therefore ill to be healed. For although they may be sometimes cicatrized, yet it being but slender may easily be broken, and the Ulcer renewed. They are almost like an ulcerated Cancer, but that they are accompanied with swelling in the adjacent parts; they are also worse than these which are termed *Cacoethe*, that is, ill-natured, or malign; whence it is that *Fernelius* thought they had a hidden cause of malignity, besides the common default of the humour, and that such as can scarce be driven away; such commonly are felt after the Plague. Wherefore *Galen* thinks such to be malign as will not suppurate or yield any quitture.

The signs of a putrid Ulcer

Gal. cap. 5. lib. 4. Meth.

* *ulcus Cacoethes.*

Com. ad aphor. 22. sect. 5.

CHAP. III.

Of the Prognosticks of Ulcers.

THe bone must necessarily scale, and hollow scars be left by malign Ulcers of a years continuance or longer, and rebellious to Medicins fitly applied. The bone must scale by reason of the continual efflux, and wearing by the acrimony of the humour, which looses the composure and glue by which the parts thereof are joined together. But the scars must become hollow, for that the bone (whence all the flesh takes its first original) or some portion thereof, being taken from under the flesh, as the foundation thereof, so much of the bulk of the flesh must necessarily sink down, as the magnitude of the portion of the wasted bone comes unto.

Aph. 45. sect. 6.

You may know that death is at hand, when the Ulcers that arise in or before diseases, are suddenly either livid or dried, or pale and withered. For such drineſs sheweth the defect of Nature, which is not able to send the familiar and accustomed nutriment to the part ulcerated. But the livid or pale colour is not onely an argument of the over-abundance of choler and melancholy, but also of the extinction of the native heat. In Ulcers where tumors appear, the Patients suffer no convulsions, neither are frantick; for the tumor being in the habit of the body possessed with an Ulcer, argues that the nervous parts and their original are free from the noxious humours. But these tumors suddenly vanishing and without manifest cause, as without application of a discussing Medicin or bleeding, those who have them on their backs have convulsions and distensions, for that the spine of the back is almost wholly nervous; but such as have them on their fore-parts, become either frantick, or have a sharp pain of their side, or pleurisie, or else a dysentery if the tumors be reddish: for, the fore-part of the body is replenished and over-spread with many and large Vessels, into whose passages the morbifick matter being translated, is presently carried to those parts which are the seats of such diseases. Soft and loose tumors in Ulcers are good, for they shew a mildness and gentleness of the humours, but crude and hard swellings are naught, for all digestion in some measure resembles elixation. Ulcers which are smooth and shining are ill, for they shew that there resides an humour malign by its acrimony, which frets asunder the roots of the hairs, and depraves the natural construction of the pores of the skin; whence it is, that such as are troubled with Quartan Agues, the Leprosie, or *Lues Venerea*, have their hair fall off. A livid flesh is ill in Ulcers which cause a rottenness or corruption of the bones lying under the flesh; for it is an argument of the dying heat and corruption of the bone, whence the flesh hath its original and integrity.

Hipp. progn. lib. 1. cap. 8. Aph. 65. sect. 5.

Aph. 97. sect. 5.

Aph. 4. sect. 6.

Those Ulcers which happen by occasion of any Disease, as a Dropsie, are hard to be cured; as also those whereinto a *varix* or swollen Vessel continually casts in matter, which a present distemper foments; which have swollen, hard and callous lips; and such as are circular or round. An *Hypersarcosis*, or fleshy excrescence usually happens to Ulcers not diligently mundified; and if they possess the Arms or Legs, they cause a Phlegmon or some other tumor in the groins, chiefly if the body be full of ill humours, as *Avicen* hath noted. For these parts by reason of their rarity and weakness are fit and subject to defluxions. *Albucrasis* writes that for nine causes Ulcers are difficultly replenished with flesh and cicatrized. The first, for want of bloud, in a bloudless body; the second, by reason

Hip. lib. de ulc. Gal. cap. 2. & 5. lib. Meth. 4.

For what causes Ulcers are hard to heal.

of

of ill humours and the impurity of the bloud; the third, by the unfit application of unconvenient Medicins; the fourth, by reaſon of the ſordidneſs of the Ulcer; the fifth, by the putrefaction of the ſoft and carion-like fleſh encompaſſing the Ulcer; the ſixth, when they take their original from a common cauſe which every where rages with fury, ſuch as are thoſe which are left by the peſtilence; the ſeventh, by reaſon of the callous hardneſs of the lips of the Ulcer; the eighth, when the Heavens and Air are of ſuch condition as miniſters fuel to the continuance of the Ulcer, as at *Saragoſa* in *Aragon*; the ninth, when the bones which lie under it are waſted by rottenneſs. An Ulcer that caſts forth white, ſmooth, equal quitture, and little or no ſtinking, is eaſily healed; for it argues the victory of the native heat, and the integrity of the ſolid parts. We term that ſmooth quitture which is abſolutely concocted, neither yields any aſperity to the touch, whereby we might ſuſpect that as yet any portion of the humour remains crude; we call that equal, wherein you can note no diverſity of parts; and white, not that which is perfectly ſo, but that which is of an aſh colour, as *Galen* obſerves. But it is ill, if when the cure is indifferently forward, a flux of bloud ſuddenly break forth in thoſe Ulcers which beat ſtrongly by reaſon of the great inflammation adjoined therewith. For, as *Hippocrates* obſerves, an effuſion of bloud happening upon a ſtrong pulſation in Ulcers is evil; for the bloud breaking out of an Artery cannot be ſtaid but by force, and alſo this bloud is ſo furious by reaſon of the heat and inflammation the nouriſhers of this Ulcer, that it breaks its receptacles, and hence enſues the extinction of the native heat, whence the defect of ſuppuration and a Gangrene enſues. Now for that there flows two ſorts of excrements from malign Ulcers, the more thin is termed *Ichor* or *Sanies*, but the more groſs is named *Sordes*, that is virulent and flows from pricked Nerves, and the *Perioſtea* when they are evil affected; but the other uſually flows from the Ulcers of the joints, and it is the worſer, if it be black, reddiſh, aſh-coloured, if muddy or unequal like Wine Lees, if it ſtink. *Sanies* is like the Water wherein fleſh hath been waſhed; it argues the preternatural heat of the part; but when it is pale coloured it is ſaid to ſhew the extinction of the heat.

What *Pus* or Matter is ſmooth, equal, and white. *Ad ſentent.* 32. *ſect.* 2. *de fract. Aph.* 21. *ſect.* 7.

Two ſorts of excrements flow from a malign Ulcer.

CHAP. IV.

Of the general Cure of Ulcers.

The curing of a ſimple Ulcer conſiſts in exſiccation. *Gal.* 7. *Meth. cap.* 12.

AN Ulcer is either ſimple or compound. A ſimple Ulcer, as an Ulcer, hath one and that a ſimple indication, that is, exſiccation; and that more than in a Wound, by how much an Ulcer is moiſter than a Wound. There are many indications propoſed for the cure of a compound Ulcer, in reſpect of which *Galen* would have us to keep this order, that we have the firſt regard of the moſt urgent, then of the cauſe, then of that, which unleſs it be taken away, the Ulcer cannot be healed. By giving you an example you may eaſily underſtand the meaning hereof. Imagine on the inſide of the leg, a little above the ancle, an Ulcer very painful, hollow, putrid, aſſociated with the rottenneſs of the bone, circular, having hard and ſwollen lips, and engirt with the inflammation and *varices* of the neighbouring parts. If you take this to cure, before you do any thing about the Ulcer, unleſs you be called upon by that which urges, as by vehemency of pain, you muſt firſt uſe general means by calling and adviſing with a Phyſician. For in *Galens* opinion, if the whole body require a preparation, then muſt that be done in the firſt place; for in ſome Ulcers purgation onely will be ſufficient, in ſome bloud-letting, others are better by uſing both means, which is as the cauſe of the Ulcer proceeds from a repletion or illneſs of humours. Now by theſe means having taken away the cauſe of the Ulcer, you muſt come to the particular cure thereof, beginning with that which is moſt urgent. Wherefore you muſt firſt aſſwage the pain by application of things contrary to the cauſe thereof: as, if it proceeded from a phlegmonous diſtemper, which hath long poſſeſt, diſtended, and hardned the part, it muſt be eaſed by evacuation. Firſt, bathing it with warm water, to mollifie and relax the skin, that ſo you may the more eaſily evacuate the contained humours; then ſhall you draw away a portion of the matter cauſing the ſwelling and pain by ſcarification, if the Patient ſhall be of ſufficient courage, or elſe by application of Horſe-leaches, if he be more faint-hearted; and then you ſhall temper the heat thereof by applying *Unguentum refrigerans Galeni*. To conclude, you ſhall attempt all things which we have formerly delivered (in our Treatiſe of Tumors) to take away the ſwelling thereof. When you have brought this to that paſs you deſire, you ſhall come to thoſe which are ſuch, that it cannot be taken away or healed without them, which ſhall be done by orderly helping the defects againſt Nature which were conjoined with the Ulcer, to wit, the rottenneſs of the bone, which you ſhall help by actual cauteries; and in the mean while you ſhall draw the Ulcer into another form, to wit, cornered, and you ſhall cut away the callous hardneſs, and help the rottenneſs; then muſt you procure the falling away of the Eſchar, and then provide for the ſcaling of the bone by the means formerly preſcribed; laſtly, the mundified Ulcer muſt be filled with fleſh. For generating of fleſh two cauſes muſt concur, the efficient, and material; the efficient is, the good temper both of the whole body, as alſo of the ulcerated part. For, this prevailing, there will be an attraction, digeſtion, oppoſition and aſſimulation of the laudable juice to the part affected; verily the laudable temper is preſerved by like things, but the vicious is amended by contraries. The matter to be ſpent upon fleſh is laudable bloud, which offends neither in quality nor quantity. In this regeneration of the fleſh there appear two kinds of excrements, the one more thin and humid called *Sanies*, the other more groſs termed *Sordes*. Both of theſe for that they are contrary to nature, do therefore hinder the regeneration of fleſh, and therefore muſt be taken away by applying their contraries, as by things drying in the firſt degree, and more ſtrongly or weakly detergent, according to the complexion of the part and the whole body, and the plenty and quality of the excrementitious humour, and the uncleanneſs of the Ulcer. For the part muſt be preſerved by the

Gal. lib. 4. *de comp. med. ſecund. gen.*

The things conducing to the generating of fleſh.

uſe

uſe of the like, but the Ulcer overcome by application of things contrary thereto. After that by Natures endeavour and the Chirurgeons help the Ulcer is replete with fleſh, it muſt be cicatrized, that is, covered with a callous skin in ſtead of the true and native skin. It may be cicatrized by ſtrewing of very drying powders having very little or no acrimony. Thus Alum and Vitriol being burnt and made into Powder, and thinly ſtrewed upon the part, do quickly cicatrize the former fleſhy Work. To this purpoſe alſo ſerve the root of *Ariſtolochia*, Aloes, burnt Lead, Pomegranat Pills burnt, Litharge, *Tutia*, and alſo plates of Lead beſmeared with Quick-ſilver, whoſe efficacy for this purpoſe Chirurgeons ſometimes find more certain and powerful than any other remedies.

What a Scar is.

Things cauſing cicatrization.

CHAP. V.

Of a diſtempered Ulcer.

BEfore we ſpeak of a diſtempered Ulcer, it is meet, leſt that the Chirurgeon take one diſtemper for anotner, briefly to relate the ſigns of each. You may know that an Ulcer is aſſociated with a dry diſtemper by your ſight, as if the Ulcer be as it were wrinkled, if it ſend forth little or no moiſture; alſo it is known by touch, if it feel rough and hard. You ſhall correct this diſtemper by humecting Medicins, as fomenting it with warm water according to *Galens* opinion, or elſe with *Hydrelæum (i.)* Oil and Water mixt: but always you muſt firſt purge, if the body ſhall abound with ill humours, or uſe Phlebotomy if the body be plethorick; otherwiſe you ſhall draw more humours into the part than it can bear. Now you ſhall ſo long foment it, untill the fleſh which is about it begin to look red, wax ſoft and moiſt, and the part it ſelf be a little ſwollen. If you proceed further, you will reſolve all the humour which you have drawn thither, and ſo your labour is in vain. After the fomentation, apply ſuch a remedy to the ulcerated part. ℞ *Cremoris hordei* ℥ ij. *fol. malvæ in aq. coct.* ℥ j. *pingued. porci* ℥ j. ß. *mellis com.* ℥ ſ. *miſce in mort. & fiat unguentum.*

Signs of a diſtempered Ulcer.

Remedies for a dry diſtempered Ulcer.

You ſhall know a moiſt diſtemper aſſociates the Ulcer by the plenty of the excrementitious humour, which the Ulcer ſends forth, by the ſpongy and fungous ſoftneſs and growth of the fleſh about it. You ſhall amend this by drying remedies, ſuch as thoſe are, which we term Sarcoticks, having always regard to the plenty of the humour, the proper temper of the part, and other indications formerly mentioned. Amongſt other remedies *Galen* much commends Alum Water, for it dries, cleanſes and corroborates the affected part. Alſo this enſuing fomentation may be applied to good purpoſe. ℞ *Roſar. rub. abſinth. beton. tapſi barbati an. m.* j. *gallarum, nucum cupreſſi, an.* ℥ ij. *aluminis rochæ* ℥ j. *fiat decoctio in vino auſtero, inſtituatur fotus.* Then let *Empl. de ceruſſa* or *de minio* be applied to the Ulcer. Alſo I have found by experience that the Powder of burnt Alum lightly ſtrewed upon the Ulcer is very effectual in this caſe. You ſhall know that an hot diſtemper aſſociates the Ulcer by the redneſs or yellowneſs thereof, by the heat manifeſt to your touch, and the propriety of your pain. Then muſt you have recourſe to refrigerating things, ſuch as *Ung. Roſatum Meſ. Refrigerans Gal. Populeon*; ſtoops and cloths dipped in Plantain Water, Nightſhade Water, or Oxycrate. I have oft found by experience that ſcarification, or Leaches being applied, did more conduce than any other remedy. For ſo the chafed bloud, which by that means is apt to corrupt, is drawn away, and the part it ſelf is alſo freed of that burden.

Gal. lib. 1. *ſimp. cap.* 7.

Signs of too moiſt an Ulcer

Signs of a hot diſtempered Ulcer.

We know a cold diſtemper by the whitiſh or pale colour, by the touch of the Chirurgeon, and ſpeech of the Patient complaining of the coldneſs of the ulcerated part. You ſhall correct this by applying and putting bottles filled with Water about the part, or elſe Swines bladders half filled with the following decoction. ℞ *Origani, pulegii, chamæm. meliloti, an. m.* j. *abſinth. majoranæ, ſalviæ, roriſmar. an. m.* ſ. *fiat decoctio in vino generoſo, addendo aquæ vitæ quod ſufficit.* Alſo the Ulcer may be conveniently fomented with Sponges dipped in the ſame decoction, and let there be applied thereto *Empl. Oxycroceum, emp. de meliloto, de Vigo cum mercurio*, and *ſine mercurio*. But if a mixt and compound diſtemper be joined to the Ulcer, the Medicins muſt in like manner be mixt and compoſed. The reſidue of the Chirurgeons care and pains muſt be ſpent upon the proper and peculiar cure of the Ulcer, as it is an Ulcer; which we ſaid in the former Chapter was contained in deterſion, regenerating fleſh, and cicatrization thereof.

Signs of a cold diſtempered Ulcer.

CHAP. VI.

Of an Ulcer with pain.

THere oft-times ſo great pain accompanieth Ulcers, that it calls thereto the counſel of the Phyſician. Wherefore if it proceed from any diſtemper, it ſhall be taken away by remedies proper againſt that diſtemper, ſuch as we mentioned in the former Chapter. But if it do not ſo ceaſe, we muſt go on to Narcoticks. Such are cataplaſms of the leaves of Mandrakes, Water-lillies, Henbane, Nightſhade, Hemlock, the ſeeds of Poppy and Oils of the ſame; to which alſo may be added *Opium*, *Populeon*, and other things of like faculties. But if a malign acrimony and virulency of an humour corroding and eating the fleſh lying under it and the lips about it, cauſe and make the pain, you ſhall neither aſſwage it by Anodynes nor Narcoticks; for by application of gentle Medicins it will become worſe and worſe. Wherefore you muſt betake you to Cathæreticks; for ſtrong Medicins are fitteſt for ſtrong diſeaſes. Wherefore let a Pledget dipped in ſtrong and more than ordinarily powerful *Ægyptiacum*, or in a little Oil of Vitriol, be applied to the Ulcer; for theſe have power to tame this raging pain, and virulent humours. In the mean ſeaſon let refrigerating things be put about the Ulcer; leſt the vehemency of acrid Medicins cauſe a defluxion.

The matter of Narcotick Cataplaſms.

Cathæreticks have power to aſſwage pain.

CHAP.

CHAP. VII.

Of Ulcers, with over-growing or proudneſs of fleſh.

Things waſting ſuperfluous fleſh.

ULcers have oft-times proud or over-growing fleſh in them, either by the negligence of the Chirurgeon, or fault of the Patient. Againſt this, drying and gently eating or conſuming Medicins muſt be applied, ſuch as are Galls, *Cortex thuris*, Aloes, *Tutia*, Antimony, *Pompholix*, Vitriol, Lead, all of them burnt and waſht if need require. Of theſe Powders you may alſo make Ointments with a little Oil and Wax; but if the proud fleſh, as that which is hard and denſe, yield not to theſe remedies, we muſt come to cauſticks, or elſe to iron, ſo to cut it off. For in *Galens* opinion, the taking away of proud fleſh is no work of Nature, (as the generating, reſtoring and agglutinating of the fleſh is) but it is performed by Medicins which dry vehemently, or elſe by the hand of the Chirurgeon; wherefore amongſt the remedies fit for this operation, the Powder of Mercury with ſome ſmall quantity of burnt Alum, or burnt Vitriol alone, ſeem very effectual to me. Now for the hard and callous lips of the Ulcer, they muſt be mollified with Medicins which have ſuch a faculty, as with Calves, Gooſe, Capons, or Ducks greaſe, the Oils of Lillies, ſweet Almonds, Worms, Whelps, *Oeſipus*, the mucilages of Marſh-mallows, Linſeed, Fænugreck-ſeed, Gum *Ammoniacum*, *Galbanum*, *Bdellium*, of which being mixed may be made Emplaiſters, Unguents, and Liniments: or you ſhall uſe *Empl. Diachylon*, or *de Mucilaginibus*, *De Vigo cum Mercurio*. To conclude, after you have for ſome few days uſed ſuch like remedies, you may apply to the Ulcer a plate of Lead rubbed over with Quickſilver, for this is very effectual to ſmooth an Ulcer and depreſs the lips: if you ſhall prevail nothing by this means, you muſt come to the Cauſticks, by which if you ſtill prevail nothing, for that the lips of the Ulcer are ſo callous lous that the cauſticks cannot pierce into them, you muſt cleave them with a gentle Scarification, or elſe cut them to the quick, ſo to make way, or as it were open a Window, for the Medicin to enter in, according to *Galen*. Neither in the interim muſt you omit *Hippocrates* his advice, which is, that by the ſame operation we reduce the Ulcer, if round, into another figure, to wit, long or triangular.

For the callous lips of Ulcers.

Lib.3. Meth. cap.6.

Lib.4. Meth. cap.2.

CHAP. VIII.

Of an Ulcer putrid and breeding Worms.

The cauſe of Worms breeding in Ulcers

WOrms are divers times bred in Ulcers, whence they are called Wormy Ulcers; the cauſe hereof is the too great excrementitious humidity prepared to putrefie by unnatural and immoderate heat. Which happens, either for that the Ulcer is neglected, or elſe by reaſon of the diſtemper and depraved humours of all the body, or the affected part; or elſe for that the excrementitious humour collected in the Ulcer, hath not open and free paſſage forth; as it happens to the Ulcers of the Ears, Noſe, Fundament, Neck of the Womb, and laſtly, to all ſinuous and cuniculous Ulcers. Yet it doth not neceſſarily follow that all putrid Ulcers muſt have Worms in them; as you may perceive by the definition of a putrid Ulcer, which we gave you before. For the cure of ſuch Ulcers after general means, the Worms muſt firſt be taken forth, then the excrementitious humour muſt be drawn away whence they take their original. Therefore you ſhall foment the Ulcer with the enſuing decoction, which is of force to kill them; for if any labour to take forth all that are quick, he will be much deceived; for they oft-times do ſo tenaciouſly adhere to the ulcerated part, that you cannot pluck them away without much force and pain. ℞ *Abſinth. centaur. majoris, marrubii, an. M.* j. *fiat decoctio ad* ℔ ſ. *in aqua diſſolve aloes* ʒ ſ. *unguenti Ægyptiaci* ʒ j. Let the Ulcer be fomented and waſhed with this Medicin, and let pledgets dipped herein be put into the Ulcer; or elſe, if the Ulcer be cuniculous or full of windings, make injection therewith which may go into all parts thereof.

A fomentation to kill the Worms.

Achigenes much commends this following Medicin. ℞ *Ceruſæ, polii montani, an.* ʒ ß. *picis navalis liquidæ quantum ſufficit, miſce in mortario pro linimento.* If the putrefaction be ſuch that theſe Medicins will not ſuffice for the amendment thereof, you muſt come to more powerful, or to Cauteries alſo, or hot Irons, or to Section; yet you muſt ſtill begin with the more gentle, ſuch as this of *Galens* deſcription. ℞ *Ceræ,* ʒ ij. *ceruſæ* ʒ j. *olei roſ.* ʒ ij. *ſalis ammon.* ʒ ſ. *ſquam. æris* ʒ ij. *thur. alum. æruginis malicor. calcis vivæ, an.* ʒ j. *fiat emplaſtrum.* Or ℞ *terebinth. lotæ* ʒ ij. *ceræ albæ* ʒ ß. *liquefiant ſimul addendo ſublimati* ʒ ſ. *ſalis torrefacti & vitrioli calcinati, an.* ʒ j. *fiat mundificativum.* Or you muſt uſe our *Ægyptiacum* alone, which hath ſublimate entering into the compoſition thereof; but in the interim the circuit of the Ulcer muſt be defended with refrigerating and defenſative things for fear of pain.

Gal.4. comp. Med.

CHAP. IX.

Of a Sordid Ulcer.

A Sordid Ulcer after the cure of the body in general, ſhall be healed with detergent Medicins; the Indication being drawn from the groſs and tough excrement, which with the excrementitious *Sanies*, as it were beſieging and blocking up the ulcerated parts, weakens and as it were dulls the force of Medicins though powerful, which cauſeth us to begin the Cure with Fomentations and Lotions; as thus: ℞ *Lixivii com.* ℔ j. *abſinth. marrub. apii, centaur. utriuſque, hypericonis, an. M. ſſ. coquantur, colaturæ, quæ ſufficiat, adde mellis roſati* ʒ j. *unguenti Ægyptiaci* ʒ ß. *fiat fotus.* Then uſe the following deterſive Medicin: ℞ *Succi apii, & plantag. an.* ʒ ij. *mellis com.* ʒ j. *terebinth.* ʒ j. ſ. *pul. Iridis Florent. & aloes an.* ʒ ſ. *fiat medicamentum.* The Chirurgeon muſt

A detergent Lotion.

well

well conſider, at how many dreſſings he ſhall be able to waſh away the groſs *ſordes*, or filth ſticking cloſe to the Ulcer, and dry up the excrementitious *ſanies*. For oft-times theſe things may be done at one dreſſing; but in others who have more quick ſenſe or feeling, not ſo ſoon. But when the Ulcer is freed of ſuch groſs *ſordes* or filth, you muſt forbear to uſe more acrid things for fear of pain, defluxion, inflammation and eroſion, whereby the Ulcer would become more hollow. Wherefore then we ſhall be content to apply remedies which dry and cleanſe without acrimony, that we may ſo help Natures endeavours in generating fleſh. Such remedies are, the powders of Aloes, Maſtick, Myrrh, Orris, Litharge, Antimony, roots of Gentian, Barley-flower, and the like, which being ſtrewed upon the Ulcer, you ſhall cover it with lint, and put over that a plate of Lead, rubbed over with quick-ſilver; and you ſhall put on theſe deterſives and deſiccatives more or leſs ſtrong, as you ſhall find it requiſite and neceſſary. For the too plentiful uſe of drying and deterſive things, doth in time hollow the Ulcer, whereby it comes to paſs that in ſhort time in like ſort, a great quantity of *ſanies* flows from the Ulcer, the proper ſubſtance of the fleſh being diſſolved by the force or acrimony of deterſive medicines; as alſo the proper alimentary humor, which flowed to the part, being in like ſort defiled: Which thing beguiles the unskilful Chirurgeon. For by how much he ſees the Ulcer flow more plentifully with *ſanies*, he endeavours by ſo much the more to exhauſt and dry up with more acrid medicines theſe humidities, as if they were excrementitious: But *Galen* hath long ago admoniſhed us to take heed hereof, ſetting forth a Hiſtory of a certain Emperick who dreſſing a ſordid Ulcer with a green, acrid and eating medicine, diſſolved the fleſh; and ſo conſequently made the Ulcer more hollow, and cauſed more pain and defluxion; whereby it hapned, that continually adding more acrid medicines, he continually (by his ignorance and unskilfulneſs) increaſed the colliquation of the fleſh, the largeneſs of the Ulcer and excrementitious humidity: Wherefore we muſt take ſpecial care whether the ſordid Ulcer grows each day worſe, by its proper fault, and the impurity of the whole body beſides, or elſe by the colliquation of the fleſh, and corruption of the benign and alimentary humor ſent thither for the nutrition of the part, by the too frequent and unskilful uſe of too acrid a medicine. You may conjecture this by the increaſe of the pain without reaſon, and by the heat and redneſs of the lips of the Ulcer. Therefore you muſt principally have regard to this, that you give each of your Patients his fit meaſure; that is, a convenient and agreeable medicine to each of their ſtrengths, taking indication from the ſtrength, diſtemper and conſiſtence of the whole body and affected part; for there is a great deal of difference whether you apply a medicine to a Plow-man or labourer, or to an Eunuch and woman; or whether to the leg or eyes: For theſe medicines which to a denſe and hard body and part are only detergent and drying, the ſame are to delicate and tender bodies and parts cathæretick and eating, by colliquation of the fleſh, and corruption of the nouriſhment, making an increaſe of *ſordes* or filth; on the contrary, thoſe things which do laudably and ſufficiently cleanſe the fleſh in a ſoft body, and dry up the *ſanies*, theſe ſame things applied to a hard body, increaſe the *ſordes* and *ſanies* by ſuffering them to breed, neither are they of ſufficient power to waſh away the tenacious impurity of a denſe body. Wherefore the skilful Chirurgeon will ſee when he muſt betake himſelf from too ſtrongly cleanſing and eating medicines to theſe which are more mild.

Detergent medicines without acrimony.

A caution very obſervable in uſe of detergent things.

A diſtinction to be obſerved concerning the impurity of Ulcers.

Diligent regard muſt be had of the Patients bodies, and the affected part.

CHAP. X.

Of a virulent, eating and malign Ulcer, which is termed Cacoethes, *and of a Chironian Ulcer.*

VIrulent and eating Ulcers differ not, unleſs in *magis* and *minus*, for we term it a virulent Ulcer, which ſends forth a virulent *ſanies*, which is properly called *Virus*. This *Virus* or virulency, when it becomes more malign, gnaws and feeds upon the parts which lie under, and are adjoyned to the Ulcer, and makes an eating Ulcer. Such Ulcers are by *Galen* called *Dyſepulotica*, that is, difficultly to be cicatrized; for, ſaith he, it happens that the Ulcer is Dyſepulotick, either for that the part affected may be vitiated, either in the habit or temper thereof ſo that it may corrupt the humor which flows thither; ſuch an Ulcer is by a particular name termed *Cacoethes*; or for that by reaſon of the evil quality of the blood flowing thither and eating the part, the part affected being too moiſt cannot heal up. He further adds, that a Chironian Ulcer is far more malign than theſe Ulcers, which are termed *Cacoethe*. For the cure; by reaſon that all theſe Ulcers have a large extent, for ſome are more malign and ill to be cicatrized than other ſome, it is alſo neceſſary to have divers medicines ready and at hand, diſtinct both in their faculties and the degrees thereof, ſo that it is no marvel if they oft fail of their purpoſe, who with the ſame medicine dreſs (and think they ſhall heal) all malign Ulcers. This following medicine deſcribed by *Aſclepiades*, is much commended by *Galen*. ℞ *Squammæ æris, æruginis raſæ, an.* ʒ i. *Ceræ* ℔ ß. *Reſinæ laricis* ʒ i ß. *Quæ liquari poſſunt aridis affundantur*, and make an Emplaiſter to be laid only upon the Ulcer; for you muſt lay a defenſative about the Ulcer, for fear of inflammation. But *Galen* ſaith, that the following Epulotick of *Primon* excels the reſt, as that which to deſperate Ulcers (which many have taken in hand and left as uncurable,) was of certain and approved uſe. ℞ *Soreos* ʒ iij. *Aluminis ſciſſilis; calcis vivæ, an.* ʒ ij. *Thuris gallarum, an.* ʒ iiij. *Ceræ* ℔ i. & ʒ iij. *Sevi vitulini* ℔ i. & ʒ vij. *Olei veteris quantum ſufficit, fiat emplaſtrum.*

How virulent and eating Ulcers differ.

Gal. lib. 4. de comp. med. ſec. genera.

How a Chironian Ulcer differs from an eating. See before, *cap.* 2.

Gal. lib. 4. See *cap.* 5.

Gal. lib. 4. *de comp. med.* See *Gen. cap.* 6.

CHAP. XI.

An Advertiſement to the young Chirurgeon, touching the diſtance of times wherein malign Ulcers are to be dreſſed.

Gal. lib. 4. de comp. med. See *Gen. cap. 5.*

TO ſhew the uſe of *Aſclepiades* his medicines, deſcribed in the former Chapter, and convince the error of thoſe Chirurgeons, who think they do well for their Patients, if they twice or thrice on a day dreſs malign Ulcers; I have here thought good to digreſs a little from my purpoſe, and to interpoſe *Galen*'s authority. Rightly (ſaith *Galen*) hath *Aſclepiades* added theſe words to the formerly deſcribed medicine: And looſe this after three days, and foment the Ulcer, and faſten the ſame emplaſter being waſhed, and apply it again; for unleſs the medicine adhere long to the skin, it will do no good. Which thing notwithſtanding many Phyſicians have been ignorant of; thinking, if they wiped away the *ſanies* from the Ulcer thrice on a day, they ſhould do better than thoſe who did the ſame but twice a day. But thoſe who dreſs it but once a day, are reproved by the Patients, as negligent. But they are much miſtaken; for you muſt remember, as we have delivered in moſt of our Writings, that the qualities of all neighbouring bodies do mutually actuate and affect each other in ſome degree, although the one thereof be much more powerful; for by this reaſon in ſpace of time they become ſomewhat alike, though they otherwiſe differ much: But when the quality of the medicine ſhall be like the *ſpecies* to the body to be cured, there follows the better ſucceſs. Wherefore he wich moved firſt by theſe reaſons, firſt appointed to uſe the emplaſter formerly applied, is worthy of commendations; and we ought to follow him much the rather, ſeeing that which he found out by reaſon, is approved by experience. Neither did he unadviſedly command, to foment the wound every third day, that is, every dreſſing; for, ſeeing it is a powerful medicine, therefore it ſtands in need of mitigation. Thus much *Galen*, whoſe opinion grounded on reaſon, he can again confirm with another reaſon. It is already ſufficiently known, that medicines can do nothing in us unleſs by the force of the native heat, which ſtirs up the faculty of the medicine to operation. But in Ulcers which are abſolutely malign, the native heat of the affected part is very languid, being broken and debilitated by the preſence of the preternatural heat; ſo that it ſtands in need of a great ſpace of time to actuate the virtue and faculty of the medicine Wherefore, if in that time, when as the native heat hath much moved and ſtirred up the faculty of the medicine, the Ulcer be looſed or opened, and that emplaſter caſt away which was laid upon the part, and a freſh one laid inſtead thereof; the heat implanted in the part, is either diſſipated by the contract of the air, or is weakned and driven in; and that endeavour which was made by the emplaiſter was to no purpoſe, being, as it were, ſtopped in the midſt of the courſe: But a new emplaiſter being laid on, the heat of the part muſt undergo a new labour, ſo to ſtir up the faculty to bring it to act.

Galen's reaſon further explained.

Medicines are only ſuch in faculty.

For all medicines are what they are in faculty. Equal to this is their errour, who by too oft renewing their emplaiſters on the ſame day, do too powerfully cleanſe; for ſo they do not only take away the excrementitious humous, both *ſordes* and *ſanies*, but alſo the alimentary juice; to wit, the *Rob*, *Cambium* and *Gluten*, which are the next matter for procreating of laudable fleſh. Wherefore, it is not good to dreſs Ulcers ſo often in one day, and to looſe them to apply new emplaiſters, unleſs ſome grievous ſymptom (as pain) force us to do it, which requires to be aſſwaged and mitigated by the often changing and renewing of Anodyne medicines.

CHAP. XII.

How to bind up Ulcers.

The beginning of your binding muſt be at the Ulcer.

FOr the binding up of Ulcers, you muſt always begin your bandage at the Ulcer. Now the rowler muſt be ſo large, that it may not only cover and comprehend the Ulcer, but alſo ſome portion of the adjacent parts above and below; and let it preſs the Ulcer with that moderation, that it may only preſs out the excrementitious humors. For ſo the Ulcer will become dry, and conſequently more near to healing, as it is obſerved by *Hippocrates*. Let this be the meaſure of your binding, that it be neither too ſtrait, for hence would enſue pain and defluxion; nor too lax, for ſuch is of no uſe. You may moiſten your boulſters and rollers in Oxycrate, or in red and aſtringent Wine, eſpecially in Summer; when you have bound it up, the part muſt be kept quiet: For according to *Hippocrates*, thoſe who have an Ulcer in the leg, ought neither to ſtand nor ſit, but to lie on a bed. Wherefore, when the legs are ulcerated, the arms muſt be exerciſed, by handling, lifting up and caſting down of divers things. But on the contrary, if the arms be ulcerated, the legs muſt be exerciſed with walking, or frictions from above downwards, if the Patient cannot endure to walk. So the humors and ſpirits which with more violence and greater plenty run down to the part affected, may be drawn back and diverted.

Revulſion into contrary parts.

CHAP. XIII.

Of the cure of particular Ulcers, and firſt of thoſe of the Eyes.

4. Meth.

FOr that (in *Galen*'s opinion) the divers Indications in curing diſeaſes are drawn from the condition of the part, to wit, the temper, complexion, ſite, figure, uſe, dull or quick ſenſe; Therefore having briefly handled the general cure both of ſimple and compound, and implicit Ulcers, I think it fit to treat of them now as they are diſtinguiſhed by the parts, beginning

ning with theſe of the eyes. Theſe according to *Celſus*, are ſometimes cauſed by puſtules, or a ſharp defluxion which frets or eats in ſunder the coats thereof, or elſe by a ſtroke.

Paulus ſets down theſe differences of the Ulcers of the eyes: If (ſaith he) a ſmall, little and hollow Ulcer be upon the horny-coat, it is by the Greeks termed *Botryon*; but if it be broader and leſs deep, it is termed *Cæloma*; about the circle of the *Iris* or Rain-bow, it is called *Argemon*; if it be cruſty and ſordid, it is termed *Epicauma*. Theſe in general require the ſame cure as the former, that is, to be mundified, incarnated, dried and cicatrized; but the part affected indicates more gentle medicines. Wherefore having purged the Patient, and taken ſome blood both from his arm, as alſo from his veins and temporal arteries, and bathed him if it be needful, to divert the defluxion, you ſhall to his ſhoulders apply Cupping-glaſſes with Scarifications; or elſe bread newly drawn out of the Oven, and ſprinkled with *Aqua vitæ*; or ſome good Wine ſhall be applied to the original of the ſpinal marrow. But you ſhall apply to the forehead and temples an aſtringent emplaiſter made of *emplaſtrum contra rupturam*, *ung. Comitiſſæ*, and *reſiccativum rubrum* mixed together. But this enſuing *Collyrium* deſcribed by *Celſus* and approved by *Hollerius*, ſhall be dropped into the eye. ℞ *Æris uſti, cadmiæ uſtæ & lotæ, an.* ʒ i. *ex aqua fingatur collyrium quod liquore ovi diſſolvatur.* But in the mean time you muſt diligently obſerve whether you put the eye to any great pain. Wherefore now and then by putting anodyne medicines thereto, it will be good to comfort it. Alſo you may make *collyria* of the decoction of Plantain, Fenugreek, Wormwood, with a little quantity of Sugar-candy, *tutia*, gum *tragacanth*, Myrrh and Vitriol diſſolved therein. When the Ulcer is mundified, the following Sarcotick will be of good uſe. ℞ *Sarcocollæ in lacte muliebri nutritæ,* ʒ iij. *pul. diaireos ſimplicis, gum. arabici, tragacanth, an.* ʒ ß. *Mucilaginis fœnugræci quantum ſufficit ut inde fiat collyrium.* But you muſt note, that for moiſt Ulcers, Powders are more convenient than *Collyria*. When the Ulcer is plained or filled with its proper fleſh, it may be cicatrized with the following *collyrium*. ℞ *Tutiæ; cadmiæ ut decet præparatæ, ceruſæ, antimonii, olibani, an.* ʒ ß. *Myrrhæ, ſarcocollæ, ſanguinis Draconis, aloes, opii, an.* ʒ ß. *Cum aqua plantaginis fiat collyrium*; or the powder only may be conveniently ſtrewed thereon.

Celſus hath noted, that the cicatrizing of the eyes is incident to two dangers; that is, leſt they be too hollow, or elſe too thick. If too hollow, they muſt be filled by the following remedy. ℞ *Papaveris lacrymæ,* ʒ ß. *Sagapeni, opopanacis, an.* ʒ ß. *æruginis* ʒ i. *Cumini* ʒ iij. *Piperis* ʒ ij. *cadmiæ lotæ & ceruſæ, an.* ʒ i ß. *Cum aqua pluviali fiat collyrium.* But if the ſcars be thick or groſs, the following remedy will extenuate them. ℞ *Cinamomi, acaciæ, an.* ʒ ß. *Cadmiæ elotæ, croci, myrrhæ, papaveris lacrymæ, gum. arabici, an.* ʒ i. *Piperis albi, thuris, an.* ʒ i ß. *Æris combuſti,* ʒ iij. *Cum aqua pluviali fiat collyrium.* But if the ſcar be upon the *Cornea* or horny coat, ſo that it cover the *pupilla* or ſight, the ſight will be intercepted by the denſeneſs of the membrane. Here you muſt alſo obſerve, that the ſcars that are on the *Cornea* are white, but theſe on the *Adnata* are red, becauſe this is ſpread over with more little veins than that.

Lib. 6. cap. 6. lib. 3. *Botryon, Cæloma, Argemon, Epicauma.*

The cure.

A *Collyrium* to cleanſe the ulcers of the eyes.

A ſarcotick *Collyrium.*

An epulotick *Collyrium. Lib. 6. cap. 6.*

A *Collyrium* for hollow ſcars.

The ſcars of the hornycoat are white, and theſe of the *Adnata* red.

CHAP. XIV.

Of the Ozæna *and Ulcers of the Noſe.*

THe *Ozæna* is a deep and ſtinking Ulcer in the inſide of the noſe, ſending forth many cruſty and ſtinking excrements: *Celſus* ſaith that ſuch Ulcers can ſcarcely be healed. It is cauſed (as *Galen* ſaith) by the diſtillation of acrid and putrid humors from the head into the noſtrils about the mammillary proceſſes. For the cure, the Patient muſt eat ſparingly; and his meat muſt neither be ſharp nor ſtrong; the humor being prepared, muſt be purged; the head dried and ſtrengthned, that ſo it may neither admit the excrementitious humors, nor ſend them down; then muſt we come to the part affected with the Ulcer. The Ulcer muſt be dried with a repelling medicine; ſuch as is the juice of Pomegranats boiled to the half in a braſs veſſel; the powder of Calamint, Creſſes, white Hellebore, the juice of Creſſes with Alum and other things which you may read in *Celſus*. *Galen* out of *Archigenes* wiſhes, to draw up into the noſtrils the juice of Calamint, or that the Calamint it ſelf being dried, and made into powder, may be blown with a quill into the noſe. Others uſe this following powder. ℞ *Roſ. rub. mint. calam. arom. rad. angelicæ, gentian. macis, caryop. an.* ʒ ß. *Camph. ambræ, an. gr.* iiij. *Moſch. gr.* vj. *fiat pulvis ſubtiliſſimus. Manardus* writes, that the urine of an Aſs, though a naſty medicine, is an excellent remedy in this affect. But if the inveterate and contumacious evil do not yield to theſe remedies, then you muſt have recourſe to Coperas, Verdigreece, *ſal ammoniacum*, and Alum with Vinegar. It divers times happens, that the Ulcer ſpreading on, comes to take hold of the *Oſſa ethmoidæa*, or ſive-like bones; in which caſe, you muſt not forcibly pluck them out, but refer the whole buſineſs to Nature, and expect when they ſhall come away of themſelves, making in the mean while injections into the noſtrils, of *Aqua vitæ*, wherein Cephalick powders have been ſteeped for the greater drying.

Lib. 6. cap. 8. Gal. lib. 3. de Comp. med. ſecund. locos c. 3.

The cure.

Lib. 20. epiſt. 5. An injection when the *Ozæna* ſhall come to the *Oſſa Ethmoidæa.*

CHAP. XV.

Of the Ulcers of the Mouth.

OF this Tribe are the *Aphthæ*, Ulcers familiar to little children, according to *Hippocrates*. They oft-times begin in the gums, and by the palat of the mouth creep into the *Uvula*, throtle, and over all the mouth, as *Celſus* ſaith. *Galen* makes two kinds of *Aphtha's*; the one of eaſie cure, ſuch as that which uſually troubles children by reaſon of the acrimony of the nurſes milk; the other is malign by reaſon of an afflux of an evil humor (that is, venenate and malign) into the mouth. For the cure, it ſhall be good to abſtain from all acrid things, and if it be a ſucking child, it will not be amiſs to temper the nurſes milk with refrigerating meats, bathing

Aph. 24. ſect. 3. Celſus lib. 6. cap 11. Gal. com ad 3. lib. epidem.

The cure.

the whole body, and fomenting the dugs with warm water; for all the members in children are moſt tender, and as it were mucous, and their mouths are unaccuſtomed to meats and drinks. For topick medicines, you muſt make choice of ſuch, which may quickly and readily work the effect; for here the condition of the affected part is ſuch, that they cannot long remain and adhere thereto. Therefore if the Ulcer be malign, it muſt be lightly touched with *Aqua fortis*, which hath been uſed in ſeparating metals, and which beſides is tempered with ſix parts of common water. You may for the ſame purpoſe uſe the Oyls of Vitriol, Sulphur, Antimony, Mercury-water, and the like. *Aetius* wiſhes you to touch and correct ſuch Ulcers with a lock of Wooll dipped in ſcalding Oyl, and ſo faſtned to the end of a Probe, until they wax white and become ſmooth or plain: For ſo their eating and ſpreading force will at length be bridled, and laudable fleſh grow up in place of that which is eaten. After ſuch burning, it will be good to waſh the mouth with the following Gargariſm, which alſo of it ſelf alone will ſerve to cure Aphtha's, which are not malign. ℞ *Hordei integri p.* i. *plant. ag. ceterach. piloſellæ, agrimoniæ, an. M.* i. *fiat decoctio ad* ℔ i. *In qua diſſolve mellis roſati* ℥ i. *Diamoron.* ʒ ſ. *Fiat gargariſma.* You may alſo make other gargles, of Pomegranate-Pills, Balauſtines, Sumach, Berberries, Red-roſes being boiled, and diſſolved in the ſtrained liquor *Diamoron* and *Dianucum*, with a little Alum: For *Galen* writes, that ſimple Ulcers of the mouth are healed with things which dry with moderation; now *Diamoron* and *Dianucum* are ſuch. But others ſtand in need of ſtrong medicines, with ſuch like. If the palat be ſeiſed upon, we muſt uſe the more diligence and care; for there is danger, leſt (being the part is hot and moiſt,) the bone (which lies under which is rare and humid) may be corrupted by the contagion, and fall away; and the voice or ſpeech be ſpoiled. If the Ulcer be pocky, omitting the common remedies of Ulcers, you muſt ſpeedily betake your ſelf to the proper Antidote of that diſeaſe, to wit, quick-ſilver. Fiſtulous Ulces often take hold on the gums, whence the root of the next tooth becomes rotten; and ſo far, that the acrimony of the *Sanies* oft-times makes its ſelf a paſſage forth on the outſide under the chin; which thing puts many into a falſe conceit of the *Scrophula*, or Kings-evil, and conſequently of an uncurable diſeaſe. In ſuch a caſe *Aetius* and *Celſus* counſel is, to take out the rotten tooth, for ſo the Fiſtula will be taken away, the gum preſſing and thruſting it ſelf into the place of the tooth which was taken forth; and ſo the cauſe nouriſhing, the putrefaction being taken away, (that is, the tooth) the reſt of the cure will be more eaſie. The Ulcers of the tongue may be cured by the ſame remedies by which the reſt of the mouth; yet thoſe which breed on the ſide thereof endure very long, and you muſt look whether or no there be not ſome ſharp tooth over againſt it, which will not ſuffer the Ulcer in that place to heal; which if there be, then muſt you take it away with a file.

A Gargariſm for the *Aphthæ*.

Lib. 6. Meth. cap. 10.

Ulcers of the palat muſt be quickly and carefully dreſſed.

Aetius lib. 6. cap. 3.

Celſus lib. 6. cap. 13.

CHAP. XVI.

Of the Ulcers of the Ears.

Their cauſes.

ULcers are bred in the auditory paſſage both by an external cauſe, as a ſtroke, or fall; as alſo by an internal, as an abſceſs there generated. They oft-times flow with much matter not there generated, for ſuch Ulcers are uſually but ſmall, and beſides in a ſpermatick part; but for that the brain doth that way disburthen its ſelf.

The cure.

A Maſticatory.

For the cure, the chief regard muſt be had of the antecedent cauſe, which feeds the Ulcer, and it muſt be diverted by purging medicines, Maſticatories and Errhines. This is the form of a Maſticatory. ℞ *Maſtich.* ʒ i. *ſtaphiſagr. & pyreth. an.* ℈ i. *Cinam. & caryoph. an.* ʒ ſ. *Fiant Maſticatoria, utatur mane & veſpere.* But this is the form of an Errhin. ℞ *Succi betonic. mercurial. & meliſſæ, an.* ʒ ſ. *Vini albi* ʒ i. *miſce & frequenter naribus attrahatur.* For topick medicines, we muſt ſhun all fatty and oily things, as *Galen* ſets down in *Method. medendi*, where he finds fault with a certain follower of *Theſſalus*, who by uſing *Tetrapharmacum*, made the Ulcer in the ear grow each day more filthy than other, which *Galen* healed with the Trochiſces of *Andronius* diſſolved in Vinegar, whoſe compoſure is as followeth. ℞ *Balaut.* ʒ ij. *Alumin.* ʒ i. *Atrament. ſutor.* ʒ ij. *Myrrhæ* ʒ i. *Thur. Ariſtoloch. gallarum. an.* ʒ ij. *Salis Ammon.* ʒ i. *Excipiantur omnia melicrato, & fiant trochiſci. Galen* in the ſame place witneſſeth, that he hath healed inveterate Ulcers, and of two years old of this kind, with the ſcales of Iron made into powder, and then boiled in ſharp Vinegar until it acquired the conſiſtence of Honey: Moreover, an Oxes gall diſſolved in ſtrong Vinigar, and dropped in warm, amends and dries up the putrefaction wherewith theſe Ulcers flow. Alſo the ſcales of Iron made into powder, boiled in ſharp Vinegar, dried and ſtrewed upon them. But if the ſtraitneſs of the paſſages ſhould not give leave to the matter contained in the windings of the ears to paſs forth, then muſt it be drawn out with an Inſtrument thereupon called a *Pyoulcus*, or Matter-drawer, whereof this is the figure.

An Errhin.

The compoſition of *Andronius* his trochiſces.

Scales of Iron.

The Figure of a Pyoulcus, *or Matter-drawer.*

Of the *Pyoulcus Galen* makes mention 2. *ad Glauconem.*

CHAP.

CHAP. XVII.

Of the Ulcers of the Wind-pipe, Weazon, Stomach and Guts.

THeſe parts are ulcerated either by an external cauſe as an acrid medicine, or poyſon ſwallowed down; or by an internal cauſe, as a malign fretting humor, which may equal the force of poyſon generated in the body, and reſtrained in theſe parts. If the pain be increaſed by ſwallowing or breathing, it is the ſign of an Ulcer in the weazon, or wind-pipe joyning thereto. But the pain is moſt ſenſibly felt whenas that which is ſwallowed is either ſour or acrid, or the air breathed in, is more hot or cold than ordinary: But if the cauſe of pain lie faſtned in the ſtomach, more grievous ſymptoms urge; for ſometimes they ſwound, have a nauſeous diſpoſition and vomiting, convulſions, gnawings, and pain almoſt intolerable, and the coldneſs of the extreme parts; all which when preſent at once, few ſcape unleſs ſuch as are young, and have very ſtrong bodies. The ſame affect may befal the whole ſtomach, but becauſe both for the bitterneſs of pain, and greatneſs of danger, that Ulcer is far more grievous which takes hold of the mouth of the ventricle, honoured by the Ancients with the name of the Heart; therefore Phyſicians do not make ſo great a reckoning of that which happens in the lower part of the ſtomach. Now we know that the guts are ulcerated, if *Pus*, or much purulent matter come forth by ſtool; if blood come that way with much griping; for by the *Pus* ſtaying, and as it were gathered together in that place, there is, as it were, a certain continual *Teneſmus*, or deſire to go to ſtool. Now all ſuch Ulcers are cured by meats and drinks, rather than by medicines, according to *Galen*: Therefore you muſt make choice of all ſuch meats and drinks as are gentle, and have a lenitive faculty, ſhunning acrid things; for *Tutia*, Litharge, Ceruſe, Verdigreece and the like, have no place here, as they have in other Ulcers: But when as the Ulcer ſhall be in the gullet or weazon, you muſt have a care that ſuch things may have ſome viſcidity or toughneſs, and be ſwallowed by little and little, and at divers times; otherwiſe they will not much avail, becauſe they cannot make any ſtay in theſe common ways of breath and meat; therefore they preſently ſlip down and flow away; wherefore all ſuch things ſhall be uſed in form of an *Eclegma*, to be taken lying on the back, and ſwallowed down by little and little, opening the muſcles of the throat, leſt the medicine paſſing down ſuddenly, and in great quantity, cauſe a Cough, a thing exceeding hurtful to theſe kinds of Ulcers. When they muſt be cleanſed, you ſhall have crude honey, which hath a ſingular faculty above all other detergent things, in theſe kinds of Ulcers: But when they can conveniently ſwallow, you ſhall mix Gum Tragacanth diſſolved in ſome aſtringent decoction. In Ulcers of the ſtomach, all acrid things (as I have formerly adviſed) muſt be ſhunned; as thoſe which may cauſe pain, inflammation and vomit, and beſides, hinder the digeſtion of the meat: Therefore let them frequently uſe a Ptiſan, and ſugred Gellies wherein Gum Tragacanth, and Bole-Armeniack have been put, the decoction of Prunes, Dates, Figs, Raiſins, Honey, Cows-milk boiled with the yolks of Eggs, and a little common Honey. When they are to be agglutinated, it will be convenient to make uſe of auſtere, aſtringent and agglutinative things, which want all acrimony, and ungateful taſte, ſuch as are *Hypociſtis*, Pomegranate-flowers and pills, *terra ſigillata*, *ſumach*, *acacia*, a decoction of Quinces, the Lentisk-wood, the tops of Vines, of Brambles, Myrtles, made in aſtringent Wine, unleſs there be fear of inflammation: Their drink ſhall be *Hydromel* water with ſugar, ſyrup of Violets and Jujubes. Honey mixed with other medicines is a very fitting remedy for Ulcers of the guts and other parts more remote from the ſtomach; for if you ſhall uſe aſtringent medicines alone of themſelves, they will ſtick to the ſtomach; neither will they carry their ſtrength any further; but honey mixed with them, beſides that it diſtributes them to the reſt of the body, and helps them forwards to the affected parts, alſo cleanſes the Ulcers themſelves. Here alſo Aſſes milk may with good ſucceſs be uſed inſtead of Goats or Cows milk; The uſe of a vulnerary potion is alſo commendable, if ſo be that it be made of ſuch Herbs and Simples, as by a certain tacit familiarity have reſpect to the parts affected: But the Ulcers of the guts have this difference amongſt themſelves, that if the greater guts be affected, you may heal them with a Clyſter and Injections, made alſo ſharp to correct the putrefaction; ſuch as are thoſe which are made of Barley-water, or Wine with *Ægyptiacum*. But if the ſmall guts be ulcerated, they muſt be rather healed by potions and other things taken at the mouth; for that (as *Galen* ſaith) theſe things which are put up into the body by the fundament, do not commonly aſcend to the ſmall or ſlender guts, but ſuch as are taken at the mouth cannot come unleſs with the loſs of their faculty, ſo far as the great guts.

The cauſes.

Signs.

Gal. lib. 5. de loc. affect. cap. 5.

Lib. 4. & 5. Method.

The cure.

How to take medicines for Ulcers of the throat.

Why acrid things muſt be ſhunned in theſe Ulcers.

How powerful Honey is to cure ſuch kind of Ulcers.

Ægyptiacum good for the Ulcers of the greater guts. *Lib. 5. meth.*

CHAP. XVIII.

Of the Ulcers of the Kidneys and Bladder.

ULcers are cauſed in the Kidneys and Bladder, either by the uſe of acrid meats drinks, or medicines, as *Cantharides*; or elſe by thecollection of an acrid humor, bred in that place, ſent or faln thither; or elſe by the rupture of ſome veſſel, or an abſceſs broken and degenerated into an Ulcer, as it ſometimes comes to paſs. They are diſcerned by their ſite, for the pain and heavineſs of Ulcers of the reins comes to the loins, and the *Pus* or matter is evacuated well and throughly mixed with the urine.

Cauſes.

Signs.

Neither doth the *Pus* which flows from the reins ſtink ſo ill, as that which is caſt forth of the bladder; the reaſon is, for that the bladder being a bloodleſs, fleſhleſs and membranous part, hath not ſuch power to reſiſt putrefaction. That *Pus* which flows from the kidneys, never

flows without water; and although by long keeping in an urinal, it at length ſubſides or falls to the bottom, and may be ſeen ſeparated; yet when it is firſt made, you may ſee it perfectly mixed with the Urine; but that *Pus* which flows from the bladder is oft-times made alone without urine; and uſually it comes to paſs that the *Pus*, or matter which flows from the ulcerated kidneys, hath in it certain caruncles, or as it were hairs according to the rule of *Hippocrates*. Thoſe who in a thick urine have little caruncles, and, as it were, hairs come forth together therewith, they come from their kidneys; but on the contrary, thoſe who have certain brain-like ſcales come from them in a thick urine, their bladder is ſcabby, or troubled with a ſcabby ulcer.

The cure.

For the cure; it is expedient that the belly be ſoluble either by Nature or Art, and the uſe of mollifying Clyſters. And it is good to vomit ſometimes, ſo to draw back the humors by whoſe conflux into the affected part the ulcer might be fed and made more ſordid and filthy. You muſt beware of ſtrong purgations, leſt the humors being moved and too much agitated, the matter fit to nouriſh the ulcer may fall down upon the kidneys or bladder. The enſuing potion is very effectual to mundifie thoſe kind of ulcers. ℞ *Hordei integri, M.* ij. *Glycyrrhizæ raſ. & contuſ.* ʒ ſs. *Rad. acetoſæ & petroſel. a n.* ʒ vi. *Fiat decoctio ad* ℔ i. *in colatura diſſolve mellis diſtum.* ʒ ij. Let him take every morning the quantity of four ounces. *Gordonius* exceedingly commends the following Trochiſces. ℞ *Quatuor ſem. frig. maj. mundatorum, ſem. papaveris albi, ſem. malvæ, portul. cydon. baccarum myrti, tragacanth. gum. arab. nucum pinearum mund. piſtach. glycyrrhizæ mund. mucilaginis ſem. pſilii, amygd. dulc. hordei mund. an.* ʒ ij. *Bol. armeni. ſang. drac. ſpodii, roſarum, myrrhæ, an.* ʒ ſs. *Exciſi untur hydromelite, & fingantur trochiſci ſinguli ponderis* ʒ ij. Let him take one thereof in the morning diſſolved in Barley-water or Goats-milk. *Galen* bids to mix honey and diuretick things with medicines made for the ulcers of the reins and bladder, for that they gently move urine, and are as vehicles to carry the medicines to the part affected. Ulcers of the bladder are either in the bottom thereof, or at the neck and urinary paſſage. If they be in the bottom, the pain is almoſt continual; if in the neck, the pain then pricks, and is moſt terrible when they make water and preſently after. The ulcer which is in the bottom ſends forth certain ſcaly or skinny excrements together with the urine; but that which is in the neck, cauſes almoſt a continual *Tentigo*. Thoſe which are in the bottom are for the moſt part incurable, both by reaſon of the bloodleſs and nervous nature of the part, as alſo for that the ulcer is continually chafed and troubled by the acrimony of the urine, ſo that it can hardly be cicatrized. For even after making of water ſome reliques of the urine always remain in the bottom of the bladder, which could not therefore paſs forth together with the reſt of the urine, for that for the paſſing forth of the urine, the bladder being diſtended before, falls and is complicated in its ſelf. Ulcers of the bladder are healed with the ſame medicines as thoſe of the reins are; but theſe not only taken by mouth, but alſo injected by the urinary paſſage. Theſe injections may be made of *Gordonius* his Trochiſces formerly preſcribed, being diſſolved in ſome convenient liquor; but becauſe ulcers of the bladder cauſe greater and more ſharp pain than thoſe of the kidneys, therefore the Chirurgeon muſt be more diligent in uſing Anodynes. For this purpoſe, I have often by experience found, that the Oyl of Henbane made by expreſſion, gives certain help. He ſhall do the ſame with Cataplaſms and Liniments applied to the parts about the *Pecten* and all the lower belly with *Perinæum*, as alſo by caſting in of Clyſters. If that they ſtink, it will not be amiſs to make injection of a little *Ægyptiacum* diſſolved in Wine, Plantain or Roſe-water. For I have often uſed this remedy in ſuch a caſe with very proſperous ſucceſs.

Signs to know what part of the bladder is ulcerated.

Why Ulcers in the bottom of the bladder are uncurable.

Ægyptiacum for the ulcers of the bladder.

CHAP. XIX.

Of the Ulcers of the Womb.

The cauſes.

ULcers are bred in the womb, either by the conflux of an acrid, or biting humor, fretting the coats thereof, or by a tumor againſt nature degenerating into an abſceſs, or by a difficult and hard labour; they are known by pain at the *Perinæum*, and the efflux of *Pus* and *Sanies* by the privity. All of them in the opinion of *Avicen*, are either putrid, when as the *Sanies* breaking forth is of a ſtinking ſmell, and in colour reſembles the water wherein fleſh hath been waſhed; or elſe ſordid, when as they flow with many virulent and crude humours; or elſe are eating or ſpreading ulcers, when as they caſt forth black *Sanies*, and have pulſation joyned with much pain. Beſides they differ amongſt themſelves in ſite, for either they poſſeſs the neck and are known by the ſight, by putting in a *ſpeculum*, or elſe are in the bottom, and are manifeſted by the condition of the more liquid and ſerous excrements, and the ſite of the pain. They are cured with the ſame remedies wherewith the ulcers of the mouth, to wit, with *Aqua fortis*, the Oyl of Vitriol and Antimony, and other things made ſomewhat more mild, and corrected with that moderation, that the ulcerated parts of the womb may be ſafely touched with them; it is requiſite that the remedies which are applied to the ulcers of the womb, do in a moment that which is expected of them, for they cannot long adhere or ſtick in the womb, as neither to the mouth. *Galen* ſaith, that very drying medicines are exceeding fit for ulcers of the womb, that ſo the putrefaction may be hindred or reſtrained, whereto this part as being hot and moiſt is very ſubject; beſides that, the whole body, unto this part, as unto a ſink, ſends down its excrements. If an ulcer take hold of the bottom of the womb, it ſhall be cleanſed, and the part alſo ſtrengthened, by making this following Injection. ℞ *Hordei integri p.* ij. *Guajaci* ʒ i. *Rad. Ireos.* ʒ ſs. *Abſinth. plant: centaur. utriuſque, an. M* i. *Fiat decocti. in aqua fabrorum ad* ℔ ij. *in quibus diſſolve mellis roſati, & ſyrupi de abſinthio, an.* ʒ iij. *Fiat injectio.* For amending the ſtinking ſmell, I have often had certain experience of this enſuing remedy. ℞ *vini rub.* ℔ i. *Unguent. ægyptiaci* ʒ ij. *Bulliant. parum.* Thus the putrefaction may be corrected, and the painful maliciouſneſs of the humor abated. Ulcers when they are cleanſed, muſt preſently be cicatrized; that may be done with Alum-water, the water of Plantain

Lib. 3. *ſect.* 12. *tract.* 2. *cap.* 5. Signs.

The cure.

Why ſtrongly drying things are good for Ulcers of the womb.

An Injection for an ulcer in the bottom of the womb.

An Injection hindring putrefaction.

wherein

wherein a little Vitriol or Alum have been diſſolved. Laſtly, if remedies nothing availing, the ulcer turn into a Cancer, it muſt be dreſſed with Anodynes and remedies proper for a Cancer, which you may find ſet down in the proper Treatiſe of Cancers. The cure of ulcers of the fundament was to be joyned to the cure of theſe of the womb; but I have thought good to refer it to the Treatiſe of Fiſtula's, as I do the cure of theſe of the urinary paſſage to the Treatiſe of the *Lues Venerea*.

CHAP. XX.

Of the Varices, *and their cure by cutting.*

A *Varix* is the dilatation of a vein, ſome whiles of one, and that a ſimple branch, other whiles of many. Every *Varix* is either ſtrait or crooked, and as it were infolded into certain windings within its ſelf. Many parts are ſubject to *Varices*; as, the temples, the region of the belly under the navil, the teſticles, womb, fundament, but principally the thighs and legs. The matter of them is uſually melancholy blood, for *Varices* often grow in men of a melancholy temper, and which uſually feed on groſs meats, or ſuch as breed groſs and melancholy humors. Alſo women with child are commonly troubled with them, by reaſon of the heaping together of their ſuppreſſed menſtrual evacuation. The precedent cauſes are a vehement concuſſion of the body, leaping, running, a painful journey on foot, a fall, the carrying of a heavy burthen, torture or racking. This kind of diſeaſe gives manifeſt ſigns thereof by the largeneſs, thickneſs, ſwelling and colour of the veins. It is beſt not to meddle with ſuch as are inveterate; for of ſuch being cured there is to be feared a reflux of the melancholy blood to the noble parts, whence there may be imminent danger of malign ulcers, a Cancer, Madneſs or Suffocation. When as many *Varices* and diverſly implicit are in the legs, they often ſwell with congealed and dried blood, and cauſe pain, which is increaſed by going and compreſſion. Such like *Varices* are to be opened by dividing the vein with a Lancet, and then the blood muſt be preſſed out, and evacuated by preſſing it upwards and downwards; which I have oft-times done, and that with happy ſucceſs to the Patients, whom I have made to reſt for ſome few days, and have applied convenient medicines. A *Varix* is often cut in the inſide of the leg a little below the knee, in which place commonly the original thereof is ſeen. He which goes about to intercept a *Varix* downwards from the firſt original, and as it were fountain thereof, makes the cure far more difficult. For hence it is divided, as it were, into many rivulets, all which the Chirurgeon is forced to follow.

What a *Varix* is, and what be the differences thereof.

The matter.

The cauſes.

Signs.

The cure.

The cutting of *Varices*.

A *Varix* is therefore cut or taken away ſo, to intercept the paſſage of the blood and humours mixed together therewith, flowing to an ulcer ſeated beneath; or elſe leſt that by the too great quantity of blood, the veſſel ſhould be broken, and death be occaſioned by a hæmorrhagie proceeding from thence. Now this is the manner of cutting it. Let the Patient lye upon his back on a bench or table, then make a Ligature upon the leg in two places the diſtance of ſome four fingers each from other, wherein the exciſion may be made, for ſo the vein will ſwell up and come more in ſight; and beſides, you may alſo mark it with ink; then taking the skin up between your fingers, cut it long-ways according as you have marked it; then free the bared vein from the adjacent bodies, and put thereunder a blunt-pointed needle (leſt you prick the vein) thred with a long double thred, and ſo bind it faſt; and then let it be opened with a Lancet in the middle under the Ligature, juſt as you open a vein, and draw as much therehence as ſhall be fit: Then ſtreight make a Ligature in the lower part of the forementioned vein, and then cut away as much of the ſaid vein as is convenient between the Ligatures, and ſo let the ends thereof withdraw themſelves into the fleſh above and below; let theſe Ligatures alone until ſuch time as they fall away of themſelves. The operation being performed, let an aſtringent medicine be applied to the wound and the neighbouring parts; neither muſt you ſtir the wound any more for the ſpace of three days. Then do all other things as are fit to be done to other ſuch affects.

For what intention a *Varix* muſt be cut. *Paulus cap.* 82. *lib.* 6.

The manner how to cut it.

CHAP. XXI.

Of Fiſtula's.

A Fiſtula is a ſinuous, white, narrow, callous, and not ſeldom unperceivable Ulcer: It took its denomination from the ſimilitude of a reeden (Fiſtula) that is, a pipe, like whoſe hollowneſs it is. A Fiſtula is bred in ſundry parts of the body, and commonly follows upon abſceſſes or ulcers not well cured.

What a Fiſtula is.

A *Callous* is a certain fleſhy ſubſtance, white, ſolid, or denſe and hard, dry and without pain, generated by heaping up of dried excrementitious phlegm, or elſe aduſt melancholy encompaſſing the circuit of the ulcer, and ſubſtituting it ſelf in the place of the laudable fleſh. The *Sinus* or cavity of a Fiſtula is ſometimes dry, and other while drops with continual moiſture: Sometimes the dropping of the matter ſuddenly ceaſes, and the orifice thereof is ſhut up, that ſo it may deceive both the Chirurgeon and the Patient with a falſe ſhew of an abſolute cure; for within a while after it will open again, and run as formerly it did. Some Fiſtula's are bred by the corruption of a bone, others of a nerve, others of membranes, and others of other parts of the body. Some run ſtrait in, others, and that the greater part, have turnings and windings; ſome have one, others have more cruches and windings; ſome are at the joynts, others penetrate into ſome capacity of the body, as into the cheſt, belly, guts, womb, bladder; ſome are eaſily, others difficultly cured, and ſome wholly uncurable. There are divers ſigns of Fiſtula's, according to the variety of the parts they poſſeſs; for if that which you touch with the end of your Probe make reſiſtance,

What a *Callous* is.

The differences of Fiſtula's.

The ſigns.

ſiſtance, and reſound, then you may know that it is come to the bone; and then if the end of the Probe ſlip up and down as on a ſmooth and polite ſuperficies, it is a ſign that the bone is yet ſound; but if it ſtop and ſtay in any place as in a rough way, then know the bone is eaten, rough and periſhed; ſometimes the bone lies bare, and then you need not uſe the Probe. Beſides alſo it is a ſign that the bone is affected, if there be a purulent efflux of an unctuous or oily matter, not much unlike that marrow wherewith the bone is nouriſhed. For every excrement ſhews the condition of the nouriſhment of the part whence it is ſent; in a Fiſtula which penetrates to a nerve, the Patient is troubled with a pricking pain, eſpecially when you come to ſearch with a Probe, eſpecially if the matter which flows down be more acrid: Oft-times if it be cold, the member is ſtupified, the motion being weakened; beſides alſo the matter which flows from thence is more ſubtle, and ſomewhat like unto that which flows from the bones, yet not oily nor fat, but ſanious and viſcous, reſembling the condition of the alimentary humour of the nerves. The ſame uſually appears and happens in Fiſtula's which penetrate to the tendons and thoſe membranes which involve the muſcles. If the Fiſtula be within the fleſh, the matter flowing thence is more thick and plentiful, ſmooth, white and equal. If it deſcend into the veins or arteries, the ſame happens as in thoſe of the nerves; but that there is no ſuch great pain in ſearching with your Probe, nor no offence or impediment in the uſe of any member: Yet if the matter of the fiſtulous Ulcer be ſo acrid, as that it corrode the veſſels, blood will flow forth; and that more thick if it be from a vein, but more ſubtle and with ſome murmuring if from an artery. Old Fiſtula's, and ſuch as have run for many years, if ſuddenly ſhut up, cauſe death, eſpecially in an ancient and weak body.

The ſign that the bone is bare from the condition of the matter which is caſt forth.

Actius tetr 4. *ſect.* 2. *cap.* 55.

Old Fiſtula's if cloſed prove mortal.

CHAP. XXII.

Of the cure of Fiſtula's.

FOr the cure; in the firſt place it will be expedient to ſearch the Fiſtula; and that either with a wax ſize, a Probe of Lead, Gold or ſilver to find out the depth and windings or corners thereof. But if the Fiſtula be hollowed with two or more orifices, and thoſe cuniculous, ſo that you cannot poſſibly and certainly ſearch or find them all out with your probe; then muſt you caſt an Injection in ſome one of theſe holes, and ſo obſerve the places where it comes forth, for ſo you may learn how many, and how deep or ſuperficiary cavities there be; then by making inciſions you muſt lay open and cut away the callous parts. You muſt make inciſions with an Inciſion-knife or Razor, or elſe apply actual or potential cauteries; for nature cannot, unleſs the callous ſubſtance be firſt taken away, reſtore or generate fleſh, or agglutinate the diſtant bodies: For hard things cannot grow together, unleſs by the interpoſition of glue, ſuch as is laudable blood; but a callous body on all ſides poſſeſſing the ſurface of the ulcerated fleſh, hinders the flowing of the blood out of the capillary veins, for the reſtoring of the loſt ſubſtance, and uniting of the diſ-joynted parts. If you at any time make cauſtick Injections into the Fiſtula, you muſt preſently ſtop the orifice thereof, that ſo they may have time to work the effect, for which they are intended. Which thing we may conjecture by the tumor of the part, the digeſture of the flowing matter, and its leſſer quantity. Then you muſt haſten the falling away of the Eſchar, and then the Ulcer muſt be dreſſed like other Ulcers. But oft-times the *Callus* which poſſeſſes the ſinuous cavity of a Fiſtula, overcome by the power of acrid and eſcarotick medicines, comes whole forth, and falls out like a pipe, and ſo leaves a pure Ulcer underneath it. Which I obſerved in a certain Gentleman, when I had waſhed with ſtrong *Ægyptiacum* divers times a fiſtulous Ulcer in his thigh, ſhot through with a bullet; then preſently by putting in my Balſam formerly deſcribed, he grew well in a ſhort time. Fiſtula's which are near great veſſels, nerves or principal intrails, muſt not be meddled with unleſs with great caution. When a Fiſtula proceeds by the fault of a corrupt bone, it is to be conſidered whether that fault in your bone be ſuperficiary or deeper in, or whether it is wholly rotten and periſhed: For if the default be ſuperficiary, it may eaſily be taken away with a deſquammatory *Trepan*; but if it penetrate even to the marrow, it muſt be taken forth with cutting mullets, firſt having made way with a *Terebellum*. But if the bone be quite rotten and periſhed, it muſt be wholly taken away, which may be fitly done, in the joynts of the fingers, the *radius* of the cubit and leg; but no ſuch thing may be attempted in the ſocket of the huckle-bone, the head of the thigh-bone, or any of the rack-bones when they are mortified, neither in thoſe Fiſtula's, which are of their own nature incurable; but you ſhall think you have diſcharged your duty and done ſufficiently for the Patient, if you leave it with a prognoſtick. Of this nature are Fiſtula's which penetrate even to the bowels, which come into the parts oreſpread with large veſſels or nerves, which happen to effeminate and tender perſons, who had rather die by much, than to ſuffer the pain and torment of the operation. Like caution muſt be uſed, when by the cutting of a Fiſtula there is fear of greater danger, as of convulſion, if the diſeaſe be in a nervous part. In theſe and the like caſes, the Chirurgeon ſhall not ſet upon the perfect cure of the diſeaſe, but ſhall think it better to prevent, by all means poſſible, that the diſeaſe by freſh ſupplies become no worſe, which may be done, if he prevent the falling down of any new defluxion into the part; if by an artificial diet he have a care that excrementitious humors be not too plentifully generated in the body; or ſo order it, that being generated, they may be evacuated at certain times, or elſe diverted from the more noble to the baſe parts. But in the mean ſpace it ſhall be requiſite to waſte the faulty fleſh, which grows up more than is fitting in the Ulcer, and to cleanſe the *ſordes* or filth, with medicines which may do it without biting or acrimony and putrefaction.

How to find out the windings and cavities of Fiſtula's.

Cauſtick Injections.

Celſus, lib. 5.

Remedies for a Fiſtula proceeding from a corrupt bone.

The cure of what Fiſtula's may be attempted, and which may not.

A palliative cure of a Fiſtula.

CHAP.

CHAP. XXIII.

Of the Fiſtula's in the Fundament.

FIſtula's in the Fundament are bred of the ſame cauſes as other kinds of Fiſtula's are; to wit, of a wound or abſceſs not well cured, or of a hæmorrhoid which is ſuppurated. Such as are occult, may be known by dropping down of the *ſanious* and purulent humor by the fundament, and the pain of the adjacent parts. But ſuch as are manifeſt, by the help of your probe you may find whither they go, and how far they reach. For this purpoſe the Chirurgeon ſhall put his finger into the fundament of the Patient, and then put a leaden Probe into the orifice of the Fiſtula; which if it come to the finger without interpoſition of any *medium*, it is a ſign it penetrates into the capacity of the gut. Beſides alſo, then there flows not only by the fundament, but alſo by the orifice which the malign humour hath opened by its acrimony, much matter, ſome whiles ſanious, and oft-times alſo breeding Worms. Fiſtula's may be judged cuniculous, and running into many turnings and windings, if the Probe do not enter far in, and yet notwithſtanding more matter flows there-hence than Reaſon requires ſhould proceed from ſo ſmall an Ulcer. You may in the orifices of all Fiſtula's, perceive a certain callous wart, which the common Chirurgeons term a Hens-arſe. Many ſymptoms accompany Fiſtula's which are in the fundament, as a *Teneſmus*, ſtrangury and falling down of the fundament. If the Fiſtula muſt be cured by manual operation, let the Patient lye ſo upon his back, that lifting up his legs, his thighs may preſs his belly; then let the Chirurgeon, having his nail pared, put his finger, beſmeared with ſome oyntment, into the Patients fundament; then let him thruſt in at the orifice of the Fiſtula, a thick leaden needle, drawing after it a thread conſiſting of thread and horſe-hairs woven together, and then with his finger taking hold thereof, and ſomewhat crooking it, draw it forth at the fundament, together with the end of the thread: Then let him knit the two ends of the thread with a draw or looſe-knot, that ſo he may ſtraiten them at his pleaſure. But before you bind them, you ſhall draw the thread ſomewhat roughly towards you, as though you meant to ſaw the fleſh therein contained, that you may by this means cut the Fiſtula without any fear of a Hæmorrhage, or flux of blood. It ſometimes happens, that ſuch Fiſtula's penetrate not into the gut; ſo that the finger by interpoſition of ſome callous body, cannot meet with the Needle or Probe. Then it is convenient to put in a hollow iron or ſilver Probe, ſo through the cavity thereof to thruſt a ſharp pointed needle, and that by pricking and cutting may deſtroy the *Callus*; which thing you cannot perform with the formerly deſcribed leaden Probe, which hath a blunt point, unleſs with great pain.

The cauſes.

Signs.

Symptoms.

The art of binding and cutting a Fiſtula of the fundament.

The Deſcription of a hollow ſilver Probe, to be uſed with a Needle, as alſo a leaden Probe.



A *Shews the Needle.*

B *The hollow Probe.*

C *The Needle with the Probe.*

D *The leaden Needle drawing a thread after it.*

The *Callus* being waſted, the Fiſtula ſhall be bound as we formerly mentioned. That which is ſuperficiary needs no binding, only it muſt be cut with a crooked *ſcalprum*, and the *Callus* being conſumed, the reſt of the cure muſt be performed after the manner of other Ulcers. But you muſt note, that if any parcel of the Callous body remain untouch'd by the medicine or Inſtrument, the Fiſtula reviving again, will cauſe a relapſe.

CHAP. XXIV.

Of Hæmorrhoides.

HÆmorrhoides as the word is uſually taken, are Tumors at the extremities of the veins encompaſſing the fundament, cauſed by the defluxion of an humor commonly melancholick, and repreſenting a certain kind of *Varices*. Some of theſe run at an hole being opened, which ſometimes in ſpace of time contracts a *Callus*; others only ſwell, and caſt forth no moiſture; ſome are manifeſt; others lye only hid within. Thoſe which run, commonly caſt forth blood mixed with yellowiſh ſerous moiſture, which ſtimulates the blood to break forth, and by its acrimony

What they are.

Their differences.

acrimony opens the mouths of the veins. But ſuch as do not run, are either like bliſters, ſuch as happen in burns, and by Practicioners are uſually called *Veſicales*, and are cauſed by the defluxion of a phlegmatick and ſerous humor; or elſe repreſent a Grape, whence they are called *Uvales*, generated by the afflux of blood, laudable in quality, but over-abundant in quantity; or elſe they expreſs the manner of a diſeaſe, whence they are termed *Morales*, proceeding from the ſuppreſſion of melancholick blood; or elſe they repreſent Warts, whence they are ſtiled *Verrucales*, enjoying the ſame material cauſe of the generation as the *Morales* do. This affect is cauſe of many accidents in men; for the perpetual efflux of blood extinguiſheth the vivid and lively colour of the face, calls on a Dropſie, overthrows the ſtrength of the whole body. The flux of Hæmorrhoides is commonly every month, ſometimes only four times in a year. Great pain, inflammation, an abſceſs which may at length end in a Fiſtula, unleſs it be reſiſted by convenient remedies, do oft-times fore-run the evacuation of the Hæmorrhoides. But if the Hæmorrhoides flow in a moderate quantity, if the Patients brook it well, they ought not to be ſtayed, for that they free the Patients from the fear of eminent evils, as Melancholy, Leproſie, Strangury, and the like. Beſides, if they be ſtopped without a cauſe. they by their reflux into the lungs cauſe their inflammation, or elſe break the veſſels thereof; and by flowing to the liver, cauſe a Dropſie by the ſuffocation of the native heat; they cauſe a Dropſie and univerſal leanneſs on the contrary, if they flow immoderately, by refrigerating the liver by loſs of too much blood; wherefore when as they flow too immoderately, they muſt be ſtayed with a pledget of Hares-down dipped in the enſuing medicine. ℞ *Pul. aloes, thuris, balauſt. ſang. draconis, an.* ʒ ß. *Incorporentur ſimul cum ovi albumine, fiat medicamentum ad uſum.* When they are ſtretched out and ſwoln without bleeding, it is convenient to beat an Onion roaſted in the embers with an Oxes gall; and apply this medicine to the ſwoln places, and renew it every five hours. This kind of remedy is very prevalent for internal Hæmorrhoides; but ſuch as are manifeſt, may be opened with Horſe-leaches, or a Lancet. The juice or maſs of the Herb called commonly Dead-nettle, or Arch-angel, applied to the ſwoln Hæmorrhoids, opens them, and makes the congealed blood flow there-hence. The *Fungus* and *Thymus*, being diſeaſes about the fundament, are cured by the ſame remedy. If acrimony, heat and pain, do too cruelly afflict the Patient, you muſt make him enter into a bath, and preſently after apply to the Ulcers (if any ſuch be) this following remedy. ℞ *Olei roſ.* ʒ iiij. *Ceruſæ* ʒ i. *Litharg.* ʒ ß. *Ceræ novæ*, ʒ vj. *Opii* ℈ i. *Fiat unguent. ſecundum artem.* Or elſe, ℞ *Thuris, myrrhæ, croci, an.* ʒ i. *Opii* ℈ i. *Fiat unguentum cum oleo roſarum & mucilagine ſem. pſillii, addendo vitellum unius ovi.* You may eaſily proſecute the reſidue of the cure according to the general rules of Art.

Symptomes.

Sent. 37. ſect. 6. epid.

A remedy for the immoderate flowing of the Hæmorrhoides.

For ſuppreſt Hæmorrhoides.

The end of the Thirteenth Book.

BOOK XIV.

Of Bandages, or Ligatures.

CHAP. I.

Of the differences of Bandages.

Lib. de faſciis.

BAndages, wherewith we uſe to bind, do much differ amongſt themſelves: But their differences (in *Galen*'s opinion) are chiefly drawn from ſix things, to wit, their matter, figure, length, breadth, making, and parts whereof they conſiſt. Now the matter of Bandages is threefold; membranous or of skins, which is accommodated peculiarly to the fractured griſles of the noſe; of woollen, proper to inflamed parts, as thoſe which have need of no aſtriction; of linnen, as when any thing is to be faſt bound; and of linnen cloaths, ſome are made of flax, other ſome of hemp, as *Hippocrates* obſerves. But Bandages do thus differ amongſt themſelves in ſtructure, for that ſome thereof conſiſt of that matter which is ſufficiently cloſe and ſtrong of it ſelf, ſuch are the membranous; others are woven, as the linnen ones. But that linnen is to be made choice of for this uſe, and judged the beſt, not which is new and never formerly uſed, but that which hath already been worn, and ſerved for other uſes; that ſo the Bandages made thereof, may be the more ſoft and pliable: Yet muſt they be of ſuch ſtrength, that they may not break with ſtretching, and that they may ſtraitly contain and repel the humor ready to flow down, and ſo hinder it from entring the part. Theſe, beſides, muſt not be hemmed nor ſtitched, muſt have no lace nor ſeam; for hems and ſeams by their hardneſs preſs into, and hurt the fleſh that lies under them. Lace, whether in the midſt or edges of the rowler, makes the Ligature unequal. For the member where it is touched with the lace, as that which will not yield, is preſſed more hard; but with the cloth in the middle more gently, as that which is more lax. Furthermore, theſe Ligatures muſt be of clean cloth, that if occaſion be, they may be moiſtened or ſteeped in liquor appropriate to the diſeaſe, and that they may not corrupt, or make worſe that liquor by their moiſtening therein. Now the Bandages which are made of of linnen clothes muſt be cut long-ways, and not athwart, for ſo they will keep more firm and ſtrong that which they bind, and beſides, they will be always alike, and not broader in one place than in another: But they thus differ in figure, for that ſome of them are rolled up, to which nothing muſt be ſowed, for that they ought to be of a due length to bind up the member; others are cut or divided, which truly conſiſt of one piece, but that divided in the end (ſuch are uſually taken to bind up the breaſts)

Sect. 3. de Chir. offic.

What doth beſt for rowlers.

or

or else in the midst; others are sowed together, which consist of many branches sowed together, and ending in divers heads, and representing divers figures, such are the Bandages appropriated to the head. But they thus differ in length, for that some of them are shorter, others longer: so in like sort for breadth; for some are broader, others narrower. Yet we cannot certainly define nor set down, neither the length nor breadth of rowlers, for that they must be various, according to the different length and thickness of the members or parts. Generally they ought both in length and breadth to fit the parts, whereunto they are used. For these parts require a binding different each from other, the head, the neck, shoulders, arms, breasts, groins, testicles, fundament, hips, thighs, legs, feet and toes. For the parts of Bandages, we term one part their body, another their heads. By the body we mean their due length and breadth; but their ends, whether they run long-ways or a-cross, we according to *Galen*, term them their heads. *Com. ad sect. 22. sect. 2. de offic. chir.*

CHAP. II.

Sheweth the Indications and general Precepts of fitting Bandages and Ligatures.

THere are, in *Hippocrates* opinion, two Indications of fitting Bandages or Ligatures; the one whereof is taken from the part affected; the other from the affect it self. From the part affected: So the leg, if you at any time bind it up, must be bound long-ways, for if you bind it over-thwart, the binding will loosen as soon as the Patient begins to go, and put forth his leg, for then the muscles take upon them another figure. On the contrary, the arm or elbow must be bound up, bending in and turned to the breast; for otherwise at the first bending, if it be bound when it it is stretched forth, the Ligature will be slacked, for that (as we formerly said) the figure of the muscles is perverted. Now for this Indication, let each one perswade himself thus much, that the part must be bound up in that figure, wherein we would have it remain. *1 & 2 sect. lib. de fract.*

Now for that Indication which is drawn from the disease, if there be a hollow Ulcer, sinuous and cuniculous, casting forth great store of *Sanies*; then must you begin the ligature and binding from the bottom of the *sinus*, and end at the orifice of the Ulcer; and this Precept must you always observe, whether the *sinus* be seated in the top, bottom, middle, or sides of the Ulcer: For thus the filth therein contained shall be emptied and cast forth, and the lips of the Ulcer too far separated, shall be joyned together; otherwise the contained filth will eat into all that lies near it, increase the Ulcer, and make it uncurable, by rotting the bones which lie under it within this acrid *Sanies* or filth. But some Ligatures are remedies of themselves; as those which perform their duties of themselves, and whereto the cure is committed; as are these which restore to their native unity, those parts which are disjoyned: Others are not used for their own sakes, but only to serve to hold fast such medicines as haye a curative faculty. This kind of Ligature is either yet a doing, and is termed by *Hippocrates*, *Diligatio operans*; or else done and finished, and is called *Diligatio operata:* For the first, that the Ligature may be well made, it is fit that it be close rowled together; and besides, that the Surgeon hold it stiff and strait in his hand, and not carelesly; for so he shall bind up the member the better. Also he must in the binding observe, that the ends of the rowler, and consequently their fastning, may not fall to be on the affected or grieved part; for it is better that they come above or below, or else on the side: Besides also, he must have a special care, that there be no knot tied upon the same place, or upon the region of the back, buttocks, sides, joynt, or back-part of the head, or to conclude, in any other part upon which the Patient uses to lean, rest or lie. Also on that part where we intend to sow or fasten the rowlers, you must double in their ends, that so the fastning or suture may be the stronger, otherwise how close soever they shall be wrapped or rowled about the member, yet will they not remain firm, especially if they be of a great breadth. For the second kind of Ligature, to wit, that which is already done and finished; the Surgeon, the performer thereof, must consider to what end it was done, and whether he hath performed it well and fitly, as also neatly and elegantly, to the satisfaction both of himself and the beholders. For it is the part of a skilful workman every where handsomely and rightly to perform that which may so be done.

We must always begin our ligatures at the bottom of a *sinus*.

Hip. cent. 4. sect. 2. offic. Initio 2 sect. off.

Ligatures must not be only lightly, but also neatly performed.

In fractures, and luxations, and all dislocations of bones, as also in wounds and contusions, you must begin your Bandage with two or three windings, or wraps about upon the place, and that (if you can) more straitly than in other places, that so the set bones may be the better kept in their places, and that the humors, if any be already fallen thither, may by this strait compression be pressed forth; as also to hinder and prevent the entrance in of any other, which may be ready to fall down. But in fractures (as those which never happen without contusion) the blood flows, and is pressed forth of its proper vessels; as those which are violently battered and torn, which causes sugillation in the neighbouring flesh, which first looks red, but afterwards black and blue, by reason of the corruption of the blood poured forth under the skin. Wherefore after these first windings, which I formerly mentioned, you must continue your rowling a great way from the broken or luxated part; he which does otherwise, will more and more draw the blood and humors into the affected part, and cause imposthumes, and other malign accidents. Now the blood which flows, goes but one way downwards, but that which is pressed, is carried as it were in two paths, to wit, from above downwards, and from below upwards. Yet you must have a care that you rather drive it back into the body and bowels, then towards the extremities thereof, as being parts which are uncapable of so much matter, and not furnished with sufficient strength to suffer that burthen, which threatens to fall upon it, without danger, and the increase of preternatural accidents. But when this mass and burthen of humors is thrust back into the body, it is then ruled and kept from doing harm by the strength and benefit of the faculties remaining in the bowels, and the native heat. *Gal. com. ad sent. 25. sect. 1. lib. de fract.*

CHAP.

CHAP. XXIV.

Of the three kinds of Bandages neceſſary in Fractures.

Sent. 24. ſect. 2. offic. TWo ſorts of Ligatures are principally neceſſary for the Surgeon, according to *Hippocrates*, by which the bones as well broken as diſlocated may be held firm when they are reſtored to their natural place.

Hypodeſmides. Of theſe, ſome are called *Hypodeſmides*, that is, Under-binders; others, *Epideſmi*, that is, Over-binders. There are ſometimes but two Under-binders uſed, but more commonly three. The firſt muſt firſt of all be caſt over the Fracture, and wrapped there ſome three or four times about, then the Surgeon muſt mark and obſerve the figure of the Fracture; for as that ſhall be, ſo muſt he vary the manner of his binding: For the Ligature muſt be drawn ſtrait upon the ſide oppoſite to that whereto the Luxation or Fracture moſt inclines; that ſo the bone which ſtands forth may be forced into its ſeat, and ſo forced, may be the more firmly there contained. Therefore, if the right ſide be the more prominent or ſtanding forth, thence muſt you begin your ligation, and ſo draw your Ligature to the left ſide. On the contrary, if the left ſide be more prominent, beginning there, you ſhall go towards the oppoſite ſide in binding and rowling it. Here therefore would I require a Surgeon to be *Ambidexter*, (i.e.) having both his hands at command, that ſo he may the more exquiſitely perform ſuch variety of ligations: But let him in rowling, bend or move this firſt Ligature upwards, that is, towards the body, for the former reaſons. But neither is this manner of ligation peculiar to Fractures, but common to them with luxations: For, into what part ſoever the luxated bone flew, then when it is reſtored, that ſide muſt be bound the more looſly and gently whence it departed, and that on the contrary more hard unto which it went: Therefore the Ligature muſt be drawn from the ſide whereunto the bone went; ſo that on this ſide it be more looſe and ſoft, and not ſtraitly preſſed with boulſters or rowlers, that ſo it may be more inclined to the ſide oppoſite to the luxation. If the ligation be otherwiſe performed, it ſucceeds not well; for the part is relaxed and moved out of its natural ſeat: Wherefore there will be no ſmall danger, leſt the bone be forced out again, and removed from its place, whereinto it was reſtored by art and the hand: Which thing *Hippocrates* ſo much feared, that on the contrary he willed that the ſet-bone ſhould be drawn ſomewhat more unto the part contrary to that whereunto it was driven by force, than the natural and proper ſite thereof ſhould require. But to return to our former diſcourſe of the three Ligatures: The firſt Under-binder being put on, we then take the ſecond, with which we in like ſort begin at the Fracture; but having wrapped it once or twice about there, for that, as we formerly ſaid, we muſt not force back, and preſs ſo much blood towards the extremities, as we muſt do towards the body and bowels: Wherefore this Ligature ſhall be drawn from above downwards, gently ſtraining it to preſs forth the blood contained in the wounded part: When by rowling you ſhall come to the end of the part, then you ſhall carry back again that which remains thereof, to wit, upwards: But otherwiſe you may take the third Under-binder, wherewith you may begin to rowl, whereas you left with the ſecond, and you may carry it thus, rowling it from below upwards. Theſe Under-bindings thus finiſhed, apply your boulſters, after them your over or Upper-bindings, which are oft-times two, but ſometimes three. The firſt hath two heads, and is wrapped both from the right hand and the left, for the preſervation of the firſt Under-binder and the boulſters, and reſtoring the muſcles to their native figure. The two other which remain, conſiſt of one head, and the one of them muſt be rowled from below upwards, the other from above downwards, after ſuch a manner, that they may be directly contrary to the Under-binders: as if they were rowled from the right hand, then theſe muſt be from the left. Now this is the manner of *Hippocrates* his Ligation, which, for that it is now grown out of uſe, we muſt here ſet down that which is in common uſe. They do not at this time uſe any Over-binders, but that which we termed the third Under-binder, ſerves our Surgeons inſtead of the three fore-mentioned Over-binders. Wherefore they carry this third Under-binder, wrapped from below upwards (as we formerly ſaid) contrary to the firſt and ſecond Under-binder; as if theſe begun on the right ſide, this ſhall be rowled from the left, and ſhall end whereas the firſt Under-binder ended. And you muſt not only draw it indifferently hard, but alſo make the ſpires and windings more rare. This third rowler is of this uſe in this manner of ligation; that is, it reſtores the muſcles to their native figure, from whence they were ſomewhat altered by the drawing and rowling of the two former Ligatures. But you muſt always have regard, that you obſerve that meaſure in wrapping your Ligature, which Reaſon, with the ſenſe of the Patient, and eaſe in ſuffering, preſcribes; having regard, that the tumor become not inflamed. Alſo the habit of the body ought to preſcribe a meaſure in ligation; for tender bodies cannot away with ſo hard binding as hard. Verily, in Fractures and Luxations, the humors by too ſtrait binding are preſſed into the extreme parts of the body; whence grievous and oft-times enormous Oedema's proceed; for healing whereof the Ligature muſt be looſed, and then the tumified parts preſſed by a new rowling, which muſt be performed from below upwards, and ſo, by forcing the matter of the tumor thither, it may be helped; for there is no other hope or way to drive the humor back again. He which doth this, forſakes the proper cure of the diſeaſe, ſo to reſiſt the ſymptom, which the Surgeon ſhall never refuſe to do, as often as any neceſſary cauſe ſhall require it. For this cauſe *Hippocrates* bids, that the Bandages be looſed every three days, and then to foment the part with hot water, that ſo the humors, which (drawn thither by the vehemency of pain) have ſettled in the part, may be diſſolved and diſperſed; and itching and other ſuch like ſymptoms prevented. The fear of all accidents being paſt, let the ligation be ſooner or later looſed, and more ſlacked than it formerly was accuſtomed; that ſo the blood and laudable matter, whereof a *Calus* may enſue, may flow more freely to the affected part.

When the third Under-binder is neceſſary.

Epideſmi.

The manner of binding now in uſe.

What mean to be obſerved in wrapping the Ligatures.

Why *Hippoc.* bids to looſe the Ligatures every third day.

CHAP.

CHAP. IV.

Of the binding up of Fractures aſſociated with a Wound.

How to bind up a fracture with a wound.

IT ſometimes happens that a fracture is aſſociated by a wound, and yet for all this it is fit to bind the part with a ligature; otherwiſe there will be no ſmall danger of ſwelling, inflammation, and other ill accidents, by reaſon of the too plentiful afflux of humors from the neighbouring parts. But it is not fit to endeavour to uſe that kind of binding which is performed with many circumvolutions or wrappings about. For ſeeing the wound muſt be dreſſed every day, the part muſt each day neceſſarily be ſtirred, and the ligature conſiſting of ſo many windings, looſed; which thing will cauſe pain, and conſequently hinder the knitting and uniting, which is performed by reſt: Therefore this kind of binding may be performed by one only rowling about the wound, and that with a rowler which conſiſts of a twice or thrice doubled cloth, made in manner of a boulſter, and ſewed with as much conveniency as you can, that it may be ſo large as to encompaſs and cover all the wound, for theſe reaſons which ſhall be delivered at large in our Treatiſe of Fractures. But if the wound run long-ways, let the boulſters and ſplints be applied to the ſides of the wound, that ſo the lips of the wound may be preſſed together, and the contained filth preſſed forth. But if it be made overthwart, we muſt abſtain from boulſters and ſplints: For that in *Galen*'s opinion, they would dilate the wound, and the purulent matter would be preſſed out, and caſt back into the wound.

Ad ſent. 12. ſect. de fract.

CHAP. V.

Certain common Precepts of the binding up of Fractures and Luxations.

IN every Fracture and Luxation, the depreſſed, hollow and extenuated parts, ſuch as are near unto the joynts, ought to be filled up with boulſters, or clothes put about them, ſo to make the part equal, that ſo they may be equally and on every ſide preſſed by the ſplints, and the bones more firmly contained in their ſeats. So when the knee is bound up, you muſt fill the ham or that cavity which is there, that ſo the ligation may be the better and ſpeedilier performed. The ſame muſt be done under the arm-pits, above the heel, in the arm near the wriſt; and to conclude, in all other parts which have a conſpicuous inequality by reaſon of ſome manifeſt cavity. When you have finiſhed your binding, then enquire of the Patient, whether the member ſeem not to be bound too ſtrait. For if he ſay that he is unable to endure it ſo hard bound, then muſt the binding be ſomewhat ſlackned. For, too ſtrait binding cauſes pain, heat, defluxion, a gangrene, and laſtly, a ſphacel or mortification: But too looſe is unprofitable, for that it doth not contain the parts in that ſtate we deſire. It is a ſign of a juſt ligation that is neither too ſtrait nor too looſe, if the enſuing day the part be ſwoln with an œdematous tumor, cauſed by the blood preſſed forth of the broken place; but of too ſtrait ligation, if the part be hard ſwoln; and of too looſe, if it be no whit ſwollen, as that which hath preſſed no blood out of the affected part. Now if a hard tumor, cauſed by too ſtrait binding, trouble the Patient, it muſt preſently be looſed for fear of more grievous ſymptoms, and the part muſt be fomented with warm *Hydræleum*, and another indifferent, yea verily, more looſe ligature muſt be made inſtead thereof, as long as the pain and inflammation ſhall continue; in which time, and for which cauſe, you ſhall lay nothing upon the part which is any thing burthenſome. When the Patient begins to recover, for three or four days ſpace, eſpecially if you find him of a more compact habit and a ſtrong man, the ligature muſt be kept firm and not looſed. If on the third day, and ſo until the ſeventh, the ſpires or windings be found more looſe, and the part affected more ſlender, then we muſt judge it to be for the better. For hence you may gather, that there is an expreſſion and digeſtion of the humors, cauſing the tumor made by force of the ligation. Verily, broken bones fitly bound up, are better ſet, and more firmly agglutinated, which is the cauſe, why in the place of the fracture, the ligation muſt be made the ſtraiter, in other places more looſly. If the fractured bone ſtand forth in any part, it muſt there be more ſtraitly preſſed with boulſters and ſplints. To conclude, the ſeventh day being paſt, we muſt bind the part more ſtraitly than before: For that then inflammation, pain, and the like accidents are not to be feared. But theſe things which we have hitherto ſpoken, of the three kinds of Ligatures, cannot take place in each fractured part of the body, as in the chaps, collar-bones, head, noſe, ribs: For, ſeeing ſuch parts are not round and long, a ligature cannot be wrapped about them, as it may on the arms, thighs and legs, but only be put on their outſides.

Hipp. ſent. 37. & 38. ſect. 1. de fract.

The ſigns of too ſtrait and looſe binding up.

Why we muſt make more ſtrait ligation on the broken part.

CHAP. VI.

The uſes for which Ligatures ſerve.

BY that which we have formerly delivered, you may underſtand that ligatures are of uſe to reſtore thoſe things which are ſeparated and moved forth of their places, and joyn together thoſe which gape; as in fractures, wounds, contuſions, ſinewous ulcers, and other like affects againſt Nature, in which the ſolution of continuity ſtands in need of the help of Bandages, for the reparation thereof. Beſides alſo, by the help of Bandages theſe things are kept aſunder or ſeparated, which otherwiſe would grow togethrr againſt Nature; as in burns, wherein the fingers and the hams would mutually grow together; as alſo the arm-pits to the cheſt, the chin to the breaſt, unleſs they be hindred by due ligation. Bandages do alſo conduce to refreſh emaciated

The firſt benefit of ligatures

The ſecond.

The third.

part: Wherefore if the right leg waſte for want of nouriſhment, the left leg, beginning at the foot, may be conveniently rowled up even to the groin. If the right arm conſume, bind the left with a ſtrait Ligature, beginning at the hand, and ending at the arm-pit. For thus a great portion of blood from the bound-up part is ſent back into the *Vena cava*, from whence it regurgitates into the almoſt empty veſſels of the emaciated part. But I would have the ſound part to be ſo bound, that thereby it become not painful; for a dolorifick ligation cauſes a greater attractation of blood and ſpirits, as alſo exerciſe: Wherefore I would have it during that time to be at reſt, and keep Holy-day.

The fourth. Ligatures alſo conduce to the ſtopping of bleedings: Which you may perceive by this, that when you open a vein with your lancet, the blood is preſently ſtayed, laying on a boulſter,

The fifth. and making a ligature. Alſo ligatures, are uſeful for women preſently after their delivery for their womb being bound about with ligatures, the blood wherewith their womb was too much moiſtened, is expelled, the ſtrength of the expulſive faculty being by this means ſtirred up to the expulſion thereof: And it alſo hinders the empty womb from being ſwoln up with wind, which

The ſixth. otherwiſe would preſently enter thereinto. This ſame ligature is a help to ſuch are with child, for the more eaſie carrying of their burthen; eſpecially thoſe whoſe child lies ſo far downwards, that lying, as it were, in the den of the hips, it hangs between the thighs, and ſo hinders the free going of the mother. Therefore the woman with child is not only eaſed by this binding of her womb with this ligature, which is commonly termed, the Navil-ligature; but alſo, her child be-

The ſeventh. ing held up higher in her womb, ſhe hath freer and more liberty to walk. Ligatures are in like ſort good for revulſion and derivation; as alſo for holding of medicines which are laid to a part, as the

The eighth, the particular uſe of ligatures in the amputation of members. neck, breaſt or belly. Laſtly, there is a triple uſe of ligatures in amputation of members, as arms and legs. The firſt to draw and hold upwards the skin and muſcles lying under it, that the operation being performed, they may, by their falling down again, cover the ends of the cut-off bones; and ſo by that means help forwards the agglutination and cicatrization; and when it is healed up, cauſe the lame member to move more freely, and with leſs pain; and alſo to perform the former actions, this, as it were, cuſhion or boulſter of muſculous fleſh lying thereunder. The ſecond is, they hinder the bleeding by preſſing together the veins and arteries. The third is, they by ſtrait binding intercept the free paſſage of the animal ſpirits, and ſo deprive the part which lyes thereunder of the ſenſe of feeling, by making it, as were, ſtupid or num.

CHAP. VII.

Of Boulſters or Compreſſes.

The firſt uſe of Boulſters. BOulſters have a double uſe, the firſt is to fill up the cavities and thoſe parts which are not of an equal thickneſs to their end. We have examples of cavities in the arm-pits, clavicles, hams and groins; and of parts which grow ſmall towards their ends, in the arms towards the wriſts, in the legs towards the feet, in the thighs towards the knees. Therefore you muſt fill theſe parts with boulſters and linnen clothes, that ſo they may be all of one bigneſs to their ends.

The ſecond uſe of them. The ſecond uſe of Boulſters, is to defend and preſerve the firſt two or three rowlers or underbinders, the which we ſaid before muſt be applied immediately to the fractured part. Boulſters, according to this twofold uſe, differ amongſt themſelves, for that when they are uſed in the firſt mentioned kind, they muſt be applied athwart; but when in the latter, long-ways or down-right.

The third uſe of them. You may alſo uſe Boulſters, leſt the too ſtrait binding of the ligatures cauſe pain and trouble to the new-ſet bones. A three or four times doubled cloth will ſerve for the thickneſs of your boulſters, but the length and breadth muſt be more or leſs, according to the condition of the parts and diſeaſe for which they muſt be applied.

CHAP. VIII.

Of the uſe of Splints, Junks and Caſes.

The matter of Splints. HAving delivered the uſes of ligatures and boulſters, it remains that we ſay ſomewhat of the other things, which ſerve to hold the bones in their places; as Splints, Junks, Caſes, and ſuch other like. Splints are made and compoſed of paſt-board, of thin ſplinters of wood, of leather, ſuch as ſhooe-ſoals are made with; of the rinds of trees, or plates of lattin, or lead, and ſuch other like, which have a gentle and yielding ſtiffneſs; yet would I have them made as light as may be, leſt they by their weight become troubleſome to the affected part. But for their length, breadth and number, let them be fitted, agreeable to the part whereto they muſt be uſed. Let alſo their figure be ſtrait or crooked according to the condition of the member whereto they muſt be applied. You muſt have a ſpecial care, that they run not ſo far as the ſwellings out, or eminencies of the bones; as the ankles, knees, elbows, and the like, leſt they hurt them by their preſſure: alſo you muſt have a care, that they be ſmaller at their ends, and

Their uſe. thicker in their middles, whereas they lye upon the broken bone. The uſe of Splints is, to hold faſt and firm, that they may ſtir no way the broken and luxated bones, after they be ſet and reſtored to their places. That they perform this uſe, it is fit there be no thick boulſters under them, nor over-many rowlers, for ſo through ſo thick a ſpace, they would not ſo ſtraitly preſs the part.

What Junks are. Junks are made of ſticks, the bigneſs of ones finger, wrapped about with ruſhes, and then with linnen cloth: They are principally uſed in fractures of the thighs and legs.

The matter and uſe of Caſes. Caſes are made of plates of lattin, or elſe ſome light wood; their uſe is, to contain the bones in their due figure, when the Patient is to be carried out of one bed or chamber into another, or elſe hath need to go to ſtool: Laſtly, if we muſt reſt ſomewhat more ſtrongly upon the broken or luxated members,

theſe

theſe caſes will hinder the bones from ſtirring or flying out on the right ſide or left, above or below, we ſleeping or waking, being willing or unwilling; and in like ſort left being not as yet well knit, or more looſly bound up for fear of Pain, Inflammation, or a Gangrene, they hang down, fall, or fly in ſunder by reaſon of the inequalities of the bed. Such Caſes, Junks, and the like, which ſerve for reſtoring and faſt holding of broken and luxated bones, we may, according to *Hippocrates* his mind, call them in general *Gloſſocomia*. All which things, the young Surgeon, which is not as yet exerciſed in the works of Art, can ſcarce tell what they are. But in the mean time, whilſt that he may come to be exerciſed therein, or ſee others perform theſe operations, I, as plainly as poſſibly I could, have in words given him their portraiture or ſhape.

Gloſſocomium, a general name for ſuch things.

The End of the Fourteenth Book.

BOOK XV.

Of Fractures.

CHAP. I.

What a Fracture is, and what the differences thereof are.

A Fracture, in *Galen*'s opinion, is the ſolution of continuity in a bone, which by the Greeks is called *Catagma*. There are many ſorts of hurting or offending the bones; as, the drawing them aſunder, luxation, or putting them out of joynt; their unnatural growing together, their cutting or dividing aſunder; contuſion, abſceſs, putrefaction, rottenneſs, laying bare the *Periſteum*, being violated or loſt; and laſtly, that whereof we now treat, a Fracture. Again, the varieties of Fractures are almoſt infinite. For one is complete and perfect, another imperfect; one runs long-wiſe, another tranſverſe, another oblique; one while it is broken into great pieces, another while into little and ſmall ſcales, which have either a blunt, or elſe a ſharp end, and prick the adjacent bodies of the muſcles, nerves, veins or arteries. It ſometimes happens, that the bone is not broken into ſplinters, that is, long-ways, but together, and at once into two pieces overthwart, which Fracture is called *Raphanedon*, that is, after the manner of a Radiſh. *Lib. 6. method.* What it is for a bone to be broken *Raphanedon.*

A Fracture is made *Caryedon*, or like a nut, when as the bone flies into many ſmall pieces, ſevered each from other, as when a nut is broken with a hammer, or mallet, upon an Anvile: Which fracture is alſo termed *Alphitidon*, by reaſon of the reſemblance it hath to meal or flour; and ſuch is often ſeen in fractures made by bullets, ſhot out of Guns and ſuch fiery Engines. Contrary to theſe are thoſe fractures which are called *Schidacidon*, as rent into ſplinters, or after the manner of a board or piece of timber, that is, right-down, and alongſt the bone: And theſe fractures either are apparent to the eye, or elſe not apparent, and therefore called Capillary, being ſo ſmall, as that they cannot be perceived by the eye, unleſs you put ink upon them, and then ſhave them with your Scrapers. Sometimes the bone is only preſſed down with the ſtroke; ſometimes on the contrary it flies up, as if it were vaulted. They call it Attrition, when the bone is broken into many ſmall fragments, and, as it were ſcales or chips. The fragments of fractured bones are ſometimes ſmooth and poliſhed, otherwhiles unequal, and, as it were ſharp and rough with little teeth or pricks. Some fractures touch only the ſurface of the bone, fetching off only a ſcale: otherſome change not the ſite of fractured bones, but only cleaves them length-ways, without the plucking away of any fragment; otherſome penetrate even to their marrow. Furthermore, ſome fractures are ſimple and alone by themſelves; otherſome are accompanied with a troop of other affects and ſymptoms, as a Wound, Hæmorrhagy, Inflammation, Gangrene, and the like. Hereunto you may alſo add the differences drawn from the parts which the fractures poſſeſs; as from the head, ribs, limbs, joynts, and other members of the body. Add alſo theſe which are taken from the habit of bodies, aged, young, full of ill humours, well tempered; almoſt all which have their proper and peculiar indications for curing. Now the cauſes of fractures, are the too violent aſſaults or ſtrokes of all external things, which may cut, bruiſe, break or ſhake: In this number of cauſes may alſo be reckoned, falls from high places, and infinite other things, which would be long and tedious to reckon up. What *Caryedon*, or *Alphitidon*. What *Schidacidon*. The cauſes of fractures.

CHAP. II.

Of the ſigns of a Fracture.

We may know by evident ſigns that a bone is broken: The firſt whereof and moſt certain, is, when by handling the part which we ſuſpect to be broken, we feel pieces of the bone ſevered aſunder, and hear a certain crackling of theſe pieces under our hands, cauſed by the attrition of the ſhattered bones. Another ſign is taken from the impotency of the part, which chiefly bewrays it ſelf, when both the bones, the leg, and brace-bones, the ell and wand are broken: For if only the brace-bone or wand be broken, the Patient may go on his leg, and ſtir his arm; for the brace-bone ſerves for the ſuſtaining of the muſcles, and not of the body, as the leg-bone doth. The third ſign is drawn from the figure of the part changed beſides Nature: For it it is there hollow, from whence the bone is flown or gone. but gibbous or bunching out whi- The firſt ſign of a broken bone. Another. A third.

ther it is run. Great pain in the interim torments the Patient by reason of the wronged *Periosteum*, and that membrane which involves the marrow and the sympathy of the adjacent parts, which are compressed or pricked.

CHAP. III.

Of Prognosticks to be made in Fractures.

WE must prognosticate in fractures whether they are to end in the destruction or welfare of the Patient; or whether their cure shall be long or short, easie, or else difficult and dangerous; and lastly, what accidents and symptoms may happen thereupon. He shall easily attain to the knowledge of all these things, who is not only well seen in the anatomical description of the bones, but also in the temper, composition and complexion of the whole body. Wherefore in the first place, I think good to admonish the Surgeon of this, that in Winter when all is stiff with cold, by a little fall, or some such sleight occasion, the bones may be quickly and readily broken. For then the bones, being dried, by the driness of the air encompassing us, become more brittle; which every one of the vulgar usually observe to happen both in waxen and tallow-candles: But when the Season is moist, the bones are also more moist, and therefore more flexible and yielding to the violence of the obvious and offending body. Wherefore also you may gather this to the framing of your Prognosticks, That bones by reason of their natural driness are not so easily agglutinated and consolidated as flesh; though in children, according to *Galen*, by reason of the abundance of their humidity, the lost substance may be repaired, according (as they term it) to the first intention, that is, by restoring of the same kind of substance or matter. But in others, about the fractures, a certain hard substance usually concretes, of that nourishment of the broken bone which abounds, which glues together the fragments thereof, being fitly put together. This substance is then termed a *Callus*, and it is so hardned in time, that the bone thereafter in the broken part is seen to be more firm and hard than it is in any other; therefore that usual saying in Physick is not without reason, That rest is necessary for the uniting of broken bones. For the *Callus* is easily dissolved, if they be moved before their perfect and solid agglutination. The matter of a *Callus* ought to be indifferent and laudable in quantity and quality, even as blood which flows for the regeneration of the lost flesh in wounds. It is fit, that there may be sufficient matter for such a *Callus*, that the part have a laudable temper, otherwise there either will be no *Callus*, or certainly it will grow more slowly. Fractures are far more easily repaired in young bodies than in old: For in these there is plenty of the primigenious and radical moisture, that is laudably holding and glutinous, and in the other there is store of waterish and excrementitious humours. By this you may easily conjecture, that you cannot certainly set down a time necessary for the generating a *Callus*: For in some it happens later, in some sooner; the cause of which variety is also to be referred to the constitution of the Year and Region, the temper and diet of the Patient, and manner of ligation: For, those Patients whose powers are weak, and blood waterish and thin, in these the generation of a *Callus* uses to be more slow: On the contrary, strong powers hasten to agglutinate the bones, if there be plenty of gross and viscous matter; whereby it comes to pass, that meats of grosser nutriment are to be used, and medicines applied which may help forwards the endeavour of Nature, as we shall declare hereafter. When the bones are broken near unto the joynts, the motion afterwards uses to be more difficult, especially if the *Callus*, which is substituted, be somewhat thick and bunching forth. But if, together with the violence and force of the fracture, the joynts shall be broken and bruised, the motion will not only be lost, but the life brought in danger, by reason of the greatness of the Inflammation, which usually happens in such affects, and the excess of pain in a tendinous body. These fractures wherein both the bones of the arm or leg are broken, are more difficult to cure, than those which happen but to one of them: For they are handled and kept in their places with more difficulty, because that which remains whole, serves the other for a rest or stay to which it may lean. Moreover, there is longer time required to substitute a *Callus* to a great bone, than to a little one. Again, these bones which are more rare and spongy, are sooner glued together by the interposition of a *Callus*, than those which are dense and solid. A *Callus* sooner grows in sanguin, than in cholerick bodies: But broken bones cannot be so happily agglutinated, nor restored in any body, but that always some asperity or unequal protuberancy may be seen on that part where the *Callus* is generated: Wherefore the Surgeon ought to make artificial ligations, that the *Callus* may not stand out too far, nor sink down too low. That fracture is least troublesome which is simple; on the contrary, that is more troublesome which is made into splinters; but that is most troublesome and worst of all, which is in small and sharp fragments, because there is a danger of Convulsion by pricking a nerve, or the *Periosteum*. Sometimes the fragment of a broken bone keep themselves in their due place: They also oft-times fly forth thereof, so that one of them gets above another; which when it happens, you may perceive an inequality by the depression of the one part, and the bunching forth of the other, as also pain by the pricking: Besides also, the member is made shorter than it was, and than the sound member on the opposite side is, and more swoln by the contraction of the muscles towards their original. Wherefore when a bone is broken, if you perceive any thing so depressed, presently putting your hand on both sides above and below, stretch forth the bone as forcibly as you can; for otherwise, the muscles and nerves, stretched and contracted, will never of their own accord suffer the bones to be restored to their proper seat of themselves. This extension must be performed in the first days, for afterwards there will happen inflammation: Which being present, it is dangerous to draw the nerves and tendons

too

Why bones are more brittle in frosty weather.

Why the solution of continuity in bones is not so easily repaired. *Gal. in arte par.*

Why bones sooner knit in young bodies.

Meats of gross and tough nourishment conduce to the generation of a *Callus*.

Fractures at joynts dangerous.

Hip. sect. 18. & 19. *sect.* 1. *de fracturis.*

Ligations conduce to the handsomness of a *Callus*.

Extention must presently be made after the bone is broken.

too violently; for hence would enſue an Impoſthume, Convulſion, Gangrene and Mortification. Therefore *Hippocrates* forbids you to defer ſuch extenſion until the third or fourth day. Fractures are thought dangerous, whoſe fragments are great, and fly out, eſpecially in theſe bones which are filled with marrow on the inſide. When broken or diſlocated bones cannot be reſtored to themſelves and their natural place, the part waſtes for want of nouriſhment; both for that the natural ſite of the veins, arteries and nerves, is perverted, as alſo becauſe the part it ſelf lies immovable, or ſcarce moveable: Whereby it cometh to paſs, that the ſpirits do not freely flow thereto, as neither the nutritive juice cometh thither in ſufficient plenty. When the diſlocated or broken member is troubled with any great inflammation, it is doubtful whether or no a Convulſion will happen, if we attempt to reſtore it, or the parts thereof to their ſeat: Therefore it is better, if it may be done, to defer the reducing thereof ſo long, until the humour which poſſeſſes the part be diſſolved, the tumor abated, and the bitterneſs of pain mitigated.

Sent. 36. ſect. 3. de fract.

In inflammations, the reſtoring of the bone muſt not be attempted.

CHAP. IV.

The general cure of broken and diſlocated Bones.

TO cure a broken and diſlocated bone, is to reſtore it to its former figure and ſite: For the performance whereof, the Surgeon muſt propoſe three things to himſelf: The firſt is, to reſtore the bone to its place: The ſecond is, that he contain or ſtay it being ſo reſtored: The third is, that he hinder the increaſe of malign ſymptoms and accidents; or elſe if they do happen, that then he temper and correct their preſent malignity: Such accidents are pain, inflammation, a feaver, abſceſs, gangrene and ſphacel. For the firſt intention, you may eaſily reſtore a broken or diſlocated bone, if preſently, as ſoon as the miſchance is got, or elſe the ſame day, you endeavour to reſtore it: For the bitterneſs of pain or inflammation, which may trouble the Patient, is not as yet very great; neither is the contraction of the muſcles upwards, as yet very much or ſtubborn: Therefore firſt of all, the Patient with his whole body, but eſpecially with the broken or diſlocated part, as alſo the Surgeon, muſt be in ſome place which hath good and ſufficient light: Then let truſty and skilful attendants be there, good ligatures, and alſo, if need ſo require, good engines. His friends which are preſent, let them ſee and hold their peace, neither ſay nor do any thing which may hinder the work of the Surgeon: Then putting one hand above, that is, towards the center of the body, and the other below, as near as he can to the part affected, let him ſtretch forth the member: For if you lay your hand any diſtance from the part affected, you will hurt the ſound part by too much compreſſion, neither will you much avail your ſelf by ſtretching it at ſuch a diſtance: But if you only endeavour below with your hand or ligature, aſſiſting to make extenſion thereof, it will be dangerous if there be nothing above which may withſtand or hold, leſt that you draw the whole body to you: This being done according as I have delivered, it is fit the Surgeon make a right or ſtrait extenſion of the part affected: For when the bone is either broken or out of joynt, there is contraction of the muſcles towards their original, and conſequently of the bones by them, as it is obſerved by *Galen:* Wherefore it is impoſſible to reſtore the bones to their former ſeat, without the extenſion of the muſcles: But the part being thus extended, the broken bones will ſooner and more eaſily be reſtored to their former ſeat: Which being reſtored, you ſhall preſently with your hand preſs it down, if there be any thing that bunches or ſtands out. And laſtly, you ſhall bind it up, by applying boulſters and ſplints as ſhall be fit. But if the bone be diſlocated or forth of joynt, then preſently after the extenſion thereof, it will be requiſite to bend it ſomewhat about, and ſo to draw it in. The Surgeon is ſometimes forced to uſe engines for this work, eſpecially if the luxation be inveterate, if the broken or luxated bones be great; and that in ſtrong and ruſtick bodies, and ſuch as have large joynts; for that then there is need of greater ſtrength than is in the hand of the Surgeon alone. For, by how much the muſcles of the Patient are the ſtronger, by ſo much will they be contracted more powerfully upwards towards their originals: Yet have a care that you extend them not too violently, leſt by rending and breaking aſunder the muſcles and nerves, you cauſe the forementioned Symptoms, Pain, Convulſion, a Palſie and Gangrene: All which ſooner happen to ſtrong and aged bodies, than to Children, Eunuchs, Women, Youths, and generally all moiſt bodies, for that they are leſs hurt by violent extenſion and pulling, by reaſon of their native and much humidity and ſoftneſs. For thus skins of Leather, moiſtened with any liquor, are eaſily retched, and drawn out as one pleaſeth: But ſuch as are dry and hard, being leſs tractable, will ſooner rend and tear, than ſtretch further out. Therefore the Surgeon ſhall uſe a mean in extending and drawing forth of members, as ſhall be moſt agreeable to the habits of the bodies. You may know the bone is ſet, and the ſetting performed as is fit, if the pain be aſſwaged; to wit, the fibres of the muſcles, and the other parts being reſtored to their former ſite, and all compreſſion, which the bones moved out of their places have made, being taken away; if, to your feeling there be nothing, bunching out, nor rugged, but the ſurface of the membrane remain ſmooth and equal; and laſtly, if the broken or diſlocated member compares with its oppoſite in the compoſure of the joynts, and knees, as the ankles anſwer juſtly and equally in length and thickneſs. For which purpoſe it muſt not ſuffice the Surgeon to view it once, but even as often as he ſhall dreſs it: For it may happen, that the bone which is well ſet, may by ſome chance, as by the Patients unconſiderate turning himſelf in his bed, or, as it were, a convulſive twitching of the members or joynts whilſt he ſleeps, the muſcles of their own accord contracting themſelves towards their originals, that the member may again fall out; and it will give manifeſt ſigns thereof by renewing the pain, by preſſing or pricking the adjacent bodies: Which pain will not ceaſe, before it be reſtored to its place: And hereof the Surgeon

Three things to be performed in curing broken and diſlocated bones.

How to put the bones in their places.

Hipp. ſent. 60. ſect. 2. de fract.

Ad ſent. 1. ſect. 1. de fract.

When inſtruments or engines are neceſſary.

What bodies are ſooner hurt by violent extenſion.

Signs of a bone well ſet.

Cauſes and ſigns of the relapſe of a ſet bone.

ought to have diligent care: For if, whilſt the *Callus* is in growing, one bone ride over another, the bone it ſelf will afterwards be ſo much the ſhorter, and conſequently the whole member; ſo that if this errour ſhall happen in a broken leg, the Patient will halt ever after, to his great grief, and the Surgeons ſhame: Wherefore the Patient ſhall take heed, as much as in him lies, that he ſtir not the broken member, before that the *Callus* be hardned. Such diligent care needs not be had in Diſlocations: For theſe once ſet, and artificially bound up, do not afterwards ſo eaſily fall forth as broken bones. The ſecond ſcope is, that the bones which ſhall be reſtored may be firmly kept in their ſtate and place: That ſhall be done by Bandages; as Ligatures, Boulſters, and other things, whereof hereafter we ſhall make particular mention: Hither tend proper and fit medicines, to wit, applying of Oyl of Roſes with the whites of Eggs, and the like repelling things, and then reſolving medicines, as the preſent neceſſity ſhall require. It will be convenient to moiſten your rowlers and boulſters in Oxycrate for this purpoſe, or elſe in Roſe-vinegar, if the Fracture be ſimple, or with Red-wine; or the liquor warm (in *Galen*'s opinion) if a wound be joyned to the Fracture; and it will be fit to moiſten Fractures often in Summer; for ſo the part is ſtrengthened, the defluxion being repelled, whereby the inflammation and pain are hindered. You muſt deſiſt from humecting and watering the part when the ſymptomes are paſt, leſt you retard the generating of a *Callus*; for which you muſt labour by theſe means which we ſhall hereafter declare. To this purpoſe alſo conduces the reſt and lying of the part in its proper figure and ſite accuſtomed in health, that ſo it may the longer remain in the ſame place unſtirred: Beſides alſo, it is expedient then only to dreſs the part, when it is needful, and with thoſe things which are requiſite, ſhunning as much as may be, inflammation and pain. That figure is thought the beſt, which is the middle; that is, which contains the muſcles in their ſite, which is without pain; ſo that the Patient may long endure it without labour or trouble. All theſe things being performed, the Patient muſt be asked, whether the member be bound up too ſtrait? If he anſwer, No, (unleſs peradventure a little upon the fracture or luxation, for there it is fit it ſhould be more ſtraitly bound) then may you know that the binding is moderate: And this ſame firſt ligation is to be kept in fractures without looſing for three or four days ſpace, unleſs peradventure pain urge you to the contrary. In diſlocations the ſame binding may be kept for ſeven or eight days, unleſs by chance ſome ſymptom may happen; which may force us to open it before that time; for the Surgeon muſt with all his art have a care to prohibit the hapning of evil accidents and ſymptoms, which, how he may bring to paſs, ſhall be declared in the following Chapter.

Ad. ſent. 21. ſect. 1. de fract.

What the middle figure is, and why beſt.

Fit time for looſing of ligatures in fractures and diſlocations.

CHAP. V.

By what means you may perform the third intention in curing Fractures and Diſlocations, which is the bindring and correction of accidents and ſymptoms.

Four choice means to hinder accidents.

THat we may attain unto this third ſcope, it is requiſite we handle as gently and without pain, as we may, the broken, or diſlocated member; we drive away the defluxion ready to fall down upon the part, by medicines, repelling the humour, and ſtrengthning the part; we, by appointing a good diet, hinder the begetting of excrements in the body, and divert them by purging and phlebotomy: But if theſe accidents be already preſent, we muſt cure them, according to the kind and nature of each of them; for they are various: Amongſt which is reckoned itching, which in the beginning torments the Patient: This ariſeth from a collection and ſuppreſſion of ſubacrid vapours, ariſing from the blood, and other humors under the skin: Whence a light biting, which cauſeth a ſimple itch, or elſe a more grievous and acrid one, from whence (in *Galen*'s opinion) proceeds a painful itching. Wherefore ſuch matter, as the cauſe, being evacuated, all itching ceaſeth: But this cannot eaſily and freely be evacuated and breathed out, becauſe the pores of the part are ſhut up, and, as it were oppreſſed with the burthen of the emplaſters, boulſters and ligatures, which are put about the part. Hereunto may be added, that the part it ſelf doth not ſo perfectly perform and enjoy its wonted faculties and actions: By which it cometh to paſs, that the heat thereof is more languid than may ſuffice to diſcuſs the fuliginous matter there collected. Wherefore it will be convenient to looſe the ligatures every third day, that as by looſing their ties, their ſanious and fuliginous excrements, ſhut up under the skin, may freely paſs forth, leſt in continuance they ſhould fret and ulcerate it; as it happens to moſt of thoſe who provide not for it by looſing their ligatures. Beſides alſo, the part muſt be long fomented with hot water alone, or elſe with a decoction, of Sage, Chamomil, Roſes, and Melilot made in Wine and water: For long fomenting attenuates and evacuates; but ſhorter fills and mollifies, as it is delivered by *Hippocrates*. Alſo gentle frictions, performed with your hand, or a warm linnen cloth upwards, to the right ſide and left, and circularly to every ſide, are good. But if the skin be already riſen into bliſters, they muſt be cut, leſt the matter contained thereunder may corrode and ulcerate the skin: Then muſt the skin be anointed with ſome cooling and drying medicine; as, *Ung. album Camphoratum Rhaſis, Deſiccativum rubrum, unguentum roſatum ſine aceto*; adding thereto the powder of a rotten poſt, or prepared *Tutia*, or the like. Other accidents more grievous then theſe, do often happen, but we will treat of them hereafter: But if the ſcales of the bone underneath, be quite ſevered from the whole, then muſt they be preſently taken forth, eſpecially if they prick the muſcles: But if the bone be broken into ſplinters, and ſo prominent out of the wounded fleſh that it cannot be reſtored into its ſeat, it muſt be cut off with your Cutting-mallets, or Parrats-beak, as occaſion ſhall offer it ſelf: In the interim you muſt have a care that the part enjoy perſpiration, and by change of place and riſing, now and then it may be, as it were ventilated: Alſo you muſt ſee that it be not over-burthened, neither too ſtrait bound, otherwiſe it will

The cauſes and differences of itching.

Ad ſen. 4. ſec. 2. de fract.

Remedies againſt the itching.

Hipp. ſent. 46. ſect. 3. de fract.

will be apt to inflammation. Thus much concerning fractures and diſlocations in general: Now we muſt deſcend to particulars, beginning with the fracture of the noſe.

CHAP. VI.

Of the Fracture of the Noſe.

THe noſe is griſtly in its lower part, but bony in the upper. Wherefore it ſuffers no fracture in the griſtly part (unleſs peradventure a *Sedes*) but only a depreſſion, diſtortion or contuſion. But a fracture often happens to the bony part, and ſo great a depreſſion to the inner ſide, that unleſs it be provided for by diligent reſtoring it, the noſe will become flat, or wreſted aſide, whence there will be difficulty of breathing. That this kind of fracture may be reſtored, that bone which ſtands too far out, muſt be preſſed down; but that which is depreſt, muſt be lifted up with a ſpathern, or little ſtick handſomely faſhioned and wrapped about with cotten or a linnen rag, ſo to avoid pain: Therefore you ſhall hold the ſpathern in one hand, and reduce and order it with the other. The bone being reſtored, directories or tents of a convenient bigneſs ſhall be put into the noſe; which tents ſhall be mad of ſpunge, or flax, or a piece of a beaſts or ſheeps lungs: For theſe things are ſoft, and do not only hinder the bones of the noſe that they fall no more, but alſo lift them up higher: And then the noſe ſhall be in ſome ſort ſtayed with boulſters on each ſide, even until the perfect agglutination of the bones, leſt the figure and ſtraitneſs ſhould be vitiated and ſpoiled. I have oft-times put golden, ſilver and leaden pipes into fractured noſes, and faſtned them with a thred to the Patients night-cap, which, by one and the ſame means, kept the bones from being again depreſt, gave the matter free paſſage forth, and nothing hindred the breathing. In the mean time we muſt ſee that we do not preſs the noſe with too ſtrait binding, unleſs peradventure ſome other thing perſwade; leſt they become either too wide, too flat, or crooked. If any wound accompany the fracture, that ſhall be cured after the ſame manner as the wounds of the head. The fracture reſtored, the following medicine, which hath a faculty to repel and repreſs the defluxion, to ſtrengthen and keep the part in its due poſture, and to dry up and waſte the matter which hath already fallen down, ſhall be applied to the noſe, and all the other dry parts.

Hipp. ſent. 46. ſect. 2. de art.

How to reduce the noſe into its natural figure.

℞ *Thuris, maſtiches, boli armeniæ, ſanguinis draconis, an.* ℥ ß. *Aluminis rochæ, reſinæ pini, an.* ℥ ij. *Pulveriſentur ſubtiliſſime:* Or elſe, ℞ *Farinæ volatilis* ℥ij ß. *Albuminum ovorum quantum ſufficit, incorporentur ſimul, & fiat medicamentum.*

A fit aſtringent and drying medicine.

Neither ſhall you uſe any other art to cure the cartilaginous part of the noſe being fractured: Wherefore *Hippocrates* terms that ſolution of continuity that there happens, a fracture, as if it were in a bone; becauſe he could find no other name more fitly to expreſs it; for a griſtle, next to a bone, is the hardeſt of all the parts of our body. A *Callus* uſes to grow in fractured noſes, unleſs ſomething hinder, within the ſpace of twelve or fifteen days.

Sent. 47. ſect. 2. de art. & Gal. in Com.

CHAP. VII.

Of the Fracture of the lower Jaw.

THe lower jaw runs into two, as it were, horns or tops: The one whereof ends ſharp, and receives a tendon from the temporal muſcle; the other ends blunt and round under the mammillary proceſs, and it is there implanted in a ſmall cavity; it is joyned together in the middle of the chin by *Symphyſis*, and is marrowy within: The fracture, which happens thereto, is reſtored by putting your fingers into the Patients mouth, and preſſing them on the inſide and outſide, that ſo the fractured bones put together may be ſmoothed and united: But if they be brokrn wholly athwart, ſo that the bones lye over each other, extenſion muſt be made on both ſides on contrary parts, upwards and downwards, whereby the bones may be compoſed, and joyned more eaſily to one another: The teeth in the mean while, if they be either ſhaken or removed out of their ſockets, muſt be reſtored to their former places, and tied with a Gold or Silver wyer, or elſe an ordinary thred, to the next firm teeth, until ſuch time as they ſhall be faſtened, and the bones perfectly knit by a *Callus:* To which purpoſe, the ordered fragments of the fractured bone ſhall be ſtayed, by putting a ſplint on the outſide, made of ſuch leather as ſhooe-ſoals are made; the midſt thereof being divided at the chin, and of ſuch length and breadth as may ſerve the jaw: Then you ſhall make ligation with a ligature two fingers broad, and of ſuch length as ſhall be ſufficient, divided at both the ends, and cut long-ways in the midſt thereof; that ſo it may engirt the chin on both ſides. Then there will be four heads of ſuch a ligature ſo divided at the ends; the two lower whereof being brought to the crown of the head, ſhall be there faſtned, and ſowed to the Patients night-cap. The two upper drawn athwart, ſhall likewiſe be ſowed as artificially as may be, to the cap in the nape of the neck. It is a moſt certain ſign, that the jaw is reſtored and well ſet, if the teeth faſtned therein ſtand in their due rank and order. The Patient ſhall not lye down upon his broken jaw, leſt the fragments of the bones ſhould again fall out, and cauſe a greater defluxion. Unleſs inflammation, or ſome other grievous ſymptom ſhall happen, it is ſtrengthened with a *Callus* within twenty days; for that it is ſpongious, hollow, and full of marrow, eſpecially in the midſt thereof: Yet ſometimes it heals more ſlowly, according as the temper of the Patient is, which takes alſo place in other fractured bones. The agglutinating and repelling medicine, deſcribed in the former Chapter, ſhall be uſed, as alſo others, as occaſion ſhall offer it ſelf.

A deſcription of the lower jaw.

The manner of reſtoring a broken jaw.

The deſcription of a fit ligature for the under-jaw.

In what time it may be healed.

The

The Patient muſt be fed with liquid meats, which ſtand not in need of chewing, until ſuch time as the *Callus* ſhall grow hard, leſt the ſcarce or ill-joynted fragments ſhould fly in ſunder with the labour of chewing. Therefore ſhall he be nouriſhed with Water-grewel, Ponado's, Cullaſſes, Barley-creams, Gellies, Broths, Rear-eggs, Reſtaurative Liquors, and other things of the like nature.

CHAP. VIII.

Of the Fracture of the Clavicle or Collar-bone.

Hipp. ſent. 63. ſect. 1. de art.

AS the nature and kind of the fractured Clavicle ſhall be, ſo muſt the cure and reſtoring thereof be performed: But howſoever this bone ſhall be broken, always the end faſtned to the ſhoulder and ſhoulder-blade, is lower than that which is joyned to the cheſt; for that the arm draws it downwards. The collar-bone, if broken athwart, is more eaſily reſtored and healed, than if it be cloven long-ways: For, every bone broken athwart doth more eaſily return into its former ſtate or ſeat, whiles you lift it up on this or that ſide with your fingers: But that which is broken *ſchidacidon*, or into ſplinters, or long-ways, is more difficultly joyned and united to the ends and fragments; for thoſe pieces, which were ſet, will be plucked aſunder, even by the leaſt motion of the arms; and that which was knit with the ſhoulder, will fall down to the lower part of the breaſt: The reaſon of which is, the collar-bone is not moved of its ſelf, but conſents in motion with the arm. In reſtoring this or any other fracture, you muſt have a care that the bones ride not one over another, neither be drawn nor depart too far in ſunder: Therefore it will be here convenient, that one ſervant draw the arm backwards, and another pull the ſhoulder towards him the contrary way; for ſo there will be made, as I may ſo term it, a counter-extenſion: While which is in doing, the Surgeon with his fingers ſhall reſtore the fracture, preſſing down that which ſtood up too high, and lifting up that which is preſſed down too low. Some, that they may more eaſily reſtore this kind of fracture, put a clew of yarn under the Patients arm-pit; ſo to fill up the cavity thereof: Then they forcibly preſs the elbow to the ribs, and then force the bone into its former ſeat: But if it happen, that the ends of the broken bones ſhall be ſo depreſt, that they cannot be drawn upwards by the fore-mentioned means; then muſt the Patient be laid with his back, juſt between the ſhoulders, upon a pillow hard ſtuffed, or a tray turned with the bottom upwards, and covered with a rug or ſome ſuch thing: Then the ſervant ſhall ſo long preſs down the Patients ſhoulders with his hands, until the ends of the bones, lying hid and preſſed down, fly out and ſhew themſelves: Which being done, the Surgeon may eaſily reſtore or ſet the fractured bone. But if the bone be ſo broken into ſplinters that it cannot be reſtored, and any of the ſplinters prick and wound the fleſh, and ſo cauſe difficulty of breathing, you then muſt cut the skin even againſt them, and with your Inſtrument lift up all the depreſſed ſplinters, and cut off their ſharp points; ſo to prevent all deadly accidents, which thereupon may be feared. If there be any fragments, they, after they are ſet, ſhall be covered with a knitting medicine made of Wheat-flour, Frankincenſe, Bole-armeniack, *Sanguis draconis*, *Reſini pini*, made into powder, and mixed with the whites of Eggs, putting upon it ſplints covered with ſoft, worn linnen rags; covered over likewiſe with the ſame medicine, and then three boulſters dipped in the ſame; two whereof ſhall be laid upon the ſides; but the third and thickeſt upon the prominent fracture, ſo to repreſs it and hold it in: For thus the fragments ſhall not be able to ſtir or lift themſelves up further than they ſhould, either to the right ſide or left. Now theſe boulſters muſt be of a convenient thickneſs and breadth, ſufficient to fill up the cavities which are above and below that bone: Then ſhall you make fit ligation with a rowler, having a double head caſt croſs-wiſe, of a hands breadth, and ſome two ells and half long, more or leſs, according to the Patients body. Now he ſhall be ſo rowled up, as it may draw his arm ſomewhat backwards, and in the interim his arm-pits ſhall be filled with boulſters, eſpecially that next the broken bone; for ſo the Patient may more eaſily ſuffer the binding. Alſo you ſhall wiſh the Patient, that he of himſelf bend his arm backwards, and ſet his hand upon his hip, as the Country Clowns uſe to do, when they play at Leap-frog. But how great diligence ſoever you uſe in curing this ſort of fracture, yet can it ſcarce be ſo performed, but that there will ſome deformity remain in the part: For that a ligature cannot be rowled about the collar-bone, as it may about a leg or an arm. A *Callus* oft-times grows on this bone, within the ſpace of twenty days becauſe it is rare and ſpongious.

How to reſtore the fractured Clavicle.

The firſt way.

The ſecond way.

The third way.

How to bind up the fractured clavicle.

It is a difficult matter perfectly to reſtore a fractured clavicle.

CHAP. IX.

Of the Fracture of the Shoulder-blade.

An anatomical deſcription of the ſhoulder-blade.

THE Greeks call that *Omoplata*, which the Latins term *Scapula*, or *Scapulæ patella*, that is, the ſhoulder-blade. It is faſtned on the back to the ribs, nowl, the *Vertebræ* of the cheſt and neck; but not by articulation, but only by the interpoſition of muſcles, of which we have ſpoken in our Anatomy: But on the forepart it is articulated after the manner of other bones, with the collar-bone, the ſhoulder, or arm-bone: For with its proceſs, which repreſents a prick or thorn, and by ſome, for that it is more long and prominent, is called *Acromion*; (that is, as you would ſay, the top or ſpire of the ſaid ſhoulder-blade) it receives the collar-bone. Therefore ſome Anatomiſts, according to *Hippocrates*, as they ſuppoſe, call all this articulation of the collar-bone, with the hollowed proceſs of the ſhoulder-blade, *Acromion*. There is another proceſs of the ſaid blade-bone, called *Cervix omoplatæ*, or the neck of the ſhoulder-blade; this truly is very ſhort, but ending in a broad inſinuated head, provided for the receiving of the ſhoulder

or

or arm-bone. Not far from this proceſs is another, called *Coracoides*, for that the end thereof is crooked like a Crows-beak. This keeps the ſhoulder-bone in its place, and conduces to the ſtrength of that part. The ſhoulder-blade may be fractured in any part thereof, that is, either on the ridge, which runs like a hill, alongſt the midſt thereof for its ſafety, as we ſee in the *Vertebræ* of the back: So alſo in the broader part thereof, it may be thruſt in and depreſt; and alſo in that articulation, whereby the top of the ſhoulder is knit to it. According to this variety of theſe fractured parts, the happning accidents are more grievous or gentle. How many ways the ſhoulder-blade may be broken.

We know the ſpine or ridge of the ſhoulder-blade to be broken, when a dolorifick inequality is perceived, by touching or feeling it: But you may know, that the broader or thinner part thereof, is depreſſed, if you feel a cavity, and a pricking pain moleſt the part, and if a numneſs trouble the arm, being ſtretched forth. The fragments, if they yet ſtick to their bones and do not prick the fleſh, must be reſtored to their ſtate and place, and there kept with agglutinative medicines, and ſuch as generate a *Callus*, as alſo with boulſters and rowlers fitted to the place: But if they do not adhere to the bone, or prick the fleſh lying under them, then muſt you make inciſion in the fleſh over againſt them, that ſo you may take them out with your Crows-beak: But although they ſtir up and down, yet if they ſtill adhere to the *Perioſteum* and ligaments, (if ſo be that they trouble not the muſcles by pricking them) then muſt they not be taken forth: For I have oftner than once obſerved, that that they have within ſome ſhort time after grown to the adjacent bones. But if they, being wholly ſeparated, do not ſo much as adhere to the *Perioſteum*, then muſt they neceſſarily be plucked away; otherwiſe within ſome ſhort ſpace after, they will be driven forth by the ſtrength of Nature, for that they participate not any more in life with the whole: For that which is quick, ſaith *Hippocrates*, uſes to expel that which is dead far from it. The truth whereof was manifeſted in the Marqueſs of *Villars*, who at the Battel of *Dreux*, was wounded in his ſhoulder with a Piſtol-bullet, certain ſplinters of the broken bone were plucked forth with the pieces of his harneſs, and of the leaden bullet; and within ſome ſhort ſpace after, the wound was cicatrized, and fully and perfectly healed: But more than ſeven years after, a defluxion and inflammation ariſing in that place by reaſon of his labour in Arms, and the heavineſs of his Armour at the Battel of *Mont-contour*, the wound broke open again: ſo that many ſhivers of the bone, with the reſidue of the leaden bullet, came forth of themſelves. But if the fracture ſhall happen in the neck of the ſhoulder-blade, or dearticulation of the ſhoulder, there is ſcarce any hope of recovery; as I have obſerved in *Anthony* of *Bourbon*, King of *Navarre*; *Francis* of *Lorrain*, Duke of *Guiſe*; the Count *Rhingrave Philipbert*, and many other in theſe late Civil Wars: For there are many large veſſels about this dearticulation, to wit, the axillary vein and artery, the nerves ariſing from the *Vertebræ* of the neck, which are thence diſſeminated into all the muſcles of the arm. Beſides, alſo inflammation and putrefaction ariſing there, are eaſily communicated by reaſon of their neighbourhood to the heart and other principal parts, whence grievous ſymptoms, and oft-times death it ſelf enſues. The cure. *Lib. de vul. capitis.* A Hiſtory. Nature of its own accord makes it ſelf way to caſt forth ſtrange bodies and matters. Why a fracture in the joynt of the ſhoulder is deadly.

CHAP. X.

Of the Fracture and Depreſſion of the Sternon *or Breaſt-bone.*

THe *Sternum* is ſometimes broken, other whiles only thruſt in without a fracture. The inequality perceivable by your feeling, ſhews a fracture, as alſo the going in with a thruſt with your finger, and the ſound or noiſe of the bones crackling under your fingers. But a manifeſt cavity in the part, a cough, ſpitting of blood, and difficulty of breathing by compreſſion of the membrane inveſting the ribs and the lungs, argue the depreſſion thereof. For the reſtoring of this bone, whether broken or depreſt, the Patient muſt be laid on his back with a cuſhion ſtuffed with tow or hay under the *Vertebræ* of the back, as we ſet down in the ſetting of the collar-bone: Then a ſervant ſhall lie ſtrongly with both his hands on his ſhoulders, as if he would preſs them down, whilſt the Surgeon, in the mean time preſſing the ribs on each ſide, ſhall reſtore and ſet the bone with his hand; and then the formerly deſcribed medicines ſhall be applied for to hinder inflammation, and aſſwage pain; boulſters ſhall be fitted thereto, and a ligature ſhall be made croſs-ways above the ſhoulders; but that not too ſtrait, leſt it hinder the Patients breathing. I by theſe means, at the appointment of *Anthony* of *Burbon* King of *Navar*, cured *Anthony Benand* a Knight of the Order, who had his breaſt-plate bended and driven in, with an iron bullet ſhot out of a Field-piece, as alſo his *ſternum* together therewith, and he fell down as dead with the blow; he did ſpit blood for three months after I had ſet the bone, yet for all this he lives at this day in perfect health. Signs that the *ſternum* is broken. Signs that it is depreſt. The cure. A Hiſtory.

CHAP. XI.

Of the Fracture of the Ribs.

THe true ribs, for that they are bony, may be broken in any part of them; but the baſtard ribs cannot be truly broken, unleſs at the back-bone, becauſe they are only bony in that part, but griſtly on the foreſide toward the breaſt-bone: Wherefore there they can only be folded or crooked in. Theſe which are ſubject to fractures, may be broken inwards and outwards. But oft-times it comes to paſs, that they are not abſolutely broken, but cleft into ſplinters, and that ſometimes inwards, but not outwards. Thus the fiſſure doth oft-times not exceed the middle ſubſtance of the rib; but ſometimes it ſo breaks through it all, that the fragments and ſplinters do prick and wound the membrane, which inveſts and lines them on the inſide, and then there is great danger. But when the fracture is ſimple without a wound, compreſſion, puncture of the membrane, In what place the ſhort ribs may be broken.

Sent. 56. ſect. 3. de art. membrane, and laſtly, without any other ſymptom, then the danger is leſs: Therefore *Hippocrates* wiſheth, that thoſe, who are thus affected, fill themſelves more freely with meat; for that moderate repletion of the belly, is (as it were) a certain prop or ſtay for the ribs, keeping them well in their place and ſtate; which rule chiefly takes place in fractures of the baſtard ribs. For ſuch as have them broken, uſually feel themſelves better after, than before meat. For emptineſs of meat, or of the ſtomach, makes a ſuſpenſion of the ribs, as not under-propped by the meat. Now

Why an internal fracture of the ribs is deadly. that fracture which is outwardly, is far more eaſie to heal, than that which is inwardly; for that this pricketh the membrane or *Pleura*, and cauſeth inflammation, which may eaſily end in an *Empyema*. Add hereunto, that this is not ſo eaſily to be handled or dealt withal, as the other; whereby it cometh to paſs, that it cannot be ſo eaſily reſtored, for that theſe things cannot be ſo fully and freely performed in this kind of fracture, which are neceſſary to the ſetting of the bone, as to draw it out, hold it and joyn it together. It is therefore healed within twenty days, if nothing elſe hinder.

The ſigns. The ſigns of fractured ribs are not obſcure; for by feeling the grieved part with your fingers, you may eaſily perceive the fracture by the inequality of the bones, and their noiſe or crackling, eſpecially if they be quite broke aſunder.

The cauſe of ſpitting blood when the ribs are broken. But if a rib be broken on the inſide, a pricking pain, far more grievous than in a pleuriſie, troubles the Patient; becauſe the ſharp ſplinters prick the Coſtal membrane: Whence great difficulty in breathing, a cough, and ſpitting of blood enſue. For blood, flowing from the veſſels broken by the violence of the thing cauſing the fracture, is (as it were) ſucked up by the lungs, and ſo by a dry cough carried into the weazon, and at length ſpit out of the mouth. Some, to pull up the bone that is quite broken and depreſt, apply a Cupping-

Sent. 15. ſect. 3. de art. Paulus lib. 6. cap. 96. Avicen. 4. glaſs, and that is ill done; for there is cauſed greater attraction of humours, and exceſs of pain by the preſſure and contraction of the adjacent parts, by the Cupping-glaſs; wherefore *Hippocrates* alſo forbids it: Therefore it is better to endeavour to reſtore it after this following manner. Let the Patient lye upon his ſound ſide, and let there be laid upon the fractured ſide an emplaſter made of

The cure. Turpentine, Roſin, Black-pitch, Wheat-flour, Maſtich and Aloes, and ſpread upon a ſtrong and new cloth. When it hath ſtuck there ſome time, then pluck it ſuddenly with great violence from below upwards; for ſo the rib will follow together therewith, and be plucked and drawn upwards. It is not ſufficient to have done this once, but you muſt do it often, until ſuch time as the Patient ſhall find himſelf better, and to breathe more eaſily. There will be much more hope of reſtitution, if, whilſt the Surgeon do this diligently, the Patient forbear coughing, and hold his breath: Otherwiſe, if neceſſity urge, as if ſharp ſplinters with moſt bitter tormenting pain prick the Coſtal membrane, overſpread with many nerves, veins and arteries, which run under the ribs, whence difficulty of breathing, ſpitting of blood, a cough and feaver enſue; then the only way to deliver the Patient from danger of imminent death, is to make inciſion on the part where the rib is broken, that ſo laying it bare, you may diſcern the pricking fragments, and take them out with your Inſtrument, or elſe cut them off. And if you make a great wound by inciſion, then ſhall

A ſimple fracture may be cured only by Surgery. you ſew it up, and cure it according to the common rules of curing wounds. Now Diet, Phlebotomy and Purgation, which (as *Hippocrates* ſaith) are not very needful in a ſimple fracture, for that there are no ſymptoms which may require ſuch remedies; yet, they, by reaſon of the complicated ſymptoms, as a convulſion, feaver, *Empyema*, and the like, muſt here be preſcribed by the advice of the Phyſician which overſees the cure. A Cerate, and other remedies fitting the occaſion, ſhall be applied to the grieved part: No other ligatures can be uſed, than ſuch as are fit to hold faſt and ſtay the local medicines. There is no other rule of ſite and lying, than ſuch as is taken from the will and content of the Patient.

CHAP. XII.

Of certain preternatural affects which enſue upon broken Ribs.

MAny ſymptoms enſue upon fractured and contuſed ribs; but amongſt the reſt, there are two which are not common, whereof we will treat in this place. The firſt is, the inflamation, or riſing up of the contuſed fleſh, which alſo enſues upon light affects of the bone, which have been neglected at the beginning. But the fleſh is not merely puffed up of it ſelf, but alſo within a certain phlegmatick, glutinous and viſcous humour gathering thereinto.

The cauſe. The cauſe hereof is, the weakneſs of the digeſtive faculty of the part, occaſioned by the ſtroke and diſtemper; which therefore cannot aſſimilate the nouriſhment flowing more plentifully than it was wont, either drawn thither by means of the pain, or ſent thither by a blind violence of nature, ſtirred thereto by a deſire of its own preſervation. Wherefore this half crude humour remaining there, raiſeth much flatuling from its ſelf, or elſe wrought upon by the weaker heat,

The ſigns. it is reſolved into cloudy vapours; whence it cometh to paſs, that the fleſh is ſwoln up in that place, and the skin on the contrary grows ſoft, as if it were blown up with a quill: Therefore laying your hand thereon, you may hear the noiſe of the wind going forth thereof, and ſee a cavity left in the part, as it is uſually ſeen in œdematous tumors. Unleſs you remedy this inflation, there will enſue an imflammation, feaver, abſceſs, difficulty of breathing; and laſtly, that ſecond kind of affect whereof we have determined to treat in this Chapter, to wit, the putrefaction, corruption, or blaſting of the ribs. An abſceſs, and the ſeparation of the fleſh from the bone is the cauſe hereof: For hence it cometh to paſs, that the bone, deſpoiled of its natural and fleſhly cloathing wherewith it was cheriſhed, is eaſily offended by the touch of the entring air, which it never formerly felt, and ſo at length it becometh (as it were) blaſted: Which when it

The cure. happens, they ſpit up filth, and ſo fall into a Conſumption, and at length die. To withſtand all theſe inconveniencies, you muſt as ſpeedily as you can, reſtore the fractured bones by the former delivered means: And then this mucous tumor muſt be reſolved by proper heating and diſcuſſing medicines,

medicines, and kept down by boulſters and rowlers; that ſo the fleſh may touch the bone, and cover it as it uſually did. But the ligature ſhall not be made ſo ſtrait, as to hinder the ribs from their wonted motion in expiration and inſpiration. If the tumor degenerate into an abſceſs, it ſhall be ſpeedily opened, leſt the matter, kept in too long, corrupt the bone which lies under it, by the contagion of its putrefaction. The Ulcer being opened, the matter ſhall be evacuated by putting a Pipe into the Ulcer; the end whereof ſhall be bound about with a thred, leſt it fall into the capacity of the cheſt, and that it may be drawn forth at your pleaſure.

CHAP. XIII.

Of the Fracture of the Vertebræ, *or Rack-bones of the Back, and of their Proceſſes.*

The affect of the *Vertebræ.*

THe *Vertebræ* are ſomewhiles broken, otherwhiles bruiſed or ſtrained on the inſide, whereby it cometh to paſs, that the membranes which inveſt the ſpinal marrow, as alſo the ſpinal marrow it ſelf, are compreſſed and ſtraitned, which cauſe many malign accidents; which, whether they be curable or not, may be certainly foretold by their magnitude. Amongſt theſe ſymptoms, are the ſtupidity, or numneſs and palſie of the arms, legs, fundament and bladder, which diminiſh, or elſe take away from them the faculty of ſenſe and motion: ſo that their urine and excrements come from them againſt their wills and knowledge, or elſe are wholly ſuppreſt. Which when they happen (ſaith *Hippocrates*) you may foretel that death is at hand, by reaſon that the ſpinal marrow is hurt. Having made ſuch a Prognoſtick, you may make an inciſion, ſo to take forth the ſplinters of the broken *Vertebræ*, which driven in, preſs the ſpinal marrow, and the nerves thereof. If you cannot do this, at leaſt you ſhall apply ſuch medicines as may aſſwage pain, and hinder inflammation; and then the broken bones ſhall be reſtored to their places, and contained therein by thoſe means which we ſhall mention, when we come to treat of the luxation of the ſpine. But if that the Proceſſes only of the *Vertebræ* be broken, the fragments ſhall be put in their places, unleſs they be quite ſevered from their *Perioſteum*. But if they be ſevered, you ſhall open the skin and take them forth, and then dreſs the wound as is fit. We underſtand that only the proceſſes of the *Vertebræ* are broken, if in the abſence of the forementioned ſymptoms of numneſs and the palſie, you laying your finger upon the grieved part, feel ſomething, as a bony fragment, ſhaking and moving thereunder, with a certain crackling noiſe, cavity and depreſſion; and then, if when the Patient holds down his head, and bends his back, he feel far more pain, than when he ſtands up ſtrait on his feet: For in ſtooping, the skin of the back is ſomewhat ſtretched forth and extended, and alſo forced upon the ſharp ſplinters of the fragments, whence proceeds a dolorifick ſolution of continuity, and a pricking: In ſtanding ſtrait up, on the contrary, the ſtretched skin is relaxed, and conſequently leſt moleſted by the ſharp fragments. The fractured proceſſes of the *Vertebræ* eaſily heal, unleſs they be aſſociated with ſome other more grievous ſymptom which may hinder; ſuch as is a certain great contuſion, and the like: For as we formerly ſaid out of *Hippocrates*, all rare and ſpongy bones are knit by a *Callus* within a few days.

Sect. 2. Proth.

The cure of fractured *Vertebræ.*

The cure of the proceſſes.

Signs that only the proceſſes are fractured.

CHAP. XIV.

Of the Fracture of the Holy-bone.

What fracture of the holy-bone curable, and what not.

ALſo the Holy-bone in a certain part thereof, which may eaſily be healed, may be broken by the blow of bruiſing things, as by a bullet ſhot out of a muſket, as I have obſerved in many: But if the fracture violate, together with the *Vertebræ* thereof, the ſpinal marrow contained therein, then the Patient can ſcarce ſcape death, for the reaſons ſhewed in the former Chapter.

CHAP. XV.

Of the Fracture of the Rump.

The deſcription of the rump.

THe Rump is compoſed of four bones; the firſt whereof hath a cavity, wherein it receives the loweſt *Vertebræ* of the holy-bone; the other three are joyned together by *Symphyſis* or Coalition; at the end of theſe hangs a certain ſmall griſtle. The fracture of theſe bones ſhall be cured by putting your finger into the Patients fundament, and ſo thruſting it even to the fractured place: For, thus you may thruſt the fragments forth, and fit and reſtore it to the reſt of the bones by your other hand lying upon the back: But that it may be the ſooner healed, it is fit the Patient keep his bed, during all the time of the cure: But if there be a neceſſity to riſe, he ſhall ſo ſit in a perforated ſeat, that there may be nothing which may preſs the broken part; and fitting remedies for healing fractures ſhall be applied as occaſion ſhall offer it ſelf.

The cure.

CHAP.

CHAP. XVI.

Of the Fracture of the Hip, or Os Ilium.

The deſcription of the hip.

THe hip conſiſts of three bones: The firſt is named *Os Ilium*, the haunch-bone; the other, *Os Iſchion*, the huckle-bone; the third, *Os pubis*, the ſhare-bone. Theſe three bones in men of full growth, are ſo faſt knit and joyned together, that they can by no means be ſeparated; but in children they may be ſeparated without much ado. This bone may be broken in any part thereof, either by a ſtroke, or by a fall from high upon any hard body. You ſhall know the fracture by the ſame kind of ſigns, as you know others, to wit, pain, pricking, a depreſſed cavity, and inequality, and alſo a numneſs of the leg of the ſame ſide. The ſplinters of the bones (if quite broke off) muſt by making inciſion, be taken away at the firſt dreſſing; in performance of which operation, you muſt have a care that you hurt not with your Inſtrument the heads of the muſcles, nor any veſſels, eſpecially which are great; nor laſtly, that large nerve which is ſent into the muſcles of the thigh and leg. On the contrary, ſuch fragments as are not broken or ſevered from their *Perioſteum*, ſhall be ſmoothed and ſet in order with your fingers, as is fitting. Other things ſhall be done acording as art and neceſſity ſhall perſwade and require.

The ſigns.

The cure.

CHAP. XVI.

Of the Fracture of the Shoulder or Arm-bone.

The deſcription of the arm, or ſhoulder-bone.

THe arm-bone is round, hollow, full of marrow, riſing up with an indifferent neck, and ending on the upper part into ſomewhat a thick head. On the lower part it hath two proceſſes, the one before, the other behind; between which there is (as it were) an half-circle, or the cavity of a pully, each end whereof leads into its cavity, of which one is interior, another exterior; that by theſe (as it were) hollow ſtops, the bending and extenſion of the arm might be limited, leſt that the bone of the cubit, if the circle ſhould have been perfect, ſliding equally this way and that way, might, by its turning, have gone quite round, as a rope runs in a pulley; which thing would much have confuſed the motion of the cubit: For ſo the extenſion or bending it back, would have been equal to the neceſſary bending it inwards. It is very expedient that a Surgeon know theſe things, that ſo he may the better know how to reſtore the fractures and luxations of this part. If one of the fragments of this broken bone ſhall lye much over the other, and the Patient have a good ſtrong body, then the arm ſhall be much extended, the Patient being ſo ſet upon a low ſeat, that he may not riſe when the fracture ſhall be a ſetting, and ſo hinder the begun work; and alſo, that ſo the Surgeon may there more eaſily perform his operation upon the Patient ſeated under him; yet *Hippocrates* regarding another thing, would have the Patient to ſit higher: But you muſt have a care that the ſhoulder-bone it ſelf be drawn directly downwards, and the cubit ſo bended, as when you put it into a ſcarf. For if any one ſet this bone, lifting the arm upwards, or otherwiſe, extending it, then muſt it be kept in that poſture; for otherwiſe, if the figure be changed, the ſetting will quickly be ſpoiled, when as you come to put the arm in a ſcarf: Wherefore the Surgeon muſt diligently and carefully obſerve, that in ſetting a broken arm, he put it in ſuch a poſture, that reſting on the breaſt, it look down toward the girdle. You muſt have a care in laying the ſplints, and rowling your ligatures, that they hurt not, nor preſs too hard upon the joynts. For, in the opinion of *Hippocrates*, by the preſſure of parts which are nervous, fleſhleſs, and conſequently endued with exquiſite ſenſe, by the ſplints there is danger of moſt grievous pain, inflammation, denudation both of the bone and nerve; but chiefly, if ſuch compreſſion hurt the inner part, towards which the arm is bended; wherefore the ſplints made for this place muſt be the ſhorter: Therefore after the arm-bone is ſet, the arm ſhall be laid upon the breaſt in a right angle, and there bound up in a ſcarf, leſt that the Patient, when he hath need to ſtir, ſpoil and undo the ſetting, and figure of the broken bone: But the arm muſt be kept in quiet, until ſuch time as the fragments ſhall be confirmed with a *Callus*, which uſually is in forty days, ſooner or later, according to the different conſtitutions of bodies.

The cure.

How the arm muſt be placed when the bone is ſet. *Sect. 3. offic. ſect. 1. de fract.*

In what time it will knit.

CHAP. XVIII.

Of the Fracture of the Cubit, or the Ell and Wand.

The differences

IT ſometimes happeneth, that the cubit and wand are broken together and at once, and at otherwhiles that but the one of them is fractured. Now they are broken either in their midſt or ends; their ends (I ſay) which are either towards the elbow, or elſe towards the wriſt. That fracture is worſt of all, wherein both the bones are broken, for then the member is made wholly impotent to perform any ſort of action, and the cure is alſo more difficult; for the member cannot ſo eaſily be contained in its ſtate: For that bone which remains whole, ſerves for a ſtay to the arm, and hinders the muſcles from being drawn back, which uſually draw back and ſhrink up themſelves, whenſoever both bones are broken: Hence it is, that that fracture is judged the worſt, wherein the cubit or ell-bone is broken: But that is eaſieſt of all, wherein only the wand is broken, for ſo the fractured part is ſuſtained by the ell-bone: When both the bones are broken, there muſt be made a ſtronger extenſion, for that the muſcles are the more contracted: Therefore, whenſoever either of them remains whole, it doth more ſervice in ſuſtaining the other, than any either ligatures or ſplints, for that it keeps the muſcles right in their places:

The cure.

Wherefore,

Wherefore after the bones ſhall be ſet and rowled up with ligatures and ſplints, the arm muſt be ſo carried up in a ſcarf put about the neck, that the hand may not be much higher than the elbow, leſt the bloud and other humours may fall down thereinto: But the hand ſhall be ſet in that poſture which is between prone and ſupine, for ſo the Wand ſhall lie directly under the Ell, as we have read it obſerved by *Hippocrates:* The reaſon is, for that by a ſupine figure or ſituation, both the bone and muſcles are perverted: for firſt, for the bone, the *Apophyſis*, *Styloides* and *Olecranum* of the cubit, ought to be in an equal plain, and to be ſeated each againſt other; which is not ſo in a ſupine figure, as wherein the *Proceſſus ſtyloides* of the cubit is ſet againſt the inner proceſs of the arm-bone. But in muſcles, for that, like as the inſertion and ſite of the head of a muſcle is, ſuch alſo is the ſite of the belly thereof: and laſtly, ſuch the inſertion of the tail thereof; but by a ſupine figure, the muſcles ariſing from the inner proceſs of the arm-bone, and bending the cubit, ſhall have the tail placed in an higher and more exteriour ſite. In the *interim*, you muſt not omit, but that the Patients Arm may with as little pain as poſſible you can, be bended and extended now and then, leſt by the too long reſt of the tied up part, and the intermiſſion of its proper function, the bones of the joint may be ſoldered together by the interpoſition, and as it were glue of the defluxion which falls abundantly into the joint of the elbow, and neighbouring parts, whence the ſtiffneſs and unmovableneſs thereof, as if there were a *Callus* grown there: from whence it may happen that the Arm thereafter may neither be bended nor extended, which I have obſerved to have happened to many: Whereof alſo *Galen* makes mention, and calls this kind of vitiated conformation *Aneyle* and *Aneyloſis*. If a Wound alſo aſſociate a fracture of the arm, then ſee that you put about it Plates of Lattin, or Paſt-board, and make a convenient ligature and that the fragments of the bones be kept in the ſame ſtate wherein they were ſet and reſtored: Moreover, let him lay his arm upon a ſoft pillow, or cuſhion, as the precedent Figure ſhews you.

Sent. 3. ſect. 2. de Fract.

Com. in lib. de Art.

The Figure of a fractured Arm, with a wound bound up, and ſeated, as is fit.

CHAP. XIX.

Of the Fracture of a Hand.

THe Bones of the Wriſt and After-wriſt, may be broken: but, in *Hippocrates* opinion, chiefly by that kind of Fracture which is called a *Sedes*; now if they ſhall happen to be broken, this ſhall be the manner of reſtoring them: Let the Patient lay forth his hand upon ſome even and ſmooth Table; then let your Servant ſtretch forth the broken bones, and the Work-maſter reſtore them thus extended, and put them in their proper ſeats. But being reſtored, they muſt be kept in their places by ſuch remedies as are uſed in other Fractures; to wit, cerates, compreſſes, linnen cloths, and ſplints. Now the fractured fingers ſhall be tied or bound to their neighbours, that ſo they may the more eaſily, as bound to a ſtake, be kept in that ſtate wherein they have been put by the hand of the Workman: But theſe bones, ſeeing they are of a rare and ſpongy nature, are in a ſhort time and eaſily ſtrengthened, or knit by a *Callus*. Theſe things being done, the hollowneſs or palm of the hand ſhall be filled with a Tennis-ball, for thus the broken bones ſhall not onely be more eaſily kept in their places, but alſo the fingers themſelves ſhall be kept in a middle poſture, that is, not wholly open, nor quite ſhut. If they be kept in any other figure, the enſuing *Callus* will either deprave or quite aboliſh that action of the hand, whereby we take hold of any thing. The caſe ſtands otherwiſe with the fractured Toes; for they ſhall be kept ſtrait and even out, leſt they ſhould hinder our going or ſtanding.

Sect. 2. de fract. ſent. 9.

The cure.

To what purpoſe the carrying of a ball in a fractured hand ſerves.

CHAP. XX.

Of the Fracture of the Thigh.

IT is a hard thing to bring the fragments of the broken Thigh together to be ſet, by reaſon of the large and ſtrong Muſcles of that part; which whileſt they are drawn back towards their original, by a motion both natural and convulſive, they carry together with them the fragment of the bone, whereinto they are inſerted: Therefore, when as the Fracture of this bone ſhall be reſtored, the Patient muſt lie upon his back with his Leg ſtretched forth, and the Surgeon muſt ſtrongly and with great force extend the thigh; but if he alone ſhall not be able ſufficiently to extend it, he ſhall imploy two other ſtrong attendants, by whoſe joint-help the fragments may be fitted and ſet each againſt other. For this purpoſe, when as the ſtrength of the hand was not ſufficient, the Ancients uſed an Inſtrument called a *Gloſſocomium*, whereof this is the Figure.

Why the bone of the Thigh is more difficultly ſet.

Sect. 67, & 68. Sect. 2. de Fract.

The Figure of a Gloſſocomium, *or Extender.*



In ſtead of this *Gloſſocomium*, you may make uſe of my Pulley; for *Hippocrates*, in this bone when it is broken, doth approve of extenſion ſo much, that although by the greatneſs of the extenſion the ends of the fragments be ſomewhat diſtant aſunder, an empty ſpace being left between; yet notwithſtanding would he have a ligature made: For it is not here as it is in the extenſions of other bones, whereas the caſting about of Ligatures keeps the muſcles unmovable: but here, in the extended thighs, the deligation is not of ſuch force as that it may ſtay and keep the bones and muſcles in that ſtate wherein the Surgeon hath placed them: For, ſeeing that the muſcles of the thigh are large and ſtrong, they overcome the ligation, and are not kept under by it. The Surgeon in ſetting it ſhall alſo conſider, that the thigh-bone is hollowed on the inner-ſide, but gibbous on the out-ſide, therefore it muſt be ſet in its native figure: Otherwiſe, if any, unmindful of this conſideration, would have it ſtraight, he ſhall make his Patient halt all his life after: wherefore this inner and native hollowneſs muſt be filled up and preſerved by putting in a compreſs or boulſter ſpread over with *Unguentum roſatum*, or the like glutinous thing that it may not fall off: for thus alſo the ligation ſhall the more faithfully keep the fragments of the bone in their places. Moreover, Compreſſes ſhall be applied to the more ſlender and leſs protuberating parts of the thigh, as thoſe which are next the ham and knee, that ſo the whole ligation may be alike, and conſequently the more firm. Now ligatures, as we formerly noted, are ordained for three things: The firſt is, that the bones may be kept in that ſtate wherein they were ſet, until they be ſtrengthened by a *Callus*: The ſecond is, to hinder defluxion, which eaſily falls into the broken and luxated parts, both by reaſon of pain, as alſo by weakneſs: The third is, to ſtay and hold faſt the ſplints and medicins which are applied. Inflammation is hindered by repreſſing and hindering the bloud and other humours, ready to flow down, from entering into the part, and by preſſing thoſe humours which are preternaturally contained in the part, into the neighbouring parts above and below: Wherefore there muſt no ſmall care be had of preparing ligatures, to wit, that they be made of choice and well woven cloth, yet not coarſe or rough; and let them be of ſuch length and bredth as the Surgeon, perſuaded by an artificial conjecture, ſhall judge to be fit for the thickneſs and length of the member and greatneſs of the fracture: for ligatures ought to be of bredth to involve and cover all the fractured part, and a great part of that which is ſound: But ſeeing that in my Book of Bandages, I have ſeemed chiefly to ſet down and approve the manner of binding uſed by *Hippocrates*, now I think good here in this place to deſcribe that which is in common uſe amongſt our Surgeons. Our Surgeons therefore at this day require three ligatures for Fractures, the firſt whereof they preſently caſt upon the hurt part, whether broken or diſlocated, or onely ſtrained, making the firſt wrappings upon it; ſo that they moſt and ſtraitlieſt bind it there, but leſs and more looſly on both ſides thereof: Such circumvolutions, or wrappings, are drawn upwards, and there ended. They muſt be rowled thick, and not wide; for ſo if they preſently follow, and lie one upon another, they will hold the bones more firmly, and more far and wide preſs forth and repreſs the ſuperfluous bloud from the ſound part. They preſently in like ſort caſt the ſecond ligature upon the very Fracture, giving it two wraps, then going downwards; yet ſo, as that they are opener or wider, and farther diſtant each from other, and not ſo cloſe together, as the circumvolutions of the firſt ligature; that ſo they may preſs the humours the leſs to the extremities of the part, as thoſe which cannot receive and bear, without inflammation and danger of a Gangrene, ſuch abundance of humours, for that they are not ſufficiently ſpacious; as alſo more remote from the fountain of native heat, which is greater in the center than in the circumference. At the lower end of the hurt part the circumvolutions either end, or elſe are twined thence back again: They caſt on the third ligature in that lower end of the hurt part, and rowl it ſmoothly and gently upwards, the windings being made contrary to the windings of the firſt and ſecond ligatures; that they may ſo draw back into their natural ſtate the muſcles, which peradventure have been drawn aſide by the force of the former wrappings. Theſe ligations finiſhed, they apply three ſplints of Paſt-board, or ſome ſuch matter; the firſt below the Fracture, and that truly more broad, and of ſufficient length; and then two others, one on each ſide, diſtant each from other ſome fingers bredth, to the end to keep the bone that it do not ſtir to this ſide or that, being wrapped about with Tow or Cotton: Then they think of placing or laying the part, to which purpoſe they propound to themſelves three ſcopes. The firſt is, that the part may lie ſoft; the ſecond, ſmooth and even; the third, ſomewhat high. The hurt part ought truly to lie ſoft, for that hard lying preſſes it, and cauſes pain and inflammation; which whiles the Patient cannot patiently endure, he is forced to change his place, whileſt he every way ſeeks eaſe for his pain; and thus he now and then moves the fractured part, which ought to be kept quiet without any motion. It muſt lie ſmooth or even, becauſe an unequal or uneven

The natural and internal crookedneſs muſt be preſerved in ſetting the bone.

The part to be bound up, muſt be made plain either by Nature or Art.

The manner of binding uſed by Surgeons at this day.

Why the winding of the upper ligatures muſt be thicker and ſtraiter than the lower.

Why the third ligature muſt be rowled contrary to the two firſt.

The Surgeon muſt be mindful of three things in placing the member.

uneven ſite diſtorts or draws awry the part, whileſt one portion of the hurt part is born up, and ſuſtained by that which lies under it; but the other hanging down hath nothing thereunder, whereupon it may reſt: Therefore *Hippocrates* bids us diligently to take heed that the heel do not hang down, nor the foot remain without a pillow, for hence pain and defluxion of humours is to be feared. *Sect. 2. de fract.* But the part ought to lie ſomewhat high, that the defluxion may be hindered, which is eaſily ſtirred up by a prone and declining ſite: for if the foot ſhall be placed in a lower figure, the bloud which flows thither from the leg, will cauſe inflammation. But on the contrary, if it be higher, nothing can flow down thereinto: Therefore abſolutely not onely the foot, but alſo the thigh and leg are to be placed higher than the reſt of the body; yet keeping ſuch a mean, that the part may not be too much diſtended, as *Hippocrates* admoniſheth us. *Sent. 33, & 56. ſect. 2. de fract.* In the mean time, this hurt leg or ſide ought to be of equal length with the ſound, and for that purpoſe it muſt be ſtaid on both ſides with Junks, as we ſhall ſhew you hereafter, when we come to ſpeak of a broken leg. The bandage being performed, as we have ſaid, the following night, and the next day the Patient feels the member more ſtraitly bound, than when it was at firſt wrapped; yea, verily the Knee is lifted up into a ſoft tumor by the expreſſion of the humour from the wounded part: but on the contrary, the enſuing day the ligation is ſlackned and relaxed, ſome portion of the humour contained in the part being digeſted. Alſo the next day all things are perceived more looſe, there being made a larger reſolution of the humour: Then therefore the bandages muſt be looſed, and that not onely, leſt that the fragments of the bones ſhould fall forth of their place, but alſo that we may gratifie the Patient by that alteration or change of place, and beſides that we may avoid itching, which uſually happens to parts too long bound up, by reaſon of the ſuppreſſion of acrid and fuliginous excrements, which uſe to be gathered in great quantity in a part at reſt and bound up, both from the excrementitious humours, wherewith the part is moiſtned, and the alimentary humours, in a part which is idle and at quiet; by reaſon the diffliation and tranſpiration are hindered by want of exerciſe, and the pores of the skin ſhut up by the abundance of the ligatures: ſo that by the ſuppreſſion thereof, many have not onely an itching, but alſo the skin being broke by the acrimony of theſe, as well vapours as humours, which are kept ſhut and pent up, have Ulcers break forth: Therefore when ſuch accidents ſhall be feared, the part ſhall ſo long be fomented with warm Water and Oil, as you ſhall think fit: for, ſuch fomenting aſſwageth pain, relaxeth that which was too much ſtraitned by the binding, and amends the refrigeration of the part, cauſed by the repercuſſion and expreſſion of the bloud and ſpirits, the native and internal heat being by this means revived. If, together with the tumour there be a contuſion and fugillation, it muſt be the longer fomented, that the excrementitious humour reſiding in the part may be digeſted. But if this quantity of time ſhall not ſuffice, then muſt you uſe ſtronger digeſtives: yet have a care you uſe them not too long; for ſo you ſhould hinder the generation of a *Callus*. Therefore that ſaying of *Hippocrates* muſt here be remembred, which ſaith, That a weak fomentation, and the ſhort time of uſing one, doth attract, but not diſcuſs; but a longer and ſtronger waſtes the fleſh. *Sent. 15. ſect. 3. de offic.* Beſides alſo you muſt have regard to the temper and habit of the Patient; for fomentations uſed to plethorick bodies, draw ſuperfluous humours to the part. The Ancients bid, that the ligatures be looſed every third day until their ſeventh day; but after the ſeventh, on every ſeventh day: but hereof nothing can be certainly and perpetually decreed: For, according to the accidents the Patients muſt be dreſſed ſooner or later, more often or ſeldom; renewing the ligatures, and the reſt of the dreſſing. Therefore, if no ſymptom urge, I would have none of theſe things which are done to the Patient at the firſt dreſſing, to be moved, unleſs as ſlowly and ſeldom as you may: For you hinder the knitting of the bone, if you never ſo little move the ends of the fragments thereof: for, as you ſee Wood is joined together by Glue, and Pewter with Solder; ſo the fragments of bones are, by a providence of Nature, glued and ſoldred together by a *Callus*. Wherefore broken bones have very much need of reſt, to the generating of a *Callus*; otherwiſe, the matter thereof flowing down, quickly flows away, and nothing is done. You may much help forwards the generation of a *Callus*, which is begun about the thirteenth or fifteenth day, by applying an emplaiſter made with the white of an Egg, having the Powder of red Roſe-leaves, and Wheat-flour mixed therewith, and catagmatick Plaſters, which ſhall hereafter be deſcribed in ſpeaking of the Fracture of a Leg.

When the firſt ligation muſt be looſed.

Reſt neceſſary for the knitting of fet bones.

CHAP. XXI.

Of the Fracture of the Thigh nigh to the Joint, or the upper or lower head of the bone.

A Fracture ſometimes happens at the joint of the hip in the neck of the thigh-bone, as I once obſerved in an honeſt Matron. I being called to her, when I had obſerved the hurt thigh to be ſhorter than the whole, with the outward prominency of the *Iſchium*, which at the firſt ſight I ſuppoſed to proceed from the head of the thigh-bone, I preſently perſwaded my ſelf it was a Diſlocation and no Fracture; I then therefore extended the bone, and forced (as I thought) the head thereof into its cavity. The equality of both the legs in bigneſs which followed upon this extenſion, increaſed my perſuaſion that it was a diſlocation. The next day I viſited her the ſecond time, and found her in great pain, her hurt leg the ſhorter, and her foot wreſted inwards. Then I looſed all her ligatures, and perceived ſuch a prominency as I did formerly: Wherefore I endeavoured again to force in the head of the bone, as I formerly did; but as I was buſied therein, I heard a little crackling, and alſo I conſidered that there was no cavity nor depreſſion in the joint, by which ſigns I certainly perſuaded my ſelf that the bone was broken, and not diſlocated. Neither onely ſuch kind of Fractures, but alſo the ſeparation of the *appendix* or head of this bone from its place, may induce one to think it a diſlocation; which thing hath ſometimes deceived ſome heedleſs Surgeons, who have not dreamt of the divulſion or ſeparation of the *appendix*

A Hiſtory.

Another Fracture of the Thigh, reſembling a luxation.

appendix from the top of the thigh-bone, but have judged it onely a diſlocation. Then therefore (that I may return to my former narration) I ſet the bone, and joined the fragments together, laid thereupon ſplints with compreſſes, made ligations with a rowler, having two heads wrapped about the joint, and the body croſs-wiſe, and I defended her foot with a caſe, that none of the cloths might preſs it: I faſtned a rope to a poſt, and ſo let it come down into the midſt of the Bed, and tied many knots thereon, for the better taking hold and lifting up her ſelf; the which thing you muſt always do in Fractures and Diſlocations of the Thigh and Leg, that ſo your Patients may have ſome ſtay, whereby they may ſuccour themſelves with their hands as oft as they deſire to riſe or lift themſelves up in their Beds, or go to ſtool; as alſo, that they may give perſpiration, and as it were ventilation to the loins, buttocks, rump, and other parts, compreſſed and wearied with long lying, for want whereof they are moleſted with heat and pain, whence Ulcers ariſe, which oft-times torment the Patient with ſuch tormenting heat and pain, that he is even conſumed by a Fever, watchings, and want of reſt. This opportunity of raiſing the body out of the Bed, is by ſo much the more needful in this place, by how much the Fracture is nearer the joint; for there it is more dangerous than in the midſt of the thigh, and conſequently more difficult to dreſs and heal, for that the part is bloudleſs, and by reaſon of the multitudes of the Nerves, Tendons, and Ligaments, which are obnoxious to many malign ſymptoms: But the Surgeon muſt have diligent care in this kind of Fracture, and muſt look often that the bone which is ſet do not fall forth again, which eaſily happens here by any light ſtirring of the body, and the like occaſion, for that the thigh hath but one onely bone: Therefore as oft as the Bandages ſhall be looſed, and the Fracture dreſſed, he ſhall attentively view the figure of the bone, and the magnitude of the affected part, comparing it with the ſound; for the ſet and compoſed fragments of the broken bone can ſcarce fall aſunder, but that the one muſt lie upon the other. But before it be knit the part muſt be extended and reſtored to its ſtate, that ſo the Patient may not halt during the reſidue of his life: For I have read it written in *Avicen*, that ſcarce any do ſo well recover a fractured thigh, that they do not halt thereof; therefore the Patient muſt be careful that he move himſelf or his body as little as he can. Many of the Ancients have ſet down the time of the conſolidation of this bone to be fifty days: but (as I formerly ſaid) there can be no certain or determinate time hereof. But in what time ſoever this bone ſhall be knit the Patient muſt not ſtand or go thereon preſently upon it, for that there remains a weakneſs in the part a long time after, ſo that the Patients are forced to uſe Crutches to go withall, in the mean ſpace while they recover more ſtrength.

Why the Fracture of a bone near a joint is more dangerous.

Lib. 3. ſent. 6. tract. 1. c. 14.

In what ſpace the thigh-bone may be knit.

CHAP. XXII.

Of the Fracture of the Patella, *or Whirl-bone of the Knee.*

The Differences.

THe Whirl-bone of the Knee is oft-times contuſed, but not ſo frequently broken; yet when that happens, it goes into two or three pieces, ſometimes long-wiſe, ſometimes athwart; ſometimes it is broken in the midſt, and ſomewhiles ſhivered into many ſplinters, and all theſe either with or without a wound.

Signs.

The ſigns are, impotency in going, a hollowneſs in that place, and a ſenſible ſeparation of the fragments of the hurt part, and the crackling of theſe parts under your hand.

Cure.

It is ſet after this manner; wiſh the Patient to ſtretch forth his leg, yea, he muſt keep it extended all the while until it be knit; and therefore leſt he ſhould bend it unawares, the hollowneſs of the ham ſhall be filled with a boulſter; for by bending of the Knee the ſet fragments of the Whirl-bone would again fly in ſunder. This being done, the fragments ſhall by the hand of the Surgeon be ſet as is fitting, and be kept ſo ſet by the application of convenient remedies, making ligatures, and applying junks, as we ſaid muſt be done in the fracture of the thigh-bone. And laſtly, you muſt obſerve and do in this as in the fracture of a leg. For the Prognoſtick, this I affirm, that I have ſeen none of thoſe who have had this bone fractured who have not halted during the reſt of their lives. The cauſe hereof is, the knitting by the concretion of a *Callus* hinders the free bending of the Knee; going, eſpecially on even ground, is more eaſie to the Patient, but an aſcent is far more difficult, and abſolutely painful. The Patient muſt neceſſarily for this kind of Fracture lie or keep his Bed, at the leaſt for forty days.

Why thoſe halt who have had this bone fractured.

CHAP. XXIII.

Of a broken Leg.

Sent. 65. ſect. 2. de Fract.

THis kind of Fracture is cured after the ſame manner as that of the arm or cubit. *Hippocrates* admoniſheth us, that the *Tibia*, or leg-bone is more dangerous to be broken, and more difficult and ſlow to be healed than the *Fibula*, or ſhin-bone; becauſe that is the thicker, and as it were the upholder of the whole bulk of the body; but this other is but as it were a certain additament or aſſiſtant, provided for the ſtaying or bearing up of the muſcles of the leg, by which the foot is moved. The leg-bone being only broken, the ſigns thereof are perceived only in the inner part of the leg; for that the ſhin-bone being whole, ſuffers it not to throw or caſt forth it ſelf. On the contrary, when the ſhin-bone only is broken, the ſigns thereof appear only in the external part of the leg; becauſe the leg-bone being oppoſed thereto, doth not ſuffer it to caſt in it ſelf, and with its fragments to turn inwards: But when both the bones are broken, the ſigns of the Fracture may equally appear both here and there. But when only one of theſe bones are broken, the Fracture is far more eaſie to dreſs and heal, becauſe that which remains whole, is a much more firm ſtay to that which is hurt than any ſplints can be. But that I may the better inſtruct and make ready the Surgeon for the reſtoring

Sign that both the bones are broken.

of

of this Fracture, I will illuſtrate the matter by an example from my ſelf. *John Neſtor*, Doctor of Phyſick, *Richard Hubert*, and I, went together to viſit a Patient at the place of the Frier Minorites. Wherefore, intending to paſs over the *Sein* within ſight of the place, I endeavoured to make my horſe take boat, and therefore ſwitched him over the buttocks: The Jade, madded herewith, ſo ſtruck at me with his heels that he brake both the bones of my left leg, ſome four fingers bredth above my ankle. Then I, fearing ſome worſe miſchief, and leſt the Jade ſhould double his blow, flew back; and as I fled back, the broken bones flew in ſunder; and breaking through the fleſh, ſtocking, and boot, ſhewed themſelves, whereby I felt as much pain as it is credible a man was able to endure; wherefore I was preſently carried into the Boat, that ſo I might be carried to the other ſide of the Water to be dreſſed; but the ſtirring of the Boat as they rowed, almoſt killed me with bitterneſs of pain, for that the ſharp fragments of the bones were rubbed againſt the fleſh which lay next them. Being ferried over, as I was conveyed into the next houſes, my pain was much increaſed, whileſt lifted by the hands of divers perſons, one while up another down, ſometimes to the left ſide, other whiles to the right with my whole body, and all the parts thereof. When at the length I was laid upon a bed, I was ſomewhat freed from the bitterneſs of my pain, and had time to wipe off the ſweat which ran down over all my body. Then was I dreſſed with ſuch a Medicin as the time and place would afford, we compoſed it of the White of Egg, Wheat-flour, Soot of a Chimney, and melted Butter. For the reſt, I entreated *Richard Hubert* that he would handle me as if he knew me not, neither that moved for love of me, he ſhould remit any thing of the ſeverity of Art, but chiefly, that he would ſtretch my foot ſtraight out, and if the wound were not ſufficiently wide, that he would enlarge it with his Inciſion-knife, that ſo he might the more eaſily ſet the broken bones in their due place; that he would with his fingers (whoſe judgment is far more certain than the beſt made inſtruments) ſearch, whether the ſplinters which were in the wound were quite ſevered from the bone, and therefore to be taken forth; that he would with his hand preſs forth the bloud, and the clods of bloud which were in a great quantity concrete at the mouth of the wound; that he would bind up and place my leg in that ſite and manner as he thought beſt; which is, that he would have three rowlers in a readineſs, the firſt whereof he ſhould caſt directly upon the wound, ſo that he ſhould begin his ligation at the wound: alſo he ſhould put ſplints about it, ſome three, but others two fingers bredth, of the length of half a foot, ſomewhat depreſſed and hollowed, whereby they might be the more eaſily put about the leg, more ſtraitly at their ends, and a fingers diſtance each from other, which at the laſt he ſhould bind with fillets, like thoſe wherewith Women uſe to bind up their hair; yet ſo that the binding might be more ſtraight upon the wound; and that he would fill the cavity of the ham and of the ankles with bouſters made of flax wrapped in linnen cloths: that he would fortifie the ſides of my leg with Junks made of bents or little ſticks, and lined with linnen cloth, ſtretched from my heel to my groin, and bound over in four places; ſo that the ſtraight figure of the leg might ſcarcely be perverted by any force: that he would gently and ſmoothly lift up my leg to an indifferent height: and laſtly, that he ſhould arm it from the violence of external injuries, by putting it in a Box or Caſe. But you muſt note, that the fit placing or laying of the Leg is a matter of ſuch moment, that if any errour be here committed, it will cauſe no leſs then lameneſs: For if it be lifted up higher than is fit, the *Callus* will be hollow on the foreſide; if lower, then it will be gibbous or bunching forth. Neither alſo do they commit a ſmall errour, who do not fill up the cavities at the ancles after the afore-mentioned manner: for, hereupon the heel will be much afflicted, whileſt it is forced to ſuſtain a tedious and painful compreſſion, which at length brings a hot diſtemper, becauſe the ſpirits cannot freely flow thereto; which I finding by experience, not knowing the cauſe, wiſhed them ever now and then to lift up my heel, whereby it might enjoy the benefit of perſpiration, and the ſpirits have free entrance thereinto, and the contained vapours paſſing forth. To conclude, my hurt leg was laid upon a cuſhion, after the manner you ſee here deſcribed.

A Hiſtory.

A ſoon made Medicin.

What to do when the Leg is broken.

The figure of a Leg fractured with a Wound, and bound up.

CHAP. XXIV.

Of ſome things to be obſerved in Ligation, when a Fracture is aſſociated with a Wound.

THis taken out of the doctrine of the Ancients, ought to be kept firm and ratified; that ligation muſt be made upon the Wound, otherwiſe the wounded part will preſently lift it ſelf up into a great tumor, receiving the humours preſſed thither by the force of the ligation made on this and that ſide, above and below, whence enſue many malign ſymptoms. You may make trial hereof upon a ſound fleſhy part; for if you bind it above and below, not touching that which is in the midſt, it will be lifted up into a great tumor, and change the flouriſhing and native colour into a livid or blackiſh hue, by reaſon of the flowing and abundance of the humours preſſed forth on every ſide from the neighbouring parts. Therefore ſuch things will happen much the rather in a wounded or ulcerated part: But for this cauſe the Ulcer will remain unſuppurated and weeping, crude and liquid *Sanies* flowing there-hence, like unto that which uſually flows from inflamed Eyes: Such *Sanies*, if it fall upon the bones, and make any ſtay there, it, with the touch thereof, burns and corrupts them, and ſo much the more, if they be rare and ſoft. Theſe will be the ſigns

That the ligation muſt be moſt ſtrait upon the wound.

What ſymtoms enſue the want of binding upon the wounded part

Signs of the corruption of the bones.

of ſuch corruption of the bones; if a greater quantity, and that more filthy *ſanies* flow from the Ulcer than was accuſtomed, or the nature of a ſimple Ulcer requires; if the lips of the Ulcer be inverted, if the fleſh be more ſoft and flaccid about them, if a ſorrowful ſenſe of a beating, and alſo deep pain torment the Patient by fits; if, by ſearching with your probe, you perceive the bone to be ſpoiled of its *periſteum*; and laſtly, if you find it ſcaly and rough; or alſo, if your probe be put down ſomewhat hard, it run into the ſubſtance of the bone. But we have treated ſufficiently hereof in our particular Treatiſe of the rottenneſs of the bones; but certainly ſuch rottenneſs will never happen to the bone, if the hurt part be bound up as is fit, and according to Art. Wherefore I judge it not amiſs again to admoniſh the Chirurgeon of this, that as far as the thing ſhall ſuffer, he make his rowlings upon the wound, unleſs by chance there be ſuch exceſſive pain and great inflammation, that through occaſion of ſuch ſymptoms and accidents, he be diverted from this proper and legitimate cure of the diſeaſe: Therefore then, becauſe nothing more can be done, let him onely do this which may be done without offence; that is, let him ſupply the defect of ligation and rowlers, with a linnen cloth, not too weak, nor too much worn, being twice or thrice doubled, and which may ſerve to compaſs the wound and neighbouring parts once about: let him ſew the edges thereof at the ſides of the wound, leſt he be forced to ſtir the fragments of the bones (which once ſet ought to be kept unmoved) as often as the wound comes to be dreſſed. For, broken bones do not require ſuch frequent dreſſing as Wounds and Ulcers do. By this it appears, that as want of binding, and too much looſneſs in abſence of pain and a phlegmon, ſo alſo too ſtrait ligation when pain is preſent, brings a phlegmon and abſceſs to the Wound: Therefore let all things here, according to the forementioned rules and circumſtances be indifferent. I have for this purpoſe thought good to reiterate theſe things, becauſe you ſhall as yet find many, who follow the practice of *Paulus*, and make many circumvolutions here and there, above and below the wound, which preſently they carry croſs-wiſe. But this croſs or Lattice-like kind of ligation is wholly to be diſliked, and that onely to be uſed which we have deſcribed, according to the mind of *Hippocrates*. Now it is time that I return to the former Hiſtory of my miſhap, and declare what was done to me after that firſt dreſſing, which I have formerly mentioned.

When the wounded part muſt be omitted in ligation

Lattice-like binding to be ſhunned.

CHAP. XXV.

What was uſed to the Authors Leg after the firſt dreſſing.

I Being brought home to mine own houſe in *Paris* in the afternoon, they took from me, out of the Baſilica of the left arm, ſome ſix ounces of bloud: And then at the ſecond dreſſing the lips or edges of the wound and places thereabout were anointed with *unguentum roſatum*, which by a joint conſent of the Ancients, is much commended in the beginnings of fractures; for it will aſſwage pain, and hinder inflammation, by repelling the humours far from the wounded part: for it is cold, aſtringent and repelling, as the compoſition thereof ſhews; for it is made *ex oleo omphacino, aqua roſacea, pauco aceto, & cera alba.* Therefore I uſed this ointment for ſix days; I dipped the compreſſes and rowlers ſomewhiles in Oxycrate, otherwiles in thick and aſtringent red Wine, for the ſtrengthening of the part, and repreſſing the humours; which two things we muſt have a care of in *Hippocrates* opinion, in Fractures eſpecially with a wound: Wherefore if at any time the compreſſes or rowlers ſeemed to dry, I now and then moiſtned them with the Oxycrate or Roſe Vinegar: for, by their too much dryneſs, pain and inflammation happen; and if they bind the part ſomewhat more ſtrait, they hurt it alſo by their hardneſs. You ſhall ſee many Surgeons, who in this kind of affect, from the beginning to the end, uſe onely aſtringent and emplaſtick Medicins, wholly contrary to the method ſet down by *Hippocrates*, and commended by *Galen:* For, by the continued uſe of ſuch things, the pores and breathing-places of the skin are ſhut up; whence the fuliginous excrement being ſuppreſt, the external heat is increaſed, and itching cauſed, and at length an Ulcer by the fretting of the acrid and ſerous humour long ſuppreſt: Whereby you may learn, that aſtringent and emplaſtick Medicins muſt not be uſed above ſix days: In ſtead hereof you ſhall uſe the emplaiſters, which I ſhall preſently deſcribe. In the beginning of my diſeaſe I uſed ſo ſpare a diet, that for nine days I ate nothing each day but twelve ſtewed Prunes, and ſix morſels of bread, and drank a *Paris* pint of ſugred Water, of which Water this was the compoſition. ℞ *Sacc. albiſ.* ʒ xij. *aquæ font.* ℔ xij. *cinam.* ʒ iij. *bulliant ſimul ſecundum artem:* Otherwiles I uſed Syrup of Maidens-hair with boiled Water: Otherwiles, the divine drink (as they term it) whereof this is the compoſition. ℞ *Aquæ cochæ* ℔ vj. *ſacc. albiſ.* ℥ iv. *ſucc. lim.* ℥ j. *agitentur & tranſvaſentur ſæpius in vaſis vitreis:* I was purged when need required with a bole of *Caſſia* with Rubarb: I uſed alſo Suppoſitories of Caſtle-Soap to make me go to ſtool; for, if at any time I wanted due evacuation, a preternatural heat preſently ſeized upon my kidnies: With this, though exquiſite manner of diet, I could not prevail, but that a Fever took me upon the eleventh day of my diſeaſe, and a defluxion, which turned into an abſceſs, long flowing with much matter: I think the occaſion hereof was ſome portion of the humour ſuppreſt in the bottom of the wound; as alſo by too looſe binding, by reaſon that I could not endure juſt or more ſtrait binding; and laſtly, ſcales or ſhivers of bones quite broke off, and therefore unapt to be agglutinated: for theſe therefore putrefying, drew by conſent the proper nouriſhment of the part into putrefaction, and by the putredinous heat thence ariſing, did plentifully adminiſter the material and efficient cauſe to the defluxion and inflammation. I was moved to think they were ſcales ſevered from their bone by the thin and crude *ſanies* flowing from the wound, the much ſwoln ſides of the wound, and the more looſe and ſpongy fleſh thereabouts. To theſe cauſes this alſo did accrew, one night amongſt the reſt, as I ſlept, the muſcles ſo contracted themſelves by a violent motion, that they drew my whole leg upwards; ſo that the bones, by the vehemency of the convulſion, were diſplaced, and preſſed the ſides of the wound; neither could they be perfectly compoſed or ſet, unleſs

Unguentum Roſatum, wherefore good in Fractures.

You muſt have a care that the compreſſes and rowlers grow not hard by drineſs.

The deſcription of a ſugred Water.

The cauſes of a Fever and Abſceſs, enſuing upon a Fracture.

Signs of ſcales ſevered from their bones.

unleſs by a new extenſion and impulſion, which was much more painful to me than the former. My Fever when it had laſted me ſeven days, at length enjoyed a *criſis* and end, partly by the eruption of matter, and partly by ſweat, flowing from me in a plenteous manner.

CHAP. XXVI.

What may be the cauſe of the convulſive twitching of broken Members.

Why the extreme parts are cold when we ſleep.

THis contraction, and (as it were) convulſive twitching, uſually happens to fractured members in the time of ſleep. I think the cauſe thereof is, for that the native heat withdraws it ſelf while we ſleep, into the center of the body; whereby it cometh to paſs, that the extreme parts grow cold. In the mean while Nature by its accuſtomed providence, ſends ſpirits to the ſupply of the hurt part: But becauſe they are not received of the part evil affected and unapt thereto, they betake themſelves together, and ſuddenly, according to their wonted celerity, thither from whence they came, the muſcles follow their motion; with the muſcles the bones whereinto they are inſerted, are together drawn; whereby it comes to paſs, that they are again diſplaced, and with great torment of pain, fall from their former ſeat. This contraction of the Muſcles is towards their original.

CHAP. XXVII.

Certain documents concerning the parts whereon the Patient muſt neceſſarily reſt whileſt he lies in his Bed.

The natural faculties languiſh in the parts by idleneſs, but are ſtrengthened by action.

How and what Ulcers happen upon the fracture of the leg, to the rump and heel.

THoſe who have their leg or the like bone broken, becauſe they are hindered by the bitterneſs of pain, and alſo wiſh for their cure or conſolidation, are forced to keep themſelves without ſtirring, and upon their backs in their beds for a long time together. In the mean ſpace the parts whereupon they muſt neceſſarily lie, as the heel, back, holy-bone, rump, the muſcles of the broken thigh or leg, remain ſtretched forth and unmovable, ſet at liberty from their uſual functions: Whereby it comes to paſs that all their ſtrength decayes, and grows dull by little. Moreover alſo, by the ſuppreſſion of the fuliginous and acrid excrements, and want of perſpiration, they grow preternaturally hot; whence defluxion, an abſceſs and ulcer happen to them, but principally to the holy-bone, the rump, and heel: to the former, for that they are defended with ſmall ſtore of fleſh; to the latter, for that it is of more exquiſite ſenſe. Now the Ulcers of theſe parts are difficultly healed, yea, and oft-times they cauſe a gangrene in the fleſh, and a rottenneſs and mortification in the bones thereunder, and for the moſt part a continued Fever, *delirium*, convulſion, and (by that ſympathy which generally accompanies ſuch affects) a hicketing: For the heel and ſtomach are two very nervous parts, the latter in the whole body thereof, and by a large portion of the Nerves of the ſixt conjugation; but the other by the great tendon paſſing under it, the which is produced by the meeting, and as it were growing together of the three muſcles of the calf of the leg. All which are deadly both by diſſipation of the native heat by the feveriſh, and that which is preternatural; as alſo by the infection of the noble parts, whoſe uſe the life cannot want, by carrion-like vapors. When as I conſidered all theſe things with my ſelf, and (become more skilful by the example of others) underſtood how dangerous they were, I wiſhed them now and then to lift my heel out of the bed; and taking hold of the rope which hung over my head, I heaved up my ſelf, that ſo the parts preſſed with continual lying, might tranſpire and be ventilated. Moreover alſo I reſted theſe parts upon a round cuſhion, being open in the middle, and ſtuffed with ſoft feathers, and laid under my rump and heel, that they might be refreſhed by the benefit and gentle breathing of the air: and I did oft-times apply linnen cloths ſpred over with *unguentum roſatum*, for the aſſwaging of the pain and heat: Beſides alſo, I deviſed

The Figure of a Caſſe.



A A *Shews the bottom or belly of the Caſſe.* B B *The wings or ſides to be opened and ſhut at pleaſure.* C *The end of the wings, whereto the ſole or arch is fitted.* D D *The Arch.* E E *The Sole.* F F *An open ſpace whereat the heel hangs forth of the Caſſe.*

Remedies for the prevention of the aforeſaid Ulcers.

The uſe of a Lattin Caſſe.

deviſed a Caſſe of Lattin, wherein the broken Leg being laid, is kept in its place, far more ſurely and certainly than by any Junks; and moreover alſo it may all be moved to and again at the Patients pleaſure. This Caſſe will alſo hinder the heel from lying with all its body and weight upon the Bed, putting a ſoft and thick boulſter under the calf, in that place where the Caſſe is hollow: beſides alſo, it arms and defends it againſt the falling down and weight of the bed-cloths, having a little arch made over and above of the ſame matter: All which ſhall be made manifeſt unto you by the precedent figure. Now it remains that I tell you what remedies I applied to the abſceſs which happened upon my wound. When therefore I perceived an abſceſs to breed, I compoſed a ſuppurative Medicin of the yolks of Eggs, common Oil, Turpentine, and a little Wheat-flour, and I uſed it till it was opened; then to cleanſe it I uſed this following remedy. ℞ *Syrupi roſati & terebinth. venetæ, an.* ℥ ij. *pulveris radicis ireos florentiæ, aloes, maſtiches, farinæ hordei, an.* ʒ ß. *incorporentur omnia ſimul, & fiat mundificativum:* but I had a care that the place whereat I conjectured the quite ſevered ſcales of the bones muſt break forth, ſhould be filled with tents made of ſponge or flax, that ſo by this means I might keep the Ulcer open at my pleaſure: But I put into the bottom of the Ulcer catagmatick and cephalick Powders, with a little burnt alum, to procure the egreſs of the formerly mentioned ſcales. Theſe at length caſt forth, I cicatrized the Ulcer with burnt alum; For, this having a drying and aſtringent faculty, confirms and hardens the fleſh, which is looſe and ſpongy, and flowing with liquid *ſanies*, and helps forward Natures endeavour in cicatrization. For, the fragments of the bones, they by reaſon of their natural drineſs and hardneſs, cannot be joined and knit together by themſelves without a *medium:* but they need a certain ſubſtance, which thickning and concreting at their ends, doth at length glue them together, and (as it were) faſten them with ſoder. This ſubſtance hath its matter of the proper ſubſtance and marrow of the bones; but the former from the native heat, and emplaſtick Medicins, which moderately heat. For on the contrary, theſe Medicins, which by their too much heat, do diſcuſs and attenuate, do (as it were) melt and diſſolve the matter of the *Callus*, and ſo hinder the knitting: Wherefore for this purpoſe, I would wiſh you to make uſe of the following emplaſters, of whoſe efficacy I have had experience; for, hence they are called knitting or conſolidating plaſters. ℞ *Olei myrtil. & roſarum omphac. an.* ℔ ß. *rad. altheæ* ℔ ij. *rad. fraxini, & fol. ejuſd. rad. conſolidæ majoris & fol. ejuſd. fol. ſalicis, an.* m. j. *fiat decoctio in ſufficiente quant. vini nigri, & aquæ fabrorum, ad medietatis conſumptionem, adde in colatura pulveris myrrhæ & thuris an.* ℥ ſ. *adipis hirci,* ℔ ß. *terebinth. lotæ* ℥ iv. *maſtiches,* ʒ iij. *litharg. auri & argenti, an.* ℥ ij. *boli armeniæ, & terræ ſigillatæ an.* ℥ j. ſ. *minii* ʒ vj. *ceræ albæ quantum ſufficit: fiat emplaſtrum, ut artis eſt.* Inſtead hereof you may uſe the black emplaſter, whereof this is the deſcription. ℞ *Litharg. auri* ℔ j. *olei & aceti* ℔ ij. *coquantur ſimul lento igne donec nigrum & ſplendens reddatur emplaſtrum, & non adhæreat digitis.* Or elſe, ℞ *Olei roſat. & myrtil. an.* ℥ ij. *nucum cupreſſi, boli armen. ſanguinis drac. pulveriſatorum an.* ℥ ß. *emplaſt. diacalcitheos* ℥ iv. *liquefaciant ſimul & fiat emplaſtrum ſecundum artem.* In defect of theſe, you may uſe a Cerecloth, or *Tela Gualteri*, whereof this is the deſcription. ℞ *Pulveris thuris, farinæ volatilis, maſtiches, boli arm. reſinæ pini, nucum cupreſſi, rubiæ tinctorum, an.* ℥ ij. *ſevi arietini & ceræ albæ, an.* ℔ ſ. *fiat emplaſtrum:* into which (whileſt it is hot) dip a warm linnen cloth, for the forementioned uſe. *Emplaſtrum Diacalcitheos*, by the common conſent of all the Ancients, is much commended for Fractures; but it muſt undergo different preparations, according to the condition of the time, for in the Summer it muſt be diſſolved in the juice of Plantain and Nightſhade, leſt it ſhould heat more than is fit. It is convenient in the interim to have regard to the temper of the affected bodies; for neither are the bodies of children to be ſo much dried as theſe of old men: otherwiſe if ſuch drying Medicins ſhould be applied to young bodies as to old, the matter of the *Callus* would be diſſolved, it would be ſo far from concreting; wherefore the Surgeon muſt take great heed in the choice of his Medicins: For often-times remedies good of themſelves, are by uſe made not good, becauſe they are uſed and applied without judgment; which is the cauſe that oft-times pernicious accidents happen, or elſe the *Callus* becomes more ſoft, hard, ſlender, crooked; or laſtly, concretes more ſlowly by the great errour, and to the great ſhame of the Surgeon.

A ſuppurative Medicin.

A deterſive.

Catagmatick Powders have power to caſt forth the ſcales of bones

The cauſes both efficient and material of a *Callus*.

Medicins conducing to the generation of a *Callus*.

The black Plaſter.

The deſcription of a *Sparadrapum*, or Cerecloth.

Medicins good of themſelves, not good by event.

CHAP. XXVIII.

By what means we may know the Callus is a breeding.

When the *Callus* is breeding the Ulcer muſt be ſeldom dreſt.

THen I knew that my Leg begun to knit, when as leſs matter than was uſual came from the Ulcer, when the pain ſlackned, and laſtly, when as the convulſive twitchings ceaſed; which cauſed me to judge it fit to dreſs it ſeldomer than I was uſed to do: For, by the frequent deterſion in dreſſing an Ulcer, whileſt a *Callus* is breeding, the matters whereof it is to be made, are drawn away and ſpent, which are (as they term them) *Ros*, *Cambium*, and *Gluten*, which are the proper and genuine nouriſhments both of the bony, as alſo of the fleſhy ſubſtance. I by other ſigns alſo conjectured the breeding of the *Callus*, to wit, by the ſweating of a certain dewy bloud out of the edges and pores of the wounds, which gently died and bedewed the boulſters and ligatures, proceeding from the efflux of the ſubtler and gentler portion of that matter, which plenteouſly flowed down for the breeding of a *Callus*. As alſo by a tickling and pleaſing ſenſe of a certain vapour continually creeping, with a moderate and gentle heat, from the upper parts even to the place of the wound. Wherefore thenceforwards I ſomewhat looſened the ligation, leſt by keeping it too ſtrait, I ſhould hinder from entering to the fragments of the bones, the matter of the *Callus*, which is a portion of the bloud, temperate in quality, and moderate in quantity. Then therefore I thought good to uſe nouriſhments fit to generate more groſs, thick, and tenacious bloud, and ſufficient for generating a *Callus*; ſuch as are the extremities, tendinous, and griſly parts of Beaſts, as the heads, feet, legs, and ears of Hogs, Oxen, Sheep, Kids; all which I boiled with Rice, French Barley, and the like, uſing ſomewhiles one, ſomewhiles another, to pleaſe my ſtomach and palate. I alſo ſometimes fed upon Frumity,

Hipp. ſent 43. ſect. 1. de fract.

Meats fit for generating a *Callus*.

mity, or Wheat ſodden in Capon broth with the yolks of Eggs; I drank red, thick and aſtringent Wine, indifferently tempered with Water. For my ſecond courſe, I ate Cheſnuts and Medlars. Neither do I without ſome reaſon, thus particularize my diet; for that groſs nouriſhments, eſpecially if they be friable and fragil, as Beef is, are alike hurtful (for as much as pertains to the generating of a *Callus*) as light meats are; for that makes the *Callus* too dry, theſe too tender. Wherefore *Galen* pronounces thoſe meats onely fit for generating a *Callus*, which are neither fragil nor friable, neither ſerous and thin, nor too dry; but indifferent groſs, and alſo viſcid, fat and tough. Theſe meats digeſted by the ſtomach into *chylus*, are ſent into the Guts, and from hence, by the meſaraick veins into the gate vein, and the hollow part of the Liver, thence into the hollow-vein, and ſo into the veins diſperſed over all the body and parts thereof. There are alſo ſome of theſe veins which carry bloud into the bones, but in the large cavities of the bones is marrow contained, as in the ſmall, a certain marrowy ſubſtance, proportionable thereto, being their proper nouriſhment. The generation of marrow is from the groſſer portion of the bloud, which flows into the greater cavities of the bones by larger Veins and Arteries, but into the leſs by leſſer, which end in their pores and ſmall paſſages: For in large bones you may obſerve large and apparent paſſages, by which the Veins and Arteries enter for the fore-mentioned uſe. By the ſame ways the Nerves alſo inſinuate themſelves, from whence proceeds a membrane which involves the marrow of the bones, the which by that means is indued with moſt exquiſite ſenſe, as experience teacheth; which is the cauſe that makes many believe that the marrow hath ſenſe of feeling, becauſe the membranes thereof being hurt cauſe moſt bitter pain. Therefore out of the marrow and the proper ſubſtance of the bone, there ſweats a certain groſs and terreſtrial juice, whereof by the power of the aſſimilating faculty, which ſerves in ſtead of the formative, a *Callus* grows and knits. Simple fractures of the leg are uſually knit in fifty days, but through the occaſion of the Wound, and the ſcales quite broke off, and other accidents which befel me, it was three whole Moneths before the fragments of the bones were perfectly knit, and it was alſo another Moneth before I could go upon my Leg without the help of a Crutch. Going was painful to me for ſome few days, becauſe the *Callus* had taken up ſome place of the muſcles: for before my former freedom of motion could return again to the broken and knit part, it was neceſſary that the tendons and membranes ſhould ſeparate themſelves by little and little from the ſcar. In the performance of all theſe things, I had the diligent and faithful aſſiſtance amongſt the Surgeons, to omit Phyſicians, of *Anthony Portal* the Kings Surgeon.

Lib.6.Meth.c.5.

Why the marrow may ſeem to have ſenſe of feeling.

In what ſpace the Leg is uſually knit.

CHAP. XXIX.

Of thoſe things which may hinder the generation of a Callus, *and how to correct the faults thereof, if it be ill-formed.*

HAving already ſpoken of the ſigns of a *Callus* beginning to concrete, of its generation and the manner thereof: it now remains that we treat of thoſe things which hinder the generation thereof; and what on the contrary help forwards the conformation and concretion thereof. Now theſe things which either wholly hinder, or elſe retard the generation of a *Callus*, have a ſtrong and powerful diſcuſſive and attenuating faculty; or elſe they are unctuous, oily, and moiſt,: For by ſuch, the juice, whereof the *Callus* ought to be, is either melted and conſumed, or elſe grows ſoft, and is relaxed. But on the contrary, thoſe things which help forwards a *Callus*, muſt be drying, incraſſating, thickning, hardning, and emplaſtick, moderately hot and aſtringent: But for moiſt and relaxing Medicins, they ought to have no place here, unleſs when it happens that the *Callus* is ill formed, that is, too thick, or crooked, or otherwiſe ill ſhapen, whereby it may be waſted and broken, ſo to be reſtored again after a better manner. Yet notwithſtanding, ſuch things are not to be attempted, unleſs when the *Callus* is yet green, and ſo depraved that the fault thereof doth very much pervert the native conformation of the part, and exceedingly offend the action: Then therefore in ſuch caſe the place muſt be fomented with a decoction of a Sheeps-head and guts, wherein ſhall be boiled the roots of Marſh-mallows, of Briony, the ſeeds of Line, Fænugreek, Pigeons-dung, Bay-berries, and the like. You ſhall alſo uſe this following Ointment and Plaſter. ℞ *Unguenti de Althæa* ℥ iv. *olei liliorum, & axungiæ anſeris, an.* ℥ j. *aquæ vitæ parum, liquefiant ſimul, fiat linimentum, quo linatur pars.* Then apply this following Emplaſter. ℞ *Emplaſt. de Vigo cum Mercurio, cerati æſypati, deſcriptione Phylagrii, an.* ℥ iij. *olei anethini & liliorum, an.* ℥ j. *liquefiant omnia ſimul, fiat emplaſtrum*; let it be ſpread upon leather for the aforeſaid uſe. When by this means the *Callus* ſhall ſeem to be ſufficiently mollified, it ſhall be broken, and the bones reſtored to their natural ſtate, and the cure of the Fracture to be followed as at the beginning. If the *Callus* be become too hard through age, it is better not to break it, but to let it alone, leſt ſome worſe accident befall the Patient: For it may ſo fall out, that by your labouring to break it, the bone may break in ſome other part, before it break in that which is knit by the *Callus*; therefore the diſcreet Patient had rather live lame, than for eſchewing it, to undergo the hazard of his life. If the *Callus* be too groſs, it ſhall be diminiſhed (if it be as yet freſh) with emollient, reſolving, and powerfully aſtringent Medicins, which have force to diſſolve, dry and exhauſt. It will alſo be good ſtrongly to rub the *Callus* with Oil of Bays, wherein Salt-petre, or ſome other kind of Salt hath been diſſolved, then wrap it about with a rowler to bind it very ſtraitly, putting a leaden plate thereon, whereby the flowing down of the nouriſhing humour into the part, may be forbidden, that thus by little and little the *Callus* may decay and diminiſh. If on the contrary it any ways happen that the *Callus* be more thin and ſlender, and grows more ſlowly, for that it is too ſtraitly bound, or becauſe the idle part is longer kept in quiet than is fit, without exerciſing of its proper function, (which cauſe is to be reckoned amongſt the chief cauſes of the leanneſs, even for this reaſon, for that exerciſe ſtirs up the native heat of the part, the worker of digeſtion and nutrition) or elſe for that they feed upon ſuch nouriſhments as offend in quality or quantity,

Diſcuſſing and unctuous Medicins hinder the generation of a *Callus*. What helps forward the generation thereof.

What *Callus* muſt not be broken, though diſtort, or otherwiſe ill-conformed.

The cauſes of too ſlender a *Callus*.

Remedies therefore

quantity, or both; or for that the ligature uſed to the part is too often looſed, or becauſe the part it ſelf is too haſtily, and before the time put to undergo ſolid offices and motions. According to the variety of cauſes medicins ſhall be applied; for if the ligature of the part be too ſtrait, it ſhall be looſed, yea, verily the fractured place, the ligature being taken away, ſhall be quite freed from ligation, and a new kind of ligature muſt be made, which muſt be rowled down from the root of the Veſſels, that is, from the arm-pits, if the arm; or from the groin, if the leg be broken, to the fracture; yet ſo, as that you may leave it untouched or taken in, for thus the bloud is preſſed from the fountain and ſpring, and forced into the affected part, by a way quite contrary to that whereby we have formerly taught, in fear of inflammation, to hinder it from entrance into the affected part: Alſo gentle frictions and fomentations with warm water may be profitably made, from which you muſt then deſiſt, when the part ſhall begin to grow hot and ſwell. If any too long continue theſe frictions and fomentations, he ſhall reſolve that which he hath drawn thither: For this we have oftentimes obſerved, that frictions and fomentations have contrary effects, according to the ſhortneſs and continuance of time. Pications will alſo conduce to this purpoſe, and other things which cuſtomarily are uſed to members troubled with an *atrophia*, or want of nouriſhment.

When we muſt deſiſt from fomenting and frictions.

CHAP. XXX.

Of fomentations which be uſed to broken bones.

Warm Water. The effects thereof.

Divers fomentations are uſed to broken bones for ſeveral cauſes. When we uſe warm water for a fomentation, we mean that which is juſt between hot and cold, that is, which feels lukewarm to the hand of the Phyſician and Patient. A fomentation of ſuch water uſed for ſome ſhort ſpace, doth moderately heat, attenuate, and prepare for reſolution, the humour which is in the ſurface of the body, it draws bloud and an alimentary humour to the part labouring of an *atrophia*, it aſſwages pain, relaxes that which is too much extended, and moderately heats the member refrigerated through occaſion of too ſtrait binding, or by any other means: On the contrary, too hot fomenting cools by accident, digeſting, and diſcuſſing the hot humour which was contained in the member. We mean a ſhort time is ſpent in fomenting, when the part begins to grow red and ſwell; a juſt ſpace, when the part is manifeſtly red and ſwollen: but we conjecture, that much or too much time is ſpent thereon, if the redneſs which formerly appeared go away, and the tumor which lifted up the part, ſubſide. Alſo in fomenting, you muſt have regard to the body whereto it is uſed: For if it be plethorick, an indifferent fomentation will diſtend the part with plenty of ſuperfluous humours; but if it be lean and ſpare, it will make the part more fleſhy and ſucculent. Now it remains that we ſay ſomewhat of the fracture of the bones of the Feet.

Notes of ſhort, juſt, and too long fomenting.

Fomentations hurt plethorick bodies.

CHAP. XXXI.

Of the Fracture of the bones of the Feet.

Why the fractured bones of the foot muſt be kept in a ſtrait poſture.

The bones of the inſtep, back and toes of the Feet, may be fractured as the bones of the hands may: Wherefore theſe ſhall be cured like them, but that the bones of the toes muſt not be kept in a crooked poſture, as the bones of the fingers muſt, leſt their action ſhould periſh or be depraved; for as we uſe our legs to walk, ſo we uſe our feet to ſtand: beſides alſo the Patient ſhall keep his bed until they be knit.

The End of the Fifteenth Book.

BOOK XVI.

Of DISLOCATIONS or LUXATIONS.

CHAP. I.

Of the Kinds and Manners of Diſlocations.

What a Luxation properly ſo called is. What a Luxation not properly ſo called is.

A Diſlocation is the departure or falling out of the head of a bone from its proper cavity into an accuſtomed place beſides nature, hindring voluntary motion. There is another kind of Luxation, which is cauſed by a violent diſtention, and as it were a certain divarication, and dilatation, or extenſion into length and bredth of the ligaments, and all the nervous bodies, which contain, ſtrengthen, and bind together the joints. Thus thoſe who have been tormented and racked, have that thick ligament which is in the inner cavity of the huckle bone too violently extended. Thoſe who have ſuffered the Strappado, have the ligaments encompaſſing the articulation of the arm-bone, with the ſhoulder blade, forcibly and violently diſtended. Such alſo is their affect, whoſe foot is ſtrained by ſlipping. There is a third kind of Luxation, when as thoſe bones which are joined contiguous, and one (as it were) bound to the ſides of another, gape or fly aſunder: as in the arm, when the Ell parts from the Wand; in the leg, when the one Focile flies from

The third kind of diſlocation.

from the other: yet this may be referred to the ſecond ſort of Diſlocations, becauſe it happens not without dilatation, or elſe the breaking of the ligaments. There is alſo a fourth added to theſe, as when the *Epiphyſes* and heads of bones are plucked from the bone whereon they were placed or faſtned; which unproperly called kind of Luxation, hath place chiefly in the bones of young people, and it is known by the impotency of the part, and by the noiſe and grating together of the crackling bones when they are handled. Now the bones of young folks are alſo incident to another caſualty; for as the bones of old people are broken by violence, by reaſon of their drineſs and hardneſs, thus the bones of children are bended or crooked in by reaſon of their natural ſoftneſs and humidity. The fourth.

CHAP. II.

Of the Differences of Diſlocations.

SOme Diſlocations are ſimple, others compound: We term them ſimple which have no other preternatural affect joined with them; and ſuch compound, as are complicated with one or more preternatural affects; as when a diſlocation is aſſociated with a wound, fracture, great pain, inflammation, and an abſceſs: For, through occaſion of theſe we are often compelled ſo long to let alone the luxation until theſe be remitted of themſelves, or by our Art. Some diſlocations are compleat and perfect, as when the bone wholly falls out of its cavity; other ſome are unperfect, as when it is onely lightly moved, and not wholly fallen out; wherefore we onely call them ſubluxations or ſtrains. Differences of Luxations are alſo drawn from the place; for ſometimes the bone is wreſted forwards, otherwhiles backwards, upwards, downwards; ſomewhiles it may be wreſted according to all theſe differences of ſite, and otherwhiles onely according to ſome of them. Differences are alſo taken from the condition of the diſlocated Joint in greatneſs and littleneſs, from the ſuperficiary or deep excavation of the *ſinus* or hollowneſs; and laſtly, from the time, as if it be lately done, or of ſome long continuance. I have judged it fit to ſet down all theſe, for that there are ſeveral Indications of curing, according to the variety of each of theſe, as we ſhall teach hereafter. What Luxations are ſimple. What compound. What a compleat Luxation is.

CHAP. III.

Of the Cauſes of Diſlocations.

THere are three general cauſes of Luxations, internal, external, and hereditary: The internal, are excrementitious humours and flatulencies, which ſetling into the joints with great force and plenty, do ſo make ſlippery, ſoften and relax the ligaments which bind together the bones, that they eaſily fall out of their cavities, or elſe they ſo fill and diſtend theſe ligaments, and make them ſo ſhort, that being contracted, they alſo contract the *appendices* of the bones from whence they ariſe, and ſo pluck them from the bone whereon they are placed, or elſe draw the heads of the bones out of their cavities, chiefly if the violence of a noxious humour doth alſo concur, which poſſeſſing and filling up the cavities of the joints, puts them from their ſeats, as it oft-times happens to the joint of the hip by Sciaticaes, and to the *Vertebræ* of the ſpine, by whoſe Luxation people become gibbous, or otherwiſe crooked. But external cauſes of Diſlocations are falls from high, bruiſing and heavy blows, the Rack, Strappado, ſlipping in going, and all ſuch like things, which may force the heads of the bones to fly out of their ſeats or cavities, which alſo happens ſometimes to Infants in their birth, when as they are too careleſly and violently drawn forth by the Midwife, ſo that either their arms or legs are put out of joint. Hereditary cauſes are ſuch as the Parents transfuſe into their off-ſpring: hence it is, that crooked not neceſſarily, but often-times are generated by crooked, and lame by lame. The truth whereof is evident by daily experience: Beſides alſo *Hippocrates* himſelf avers, that Infants in the very Womb may have their joints diſlocated by a fall, blow, and compreſſion, and by the too much humidity and looſneſs of the joints: whence alſo we ſee many crook-legged and footed from their nativity, ſo that none need marvel or make any doubt hereof. We have read it obſerved by *Galen*, *In Libro de Artic.* that children may have impoſthumes in their Mothers Wombs, which may caſt forth quitture, the Ulcers being opened of their own accord, and be cicatrized by the onely benefit of Nature. It alſo happens to many from their firſt conformation, that the cavities of their joints are leſs depreſſed than they ſhould be, and that their verges are more dilated than they ought to be; whereby it happens that the heads of the bones can the leſs enter into them. It falls out that otherſome have the ligaments appointed by Nature for faſtning together the bones of the joint, whether inſerted or placed about, ſo weak, that from their firſt original they are not of ſufficient ſtrength, or elſe abound with much phlegm, either bred together with them, or flowing from ſome other place; ſo that by their too much ſlipperineſs they leſs faithfully contain the knittings or articulations of the bones. In all theſe, as the bones are eaſily diſlocated, ſo they may preſently be eaſily reſtored, without the aſſiſtance of a Surgeon, as I have oft-times obſerved in ſome. What a ſubluxation or ſtrain. Internal cauſes of diſlocations. External cauſes. Hereditary cauſes. *Sect.* 3. *ſent.* 88. & 94. *ſect.* 82. 4. *ſent.* 3, & 4. *lib. de art.* Children may have Impoſthumes in their Mothers Wombs.

CHAP. IV.

The ſigns of Diſlocations.

SOme of the ſigns whereby we come to the knowledge of a luxated bone, are common to all diſlocations; others are proper onely to ſeveral Luxations. It is a common ſign that there is always a tumor in that part whereto the bone runs, and a hollowneſs on that ſide from whence it is flown. Now the proper ſigns ſhall be ſhewed, when as we come to treat of the particular The common ſign of all diſlocations.

ticular kinds of Luxations. We know a perfect Diſlocation by the loſt action of the part, that is, to ſay, the loſt motion; pain alſo breeds a ſuſpition of a diſlocation; for the head of the bone, which (moved out of its place) is forced into another, preſſes the fleſh, and diſtends the nerves alſo moved out of their place. Hereto alſo conduces the comparing of the ſound joint with that which is hurt, in which collation it is fit the ſound part, which is compared with the hurt, be no ways, neither by Nature or any accident, wronged, nor deformed, nor withered or decayed, nor ſwollen above meaſure, otherwiſe it may cozen and deceive you, if you be leſs wary. Labour and difficulty of action in moving, is a ſign of an uncompleat Luxation, or ſtrain. Now we thus know that the ligaments ſerving to the connexion of the articulations, are extended and relaxed, if the head of the bone, preſſed with your fingers, be eaſily driven to the contrary part, and ſuddenly fly thence back again; if thruſting your finger into the Joint, it eaſily enter, nothing reſiſting it, as though all were empty within; if the motion be difficult, or none at all.

Signs of an imperfect diſlocation.

CHAP. V.

Of Prognoſticks to be made upon Luxations.

What luxations be uncurable.

ALl Joints may be perverted and luxated, but all of them cannot in like manner be reſtord; For the head may be diſlocated, but thereupon preſent death enſues, by reaſon of the compreſſion of the whole ſpinal marrow preſently at the original thereof; ſuch alſo is the diſlocation of a *vertebra* of the ſpine, and of the Jaw-bone, which, ſlipped forth on both ſides, hath cauſed inflammation, and a great tumor before it be ſet. The bones of other Joints, as they are more or leſs diſlocated, and moved out of their ſeats, ſo may they be more eaſily or difficultly reſtored: For, by how much they are the leſs moved out of their places, by ſo much they are the more quickly, and by how much they are the further by ſo much they are the more ſlowly and difficultly ſet. Alſo an indication taken from the figure of the luxated bone, gives a ſign of the eaſie or hard reſtoring of the diſlocation; as in the arm, by how much the bones be the more eaſily diſlocated, by ſo much once laxated they are the more eaſily reſtored. Bones do not eaſily fall out of joint in fleſhy bodies; but when they chance to be put out, they are not eaſily got in again: For in ſuch, the articulation is ſtraitly on every ſide held in by the thickneſs of the muſcles and the plenty of the fat lying thereabouts. On the contrary, ſuch as are lean, eſpecially thoſe who formerly have been more fat, have their joints more lax, whereby it comes to paſs, that their bones may eaſily be put forth of joint: beſides alſo, through the default of the digeſtive faculty, they have their joints replete with mucous humours; whence it is, that the heads of the bones, as ſtanding in a ſlippery place, are the leſs ſtable, as it is recorded by *Hippocrates*: But ſlender bodies, which are naturally dry, compact and denſe, have their muſcles and ligaments more ſtrong and dry; wherefore their bones are the more difficultly diſplaced; and diſplaced, the more difficultly ſet. Some bones, joined amongſt themſelves, do ſometimes fly aſunder, as when the ſhoulder-blade flies from the collar-bone at the *Acromium*, and in the Arm, the Ell from the Wand; and in the Leg, the one ſocile from the other, and the Heel-bone from the Ancle. Bones thus ſeparated will never be joined together again, will never recover their former comely figure, never their ſtrength of action: For then it moſt uſually happens that the ligaments are either broke aſunder, or elſe reſolved and become lax. Thoſe whoſe bones are diſlocated by an external cauſe, they, after they be ſet, may eaſily fall out again, for that the ligaments, moiſtned and bedewed with an excrementitious humour, cannot firmly hold them: oft-times the ligaments are not wholly broken, but onely in ſome portion thereof; and hence the action of the part either periſhes, or is debilitated: Alſo that diſlocation is uncurable, when as the ligaments, ſteeped and ſwollen up with an excrementitious humidity, are ſo much ſhortned and contracted in their length, as they have acquired in their breadth: and thus they draw away and pluck off the *appendices* of the bones from whence they ariſe, and by reaſon the bone and the *appendix* do enter and receive each other by many cavities and prominencies, therefore they cannot, by how skilful hand ſoever they be handled, be again fitly placed and put together. Old and inveterate diſlocations, wherein a tough humour poſſeſſing the cavity is concrete in ſtead of the head of the bone, are not to be reſtored; as neither when the heads of the luxated bones have by continual attrition made themſelves a new cavity in the neighbouring bone: neither if they be reſtored, is the reſtitution firm and of continuance, becauſe the natural cavity is poſſeſſed by another matter, and the new made near thereto cannot well and faithfully contain the received head of the bone. Thoſe who have their ſhoulder diſlocated, may uſe their hand for many actions, as well as the oppoſite ſound hand, for the weight of the body is not ſuſtained by the hands as it is by the legs: and by how much the hand is the more exerciſed, by ſo much the arm becomes the more corpulent. Contrarily, if the thigh-bone be diſlocated, eſpecially if it be wreſted inwards, the whole leg quickly decays by an *atrophia*, becauſe the part doth abſolutely loſe all motion: for by the opinion of *Hippocrates*, the performance of the proper action increaſes ſtrength, and makes the part in better plight; but idleneſs debilitates and makes it lean. If a great wound and fracture be joined with a luxation, there is danger, leſt while we uſe extention for reſtoring the part, we draw the nerves too violently, and ſo break the nerves, veins, and arteries, whence would enſue fear of inflammation, convulſion, and other malign ſymptoms. Wherefore *Hippocrates* judges it better in ſuch a concourſe and complication of preternatural affects, abſolutely not to meddle at all with the ſetting of the diſlocated bone: for, by attempting the reſtitution, certain death; but by omitting it, onely lameneſs is to be feared. Every diſlocation muſt be reſtored before inflammation come; but if it be already preſent, you muſt preſently be careful to take it away: For other things, let the Patient reſt, leſt if the affect be irritated, the increaſe and acceſs of pain cauſe a convulſion, gangrene, and laſtly death, as I remember I have ſometimes obſerved. Therefore when inflammation, and other malign ſymptoms ſhall be mitigated and

Why thoſe bones which are hardly diſlocated, are hard to be ſet.

Sect.1. de Art. ſent.29. Celſus lib.8. cap.11.

Why the plucking of an *appendix* from a bone is uncurable.

Hipp.ſent.88. ſect.3. de art.

Sent.10. ſect.5. lib.6. epid. & ſect.3. de art. ſent.88.

You muſt not endeavour to ſet an inflamed joint.

and corrected, then may you endeavour to reſtore the luxation, eſpecially if the habit of the body and member affected may admit it. For if the body be ſlender, delicate and tender, then the reſtitution will be more ſpeedy and facile. But on the contrary, more difficult if it be groſs and compact. And let thus much ſuffice for Prognoſticks in Luxations.

CHAP. VI.

Of the general cure of Diſlocations.

FOr all that I have heretofore delivered the general method of curing Fractures and Diſlocations, yet it ſhall not be unprofitable to repeat here in this place thoſe things which may be accommodated to this Treatiſe of curing Luxations. Now he that will cure Diſlocations, muſt have regard to five intentions, which it will be fitting to perform in order. The firſt is, of holding; the ſecond, of drawing or extending; the third, of forcing in; the fourth, of placing in convenient figure and ſite; the fifth, of correcting the concomitant, or following ſymptoms. *Five inventions in curing Diſlocations.*

The firſt ſcope, which we ſaid was of holding, is meant either of the whole body, or elſe of ſome part thereof onely. The whole body muſt be holden by the ſtrong embracement of your Servant or Attendant, when as the ſhoulder, the *vertebræ*, or the thigh-bones are diſlocated. But in the diſlocation of the Collar-bone, Elbow, Hand, Knee, or Foot and Leg, it is ſufficient onely to hold the part ſtraitly in your hands. There is neceſſity of holding either the body, or elſe ſome part thereof, leſt while the diſlocated bone is extended, the whole body follow by continuance of parts, if there be nothing which may hinder: for if the body ſhould follow him that draws or extends, all the Work-maſters labour and endeavour to reſtore it is to no purpoſe. *The benefit of holding the member in Diſlocations.* The uſe of the ſecond ſcope, that is, of drawing or extending, is, that there may be a free ſpace and diſtance between the luxated bones, by which diſtance the diſlocated bone may the more freely be forced into its cavity. But the manner of drawing or extending is different in quantity and manner, according to the various ſtrength of the muſcles and ligaments, and diſlocation of the bones to this or that part. Therefore this work is almoſt always performed by the hands, which when they cannot ſuffice, we muſt have the aſſiſtance of Inſtruments and Engines, whoſe figures you ſhall ſee hereafter delineated: But that you may not do amiſs, you may ſo far uſe extenſion, until the head of the bone be brought juſt againſt its cavity. *The uſe of extenſion.* When the Surgeon hath brought it to this paſs, then muſt he haſten to the third intention, which is, to put the head of the bone firſt moved and gently bended, into its cavity: For he muſt have a ſpecial care that he force it no other way than into its proper cavity; for it would be dangerous, leſt he ſhould turn it from one extreme into another, and the bone, for example ſake, of the thigh, which was diſlocated into the fore-part by too violent forcing, by exceeding the middle cavity, may be driven and diſlocated into the hinder part. To ſhun this, the bone ſhall be put back the ſame way that it fell out, which may eaſily be done in freſh and late happening diſlocations. *The manner of ſetting it, or putting it into its place.* We underſtand that the bone is ſet by the noiſe, or as it were a pop or ſound like that, which ſolid and ſounding bodies, being fully and forcibly thruſt into their cavities, do make; by the ſimilitude and conſent in figure, magnitude, and all conformation of the affected part with the ſound; and laſtly, by the mitigation of the pain. *Signs that the bone is ſet.* The fourth ſcope, which is of the convenient ſite of the part, muſt be ſo fulfilled, that the bone after it is ſet may be kept in its cavity, and not fly forth again: Wherefore if the arm be diſlocated it ſhall be carried bound up in a ſcarf; if the thigh, knee leg, or foot be luxated, they ſhall be fitly laid in a bed; but in the *interim* the Surgeon, preſently after he hath ſet them, ſhall have a care that the affected joint be wrapped about with ſtoups and cloths, or compreſſes ſteeped in Roſe Vinegar, and ſpred with convenient Medicins; then let it be bound with an artincial deligation, rowling the ligatures unto the part contrary to that whereto the diſlocated bone flew. *The benefit of fit placing the member.* For the which purpoſe thicker boulſters ſhall be there applied whence the bone came out, otherwiſe there will be ſome danger leſt it ſhould be again diſplaced: when theſe things are done, he ſhall for four or five days ſpace meddle with nothing about the diſlocation, unleſs pain, or ſome ſuch like ſymptom happen. For then the fifth ſcope will call us from that ceſſation and reſt, which is, to correct the ſymptoms and complicate affections, as pain, inflammation, a wound, fracture, and others, whereof we have ſpoken abundantly in our Treatiſe of Fractures. *The manner of binding up the ſet joint.* Before we attempt to ſet inveterate Diſlocations, we muſt endeavour to humect the ligaments, tendons, and muſcles, by fomentations, cataplaſms, emplaſters, liniments, and other remedies, that ſo theſe parts may be more obedient to the Surgeons hand; then muſt the diſlocated bones be moved with a gentle motion up and down, to and again, that by this means the excrementitious humour, which by continuance of time hath flowed down, may wax hot, be attenuated, reſolved or made ſlippery, and alſo the fibres of the muſcles, ligaments, and nervous bodies, placed about the joint for the defence thereof, may be looſed, that ſo they may preſently be more freely extended: But if a great ſwelling, pain, and inflammation urge, we muſt firſt think of aſſwaging and curing them; then of the reſtoring the Diſlocation. *The cure of inveterate luxations.*

CHAP. VII.

The deſcription of certain Engines ſerving for the reſtoring of Diſlocations.

BEfore I come to the particular kinds of Diſlocations, I think it not amiſs to deſcribe three ſorts of Bandages, and give you their Figures, as thoſe which are moſt fit to hold and extend diſlocations. The firſt ligature, deſigned by this letter *A*, is made for holding the member. The ſecond, marked with the letter *B*, is fit for drawing or extenſion, and conſiſts of one knot. The third, whereto the letter *C* is put, conſiſting of two knots, is to hold or bind more ſtraightly. *Theſe ligatures are not for deligation, but extenſion.*

The delineation of the three Ligatures.



I have thought good alſo to delineate the following Engine, made for to draw and extend more powerfully, when the hand will not ſerve. It is made like a Pulley, marked with theſe Letters *D D.* Within this there lie hid three Wheels, through whoſe furrows runs the rope which is to be drawn, marked with this Letter *H.* At the ends of the Pulley are hooks faſtned, the one of which is to faſten the Pulley to a Poſt, the other is to draw the ligature faſtned to the part. The Boxes or Caſes wherein the Pulley is kept, is marked with *B B.* Their Covers are marked with *A A.*



A Screw-pin which may be twined, and ſo faſtned to a Poſt, that ſo one of the ends of the Pulley may be hooked thereto, is ſigned with *C.* A Gimlet (marked by *F*) to make a hole in a Poſt, ſo to let in the Screw-pin. You may ſee all theſe things expreſt in this Figure.

Some Practitioners in ſtead of this Pulley, make uſe of this deſcribed Inſtrument, which they term *Manubrium verſatile*, or a Hand-vice. The end thereof is faſhioned like a Gimblet, and is to be twined into a Poſt. Within that handle lies a Screw with a hooked end, whereto the ſtring or ligature muſt be faſtned. Now the Screw-rod or Male-ſcrew runs into the Female by twining about of

Manubrium verſatile, or a Hand-vice.



the handle; and thus the ligature is drawn as much as will ſuffice, for the ſetting the diſlocated bone. Having delivered theſe things thus in general, now I come to treat of the Luxations of each part, from the Jaw-bone even to the Toes of the Feet.

CHAP.

CHAP. VIII.

Of the Diſlocation of a Jaw-bone.

THE Jaw bone is diſlocated by many occaſions, and not ſeldom by yawning, and other more ſtrong openings of the mouth. It is more frequently luxated into the fore, than into the hinder part, by reaſon of the mamillary additaments, which hinder it from falling backwards. The diſlocation is ſometimes but on one ſide, otherwhiles on both. If the one ſide onely be luxated, it (together with the chin) is drawn awry unto the contrary ſide, which is not diſlocated; the place is hollow from whence it is flown, but ſwollen whither it is gone; the Patient cannot ſhut his mouth, but is forced to gape, ſo that he cannot eat; the Jaw, together with the teeth therein, hangs ſomewhat forwards; neither do the teeth anſwer fitly to one another, but the dog teeth are under the ſhearers. But if both ſides be diſlocated, all the Jaw and Chin hang forwards and towards the Breſt; beſides alſo, the temporal muſcles appear diſtended, ſpittle runs out of the Patients mouth againſt his will, the lower teeth ſtand further forth than the upper, which is the occaſion that the mouth cannot be ſhut, neither the tongue have free volubility to ſpeak, the Patient ſtammering in his ſpeech. When it is diſlocated on both ſides, it is more difficultly reſtored, and all the ſymptoms are more vehement; wherefore it muſt be ſet with all ſpeed, otherwiſe the Patient will preſently have grievous pain about his throat, inflammation, a fever, whereupon oft-times death enſues within ten days, by reaſon of the five branches of nerves, which ariſing from the ſecond and fifth conjugation of the brain, are diſtributed into the moving muſcles thereof, which too violently extended, brings the fore-mentioned ſymptoms. Practitioners affirm, that the Jaw twelve days after it is ſet, is free from the danger of relapſe. If it have been diſlocated ſome few days before you go about to reſtore it, you muſt uſe ſoftning and relaxing Medicins to it; but when it is put in the joint, apply a Medicin made of the Whites of Eggs and Oil of Roſes to aſſwage the pain, and apply cloths dipped in oxycrate. At the ſecond dreſſing you ſhall apply ſuch things as have power to agglutinate and ſtrengthen the ligaments and other relaxed parts, and alſo to keep it being reſtored in its place. This ſhall be the form of ſuch a Medicin: ℞ *Pulv. boli armeni. ſang. draconis, farinæ volat. maſtich. picis, reſinæ, an.* ʒ ß. *albuminis ovorum q. ſ. fiat medicamentum*; afterwards you may uſe *Emplaſt. Diacalcitheos* diſſolved in Oil of Roſes and Vinegar, and other things, as occaſion ſhall be.

The Cauſes. Differences.

Signs that only one part is diſlocated.

Signs that both ſides are diſlocated.

Prognoſticks. Why death quickly enſues upon the diſlocation of both ſides of the Jaw.

An aſtringent Medicin.

CHAP. IX.

How to ſet the Jaw diſlocated forwards on both ſides.

FIrſt of all the Patient muſt be placed upon the ground or ſome low ſeat, with his face upwards, and his head muſt be firmly held by your Servant, that ſo it may be the more immovable: then the Surgeon ſhall put both his thumbs, wrapped in cloths (leſt he hurt them by rubbing them upon the Patients teeth, as alſo to keep them from ſlipping) into the Patients mouth, and preſs with them the larger teeth of the luxated jaw, but put his other fingers without under his chin, and ſo lift up the whole jaw with them. But if the operation cannot be thus done, for that the mouth on the inſide is ſo ſhut and cloſed, that the thumbs cannot be put thereinto, then muſt you thruſt in wooden wedges made of ſoft wood, as hazle or fir, being cut ſquare, and of ſome fingers thickneſs. Theſe ſhall be wedged in on each ſide above the grinders; then caſt a ligature under his chin, whoſe ends your ſervant ſhall hold in his hands, and ſetting his knees upon the Patients ſhoulders, ſhall pull them upwards; then at the ſame time the Surgeon ſhall preſs downwards the wooden wedges. The Jaw bones thus reſtored, ſhall be kept ſo by convenient ligation, and dreſſed with medicins, as it is fitting; and in the mean ſpace you muſt forbid the Patient to ſpeak, or needleſſly to open his mouth. Wherefore he muſt abſtain from hard meats, and ſuch as require much chewing, until his pain be quite paſſed, and uſe onely ſpoon-meats, as Barley Creams, Panadoes, Jellies, Cullaſſes, Broths, and the like.

The firſt manner of ſetting a Jaw-bone.

Another.

Diet.

CHAP. X.

Of reſtoring the Jaw diſlocated forwards but on one ſide.

THE Patient muſt be placed on a low ſeat, ſo that he may be under the Surgeon; then your Servant, ſtanding at his back, ſhall hold his head firm and ſteddy, that it may not follow the Surgeon, drawing, extending, and doing other things neceſſary for reſtoring it. Then the Surgeon putting his thumb between the grinders, ſhall preſs down the Jaw, and gently drawing it aſide, force it into its cavity; in the mean while alſo the Patient, as much as in him lies, ſhall help forwards the Surgeons endeavour, in opening his mouth as little as he can, leſt the muſcles ſhould be extended; and he ſhall onely gape ſo wide as to admit the Surgeons thumb, for ſo the temporal muſcles ſhall be reſtored to their place and favour the reſtitution. If he open his mouth as wide as he can, they will be extended after a convulſive manner; if on the contrary he ſhut his teeth too cloſe, there will be no paſſage for the Surgeons thumb unto his grinding teeth. Some there be which affirm, that the Jaw bone may ſometimes be diſlocated towards the hind part, and that then the mouth is ſo cloſe ſhut, that the Patient cannot open it nor gape, and that the lower rank of teeth ſtands further in, and nearer the throat than the upper. Now for reſtoring it, the Patients head muſt be ſtraightly holden behind, whileſt the Surgeon, the mean while putting both his thumbs into the Patients mouth, holding his other fingers without under the Patients chin, he ſhall by

What the Surgeon.

What the Patient ought to do.

Signs that the Jaw is diſlocated backwards.

The Cure.

ſhaking it, draw it to him, or forwards, and ſo reſtore it to its place. For my own part, I confeſs I never ſaw this kind of Luxation, and I eaſily perſuade my ſelf that it can ſcarce ever happen, for the reaſon I gave in the former Chapter. But nevertheleſs, if it by any means chance to happen, yet can it not be a perfect luxation, but an imperfect one; the jaw being onely but a little thruſt back to the throat to thoſe mamillary additaments; and then it may eaſily be reſtored by lifting or drawing forth the jaw, and ſuddenly forcing it from below upwards.

CHAP. XI.

Of the luxation of the Collar-bone.

Differences of the luxated collar-bones.

AS the Collar-bones may be broken, wreſted, and crooked, ſo alſo they may be diſlocated. Now they are diſlocated, either againſt the *ſternum*, or againſt the ſhoulder blade, or *acromion* thereof: yet both theſe kinds of diſlocations are very rare, by reaſon of the ſtrait and firm connexion which the collar-bone hath with the foreſaid parts; but chiefly where it is joined to the *ſternum* it can ſcarcely be depreſt, for that it is as it were underpropt with the firſt rib: But it may be diſlocated inwardly, outwardly, and ſide-wiſe, and according to this variety there muſt be divers ways to reſtore it; yet generally the Collar-bone is put into its place by moving or extending the arm: But if need require, the Patient ſhall be laid upon the ground with his face upwards, a Tray with the bottom upwards, a hard ſtuffed cuſhion, or the like thing being put under his ſhoulders; for thus it will ſo come to paſs, that the ſhoulder and cheſt will ſtand ſo forth, that preſently by lifting up, by preſſing down, or drawing forth the arm forwards or backwards, as the bone ſhall be flown out to this or that part, you may reſtore it; for thus the prominency may be forced into its cavity. But it will be requiſite to bind it up and lay boulſters thereon, and to give it reſt, as if it were fractured. *Galen* writes, that when he was five and thirty years old, whileſt he exerciſed himſelf in the place of exerciſe, his Collar bone was ſo far ſeparated from the *Acromion*, that there was the ſpace of three fingers between them. And that this luxation was reſtored in forty days ſpace, by ſo ſtrait and ſtrong a ligation, that he perceived the motion of the beating arteries under the bone. But you ſhall find very few who will ſuffer ſuch ſtrait ligation ſo long, though it be never ſo neceſſary. Verily, this kind of luxation is hard to be known, but far more difficult to be healed. I have known many Surgeons deceived, who have taken the luxation of the Collar-bone for the diſlocation of the top of the ſhoulder: for then the *Epomis*, or top of the ſhoulder ſwells, and the place from whence the collar bone is flown, is depreſſed with a manifeſt cavity, with vehement pain, inflammation and impotency of lifting up, or otherwiſe moving the arm, or performing other actions which are done by the help of the ſhoulder. Certainly if this bone when it is diſlocated, be not ſet, the Patient ſhall be lame during his life, ſo that he ſhall not be able, neither to put his hand to his head nor mouth.

Com. ad ſent. 62. ſect. 1. de art.

The Cure.

CHAP. XII.

Of the luxation of the Spine, or Back-bone.

An anatomical deſcription of the Spine.

THE Back bone conſiſts of many bony *Vertebræ*, like rowls or wheels mutually jointed or knit together, by their ſmoothneſs and circular form conſpiring to an aptneſs of moving or bending forwards. For if it ſhould conſiſt of one bone, we ſhould ſtand continually with the trunk of our bodies immovable, as thruſt through with a ſtake. The *Vertebræ* have a hole paſſing through the midſt of them, whereby the marrow paſſing this way out from the brain as by a pipe, may ſerve for the generation of the ſenſitive and motive nerves, and their diſtribution into all parts beneath the head. For which purpoſe it is perforated with many holes on the ſides, through each whereof certain conjugations of the nerves paſs forth into the reſt of the body, and veins and arteries paſs in for the propagation of nouriſhment and life. The whole exteriour face of the ſpine is rough, and as it were armed with four ſorts of *apophyſes* or proceſſes, whereof ſome ſtand up, others down; ſome direct, others tranſverſe: Wherefore from theſe thorny and ſharp proceſſes, the whole hath acquired the name of the *Spina*. The *Vertebræ* the further from the neck they are, the greater they grow, ſo that thoſe which are the loweſt, are the largeſt; for it is agreeable to reaſon, that that which bears ſhould be greater than that which is born. Hence we ſee, that the holy bone is placed under the reſt as a foundation. The ſide proceſſes of the Rack bones of the cheſt, beſides the benefit of defending the ſpinal marrow ſhut up therein from external injuries, have alſo another, which is, they firm and faſten the bones of the ribs by a ſtrong tie. There lies a griſle, and a tough, and (as it were) albuminous humour between the *Vertebræ*, which makes them, as alſo all the other joints of the body ſlippery and fit for motion: the ſpine is flexible with notable agility forwards onely, but not backwards, for that ſo there would be continual danger of breaking the hollow aſcendent vein, and the great deſcending artery running thereunder: Therefore the dearticulations of the *Vertebræ*, mutually ſtrengthened with ſtrong ligaments, do look more backwards. I have thought good to premiſe theſe things of the nature of the ſpine, before I come to diſlocations happening thereto. I willingly omit divers other things which are moſt copiouſly delivered by *Galen*; content onely to add thus much, that there is nothing to be found in the whole ſtructure of mans bones, which more clearly manifeſts the induſtry of Gods great workmanſhip, than this compoſure of the Spine and the *Vertebræ* thereof.

The variety of the proceſſes of the Spine.

Gal. cap. 7. lib. 13. de uſu partium.

Lib. 13. de uſu partium.

CHAP.

CHAP. XIII.

Of the Diſlocation of the Head.

THe Head ſtands upon the Neck knit by dearticulation to the firſt *Vertebra* thereof, by the interpoſition of two proceſſes which ariſe from the *baſis* thereof, near the hole through which which the marrow of the brain paſſes down into the back-bone; and they are received by fit cavities, hollowed in this firſt *Vertebra*. Theſe proceſſes ſometimes fall out of their cavities, and cauſe a diſlocation behind, whereby the ſpinal marrow is too violently and hard compreſſed, bruiſed and extended, the chin is faſtned to the breſt, and the Patient can neither drink nor ſpeak: wherefore death ſpeedily follows upon this kind of luxation, not through any fault of the Surgeon, but by the greatneſs of the diſeaſe, refuſing all cure.

The connexion of the head with the firſt Rack-bone of the Neck. Prognoſticks.

CHAP. XIV.

Of the Diſlocation of the Vertebræ, *or Rack-bones of the Neck.*

THe other *Vertebræ* of the Neck may be both diſlocated and ſtrained. Diſlocation verily, unleſs it be ſpeedily helped, brings ſudden death: for, by this means the ſpinal marrow is preſently oppreſſed at the very original thereof, and the nerves therehence ariſing, ſuffer alſo together therewith, and principally thoſe which ſerve for reſpiration; whereby it cometh to paſs, that the animal ſpirit cannot come and diſperſe it ſelf into the reſt of the body lying thereunder; hence proceed ſudden inflammation, the ſquinſie, and a difficulty, or rather a defect of breathing. But a ſtrain or incompleat luxation brings not the like calamity: by this the *Vertebræ*, a little moved out of their ſeats, are turned a little to the hind or fore-part; then the Neck is wreſted aſide, the Face looks black, and there is difficulty of ſpeaking and breathing. Such, whether Diſlocation or ſtrain, is thus reſtored. The Patient muſt be ſet upon a low ſeat, and then one muſt lean and lie with his whole weight upon his ſhoulders; and the mean while the Surgeon muſt take the Patients head, about his ears, betwixt his hands, and ſo ſhake and move it to every part, until the *Vertebra* be reſtored to its place. We may know it is ſet by the ſudden ceaſing of the pain, which before grievouſly afflicted the Patient, and by the free turning and moving his head and neck every way. After the reſtoring it, the Head muſt be inclined to the part oppoſite to the Luxation, and the Neck muſt be bound up about the dearticulation of the Shoulder; but yet ſo, that the ligature be not too ſtrait, leſt by preſſing the Weazon and Gullet, it ſtraiten the paſſages of breathing and ſwallowing.

The danger hereof. Signs and ſymptoms of their ſubluxation. The Cure. Signs of their reſtitution.

CHAP. XV.

Of the Diſlocated Vertebræ *of the Back.*

THe Rack-bones of the Back may be diſlocated inwards, outwards, to the right ſide, and to the left. We know they are diſlocated inwards, when as they leave a depreſſed cavity in the ſpine; outwardly, when they make a bunch on the back; and we know they are luxated to the right or left ſide, when as they obliquely bunch forth to this or that ſide. The *Vertebræ* are diſlocated by a cauſe either internal or external, as is common to all other Luxations; the internal is either the defluxion of humours from the whole body, or any part to them and their ligaments; or elſe a congeſtion proceeding from the proper and native weakneſs of theſe parts; or an attraction ariſing from pain and heat. The external is a fall from high upon ſome hard body, a heavy and bruiſing blow, much and often ſtooping, as in Dreſſers and Lookers to Vineyards, and Paviers, decrepit Old Men; and alſo ſuch as through an incurable diſlocation of the thigh-bone are forced in walking to ſtoop down and hold their hand upon their thigh. But a *Vertebra* cannot be forced or thruſt inwards, unleſs by a great deal of violence; and if it at any time happen, it is not but with the breaking of the ties and ligaments, for they will break rather than ſuffer ſo great extenſion. Such a Diſlocation is deadly, for that the ſpinal marrow is exceedingly violated by too ſtrait compreſſion, whence proceeds dulneſs, and loſs of ſenſe in the members lying thereunder. Neither is reſtitution to be hoped for, becauſe we cannot through the belly force it into its place: the Urine is then ſuppreſt, as alſo the excrements of the belly; ſometimes on the contrary, both of them break forth againſt the Patients mind, the knees and legs grow cold, their ſenſe and motion being loſt. Such things happen more frequently when the ſpine is luxated inwards than when it is diſlocated outwards, for that the Nerves thence ariſing, run and are carried more inwardly into the body. Beſides the preſſed ſpinal marrow becomes inflamed, and that being inflamed, the parts of the ſame kind, and ſuch as are joined thereto, are alſo inflamed by conſent, whence it happeneth that the bladder cannot caſt forth the Urine. Now where the ſinews are preſſed, they can no more receive the irradiation of the animal faculty. Hence follows the deprivation of the ſenſe and motion in the parts whereto they are carried, therefore the contained excrements do no more provoke to expulſion by their troubleſom ſenſe, neither are preſſed to keep them in: thence proceeds their ſuppreſſion, and hence their breaking forth againſt their wills. But the ſpine outwardly diſlocated, ſcarce cauſes any compreſſion of the marrow or nerves.

Differences and ſigns. Cauſes. The danger of a *Vertebra* diſlocated inwards. *Hipp. ſent. 51. ſect. 3. de art. & Gal. in com.*

CHAP. XVI.

How to reſtore the Spine outwardly diſlocated.

The Cure.

THe *Vertebræ* outwardly diſlocated, when as they ſtand bunching forth, then it is fit to lay and ſtretch forth the Patient upon a Table with his face downwards, and ſtraitly to bind him about with Towels under the arm-pits, and about the flanks and thighs; and then to draw and extend, as much as we can, upwards and downwards, yet without violence: for unleſs ſuch extenſion be made, reſtitution is not to be hoped for, by reaſon of the proceſſes and hollowed cavities of the *Vertebræ*, whereby, for the faſter knitting, they mutually receive each other. Then muſt you lie with your hands upon the extuberancies, & force in the prominent *vertebra*. But if it cannot be thus reſtored, then will it be convenient to wrap two pieces of wood, of four fingers long, and one thick, more or leſs, in linnen cloths, and ſo to apply one on each ſide of the diſlocated *Vertebræ*, and ſo with your hands to preſs them againſt the bunching forth *Vertebræ*, until you force them back into their ſeats, juſt after the manner you ſee it before delineated.

Another manner of cure.

How to keep the reſtored *Vertebræ* in their places.

In the mean while have a care that you touch not the proceſſes which ſtand up in the ridge of the Spine, for they are eaſily broken. You may know that the *Vertebræ* are reſtored by the equal ſmoothneſs of the whole Spine. It is fit, after you have reſtored it, to bind up the part, and lay ſplints or plates of Lead neatly made for that purpoſe upon it; but ſo, that they may not preſs the criſts or middle proceſſes of the *Vertebræ*, which I formerly mentioned, but onely the ſides: then the Patient ſhall be laid upon his back in his bed, and the ſplints long kept on, leſt the *Vertebræ* ſhould fall out again.

CHAP. XVII.

A more particular enquiry of the diſlocation of the Vertebræ, *proceeding from an internal cauſe.*

THe *Vertebræ* are in like ſort luxated by the antecedent cauſe, as we have formerly ſaid, which is cauſed by the natural imbecillity of the parts, principally of the nervous ligament, by which all the *Vertebræ* are bound each to other; this ligament comes not to the ſpinal marrow, but onely binds together the *Vertebræ* on their out-ſides: For, beſides the two membranes proceeding from the two *Meninges* of the Brain, wherewith the marrow is covered, there is a third ſtrong and nervous coat put upon it, leſt while the ſpine is diverſly bended, the bended marrow ſhould be broken. This third coat ariſes from the *Pericranium*, as ſoon as it arrives at the firſt *Vertebra* of the neck. Now that ligament, wherewith we ſaid the Joints of the *Vertebræ* were mutually knit and faſtned, is encompaſſed with a tough and glutinous humour for the freer motion of the *Vertebræ*. Sometimes another cold, crude, groſs and viſcid humour, confuſed and mixed herewith by great defluxions and catarrhs, begets a tumour, which doth not onely diſtend the Nerves proceeding forth of the holes of the *Vertebræ*, but alſo diſtends the ligaments wherewith they are bound together: which ſo diſtended, and (as it were) drawn aſide, do draw together with them the *Vertebræ*, one while towards the right ſide, another while to the left, ſomewhiles inwards, otherwhiles outwards, and thus move them out of their ſeats, and diſlocate them. A diſlocated *Vertebra*, ſtanding forth and making a bunch is termed in Greek *Cyphoſis*, (Thoſe thus affected we may call *Bunch-backt:*) But when it is depreſſed, it is named *Lordoſis*, (Such we may term *Saddle-backt:*) But when the ſame is luxated to the right or left ſide, it maketh a *Scolioſis* (or *Crookedneſs*,) which wreſting the ſpine, draws it into the ſimilitude of this letter *S*. *Galen* adds a fourth default of the *Vertebræ*, which is, when their joints are moved by reaſon of the looſneſs of their ligaments, the *Vertebræ* yet remaining in their places, and he calls it a *Seiſis*, or ſhaking. They alſo note another defect peculiar to the ſpinal marrow, which is, when as it (the *Vertebræ* being not moved whereto it adheres) is plucked and ſevered from them: this diſeaſe is occaſioned by a fall from on high, by a great ſtroak, and by all occaſions which may much ſhake, and conſequently depreſs the ſpinal marrow, or by any other means remove, or put it forth of its place. Scarce any recovers of this diſeaſe, for many reaſons, which

Cyphoſis. Lordoſis. Scolioſis. Com. ad Sent. 2. ſect. 3. l. de art. Seiſis.

The ſeparation of the ſpinal marrow from the encompaſſing *Vertebræ*.

which any exerciſed in the Art, may eaſily think upon: But let us return to the internal cauſe of Luxations. Fluid and ſoft bodies, ſuch as Childrens, uſually are very ſubject to generate this internal cauſe of defluxion. If external occaſions ſhall concur with theſe internal cauſes, the *Vertebræ* will ſooner be diſlocated: Thus Nurſes, whileſt they too ſtraitly lace the breſts and ſides of Girls, ſo to make them ſlender, cauſe the breſt-bone to caſt it ſelf in forwards or backwards, or elſe the one ſhoulder to be bigger or fuller, the other more ſpare and lean. The ſame errour is committed if they lay children more frequently and long upon their ſides, than upon their backs; or if, taking them up when they wake, they take them onely by the feet or legs, and never put their other hand under their backs, never ſo much as thinking that children grow moſt towards their heads.

The errour of Nurſes in ſwadding and lacing of Children.

CHAP. XVIII.

Prognoſticks of the diſlocated Vertebræ *of the Back.*

IF in Infancy it happen that the *Vertebræ* of the back ſhall be diſlocated, the ribs will grow little or nothing in bredth, but run outwards before; therefore the Cheſt loſeth its natural latitude, and ſtands out with a ſharp point. Hence they become aſthmatick, the lungs and muſcles which ſerve for breathing, being preſſed together and ſtraitned; and that they may the eaſilier breathe, they are forced to hold up their heads, whence alſo they ſeem to have great throats. Now becauſe the Weazon being thus preſſed, the breath is carried through a ſtrait paſſage, therefore they wheaze as they breathe, and ſnort in their ſleep, for that their lungs, which receive and ſend forth the breath or air, be of leſs bigneſs: beſides alſo they are ſubject to great diſtillations upon their lungs, whereby it cometh to paſs that they are ſhorter lived. But ſuch as are bunch-backed below the midriff, are incident to diſeaſes of the Kidneys and Bladder, and have ſmaller and ſlenderer thighs and legs, and they more ſlowly and ſparingly caſt forth hair and have Beards: to conclude, they are leſs fruitful, and more ſubject to barrenneſs, than ſuch as have their crookedneſs above their midriff. The bunches which proceed from external cauſes are oft-times curable; but ſuch as have their original from an inward cauſe, are abſolutely uncurable, unleſs they be withſtood at the firſt with great care and induſtry. Wherefore ſuch as have it by kind, never are helped. Such as, whilſt they are yet children, before their bodies be come to perfect growth, have their ſpine crooked and bunching out, their bodies uſe not to grow at the ſpine, but their legs and arms come to their perfect and full growth; yet the parts belonging to their breſt and back, become more ſlender: Neither is it any wonder, for ſeeing the Veins, Arteries, and Nerves are not in their places, the ſpirits do neither freely, nor the alimentary juices plenteouſly flow by theſe ſtraitned paſſages, whence leanneſs muſt needs enſue: but the limbs ſhall thence have no wrong, for that not the whole body, but the neighbouring parts onely are infected with the contagion of this evil. When divers *Vertebræ*, following each other in order, are together and at one time diſlocated, the diſlocation is leſs dangerous, than if one alone were luxated: For, when one onely *Vertebra* is diſlocated, it carries the ſpinal marrow ſo away with it, that it forces it almoſt into a ſharp angle; wherefore being more ſtraitly preſſed, it muſt neceſſarily be either broken or hurt, which is abſolutely deadly, for that it is the brains ſubſtitute. But when divers *Vertebræ* are diſlocated at once, it muſt of neceſſity be forced onely into an obtuſe angle, or rather a ſemicircle; by which compreſſion it certainly ſuffers, but not ſo, as that death muſt neceſſarily enſue thereon. Hereto may ſeem to belong that which is pronounced by *Hippocrates*; a circular moving of the *Vertebræ* out of their places is leſs dangerous than an angular.

Hipp. ſent. 6. ſect. 3. de art.

Why when the ſpine is luxated, the parts belonging to the cheſt are nouriſhed and grow the leſs.

Why the luxation of one *Vertebra* is more dangerous than of many.

Sent. 51. ſect. 3. lib. de art.

CHAP. XIX.

Of the diſlocation of the Rump.

THE Rump oft-times is after a ſort diſlocated inwards by a violent fall upon the buttocks, or a great blow; in this affect the Patient cannot bring his heel to his buttocks, neither unleſs with much force, bend his Knee; Going to ſtool is painful to him, neither can he ſit unleſs in a hollow chair; That this (as it were) diſlocation may be reſtored, you muſt thruſt your finger in by the Fundament, even to the place affected, as we have ſaid in a Fracture; then muſt you ſtrongly raiſe up the bone, and with your other hand at the ſame time join it rightly on the outſide with the neighbouring parts: Laſtly it muſt be ſtrengthened with the formerly mentioned remedies, and kept in its place. Now it will be recovered about the twentieth day after it is ſet. During all which time the Patient muſt not go to ſtool, unleſs ſitting upon a hollow ſeat, leſt the bone, as yet ſcarce well recovered, ſhould fall again out of its place.

The Signs.

The Cure.

CHAP. XX.

Of the Luxation of the Ribs.

THE Ribs may by a great and bruiſing ſtroak be diſlocated, and fall from the *Vertebra* whereto they are articulated, and they may be driven inwards, or ſide-ways. Of which kind of luxation, though there be no particular mention made by the Ancients, yet they confeſs that all the bones may fall, or be removed from their ſeats or cavities, wherein they are received and articulated. The ſign of a rib diſlocated and ſlipped on one ſide, is a manifeſt inequality, which here makes a hollowneſs, and there a bunching forth; but it is a ſign that it is driven in, when as there

Cauſes.

Signs.

there is onely a depreſſed cavity where it is knit and faſtned to the *Vertebræ*. Such diſlocations cauſe divers ſymptoms, as difficulty of breathing, the hurt rib hindering the free moving of the cheſt; a painfulneſs in bowing down or lifting up the body, occaſioned by a pain, counterfeiting a pleuriſie; the riſing or puffing up of the muſculous fleſh about the rib, by a mucous and flatulent humour there generated: the reaſons whereof we formerly mentioned in our Treatiſe of Fractures. To withſtand all theſe, the diſlocation muſt be forthwith reſtored, then the puffing up of the fleſh muſt be helped. Wherefore, if the diſlocated rib ſhall fall upon the upper ſide of the *Vertebra*, the Patient ſhall be ſet upright, hanging by his arms upon the top of ſome high door or window: then the head of the rib, where it ſtands forth, ſhall be preſſed down until it be put into its cavity. Again, if the rib ſhall fall out upon the lower ſide of the *Vertebra*, it will be requiſite that the Patient bend his face downwards, ſetting his hands upon his knees; then the diſlocation may be reſtored by preſſing or thruſting in the knot or bunch which ſtands forth. But if the luxated rib fall inwards, it can no more be reſtored or drawn forth by the hand of the Surgeon, than a *Vertebra* which is diſlocated towards the inſide, for the reaſons formerly delivered.

Gal. com. ad ſen. 3. ſect. 1. de art.

CHAP. XXI.

Of a diſlocated ſhoulder.

THe ſhoulder is eaſily diſlocated, beauſe the ligaments of its dearticulation are ſoft and looſe; as alſo for that the cavity of the ſhoulder-blade is not very deep; and beſides it is every where ſmooth and polite, no otherwiſe than that of the ſhoulder-bone, for that it is herein received. Add hereunto, that there is no internal ligament from bone to bone, which may ſtrengthen that dearticulation, as is in the leg and knee. Wherein notwithſtanding, we muſt not think Nature defective, but rather admire Gods providence in this thing; for that this articulation ſerves not onely for extenſion and bending, as that of the elbow, but beſides, for a round or circular motion, as that which carries the arm round about, now up then down, according to each difference of ſite. The ſhoulder-bone, which *Hippocrates* calls the arm-bone, may be diſlocated four manner of ways, upwards, downwards, or into the arm-pit, forwards and outwards, but never backwards, or to the hinder part: For, ſeeing that there the cavity of the blade-bone, which receives the head of the arm-bone, which *Hippocrates* calls a joint, lies and ſtands againſt it; who is it that can but imagine any ſuch diſlocation? In like ſort it is never diſlocated inwardly, for on this part it hath the fleſh of a ſtrong muſcle, termed *Deltoides*, lying over it, beſides alſo the back and *acromion* of the blade; and laſtly, the Anchor-like, or beak-like proceſs, all which four hinder this joint from ſlipping inwards. Now *Hippocrates* ſaith, that he hath onely ſeen one kind of diſlocation of this bone, to wit, that which is downwards or to the arm-pit; and certainly it is the moſt uſual and frequent; wherefore we intend to handle it in the firſt place. When the ſhoulder is diſlocated downwards into the arm-pit, a depreſſed cavity may be perceived in the upper part of the joint; the *acromion* of the blade ſhews more ſharp and ſtanding forth than ordinary, for that the head of the ſhoulder-bone is ſlipt down and hid under the arm-pit, cauſing a ſwelling forth in that place; the elbow alſo caſts it ſelf (as it were) outwards, and ſtands further off from the ribs, and though you force it, yet can you not make it to touch them; the Patient cannot lift up his hand to his ear on that ſide, neither to his mouth nor ſhoulder. Which ſign is not peculiar to the luxated ſhoulder, but common to it, affected with a contuſion, fracture, inflammation, wound, abſceſs, *ſchirrus*, or any defluxion upon the Nerves, ariſing out of the *Vertebræ* of the neck, and ſent into the arm; alſo this arm is longer than the other. Laſtly, (which alſo is common to each difference of a luxated ſhoulder) the Patient can move his arm by no kind of motion without ſenſe of pain, by reaſon of the extended and preſſed muſcles, ſome alſo of their fibres being broken. There are ſix ways to reſtore the ſhoulder luxated downwards into the arm-pit: The firſt is, when it is performed with ones fiſt, or a towel; the ſecond with a clew of yarn, which put under the arm-pit, ſhall be thruſt up with ones heel; the third, with ones ſhoulder put under the arm-hole; which manner, together with the firſt, is moſt fit for new and eaſily to be reſtored luxations, as in thoſe who have looſe fleſh, and effeminate perſons, as children, eunuchs, and women; the fourth, with a ball put under the armpit, and then the arm caſt over a piece of wood held upon two mens ſhoulders, or two ſtanding poſts; the fifth, with a Ladder; the ſixth, with an inſtrument called an *Ambi*. We will deſcribe theſe ſix ways, and preſent them to your view.

Why there is no internal ligament from the arm-bone to the ſhoulder-blade.

Differences of a luxated ſhoulder. *Sent. 1. ſect. 1. lib. de art.*

Signs of the ſhoulder diſlocated downwards.

The ways to reſtore it.

CHAP. XXII.

Of the firſt manner of ſetting a Shoulder, which is with ones Fiſt.

FIrſt, let one of ſufficient ſtrength, placed on the oppoſite ſide, firmly hold the Patient upon the joint of the ſhoulder, leſt he move up and down with his whole body, at the neceſſary extenſion, working and putting it in: then let another, taking hold of his arm above the elbow, ſo draw and extend it downwards, that the head thereof may be ſet juſt againſt its cavity, hollowed in the blade-bone: Then at laſt let the Surgeon lift and force up with his fiſt the head of the bone into its cavity. Here this is chiefly to be obſerved, that in freſh luxations, eſpecially in a body ſoft, effeminate, moiſt, and not over corpulent, that it ſometimes comes to paſs, that by the onely means of juſt extenſion, the head of the bone freed from the muſcles and other particles wherewith it was, as it were, entangled, will betake it ſelf into its proper cavity; the muſcles being by this means reſtored their place and figure, and drawing the bone with them, as they draw themſelves towards their heads, as it were with a ſudden gird or twitch: wherefore in many, whileſt we thought

Gal. com. ad ſent. 23. ſect. 1. de art.

An Expreſſion of the firſt manner of putting a Shoulder into joint.

thought no ſuch thing, it ſufficed or reſtitution only to have extended the arm. But if the luxation be inveterate, and the hand cannot ſerve, then muſt the Patients ſhoulder be faſtned to a poſt with the forementioned ligature, or elſe committed to ones charge, who may ſtand at his back and hold him faſt: Then the arm ſhall preſently be tied about, a little above the elbow with a fillet, whereto a cord ſhall be faſtned; which being put or faſtned to the pulley, ſhall be drawn or ſtretched forth as much as need ſhall require. Laſtly, the Surgeon, with a towel, or ſuch like ligature, faſtned about his neck and hanging down, and ſo put under the Patients arm-pit, near to the luxation, ſhall, raiſing himſelf upon his feet with the whole ſtrength of his neck, lift up the ſhoulder, and alſo at the ſame time bringing his arm to the Patients breſt, ſhall ſet the head of the ſhoulder-bone, forced with both his hands into its cavity, as you may ſee by the precedent Figure. Then muſt you cover all the adjacent parts with a Medicin made *ex farina volatili, bolo armenio, myrtillis, pice, reſina & alumine*, beaten into Powder, and mixed with the white of an Egg. Then muſt the hollowneſs under the arm be filled with a clew of woollen or cotten yarn, or a linnen cloth ſpred over with a little Oil of Roſes or Myrtles, a little Vinegar, and *unguentum roſatum*, or *refrigerans Galeni*, leſt it ſtick to the hairs, if there be any there. The part muſt afterwards be bound up with a ligature, conſiſting of two heads, of ſome five fingers bredth, and two ells long; more or leſs, according as the body ſhall require. The midſt thereof ſhall be put immediately under the arm-pit, and then croſſed over the lame ſhoulder, and ſo croſſing it as much as ſhall be fit, it ſhall be wrapped under the oppoſite arm. And laſtly, the arm ſhall be laid upon the breſt, and put in a ſcarf, in a middle figure almoſt to right angles, ſo that by litting up the hand he may almoſt touch his ſound ſhoulder, leſt the bone newly ſet, may fall out again: neither ſhall the firſt dreſſing be ſtirred, untill four or five days be paſt, unleſs the greatneſs of ſome happening ſymptom divert us from this our purpoſe.

A perfect ſetting the luxated ſhoulder by extenſion onely.

CHAP. XXIII.

Of the ſecond manner of reſtoring a Shoulder, that is, with the heel, when as the Patient by reaſon of pain, can neither ſit nor ſtand.

THe Patient muſt be laid with his back on the ground upon a coverlid, or mat, and a clew of yarn, or leathern ball, ſtuffed with Tow or Cotton, of ſuch bigneſs as may ſerve to fill up the cavity, muſt be put under his arm-pit, that ſo the bone may ſtraight-ways the more eaſily be forced by the heel into its cavity. Then let the Surgeon ſit beſide him, even over againſt the luxated ſhoulder; and if his right ſhoulder be luxated, he ſhall put his right heel to the ball, which filled up the arm-pit; but if the left, then the left heel; then let him forth-with draw towards him the Patients arm, taking hold thereof with both his hands, and at the ſame inſtant of time ſtrongly preſs the arm-pit with his heel. Whileſt this is in doing, one

Hipp. ſent. 12. ſect. 1. de art.

The expreſſion of the ſecond manner of reſtoring a Shoulder.

one ſhall ſtand at the Patients back, who ſhall lift up his ſhoulder with a towel, or ſome ſuch thing fitted for that purpoſe, and alſo with his heel preſs down the top of the ſhoulder blade: another alſo ſhall ſit on the other ſide of the Patient, who holding him, ſhall hinder him from ſtirring this way or that way at the neceſſary extenſion in ſetting it, as you may ſee it expreſſed by the precedent figure.

CHAP. XXXIV.

The third manner of reſtoring a Shoulder.

SOme one who is of a competent height and ſtrength, ſhall put the ſharp part of the top of his ſhoulder under the Patients arm-pit, and alſo at the ſame time, ſhall ſomewhat violently draw his arm towards his own breſt, ſo that the Patients whole body may (as it were) hang thereby. In the mean time another, for the greater impreſſion, ſhall lay his weight on the luxated ſhoulder, ſhaking it with his whole body. Thus the ſhoulder, drawn downwards by the one which ſtands under the arm-hole, and moved and ſhaken by the other, who hangs upon it, may be reſtored into its ſeat, by the help of the Surgeon concurring therewith, and with his hand governing theſe violent motions, as this Figure ſhews.

The Figure of the third manner of putting a Shoulder into joint.

CHAP. XXV.

Of the fourth manner of reſtoring a diſlocated ſhoulder.

The Figure of the fourth manner of reſtoring the ſhoulder.

YOu muſt take a Perch, or piece of wood (ſomewhat reſembling that which the Water-bearers of *Paris* uſe to put on their ſhoulders) ſome two inches broad, and ſome ſix foot long; in the midſt hereof let there be faſtned a clew of Yarn, or ball of ſufficient bigneſs to fill up the cavity of the arm-hole: Let there be two pins put in, one on each ſide of the ball, each alike diſtant therefrom, with which, as with ſtays, the ſhoulder may be kept in, and upon the ball, that it ſlip not away from it: Let two ſtrong men, taller than the Patient, either by Nature or Art, put this Perch upon their ſhoulders; then let the Patient put his arm-pit upon that place where the ball ſtands up; the Surgeon muſt be ready to pull his hanging arm downwards. Thus the Patient ſhall (as it were) hang on the Perch with his ſhoulder, and ſo the head of the bone ſhall be forced into its cavity, as this figure declares; wherein you may ſee the Perch or Yoak, with the two wooden Pins and Ball faſtned in the midſt, delineated by it ſelf.

CHAP.

CHAP. XXVI.

Of the fifth manner of putting the ſhoulder into joint, which is performed by a Ladder.

The delineation of the fifth manner of reſtoring a ſhoulder.

YOu may alſo reſtore a ſhoulder diſlocated into the arm-pit, by the help of a Ladder, after this manner. Let ſome round body, as a Ball or Clew of Yarn, which (as we formerly ſaid) may ſerve to fill the arm-pit, be faſtned upon one of the upper ſteps of a Ladder; at the foot of the Ladder ſet a low ſtool, whereupon let the Patient mount; then bind both his legs, and alſo his ſound arm behind his back, leſt, when you are about your operation, he hinder and ſpoil all you do, by laying his hand, or ſetting his foot upon the Ladder: Then let his arm be preſently put over the ſtep of the Ladder, and his arm-pit put upon the there faſtned ball, the Patient in the mean while being wiſhed to come with his whole body as near unto the ſteps of the Ladder as he is able; for otherwiſe, beſides that there is no other hope of reſtoring the luxation, there would be no ſmall danger of breaking the ſhoulder-bone: Alſo let him take heed that he put not his head between the ſteps. Then his arm, bound above the Elbow with filleting, or ſome other ligature fit for that purpoſe, ſhall be drawn down by the hand of ſome that aſſiſt you, and at the ſame time let the ſtool be plucked from under his feet, ſo that he may hang upon the Ladder. Thus by this means the head of the ſhoulder will be reſtored by it ſelf, the endeavour of the Surgeon aſſiſting, and preſſing down the ſhoulder-blade, and moving it to and again. The bone being ſet, the ſtool, which a little before was plucked from under the Patients feet, ſhall be put there again, that he may with the more eaſe and leſs pain, pull back his arm from the ſtep of the Ladder; for if he ſhould lift it high up to draw it over, there would be danger, leſt being newly ſet, and not well ſtaid, the head of the bone might fall out again. I have thought good to have all theſe things here expreſſed, that you may learn this operation, as if you ſee it done before you. I have

Another Figure expreſſing the fourth manner of reſtoring a diſlocated ſhoulder.

Another Figure to the ſame purpoſe.

not

not thought fit in this place to omit the induſtry of *Nicholas Picart*, the Duke of *Guiſe* his Surgeon, who being called to a certain Country man to ſet his ſhoulder being out of joint, and finding none in the place beſides the Patient and his wife, who might aſſiſt him in this work, he put the Patient, bound after the aforementioned manner, to a Ladder; then immediately he tied a ſtaff at the lower end of the ligature, which was faſtned about the Patients arm above his elbow; then put it ſo tied under one of the ſteps of the Ladder, as low as he could, and got aſtride thereupon, and ſate thereon with his whole weight, and at the ſame inſtant made his Wife to pluck the ſtool from under his feet: which being done, the bone preſently came into its place, as you may ſee by the foregoing figure.

If you have never a Ladder, you may uſe a piece of Wood laid acroſs upon two Poſts. Alſo you may uſe a Door, as the other Figure ſhews, wherein you muſt obſerve a flat piece of Wood or *ſpatula*, with ſtrings thereat, whoſe uſe ſhall be ſhewn in the following Chapter.

CHAP. XXVII.

The ſixth manner of reſtoring a ſhoulder luxated into the arm-pit.

Sect.1.lib.1.de art.ſent.19. HIppocrates writes, that this is the beſt way of all to reſtore a diſlocated ſhoulder. You muſt take a woodden *ſpatula* of ſome four or five fingers breadth, and ſome two fingers thickneſs or leſs, but ſome yard or thereupon long; the one end thereof muſt be narrow and thin, with a round head ſtanding up and lightly hollowed, that put under the arm-pit, it may receive part of the head of the ſhoulder. This upper part of the *ſpatula* muſt be wrapped about with a linnen or woollen rag, or ſome ſuch ſoft thing, that it may be the ſofter and hurt the leſs; and then it muſt be ſo thruſt under the arm-pit, that it may throughly penetrate into the inner part between the ribs, and the head of the ſhoulder-bone. There muſt, beſides in this *ſpatula*, be two holes in three ſeveral places, each alike diſtant from other, through which let ſoft ſtrings be put, whereby it may be tied to the arm, ſtretched all the length thereof even to the fingers, in one place a little below the head of the ſhoulder-bone, in another a little above the elbow, and the third at the wriſt, that ſo they may hold it firm: Therefore let the diſtances of the holes be fitted to this purpoſe; but principally you muſt have a care of this, that the upper part of the *ſpatula*, reaching beyond the head of the arm, enter even to the innermoſt cavity of the arm-pit; then a croſs pin or piece of wood muſt be made faſt through two Poſts or a Frame, and well faſtned thereto, and thereupon the Arm with the *ſpatula* muſt be ſo put over, that the pin may be under the arm-pit, the body weighing one way, and the arm another: which being done, the arm muſt be drawn down one way, and the body another about the pin. Now this croſs pin muſt be put on ſuch a height that the Patient may ſtand on tip-toes Now this is the very beſt way of reſtoring a ſhoulder. In ſtead of two Poſts or a Frame, you may make ſhift with a Ladder, Door, Bed-poſts, and ſuch like things as ſhall be there preſent. I have heard *Henry Arvet*, a very good Surgeon of *Orleans* ſay, that he never attempted this manner of putting into joint a ſhoulder diſlocated into the arm-pit without good ſucceſs, unleſs by chance (which alſo is noted by *Hippocrates*) that the fleſh is grown into the cavity, and the head of the bone hath made it ſelf another cavity in the place whereinto it is fallen, for in this caſe the bone will either not be reſtored, or elſe not remain in its place, but fall back notwithſtanding into the new hollowed cavity, which ſerves it in ſtead of its natural ſocket or cavity. But I muſt here admoniſh young Surgeons, that if the bone be not reſtored at the firſt endeavour and on-ſet, that they do not deſpair and preſently deſiſt from their intended operation, but they muſt winde about, and gently move the joint: for ſo at the length it will be more eaſily moved, and enter into the natural cavity: When it is in, it muſt be bound up with compreſſes and rowlers after the fore-mentioned manner.

The deſcription of the *Gloſſocomium*, termed *Ambi.*

Sect.1. de art. ſent.21.

Hippocrates *his* Gloſſocomium *termed* Ambi.



Hippo ſent.64. 4. de artic. To the former Figures I have thought good to add this, which expreſſeth the manner of reſtoring a ſhoulder luxated into the arm-pit, with a *ſpatula* after the manner of *Hippocrates*. This *ſpatula* faſtned with an iron pin to the ſtanding Frame, may be turned, lifted up, and preſſed down at your pleaſure. *A* Shews the wooden *ſpatula*. *B* The frame or ſtanding poſts.

How to make uſe of the *Ambi.* For the more certain uſe of this Inſtrument the Patient muſt ſit upon a ſeat which muſt be ſomewhat lower than the ſtanding Frame, that ſo the *ſpatula* which is thruſt into the arm-pit may be the more forcibly depreſt, ſo to force in the head of the ſhoulder-bone; the Patients feet muſt alſo be tied, that he may not raiſe himſelf up whileſt the Surgeon endeavours to reſtore it. Now he ſhall then endeavour to reſtore it when he ſhall have bound the ſtretched forth arm of the diſlocated ſhoulder unto the *ſpatula*, and thruſt the one end thereof under the ſlipped forth head of the ſhoulder-bone, as we have formerly ſhewed, for then by preſſing down the other end of the *ſpatula* which goes to the hand, the bone is forced into its cavity. You muſt diligently obſerve the wooden *ſpatula*, which therefore I have cauſed to be expreſſed by it ſelf, which *Hippocrates* calleth *Ambi*, whoſe head is a little hollowed, where it is noted with this letter *B*. The whole *ſpatula* is marked with this letter *A*. with three

three ſtrings hanging thereat, provided for the binding of the arm, that it may be kept ſteddy, as you may perceive by the annexed figure.

There are other additions to this *Ambi*, whoſe figure I now exhibited to your view, by the invention of *Nicholas Picart* the Duke of *Lorrain*'s Surgeon, the uſe and knowledge whereof, beſtowed upon me by the inventor himſelf, I would not envy the ſtudious Reader.

Another Figure of an Ambi *with the Additaments.*



AA *Shews the two ears, as it were ſtops made to hold and keep in the top of the ſhoulder, leſt it ſhould ſlip out when it is put into the frame or ſupporter.*

BB *The frame or ſupporter whereon the* Ambi *reſts.*

CC *The pin or axeltree which faſtens the* Ambi *to the ſupporter.*

DD *Screw-pins to faſten the foot of the ſupporter that it ſtir not in the operation.*

EE *The holes in the foot of the ſupporter, whereby you may faſten the Screw-pins to the floor.*

CHAP. XXVIII.

How to reſtore a Shoulder diſlocated forwards.

IT is ſeldom that the ſhoulder is luxated towards the foreſide; yet there is nothing ſo ſtable and firm in our bodies which may not be violated by a violent aſſault; ſo that thoſe bones do alſo fall out of joynt, whoſe articulations are ſtrengthned for the firmer connexion with fleſhy, nervous, griſtly and bony ſtays, or bars: This you may perceive by this kind of diſlocated ſhoulder, ſtrengthned, as it were, with a ſtrong wall on every hand; to wit, the *Acromium* and the end of the collar-bone, ſeeming to hinder it, as alſo the great and ſtrong muſcles, *Epomis*, and *Biceps*. *Hippocrates*, ſhut up within the ſtrait bounds of the leſſer *Aſia*, never ſaw this kind of diſlocation, which was obſerved five times by *Galen*: I profeſs I have ſeen it but once, and that was in a certain Nun, which weary of the Nunnery, caſt her ſelf down out of a window, and bore the fall and weight of her body upon her elbow, ſo that her ſhoulder was diſlocated forwards. This kind of diſlocation is known by the depravation of the conformation or figure of the member, by the head

Com. ad ſent. 22. & 23. ſect. 1 de articulis.

Signs.

Cure. of the ſhoulder wreſted out towards the breaſt, as alſo the Patient cannot bend his elbow: It is reſtored by the ſame means as other luxations of other parts, to wit, by ſtrait holding, extending and forcing in: Therefore the Patient muſt be placed upon the ground with his face upwards, and then you muſt extend the ſhoulder otherwiſe than you do when it is luxated into the arm-pit; for when it falleth into the arm-hole, it is firſt drawn forwards, then forced upwards, until it be brought juſt againſt the cavity whereinto it muſt enter: But in this kind of luxation, becauſe the top of the ſhoulder is in the foreparts of the dearticulation ſhut up with muſcles, opened both to the outer, as alſo the inner part, you muſt work to the contrary; to wit, to the hind part: But firſt of all you muſt place a ſervant at the back of the Patient, who may draw back a ſtrong and broad Bandage caſt about the arm-pit (ſuch as is the *Carchefius*, which conſiſts of two contrary and continued ſtrings) leſt that when the arm ſhall be extended, the ſhoulder follow: Alſo you muſt *Sent. 23. fol. 1. de art.* put a clew of yarn to fill up the arm-pit; then muſt you extend the arm, caſting another ligature a little above the elbow, and in the interim have a care that the head thereof fall not into the arm-pit, which may be done both by putting the fore-mentioned clew under the arm, and drawing the head another way; then muſt you perm it, by ſlacking your extenſion, the joynt from the encompaſſing muſcles, to be drawn and forced into its cavity by the muſcles forcible recoiling, as with an unanimous conſent, into themſelves and their originals, for thus it will eaſily be reſtored, and ſuch extenſion only is ſufficient thereto.

CHAP. XXIX.

Of the ſhoulder luxated outwardly.

Signs. THe diſlocation alſo of the ſhoulder to the outward parts ſeldom happens; but yet, if it may at any time happen, the extenſion of the arm will be very difficult, but yet more difficult towards the outward part than towards the inward: There is a depreſſed cavity perceived towards the cheſt; but externally a bunching forth, to wit, in that part from whence the The cure. head of the ſhoulder-bone is fled: For the reſtoring hereof, the Patient muſt be laid flat on his belly, and the elbow muſt be forcibly drawn contrary to that whereto it is fled, to wit, inwardly to the breaſt; and alſo the ſtanding-forth head of the arm-bone muſt be forced into its cavity, for thus it ſhall be eaſily reſtored: But into what part ſoever the ſhoulder-bone is diſlocated, the arm muſt be extended and drawn directly downwards. After the reſtitution fitting medicines What to be done to hold in the ſhoulder after it is reſtored. ſhall be put about the joynt. Let there be ſomewhat put into the arm-pit which may fill it up, and let compreſſes or boulſters be applied to that part to which the luxated bone fell; then all theſe things ſhall be ſtrengthened and held faſt with a ſtrong and broad two headed ligature put under the arm-pit, and ſo brought acroſs upon the joynt of the ſhoulder, and thence carried unto the oppoſite arm-pit by ſo many windings as ſhall be judged requiſite: Then the arm muſt be put and carried in a ſcarf to right angles, which figure muſt be obſerved not only in every luxation of the ſhoulder, but in each fracture of the arm alſo, for that it is leſs painful, and conſequently, ſuch as the arm may ſtand the longeſt therein without moving.

CHAP. XXX.

Of the Shoulder diſlocated upwards.

Signs. THe head of the ſhoulder alſo may ſometimes be luxated into the upper part: Which when it happens, it ſhews it ſelf by bunching forth at the end of the collar-bone, the hollowneſs of the arm-pit is found larger than uſual, the elbow flies further from the ribs than Cure. when it fell downwards, now the arm is wholly unable to perform the uſual actions. It is fit for the reſtitution of ſuch a luxation, that the Surgeon ſtoop down, and put his ſhoulder under the Patients arm, and then ſtand up as high as he can upon his feet, and therewithal preſs down the head of the ſhoulder-bone into the cavity, or elſe make ſome other to do it. Otherwiſe it is fit to lay the Patient upon his back on the ground, and whilſt ſome one extends the affected arm by drawing it downwards, the Surgeon with his own hand may force down the head of the bone into its cavity. The operation performed, the ſame things ſhall be done as in other luxations, compreſſes being applied to that part whereto the bone flew, and it being alſo bound up with ligatures. Now you may underſtand in theſe four fore-mentioned kinds of diſlocations, that the bone which was luxated is reſtored, by the ſound which ſhall be heard as you force it in, by the reſtitution of the accuſtomed actions, which are perceived by the bending, extending and lifting it up, by the mitigation of the pain, and laſtly, by the collation and comparing of the affected arm with the ſound, and by its ſimilitude and equality therewith.

CHAP.

CHAP. XXXI.

Of the Diſlocation of the Elbow.

THe elbow may alſo be four manner of ways diſlocated; to wit, inwardly, outwardly, upwards and downwards. By the part which is inwards, I mean that which looks towards the center of the body, when as the arm is placed in a natural ſite, to wit, in a middle figure between prone and ſupine; I make the outward part, that which is contrary thereto. By the upper part I mean that which is towards the heaven, and by the lower that which is next to the earth: And by how much the joynt of the elbow conſiſts of more heads and cavities than that of the ſhoulder, by ſo much when it is luxated it is the more difficultly ſet, and is alſo more ſubject to inflammation, and to grow hard thereupon, as *Hippocrates* ſaith. Now the joynt of the elbow is more difficultly diſlocated than that of the ſhoulder, and more hardly ſet, for that the bones of the cubit and arm do receive and enter each other by that manner of articulation which is termed *Ginglymus*, as we have formerly more at large treated in our Anatomy, and a little before in our Treatiſe of Fractures. The elbow is therefore diſlocated, for that the proceſſes thereof are not turned about the ſhoulder-bone in a full orb, and by an abſolute turning. Wherefore if at any time the cubit be bended more ſtraitly and cloſely than that the inner proceſs can retain its place and ſtation in the bottom of its *ſinus*, the hind-proceſs fal'eth out and is diſlocated backwards: But when as the fore-proceſs is extended more violently, and forced againſt the bottom of its cavity, it flies and departs out of its place as beaten or forced thence, and this kind of luxation is far more difficultly reſtored than the former: Add hereunto, that the utter extremity of the cubit, which is called *Olecranum*, is the higher, but the other inner is the lower; whence it is that every one can better and more eaſily bend than extend their cubits: Therefore ſuch a diſlocation is cauſed by a more violent force, than that which is made to the inner ſide. * The ſign of this luxation is, the arm remains extended, neither can it be bended, for the inner proceſs ſtays in the external cavity which is hollowed in the bottom of the ſhoulder-bone, which formerly was poſſeſſed by the inner part of the *Olecranum*; which thing makes the reſtitution difficult, for that this proceſs is kept, as it were, impriſoned there: But when it falleth out diſlocated to the fore-part, the arm is crooked, neither is it extended, and it is alſo ſhorter than the other. But if the elbow be fallen out of its place according to the other manner of diſlocations, to wit, upwards or downwards, the natural figure thereof is perverted, for the arm is ſtretched forth, but little notwithſtanding bended towards that part from whence the bone went, that is, figured after a middle manner between bending and extending thereof. What kind ſoever of diſlocation ſhall befal it, the action of the elbow will either not be at all, or certainly not well, until that it be reſtored to its former place; there is a ſwelling in the part whereinto it is flown, and a cavity there from whence it is fled, which alſo happens in the diſlocations of all other parts. Furthermore, one diſlocation of the elbow is complete and perfect, another imperfect. The later as it eaſily happens, and through a ſmall occaſion, ſo it is eaſily reſtored; but on the contrary a perfect, as it hardly happens, and not unleſs with great violence, ſo it is not ſo eaſily reſtored again, eſpecially if that you do not prevent inflammation, for being inflamed it makes the reſtitution either difficult, or wholly impoſſible, principally that which falleth outwards.

The Author ſeems not to agree with *Hip. Sent. ult. ſect. 3. fract.* and *Celſus* in the ſetting down the kinds of a diſlocated elbow.

* The Author doth not agree with *Hippocr.* and *Celſus*, in ſetting down the notes of theſe diſlocations: for thoſe notes which are here attributed to an outward and inward luxation, theſe *Celſus* hath given to an elbow diſlocated towards the fore and out-part; and thoſe which are here attributed to the elbow, diſlocated upwards and downwards; thoſe *Celſus* hath attributed to a diſlocation to the out and infides.

Inflammation hinders repoſition.

CHAP. XXXII.

How to reſtore the Elbow, diſlocated outwardly.

YOu may know that the elbow is diſlocated outwardly, if at any time you ſhall obſerve the arm to be diſtended, and not able to be bended. Wherefore you muſt forthwith undertake the reſtitution thereof, for fear of defluxion and inflammation which the bitterneſs of pain uſually cauſeth, upon what part ſoever the luxation happens. There is one manner of reſtoring it, which is, you muſt cauſe one to hold hard and ſteddy the Patients arm a little under the joynt of the ſhoulder, and in the mean while let the Surgeon draw the arm, taking hold thereof with his hand, and alſo force the ſhoulder-bone outwards, and the eminence of the cubit inwards, but let him by little and little draw and extend the arm, wreſting it gently this way and that way, that he may bring back the bone which fell out into its cavity. I have thus expreſly delivered this, that the young Surgeon may underſtand, that the arm muſt not be bended for the reſtoring of this kind of diſlocation; for reſtitution cannot ſo be hoped for, becauſe by this kind of luxation the inner proceſs of the cubit poſſeſſeth the place of the exterior proceſs in the cavity of the ſhoulder-bone. Wherefore whilſt the arm is bended or crooked, the cubit is only lifted up, and not drawn into its ſeat. But if we cannot attain to the reſtitution thereof with our hands alone, you muſt cauſe the diſlocated arm, lightly bended, to embrace a poſt, then muſt the end of cubit called *Olecranum* be tied or bound about with a ſtrong ligature or line, and then reſted into its cavity by putting a battoon or ſtaff into the ligature, as is demonſtrated by this enſuing figure.

Sign.

Cure.

A Caution.

A Figure which ſhews the way how to reſtore the Elbow by putting it about a poſt, with a batton.

A Figure which ſhews how to reſtore the Elbow by only caſting a line about it.

Thereis alſo another more exquiſite way of reſtoring it, which is expreſſed by the latter figure wherein a line of ſome inch breadth is caſt about the *Olecranum* of the arm, embracing a poſt or pillar, and it is drawn ſo long, until the diſlocated bone be brought into its ſeat. Now we know that the bone is returned into its place, and reſtored, when the pain ceaſeth, and the figure and whole natural conformation is reſtored to the arm, and the bending and extending thereof is eaſie, and not painful.

CHAP. XXXIII.

Of the Diſlocation of the Elbow to the inſide, and of a complete and uncomplete Luxation.

The cure.

IF the elbow be diſlocated to the inner part, the arm muſt be ſtrongly and powerfully extended, then bended quickly, and with ſudden violence, ſo that his hand may ſmite upon his ſhoulder. Some put ſome round thing into the bout of the elbow, and upon that do ſuddenly force the elbow to the ſhoulder, as we have formerly ſaid. If the cubit-bone be only lightly moved out of its place into the upper or lower place, it is eaſily reſtored by drawing and forcing it into its cavity, after this following manner. Let two extend the arm, taking hold thereof at the ſhoulder and wriſt, and each draw towards himſelf: And alſo the Surgeon (who ſhall there be preſent) ſhall force the bone which is diſlocated from that part whereunto it is bended, unto the contrary: After he ſhall thus have reſtored it, he ſhall lay the arm in a ſtrait angle, and ſo bind it up, and apply fit medicines formerly mentioned, and ſo let him carry it in a ſcarf put about his neck, as we ſaid in the diſlocation of the ſhoulder. *Hippocrates* bids, that the Patient, after it is ſet, ſhall often endeavour to bend his hand upwards and downwards, and alſo extend and bend his arm, yea, and alſo to attempt to lift up ſome heavy thing with his hand; for ſo it will come to paſs, that the ligaments of this joynt may become more ſoft, ready and able to perform their accuſtomed functions, and alſo the bones of the cubit and ſhoulder ſhall be freed from the affect termed *Ancyloſis*, whereto they are incident by the luxations of this part. Now *Ancyloſis* is a certain preternatural agglutination, coagmentation, and, as it were, union of ſundry and ſeveral bones in the ſame joynt, which afterwards hinders the bending and extenſion thereof. Now a *Callus* is generated in the elbow ſooner than in any other articulation, whether it remaineth out, or be put into joynt, by reaſon that by reſt and ceſſation from the accuſtomed actions, a viſcid humor which is placed naturally in the joynts, as alſo another which is preternatural drawn thither by pain, floweth down, and is hardned, and gleweth the bones together, as I have obſerved in many, by reaſon of the idleneſs and too long reſt of this part: Wherefore that we may withſtand this affect, the whole ligation muſt be looſed ſooner and oftner than otherwiſe, that is to ſay, every third day, and then the Patients arm muſt be gently moved every way. Within the ſpace of twenty, or twenty five days, theſe reſtored Bones recover their ſtrength, ſooner or later, according to the hapning accidents. It is neceſſary alſo that the Surgeon know that the *Radius*, or wand, ſometimes falleth out, when the cubit or ell is wholly diſlocated; wherefore he muſt be mindful in ſetting the cubit, that he alſo reſtore

Sent. 63. ſect. 3. de fract.

Why the elbow is moſt ſubject to *Ancyloſis.*

the

the wand to its place; in the upper part it hath a round proceſs lightly hollowed, wherein it receiveth the ſhoulder-bone: it hath alſo an eminency which admitteth the two headed muſcle.

CHAP. XXXIV.

Of the Diſlocation of the Styliformis, or bodkin-like proceſs of the Cubit or Ell.

THe proceſs of the Ell called *Styloides*, being articulated to the wriſt by *Diarthroſis*, by which it is received in a ſmall cavity, is diſlocated, and falleth out ſometimes inwards, ſomewhiles outwards: The cauſe uſually is the falling of the body from high upon the hands: It is reſtored, if that you force it into its ſeat, diligently bind it, and apply thereto very aſtringent and drying medicines: But yet, though you ſhall diligently perform all things which may be done in diſlocations, yet you ſhall never ſo bring it to paſs that this bone ſhall be perfectly reſtored, and abſolutely put into the place where-hence it went: Which thing we have read, obſerved by *Hippocrates*; When (ſaith he) the greater bone, to wit, the Ell, is removed from the other, that is, the Wand, it is not eaſily reſtored to its own nature again; for that, ſeeing that neither any other common connexion of two bones, which they call *Symphyſis* or union, when it is drawn aſunder and deſtroyed, may be reduced into its former nature, by reaſon theſe ligaments wherewith they were formerly contained, and as it were continued, are too violently diſtended and relaxed, whence it happens, that I have in theſe caſes often obſerved, that the diligence and care of the Surgeon hath nothing availed.

Differences and cauſes.

Cure.

Sent. 1. *ſect.* 2. & *ſent. ult. ſect.* 3. *de fract.*

CHAP. XXXV.

Of the Diſlocation of the Wriſt.

WE underſtand by the wriſt, a certain bony body, conſiſting of a compoſure of eight bones knit to the whole cubit by *Diarthroſis*: For the wriſt conſidered wholly in its ſelf, is knit and articulated with the ell and wand: With that, againſt the little finger; with this, againſt the thumb: For thus, as it were, by two connexions the joynt is made more firm; yet may it be diſlocated inwardly, outwardly, and towards the ſides. We ſay it is luxated inwardly when the hand ſtands upwards, but outwardly, when it is crook'd in and cannot be extended: But if it chance to be diſlocated ſide-ways, it ſtands awry either towards the little finger, or elſe towards the thumb, as the luxation befals to this or that ſide. The cauſe hereof may ſeem to depend upon the different dearticulation of the ell and wand with the hand or wriſt: For the wand, which is articulated on the lower part with the wriſt at the thumb, by its upper part, whilſt it receives the outward ſwelling or condyle of the ell in its cavity, performs the circular motions of the hands: But the cubit or ell, which in like ſort is connected on the lower part by *Diarthroſis* at the little finger with the wriſt, being articulated on the upper part with the ſhoulder-bone, bends and extends, or ſtretches forth the hand. There is one way to reſtore the formerly mentioned diſlocations: The arm on one ſide and the hand on another muſt be extended upon a hard reſiſting and ſmooth place, ſo that it may lie flat; and you muſt have a care that the part whence the diſlocated bone fell, be the lower in its ſite and place, and the part whither it is gone, the higher: Then to conclude, the prominencies of the bones muſt be preſſed down by the hand of the Surgeon, until by the force of compreſſion and ſite the luxated bones be thruſt and forced into their places and cavities.

Here, as before *chap.* 31. the Author diſſents from *Celſus* and *Hippocrat.* in expreſſing the names and ſigns of theſe diſlocations.

CHAP. XXXVI.

Of the diſlocated bones of the Wriſt.

THe wriſt conſiſts of eight bones, which cannot, unleſs by extraordinary violence, be put or fall out of their places. Yet if they ſhall at anytime fall out, they will ſhew it by the tumor of the part whereto they are gone, and by the depreſſion of that wherefrom they are fled: They may be reſtored, if the diſeaſed hand be extended upon a table; and if the bones ſhall be diſlocated inwards, the hand ſhall be placed with the palm upwards, then the Surgeon ſhall, with the palm of his hand, preſs down the eminencies of the bones, and force each bone into its place: But if the luxation be outwards, he ſhall lay the palm next to the table, and preſs it after the ſame manner. To conclude, if the luxation ſhall be toward either ſide, the luxated bones ſhall be thruſt towards the contrary, and the reſtored bones ſhall be preſently contained in their places with fit remedies, binding, rowling, and carrying the hand in a ſcarf.

Sign.

Cure.

CHAP. XXXVII.

Of the diſlocated bones of the After-wriſt.

THere are four bones in the palm or after-wriſt, the two middlemoſt whereof cannot be diſlocated ſide-ways, becauſe they are hindred and kept from falling aſide by the oppoſition of the parts, as it were reſiſting them. Neither can that which anſwereth to the little finger, nor that whereon the fore-fingers reſt, be diſlocated towards that ſide which is next the middle bones, whereof we now ſpake, but only on the other ſide, freed for the neighbour-hood of the bones: But all of them may be diſlocated inwardly and outwardly. They may be reſtored as thoſe of the wriſt.

Celſus lib. 8. *cap.* 18.

CHAP. XXXVIII.

Of the diſlocated Finger.

Why the diſlocated fingers may be eaſily reſtored.

ALſo the bones of the fingers may be four ſeveral ways diſlocated, inwardly, outwardly, and at each ſide. To reſtore them, they muſt be laid ſtrait upon a table, and ſo put into joynt again. For thus they may be eaſily reſtored, by reaſon their ſockets are not deep, and their joints are ſhorter, and ligaments leſs ſtrong. In twelve days ſpace they will recover their ſtrength, as alſo thoſe diſlocations that happen to the wriſt and after-wriſt.

CHAP. XXXIX.

Of a diſlocated Thigh or Hip.

Hipp. ſent. 68. ſect. 3. de art.

THe thigh or hip may be diſlocated, and fall forth towards all the four parts, but moſt frequently inwards, next to that outwards, but very ſeldom either forwards or backwards. A ſubluxation cannot happen in this joynt, as neither in the ſhoulder, eſpecially from an external cauſe, contrary to which it uſually happens in the elbow, hand, knee, and foot. The cauſe hereof is, for that the heads of thigh and ſhoulder-bone are exactly round, and the ſockets which receive them have certain borders and edges encompaſſing them. Hereunto may be added, that ſtrong muſcles encompaſs each dearticulation, ſo that it cannot come to paſs that part of the heads of ſuch bones may be contained in the cavity, and other parts ſtand or fall forth, but that they will quickly be reſtored to their places by the motion and wheeling about of the joynt, and the ſtrength of the encompaſſing muſcles. But a ſubluxatio may ſeem to happen in theſe parts from an internal cauſe. For then the ligaments and ties being ſoftned and relaxed, cannot draw and carry back the head of the bone ſtanding forth ſo far as the edges of the ſocket. If the hip be diſlocated towards the inner part, that leg becomes longer and larger than the other, but the knee appears ſomewhat lower, and looks outwardly with the whole foot, neither can the Patient ſtand upon his leg. To conclude, the head of the thigh-bone bewrays it ſelf lying in the groin, with a ſwelling manifeſt both to the eye and hand; now the leg is longer than that which is ſound, for that the head of the thigh is out of its ſocket or cavity, and ſituated lowered, to wit, in the groin, therefore the leg is made by ſo much the larger. Now the knee ſtands forth, becauſe neceſſarily the lower head of the thigh-bone ſtands contrary to the ſocket. For this is common to all diſlocated bones, that when as the diſlocation happens to the one ſide, the other end of the bone flies out to the contrary. Whence it is, that if the upper-head of the thigh-bone ſhall fall inwards, then the other head, which is at the knee, muſt neceſſarily look outwards. The like happens in other diſlocations. The leg cannot be bended towards the groin, for that the diſlocated bone holds the extending muſcles of the ſame part ſo ſtiffly ſtretched out, that they cannot yield, or apply themſelves to the benders. For flexion or bending ought to precede extenſion, and extenſion, flexion.

Gal. com. ad ſent. 47 ſect. 4. de art.

A ſubluxation may befal the thigh from an internal cauſe.

CHAP. XL.

Prognoſticks belonging to a diſlocated Hip.

Why the thigh bone diſlocated, is difficultly reſtored, or reſtored, eaſily falls out again.

THere is this danger in the diſlocation of the hip, that either the bone cannot be put into the place again, at leaſt unleſs with very much trouble, or elſe being put in, that it may preſently fall out again. For if the tendons of the muſcles, the ligaments, and other nervous parts of the member be hard and ſtrong, they, by reaſon of their contumacy and ſtiffneſs will hardly ſuffer the bone to return to its place. If that they be ſoft, looſe, effeminate and weak, they will not contain the reſtored bone in its place. Neither will it be any better contained, if that ſhort, but yet ſtrong and round ligament, which faſtens the head of the thigh-bone on the inſide in the ſocket or cavity of the huckle-bone, be broken or relaxed. Now it may be broken by ſome violent ſhock or accident, it may be relaxed by the congeſtion and long ſtay of ſome excrementitious, tough and viſcous humour lying about the joynt, through which means it waxeth ſoft. But if it be broken, how often ſoever the bone be reſtored, it will preſently fall out again. If it be relaxed, there is only this hope to contain the reſtored bone, that is, To conſume and draw away the heaped up humidity by application of Medicines and Cauteries of both kinds, for which purpoſe thoſe are more effectual which do actually burn, for that they dry and ſtrengthen more powerfully. Leanneſs of the body, and the want of *Aponeuroſes*, that is, of broad tendons, and external ligaments, whereof many encompaſs the knee, increaſes the difficulty of containing it in the place. But the parts adjoyning to the diſlocated and not-ſet bone fall away by little and little, and conſume with an *Atrophia* or want of nouriſhment; both becauſe the part it ſelf is forced to deſiſt from the accuſtomed actions and functions, as alſo for that the veins, arteries and nerves being more ſtraitned and put out of their places, hinder the ſpirits and nouriſhment frow flowing ſo freely as they ought, to the part: Whence it comes to paſs, that the part it ſelf is made more weak, the native heat being debilitated through idleneſs, it can neither attract the alimentary juice, neither can it digeſt and aſſimilate that little thereof which flows and falleth thereto. Verily the thigh-bone, as long as it is forth of the cavity, grows no more after the manner as the other bones of the body do, and therefore in ſome ſpace of time you may perceive it to be ſhorter than the ſound bone. Notwithſtanding the bones of the leg and foot are not hindred of their growth,

The breaking and relaxation of the internal ligament.

Gal. com. ad ſent. 42. ſect. 4. de art.

growth, for they are not out of their proper places. Now for that the whole leg appears more ſlender, you muſt think that happens only by the extenuation and leanneſs of the proper muſcles thereof. The ſame thing happens to the whole hand, in the largeſt acception, when as the ſhoulder is out of joynt, unleſs that the calamity and loſs hereof is the leſs. For the ſhoulder being forth of joynt you may do ſomething with your hand, whereby it will come to paſs that no ſmall portion of nouriſhment may flow down into theſe parts. But the thigh-bone being diſlocated, eſpecially inwards in a child unborn, or an infant, much leſs alimentary nouriſhment flows to that part, becauſe it can much leſs uſe the foot and leg by reaſon of the diſlocation of the hip, than it can do the hand by a luxation of the ſhoulder. But now we muſt thus underſtand that which is ſaid by *Hippocrates*, That diſlocated bones, and not reſtored, do decreaſe or are hindred from their juſt growth, to be only in thoſe who have not yet attained to their full and naturally appointed growth in every dimenſion. For in men of full growth, the bones which are not reſtored, become more ſlender, but yet no ſhorter, as appears by that which he hath delivered of the ſhoulder.

Hippocrates explained *ſect.* 1. & 3. *lib. de art.*

CHAP. XLI.

Of the ſigns of the Hip diſlocated outwardly or inwardly.

THe thigh-bone or hip when it is diſlocated outwardly, and not reſtored, after ſome time the pain is aſſwaged, and fleſh grows about it, the head of the bone wears it ſelf a new cavity in the adjoyning hip, whereinto it betakes it ſelf, ſo that at the length the Patients may go without a ſtaff, neither ſo deformed a leanneſs will waſte their leg. But if the luxation happen inwards, a greater leanneſs will befal them, by reaſon that the veſſels naturally run more inwardly as *Galen* obſerves in the diſlocation of the *Vertebræ* to the inſide; therefore it comes to paſs that they are more grievouſly oppreſſed: Beſides, the thigh-bone cannot wag or once ſtir againſt the ſhare-bone; wherefore if the bone thus diſlocated be not reſtored to its joynt again, then they muſt caſt their leg about as they walk, juſt as we ſee Oxen do. Wherefore the ſound leg whilſt they go, takes much leſs ſpace than the lame, becauſe this, whilſt it ſtirreth or moveth, muſt neceſſarily fetch a compaſs about, but that performeth its motion in a right line. Beſides, whilſt the Patients ſtand upon their lame leg to put forwards the ſound, they are forced to ſtand crooked, whereupon they are forced to ſtay themſelves with a ſtaff that they fall not.

Al ſent. 51. *ſect.* 3. *de art.*

Furthermore thoſe who have this bone diſlocated either backwards or outwards, ſo that it cannot be reſtored, have the part it ſelf grow ſtiff and hard; which is the cauſe why the ham may be bended without great pain, and they may ſtand, and go upon the tops of their toes; beſides alſo, when they deſire to go faſter, they are forced to ſtoop, and ſtrengthen themſelves by laying their hand on their lame thigh at every ſtep, both for that their lame leg is the ſhorter, as alſo becauſe the whole weight of the body ſhould not lie wholly or perpendicularly upon the joynt or head of the thigh-bone. Yet in continuance of time, when they are uſed to it, they may go without any ſtaff in their hands. Yet in the interim, the ſound leg becomes more deformed in the compoſure and figure, becauſe, whilſt it ſuccours the oppoſite and lame leg by the ham ſtanding on the ground, it bears the weight of the whole body, in performance whereof the ham muſt neceſſarily now and then bend. But on the contrary, when as the head of the thigh being diſlocated inwards is not put into the joynt, if the Patient be arrived at his full growth, after that the head of the bone hath made it ſelf a cavity in the neighbouring bone wherein it may reſt, he may be able to walk without a ſtaff, becauſe the diſlocated leg cannot eaſily be bended toward the groin or ham, and he will ſooner reſt upon his heel than upon his toes. This kind of diſlocation if it be inveterate, can never be reſtored. And theſe things happen, when as the thigh-bone is diſlocated inwards, or when the internal ligament which faſtens the dearticulation ſhall be broken or relaxed. But the contrary ſhall plainly appear if the diſlocation ſhall happen to be outwards; for then the lame leg becomes the ſhorter, becauſe the head of the thigh flies into a place higher than its cavity, and the muſcles of that part are contracted towards their original, and convulſively draw the bone upwards together with them. The whole leg, together with the knee and foot looketh inwards, they cannot go upon their heels, but upon the ſetting on of the toes. The leg may be bended, which it cannot be in a diſlocation of the thigh inwards, as *Paulus* ſhews. Therefore we muſt diligently obſerve that ſentence of *Hippocrates* which is read with a negative, in theſe words, *Sed neque conflectere quemadmodum ſanum crus poſſunt*, that they ought to be read with an affirmative after this manner, *Sed conflectere, &c. quin & crus ipſum, &c.* But now the lame leg will better ſuſtain the weight of the body in an external, than in an internal diſlocation; for then the head of the thigh is more perpendicularly ſubject to the whole weight of the body. Therefore when in the ſucceſs of time it ſhall by wearing have made it ſelf a cavity in the neighbouring bone, which in time will be confirmed, ſo that there will remain no hope of reſtoring the diſlocation, nevertheleſs the Patient ſhall be able to go without a ſtaff, for that then no ſenſe of pain will trouble him; whence it follows, that the whole leg alſo will become leſs lean, for that going is leſs painful, neither are the veſſels ſo much preſſed as in that diſlocation which is made inwardly.

Signs of the thigh-bone diſlocated outwards.

Paul. Æg. l. 6. c. 8. Hip ſent. 91. ſect. 3. lib. de artic.

CHAP.

CHAP. XLII.

Of the Thigh-bone diſlocated forwards.

IT ſeldom hapneth that the thigh is diſlocated forwards; yet when as it ſhall happen, it is by theſe ſigns. The head of the thigh lieth towards the ſhare; whence the groins ſwell up, and the buttock on the contrary is wrinkled and extenuated by reaſon of the contraction of the muſcles; the Patient cannot extend his leg without pain, no verily, not ſo much as bend it towards the groin, for for the fore-muſcle which ariſeth from the hanch bone is ſo preſſed by the head of the thigh, that it cannot be diſtended; neither can the ham be bended without very much pain, But the ſame leg is equal at the heel with the other leg, yet the Patient cannot ſtand upon the ſetting on of the toes; therefore when he is forced to go, he toucheth the ground with his heel only, yea verily the ſole of his foot is leſs inclined to the foreſide, neither doth it ſeldom happen, that the urine, by this accident, is ſuppreſt; becauſe the head of the thigh oppreſſes the greater nerves from whence thoſe ariſe which are carried to the bladder, which through the occaſion of this compreſſion is pained and inflamed by conſent: Now when inflammation ſhall ſeize upon the *Spinti*-muſcle, the urine can ſcarcely flow out, for that it is hindred by the ſwelling.

Stopping of urine by reaſon of an internal diſlocation of the thigh-bone.

CHAP. XLIII.

Of the Thigh-bone diſlocated backwards.

SEldom alſo is the thigh-bone diſlocated backwards, becauſe the hind-part of the cavity of the huckle-bone is deeper and more depreſſed than the force; whence it is that the diſlocation of the thigh to the inner part is more frequent than the reſt. The Patient can neither extend nor bend his leg by reaſon of the much compreſſion and tention of the muſcles which encompaſs the head of the thigh by this kind of luxation. But the pain is increaſed when he would bend his ham, for that then the muſcles are more ſtrongly extended. The lame leg is ſhorter than the ſound: When the buttocks are preſſed, the head of the thigh is perceived hid amongſt the muſcles of that part, but the oppoſite groin is lax, ſoft, and depreſt with a manifeſt cavity. The heel touches not the ground, for that the head of the thigh is plucked back again by the muſcles of the buttocks, amongſt which it lieth hid: But principally by that which is the larger, and which is ſaid to make, as it were the pillow or cuſhion of the buttocks; for this is much more preſſed in this kind of diſlocation than the reſt: Whence it is, that the Patient cannot bend his knee, becauſe the extention of the nervous production or large tendon which covers the knee is ſo great. But if the Patient will ſtand upon the foot of his luxated leg without a ſtaff, he ſhall fall down backwards, for that the body is inclined to that part, the head of the thigh being not directly underneath for the propping or bearing up of the body; wherefore he is forced to ſuſtain himſelf upon a crutch on his lame ſide. Having promiſed theſe things of the differences, ſigns, ſymptoms and prognoſticks, it now remaineth, that we briefly deſcribe the different ways of reſtoring them, according to the difference of the parts whither it is fallen. Firſt, you muſt place the Patient upon a bench or table, groveling, or with his face upwards, or upon one ſide, laying ſome ſoft quilt or coverlid under him, that he may lie the eaſier. Now you muſt place him ſo, that the part unto which the bone is flown, may be higher, but from whence it is fled, the lower. For if the thigh-bone be diſlocated outwards or backwards, then muſt the Patient be laid groveling; if inwardly, upon his back; if forwards, then upon his ſide. Then muſt extenſion and impulſion be made towards the cavity, that ſo it may be forced thereinto: But if the diſlocation be freſh, and in a ſoft body, as a woman, child, and ſuch like, whoſe joynts are more lax, it ſhall not be any ways needful to make great extenſion with ſtrong ligatures for the reſtoring it; the Surgeons hand ſhall ſuffice, or a liſt or towel caſt about it. In the interim the bone ſhall be kept faſt with compreſſes applied about the joynt: Then the Surgeon ſhall extend the thigh, taking hold thereof above the knee, in a ſtrait line, and ſo ſet it directly againſt the cavity, and then preſently thruſt it thereinto. For thus ſhall he reſtore it, if ſo be that in thruſting it he lift up the head thereof ſomewhat higher, leſt the lips of the cavity force it back, and hinder it from entring. Now becauſe unleſs there be juſt extenſion, there can be no reſtitution hoped for, it is far better in that part, that is, to extend in ſomewhat more than is neceſſary, yet ſo, that you do not endanger the breaking of any muſcles, tendon or other nervous body. For that as *Hippocrates* writes, when as the muſcles are ſtrong and large, you may ſafely extend them, if ſo be that you diſplace nothing by the force of the extenſion. If your hand will not ſuffice to make juſt extenſion, you muſt uſe the help of an Engine, ſuch as is our Pulley, faſtned to two poſts, ſo much of the rope being let forth and drawn up again as ſhall ſuffice for the buſineſs in hand; in the performance whereof, it is fit that the Patients friends abſent themſelves from this ſad ſpectacle, and that the Surgeon be reſolute, and not deterred from his buſineſs by the lamentation, neither of the Patient nor his friends. But for that we write theſe things chiefly for the benefit of young Practicioners, it ſeemeth meet, that having delivered theſe things in general, of reſtoring the thigh-bone, that we run over theſe generalities in each particular, beginning with that diſlocation which is made inwardly.

Signs.

The general cure.

Sect. 2. lib. de fract.

CHAP.

CHAP. XLIV.

Of reſtoring the Thigh-bone diſlocated inwards.

IT is fit to place the Patient after the foreſaid manner, upon a table or bench, in the midſt whereof ſhall ſtand faſtned a wooden pin of a foots length, and as thick as the handle of a ſpade uſeth to be; but it muſt be wrapped about with ſome ſoft cloth, leſt the hardneſs hurt the buttocks, betwixt which it muſt ſtand, as we read that *Hippocrates* did in the extenſion of a broken leg. The wooden pin hath this uſe, to hold the body that it may not follow him that draweth or extendeth it; and that the extenſion being made as much as is requiſite, it may go between the *Peritonæum* and the head of the diſlocated thigh. For thus there is no great need of counter-extenſion towards the upward parts; and beſides it helpeth to force back the bone into its cavity, the help of the Surgeon concurring, who twining ſomewhiles to this, and otherwhiles to that ſide, doth direct the whole work. But when the extenſion hath need of counter-extenſion, then it is needful you have ſuch ligatures at hand, as we have mentioned in the reſtoring of a diſlocated ſhoulder, to be drawn above the ſhoulder. One of theſe ſhall be faſtned above the joynt of the hip, and extended by a ſtrong man; another ſhall be caſt above the knee by another with the like force. But if you cannot have a wooden pin, another ſtrong and like ligature ſhall be put upon the joynt directly at the hip, and held ſtiff by the hands of a ſtrong man, yet ſo that it may not touch the head of the thigh by preſſing it, for ſo it would hinder the reſtoring thereof. This manner of extenſion is common to four kinds of luxation of the thigh-bone. But the manner of forcing the bone into its cavity muſt be varied in each, according to the different condition of the parts whereunto the head inclineth; to wit, it muſt be forced outwards if it be fallen inwards, and contrary in the reſt, as the kind of the diſlocation ſhall be. Some too clowniſh and ignorant knot-knitters faſten the lower ligature below the ankle, and thus the joynts of the foot and knee are more extended than that of hip or huckle-bone, for they are nearer to the ligature, and conſequently to the active force: But they ought to do otherwiſe; therefore in a diſlocated ſhoulder you ſhall not faſten the ligatures to the hand or wriſt, but above the elbow. But if the hands ſhall not be ſufficient for this work, then muſt you make uſe of engines. Wherefore then the Patient being placed as is fit, and the affected part firmly held, ſome round thing ſhall be put into the groin, and the Patients knee, together with his whole leg, ſhall be drawn violently inwards, towards the other leg. And in the mean while the head of the thigh ſhall be ſtrongly forced towards the cavity of the huckle-bone, and ſo at length reſtored, as the following figure ſhews:

Sect. 2. lib. de fract.

How to make extenſion and counter-extenſion in this kind of fracture.

Ligatures made for extenſion muſt be faſtned near the part to be extended.

A Figure which manifeſteth the way of reſtoring the Thigh-bone diſlocated inwards.

When the head of the thigh by juſt extenſion is freed from the muſcles wherewith it was infolded, and the muſcles alſo extended that they may give way and yield themſelves more pliant, then muſt the rope be ſomewhat ſlacked, and then you muſt alſo deſiſt from tending, otherwiſe the reſtitution cannot be performed, for that the ſtronger extenſion of the engine will reſiſt the hand of the Surgeon, thruſting and forcing it into the cavity. This precept muſt be obſerved in the reſtoring of this and other diſlocations. You ſhall know that the thigh is reſtored by the equality of the legs, by the free and painleſs extenſion and inflection of the lame leg. Laſtly, by the application of agglutinative medicines (whereof we have formerly ſpoken) the reſtored bone ſhall be confirmed in its place; to which purpoſe ligation ſhall be made, the ligature being firſt caſt upon the place whereinto the head of the thigh fell, and thence brought to the oppoſite or ſound ſide by the belly and loyns. In the mean while the cavity of the groin muſt be filled with ſomewhat a thick boulſter, which may keep the head of the bone in the cavity. Neither muſt you omit junks ſtretched down even to the ankles, as we have obſerved in the fracture of the thigh. Then muſt both the thighs be bound together, whereby the diſlocated member may be unmoveable, and more and more ſtrengthned. Neither muſt this dreſſing be looſed until four or five days be paſſed, unleſs peradventure the ſudden happening

A general precept.

ning of ſome other more grievous ſymptom ſhall perſwade otherwiſe. To conclude, the Patient muſt be kept in his bed for the ſpace of a month, that the relaxed muſcles, nerves and ligaments may have ſpace to recover their former ſtrength, otherwiſe there is danger leſt the bone may again fall out by the too forward and ſpeedy walking upon it. For the ſite of the thigh it muſt be placed and kept in a middle figure, yet this middle figure conſiſts in the extenſion, not in the flexion, as it is demonſtrated by *Hippocrates*, for that ſuch a figure is accuſtomable to the leg.

Sect. 2. lib. de fract.

CHAP. XLV.

Of reſtoring the Thigh diſlocated outwardly.

THe Patient muſt be placed groveling upon a table in this kind of diſlocation alſo, and ligatures as before, caſt upon the hip and lower part of the thigh, then extenſion muſt be made downwards, and counter-extenſion upwards; then preſently the head of the bone muſt be forced by the hand of the Surgeon into its place. If the hand be not ſufficient for this purpoſe, our Pulley muſt be uſed, as the following figure ſheweth.

A Figure which expreſſeth the manner of reſtoring the Thigh luxated outwards.

When it is that only extenſion ſerves for the reſtoring the diſlocated thigh.

This kind of diſlocation is the eaſilieſt reſtored of all thoſe which happen in the thigh or hip, ſo that I have divers times obſerved the head of the thigh to have been drawn back into its cavity, by the only regreſs of the extended muſcles into themſelves towards their originals, ſomewhiles with a noiſe or pop, otherwhiles without; which being done, laying a compreſs upon the joynt, you ſhall perform all other circumſtances as before, in an internal diſlocation.

CHAP. XLVI.

Of reſtoring the Thigh diſlocated forwards.

WHen the thigh is luxated forwards, the Patient muſt be laid upon his ſound ſide, and tied as we have formerly delivered. Then the Surgeon ſhall lay a boulſter upon the prominent head of the bone, and have a care that his ſervant firmly hold it: Then immediately juſt extenſion being made, he ſhall with his hand force the bone into the cavity; but if his hand will not ſerve, he ſhall attempt it with his knee. Then to conclude, he ſhall uſe the reſt of the things formerly mentioned to contain the reſtored bone.

CHAP. XLVII.

Of reſtoring the Thigh diſlocated backwards.

THe Patient ſhall be placed groveling upon a table or bench, and the member extended, as in the reſt, one ligature ſtretched from the groin, another from the knee; then the Surgeon ſhall endeavour to force back with his hand that which ſtands up, and alſo to draw away the knee from the ſound leg. The bone thus placed and reſtored, the cure requires nothing elſe than to be bound up and kept long in bed, leſt that the thigh, if it ſhould be moved, the nerves being yet more looſe, might again fall out: For the thigh is in great danger of relapſe, for that the cavity of the huckle-bone is only depreſt, as far as it goes in, and the burthen of the hanging or adjoyning thigh is heavy.

CHAP.

CHAP. XLVIII.

Of the diſlocation of the Whirl-bone of the Knee.

THe Whirl-bone of the knee may fall forth into the inner, outer, upper and lower part; but never to the hind-part, becauſe the bones which it covers do not ſuffer it. To reſtore it, the Patient muſt ſtand with his foot firmly upon ſome even place, and then the Surgeon muſt force and reduce it with his hands from the part into which it is preternaturally ſlidden. When it ſhall be reſtored, the cavity of the ham ſhall be filled up with boulſters ſo that he may not bend his leg, for if it be bended, there is no ſmall danger of the falling back of the whirl-bone. Then a caſe or box ſhall be put about it, on the ſide eſpecially whereto it fell, being made ſomewhat flat and round, reſembling the whirl-bone it ſelf, and it ſhall be bound on with ligatures and medicines ſo faſt, that it may not ſtir a jot. After the part ſhall ſeem to have had ſufficient reſt, it is fit that the Patient try and accuſtom by little and little to bend his knee, until at length he ſhall find that he may eaſily and ſafely move that joynt.

CHAP. XLIX.

Of the diſlocated Knee.

THe knee alſo may be diſlocated three manner of ways, that is, into the inner, outer and hind-part, but very ſeldom towards the fore-ſide, and that not without ſome grievous and forcible violence; for the whirl-bone lying upon it, hinders it from ſlipping out, and holds it in. The other ways are eaſie, becauſe the cavity of the leg-bone is ſuperficiary and very ſmooth, but the cavity of the lower end of the thigh-bone is made in the manner of a ſpout or gutter, and beſides, the head thereof is very ſmooth and ſlippery; but the whole joynt is much more lax than the joynt of the elbow: So that as it may be the more eaſily diſlocated, ſo may it the better be reſtored; and as it may be the more eaſily, ſo may it be the more ſafely diſlocated, for that inflammation is leſs to be feared here, as it is obſerved by *Hippocrates*. Falls from high, leaping, and too violent running are the cauſes of this diſlocation. The ſign thereof is the diſability of bending or liſting up the leg to the thigh, ſo that the Patient cannot touch his buttock with his heel. The diſlocation of the knee which is inwardly and outwardly, is reſtored with indifferent extenſion and forcing of the bones into their ſeats from thoſe parts whereunto they have fallen. But to reſtore a diſlocation made backwards, the Patient ſhall be placed upon a bench of an indifferent height, ſo that the Surgeon may be behind him, who may bend with both his hands and bring to his buttocks the Patients leg put between his legs. But if the reſtitution do not thus ſucceed, you muſt make a clew of yarn, and faſten it upon the midſt of a ſtaff, let one put this into the cavity of the ham, upon the place whereas the bone ſtands out, and ſo force it forwards; then let another caſt a ligature of ſome three fingers breadth upon his knee, and draw it upward with his hands, then preſently and at once they ſhall ſo bend and crook the lame leg, that the heel thereof may touch his buttocks.

The differences.

Ad finem ſect. 3. de fract.

How to reſtore a knee diſlocated backwards.

CHAP. L.

Of a Knee diſlocated forwards.

BUt if the knee be diſlocated forwards (which ſeldom happens) the Patient ſhall be placed upon a table, and a convenient ligation made above, and another cloſe beneath the knee. Then the Surgeon ſhall ſo long preſs down with both his hands the bone which is out of joynt, until it ſhall return to its place gain. To which purpoſe if the ſtrength of the hand will not ſerve to make juſt extenſion each way, you may make uſe of our engine, as you may perceive by this following figure.

The cure.

A Figure ſhewing the manner of reſtoring a Knee diſlocated forwards.

You

You ſhall know that the bone is reſtored by the free and painleſs extenſion of the leg; then will there be place for medicines, boulſters and ſtrengthening ligatures. In the mean ſpace the Patient ſhall forbear going ſo long as the part ſhall ſeem to require.

CHAP. LI.

Of the ſeparation of the greater and leſſer Focile.

The joyning of the leg and ſhin-bones.

THe *Fibula* or leſſer Focile is faſtned and adheres to the *Tibia*, leg-bone, or greater Focile without any cavity, above at the knee, and below at the ankle. But it may be pluck'd or drawn aſide three manner of ways, that is, forwards, and to each ſide: This chance happens when in going we take no ſure footing, ſo that we ſlip with our feet this and that way as in a ſlippery place, and ſo wreſt it inwards or outwards; for then the weight of our body lying open upon it, draws the leg, as it were, in ſunder, ſo that the one Focile is diſlocated or ſeparated from the other. The ſame may happen by a fall from an high place, or ſome grievous and bruiſing blow: Beſides alſo, their appendices are ſometimes ſeparated from them. For the reſtoring of all theſe into their proper places, it is fit they be drawn and forced by the hand of the Surgeon into their ſeats: Then ſhall they be ſtraitly bound up, putting compreſſes to that part unto which the *Fibula* flew; beginning alſo your ligation at the very luxation, for the fore-mentioned reaſons. The Patient ſhall reſt forty days, to wit, as long as ſhall be ſufficient for the ſtrengthening of the ligaments.

The cure.

CHAP. LII.

Of the Leg-bone or greater Focile diſlocated and divided from the Paſtern-bone.

Differences and ſigns.

ALſo the Leg-bone is ſometimes diſlocated and divided from the Paſtern-bone, as well inwardly, as outwardly; which may be known by the ſwelling out of the bone to this or that part; if it be only a ſubluxation or ſtrain, it may be eaſily reſtored by gently forcing it into the place again. After the bone ſhall be reſtored, it ſhall be kept ſo by compreſſes and fit deligation, by croſs and contrary binding to the ſide oppoſite to that towards which the bone fell, that ſo alſo in ſome meaſure it may be more and more forced into its place. In the mean time you muſt have a care that you do not too ſtraitly preſs the great and large tendon which is at the heel. This kind of diſlocation is reſtored in forty days, unleſs ſome accident happen which may hinder it.

CHAP. LIII.

Of the diſlocation of the Heel.

Cauſes and differences.

WHoſoever leaping from an high place have fallen very heavy upon their heel, have their heel diſlocated and divided from the Paſtern-bone. This diſlocation happens more frequently inwardly than outwardly, becauſe the prominency of the leſſer Focile embraces the Paſtern-bone; whence it is that there it is more ſtraitly and firmly knit. It is reſtored by extenſion and forcing it in, which will be no very difficult matter, unleſs ſome great defluxion or inflammation hinder it. For the binding up it muſt be ſtraiteſt in the part affected, that ſo the blood may be preſſed from thence into the neighbouring parts; yet uſing ſuch a moderation, that it may not be painful, nor preſs more ſtraitly than is fit, the nerves and groſs tendons which runs to the heel. This diſlocation is not confirmed before the fortieth day, though nothing happen which may hinder it. Yet uſually it happeneth that many ſymptoms enſue by the vehemency of the contuſion. Wherefore it will not be amiſs to handle them in a particular Chapter.

The cure.

CHAP. LIV.

Of the Symptoms which follow upon the contuſion of the Heel.

Why bloodletting neceſſary in the fracture of a heel. *Hip. ſect. 3. de fracturis.*

IT happenth by the vehemency of this contuſion, that the veins and arteries do, as it were, vomit up the blood both through the ſecret paſſages of their coats, as alſo by their ends or orifices, whence an *Ecchymoſis* or blackneſs over all the heel, pain, ſwelling, and other the like enſue, which implore remedies and the Surgeons help, to wit, convenient diet, and drawing of blood by opening a vein, (of which though *Hippocrates* makes no mention, yet it is here requiſite by reaſon of the feaver and inflammation) and if need require, purgation; principally ſuch as may divert the matter by cauſing vomit; and laſtly, the application of local medicines, chiefly ſuch as may ſoften and rarifie the skin under the heel, otherwiſe uſually hard and thick (ſuch as are fomentations of warm water and oyl) ſo that divers times we are forced to ſcarifie it with a lancet, ſhunning the quick fleſh. For ſo at length the blood poured forth into the part, and there heaped up, is more eaſily attenuated, and at length reſolved. But theſe things muſt all be performed before the inflammation ſeize upon the part, otherwiſe there will be danger of a convulſion. For the blood, when it falls out of the veſſels, readily putrifies, by reaſon the denſity of this part hinders it from ventilation and diſperſing to the adjacent parts. Hereto may be added, that the large and great tendon which covers the heel, is endued with exquiſite ſenſe, and alſo the part it ſelf is on every ſide ſpread over with

Why the heel is ſubject to inflammation.

with many nerves. Beſides alſo there is further danger of inflammation by lying upon the back and heel, as we before admoniſhed you in the fracture of a leg. Therefore I would have the Surgeon to be here moſt attentive and diligent to perform theſe things which we have mentioned, leſt by inflammation a Gangrene and Mortification (for here the ſanious fleſh preſently falls upon the bone) happen together with a continued and ſharp Feaver, with trembling, hicketting and raving. For the corruption of this part firſt by contagion aſſails the next, and thence a Feaver aſſails the heart by the arteries preſſed and growing hot by the putrid heat, and by the nerves and that great and notable tendon made by the concourſe of the three muſcles of the calf of the leg, the muſcles, brain and ſtomach are evilly affected and drawn into conſent; and ſo cauſe convulſions, raving and a deadly hicketting. *Gal. ad ſent. 23. ſect. 2. lib. de fract.*

CHAP. LV.

Of the diſlocated Paſtern, or Ancle-bone.

THe *Aſtragalus* or paſtern bone may be diſlocated and fall out of its place to every ſide. Wherefore when it falls out towards the inner part, the ſoal of the foot is turned outwards, when it flies out to the contrary, the ſign is alſo contrary; if it be diſlocated to to the foreſide, on the hind ſide the broad tendon coming under the heel is hardned and diſtended; but if it be luxated backwards, the whole heel is, as it were, hid in the foot: neither doth this kind of diſlocation happen without much violence. It is reſtored by extending it with the hands, and forcing it into the contrary part to that from whence it fell. Being reſtored, it is kept ſo by application of medicines and fit ligation. The Patient muſt keep his bed long in this caſe, leſt that bone which ſuſtains and bears up the whole body, may again ſink under the burthen, and break out, the ſinews being not well knit and ſtrengthned. **Sign.** **Cure.**

CHAP. LVI.

Of the diſlocation of the In-ſtep and back of the Foot.

THe bones alſo of the In-ſtep and back of the foot may be luxated, and that either upwards or downwards, or to one ſide, though ſeldom ſide-wiſe, for the reaſon formerly rendred, ſpeaking of the diſlocation of the like bones of the hand. If that they ſtand upwards, then muſt the Patient tread hard upon ſome plain or even place, and then the Surgeon by preſſing them with his hand ſhall force them into their places; on the contrary, if they ſtand out of the ſoal of the foot, then muſt you preſs them thence upwards, and reſtore each bone to its place. They may be reſtored after the ſame manner if they be flown out to either ſide. But you muſt note, that although the ligatures conſiſt but of one head in other diſlocations, yet here *Hippocrates* would have ſuch uſed as have two heads, for that the diſlocation happens more from below upwards, or frome above downwards than ſide-wiſe. **Cure.** *Sent. 14. ſect. 2. lib. de fract.*

CHAP. LVII.

Of the diſlocation of the Toes.

NOw the toes may be four ways diſlocated, even as the fingers of the hand; and they may be reſtored juſt after the ſame manner, that is, extend them directly forth, and then force each joynt into its place, and laſtly, bind them up as is fitting. The reſtitution of all them is eaſie, for that they cannot far tranſgreſs their bounds. To conclude, the bones of the feet are diſlocated and reſtored by the ſame means as thoſe of the hands, but that when as any thing is diſlocated in the foot, the Patient muſt keep his bed; but when any thing is amiſs in the hand, he muſt carry it in a ſcarf. The Patient muſt reſt twenty days, that is, until he can firmly ſtand upon his feet. **The differences.** **Cure.**

CHAP. LVIII.

Of the ſymptoms and other accidents which may befal a broken or diſlocated member.

MAny things may befal broken or diſlocated members by the means of the fracture or diſlocation; ſuch as are bruiſes, great pain, inflammation, a Feaver, Impoſtume, Gangrene, Mortification, Ulcer, *Fiſtula* and *Atrophia*, all which require a skilful and diligent Surgeon for their cure. A contuſion happens by the fall of ſome heavy thing upon the part, or by a fall from high, whence follows the effuſion of blood poured out under the skin: Which if it be poured forth in great plenty, muſt be ſpeedily evacuated by ſcarification, and the part eaſed of that burthen, leſt it ſhould thence gangrenate. And by how much the blood ſhall appear more thick, and the skin more denſe, by ſo much the ſcarification ſhall be made more deep. You may alſo for the ſame purpoſe apply Leeches. **Remedies for a contuſion.**

Concerning pain we formerly ſaid, that it uſually happens by reaſon that the bones are moved out of their places, whence it hapneth that they become troubleſom to the muſcles and nerves, by pricking and preſſing them. Hence enſue inflammations, as alſo impoſtumation and a feaver, oft-times a gangrene, and in concluſion a mortification, corrupting and rotting the bones; otherwhiles a ſinuous ulcer or *fiſtula*. But an *Atrophia* and leanneſs ariſeth by the ſloth and idleneſs of the member decaying all the ſtrength thereof, and by too ſtrait ligation intercepting the paſſages of the blood, otherwiſe ready to fall and flow thither. **What may happen by pain.**

Remedies for the leanneſs or *Atrophia* of any member.

Now the leanneſs which is occaſioned by too ſtrait ligation receives cure by the ſlackning of the ligatures wherewith the member was bound. That which proceeds from idleneſs, is helped by moderate exerciſe, by extending, bending, lifting up, and depreſſing the member, if ſo be that he can away with exerciſe. Otherwiſe he ſhall uſe frictions and fomentations with warm water. The frictions muſt be moderate in hardneſs and gentleneſs, in length and ſhortneſs. The ſame moderation ſhall be obſerved in the warmneſs of the water, and in the time of fomenting. For too long fomenting reſolves the blood that is drawn. But that which is too little or ſhort a ſpace draws little or nothing at all: After the fomentation, hot and emplaſtick medicines made of Pitch, Turpentine, *Euphorbium*, Pellitory of Spain, Sulphur, and the like, ſhall be applied. They ſhall be renewed every day more often or ſeldom, as the thing it ſelf ſhall ſeem to require.

What meaſure to be uſed in fomenting.

A *dropax.*

Theſe medicines are termed *Dropaces*, whoſe form is thus: ℞ *Picis nigræ, ammoniaci, bdelii gummi elemi in aqua vitæ diſſolutorum an.* ℥ ii. *Olei laurini* ʒ i *pulveris piperis, zinziberis, granorum paradiſi, bacacrum lauri & juniperi, an.* ʒ ii. *Fiat emplaſtrum ſecundum artem, extendatur ſuper alutam.* It is alſo good to bind about the oppoſite ſound part with a ligature, yet without pain: As if the right arm ſhall decay for want of nouriſhment, the left ſhall be bound, beginning your ligation at the hand, and continuing it up to the arm-pit. If this miſchance ſhall ſeize upon the right leg, then the left ſhall be ſwathed up from the ſole of the foot to the groin. For thus a great portion of the blood is forced back into the *vena cava*, or hollow vein, and from this being diſtended and over full, into the part affected and gaping with the veſſels almoſt empty; beſide alſo it is convenient to keep the ſound part in reſt, that ſo it may draw the leſs nouriſhment, and by that means there will be more ſtore to refreſh the weak part.

Binding of the ſound part oppoſite to the emaciated.

How to bind up the emaciated part.

Some wiſh alſo to bind up the decaying member with moderate ligation; for thus, ſay they, the blood is drawn thither: for when as we intend to let blood by opening a vein with a lancet, we bind the arm. Alſo it is good to dip it into water ſomewhat more than warm, and hold it there until it grow red, and ſwell; for thus blood is drawn into the veins, as they find, which uſe to draw blood of the *Saphena* and *Salvatella*. Now, if when as theſe things and the like be done, the lame part grows hot, red and ſwoln, then know that health is to be hoped for; but if the contrary happen, the caſe is deſperate: Wherefore you need attempt nothing further.

Signs that an *Atrophia* is curable.

Furthermore, there is ſometimes hardneſs left in the joynts, after fractures and diſlocations are reſtored. It is fit to ſoften this, by reſolving the contained humor, by Fomentations, Liniments, Cataplaſms, emplaſters made of the roots of Marſh-mallows, Briony, Lilies, Line-ſeed, Fenugreek-ſeed, and the like, and alſo of Gums diſſolved in ſtrong Vinegar; as, *Ammoniacum, bdelium, opopanax, labdanum, ſagapenum, ſtyrax liquida*, and *adeps anſerinus, gallinaceus, humanus, oleum liliorum*, and the like. Alſo you muſt wiſh the Patient to move the part ever now and then, every day; yet ſo, that it be not painful to him, that ſo the pent up humor may grow hot, be attenuated, and at length diſcuſſed, and laſtly the part it ſelf reſtored as far as Art can perform it; for oft-times it cannot be helped any thing at all. For if the member be weak and lame, by reaſon that the fracture hapned near the joynt, for the reſidue of his life the motion thereof uſeth to be painful and difficult, and oft-times none at all, eſpecially if the *callus*, which grows there, be ſomewhat thick and great; and laſtly, if the joynt it ſelf ſhall be contuſed and broken by the ſtroke, as it oft-times happens in wounds made by Gunſhot.

BOOK XVII.

Of divers other Preternatural Affects, whoſe cure is commonly performed by Surgery.

CHAP. I.

Of an Alopecia, *or the falling away of the hairs of the head.*

Gal. c.2. l.1. de comp. med. ſecun. locos.

The cauſe.

AN *Alopecia* is the falling away of the hair of the head, and ſometimes alſo of the eye-brows, chin and other parts; the French commonly call it the *Pelade*: Phyſicians term it the *Alopecia*, for old Foxes (ſubject, by reaſon of their age to have the ſcab) are troubled oft-times with this diſeaſe. This affect is cauſed either through defect of nouriſhment fit to nouriſh the hairs, as in old age through want of the radical humidity, or by the corruption of the alimentary matter of the ſame, as after long Feavers, in the *Lues venerea*, Leproſie, the corruption of the whole body and all the humors, whence follows a corruption of the vapors and fuliginous excrements; or elſe by the vicious conſtitution of pores in the skin in rarity, and conſtriction or denſity, as by too much uſe of hot ointments made for colouring the hair, or ſuch as are uſed to take off hair, therefore called *Depilatoria*, or by the burning of the skin, or loſs thereof, having a ſcar inſtead thereof, by reaſon of whoſe denſity the hair cannot ſpring out; as by too much laxity the fuliginous matter of the hair ſtays not, but preſently vaniſheth away. The *Alopecia* which comes by old Age, a Conſumption, Burn-baldneſs, Leproſie, a Scald head, is incurable: That which admits of cure, the cauſe being taken away, is helped. Wherefore if it proceed from the corruption of humors, let a Phyſician be called, who, as he ſhall think fit, ſhall appoint diet, purging and phlebotomy. Then the Surgeon ſhall ſhave off the hair which is remaining, and ſhall firſt uſe reſolving Fomentations, apply Leeches and Horns to digeſt the vicious humour which is under the skin,

What *Alopecia* uncurable.

What curable, and how.

skin, then shall he wash the head to take way the filth with a Lee wherein the roots of Orris and Aloes have been boiled. Lastly, he shall use both attractive fomentations and medicines for to draw forth the humor which is become laudable in the whole body by the benefit of diet fitly appointed. But if the *Alopecia* shall happen through defect of nourishment, the part shall be rubbed so long with a coarse linnen cloth, or fig-leaf, or onions until it wax red; besides also the skin shall be pricked in many places with a needle, and then ointments applied made of *Labdanum*, Pigeons dung, Staves-acre, Oyl of Bays, Turpentine and Wax, to draw the blood and matter of the hairs. If the hair be lost by the *Lues venerea*, the Patient shall be anointed with Quick-silver to sufficient salivation. To conclude, as the causes of this disease shall be, so must the remedies be fitted which are used. Σταφὶς ἀγρία.

CHAP. II.

Of the Tinea, *or Scald-head.*

THe *Tinea* (let me so term it in Latine, whil'st a fitter word may be found) or a Scald-head, is a disease possessing the musculous skin of the head or the hairy scalp, and eating thereinto like a Moth. There are three differences thereof; the first is called by *Galen*, *Scaly or bran-like*, for that whilst it is scratched it casts many bran-like scales: Some Practicioners term it, *A dry scall*, because of the great adustion of the humor causing it. Another is called, *Ficosa*, *a fig-like scall*, because when it is despoiled of the crust or scab which is yellow, there appear grains of quick and red flesh, like to the inner seeds or grains of figs, and casting out a bloody matter. *Galen* names the third *Achor*, and it is also vulgarly termed, the *Corrosive*, or *Ulcerous scall*, for that the many ulcers wherewith it abounds are open with many small holes flowing with liquid *sanies* like the washing of flesh, stinking, corrupt and Carrion-like, somewhiles livid, somewhiles yellowish. These holes, if they be somewhat larger, make another difference, which is called *Cerion* or *Favosa*, (that is, like a honey-comb) because as *Galen* thinks, the matter which floweth from these, resembleth honey in colour and consistence. They all proceed of an humor which is more or less vicious, for a less corrupt humor causeth a scaly, a more corrupt the fig-like, but the most corrupt produceth the ulcerous. If it shall happen to an Infant by reason of the fault and contagion of the Nurse, or else presently after it is born, it scarce admits of cure; neither must we attempt that, before the child come that to age that he may be able to endure the cure and medicines. But you may in the mean while apply the leaves of Colworts or Beets besmeared with fresh butter, or other gentle medicine having a faculty to mollifie and open the passage for the shut-up matter. Those who are of sufficient age to away with medicine, may bleed, purge, bathe, according to art by the advice of a Physician. For local medicines in a scaly scall, softning and discussing fomentations shall be appointed, made of the roots of Marsh-mallows, Lilies, Docks, Sorrel boiled in Lee with a little Vineger added thereto. The head shall be twice in a day fomented with such a decoction, and on the sixth day, the hair being shaven off, it shall be scarified, and then Leeches and Horns put to it so scarified. Then it shall be forthwith anointed with Oyl of Staves-acre mixed with black-sope, both to draw and repress the malignity of the humor impact in the part. You may also use the following medicine even to the perfect cure of the disease, as that which is much commended in this kind of disease by *Vigo*, *Gordonius* and *Guido*; it is thus made. ℞ *Elleb. albi & nigri, atrament. auripigmenti, litharg yri auri, calcis vivæ, vitriol. alum. galla. fulg. ciner. fæcis vini usti, an,* ʒ ß. *Argenti vivi extincti,* ʒ iij. *æruginis æris* ʒ ii. *Fiat pulvis qui incorporetur cum succo boraginis, scabiosæ, fumariæ, oxylapathi, aceti, an. quart.* i. *Olei antiqui lib.* i. *bulliant usque ad consumpt. succorum in fine decoctionis cineres ponantur, addendo picis liquidæ* ʒ ß. *Ceræ quantum sufficit, fiat unguentum*: These Authors testifie that this will heal any kind of scall. Certainly none can disallow of it, who well considereth the ingredients and composure thereof. *Lib.* 1. *de comp. med. sect. locos.* *Cap.* 8. *lib. citat.* The cure. For a scaly scall. An ointment for a scalled head.

A crusty also or fig-like scall may be so long fomented with the prescribed fomentation, until the crusts or scabs fall off, yet there is nothing so good and effectual as Cresses beaten or fried with Hogs suet. For it will make it fall off in the space of four and twenty hours, besides if it be continued, it will heal them throughly, as I have known by experience, and reason also stands therewith; for according to *Galen*, Cresses are hot and dry. When the crusts shall be fallen away, the parts affected shall be anointed with the formerly prescribed ointment. I have cured many with a little Oyl of Vitriol, and sometimes also with *Ægyptiacum* made somewhat more strong than ordinary. But if the root of the hairs appear rotten, they shall be plucked out one by one; yet if such putrefaction shall possess the whole hairy scalp, and trouble all the roots of the hair, that you may pluck them out the more readily, and with less pain, you may besmear a cotten-cloth on the rougher side with this following medicine. ℞ *Picis nigræ* ʒ vi. *Picis res.* ʒ ii. *Pul. viridis æris, & vitriol. Rom. an.* ʒ i. *vel* ʒ ß. *Sulphuris viv.* ʒ ß *coquantur omnia simul in aceti acerrimi quantitate sufficiente, fiat medicamentum ad usum*: Let it be applied to the head and remain on for two days, then let it be quickly and forcibly plucked away against the hair, that so the hairs sticking to the plaster may by that means be plucked away therewith: You shall use this medicine so long as need shall seem to require. The cure for a crusty scall. A poultis of Cresses. *Lib.* 7. *simp.* A plaster to pluck away the hair at once.

For the third kind of scall which is termed a Corrosive or Ulcerous, the first indication is to cleanse the ulcers with this following ointment. ℞ *Unguenti enulati cum mercurio duplicato, ægyptiaci, an.* ʒ iij. *vitriol. albi in pulverem redacti* ʒ i. *incorporentur simul, fiat unguentum ad usum*; also you may use the formerly described oyntment. But if any other pain or accident fall out, you must withstand it by the assistance and direction of some good Physician; verily these following medicines against all kinds of scalls have been found out by reason, and approved by use. ℞ *Camphur.* ʒ ß. *Alum. roch. vitriol vir. æris, sulp. vivi, fulig. forn. an.* ʒ vi. *Olei amygd. dulcium & axungiæ porci, an.* ʒ ij. *Incorporentur simul in mortario, fiat unguentum.* Some take the dung which lieth rotting in a sheep-fold; they use that which is liquid, and rub it upon the ulcerated places, and lay a double cloth dipped in that liquor upon it. But if the Patient cannot be cured with all these medicines, and that you find his body in some parts thereof The cure of an ulcerous scall.

troubled in like ſort with cruſty ulcers, I would wiſh that his head might be anointed with an ointment made of *Axungia*, *argentum vivum*, and a little *Sulphur*, and then fit ſome *emplaſtrum Vigonis cum mercurio* into the faſhion of a cap; alſo ſome plaiſters of the ſame may be applied to the ſhoulders, thighs and legs, and ſo let him be kept in a very warm chamber, and all things done as if he had the *Lues venerea*. This kind of cure was firſt (that I know of) attempted by *Simon Blanch* the King's Surgeon, upon a certain young man, when as he in vain had diligently tried all other uſual medicines. A ſcalled head oft-times appeareth very loathſom to the eye, caſting forth virulent and ſtinking *ſanies*; at the firſt it is hardly cured, but being old, far more difficultly. For divers times it breaketh out afreſh, when you think it kill'd, by reaſon of the impreſſion of the malign putrefaction remaining in the part, which wholly corrupts the temper thereof. Moreover, oft-times being healed, it hath left an *Alopecia* behind it, a great ſhame to the Surgeons. Which is the reaſon that moſt of them judg it beſt to leave the cure thereof to Empericks and Women.

A contumacious ſcall muſt be cured as we cure the *Lues venera.*

CHAP. III.

Of the Vertigo, *or Giddineſs.*

THe *Vertigo* is a ſudden darkning of the eyes and ſight by a vaporous and hot ſpirit, which aſcendeth to the head by the ſleepy arteries, and fills the brain, diſturbing the humors and ſpirits which are contained there, and toſſing them unequally, as if one run round, or had drunk too much Wine. This hot ſpirit oft-times riſeth from the heart upwards by the internal ſleepy arteries to the *Rete mirabile*, or wonderful net; otherwhiles it is generated in the brain it ſelf, being more hot than is fitting; alſo it oft-times ariſeth from the ſtomach, ſpleen, liver, and other entrails being too hot. The ſign of this diſeaſe is the ſudden darkning of the ſight, and the cloſing up, as it were, of the eyes, the body being lightly turned about, or by looking upon wheels running round, or whirl-pits in waters, or by looking down any deep or ſteep places. If the original of the diſeaſe proceed from the brain, the Patients are troubled with the head-ach, heavineſs of the head, and noiſe in the ears, and oft-times they loſe their ſmell. *Paulus Ægineta* for the cure bids us to open the arteries of the temples. But if the matter of the diſeaſe ariſe from ſome other place, as from ſome of the lower entrails, ſuch opening of an artery little availeth. Wherefore then ſome skilful Phyſician muſt be conſulted with, who may give directions for Phlebotomy, if the original of the diſeaſe proceed from the heat of the entrails; by purging, if occaſioned by the foulneſs of the ſtomach, But if ſuch a *Vertigo* be a critical ſymptom of ſome acute diſeaſe affecting the *Criſis* by vomit or bleeding, then the whole buſineſs of freeing the Patient thereof muſt be committed to nature.

What the *Vertigo* is, and the cauſes thereof

The ſigns.

Lib. 6.

A critical *Vertigo.*

CHAP. IV.

Of the Hemicrania, *or Megrim.*

THe *Megrim* is properly a diſeaſe affecting the one ſide of the head, right or left. It ſometimes paſſeth no higher than the temporal muſcles, otherwhiles it reacheth to the top of the crown. The cauſe of ſuch pain proceedeth either from the veins and external arteries, or from the *Meninges*, or from the very ſubſtance of the brain, or from the *Pericranium*, or the hairy ſcalp covering the *Pericranium*, or laſtly, from putrid vapours ariſing to the head from the ventricle, womb, or other inferior member. Yet an external cauſe may bring this affect, to wit, the too hot or cold conſtitution of the encompaſſing air, drunkenneſs, gluttony, the uſe of hot and vaporous meats, ſome noiſom vapour or ſmoak, as of Antimony, Quick-ſilver, or the like, drawn up by the noſe, which is the reaſon that Gold-ſmiths, and ſuch as gild Metals are commonly troubled with this diſeaſe. But whenceſoever the cauſe of the evil proceedeth, it is either a ſimple diſtemper, or with matter: With matter, I ſay, which again is either ſimple or compound. Now, this affect is either alone or accompanied with other affects, as inflammation and tenſion. The heavineſs of head argues plenty of humor; pricking, beating, and tenſion ſhews that there is a plenty of vapours mixed with the humors, and ſhut up in the nervous, arterious, or membranous body of the head. If the pain proceed from the inflamed *Meninges*, a Feaver followeth thereon, eſpecially, if the humor cauſing pain do putrefie. If the pain be ſuperficiary, it is ſeated in the *Pericranium*. If profound, deep and piercing to the bottom of the eyes, it is an argument that the *Meninges* are affected, and a Feaver enſues, if there be inflammation, and the matter putrefie; and then oft-times the tormenting pain is ſo great and grievous, that the Patient is afraid to have his head touched, if it be but with your finger, neither can he away with any noiſe, or ſmall murmuring, nor light, nor ſmells however ſweet, no nor the fume of Wine. The pain is ſometimes continual, otherwhiles by fits. If the cauſe of the pain proceed from hot, thin and vaporous blood, which will yield to no medicines, a very neceſſary, profitable and ſpeedy remedy may be had by opening an artery in the temples, whether the diſeaſe proceed from the internal or external veſſels. For, hence always enſueth an evacution of the conjunct matter, blood and ſpirits. I have experimented this in many, but eſpecially in the Prince de la *Roche-ſur-yon*. His Phyſicians when he was troubled with this grievous *Megrim*, were *Chaplain*, the Kings, and *Caſtellane* the Queens chief Phyſicians, and *Lewes Duret*, who notwithſtanding could help him nothing by blood-letting, cupping, bathes, frictions, diet or any other kind of remedy either taken inwardly or applied outwardly. I being called, ſaid, that there was only hope one way to recover his health, which was to open the artery of the temple in the ſame ſide that the pain was; for I thought it probable, that the cauſe of his pain was not contained in the veins, but in the arteries, in which caſe by the teſtimony of the Ancients, there was nothing better than the opening or bleeding of an artery,

The differences.

In what kind of *Megrim* the opening of an Artery is good.

A Hiſtory.

artery, whereof I have made trial upon my self to my great good. When as the Physicians had approved of this my advice, I presently betake my self to the work, and chose out the artery in the pained temple, which was both the more swoln and beat more vehemently than the rest. I open this, as we use to do in the bleeding of a vein, with one incision, and take more than two sawcers of blood flying out with great violence and leaping; the pain presently ceased, neither did it ever molest him again. Yet this opening of an artery is suspected by many, for that it is troublesome to stay the gushing forth blood, and cicatrize the place, by reason of the density, hardness, and continual pulsation of the artery; and lastly, for that when it is cicatrized, there may be danger of an *Aneurisma*. Wherefore they think it better first to divide the skin, then to separate the artery from all the adjacent particles, and then to bind it in two places; and lastly, divide it, as we have formerly told you must be done in *Varices*. But this is the opinion of men who fear all things where there is no cause; for I have learn'd by frequent experience, that the apertion of an artery, which is performed with a Lancet, as we do in opening a vein, is not at all dangerous; and the consolidation or healing is somewhat slower than in a vein, but yet will be done at length, but that no flux of blood will happen, if so be that the ligation be fitly performed, and remain so for four days with fitting pledgets.

No danger in opening an artery.

CHAP. V.

Of certain affects of the Eyes, and first of staying up the upper Eye-lid when it is too Lax.

OF the diseases which befal the eyes, some possess the whole substance thereof, as the *Ophthalmia*, a *Phlegmon* thereof: Others are proper and peculiar to some parts thereof, as that which is termed *Gutta serena* to the optick nerve. Whence *Galen* made a threefold difference of the diseases of the eyes, as that some happened to the eye by hurting or offending the chief organ thereof; that is, the crystalline humor; others by hindring the animal faculty, the chief causer of sight, from entring into them; and lastly, other some by offending the parts subservient to the prime organ or instrument. Now of all these diseases, the eye hath some of them common with the other parts of the body, such as are an ulcer, wound, *Phlegmon*, contusion, and the like: Other some are peculiar and proper to the eye, such as are the *Egilops*, *Cataracta*, *Glaucoma*, and divers others of this kind. Some have their upper eye-lid fall down, by reason that the upper skin thereof is relaxed more than is sufficient to cover the eye, the gristle in the mean while not relaxing it self together therewith. Hence proceeds a double trouble; the first, for that the eye cannot be easily opened; the other, because the hairs of the relaxed eye-lid run in towards the eye, and become troublesome thereto by pricking it. The cause of such relaxation is either a particular palsie of that part, which is frequent in old people, or the defluxion or falling down of a waterish humor, and not acrid or biting; which appears by this, that those who are thus affected have a rank of hairs growing under the natural rank, by reason of abundance of heaped-up humor, as it is most probable. For thus a wet and marish ground hath the greatest plenty of grass. Now if this same humor were acrid, it would cause an itching, and consequently become troublesome to the Patient, and it would also fret in sunder and destroy the roots of the other hairs, so far it is from yielding matter for the preternatural generation of new. It is fit before you do any thing for the cure, that you mark with ink the portion thereof which is superfluous, and therefore to be cut away, lest if you should cut off more than is requisite, the eye-lid should remain turned up, and so cause another kind of affect, which the Ancients have called *Ectropion*. Then the eye being covered, take and lift up with your fingers the middle part of the skin of the eye-lid, not taking hold of the gristle beneath it, and then cut it athwart, taking away just so much as shall be necessary to make it, as it were, natural; lastly, joyn the lips of the wound together with a simple suture of three or four stitches, that so it may be cicatrized; for the cicatrization restrains the eye-lid from falling down so loosly, at least some part thereof being taken away. There ought to be some measure and heed taken in the amputation, otherwise you must necessarily run into the one or other inconvenience, as if too much be cut away, then the eye will not be covered; if too little, then you have done nothing, and the Patient is troubled to no purpose. If there shall be many hairs grown preternaturally, you shall pluck them away with an Instrument made for same purpose; then their roots shall be burned with a gentle cautery, the eye being left untouch'd, for a scar presently arising will hinder them from growing again.

Differences.

Paul. Ægin. 8. cap. 6.

The cause.

The cure.

CHAP. VI.

Of Lagophthalmus, *or the Hare-eye.*

SUch as have their eye-lids too short, sleep with their eyes open, for that they cannot be covered by the too short skin of the eye-lids: The Greeks term this affect, Λαγόφθαλμος. The cause is either internal or external: Internal, as by a Carbuncle, Impostume or Ulcer; external, as by a wound made by a sword, burn, fall, and the like. If this mishap proceed by reason of a cicatrization, it is curable, if so that the short eye-lid be of an indifferent thickness. But if it have been from the first conformation, or by some other means, whereby much of the substance is lost, as that which happens by burning, and a carbuncle, then it is uncurable. For the cure, you shall use relaxing and emollient fomentations, then the skin shall be divided above the whole scar, in figure of an Half-moon, with the horns looking downwards. Then the edges of the incision shall be opened, and lint put into the middle thereof, that so it may hinder the lips from joyning together again. Then shall you apply a plaster upon the lint, and so bind up the part with a fitting ligature, that may somewhat press upon the whole eye, lest it should lift it self somewhat upwards again, and so return into its ancient, but not natural figure. But in cutting the skin, you

Paulus Ægin. l. 6. cap. 10.

The cure.

must take care that your inciſion harm not the griſtle; for if it be cut, the eye-lid falls down, neither can it be afterwards lifted up. But now for the lower eye-lid: it is ſubject to ſundry diſeaſes, amongſt which there is one which anſwereth in proportion to that, which we late mentioned, which is, when as it is lifted upwards little or nothing, but hangs and gapes, and cannot be joyned with the upper, and therefore it doth not cover the eye, which affect is familiar to old people; it is called *Ectropion*, and it may be helped by means formerly delivered.

Ectropion, or the turning up, or out of the eye-lid.

CHAP. VII.

Of the Chalazion, *or Hail-ſtone, and the* Hordeolum, *or Barly-corn of the Eye-lids.*

Paul. cap. 6. lib. 6.

THe *Chalazion* is a round and clear pimple, which grows upon the upper eye-lid; it is alſo moveable, and may be ſtirred this way and that way with your fingers. The Latins call it *Grando*, for that it reſembles a hail-ſtone. Another pimple not much like this grows ſometimes upon the verges of the eye-lids above the place of the hairs. It is termed *Hordeolum*, by reaſon of the ſimilitude it hath with a barly-corn. The matter of theſe is contained in its proper ciſt or skin, and therefore is hardly brought to ſuppuration. At the firſt beginning it may be reſolved and diſcuſſed: But when as it is once grown and concrete into a plaſter or ſtone-like hardneſs, it is ſcarce curable. Wherefore it is beſt to perform the cure by opening them, that ſo the contained matter may flow or be preſſed forth. If the pimple or ſwelling be ſmall, then thruſt it through with a needle and thread, and leave the thread therein of ſuch length, that you may faſten the ends thereof with a little of the emplaſter called *Gratia Dei*, like glue to the forehead, if it be on the upper eye-lid; or to the cheeks, if on the lower. You muſt draw through a freſh one every ſecond day, as is uſually done in chirurgical ſetons: For thus at length the ſwelling will be deſtroyed, and made plain.

The cure.

CHAP. VIII.

Of the Hydatis, *or fatneſs of the Eye-lids.*

What *Hydatis* is.

THe *Hydatis* is a certain fatty ſubſtance, like a piece of fat, ſeated and lying under the skin of the upper eye-lid. It is a diſeaſe incident to children, who are of a more humid nature: Wherefore it is a ſoft and looſe tumor, making the whole eye-lid, which it poſſeſſeth, œdematous; ſo that as if depreſſed with a weight, it cannot be lifted up. It hath its name, for that it hath, as it were, a bladder diſtended with a wheyiſh humor, which kind of fault is obſerved by *Galen* in the liver, Thoſe who are thus affected, have their eyes look red, and flow with tears, neither can they behold the Sun, or endure the light. The cure is performed by cutting off the ſuperfluous ſubſtance, not hurting the neighbouring parts; and then preſently put ſome ſalt into the place whence it was taken out (unleſs the vehemency of pain hinder) that ſo the place may be dried and ſtrengthned, and the reſt of the matter (if any ſuch be) may be conſumed, and hindred from growing again. Laſtly, you ſhall cover the whole eye with the white of an egg diſſolved in Roſe-water, or ſome other repercuſſive.

Com. ad aphor. 55. ſect. 7.

The cure.

CHAP. IX.

Of the Eye-lids faſtened or glued together.

Paulus cap. 15. lib. 6.

SOmetimes it cometh to paſs that the upper-eye-lid is glued or faſtened to the under, ſo that the eye cannot be opened, or ſo that the one of them may ſtick or be faſtned to the white coat of the eye, or to the horny. This fault is ſometimes drawn from the firſt original, that is, by the default of the forming faculty in the womb (for thus many Infants are born with their fingers faſtned together, with their fundaments, privities and ears unperforated) the eye in all other reſpects being well compoſed. The cauſe of this affect ſometimes proceeds from a wound, otherwhiles from a burn, ſcald, or impoſtumation, as the breaking of the Small-pox. It is cured by putting in a fit inſtrument, and ſo opening them; but with ſuch moderation, that you touch not the horny coat, for otherwiſe it would fall out. Therefore you muſt put the end or point of your probe under the eye-lids, and ſo lifting them up (that you hurt not the ſubſtance of the eye) divide them with a crooked Inciſion-knife.

The cauſe.

The cure.

The inciſion made, let the white of an egg beaten with ſome Roſe-water be put into the eye, let the eye-lids be kept open; yea, let the Patient himſelf be careful that he often turn it upwards, and lift it up with his fingers, not only that the medicine may be applied to the ulcer, but alſo that they may not grow together again. In the night time let a little pledget dipped in water, and that either ſimple, or wherein ſome vitriol hath been diſſolved, be laid thereon. For thus you ſhall hinder the eye-lids from joyning together again. Then on the third day the parts or edges of the eye-lids ſhall be touched with waters drying without biting or acrimony, that ſo they may be cicatrized. But if the eye-lid adhere to the horny-coat at the *pupilla* or apple of the eye, the Patient will either be quite blind, or very ill of ſight. For the ſcar which enſues will hinder the ſhapes of things from entring to the cryſtalline humor, and the viſive ſpirits from paſſing forth to the objects. For prognoſticks you may learn out of *Celſus*, that this cure is ſubject to a relapſe, ſo that it may be ſhunned neither by diligence nor induſtry, but that the eye-lid will always adhere and cleave to the eye.

A diſeaſe ſubject to relapſe.

CHAP.

CHAP. X.

Of the itching of the Eye-lids.

MAny have their eye-lids itch vehemently by reason of salt phlegm, which oftentime excoriating and ulcerating the parts themselves, yields a *sanies*, which joyns together the eye-lids in the night time, as if they were glued together, and makes them watry and bleared. This affect doth so torment the Patients, that it oft-times makes them require the Physicians help. Wherefore general medicines being premised, the ulcers shall be washed with the following *Collyrium:* ℞ *Aquæ mellis in balneo mariæ distillatæ* ʒ iij. *Sacchari candi* ʒ i. *Aloes lotæ & in pollinem redactæ* ʒ ß. *Fiat Collyrium.* Which if it do no good, you may use this which follows: ℞ *Ung. Ægyptiac.* ʒ i. *Dissolve in aquæ plantaginis quantitate sufficienti.* Let the ulcerated eye-lids be touched with a soft linnen rag dipped therein, but with care that none thereof fall upon the eye. But when the Patient goes to bed, let him cause them to be anointed with the following ointment, very effectual in this case: ℞ *Axungiæ porci & butyri recentis, an.* ʒ ß. *Tut. præpar.* ʒ ß. *Antimon. in aqua euphrasiæ præparati,* ℈ ij. *Camphoræ gra.* iv. *Misce, & in mortario plumbeo ducantur per tres horas, conflatum inde unguentum, servetur in pyxide plumbea.* Some commend and use certain waters fit to cleanse, dry, bind, strengthen, and absolutely free the eye-lids from itching and redness; of which this is one.

A detergent *Collyrium.*

℞ *Aquæ euphrag. fœniculi, chelidon. an.* ʒ ß. *Sarcocol. nutritæ* ℈ ij. *Vitriol. rom.* ʒ i. *Misceantur simul, & bulliant unica ebullitione; postea coletur liquor, & servetur ad usum dictum.* Or else, ℞ *Aquæ ros. & vini alb. boni an.* ʒ iv. *Tut. præpar. aloes an.* ʒ i. *Flor. æni* ℈ ii. *Camphor. gra.* ij. Let them be boiled according to art, and kept in a glass to wash the eye-lids. Or else, ℞ *vini albi* ℔ ß *salis com.* ʒ i. Let them be put into a clean Barbers bason and covered, and kept there five or six days, and be stirred once a day, and let the eye-lids be touched with this liquor. Some wish that the Patients urine be kept all night in a Barbers bason, and so the Patients eye-lids be washed therewith. Verily in this affect we must not fear the use of acrid medicines, for I once saw a woman of fifty years of age, who washed her eye-lids when they itched, with the sharpest vinegar she could get, and affirmed that she found better success of this than of any other medicine. *Vigo* prescribes a water, whose efficacy above other medicines in this affect, he saith, hath been proved; and that it is to be esteemed more worth than gold, the description thereof is thus: ℞ *Aq. ros. vini albi odoriferi mediocris vinositatis, an.* ʒ iv. *Myrobalan. citrini trit.* ʒ i ß. *Thuris* ʒ ij. *Bulliant omnia simul usque ad consumptionem tertiæ partis; deinde immediate addantur flores æris* ℈ ij. *Camph. gr.* ij. Let the liquor be kept in a glass well stopped for the foresaid use.

You need not fear to use acrid medicines in the itching of the eye-lids. *Lib. 2. cap. 9. tract. 3.*

CHAP. XI.

Of Lippitudo, *or Blear-eyes.*

THere are many whose eyes are never dry, but always flow with a thin, acrid, and hot humor which causeth roughness, and upon small occasions, inflammations, blear or blood-shot eyes, and at length also *Strabismus* or squinting. *Lippitudo* is nothing else but a certain white filth flowing from the eyes, which oft-times agglutinates or joyns together the eye-lids. This disease often troubles all the life time, and is to be cured by no remedy; in some it is curable. Such as have this disease from their infancy, are not to be cured, for it remains with them till their dying day. For large heads, and such as are repleat with acrid or much excrementitious phlegm, scarce yield to medicines. There is much difference whether the phlegm flown down by the internal vessels under the skull; or by the external, which are between the skull and the skin, or by both. For if the internal veins cast forth this matter, it will be difficultly cured, if it be cured at all. But if the external vessels cast forth, that cure is not unprofitable, which having used medicines respecting the whole body, applies astringent medicines to the shaved crown, as, *Empl. contra rupturam,* which may straiten the veins, and, as it were, suspend the phlegm, useth cupping, and commands frictions to be made towards the hind-part of the head, and lastly, maketh a seton in the neck. There are some who cauterize the top of the crown with an hot iron, even to the bone, so that it may cast a scale, thus to divert and stay the defluxion. For local medicines, a *Collyrium* made with a good quantity of Rose-water, with a little vitriol dissolved therein may serve for all.

What *Lippitudo* is.

A *Collyrium* of vitriol to stay the defluxions of the eyes.

CHAP. XII.

Of the Ophthalmia, *or inflammation of the Eyes.*

AN *Ophthalmia* is an inflammation of the coat *Adnata*, and consequently of the whole eye, being troublesome by the heat, redness, beating, renitency, and lastly pain. It hath its original either by some primitive cause or occasion, as a fall, stroke, dust, or small sand flying into the eyes. For the eye is a smooth part, so that it is easily offended by rough things, as saith *Hippocrates, lib. de Carnibus.* Or by an antecedent cause, as a defluxion falling upon the eyes. The signs follow the nature of the material cause, for from blood especially cholerick and thin, it is full of heat, redness and pain; from the same allayed with phlegm all of them are more remiss. But if a heaviness possess the whole head, the original of the disease proceeds there from. But if a hot pain trouble the forehead, the disease may be thought to proceed from some hot distemper of the *Dura mater*, or the *Pericranium*; but if in the very time of the raging of the disease the Patient vomit, the matter of the disease proceeds from the stomach. But from whencesoever it cometh, there

What *Ophthalmia* is, and the causes thereof.

Signs.

there is ſcarce that pain of any part of the body, which may be compared to the pain of the inflamed eyes. Verily the greatneſs of the inflammation hath forced the eyes out of their orb, and broken them aſunder in divers. Therefore there is no part of Phyſick more blazed abroad than for ſore eyes. For

The cure. the cure, the Surgeon ſhall conſider and intend three things, diet, the evacuation of the antecedent and conjunct cauſe, and the overcoming it by topick remedies. The diet ſhall be moderate, eſchewing all things that may fill the head with vapours; and thoſe things uſed that by aſtriction may ſtrengthen the orifice of the ventricle, and prohibit the vapors from flying up to the head; the Patient ſhall be forbidden the uſe of Wines, unleſs peradventure the diſeaſe may proceed from a groſs

Com. ad aphor. 31. ſect. 6. and viſcid humor, as *Galen* delivers it. The evacuation of the matter flowing into the eye ſhall be performed by purging medicines, phlebotomy in the arm, cupping the ſhoulders and neck with ſcarification, and without: And laſtly, by frictions, as the Phyſician that hath undertaken the cure

Lib. 13. meth. cap. ult. ſhall think fit. *Galen* after univerſal remedies for old inflammations of the eyes, commends the opening of the veins and arteries in the forehead and temples, becauſe for the moſt part the veſſels thereabouts diſtended with acrid, hot, and vaporous blood, cauſe great and vehement pains in the eye.

For the impugning of the conjunct cauſe, divers topick medicines ſhall be applied according to the four ſundry times or ſeaſons that every phlegmon uſually hath. For in the beginning when as the acrid matter flows down with much violence, repercuſſives do much conduce; and tempered with reſolving medicines, are good alſo in the increaſe. ℞ *Aq. roſ. & plantag. an.* ℥ ß *mucilag. gum,*

A repercuſſive medicine. *Tragacanth.* ʒ ij *album. ovi quod ſufficit, fiat collyr.* Let it be dropped warm into the eye, and let a double cloth dipped in the ſame *Collyrium* be put upon it. Or, ℞ *Mucil. ſem. pſil. & cydon extractæ in aq. plant. an.* ʒ ß. *Aq. ſolan. & lactis muliebris, an.* ℥ i. *trochiſc. alb. rha.* ϑ. *Fiat collyrium.* Uſe

Aſtringent emplaſters. this like the former. The veins of the temples may be ſtraitned by the following medicine. ℞ *Bol. arm. ſang. drac. & maſt. an.* ℥ ß. *Alb. ovi, aquæ roſ. & acet. an.* ℥ i. *Tereb. lot. & ol. cidon. an.* ℥ i. ſs, *Fiat defenſitum.* You may alſo uſe *Ung. de Bolo, empl. diacal.* or *contra rupturam* diſſolved in oyl of myrtles, and a little vineger. But if the bitterneſs of pain be intolerable, the following Cataplaſm ſhall

An anodyne Cataplaſm. be applied. ℞ *Medul. pomor. ſub ciner. coctorum* ℥ iiij. *Lactis muliebris* ʒ ſs; let it be applied to the eye, the formerly preſcribed *Collyrium* being firſt dropped in. Or ℞ *mucilag. ſem. pſil. & cidon. an.* ℥ ſs *micæ panis albi in lacte infuſi,* ʒ ij. *Aquæ roſ.* ʒ ß *fiat cataplaſma.* The blood of a Turtle Dove, Pigeon, or Hen, drawn by opening a vein under the wings, dropped into the eye, aſſwageth pain.

The efficacy of Bathes in pains of the eyes. Baths are not only anodyne, but alſo ſtay the defluxion by diverting the matter thereof by ſweats; therefore *Galen* much commends them in ſuch defluxions of the eyes as come by fits. In the ſtate when as the pain is either quite taken away or aſſwaged, you may uſe the following medicines. ℞

Ad Aphor. ſect. 7. *Sarcocol. in lacte muliebri nutritæ,* ʒ i. *Aloes lotæ in aq. roſar.* ϑ ii. *Trochiſc. alb. rha.* ʒ ß *ſacchar. cand.* ʒ ij. *Aq. roſ.* ℥ iij. *Fiat collyrium.* Or, ℞ *Sem. fœniculi, & fœnug. an.* ʒ ij. *Flo. chamæ. & melil. an.* m. ſs. *Coquantur in aq. com. ad* ℥ iij. *colaturæ adde tutiæ præp. & ſarcoc. nutritæ in lacte muliebri an.* ʒ i. ſs. *Sacchari cand.* ℥ ſs. *Fiat collyrium ut artis eſt.* In the declination the eye ſhall be fomented with a carminative decoction, and then this *Collyrium* dropped thereinto. ℞ *Sarcoc. nutritæ* ʒ ij. *Aloes & myrrh. an.* ʒ i. *Aq. roſ. & euphrag. an.* ℥ ij. *Fiat collyrium, ut artis eſt.*

Detergent *Collyria.*

CHAP. XIII.

Of the Proptoſis, *that is, the falling or ſtarting forth of the eye, and of the* Phthiſis *and* Chemoſis *of the ſame.*

THe Greeks call that affect *Proptoſis*, the Latines *Procidentia*, or *Exitus oculi* when as the eye ſtands, and is caſt out of the orb, by the occaſion of a matter filling and lifting up the eye into a great bigneſs and largeneſs of ſubſtance. The cauſe of this diſeaſe is ſometimes

The cauſe. external, as by too violent ſtraining to vomit, by hard labour in child-birth, by exceſſive and wondrous violent ſhouting, or crying out. It ſometimes happeneth that a great and cruel pain of the head, or the too ſtrait binding of the forehead and temples for the eaſing thereof, or the palſie of the muſcles of the eye, give beginning to this diſeaſe. Certainly ſometimes the eye is ſo much diſtended by the defluxion of humors, that it breaks in ſunder, and the humors thereof are ſhed, and blindneſs enſues thereof, as I remember befel the ſiſter of *Lewis de Billy* Merchant, dwelling at *Pa-*

The cure. *ris* near St. *Michael's* Bridge. The cure ſhall be diverſified according to the cauſes. Therefore univerſal medicines being premiſed, Cupping-glaſſes ſhall be applied to the original of the ſpinal marrow, and the ſhoulders; as alſo Cauteries or Setons: The eye ſhall be preſſed or held down with clothes doubled and ſteeped in an aſtringent decoction made of the juice of *Acacia*, Red-roſes, the leaves of Poppy, Henbane, Roſes and Pomegranate-pills; of which things poultiſſes may be made by addition of Barly-meal, and the like.

The *Atrophia* of the eye. There is ſometimes to be ſeen in the eye an affect contrary to this, and it is termed *Atrophia*. By this the whole ſubſtance of the eye grows lank and decays, and the apple it ſelf becomes much leſs. But

The *Phthiſis* thereof. *Lib. 3. cap. 22.* if the conſumption and emaciation take hold of the pupil only, the Greeks, by a peculiar name and different from the general, term it a *Phthiſis*, as *Paulus* teacheth. Contrary cauſes ſhall be oppoſed to each affect; hot and attractive fomentations ſhall be applied, frictions ſhall be uſed in the neighbouring parts, and laſtly, all things ſhall be applied which may without danger be uſed to attract the blood and ſpirits into the parts.

The *Chemoſis. Paulus l. 3. c. 2.* There is another affect of the eye, of affinity to the *Proptoſis*, which by the Greeks is termed *Chemoſis*. Now this is nothing elſe then when both the eye-lids are turned up by a great inflammation, ſo that they can ſcarce cover the eyes, and the white of the eye is lifted much higher up than the black. Sometimes the *Adnata* changing his wont, looketh red; beſides alſo, this affect may take its original from external cauſes, as a wound, contuſion, and the like. But according to the variety of the cauſes, and the condition of the preſent affect fixed and remaining in the parts, divers remedies ſhallbe appointed.

CHAP.

CHAP. XIV.

Of the Ungula, or Web.

THe *Ungula*, *Pterygion* or Web is the growth of a certain fibrous and membranous fleſh upon the upper coat of the eye called *Adnata*, ariſing more frequently in the bigger, but ſometimes in the leſſer corner towards the temples. When it is neglected, it covers not only the *Adnata*, but alſo ſome portion of the *Cornea*, and coming to the pupil it ſelf hurts the ſight therefore. Such a web ſometimes adheres not at all to the *Adnata*, but is only ſtretched over it from the corners of the eye, ſo that you may thruſt a *Probe* between it and the *Adnata:* It is of ſeveral colours, ſomewhiles red, ſomewhile yellow, ſomewhiles duskiſh, and otherwhiles white. It hath its original either from external cauſes, as a blow, fall, and the like; or from internal, as the defluxion of humors into the eyes. The *Ungula* which is inveterate, and that hath acquired much thickneſs and breadth, and beſides doth difficultly adhere to the *Adnata*, is difficultly taken away; neither may it be helped by medicines whereby ſcars in the eyes are extenuated. But that which covereth the whole pupil muſt not be touched by the Surgeon, for being cut away, the ſcar which is left by its denſity hindreth the entrance of objects to the cryſtalline humour, and the egreſs of the animal ſpirit to them. But oftentimes it is accompanied with an inflammation of the eyes, a burning, itching, weeping defluxion, and ſwelling of the eye-lids. That the cure may rightly and happily proceed, he muſt firſt uſe a ſpare diet, purging medicines ſhall be given, and blood taken away by opening a vein, eſpecially if there be great inflammation. For peculiar remedies, this excreſcence ſhall be eaten away, or at leaſt kept from growth, by dropping into the eye *Collyrium* of Vitriol deſcribed in wounds of the eyes. But if that we profit nothing by this means, it remaineth, that we take it away with the hand after the following manner;

What web curable, and what incurable.

The cure.

You ſhall ſet the Patient upon a form or ſtool, and make him lean much back, and be held ſo firmly, that he may not fall nor ſtir, then muſt you open his ſore eye, putting therein a *ſpeculum oculi* formerly deſcribed in treating of the wounds of this part, and then muſt you lift up the web it ſelf with a ſharp little hook, with the point turned a little in, and put under the midſt of the web; when you have lifted it a little up, thruſt a needle threaded with a ſmooth thread between it and the *Adnata*, then taking hold of the hook, and the two ends of the thread drawn through with the needle, and lifting up the web by them, you ſhall gently begin to ſeparate it from the ſubſtance of the eye lying thereunder, beginning at the original thereof with a crooked Inciſion-knife, and ſo proſecute it even to the end, yet ſo as you hurt no part of the *Adnata* nor *Cornea*.

The cutting of the web.

The Figure of little Hooks, a Needle, and crooked Inciſion-knife.

Little Hooks. *A Needle.* *A crooked Inciſion-knife.*



Then muſt it be cut off with a pair of ſciſſers, and the white of an Egg beaten with ſome Roſe-water laid thereon, and often renewed. Afterwards the eye muſt every day be opened, leſt coming to cicatrization, the eye-lids ſhall be glued together in that part whereas the web is taken away, which alſo ſhall be hindred by putting of common Salt, Sage and Cummin-ſeed into the eye, being firſt champed and chawed in the mouth. There are ſome who inſtead of the crooked Knife ſeparate the web from the *Adnata* with a Horſes hair, others do it with a Gooſe-quill made ready for the ſame purpoſe, taking heed that they hurt not the caruncle at the corner by the noſe, for it will follow if that you draw the web away too violently; and if it be cut, there will remain a hole, through which during the reſt of the life a weeping humor will continually flow; a diſeaſe by the Greeks termed *Rhyas*. If after the cutting there be fear of inflammation, linnen rags moiſtned in repelling medicines, formerly preſcribed in wounds of the eye, ſhall be laid thereupon,

CHAP.

CHAP. XV.

Of the Ægilops, Fiſtula lacrymoſa, *or weeping of the Fiſtula of the Eye.*

The uſe of the glandule at the greater corner of the eye. The differences.

AT the greater corner of the eye there is a glandule, made for the receiving, and containing the moiſture which ſerveth for the lubricating and humecting the eye, leſt it ſhould dry by continual motion. This glandule ſometimes by a ſanguine or pituitous defluxion falling violently from the brain, ſwells, impoſtumates, and ulcerates with an ulcer, not ſeldom degenerating into a fiſtula, ſo that in ſucceſs of time it rotteth the bone that lieth under it. Of ſuch fiſtula's, ſome are open outwardly, and theſe uſually have their original from a phlegmon; otherſome are inwardly, and thoſe are ſuch as at firſt ſwelled by the defluxion or congeſtion of a phlegmatick matter, ſo that there appeareth no hole outwardly, but only a tumor of the bigneſs of a peaſe, this tumor being preſſed, floweth with a ſanious, ſerous and red, or otherwiſe with a white and viſcid matter, and that either by the corner of the eye, or by the inſide of the noſe. Some have this matter flowing continually, others have it only monthly, which is proper alſo to ſome fiſtula's. Such weeping fiſtula's if they become old, cauſe an *Atrophia* of the eye, and ſometimes blindneſs and a ſtinking breath. Therefore we muſt diligently and ſpeedily by phyſical and chirurgical means reſiſt the breeding diſeaſe. Wherefore, having uſed general medicines, we muſt come to particulars. Therefore if the ulcer be not ſufficiently wide, it ſhall be enlarged by putting tents of ſpunge therein. The fleſh of the glandule increaſing more than is fit, ſhall be corrected by putting therein the catheretick powders of Mercury, calcined Vitriol, or ſome *Aqua fortis*, or oyl of Vitriol; and laſtly, by a potential cautery. If you cannot prevail by theſe means, and that the bone begins to rot, and the Patient be ſtout hearted, then uſe an actual cautery whoſe uſe is far more effectual, ready, certain and excellent, than a potential cantery, as I have tried in many with happy ſucceſs. In my opinion it makes no matter, whether the cautery of Gold, Silver or Iron; for the efficacy it hath proceedeth not from the matter, but from the fire. Yet if we muſt religiouſly obſerve and make choice of metals, I had rather have it of Iron, as that which hath a far more drying and aſtringent faculty than Gold, for that the Element of Earth beareth the chief ſway therein, as appeareth by the waters which flow through Iron mines. Wherefore you ſhall cauſe to be made a triangular Iron, ſharp at the end, that it may the more ſpeedily penetrate. And then the ſound eye and adjacent parts being well covered and defended, and the Patients head firmly holden in ones hand, leſt the Patient being affrighted, ſtir himſelf in the very inſtant of the operation. But a plate of Iron ſomewhat depreſſed in the midſt, for the cavity of the greater corner ſhall be applied and fitted to the pained eye. This plate ſhall be perforated that the hot Iron may paſs thereby to the fiſtula lying thereunder and ſo may only touch that which is to be cauterized.

Periodical and typical fiſtula's.

The cure.

The efficacy of an actual Cautery.

The Figure of a Cautery, and a Plate with a hole therein.



Things to be done after the cauterzing.

After the bone is burnt with the Cautery, a *Collyrium* made of the whites of Eggs beaten in Plantain and Night-ſhade waters muſt be poured into the hole it ſelf, the eye and all the neighbouring parts; but the Patient ſhall be laid in bed with his head ſomewhat high, and the *Collyrium* ſhall be renewed as often and as ſoon as you ſhall perceive it to grow dry. Then the fall of the Eſchar ſhall be procured by anointing it with freſh Butter; when it is fallen away, the ulcer ſhall be cleanſed, filled with fleſh, and laſtly cicatrized.

CHAP. XVI.

Of the Staphyloma, *or Grape-like ſwelling.*

What a *Staphyloma*, is and the cauſes thereof.

Staphyloma is the ſwelling of the horny and Grape-like Coat, bred through the occaſion of an humor flowing down upon the eye, or by an ulcer, the horny coat, being relaxed, or thruſt forth by the violence of the puſtule generated beneath. It in ſhape reſembleth a Grape, whence the Greeks ſtile it *Staphyloma*. This tumor is ſometimes blackiſh, otherwhiles whitiſh. For if the horny coat be ulcerated and fretted in ſunder, ſo that the grapy coat ſhew it ſelf and fall through the ulcer, then the *Staphyloma* will look black like a ripe Grape, for the utter part of the *Uvea* is blackiſh. But if the *Cornea* be only relaxed and not broken, then the ſwelling appears of a whitiſh colour like an unripe Grape. The Ancients have made many kinds or differences thereof. For if it be but a ſmall hole of the broken *Cornea* by which the *Uvea* ſheweth or thruſteth forth it ſelf, then they termed it *Myocephalon*, that is, like the head of a Flie. But if the hole were large, and alſo callous, they called it

Paulus and Ætius.

Clavus,

Clavus, or a nail; if it were yet larger, then they termed it *Acinus*, or a Grape. But in what shape or figure soever this disease shall happen, it bringeth two discommodities, the one of blindness, the other of deformity. Wherefore here is no place for Surgery to restore the sight, which is already lost, but only to amend the deformity of the eye; which is by cutting off that which is prominent. But you must take heed that you cut away no more than is fit, for so there would be danger of pouring out the humors of the eye.

Every *Staphiloma* infers incurable blindness.

CHAP. XVII.

Of the Hypopyon, *that is, the suppurate or putrified eye.*

PUS or Quitture is sometimes gathered between the horny and grapy coat from an internal or external cause: From an internal, as by a great defluxion, and oft-times after an inflammation; but externally by a stroke, through which occasion, a vein being opened hath poured forth blood thither, which may presently be turned into Quitture. For the cure, universal remedies being premised, Cupping-glasses shall be applied, with Scarifications and Frictions used. Anodine and digestive *Collyria* shall be poured from above downwards. *Galen* writes that he hath sometimes evacuated this matter, the *Cornea* being opened at the *Iris*, in which all the coats meet, concur and are terminated. I have done the like, and that with good success, *James Guillemeau* the King's Surgeon being present, the Quitture being expressed and evacuated after the apertion. The ulcer shall be cleansed with *Hydromel*, or some other such like medicine.

The cause.

Lib. 14. *Method. cap. ult.*

CHAP. XVIII.

Of the Mydriasis, *or dilatation of the Pupil of the* Eye.

MYdriasis is the dilatation of the pupil of the eye, and this hapneth either by nature or chance: The former proceedeth from the default of the first conformation, neither is it curable; but the other is of sorts, for it is either from an internal cause, the off-spring of an humour flowing down from the brain, wherefore physical means must be used for the cure thereof. Now that which cometh by any external occasion, as a blow, fall or contusion upon the eye, must be cured by presently applying repercussive and anodyne medicines, the defluxion must be hindred by diet skilfully appointed, phlebotomy, cupping, scarification, frictions, and other remedies which may seem convenient. Then must you come to resolving medicines, as the blood of a Turtle-dove, Pigeon or Chicken, reeking-hot out of the vein, being poured upon the eye and the neighbouring parts. Then this following Cataplasm shall be applied thereto, ℞ *Farinæ fabar. & hordei an.* ℥ iij. *Ol. rosar. & myrtillor. an.* ℥ i. ß *pul. ireos flor.* ʒ ij. *Cum sapa fiat cataplasm.* You may also use the following fomentation: ℞ *Rosar. rub. & myrtil. an.* m. i *florum melil. & chamæm. an.* p. i. *Nucum cupress.* ℥ i. *Vini austeri* ℔ ß. *Aq. rosar. & plantag. an.* ℥ iii. Make a decoction of them all for a Fomentation to be used with a sponge.

The cause.

The cure.

A digesting Cataplasm

CHAP. XIX.

Of a Cataract.

A Cataract is called also by the Greeks *Hypochima*, by the Latines *Suffusio*. Howsoever you term it, it is nothing else but the concretion of an humor into a certain thin skin under the horny coat, just against the apple or pupil, and as, it were swimming upon the watery humor; and whereas the place ought to be empty, opposing it self to the internal faculty of seeing, whereby it differeth from spots and scars growing upon the horny coat and *Adnata*. It sometimes covereth the whole pupil, otherwhiles but the one half thereof, and somewhiles but a small portion thereof. According to this variety the sight is either quite lost, weak, or somewhat depraved, because the animal vitive spirit cannot in its entire substance pass through the density thereof. The defluxion of the humor whence it proceeds, is either caused by an external occasion, as a stroke, fall, or by the heat or coldness of the encompassing air, troublesome both to the head and eyes; or else it is by an internal means, as the multitude, or else the acrid hot and thin quality of the humors. This disease also sometimes taketh its original from gross and fumid humors sent from a crude stomach, or from vaporous meats or drinks, up to the brain, and so it falleth into the eyes, where, by the coldness, straitness, and tarrying in the place, they turn into moisture, and at length into that concretion or film which we see: The signs may be easily drawn from that we have already delivered. For when the Cataract is formed and ripe, it resembleth a certain thin membrane spred over the pupil, and appeareth of a different colour, according to the variety of the humor whereof it consisteth, one while white, another while black, blue, ash-coloured, livid, citrine green. It sometimes resembleth Quick-silver, which is very trembling and fugitive, more than the rest. At the first when it beginneth to breed, they seem to see many things, as Flies flying up and down, Hares, Nets, and the like, as if they were carelesly tossed up and down before their eyes: Sometimes every thing appeareth two, and some whiles less than they are, because the vitive spirit is hindred from passing to the objects by the density of the skin, like as a cloud shadowing the light of the Sun. Whence it is that the Patients are duller sighted about noon, and surer and quicker sighted in the morning and evening, for that the little vitive spirit diffused through the air, is dispersed by the greater light, but contracted by the less. Now if this film cover half the pupil, then all things shew but by halfs; but if the midst thereof be covered, and, as it were, the centre of the crystalline humor,

A Cataract.

The differences.

Causes.

Signs.

humor, then they ſeem as if they had holes or windows: But if it cover it all, then can he ſee nothing at all, but only the ſhadows of viſible bodies, and of the Sun, Moon, Stars, lighted candles, and the like luminous things, and that but confuſedly, and as by conjecture.

CHAP. XX.

Of the phyſical cure of a beginning Cataract.

Diet for ſuch as are troubled with a Cataract.

A Beginning Cataract is hindred from growing and concretion by diet conveniently and artificially preſcribed, by the abſtinence from Wine, eſpecially more ſtrong and vaporous, and forbearing the uſe of meats, which yield a phlegmatick juice and vaporous; as, Peaſe, Beans, Turneps, cheſnuts, and laſtly, all ſuch things as have the faculty of ſtirring up the humors, and cauſing defluxion in the body; ſuch as are all ſalt, and ſpiced meats, as alſo garlike, onions, muſtard. The immoderate uſe of venery hurts more than all the reſt, for that it more violently exagitates the whole body, weakens the brain and head, and begets crude humors. Let his bread be ſeaſoned with ſome Fennel-ſeeds, for it is thought to have a faculty of helping the ſight, and clearing the eyes, and diſſipating the miſty vapours in the ſtomach before they can aſcend to the brain. Wherefore by the ſame reaſon it is good to uſe Marmelade of Quinces, Conſerve of Roſes, and common Dridge-powder, or any ſuch like compoſed of things good to break wind, or corroborate the ventricle. Phlebotomy and purging, if they be requiſite, ſhall be fitly appointed: Ventoſes ſhall be applied to the ſhoulders and neck; and phlegmatick matter ſhall be diverted and evacuated by the mouth with uſing maſticatories in the morning. There be ſome which believe, that a beginning Cataract may be diſſipated and diſcuſſed by often rubbing the eye-lids with his fingers, and in like ſort by the often and earneſt beholding of the Stars and the Moon when it is at the full, Looking-glaſſes, Diamonds, and all other ſuch like bright ſhining things. I believe, that by beams plentifully and ſuddenly brought and diffuſed over the eye, directly oppoſite againſt ſome bright ſhining thing, it may ſeem to have a penetrating, dividing, diſſolving, as alſo a conſuming and drying faculty. Beſides, alſo the hot breath of him who holdeth in his mouth, and chaweth Fennel-ſeeds, Annis-ſeeds, Coriander-ſeeds, Nutmeg, Cinnamon, Cloves, and the like, hath a great faculty, the eyes being firſt gently rubbed with the finger, it being breathed in near at hand, and often received, to heat, attenuate, reſolve, digeſt and diffuſe the humor which is ready to concrete. Moreover, this *Collyrium* of *John Vigo* is thought very powerful to clear the eyes, ſtrengthen the ſight, hinder ſuffuſions, and diſcuſs them, if at any time they concrete, and begin to gather. ℞ *Hepatis hircini ſani & recentis* ℔ ij *calami aromatici & mellis an.* ℥ ſ. *Succi rutæ,* ʒ iij. *Aquæ chelidoniæ, fœniculi, verbenæ, euphraſiæ an.* ℥ iij. *Piperis longi, nucis moſchatæ, caryophyllorum an.* ʒ ij. *Croci* ℈ i. *floris roriſmarini aliquantum contriti,* m. ſ. *Sarcocollæ, aloes hepaticæ, an.* ʒ iij. *Fellis ratæ, leporis & perdicis. an.* ʒ i. *terantur omnia, tritiſq; adde ſacchari albi* ℥ ij. *mellis roſati* ʒ vi. *conjiciantur in alembicum vitreum, & deſtillentur in balneo Mariæ:* Let this diſtilled liquor be often dropped into the eyes. But if you prevail nothing by all theſe medicines, and that the cloudy and heaped-up humor doth daily increaſe and thicken, then muſt you abſtain from remedies, and expect until it be no more heaped up, but thickned, yea until it ſeem to be grown ſomewhat hard: For ſo it may be couched with a needle; otherwiſe if this ſame skin ſhall not be ripe, but more tender than is fitting, when you ſhall come to the operation, it will be broken and thruſt through with the needle, and not couched. On the contrary, if it be too hard hard, it will reſiſt the needle, neither will it ſuffer it ſelf to be eaſily couched. Wherefore it is requiſite that the Surgeon know when it is ripe, and he muſt diligently obſerve the ſigns whereby he may diſcern a ripe Cataract from an unripe; and that which is curable, from that which is uncurable. For that only which is ripe and curable, is to be couched; that which is unripe, that is ſuch an one as is more tender, and as it were crude, and that which is more hard and denſe, and laſtly, that which is uncurable muſt not be attempted at all.

How bright ſhining things may diſſipate a beginning Cataract.

A *Collyrium* diſſipating a beginning Cataract.

A Cataract muſt not be couched, unleſs it be ripe.

CHAP. XXI.

By what ſigns ripe and curable Cataracts may be diſcerned from unripe and uncurable ones.

Uncurable Cataracts.

IF the ſound eye being ſhut, the pupil of the ſore or ſuffuſed eye, after it ſhall be rubbed with your thumb, be preſently dilated and diffuſed, and with the like celerity return into the place, figure, colour and ſtate, it is thought by ſome to ſhew a ripe and confirmed Cataract. But an unripe, and not to be couched, if the pupil remain dilated and ſuffuſed for a long while after. But it is a common ſign of a ripe, as alſo more denſe, and conſequently uncurable ſuffuſion, to be able to ſee nor diſtinguiſh no viſible thing beſide light and brightneſs; for to diſcern other objects ſheweth that it is not yet ripe: Therefore the ſound eye being ſhut and preſſed, the pupil of the other rubbed with your thumb, is dilated, enlarged, ſwelleth, and is more diffuſed; the viſive ſpirits by this compreſſion being, as it were, forced from the ſound into the ſore-eye. But theſe following Cataracts are judged uncurable, that is, ſuch as are great, ſuch as when the eye-lid is rubbed are nothing dilated or diffuſed, whoſe pupil becometh no broader by this rubbing: For hence you may gather, that the ſtopping or obſtruction is in the optick nerve, ſo that how cunningly and well ſoever the Cataract be couched, yet will the Patient continue blind; you ſhall do no more good in couching a Cataract, which is in an eye conſumed and waſted with a *Phthiſis*. Alſo that Cataract is incurable, which is occaſioned by a moſt grievous diſeaſe, to wit, by moſt bitter and cruel pains of the head, or by a violent blow. Such as are of a plaſter-like green, black, livid, citrine and quick-ſilver-like colour, are uſually uncurable. On the contrary, ſuch as are of a Cheſnut colour, or of a ſky or ſea-water colour, with ſome little whiteneſs, yield great hope of a happy and ſucceſsful cure.

Curable Cataracts.

CHAP.

CHAP. XXII.

Of the couching a Cataract.

When to couch a Cataract.

After you ſhall know by the ſore-mentioned ſigns that the Cataract is curable, it remains that you attempt the couching thereof, but ſo, that there be nothing which may hinder. For if the pain of the head, cough, nauſeouſneſs or vomiting at that time trouble the Patient, you ſhall then beſtow your labour in vain: wherefore you muſt expect till theſe ſymptoms are gone. Then make choice of a ſeaſon fitting for that purpoſe, that is, in the decreaſe of the Moon, when the Air is not troubled with Thunder nor Lightning, and when as the Sun is not in *Aries*, becauſe that ſign hath dominion over the head. Then let the Surgeon conſult a Phyſician whether purging or bloud-letting be convenient for the Patient, ſo to reſiſt plethorick ſymptoms, otherwiſe ready to yield matter for relapſe. Two days after you muſt make choice of a place furniſhed with indifferent or competent light, and the Patient being faſting ſhall be placed in a ſtraight Chair, ſo that the light may not fall with the beams directly upon him, but ſide-wiſe. The eye which ſhall be cured, muſt be made more ſteddy by laying and binding Wool upon the other. Then the Surgeon ſhall ſeat and place himſelf directly againſt the Patient upon a ſeat ſomewhat higher, and bidding the Patient put his hands down to his girdle, he ſhall hold the Patients legs between his knees. One ſhall ſtand at the Patients back, who ſhall hold his head, and keep it from ſtirring; for by a little ſtirring he may loſe his ſight for ever. Then muſt you prepare and make ready your Needle, and thruſt it often into ſome ſtrong thick cloth, that it may be as it were ſmooth by this motion, and for the performance of the work in hand with the leſs pain ſomewhat warmed. It muſt be made of iron, or ſteel, and not of gold or ſilver, it muſt be alſo flatted on the ſides, and ſharp-pointed, that ſo it may the better pierce into the eye, and wholly couch the Cataract once taken hold of; and leſt it ſhould ſlip in the Surgeons hand, and be leſs ſteddy, it ſhall be put into a handle, as you may ſee by this Figure.

The place.

The Needle.

A Needle inſerted in a handle for the couching of Cataracts.



All things being thus in a readineſs, you muſt bid the Patient to turn the ſight of his eye towards his noſe, and the Needle muſt be boldly thruſt (for it is received in a place that is void, and onely filled with ſpirits) directly by the coat *Adnata*, in the middle ſpace between the leſſer corner and the horny coat, juſt againſt the midſt of the Cataract, yet ſo as that you hurt no vein of the *Adnata*, and then by ſtirring it as it were diverſly until it come to the midſt of the pupil and ſuffuſion. When it is come thither, the Needle muſt be inclined from above downwards to the ſuffuſion, and there to be ſtirred gently until by little and little it couch or bring down the Cataract as whole as may be beneath the compaſs of the pupil; let him ſtill follow it though couched with his Needle, and ſomewhat violently depreſs and keep it down for ſome ſhort ſpace, that ſo it may reſt and ſtay in that lower place whither it is depreſſed. The Surgeon ſhall try whether it firmly remain there or no, bidding the Patient preſently to move his eye; for if it remain conſtantly ſo, and do not return again, the Cure is perfect. Then muſt the Needle be lifted up by little and little, neither muſt it preſently be taken forth, that if the Cataract ſhould bear up, or riſe again, that it might again, and ſo often (whileſt the work is yet hot, and all things in a readineſs) be couched towards the leſſer corner, until it be fully and ſurely hid. Then muſt you draw back the Needle gently, and after the ſame manner as you put it in; leſt if you uſe not moderation, you bring back the Cataract from whence you couched it, or grievouſly offend the chryſtalline humour, the prime inſtrument of ſight, or the pupil with danger of dilating thereof. Some as ſoon as the work is done, give the Patient ſomething in his hand to look upon: but *Paulus* approves not thereof, for he fears leſt his endeavoring or ſtriving to ſee, may draw back the Cataract. Wherefore it is more wiſdom, and better preſently after the drawing forth of the Needle, to put on a ſoft rag the white of an Egg beaten in Roſe-water with a little choice Alum, and ſo apply it to the eye and neighbouring parts for to bind and hinder the inflammation; then alſo you muſt together therewith bind up the ſound eye, leſt by ſtirring to ſee, it might together therewith draw and move the ſore eye, by reaſon of the ſympathy and conſent they mutually have by the optick nerves. After all things are thus performed, the Patient ſhall be laid in a ſoft bed, and ſo placed, that his head may lie ſomewhat high; let him be laid far from noiſe, let him not ſpeak, nor eat any hard thing that may trouble his jaws, wherefore let him feed upon liquid meats, as panado, barley-cream, cullifſes, gellies, rear-eggs, and other meats of the like nature. At the end of eight days the ligature that binds up the eyes ſhall be looſed, and his eyes waſhed with Roſe-water, and putting on Spectacles, or ſome Taffaty, the Patient ſhall by little and little accuſtom himſelf to the light, leſt he ſhould be offended by the ſudden meeting with light. But if the ſuffuſion, after ſome ſhort while after lift it ſelf up again, it muſt be couched again, but through a new hole, for the eye is pained and tender in the former place. It ſometimes happens by the touch of the Needle that the Cataract is not couched whole, but is broken into many pieces; then therefore each of them muſt be followed, and couched ſeverally: if there be any very ſmall particle which ſcapes

Gal. lib. 10. de uſu partium c. 5. Celſ. lib. 7.

The ſign of a Cataract well couched.

Lib. 6. cap. 21.

What to be done after the couching of a Cataract.

Of a Cataract which is broken to pieces.

the needle, it must be let alone, for there is no doubt but that in process of time it may be dissolved by the force of the native heat. There are also some Cataracts which at the first touch of the needle are diffused and turn into a substance like to Milk or troubled Water, for that they are not throughly ripe, yet these put us in good hope of recovery, if it be but for this, that they can never afterwards concrete into one body as before. Wherefore at the length they are also discussed by the strength of the native heat, and then the eye recovers its former splendor. If that any other symptoms come unlooked for, they shall be helped by new counsels and remedies.

CHAP. XXIII.

Of the stopping of the passage of the Ears, and the falling of things thereinto.

The Cause.

IT sometimes happeneth that children are born without any holes in their ears, a certain fleshly or membranous substance growing in their bottom or first entrance. The same may also happen afterwards by accident, they being ulcerated by some impostume or wound, and the ear shut up by some fleshly excrescence or scar. When as the stopping is in the bottom of the cavity, the cure is more difficult than if it were in the first entrance. But there is a double way of cure; for this substance, whatsoever it be, must either be cut out, or else eaten away and consumed by acrid and catheretick Medicins; in performance of which there is need of great moderation of the mind and hand. For it is a part enduced with most exquisite sense and near the brain, wherefore by handling it too roughly, there is fear of distension of the nerves, and consequently of death.

The Cure.

Sometimes also the preternatural falling of some strange bodies into this passage maketh a stopping of the ears, such as are fragments of Stone, Gold, Silver, Iron, and the like Metals, Pearls, Cherry-stones, or Kernels, Pease and other such like Pulse. Now solid and bony bodies still retain the same magnitude; but Pease Seeds and Kernels, by drawing the moisture there implanted into them, swell up, and cause vehement pain by the distension of the neighbouring parts, wherefore the sooner they are drawn forth, the better it is for the Patient. This shall be done with small pincers and instruments made in the shape of Ear-picks. But if you profit nothing thus, then must you use such gimblets as are made for the drawing forth of bullets shot deep into the body. Little stones and bodies of the like stony hardness, shall be forced forth by the brain, provoked to concussion by sneezing, and by dropping some Oil of Almonds first into the passage of the Ear, that the way may be the more slippery; for it will come to pass by this sneezing, or violence of the internal air forcibly seeking passage out, that at length they may be cast forth, the mouth and nostrils being stopped with the hand. But if we cannot thus prevail, it remains, that we cut open the passage with an incision knife, so much as shall be sufficient for the putting in and using of an Instrument to extract them. If any creeping things of little creatures, as Fleas, Ticks, Pismires, Gnats, and the like, which sometimes happeneth, shall get therein, you may kill them by dropping in a little Oil and Vinegar. There is a certain little creeping thing, which for piercing and getting into the Ears, the *French* call *Perse-oreille* (we an Ear-wig,) this if it chance to get into the Ear, may be killed by the fore-said means; you may also catch it, or draw it forth by laying half an apple to your Ear, as a bait for it.

The concussive force of sneezing.

CHAP. XXIV.

Of getting of little bones and such like things out of the Jaws and Throat.

The Cure different according to the places where they stick.

SOmetimes little bones and such like things in eating greedily use to stick, or as it were fasten themselves in the Jaws or Throat. Such bodies if you can come to the sight of them, shall be taken out with long, slender and crooked Mallets made like a Cranes beak. If they do not appear, nor there be no means to take them forth, they shall be cast forth by causing vomit, or with swallowing a crust of bread, or a dry fig gently chawed, and so swallowed; or else they shall be thrust down into the stomach, or plucked back with a leek, or some other such long and stiff crooked body anointed with Oil and thrust down the throat. If any such like thing shall get into the Weazon, you must cause coughing, by taking sharp things, or else sneezing; so to cast forth whatsoever is there troublesom.

CHAP. XXV.

Of the Tooth-ach.

The Tooth-ach a most cruel pain.

OF all pain, there is none which more cruelly tormenteth the Patients than the Tooth-ach. For we see them often-times after the manner of other bones to suffer inflammation, which will quickly suppurate, and they become rotten, and at length fall away piece-meal; for we see them by daily experience to be eaten and hollowed, and to breed Worms, some portion of them putrefying. The cause of such pain is either internal, or external and primitive. The internal is a hot or cold defluxion of humours upon them, filling their sockets, and thence consequently driving out the teeth; which is the reason that they stand sometimes so far forth, that the Patient neither dares, nor can make use of them to chaw for fear of pain; for that they are loose in their sockets by the relaxation of the Gums, caused by the falling down of the defluxion. When as they are rotten and perforated even to the roots, if any portion of the liquor in drinking fall into them, they are pained as if you thrust in a pin or bodkin, the bitterness of the pain is such. The signs of a hot defluxion are sharp and pricking pain, as if needles were thrust into them, a great pulsation in the root of the pained Tooth and the Temples, and some ease by

The cause thereof.

The signs of this or that defluxion.

by the use of cold things. Now the signs of a cold defluxion are a great heaviness of the head, much and frequent spitting, some mitigation by the use of hot remedies. In the bitterness of pain we must not presently run to Tooth-drawers, or cause them presently to go in hand to pluck them out. First consult a Physician, who may prescribe remedies according to the variety of the causes. Now here are three intentions of Curing. The first is concerning Diet, the other for the evacuation of the defluxion or antecedent cause, the third for the application of proper remedies for the assuaging of pain. The two former scopes, to wit, of Diet, and diverting the defluxion by Purging, Phlebotomy, application of Cupping-glasses to the Neck and Shoulders, and Scarification, do absolutely belong to the Physician. Now, for proper and topick Medicins they shall be chosen contrary to the cause. Wherefore in a hot cause it is good washing the mouth with the juice of Pomgranates, Plantain Water, a little Vinegar, wherein Roses, *Balaustiæ* and *Sumach* have been boiled. But such things as shall be applied for the mitigating of the pain of the Teeth, ought to be things of very subtle parts, for that the Teeth are parts of dense consistence. Therefore the Ancients have always mixed Vinegar in such kind of remedies. ℞ *Rosar. rub. Sumach. hordei, an.* m. ſ. *seminis hyoscyami conquassati,* ʒ ij. *santalorum an.* ʒ j. *lactucæ summitatum rubi, solani, plantaginis, an.* m. ſ. *buliant omnia in aquæ* ℔ iv. *& pauco aceto ad hordei crepaturam.* Wash the mouth with such a decoction being warm. You may also make Trochisces for the same purpose after this manner. ℞. *Sem. hyoscyami, sandaracha, coriandri, opii, an.* ʒ ß. *terantur & cum aceto incorporentur, formenturque trochisci apponendi dentibus dolentibus.* Or else, ℞ *Sem. portulacæ, hyoscyami, coriandri, lentium, corticis, santali citrini, rosar. rub. pyrethri, camphoræ, an.* ʒ ſ. let them all be beaten together with strong Vinegar, and made into Trochisces, with which being dissolved in Rose-water, let the Gums and whole mouth be washed when need requireth. But if the pain be not assuaged with these, you shall come to narcoticks which may stupefie the nerve; as, ℞. *Sem. hyoscyami albi, opii camphoræ, papav. albi, an. quantum sufficit, coquantur cum sapa, & denti applicentur.* Besides you must also put this following Medicin into the ear of the pained side. ℞ *Opii & castorei, an.* ℈ j. *misceantur cum oleo rosato:* It hath sometimes availed in swollen and distended Gums, being first lightly scarified, to have applied Leeches, for the evacuation of the conjunct matter, as also to have opened the Veins under the Tongue, or these which are behind the ears. For I remember that I, by these three kinds of remedies, assuaged great pains of the Teeth. Yet there be some who in this affect open not these veins which are behind the ears, but those which are conspicuous in the hole of the ear, in the upper part thereof.

Three scopes of curing.

A cold and repercussive lotion for the mouth.

Trochisces for a hot defluxion.

Narcoticks.

Pain of the Teeth arising from a cold cause and defluxion, may be helped by these remedies; boil Rosemary, Sage, and Pellitory of *Spain* in Wine and Vinegar, and add thereto a little *aqua vitæ*; in this liquor dissolve a little treacle, and wash your Teeth therewith. Others mingle Gum *ammoniac* dissolved in *aqua vitæ* with a little *sandarachæ* and myrrh, and lay it to the pained Tooth after *Vigo*'s counsel. *Mesue* thinks that beaten Garlick carried in the right or left hand, assuages the pain, as the Teeth ake upon the right or left side. But I being once troubled with grievous pain in this kind, followed the counsel of a certain old Woman, and laid Garlick roasted under the embers to my pained tooth, and the pain fortwith ceased. The same remedy used to others troubled with the like affect, had like success. Moreover, some think it available if it be put into the auditory passage. Others drop into the ears Oil of *Castoreum*, or of Cloves, or some such other Chymical Oil. It is good also to wash the Teeth with the following decoction. ℞ *Rad. pyrethri* ʒ ß. *menthæ & rutæ, an.* p. j. *buliant in aceto,* and with this decoction being warm, wash the Teeth. Some like fumes better, and they make them of the Seeds of *Coloquintida* and mustard, and other like; they take the smoak by holding their mouths over a Funnel. Other some boil Pellitory of *Spain*, Ginger, Cinnamon, Alum, common Salt, Nutmegs, Cypress-nuts, Anise and Mustard Seeds, and *Euphorbium* in Oxycrate, and in the end of the decoction add a little *aqua vitæ*, and receive the vapour thereof through a Funnel; as also they wash their Teeth with the decoction, and put Cotton dipped therein into the ear, first dropping in a little thereof. Some there are which affirm, that to wash the Teeth with a decoction of Spurge is a very good and anodyne Medicin in the Tooth-ach. I have oft-times assuaged intolerable pains of the Teeth, by applying vesicatories under the ear, to wit, in that cavity whereas the lower jaw is articulated with the upper; for the vein, artery, and sinew that are distributed to the roots of the Teeth, lie thereunder. Wherefore the blisters being opened, a thin liquor runs out, which doth not only cause, but also nourish or feed the disease. But if the tooth be hollowed, and that the Patient will not have it pulled out, there is no speedier remedy than to put in caustick medicins, as oil of vitriol, *aqua fortis*, and also an hot iron; for thus the nerve is burnt in sunder, and loseth its sense. Yet some affirm that the milky juice that flows from Spurge made into a paste with *olibanum* and *amylum*, and put into the hollow tooth, will make it presently to fall away in pieces. When the gums and cheeks are swollen with a manifest tumor, then the Patient begins to be somewhat better and more at ease. For so by the strength of Nature the tumor causing the pain is carried from within outwards. But of what nature soever the matter which causeth the pain be, it is convenient to intercept the course thereof with *Empl. contra rupturam* made with Pitch and Mastich, and applied to the temple on that side where the tooth aketh.

Hot Fumes.

Vesicatories.

Caustick.

CHAP. XXVI.

Of other Affects of the Teeth.

THe Teeth are also troubled with other preternatural affects. For sometimes they shake by relaxation of the Gums, or else become corrupt and rotten, or have Worms in them, or else are set on edge. For the first, the Gums are relaxed either by an external or primitive cause, as a Fall or Blow: or else by an internal or antecedent, as by the defluxion of acrid or wateriſh humours from the brain, or through want of nourishment in old bodies. If the Teeth grow loose by the means of the decaying Gums, the disease is then uncurable: but

Causes of looseness of the Teeth.

you may withſtand the other cauſes by the uſe of ſuch things as faſten the teeth, ſhunning on the contrary ſuch as may looſen them. Therefore the Patient muſt not ſpeak too earneſtly, neither chew hard things. If they become looſe by a fall or blow, they muſt not be taken forth, but reſtored and faſtned to the next that remain firm, for in time they will be confirmed in their ſockets, as I tried in

A Hiſtory. *Antony de la Rue* a Tailor, who had his Jaw broken with the Pommel of a Dagger, and three of his teeth were looſened, and almoſt ſhaken out of their ſockets; the Jaw being reſtored the teeth were alſo put in their places, and bound to the reſt with a double waxed thred; for the reſt, I fed the Patient with Broths, Gellies, and the like, and I made aſtringent Gargariſms of Cypreſs-nuts, Myrtle-berries, and a little Alum boiled in Oxycrate, and I wiſhed him to hold it a good while in his mouth: by theſe means I brought it ſo to paſs that he within a while after could chew as eaſily upon thoſe teeth as upon the other. I heard it reported by a credible perſon, that he ſaw a Lady of the prime Nobility, who in ſtead of a rotten tooth ſhe drew, made a ſound tooth, drawn from one of her waiting Maids at the ſame time, to be ſubſtituted and inſerted, which tooth in proceſs of time, as it were taking root, grew ſo firm, that ſhe could chew upon it as well as upon any of the reſt. But as I formerly ſaid, I have this but by hear-ſay.

The cauſes of hollow teeth. Now the teeth are corroded or eaten in by an acrid and thin humour penetrating by a plenteous and frequent defluxion even to their roots, and being there contained, it putrefies, and becoming more acrid, it doth not onely draw the teeth into the contagion of its putrefaction, but alſo perforates and corrodes them.

The Cure. The putrefaction may be corrected, if after general Medicins you put Oil of Vitriol or *aqua fortis* into the hole of the eaten tooth: or elſe, if you burn the tooth it ſelf to the root with a ſmall iron Wier being red hot: you ſhall thruſt this hot iron thorow a Pipe or Cane made for the ſame purpoſe, leſt it ſhould harm any ſound part by the touch thereof, and thus the putrefaction, the cauſe of the arroſion may be ſtaid. But if the hole be on the one ſide between two teeth, then ſhall you file away ſo much of the ſound tooth, as that you may have ſufficient liberty to thruſt in your Wier without doing any harm.

The forms of Files made for filing the Teeth.



Cauſes of Worms in the teeth. Worms breeding by putrefaction in the roots of the teeth, ſhall be killed by the uſe of cauſticks, by gargles or lotions made of Vinegar, wherein either Pellitory of *Spain* hath been ſteeped, or treacle diſſolved; alſo aloes and garlick are good to be uſed for this purpoſe.

Cauſes of ſetting the teeth on edge. Setting the teeth on edge happens to them by the immoderate eating of acrid or tart things, or by the continual aſcent of vapours endued with the ſame quality, from the orifice of the ventricle to the mouth, or by a cold defluxion, eſpecially of acrid phlegm, falling from the brain upon the teeth, or elſe by the too exceſſive uſe of cold or ſtupefying liquors. This affect is taken away, if after general Medicins and ſhunning thoſe things that cheriſh the diſeaſe, the teeth be often waſhed with *aqua vitæ*, or good Wine wherein Sage, Roſemary, Cloves, Nutmegs, and other things of the like nature have been boiled.

CHAP. XXVII.

Of drawing of Teeth.

TEeth are drawn, either for that they cauſe intolerable pains, which will not yield to Medicins, or elſe for that they are rotten and hollowed, ſo that they cauſe the breath to ſmell; or elſe for that they infect the ſound and whole teeth, and draw them into the like corruption, or becauſe they ſtand out of order. Beſides, when they are too deep and ſtrongly rooted, ſo that they cannot be plucked out, they muſt oft-times be broken of neceſſity, that ſo you may drop ſome cauſtick thing into their roots, which may take away the ſenſe, and conſequently the pain. The hand

A caveat in drawing of teeth. muſt be uſed with much moderation in the drawing out of a tooth; for the jaw is ſometimes diſlocated by the too violent drawing out of the lower teeth. But the temples, eyes, and brain are ſhaken with great danger by the too rude drawing of the upper teeth. Wherefore they muſt firſt be cut about, that the Gums may be looſed from them, then ſhake them with your fingers, and do this until they begin to be looſe; for a tooth which is faſt in, and plucked out with one pull, oft-times breaks the jaw, and brings forth the piece together therewith, whence follows a Fever and a great flux of bloud not eaſily to be ſtaid (for bloud or *pus* flowing out in great plenty is, in *Celſus*'s opinion, the ſign of a broken bone) and many other malign and deadly

Lib.7.cap.8. ſymptoms. Some have had their mouths drawn ſo awry, during the reſt of their lives, that they could ſcarce gape. Beſides, if the tooth be much eaten, the hole thereof muſt be filled either with Lint, or a Cork, or a piece of Lead well fitted thereto, leſt it be broken under your *forceps*, when it

it is twitched more ſtraightly to be plucked out, and the root remain, ready in a ſhort time to cauſe more grievous pain. But judgment muſt be uſed, and you muſt take ſpecial care, leſt you take a ſound tooth for a pained one; for oft-times the Patient cannot tell, for that the bitterneſs of pain by neighbourhood is equally diffuſed over all the Jaw. Therefore for the better plucking out a tooth, obſerving theſe things which I have mentioned, the Patient ſhall be placed in a low ſeat, bending back his head between the Tooth-drawers legs; then the Tooth-drawer ſhall deeply ſcarifie about the tooth, ſeparating the gums therefrom with the inſtruments marked with this letter *A*, and then if ſpoiled as it were of the wall of the gums, it grow looſe, it muſt be ſhaken and thruſt out, by forcing it with the three-pointed Levatory noted with this Letter *B*; but if it ſtick in too faſt, and will not ſtir at all, then muſt the tooth be taken hold of with ſome of theſe toothed *forcipes* marked with theſe letters *C C D*; now one, then another, as the greatneſs, figure and ſite ſhall ſeem to require. I would have a Tooth-drawer expert and diligent in the uſe of ſuch toothed Mullets; for unleſs one know readily and cunningly how to uſe them, he can ſcarce ſo carry himſelf, but that he will force out three teeth at once, oft-times leaving that untoucht which cauſed the pain.

The manner of drawing Teeth.

The Effigies of Forcipes, *or Mullets for the drawing of Teeth.*

Inſtruments for ſcraping the Teeth and a three-pointed Levatory.



The form of another Inſtrument for drawing of Teeth.



After the Tooth is drawn, let the blood flow freely, that ſo the part may be freed from pain, and the matter of the tumor diſcharged. Then let the Tooth-drawer preſs the fleſh of the gums on both ſides with his fingers whereas he took out the Tooth, that ſo the ſocket that was too much dilated, and oft-times torn by the violence of the pluck, may be cloſed again. Laſtly, The mouth ſhall be waſhed with Oxycrate; and if the weather be cold, the Patient ſhall take heed of going much in the open air, leſt it cauſe a new defluxion upon his Teeth.

What to be done when the Tooth is pluckt out.

CHAP. XIV.

Of cleanſing the Teeth.

Pieces of meat in eating ſometimes ſtick between the teeth, and becoming corrupt by long ſtaying there, do alſo hurt the teeth themſelves, and ſpoil the ſweetneſs of the breath. He that would eſchew this, ought preſently after meat, to waſh his mouth with Wine mixed with Water, or Oxycrate, and well to cleanſe his teeth, that no ſlimy matter adhere to them. Many folks teeth by their own default gather an earthy filth of a yelloviſh colour, which eats into them by little and little, as ruſt eats into iron. This ruſty filthineſs, or as it were mouldineſs of the teeth, doth alſo oft-times grow by the omitting of their proper duty, that is of chawing. Whence-

Cauſes of foul or ruſty Teeth.

The Cure. soever this ſlimy filth proceeds, we muſt get *Dentrifrices* to fetch it off withall, and then the teeth muſt be preſently rubbed with *aqua fortis* and *aqua vitæ* mixed together, that if there be any thing that hath ſcaped the *Dentrifrices*, it may be all fetched off; yet ſuch acrid waſhings are hurtful to the ſound teeth, for that they by little and little conſume and waſte the fleſh of the gums.

A caution in the uſe of acrid things. *Dentifrices* ſhall be made of the root of Marſh-mallows boiled in white Wine and Allum; and, as when the teeth are looſe, we muſt abſtain from ſuch things as are hard to be eaten and chawed, but much more from breaking of ſuch things as are of a bony conſiſtence, ſo alſo here we muſt ſhun all things that by their toughneſs ſtick to the teeth. Many for the cleanſing of the teeth commend a Powder made of Scuttle-bones, Purple-ſhells, Pumice-ſtone, burnt Allum, and Harts horn, and a little Cinnamon, which is a ſingular remedy for the teeth howſoever affected. Many other are content with bread onely toſted and beaten; but this following Water is very effectual to whiten the teeth.

A Water to whiten the teeth. R. *Sal. ammon. & gemmei, an.* ʒ j. *alum. roch.* ʒ ß. *aquæ roſ. quod ſufficit, diſtillentur.* And let the teeth be cleanſed with this diſtilled liquor.

CHAP. XXIX.

Of the impediment and contraction of the Tongue.

The cauſe of being Tongue-tied. THe Tongue is ſometimes tied and ſhort from the nativity; as when the liberty of the Tongue is reſtrained by the ſubject and neighbouring, as well membranes as muſcles, being either too ſhort or too hard. Sometimes this diſeaſe happens after they are born by ſome accident or preternatural affect, as by too hard a ſcar left by the healing of an Ulcer under the Tongue.

The Cure. The Patient at his beginning to ſpeak, is too ſlow in ſpeaking, but preſently leaving his ſlowneſs, he becomes too quick, ſo that he ſtammers. If the diſeaſe proceed from the aſtriction and ſhortneſs of the ligamental membrane lying under the Tongue, then the inciſion ſhall be made broad-wiſe, having great care that the veins and arteries which are there, be not violated, for fear left they ſhould cauſe an *Hemorrhagie*, not eaſily to be ſtaid. Then the mouth ſhall be preſently waſhed with Oxycrate, and ſome lint dipped in Syrup of dried Roſes, or Honey of Roſes put into the midſt of the inciſion, leſt the part of the ligament, eſpecially in the night time when the Tongue is ſilent and at reſt, ſhould grow to the reſt of the ligament. For the ſame purpoſe the finger ſhall be often thruſt this way, and the Tongue more violently rowled up and down and thruſt out of the mouth. Yet ſometimes this ligament is ſo thick and ſhort, and therefore holds down the Tongue ſo cloſe, that you cannot come to cut it with a knife or lancet, without great and manifeſt danger of death by bleeding.

Another way to cut it. Therefore in ſuch a caſe a needle and thred ſhall be thruſt through it, and ſo the thred ſhall be tied ſtraighter and ſtraighter every day, until by little and little this ligamental tie of the Tongue, which by its immoderate ſhortneſs intercepts the liberty of the motion, ſhall be conſumed and broken.

CHAP. XXX.

Of ſuperfluous Fingers, and ſuch as ſtick together.

The differences. EAch hand hath naturally five Fingers onely; whatſoever is more or leſs is againſt Nature: and if there be fewer, it a fault not to be helped by Art. But if there be more, that for the moſt part maybe helped by Art. Superfluous Fingers uſually grow by the Thumb or the little Finger, but ſeldom otherwiſe. Theſe are either wholly fleſhy, or have bones of their kind and nails upon them. Thoſe which are of a bony nature, do either ariſe from the joints of the natural Fingers, and are jointed like them, and ſo are oft-times movable; or elſe from ſome middle ſpace of a joint, and theſe have not power to ſtir or move. Now they are ſometimes equal

Cutting Mullets neatly made for the cutting off ſuperfluous Fingers.

in magnitude to the natural Fingers to which they grow, yet more frequently they are ſhorter. Thoſe which are onely fleſhy, are eaſily amputated and made even with a razor; but ſuch as are alſo bony cannot be cut off, unleſs with the cutting Mullets here deſcribed, and this is a diſeaſe of the Fingers in number. There is alſo another diſeaſe in Fingers, for they ſometimes ſtick together,

gether, and otherwhiles they are very little separated. This fault happens either from the first original, by the errour of the formative faculty; or else it happens afterwards by accident, as by a Wound, or Burn ill cured. For neighbouring Fingers being ulcerated do easily grow together, unless they be kept asunder by a linnen rag. And if they by chance shall grow together by a little and thin skin and flesh, they shall forthwith be divided with a sharp Razor; but if they be joined by the interposition of a more gross and dense substance, to wit, the nerves, tendons, and vessels being knit together on each side, it will be best not to meddle at all with the dividing them.

The cure of nails running into the flesh of the fingers.

Neither must we omit, that many have their nails run with such bony sharpness into the flesh of their fingers lying under them, that they cause most cruel pain; neither commonly do you avail any thing by paring them; for growing up within a while after, they press downwards again with the more violence. Therefore the Surgeon is often forced to cut away all the flesh whereinto the sharpness of the nail runs. Which I have done in many with happy success. Many have Corns growing upon their Fingers in divers fashions: They are taken off by paring away by little and little, the callous hardness, and then laying a head of Garlick beaten thereon. Yet the Cure is more quick and certain, which is performed by caustick, as *aqua fortis*, or Oil of Vitriol.

How to take off the Corns of the fingers.

CHAP. XXXI.

Of the too short a Prepuce, and of such as have been circumcised.

The Cause.

The Cure.

When as the Prepuce ot fore-skin is too short, it cannot cover the *Glans*. This happens either by Nature, to wit, by the first conformation, or afterwards by some accident, as to those whom Religion and the custom of their Nation bids to be circumcised. The Cure is thus: The Prepuce is turned up, and then the inner membrane thereof is cut round, and great care is had, that the Vein and Artery which are there between the two membranes of the Prepuce, be not cut in sunder. Hence it is drawn downward by extension, until it cover the *Glans*, a deiccative emplaister being first put between it and the *Glans*, lest they should grow together. Then a Pipe being first put into the urinary passage, the Prepuce shall be there bound until the incision be cicatrized. This cure is used to the *Jews*, when having abjured their Religion full of superstitions, for handsomness sake, they would cover the Nut of their Yard with a Prepuce, and so recover their cut-off-skin.

CHAP. XXXII.

Of Phimosis *and* Paraphimosis, *that is, so great a constriction of the Prepuce about the* Glans *or Nut, that it cannot be bared or uncovered at pleasure.*

The Causes.

The Cure.

The Prepuce is straightned about the *Glans* two ways; for it either covers the whole Nut, and so straightly encompasses the end thereof, that it cannot be drawn upwards, and consequently the Nut cannot be uncovered; or else it leaves the *Glans* bare under it, being fastned so stiffly to the roots thereof, that it cannot be turned up, nor drawn down, or over the *Glans*. The first manner of constriction is termed *Phimosis*, the latter *Paraphimosis*. The *Phimosis* happens either by fault of the first conformation, or else by a scar, through which occasion the Prepuce hath grown lesser, as by the growing of Warts. Now *Paraphimosis* is often occasioned by the inflammation of the Yard, by impure copulation; for hence Ulcers breed between the Prepuce and *Glans*, with swelling and so great inflammation, that the Prepuce cannot be turned back. Whence it is that they cannot be handled and cured as you would, and a Gangrene of the part may follow, which may by the contagion bring death to all the body, unless it be hindred by amputation: but if a scar be the cause of the constriction of the prepuce, the Patient being placed in a convenient site, let the Prepuce be drawn forth and extended, and as much as may be stretched and enlarged, then let the scar be gently cut in three or four places on the inner side with a crooked Knife, but so, that the gashes come not to the outside, and let them be an equal distance each from other. But if a fleshly excrescence or a Wart shall be the occasion of this straitness and constriction, it shall be consumed by the same remedies, by which the Warts of the Womb and Yard are consumed or taken off. But when as the Prepuce doth closely adhere to the *Glans* on every side, the Cure is not to be hoped for, much less to be attempted.

CHAP. XXXIII.

Of those whose Glans *is not rightly perforated, and of the too short or strait ligament, bridle, or cord of the Yard.*

The Cause.

The Cure.

Some at their birth, by evil conformation, have not their *Glans* perforated in the middle, but have onely a small hole underneath, toward the bridle and ligament of the Yard, called the Cord. Which is the cause that they do not make water in a strait line, unless they turn up their Yard toward their belly, neither by the same reason can they beget children, because through this fault of conformation, the seed is hindred from being cast directly into the Womb. The Cure is altogether Chirurgical, and is thus performed. The Prepuce is taken hold of and extended with the left hand, but with the right hand, the extremity thereof, with the end of the *Glans*, is cut even to that hole which is underneath. But such as have the bridle or ligament of the Yard too short, so that the Yard cannot stand straight, but crooked, and as it were turned downwards; in these also the generation of children is hindred, because the seed cannot be cast directly and plentifully

tifully into the Womb. Therefore this ligament muſt be cut with much dexterity, and the wound cured after the manner of other wounds, having regard to the part.

Such as are born without a hole in their Fundament are not long-lived.

Children alſo are ſometimes born into the World with their fundaments unperforated, for a skin preternaturally covering the part, hinders the paſſage forth of the excrement; thoſe muſt have a paſſage made by Art with an Inſtrument, for ſo at length the excrements will come forth: yet I have found by experience, that ſuch Children are not naturally long-lived, neither to live many days after ſuch ſection.

CHAP. XXXIV.

Of the Cauſes of the Stone.

Why children are ſubject to the Stone in the Bladder.

THe Stones which are in the bladder have for the moſt part had their firſt original in the reins or kidnies, to wit, falling down from thence by the Ureters into the Bladder. The cauſe of theſe is two-fold, that is, material and efficient. Groſs, tough, and viſcid humours, which crudities produce by the diſtempers of the bowels and immoderate exerciſes, chiefly and immediately after meat, yield matter for the Stone; whence it is that children are more ſubject to this diſeaſe than thoſe of other Ages: But the efficient cauſe is either the immoderate heat of the kidnies, by means whereof the ſubtiler part of the humours is reſolved, but the groſſer and more earthly ſubſides, and is hardned as we ſee Bricks hardned by the Sun and Fire; or the more remiſs heat of the bladder, ſufficient to bake into a ſtone the *fæces* or dregs of the Urine gathered in great plenty in the capacity of the Bladder. The ſtraightneſs of the Ureters and urinary paſſage may be accounted as an aſſiſtant cauſe: For by this means the thinner portion of the Urine floweth forth, but that which is more feculent and muddy being ſtaid behind, groweth as by ſcale upon ſcale, by addition and collection of new matter into a ſtony maſs. And as a wick often times dipped by the Chandler into melted Tallow, by the copious adheſion of the tallowy ſubſtance preſently becomes a large Candle; ſo the more groſs and viſcid *fæces* of the Urine ſtay as it were at the barrs of the gathered gravel, and by their continual appulſe are at length wrought and faſhioned into a true ſtone.

The Cauſe.

CHAP. XXXV.

Of the Signs of the Stone in the Kidnies and Bladder.

Why the thigh is numb in the Stone of the Reins.

THe ſigns of the Stone in the Reins, are the ſubſiding of red or yellow Sand in the Urine, a certain obſcure itching at the Kidnies, and the ſenſe of a weight or heavineſs at the loins, a ſharp and pricking pain in moving or bending the body, a numbneſs of the thigh of the ſame ſide, by reaſon of the compreſſion cauſed by the ſtone, of the nerves deſcending out of the *Vertebræ* of the loins of the thigh. But when the ſtone is in the Bladder, the fundament and whole *perinæum* is preſſed as it were with a heavy weight, eſpecially if the ſtone be of any bigneſs, a troubleſom and pricking pain runs to the very end of the Yard, and there is a continual itching of that part, with a deſire to ſcratch it: hence alſo by the pain and heat there is a tenſion of the Yard, and a frequent and needleſs deſire to make water, and ſometimes their urine cometh from them drop by drop. A moſt grievous pain torments the Patient in making water, which he is forced to ſhew by ſtamping with his feet, bending of his whole body, and the grating of his teeth. He is oft-times ſo tormented with exceſs of pain, that the *Sphincter* being relaxed, the right gut falleth down, accompanied with the ſwelling heat and pain of the *Hemorrhoid* veins of that place. The cauſe of ſuch torment is the frequent ſtriving of the bladder to expel the ſtone wholly contrary to the nature thereof, whereto by ſympathy the expulſive faculty of the guts and all the parts of the belly come as it were for ſupply. The ſediment of the Urine is groſs and viſcid, and oft-times like the whites of Eggs, which argueth the weakneſs of the native heat not attenuating the juices. The Patient looketh of a pale and yellowiſh complexion and hollow-eyed, by reaſon of the almoſt continual watching which is cauſed by the bitterneſs of pain; yet may it more certainly be known by putting in or ſearching with a *Catheter*. Which to do, the Patient ſhall be wiſhed to ſtand with his body ſomewhat ſtooping, leaning againſt ſomewhat with his back, and holding his knees ſome foot aſunder. Then the *Catheter* being bigger or leſſer, as the body ſhall require, and anointed with oil or butter, ſhall be thruſt with a skilful hand into the paſſages of the Urine, and ſo into the capacity of the bladder. But if the *Catheter* cannot come to that capacity, the Patient ſhall be placed in ſuch a poſture; then ſhall he be laid upon his back on a bench, or the feet of a bed, with his knees bended, and his heels drawn to his buttocks, after which manner he muſt almoſt lie when he is to be cut for the ſtone, as ſhall be ſhewn hereafter. For thus the *Catheter* is more eaſily thruſt into the Bladder, and ſhews there is a ſtone by the meeting and obſcure ſound of the obvious, hard and reſiſting body. You muſt have ſundry *Catheters*, that they may ſerve for every body bigger and leſſer, and theſe muſt be crooked, ſmooth and hollow. When being thruſt into the urinary paſſage (which before unawares I omitted) they come to the neck of the bladder, they muſt not be thruſt ſtraight into the bladder; but taking hold of the Yard with the left hand, they muſt be gently thruſt with the right directly into the bladder, eſpecially in men, by reaſon of the length and crookedneſs of the way, which tends in the form of this letter *S*. It is not ſo in women by reaſon of the ſhortneſs and ſtraitneſs of the neck of the bladder. It is fit your *Catheters* be hollow or fiſtulous in manner of a pipe, that they may receive a ſilver Wiar or String, that may hinder the groſs and viſcid humour, clotted bloud, or the like, from ſtopping the further end of the *Catheter*, through which the ſuppreſſed Urine ought to paſs and be made. But now as ſoon as we perceive that the *Catheter* is come into the capacity of the bladder, the Wiar muſt be drawn forth, that ſo the Urine may the freelier flow out by the hollowneſs of the *Catheter*. You may perceive the ſhapes of theſe inſtruments by this following Figure.

Signs of the Stone in the Bladder.

Why ſuch as have a ſtone in the Bladder are troubled with the falling of the Fundament.

How to ſearch for the Stone in the Bladder with a *Catheter*.

The Figure of the neck of the Bladder is different in Men and Women.

The

The Figure of Catheters, *and of a ſilver String or Wiar.*



CHAP. XXXVI.

Prognoſticks in the Stone.

WHen the Stone is caſt forth of the Kidney (whereas it bred by little and little) and is ſo driven into one of the Ureters, that it wholly ſtop it, yet thereupon there followeth no ſuppreſſion of the Urine; for ſeeing Nature hath made divers parts of our body double, all the Urine floweth into the other Ureter: But if they ſhall be both ſtopped with ſtones, there is no doubt but the Urine will be wholly ſuppreſt, and death enſue by the ſuffocation and extinction of the native heat, by the Urine flowing back by the rivelets of the Veins over all the whole body. Such as have a ſmall ſtone caſt forth of their Reins into the cavity of the Ureters, until this ſtone be fallen into the Bladder, have cruel pain with gripings, with often deſire to go to ſtool and make water, but oft-times do neither; For ſuch oft-times have their bellies diſtended with flatulencies: an argument hereof is their continual belching or breaking of wind: But by ſneezing and coughing, or any other conceſſion of the whole body, a pricking pain is forthwith felt, whereas the ſtone ſtops, eſpecially if it be either rough, or have ſharp points like horns. This pain is communicated to the hip and thigh by ſympathy, and ſome have the ſtones drawn up as it were with great violence. To theſe may be added the Colick, cholerick vomiting, and almoſt a general ſweat. The ſtone in the Kidnies is moſt commonly bred in ſuch as are ancient, by reaſon of the weakneſs of the expulſive faculty: But the ſtone in the Bladder happeneth to ſuch as are more young, becauſe the native heat is more vigorous in ſuch, and ſtrong and inordinate motions increaſe the ſtrength of the expulſive faculty. When the ſtone is in the bladder, and the Urine appeareth bloudy, it is the ſign of a ſmall, as alſo a prickly and rough ſtone, for thus it more eaſily entereth into the neck of the bladder, and exulcerateth it being fleſhy, whence the bloud cometh away with the Urine, and moſt cruel pain, as of needles thruſt into the fleſh, eſpecially after labour and much exerciſe: on the contrary, a large and more ſmooth ſtone will not cauſe ſuch tormenting pain, and it cauſeth a milky water. The ſhapes of ſtones in the kidnies are various, according to the variety of the ſtrainers through which they paſs whileſt they are bred. Verily I have ſeen ſtones which repreſented the figure of Gray-hounds, Hogs, and other Creatures, and things wholly contrary to mans nature, by the production of their prickles, and as it were branches. Some are four-ſquare, others longiſh and like a finger, other-ſome of a round figure with many protuberancies like a Pine-apple kernel; neither is the variety leſs in magnitude, number, and colour; for ſome are yellowiſh, others whitiſh, red, aſh-coloured, or ſome other like, according to the various temper of the affected bodies. The ſtones of cholerick and lean men uſually concrete by preternatural heat and drineſs; but thoſe of phlegmatick or fat bodies, of a certain congelation as it were, and obſtruction of the paſſages. A ſtone falling ſometimes from the bottom of the bladder into the paſſages of the Urine quite ſtops it up, and thence followeth a total ſuppreſſing of the Urine. Therefore then the Patient ſhall be placed upon his back and his legs being lifted up on high, he ſhall be ſhaken and toſſed up and down juſt as one would ſhake up a ſack to fill it; for thus it is forced back into the Bladder from whence it came, from the paſſage of the Urine whereinto it was got, yet it may alſo be forced back by thruſting in a *Catheter*. The pain which afflicteth ſuch as have the ſtone is ſomewhiles continual, yet more frequently it cometh by fits and returns, ſometimes monethly, otherwhiles yearly. Such as have the ſtone in the Kidnies make for the moſt part wateriſh Urine. Women are not ſo ſubject to the Stone as men, for they have the neck of their bladder more ſhort and broad, as alſo more ſtraight; wherefore the matter of the Stone by reaſon of the ſhortneſs of the paſſage is evacuated in gravel, before it can be gathered and grow into a ſtone of a juſt magnitude; yet ſtones breed in ſome Women, and thoſe equally as big as in Men, and therefore they are to be cured by ſection and the like remedies. When the ſtone exceedeth the bigneſs of an Egg, it can ſcarce be taken away without tearing of the Bladder; whence happeneth an unvoluntary ſhedding of the Water, curable by no Art, becauſe the bladder, ſeeing it is nervous and without bloud,

How death may enſue by the ſuppreſſing of Urine.

Why ſtones of the Kidnies have ſundry ſhapes.

Why men are more ſubject to the ſtone then Women.

What ſtones cannot be taken out of the Bladder without killing the Patient.

bloud, being once torn admitteth no conſolidation: add hereto that inflammation and a gangrene often following the rending of the Bladder, brings inevitable death. The Patient runs the ſame hazard, if a long ſtone be pulled out ſidewiſe with your Inſtrument, or if it be incloſed in a membrane (which kind of ſtone can ſcarce be found with a Catheter) and ſo be faſtned to the Bladder, or otherwiſe if the ſtone it ſelf be faſtned into the ſubſtance of the Bladder; or laſtly, if by any chance the Surgeon being about to pluck out the ſtone, ſhall hurt the body of the Bladder with his Inſtruments. Yet ſtones of a more indifferent bigneſs are more ſafely extracted out of the Bladder then thoſe which are leſs, and the Patient more frequently and happily recovereth; For they do not ſcape from the Inſtrument, and the Patient being uſed a long while to endure pain, as that which hath been a long time a growing, doth more eaſily and conſtantly away with the inflammation, pain and other ſymptoms which happen after cutting, yea in cutting. Having thus ſpoken of the Cauſes, Signs, Places, Symptoms, and Prognoſticks, we muſt come to the Cure, beginning with that part which is termed *Prophylactice*, that is the preventing part.

CHAP. XXXVII.

What Cure is to be uſed when we fear the Stone.

What Diet ſuch muſt uſe as fear the Stone.

Diet muſt firſt be appointed, which by the convenient uſe of the ſix things Not Natural (as they term them) may heap up ſmall ſtore of groſs, tough and viſcid humours in our bodies. Therefore cold and cloudy air is to be ſhunned. They muſt abſtain from Fiſh, Beef, Pork, Water-fowl, Pulſe, Cheeſe, Milk-meats, fried and hard Egs, Rice, Cakes and all Paſtry, unleavened Bread, and laſtly, all manner of obſtructing meats. Alſo Garlick, Onions, Leeks, Muſtard, Spices, and laſtly, all things which over-heat the bloud and humours muſt be ſhunned, eſpecially if you fear that the ſtone is concrete by the heat of the reins. Standing and muddy Waters, thick, and troubled Wines, Beer, and ſuch kind of Liquors muſt be eſchewed. Satiety in meats and drinks is to be ſhunned, as that which breeds crudities. Alſo long watching and continual labour becauſe they inflame the bloud, cauſe crudities and preternatural heat, muſt carefully be eſchewed, as alſo more vehement paſſions of the mind. If the body be plethorick, then it muſt be evacuated by Phlebotomy, Purging, and Vomiting, which is accounted for a ſingular remedy for the prevention of this diſeaſe. For the performance of all which things a Phyſician ſhall be conſulted with. But becauſe Phyſicians are not in every place and always at hand, I have thought good to ſet down theſe following Medicins; yet we muſt firſt remember this Counſel of *Galen*; the uſe of Diureticks and ſtrong purging Medicins is hurtful, as often as there is inflammation in the reins and bladder, for ſo the conflux of the humours to the affected parts is the greater, whence the inflammation and pain are increaſed.

*Lib.*13.*Method.*

Wherefore firſt uſing relaxing Medicins, as ſix drams of *Caſſia* newly drawn, with ℈ iv. of *Rubarb* in Powder mixed therewith, then lenitive and refrigerating Medicins ſhall be inwardly and outwardly uſed, ſuch as is this following ſyrup. ℞ *Summitatum malv. biſmal. & violar. an.* m. ß. *rad. alth.* ʒ j. *glycyr.* ʒ ß. 4. *ſem. frigid. major. an.* ʒ j. *fiat decoctio.* ℞ *prædict. decoctionis* ℔ ß. *in colatura diſſolv. ſacc. albiſſ.* ʒ ij. *mellis albi* ʒ j. ß. *fiat ſyrupus ſecund. artem*; let the Patient uſe this often. This following Apozeme is alſo very effectual for the ſame purpoſe. ℞ *Rad. aſpar. gramin. polyp. quercini, paſſul. mund. an.* ʒ ß. *betonic. herniar. ægrimon. omnium capill. & pimpinel. an.* m. ß. 4. *ſem. frigid. major. & ſem. fœnic. an.* ʒ j. *folior. ſen.* ʒ vj. *fiat decoct. ad* ℔ ß, *in colatura diſſolve ſyrupi de Althæa & de herniar. an.* ʒ j. ß. Make a clear Apozeme and let it be aromatized with a little Cinnamon, for two doſes; let him take the firſt doſis in the morning two hours before meat, and the other at four of the clock in the afternoon. Moreover this following broth hath an excellent and certain power to prevent the ſtone. ℞ *Hordei integr.* p. j. *radic. petroſelini, acetoſ. fœnic. cichor. bruſci an.* ʒ j. 4. *ſem. frigidorum conquaſſatorum an.* ʒ ß. *fol. acetoſ. portul. lactucæ, ſummitatum malvæ, & violar. an.* m. ß. *bulliant in aqua fluviatili cum gallo gallinaceo & crure vitulino*; let the broth be kept, and let the Patient take thereof ſix ounces for four days, in the morning two hours before meat, with an ounce of the juice of Citrons gently warmed with the ſame broth at the taking thereof: for thus, much urine will be made in a ſhort while after, full of a ſandy ſediment and a groſs viſcid humor. Whereby you may certainly gather, that this kind of broth is very effectual to cleanſe the paſſages of the Urine, neither in the interim doth it any harm to the ſtomach and other parts by which it paſſeth: ſo that it may be rightly termed a Medicinal nouriſhment. You may alſo profitably uſe this following Powder. ℞ *Nucleorum meſpilorum* ʒ j. *pul. elect. diamarg. frig.* ʒ ij. 4. *ſem. frig. major. mund. glycyrrhizæ razæ,* ʒ j. *ſem. ſaxifrag.* ʒ ij. ℈. *ſem. milii ſolis geniſt. pimpin. bruſci & aſparag. an.* ℈ j. *ſem. altheæ,* ʒ ß. *ſacch. albiſſ.* ʒ vj. *fiat pulvis*; let him take a ſpoonful in the morning three hours before meat. Alſo ſome think that Lee made of the ſtalks and huſks of Beans is a good preſervative againſt this Diſeaſe. Beſides the uſe of this following Clyſter hath done good to many. ℞ *Fol. lactuc. ſcariol. portul. an.* m. j. *flor. viol. & nenuph. an.* p. j. *fiat decoctio ad* ℔ j. *in colatura diſſolve caſſiæ fiſtulæ* ʒ i. *mellis viol. & ſacc. rub. an.* ʒ j. ß. *olei viol.* ʒ iv. *fiat clyſter.* This which followeth is the fitter to aſſwage the pain. ℞ *Flor. cham. melil. ſummitat. aneth. berul. an.* p. ij. *fiat decoctio in lacte vaccino, in colatura diſſolve caſſiæ fiſtul. & ſaccar. alb. an.* ʒ j. *vitellos ovorum num.* ij. *olei anethini, & chamæm. an.* ʒ ij. *fiat clyſter.* In the interim let the Kidnies be anointed on the outſide with *unguentum roſatum, refrigerans Galeni* and *populeon* uſed ſeverally or mixed together, laying a double linnen cloth dipped in oxycrate. But if the concretion of the ſtone be of a cold cauſe, the remedies muſt be varied, as follows: ℞ *Terebinth. venet.* ʒ j. *cort. citri.* ʒ ij. *aquæ coct.* ʒ ij. *fiat potio.* Or elſe, ℞ *Caſſiæ recent. extract.* ʒ vj. *benedict. lax.* ʒ iij. *aq. fœnic.* ʒ ij. *aq. aſparag.* ʒ j. *fiat potio*; let him take it three hours before dinner. This following Apozeme is alſo good. ℞ *Rad. cepet. bardan. & gram. an.* ʒ iij. *biſmal. cum toto, beton. an.* m. ℈. *ſem. milii ſolis bard. utrio an.* ʒ ij. *ſem. melon. glycyrrhiz. raſ. an.* ʒ ij. ß. *ficus num.* 4. *fiat decoct. ad quart.* iij. *in expreſſa colatura, diſſolve ſyrup. de raphan. & oxymelitis ſcyllitici an.* ʒ j. ℈. *ſacchar. albiſſ.* ʒ iv. *fiat*

A lenitive and lubricating ſyrup.

A Diuretick Apozeme.

A Diuretick and Lenitive Broth.

A Diuretick Powder.

The lee made of the aſhes of Bean-ſtalks a Diuretick.

Anodyne Clyſters in the Stone.

Remedies againſt the Stone of the Kidnies coming from a cold cauſe.

fiat apozema pro tribus dosibus, clarificetur & aromatiz. cum ʒ j. *cinam. &* ʒ ß. *sant. citrin.* let him take four ounces three hours before dinner. ℞ *Rad. petrosel. fœnicul. an.* ℥ j. *saxifrag. pimp. gram. & bardan. an.* m. ß. *quatuor seminum frig. major mundat. & milii solis an.* ʒ ij. *fiat decoctio. cape de colatura* ℔ ß. *in qua dissolve sacch. rub. & syrup. capill. ven. an.* ℥ j. ß. Let it be taken at three doses, two hours before meat. The following Powder is very effectual to dissolve the matter of the Stone. ℞ *Sem. petrosel. & rad. ejusdem mundat. an.* ℥ ß. *sem. cardui, quem colcitrapam vocant,* ℥ j. let them be dried in an Oven or Stone, with a gentle fire, afterwards let them be beaten severally and make a Powder, whereof let the Patient take ϑ j. ß. or two scruples with white Wine, or Chicken-broth fasting in the morning by the space of three days. Or, ℞ *Coriand. præp.* ϑ iv. *anis. marathri, granor. alkekengi, milii solis, an.* ʒ ij. *zinzib. & cinam. an.* ϑ ij. *turbith. electi* ʒ j. *cari* ϑ ij. *galang. nucis moschat. & lapid. judiaci, an.* ϑ j. *fol. sennæ mund. ad duplum omnium, diacrydii* ʒ ij. ß. *misce, fiat pulvis:* the dosis is about ʒ j. with white Wine three hours before meat. Against the flatulencies which much distend the guts in this kind of Disease, Clysters shall be thus made; ℞ *Malv. bismal. pariet. origani, calament. flor. chamæm. summitat. anethi, an.* m. ß. *anisi, carui, cumini, fœnic. an.* ℥ ß. *baccar. laur.* ʒ iij. *sem. rutæ* ʒ ij. *fiat decoctio, in colatura, dissolve bened. lax. vel diaphœnic.* ℥ ß. *confect. hac. lauri* ʒ iij. *sacchar. rub.* ℥ j. *olei aneth. chamæm. & rutæ. an.* ℥ j. *fiat clyster.* Or ℞ *Olei nucum & vini mal. an.* ℔ ß. *aq. vitæ* ℥ ß. *fiat clyster*; let it be kept long, that so it may have the more power to discuss the wind.

Carminative Clysters.

CHAP. XXXVIII.

What is to be done when the stone falleth out of the Kidnies into the Ureter.

OFt-times it falleth out that the reins using their expulsive faculty, force down the stone (whose concretion and generation the Physicians by the formerly prescribed means could not hinder) from themselves into the Ureters; but it stayeth there either by reason of the straightness of the place, or the debility of the expulsive faculty. Therefore then cruel pain tormenteth the Patient in that place whereas the stone sticketh, which also by consent may be communicated to the Hip, Bladder, Testicles, and Yard, with a continual desire to make Water and go to Stool. In this case it behoveth the Physician that he supply the defect of Nature, and assist the weak endeavours.

Signs of the stone stopping in the ureter.

Therefore let the Patient, if he be able, mount upon a trotting Horse, and ride upon him the space of some two miles, or if he can have no opportunity to do so, then let him run up and down a pair of stairs, until he be weary, and even sweat again; for the stone by this exercise is oft-times shaken into the Bladder; then presently shall be given or taken by the mouth such things as have a lenitive and relaxing faculty, as Oil of Sweet Almonds newly drawn, and that without fire, and mixed with the Water of Pellitory of the Wall and White Wine. Let frictions of the whole body be made from above downwards with hot cloths; let Ventoses with a great flame be applied one while to the loins, and another while to the bottom of the belly, a little below the grieved place; and unless the Patient vomit of his own accord, or by the bitterness of his pain, let vomiting be procured with a draught of Water and Oil luke-warm; for vomiting hath much force to drive down the stone by reason of the compression of the parts, which is caused by such an endeavour. Lastly, if the stone descend not by the power of these remedies, then the Patient must be put into a *Semicupium*, that is, a Half-bath, made of the following decoction. ℞ *Malvæ, bismal. cum toto an.* m. ij. *beton. nasturt. saxifrag. berul. parietar. violar. an.* m. iij. *sem. melonum, milii solis, alkekengi an.* ʒ vj. *cicer. rub.* ℔ j. *rad. apii. gram. fœniculi, & eringii. an.* ℥ iv. *in sufficienti quantitate aquæ pro incessu; coquantur ista omnia inclusa sacco:* herein let the Patient sit up to the Navel, neither is it fit that the Patient tarry longer in such a bath than is requisite, for the spirits are dissipated, and the powers resolved by too long stay therein. But on the contrary, if the Patient remain as long as is sufficient in these rightly made, the pain is mitigated, the extended parts relaxed, and the passages of the Urine opened and dilated, and thus the stone descendeth into the bladder. But if it be not moved by this means any thing at all out of the place, and that the same total suppression of Urin does as yet remain, neither before the Patient entered into the bath the putting of a *Catheter* into the bladder did any thing avail, yet notwithstanding he shall try the same again after the Patient is come out of the bath, that he may be throughly satisfied whether peradventure there may be any other thing in these first passages of the yard and neck of the bladder, which may with-hold the Urine; for the *Catheter* will enter far more easily, the parts being relaxed by the warmness of the bath: then inject some Oil of Sweet Almonds with a Syringe into the *Urethra* or passage of the yard; whilest all these things are in doing, let not the Patient come into the cold air. But I have thought good to describe a Chair for a Bath, wherein the Patient may fitly sit, as you may see in the following Figure.

Remedies to force down the stone sticking in the ureter.

A Decoction for a Bath.

There may also be another decoction made for the bath, as thus: ℞ *Rad. raph. alth. an.* ℔ ij. *rad. ruse. petrosel. & asparag. an.* ℔ j. *cumin. fœnicul. ameos an.* ℥ iv. *sem. lini, fœnug. an.* ʒ vj. *fol. marrub. parietar. florum chamæm. melil. anethi, an.* m. ij. *bulliant omnia secundum artem in aquæ sufficienti, & vini albi odoriferi exigua quantitate ad consumptionem tertiæ partis pro Semicupio.* Also the same decoction may be used for Clysters, adding thereto two yolks of Egs, and four ounces of Oil of Lillies, with ʒ j. of Oil of Juniper, which hath a certain force to assuage the pain of the Stone and Collick. But a far less quantity of the decoction in a Clyster must be used in these diseases, than usually is appointed in other diseases; otherwise there will be danger lest the guts being distended, should more press upon the kidnies and ureters, troubled in some sort with inflammation, and so increase the pain and other symtoms. This following Cataplasm shall be profitably applied to the grieved place, to wit, the loins, or flanks, and bottom of the belly, for it is very powerful to assuage pain, and help forwards the falling down of the stone. ℞ *Rad. alth. & raphani, an.* ʒ iv. *pariet. fœnic. senecionis, nasturt. berul. an.* m. j. *herniariæ* m. ß. *omnibus in aqua sufficienti decoctis, & deinde contritis, adde olei aneth. chamæm. & pingued. cuniculi,*

An anodyne Cataplasm.

Signs of the Stone fallen out of the ureters into the bladder.

cuniculi, an. ℥ ij. *farin. cicer. quantum ſufficit, fiat cataplaſma ad uſum prædictum.* After, by theſe means, the ſtone forced out of the ureter is fallen into the bladder, the pain preſently (if there be but one ſtone, for ſometimes more with much gravel do again fall into the ureter) is mitigated, and then the Patient is troubled with an itching and pricking at the end of his Yard and Fundament. Therefore then unleſs he be very weak, it is fit that he ride and walk afoot, and take ʒ iv. of *ſpecies Lithontribon* in four doſes with white Wine, or the broth of red Cicers three hours before dinner and ſupper. Beſides, let him plentifully drink good Wine, and after he hath drunk, let him hold in his Urin as long as he can; that ſo it being gathered in great plenty, it may preſently thruſt the ſtone out of the bladder with the more force: for which purpoſe you may alſo inject the following liquor into the bladder. ℞ *Syrupi capill. ven.* ʒ j. *aquæ alkekengi* ʒ iij. *oleo ſcorpionum* ʒ β. Let it be injected into the bladder with a ſyringe.

The Figure of a Chair for a Semicupium.

A *Sheweth the whole frame of the Chair.*
B *The hole wherein the Patient muſt ſit.*
C *The Ciſtern that holds the Water.*
D *A Cock to empty the Water when it groweth cold.*
E *A Funnel whereby to pour in warm water.*

CHAP. XXXIX.

What muſt be done to the Stone being fallen into the neck of the Bladder, or paſſage of the Yard.

After the ſtone is fallen out of the capacity of the Bladder, and ſtops in the neck thereof, or paſſage of the Yard, the Surgeon ſhall have a ſpecial care that he do not force or thruſt back the ſtone from whence it came, but rather that he preſs it gently with his fingers to the end of the Yard, the paſſage being firſt made ſlippery by injecting ſome Oil of Sweet Almonds. But if it ſtop in the end of the *Glans*, it muſt be plucked out with ſome crooked inſtrument; to which if it will not yield a Gimblet with a Pipe or caſe thereto, ſhall be put into the paſſage of the Yard, and ſo it ſhall be gotten out, or elſe broken to pieces by the turning or twining about of the Gimblet, which I remember I have divers times attempted and done; for ſuch Gimblets are made with ſharp Screws, like ordinary Gimblets.

The delineation of a Gimblet made to break the ſtones in the paſſage of the Yard, together with its Pipe, or Caſe.



CHAP.

The effigies of another lesser Gimblet.



Verily what Gimblets soever are made for this business, their body or point must be no thicker than a small *Probe*; lest whilest they are forced or thrust into the *Urethra*, or urinary passage, they might hurt the bodies next unto them by their violent entrance.

CHAP. XL.

What course must be taken, if the stone sticking in the Urethra, *or urinary passage, cannot be gotten out by the fore-mentioned Arts.*

BUt if the stone be more thick, hard, rough and remote from the end of the Yard, than that it may be gotten out by the means formerly mentioned in the precedent Chapter, and if that the urin be wholly suppresst therewith; then must you cut the Yard upon the side with a straight wound: for you must not make incision on the upper part, for fear of a flux of bloud, for a large vein and artery lieth thereunder; nor in the lower part, for so it would scarce ever heal again, for that it is a bloudless part, and besides, the continual and acrid falling of the urine would hinder the agglutination: wherefore the incision must be made on the side, on that part whereas the stone most resists and swells out. For that part is the more fleshy; yet first the end of the skin of the prepuce must be much drawn up so to cover the *Glans*, which being done, the *Urethra* shall be tied with thred a little above the stone, that so the stone may be staid there, and may not fall back again. Therefore then, incision being made, the stone must be taken forth, and the skin which was drawn more violently to cover the *Glans*, is to be let go back again; for so it will come to pass that a whole part of the skin may cover the cut Yard, and so it may be the more speedily united, and the urin may naturally flow out. I have by this means oft-times taken forth the stone with the instruments here delineated.

When the Yard may be safely cut.

Instruments fit to take the stone forth of the opened Urethra, *or urinary passage of the Yard.*



Then for the agglutination, if need require, it will be requisit to sew up the lips of the wound, and apply this agglutinative Medicin following. ℞ *Tereb. venet.* ℥ iv. *gum. elemi*, ℥ j. *sang. dracon. & mastic. an.* ʒ ß. *fiat medicamentum ut dictum est:* then the whole Yard must be covered over with a repercussive Medicin made of the whites of Eggs, with the Powder of Bole Armenick, Aloes, *farina volatilis*, and Oil of Roses. Lastly if need so require, a Wax-candle, or Leaden string anointed with Venice Turpentine shall be thrust into the *Urethra*, to hasten the agglutination, and retain the natural smoothness and straightness of the urinary passage, lest peradventure a caruncle grow therein.

An agglutinative medicin.

How to hasten the agglutination.

CHAP. XLI.

What manner of Section is to be made when a stone is in a Boys Bladder.

HItherto we have shewed, by what means it is convenient to draw small stones out of the Ureter, Bladder, and passage of the urin; now will we briefly shew the manner of taking of greater stones out of the bladder, which is performed by incision and iron instruments, and I will deliver the practice thereof first in children, then in men, and lastly in women. First therefore let the Surgeon take the Boy (upon whom it is determined the work shall be performed) under the arm-holes, and so give him five or six shakes, that so the stone may descend the more downwards to the neck of the bladder. Then must you cause a strong man, sitting upon an high seat, to lay the child upon his back with his face from him-ward, having his hips lying upon his knees. The child must lie somewhat high, that he may breath the freelier, and let not the nervous part be too much stretched, but let all parts be loose and free for the drawing forth of the stone. Furthermore, it is fit that this strong man, the childs legs being bended back, wish the child, that putting his legs to his hams, that he draw them up as much as he can, and let the other be sure he keep them so; for this site of the child much conduceth to well performing of the work. Then let the Surgeon thrust two of the fingers of his left hand as far into the childs Fundament as he is able; but

Why the Boy must be shaken before cutting.

How to place the child before dissection.

let him with his other hand preſs the lower belly, firſt wrapping a cloth about his hand, that ſo the compreſſion may be the leſs troubleſom, and leſt inflammation ſhould happen rather by this means than by the inciſion. Now the compreſſion hath this uſe, to cauſe the ſtone to deſcend out of the bottom of the Bladder into the neck thereof under the *os pubis*, whither after it is arrived, it muſt be there kept, and as it were governed by the command of your hand, leſt it ſhould ſlide from that place whereto you have brought it. Theſe things thus done, nothing now remaineth, but that the Surgeon, with a wound ſome two fingers bredth diſtant from the Fundament, cut through all the fleſh even to the ſtone on the left ſide of the *Perinæum*. But in the *interim*, let him beware that he hurt not the *inteſtinum rectum*; for it may, and uſually doth happen, that whileſt the ſtone is brought out of the bottom of the bladder to the neck thereof, this gut is doubled in: now if it be cut with your inciſion-knife, it cometh to paſs that the excrements may ſometimes come out at the wound, and the urin by the fundament, which thing hath in many hindred the agglutination and conſolidation of the wound; yet in ſome others it hath done little harm, becauſe in this tender age many things happen which may ſeem to exceed Nature: the inciſion being made, the ſtone muſt be plucked forth with the inſtrument here expreſſed.

Where to divide the *perinæum*.

Nature very powerful in children.

Hooks to pull ſtones forth of Childrens Bladders.

The ſtone being drawn out, a ſmall pipe ſhall be put into the wound, and there kept for ſome ſpace after, for reaſons hereafter to be delivered; then his knees ſhall be bound together, for thus the wound will the ſooner cloſe and be agglutinated. The reſidue of the Cure ſhall be performed by reducing the general Cure of Wounds to the particular temper of the childs age, and the peculiar nature of the child in cure.

General Rules muſt be reduced to particular bodies.

CHAP. LII.

How to cut men for the taking out of the Stone in the Bladder.

What to be done before diſſection.

SEeing we cannot otherwiſe help ſuch men as have ſtones in their Bladders, we muſt come to the extreme remedy, to wit, Cutting. But the Patient muſt firſt be purged, and if the caſe require, draw ſome bloud; yet muſt you not immediately after this, or the day following haſten to the work: for the Patient cannot but be weakned by purging and bleeding. Alſo it is expedient for ſome days before to foment the Privities with ſuch things as relax and ſoften, that by their yielding, the ſtone may the more eaſily be extracted. Now the Cure is thus to be performed. The Patient ſhall be placed upon a firm Table or Bench with a cloth many times doubled under his buttocks, and a Pillow under his loins and back, ſo that he may lie half upright with his thighs lifted up, and his legs and heels drawn back to his buttocks. Then ſhall his feet be bound with a ligature of three fingers bredth caſt about his ankles, and with the heads thereof being drawn upwards to his neck, and caſt about it, and ſo brought downwards, both his hands ſhall be bound to his knees, as the following figure ſheweth.

How to lay the Patient.

The Figure of a man lying ready to be cut of the Stone.

The Patient thus bound, it is fit you have four ſtrong men at hand; that is, two to hold his arms, and other two who may ſo firmly and ſtraightly hold the knee with one hand and the foot with the other, that he may neither move his limbs, nor ſtir his buttocks, but be forced to keep in the ſame poſture with his whole body. Then the Surgeon ſhall thruſt into the urinary paſſage even to the bladder a ſilver or iron and hollow Probe anointed with Oil, and opened or ſlit on the outſide, that the point of the knife may enter thereinto, and that it may guide the hand of the Workman, and keep the knife from piercing any further into the bodies lying there-under. The Figure of this Probe is here expreſt.

Why the Probe muſt be ſlit on the outſide.

Probes

Probes with ſlits in their ends.

He ſhall gently wreſt the Probe, being ſo thruſt in, towards the left ſide, and alſo he who ſtandeth on the Patients right hand, ſhall with his left hand gently lift up his cods, that ſo in the free and open ſpace of the left ſide of the *Perinæum*, the Surgeon may have the more liberty to make the inciſion upon the Probe, which is thruſt in and turned that way. But in making this inciſion, the Surgeon muſt be careful that he hurt not the ſeam of the *Perinæum* and Fundament. For if that ſeam be cut, it will not be eaſily conſolidated, for that it is callous and bloudleſs, therefore the urin would continually drop forth this way. But if the wound be made too near the Fundament, there is danger leſt by forcible plucking forth of the ſtone he may break ſome of the hæmorrhoid veins, whence a bleeding may enſue, which is ſcarce to be ſtopped by any means, or that he may rend the ſphincter muſcle, or body of the bladder, ſo that it never can be repaired. Therefore it muſt be made the ſpace of two fingers from the fundament, according to the ſtraightneſs of the fibres, that ſo it may be the more eaſily reſtored afterwards. Neither muſt the inciſion thus made, exceed the bigneſs of ones thumb, for that it is afterwards enlarged by putting in the Crows-beak and the Dilater, but more by the ſtone as it is plucked forth. But that which is cut, is neither ſo ſpeedily nor eaſily healed up as that which is torn. Then preſently put into the wound ſome one of theſe ſilver inſtruments delineated here below, and called by the name of *Guiders*, for that they ſerve as guides to the other inſtruments which are to be put into the bladder; theſe are made with a round and prominent head, whereby it may be put into the deſcribed cavity of the Probe, and they are noted by theſe letters *A A*, then there are others marked with the letters *B B*, and called by the like name, and are to be put under the former, being made forked at the end, that ſo it may, as it were, embrace the end of the former.

Why the ſeam of the *Perinæum* muſt not be cut.

Where to make the wound to take forth the ſtone.

That which is torn ſooner healeth than that which is cut.

The Figures of Guiders of two ſorts.



Now the Probe is to be drawn forth, and the Guiders to be thruſt and turned up and down in the bladder, and at length to be ſtaid there by putting in the pin; yet ſuch Guiders as want a Pin are fitter for the hand, and are by ſome called *ſpathæ*. Then muſt they be held betwixt the Surgeons fingers. It will be alſo neceſſary for the Surgeon to put another inſtrument called the Ducks-bill between the two guiders into the capacity of the bladder; he muſt thruſt it in ſomewhat violently, and dilate it ſo thruſt in with both his hands, turning it every way to enlarge the wound as much as ſhall be ſufficient for the admitting the other inſtruments which are to be put into the bladder; yet it is far better for the Patient, if that the wound may with this one inſtrument be ſufficiently dilated, and the ſtone pulled forth with the ſame without the help of any other.

The effigies of an Inſtrument called a Ducks-bill.



Which if you have not in readineſs, and the largeneſs of the ſtone require more dilatation, then muſt you put in this dilater; for being put into the bladder, and the handle preſſed together, it will dilate the inciſion as much as you deſire.

The Figure of a Dilater ſhut and opened.



The wound by the help of this Inſtrument being dilated as much as is ſufficient, then put in the ſtraight Ducks-bill before deſcribed, or the crooked here expreſt.

Crooked Forcipes *like a Ducks-bill.*



The ſtone may be ſought and taken hold of with theſe Inſtruments, and being taken hold on, the branches of the Inſtrument ſhall be tied together, leſt they ſhould ſuffer that to ſlide away which

which they have once taken hold of. Neither ſhall the ſtone be ſuddenly plucked out, but eaſily ſhaken to and again, and at length gently drawn forth. Yet you muſt beware that you do not preſs it too ſtraitly in the *forceps*, leſt you ſhould break it in pieces: Some, leſt it ſhould ſlip away, when they have once taken hold thereof, put their two fingers into the Fundament, and put them about the ſtone that it may not fall out, nor ſlip back again, which I think conduceth much to the eaſie extraction of the ſtone. There are others who ſtrengthen this comprehenſion by putting in on each ſide above and below theſe winged inſtruments, ſo that the ſtone can ſlip forth on no ſide.

Winged Inſtruments to hold the ſtone with the Ducks-beak.



The Figure of another.



The Figure of another winged Inſtrument, the end of whoſe handle is faſtned by a ſcrue, as alſo a bended iron plate, which is marked with this letter A, *for the firmer holding thereof.*



After the ſtone is by this means drawn forth, obſerve diligently whether it be worn on any ſide, and as it were levigated; for that happeneth by the wearing or rubbing of one or more ſtones upon it; yet there is no ſurer way to know this, than by ſearching with a Catheter. The one end of the following Inſtrument may ſupply the want of a Catheter or Probe, and the other may ſerve for a ſcoop or cleanſer. A note of more ſtones than one.

A Cleanſer or Scoop whereby you may ſearch whether there be any more ſtones behind, as alſo cleanſe or purge the bladder from gravel, clots of bloud, and other ſuch bodies as uſe to remain behind after the drawing forth of the ſtone.



How to cleanſe the bladder.

For if other ſtones remain behind, they ſhall be drawn forth as the former, which being done, the end of the Inſtrument, which is crooked and hollowed like a ſcoop or ſpoon, ſhall be thruſt by the wound into the bladder, and therewith you ſhall gather together and take out what gravel ſoever, clotted bloud, and the like refuſe as ſhall be there, for that they may yield matter for another ſtone.

How to break a ſtone that cannot be taken out whole and at once.

But if you find that the ſtone which is in the bladder be too great, ſo that it may not be plucked forth without great and fearful rending of the bladder, as it will be better to take hold thereof with this Crows bill, and ſo break it to pieces.

The effigies of a toothed Crows-bill made neatly to break greater ſtones, with a Screw to force it together.



This Crows-bill hath onely three teeth, and thoſe ſharp ones on the inſide, of which two are placed above, and one below, which is the middlemoſt, ſo that it falleth between the two upper. When the ſtone is broken, all the pieces thereof muſt be taken forth, and we muſt have a ſpecial care, leſt any piece thereof lie hid, for that in time, increaſed by the acceſs of a tough and viſcous matter, or conjoined with other fragments by the interpoſition of the like matter as glew, may riſe to a ſtone of a large bigneſs.

CHAP. XLIII.

What cure muſt be uſed to the wound, when the ſtone is taken forth.

Of ſewing the wound when the ſtone is taken forth.

THe ſtone being drawn out, if the greatneſs of the wound ſo require, it ſhall have one or two ſtitches with a needle and thred, leaving onely ſo much ſpace as ſhall be ſufficient to put in a pipe for the uſe we ſhall hereafter ſhew; your thred muſt be of crimſon ſilk waxed, and let it not be too ſmall, leſt it by binding ſhould cut aſunder the fleſhy lips of the wound, or rot in a ſhort time, either by the moiſture of the Urin, or matter flowing from the Ulcer. Therefore you ſhall take up much fleſh with the skin in ſewing it, leſt the lips of the wound being torn, your labour prove in vain, and ſo you are forced to trouble the Patient with making a new one. Things being thus performed, a ſilver pipe ſhall be put through the wound into the bladder, whereof I have here given you divers forms, that you may take your choice, and ſo fit them to the wounds, and not the wounds to them, which oft-times in want of inſtruments the Surgeons are forced to do, to the great harm of the Patient.

Silver

Silver Pipes to be put in the Bladder when the ſtone is drawn out.



Theſe muſt have no holes in their ſides (as thoſe here expreſſed) but onely in their ends, that all the matter of the wound, and the filth gathered and concrete in the bladder may flow and be carried forth this way. When clear Urine ſhall begin to flow out of the wound, there ſhall be no more need of a Pipe; therefore if you continue it and keep it longer in the wound, there is ſome danger leſt Nature accuſtomed to that way, may afterwards neglect to ſend the Water through the *Urethra*, or urinary paſſage. Neither muſt you forget to defend the parts near to the wound with the following repercuſſive Medicin, to hinder the defluxion and inflammation, which are incident by reaſon of the pain. ℞ *Album. ovorum, nu.* iij. *pul. boli armeni, ſanguinis dracon. an.* ʒ iij. *olei roſ.* ʒ j. *pilorum leporinum quantum ſufficit:* make a Medicin of the conſiſtence of honey. A repercuſſive Medicin.

CHAP. XLIV.

How to lay the Patient after the Stone is taken away.

ALl things which we have recited, being faithfully and diligently performed, the Patient ſhall be placed in his bed, laying under him as it were a pillow filled with Bran, or Oat Chaff, to drink up the Urin which floweth from him. You muſt have divers of theſe pillows, that they may be changed as need ſhall require. Sometimes after drawing forth of the ſtone, the bloud in great quantity falleth into the Cod, which unleſs you be careful to provide againſt, with diſcuſſing, drying and conſuming Medicins, it is to be feared that it may gangrenate. Wherefore if any accident happen in curing theſe kind of Wounds, you muſt diligently withſtand them. After ſome few days a warm injection ſhall be caſt into the Bladder by the wound, conſiſting of the Waters of Plantain, Night-ſhade, and Roſes, with a little Syrup of dried Roſes. It will help to temper the heat of the Bladder cauſed both by the wound and contuſion, as alſo by the violent thruſting in of the Inſtruments. Alſo it ſometimes happens, that after the drawing forth of the ſtone, clots of bloud and other impurity may fall into the urinary paſſage, and ſo ſtop the Urin that it cannot flow forth. Therefore you muſt in like ſort put a hollow Probe for ſome days into the *Urethra*, that keeping the paſſage open, all the groſſer filth may flow out together with the Urin. Remedies for the Cod, leſt it gangrenate.

CHAP. XLV.

How to cure the Wound made by Inciſion.

YOu muſt cure this wound after the manner of other bloudy wounds, to wit, by agglutination and cicatrization, the filth, or ſuch things as may hinder, being taken away by detergent Medicins. The Patient ſhall haſten the agglutination if he lie croſs-legged, and keep a ſlender diet until the ſeventh or nineth day be paſt. He muſt wholly abſtain from Wine, unleſs it be very weak; in ſtead thereof let him uſe a decoction of Barley and Licoriſh, or Mead, or Water and Sugar, or boiled Water mixed with Syrups of dried Roſes, Maiden-hair, and the like. Let his Meat be Panado, Raiſins, ſtewed Prunes, Chickens boiled with the cold Seeds, Purſlain, Sorrel, Borage, Spinage, and the like. If he be bound in his belly, a Phyſician ſhall be called, who may help it, by appointing either *Caſſia*, a Clyſter, or ſome other kind of Medicins as he ſhall think good. What things haſten the union.

CHAP. XLVI.

What cure is to be uſed to Ulcers, when as the Urine flows through them, long after the ſtone is drawn out.

MAny after the ſtone is drawn out, cannot have the Ulcer conſolidated, therefore the Urin flows out this way continually by little and little, and againſt the Patients will during the reſt of his life, unleſs the Surgeon help it. Therefore the callous lips of the wound muſt be amputated, ſo to make a green wound of an old ulcer; then muſt they be tied and bound with the inſtrument we term a *Retinaculum* or ſtay; this muſt be perforated with three holes, anſwering to three other on the other ſide; Needles ſhall be thruſt through theſe holes, taking hold of much fleſh, and ſhall be knit about it, then glutinative Medicins ſhall be applied, ſuch as are Venice Turpentine, Gum *Elemi*, *Sanguis draconis*, Bole Armenick, and the like; after five or ſix days the Needles ſhall be taken out and alſo the ſtay taken away. For then you ſhall find the Wound almoſt glewed, and there will nothing remain but onely to cicatrize it. How to make a freſh wound of an old ulcer.

The

The Figure of a Retinaculum, *or Stay.*



A *Shews the greater.* B *The leſſer, that you may know that you muſt uſe divers according to the different bigneſs of the Wound.*

What to do in want of a ſtay.

If a *Retinaculum* or Stay be wanting, you may conjoin the lips of the Wound, after this following manner. Put two Quills ſomewhat longer than the Wound, on each ſide one, and then preſently thruſt them through with Needles having Thread in them, taking hold of the fleſh between, as often as need ſhall require, then tying the thread upon them. For thus the Wound ſhall be agglutinated, and the fleſhy lips of the wound kept from being torn, which would be in danger if the needle and thred were onely uſed.

CHAP. XLVII.

How to take ſtones out of Womens bladders.

How to ſearch for the ſtone in Women.

WE know by the ſame ſigns that the ſtone is in a womans bladder as we do in a mans, yet it is far more eaſily ſearched by a Catheter, for that the neck of the bladder is the ſhorter, broader, and the more ſtraight. Wherefore it may not onely be found by a *Catheter* put into the bladder, but alſo by the fingers thruſt into the neck of the Womb, turning them up towards the inner ſide of the *Os pubis*, and placing the ſick woman in the ſame poſture as we mentioned in the cure of men. Yet you muſt obſerve that maids younger than ſeven years old, that are troubled with the ſtone, cannot be ſearched by the neck of the womb, without great violence. Therefore the ſtone muſt be drawn from them by the ſame means as from Boys, to wit, by thruſting the fingers into the Fundament; for thus the ſtone being found out, and the lower belly alſo preſſed with the other hand it muſt be brought to the neck of the bladder, and then drawn forth by the forementioned means. Yet if the riper years of the Patient permit it to be done without violence, the whole work ſhall be more eaſily and happily performed, by putting the fingers into the neck of the Womb, for that the bladder is nearer the neck of the womb than it is to the right gut. Wherefore the fingers thus thruſt in, a Catheter ſhall be preſently put into the neck of the bladder: This Catheter muſt be hollow, or ſlit on the outſide like thoſe before deſcribed but not crooked, but ſtraight, as you may perceive by the following Figure.

A Catheter, *upon which, being put into the bladder, the neck thereof may be cut to draw out a ſtone from a Woman.*



Upon this Inſtrument the neck of the bladder may be cut, and then with the Dilater made for the ſame purpoſe, the inciſion ſhall be dilated as much as need requires; yet with this caution, that ſeeing the neck of a womans bladder is the ſhorter, it admits not ſo great dilation as a mans, for otherwiſe there is danger that it may come to the body of the bladder, whence an involuntary ſhedding of the water may enſue and continue thereafter. The inciſion being dilated, the Surgeon putting one or two of his fingers into the neck of the womb, ſhall preſs the bottom of the bladder, and then thruſt his crooked Inſtruments or *forcipes* in by the wound, and with theſe he ſhall eaſily pluck out the ſtone, which he ſhall keep with his fingers from ſlipping back again. Yet *Laurence Collo* the Kings Surgeon, and both his ſons (than whom I do not know whether ever there were better cutters for the ſtone) do otherwiſe perform this operation; for they do not thruſt their fingers into the Fundament or neck of the womb, but contenting themſelves with putting in onely the Guiders (whereof we formerly made mention) into the paſſage of the Urine, they preſently thereupon make ſtraight inciſion directly at the mouth of the neck of the bladder, and not on the ſide as is uſually done in men. Then they gently by the ſame way thruſt the *forcipes* hollowed on the outſide formerly delineated, and ſo dilate the wound by tearing it as much as ſhall be ſufficient for the drawing of the ſtone forth of the bladder. The reſidue of the cure is the ſame with that formerly mentioned in men: yet this is to be added, that if an ulcer grow in the neck of the bladder by reaſon of the rending it, you may by putting in the *ſpeculum matricis*, dilate the neck of the womb, that fitting remedies may be applied with the more eaſe.

CHAP.

CHAP. XLVIII.

Of the ſuppreſſion of the Urin by internal cauſes.

BEſides the fore-mentioned cauſes of ſuppreſſed Urin, or difficulty of making water there are many other, leſt any may think that the Urin is ſtopt onely by the Stone or Gravel, as Surgeons think, who in this caſe preſently uſe Diureticks. Therefore the Urin is ſuppreſt by external and internal cauſes. The internal cauſes are clotted bloud, tough phlegm, warts, caruncles bred in the paſſages of the Urin, ſtones and gravel; the Urin is ſometimes ſuppreſt, becauſe the matter thereof, to wit, the ſerous or whayiſh part of the bloud, is either conſumed by the feveriſh heat, or carried other ways by ſweats or a ſcouring; ſometimes alſo the flatulency there contained, or inflammation ariſing in the parts made for the Urin and the neighbouring members, ſuppreſſes the Urin. For the right gut, if it be inflamed, intercepts the paſſage of the Urin, either by a tumor whereby it preſſeth upon the bladder, or by the communication of the inflammation. Thus by the default of an ill-affected Liver, the Urin is oft-times ſuppreſt in ſuch as have the dropſie; or elſe by dulneſs or decay of the attractive or ſeparative faculty of the reins by ſome great diſtemper, or by the default of the animal faculty, as in ſuch as are in a Phrenſie, Lethargy, Convulſion, Apoplexy. Beſides alſo a tough and viſcid humour falling from the whole body into the paſſages of the Urin, obſtructs and ſhuts up the paſſage. Alſo too long holding the water ſometimes cauſes this affect. For when the bladder is diſtended above meaſure, the paſſage thereof is drawn together and made more ſtraight: hereto may be added, that the too great diſtenſion of the bladder is a hinderance that it cannot uſe the expulſive faculty, and ſtraighten it ſelf about the Urin to the excluſion thereof; hereto alſo pain ſucceeds which preſently dejects all the faculties of the part which is ſeized upon. Thus of late a certain young man riding on horſe-back before his Miſtreſs, and therefore not daring to make water, when he had great need ſo to do, had his Urin ſo ſuppreſt, that returning from his journy home into the City, he coûld by no means poſſible make water. In the mean time he had grievous pain in the bottom of his belly and the *Perinæum*, with gripings and a ſweat all over his body, ſo that he almoſt ſwooned. I being called, when I had procured him to make water by putting in a hollow Catheter, and preſſing the bottom of his belly, whereof he forthwith made two pints; I told them that it was not occaſioned by the ſtone, which notwithſtanding the ſtanders by imagined to be the occaſion of that ſuppreſſion of Urin. For thence forward there appeared no ſigns of the ſtone in the Youth, neither was he afterwards troubled with the ſtopping of his Urin.

In ſuppreſſion of the urin we muſt not preſently fly to Diureticks.

Why the too long holding the urin cauſeth the ſuppreſſion thereof.

An hiſtory.

CHAP. XLIX.

A digreſſion concerning the purging of ſuch things as are unprofitable in the whole Body by the Urin.

I Think it not amiſs to teſtifie by the following Hiſtories, the providence of Nature in expelling by Urin ſuch things as are unprofitable in the whole body. *Monſieur Sarret* the Kings Secretary was wounded in the right arm with a Piſtol bullet; many and malign ſymptoms happened thereupon, but principally great inflammations, flowing with much *ſanies* and *pus* or quitture: it ſometimes happened that without any reaſon, this purulent and ſanious efflux of matter was ſtaid in inflammation; whereof while we ſolicitouſly inquired the cauſe, we found both his ſtools and water commixed with much purulent filth, and this through the whole courſe of the diſeaſe, whereof notwithſtanding by Gods aſſiſtance he recovered, and remains whole and ſound: we obſerved that as long as his arm flowed with this filthy matter, ſo long were his excrements of the belly and bladder free from the ſanious and purulent matter: as long on the contrary as the ulcers of the arm were dry, ſo long were the excrements of the guts and bladder ſanious and purulent. The ſame accident befel a Gentleman called *Monſieur de la Croix*, who received a deadly wound with a ſword on the left arm, though *German Cheval* and Maſter *Raſs* moſt expert Surgeons, and others, who together with me had him in cure, though it was not ſo for this reaſon, becauſe the *pus* cannot run ſo long a way in the body, neither if it were ſo, could that be done without the infection and corruption of the whole maſs of bloud, whileſt it flows through the Veins; therefore to be more probable that this quantity of filth, mixed with excrements and urine, flowed out by the default of the liver, or of ſome other bowel, rather than from the wounded arm. I was of a contrary opinion for theſe following reaſons: Firſt for that which was apparently ſeen in the Patient; for as long as the excrement and urin were free from this purulent matter, ſo long his arm plentifully flowed therewith; this on the contrary being dry, much purulent matter was voided both by ſtool and urin. Another was, that as our whole body is perſpirable, ſo it is alſo (if I may ſo term it) confluxible. The third was an example taken from the Glaſſes which the *French* term *Monte vins*, (that is, Mount-wines) for if a Glaſs that is full of Wine be ſet under another that is filled with Water, you may ſee the Wine raiſe it ſelf out of the lower veſſel to the upper through the midſt of the Water, and ſo the Water deſcends through the midſt of the Wine, yet ſo, that they do not mix themſelves, but the one take and poſſeſs the place of the other. If this may be done by Art, by things onely natural, and to be diſcerned by our eyes, what may be done in our bodies, in which by reaſon of the preſence of a more noble ſoul, all the works of Nature are far more perfect? What is it which we may deſpair to be done in the like caſe? For doth not the laudable bloud flow to the guts, kidnies, ſpleen, bladder of the gall, by the impulſe of Nature together with the excrements, which preſently the parts themſelves ſeparate from their nutriment? Doth not milk from the breſts flow ſometimes forth of the wombs of women lately delivered? Yet that cannot be carried down thither, unleſs by the paſſages of the mamillary veins and arteries, which meet with the mouths of the veſſels of the womb in the middle of the ſtraight

An Hiſtory.

An Hiſtory

How the *pus* may flow from the wounded arm by the urin and excrements.

Lib de loc. affec. 6. cap. 4.

ſtraight muſcles of the *Epigaſtrium*. Therefore no marvel, if according to *Galen*, the *pus* unmixt with the bloud flowing from the whole body by the veins and arteries into the kidnies and bladder, be caſt forth together with the urin. Theſe and the like things are done by Nature, not taught by any Counſel or Reaſon, but onely aſſiſted by the ſtrength of the ſegregating and expulſive faculty; and certainly we preſently diſſecting the dead body, obſerved that it all, as alſo all the bowels thereof, were free from inflammation and ulceration, neither was there any ſign of impreſſion of any purulent matter in any part thereof.

CHAP. L.

By what external cauſes the urin is ſuppreſt, and prognoſticks concerning the ſuppreſſion thereof.

THere are alſo many external cauſes, through whoſe occaſion the urin may be ſuppreſt; ſuch are bathing and ſwimming in cold water; the too long continued application of Narcotick Medicins upon the Reins, *Perinæum*, and Share; the uſe of cold meats and drinks, and ſuch other like. Moreover, the diſlocation of ſome *Vertebra* of the loins to the inſide, for that it preſſeth the nerves diſſeminated thence into the bladder; therefore it cauſeth a ſtupidity or numbneſs of the bladder. Whence it is, that it cannot perceive it ſelf to be vellicated by the acrimony of the urin, and conſequently it is not ſtirred up to the expulſion thereof. But from whatſoever cauſe the oppreſſion of the urin proceeds, if it perſevere for ſome days, death is to be feared, unleſs either a Fever which may conſume the matter of the urin, or a Scouring or Flux, which may divert it, ſhall happen thereupon. For thus by ſtay it acquireth an acrid and venenate quality, which flowing by the veins readily infecteth the maſs of bloud, and carried to the brain, much moleſts it by reaſon of that ſimilitude and ſympathy of condition which the Bladder hath with the *Meninges*. But Nature, if prevalent, eaſily freeth it ſelf from this danger by a manifeſt evacuation by ſtool, otherwiſe it muſt neceſſarily call as it were to its aid, a feverith heat, which may ſend the abounding matter of this ſerous humidity out through the skin, either by a ſenſible evacuation as by ſweat; becauſe ſweat and urin have one common matter: or elſe diſperſe and breath it out by tranſpiration, which is an inſenſible excretion.

Why the diſlocation of a *Vertebra* of the loins may cauſe a ſuppreſſion of urin.

Why the ſuppreſſion of the urin becomes deadly.

A Fever following thereon helps the ſuppreſſion of urin.

CHAP. LI.

Of bloudy Urin.

SOme piſs pure blood, others mixt, and that either with urin, and then that which is expelled reſembles the waſhing of fleſh newly killed; or elſe with *pus* or matter, and that either alone or mixed with the urin. There may be divers cauſes of this ſymptom, as the too great quantity of bloud gathered in the body, which by the ſuppreſſion of the accuſtomed and periodical evacuation, by the Courſes or Hemorrhoids, now turns its courſe to the reins and bladder: the fretting aſunder of ſome veſſel by an acrid humour, or the breaking thereof by carrying or lifting of ſome heavy burden, by leaping, falling from high, a great blow, the falling of ſome weight upon the loins, riding poſt too violently, the too immoderate uſe of venery, and laſtly, from any kind of painful and more violent exerciſe, by a rough and ſharp ſtone in the kidnies, by the weakneſs of the retentive faculty of the kidnies, by a wound of ſome of the parts belonging to the urin, by the too frequent uſe of diuretick and hot meats and medicins, or elſe of things in their whole nature contrary to the urinary parts; for by theſe and the like cauſes, the reins are oft-times ſo inflamed, that they neceſſarily impoſtumate, and at length the impoſtume being broken it turns into an ulcer, caſting forth quitture by the urin. In ſo great variety of the cauſes of bloudy urin, we may gather whence the cauſes of this ſymptom may ariſe, by the depraved action of this, or that part, by the condition of the flowing bloud, to wit, pure or mixt, and that either with the urin alone, or with *Pus*. For example, if this bloudy matter flow from the lungs, liver, kidnies, diſlocated *Vertebræ*, the ſtraight gut, or other the like part: you may diſcern it by the ſeat of the pain and ſymptoms, as a Fever: and the propriety of the pain, and other things which have preceded, or are yet preſent. And we may gather the ſame by the plenty and quality; for if, for example, the *pus* flow from an ulcer of the arm, the purulent matter will flow by turns, one while by the urin, ſo that little is caſt forth by the ulcer; then preſently on the contrary the urin becomes more clear. That purulent matter which flows from the lungs by reaſon of an *Empyema*, or from the liver, or any other bowel placed above the midriff, the *pus* which is caſt forth with the urin, is both in greater plenty and more exactly mixed with the urin than that which flows from the kidnies and bladder. It neither belongs to our purpoſe, or a Surgeons office either to undertake, or deliver the cure of this affect. It ſhall ſuffice onely to note that the cure of this ſymptom is not to be hoped for ſo long as the cauſe remains. And if this bloud flow by the opening of a veſſel, it ſhall be ſtaid by aſtringent medicins; if broken, by agglutinative; if corroded or fretted aſunder, by ſarcotick.

The differences.

Cauſes.

Signs of what cauſes they proceed.

Cure.

CHAP. LII.

Of the Signs of the ulcerated Kidnies.

I Had not determined to follow or particularly handle the cauſes of bloudy urins, yet becauſe that which is occaſioned by the ulcerated reins or bladder more frequently happens, therefore I have thought good briefly to ſpeak thereof in this place. The ſigns of an ulcer of the reins are, pain in the loins, matter howſoever mixt with the urin, never evacuated by it ſelf, but always flowing forth

forth with the Urin, and reſiding in the bottom of the Chamber-pot, with a ſanious and red ſediment, fleſhy and as it were bloudy fibres ſwimming up and down in the Urin, the ſmell of the filth is not ſo great as that which flows from the ulcerated bladder, for that the kidnies, ſeeing they are of a fleſhy ſubſtance, do far better ripen and digeſt the purulent matter than the bladder which is nervous and bloudleſs. Why the matter which flows from the kidnies is leſs ſtinking than that which flows from the bladder.

CHAP. LIII.

Of the ſigns of the ulcerated Bladder.

ULcers are in the bottom of the Bladder, and the neck thereof. The ſigns of an ulcer in the Bladder are, a deep pain at the ſhare-bones; the great ſtench of the matter flowing therefrom, white and thin skins ſwimming up and down in the water. But when the Ulcer poſſeſſeth the neck of the bladder, the pain is more gentle, neither doth it trouble before the Patient come to make water, but in the very making thereof, and a little while after. Differences.

But it is common both to the one and the other, that the Yard is extended in making water, to wit, by reaſon of the pain cauſed by the Urin fretting of the ulcerated part in the paſſage by: neither is the matter ſeen mixed with the Urin, as is uſual in an ulcer of the upper parts, becauſe it is poured forth not together with the Urin, but after it.

CHAP. LIV.

Prognoſticks of the ulcerated Reins and Bladder.

ULcers of the kidnies are more eaſily and readily healed than thoſe of the bladder; for fleſhy parts more ſpeedily heal and knit than bloudleſs and nervous parts. Ulcers which are in the bottom of the bladder, are incurable, or certainly moſt difficult to heal; for beſides that they are in a bloudleſs part, they are daily vellicated and exaſperated by the continual afflux of the contained Urin, for all the Urin is never evacuated: now that which remains after making water, becomes more acrid by the diſtemper and heat of the part, for that the bladder is always gathered about it, and dilated and ſtraitned according to the quantity of the contained Urin: therefore in the *Iſchuria*, that is, the ſuppreſſion or difficulty of making water, you may ſometimes ſee a quart of water made at once. Thoſe which have their legs fall away, having an ulcer in their bladder, are near their deaths. Ulcers ariſing in theſe parts, unleſs they be conſolidated in a ſhort time, remain uncurable. Why ulcers of the bladder are cured with more difficulty.

CHAP. LV.

What Cure muſt be uſed in the ſuppreſſion of the Urin.

IN curing the ſuppreſſion of the Urin, the indication muſt be taken from the nature of the diſeaſe, and cauſe thereof, if it be yet preſent or not. But the diverſity of the parts by which being hurt, the *Iſchuria* happens, intimates the variety of Medicins, neither muſt we preſently run to diureticks, and things breaking the ſtone, which many Empericks do. For hence grievous and malign ſymptoms often ariſe, eſpecially if this ſuppreſſion proceed from an acrid humour, or bloud preſſed out by a bruiſe, immoderate venery, and alſo more vehement exerciſe, a hot and acrid potion, as of *Cantharides*, by too long abſtaining from making water, by a *Phlegmon*, or ulcer of the urinary parts. For thus the pain and inflammation are increaſed, whence follows a gangrene, and at length death. Wherefore attempt nothing in this caſe without the advice of a Phyſician, no not when you muſt come to Surgery. For diureticks can ſcarce have place in another caſe, then when the urinary paſſages are obſtructed by gravel, or a groſs and viſcid humour, or elſe in ſome cold Country, or in the application of Narcoticks to the loins, although we muſt not here uſe theſe before we have firſt made uſe of general Medicins: now Diureticks may be adminiſtred ſundry ways, as hereafter ſhall appear. Scopes of curing. To what ſuppreſſion of the urin diureticks muſt not be uſed. To which, and when to be uſed.

℞ *Agrimon. urtic. parietar. ſurculos rubros habentis, an.* m.j. *rad. aſparag. mundat.* ℥ iv. *gran. alkekengi, nu.* xx. *ſem. malvæ* ʒ ß. *rad. acor.* ℥ j. *bulliant omnia ſimul in ſex libris aquæ dulcis ad tertias, deinde coletur.* Let the Patient take ℥ iv. hereof with ℥ j. of Sugar-candy, and drink it warm faſting in a morning, three hours before meat. Thirty or forty Ivy-berries beaten in white Wine, and given the Patient to drink ſome two hours before meat, are good for the ſame purpoſe. Alſo ʒ j. of nettle-ſeeds made into fine powder, and drunk in chicken-broth, is good for the ſame purpoſe. A decoction alſo of grummel, Goats-ſaxifrage, Pellitory of the Wall, white Saxifrage, the roots of Parſley, *aſparagus*, *acorus*, *bruſcus*, and Orris drunk in the quantity of ſome three or four ounces, is profitable alſo for the ſame purpoſe. Yet this following Water is commended above the reſt to provoke Urin, and open the paſſages thereof, from what cauſe ſoever the ſtopping thereof proceeds. ℞ *Rad. oſmund. regal. cyp. biſmal. gram. petroſel. fœnic. an.* ʒ ij. *raph. craſſior. in taleol.* ℥ iv. *macerentur per noctem in aceto albo acerrimo, bulliant poſtea in aquæ fluvialis* lb x. *ſaxifrag. criſt. marin. rub. tinct. milii ſolis, ſummitat. malvæ biſmal. an.* p. ij. *berul. cicer. rub. an.* p. j. *ſem. melon. citrul. an.* ℥ ij. ß. *alkekengi, gra.* xx. *glycyrrhiz.* ʒ j. *bulliant omnia ſimul ad tertias: in colatura infunde per noctem fol. ſen. oriental.* lb ß. *fiat iterum parva ebullitio, in expreſſione colata infunde cinam. elect.* ʒ vj. *colentur, iterum colatura injiciatur in alembicum vitreum, poſtea tereb. venet. luc.* lb ij. *aq. vitæ* ℥ vj. *agitentur omnia ſimul diligentiſſime. Lutetur alembicum luto ſapientiæ, fiat diſtillatio lento igne in balneo Mariæ.* Uſe it after the following manner: ℞ *Aq. ſtillatitiæ ſcriptæ* ℥ ij. *aut* iij. According to the operation which it ſhall perform, let the Patient take it four hours before meat. A diuretick Water.

Alſo

Why the uſe of diureticks is better after bathing.

To cleanſe the ulcers of the Kidnies and Bladder.

Also Radiſh-water diſtilled in *balneo Mariæ* is given in the quantity of ʒ iv. with ſugar, and that with good ſucceſs. Baths and *Semicupia*, or half-baths are artificially made, relax, ſoften, dilate, and open all the body; therefore the preſcribed Diureticks mixed with half a dram of Treacle may be fitly given at the going forth of the Bath. Theſe Medicins following are judged fit to cleanſe the ulcers of the Kidnies and Bladder. Syrup of Maiden-hair, of Roſes, taken in quantity of ʒ j. with *hydromel*, or barley-water: Aſſes or Goats milk are alſo much commended in this affect, becauſe they cleanſe the ulcers by their ſerous or whayiſh portion, and agglutinate by their Cheeſe-like. They muſt be taken warm from the dug, with honey of Roſes or a little ſalt, leſt they corrupt in the ſtomach; and that to the quantity of four ounces, drinking or eating nothing preſently upon it.

Trochiſces to heal the ulcers of the Kidnies.

The following Trochiſces are alſo good for the ſame purpoſe. ℞ *Quatuor ſem. frigid. major. ſeminis papaveris albi, portulacæ plantag. cydon, myrtil. gum. tragacanth. & arab. pinear. glycyrrh. mund. hordei mund. mucilag. pſilii, amygdal. dulcium an.* ʒ j. *boli armen. ſanguin. dracon. ſpodii, roſar. maſtich. terræ ſigil. myrrhæ, an.* ʒ ij. *cum oxymelite, conficiantur ſecundum artem trochiſci.* Let the Patient take ʒ ſ. diſſolved in Whay, Ptiſan, Barly-water, and the like; they may alſo be profitably diſſolved in Plantain-

Drink in ſtead of Wine.

water, and injected into the bladder. Let the Patient abſtain from Wine, and in ſtead thereof let him uſe Barley-water or *hydromel*, or a Ptiſan made of an ounce of Raiſins of the Sun, ſtoned and boiled in five pints of fair water, in an earthen Pipkin well leaded, or in a Glaſs, until one pint be conſumed, adding thereto of licorice ſcraped and beaten ʒ j. of the cold ſeeds likewiſe beaten two drams. Let it after it hath boiled a little more, be ſtrained through an Hypocras bag, with a quartern of Sugar, and two drams of choice Cinamon added thereto, and ſo let it be kept for uſual drink.

CHAP. LVI.

Of the Diabete, *or inability to hold the Urin.*

What *Diabete* is.

The Cauſes.

THe *Diabete* is a Diſeaſe, wherein preſently after one hath drunk, the Urin is preſently made in great plenty, by the diſſolution of the retentive faculty of the reins, and the depravation or immoderation of the attractive faculty. The external cauſes are the unſeaſonable and immoderate uſe of hot and diuretick things, and all more violent and vehement exerciſes. The internal cauſes are the inflammation of the Liver, Lungs, Spleen, but eſpecially of the kidnies and bladder. This affect muſt be diligently diſtinguiſhed from the excretion of the morbifick cauſes by Urin.

Signs.

The loins in this diſeaſe are moleſted with a pricking and biting pain, and there is a continual and unquenchable thirſt: and although this diſeaſe proceed from a hot diſtemper, yet the

Why the Urins are wateriſh.

Urin is not coloured, red, troubled, or thick, but thin, and white or wateriſh, by reaſon the matter thereof makes very ſmall ſtay in the Stomach, Liver, and hollow Vein, being preſently drawn away by the heat of the Kidnies or Bladder. If the affect long endure, the Patient for want of nouriſhment falleth away, whence certain death enſues. For the cure of ſo great a diſeaſe, the matter muſt be purged, which cauſes or feeds the inflammation or *phlegmon*, and conſequently bloud muſt be let.

The Cure.

We muſt abſtain from the four cold ſeeds, for although they may profit by their firſt quality, yet will they hurt by their diuretick faculty. Refrigerating and aſtringent nouriſhments muſt be uſed, and ſuch as generate groſs humours; as Rice, thick and aſtringent wine mixed with much water. Exceeding cold, yea narcotick things ſhall be applied to the loins, for otherwiſe by reaſon of the thickneſs of the muſcles of thoſe parts, the force, unleſs of exceeding refrigerating things, will not be able to arrive at the reins; of this kind are Oil of white Poppy, Henbane, *Opium*, Purſlain, and Lettuce-

Narcotick things to be applied to the loins.

ſeed, Mandrage, Vinegar, and the like: of which Cataplaſms, Plaſters, and Ointments, may be made fit t corroborate the parts, and correct and heat.

CHAP. LVII.

Of the Strangury.

What the Strangury is.

THe Strangury is an affect having ſome affinity with the *Diabete*, as that wherein the water is involuntarily made, but not together at once, but by drops, continually and with pain.

The Cauſes.

The external cauſes of a Strangury are, the too abundant drinking of cold water, and all too long ſtay in a cold place. The internal cauſes are, the defluxion of cold humours into the Urinary parts; for hence they are reſolved by a certain palſie, and the *ſphincter* of the bladder is relaxed, ſo that he cannot hold his water according to his deſire: inflammation alſo and all diſtemper cauſeth this affect, and whatſoever in ſome ſort obſtructs the paſſage of the Urin; as clotted bloud, thick phlegm, gravel, and the like. And becauſe, according to *Galens* opinion, all ſorts of diſtemper may cauſe this diſeaſe, divers Medicins ſhall be appointed according to the difference of the diſtemper.

Com. ad aphor. 15. ſect. 3.

Therefore againſt a cold diſtemper fomentations ſhall be provided of a decoction of Mallows, Roſes, *Origanum*, Calamint, and the like, and ſo applied to the Privities: then preſently after, let them be anointed with Oil of Bays, and of *Caſtoreum*, and the like. Strong and pure Wine ſhall be preſcribed for his drink, and that not onely in this cauſe, but alſo when the Strangury happens by the occaſion of obſtruction, cauſed by a groſs and cold humour, if ſo be that the body be not plethorick. But if inflammation, together with a *Plethora* or fulneſs, hath cauſed this affect, we may, according to

Ad aphor. 48. ſect. 7.

Galens advice, heal it by bloud-letting. But if obſtruction be in fault, that ſhall be taken away by Diureticks either hot or cold, according to the condition of the matter obſtructing. We here omit to ſpeak of the *Dyſuria*, or difficulty of making water, becauſe the remedies are in general the ſame with thoſe which are uſed in the *Iſchuria*, or ſuppreſſion of Urin.

CHAP.

CHAP. LVIII.

Of the Colick.

WHensoever the guts being obstructed, or otherwise affected, the excrements are hindred from passing forth, and if the fault be in the small guts, the affect is termed *Volvulus*, *Ileas*, and *Miserere mei*; but if it be in the greater guts, it is called the Colick, from the part affected, which is the *Colon*, that is, the continuity of the greater guts; but especially that portion of the greater guts, which is properly and especially named *Colon*, or the Colick-gut. Therefore *Avicen* rightly defines the Colick, A pain of the guts, wherein the excrements are difficultly evacuated by the fundament. *Paulus Ægineta* reduceth all the causes of the Colick, how various soever, to four heads: To wit, to the grossness or toughness of the humors impact in the coats of the guts: Flatulencies hindred from passage forth; the inflammation of the guts; and lastly, the collection of acrid and biting humors. Now we will treat of each of these in particular. Almost the same causes produce the grossness of humors and flatulencies in the guts, to wit, the use of flatulent and phlegmatick, tough and viscid meats, yea also of such as are of good nourishment, if sundry thereof, and of sundry kinds be eaten at the same meal, and in greater quantity then is fit. For hence crudity and obstruction, and at length the collection of flatulencies, whereon a tensive pain ensues. This kind of Colick is also caused by the use of crude fruits, and too cold drink, drunken especially when any is too hot by exercise, or any other way: For thus the stomach and the guts continued thereto, are refrigerated, and the humors and excrements therein contained are congealed, and, as it were, bound up. The Colick which is caused by the inflammation of the kidneys, happens by the sympathy of the reins pained or troubled with the stone or gravel contained in them or the ureters. Therefore then also pain troubles the Patient at his hips and loins, because the nerves, which arising from the *vertebræ* of the loins, are oppressed by the weight of the stones and gravel, about the joynt of the hip are disseminated into the muscles of the loins and thigh. Also the ureter are pained (for they seem nothing else but certain hollow nerves) and also the cremaster muscles, so that the Patients testicles may seem to be drawn upwards with much violence. Hence great phlegmatick, and cholerick vomiting, and sweat of the whole body, all which do not surcease before that the stone or gravel shall be forced down into the bladder. Now vomiting happens in this affect, for that the ventricle by reason of its continuity and neighbourhood which it hath with the guts, suffers by consent or sympathy. For the stomach is of the same kind or matter as the guts are, so that the guts seem nothing else but a certain production of the stomach. Therefore if at any time Nature endeavour to expel any thing that is troublesome in the kidneys, ureters, coats of the guts, mesentery, *pancreas*, and hypocondries, it causeth a Colick with pain and vomiting. An hot and dry distemper also causeth the Colick, prducing a pricking and biting pain, by drying the excrements shut up in the guts, as also by wasting, as it were, the radical humors of that place provided for the lubricating of the guts. Acrid, viscid and tough phlegm causeth the same. There is also another cause of the Colick which is not so common; to wit, the twining of the guts, that is, when they are so twined, folded, and doubled, that the excrements, as it were, bound in their knots, cannot be expelled, as it manifestly happens in the rupture called *Enterocele*, by the falling of the guts into the cod: Likewise also Worms generated in the Colick-gut, whilst that they mutually fold or twine themselves up, do also twine the *Colon* it self, and fold it with them. Also the too long stay of the excrements in the guts, whether it shall happen by the peculiar default of the too hot and dry body of the Patient, or by his diet, that is, the use of too dry meats, or exercises and pains taken in the heat of the Sun, or by the greatness of business, the mind being carried away, causeth the Colick, with Head-ach, and plenty of vapors flying upwards.

What *Ileos*, or *illaca passio* is.

What *Colica passio* or the Colick is.

Lib. 3.

Lib. 3. *c.* 43.

The manner of the Stone-colick.

How a hot distemper causeth the colick.

The folding of the guts the cause of the colick.

I remember I once dissected the body of a Boy of some twelve years old, who had his guts folded with many, as it were, ties or knots of the restrained, too hard and dry excrements, the which he cast out by his mouth a little before his death, which brought him to his end, being not helped in time by fitting medicines. Now these are the causes of the Colick, according to the opinion of the Ancient and Modern Physicians, of whose signs I judge it not amiss here to treat in particular. You shall know the Patient is troubled with the Stone-colick, by the pain which is fixed, and, as it were, kept in one place, to wit, of the kidneys; by his former manner of life; as if the Patient hath formerly voided stones or gravel together with his urine; by the pain of the hips and testicles for the formerly mentioned causes; and lastly, by that the Patient casteth forth by stone or urine, for that the great and laborious endeavour of Nature to cast forth the stone which is in the Kidneys, is propagated by a certain sympathy and like study of the neighbouring parts, stirring up the expulsive faculties each to his work. The signs of a flatulent colick are, a tensive pain, such as if the guts were rent or torn in pieces, together with a noise or rumbling in the belly. The force of the shut-up wind is sometimes so great, that it rendeth or teareth the guts in sunder, no otherwise than a Swines bladder too hard blown up: Which when it happens, the Patient dies with much vomiting, because the stomach oppress with wind, can contain nor imbrace no meat. The Colick which is occasioned by the too long keeping in of the excrements, is accompanied with the weight and pain of the belly, the tension of the guts, head-ach, apparent hardness of the belly, and the complaint of the Patient that he hath not gone to stool in a long time. That which proceeds from a cholerick inflammation, yields a sense of great heat and pulsation in the midst of the belly, by reason of the veins and arteries which are in the *pancreas* and coats of the guts, and there are the other signs of a *Phlegmon*, although also this, as it were, inflammation may arise also from salt, acrid and viscous phlegm, which Nature can neither expel upwards by vomit, nor downwards by stool; this sundry times is associated with a difficulty of making water,

An History.

Signs whereby we know that the colick proceeds from this or that cause.

ter, for that when as the right gut is inflamed, the bladder is preſſed by reaſon of their ſociety or neighbourhood. The Colick which proceeds from the conuſion of the guts, ſhews it ſelf by the exceſſive cruelty of the pain ariſing, for that the guts are not in their due ſite and place, and becauſe the excrements by their too long detention acquire a preternatural heat; and this is the cauſe of the death of many ſuch as have ruptures, for that the gut falling down from the natural place into the cod, being a preternatural place, is redoubled, and kept there, as it were, bound, whereby the excrements being baked, becoming more acridly hot, cauſe inflammation, and by raiſing up flatulencies, increaſe the diſtenſion through all the guts, until at length a deadly *Ileos* or colick ariſing, they come forth at the mouth. For prognoſticks, it is better to have the pain in the colick to wander up and down, than to be fixed: It is good alſo that the excrements are not wholly ſuppreſt. But the evil ſigns that are here, pronounce the affect either difficult or deadly. Now theſe ſhew that it is deedly, intolerable tormenting pain, continual vomiting, cold ſweat, coldneſs of the extreme parts, hicketing by reaſon of the ſympathy the ſtomach hath with the guts, a phrenſie by the conſent of the brain with the ſtomach, and oft-times a convulſion, by drawing the matter into the nerves. But ſuch as have griping and pain about their navil and loins, which can neither be helped by medicine nor otherwiſe, it ends in a Dropſie. The cure muſt be diverſified according to the variety of the cauſes, for the Stone-colick is cured by medicines proper to the ſtone; that which is cauſed by an *Enterocele*, is cured by the only reſtoring the gut to its place; that which is occaſioned by Worms, requires medicines fit to kill and caſt forth the Worms. But that which proceeds from the weakneſs and refrigeration of the guts and ſtomach, is cured by heating and ſtrengthning medicines as well applied outwardly, as taken inwardly by the mouth, or otherways. The beginning of the cure of that which is occaſioned by tough phlegm and flatulencies, is by the mitigation of the pain, ſeeing there is nothing which more dejects the powers than pain. To this purpoſe ſhall you provide Baths, *Semicupia*, fomentations of Mallows, Marſh-mallows, Violet leaves, Peny-royal, Fennel, *Origanum*, the ſeeds of Thyme and Fenugreek, flowers of Camomil, Melilote, and other ſuch like, which have power to heat, dry, attenuate and rarifie the skin, ſo to diſſipate the wind. But all muſt be actually hot. Alſo the belly may be anointed with this following oyntment. ℞ *Olei chamæm. aneth. butyr. recent. an.* ℥ i. *ſem. apii, petroſ. & galang. an.* ℥ ß. *Aq. vitæ, ol. ſalviæ aut Thymi chimici extracti. q.ſ.* The following liniment is much commended by *Hollerius*. ℞ *Olei. rut. & nardi an.* ʒ vi. *Galbani cum aq. vit. diſſoluti* ℥ ii. *Liquefactis ſimul adde zibetæ gr.* iiij. *Croci, gr.* vi. *Fiat linimentum.* Alſo little bags made with Millet, Oats, and Salt fried with a little White-wine in a frying-pan, ſhall be applied hot upon the belly and flanks, and renewed before they grow cold. You may, inſtead of theſe bags, uſe Ox-bladders half filled with a decoction of reſolving things; as Salt, Roſemary, Thyme, Lavender, Bay-berries, and the like: Then inject a Clyſter being thus made. ℞ *Quatuor emol. an.* m.i. *orig. puleg. calamenth. an.* m. ß. *aniſi, carui an.* m. ß. *Flor. aneth. an.* p.i. *buliant in hydromele ad* ib i. *in qua diſſolve bened. laxat. mellis anthoſati, ſacc. rub. an.* ℥ i. *Olei aneth. & chamæm. an.* ℥ i ß. Let a clyſter be made to be injected at twice; for the guts being ſtretched out cannot contain the accuſtomed *doſis* of a clyſter; Alſo this following clyſter is much approved. ℞ *Vini malvat. & olei nucum an.* ℥ iij. *Aq. vitæ,* ℥ i. *Olei juniperi, & rut. per quintum eſſent. extracti. an.* ℥ iij. Let this be injected as hot as the Patient can endure. I have oft-times, as by miracle, helped intolerable pain cauſed by the Wind-colick and Phlegm with this clyſter. *Avicen* preſcribes a carminative clyſter made of Hyſſop, *Origanum acorus*, Anis-ſeeds, and Engliſh Galengal. Let the Patient feed upon meats of good juice and eaſie digeſtion, as Broths made with the yolks of Eggs, Saffron, hot Herbs, and a Nutmeg, let him drink good Wine, as Muſcadine, or Hypocraſs made with good Wine, ſo to heat the ſtomach and guts. For in *Galen*'s opinion, all windineſs is generated by a remiſs heat. But if the pain ſhall continue, a large Cupping-glaſs ſhall be applied to the navel, to draw and diſſipate the windineſs; the belly ſhall be bound with ſtrong and broad ligatures, to ſtrengthen the guts, and diſcuſs the matter of flatulencies. The Patients taught by Nature to uſe this remedy, whilſt none admoniſhing them, they preſs the belly with their hands in the bitterneſs of pain. But if the pain cannot be thus appeaſed, we muſt come to ſuch medicines as work by an occult property, as the dried gut of a Wolf, for a dram thereof made into powder is given in Wine with good ſucceſs. That Colick which is cauſed by a cholerick inflammation requires contrary medicines, to wit, blood-letting, and a refrigerating diet; potions made of *Diacatholicon* and *Caſſia* diſſolved in Barley-water, alſo cooling clyſters. *Avicen* preſcribes narcoticks, for that being cold, they are contrary to the morbifick cauſe which is hot and dry; ſuch are pills of *Philonium*. Alſo pills of *Hiera picra* in the quantity of ʒ iv. with *Opium* and Saffron, of each one grain, may be uſed. Alſo Baths are appointed, made of water wherein Mallows, Marſh-mallows, Violet leaves, flowers of white Lilies, Lettuce, Purſlan have been boiled, to correct the acrimony of the cholerick and hot humors, whence the diſeaſe and ſymptom ariſeth. That Colick which is like to this, and proceeds from ſalt, acrid, thick and tough phlegm, is cured, the humor being firſt attenuated, and diffuſed, and at length evacuated by medicines taken by the mouth and otherwiſe, according to the preſcription of the learned Phyſician. But *Avicen* cures that which is occaſioned by the ſuppreſſion of the hardned excrements, and twining of them by meats which have an emollient faculty, ſuch as humecting broths, as that which is made of an old Cock tired with running, and threſhed to death, and ſo boiled with Dill, Polypody, and a little Salt, until the fleſh fall from the bones; alſo he uſeth detergent clyſters, ſuch as this which follows. ℞ *Betæ*, m.i *Furfuris*, p. i. *ficus*, nu. x. *alth.* m.i. *Fiat decoctio ad* ib i. *In qua diſſolve nitri & mutriæ an.* ʒ ii. *Sacc.* ℥ i. *Ol. ſeſamini*, ℥ ij. But if the obſtruction be more contumacious, you muſt uſe more powerful ones made *ex cyclamin. centaurio, & hiira diacolocinth. an.* ʒ ij. But if the obſtruction do notwithſtanding remain, ſo that the excrements come forth at the mouth, *Marianus Sanctius* witheth (by the counſel of many who have ſo freed themſelves from this deadly ſymptom) to drink three pounds of Quick-ſilver with water only. For the doubled, and, as it were, twined up-gut is unfolded by the weight of the Quick-ſilver, and the excrements are depreſt and thruſt forth, and

Avicen. lib. 3. *Hip aphor.* 10. *ſect.* 4.

The cure.

Baths and anodine fomentations.

An ointment.

Why clyſters in the Colick muſt be given in leſs quantity.

Specifick medicines.

The cure of a cholerick colick.

The force of quick-ſilver in the unfolding of the guts.

and the Worms are killed which gave occaſion to this affect. *John* of S. *Germans*, that moſt worthy Apothecary, hath told me that he ſaw a Gentleman, who when as he could not be freed from the pain of the colick by any means preſcribed by learned Phyſicians, at length by the counſel of a certain German his Friend, drank three ounces of oyl of Sweet-almonds drawn without fire, and mixed with ſome White-wine and Pellitory-water, and ſwallowed a leaden Bullet beſmeared with Quick-ſilver, and that Bullet coming preſently out by his fundament, he was wholly freed from his colick.

CHAP. LIX.

Of Phlebotomy, or Blood-letting.

PHlebotomy is the opening of a vein, evacuating the blood with the reſt of the humors; thus Arteritomy, is the opening of an artery. The firſt ſcope of Phlebotomy is the evacuation of the blood offending in quantity, although oft-times the Phyſicians intention is to draw forth the blood which offends in quality, or either way by opening a vein. Repletion, which is cauſed by the quantity, is two-fold; the one *ad vires*, that is, to the ſtrength, the veins being otherwiſe not very much ſwelled: This makes men infirm and weak, Nature not able to bear his humor, of what kind ſoever it be. The other is termed *ad vaſa*, that is, to the veſſels, the which is ſo called comparatively to the plenty of blood, although the ſtrength may very well away therewith. The veſſels are oft-times broke by this kind of repletion, ſo that the Patient caſts and ſpits up blood, or elſe evacuates it by the noſe, womb, hemorrhoids, or *varices*. The repletion which is *ad vires*, is known by the heavineſs and wearieſomneſs of the whole body; but that which is *ad vaſa*, is perceived by their diſtenſion and fulneſs, both of them ſtand in need of evacuation. But blood is only to be let by opening a vein, for five reſpects: The firſt is to leſſen the abundance of blood, as in plethorick bodies, and thoſe who are troubled with inflammation without any plenitude. The ſecond is for diverſion or revulſion, as when a vein of the right is opened to ſtay the bleeding of the left noſtril. The third is to allure or draw down; as when the *ſaphena* is opened in the ankle, to draw down the courſes in women. The fourth is for alteration or introduction of another quality; as when in ſharp feavers we open a vein to breathe out that blood which is heated in the veſſels, and cooling the reſidue which remains behind. The fifth is to prevent imminent diſeaſes; as when in the Spring and Autumn we draw blood by opening a vein in ſuch as are ſubject to ſpitting of blood, the Squinancy, Pluriſie, Falling-ſickneſs, Apoplexy, Madneſs, Gout, or in ſuch as are wounded, for to prevent the inflammation which is to be feared. Before blood-letting, if there be any old excrements in the guts, they ſhall be evacuated by a gentle Clyſter or ſuppoſitory, leſt the meſaraick veins ſhould thence draw unto them any impurity. Blood muſt not be drawn from ancient people, unleſs ſome preſent neceſſity require it, leſt the native heat, which is but languid in them, ſhould be brought to extreme debility, and their ſubſtance decay; neither muſt any in like ſort be taken from children, for fear of reſolving their powers by reaſon of the tenderneſs of their ſubſtance, and rareneſs of their habit. The quantity of blood which is to be let, muſt be conſidered by the ſtrength of the Patient and greatneſs of the diſeaſe: Therefore if the Patient be weak, and the diſeaſe require large evacuation, it will be convenient to part the letting of blood, yea by the interpoſition of ſome days. The vein of the forehead being opened is good for the pain of the hind-part of the head, yet firſt we foment the part with warm water, that ſo the skin may be ſofter; and the blood drawn into the veins in greater plenty. In the Squinancy, the veins which are under the tongue muſt be opened aſſant, without putting any ligagatures about the neck, for fear of ſtrangling. Phlebotomy is neceſſary in all diſeaſes which ſtop or hinder the breathing, or take away the voice or ſpeech; as likewiſe in all contuſions by a heavy ſtroke, or fall from high, in an Apoplexy, Squinancy, and Burning-feaver, though the ſtrength be not great, nor the blood faulty in quantity or quality, blood muſt not be let in the height of a Feaver. Moſt judge it fit to draw blood from the veins moſt remote from the affected and inflamed part, for that thus the courſe of the humors may be diverted, the next veins on the contrary being opened, the humors may be the more drawn into the affected part, and ſo increaſe the burthen and pain. But this opinion of theirs is very erroneous, for an opened vein always evacuates and burthens the next part. For I have ſundry times opened the veins and arteries of the affected part, as of the hands and feet in the Gout of their parts; of the temples in the Megrim; whereupon the pain always was ſomewhat aſſwaged, for that together with the evacuated blood, the malignity of the Gout, and the hot ſpirits (the cauſes of the Head-ach or Megrim) were evacuated. For thus *Galen* wiſheth to open the arteries of the temples in a great and contumacious defluxion falling upon the eyes, or in the Megrim or Head-ach.

What Phlebotomy is.

The uſe.

Repletion two-fold.

The ſigns.

Five ſcopes in letting blood.

From whence we muſt not draw blood.

When and for what it is neceſſary.

13. *Meth. cap. ult.*

CHAP. LX.

How to open a vein, or draw blood from thence.

How to place the Patient.

THe firſt thing is, to ſeat or place the Patient in as good a poſture as you can, to wit, in his bed, if he be weak; but in a chair, if ſtrong, yet ſo, that the light may fall directly upon the vein which you intend to open. Then the Surgeon ſhall rub the arm with his hand, or a warm linnen cloth, that the blood may flow the more plentifully into the vein: Then he ſhall bind the vein with a ligature a little above the place appointed to be opened, and he ſhall draw back the blood upwards towards the ligature from the lower part; and if it be the right arm, he ſhall take hold thereof with his left hand; but if the left, then with his right hand, preſſing the vein in the mean time with his thumb a little below the place were you mean to open it, leſt it ſhould ſlip away; and that it may be the more ſwoln by forcing up the blood: Then with with his nail he ſhall mark or deſign the place to be opened, and ſhall anoint it, being ſo marked, with butter or oyl, whereby the skin may be relaxed, and the lancet enter more eaſily, and therefore the ſection may be the leſs painful. He ſhall hold his lancet between his thumb and fore-finger, neither too near, nor too far from the point; he ſhall reſt his other three fingers upon the Patients arm, that ſo his hand may be the more ſteddy, and leſs trembling. Then ſhall he open the vein with an Inciſion agreeable to the magnitude of the veſſel, and the indifferent thickneſs of the contained blood, ſomewhat aſſant, diligently avoiding the artery which lies under the *Baſilica*, and the nerve or tendon of the two-headed muſcle, which lies under the Median vein. But for the Cephalick, it may be opened without danger. As much blood as is ſufficient being drawn, according to the mind of the Phyſician, he ſhall looſe the ligature, and laying a little boulſter under, he ſhall with a ligature bind up the wounded part to ſtay the bleeding, the ligature ſhall be neither too ſtrait nor looſe, but ſo that the Patient may freely bend and extend his arm; wherefore whilſt that is in doing, he muſt not hold his arm ſtrait out, but gently bended, otherwiſe he cannot freely bend it.

Rubbing the arm.

Binding it before we open the vein.

Why the *Baſilica* and Median may not be opened ſo ſafely as the Cephalick.

The binding up after blood-letting.

The Figure of a Lancet to let blood withal.

CHAP. LXI.

Of Cupping-glaſſes or Ventoſes.

The uſe of Cupping-glaſſes.

CUpping glaſſes are applied eſpecially when the matter conjunct and impact in any part is to be evacuated, and then chiefly there is place for ſcarification after the Cupping glaſſes: yet they are alſo applied for revulſion and diverſion; for when an humor continually flows down into the eyes, they may be applied to the ſhoulders with a great flame, for ſo they draw more ſtrongly and effectually. They are alſo applied under womens breaſts, for to ſtop the courſes flowing too immoderately, but to their thighs, for to provoke them. They are alſo applied to ſuch as are bit by venemous beaſts, as alſo to parts poſſeſſed by a peſtiferous *Bubo* or Carbuncle, ſo to draw the poyſon from within outwards. For (as *Celſus* ſaith) a Cupping glaſs where it is faſtned on, if the skin be firſt ſcarified, draws forth blood; but if it be whole, then it draws ſpirit. Alſo they are applied to the belly, when any groſs or thick windineſs ſhut up in the guts, or membranes of the *Epigaſtrium*, or lower belly cauſing the colick, is to be diſcuſſed. Alſo they are faſtned to the *Hypocondries*, when as flatulency in the liver, or ſpleen, ſwells up the entrail lying thereunder, or in too great a bleeding at the noſe. Alſo they are ſet againſt the reins in the bottom of the belly, whereas the ureters run down to draw down the ſtone into the bladder, when as it ſtops in the middle or entrance of the ureter. You ſhall make choice of greater and leſſer Cupping glaſſes, according to the condition of the part, and the contained matter. But to thoſe parts whereto theſe cannot by reaſon of their greatneſs be applied, you may fit horns for the ſame purpoſe.

Lib. 8. *cap.* 1.

The

The Figures of Cupping-glaſſes of different bigneſs, with little holes in their bottoms, which ſhall be ſtopped with wax, when you apply them to the parts; but opened when you would take them off, that ſo the air may enter in with the more eaſe.

A Lancet.



Horns which without fire, by only ſucking at the upper holes draw from the part lying under them.



CHAP. LXII.

Of Leeches, and their uſe.

The uſe of Leeches.

IN thoſe parts of the body whereto Cupping-glaſſes and horns cannot be applied, to thoſe Leeches may for the moſt part be put, as to the fundament, to open the coat of the Hemorrhoid veins, to the mouth of the womb, the gums, lips, noſe, fingers. After the Leeches being filled with blood, ſhall fall off, if the diſeaſe require a large evacuation of blood, and the part affected may endure it, Cupping-glaſſes, or Horns, or other Leeches ſhall be ſubſtituted. If the Leeches be handled with the bare hand, they are angred, and become ſo ſtomachful, as that they will not bite; wherefore you ſhall hold them in a white and clean linnen cloth, and apply them to the skin, being firſt lightly ſcarified, or beſmeared with the blood of ſome other creature; for thus they will take hold of the fleſh, together with the skin more greedily and fully. To cauſe them fall off, you ſhall put ſome powder of Aloes, Salt or Aſhes upon their heads. If any deſire to know how much blood they have drawn, let him ſprinkle them with Salt made into powder, as ſoon as they are come off; for thus they will vomit up what blood ſoever they have ſucked. If you deſire they ſhould ſuck more blood than they are able to contain, cut off their tails as they ſuck, for thus they will make no end of ſucking, for that it runs out as they ſuck it. The Leeches by ſucking, draw the blood not only from the affected part whereto they are applied, but alſo from the adjacent and diſtant parts. Alſo ſometimes the part bleeds a good while after the Leeches be fallen away, which happens not by ſcarification after the application of Cupping-glaſſes or Horns. If you cannot ſtop the bleeding after the falling away of the Leeches, then preſs the half of a Bean upon the wound, until it ſtick of it ſelf, for thus it will ſtay; alſo a burnt rag may be fitly applied with a boulſter and fit ligature.

How to apply them.

How to cauſe them to fall off.

The end of the Seventeenth Book.

BOOK XVIII.

Of the Gout.

CHAP. I.

The deſcription of the Gout.

What it is.

THE Gout is a diſeaſe occupying and harming the ſubſtance of the joynts by the falling down and collection of a virulent matter accompanied by four humors. This word *Arthritis* or Gout, is general for every joint ſo affected; yet it enjoys divers particular names in ſundry joynts of the body; as that which falleth upon the joint of the Jaw, is termed *Siagonagra*, for the Greeks call the Jaw *Siagon*; that which affects the neck is termed *Trachelagra*, for that the neck is termed *Trachelos:* That which troubles the back-bone is called *Rhaciſagra*, for the ſpine is termed *Rhacis:* That which moleſts the ſhoulders *Omagra*, for the joynt of the ſhoulder is called *Omos:* That which affects the joynt of the collar-bones *Cleiſagra*, for that the Greeks call this bone *Cleis:* That in the elbow *Pechyagra*, for *Pechys* ſignifieth the elbow: The Gout in the hand is called *Chiragra*, in the hip *Iſchias*, in the knee *Gonagra*, in the feet *Podagra*, for that the hand, hip, knee and foot are in Greek termed, *Cheir*, *Iſchion*, *Gonia* and *Pous*. When as there is great abundance of humors in a body, and the Patient leads a ſedentary life, not ſome one, but all the joynts of the body are at once troubled with the Gout.

Particular Gouts.

CHAP. II.

Of the occult cauſes of the Gout.

THE humor cauſing the Gout is not of a more known, or eaſily expreſt nature than that which cauſeth the plague, *Lues venerea*, or Falling ſickneſs. For it is of a kind and nature clean different from that which cauſeth a *Phlegmon*, *Oedema*, *Eryſipelas*, or *Scirrhus*; for as *Aetius* ſaith, it never cometh to ſuppuration like other humors, not for that, as I think, becauſe it happens in bloodleſs parts, but through the occaſion of ſome occult malignity. Hereto may be added, that the humors which cauſe the fore-mentioned tumors, when as they fall down upon any part, not then truly when they are turned into *Pus* or matter, do they cauſe ſo ſharp pains as that which cauſeth the Gout, for the pain thereof is far more ſharp, than of that humor which cauſeth an ulcerated *Cancer*. Beſides theſe humors, when they fall upon the joynts through any other occaſion, never turn into knots, only that which cauſeth the Gout in the joynts, after it hath fallen thither, is at length hardned into a certain knotty, and, as it were, plaſter-like ſubſtance to be amended by no remedies. But ſeeing it offends not the parts by which it flows down (no more than the matter which creeping upwards from the lower parts to the brain, cauſeth the *Epilepſie*) as ſoon as it falleth into ſpaces of the joynts, it cauſeth cruel pain, one while with heat, another while with cold.

Lib. 12. *cap.* 12.

The reſemblance of the Gout or the Epilepſie.

For

For you may ſee ſome troubled with the Gout, who complain that their pained joynts are burnt; there are others to whom they ſeem colder than any ice, ſo that they cannot be ſufficiently heated to their hearts deſire; verily you may ſometimes ſee in the ſame body troubled with the Gout, that the joynts of the right ſide will, as it were, burn with heat, but on the left ſide will be ſtiff with cold; or which is more, the knee in the ſame ſide to be tormented with a hot diſtemper, and the ankle troubled with a cold. Laſtly, there ſometimes happens a ſucceſſion of pain in a ſucceſſion of days, as the ſame joynts will be this day troubled with a hot, to morrow with a cold diſtemper, ſo that we need not marvel to ſee Phyſicians preſcribe one while hot, another while cold medicines againſt the ſame diſeaſe of the ſame part and body. Alſo it ſometimes happens that the malignity of this humor doth not only not yield to medicines, but it is rather made worſe, ſo that the Patients affirm that they are far better when they have none, than when they have any remedies applied. For all things being rightly done, and according to reaſon, yet the diſeaſe will come again at certain ſeaſons by fits; and hereupon it is ſaid by *Horace:*

The ſtrange variety of the Gout.

Qui cupit, aut metuit, juvat illum ſic domus aut res,
Ut lippum pictæ tabulæ, fomenta podagram.

Riches the covetous, and fearful ſo do pleaſe,
As Pictures ſore eyes, Bathes the Gout do eaſe.

Certainly ſuch as have this diſeaſe hereditarily, can no more be helped and throughly freed therefrom, than thoſe in whom the matter of the diſeaſe is become knotty, whereof *Ovid* thus ſpeaketh:

Tollere nodoſam neſcit medicina podagram.

Phyſick the knotty Gout it cannot heal.

Theſe reaſons have induced many to believe, that the eſſence of this diſeaſe is unknown, for there is a certain occult and inexplicable virulency, the author of ſo great malignity and contumacy; which *Avicen* ſeems to acknowledge, when he writes that there is a certain kind of Gout whoſe matter is ſo acute and malign, that if it at any time be augmented by the force of anger, it may ſuffice to kill the party by ſudden death. Therefore *Galen* himſelf writes that Treacle muſt be uſed in all Arthritical and gouty affects, and as I think for no other reaſon, than for that it dries, waſtes, and weakens the malignity thereof. *Gordonius* is of the ſame opinion, but addeth withal, that the body muſt be prepared and purged before we uſe Treacle. Therefore the matter of the Gout is a thin and virulent humor, yet not contagious, offending in quality rather than quantity, cauſing extreme pains, and therefore inſtigating the humors together with the caliginous and flatulent ſpirits prepared or ready for defluxion upon the affected parts. Therefore as the bitings of Aſps, and ſtingings of Waſps cauſe cruel pain with ſudden ſwelling and bliſtering, which is by the heat of the humors which the poyſon hath tainted, and not by the ſimple ſolution of continuity, ſeeing that we daily ſee Shoo-makers and Taylors pricking their fleſh with auls and needles, without having any ſuch ſymptom: So the virulency of the Gout cauſeth intolerable tormenting pain, not by the abundance, becauſe it happens to many who have the Gout, no ſign of defluxion appearing in the joynts, but only by a malignant and inexplicable quality, by reaſon whereof theſe pains do not ceaſe unleſs abated by the help of medicines, or nature, or both. The recital of the following Hiſtories will give much light to that inexplicable and virulent malignity of the matter cauſing the Gout. Whilſt King *Charles* the ninth of happy memory, was at *Burdeaux*, there was brought to *Chappellain* and *Caſtellan* the Kings Phyſicians, and *Taſte* a Phyſician of *Burdeaux*, *Nicolas Lambert* and my ſelf, Surgeons, a certain Gentlewoman ſome forty years old, exceedingly troubled for many years, by reaſon of a tumor ſcarce equalling the bigneſs of a Peaſe, on the outſide of the joynt of the left hip: One of her tormenting fits took her in my preſence; ſhe preſently began to cry and roar, and raſhly and violently to throw her body this way and that way, with motions and geſtures above a womans, yea a mans nature; for ſhe thruſt her head between her legs, laid her feet upon her ſhoulders; you would have ſaid ſhe had been poſſeſſed of the Devil. This fit held her ſome quarter of an hour; during all which time I heedfully obſerved whether the grieved part ſwelled any bigger than it was accuſtomed, whether there hapned any new inflammation; but there was no alteration as far as I could gather by ſight or feeling, but only that ſhe cried out more loudly when as I touched it. The fit paſſed, a great heat took her, all her body ran down with ſweat, with ſo great wearineſs and weakneſs of all her members, that ſhe could not ſo much as ſtir her little finger. There could be no ſuſpicion of an Epileptick, for this woman all the time of her agony did perfectly make uſe of all her ſenſes, did ſpeak, diſcourſe, and had no convulſion. Neither did ſhe ſpare any coſt or diligence, whereby ſhe might be cured of her diſeaſe by the help of Phyſicians or famous Surgeons; ſhe conſulted alſo with Witches, Wizzards, and Charmers, ſo that ſhe had left nothing unattempted, but all art was exceeded by the greatneſs of the diſeaſe. When I had ſhewed all theſe things at our conſultation, we all with one conſent were of this opinion, to apply a potential Cautery to the grieved part, or the tumor. I my ſelf applied it; after the fall of the Eſchar very black and virulent *ſanies* flowed out, which freed the woman of her pain and diſeaſe for ever after. Whence you may gather, that the cauſe of ſo great evil was a certain venenate malignity, hurting rather by an inexplicable quality than quantity; which being overcome and evacuated by the Cautery, all pain abſolutely ceaſed. Upon the like occaſion, but on the right arm, the wife of the Queens Coach-man at *Amboiſe*, conſulted *Chappellain*, *Caſtelan* and me, earneſtly craving eaſe of her pain, for ſhe was ſo grievouſly tormented by fits, that through impatiency, being careleſs of her ſelf, ſhe endeavoured to caſt her ſelf headlong out of her chamber window, for

Lib. 3. ſect. 22. tract. 2. cap.

Lib. de ther. ad Piſonem. c. 15.

The matter of the Gout partakes of occult maligni-ty.

An Hiſtory.

A terrible fit.

How an Epileptick fit differs from the Gout.

for fear whereof ſhe had a'guard put upon her. We judged that the like Monſter, was to be aſſaulted with the like weapon, neither were we deceived, for uſing a potential Cautery, this had like ſucceſs as the former. Wherefore the bitterneſs of the pain of the Gout is not occaſioned by the only weakneſs of the joynts, for thus the pain ſhould be continual, and always like it ſelf; neither is it from the diſtemper of a ſimple humor, for no ſuch thing happens in other tumors of what kind ſoever they be; but it proceeds from a venenate, malign, occult and inexplicable quality of the matter: Wherefore this diſeaſe ſtands in need of a diligent Phyſician, and a painful Surgeon.

CHAP. III.

Of the manifeſt cauſes of the Gout.

The firſt primitive cauſe of the Gout.

Although theſe things may be true which we have delivered of the occult cauſe of the Gout, yet there be and are vulgarly aſſigned others, of which a probable reaſon may be rendred, wherein this malignity, whereof we have ſpoke, lies hid and is ſeated. Therefore as of many other diſeaſes, ſo alſo of the Gout, there are aſſigned three cauſes; that is, the primitive, antecedent, and conjunct: The primitive is twofold, one drawn from their firſt original and their mothers womb, which happens to ſuch as are generated of gouty Parents, chiefly if whilſt they were conceived, this gouty matter did actually abound and fall upon the joynts. For the ſeed falls from all the parts of the body, as ſaith *Hippocrates*, and *Ariſtotle* affirms *lib. de gen. animal.* Yet this cauſes not an inevitable neceſſity of having the Gout, for as many begot of ſound and healthful Parents are taken by the Gout by their proper and primary default; ſo many live free from this diſeaſe, whoſe fathers notwithſtanding were troubled therewith. It is probable that they have this benefit and priviledge by the goodneſs of their Mothers ſeed, and the laudable temper of the womb; whereof the one by the mixture, and the other by the gentle heat, may amend and correct the faults of the paternal ſeed; for otherwiſe the diſeaſe would become hereditary, and gouty perſons would neceſſarily generate gouty; for the ſeed followeth the temper and complexion of the party generating, as it is ſhewed by *Avicen.* Another primitive cauſe is from inordinate diet, eſpecially in the uſe of meat, drink, exerciſe and venery. Laſtly, by unprofitable humors which are generated and heaped up in the body, which in proceſs of time acquire a virulent malignity; for theſe fill the head with vapors raiſed up from them, when the membranes, nerves and tendons, and conſequently the joynts become more lax and weak. They offend in feeding who eat much meat, and of ſundry kinds at the ſame meal, who drink ſtrong Wine without any mixture, who ſleep preſently after meat, and which uſe not moderate exerciſes; for hence a plenitude, an obſtruction of the veſſels, crudities, the increaſe of excrements, eſpecially ſerous: Which if they flow down unto the joynts, without doubt they cauſe this diſeaſe; for the joynts are weak either by nature or accident, in compariſon of the other parts of the body: By nature, as if they be looſe and ſoft from their firſt original; by accident, as by a blow, fall, hard travelling, running in the Sun by day, in the cold by night, racking, too frequent venery, eſpecially ſuddenly after meat; for thus the heat is diſſolved by reaſon of the diſſipation of the ſpirits cauſed in the effuſion of ſeed, whence many crude humors, which by an unſeaſonable motion are ſent into the ſinews and joynts. Through this occaſion old men, becauſe their native heat is the more weak, are commonly troubled with the Gout. Beſides alſo the ſuppreſſion of excrements accuſtomed to be avoided at certain times, as the courſes, hemorrhoids, vomit, ſcouring, cauſeth this diſeaſe. Hence it is, that in the opinion of *Hippocrates*, a woman is not troubled with the Gout, unleſs her courſes fail her. They are in the ſame caſe who have old and running ulcers ſuddenly healed, or *varices* cut and healed, unleſs by a ſtrict courſe of diet they they hinder the generation and increaſe of accuſtomed excrements. Alſo thoſe which recover of great and long diſeaſes, unleſs they be fully and perfectly purged, either by nature or art; theſe humors falling into the joynts, which are the reliques of the diſeaſe, make them to become gouty: And thus much for the primitive cauſe. The internal or antecedent cauſe is the abundance of humors, the largeneſs of the veſſels and paſſages which run to the joynts, the ſtrength of the amandating bowels, the looſneſs, ſoftneſs, and imbecillity of the reviving joynts. The conjunct cauſe is the humor, it ſelf repact and ſhut up in the capacities and cavities of the joynts. Now the unprofitable humor, on every ſide ſent down by the ſtrength of the expulſive faculty, ſooner lingers about the joynts, for that they are of a cold nature and denſe, ſo that once impact in that place, it cannot be eaſily digeſted and reſolved. This humor then cauſeth pain by reaſon of diſtention or ſolution of continuity, diſtemper; and beſides the virulency and malignity which it requires. But it ſavours of the nature ſometimes of one, ſometimes of more humors; whence the Gout is either phlegmonous, eryſipelatous, œdematous, or mixt. The concourſe of flatulencies, together with the flowing down humors, and as it were tumult by the hinderance of tranſpiration, increaſeth the dolorifick diſtention in the membranes, tendons, ligaments and other bodies wherein the joynt conſiſts.

Lib. de aere, loc. & aqua. *Lib. 1. cap. 17.*

Lib. 3. ſen. 22. tract. 2 cap.

Another primitive cauſe of the Gout.

Alph. 19. ſect. 9.

The antecedent cauſe of the Gout.

The conjunct.

Five cauſes of the pain of the Gout.

What and how the matter of the Gout comes down from the brain.

CHAP. IV.

Out of what part the matter of the Gout may flow down upon the joynts.

The matter of the Gout comes for the moſt part from the liver, or brain; that which deſcends from the brain is phlegmatick, ſerous, thin and clear, ſuch as uſually drops out of the noſe, endued with a malign and venenate quality. Now it paſſeth out by the muſculous skin and *Pericranium*, as alſo through that large hole by which the ſpinal marrow, the brains ſubſtitute, is propagated into the ſpine, by the coats and tendons of the nerves into the ſpaces of

of the joynts, and it is commonly cold. That which proceeds from the liver is diffuſed by the great vein and arteries filled and puffed up, and participates of the nature of the four humors, of which the maſs of the blood conſiſts, more frequently accompanied with an hot diſtemper, together with a gouty malignity. Beſides this manner of the Gout, which is cauſed by defluxion, there is another which is by congeſtion; as, when the too weak digeſtive faculty of the joynts cannot aſſimilate the juices ſent to them.

Gout by congeſtion.

CHAP. V.

The ſigns of the Arthritick humor flowing from the Brain.

WHen the defluxion is at hand, there is an heavineſs of the head, a deſire to reſt, and a dulneſs with the pain of the outer parts, then chiefly perceptible, when the hairs are turned up, or backwards; moreover, the muſculous skin of the head is puffed up, as ſwoln with a certain œdematous tumor; the Patients ſeem to be much different from themſelves by reaſon of the functions of the mind hurt by the malignity of the humor, from whence the natural faculties are not free; as the crudities of the ſtomach, and the frequent and acrid belchings may teſtifie.

CHAP. VI.

The ſigns of a gouty Humor, proceeding from the Liver.

THe right Hypocondry is hot in ſuch gouty perſons, yea the inner parts are much heated by the bowels, blood and choler carry the ſway, the veins are large and ſwoln, a defluxion ſuddenly falls down, eſpecially if there be a greater quantity of choler than of other humors in the maſs of the blood. But if, as it often falls out, the whole blood, by means of crudities degenerate into phlegm and a wheyiſh humor; then will it come to paſs, that the Gout alſo, which proceeds from the liver, may be pituitous or phlegmatick, and participate of the nature of an *œdema*, like that which proceeds from the brain. As if the ſame maſs of blood decline towards melancholy, the Gout which thence ariſeth, reſembles the nature of a *ſcirrhus*; yet that can ſcarce happen, that melancholy by reaſon of the thickneſs and ſlowneſs to motion may fall upon the joynts. Yet notwithſtanding, becauſe we ſpeak of that which may be of theſe, it will not be unprofitable briefly to diſtinguiſh the ſigns of each humor, and the differences of Gouts to be deduced from thence.

When the Gout which proceeds from the default of the liver, aſſimilates the nature of an *œdema*.

Why the Gout ſeldom proceeds from melancholy.

CHAP. VII.

By what ſigns we may underſtand this or that humor to accompany the gouty malignity.

YOu may give a gueſs hereat by the Patients age, temper, ſeaſon of the year, condion of the Country where he lives, his diet and condition of life, the increaſe of the pain in the morning, noon, evening or night, by the propriety of the beating, pricking, ſharp or dull pain; by numneſs, as in a melancholy Gout or Itching; as in that which is cauſed by tough phlegm, by the ſenſible appearance of the part in ſhape and colour (as for example ſake) in a phlegmatick Gout, the colour of the affected part is very little changed from its ſelf, and the neighbouring well parts, in a ſanguine Gout it looks red, in a cholerick it is fiery or pale, in a melancholy livid or blackiſh, by the heat and bigneſs which is greater in a ſanguine and phlegmatick than in the reſt, by the change; and laſtly, by things helping and hurting. And there be ſome, who for the knowledge of theſe differences, wiſh us to view the Patients urine, and feel their pulſe, and conſider theſe excrements, which in each particular nature, are accuſtomed to abound or flow, and are now ſuddenly and unaccuſtomarily ſuppreſt. For hence may be taken the ſigns of the dominion of this or that humor. But more ample knowledge of theſe things may be drawn from the humors predominant in each perſon, and the ſigns of tumors formerly delivered. Only this is to be noted by the way, that the Gout which is cauſed by melancholy, is rare to be found.

CHAP. VIII.

Prognoſticks in the Goat.

BY the Writings of Phyſicians the pains of the Gout are accounted amongſt the moſt grievous and acute; ſo that through vehemency of pain many are almoſt mad, and wiſh themſelves dead. They have certain periods and fits, according to the matter and condition of the humor wherein this malign and inexplicable gouty virulency reſides. Yet they more frequently invade in the Spring and Autumn; ſuch as have it hereditary are ſcarce ever throughly free therefrom, as neither ſuch as have it knotty: For in the former it was born with them, and implanted, and, as it were, fixed in the original of life; but in the other, the matter is become plaſter-like, ſo that it can neither be reſolved nor ripened. That which proceeds from a cold and pituitous matter, cauſeth not ſuch cruel tormenting pain, as that which is of an hot, ſanguine or cholerick cauſe, neither is it ſo ſpeedily healed, for that the hot and thin matter is more readily diſſolved; therefore commonly it ceaſeth not until forty days be paſt: Beſides alſo, by how much the ſubſtance of the affected part is more denſe, and the expulſive faculty more weak, by ſo much the pain is more tedious. Hence it is, that thoſe Gouty pains which moleſt the knee, heel and

The Gout frequent in the Spring and Fall.

What Gout uncurable.

Gal. ad aphor. 49. ſect. 5.

and huckle-bone, are more contumacious. The Gout which proceeds of an hot matter, reſts not before the fourteenth or twentieth day. That which is occaſioned by acrid choler, by the bitterneſs of the inflammation of the pain cauſeth a difficulty of breathing, raving, and ſundry times a Gangrene of the affected part, and laſtly death; and healed, it often leaves a palſie behind it.

Why the Sciatica cauſeth lameneſs.

Amongſt all the gouty pains, the Sciatica challengeth the prime place, by the greatneſs of the pain and multitude of ſymptoms; it brings unquietneſs and watching, a Feaver, Diſlocation, perpetual lameneſs, and the decay of the whole leg, yea and oftentimes of the whole body. Now lameneſs and leanneſs, or decay of the part are thus occaſioned, for that the decurrent humor forceth the head of the thigh-bone out of the cavity of the huckle-bone; this being forceth out preſſed the muſcles, veins, arteries, and that notable and large nerve which runs along the thigh, even to the further joynts of the toes, and by the way is diverſly diſperſed over the muſcles of the whole leg: Therefore becauſe the head of the thigh is put out of its place, the Patient is forced to halt; becauſe the veſſels and nerves are oppreſſed, the nouriſhment and ſpirits do not freely flow into the parts there-under, whence proceeds their decay. Yet it ſundry times happens, that the head of the thigh being not diſplaced, many halt becauſe the viſcid humor, which is naturally implanted in that place, and continually flows thither, both for the nutrition of theſe parts, and the lubrication of the joynt for quicker motion, is hardned by heat and idleneſs, and the other unprofitable humors which flow down to their concrete, and ſo intercept the liberty of motion. A groſs and viſcid humor in what joynt ſoever it falleth and ſtayeth, doth the ſame. For by concretion it turns into a plaſter-like nature at or near the joynt, poſſeſſing the cavities thereof, and it depraveth the figure of the part, making it crooked and knotted, which formerly was ſtrait and ſmooth. Furthermore, every diſtemperature cauſed by the defluxion of humors, if it ſhall lye long upon any part, depraves all the actions, and oft-times wholly aboliſheth them; ſo that there may be three cauſes of the leanneſs or decay of the joynt by the Gout, the obſtruction or compreſſion of the veſſels, idleneſs, and an hectick diſtemper: But two of lameneſs, diſlocation and the concretion of an adventitious humor impact in the joynt. If contrary to cuſtom and reaſon the pains of the Gout do not go away, or return at their accuſtomed periods, moſt grievous and dangerous diſeaſes thereon follow; for the matter accuſtomed to flow down into the joynts, if it ſeize upon the ſubſtance of the liver, cauſes a ſtegmon; if it ſtay in the larger veins, a continual Feaver; if it flow in the membrane inveſting the ribs, a Pluriſie; if it betake it ſelf to the guts, and adhere to their coats, the Colick, or *Iliaca paſſio:* And to conclude, it produceth divers other ſymptoms, according to the diverſity of the parts whereto it flows and abides. For thus ſundry that have been troubled with the Gout, become paralytick, becauſe the matter, which formerly flowed down into the joynts, ſtays in the ſubſtance and pores of the nerves, and ſo hinders the ſpirit that it cannot freely in its whole ſubſtance paſs through them: Hence therefore comes the reſolution of the part, whereinto the nerve is inſerted. Old men can never be quite or abſolutely cured of the Gout, for that the maſs of their blood is ſo departed from its primary and native goodneſs, that it can no more be reſtored, than dead or ſowred Wine. The Gout, which proceeds from a cold cauſe, invadeth ſlowly, and by little and little, and is helped by the uſe of hot things; that which is from an hot matter quickly ſhews it ſelf, and is helped by the uſe of cold things. Now, although the Gout more frequently returns in the Spring and Fall, yet it comes in the midſt of Winter, the nerves being weakned by the exceſs of cold, and the humors preſſed out; otherwhiles in the midſt of Summer, the ſame being diffuſed and diſſipated. Laſtly, it comes at any time or ſeaſon of the year, if thoſe who are ſubject to this diſeaſe feed plenteouſly, and do all things according to their own minds and deſire. Thoſe who are troubled with the Gout, feel and perceive change of weather, ſtorms, rains, ſnows, winds, and ſuch like, before they come. A Southerly conſtitution of the air, for example, fills the body with humidities, and ſtirs up the humors that lye quiet in the body; and therefore cauſe defluxions upon the weaker parts, ſuch as the joynts, both by nature, as being without blood and fleſh, as alſo by accident, for that they a long time have been accuſtomed to be ſo tormented; therefore their pains are increaſed in a wet ſeaſon. Many of theſe that are troubled with the Gout, deſire venery in the bitterneſs of their pain, becauſe the internal heat wherewith they then are inflamed, doth not diſſipate into ſpirits and air, as the feaveriſh heat doth, but diſſolves, and, as it were, melts down the ſeminal humor, which diſſolved, flows to the genitals, filleth and diſtends them. The ſame thing befals carriage and running horſes, for in theſe by labour, much heat ſends flatulencies to the bottom of the belly. Yet venery is very hurtful to ſuch as are troubled with Gout, becauſe it diſſipates the ſpirits and native heat, and increaſeth the unnatural heat; whereby it cometh to paſs, that the nervous parts are weakned, and the pain exaſperated. Rich men, that is, ſuch as feed riotouſly on variety of dainties, and in the mean ſpace live idly and lazily are more frequently and cruelly tormented with the Gout than poor people, who live ſparingly and hardly: Wherefore there have been ſeen not a few of ſuch rich and riotous perſons, who having ſpent their eſtates, therewith changed their health, together with their fortune and diet, and ſo have been wholly freed from the Gout.

The cauſes of the lameneſs or decay of the limbs.

How the Gout turns into the Palſie.

Why the Gout takes one in Winter, and the midſt of Summer.

Why ſuch as have the Gout upon them, do oft-times deſire venery.

Venery hurtful in the Gout.

CHAP. IX.

The general method of preventing and curing the Gout.

Aph. 30. ſect. 6.

THoſe who deſire to prevent the Gout, muſt not glut themſelves with meat, muſt be quick to labour, and abſtain from Wine and Venery, or certainly muſt not uſe them unleſs for their healths ſake, muſt vomit and purge at certain times. *Hippocrates* writes, that bodies are not troubled with the Gout before the uſe of Venery. Yet at this day many Eunuchs are ſeen to

to have the Gout, but especially those who abound with idleness and pleasure; yet these we have heretofore mentioned are very effectual, not only for the prevention, but also for the cure of the present disease. Yet we must diligently distinguish the causes, what they be, and whence they may proceed, and oppose thereto remedies contrary in quantity and quality. There are absolutely three distinct causes of Gout: A tainture from the Parents; a corruption of the humors by diet and air; a native, or adventitious weakness of the joynts. Against these there is a twofold indication: The first is the evacuation and alteration of the peccant humors, the other the strengthning of the weak joynts. These two shall be performed by diet conveniently appointed, purging, blood-letting, provocation of the hemorrhoids, courses, vomit, sweat, urine, and fit application of local medicines. Therefore, when the time shall come, wherein the Gout accustometh to return by course, the Patient shall have a care of himself by a diligent manner of diet, he shall lessen the matter of the disease by Phlebotomy (if that the Gout shall arise from the blood) from the opposite part, that by the same means revullion and evacuation may be made; as if the upper parts be inflamed, blood shall be drawn from the lower; if on the contrary the lower, out of the upper, always observing the straitness of the fibres. Thus the right arm being troubled with a gouty inflamm ation, the *Saphena* of the right leg shall be opened, and so on the contrary; but if this general blood-letting being premised, the pain shall not cease, it will be requisite to open the vein next to the pain, which I have often performed with happy success.

Two general scopes of curing the Gout.

Whence blood must be let in the Gout.

Yet Phlebotomy hath not the like effect in all, for it is not available to such as are continually and uncertainly troubled with gouty pains, or whose bodies are weak and cold, wherein phlegm only is predominant. We may say the same of purging, for though it be oft-times necessary, yet too frequently re-iterated, it proves hurtful; furthermore, neither of these remedies is usually very profitable to such as observe no order in meat and drink, which use venery too intemperately, who abound with crude and contumacious humors, whose joynts by long vexation of the disease, have contracted an hectick distemper and weakness, so that they are departed from their natural constitution, and suffer a great change of their proper substance. Wherefore as often as these greater remedies shall be used, a Physician shall be called, who according to his judgment may determine thereof. For oft-times diet proveth more available than medicines; Therefore the Patient (if the matter of the Gout be hot) shall either drink no Wine at all, or else very much allayed, that is, as much as his custom and the constitution of his stomach can endure. A fit time for purging and bleeding is the Spring and Autumn, because, according to the opinion of *Hippocrates*, Gouts reign chiefly in these seasons; in Autumn, for that the heat of the precedent Summer debilitateth the digestive faculty, the native heat being dissipated: As also the eating of Summer-fruits hath heaped up plenty of crude humors in the body, which easily flow down into the passages of the joynts opened and dilated by the Summers heat: Add hereunto, that the inequality or variableness of Autumn weakneth all nervous parts, and consequently the joynts. But in the Spring, for that the humors forced inward, by the coldness of the Winter, are drawn forth from the centre to the circumference of the body, and being attenuated, fall into the joynts upon a very small occasion, therefore there is great both necessity and opportunity for evacuation, which if it shall not avert the accustomed fit, yet it will make it more gentle and easie.

What gouty persons find no benefit by phlebotomy.

In what Gout diet proves more effectual than medicines.

Aph 55. *sect.* 6.

CHAP. X.

Of Vomiting.

VOmiting is by all the Antients exceedingly commended, not only for the prevention, but also for the cure, especially when as the matter floweth from the brain and stomach; for the phlegmatick, serous and cholerick humors, which usually flow from the joynts, are excluded and diverted by vomit, and also there is attenuation of that phlegm, which being more thick and viscid, adhereth to the roots of the stomach: yet you must consider and see, that the Patient be not of too weak a stomach and brain, for in this case vomiting is to be suspected. For the time, such as have excrementitious humors flowing down to the stomach through any occasion, as by exercise and motion, must vomit before they eat; on the contrary, such as are over-charged with an old congestion of humors, must vomit after they have eaten something. Certainly, it is safer vomiting after meat, than it is before. For the dry stomach cannot, unless with great contention and straining, free it self from the viscid humors impact in the coats thereof; and hence there is no small danger of breaking a vein or artery in the chest or lungs, especially if the Patient be straitchested, and long-necked, the season cold, and he unaccustomed to such evacuation. I remember that with this kind of remedy I cured a certain Gentleman of *Geneva*, grievously molested with a cruel pain in his shoulder, and thereby impotent to use his left arm; the Physicians and Surgeons of *Lions* seemed to omit nothing else for his cure. For they had used purging, phlebotomy, hunger, a diet-drink of *Guaiacum* and *China* (although his disease was not occasioned by the *Lues venerea*) and divers other topick medicines, nether yet did they any thing avail. Now learning by him that he was not apt to vomit, but that it was difficult to him. I wished him to feed more plentifully, and that of many and sundry meats; as, fat meats, onions, leeks; with sundry drinks, as Bear, Ptisan, sweet and sharp Wine, and that he should, as it were, over-charge his stomach at his meal, and presently after get him to his bed; for so it would happen, that Nature not enduring so great confusion and perturbation of meats and drinks, whereof some were corrupted already in the stomach, and other-some scarce altered at all, Nature not enduring this confusion and perturbation, would easily, and of its own accord provoke the stomach to vomit; which that it might the better succeed, he should help forward Natures endeavour, by thrusting his finger or a teather into his throat, that so the thick and tenacious phlegm might by the same means be evacuated:

To what Gout vomiting is to be used.

What time the fittest therefore.

An History.

How to make one vomit easily.

And

Lib. de rat. victis.

And not content to do thus once, I wiſhed him to do the like the ſecond and third day following; for ſo it veriſieth that ſaying of *Hippocrates*, *The ſecond and third day exclude the reliques of the firſt:* Afterwards, that he ſhould vomit twice a month, chaw Maſtick faſting, rub his neck and the pained part with *Aqua vitæ*, ſtrengthned by infuſing therein Lavander, Roſemary, and Cloves groſly beaten, confirm his arm by indifferent exerciſe: He performed all this, and ſo became free from his pain, and recovered the uſe of his arm. Thoſe who do not like ſuch plentiful feeding, ſhall drink a great quantity of warm water, wherein Radiſh roots have been boiled, and they ſhall have a care leſt by uſing their ſtomachs to this excretion by vomit, they weaken the digeſtive and retentive faculty thereof. Wherefore ſuch as can naturally, ſhall think it ſufficient to vomit twice a month.

CHAP. XI.

The other general remedies for the Gout.

How diureticks are good for the Gout.

THe defluxion of ſerous humors is very fitly diverted from the joynts by the urine, by the uſe of diuretick medicines. Therefore the roots of Sorrel, Parſly, *Ruſcus*, *aſparagus*, and Graſs, and the like, ſhall be boiled in Broth, and given to ſuch as have the Gout: For when the urine floweth much and thick, the pain is leſſened. Many have found benefit by iſſues; for the Arthritick malignity flows forth of theſe, as by rivulets; experience ſhews it in ſuch as are troubled with the *Lues venerea*, for in thoſe that you cannot overcome the malignity by the proper antidote, that is, Quick-ſilver, they feel no greater eaſe of the pain, then by application of Cauſticks, and making of iſſues. They ſhall be made in ſundry places, according the difference of the pained joynts, to wit, in the beginning of the neck, if the defluxion proceed from the brain, and fall into the joynts of the collar-bones or ſhoulder; if into the elbow or hand, under the muſcle *Epomis*; if into the hip, knees and feet, ſome three fingers breadth under the knee, on the inſide: For thus there will follow more plentiful evacuation, by reaſon that the *Sapheia* runneth down that way. Yet if the Patient be troubled with much buſineſs, and muſt travel much on horſe-back, then ſhall they be made on the out-ſide of the leg, between the two bones thereof, that ſo they may trouble him the leſs in riding. If any had rather uſe an actual Cautery, let him take ſuch an one as is triangular and ſharp, that ſo he may with more ſpeed and leſs pain, perform that which he intends, and let him thruſt it through a plate of iron which hath an hole therein, and let the plate be marked, leſt he ſhould err; the ulcer ſhall be kept open, by putting in a pill of gold, ſilver, lint, or the root of Orris, Hermodactiles, Gentian, Wax, wherewith ſome powder of Vitriol, Mercury or Alum ſhall be incorporated, leſt it ſhould fill up with fleſh ſooner than the Phyſician ſhall think fit. In the mean ſpace, the head, oft-times the original of the evil, ſhall be evacuated by taking in the Winter the pills *Cochiæ*, and *de Aſſajereth*; but in Summer *ſine quibus*, or *Imperiales*, before the full of the Moon. ℞ *Pul. hieræ ſimp.* ʒ i. *agar. recent. troch. & rhei an.* ʒ ij. *myrobal. chebul.* ʒ ß. *Tamarind.* ϑ ij. *Cum infuſione ſenæ, fiat maſſa de qua formentur pil.* vi. *pro drachma:* Let the Patient take two before ſup per every eighth day; the day after he ſhall drink ſome broth of the decoction of cicers, and the diuretick roots. Alſo theſe following pills will be good to purge the phlegmatick and ſerous humor. ℞. *Pilular. fœtid. & de hermodactyl. an.* ʒ ß, *formentur cum ſucco vel ſyrup. roſar. ſolut.* Or elſe, ℞ *Aloes* ʒ iij. *Agarici trochiſ. & rhei, an.* ʒ i. *Maſſæ pilul. arthrit. & de Hermodact. an.* ϑ ij. *Diacrid.* ϑ; *cum melle roſato fiat maſſa, capiat pondus,* ʒ i. as the Phyſician ſhall think fit, by whoſe adviſe theſe ſhall be uſed and changed as occaſion ſhall offer it ſelf, and the nature of the humor cauſing the diſeaſe. The day after the purging, the Patient ſhall take three hours before meat half a dram of treacle, to ſtrengthen the entrails: Pills are preferred before liquid medicines, for that by their too long ſtay in the ſtomach they eaſily attract the noxious humor from the brain, and the other more diſtant parts. I have known ſome Phyſicians, who mixing with ordinary pills a good quantity of Scamony, as ſeven or eight grains, with a little Ginger, leſt it ſhould hurt the ſtomach, have purged by ſtool a great quantity of ſerous humors; the day following they gave Barley cream to correct the harm which the Scamony may have done to the ſtomach. Others for the ſame purpoſe give treacle, which doth not only ſtrengthen the entrails, but alſo weakens the virulency of the gouty malignity; the orifice of the ventricle muſt be ſhut after meat, that ſo the vapors aſcending to the brain may be reſtrained: For this purpoſe common drige-powder, marmelate, or conſerve of Roſes are good. In a wet ſeaſon uſe Cephalick perfumes thus made: ℞ *Thuris vernicis, & maſtich. an.* ʒ i. *granorum juniperi, baccarum lauri, an.* ʒ ß. *Ligni aloes* ʒ ij. *Aſſæ odoratæ* ʒ i. ß. Let them be groſly beaten; let the fume be received in tow, or carded cotton, and ſo applied to the Head. Alſo the excrementitious humors ſhall be dried up by the following powder ſtrewed on the Patients head for fifteen days. ℞ *Fol. roſ. rub. ſenæ, ſtœchad. utriuſque an.* m. ß. *Milii,* ℥. iiij. *Furfuris loti in vino albo,* ʒ iij. *Florum chamæm. melil. an.* p. i. *Sem. aniſi* ʒ i. *Salis com.* ʒ ii. *Fiat omnium pulvis.* Let it be put into linnen bags, with which, being warmed at the fire in a frying-pan, and kept with ſtirring, the head ſhall be rubbed. Let the following medicine be chawed, and kept in the mouth in the form of a Maſticatory, in the time of the falling down of the defluxion. ℞ *Cubebarum, nucis moſchat. glycyrrhiz. aniſ. an.* ʒ i. *Pyrethri,* ʒ ij. *Maſtich. rad. ſtaphiſarg. eryngii, an.* ʒ ij. Let them all be made into powder, and mixed together, and tied up in a little taffaty to the bigneſs of a haſel-nut, and let them be rowled up and down the mouth with the tongue to cauſe ſpitting or ſalivation. Working with the hands, and frictions of the arms, eſpecially in the morning after the evacuation of the excrements, are good for ſuch as are troubled with the Gout in the feet, for ſo, it not only cauſeth revulſion from the feet, but alſo the reſolution of that which is unprofitable.

Iſſues or fontanels.

Where to be made.

An actual cautery.

Pills.

Common pills with the addition of Scamony.

Treacle, how uſeful in the Gout.

Cephalick fumigations.

Cephalick bags.

A Maſticatory.

CHAP.

CHAP. XII.

What diet is convenient for such as have the Gout.

AFter the body is once fed, they must not return to meat before that the concoction be perfected in the stomach, lest the liver be forced to draw by the mesaraick veins that which is yet crude and ill digested, and as it were forced thence. Whence the depravation of the nutriment of the whole body; for the following decoctions do not amend the default of the first. Let them make choice of meat of good juice and easie digestion, rosted for such as are phlegmatick, but boiled for such as are cholerick: As they shall shun much variety one meal, so must they eschew the use of pulses, milk-meats, sallads, and sharp things; as verjuice, vinegar, the juice of oranges, and citrons. They shall not eat unless they be hungry, and shall desist therefrom before they be fully satisfied, if it be but for this, that whilest the native heat is busied in the digestion of meat plenteously eaten, it is diverted from the concoction of the noxious humors. The flesh of great fowl, as swans, cranes, peacocks are not of laudable juice, and are with more difficulty digested in the stomach. Some of the ancients have disallowed of the eating of capons, and such like birds, because they are subject to be troubled with the Gout in the feet. Fishes are to be shunned, for that they heap up excrementitious humors, and are easily corrupted in the stomach, yea and relax it by continual use. Of the flesh of beasts, veal is most to be commended, for that it breeds temperate blood, and laudable juice, and is easily digested. Neither in the mean time is mutton to be found fault withall. But the like hunger or abstinence must not be appointed to all men troubled with the Gout, for such as are of a sanguine and cholerick complexion, because they are endued with much, and much wasting heat, are to be refreshed with more plentiful nourishment; for hunger sharpens choler, and so augments their pains; neither in the *interim* must they be fed with too much moist meats, for too much moisture, besides that it is the author of the putrefaction, will cause desluxions, and draw down the matter to the joint. Therefore the cholerick humor must be incrassated and refrigerated by taking things inwardly, and applying things outwardly lest by its tenuity it should fall down into the grieved parts. To this purpose conduce broths altered with lettuce, purslain, sorrel, and the like herbs, and barly creams made with a decoction of the four cold seeds. Phlegmatick bodies, by reason that they have not so vigorous heat, do as it were carry their provant about them, wherefore they must not be fed, neither with many, nor with moist meats. All that are troubled with the Gout, must shun those things that are hard of digestion, and which are soon corrupted, for they all have a certain remiss feaver, which diminisheth the native heat, and makes the meats apt to putrifie. Too plentiful drinking not only of wine, but also of any other liquor is to be avoided. For by too great a quantity of moisture the meat float in the stomach and the native heat is in some sort extinguished, whence proceed crudities. Some Physicians commend the use of white wine, for that it provokes urine, which is not altogether to be disallowed, if so be that the body be free from excrements, otherwise by this, as it were a vehicle, especially if the temperature of the body be somewhat more hot, they shall be carried down into the joints. Therefore in such a case I should rather advise them to use claret, which is somewhat weak and astringent, for that it doth not so much offend the head nor joints, and it shuts and strengthens the orifices of the vessels, yet it will be more convenient wholly to abstain therefrom, and instead thereof to drink an *Hydromel* made after this manner: ℞ *aquæ* ℔ iv. *mellis opt.* q. j. *bulliant ad consumptionem* ℔ j. *bene despumando, adde ad finem salviæ* p. j. *imo si æger sit pituitosus, cinnamomi aut caryophyllorum momentum.* For cholerick persons make a sugred water thus: ℞ *aquæ fontis* ℔ iv. *sacchari* ℔. ß. *colentur per manicam sine ebullitione, addendo in fine cinnamomi* ʒij. For thus the stomach shall also be strengthened; also he may drink *ptisan*, wherein at the end of the decoction shall be boiled some dried roses, or else some syrup of pomegranates added thereto, lest it should offend the stomach; as soon as it comes from off the fire, let it stand and settle, and then strain it through an hypocras bag, or clean linnen cloth.

The fault of the first concoction, is not amended in the after.

Capons subject to the Gout.

Cholerick persons cannot away with long fasting.

Phlegmatick bodies in fasting feed upon themselves.

White wine not good for the gout.

Claret may be the safelier drunk.

Hydromel most safely.

An *Hydrosaccharum.*

CHAP. XIII.

How to strengthen the Joints.

IT is a matter of much consequence for the prevention of this evil, to strengthen the joints, whereby they may be able to resist the humors preternaturally falling down upon them. Wherefore it is good morning and evening to rub them with *oleum omphacinum*, that is, oil made of olives not come to their perfect maturity; or with oil of roses mixed with common salt finely powdered. It may also be mixed with common oil, adding thereto the powder of Harts-horn, as that which hath an astringent and drying faculty. Also it is good to bathe them in this following lee: ℞ *cort. granat. nucum cupress. gallarum, sumach. cortic. querni, an.* ʒij. *salis com. alumin. roch. an.* ʒj. *salviæ, rorismar. lavendul. lauri, ivæ arthritic. an.* m. j. *rosar. rub.* m. ß. *bulliant omnia in* vi. ℔ *vini crassi & astringentis, & lixivio parato ex aqua chalibeata, & cinere querno.* Then foment the part with spunges or cotten cloths; after, this fomentation shall be carefully wiped and dried with hot linnen cloths, taking heed of cold. The juice of unripe haws tempered with oxycrate is a singular thing for this purpose. But if you desire to strengthen the joints weakned by a cold cause, then, ℞ *salviæ, rorismar. thymi, lavendul. laur. absinth. an.* m. j. *caryophyl. zinzib. piperis, conquassatorum an.* ʒj. *infundantur in aqua vitæ & vini rubri astringentis, an.* ℔ iv. *bulliant leniter in balneo Mariæ.* With this liquor foment the joints morning and evening. Some think it good to strengthen the joints, to tread grapes in vintage-time, which if they be not able to do, then let them wash their feet in the must or new pressed wine.

A fomentation to strengthen the joints.

The juice of haws with oxycrate.

Bags. Alſo bags may be thus made for the ſame purpoſe. ℞ *ſalis com. alum. roch. cort. granat, ſumach. berberis, nucum cupreſſi, an.* ℥iv. *fol. ſalviæ, roriſm. roſar. rub. an.* m. ß. Let them be all put in linnen bags, and boiled in lee, and ſo make a decoction, for to foment the joints.

CHAP. XIV.

Of the Palliative Cure of the Gout and the material cauſes thereof.

The ſcopes of curing. HEre alſo muſt we conſider the cauſes whence this diſeaſe proceeds, the temper of the diſeaſed body, the parts affected, and thoſe from whence it proceeds. For as theſe are not always alike, ſo neither can one and the like remedy be uſeful in every Gout. For firſt thoſe which proceed of a cold cauſe require other remedies, than thoſe which ariſe from a hot, and that which proceeds from any one ſimple humor, than that which ariſeth from diverſe mixed together. For Choler alone cauſeth cruel pains, but tempered by the admixture of Phlegm, it becomes more gentle. Furthermore ſome remedies are good in the beginning, ſome in the encreaſe, and ſome at other times. Neither may we uſe repercuſſives in the Sciatica, as we may in the Gout of the feet and other joints; unleſs peradventure the part be fearfully inflamed.

Repercuſſives not to be uſed in the *Sciatica.* Taking theſe things to conſideration we muſt obſerve that the Palliative cure of that Gout, which cannot abſolutely be helped, as that which is hereditary and inveterate, is performed by four ſcopes. The firſt is by appointing a convenient diet in the *ſix things* which are termed *not-natural.* The ſecond by evacuating and diverting the antecedent matter, both by purging and phlebotomy. The third by topick medicines according to the condition of the morbifick humor and nature. The fourth by correcting the ſymptoms, but eſpecially the pain, whereof in theſe affects there is oft-times ſo great exceſs by reaſon of the inexplicable and invincible malignity of the virulent quality aſſociating the humor that it alone is oft-times ſufficient to kill the patient. And becauſe the variety of morbifick cauſes, brings a variety of remedies, fitted to theſe four intentions, therefore it behoves a Phyſician to be moſt attentive in the diſtinction of the cauſes. For he may be eaſily deceived and miſtake one for another; for arthritick pains proceeding from a cold matter, if they be mitigated by the application of Narcotick and cold medicines, it may induce us to believe that the material cauſe is hot, though really it be not ſo; for Narcoticks aſſwage pain, not for that they are contrary to the cauſe thereof, but becauſe they take away the ſenſe by inducing a numnneſs; on the contrary, the material cauſe may ſeem cold, which notwithſtanding is hot, for that it becomes better by application of hot medicines, that is, by taking an argument from that which helps, becauſe contraries are cured by contraries, and the like preſerved by the like. But herein conſiſts the error, for that hot medicines profit not by their contrariety, but by the attenuation of the groſs matter, by the rarefaction of the skin, and diſſipating them into air. Whence you may gather, that an argument drawn from that which helps and hurts, is very deceitful: moreover it may happen that a large quantity of cold matter flowing down from the brain, may cauſe great pain by reaſon of the virulency, and a ſmall quantity of choler mixed therewith, which ſerves for a *vehicle* to carry down the tough and ſlow phlegm into the joints, whence the patient becomes thirſty and feaveriſh by reaſon of the heat and inflammation of theſe parts, whereby ſuch as are leſs cautelous and heedy will eaſily be induced to believe that ſome hot matter is the occaſion of this Gout. Now when as not ſome one ſimple humor, but different by reaſon of mixture, cauſeth the Gout, the yelloviſh colour of the part may deceive one, as, if the evil matter ſhould proceed from choler only, which by the tenuity of its ſubſtance leaving the center, eaſily poſſeſſeth the circumference of the body or part: and notwithſtanding much phlegm being as it were enraged by the admixtion of a little choler, may be the chief cauſe of the diſeaſe, and may peradventure be diſcovered by the encreaſe of pain in the night ſeaſon. A feaver ariſing by means of pain and watching may encreaſe the conceived opinion of choler, which attenuating and diffuſing the humors, drives them into the joints, and cauſeth fiery urines, tinctured with much choler, and a quick pulſe. Yet notwithſtanding the Phyſician ſhall be in an error, if deceived with theſe appearances, he attempt the cure of this Gout, as ariſing from a hot, and not from a cold cauſe: yet I am not ignorant that the cure of the proper diſeaſe muſt be neglected for the cure of the ſymptoms. Beſides alſo it may come to paſs that choler may be the cauſe of the Gout, and notwithſtanding no ſigns thereof may appear in the skin and ſurface of the affected part, becauſe the coldneſs of the ambient air, and the force of applied Narcoticks may have deſtroyed the colour of the juices lying thereunder, and as it were imprinted a certain blackneſs. It alſo happens that the body being overcharged with a great quantity of groſs and viſcid humors the expulſive faculty may diſcharge ſome portion thereof unto the joints, but leave the reſt impact in the cavity of ſome entrail, where cauſing obſtruction and putrefaction, may preſently cauſe a feaver, and that intermitting, if it be ſmall, and obſtruct only the leſſer veins, and theſe of the habit of the body. Wherefore then it is not ſufficient that the Phyſician employ himſelf in the cure of the Gout, but it behoves him much to attend the cure of the feaver, which if it be continual, it diſcredits the Phyſician, and endangers the patient; if it be intermitting, it eaſily becomes continual, unleſs it be withſtood with fit remedies, that is, unleſs you let blood, the belly being firſt gently purged, and nature be preſently freed by a ſtronger purge of the troubleſome burden of humors. Now it is convenient, the purge be ſomewhat ſtronger than ordinary; for if it ſhould be too weak, it will ſtir up the humors, but not carry them away, and they thus agitated will fall into the pained and weak joints, and cauſe the Gout to encreaſe. By this it appears how deceitful that conjecture is, which relies and is grounded on one ſign, as often as we muſt pronounce judgment of morbifick cauſes. Wherefore to conclude, we muſt think that opinion moſt certain concerning the matter of the diſeaſe, which is ſtrengthned with multiplicity of ſigns, as thoſe which are drawn from the colour of the part, the heat or coldneſs manifeſt to the touch,

An argument taken from that which helpeth or giveth eaſe, is not always certain.

How cold diſeaſes may be helped by cold, and hot, by hot medicines.

The firſt thing that may deceive a Phyſician.

The ſecond.

The third.

The fourth.

The fifth.

The ſixth.

Why ſtrong purges muſt be given to ſuch as have the Gout.

That judgment moſt certain which reſts upon multiplicity of ſigns.

thoſe

thoſe things that help and hurt, the patients familiar and uſual diet, temper, age, region, ſeaſon of the year, propriety of pain, the exacerbation or exceſs thereof, in what days, and in what hours of the day, the length of theſe fits, the urine and other excrements coming from the patients body. But for that not a few are in that hereſie, that they think that we muſt neither purge nor let blood in the Gout, we muſt here convince that opinion; For ſeeing that phyſick is the addition of that which wants, and the taking off thoſe things that are ſuperfluous, and the Gout is a diſeaſe which hath its eſſence from the plenty of abounding humors, certainly, without the evacuation of them by purging and bleeding, we cannot hope to cure, either it, or the pain which accompanies it. *Metrius*, in his Treatiſe of the Gout writes, that it muſt be cured by purging, uſed not only in the declination, but alſo in the height of the diſeaſe, which we have found true by experience; and it is conſonant to this ſaying of *Hippocrates*; In pains we muſt purge by the ſtool. Beſides alſo, *Galen* profeſſeth that in great inflammations, fevers and pains, he knew no greater nor ſurer remedy than to let blood, even to the fainting of the Patient. If thoſe which are in this caſe ſhall not become better by purging and phlebotomy conveniently preſcribed, then it happens by the means of drunkenneſs, gluttony, and the like diſtemper. For hence abundance of crude humors are heaped up, which by their contumacy yield themſelves leſs obedient to medicines. Therefore ſuch gouty perſons as are intemperate and given to gluttony and venery; may hope for no health by uſe of medicines.

Why we muſt uſe purging and bleeding in the Gout.

Lib de affect. ubi de Arthrit. loquitur.

Ad aph. 23. ſect. 1.

Lib. de cur. per ſang. miſſionem.

CHAP. XV.

Of local medicines which may be uſed to a cold Gout.

LIttle do topick medicines avail, unleſs the body of the gouty patient ſhall be purged from excrementitious humors; beſides alſo there is danger leſt by the uſe of repelling medicines, the virulency of the humor may be driven into the entrails, which thing hath been the cauſe of ſudden death to many. Now in the firſt place we will ſpeak of local medicines which are thought meet for a phlegmatick juice, becauſe this is more frequent, than that which is from a hot cauſe. At the beginning in every Gout, the *Sciatica* excepted, we muſt uſe aſtringent things which have a faculty to bind or ſtrengthen the joints, and to dry and waſte the excrementitious humor. As, ℞ *fol. ſabinæ* m. ß. *nucum cupreſſi* ʒiij. *aluminis roch.* ʒj. *gum. tragacanthæ* ʒiv. *mucilaginis pſilii & cydon. quantum ſufficit, fiat cataplaſma.* Or, ℞ *ſtercoris bubuli recentis* ℔ j. *mellis roſ.* ʒiv. *olei roſ. & aceti an.* ʒij. *bulliant ſimul parum, fiat cataplaſma.* Or elſe, ℞ *olei roſar. & myrtill. an.* ʒij. *pulveris myrrhæ & aloes an.* ʒj. *acaciæ* ʒij. ß. *incorporentur cum aqua gallarum coctarum, & fiat unguentum.* Some boil ſage, camomile and melilote flowers, wormwood and danewort, of each a handful in a ſufficient quantity of vinegar, then they put the grieved part into this decoction being warm; and by frequent uſing this medicine, it hath been found to repel and conſume the noxious humor, not only cold, but alſo cholerick; and alſo to ſtrengthen the part. The freth *fæces* of Olives laid to the part, aſſwage pain: dried Oranges boiled in vinegar, beaten and applied, do the ſame. Or, ℞ *medii corticis ulmi* ℔ ß. *caudæ equin. ſtœchad. conſolid. majoris, an.* m. ſ. *aluminis roch. thuris an.* ʒiij. *farin. hordei* ʒv. *lexivii com. quantum ſufficit, fiat cataplaſma ad formam pultis ſatis liquidæ.* Commonly then when as the part ſwelleth up, the pain is leſſened, for that the expulſive faculty driveth the humor from the center into the circumference of the part, that is, from within outward; for in like ſort, ſuch as have the tooth-ach have leſs pain when their cheeks begin to ſwell.

It is not ſafe to uſe repercuſſives in the Gout before purging.

An aſtringent Cataplaſm.

A diſcuſſing ſomentation.

One, partly aſtringent and partly diſcuſſing.

After repercuſſives, we muſt come to thoſe which evacuate the contained humor by evacuating or reſolving it. For every defluxion of humors remaining in any part requires evacuation. Neither muſt we marvel thereat, if the digeſted humor doth not vaniſh at the firſt time; for we muſt have regard to the cold phlegm which is thick and viſcid, as alſo of the part which is ligamentous, membranous and nervous, and conſequently more denſe than fleſhy parts. ℞ *rad. bryon. ſigilli beat. Mariæ an.* ʒiv. *bulliant in lixivio, poſtea terantur, & colentur per ſetaceum, addendo farin. hordei & faharum an.* ʒj. *olei chamæm.* ʒiij. *fiat cataplaſma.* Or, ℞. *hordei & lupin. an.* ʒiij. *ſulphuris vivi & ſalis com. an.* ʒj. *mellis com.* ʒv. *pul. aloes & myrrhæ an.* ʒ ß. *aq. vit.* ʒj. *cum lixivio, fiat cataplaſma.* Or, ℞ *ſucci calium rub. aceti boni, an.* ʒiv. *farin. hordei* ʒj ß. *pul. Hermodactyl.* ʒ ß. *vitellos ovorum* nu. iij. *olei chamæm.* ʒij. *croci* ℈ij. ſome burn the roots and ſtalks of Coleworts, and mix the aſhes with hogs greaſe and the powder of Orris, and ſo make a pultis. Or, ℞ *Lactis vaccini* lb. ij. *micæ panis albi quantum ſufficit, bulliant ſimul, addendo pulveris ſubtilis florum chamæm. & meliloti an.* m. ß. *croci* ℈j. *vitellos ovorum* nu. iv. *ol. roſ.* ʒiij. *butyri recentis* ʒj. *terebinth.* ʒij. *fiat cataplaſma ad formam pultis ſatis liquidæ.* This Cataplaſm may be applied with good ſucceſs, not only to phlegmatick and cold, but alſo to any gout, at any time to mitigate the extremity of the pain in men of any temper, and it muſt be changed twice or thrice a day. Alſo Treacle diſſolved in wine, and anointed on the part, is ſaid to aſſwage this pain. You may for the ſame purpoſe make and apply emplaiſters, unguents, cerats, and liniments: This may be the form of an emplaiſter. ℞ *gummi ammoniaci, bdellii, ſtyracis, an.* ʒij. *cum aceto & aqua vit. diſſolve & adde farin. fœnugr.* ʒ ſ. *olei chamæm. & aneth. an.* ʒij. *ceræ quantum ſufficit, fiat emplaſtrum molle.* Or, ℞ *rad. bryon. ſigill. beat. Mariæ an.* ʒv. *bulliant in lixivio complete, & colentur per ſetaceum, addendo olei cham.* ʒiv. *ſevi hircini* ʒiv. *ceræ nov. quantum ſufficit, fiat emplaſtrum molle.* Or, ℞ *gum. ammon. opopanacis, galbani, an.* ʒij. *diſſolvantur in aceto, poſtea colentur, adde olei liliorum, terebinth. venet. an.* ʒj. *picis navalis, & cer. nov. quantum ſufficit, fiat emplaſtrum molle.* Or elſe, ℞. *ſucci rad. enul. camp. & ebuli an.* ʒiij. *rad. alth.* lb ſ. *coquantur & colentur per ſetaceum, addendo florum cham. melil. ſambuci, roriſmar. & hyperici an.* p. ij. *nucum cupreſſi,* nu. iv. *ol. cham. aneth. hyper. liliorum, deſpica an.* ʒij. *pinguedinis anatis, gallin. anſeris an.* ʒ ß. *ranas virides vivas* nu. vi. *catellos duos nuper natos, bulliant. omnia ſimul, in* ℔ ij. ſ. *vini odoriferi & una aquæ vit. ad conſumptionem ſuccorum & vini, & oſſium catellorum diſſolutionem, & fortiter exprimantur;*

Why the gouty humor doth not preſently vaniſh upon the uſe of repercuſſives. Greater diſcuſſers.

A cataplaſm good for any Gout at any time.

Diſcuſſing emplaiſters.

primantur ; & expreſſis adde terebinth. ℥iij. *cer. quantum ſufficit, fiat emplaſtrum mol'e.* Alſo, *Emp. de Vigo. Oxycroceum, de mucilaginibus, de meliloto* and the like mixed together, and ſoftned with a little oil or *axungia*, are of the like faculty, and good for the ſame purpoſe.

Ointments.

Let this be the form of an ointment. ℞ *anſerem pinguem, & imple catel'is duobus, de quibus deme cutem, viſcera, caput & pedes ; item accipe ranas* nu.x. *colubros detracta cute in fruſta diſſectos* nu. iv. *mithridat. & theriac. an.* ℥ ß. *fol. ſalviæ, roriſmar. thymi, rutæ, an.* m. ß. *baccarum lauri, & juniperi, conquaſſat. an.* ℥j. *pulveris nuc. moſchat. zinzib. caryophyl. & piper. an.* ʒj. *de eo quod ſtillabat fiat unguentum vel linimentum cum cera & terebinth. veneta, pauca, aq. vitæ addita* ; this marvelouſly aſſwageth the pain of the Gout ariſing from a cold cauſe. Another, ℞ *gummi pini, & laudani, an.* ℥iv. *gummi elemi & picis naval. an.* ℥ ß. *terebinth. venet. claræ* ʒvi. *chamæm, & liliorum an.* ℥vi. *vini. rub.* ℔. i ß. *aq. vit. & ſalv. an.* ʒvj. *diſſolvantur omnia ſimul lento igne baculo ſemper agitando, deinde adde pul. ireos, flor. baccarum lauri & hermodactyl. an.* ℥ij ß. *maſtiches, myrrhæ & olibani an.* ℥ij. *farinæ fabar.* ℥iv. *incorporentur omnia ſimul, fiat unguentum molle.* Or elſe, ℞. *mucilag. ſeminis fœnugr. in aceto extract. quantum volueris, cui miſce mellis quantum ſufficit* ; let them be boiled together until they acquire the conſiſtence of an ointment. Theſe things ſhall be changed, as often as need ſhall ſeem to require. Alſo an anodyne and diſcuſſing fomentations are good to reſolve ; as this, ℞ *fol. rutæ, ſalv. roriſmar. an.* m. j. *bulliant cum aceto & vino* ; and ſo make a decoction for a fomentation, which you may uſe not only in a cold Gout, but alſo in a hot, becauſe it reſolveth and ſtrengtheneth the part by aſtriction, and freeth it from the defluxion : you muſt have a care that the medicines which are uſed to pains of the Gout be changed now and then. For in this kind of diſeaſe that remedy which did good a little before, and now availeth, will in a ſhort time become hurtful.

Diſcuſſing fomentations.

Remedies muſt be often changed in the Gout.

But if the the contumacy and exceſs of the pain be ſo great, that it will not yield to the deſcribed medicines ; then it is fit, becauſe the diſeaſe is extreme, to uſe (according to *Hippocrates* counſel) extreme, ſuch are are thoſe which follow. ℞ *axungiæ gallinæ, olei laurini maſtic. & euphorb. an.* ℥j. *pulv. euphorb. & pyreth. an.* ʒj. *fiat litus* ; herewith let the part be rubbed every day, for it is a very effectual medicine. For *Euphorbium* and Pellitory by their heat attenuate and reſolve, the capons greaſe and oil of bays relax, the oil of maſtich ſtrengtheneth the part and hindreth a new defluxion. Alſo there is made a very anodyne ointment of oil of Foxes, wherein earth worms, the roots of elecampane and bryony have been boiled, with a little turpentine and wax ; this ſoftens, attenuates and reſolves the cold humor impact in the joints. Or elſe, ℞ *ſeminis ſinapi pulviſerati, & aceto acerrimo diſſoluti,* ℥iij. *mellis anacardani* ℥ij. *aquæ vitæ* ℥j. *ſalis com.* ʒij. let them be all mixed together, and applied to the pained part. Or, ℞ *picis nigræ,* ℥iij. *terebinth. venetæ* ℥j. *ſulphuris vivi ſubtiliter pulveriſati* ℥iij. *olei quantum ſufficit, liquefiant ſimul, fiat emplaſtrum* ; let it be ſpread upon leather, and laid upon the part for two or three days ſpace, if the patient perceive any eaſe thereby ; if otherwiſe, let it be changed as we ſaid before. Some for the ſame purpoſe apply nettles thereto, and preſently after wath the part in the ſea or ſalt water. Others foment the part with vinegar wherein pigeons have been boiled. A veſicatory made of very ſower leaven, *cantharides*, and a little *aqua vitæ* is very powerful to evacuate the conjunct matter. For thus the malign and virulent *ſerum*, or whayiſh humor is let out, whence follows ſome caſe of the pain. Now there are ſome gouty pains, which cannot be leſſened or aſſwaged unleſs by remedies more powerful than the diſtemper, therefore veſicatories ought not to be rejected, ſeeing that the Ancients in this affect have alſo made uſe of actual cauteries, as we ſhall ſhew hereafter. *Chriſtopher Andreas* in his book termed *Oecoitarie* [that is, domeſtick phyſick] much commends Oxdung wrapped in cabbage or vine-leaves, and roaſted in the embers, and ſo applied hot to the grieved part.

A great diſcuſſer.

An Anodyne.

A veſicatory againſt the contumacy of the conjunct matter.

CHAP. XVI.

Of local medicines to be applied to a hot or ſanguin Gout.

What repercuſſives are here required.

HEre muſt we in the beginning make uſe of repercuſſives, ſuch as are cold and dry, that they may contend with the morbifick matter by both their qualities ; alſo let them be aſtrictive, ſo to add ſtrength to the part. But I would have you always to underſtand that you muſt firſt premiſe general medicines. ℞ *albuminum ovorum* nu. iv. *ſucci lactucæ & ſolani an.* ℥j. *aq. roſar.* ℥ij. *incorporentur ſimul, & fiat linimentum ſæpius renovandum.* Others take the meal of barly, lentils, *acatia*, oil of roſes, myrtles, and with a little vinegar they make a cataplaſm ; Or, ℞. *ſumach. myrtillorum, boli arm. an.* ʒ ß. *acaciæ, corticum granat. balauſt. an.* ʒij. *aq. plantag. & roſar. an.* ℥iij. *ol. roſati* ℥j ß. *aceti* ℥ij. *farinæ hordei & lentium quantum ſatis erit, fiat cataplaſma.* This is very excellent and effectual to ſtay or hinder phlegmonous and eryſipelatous tumors. Alſo you may make a cataplaſm *ex mucagine Cidoniorum in aquâ roſarum extractâ, caſſia fiſtula, oleo roſato, & aceto :* Or, ℞ *pampinorum vitis viridium,* m. ij. *terantur & bulliant in oxycrato ex aqua fabrorum, cui adde ſumach. conquaſſat.* ʒj. *olei roſat.* ℥ij. *farinæ hordei quantum ſufficit, fiat cataplaſma.* Or elſe, ℞ *ſucci ſempervivi, hyoſcyami, portulacæ an.* ℥iv. *corticum mali granati* ℥j ß. *farinæ hordei* ℥v. *vini auſteri quantum ſufficit, fiat cataplaſma* ; this is much commended, for it hath entring thereinto wine and the pomgranate pill, which both are very great aſtrictives ; and the juices are exceeding cooling, the meal alſo hinders and thickens the ſanguin humors that are ready to flow down, and make the medicine of a good conſiſtence. Another : ℞ *fol. hyoſcyami & acetoſæ an.* m. j. *involvantur papyro, & ſub cineribus coquantur, mox cum unguento populeon, aut roſat.* ℥ij. *incorporentur* ; and then lay this Cataplaſm thus made warm unto the part. Another : ℞. *florum hyoſcyami* ℔ ij. *ponantur in phiala vitreata, & reconde in fimo equino donec putruerint, accipe ex putredine* ℥ij. *in quibus diſſolve olei de junipero* ℥ ß. *fiat linimentum ad uſum.* Others beat pulp of a Gourd or Citrul in a mortar, and ſo apply it. Another : ℞ *mucilag. ſem. pſilii, & cydon. extract. in aq. roſar. & ſolani an.* ℥iv. *olei roſati*

An excellent aſtringent cataplaſm.

omphacini

omphacini ʒiii. *vini granat.* ʒi. *vitellos ovor. cum albumine* nu. iii. *camphoræ* ʒi. *incorporentur simul, fiat linimentum.* Or elſe, ℞. *ol. roſat. omphacini* ʒiv. *album ovorum cum vitellis* nu. vi. *ſucci plantag. & ſolani an.* ʒi. *farinæ hordei* ʒiii. *incorporentur ſimul, fiat cataplaſma.* Or, ℞. *farinæ faharum & hordei an.* ʒiii. *olei roſati,* ʒii. *oxycrati quantum ſufficit, coquantur ſimul, fiat cataplaſma.* Another, ℞. *mucilag. cent. pſilii.* ʒiv. *ol. roſati* ʒii. *acet.* ʒi. *vitellos ovorum,* nu. iii. *croci* ϑi. *miſce. Pliny* reporteth that *Sextus Pomponius* the Governour of the hither-Spain, as he overlooked the winnowing of his corn, was taken by the pain of the Gout in his feet, wherefore he covered himſelf with the Wheat above his knees, and ſo was eaſed, his feet being wonderfully dryed; and he afterwards uſed his kind of remedy. *Lib. 22. cap. 25.*

It is note-worthy, which often happeneth, that the pain cannot be altogether eaſed by ſuch remedies, by reaſon of the abundance of blood impact in the part; wherefore it muſt be evacuated: which I have done in many with good ſucceſs, opening the vein which was moſt ſwelled and nigh to the affected part; for the pain was preſently aſſwaged. Neither muſt we too long make uſe of repercuſſives; leſt the matter become ſo hardned, that it can ſcarce be afterwards reſolved, as when it ſhall be concrete into knots and plaſter-like-ſtones: reſolving medicines are to be mixed with repercuſſives conveniently applyed, ſo to diſcuſs the humor remaining as yet in the part, whereof ſhall be ſpoken in the following Chapter.

Phlebotomy to evacuate the conjunct matter, and aſſwage pain.

CHAP. XVII.

Of Local medicines for a cholerick Gout.

THe repercuſſives that muſt firſt be uſed in this kind of Gout ought to be cold and moiſt that ſo they may reſiſt both the qualities of choler; ſuch are the leaves of night-ſhade purſlain, houſ-leek, henbane, ſorrel, plantain, poppy, cold water and the like, whereof may be made divers compoſitions. As, ℞. *ſucci hyoſcyami, ſempervivi, lactuc. an.* ʒii. *farin. hordei* ʒi. *olei roſati* ʒii. *agitando ſimul fiat medicamentum*; Let it be applyed and often changed, for ſo at length it will aſſwage the inflammation. Some think the brain of a hog mixed with white ſtarch, or barly-meal and oil of roſes, an excellent medicine. The leaves of mallows boiled in water, and beaten with a peſtle, and applied, aſſwage pain. ℞. *mucilag. ſem. pſilii extract. in aq. ſolani, vel roſarum* ʒii. *farin. hordei* ʒi. *aceti q. ſ. fiat linimentum.* Or elſe, ℞. *unguent. roſat. meſue, & populei an.* ʒiii. *ſucci melonum* ʒii. *alb. ovorum,* nu. iii. *miſceantur ſimul pro litu.* Alſo a ſponge dipped in oxycrate, and preſſed out again and applied thereto doth the ſame. Or elſe, ℞. *fol. caulium rub.* m. ii. *coquantur in oxycrato & terantur, adde ovorum vitellos tres, olei roſati* ʒiii. *farinæ hordei quantum ſufficit, fingantur cataplaſma.* Alſo you may take the crude juice of cole-worts, dane-weed, and roſes beaten and preſſed out, and of theſe incorporated with oil of roſes and barly-meal make a cataplaſm. In winter-time, when as theſe things cannot be had green, you may uſe *unguent. infrigidans Galeni & populeon.* Or elſe, ℞. *ceræ albæ* ʒi. *croci* ϑi *opii* ϑiv. *olei roſati quantum ſufficit, macerentur opium & crocus in aceto, deinde terantur & incorporentur cum cera & oleo, fiat ceratum*; ſpread it upon a cloth, and lay it upon the part, and all about it, and let it be often renewed. Some cut frogs open and apply them to the grieved part. It is confirmed by ſundry mens experience, that pain of the *Sciatica*, when it would yield to no other remedy, to have been aſſwaged by anointing the affected part with the mucous water or gelly of Snails, being uſed for the ſpace of ſeven or eight days; truth whereof was aſſured me by the worthy Gentleman the Lord of *Longeman*, a man of great honeſty and credit, who himſelf was troubled for ſix months ſpace with the *Sciatica*. This water is thus made, Take fifty or ſixty red Snails, put them in a copper-pot or kettle, and ſprinkle them over with common ſalt, and keep them ſo for the ſpace of a day; then preſs them in a coarſe or hair cloth: in the expreſſed liquor dip linnen rags and apply them ſo dipped to the part affected, and renew them often. But if there be great inflammation, the Snails ſhall be boiled in Vinegar and Roſe-water They ſay that Citrons or Oranges boiled in Vinegar, and beaten in a mortar, and incorporated with a little barly or bean flower, are good againſt theſe pains. Or elſe, ℞. *pomorum coctorum in lacte* ℔. i. *butyri* ʒi. *vitellos ovorum,* nu. ii. *aceti* ʒi. *fiat cataplaſma.* There are ſome who take cheeſ-curd newly made, and mix it in a mortar with oil of Roſes and barly-meal, and ſo apply it; it repreſſeth inflammation and aſſwageth pain. Others mix *caſſia* newly extracted forth of the cane, with the juice of Gourds or Melons. Others apply to the part the leaves of Coleworts, and Dane-weed or Smallage, or all three mixed together and beaten with a little Vinegar. Others macerate or ſteep an ounce of linſeed in Wort and make the mucilage extracted therefrom into a Cataplaſm with ſome oil of Roſes and barly-meal. Some put oil of poppies to the pulp of Citrulls or Gourds being beaten, and ſo incorporate them together, and apply it.

What repercuſſives are here required.

A cerate with *opium*.

The water of Snails.

This following medicine hath its credit from a certain Gaſcoin of *Baſas* that was throughly cured therewith, when as he had been vexed long and much with gouty pains, above the common cuſtom of ſuch as are troubled with that diſeaſe. Thus it is; Take a great ridg-tile thick and ſtrong, and heat it red hot in the fire, then put it into ſuch another tile of the ſame bigneſs, but cold, leſt it ſhould burn the bed cloths, then forthwith fill the hot one with ſo many Dane-wort-leaves, that the patient may ſafely lay the affected part therein without any danger of burning it. Then let the patient endure the heat that comes therefrom, and by ſweat receive the fruit thereof, for the ſpace of an hour, ſubſtituting freſh Dane-wort-leaves, if the former become too dry; as alſo another hot tile, if the former ſhall grow too cold before the hour be ended. This being done, let the part be dried with warm and dry linnen cloths. Uſe this particular ſtove for the ſpace of fifteen days, and that in the morning faſting; afterward anoint the part with this following ointment. ℞. *ſucci ebuli* ℔. ʃ. ß. *olei com.* ℔. ʃ. *miſceantur ſimul*, and let them be put into a ſtraight mouthed glaſs, and well luted up; then let it boil in *balneo Mariæ*, being firſt mixed with ſome wine, until the half thereof be conſumed, for the ſpace of ten or twelve hours, then let it cool, and

An hiſtory.

A particular ſtove.

An ointment of the juice of Dane-wort.

and ſo keep it for uſe, adding thereto in the time of anointing, ſome few drops of *aqua vitæ*. It may be anointed twice or thrice in a day, long after meat. Moreover; the roots and leaves of Dane-wort boiled in water, beaten and applyed aſſwage pain; the oyl thereof chymically extracted performs the ſame.

When to uſe narcoticks.

But if the contumacious pain cannot be mitigated by the deſcribed remedies, and becoming intolerably hot and raging, make the patient almoſt to ſwoun; then muſt we flie to Narcoticks; For although the temper of the part may be weakned by theſe, the native heat diminiſhed or rather extinguiſhed; yet this is a far leſs inconvenience than to let the whole be waſted by pain. Theſe things have a powerful refrigerating and drying faculty, taking away the ſenſe of the pain, and furthermore, incraſſate, thin acrid and biting humours, ſuch as cholerick humors are. Wherefore if the matter which cauſeth the pain be thick, we muſt abſtain from Narcoticks, or certainly uſe them with great caution. ℞. *micæ panis ſecalini parum cocti in lacte*, ʒii. *vitellos ovorum*, nu. ii. *opii* ʒi. *ſuccorum ſolani, hyoſcyami, mandragoræ, portulacæ, ſempervivi, an.* ʒi. let them be mixed together and applied, and often changed. Or elſe, ℞. *fol. hyoſcyami cicutæ, acetoſ. an.* m. i. *bulliant in oxycrato & contundantur, cumque vitellis ovorum crudorum* nu. ii. *& olei roſat.* ʒii. *farin. hordei quod ſatis ſit, incorporentur, fiat cataplaſma*; with the uſe thereof I am accuſtomed to aſſwage great pains. Or elſe, ℞. *opii.* ʒiii. *camphor.* ʒ ß, *olei nenuph.* ʒi. *lactis* ʒii. *unguent. roſ. Galeni* ʒiv. *incorporentur ſimul in mortario, applicentur.* Moreover, cold water applied and dropped upon the part drop by drop, is narcotick and ſtupefactive, as *Hippocrates* affirmeth, *Aphor.* 29. *Sect.* 5. for a moderate numneſs mitigateth pain. There is alſo another reaſon why it may be profitably uſed in all pains of the Gout, for that by repelling the humors, it hindereth their defluxion into the part. Mandrag-apples boiled in milk, and beaten, do the ſame thing; alſo the leaves of henbane, hemlock, lettuce, purſlain, being ſo boiled do the ſame. If any deſire to uſe theſe more cold, he muſt apply them crude, and not boiled.

A cataplaſm with *opium*.

But the exceſs of pain being mitigated, we muſt deſiſt from the uſe of ſuch narcoticks, and they muſt rather be ſtrengthned with hot and digerating things; otherwiſe there will be danger leſt it be too much weakned, the temper thereof being deſtroyed, and ſo afterwards it may be ſubject to every kind of defluxion. Wherefore it ſhall be ſtrengthned with the formerly diſcuſſing fomentations, and theſe enſuing remedies. As, ℞. *gum. ammoniaci & bdelii an.* ʒi. *diſſolvantur in aceto, & paſſentur per ſetaceum, addendo ſtyracis liquid. & farin. fœnugr. an.* ʒ ß. *pulv. ireos.* ʒiv. *olei chamæm.* ʒii. *pulveris pyrethri* ʒii. *cum cera, fiat emplaſtrum molle.* Or elſe, ℞. *rad. emulæ, ebuli, althææ an.* ℔ ß. *ſem. lini, fœnugr. an.* ʒii. *ficuum ping.* nu. xx. *coquantur completè & trajiciantur per ſetaceum, addendo pul. euphorb.* ʒii. *olei chamæm. aneth. & rutacei, an.* ʒiii. *medullæ cervi* ʒiv. *fiat cataplaſma.* Yet you muſt uſe moderation in diſcuſſing, leſt the ſubtler part of the impact humor being diſcuſſed, the groſſer part may turn into a ſtony conſiſtence, which alſo is to be feared in uſing repercuſſives.

How to mend the harm done by Narcoticks. Diſcuſſers.

A mean to be uſed in diſcuſſing

Baths aſſwage the pain of the Gout.

I alſo omitted, that according to the opinion of the Ancients, baths of freſh-water, wherein cooling herbs have been boiled, uſed three hours after meat, conduce much to the aſſwaging of pain; for ſo uſed, they are more convenient in cholerick natures, and ſpare bodies, for that they humect the more, and quickly digeſt the thin and cholerick, and conſequently acrid vapors, the pores being opened, and the humors diſſipated by the gentle warmneſs of the bath. After the bath the body muſt be anointed with *hydrelium*, or oil and water tempered together, leſt the native heat exhale and the body become more weak. Meats of more groſs juice are more convenient, as beef, ſheeps-feet, and the like, if ſo be that the patient can digeſt them, for theſe inſpiſſate the cholerick blood, and make it more unfit for defluxion.

How meats of groſs juice are profitable.

CHAP. XVIII.

What remedies muſt be uſed in pains of the joints proceeding of a diſtemper only, without matter.

An hiſtory.

PAins alſo happen in the joints by diſtemper without any matter, which though rare, yet becauſe I hapned once to feel them, I have thought good to ſhew what remedies I uſed againſt them. I once earneſtly buſied in ſtudy, and therefore not ſenſible of ſuch external injuries as might befal me; a little wind coming ſecretly in by the crannies of my ſtudy, fell upon my left Hip; at length wearied with ſtudy, as ſoon as I roſe up to go my way, I could not ſtand upon my feet, I felt ſuch bitter pain without any ſwelling or humor which might be diſcerned. Therefore I was forced to go to bed, and calling to mind, that cold, which was abſolutely hurtful to the nerves, had bred me that pain, I attempted to drive it away by the frequent application of very hot cloths, which though they ſcorched and bliſtered the ſound parts adjoining thereto, yet did they ſcarce make any impreſſion upon the part where the pain was ſetled, the diſtemper was ſo great, and ſo firmly fixed therein. And I laid thereto bags filled with fried oats and millet, and dipped in hot red wine; as alſo ox-bladders half filled with a decoction of hot herbs. And laſtly, a wooden diſh almoſt filled with hot aſhes, covered over with ſage, roſemary, and rue lightly bruiſed, and ſo covered with a cloth, which, ſprinkled over with *aqua vitæ*, ſent forth a vapor which aſſwaged the pain. Alſo brown bread newly drawn out of the oven, and ſprinkled over with roſe-water, and applied, did very much good. And that I might more fully expel this hurtful cold, I put ſtone bottles filled with hot water to the ſoals of my feet, that the brain might be heated by the ſtraitneſs and continuity of the nerves. At length, by the help of theſe remedies, I was very well freed from this contumacious diſtemper, when it had held me for the ſpace of four and twenty hours.

Hip. ap. 10. *ſect.* Divers remedies for pain ariſing from a cold diſtemper without matter.

A fuliginous vapour ſometimes the cauſe of the Gout.

There is another kind of Gouty pain ſometimes cauſed by a certain excrementitious matter, but ſo thin and ſubtle that it cannot be diſcerned by the eyes. It is a certain fuliginous or ſooty vapor, like

like to that which passeth from burning candles or lamps, which adheres and concretes to any thing that is opposed thereto; which being infected by the mixture of a virulent serous humor whithersoever it runneth, causeth extreme pain, some whiles in these, and otherwhiles in other joints, unless you make a way therefore, when as it seeketh passage forth, which must be done by horns cupping glasses, vesicatories, cauteries, or other the like art.

CHAP. XIX.

What is fit to be done after the fit of the Gout is over.

How to strengthen the joints.

IT is convenient when the pain is asswaged, that you strengthen the joints. Now, to strengthen them is not only to bind and dry, but wholly to amend the weakness left in the part by the disease, that is to discuss the humor, if any superfluity thereof remain; but to humect the part; if the moisture be exhausted and dryed up. But such as are troubled with the Gout, after they are freed from their pain, have notwithstanding such impotency of their joints that they cannot go of a long time after; for that the nerves and tendons which are in great number in the feet, being moistned with much Phlegm, are so relaxed, that they can no more sustain or bear themselves upon their feet, than paper when it is wet can be made stand. Wherefore, that they may recover the use of their feet, the impacted humor must by all means be discussed, and spent with fomentations, cataplasms, drying and astringent emplasters. You may use the formerly described fomentation, encreasing the quantity of alum and salt, and adding thereto a like quantity of *sulphur vivum*: then the following emplaster shall be applyed thereto. ℞. *mas. emplast. contra rupturam* ʒiv. *tereb.* ʒii. *pulv. ros. rub. nucum cupress. gallarum, gran. myrtil. & fol. ejusdem, thuris, mastich. & caryophyl. an.* ʒi *malexentur omnia simul, manibus injunctis oleo myrtino & mastichino, fiat emplastrum.* Let it be spread upon leather to a just bigness, and applied to the top and soal of the foot. Draw over the plaster, and the whole leg a stocking made of a tanned-dogs-skin; this emplaster strengthneth the nerves, draweth forth the humor impact therein, and intercepts the defluxion. But the Dog-skin-stocking preserveth the native heat of the part, and for that it bindeth, hindreth the defluxion into the feet.

Remedies for the weakness left in the joints after the pain is gone.

The benefit of a dog-skin stocking.

CHAP. XX.

Of the Tophi, *or knots which grow at the joints of such as are troubled with the Gout.*

SOme that are troubled with the Gout, have knotty bunches growing in their joints, which by the ancients were called *Tophi*. These are generated by the congestion of gross viscid and crude Phlegm, with a little admixtion of an acrid and cholerick humor. These matters remain setled in the part, for that it being too weak cannot digest and depress them; wherefore being there impact, they easily concrete into a certain plaster-like or chalk-like substance, whilest by the adventitious and burning heat caused by pain, and the gouty malignity, their more subtle part is dispersed, but the grosser subsides. Yet sometimes the unfit application of repercussive or discussive medicines is a cause of the generation of these *Tophi*. For by the former, the impact matter is incrassated and gathered together; but by the latter, the subtle part being discussed, the remnant that subsides, concretes into *Tophi*. Those medicines which are made to mollifie, ought to have a moderately heating, and humecting faculty, that they may diffuse, and as it were dissolve the impact matter; such is warm water, the decoction of emollient herbs, the decoction of calves or sheeps entrails, heads and feet: after these or the like fomentations, you shall use the following medicine. ℞. *axungiæ human. anseris & gallinæ, medul. cervin. an.* ʒii. *tereb. ven.* ʒi. *aq. vitæ parum, ceræ quantum sufficit, fiat unguentum molle.* Then this which followeth will be good. ℞. *rad. alth. liliorum, bryon. lapath. acuti, an.* ℥iv. *coquantur complete, & trajiciantur per setaceum; adde gum. ammon. bdel. galb. opopanacis in aceto dissolutorum* ʒi. *medul. cervin.* ʒiß. *incorporentur simul, & applicentur.* Or else, ℞. *olei liliorum, amygd. dul. medullæ cruris cer. an.* ʒii. *mucag. sem. lini, alth. fœnugr. an.* ʒi. *ceræ quantum sufficit; fiat ceratum.* Or else, ℞. *empl. de Vigo cum mercurio, & cerat. de æsipo humidâ descript. Philagrii, an.* ʒii. *malexentur simul cum oleo lilior. fiat massa.* Or else, ℞. *gum. ammon. opopan. galb. bdel. dissolutorum in aceto an.* ʒii. *panno linteo calatis, adde pulv. sulph. nitr. sinapi, pyrethri, an.* ʒß. *styracis liq. & axung. hum. an.* ʒi. *res. pini, tereb. ven. an.* ʒß. *ceræ quantum sufficit, fiat ceratum molle.* This which follows is thought most effectual in the opinion of *Galen* and *Avicen*. ℞. *pedes porcel. bene salsos, nu.* iv. *veterem pernam cum illis coque; addendo sub finem, radicis bryoniæ, lapath. acut. an.* ʒiii. *axungiæ tauri, & medul. cervi, an.* ʒi. *cum caseo putrefacto fiat empl. molle ad usum.* This which follows is also most effectual. ℞. *casei acris & putrefacti,* ʒiv. *pulv. sulph. vivi euphorb. & pyreth. an.* ʒiii. *decoctionis veteris pernæ & porcellorum quod sufficit ad incorporandum, ducantur in mortario, & fiat empl. ad usum.* Or else, ℞. *spumæ nitri,* ʒvi. *tereb.* ʒii. *olei veteris, lixivii, quo lanæ pileorum lavantur, & ceræ quantum sufficit, fiat ceratum satis molle.* After the use of emollients, a fumigation shall be made in this manner: Heat a cogle-stone, mill-stone or brick red hot in the fire, take it forth, and cast upon it a sufficient qnantity of very sharp vinegar, and *aqua vitæ*, the rising vapor shall be diligently received by the affected member, for this hath a faculty to attenuate and cut gross, viscid, and plaster-like matter, yea also, and to break the skin; yet that is broken oft times of its own accord without the help of either medicine or instrument. To conclude, those medicines which are good to mollifie scirrhous tumors, the same are also good to soften the gouty knots and *tophi*. But we must note; that these knotty bunches are sometimes suppurated, not truly by the impact and plaster-like matter, but by a new defluxion coming on a sudden, and then it is necessary to make way for the contained matter, which being done, first there cometh forth an humor like milk, then a plaster-

Whence the *Tophi* are generated.

The unfit application of discussive and repercussive medicines cause the *Tophi*.

Mollifying medicines.

Lib. 10. simp. c. 7 sect. 2. 2 libri 3. tract. 2. c. 21.

An effectual fumigation.

plaſter-like matter, then it leaves behind it an ulcer to be cured by applying thereto *empl. gratia Dei*, and others as the Surgeon ſhall think fit.

CHAP. XXI.

Of Flatulencies contained in the joints, and counterfeiting true Gouts, and of the remedies to be uſed thereto

In what joints flatulencies are chiefly generated.

OFt-times there is ſmall quantity of humor, which moves the pain of the Gout but much flatulency mixed therewith, eſpecially in great joints, as in the huckle or hip-bone, and the knees; they ſometimes cauſe ſo great diſtention, that they drive the heads of the bones forth of their places.

Signs of flatulencies.

You may partly underſtand it is ſo, if a tenſive pain afflict the patient with any ſenſe of heavineſs; if when you preſs the tumor with your fingers, the place retain no mark or impreſſion thereof, as happens in an *œdema*; but on the contrary, a flatulent ſpirit lifts it up as it were by renitency, as if one ſhould thruſt a pair of bellows, which are filled with wind; hence the part cannot perform its duty, for that the ſpaces of the joints are poſſeſſed with abundance of flatulencies, ſo that the liberty of motion is intercepted, and the member is kept as it were bound up.

How flatulencies may make you believe there is *pus*, or matter.

Many no very skilful Surgeons, putting their fingers to theſe kind of tumors, ſo that lifting up the one, they preſs down the other, when as they perceive the flatulency, as it were riſing between their fingers, ſuppoſing it to be the motion of *pus*, or matter already generated and flowing up and down, as is uſual in impoſtumes, they have opened it by inciſion; but when as nothing flowed forth, it appeared how much they were deceived, yet in the *interim*, by this their raſhneſs they have cauſed many dangerous ſymptoms: as increaſe of pain, defluxion of humors, by force whereof the bones have been diſlocated, and brought to the patient an incurable lameneſs.

Why hard to cure.

But theſe flatulent Gouts are ſeldom without ſome plegmatick matter; which is neither too crude nor viſcid. Such like flatulencies are not eaſily diſcuſſed, nor at the firſt endeavour, by reaſon of a cold diſtemper which they bring to the part, and the denſity of the membranes and ligaments, by which the articulation is knit and faſtned, ſo that ſcarce any part of that which is there ſhut up, can breath forth of ſuch ſtrait paſſages. Therefore the cure muſt be undertaken with reſolving, diſcuſſing, and drying fomentations; as for example, with a decoction of fennel, aniſ-ſeeds, rue, camomil, melilote, ſage, roſemary, *origanum*, calamints, hore-hound, and the like, boiled in wine with a little lee, roſe-vinegar, and common ſalt. This following ointment ſhall be uſed after the fomentation. ℞ *olei chamæm. aneth. rut. lauri, an.* ℥ij. *cum cerâ albâ, fiat linimentum. addendo aq. vitæ parum.* After you have anointed it, apply thereto this following Cataplaſm. ℞ *flor. cham. melil. aneth. roſ. rub. pulv. an.* m.j. *fol. malv. & abſinth, an.* m.ſ. *furfur.* m.j. *bulliant omnia ſimul cum lixivio, & vino rubro, deinde piſtentur cum medulla panis, & farina fabarum, quantum ſufficit, fiat cataplaſma, addendo ol. roſar. & myrtil. an.* ℥ij. Some highly approve of this following medicine for the waſting of flatulencies. ℞ *axung. ſuil.* ℥iv. *calcis vivæ,* ℥iſ. *terantur diligenter in mortario, & incorporata applicentur.* Or elſe, ℞ *ſtercor. caprar. cocti cum vino & aceto, an.* lbſ. *tereb. venet. & mel. com. an.* ℥ij. *aq. vitæ,* ℥ſ. *pul. rad. Ireos florent. & ſabin. an.* ℥iij. *olei. rut. & aneth. an.* ℥j. *farin. fabarum quantum ſufficit.* Make a cataplaſm to the form of a pultis. Alſo ſtoups dipped in oxycrate, and wrung out, ſhall be applied: in this oxycrate ſhall be boiled wormwood, *origanum*, chamomil, melilote, rue, common ſalt, adding thereto ſome *aqua vitæ*. Then the part ſhall be bound up as ſtraight as the patient can endure it: in concluſion that the native ſtrength may by little and little be reſtored to the part, it ſhall be fomented with lee made of the aſhes of oak-wood and the cuttings of vines, wherein ſhall be boiled ſalt, ſulphur, choice alum; and wetting linnen clothes, or ſtoups therein, and applying them, it ſhall be ſtraitly ſwathed up. Yet if great pain ſhall more cruelly vex the part, then neglecting for a time the proper cure of the diſeaſe, you ſhall withſtand the ſymptom by rubbing the part, and anointing it with ſome diſcuſſing oil laying thereon ſome moiſt wool, and other anodyne things.

CHAP. XXII.

Of the Iſchias, *Hip-gout, or* Sciatica.

Why it hath the moſt grievous ſymptoms.

FOr that the hip-gout in the greatneſs of other cauſes, bitterneſs of pain, and vehemency of other ſymptoms, eaſily exceeds the other kinds of Gout, therefore I have thought good to treat thereof in particular. The pain of the *Sciatica* is therefore the moſt bitter, and the ſymptoms moſt violent for that the dearticulation of the huckle bone, with the head of the thigh-bone, is more deep than the reſt; becauſe alſo the phlegmatick humor which cauſeth it, is commonly more plenteous, cold, groſs, and viſcid, that flows down into this joint: and laſtly, becauſe the *Sciatica* commonly ſucceeds ſome other chronical diſeaſe, by reaſon of the tranſlation and falling down thither of the matter, become malign and corrupt by the long continuance of the former diſeaſe.

The cauſe of the large ſpreading of the pain.

But the pain not only troubles the hip, but entring deep, is extended to the muſcles of the buttocks, the groins, knees, and very ends of the toes, yea often times it vexeth the patient with a ſenſe of pain in the very *vertebra* of the loins, ſo that it makes the patients, and alſo oft-times the very Phyſicians and Surgeons to think it the wind or ſtone-colick. The cauſe of ſuch wandring and diſperſed pain is to be referred to the manifold diſtribution of the nerves which come to that joint from the loins and *holy-bone*, for they are ſent into the muſcles of the buttocks, and ſo diſperſed over the whole leg to the very ends of the toes, as it is ſhewed in our Anatomy. Therefore the pain is largely extended, that is, to what part ſoever a nerve runs which comes from the affected hip. Oftentimes there is no ſwelling, no redneſs, nor diſtemper manifeſt to the eye, by reaſon that the veins are very few which riſe into the ſurface and

skin

skin of this part, and the humor lies, as it were, ſunk in; which is the cauſe that divers times the excrementitious humors mixed with flatulency, run ſo violently into the cavity of this joint, that relaxing the ligaments, as well proper as common, the head of the thigh-bone is eaſily driven out from hence, ſo that it may never be reſtored again, if it remain ſo for any ſpace of time; for that in this time the humor falling down into this cavity, by delay concretes as it were into a ſtony body, and the head of the thigh-bone wears it ſelf another cavity in the neighbouring bone; but the lips of the true cavity, which are griſtly, become more ſtraight and depreſt: and laſtly, all the ligamentous bodies moiſtened with this excrementitious humor become more looſe and weak, whence ſucceed many and moſt grievous ſymptoms; as lameneſs, and the decay not only of the thigh and leg, but at length of the whole body; and laſtly, a ſlow and hectick feaver, which in continuance of time will conſume the Patient for the cauſes formerly mentioned. Therefore let Phyſicians and Surgeons have a care that they reſiſt it at the firſt, and, with ſuch powerful remedies as are mentioned in the following Chapter, hinder the ſpringing up and growth of the formerly mentioned ſymptoms.

The thigh-bone often diſlocated by the *Sciatica*.

CHAP. XXIII.

The cure of the Sciatica.

THough the *Sciatica* be commonly occaſioned by tough phlegm, yet if the patient be ſtrong, and abound with blood, and all things elſe conſent, it ſhall be good to draw blood by opening a vein; for phlebotomy equally evacuates all humors: therefore the falling down of the humors into the part affected, is thereby hindred or retarded. Verily, I have known no ſpeedier remedy to aſſwage the pain of inflammation, than blood-letting, being firſt made on the *Baſilica* of the grieved ſide for revulſions ſake; and then for evacuation of the conjunct matter on the *vena Iſchiadica*, which is at the cut-ſide of the ankle, if the pain of the *Sciatica* be more on the out-ſide; or elſe on the *Sapheia*, which is on the inſide of the ankle, if the inner parts be more pained. The quantity of blood which is to be drawn, muſt be left to the judgment of the Phyſician, without whoſe advice I would attempt nothing in this caſe. Alſo acrid clyſters are good, if there be nothing which may hinder; as ulcers of the guts, or hemorrhoids. ℞ *rad. acor.* ℥ij. *centaur. rut. ſalv. roriſm. calam. origan. puleg. an.* m. ℈. *ſtœchad. arabic. flo. cham. melil. aneth. an.* p. j. *ſem. aniſ. & fœnic. an.* ℥ ℈. *fiat decoctio ad* lb j. *in colatura diſſolve hieræ & diaphen. an.* ʒ ℈. *mellis anthoſ. ſacch. rub. an.* ℥j. *olei liliorum* ℥iij. *fiat clyſter.* Strong purgations are alſo here uſeful, as of *pillul. fœtid. arthritic. Aſſajereth de Hermodactylis*, and others uſed in phlegmatick cauſes. *Electuarium Diacarthami* purgeth choler and phlegm. Often vomitings do not only evacuate the humors, but alſo make revulſion, as we have formerly delivered, Baths and ſweats profit no otherwiſe than a decoction of *Guaiacum* or *Sarſaparilla*. If heat moleſt the part, then foment it with oil of roſes and vinegar, eſpecially if the pain be deep in, for vinegar by its tenuity pierceth to the bottom, and makes way for the oil, which of its own nature is anodyne. After the uſe of general medicines, you ſhall apply attractive and reſolving things: emplaſters of pitch and ſulphur, or of *ammoniacum, euphorbium, terebinthina, propolis, galbanum, bdelium, opopanax*, draw the humor from within to the ſurface or skin. As in like ſort alſo the chymical oil of ſage, roſemary, Pellitory of Spain, and other ſuch like do the ſame, which by reaſon of the tenuity of their ſubſtance, and their ſeparation from earthy impurity, have far more powerful and expedite faculties to penetrate and diſcuſs. Yet muſt you uſe none of all theſe without very good judgment and deliberation, otherwiſe there will be danger of inflammation.

When the *vena Iſchiadica* and *Sapheia* muſt be opened in the *Sciatica*.

Strong purgations in the *Sciatica*.

There may alſo be made fomentations of diſcuſſing and reſolving herbs, as the roots and leaves of dane-weeds, orris, bay and juniper-berries, the ſeeds of fenugreek, anis, fennel, the leaves of ſage, roſemary, chamomil, melilote, elder, and the like, boiled in wine and oil; the following plaſter is much commended by the ancients to digeſt, or reſolve and aſſwage the pain, with this which draws forth thorns, ſplinters, and rotten bones. ℞. *ſem. urtic. mundat. ſpumæ borac. ſalis ammoniaci, rad. ariſtoloch. rotund. colocinth. terebinth. venet. an.* ℥.x. *fœnug. piperis longi, xylobalſam. thur. myrrhæ, adipis cap. gum. pini, an.* ℥.v. *ceræ* lb ℈. *lactis ficus ſylv.* ℥ ℈. *ex omnibus ſecundum artem præparatis cum olei liliorum, & vini generoſi quantitate ſufficiente fiat emplaſtrum.* Let it be applied to the hip. Or, ℞ *ſinapi acerrimo aceto diſſoluti*, ℥ij. *fermenti aceris*, ʒ ℈. *pul. hermodact.* ʒij. *mellis com.* ℥iij. *tereb.* ℥iv. *olei laur. & de ſpica. an.* ℥ij. *far, fœnug.* ʒi ℈. *terræ formicarum cum ovis*, lb j. *fol. laur. ſalv. rut. roriſm. an.* m. ℈. *vermium terreſt. præpar.* lb ℈. The earth with the eggs and worms ſhall be boiled apart with the white wine, and herbs cut in pieces, and theſe being ſtrained out, the reſt of the things ſhall be added according to art, and then it ſhall be applied to the hip. Or elſe, ℞ *rad. enul. camp. ſigil. Salom. bryon. biſmal. an.* ℥ij. *coquantur complete & terantur, trajiciantur per ſetaceum, addendo farin. fœnug. & hordei, an.* ℥j. *olei liliorum, & chamæm. an.* ℥iij. *tereb.* ℥iv. *ceræ quantum ſufficit, fiat cataplaſma.* It reſolves, aſſwageth pain, and calleth forth the humors to the skin. Or elſe, ℞. *rad. ſigil. beatæ Mariæ*, ℥vj. *empl. diachyl. albi*, ʒiv. *croci in aqua vitæ diſſoluti*, ℥ij. *terebinth.* ℥j. *ol. de ſpica nardi quantum ſufficit, fiat empl.* Let it be ſpread upon leather, and applied warm. I have oftentimes ſuddenly aſſwaged the pain of the *Sciatica*, by putting to the pained hip the root of black Briony cut into ſlices, and applied, when the matter was cold. Or elſe, ℞ *ceræ citrin. & tereb. abiet. an.* ℥ij. *liquefiant ſimul in vaſe duplici, & ubi refrixerint, adde pulv. hermodact.* ʒ ℈. *flor. chamæm. irid. flor. an.* ʒiij. *ſpicæ nardi, flor. thymi, an.* ʒij. *interioris cinamomi elect. & ſeminaſturt. an.* ʒij. *croci,* ℈iv. *malaxantur ſimul manibus axungia porci vetere non ſalita unctis, & fiat maſſa empl.* But if the pain be not by this means aſſwaged, then muſt we come to powerful medicines, as to uſe great cupping-glaſſes applied with much flame, and to veſicatories: As, ℞. *cantharid. quibus detractæ ſunt alæ*, ʒii. *ſtaphiſagr.* ℥iij. *ſinapi* ʒi ℈. *fermenti acerrimi* ʒ ℈. *incorporentur ſimul, & fiat veſicatorium.* Alſo bliſters may

Black briony diſcuſſeth.

A ſtrong veſicatory.

The inner rind of Travellers-joy a vesicatory.

may be raised by applying the inner rind of Travellers-joy to the weight of some two drams, a little beneath the grieved part: you must have a care that the ulcers that remain after the skin of the blisters is taken off, do run, and be kept open for some time after, and so more of the humor contained in the part may be drawn away. But if we cannot avail by these means, we must according to *Hippocrates* his counsel, come to the last and extremest remedy. *Such* (saith he) *as are troubled with a long pain of the* Sciatica, *have their hip fall out of joint, their leg consumes, and they become lame, unless they be burnt.* We have also read the same approved by *Celsus*. *It is the last* (saith he) *and most effectual medicine in longer diseases, to cauterize with hot irons, the skin of the hip in three or four places; and then not heal up these ulcers or fontanels as soon as may be, but to keep them open, by putting thereinto bullets of gold, or silver, or pills of gentian, or wax melted and wrought up with the powder of vitriol, mercury, and the like catheretick, until the affect against which we use this remedy, be helped, for by this means many have been helped.* Therefore three or four actual canteries, or hot irons shall be thrust in, about the joint of the hip, that they may enter into the flesh some fingers breadth, yet so that you shun the nerves. Cauteries here do good, for that by heating the part, they heat and dissolve the cold humors, they cut, attenuate, and draw forth the gross, and viscid, so that they flow out by the ulcers, together with the quitture. Over and besides, the ligaments are strengthened by their cicatrization, and their looseness helped, and by this means the whole part is notably corroborated.

Hip. ult. sect. 6.

Lib. 4. cap. 22.

The use of cauteries in the *Sciatica*.

CHAP. XXIV.

Of the flatulent convulsion, or convulsive contraction, which is commonly called by the French, Gout Cramp, *and by the English,* The Cramp.

What the Cramp is.

THat which the French call *Gout Cramp*, we here intend to treat of, induced thereto rather by the affinity of the name, than of the thing; for if one speak truly, it is a certain kind of convulsion generated by a flatulent matter, by the violence of whose running down or motion, oft-times the neck, arms, and legs are either extended, or contracted into themselves with great pain, but that for a short time. The cause thereof is a gross and tough vapor, insinuating it self into the branches of the nerves, and the membranes of the muscles. It takes one on the night, rather than on the day, for that then the heat and spirits usually retire themselves into the entrails and centre of the body; whence it is that flatulencies may be generated, which will fill up, distend and pull the part whereinto they run, just as we see lute-strings are extended. This affect often takes such as swim in cold water, and causeth many to be drowned, though excellent swimmers, their members by this means being so straightly contracted, that they cannot by any means be extended: For the skin, by the coldness of the water is contracted and condensed, and the pores thereof shut, so that the engendred flatulencies have no passage forth. Such as give themselves to drunkenness and gluttony, or sloth and idleness, are usually more frequently troubled with this disease, by reason of their heaping up of crudities. Therefore it is cured by moderate diet, and ordering of the body, and exercise of each part thereof; for thus they gather strength, and the generation of the flatulent matter is hindred, In the very time when it takes one, the patient shall be cured by long rubbing with warm cloths, and *aqua vitæ*, wherein the leaves of sage, rosemary, thyme, savory, lavendar, cloves, ginger, and the like discussing and resolving things have been infused. The extension and flexion of the members or joints, and walking, are also good.

The cause thereof.

Who subject thereto.

The cure.

The end of the Eighteenth Book.

BOOK XIX.

Of the LUES VENEREA, and those Symptoms which happen by means thereof.

CHAP. I.

What the *Lues Venerea* is.

THe French call the *Lues Venerea* the *Neapolitan disease*; the Italians and Germans (as also the English) term it the *French disease*; the Latines call it *Pudendagra*: others name it otherwise. But it makes no great matter how it be called, if the thing it self be understood: Therefore the *Lues Venerea* is a disease gotten or taken by touch, but chiefly that which is in unclean copulation; and it partakes of an occult quality, commonly taking its original from ulcers of the privy parts, and then further manifesting it self by pustles of the head, and other external parts; and lastly, infecting the entrails and inner parts, with cruel and nocturnal tormenting pain of the head, shoulders, joints, and other parts. In process of time, it causeth knots and hard *tophi*: and lastly, corrupts and fouls the bones, dissolving them, the flesh about them being oft-times not hurt; but it corrupteth and weakneth the substance of other parts, according to the condition of each of them, the distemper and evil habit of the affected bodies, and the inveteration or continuance of the morbifick cause. For some lose one of their eyes, others both: Some lose

What hurt it doth to the Body.

loſe a great portion of their eye-lids, other ſome look very gaſtly, and not like themſelves, and ſome become ſquint-eyed. Some loſe their hearing, others have their noſes fall flat, the palat of their mouths perforated with the loſs of the bone *Ethmoides*, ſo that inſtead of free and perfect utterance, they faulter and fumble in their ſpeech. Some have their mouths drawn awry, others their yards cut off, and women a great part of their privities tainted with corruption. There be ſome, who have the *Urethra* or paſſage of the yard obſtructed by budding caruncles, or inflamed puſtles, ſo that they cannot make water without the help of a Catheter, ready to die within a ſhort time, either by the ſuppreſſion of the urine, or by a gangrene ariſing in theſe parts, unleſs you ſuccor them by the amputation of their yards. Others become lame of their arms, and other ſome of their legs, a third ſort grow ſtiff by the contraction of all their members; ſo that they have nothing left them ſound but their voice, which ſerveth for no other purpoſe but to bewail their miſeries, for which it is ſcantly ſufficient. Wherefore ſhould I trouble you with mention of thoſe that can ſcantly draw their breath by reaſon of an *Aſthma*: or thoſe whoſe bodies waſte with an hectick feaver, and ſlow conſumption? it fares far worſe with theſe, who have all their bodies deformed by a leproſie ariſing there-hence, and have all their throttles and throats even with putrid and cancrous ulcers; their hair falling off from their heads, their hands and feet cleft with tetters and ſcaly chinks: neither is their caſe much better, who, having their brains tainted with this diſeaſe, have their whole bodies ſhaken by fits of falling-ſickneſs; who troubled with a filthy and curſed flux of the belly, do continually caſt forth ſtinking and bloody filth. Laſtly, there are no kinds of diſeaſes, no ſorts of ſymptoms, wherewith this diſeaſe is not complicate, never to be taken away, unleſs the virulency of this murrain be wholly taken away, and impugned by its proper antidote, that is, *argentum vivum*.

The Leproſie ſometimes the off ſpring of the *Lues Venerea*.

CHAP. II.

Of the cauſes of the Lues Venerea.

THeſe are two efficient cauſes of the *Lues venerea*; the firſt is, a certain occult and ſpecifick quality which cannot be demonſtrated; yet it may be referred to God, as by whoſe command this hath aſſailed mankind, as a ſcourge or puiſhnent to reſtrain the too wanton and laſcivious luſts of unpure whoremongers. The other is an impure touch or contagion, and principally, that which happeneth in copulation, whether the man or woman have their privities troubled with virulent ulcers, or be moleſted with a virulent ſtrangury (which diſeaſe crafty Whores colour by the name of the whites) the malignity catcheth hold of the other; thus a woman taketh this diſeaſe by a man, caſting it into her hot, open and moiſt womb; but a man taketh it from a woman, which for, example ſake, hath ſome ſmall while before received the virulent ſeed of a whoremaſter polluted with this diſeaſe, the mucous *ſanies* whereof remaining in the wrinckles of the womans womb, may be drawn in by the pores of the ſtanding and open yard, whence ſucceed malign ulcers, and a virulent ſtrangury. This virulency, like a torch or candle ſet on fire, will by little and little be propagated and ſent by the veins, arteries and nerves to the noble parts; whoſe malignity a ſtrong liver not enduring, by the ſtrength of the natural expulſive faculty, will ſend it into the groins, whereon follow abſceſſes, therefore called *Venereal Buboes*. Theſe if they return in again, and caſt not forth matter by being opened, will by their falling back into the veins and arteries, infect the maſs of the blood by the like tainture, and thence will enſue the *Lues Venerea*: Yet this diſeaſe may be got by a more occult manner of touch, as by breathing only. For it is not altogether beſide reaſon and experience, that a woman long troubled with this diſeaſe, may by importunate and often kiſſing, transfuſe malignity into a child; for the tender and ſoft ſubſtance of a little child may be altered, infected, and by little and little corrupted by receiving of filthy, and in their whole kind malign vapors. For it is known, and now vulgarly believed, that mid-wives, by receiving the child of a woman infected with this diſeaſe, have got this affect, the malignity being taken and drawn into their bodies through the pores of their hands by the paſſage of the veins and arteries. Neither doth it ſpare any condition, ſex, nor age of men: for not only whoſoever uſe copulation, but ſuch as only lie with them, may be taken with this virulency; yea verily, if they only lie in the ſheets or coverings which retain his ſweat, or the virulency caſt forth by an ulcer. The ſame danger may aſſail thoſe who ſhall drink in the ſame veſſel after ſuch as are troubled with this diſeaſe: For by the impure touch of their lips, they leave a virulent *ſanies* and ſpittle upon the edges of the cup, which is no leſs contagious in its kind, than the virulency of leprous perſons, or the ſome of mad dogs. Wherefore it is no marvel if children nurſed by an infected nurſe, draw in the ſeeds of this diſeaſe together with the milk, which is only blood whitened in the breaſts; or infected ſucking children by their hot and ulcerated mouths, may transfuſe this malignity into the body of the nurſe, by the rare, looſe and porous ſubſtance of the dugs which it frequently ſucketh.

The *Lues Venerea* the ſcourge of Whoremongers.

Venereal buboes returning inagain, occaſion the *Lues venerea*.

The *Lues venerea* may be got by the only communication of vapor.

How nurſes may infect children, and they their nurſes.

This following hiſtory is very memorable to this purpoſe. A certain very good Citizen of this City of *Paris* granted to his wife, being a very chaſte woman, that conditionally ſhe ſhould nurſe her own child, of which ſhe was lately delivered, ſhe ſhould have a nurſe in the houſe to eaſe her of ſome part of the labour: by ill hap, the nurſe they took was troubled with this diſeaſe; wherefore ſhe preſently infected the child, the child the mother, the mother her husband, and he two of his children, who frequently accompanied him at bed and board, being ignorant of that malignity wherewith he was inwardly tainted. In the mean while the mother when ſhe obſerved that her nurſe-child came not forward, but cried almoſt perpetually, ſhe asked my counſel to tell her the cauſe of the diſeaſe; which was not hard to be done, for the whole body thereof was repleniſhed with venereal ſcabs and puſtles, the hired nurſes and the mothers nipples were eaten in with virulent ulcers; alſo the fathers, and the two other childrens bodies, whereof the

An hiſtory.

the one was three, the other four years old, were troubled with the like puſtles and ſcabs. I told them, that they had all the *Lues Venerea*, which took its original and firſt off-ſpring by malign contagion from the hired nurſe. I had them in cure, and by Gods help healed them all, except the ſucking child, which died in the cure. But the hired nurſe was ſoundly laſhed in the priſon, and ſhould have been whipped through all the ſtreets of the City, but that the Magiſtrate had a care to preſerve the credit of the unfortunate family.

CHAP. III.

In what humor the malignity of the Lues Venerea *reſides.*

THough in the opinion of many the antecedent cauſe of this diſeaſe be the maſs of blood containing the four humors, yet I had rather place the matter, and primary and chief ſeat thereof in groſs and viſcid phlegm infected with the malign quality of the venereous venom, and from this beginning and foundation, I think by a certain contagious growth, it ſooner or later infects the other humors, as each of them is diſpoſed or apt to ſuffer: Of which my opinion there are many arguments, but this chiefly, That by the evacuation of a phlegmatick humor, whether by the mouth and ſalivation, or by ſtool, urine, or ſweat in men of what temper ſoever, whether cholerick, ſanguine or melancholick, the diſeaſe is helped or cured. Secondly, for that the exceſs of pain is more by night than by day, becauſe then the phlegm bearing ſway, ſevers the *perioſteum* from the bone, or elſe offends it and the reſt of membranous and nervous bodies by the acrimony of its malignity. Thirdly, becauſe the patients are hurt by the uſe of cold things, but uſually find benefit by hot medicines, whether they be ointments, plaiſters, fumigations, or whatſoever elſe, inwardly taken, or outwardly applied. Fourthly, for that in venereous puſtles there is found a certain hardneſs at the root, though outwardly they make ſhew of choler or blood: For being opened, you ſhall find them ſtuffed with a certain plaiſter-like and tophous matter, or elſe with rough phlegm, or viſcous *pus*; whence ariſe theſe hard *tophi*, or bony excreſcences upon the bones, if not from phlegmatick humors there heaped up and concrete. Fifthly, for that the ſpermatick and cold parts do primarily and principally feel the harm of this diſeaſe. Sixthly, for that the ulcers which over-ſpread the body, by reaſon of this diſeaſe, admit of no cure, unleſs you cauſe ſweats. Therefore if the matter of the diſeaſe, and ſuch ulcers as accompany it, were hot and dry, it would grow worſe, and be rather increaſed by a decoction of *Guaiacum*, the roots of *China*, or *Sarſaparilla*. Seventhly, becauſe oft-times this diſeaſe, the ſeed thereof being taken or drawn into the body, ſo lieth hid for the ſpace of a year, that it ſhews no ſign thereof, which happens not in diſeaſes proceeding from a hot matter, which cauſeth quick and violent motions. By this it appeareth that the *Baſis* and foundation of the *Lues Venerea* is placed or ſeated in a phlegmatick humor: yet may not deny, but that other humors confuſed therewith may be alſo in fault, and defiled with the like contagion. For there are ſcarce any tumors which proceed from a ſimple humor, and that of one kind, but as in tumors, ſo here the denomination is to be taken from that humor which carrieth the chief ſway.

Why the pain is worſe upon the night than on the day.

The diſeaſe ſometimes lies long hid in the body before it ſhews it ſelf.

CHAP. IV.

Of the ſigns of the Lues Venerea.

WHen the *Lues Venerea* is lately taken, malign ulcers appear in the privities, ſwellings in the groins, a virulent ſtrangury runneth oft-times with filthy *ſanies*, which proceeds either from the *proſtatæ*, or the ulcers of the *urethra*; the patient is troubled with pains in his joints, head, and ſhoulders, and as it were breakings of his arms, legs and all his members, they are weary without a cauſe, ſo that neither the foot nor hand can eaſily perform his duty; their mouths are inflamed, a ſwelling troubles their throats, which takes away their freedom of ſpeaking and ſwallowing, yea of their very ſpittle; puſtles riſe over all their bodies, but chiefly certain garlands of them engirt their temples and heads; the ſhedding or loſs of the hair, diſgraceth the head and chin; and leanneſs deformeth the reſt of the body; yet all of theſe uſe not to appear in all bodies, but ſome of them in ſome. But the moſt certain ſigns of this diſeaſe are, a callous ulcer in the privities, hard and ill conditioned, and this ſame is judged to have the ſame force in a prognoſtick, if after it be cicatrized, it retain the ſame callous hardneſs; the Buboes or ſwellings in the groins to return back into the body without coming to ſuppuration or other manifeſt cauſe, theſe two ſigns, if they concur in the ſame patient, you may judge or foretel that the *Lues venerea* is either preſent, or at hand; yet this diſeaſe happeneth to many without the concourſe of theſe two ſigns, which alſo bewraieth it ſelf by other manifeſt ſigns, as ulcers and puſtles in the reſt of the body, rebellious againſt medicines though powerful, and diſcreetly applyed, unleſs the whole body be anointed with *Argentum vivum*. But when as the diſeaſe becometh inveterate many become impotent to venery, and the malignity and number of the ſymptoms increaſe, their pains remain fixed and ſtable, very hard and knotted *tophi* grow upon the bones, and oft-times they become rotten and foul, as alſo the hands and feet by the corruption of ſalt phlegm are troubled with chops or clefts, and their heads are ſeized upon by an *ophiaſis* and *alopecia*; whitiſh tumors with roots deep faſtned in, ariſe in ſundry parts of the body, filled with a matter like the meat of a cheſnut, or like a tendon; if they be opened they degenerate into divers ulcers, as putrid, eating and other ſuch, according to the nature and condition of the affected bodies. But why the pains are more grievous on the night ſeaſon, this may be added to the true reaſon we rendred in the precedent Chapter, firſt, for that the venereous virulency lying as it were aſleep is ſtirred up and enraged by

The moſt certain ſigns of the *Lues venerea.*

Two other cauſes of the exceſs of pain in the night.

by the warmneſs of the bed and coverings thereof; ſecondly, by reaſon of the Patients thoughts which on the night ſeaſon are wholly turned and fixed upon the onely object of pain.

CHAP. V.

Of Prognoſticks.

IF the Diſeaſe be lately taken, aſſociated by a few ſymptoms, as with ſome ſmall number of puſtles, and little and wandring pains, and the body beſides be young and in good caſe, and the conſtitution of the ſeaſon be good and favourable, as the Spring, then the Cure is eaſie, and may be happily performed. The ſigns of a curable *Lues Venerea.* But on the contrary, that which is inveterate and enraged by the fellowſhip of many and malign ſymptoms, as a fixed pain of the head, knots and rottenneſs of the bones, ill-natured ulcers in a body very much fallen away and weak, and whereof the cure hath been already ſundry times undertaken by Empericks, but in vain; or elſe by learned Phyſicians, but to whoſe remedies, approved by reaſon and experience, the malignity of the diſeaſe and the rebellious virulency hath refuſed to yield, is to be thought incurable, eſpecially if to theſe ſo many evils this be added, that the Patient be almoſt waſted with a conſumption and hectick leanneſs, by reaſon of the decay of the native moiſture. The ſigns of an incurable one. Wherefore you muſt onely attempt ſuch by a palliative cure; yet be wary here in making your Prognoſticks: for many have been accounted in a deſperate caſe, who have recovered; for by the benefit of God and Nature, wonders oft-times happen in diſeaſes. Young men who are of a rare or lax habit of body, are more ſubject to this diſeaſe, than ſuch as are of a contrary habit and complexion. For as not all who are converſant with ſuch as have the Plague, or live in a peſtilent Air, are alike affected; ſo neither all who lie or accompany with ſuch who have the *Lues Venerea*, are alike infected or tainted. How theſe pains differ from thoſe of the Gout. The pains of ſuch as have this diſeaſe, are far different from the pains of the Gout. For thoſe of the Gout return and torment by certain periods and fits, but the other are continual and almoſt always like themſelves; Gouty pains poſſeſs the joints, and in theſe condenſe a plaſter-like matter into knots; but thoſe of the Pox are rather faſtned in the midſt of the bones, and at length diſſolve them by rottenneſs and putrefaction. Venereous ulcers which are upon the Yard, are hard to cure, but if being healed, they ſhall remain hard and callous, they are ſigns of the diſeaſe lying hid in the body.

Generally, the *Lues Venerea* which now reigneth is far more mild and eaſie to be cured then that which was in former times, when as it firſt began amongſt us: beſides, each day it ſeemeth to be milder than other. The *Lues Venerea* becomes more gentle than formerly it was. Aſtrologers think the cauſe hereof to be this, for that the celeſtial influences which firſt brought in this diſeaſe, in ſucceſs of time by the contrary revolutions of the Stars loſe their power and become weak, ſo that it may ſeem ſomewhat likely, that at length after ſome few years it may wholly ceaſe; no otherwiſe than the diſeaſe termed *Mentagra*, which was very like this in many ſymptoms, and troubled many of the *Romans* in the reign of *Tiberius*; and the *Lichen*, which in the time of *Claudius* (who ſucceeded *Tiberius*) vexed not onely *Italy*, but all *Europe* beſides: Yet Phyſicians had rather take to themſelves the glory of this leſs raging diſeaſe, and to refer it to the many and wholſom means which have been invented, uſed and oppoſed thereto by the moſt happy labours of noble Wits.

CHAP. VI.

How many, and what means there are to oppugn this Diſeaſe.

MAny ſorts of remedies have been found out by many to oppugn and overcome this Diſeaſe. Why the decoction of *Guaiacum* is not ſufficient to impugn the diſeaſe. Yet at this day there are onely four which are principally uſed. The firſt is by a decoction of *Guaiacum*, the ſecond by Unction, the third by Emplaſters, and the fourth by Fumigation: all of them by *Hydrargyrum*, the firſt excepted. Yet that is not ſufficiently ſtrong and powerful; for experience hath taught, that the decoction of *Guaiacum* hath not ſufficient ſtrength to extinguiſh the venom of the venerous virulency, but onely to give it eaſe for a time; for becauſe it heats, attenuates, provokes Sweat and Urin, waſtes the excrementitious humours by drying them; it ſeemeth to cure the diſeaſe, for that thereupon for ſome time the pain and all other ſymptoms ſeem more remiſs: but theſe endeavours are weak and deceitful, as whereby that onely which is more ſubtle in the humours in fault, is exhauſted and diſperſed by ſweat. But *Hydrargyrum* is a certain higher power, contains therein all the power of *Guaiacum*, yet much more excellent and efficacious; for beſides that it heats, attenuates, cuts, reſolves and dries, it provokes Sweat and Urin, and beſides it expels noxious humours upwards and downwards, by the Mouth and Stool. *Hydrargyrum* is ſufficient to overcome the diſeaſe. By which evacuations not onely the more ſubtle, but alſo the more groſs and feculent excrements, wherein the ſeat of this diſeaſe is properly fixed, are diſperſed and evacuated; by which the Phyſician may be bold to aſſure himſelf of certain victory over the diſeaſe. But after the uſe of the decoction of *Guaiacum*, freſh pains and knots ariſe by the reliques of the more groſs and viſcous humours left in the cavities of the entrails; but *Hydrargyrum* leaves no reliques behind it.

CHAP. VII.

How to make choice of the Wood Guaiacum.

THat is preferred before the reſt which is of a great log, of a duſky colour, new, gummy, with a freſh ſtrong ſmell, an acrid, and ſomewhat biting taſte, the bark cleaving very cloſe to the Wood. The faculty. It hath a faculty to heat, rarifie, attenuate, attract, to cauſe Sweat, and move

The parts.

Urin, and beſides by a ſpecifick property to weaken the virulency of the *Lues Venerea*. There are three ſubſtances taken notice of in this wood, the firſt is the bark, the other is a whitiſh wood which is next to the bark, the third is the heart of the wood, that is, the inner, blackiſh, and more dusky part thereof. The bark is more dry, wherefore you ſhall uſe it when as you would dry more powerfully; the middle ſubſtance is more moiſt, becauſe it is more ſucculent and fat; that which lieth between both, is of a mild temper: wherefore the two laſt are more convenient for delicate Natures and rare Bodies, which require leſs drying. Furthermore, the bark muſt be given to denſe and ſtrong Natures, that by the more fiery force thereof, the humours may be made more fluid, and the paſſages of the body more paſſable. But I would here be underſtood to mean ſuch bark as is not putrid and rotten with age, to which fault it is very ſubject, for that long before it be ſhipped by our people, the wood lieth in heaps upon the ſhore in the open air, until they can find Chapmen for it; which when it is brought aboard, it is ſtowed in the hold or bottom of the ſhip, where beneath by the Sea through the chinks of the boards, and above by the Mariners, it uſually gathereth much dirt. When it is brought hither to us, it is bought and ſold by weight, wherefore that it may keep the weight, the Druggiſts lay it up in Vaults and Cellers under ground, where the ſurface thereof bedewed with much moiſture, can ſcarce eſcape mouldineſs and rottenneſs. Wherefore, I do not like to give the decoction either of the bark or wood which is next thereto, to ſick people.

The hot and fiery faculty of the bark.

CHAP. VIII.

Of the preparation of the decoction of Guaiacum.

The proportion of the *Guaiacum* to the Water.

Firſt you muſt have your *Guaiacum* ſhaved into ſmall pieces, and to every pound of the ſhavings, add of fair water eight, ten, or twelve pints, more or leſs, as the nature of the party, and condition of the diſeaſe ſhall ſeem to require, according to the rule of the formerly mentioned Indications. Let the Water be hot or warm, eſpecially if it be in Winter, that ſo it may the more eaſily and throughly enter into the body of the wood, and draw into it ſelf the faculties thereof in the ſpace of twenty four hours, wherein it is macerated, then boil it in *balneo*, to avoid *Empyreuma*, or taſte of fire, which it will contract by boiling it over a hot fire. Yet ſome nothing regard this, but think the Patient ſufficiently ſerved, if they make a decoction in an earthen pot well glazed over a gentle fire, ſo that no part of the liquor may run over the mouth of the veſſel, for that thus ſo much of the ſtrength of the decoction might vaniſh away. Howſoever it be made, let it be boiled to the conſumption of half, a third, or fourth part, as the nature of the Patient and Diſeaſe ſhall ſeem to require. There be ſome who mix divers Simples therewith, which have an occult and proper ſympathy with that part of the body which is principally hurt by the Diſeaſe, which at the leaſt may ſerve in ſtead of a vehicle to carry the faculties of the decoction thither where the diſeaſe moſt reigneth. Others add thereto purging Medicins, whoſe judgment I cannot approve of, for that I think it is not for the Patients good to attempt two evacuations at once; that is, to expel the humours by Sweat by the habit of the body, and by purging by the belly; for that as much Urin, ſo alſo much Sweat ſhews little evacuation by Stool. For theſe two motions are contrary, which Nature cannot brook at once: For Purging draws from the Circumference to the Center, but Sweat runs a quite contrary courſe, and this is the opinion of many and great Phyſicians. This firſt decoction being boiled out and ſtrained, the like quantity of Water ſhall be put to the ſtuff, or maſs, that ſo being boiled again without any further infuſion, and ſtrained, with the addition of a little Cinamon for the ſtrengthening of the Stomach, the Patient may uſe it at his meals, and between his meals (if he be dry) for his ordinary drink. The quantity of the firſt decoction to be taken at once, ought to be ſome five or ſix ounces, and it ſhall be drunk warm, that ſo it may be the ſooner brought into action, and leſt the actual coldneſs ſhould offend the ſtomach; and then the Patient being well covered, ſhall keep himſelf in bed, and there expect ſweat, which if it come ſlowly on, it ſhall be helped forwards with ſtone-bottles filled full of Water, and put to the ſoals of the feet. If any parts in the *interim* ſhall be much pained, they ſhall be comforted by applying of Swines bladders half filled with the ſame decoction heated. Neither will it be unprofitable before the decoction be drunk, to rub over all the body with warm linnen cloths, that by this means the humours may be attenuated, and the pores of the skin opened. When he ſhall have ſweat ſome two hours, the parts oppoſite to the grieved places ſhall firſt be wiped, then preſently, but more gently, the grieved parts themſelves, leſt a greater conflux of humours flow thereto. Theſe things being done, he ſhall keep himſelf in bed, ſhunning the cold air until he be cooled and come to himſelf again, ſome two hours after he ſhall ſo dine, as the diſeaſe and his former cuſtom ſhall ſeem to require; ſix hours after, betaking himſelf to his bed, he ſhall drink the like quantity of the decoction, and order himſelf as before. But if he be either weak, or weary of his bed, it ſhall be ſufficient to keep the houſe without lying down; for although he ſhall not ſweat, yet there will be a great diſſipation of the vapours and venenate ſpirits, by inſenſible tranſpiration; for the *Lues Venerea* by the onely communication of theſe, often times catcheth hold, and propagates it ſelf in lying with a bedfellow tainted therewith. But it is requiſite to have let blood, and purge the body by the advice of a Phyſician, before the taking of the decoction of *Guaiacum*; ſo whileſt he doth take it, it much conduceth to keep the belly ſoluble (which is much bound by the heat and drineſs of ſuch a drink) and to preſerve the purity of the firſt Veins by a Clyſter, or laxative Medicin taken every fifth or ſixth day. But for the uſe of it, we muſt warily obſerve, taking indication, not onely from the malignity and contumacy of the diſeaſe, but alſo from the particular nature of the Patient; for ſuch as have their body waſted by heat and leanneſs, and their skin dry and ſcaly (whence you may gather a great aduſtion of the humours, and as it were, a certain incineration of the habit of the body) muſt more ſparingly make

Whether it be fit to add purges to a decoction of *Guaiacum*.

Hip. aph. ult. ſect.6.

How, and in what quantity this decoction muſt be taken

How to dry the ſweat of the body.

How long this decoction muſt be uſed.

make uſe of theſe things, but rather temper the body by humecting things taken inwardly, and applied outwardly, as Baths, Ointments without Quick-ſilver, and other ſuch like things: And then a very weak decoction of *Guaiacum* ſhall be uſed for a few days before your unction with Quickſilver. A more plentiful diet, as it draws forth the diſeaſe, which of its own nature is long, ſo a more ſparing and ſlender diet makes the ulcers more rebellious and contumacious, by a hectick drineſs. The manner of Diet.

Therefore a middle courſe muſt be kept, and meats made choice of, which are fit and naturally engender good and laudable juice in the body. For it is not onely great ignorance, but much more cruelty to go about to contain all Patients without any difference, within the ſtraight allowance of four ounces of Ship-bisket, and twelve damask Prunes: for I judge it far better to diet the Patient with Lamb, Veal, Kid, Pullets, fat Larks, and Black-birds, as thoſe which have a greater familiarity with our bodies, than Prunes and the like Junkets. Let his bread be made of white wheat well leavened, neither too new, or tough, neither too old or hard. Let his drink be made of the maſs or ſtrainings of the firſt decoction of *Guaiacum* boiled with more water, as was formerly mentioned; yet if there ariſe any great weakneſs of the faculties, you may permit the uſe of ſome little Wine, drinking eſpecially before each, a cup of the laſt mentioned decoction. Let him avoid ſleep preſently after meat, for ſo the head is filled with groſs vapors. Paſſions or perturbations of the mind muſt alſo be avoided, for that by theſe the ſpirits are inflamed and diſſipated; all the delights of honeſt pleaſure are to be deſired, but venery wholly avoided, as that which weakens all the nervous parts. Many in ſtead of a decoction of *Guaiacum*, uſe a decoction of *China*. Now this *China* is the root of a certain Ruſh, knotty, rare, and heavy when it is freſh, but light when it is waxed old; it is alſo without ſmell, whence many judge it void of any effectual quality, it is brought into uſe out of *India*, it is thus prepared, it is cut into thin round ſlices, boiled in Fountain or River Water, and is given to Patients to drink morning and evening after this manner. ℞ *Rad. chin. in taleol. ſect.* ℥ ij. *aquæ font.* ℔ xij. *infundantur per hor.* xij. *& coquantur ad conſumption. tertiæ partis.* Let him take ℥ vj. in the morning, and ſo much at night; let him expect a ſweat in his bed: a ſecond decoction may be made of the maſs remaining of the firſt, but with a leſs quantity of water put thereto, which alſo by longer boiling may draw forth the ſtrength remaining in the maſs, and be uſed at meals for ordinary drink. There are ſome who make a third decoction thereof, but that is wholly unprofitable and unuſeful. *Sarſaparilla* is prepared alſo juſt after the ſame manner. To whom, and what manner of Wine may be allowed. The deſcription of *China*. The preparation. Of *Sarſaparilla*.

CHAP. IX.

Of the ſecond manner of curing the Lues Venerea, *which is performed by Friction or Unction.*

THe Cure of the *Lues Venerea* which is performed by Unction and Friction is more certain, yet not in every kind, condition, and ſeaſon thereof. For if the diſeaſe be inveterate from an humour, tough, groſs, viſcous, and more tenaciouſly fixed in the ſolid parts, as you may gather by the knotty tumours of the bones; for then we are ſo far from doing any good with a Friction uſed at the firſt, that on the contrary, we bring the Patient in danger of his life, unleſs we ſhall have firſt prepared the tumor to expulſion, by emollient and digeſting things firſt uſed. But if it be lately taken with moveable pains, puſtles, and ulcers in the jaws, throat, and privy parts, then may it be eaſily cured without ſuch preparatives, eſpecially if the humour be ſufficiently obedient, and as it were prepared of it ſelf, and its own nature. Therefore firſt uſing general medicins, you may afterwards come to uſe the Unction with *Hydrargyrum*. When the body muſt be prepared with humecting things before unction.

CHAP. X.

Of the choice preparation and mixing of Hydrargyrum.

Hydrargyrum which is clear, thin, white, and fluid, is the beſt: on the contrary, that which is livid, and not ſo fluid, is thought to be adulterated, by the admixture of ſome Lead. That it may be the purer, ſtrain it through ſome ſheeps-leather, for by preſſing it when it is bound up, it paſſeth through by its ſubtilty, and leaves the filth and leaden droſs behind it on the inſide: Then it may be boiled in Vinegar, with Sage, Roſemary, Thyme, Camomil, Melilot, and ſtrained again, that ſo many ways cleanſed, it may enter into Ointments and Platters. To kill it more ſurely, it ſhall be long wrought, and as it were ground in a Mortar, that it may be broken and ſeparated into moſt ſmall particles, that by this means it may not be able to gather it ſelf into the former body: to which purpoſe you may alſo add ſome *ſulphur* or *ſublimate*, as we ſhall ſhew hereafter. It is moſt uſually mixed with Hogs-greaſe, adding thereto ſome Oil of Turpentine, Nutmegs, Cloves, Sage, and *Galens* Treacle. If a *Leucophlegmatia* together with the *Lues Venerea* affect the body, then hot, attenuating, cutting and drying things ſhall be added to the Medicin, which ſhall be provided for Unction; the ſame ſhall be done when as we would have it to enter into the ſubſtance of the bones. But if the Patient be of a cholerick temper, and his bloud eaſie to be inflamed, you ſhall make choice of leſs hot attractive and diſcuſſing things; as when the body ſhall be repleniſhed with knotty and ſcirrhous tumours, or ſqualid by exceſſive drineſs, then ſhall emollient and humecting things mixed therewith: But that ſuch Ointments may have a better conſiſtence, I uſe to add to each pound thereof, four, five, or ſix yolks, of hard Egs. Therefore this ſhall be the form of the Ointment called Vigoes. ℞ *Axung. porci,* ℔ j. *olei chamæm. anethi maſtich. & laurini an.* ℥ j. *ſtyrac. liquid.* ℥ x. *rad. enulæ cam. parum tritæ, & ebuli, an.* ʒ iij. *pul. euphorb.* ℥ ß. *vini odorif.* ℔ j. *buliant omnia ſimul uſque ad conſumptionem vini, deinde colentur; colaturæ adde lythargyri auri* ℥ vj. *thuris, maſtich. an.* ℥ vj. *reſ. pini,* ℥ j. ℔. *tereb. venet.* ℥ j. *argenti vivi,* ℥ iv. *ceræ albæ,* ℥ j. ℔. *liquefactis oleis, cum cera incorporentur omnia ſimul, fiat linimentum ad uſum.* Or elſe ℞ *Argenti vivi præparati,* ℥ vj. *ſublimati,* ʒ ℔. *ſulphuris vivi,* ℥ ℔. *axung. porci ſalis expertis* How to kill *argentum vivum*. What to mix therewith. An unction with *argentum vivum*. Another.

experti, ℔ j. *vitellos ovorum ſub cineribus coctorum*, nu. iij. *olei terebinth. & laurini, an.* ℥ ij. *theriac. vet. & mithridat.* ℥ ſ. *fiat linimentum ut artis eſt.* You ſhall compoſe it thus, firſt the *ſublimatum* and *ſulphur* ſhall be finely powdered, then ſome part of the *Argentum vivum* and Hogs-greaſe put to them, then preſently after, ſome of the hard yolks of Eggs, continually and diligently ſtirring and mixing them all together. All theſe being well incorporate, add ſome more *Argentum vivum*, Hogs-greaſe, and yolks of Eggs, and incorporate them with the former; at laſt add the Oils, then Treacle and Mithridate, and ſo let them be all beaten together for a whole days ſpace, and thus you ſhall make an ointment of a good conſiſtence, which I have often uſed with good ſucceſs. Yet the Hogs-greaſe ſhall be firſt boiled with the hot herbs good for the ſinews, as Sage, Roſemary, Thyme, Marjerom, Lavender, and others which the Seaſon affords. For ſo the *axungia* acquires a more attenuating faculty, and conſodating of thoſe parts which the *Lues Venerea* afflicts. Beſides, when unguents are made for this purpoſe, that ſuch virulency may be drawn from within outwards, by ſweats and tranſpiration through the pores of the skin, no man need doubt but that they ought to be furniſhed with relaxing and rarifying and attractive faculties. But *axungia*, beſides that it is very fit to kill the *Argentum vivum*, it alſo relaxeth and mollifieth. Now *Oleum laurinum, de ſpica, rutaceum*, rarifie, digeſt, and aſſwage pain, Turpentine alſo extinguiſheth and bridleth the *Argentum vivum*, moderately heats, reſolves, and ſtrengthens the nervous parts. But *Argentum vivum* is the proper antidote of the *Lues Venerea*, as that which cures it howſoever uſed, drying by the ſubtilty of the parts, and provoking ſweat. Verily Treacle and Mithridate ſomewhat conduce to retund the virulency of this diſeaſe, but unleſs *Argentum vivum* aſſiſt as a ferret to hunt, and an *Alexiterium* to impugn the diſeaſe, they can do no great matter.

How to make it.

How to prepare the hogs-greaſe before you mix the *argentum vivum* therewith

CHAP. XI.

How to uſe the Unction.

THe body and humours apt to cauſe or nouriſh a *plethora* or inflammation, being prepared by digeſtive ſyrups, and evacuated by purging and bleeding as is fitting, according to the direction of ſome Phyſician, the Patient ſhall be ſhut up in a Parlour or Chamber, hot either by Nature or Art, and free from cold blaſts of wind; for cold is moſt pernicious in this diſeaſe, both for that it hurts the nervous parts, already ill-affected by reaſon of the diſeaſe, as alſo for that it leſſens the efficacy of Medicins. Wherefore many do ill in this, who, whether in Winter or Summer anoint their Patients in a large room, expoſed on every ſide to the winds. They deal ſomewhat more wiſely, who put a cloth faſtned like half a Tent preſently behind the Patient, though anointed by the Fire ſide, ſo to keep away the cold air from him. Yet it is the ſafeſt to ſet, and anoint the Patient either in a little Room, or elſe in ſome corner of a large Room, ſeparated from the reſt of the Room by ſome hangings, and building a ſtove, or making ſome fire therein, for ſo he may ſtand or ſit as he beſt likes, the longer, and with the leſs offence, and be equally heated on every ſide; whereas ſuch as are anointed in a Chimney by a fires-ſide cannot but be heated unequally, being ready to burn on the one ſide, whileſt the other is cold, which motions are contrary hurtful to that we require: beſides, if the Patient ſhall be weak he cannot ſtand and endure the heat of the fire. Or if he be ſhame-faced, he will be unwilling to ſhew all his body at once naked to the Surgeon, but he may without any harm, and with modeſty, lying on a Bed in a little Room wherein a ſtove is made, have all his limbs anointed about the joints, and preſently bound up, either with ſtoups, or carded cotten, or brown paper.

Cold moſt hurtful to ſuch as are troubled with the *Lues Venerea*.

CHAP. XII.

What cautions to be obſerved in rubbing or anointing the Patient.

HE ſhall be anointed orrubbed over with the Ointment in the morning, the concoction and diſtribution of the meat being perfected, which functions otherwiſe would not be well performed, the powers of Nature being diſtracted into ſeveral operations: Yet if the Patient ſhall be weak, you may ſome hour before the unction give him ſome Gelly, the yolk of an Egg, or ſome Broth made of Meat boiled to pieces, but very ſparingly, leſt Nature intent upon the concoction of ſolid Meats, or in great quantity, ſhould be drawn away from that which we intend. At firſt let onely the joints of the limbs be anointed, as about the Wriſts, Elbows, Knees, Ankles, Shoulders. But afterward, if the Patient ſhall be more ſtrong, and a greater commotion of the humours and body ſeem neceſſary; the emunctories of the principal parts may alſo be anointed, and the whole ſpine of the back; yet having much care, and always ſhunning the principal and noble parts, leſt we ſhould do as thoſe butcherly Empericks do, who equally, and in like manner daub and rub over all the body, from the ſoles of the feet to the crown of the head: moreover, diligent regard muſt be had of thoſe parts which are ſeized upon by the ſymptoms of this diſeaſe, that they may be more anointed, and that it may be more throughly rubbed in. Yet you may always begin your anointing or rubbing at thoſe parts which are leſs offended, leſt the humours ſhould be drawn in greater meaſure to the grieved part. And as gentle frictions do not ſufficiently open the pores of the skin, ſo more ſtrong and hard ones ſhut them up, cauſe pain, and more plentifully attract the morbifick matter. Wherefore it will be more convenient to uſe moderate frictions, taking indication from the ſtrength of the Patient, as that whereto we muſt ſtill have the chief regard. There is alſo another thing whereto the Phyſician and Surgeon muſt diligently attend, as that, which if it be not carefully prevented, will either haſten the death of the Patient, or make him ſubject to a relapſe; that is, the quantity of the remedies and unctions, and the number

The Patient, if it may be conveniently done, muſt be anointed faſting.

In what places the body muſt be anointed.

Where to begin the Unction.

number of the frictions. Which conſideration, together with that which is of the degrees of the temperaments of the whole body, and each part thereof, much troubles the minds of good Phyſicians, and maketh the Art conjectural. It is far from being attained to by Empericks; yet we muſt endeavour by Method and Reaſon, that by the Rule of Indications ſo frequently mentioned, we may attain to the knowledge thereof, as near as may be: for to have perfect knowledge hereof, and to ſay that thoſe need onely four, others five, and otherſome ſix, more or fewer frictions at the beginning, which Empericks, commonly do, is a thing both impoſſible and vain. All theſe muſt be changed and ordered according to the malignity and continuance of the diſeaſe, and the condition of the affected bodies. Verily we muſt ſo long uſe frictions and unctions, until the virulent humours be perfectly evacuated by Spitting and Salivation, by Stool, Urin, Sweat, or inſenſible tranſpiration. Which you may underſtand by the falling away and drying up of the Puſtles and Ulcers, and the ceaſing of the pains and other ſymptoms proper to this diſeaſe. In many, by reaſon of the more denſe and compact habit of the body Nature is more ſlow in excretion. Yet I have learnt by long experience, that it is beſt to anoint and chafe ſuch twice in a day, to wit Morning and Evening, ſix hours after meat. For ſo you ſhall profit more in one day, then by the ſingle friction of three days. But on the contrary, I have often, and with good ſucceſs, rubbed over but each other day more rare and delicate bodies, giving them one or two days reſt to recollect their ſtrength, which by the too much diſſolution of their ſpirits becoming too weak, were not ſufficient to expel the reliques of the morbifick matter. And certainly about the end of the appointed friction, eſpecially when as the Patient begins to flux at the mouth, the bodies, together with the noxious humours are made ſo fluid by the means of the precedent friction, that one friction is then more efficacious then two were at the beginning. Therefore as *Galen* bids, when as the diſeaſe is great, and the ſtrength of the Patient infirm, that we ſhould part our bloud-lettings, and draw a little and a little at once; ſo alſo here, when as we ſhall obſerve Nature ſtirred up, and ready bent to any kind of evacuation by the Mouth, Stool, or other like; you ought not to uſe any Unction or Friction oftner than once in a day; yea, certainly it will be better to intermit for ſome few days. For thus *Maſſa* reports, that there was a certain man who almoſt waſted with a Conſumption, being continually afflicted with the moſt grievous pains of this diſeaſe, and reputed in a deſperate caſe by other Phyſicians, was notwithſtanding at length recovered by him, when as he had anointed him thirty ſeven times, putting ſome time between for the recovery of his ſtrength. I my ſelf have obſerved others, who thus, by the interpoſition of one or two days, being rubbed over for fifteen or ſeventeen times, have perfectly recovered. Where you muſt take this courſe in reſolved and weak bodies, yet in the *interim* muſt you have a care that the frictions be not too weak, and ſo few, that the morbifick cauſe may not be touched to the quick: for in this kind of diſeaſe Nature doth not of it ſelf endeavour any *criſis*, or excretion; it requires the auxiliary forces of Medicins, by whoſe aſſiſtance it may expell all the malignity. Theſe are ſigns of ſuch a *criſis*, either at hand or already preſent, if the Patient be ſo reſtleſs, ſo loath all things, that he cannot remain in one place either ſtanding or lying; he can neither eat nor drink, if he be oppreſſed with a continual wearineſs, almoſt ready to ſwound, yet have a good and equal pulſe, and gripings in his belly afflict him, with bloudy and viſcous dejections, until at length Nature after one or two days portion of the morbifick matter being ſpent, be ſomewhat freed, and all pains and ſymptoms ſo much abated, as the excretions have proceeded. But whereas Medicins are not ſufficient in number or ſtrength, there follows an imperfect *criſis*, which leaves behind it ſome reliques of the morbifick matter, which like leven do ſo by little and little infect the whole maſs of the humours, that oft-times after ten years ſpace the diſeaſe riſeth as out of an ambuſh, or lurking-hole, and becomes far worſe than before. But we muſt in like manner have a care leſt theſe Medicins, that are either given inwardly, or applied outwardly, be not too ſtrong: for by cauſing ſuch colliquation of the radical moiſture and ſolid parts, many have been brought into an incurable conſumption. In others ſordid and putrid ulcers have thence ariſen in the mouth, which having eaten a great part of the Palate and Tongue, have degenerated into a deadly *Cancer*. In others hereupon the tongue hath ſo ſwelled up, that it hath filled the whole capacity of the mouth, ſo that it could not be bended to any part of the mouth for chawing, whereupon they have by little and little, been famiſhed. In other ſome there hath been cauſed ſo great colliquation of humours, that for a whole moneth after tough and filthy ſlaver hath continually flowed out of their mouths. Other ſome have the muſcles of their jaws relaxed, others troubled with a Convulſion, ſo that during the reſt of their lives they can ſcarce gape. Others by loſing a portion of their jaw, have loſt ſome of their teeth. But you muſt not always ſo long anoint and chafe the body, until a flux of the mouth or belly appear: For you may find ſundry perſons, who if you ſhould anoint or rub them to death, you cannot bring them to flux at the mouth; yet theſe will recover notwithſtanding, excretion being made either by inſenſible tranſpiration, or evacuation of Urin, or ſome gentle flux of the belly, either procured by Art, or coming of it ſelf. In which caſe I have obſerved that many have received much good by a purging decoction of *Guaiacum*, adminiſtred according to the quantity of the peccant humour, and given for ſome days in the morning, adding thereto white Wine, if the body abounded with tough and viſcid humours. Dyſenteries, or bloudy Fluxes cauſed by Unctions, may be helped by Clyſters, wherein much Hogs-greaſe is diſſolved to retund the acrimony cauſed by the Medicin and humour which nouriſheth the Dyſentery. Alſo new Treacle diſſolved in new milk, is thought wonderfully to mitigate this ſymptom.

What it is that maketh the Art of Phyſick conjectural.

Who muſt be rubbed over once, who twice in a day, and who but every other day.

Lib. de vent. ſect.

Nature is not ſufficiently able to expel the virulent matter.

Signs that the *Criſis* is nigh.

Inconveniences following upon immoderate unctions.

For what perſons a purging decoction of *Guaiacum* is good.

The cure of a Dyſentery occaſioned by too ſtrong friction.

CHAP. XIII.

Of the third manner of Cure, which is performed by Cerates and Emplaſters, as ſubſtitutes of Unctions.

The cure by Emplaſters more ſlow.

FOr that ſundry by reaſon of the name, abhor the uſe of friction, which is performed by the fore-mentioned Ointments, therefore there is found out another manner of cure by Cerates and Emplaſters, as ſubſtitutes of Frictions, but that uſually is ſomewhat ſlower; for which purpoſe it is not needful onely to uſe the things which are deſcribed by *Vigo*, but you may alſo deviſe other, which are more or leſs anodyne, emollient, attenuating, diſcuſſing, or drying, according to the condition of the preſent diſeaſe, ſymptoms, humours, and Patient, never omitting *Hydrargyrum*, the onely antidote of this diſeaſe. Such Emplaſters mitigate pains, and knots, and reſolve all hardneſs, and are abſolutely very effectual; for continually ſticking to the body, they continually operate:

In what caſe they are chiefly uſeful.

Wherefore they are of prime uſe in relapſes of this diſeaſe, or when the humours are thick and viſcous, or otherwiſe lie deep in the body, and very difficult to root out. But for that they work more ſlowly oft-times, ſuch as uſe them are forced at length to uſe ſome frictions to ſtimulate Nature, and cauſe the ſpeedier excretion. Yet in ſome, whoſe bodies and humours have been fluid, either by Nature or Art, the applied Emplaſters have in three days ſpace procured evacuation ſufficient for the diſeaſe, ſo that if they had not been taken away, they would have cauſed a colliquation, like that which we lately mentioned in too violent friction: Wherefore you ſhall uſe the like diſcretion in taking of

The deſcription of an Emplaſter.

theſe, as you uſe in your unctions and friction. In ſtead of *Emp. de Vigo*, this following may be fitly uſed. ℞ *Maſſæ Emp. melil. & oxycr. an.* ℔ ß. *argenti vivi extin.* ʒ vj. *oleo laurino, & de ſpica reducantur ad formam emplaſtri.* Theſe Plaiſters muſt be equally ſpread upon leather, and laid upon the ſame places of the joints, as were formerly mentioned in the cure by frictions. Yet ſome there be who cover with the plaiſter all the arm, from the hand even to the ſhoulder, and all the leg from the top of the knee, even to the ends of the toes, which thing I do not diſallow of, if ſo be that the places or the joints be covered over with a thicker Plaiſter. They muſt be left ſticking thereon ſo long, until Nature be ſtirred up and provoked to cauſe excretion of the virulent humours. Yet if in the *interim*, great itching ſhall ariſe in the parts, you may take them off ſo long until the parts ſhall be fomented with a decoction of the flowers of Camomil, Melilot, red Roſes, and the like, made in Wine, to diſcuſs that which cauſed the itching, and then you may lay them on again. Some to hinder the riſing of any itch, lay not the bare Plaiſter to the part, but cover it over with Sarcenet, ſo to keep it from ſticking, and thus intercept the tranſpiration of the part, the cauſe of itching. They ſhall be ſtronger or weaker, and lie to the part a long or ſhorter ſpace, as long as the indications ſo often formerly mentioned, ſhall ſeem to require. The effects of Emplaſters are the ſame as of frictions: for they cauſe excretion, one while by inſenſible tranſpiration, otherwhiles by a *Diarrhœa*, or flux of the belly; ſometimes by Urins, but moſt frequently (which *Criſis* is alſo moſt certain) by ſalivation. Sordid and virulent ulcers often breed in the Mouth, Tongue, Pallat, and Gums by ſalivation, by reaſon of

What excretion beſt in this diſeaſe.

the acrimony of the virulent humours adhering to the ſide of the mouth: to hinder the growth of theſe, many inject Clyſters made of emollient things, eſpecially at the beginning of the ſalivation, ſo to draw downwards the humours forcibly flying up in greater quantity than is fit, although the part it ſelf may endure them.

There are alſo ſome, who to the ſame end give a purging Medicin at the very time when as the humours are ready to move upwards, the which I think is not a ſafe courſe. The cure of ſuch ul-

To avoid the ulcers of the mouth.

cers is far different from the cure of others; for they ought by no means to be repercuſſed or repelled, how inflamed ſoever they be, but onely to be mitigated by gargariſms, ſo onely to leſſen the heat, and that by this frequent waſhing of the mouth, you may hinder the ſticking or furring of viſcid

To cure them.

humours to ſuch like ulcers. A decoction of Barley, Cows milk warm, held and gargled in the mouth, the mucilages of the ſeeds of Mallows, Marſh-mallows, *Pſilium*, Lettuce, Line extracted in the Water of Barley, Mallows, and Pellitory of the Wall, are good for this purpoſe; for thus the ulcers become more mild, and the tenacity of the adherent humours is looſed. You muſt at the firſt beware of ſtrong detergent Medicins, for almoſt all ſuch have acrimony joined with them, which will increaſe the pain, but chiefly in the ſtate of the diſeaſe: for ſo, the ulcers gently cleanſed by frequent gargling, would become worſe by the uſe of acrid things. Therefore it ſhall be ſufficient to make uſe of the fore-mentioned Medicins, ſo to hinder the increaſe of the filth, and inflammation of the ulcers, if ſo be that ſuch ulcers be not too exceeding malign and burning. For if it ſhall happen either by the powerful efficacy of the applied Plaſters, or by the violence of Nature in its motion of the ill humours upward, that ſuch ſtore of viſcous and groſs humours are carried to the mouth, that it wants little, but that the part it ſelf is over-ruled by the morbifick matter, ſo that by the violence and continuance of the flux, the Mouth and Jaws become ſo ſwelled, that a gangrene is to be feared, by hindring the entrance of the ſpirits, and extinguiſhing of the native heat of theſe parts. In this caſe

Reſtrictive repelling Gargariſms.

we are forced to leave the proper cure for to withſtand the accidents, and for this purpoſe we uſe reſtrictive and repelling things, ſuch as are Barley Water, Plantain, Night-ſhade, Knot-graſs, Shepherds-purſe, and the like; with ſyrup of Roſes, Violets, Quinces, Berberies, Pomgranats, and the like; alſo ſuch are the mucilages and decoctions of the ſeeds of Lettuce, Piſilium, Quinces, Plantain, Night-ſhade, Water-lillies, Wood-bind, &c. Alſo it is convenient to procure ſweats by Stoves, or the application of any hot and dry things; for thus the humours which run forth of the veſſels into all the ſurface of the body, are diverted. But when as the courſe of the humours running to the mouth, is begin-

To dry the ulcers of the mouth.

ning to ſtop, and the tumours of ulcers begin to leſſen, then nothing hinders, but that we may uſe gently detergent things, as *Syrup. roſarum ſiccar. mel roſat. Diamoron, Dianucum*, and the like. But when it is time to dry the ulcers, they may be lightly touched with Alum-water, or with *Aqua fortis*, ſuch as Goldſmiths have uſed for the ſeparation of Metals. They may alſo frequently uſe drying

Gargariſms

Gargariſms made with aſtriction of the water of Roſes, Plantain, Night-ſhade, Shepherds-purſe, Knot-graſs, and Dogs-tongue, boiling therein *balauſt. roſ. rub. myrtil. ſumach. alum. acacia, berber. gallar. malicor.* and the like. During the time of fluxing or ſalivation, you muſt diet and feed the Patient with liquid meats, and thoſe of good juice and eaſie digeſtion, for that then he can neither chaw, ſwallow, nor digeſt hard things: For Nature wholly intent upon the excretion of the noxious and peccant humours, as alſo weakned by the bitterneſs of pain, watchings and unquietneſs, and conſequently a great reſolution of the ſpirits, cannot inſiſt powerfully upon the work of concoction. Therefore he ſhall be fed with rear new-laid Egs, Caudles of the ſame, Barley-creams, Culleſſes made of a decoction of Knuckles of Veal, and a Capon, and Gellies; and with theſe in ſmall quantity, but frequently adminiſtred, always gargling his mouth before he eat. For his drink he ſhall uſe a decoction of *Guaiacum* aromatized with a little Cinamon; but if any deſire that the drink ſhall become nouriſhment; for that the Patients cannot feed on more ſolid meats, you may give them old Wine, Claret and thin, mixed with ſome Barley-water. Some there are who ſteep ſome crums of pure Manchet in the forcſaid Wine, and then preſs it out, but yet ſo, that there may ſome part of the bread remain therein, which may make it more nouriſhing, and leſs ſharp or acrid. Others ſteep bread hot out of the Oven in Wine for the ſpace of a night, then they diſtil it all over in *balneo Mariæ*; the liquor which comes over is more ſtrong and hot, but that which flows out afterwards, more mild, and ſuch as the Patient may uſe to mix with his Wine without any danger, for his better nouriſhment, and the recovery of his ſtrength.

Manner of diet when the mouth is ulcerated.

To make their drink nouriſh.

For to refreſh the ſpirits in fear of fainting, Muſcadine, Hippocras, Roſe Vinegar, and the like, put to the noſe to ſmell to, will be ſufficient, unleſs peradventure the Patient ſhould naturally abhor ſuch things, for ſo they would rather deject the powers and ſpirits. In the *interim* you muſt have care of the belly, that you keep it open by gentle and emollient Clyſters.

CHAP. XIV.

Of the fourth manner of Curing the Lues Venerea.

SOme have deviſed a fourth manner of curing the *Lues Venerea*, which is by *Suffitus*, or Fumigations. I do not much approve hereof, by reaſon of ſundry malign ſymptoms which thence ariſe, for they infect and corrupt by their venemous contagion, the Brain and Lungs, by whom they are primarily and fully received, whence the Patients during the reſidue of their lives, have ſtinking breaths. Yea many while they have been thus handled have been taken hold of by a convulſion and a trembling of their Heads, Hands, and Legs, with a Deafneſs, Apoplexy, and laſtly, miſerable death, by reaſon of the malign vapours of Sulphur and Quickſilver, whereof *Cinnabaris* conſiſts, drawn in by their mouth, noſe, and all the reſt of the body. Wherefore I can never approve the uſe of ſuch fumigations which are to be received in fumes by the mouth and noſtrils for to work upon the whole body; yet I do not diſlike of that which is undertaken for ſome one part onely, as to dry up ill-conditioned ulcers, which ſo affect it, they cannot be overcome by any other means, or for to diſperſe or digeſt knots, or to reſolve fixed pains, otherwiſe unmoveable. Theſe Fumigations, by reaſon of the admixture of *argentum vivum*, have an attenuating, cutting, reſolving, and colliquating faculty. Thoſe who prepare theſe Fumigations for the cure of the whole diſeaſe and body, take this courſe. They put the Patient under a Tent or Canopy made cloſe on every ſide, leſt any thing ſhould expire, and they put in unto him a Veſſel filled with hot coals, whereupon they plentifully throw *Cinnabaris*, that ſo they may on every ſide enjoy the riſing fume, juſt after the ſame manner as Farriers uſe to ſmoak their Horſes for the Glaunders: they repeat this every day ſo long, until they begin to flux at the mouth. The principal matter or *baſis* of ſuch Fumigations, as we have already noted, is *Cinnabaris* conſiſting of Sulphur and *argentum vivum* mixed together: there is added alſo, *Radix ireos flor. thus, olibanum myrrha, juncus odoratus, aſſa odorata, maſtiche terebinthina & theriaca*, all which have a faculty to reſolve and ſtrengthen the Spirits and Nature, and correct the ſtench and evil quality of the *argentum vivum*. There are alſo other Fumigations made after another manner, but that alſo when as the *argentum vivum* is extinct, and as it were fixt after this manner, let ſome Lead be melted, and let there be poured or put thereto ſome *argentum vivum*, then let it all be powdered, adding thereto Antimony, Aloes, Maſtich, Coperas, Orpiment, and Benjamin made into Powder, and framed into Trochiſces with ſome Turpentine. Or elſe ℞ *Cinnabaris* ʒ j. *ſtyracis liq. & calamitæ, nucis moſchat. an.* ʒ iij. *benzoini* ʒ ß. *excipe terebinth. fiant trochiſci ponderis* ʒ ij. for the aforeſaid uſe. The *terebinthina* is added to incorporate the dry things, and the gums are added to yield matter to the fume. But virulent ulcers of the *Lues Venerea* ſhall not be fumigated before they be cleanſed; alſo this following Fumigation is good. ℞ *Cinnab.* ʒ j. *benzoini, myrrhæ, ſtyracis, olibani, opopanacis, an.* ʒ ß. *maſtiches, macis, thuris, an.* ℈ ij. *excipiantur terebinth. & fiat ſuffumigium.*

What fumigations good.

The common manner of uſing them.

The matter of them.

Trochiſces for fumigations.

CHAP. XV.

The Cure of the ſymptoms, or ſymptomatick affects of the Lues Venerea: *and firſt, of the Ulcers of the Yard.*

CAllous and malign ulcers in this diſeaſe may grow all over the Yard; but theſe are far more malign which ariſe upon the Prepuce, than thoſe that grow on the *Glans* or Nut of the Yard. Now they are rebellious to the common Medicins of Ulcers which happen otherways, and they are alſo ſubject to turn into a Gangrene, ſo that ſundry who have not in time provided for themſelves by the uſe of *argentum vivum*, are forced for their negligence, to ſuffer the loſs of their *Glans*, and oft times of their whole Yard. Yet I am of opinion, that I think we muſt begin the cure of Ulcers

The Ulcers of the prepuce more malign than thoſe of the *Glans*.

Ulcers of the Yard with the general remedies of Ulcers. For all Ulcers arising in these parts by reason of copulation, are not virulent. But when as we shall find that we do no good by this means, and that the disease notwithstanding grows worse and worse, then must we come to make use of such things as receive *argentum vivum*, that by these we may resist the virulency which is ready to disperse it self over all the body; yet it is absolutely necessary that all these things be endued with such faculties as may return the malign acrimony of this venom, such an one is this following *collyrium* of *Lanfrank*. ℞ *Vini albi*, ℔ j. *aq. ros. & plantag. an.* quart 1. *auripig.* ʒ ij. *viridis æris*, ʒ j. *aloes, myrrhæ, an.* ʒ ij. *terantur subtilissime, & fiat collyrium.* Also these ulcers may be profitably touched with Mercury water, or *aqua fortis* which the Goldsmiths have used, or else Mercury in Powder, or our *Ægyptiacum:* but the falling away of the Eschar shall be procured with *basilicon*, or fresh butter. Yet I think it not fit to use these acrid things without very great caution, for fear of a Gangrene, which easily happens to this part: but if such Ulcers are so stubborn, that they will not yield to these remedies, then must we come to the friction or unction of the groins, *perinæum*, and ulcers, with the Ointments formerly prescribed for the general friction. Also Fumigations may be made, as we mentioned in the former Chapter: For thus at length the malignity of the virulent humour will be overcome, and the callous hardness mollified; and lastly, the Ulcers themselves cleansed, and being cleansed, consolidated. Sometimes after the perfect cure of such Ulcers, there will appear manifest signs of the *Lues Venerea* in many, which shewed not themselves before, for that the virulency flowed forth of the running Ulcers, and now this vent being stopt, it flows back into the body, and shews signs thereof in other parts; and these men have need of a general Unction.

Lanfranks Collyrium.

CHAP. XVI.

How a Gonorrhœa *differeth from a* * *Virulent Strangury.*

EVen to this day very many have thought that the virulent Strangury hath some affinity with the *Gonorrhœa* of the Ancients, but you shall understand by that which follows, that they are much different. For a *Gonorrhœa* is an unvoluntary effusion of seed running from the whole body to the genitals, by reason of the resolution and palsie of the retentive faculty of these parts, as it is delivered by *Galen, lib. de loc. affect.* This disease befalleth others by the collection of the bloud and seminal matter by the Vessels of the whole body, which not turning into fat and good flesh, takes its course to the genitals; but on the contrary, a virulent Strangury is a running, or rather dropping out of the urinary passage, of a yellowish, livid, bloudy, filthy *sanies*, like to *pus*, or matter not well concocted, oftentimes fretting and exulcerating the passage with the acrimony, and causing a painful erection of the Yard, and distension of all the genital parts. For in this erection there is caused as it were a convulsive contraction of these parts. And hence it is that the Patients complain that they feel as it were a string stretched stiff in that part, which draws the yard as it were downwards. The cause hereof is a gross and flatulent spirit, filling and distending by its plenty, the whole channel or hollow nerve, yea verily, the whole porous substance of the Yard. If to these symptoms this be added, that the urinary passage be exulcerated, a grievous pain afflicts the Patient whilest he makes water, for that the Ulcers are irritated by the sharp Urin passing that way. Such a virulent Strangury, or Running of the Reins oft-times continueth for two or three years space: but the *Gonorrhœa*, or Running of the Seed cannot endure so long, but that it will bring the body to an extreme and deadly leanness, for that the matter of the Seed is of the more benign and laudable portion of the bloud, as you may perceive by those who have too immoderately used copulation but the space of one night: For such have their Faces more lean and lank, and the rest of their bodies enervated, languisheth and becometh dull. By this we have delivered, it may be perceived that the running of virulent Strangury, is not the running of a seminal humour, fit for generation of issue, but rather of a viscous and acrid filth, which hath acquired a venenate malignity by the corruption of the whole substance.

* This which by our Author is here termed *Stranguria virulenta*, and in French *Chaudepisse*, is the same which by other Authors is usually termed *Gonorrhœa virulenta*, and by us vulgarly in English, *The Running of the Reins.*

What a virulent Strangury is.

The cause of the convulsive distension of the Yard.

Vid. aut. defin. med. apud Galen.

What kind of matter floweth forth in a virulent Strangury.

CHAP. XVII.

Of the Causes and Differences of the Scalding or Sharpness of the Urin.

THe heat or scalding of the Water, which is one kind of the virulent Strangury, ariseth from some one of these three Causes; to wit, Repletion, Inanition, and Contagion. That which proceeds from Repletion, proceeds either from too great abundance of bloud, or by a painful and tedious Journey in the hot Sun, or by feeding upon hot, acrid, diuretick, and flatulent Meats causing tension and heat in the urinary parts, whence proceeds the inflammation of them and the genital parts; whence it happens that not onely a seminal, but also much other moisture may flow unto those parts, but principally to the *Prostatæ*, which are Glandules situate at the roots, or beginning of the neck of the bladder, in which place the spermatick vessels end; also abstinence from Venery causeth this plenitude in some who have usually had to do with Women, especially the expulsive faculty of the seminal and urinary parts being weak, so that they are not of themselves able to free themselves from this burden: For then the suppressed matter is corrupted, and by its acrimony contracted, by an adventitious and putredinous heat, it causeth heat and pain in the passage forth. The *Prostatæ* swelling with such inflamed matter, in process of time become ulcerated, the abscess being broken. The purulent *sanies* dropping and flowing hence alongst the urinary passage causes the Ulcers by acrimony, which the Urin falling upon, exasperates; whence sharp pain, which also continueth for some short time after making of water, and together therewith by reason of the inflammation, the pains attraction, and the vaporous spirits distension, the Yard stands, and is contracted with

The cause of a particular repletion of the privy parts.

with pain, as we noted in the former Chapter. But that which happens through inanition, is acquired by the immoderate and unfit uſe of Venery, for hereby the oily and radical moiſture of the fore-mentioned Glandules is exhauſted, which waſted, and ſpent, the Urin cannot but be troubleſome and ſharp by the way to the whole *Urethra*. From which ſenſe of ſharp pain, the ſcalding of the Urin hath its denomination. That which comes by contagion, is cauſed by impure copulation with an unclean perſon, or with a woman, which ſome ſhort while before hath received the tainted ſeed of a virulent perſon, or elſe hath the Whites, or her Privities troubled with hidden and ſecret ulcers, or carrieth a virulent ſpirit ſhut up or hidden there, which heated and reſuſcitated by copulation, preſently infects the whole body with the like contagion, no otherwiſe then the ſting of a Scorpion or *Phalangium*, by caſting a little poiſon into the skin, preſently infects the whole body, the force of the poiſon ſpreading farther than one would believe, ſo that the party falls down dead in a ſhort while after. Thus therefore the ſeminal humour contained in the *proſtatæ*, is corrupted by the tainture of the ill, drawn thence by the Yard, and the contagion infects the part it ſelf; whence follows an abſceſs, which caſting forth the virulency by the urinary paſſage, cauſeth a virulent ſtrangury; and the malign vapour carried up with ſome portion of the humour unto the entrails and principal parts, cauſe the *Lues Venerea*.

The cauſes of the inanition of the genital parts.

The reaſon of a contagious Strangury.

CHAP. XVIII.

Prognoſticks in a virulent Strangury.

WE ought not to be negligent or careleſs in curing this affect, for of it proceed pernicious accidents, as we have formerly told you, and neglected, it becomes uncurable, ſo that ſome have it run out of their urinary paſſage during their lives; oft-times to their former miſery is added a ſuppreſſion of the Urin, the *proſtatæ* and neck of the bladder being inflamed and unmeaſurably ſwelled. Copulation, and the uſe of acrid or flatulent meats increaſe this inflammation, and alſo together therewith cauſe an *Iſchuria* or ſtoppage of the urin; they are worſe at the change of the Moon: certain death follows upon ſuch a ſtoppage; as I obſerved in a certain man, who troubled for ten years ſpace with a virulent Strangury, at length died by the ſtoppage of his water. He uſed to be taken with a ſtopping of his urin as often as he uſed any violent exerciſe, and then he helped himſelf by putting up a ſilver Catheter, which for that purpoſe he ſtill carried about him; it happened on a certain time that he could not thruſt it up into his bladder, wherefore he ſent for me, that I might help him to make water, for which purpoſe when I had uſed all my skill, it proved in vain: when he was dead and his body opened, his bladder was found full, and very much diſtended with urin, but the *proſtatæ* preternaturally ſwelled, ulcerated, and full of matter reſembling that which formerly uſed to run out of his Yard, whereby you may gather that this virulency flows from the *proſtatæ*, which runs forth of the Yard in a virulent Strangury, and not from the Reins, as many have imagined. Certainly a virulent Strangury, if it be of any long continuance, is to be judged a certain peculiar *Lues Venerea*, ſo that it cannot be cured unleſs by frictions with *Hydrargyrum*. But the ulcers which poſſeſs the neck of the bladder are eaſily diſcerned from theſe which are in the body or capacity thereof. For in the latter the filth comes away as the Patient makes water, and is found mixed with the Urin, with certain ſtrings or membranous bodies coming forth in the urin: to theſe may be added, the far greater ſtench of this filth, which iſſueth out of the capacity of the bladder. Now muſt we treat of the Cure of both theſe Diſeaſes, that is, the *Gonorrhœa* and virulent Strangury; but firſt of the former.

A virulent Strangury continues with ſome during their lives.

An Hiſtory.

From what part the matter of a virulent Strangury flows.

CHAP. XIX.

The chief heads of curing a Gonorrhœa.

LEt a Phyſician be called, who may give direction for purging, bleeding, and diet, if the affect proceed from a fulneſs and abundance of bloud and ſeminal matter; all things ſhall be ſhunned which breed more bloud in the body, which increaſe ſeed, and ſtir to venery. Wherefore he muſt abſtain from Wine, unleſs it be weak and aſtringent, and he muſt not onely eſchew familiarity with women, but their very pictures, and all things which may call them to his remembrance, eſpecially if he love them dearly; ſtrong exerciſes do good, as the carrying of heavy burdens even until they ſweat, ſwimming in cold water, little ſleep, refrigerations of the loins and genital parts, by anointing them with *unguentum roſarum refrigerans Galeni & nutritum*, putting thereupon a double cloth ſteeped in oxycrate, and often renewed. But if the reſolution or weakneſs of the retentive faculty of theſe parts be the cauſe of this diſeaſe, contracted by too much uſe of venery before they arive at an age fit to perform ſuch exerciſe; in this caſe ſtrengthening and aſtringent things muſt both be taken inwardly, and applied outwardly. But now I haſten to treat of the virulent Strangury, which is more proper to my purpoſe.

Diet.

For a Strangury occaſioned by repletion.

For the decay of the retentive faculty.

CHAP. XX.

The general Cure both of the ſcalding of the Water, and the virulent Strangury.

WE muſt diverſly order the Cure of this Diſeaſe, according to the variety of the Cauſes and Accidents thereof. Firſt, care muſt be had of the diet, and all ſuch things ſhunned as inflame the bloud, or cauſe windineſs; of which nature are all diuretick and flatulent things, as alſo ſtrong and virulent exerciſes. Purging and bleeding are convenient, eſpecially if fulneſs

Diet.

neſs cauſe the affect. Womens companies muſt be ſhunned and thoughts of venereous matters; the Patient ought not to lie upon a ſoft bed, but upon a quilt or mattrice, and never, if he can help it, upon his back: boiled meats are better than roſted, eſpecially boiled with Sorrel, Lettuce, Purſlain, cleanſed barley, and the four cold ſeeds beaten: for ſauce, let him uſe none, unleſs the juice of an Orange, Pomgranate, or Verjuice: let him ſhun Wine, and in ſtead thereof uſe a decoction of Barley and Licorice, an *hydromel*, or *hydroſaccarum*, with a little Cinamon, or that which is termed *Potus divinus*. In the morning let him ſup of a Barley Cream, wherein hath been boiled a *nodulus* of the four cold Seeds beaten together with the ſeeds of white Poppy; for thus it refrigerateth, mitigateth, and cleanſeth; alſo the ſyrups of Marſh-mallows and Maiden-hair are good. Alſo purging the belly with half an ounce of *Caſſia*, ſometimes alone, otherwhiles with a dram, or half a dram of Rhubarb in powder put thereto, is good. And theſe following Pills are alſo convenient. ℞ *Maſſæ pilul. fine quibus* ℈ j. *rhei electi* ʒ ß. *camphuræ gr.* iv. *cum terebinthina formentur pilulæ*; let them be taken after the firſt ſleep.

Pills.

The force of Venice Turpentine in this diſeaſe.

Venice Turpentine alone, or adding thereto ſome Rhubarb in powder, with Oil of ſweet Almonds newly drawn without fire, or ſome ſyrup of Maiden-hair, is a ſingular Medicin in this caſe, for it hath an excellent lenitive and cleanſing faculty, as alſo to help forwards the expulſive faculty to caſt forth the virulent matter contained in the *Proſtatæ*. You may by the bitterneſs perceive how it reſiſts putrefaction, and you may gather how it performs its office in the Reins and Urinary parts, by the ſmell it leaves in the Urin after the uſe thereof. But if there be any who cannot take it in form of a Bole, you may eaſily make it potable, by diſſolving it in a Mortar with the Yolk of an Egg, and ſome white Wine, as I learned of a certain Apothecary, who kept it as a great ſecret. If the diſeaſe come by inanition or emptineſs, it ſhall be helped by fatty injections, oily and emollient potions, and inwardly taking and applying theſe things which have the like faculty, and ſhunning theſe things which cauſed the diſeaſe. How to cure that which happens by contagion, or unpure copulation, it ſhall be abundantly ſhewed in the enſuing Chapter.

How to be made potable.

CHAP. XXI.

The proper Cure of a virulent Strangury.

An injection to ſtay inflammation.

FIrſt, we muſt begin with the mitigation of pain, and ſtaying the inflammation, which ſhall be performed by making injection into the *Vrethra* with this following decoction warm. ℞ *Sem. pſilii, lactucæ, papav. albi, plantag. cydon. lini, hyoſcyami albi an.* ʒ ij. *detrahantur mucores in aquis ſolani & roſar. ad quantitatem ſufficientem, adde trochiſc. alborum Rhaſis camphoratorum in pollinem redactorum,* ʒ j. *miſce ſimul, & fiat injectio frequens:* For this becauſe it hath a refrigerating faculty, will help the inflammation, mitigate pain, and by the mucilaginous faculty lenifie the roughneſs of the *Vrethra*, and defend it by covering it with the ſlimy ſubſtance, againſt the acrimony of the Urin and virulent humours. In ſtead hereof you may uſe Cows milk newly milked, or warmed at the fire. Milk doth not onely conduce hereto, being thus injected, but alſo drunk, for it hath a refrigerating and cleanſing faculty, and by the ſubtilty of the parts it quickly arrives at the urinary paſſages. Furthermore, it will be good to anoint with *Cerat. refriger. Galeni, addita camphora*, or with *Ceratum centalinum, ung. comitiſſæ*, or *nutritum*, upon the region of the kidnies, loins, and *perinæum*, as alſo to anoint the Cods and Yard. But before you uſe the aforeſaid Ointments, or the like, let them be melted over the fire, but have a care that you make them not too hot, leſt they ſhould loſe their refrigerating quality, which is the thing we chiefly deſire in them. Having uſed the aforeſaid ointment, it will be convenient to apply thereupon ſome linnen cloths moiſtned in oxycrate, compoſed *ex aquis plantaginis, ſolani, ſempervivi, roſarum*, and the like. If the Patient be tormented with intolerable pain in making water, and alſo ſome ſmall time after, as it commonly cometh to paſs, I would wiſh him that he ſhould make water, putting his Yard into a Chamber-pot filled with milk or water warmed. The pain by this means being aſſwaged, we muſt come to the cleanſing of the ulcers by this or the like injection: ℞ *Hydromelitis ſympt.* ʒ iv. *ſyr. de roſis ſiccis, & de abſinth. an.* ʒ ß. *fiat injectio.* But if there be need of more powerful deterſion, you may ſafely add, as I have frequently tried, a little *Ægyptiacum*. I have alſo found this following decoction to be very good for this purpoſe. ℞ *Vini albi odoriferi,* ℔ ß. *aquar. plantag. & roſ. an.* ʒ ij. *auripigmenti,* ʒ ß. *viridis æris,* ℈ j. *aloes opt.* ʒ ß. *pulveriſentur pulveriſanda, & bulliant ſimul.* Keep the decoction for to make injection withall. You may increaſe or diminiſh the quantity and force of the ingredients entering into this compoſition, as the Patient and Diſeaſe ſhall ſeem to require. The Ulcers being thus cleanſed, we muſt haſten to dry them, ſo that we may at length cicatrize them. This may be done by drying up the ſuperfluous moiſture, and ſtrengthening the parts that are moiſtned and relaxed by the continual defluxion, for which purpoſe this following decoction is very profitable. ℞ *Aq. fabrorum,* ℔ j. *pſidiarium, balauſt. nucum cupreſ. conquaſſatorum, an.* ʒ j. ℥. *ſemin. ſumach. & berber. an.* ʒ ij. *ſyrup. roſar. & de abſinth. an.* ʒ j. *fiat decoctio.* You may keep it for an injection to be often injected into the *Vrethra* with a ſyringe, ſo long as that there ſhall no matter or filth flow over thereat, for then there is certain hope of the cure.

The faculties of Milk againſt a virulent Strangury.

How to make water without pain.

Detergent injections.

How the cleanſed ulcers may be dried.

CHAP.

CHAP. XXII.

Of Caruncles or fleshy Excrescences which sometimes happen to grow in the Urethra, *by the heat or scalding of the Urin.*

A Sharp humour which flows from the Glandules, termed *Prostatæ*, and continually runs alongst the urinary passage, in some places by the way it frets, and exulcerates by the acrimony the *Urethra* in men, but the neck of the womb in women. In these, as also is usual in other ulcers, there sometimes grows up a superfluous flesh, which oft-times hinders the casting or coming forth of the Seed and Urin by their appropriate and common passage, whence many mischiefs arise; whence it is that such ulcers as have caruncles growing upon them must be diligently cured. But first we must know whether they be new or old. For the later are more difficultly to be cured than the former, because the caruncles that grow upon them become callous and hard, being oft-times cicatrized. We know that there are caruncles, if the *Catheter* cannot freely pass alongst the passage of the Urin, but finds so many stops in the way, as it meets with caruncles that stop the passage; if the Patient can hardly make water, or if his water run in a very small stream, or two streams, or crookedly, or onely by drop and drop, with such tormenting pain, that he is ready to let go his excrements, yea and oft-times doth so, after the same manner as such as are troubled with the stone in the bladder. After making water, as also after copulation, some portion of the urin and seed stays at the rough places of the caruncles, so that the Patient is forced to press his Yard, to press forth such reliques. Sometimes the urin is wholly stopped, whence proceeds such distension of the bladder, that it causeth inflammation, and the urin flowing back into the body, hastens the death of the Patient. Yet sometimes the urin thus suppresst, sweats forth preternaturally in sundry places, as at the Fundament, *Perinæum*, Cod, Yard, Groins. As soon as we, by any of the fore-mentioned signs, shall suspect that there is a caruncle about to grow, it is expedient forthwith to use means for the cure thereof; for a caruncle from a very little beginning doth in a short time grow so big, that at the length it becomes incurable: verily, you may easily guess at the difficulty of the cure, by that we have formerly delivered of the essence hereof; besides, Medicins can very hardly arrive thereat. The fittest season for the undertaking hereof is the Spring, and the next thereto is Winter; yet if it be very troublesom, you must delay no time. Whilest the cure is in hand, the Patient ought wholly to abstain from Venery, for by the use thereof, the Kidnies, Spermatick Vessels, *Prostatæ*, and the whole Yard, swell up and wax hot, and consequently draw to them from the neighbouring and upper parts, whence abundance of excrements in the affected parts, much hinder the cure. You must beware of acrid and corroding things in the use of detergent injections, for that thus the *Urethra* being induced with most exquisit sense, may be easily offended, whence might ensue many ill accidents. Neither must we be frighted, if at sometimes we see bloud flow forth of secret or hidden caruncles. For this helps to shorten the cure, because the disease is hindered from growth, by taking away portion of the conjunct matter, the part also it self is eased from the oppressing burden, for the material cause of caruncles is superfluous bloud. Wherefore unless such bleeding happen of it self, it is not amiss to procure it by thrusting in a *Catheter* somewhat hard, yet with good advice. If the caruncles be inveterate, and callous, then must they be mollified by Fomentations, Ointments, Cataplasms, Plasters, and Fumigations; you may thus make a Fomentation. ℞ *Rad. althæ. & lilior. alb. an.* ℥ v. *rad. bryoniæ, & fœnic. an.* ℥ j. ß. *fol. malvar. violarum parietar. & mercur. an.* m. ß. *sem. lini. fœnugr. an.* ℥ ß. *caricas ping.* nu. xij. *florum chamæm. & melil. an.* p. j. *contundantur contundenda, incidenda incidantur, bulliant omnia in aqua communi:* make a Fomentation, and apply it with soft Sponges. Of the mass of the strained-out things you may make a cataplasm after this manner. ℞ *Prædicta materialia, terantur, & trajiciantur, adde axungiæ porci, unguenti basiliconis, an.* ℥ ij. *fiat cataplasma:* let it be applied presently after the fomentation. You may use this following Liniment whilest the Cataplasm is providing. ℞ *Unguenti althæ. & agrippæ, an.* ℥ j. ß. *æspi humidæ, & axung. human. an.* ℥ j. *butyri recentis, olei lilior. & chamæm. an.* ʒ vj. *liquefiant simul, addendo aquæ vitæ* ℥ j. *fiat linimentum.* Let it be applied outwardly upon the part wherein the caruncles are. For the same purpose Plasters shall be applied, which may be diversified and fitted as you shall think good; yet *Emplastrum de Vigo* truly made, exceedeth all the rest in a mollifying faculty, and in wasting such callous hardness. The following Fumigation is also good for the same purpose; take some pieces of a Mill-stone (for this we use in stead of the *Pyrites* mentioned by the Ancients) or else some Bricks of large size, after they are heated hot in the fire, let them be put into a Pan and set under a Close-stool, then cause the Patient to sit thereon as if he were going to Stool, then pour upon the hot stones equal parts of very sharp Vinegar, and very good *aqua vitæ*, and casting cloths about him, that nothing may exhale in vain: let him receive the ascending vapour at his Fundament, *Perinæum*, *Scrotum*, and *Urethra*. Moreover that this Medicin may work the better effect, you may put the Patient naked into the Barrel noted with this letter *A*, so that he may sit upon a seat or board perforated on that part, whereas his genitals are, then place the Pan holding the hot stones between his legs, then presently sprinkle the stones with the fore-mentioned liquor, by the door marked with the letter *B*. Thus the Patient shall easily receive the fume that exhales therefrom, and none thereof be lost, he covering and vailing himself on every side. Such a fumigation in *Galen*'s opinion, hath a faculty to penetrate, cut, resolve, soften and digest scirrhous hardnesses.

How caruncles come to grow upon the ulcers of the genital parts.

Callous caruncles hard to cure. Signs.

The suppresst urin comes forth whereas it can get vent

The fittest time for the cure.

Why Venery must be eschewed.

The particular cure.

A Fomentation.

A Caraplasm.

A Liniment.

Vigo's Emplaster effectual to soften a caruncle.

A Suffumigium.

Ad Glauc. lib. 2. cap. 5.

A Barrel fitted to receive the Fume in.



CHAP. XXIII.

What other remedies ſhall be uſed to Caruncles occaſioned by the Lues Venerea.

Particular defaults of the *Lues Venereæ* not to be cured unleſs by the general remedy of the virulency.

BUt if you ſuſpect that theſe Caruncles come or are occaſioned by a virulent humour, or the malignity of the *Lues Venerea*, it is meet that the Patient obſerve ſuch a diet as uſually is preſcribed to ſuch as are troubled with the *Lues Venerea*; let him uſe a decoction of *Guaiacum*, and let the *perinæum* and the whole Yard be anointed with ointment made for the *Lues Venerea*; otherwiſe the Surgeon will loſe his labour. In the *interim*, whileſt he ſhall ſweat in his bed, he ſhall be wiſhed to hold between his legs a ſtone-bottle filled with hot water, or elſe a hot brick wrapped in linnen cloths moiſtned in Vinegar and *Aqua vitæ*; for thus the heat and vapour will aſcend to the genitals, which, together with the help of the applied ointment, will diſſolve the matter of the Caruncles, and being thus ſoftned, they muſt be conſumed with convenient Medicins. Wherefore firſt, if they become callous, or cicatrized (which you may ſuſpect if they caſt forth no excrementitious humidity) they ſhall be exaſperated, excoriated and torn with a leaden *Catheter* having a rough button at the end like a round file. He ſhall ſo long uſe the *Catheter* put into the *Urethra*, thruſting it up and down the ſame way ſo long and often as he ſhall think fit for the breaking and tearing the Caruncles, he ſhall permit them thus torn to bleed freely, ſo to eaſe the affected part. You may alſo for the ſame purpoſe put into the *Urethra* the *Catheter* marked with this letter *B*; whereinto putting a ſilver wier ſharp at the upper end, that by oft thruſting it in and out it may wear and make plain the reſiſting Caruncles. Verily by this means I have helped many much perplexed with the fearful danger of this diſeaſe. Some better like of the *Catheter* marked with this letter *A*, being thus uſed: it is thruſt into the *Urethra* with the prominent cutting ſides downwards, and then preſſing the Yard on the outſide cloſe with your hand to the *Catheter* in the place where the Caruncles are, it is drawn forth again.

Caruncles, if callous, muſt firſt be ſoftned.

A Powder to waſte Caruncles.

The Caruncle thus torn ſhall be ſtrewed over with the following powder, being very effectual to waſte and conſume all Caruncles of the Privities without much pain. ℞ *Herb. ſabin. in umbra exſiccat.* ʒ ij. *ocræ, antimon. tut. præparat. an.* ʒ ß. *fiat pulv. ſubtiliſſimus*; let it be applied in the following manner. Put the powder into the Pipe or *Catheter* having holes in the ſides thereof, the which is the lowermoſt of the laſt deſcribed: then put the *Catheter* into the urinary paſſage until the ſlit or openneſs of the ſide come to the Caruncle, then into the hollowneſs of the *Catheter* put a ſilver wier, wrapped about the end with a little linnen rag, which as it is thruſt up, will alſo thruſt up the powder therewith, until it ſhall come to the ſlit againſt the Caruncle, then will it adhere to the Caruncle bloudy, by reaſon of the ſaid attrition. Then ſhall you draw forth the *Catheter*, firſt twining it about, that ſo it may not ſcrape off the powder again. If intolerable pain hereupon happen, it ſhall be aſſwaged, and the inflammation reſtrained by the following injection. ℞. *Succorum portulacæ, plantag. ſolani, & ſempervivi, an.* ʒ ß. *album ovorum*, nu.vj. *agitentur diu in mortario plumbeo*; let it be injected warm into the *Urethra* with a ſyringe. In ſtead hereof you may alſo make uſe of another injection, which is formerly preſcribed. Neither will it be unprofitable to apply repercuſſives to the genitals to hinder pain and inflammation. You may alſo uſe other Medicins, having a faculty to conſume the Caruncle, amongſt which theſe following are excellent. ℞ *Viridis æris, auripigmenti, vitriol. Rom. aluminis roch. an.* ʒ ij. *infundantur omnia in aceto acerrimo, atque inter duo marmora in pollinem redigantur:* then let it be expoſed to Summers Sun, and dried, again infuſed in ſharp Vinegar, and then as before ground upon a Marble, ſo that you find nothing ſharp with your fingers; laſtly, let it be oppoſed to the Sun until it may be made into moſt ſubtil Powder, and all the acrimony be vaniſhed, which will be commonly in eight days ſpace. Then, ℞ *ol. roſar.* ʒ iv. *litharg yr.* ʒ ij. *coquantur ad*

How to apply it.

An injection to hinder inflammation.

An Emplaſter uſed by the Surgeons of *Mountpelier* for Caruncles.

ignem

which will be commonly in eight days ſpace. Then ℞ *Ol. roſat.* ℥ iv. *lithargyr.* ℥ ij. *coquantur ad ignem, quouſque coierint in emplaſt. ſolidæ conſiſtentiæ, ab igne tum ſemotis, adde pulv. prædict.* ℥ ij. let them be mixed with a Spatula, and put it upon the fire until it come to ſo hard a conſiſtence, that it will ſtick faſt to a Wax Candle, or Lead Wier, ſo that it may not come off by handling with your hands. The Surgeons of *Montpelier* uſe this Medicin. This following is another; ℞ *Tutiæ præparat.* ℥ vj. *antimonii* ℥ iij. *trochiſc. alborum, Rhaſ. camphorat.* ʒ j. *corticis granati, aluminis uſti, an* ℥ j. ß. *ſpongiæ uſtæ,* ʒ ij. let them be all made into powder: then, ℞ *Ung. diapompholygos, & alb. Rhaſis, an.* ℥ ij. *miſceantur cum prædictis pulveribus in mortario plumbeo, & diu agitentur:* let a very fine rag be ſpread over with this ointment, and wrapped about a Wax Candle, and ſo thruſt into the *Urethra*, and then draw forth the Candle by twining it a contrary way; ſo let the end of the rag hang out of the Yard ſo to pluck it forth again, when as you ſhall think it hath done what it can to the Caruncle, which is, when it hath covered it with the Medicin with which it was ſpread. Some alſo make Wax Candles with a ſlender, but ſtiff wick, whoſe end, which is to be put to wear and conſume the Caruncle, is compoſed of the following Medicin. ℞ *Emplaſtri nigri, vel diachylonis ireati,* ℥ ij. *pulv. ſabinæ, ocræ, vitriol. Rom. calcin. pul. mer. an.* ʒ ß. *omnia liqueſcant ſimul ad dictum uſum.* Whileſt the cure ſhall be in hand, by theſe following Medicins, let the Patient be careful that he ſo ſhake his Yard after making water, that he may ſhake forth all the reliques of the Urin which may chance to ſtop at the Caruncles, for if but one drop ſhould ſtay there, it would be ſufficient to ſpoil the whole operation of the applied Medicins. After that the Caruncle ſhall be worn away and wholly conſumed by the deſcribed Medicins, which you may know by the Urin flowing forth freely, and in a full ſtream, and by thrutting up a *Catheter* into the bladder without any ſtoppage; then it remains that the ulcers be dried and cicatrized, for which purpoſe the following injection is very powerful and effectual, and without any acrimony. ℞ *Aq. fabrorum,* ℔ ß. *nuc. cupreſ. gallar. cort. granat. an.* ʒ j. ß. *alum. roch.* ʒ ß. *bulliant. omnia ſimul ſecund. art.* ſo make a decoction for an injection, which you ſhall uſe ſo long until no excrementitious humidity diſtil out of the Yard. The following Powder dries more powerfully, and conſequently haſtens forwards cicatrization, and it is alſo without acrimony. ℞ *Lapidem calamin. lotum, teſtas ovorum uſtas, corallum rubrum, corticem granat. comminue omnia in pollinem;* let this Powder be uſed to the ulcers with a Wax Candle joined to ſome *unguentum deſiccativum rubrum*, or ſome ſuch like thing. Alſo ſtrings or rods of lead thruſt into the *Urethra* as thick as the paſſage will ſuffer, even to the Ulcers, being firſt beſmeared with quick-ſilver, and kept in day and night as long as the Patient can endure, are good to be uſed. For they dry by their touch and cicatrize, they dilate the urinary paſſage without pain, and laſtly hinder the ſides of the Ulcers from corrupting one another.

Another Emplaſter.

How to apply it.

A caution in making water.

Signs that the Caruncle is worn away.

An Epulotick injection.

Quick-ſilver by drying cauſeth cicatrization.

Catheters fit to wear aſunder, or tear Caruncles.

A *Sheweth the* Catheter *with the inſerted ſilver Wier, but not hanging forth thereat.*
B *Sheweth the* Catheter *with the inſerted ſilver Wier hanging forth at the end.*

CHAP. XXIV.

Of venereal Buboes, *or ſwellings in the Groins.*

THe virulency of the *Lues Venerea* is ſometimes communicated to the Liver, which if it have a powerful expulſive faculty, it expels it into the groins, as the proper emunctories thereof, whence proceed venereal Buboes. The matter of theſe, for the moſt part, is abundance of cold, tough, and viſcous humours, as you may gather by the hardneſs and whiteneſs of the tumor, the pravity of the pain, and contumacy of curing; which alſo is another reaſon, beſides theſe that we formerly mentioned, why the virulency of this diſeaſe may be thought commonly to faſten it ſelf in a phlegmatick humour. Yet ſometimes venereal Buboes proceed from a hot, acrid, and cholerick humour, aſſociated with great pain and heat, and which thereupon often degenerate into virulent and corroding ulcers. Some venereous Buboes are ſuch conjoined accidents of the *Lues Venerea*, that they foretell it; ſuch are theſe which for a ſmall while ſhew a manifeſt tumor, and ſuddenly, without any manifeſt occaſion hide themſelves again, and return back to the noble parts. Others are diſtinct from the *Lues Venerea* though they have a ſimilitude of eſſence and matter therewith, and which therefore may be healed, the *Lues Venerea* yet remaining uncured. Such are theſe which are uſually ſeen, and which therefore compared with the former, may be termed ſimple and not implicit. For the cure, you muſt not uſe diſcuſſing Medicins, leſt reſolving the more ſubtil part, the groſſer dregs become impact and concrete there; but much

The efficient and material cauſes of venereous Buboes.

What Buboes fore-tell the *Lues Venerea*.

leſs muſt we uſe repercuſſives, for that the matter is virulent. Wherefore onely attractive and ſuppurating Medicins are here to be uſed, agreeable to the humour predominant and cauſing the tumor, as more hot things in œdematous and ſcirrhous tumors, than in thoſe which reſemble the nature of a *phlegmon*, or *eryſipelas*: the indication taken from the rarity and denſity of bodies inſinuates the ſame variety. The applying of Cupping-glaſſes is very effectual to draw it forth: But when as it is drawn forth, you ſhall forthwith apply an emplaſtick Medicin, and then you ſhall come to ſuppuratives. When the tumor is ripe it ſhall be opened with a potential cautery, if it proceed from a cold cauſe; for by the inducing of heat the reſidue of the crude matter is more eaſily concocted; beſides, when as an ulcer of this kind is opened, the matter will be more eaſily evacuated, neither ſhall it be fit to uſe any tent, but only to apply pledgets. The reſidue of the cure ſhall be performed by detergent Medicins, and then, if need require, the Patient ſhall be let bloud, and the humours evacuated by a purging Medicin, but not before the perfect maturity thereof.

Cupping.

A potential Cautery.

CHAP. XXV.

Of the Exoſtoſis, *bunches or knots growing upon the bones by reaſon of the* Lues Venerea.

The matter of knots and virulent *Tophi*.

HArd tumors, *Exoſtoſes* and knots, have their matter from thick and tough phlegm, which cannot be diſſolved unleſs by hot Medicins, which have a mollifying and diſſolving faculty. For which purpoſe, beſides thoſe Medicins which uſually are applied to ſcirrhous humours, you muſt alſo make uſe of *Argentum vivum* commonly after this manner. ℞ *Emplaſt. filii Zach. & Ceronei, an.* ʒ iij. *cuphorb.* ʒ ß. *emplaſt. de Vigo,* ʒ ij. *cerat. æſp. deſcript. Philagr.* ʒ j. *argent. vivi extinct.* ʒ vj. *fiat emplaſtrum.* Spread it upon Leather for your uſe. In the mean ſpace let the Patient obſerve a ſparing diet; for thus he ſhall be helped, if ſo be that the ſubſtance of the bones be yet unperiſhed: For if it be putrefied and rotten, then deſcribed Medicins are of no uſe, but you muſt of neceſſity lay bare the bone, either by inciſion, or elſe by an actual or potential cautery; but I had rather do it with an actual, for that it extracts the virulency impact in the bones, as alſo it haſtens the abſceſs, or falling away of the corrupted bone. It ſhall be of a convenient figure to cauterize the bone, as round, ſquare, or long. I uſually before the application of ſuch a Cauſtick, firſt divide the fleſh that lies over it with an inciſion-knife, that ſo the pain may be the leſs, becauſe the fleſh cannot burn through but in a long time, by which the fire may come to the bone. But it will not be amiſs before we treat of this Art, firſt to conſider the nature of the rottenneſs of the bones.

An emplaſter againſt the bunching out of the bones.

CHAP. XXVI.

Why the bones become rotten, and by what ſigns it may be perceived.

Gal. meth. 6.

THat ſolution of continuity which is in the bones, is called by *Galen*, *Catagma*. This uſually is the cauſe of rottenneſs; for bones that are grated, bruiſed, rent, perforated, broken, luxated, inflamed and deſpoiled of the fleſh and skin, are eaſily corrupted; for deſpoiled of their covering, they are altered by the appulſe of the air, which they formerly never felt; whence alſo their bloud and proper nouriſhment is dried up and exhauſted. Beſides alſo, the *ſanies* running down by reaſon of wounds and old ulcers, in proceſs of time faſtens it ſelf into their ſubſtance, and putrefies by little and little: this putrefaction is increaſed and cauſed by the too much uſe of oily and fatty Medicins, as moiſt and ſuppurate things; for hence the Ulcer becometh more filthy and malign, the fleſh of the neighbouring parts groweth hot, is turned into *pus*, which preſently falling upon the bone lying under it, inflames it. Laſtly, the bones are ſubject to the ſame diſeaſes as the fleſh that lieth under them is; beſides alſo, according to *Galen*, the beginning of inflammation oft-times proceeds from the bones, but they heat not, becauſe according to the opinion of the Ancients, pulſation is a dolorifick motion of the Arteries, but the bones want ſenſe. Which verily I cannot deny, but alſo we muſt confeſs that the membrane that encompaſſeth them, and the arteries that enter into their body, are endued with moſt exquiſite ſenſe. Wherefore the arteries compreſſed and waxing hot by reaſon of the inflamed bone, cauſe a ſenſe of pain in the *periоſteum*, ſo that the Patients complain of a dull and deep pain, as it were ſunk into the ſubſtance of the bones. The rottenneſs or corruption is oft-times manifeſt to the eye, as when the bone is laid bare, for then it varieth from the natural colour, and becomes livid, yellowiſh, or black. Otherwiſe you may perceive it by touch, as by ſearching it with a probe, as when you meet with any inequality or roughneſs, or when but gently touching it your Probe runs into the ſubſtance of the bone as into rotten wood; for a bone is naturally hard, but being rotten, becomes ſoft. Yet hardneſs is not an infallible ſign of a ſound bone: for I have ſeen rotten and bared bones to have ſometimes grown ſo hard, by the appulſe of the air, that a Trepan could not, without a ſtrong endeavour, enter them. Alſo the rottenneſs of the bone is known by the condition of the filth which flows forth of the ulcer, for it is not onely more thin and liquid, but alſo more ſtinking. Furthermore, ſuch ulcers have a ſoft, looſe, and watery fleſh; beſides alſo they are untoward and rebellious to ſarcotick and epulotick Medicins; to which if they chance to yield and be cicatrized, yet within a ſhort while after, the ſcar will relent of its own accord, for that Nature deſtitute of the firm and ſound foundation of the bones, cannot build up a laudable and conſtant fleſh. Neither is it ſufficient that the Surgeon know certainly that the bone is rotten and corrupt; it is furthermore fit he know, whether the corruption be ſuperficiary, or pierce deep into the ſubſtance of the bone, that he may know how much of the bone muſt be ſcaled: for ſcaling is the onely cure of that which is corrupted; now it is ſcaled by that which dries exceedingly, and draws forth all the humidity, as well the excre-

Hip. lib. de ulc. fract. *Gal. lib. de tum. cont. nat.*

The frequent cauſe of the rottenneſs of bones.

Signs of the rottenneſs.

Hardneſs is no infallible ſign of ſound bones

The cure of a rotten bone.

excrementitious, the author of the rottenneſs, as the alimentary: For thus it remains without bloud and nouriſhment, and conſequently life alſo; whence it muſt of neceſſity ſcale or fall off, being deſtitute of the glue or moiſture which joined it to the ſound parts in vicinity and communion of life, like as leaves which fall away from the trees, the humidity being exhauſted, by which, as by glue, they adhered to the boughs. For this purpoſe Catagmatick powders are prepared to amend the corruption which is onely ſuperficiary. ℞ *Pul. aloes, cretæ combuſtæ, pompholygos, an.* ʒ ij. *ireos flor. ariſtoloch. rot. myrrh. ceruſſæ, an.* ʒ j. *pul. oſteor. combuſt.* ʒ ß. *terantur ſubtiliſſ. fiat pulvis*; let it be applied either alone by it ſelf, or elſe with Honey and a little *Aqua vitæ*. Alſo the following Emplaſter being applied, ſtirs up Nature to the excluſion of the broken bones, and cleanſeth the ulcers from the more groſs and viſcid *ſanies*. ℞ *Cer. nov. reſ. pini, gum. ammon. & elemi, an.* ʒ vj. *tereb.* ℥ iij. *pul. maſtich. myrrh. an.* ℥ ß. *ariſtol. rot. ireos flor. aloes, opopan. euphorb. an.* ʒ j. *olei roſati quantum ſufficit, fiat emplaſt. ſecundum artem.* *Euphorbium*, according to *Dioſcorider*, takes off the ſcales of bones in one day. Hereto alſo conduceth *Emp. de betonica*. Or, ℞ *olei caryophyl.* ℥ ß. *camph.* ʒ ij. *miſceantur ſimul in mortario, & utere*. But if that part of the bone which is corrupt cannot thus be taken away, then muſt you uſe the ſcaling Trepans and Scrapers deſcribed formerly in wounds of the head; eſpecially if any more great or ſolid bone be foul. Furthermore the here-deſcribed Trepan will be good to perforate the rotten bone in many places where it is corrupted, until as it were a certain bloudy moiſture iſſue forth at the holes; for thus it more freely enjoys the air, and alſo the force of the medicins admitted by theſe holes work more powerfully.

A catagmatick Powder.

A deſquamatory or ſcaling Plaſter. *Dioſc. lib. 7. cap. 78.*

A Trepan with two triangular bits and a pin no hold them in the ſtock: as alſo another Trepan having four-ſquare and ſix-ſquare bits convenient to be uſed in the rottenneſs of greater bones.



But if the rottenneſs be more deep, and the bone more hard, either by Nature or Accident, as by the occaſion of the too long admiſſion of the air, then the rotten ſcales ſhall be cut off by the inſtruments deſcribed in wounds of the head, driving them into the bone with leaden mallets, leſt the part ſhould be too much offended or ſhaken with the blow. The ſcales and fragments ſhall be taken forth with mullets; the ſigns that all the rottenneſs is taken away, are the ſolidneſs of the bone thereunder, and the bloudy moiſture ſweating out thereat.

Signs that the rottenneſs is taken away.

CHAP. XXVII.

Of actual and potential Cauteries.

BUt if the deſcribed remedies cannot take place, by reaſon of the malignity or magnitude of the rottenneſs, then muſt we come to actual and potential Cauteries. But I ſhould rather approve of actual, becauſe by ſtrengthening the part they conſume the excrementitious humours wherewith it is overcharged, to wit, the matter of the *Caries*; which is not ſo effectually performed by potential cauteries. Yet are we oft-times forced to uſe theſe, to pleaſe the Patients which are terrified at, and afraid of hot irons. Potential Cauteries are *Aqua fortis, Aqua vitrioli*, ſcalding Oil, melted Sulphur and boiling, and the like; in pouring on of which I would have the Surgeon to be prudent and induſtrious, leſt he ſhould raſhly violate the neighbouring ſound parts by the burning touch of theſe things; which his temerity would cauſe vehement pains, inflammations, and other horrid ſymptoms. For actual Cauteries, their variety in figure is ſo great, that it cannot be defined, much leſs ſet down in writing; for they muſt be varied according to the largeneſs of the rottenneſs, and the figure and conformation of the fouled bones. Such as are more uſual I have thought good to delineate unto you, content onely to admoniſh you thus much, that ſome of theſe work by pricking, ſome by cutting, ſome flatwiſe, and other ſome with their points made to the form of an Olive-leaf.

Actual Cauteries to be preferred before Potential.

Potential Cauteries.

Sundry forms of actual Cauteries fit in all neceſſary caſes of all parts.



Other Cauteries.



Other Cauteries for the ſame purpoſe.



The following figure of a Cautery is fit for virulent knots that ariſe in the ſcull, when you deſire to take away the fleſh that covers the bone; for this purpoſe it is made hollow and ſharp in a triangular and quadrangular form, divided as it were into three branches, that you may ſo make uſe of which you pleaſe.

The Figure of an hollow and cutting Cautery.



The Cauteries whoſe forms are hereafter expreſt, take place in rotten bones that lie deep in, where in you cannot make uſe of the formerly deſcribed, without touching of the neighbouring ſound parts. To avoid which danger, you ſhall put your cautery even to the bone through an iron pipe, which may keep the neighbouring and fleſhy parts from burning.

Actual Cauteries with their Pipes.



Great diſcommodities enſue upon too raſh, that is, too frequently applied Cauteries, or too long adhering to the bone; for by this immoderate and fiery heat not onely the excrementitious humidity of the rotten bone is conſumed, but alſo the radical and ſubſtantial moiſture of the part is exhauſted, wherein alone Nature endeavouring to caſt off the corrupt ſcales, and ſever the ſound from the rotten bone, and to ſubſtitute fleſh, ſtands and conſiſts. Wherefore, the meaſure of applying of cauteries ought to be taken from the greatneſs of the rottenneſs, and the excrementitious, or after a manner, foming humidity ſweating through the pores of the bone. But before you preſs your cautery into the rotten bone which lies very deep in, as that which happens in the thigh-bone, and upon other very fleſhy parts, you muſt diligently defend the neighbouring ſound and fleſhy part, as it were with a covering, for that the humour diffuſed by the touch of the fire, burns the other places whereunto it diffuſeth it ſelf like ſcalding oil. After the cauterization, you muſt help forwards the falling away of the ſcales by ſometimes dropping in our Oil of Whelps, being made ſcalding hot. This Oil, though very fit for this purpoſe, yet do I not judge it fit to uſe it too often, it may ſuffice to have dropped it in ſome twice or thrice: for at length it may violate the ſound bone that lies under the rotten, by the oily, ſubtil and moiſt ſubſtance. Furthermore, a bone is the moſt dry part of the body, therefore unctuous and moiſt Medicins are contrary to its temper and conſiſtence. But it conduceth often and gently to move the ſcales already beginning to ſeparate themſelves, and it haſtens the ſlackneſs of Nature in caſting them off. Yet may you not uſe force, unleſs peradventure when as they hang by a ſlender thread; otherwiſe if the unwary Surgeon forcibly pluck away the ſcales before that Nature hath put a cover upon the ſound bone, he ſhall give way to a new alteration and foulneſs, by the appulſe of the air. Furthermore, after the corrupt ſcale is falling off, by the force of Nature expelling it, you muſt have a diligent heed that you put not eating or corroding Medicins upon the bone that is under it; for thus thou ſhalt conſume or waſte the fleſh which Nature hath generated thereupon, which compoſed of newly concreted bloud, is like in ſoftneſs to newly curdled milk, which otherwiſe in time would grow into a more ſolid and hard conſiſtence. This under-growing fleſh by little and little thruſts the rotten bone above it, out of its place, and is the cauſe of the ſcaling thereof; it is at the firſt gathered together like the grains of a pomgranate, with a red, ſmooth and equal *ſanies*, and not ſtinking, and at length it caſts forth a white matter. Therefore then we muſt rather ſtrew thereon Cephalick powder compoſed of ſuch things as have a faculty to dry without biting, ſuch as are Orris-root, waſhed Aloes, Maſtich, Myrrh, Barly-flower, and the like. Laſtly, it muſt be cicatrized, it is better that ſcales of bones fall away of themſelves, by the onely force of Nature, than to be plucked away by the force of Medicins or Inſtruments; becauſe ſuch as are too violently and forcibly plucked away, leave corners like to fiſtulous ulcers. Neither ought the corrupted membranes when they are turned into *pus*, to be plucked away too violently, or to be touched by too acrid Medicins; for pain hereupon ariſing, hath divers times cauſed inflammation, convulſion, and other pernicious ſymptoms. Therefore it is better to commit this buſineſs to Nature, which in ſucceſs of time, by making uſe of the expulſive faculty, will eaſily free it ſelf from this rotten ſubſtance; for that which is quick as far as it is able, will ſtill put away that which is dead from it.

Manner of applying of Cauteries.

Oil of Whelps helps forwards the caſting off of ſcales.

A caution in moving the ſcales of burnt bones.

Cephalick Powders of what compoſed.

CHAP. XXVIII.

Of a Vulnerary Potion.

The uſe of Vulnerary Potions.

But if the contumacious rottenneſs of the bone, and alſo a rebellious ulcer ſhall not yield to the deſcribed remedies, it will be convenient to preſcribe a Vulnerary Potion to the Patient. For Nature helped by ſuch a Potion, hath to my knowledge ſundry times done wondrous things in amendment of corrupt bones, and conſolidation of ulcers. For theſe potions, though they do not purge the noxious humours away by ſtool, yet are they wondrous effectual to cleanſe ulcers, and free them from the exceſs of excrementitious humours, to cleanſe the bloud, and purge it from all impurity, to agglutinate broken bones, and knit the ſinews. I have here thought good to ſpeak of them, and chiefly, for that they were much commended by the Ancients, but neglected by the modern Phyſicians and Surgeons. But if the cure of Wounds and old Ulcers be performed by deterſion, and the repoſition of the loſt ſubſtance, what Medicin can ſooner or rather do it than that, which by its admirable and almoſt divine force, ſo purgeth the bloud, that thereof, as from a fit and laudable matter, the fleſh or any other loſt ſubſtance may be fitly reſtored, and the part recover its former union? But if fiſtulous Ulcers, Cancers, Gouts, and the like diſeaſes be offended by the uſe of ſalt, ſpiced, acrid meats, and others which are of ſubtil parts, as Muſtard, Onions, and Garlick, or any other exceſs in meat or drink; why may they not become mild and gentle by medicated and contrary meats and drinks, or at leaſt be reduced to a more equal temper? Therefore that Surgeons may know of what things ſuch compoſitions may ariſe, I have here thought good to reckon them up, that you may learn what they are.

Scabious.	*Centaury.*	*Gentian.*
Sanicle.	*Adders-tongue.*	*Herniaria.*
Bugle.	*Betony.*	*Red Colewort, or Cabbage.*
Mouſ-ear.	*Carduus benedictus.*	*Scordium.*
Burnet.	*The Cordial Flowers.*	*Cats-mint.*
Madder.	*Ariſtolochia, or Birth-worts.*	*Cinque-foil.*
Tanſie.	*Speed-well.*	*River-Crabs.*
Tops of Hemp.	*Agrimony.*	*Mace.*
Tops of Brambles.	*The Capillaries.*	*Bole-armenick.*
Sow-bread.	*Herb-Robert.*	*Petum, or Tobacco.*
Comfrey the greater and leſſer.	*Doves-foot.*	*Mead-ſweet.*
Vervain.	*Dogs-tongue Avens.*	*Colts-foot.*
Biſtort.	*Prunella.*	*Dandelion.*
Mug-wort.	*Oſmund.*	*Plantain.*
Periwincle.	*Clary.*	*St. Johns-wort.*

Of all theſe the Surgeon ſhall make choice according to the mind and judgment of the Phyſician, ſuch as he ſhall think fit and proper to every Ulcer or Wound, or to each wounded and ulcerated part, according to the condition of the time, the temper of the Patient, and kind or nature of the diſeaſe. You may make drinks not onely of the decoctions of theſe, but alſo of their juices in white Wine, or *ænomel*, which are good not onely to purifie the maſs of the bloud, to cleanſe ſanious, virulent, filthy, and dyſenterious ulcers, but alſo to drive away putrefaction, ſcale-bones, diſſolve clotted bloud in bruiſes, to draw, pluck out and exterminate all ſtrange bodies, as I have often obſerved to my great admiration. They are compoſed uſually after this manner. ℞ *Savie. bugul. ſcabioſ. beton. ſcord. nepet. an.* m. ſ. *uvar. mund. ſem. hyper. & card. ben. an.* ℥ j. *trium flor. cord. an.* p. ij. *coquantur complete in aqu. communi; poſtea in fine adde vini alb. mel. roſ. & cinnam. quod ſufficit, fiat decoctio, coletur per manicam.* Let him drink ℥ iij. in the morning three hours before dinner. You may alſo with good ſucceſs make injections with the ſame liquor into fiſtulous and ſinuous ulcers, as alſo to waſh the ſordid ulcers therewith. You may alſo boil the ſame Simples, as herbs, flowers, and ſeeds, in the Patients broths, that ſo they may acquire a medicinable and nouriſhing faculty. For the time of the affect, wherein you may with good ſucceſs make uſe of theſe, we have read in *Guido*, that he uſed not to preſcribe theſe potions to his Patients when as they were newly wounded, for that they commonly are compoſed of things hot and opening, which heat and attenuate the bloud, whence there would be danger of a defluxion upon the affected part. Wherefore when the matter is come to ſuppuration, when as there is nothing remains, but to cleanſe the ulcer, and fill it with fleſh, no inflammation as now remaining in the part, I judge theſe potions may then be uſed with good ſucceſs.

The form of a Vulnerary Potion.

In what time of the diſeaſe they are chiefly to be uſed.

CHAP. XXIX.

Of Tetters, Ring-worms, or Chops occaſioned by the Lues Venerea.

Upon the cure of the *Lues Venerea*, uſually Tetters and Chops happen thereupon, which makes furrows in the palms of the hands and ſoals of the feet. They acquire their matter from ſalt phlegm, or aduſt choler, or the reliques of the venereous virulency ſent thither. The cure, eſpecially when as the diſeaſe is grown old, is difficult; by reaſon that the humour hath long accuſtomed to flow that way, and for that it hath corrupted the habit of the part by the continual

nual defluxion; but the cure is more eaſie, if the diſeaſe be newly bred. Now you may know it is newly bred by the redneſs, accompanied by a great itching, and not onely a drineſs of the skin, but alſo a thickneſs and denſneſs thereof. That which is old, beſides theſe fore-recited ſigns, hath ſcaly and bran-like hardneſſes conjoined therewith, which by ſcratching and rubbing caſteth off ſcales. For general Medicins, the diſtemper of the Liver, and habit of the Body muſt be corrected, which by the occaſion of the former diſeaſe and remedies, apt to inflame the bloud, cannot but much ſwerve from their native temper. This may be done by diet conveniently appointed, by purging and altering Medicins, bleeding, Bathing, applying of Cupping-glaſſes and horns. For topick, or particular Medicins, waſh ſuch as are newly or lately bred with the following water which dries, and is of ſubtil parts. ℞ *Aq. roſ. & pariet. an.* ʒ j. *aq. alum.* ʒ ij. *calc.* ʒ ij. *alum.* ʒ iij. *pul. ſubl.* ℈ iv. *fiat lenis, & minim. ebul. in baln. mar.* This water ſhall be made more or leſs forcible, according to the condition of the diſeaſe. Or, ℞ *Ol. tart.* ʒ ij. *ſep. com.* ʒ iv. *miſc. fiat unguent. ad uſum.* If the Phyſician ſhall thing good, let the Patient uſe a decoction of *Guaiacum*, but that very weak. But old Tetters and Chops muſt be ſoftned with emollient, attenuating, and inciding decoctions, as alſo with Liniments, Ointments, and Plaſters having the ſame effect. Then let the reſidue of the cure be performed by Fumigations, ſuch as this which follows: ℞ *Pul. cinab.* ʒ ij. *lad. aſſ. odor. ſtyrac. cal. an.* ʒ ß. *olib. maſtic. an.* ʒ iij. *olei tart. & theriac. q. ſ. fiant trochiſci*; uſe at each time ſome ʒ ſ. of them, and let onely the affected parts receive the ſmoak. Some commend the rubbing of the hands with the following Medicin. Take the aſhes of Wine-lees, make thereof a lee, and ſtrain it through an hypocras-bag, then put thereto ſome rennet; let them be well mixed together in a mortar, and herewith let the hands be rubbed or waſhed. Or, ℞ *unguent. enul.* ʒ iij. *fugit.* ʒ ij. Or elſe, ℞ *Reſ. pini.* ʒ j. *ceruſ. an.* ʒ ſ. *argent. viv.* ʒ iij. *ſucci citri & lapath. acut. an.* ʒ . Let them be incorporated, and make a Liniment to be uſed to the part. If to this you add *ſublimate* ſo waſhed and prepared, as women uſe for their Faces, you ſhall make it more effectual. Others take burnt alum made into Powder, and incorporated with the yolk of an Egg, the juice of Citrons, and a little Aloes diſſolved in *Oxymel ſciliticum.*

Signs of the new-bred diſeaſe.

The cure of newly come Tetters.

A Water drying virulent Tetters.

The cure of old Tetters.

A Fumigation.

A Liniment.

CHAP. XXX.

Of curing the Lues Venerea *in Infants, and little children.*

INfants oft-times conceive the ſeeds of this diſeaſe in the wombs of their mothers, and are born infected therewithall, puſtles preſently ariſing over all the bodies, infecting with the like diſeaſe as many Nurſes as give them ſuck; they ſcarce ever recover thereof, for that they contracted the diſeaſe from their firſt conformation. But ſuch as are ſomewhat bigger, if they chance to catch the diſeaſe after they are born, by ſucking ſome infected Nurſe, or by any other occaſion or kind of contagion, oftentimes receive cure. For firſt, you ſhall cauſe the Nurſe to uſe the *Aqua theriacalis* here-under deſcribed, for the ſpace of twenty or more days, that ſo ſhe may the better arm her ſelf againſt the contagion of this diſeaſe, and yield Milk which may have the faculty of meat and medicin; ſhe ſhall be careful, as often as ſhe gives the child ſuck, to waſh and dry her teat or pap, leſt the virulency that the child breaths out at his mouth, be impact in the little holes of the teat through which the milk flows out. Now the puſtles of little children ſhall be anointed with ſome ointment that receives *Argentum vivum* in ſome ſmall quantity, as *Ungiuentum enulatum cum mercurio*, or the like. Then ſhall it be ſwathed or bound up in ſwaths and cloths aired with the formerly deſcribed Fumigations. For the reſt, it ſhall be kept as warm as you can in ſome warm place. Theſe and the like muſt be done, not in one continued courſe, but at ſeveral ſeaſons, otherwiſe it is to be feared that it would cauſe ulcers to ariſe in the mouth, or elſe ſalivation. If any Ulcers ariſe in the mouth, and ſpread therein, they ſhall be touched with the formerly deſcribed waters, but made ſomewhat weaker, having regard to the tender age of the Patient; if the Infant ſhall get this diſeaſe of its Nurſe, let the Nurſe be preſently changed, for it being otherwiſe nouriſhed with tainted and virulent bloud, can never be healed. Many have by theſe means recovered; but ſuch as have periſhed, have not periſhed by the default of Medicins, but by the malignity and vehemency of the diſeaſe.

The Cure.

A deſcription of the Aqua Theriacalis, *or Treacle-water formerly mentioned.*

℞ *Raſor. interior. ligni ſancti gummoſi*, ℔ ij. *polypod. querni*, ʒ iv. *vini albi dulcedinis expertis* ℔ ij. *aqua fontan. puriſſ.* ℔ viij. *aquar. cichor. & fumar. an.* ʒ iv. *ſem. junip. heder. & baccar. lauri an.* ʒ ij. *caryophil. & macis, an.* ʒ . *cort. citri ſaccaro condit. conſ. roſ. anthos. cichor. bugloſ. borag. an.* ʒ ſ. *conſ. ænulæ camp. theriac. vet. & mithrid. an.* ʒ ij. diſtil them all in *Balneo Mariæ*, after the following manner. Let the *Guaiacum* be infuſed in equal parts of Wine, and the fore-mentioned waters for the ſpace of twelve hours, and the reſidue of the things in that which remains, of the ſame Wine and Waters for ſix hours ſpace, beating ſuch things as may require it, then let them be mixed together. that ſo the liquor may be endued with all their faculties. Which, that it may be the more effectually performed, let them be boiled, put up in glaſs bottles cloſely ſtopped for ſome three or four hours ſpace, in a large Kettle filled with boiling water; then let them be put into a Glaſs Alembick, and ſo diſtilled. Give ʒ iv. of this diſtilled liquor at once, being aromatized with ʒ j. of Cinamon, and ʒ j. of *Diamargariton*, and ʒ ß of Sugar, to give it a pleaſing taſte. Such a drink doth not onely retund the virulency of the *Lues Venerea*, but ſtrengthens the noble parts. *Rondeletius* makes an *Aqua Theriacalis* after this manner: ℞ *Theriac. vet.* ℔ j. *acetoſ.* m. iij. *rad. gram.* ℥ iij. *puleg. card. ben. an.* m. ij. *flor. chamæm.* p. ij. *temperentur omnia in vino albo, & diſtillantur in vaſe vitreo:* reſerve the water for uſe; where-

A Treacle-water.

The manner making it.

Rondeletius his Treacle-water.

whereof let the Patient take ʒ ij. with ʒ iij. of Sorrel and Bugloſs water: he wiſheth this to be done when he ſhall enter into bed or a ſtove, for ſo this diſtilled liquor will cauſe ſweat more eaſily, and mitigate pain, whether given by it ſelf, or with a decoction of grommel, or of *China*, or Burdock-roots; yet if the Patient be of a phlegmatick conſtitution, he ſhall uſe a decoction of *Guaiacum* in ſtead of a decoction of *China*, for it penetrates more ſpeedily, by reaſon of its ſubtilty of parts, and alſo expels the dolorifick matter.

The End of the Nineteenth Book.

BOOK XX.

Of the SMALL POX and MEAZLES:

As alſo of WORMS, *and the* LEPROSIE.

CHAP. I.

Of the cauſes of the Small Pox and Meazles.

FOr that the Small Pox and Meazles are diſeaſes which uſually are fore-runners and fore-tellers of the Plague, not onely by the corruption of humours, but oft-times by default of the air. Moreover, for that Worms are oft-times generated in the Plague, I have thought good to write of theſe things, to the end, that by this Treatiſe the young Surgeon may be more amply and perfectly inſtructed in that peſtilent diſeaſe. Alſo I have thought good to treat of the Leproſie, as being the off-ſpring of the higheſt corruption of humours in the body. Now the ſmall Pox are puſtiles, and the Meazles ſpots which ariſe in the top of the skin by reaſon of the impurity of the corrupt bloud ſent thither by the force of Nature. Moſt of the Ancients have delivered that this impurity is the reliques of the menſtruous bloud remaining in the body of the Infant, being of that matter from whence it drew nouriſhment in the womb, which lying ſtill or quiet for ſome ſpace of time, but ſtirred up at the firſt opportunity of a hotter Summer, or a ſoutherly or rainy ſeaſon, or a hidden malignity in the air, and boiling up, or working with the whole maſs of the bloud, ſpread or ſhew themſelves upon the whole ſurface of the body. An argument hereof is, there are few or none who have not been troubled with this diſeaſe, at leaſt once in their lives, which when it begins to ſhew it ſelf, not content to ſet upon ſome one, it commonly ſeizeth upon more: now commonly there is as much difference between the ſmall Pox and Meazles, as there is between a Carbuncle and a peſtilent Bubo: for the Small Pox ariſes of a more groſs and viſcous matter; to wit of a Phlegmatick humour: but the Meazles of a more ſubtil and hot; that is, a cholerick matter, therefore this yields no marks, but certain ſmall ſpots without any tumour, and theſe either red, purple, or black. But the Small Pox are extuberating puſtles, white in the midſt, but red in the circumference, an argument of bloud mixed with choler, yet they are ſcarce known at the beginning, that is, on the firſt or ſecond day they appear; but on the third and fourth day they bunch out and riſe up into a tumour, becoming white before they turn into a ſcab; but the Meazles remain ſtill the ſame. Furthermore, the ſmall Pox prick like needles by reaſon of a certain acrimony, and cauſe an itching; the Meazles do neither, either becauſe the matter is not ſo acrid and biting, or elſe for that it is more ſubtil, it eaſily exhales, neither is it kept ſhut up under the skin. The Patients often ſneeze when as theſe matters ſeek paſſage out, by reaſon of the putrid vapours aſcending from the lower parts upwards to the brain. They are held with a continual Fever, with pains in their backs, itching of their noſe, head-ach, and a vertiginous heavineſs, and with a kind of ſwounding or fainting, a nauſeous diſpoſition, and vomiting, a hoarſneſs, difficult and frequent breathing, an inclination to ſleep, a heavineſs of all the members, their eyes are fiery and ſwollen, their urin red and troubled. For Prognotticks we may truly ſay thus much, That the matter whence this affect takes its original, partakes of ſo malign, peſtilent and contagious a quality, that not content to mangle and ſpoil the fleſhy part, it alſo eats and corrupts the bones like the *Lues Venerea*, as I obſerved not onely in *Anno Dom.* 1568. but alſo in divers other years, whereof I think it not amiſs to ſet down this notable example.

What the Small Pox and Meazles are. Their matter.

Why the Meazles do not itch.

An Hiſtory.

The daughter of *Claude Pique* a Book-ſeller, dwelling in St. *James* his ſtreet in *Paris*, being ſome four or five years old, having been ſick of the Small Pox for the ſpace of a Moneth, and Nature could not overcome the malignity of the diſeaſe, there roſe abſceſſes upon the *ſternon*, and the joints of the ſhoulders, whoſe eating and virulent matter, corroded the bones of the *ſternon*, and divided them in ſunder; alſo it conſumed a great part of the top of the ſhoulder-bone, and the head of the blade-bone: of this thing I had witneſſes with me, *Marcus Myron* Phyſician of *Paris*, and at this preſent the Kings chief Phyſician, *John Doreau* Surgeon to the *Conte de Bryane*, the body being diſſected in their preſence. Alſo you may obſerve in many killed by the malignity of this diſeaſe and diſſected, that it cauſeth ſuch impreſſion of corruption in the principal parts, as brings the Dropſie, Ptiſick, Hoarſneſs, Aſthma, Bloudy-flux ulcerating the Guts, and at length bringeth death, as the puſtles have raged or reigned over theſe or thoſe entrails, as you ſee them do over the ſurface of the body; for they do not onely moleſt the external parts, by leaving the impreſſions and ſcars of the puſtles and ulcers, rooting

What grievous and pernicious ſymtoms may happen by the Small Pox.

rooting themſelves deep in the fleſh, but alſo oft-times then take away the faculty of motion, eating aſunder, and weakning the joints of the Elbow, Wriſt, Knee, and Ankle. Moreover ſundry have been deprived of their ſight by them, as the Lord *Guymenay*, others have loſt their hearing, and otherſome the ſmelling, a fleſhy excreſcence growing in the paſſages of the noſe and ears. But if any relique of the diſeaſe remain, and that the whole matter thereof be expelled by the ſtrength of Nature, then ſymptoms afterwards ariſe, which ſavour of the malignity of the humour, yea and equal the harm of the ſymptoms of the *Lues Venerea*.

CHAP. II.

Of the Cure of the Small Pox and Meazles.

The Cure.

THe Cure of this Diſeaſe uſeth to be diverſe, according to the condition of the humour free from, or partaker of the venenate quality: For if it partake of malignity, and the child be a ſucking child, ſuch things ſhall be given to the Nurſe as may infringe and overcome the ſtrength of the malignity, as we ſhall ſhew more at large when we come to treat of the Cure of children which are ſick of the Plague; howſoever it be, the child muſt be kept in a warm room free from wind, and muſt be wrapped and covered with ſcarlet cloths, until the Pox come forth. There ſhall be provided for the Nurſe medicated Broths, with Purſlain, Lettuce, Sorrel Succory, Borage, and French-Barley bound up in a cloth. She ſhall ſhun all ſalt, ſpiced and baked Meats, and in ſtead of Wine, drink a decoction of Licorice, Raiſins, and Sorrel-roots. She ſhall alſo take purging Medicins, as if ſhe were ſick of the ſame diſeaſe, that ſo her milk may become medicinable. Laſtly, She ſhall obſerve the ſame diet as is uſually preſcribed to ſuch as have the Plague. You ſhall give the child no Pap, or if you give it any, let it be very little. But if the child be weaned, let him abſtain from fleſh until the Fever have left him, and the Pox be fully come forth: in ſtead of fleſh let him feed on Barley and Almond Creams, Chicken Broths, wherein the fore-named Herbs have been boiled, Panadoes, Gellies, Cullaſſes, Prunes, and Raiſins. Let his drink be a Ptiſan made of French-Barley, Graſs and Sorrel-roots or with a Nodula containing the four Cold Seeds, the pulp of Prunes and Raiſins, with the ſhavings of Ivory and Harts-horn; between meals the ſame decoction may be mixed with ſome Syrup of Violets, but not of Roſes or any other aſtringent Syrup, leſt we hinder the courſe and inclination of the humour outwards. Let his ſleep be moderate, for too ſound ſleep draws back the matter to the center, and increaſeth the Fever; you muſt neither purge, nor draw bloud, the diſeaſe increaſing or being at the height, unleſs peradventure there be a great plenitude, or elſe the diſeaſe complicate with other, as with a Pleuriſie, inflammation of the eyes, or a ſquinancy which require it, leſt the motion of Nature ſhould be diſturbed; but you ſhall think it ſufficient to looſe the belly with a gentle Clyſter: but when the height of the diſeaſe is over, and in the declenſion thereof, you may with *Caſſia* or ſome ſtronger Medicin evacuate part of the humours, and the reliques of the diſeaſe. But in the ſtate and increaſe, it is better to uſe Sudoriſicks, which by attenuating the humours and relaxing the pores of the skin may drive the cauſe of the diſeaſe from the center to the circumference, which otherwiſe reſiding in the body might be a cauſe of death; as I and *Richard Hubert* obſerved in two Maids, whereof one was four, and the other ſeventeen years old; for we diſſecting them both being dead, found their entrails covered with ſcabby or cruſted puſtles, like thoſe that break forth upon the skin. We muſt not think that a bleeding at noſe at the beginning of the diſeaſe, or in the firſt four or five days, ſhould carry away the matter and original of the diſeaſe, for nevertheleſs the Pox will come forth; but for that this is a true and natural *Criſis* of this diſeaſe, as that which is carried to the ſurface and circumference of the body, ſuch bleeding muſt not be ſtopped, unleſs you fear it will cauſe ſwounding. The matter ſhall be drawn forth with a decoction of Figs, husked Lentils, Citron-ſeeds, the Seeds of Fennel, Parſly, Smallage, roots of Graſs, Raiſins, and Dates. For ſuch a decoction, certainly if it have power to cauſe Sweat, hath alſo a faculty to ſend forth unto the skin the morbifick humour; the Seeds of Fennel, and the like opening things relax and open the pores of the skin; Figs leniſie the acrimony of the matter, and gently cleanſe, the Lentils keep the jaws and throat, and all the inward parts from puſtles, and hinder a flux by reaſon of their moderate aſtriction, but having their husks on, they would bind more then is required in the diſeaſe; Dates are thought to comfort the ſtomach, and Citron Seeds to defend the heart from malignity; Licorice to ſmooth the throat, and hinder hoarſneſs and cauſe Sweat. But theſe things ſhall be given long after meat, for it is not fit to ſweat patiently after meat; ſome there be who would have the child wrapped in linnen cloths ſteeped in this decoction being hot, and afterwards hard wrung forth. Yet I had rather to uſe bladders or ſponges, or hot bricks for the ſame purpoſe; certainly a decoction of Millet, Figs and Raiſins, with ſome Sugar, cauſeth Sweat powerfully. Neither is it amiſs whileſt the Patient is covered in all other parts of the body, and ſweats, to fan his face, for thus the native heat is kept in, and ſo ſtrengthened, and fainting hindered, and a greater excretion of excrementitious humours cauſed. To which purpoſe you may alſo put now and then to the Patients noſe a *Nodulus* made with a little Vinegar and Water of Roſes, Camphire, the Powder of Sanders, and other odoriferous things which have a cooling faculty; this alſo will keep the noſe from puſtles.

The Child muſt have no Pap.

How ſound ſleep doth harm in this diſeaſe.

Of purging, bleeding, and ſudoriſicks.

An Hiſtory.

A ſudorifick decoction.

When it is beſt to procure Sweat.

CHAP.

CHAP. III.

What parts muſt be armed againſt, and preſerved from the Pox.

How to defend the Eyes.

THe eyes, noſe, throat, lungs, and inward parts ought to be kept freer from the eruption of puſtles than the other parts, for that their nature and conſiſtence is more obnoxious to the malignity of this virulency, and they are eaſilier corrupted and blemiſhed. Therefore leſt the eyes ſhould be hurt, you muſt defend them when you firſt begin to ſuſpect the diſeaſe, with the eye-lids, alſo moiſtning them with Roſe-water, Verjuice or Vinegar, and a little Camphire. There are ſome alſo who for this purpoſe make a decoction of Sumach, Berbery-ſeeds, Pomgranat-pills. Aloes, and a little Saffron, the juice of ſower Pomgranats, and the water of the Whites of Eggs dropped in with Roſe-water are good for the ſame purpoſe, alſo Womens milk mixed with Roſe-water and often renewed, and laſtly all ſuch things as have a repercuſſive quality. Yet if the eyes be much ſwollen and red, you ſhall not uſe repercuſſives alone, but mix therewith diſcuſſers and cleanſers, ſuch as are fit by a familiarity of Nature to ſtrengthen the ſight; and let theſe be tempered with ſome Fennel or Eye-bright water. Then the Patient ſhall not look upon the light, or red things, for fear of pain and inflammation; wherefore in the ſtate of the diſeaſe, when the pain and inflammation of the eyes are at their height, gently drying and diſcuſſive things properly conducing to the eyes, are moſt convenient, as waſhed Aloes, Tutty, and Antimony, in the Water of Fennel, Eye-bright, and Roſes.

When the Eyes muſt not be defended by repercuſſives onely.

How to defend the Noſe.

The formerly mentioned *Nodulus* will preſerve the noſe, and linnen cloths dipped in the fore-ſaid aſtringent decoction, put in the noſtrils, and outwardly applied.

How the Mouth.

We ſhall defend the jaws, throat, and throtle, and preſerve the integrity of the voice by a gargle of oxycrate, or the juice of ſower Pomgranats, holding alſo the grains of them in their mouths, and often rouling them up and down therein,

How the Lungs.

as alſo by Nodulaes of the ſeeds of *Pſilum*, Quinces, and the like cold and aſtringent things. We muſt provide for the lungs and reſpiration by ſyrups of Jujubes, Violets, Roſes, white Poppies, Pomgranats, Water-Lillies, and the like. Now when as the Pox are throughly come forth, then may you permit the Patient to uſe ſomewhat a freer diet, and you muſt wholly buſie your ſelf in ripening and evacuating the matter, drying and ſcaling them. But for the Meazles, they are cured by reſolution onely, and not by ſuppuration; the Pox may be ripened by anointing them with freſh butter, by fomenting them with a decoction of the Roots of Mallows, Lillies, Figs, Line-ſeeds, and the like.

How to prevent Pock-arrs

After they are ripe, they ſhall have their heads clipped off with a pair of Sciſſers, or elſe be opened with a golden or ſilver needle, leſt the matter contained in them ſhould corrode the fleſh that lies thereunder, and after the cure, leave the prints or pock-holes behind it, which would cauſe ſome deformity; the *pus* or matter being evacuated, they ſhall be dried up with *unguent. roſat.* adding thereto Ceruſs, Litharge, Aloes, and a little Saffron in Powder; for theſe have not onely a faculty to dry, but alſo to regenerate fleſh; for the ſame purpoſe the flower of Barley and Lupines are diſſolved and mixed with Roſe-water, and the affected parts anointed therewith with a fine linnen rag; ſome anoint them with the ſward of Bacon boiled in Water and Wine, then preſently ſtrew upon them the flower of Barly or Lupines, or both of them. Others mix crude Hony newly taken from the Comb, with Barly-flower, and therewithal anoint the puſtles ſo to dry them; being dried up like a ſcurf or ſcab, they anoint them with Oil of Roſes, Violets, Almonds, or elſe with ſome Cream, that they may the ſooner fall away, the puſtles being broken; tedious itching ſolicits the Patient to

Remedies for excoriation.

ſcratch, whence happens excoriation and filthy ulcers, for ſcratching is the occaſion of greater attraction. Wherefore you ſhall bind the ſick childs hands, and foment the itching parts with a decoction of Marſh-mallows, Barly and Lupines, with the addition of ſome ſalt. But if it be already excoriated, then ſhall you heal it with *unguentum album camphorat.* adding thereto a little Powder of Aloes or *Cinnabaris*, or a little *deſiccativum rubrum.* But if notwithſtanding all your application of repelling medicins, puſtles nevertheleſs break forth at the Eyes, then muſt they be diligently cured with all manner of *Collyria*, having a care that the inflammation of that part grow not to that bigneſs as to break the Eyes, and that which ſometimes happens to drive them forth of their proper orbs. If any cruſty ulcers ariſe in the noſtrils, they may be dried and cauſed to fall away by putting up of Ointments. Such as ariſe in the Mouth, Palate, and throat, with hoarſneſs and difficulty of ſwallowing, may be helped by Gargariſms made with Barly-water, the Waters of Plantain and Chervil, with ſome ſyrup of Roſes, or *Diamoron* diſſolved therein; the Patient ſhall hold in his mouth Su-

For the ulcers of the mouth and jaws.

gar of Roſes, or the Tablets of *Elect. diatragacanth. frigid.* The Pock-arrs left in the Face, if they bunch out undecently, ſhall be clipped away with a pair of Sciſſers, and then anointed with freſh *Unguent. citrin.* or elſe with this liniment. ℞ *Amyli triticei & amygdalar. excorticatarum an.* ʒ j ß. *gum. tragacanth.* ʒ ½. *ſeminis melonum, fabarum ſiccarum excorticat. farinæ hordei, an.* ʒ iv. Let them

To help the unſightly ſcars of the Face.

all be made into fine Powder, and then incorporated with Roſe-water, and ſo make a Liniment, wherewith anoint the face with a feather; let it be wiped away in the morning, waſhing the face with ſome water and wheat-bran; hereto alſo conduceth *lac virginale*; Gooſe, Ducks, and Capons greaſe are good to ſmooth the roughneſs of the skin, as alſo of Oil of Lillies; Hares bloud of one newly killed and hot, is good to fill and plain, as alſo whiten the Pock-holes, if they be often rubbed therewith. In ſtead hereof many uſe the ſward of Bacon rubbed warm thereon; alſo the diſtilled Waters of Bean-flowers, Lilly-roots, Red-roots, Egg-ſhells, and Oil of Eggs are thought very prevalent to waſte and ſmooth the Pock-arrs.

A Diſcourſe of certain monſtrous Creatures which breed againſt Nature in the bodies of Men, Women, and little Children, which may ſerve as an Induction to the enſuing Diſcourſe of WORMS.

AS in the *Macrocoſmos* or bigger World, ſo in the *Microcoſmos* or leſſer World there are Winds, Thunders, Earthquakes, Showrs, Inundations of Waters, Sterilities, Fertilities, Stones, Mountains, and ſundry ſorts of Fruits and Creatures thence ariſe. For who can deny but that there is Wind contained and ſhut up in flatulent abſceſſes, and in the guts of thoſe that are troubled with the Colick? Flatulencies make ſo great a noiſe in divers womens bellies, if ſo be you ſtand near them, that you would think you heard a great number of Frogs croaking in the night time. That Water is contained in watery abſceſſes, and the belly of ſuch as have the dropſie, is manifeſted by that cure which is performed by the letting forth of the water. In fits of Agues the whole body is no otherwiſe ſhaken and trembles, than the Earth when it is heard to bellow, and felt to ſhake under our feet. He which ſhall ſee the Stones which are taken out of the bladder, and come from the kidnies and divers other parts of the body, cannot deny but that Stones are generated in our bodies. Furthermore we ſee both Men and Women, who in their Face or ſome other parts ſhew the impreſſion or imprinted figure of a Cherry, Plumb, Service, Fig, Mulberry, and the like Fruit; the cauſe hereof is thought to be the power of the Imagination concurring with the formative faculty, and the tenderneſs of the yielding and wax-like *Embryon*, eaſie to be brought into any form or figure, by reaſon of the proper and native humidity. For you ſhall find that all their Mothers whileſt they went with them have earneſtly deſired or longed for ſuch things, which, whileſt they have too earneſtly agitated in their minds, they have transferred the ſhape unto the child, whileſt that they could not enjoy the things themſelves. Now who can deny but that the Bunches of the Back and large Wens reſemble Mountains? Who can gain-ſay, but that the ſqualid Sterility may be aſſimilate to the hectick drineſs of waſted and conſumed perſons? and Fertility deciphered by the body diſtended with much fleſh and fat, ſo that the legs can ſcarce ſtand under the burden of the belly? But that divers Creatures are generated in one Creature, that is in Man, and that in ſundry parts of him, the following Hiſtories ſhall make it evident.

A compariſon between the bigger and leſſer World.

The anergation of wind in mans body.

Of Water.

Of Stones.

Of fruits from the firſt conformation.

Hollerius tells that a certain *Italian* by frequent ſmelling to the Herb Baſil, had a Scorpion bred in his Brain, which cauſed long and vehement pain, and at length death; therefore I have here expreſt the figure of that Scorpion, found when as his Brain was opened. *Lib. de morb. inter. cap. 1.*

The Figure of a Scorpion.

It makes *Hollerius* conjecture of the cauſe and original of this Scorpion probable, for that *Chryſippus*, *Diophanes*, and *Pliny* write, that of Baſil beaten between two ſtones, and laid in the Sun, there will come Scorpions.

Fernelius writes that in a certain Souldier who was flat noſed, upon the too long reſtraint or ſtoppage of a certain filthy matter that flowed out of the noſe, that there were generated two hairy worms of the bigneſs of ones finger, which at length made him mad; he had no manifeſt Fever, and he died about the twentieth day. This was their ſhape, by as much as we can gather by *Fernelius* his words. *Lib. 5. de part. morbic. cap. 7.*

The Effigies of Worms mentioned by Fernelius.

The ſhape of a Millepes caſt forth by Urin.

Lues Duret, a man of great learning and credit, told me that he had come forth with his Urin, after a long and difficult diſeaſe, a quick Creature, of colour red, but otherwiſe in ſhape like a Millepes, that is, a Cheſlop, or Hog-louſe. An Hiſtory.

Count *Charles* of *Mansfieldt* laſt Summer troubled with a grievous and continual Fever, in the Duke of *Guiſes* place caſt forth a filthy matter at his Yard, in the ſhape of a live thing almoſt juſt in this form. An Hiſtory.

The

The ſhape of a thing caſt forth by Urin.

Nicolaus Flor. God. lib. 7 c. 18.

Monſtrous Creatures alſo of ſundry forms are alſo generated in the wombs of women; ſomewhiles alone, otherwhiles with a *Mola*, and ſometimes with a Child naturally and well made; as Frogs, Toads, Serpents, Lizzards: which therefore the Ancients have termed the Lombards brethren, for that it was uſual with their Women, that together with their natural and perfect iſſue, they brought into the World Worms, Serpents, and monſtrous Creatures of that kind generated in their wombs, for that they always more reſpected the decking of their bodies than they did their diet. For it happened whileſt they fed on Fruits, Weeds and Traſh, and ſuch things as were of ill juice, they generated a putrid matter, or certainly very ſubject to putrefaction and corruption, and conſequently opportune to generate ſuch unperfect creatures. *Jouhartas* telleth that there were two *Italian* women that in one moneth brought forth each of them a monſtrous birth; the one that married a Tailor, brought forth a thing ſo little, that it reſembled a Rat without a tail; but the other a Gentlewoman, brought forth a larger, for it was of the bigneſs of a Cat; both of them were black, and as ſoon as they came out of the Womb, they ran up high on the wall, and held faſt thereon with their nails. *Lycoſthenes* writes that in *Anno Dom.* 1494. a woman in *Cracovia*, in the ſtreet which taketh name from the Holy Ghoſt, was delivered of a dead child who had a Serpent faſtned upon his back, which fed upon this dead child, as you may perceive by this following Figure.

Lib. error. popul.

The Figure of a Serpent faſtned to a Child.

Lib. de occult. nat. mir. cap. 8.

Levinus Lemnius tells a very ſtrange Hiſtory to this purpoſe. Some few years agone (ſaith he) a certain woman of the Iſle in *Flanders*, which being with child by a Sailor, her belly ſwelled up ſo ſpeedily, that it ſeemed ſhe would not be able to carry her burden to the term preſcribed by Nature; her nineth moneth being ended, ſhe calls a Midwife, and preſently after ſtrong throws and pains, ſhe firſt brought forth a deformed lump of fleſh, having as it were two handles on the ſides, ſtretched forth to the length and manner of arms, and it moved and panted with a certain vital motion, after the manner of Sponges and Sea-nettles; but afterwards there came forth of her womb a monſter with a crooked noſe, a long and round neck, terrible eyes, a ſharp tail, and wonderful quick of the feet: it was ſhaped much after this manner.

The ſhape of a Monſter that came forth of a Womans Womb.

As ſoon as it came into the light, it filled the whole room with a noiſe and hiſſing, running to every ſide to find out a lurking hole wherein to hide its head, but the Women which were preſent, with a joint conſent fell upon it, and ſmothered it with cuſhions, at length the poor woman wearied with long travel, was delivered of a Boy, but ſo evilly entreated and handled by this Monſter, that it died as ſoon as it was chriſtened.

Corne-

Cornelius Gemma, a Phyſician of *Lovain*, telleth that there were many very monſtrous and ſtrange things caſt caſt forth, both upwards and downwards out of the belly of a certain Maid of *Lovain*, of the age of fifteen years. Amongſt the reſt, ſhe caſt forth at her fundament, together with her excrements, a living creature ſome foot and half long, thicker then ones thumb, very like an Eel, but that it had a very hairy tail. I have here given you the figure of the Monſter, as it was expreſſed by him. *Lib. de diviniſ. natur. Characte riſmis.*

The Figure of a Monſter that came forth of a Maids Belly.

Maſter *Peter Barque* and *Claude le Grand*, Surgeons of *Verdun*, lately affirmed to me, that they cured the wife of a certain Citizen of *Verdun*, which out of an Abſceſs broken in the belly, caſt forth a great number of Worms, together with the quitture; and theſe were of the thickneſs of ones finger, with ſharp heads, which ſo gnawed her guts, that the excrements for a long time came forth at the ulcer, but now ſhe is perfectly recovered. An Hiſtory.

Anthony Benenius a Phyſician of *Florence*, telleth that one *John Menuſierus*, a man of forty years of age, troubled with continual pains at his ſtomach, was often at the point of death, neither found he any help by the counſels of many Phyſicians which he uſed. At length coming to have his advice, he gave him a vomit, by means whereof he caſt up a great quantity of corrupt and putrid matter, yet was he not thereby eaſed of his pain: Therefore he gave him another vomit, by force whereof he caſt up much matter like to the former, and together therewith a Worm of four fingers long, having a red round head, of the bigneſs of a great Peaſe, covered over the body with a ſoft downineſs, with a forked tail in manner of a half Moon, going upon four feet, two before, and two behind. An Hiſtory.

The Figure of a Worm caſt forth by Vomit.

Why ſhould I mention the prodigious bodies which are found in Abſceſſes, as Stones, Chalk, Sand, Coals, Snail-ſhells, Straws, Hay, Horns, Hairs, and many kinds of living and dead creatures? For there is nothing in the generation of theſe things (cauſed by corruption, preceded by much alteration) which may make us admire, or hold us in ſuſpence, eſpecially if we ſhall conſider that Nature, the fruitful Parent of all things, hath put divers portions and particles of the univerſal matter whereof the greater World is compoſed into this *Microcoſmos*, or little World, Man; whereby he might the rather ſeem to be made to the reſemblance and form of the greater. Wherefore it ſo diſports it ſelf here, that it may counterfeit and reſemble all the actions and motions which it uſeth to perform in the Scene of the greater World in this little one, if ſo be that matter be not wanting. The efficient and material cauſes of ſuch things as are preternaturally generated in our bodies.

CHAP. IV.

Of the Worms which uſe to breed in the Guts.

A Groſs viſcid and crude humour is the material cauſe of Worms, which having got the beginning of corruption in the Stomach, is quickly carried into the Guts, and there it putrefies, having not acquired the form of laudable *Chylus* in the firſt concoction. This, for that it is viſcid, tenaciouſly adheres to the Guts, neither is it eaſily evacuated with the other excrements; therefore by delay it further putrefies, and by the efficacy of heat, it turns into the matter and nouriſhment for Worms. This alimentary humour being conſumed, unleſs ſome freſh ſupply the want thereof, which may eaſe their hunger, they move themſelves in the Guts with great violence, they cauſe grievous and great pains, yea, and oft-times they creep up to the Stomach, and ſo come forth by the Mouth, and ſometimes they aſcend into the holes of the Palat, and come forth at the Noſe. Worms are of three ſorts, for ſome are round and long, others broad and long, others ſhort and ſlender. The firſt are called by the Ancients *Teretes*, that is round, for that they are long and round. The ſecond are named *Teniæ*, for that their bodies are long and broad, like a Rowler or Swathe. The third are termed *Aſcarides*, for that they commonly wrap themſelves up round. Other differences of Worms are taken from their colours, as red, white, black, aſh-coloured, yellowiſh. Some alſo are hairy, with a great head like the little Fiſh which the *French* call *Chabot*, we a *Millers Thumb*; in ſome diſeaſes many worms are generated and caſt forth by the Fundament, as ſmall as hairs, and uſually of colour white, and theſe are they which are called *Aſcarides*. The diverſity of colours in Worms proceedeth not from the like diſtinct diverſity of humours whereof they are generated. For the melancholick and cholerick humour by their qualities are wholly unfit to generate Worms. But this manifold variety in colour, is by reaſon of the different corruption of the *chylus* or phlegmatick humour whereof they are bred. The long and broad Worms are often-times ſtretched alongſt all the Guts, being like to a mucous or albuminous ſubſtance; and How Worms are generated. The reaſon that they ſome times come forth at the mouth. The differences of Worms.

An Hiſtory. verily I ſaw one voided by a Woman which was like to a Serpent, and ſome ſix foot long, which ought not to ſeem ſtrange, ſeeing it is noted by the Ancients, that they have ſeen Worms ſo long

An Hiſtory. as the length of the whole Guts, that is ſeven times the length of ones body. *Wierus* writes, that he ſaw a Country-man who voided a Worm eight foot and one inch long, in head and mouth reſembling a Duck, which therefore I have thought good here to expreſs.

The Figure of a Worm, generated in, and caſt forth of the Gut.



In obſervat. *Valeriola* affirmeth, that he ſaw a Worm above nine foot long Now as Worms differ in ſhape, ſo are their places of generation alſo different. For the round and long Worms are commonly gene-

In what places of the belly worms are generated. rated in the ſmaller guts, the reſt in the greater, but eſpecially the *Aſcarides:* none breed in the Stomach, as that which is the place of the firſt concoction. There truly the matter which breedeth theſe Worms, gets the firſt rudiment of corruption, but comes to perfection onely in the guts; they breed in ſome Infants in their mothers bellies, by the pravity and corrupt nature of the humour flowing from the Mother for the nouriſhment of the Child, which for that then they do not expel it by ſiege, it by delay putrefieth the more, and yields fit matter for the breeding of Worms, as ſome

Ad finem lib. 4. de morbis. have obſerved out of *Hippocrates*. Laſtly, Worms breed in people of any age that are Belly-gods and given to gluttony, as alſo in ſuch as feed upon meats of ill juice, and apt to corrupt, as crude Summer-fruits, Cheeſe, and Milk-meats. But to know in what part of the guts the Worms do lurk, you muſt

Signs of Worms in the ſmall guts. note that when they are in the ſmall guts, the Patients complain of a pain in their Stomach, with a dog-like appetite, whereby they require many and ſeveral things without reaſon, a great part of the nouriſhment being conſumed by the Worms lying there; they are alſo ſubject to often fainting, by reaſon of the ſympathy which the ſtomach, being a part of moſt exquiſit ſenſe, hath with the heart, the noſe itches, the breath ſtinks, by reaſon of the exhalations ſent up from the meat corrupting in the ſtomach; through which occaſion they are alſo given to ſleep, but are now and then waked therefrom by ſudden ſtartings and fears; they are held with a continued and ſlow fever, a dry cough, a winking with their eye-lids, and often changing of the colour of their faces. But long and broad

Signs of worms in the great guts. Worms, being the innates of the greater guts, ſhew themſelves by ſtools repleniſhed with many ſloughs, here and there reſembling the ſeeds of a Muſk-melon or Cucumer. *Aſcarides* are known by the itching they cauſe in the Fundament, cauſing a ſenſe as if it were Ants running up and down; cauſing alſo

Signs of *Aſcarides.* a *tenaſmus*, and falling down of the Fundament. This is the cauſe of all theſe ſymptoms; their ſleep is turbulent and often clamorous, when as hot, acrid and ſubtil vapours, raiſed by the Worms from the like humour and their food, are ſent up to the head; but ſound ſleep by the contrary, as when a miſty vapour is ſent up from a groſs and cold matter. They dream they eat in their ſleep, for that while the Worms do more greedily conſume the chylous matter in the guts, they ſtir up the ſenſe of the like action in the phantaſie. They grate or gnaſh their teeth by reaſon of a certain convulſifick repletion, the muſcles of the temples and jaws being diſtended by plenty of vapours. A dry cough comes by the conſent of the vital parts ſerving for reſpiration, which the natural, to wit, the *Diaphragma*, or Midriff, ſmit upon by acrid vapours, and irritated as though there were ſome humour to be expelled by coughing. Theſe ſame acrid fumes aſſailing the orifice of the ventricle, cauſe either an hicketting, or elſe a fainting, according to the condition of their conſiſtence, groſs or thin; theſe carried up to the parts of the Face cauſe an itching of the Noſe, a darkneſs of the Sight, and a ſudden changing of the colour in the cheeks. Great Worms are worſe than little ones, red than white, living than dead, many than few, variegated than thoſe of one colour, as thoſe which are

Why worms of divers colours are more dangerous. ſigns of a greater corruption. Such as are caſt forth bloudy and ſprinkled with bloud, are deadly, for they ſhew that the ſubſtance of the guts is eaten aſunder; for oft-times they corrode and perforate the body of the gut wherein they are contained, and thence penetrate into divers parts of the belly; ſo that they have come forth ſometimes at the navel, having eaten themſelves a paſſage forth, as *Hollerius* affirmeth. When as children troubled with the Worms draw their breath with difficulty, and wax moiſt over all their bodies, it is a ſign that death is at hand. If at the beginning of ſharp Fevers, round worms come forth alive, it is ſign of a peſtilent Fever, the malignity of whoſe matter they could not endure, but were forced to come forth. But if they be caſt forth dead, they are ſigns of greater corruption in the humours, and of a more venenate malignity.

CHAP.

CHAP. V.

What Cure to be uſed for the Worms.

IN this diſeaſe there is but one Indication, that is, the excluſion or caſting out of the Worms either alive or dead forth of the body, as being ſuch that in their whole kind are againſt Nature; all things muſt be ſhunned which are apt to heap up putrefaction in the body by their corruption, ſuch as are crude Fruits, Cheeſe, Milk-meats, Fiſhes; and laſtly ſuch things as are of a difficult and hard digeſtion, but prone to corruption. Pap is fit for children, for that they require moiſt things; but theſe ought to anſwer in a certain ſimilitude to the conſiſtence and thickneſs of Milk, that ſo they may be the more eaſily concocted and aſſimilated, and ſuch onely is that pap which is made with Wheat-flower, not crude, but baked in an Oven, that the Pap made therewith may not be too viſcid nor thick, if it ſhould onely be boiled in a Pan as much as the Milk would require; or elſe the Milk would be too terreſtrial or too wateriſh, all the fatty portion thereof being reſolved, the cheeſie and whayiſh portion remaining, if it ſhould boil ſo much as were neceſſary for the full boiling of the crude meat; they which uſe meal otherwiſe in pap, yield matter for the generating of groſs and viſcid humours in the ſtomach, whence happens obſtruction in the firſt veins and ſubſtance of the liver; by obſtruction worms breed in the guts, and the ſtone in the kidnies and bladder. The Patient muſt be fed often, and with meats of good juice, leſt the worms through want of nouriſhment ſhould gnaw the ſubſtance of the guts. Now when as ſuch things breed of a putrid matter, the Patient ſhall be purged, and the putrefaction repreſt by Medicins mentioned in our Treatiſe of the Plague. For the quick killing and caſting of them forth, Syrup of Succory or of Limmons with Rubarb, a little Treacle or Mithridate, is a ſingular Medicin, if there be no Fever. You may alſo for the ſame purpoſe uſe this following Medicin. ℞ *Cornu cervi, pul. raſur. eboris, an.* ʒ j. ſ. *ſem. tanacet. & contra verm. an.* ʒ j. *fiat decoct. pro parva doſi, in colat. infunde rhei optimi,* ʒ j. *cinam.* ℈ j. *diſſolve ſyrupi de abſinth.* ℥ ß. make a potion, give it in the morning three hours before any broth. Oil of Olives drunk, kills Worms; as alſo Water of Knotgraſs drunk with Milk; and in like manner all bitter things. Yet I could firſt wiſh them to give a Clyſter made of Milk, Honey, and Sugar, without Oils and bitter things, leſt ſhunning thereof they leave the lower guts and come upwards; for this is natural to Worms to ſhun bitter things, and follow ſweet things. Whence you may learn, that to the bitter things which you give by the mouth, you muſt always mix ſweet things, that allured by the ſweetneſs, they may devour them more greedily, that ſo they may kill them. Therefore I would with Milk and Sugar mix the ſeeds of Centaury, Rue, Womwood, Aloes, and the like: Harts-horn is very effectual againſt Worms, wherefore you may infuſe the ſhavings thereof in the Water or Drink that the Patient drinks, as alſo to boil ſome thereof in his broths. So alſo Treacle drunk or taken in broth, killeth the Worms; Purſlain boiled in broths, and diſtilled and drunk, is alſo good againſt the Worms; as alſo Succory and Mints; alſo a decoction of the leſſer Houſleek and Sebettens given with Sugar before meat; it is no leſs effectual to put Worm-ſeeds in their Pap, and in roaſted Apples, and ſo to give them it. Alſo you may make ſuppoſitories after this manner, and put them up into the Fundament. ℞ *Coralli ſubalbi, raſuræ eboris, corn. cerv. uſti, ireos, an.* ℈ ij. *mellis albi* ℥ ij. ſ. *aquæ centinodiæ q.ſ. ad omnia concorporanda, fiant Glandes:* let one be put up every day, of the weight of ʒ ij. for children; theſe ſuppoſitories are chiefly to be uſed for *Aſcarides*, as thoſe which adhere to the right gut. To ſuch children as can take nothing by the mouth, you ſhall apply Cataplaſms to their navels made of the Powder of Cummin-ſeeds, the flower of Lupines, Wormwood, Southernwood, Tanſie, the leaves of Artichokes, Rue, the Powder of *Coloquintida*, Citron-ſeeds, Aloes, Arſeſmart, Horſe-mint, Peach-leaves, *Coſtus amarus*, *Zedoaria*, Sope, and Ox-gall. Such Cataplaſms are oft-times ſpread over all the belly, mixing therewith aſtringent things for the ſtrengthening of the part, as Oil of Myrtils, Quinces and Maſtich; you may alſo apply a great Onion hollowed in the the midſt, and filled with Aloes and Treacle, and ſo roaſted in the Embers, then beaten with bitter Almonds, and an Ox gall. Alſo you may make Emplaſters of bitter things, as this which follows: ℞ *Felis bubuli, ſucci abſinth. an.* ℥ ij. *colocyn.* ʒ j. *terantur & miſceantur ſimul, incorporentur cum farina lupinorum:* make hereof an Emplaſter to be laid upon the navel.

Liniments and Ointments may be alſo made for the ſame purpoſe, to anoint the belly; you may alſo make Plaſters for the navel of *Pilulæ Ruf.* anointing in the mean time the Fundament with Honey and Sugar, that they may be chaſed from above with bitter things, and allured downwards with ſweet things. Or elſe take Worms that have been caſt forth, dry them in an iron pan over the fire, then powder them, and give them with Wine or ſome other liquor to be drunk, for ſo they are thought quickly to kill the reſt of the Worms. Hereto alſo conduceth the juice of Citrons drunk with the Oil of bitter Almonds or Sallet-oil. Alſo ſome make Baths againſt this affect, of Wormwood, Galls, Peach-leaves boiled in Water, and then bathe the child therein.

But in curing the Worms, you muſt obſerve that this diſeaſe is oft-times entangled with another more grievous diſeaſe, as an acute and burning Fever, a flux or ſcouring, and the like; in which (as for example ſake) a Fever being preſent and conjoined therewith, if you ſhall give Worm-ſeeds, old Treacle, Myrrh, Aloes, you ſhall increaſe the Fever and Flux, for that bitter things are very contrary to theſe affects. But if on the contrary, in a Flux whereby the Worms are excluded, you ſhall give Corral, and the Flower of Lentils, you ſhall augment the Fever, making the matter more contumacious by dry and aſtringent things. Therefore the Phyſician ſhall be careful in conſidering whether the Fever be a ſymptom of the Worms, or on the contrary it be eſſential, and not ſymptomatick; that this being known, he may principally inſiſt in the uſe of ſuch Medicins as reſiſt both affects, as Purging and bitteriſh in a Fever and Worms, but bitter and ſomewhat aſtrictive things in the Worms and Flux.

The general Indications of curing the Worms.

Wherefore, and wherewith ſuch as have the Worms muſt be purged.

Harts-horn good againſt the Worms.

Suppoſitory againſt the *Aſcarides.*

A Plaſter againſt the Worms.

A Fever ſometimes a ſymptom, and ſometimes a diſeaſe.

CHAP. VI.

A ſhort deſcription of the Elephantiaſis *or Leproſie, and of the Cauſes thereof.*

THis diſeaſe is termed *Elephantiaſis*, becauſe the skin of ſuch as are troubled therewith is rough, ſcabious, wrinkled, and unequal, like the skin of an Elephant. Yet this name may ſeem to be impoſed thereon, by reaſon of the greatneſs of the diſeaſe. Some from the opinion of the *Arabians*, have termed it *Lepra*, or Leproſie (but unproperly, for the *Lepra* is a kind of ſcab and diſeaſe of the skin, which is vulgarly called *Malum ſancti manis*) which word for the preſent we will uſe, as that which prevails by cuſtom and antiquity. Now the Leproſie (according to *Paulus*) is a Cancer of the whole Body, the which (as *Avicen* adds) corrupts the complexion, form and figure of the members. *Galen* thinks the cauſe ariſeth from the error of the ſanguifying faculty, through whoſe default the aſſimilation in the fleſh and habit of the body is depraved, and much changed from it ſelf, and the rule of Nature. But *ad Glauconem*, he defines this diſeaſe, An effuſion of troubled or groſs bloud into the veins and habit of the whole body. This Diſeaſe is judged great, for that it partakes of a certain venenate virulency, depraving the members and comelineſs of the whole body. Now it appears that the Leproſie partakes of a certain venenate virulency by this, that ſuch as are melancholick in the whole habit of their bodies, are not leprous. Now this diſeaſe is compoſed of three differences of Diſeaſes: Firſt, it conſiſts of a diſtemper againſt Nature, as that which at the beginning is hot and dry, and at length the ebullition of the humours ceaſing, and the heat diſperſed, it becomes cold and dry, which is the conjunct cauſe of this ſymptom. Alſo it conſiſts of an evil compoſition or conformation, for that it depraves the figure and beauty of the parts. Alſo it conſiſts of a ſolution of continuity, when as the fleſh and skin are cleft in divers parts with ulcers and chops. The Leproſie hath for the moſt part three general cauſes, that is, the Primitive, Antecedent, and Conjunctive. The Primitive cauſe is either from the firſt conformation, or comes to them after they are born. It is thought to be in him from the firſt conformation, who was conceived of depraved and menſtruous bloud, and ſuch as are inclined to melancholy; who was begot of the leprous ſeed of one or both his Parents, for leprous perſons generate leprous, becauſe the principal parts being tainted and corrupted with a melancholick and venenate juice, it muſt neceſſarily follow, that the whole maſs of bloud and ſeed that falls from it, and the whole body ſhould alſo be vitiated. This cauſe happens to thoſe that are already born, by long ſtaying, and inhabiting in Maritime Countries, whereas the groſs and miſty air, in ſucceſs of time, induceth the like fault into the humours of the body; for that, according to *Hippocrates*, ſuch as the air is, ſuch is the ſpirit, and ſuch the humours. Alſo long abiding in very hot places, becauſe the bloud is torrified by heat, but in cold places, for that they incraſſate, and congealing the ſpirits, do after a manner ſtupifie, may be thought the primitive cauſes of this diſeaſe. Thus in ſome places of *Germany* there are divers leprous perſons; but they are more frequent in *Spain*, and over all *Africa*, than in all the World beſide, and in *Languedoc*, *Provence*, and *Guyenne*, are more than in whole *France* beſides. Familiarity, copulation, and cohabitation with leprous perſons may be reckoned amongſt the cauſes thereof, becauſe they transfer this diſeaſe to their Familiars by their breath, ſweat, and ſpittle, left on the edges of the Pots or Cups. This diſeaſe is alſo cauſed by the too frequent uſe of ſalt, ſpiced, acrid and groſs meats, as the fleſh of Swine, Aſſes, Bears, Pulſe, Milk-meats; ſo alſo groſs and ſtrong Wines, Drunkenneſs, Gluttony, a laborious life, full of ſorrow and cares, for that they incraſſate, and as it were burn the bloud. But the retention of melancholick excrements, as the ſuppreſſion of the Hemorrhoids, Courſes, Small Pox, and Meazles, as alſo a Quartan Fever accuſtomed to come at ſet times; the drying up of old ulcers, for that they defile the maſs of the bloud with a melancholick droſs and filth. Now you muſt underſtand, that the cauſe of the Leproſie by the retention of the ſuperfluities, happens, becauſe the corrupt bloud is not evacuated, but regurgitates over the whole body, and corrupts the bloud that ſhould nouriſh all the members; wherefore the aſſimilative faculty cannot well aſſimilate by reaſon of the corruption and default of the juice; and thus in concluſion the Leproſie is cauſed. The Antecedent cauſes are the humours diſpoſed to aduſtion and corruption into melancholy, by the torrid heat; for in bodies poſſeſſed with ſuch heat, the humours by aduſtion eaſily turn into melancholy, which in time acquiring the malignity and corruption of a virulent and venenate quality, yields a beginning and eſſence to the Leproſie. The Conjunct cauſes are the melancholick humours, which are now partakers of a venenate and malign quality, and ſpread over the whole habit of the body, corrupting and deſtroying it firſt by an hot and dry diſtemper, and then by a cold and dry, contrary to the beginnings of life. For hence inevitable death muſt enſue, becauſe our life conſiſts in the moderation of heat and moiſture.

Lib 4. cap. 1.
Lib. 2. cap. 11.

There is a certain hidden virulency in the Leproſie.

The primitive cauſe of a Leproſie.

How they may be leprous from their firſt conformation.

The Antecedent cauſe of Leproſie.

The Conjunct cauſe.

How it comes to be deadly.

CHAP. VII.

The ſigns of a Leproſie, breeding, preſent, and already confirmed.

THe diſpoſition of the body and humours to a Leproſie, is ſhewed by the change of the native and freſh colour of the Face, by that affect of the Face, which is commonly called *Gutta roſacea*, red and blackiſh ſuffuſions and puſtles, the falling away of the hairs, and a great thirſt, and a drineſs of the mouth both by night and day, a ſtinking breath, little ulcers in the mouth, the change of the voice to hoarſneſs, a deſire of venery above nature and cuſtom. Now there are four times of this diſeaſe, the beginning, increaſe, ſtate, and declenſion. The beginning is, when as the malignity hath not gone further than the inner parts and bowels, whereupon the ſtrength

The beginning of a Leproſie.

ſtrength muſt needs be more languid. The increaſe is, when as the virulency comes forth, and the ſigns and ſymptoms are every day increaſed in number and ſtrength. The ſtate is, when as the members are exulcerated. The declenſion is, when as the aſpect of the Face is horrid, the extreme parts fall away by the profundity and malignity of the ulcers, ſo that none, no not of the common ſort of People, can doubt of this diſeaſe. According to the doctrin of the Ancients, we muſt in ſearching out of the ſigns of this diſeaſe being preſent, have chief regard to the head. For the ſigns of diſeaſes more properly and truly ſhew themſelves in the Face by reaſon of the ſoftneſs and rarity of the ſubſtance thereof, and the tenuity of the skin that covers it; wherefore a black and aduſt humour diffuſed thereunder, eaſily ſhews it ſelf, and that not onely by the mutation of the colour, but alſo of the character, and bulk, and oft-times by manifeſt hurting it. Wherefore you muſt obſerve in the head, whether it have ſcales, and whether in the place of thoſe hairs that are fallen away, others more tender, ſhort and rare grow up, which is likely to happen through defect of fit nouriſhment to preſerve and generate hairs through corruption of the hairy ſcalp that ſhould be ſtored with ſuch nouriſhment, and of the habit it ſelf, and through the unfitneſs thereof to contain hairs: laſtly, by the acrimony of the vapours ſent up from the aduſt humours and entrails, fretting aſunder the roots of the hairs. But if not onely the hair, but alſo ſome portion of the skin and fleſh about the roots of the hair, come away by pulling, it is an argument of perfect corruption: let this therefore be the firſt ſign of a Leproſie. A ſecond and very certain ſign, is a numerous and manifeſt circumſcription of round and hard puſhes or puſtiles under the eye-brows, and behind the ears, and in ſeveral places of the Face, reſembling round and hard kernels, occaſioned by the default of the aſſimilating faculty. The cauſe of this default is the groſsneſs of the flowing nouriſhment, by which means it being impact, and ſtopping in the ſtraitneſs of the way, it grows round, as it were compaſſed about in the place whereas it ſticks, and by the means of the crudity, for that it is not aſſimilated, and by delay, it is further hardned. The third ſign is, the more contract and exact roundneſs of the ears, their groſsneſs, and as it were grainy ſpiſſitude or denſneſs; the cauſe of their roundneſs is the conſumption of the flaps and fleſhy part through want of nouriſhment, and exceſs of heat; but the occaſion of their grainy ſpiſſitude is the groſsneſs of the earthy nouriſhment flowing thither. The fourth ſign is a Lion-like wrinkling of the fore-head, which is the reaſon that ſome term this diſeaſe *Morbus Leoninus*; the cauſe hereof is the great drineſs of the habit of the body, which alſo is the reaſon that the bark of an old Oak is rough and wrinkled. The fifth is, the exact roundneſs of the eyes, and their fixt and immoveable ſteddineſs; verily the eyes are naturally almoſt round, yet they appear obtuſe, and ſomewhat broad on the foreſide, but end in a *Conus* on the hind part, by reaſon of the concourſe and figure of the muſcles and fat inveſting them. Therefore theſe being conſumed either through defect of laudable nouriſhment, or elſe by the acrimony of the flowing humour, they are reſtored to their proper figure and roundneſs. Now the muſcles which moved the eyes being conſumed, and the fat which facilitated their motion waſted, it comes to paſs that they ſtand ſtiff and unmovable, being deſtitute of the parts yielding motion, and the facility thereof. The ſixth ſign is, the Noſtrils flat outwardly, but inwardly ſtraight and contracted, that is, an earthy and groſs humour forced from within outwards, which ſwells the ſides or edges of the Noſtrils; whence it is, that the paſſages of the Noſe appear as it were obſtructed by the thickneſs of this humour, but they are depreſſed and flatted by reaſon of the reſt of the Face and all the neighbouring parts ſwollen more than their wont; add hereto that the partition is conſumed by the acrimony of the corroding and ulcerating humour. The ſeventh is, the lifting up, thickneſs and ſwelling of the lips, the filthineſs, ſtench and corroſion of the gums by acrid vapours riſing to the mouth; but the lips of leprous perſons are more ſwollen by the internal heat burning and incraſſating the humours, as the outward heat of the Sun doth in the Moors. The eighth ſign is, the ſwelling and blackneſs of the Tongue, and as it were varicous veins lying under it; becauſe the Tongue being by nature ſpongeous and rare, is eaſily ſtored with excrementitious humours, ſent from the inner parts unto the habit of the body: which ſame is the cauſe why the glandules placed about the Tongue above and below, are ſwollen hard and round, no otherwiſe then ſcrophulous or meazled Swine. Laſtly, All their Face riſeth in red bunches or puſhes, and is over-ſpread with a dusky and obſcure redneſs; the eyes are fiery, fierce and fixed, by a melancholick cachectick diſpoſition of the whole body, manifeſt ſigns whereof appear in the Face, by reaſon of the fore-mentioned cauſes, yet ſome leprous perſons have their Faces tinctured with a yellowiſh, others with a whitiſh colour, according to the condition of the humour, which ſerves for a *baſis* to the leprous malignity. For hence Phyſicians affirm that there are three ſorts of Leproſies, one of a reddiſh black colour, conſiſting in a melancholick humour; another of a yellowiſh green, in a cholerick humour; another in a whitiſh yellow, grounded upon aduſt phlegm. The ninth ſign is a ſtinking of the breath, as alſo of all the excrements proceeding from leprous bodies, by reaſon of the malignity conceived in the humours. The tenth is, a hoarſneſs, a ſhaking, harſh and obſcure voice, as it were coming out of the Noſe, by reaſon of the Lungs, recurrent Nerves and Muſcles of the Throttle tainted with the groſsneſs of a virulent and aduſt humour; the fore-mentioned conſtriction and obſtruction of the inner paſſage of the Noſe; and laſtly, the aſperity and inequality of the Weazon by immoderate drineſs, as it happens to ſuch as have drunk plentifully of ſtrong Wines without any mixture. This immoderate drineſs of the Muſcles ſerving for reſpiration makes them to be troubled with a difficulty of breathing. The eleventh ſign is very obſervable, which is a Morphew or defedation of all the skin, with a dry roughneſs and grainy inequality, ſuch as appears in the skins of plucked Geeſe, with many tetters on every ſide, a filthy ſcab, and ulcers not caſting off onely a bran-like ſcurff, but alſo ſcales and cruſts. The cauſe of this dry ſcab is the heat of the burning bowels and humours unequally contracting and wrinkling the skin, no otherwiſe than as leather is wrinkled by the heat of the Sun or Fire. The cauſe of the filthy ſcab and ſerpiginous ulcers, is the eating and corroding condition of the melancholick humour, and the venenate corruption, it alſo being

The increaſe. The ſtate. The declenſion.

The firſt ſign of the Leproſie.

II.

III.

IV.

Why it is called *Morbus Leoninus*.

V.

VI.

VII.

VIII.

IX.

X.

XI.

being the author of corruption, ſo that it may be no marvel, if the digeſtive faculty of the liver being ſpoiled, the aſſimilative of a malign and unfit matter ſent into the habit of the body, cannot
XII. well nor fitly perform that which may be for the bodies good. The twelfth is, the ſenſe of a certain pricking as it were of Goads or Needles over all the skin, cauſed by an acrid vapour hindred from
XIII. paſſing forth, and intercepted by the thickneſs of the skin. The thirteenth is a conſumption and emaciation of the muſcles which are between the thumb and fore-finger, not onely by reaſon that the nouriſhing and aſſimilating faculties want fit matter wherewith they may repair the loſs of theſe parts, for that is common to theſe with the reſt of the body; but becauſe theſe muſcles naturally riſe up unto a certain mountainous tumour, therefore their depreſſion is the more manifeſt. And this is the cauſe that the ſhoulders of leprous perſons ſtand out like wings; to wit, the emaciation of
XIV. the inward part of the muſcle *Trapezites*. The fourteenth ſign is, the diminution of ſenſe, or a numbneſs over all the body by reaſon that the nerves are obſtructed by the thickneſs of the melancholick humour hindring the free paſſage of the animal ſpirit, that it cannot come to the parts that ſhould receive ſenſe, theſe in the interim remaining free which are ſent into the muſcles for motions ſake, and by this note I chiefly make trial of leprous perſons, thruſting a ſomewhat long and thick needle ſomewhat deep into the great tendon endued with moſt exquiſit ſenſe, which runs to the heel, which if they do not well feel, I conclude that they are certainly leprous. Now for that they thus loſe their ſenſe, their motion remaining entire; the cauſe hereof is, that the nerves which are diſſeminated to the skin, are more affected, and thoſe that run into the muſcles are not ſo much, and therefore when as you prick them ſomewhat deep, they feel the prick, which they do not in the ſurface
XV. of the skin. The fifteenth is, the corruption of the extreme parts poſſeſſed by putrefaction and a Gangrene, by reaſon of the corruption of the humours ſent thither by the ſtrength of the bowels, infecting with the like tainture the parts wherein they remain: add hereto that the animal ſenſitive faculty is there decayed, and as often as any faculty hath forſaken any part, the reſt preſently after a
XVI. manner neglect it. The ſixteenth is, they are troubled with terrible dreams; for they ſeem in their ſleep to ſee Devils, Serpents, Dungeons, Graves, dead bodies, and the like, by reaſon of the black vapors of the melancholick humour troubling the phantaſie with black and diſmal viſions, by which reaſon alſo
XVII. ſuch as are bitten of a mad Dog fear the water. The ſeventeenth is, that at the beginning and increaſe of the diſeaſe they are ſubtil, crafty and furious, by reaſon of the heat of the humours and bloud; but at length in the ſtate and declenſion, by reaſon of the heat of the humours, and bloud, and entrails decaying by little and little; therefore then fearing all things whereof there is no cauſe, and diſtruſting of their own ſtrength, they endeavour by craft maliciouſly to circumvent thoſe with whom
XVIII. they deal, for that they perceive their powers to fail them. The eighteenth, is a deſire of venery above their nature, both for that they are inwardly burned with a ſtrange heat; as alſo by the mixture of flatulencies therewith (for whoſe generation the melancholick humour is moſt fit) which are agitated, and violently carried through the veins and genital parts by the preternatural heat; but at length, when this heat is cooled, and that they are fallen into an hot and dry diſtemper, they mightily abhor venery, which then would be very hurtful to them, as it is alſo at the beginning of the diſeaſe, becauſe they have ſmall ſtore of ſpirits and native heat, both which are diſſipated by venery. The nineteenth is, the ſo great thickneſs of their groſs and livid bloud, that if you waſh it,
XIX. you may find a ſandy matter therein, as ſome have found by experience, by reaſon of the great aduſtion and aſſation thereof. The twentieth is, the languidneſs and weakneſs of the pulſe (by reaſon
XX. of the oppreſſion of the vital and pulſifick faculty by a cloud of groſs vapours.) Herewith alſo their urin ſometimes is thick and troubled, like the urin of carriage-beaſts, if the urinary veſſels be permeable and free, otherwiſe it is thin, if there be obſtruction, which onely ſuffers that which is thin to flow forth by the urinary paſſages; now the urin is oftentimes of a pale aſh-colour, and oft-times it ſmells like as the other excrements do in this diſeaſe. Verily there are many other ſigns of the Leproſie, as the ſlowneſs of the belly by reaſon of the heat of the Liver, often belchings by reaſon that the ſtomach is troubled by the reflux of a melancholick humour, frequent ſneezing by reaſon of the fulneſs of their brain; to theſe this may be added moſt frequently, that the face and all the skin
Why their Faces ſeem to be greaſie. is unctuous or greaſie, ſo that water poured thereon, will not in any place adhere thereto: I conceive it is by the internal heat diſſolving the fat that lies under the skin, which therefore always looks as if it were greaſed or anointed therewith in leprous perſons. Now of theſe fore-mentioned ſigns, ſome are univocal, that is, which truly and neceſſarily ſhew the Leproſie: other ſome are equivocal or common, that is, which conduce as well to the knowledge of other diſeaſes as this. To conclude, that aſſuredly is a Leproſie which is accompanied with all, or certainly the moſt part of theſe fore-mentioned ſigns.

CHAP. VIII.

Of Prognoſticks in the Leproſie; and how to provide for ſuch as ſtand in fear thereof.

Why the Leproſie is incurable. THe Leproſie is a diſeaſe which paſſeth to the iſſue, as contagious almoſt as the Plague, ſcarce curable at the beginning, incurable when as it is confirmed, becauſe it is a Cancer of the whole body; now if ſome one Cancer of ſome one part ſhall take deep root therein, it is judged incurable. Furthermore, the remedies which to this day have been found out againſt this Diſeaſe are judged inferiour and unequal in ſtrength thereto. Beſides, the ſigns of this diſeaſe do not outwardly ſhew themſelves before that the bowels be ſeized upon, poſſeſſed and corrupted by the malignity of the humour, eſpecially in ſuch as have the white Leproſie, ſundry of which you may ſee about *Bourdeaux*, and in *Little-Britain*, who notwithſtanding inwardly burn with ſo great heat, that it will ſuddenly wrinkle and wither an Apple held a ſhort time in their hand, as if it had laid for many days

days in the Sun. There is another thing that increaseth the difficulty of this disease, which is an equal pravity of the three principal faculties whereby life is preserved. The deceitful and terrible visions in the sleep, and numbness in feeling, argue the depravation of the animal faculty; now the weakness of the vital faculty is shewed by the weakness of the pulse, the obscurity of the hoarse and jarring voice, the difficulty of breathing, and stinking breath; the decay of the natural is manifested by the depravation of the work of the Liver in sanguification, whence the first and principal cause of this harm ariseth. Now because we cannot promise cure to such as have a confirmed Leprosie, and that we dare not do it to such as have been troubled therewith but for a short space, it remains that we briefly shew how to free such as are ready to fall into so fearful a disease. Such therefore must first of all shun all things in diet and course of life, whereby the bloud and humours may be too vehemently heated, whereof we have formerly made some mention. Let them make choice of meats of good or indifferent juice, such as we shall describe in treating of the diet of such as are sick of the Plague; Purging, Bleeding, Bathing, Cupping, to evacuate the impurity of the bloud, and mitigate the heat of the Liver, shall be prescribed by some learned Physician. *Valesius de Tarenta* much commends gelding in this case, neither do I think it can be disliked; for men subject to this disease may be effeminated by the amputation of their testicles, and so degenerate into a womanish nature, and the heat of the Liver boiling the bloud, being extinguished, they become cold and moist, which temper is directly contrary to the hot and dry distemper of leprous persons; besides the leprous being thus deprived of the faculty of generation, that contagion of this disease is taken away which spreadeth, and is diffused amongst mankind, by the propagation of their issue.

The Cure.

The Diet.

Gelding good against the Leprosie.

The End of the Twentieth Book.

BOOK XXI.

Of Poysons, *and of the* Biting *of a* Mad Dog; *And the* Bitings *and* Stingings *of other Venomous Creatures.*

CHAP. I.

The cause of writing this Treatise of Poysons.

Five Reasons have principally moved me to undertake to write this Treatise of Poysons, according to the opinion of the Ancients. The first is, that I might instruct the Surgeon what remedies must presently be used to such as are hurt by poisons, in the interim whilest greater means may be expected from a Physician. The second is, that he may know by certain signs and notes such as are poisoned or hurt by poysonous meats, and so make report thereof to the Judges, or to such as it may concern. The third is, that those Gentlemen and others who live in the Country, and far from Cities, and store of greater means, may learn something by my labour, by which they may help their friends bitten by an Adder, mad Dog, or other poysonous creatures, in so dangerous, sudden and unusual a case. The fourth is, that every one may beware of poysons, and know their symptoms when present, that being known, they may speedily seek for a remedy. The fifth is, that by this my labour all men may know what my good will is, and how well-minded I am towards the Common-wealth in general, and each man in particular, to the glory of God. I do not here so much arm malicious and wicked persons to hurt, as Surgeons to provide to help and defend each mans life against poyson; which they did not understand, or at least seemed not so to do, which taking this my labour in evil part, have maliciously interpreted my meaning.

But now at length, that we may come to the matter, I will begin at the general division of Poysons, and then handle each *species* thereof severally; but first let us give this Rule, That poyson is that which either outwardly applied or struck in, or inwardly taken into the body, hath power to kill it, no otherwise than meat well dresst is apt to nourish it. For *Conciliator* writes that the properties of Poyson are contrary to nourishments in their whole substance; for as nourishment is turned into bloud, and in each part of the body whereto it is applied to nourish, by perfect assimilation substituted in the place of that portion which flies away each moment. Thus on the contrary Poyson turns our bodies into a nature like it self and venenate, for as every agent imprints the force and qualities thereof in the subject patient, thus Poyson by the immoderation of faculties in their whole nature contrary to us, changeth our substance into its nature, no otherwise then fire turneth chaff in a moment into its own nature, and so consumes it. Therefore it is truly delivered by the Ancients, who have diligently pried into the faculties of Natural things, that it is poyson that may kill men by destroying and corrupting their temper, and the composure and conformation of the body. Now all poysons are said to proceed either from the corrupt Air, or from living Creatures, Plants and Minerals, or by any artificial malignity in distilling, subliming, and diversly mixing of poysonous and fuming things. Hence arise sundry differences of Poysons, neither do they all work after the same manner; for some corrupt our nature by the unmeasurableness of the manifest and elementary qualites whereof they consist, others from a specifick and occult property. Hence it is that

What is to be accounted Poyson.

The differences of Poysons.

All poysons have not a peculiar antipathy with the heart.

that some kill sooner than other some; neither is it true that all of them presently assail the heart, but others are naturally at deadly strife with other parts of the body; as *Cantharides* with the bladder, the Sea-Hare with the Lungs, the *Torpedo* with the hands, which it stupefieth, though the Fishers rod be betwixt them. Thus of Medicins, there are some which are apt presently to comfort and strengthen the heart, others the brain, as *stœchas*; others the Stomach, as Cinamon. Also there are some poysons which work both ways, that is, by manifest and occult qualities, as *Euphorbium*; for that both by the excessive heat and the whole substance, or the discord of the whole substance with ours, corrupts our nature. An argument hereof is, that Treacle, which by its quality is manifestly hot, infringeth the force thereof, as also of all others of an occult property. Poysons which work by an occult and specifick property, do not therefore do it, because they are too immoderately hot, cold, dry, moist; but for that they are absolutely such, and have that essence from the Stars and celestial influence, which is apt to dissolve and destroy the strength of mans body, because being taken but even in a small quantity, yet are they of so pernicious a quality that they kill almost in a moment. Now Poysons do not only kill being taken into the body, but some being put or applied outwardly; neither do venomous creatures onely harm by their stinging and biting, but also by their excrements, as Spittle, Bloud, the Touch and Breath.

CHAP. II.

How Poysons being small in quantity, may by their onely touch cause so great alterations.

IT seemeth strange to many how it may come to pass, that poyson taken or admitted in small quantity, may almost in a moment produce so pernicious effects over all the body, and all the parts, faculties, and actions; so that being admitted but in a little quantity, it swells up the body into a great bigness. Neither ought it to seem less strange, how Antidotes and Counter-poysons, which are opposed to poyson, can so suddenly break and weaken the great and pernicious effects thereof, being it is not so likely that so small a particle of poyson or antidote can divide it self into so many, and so far severed particles of our body. There are some (saith *Galen*) who think that some things by touch onely, by the power of their quality, may alter those things which are next to them; and that this appears plainly in the Fish *Torpedo*, as that which hath so powerful a quality, that it can send it along the Fishers rod to the hand, and so make it become torpid or numb. But on the contrary, Philosophers teach that accidents, such as qualities are, cannot without their subjects remove and diffuse themselves into other subjects. Therefore *Galen*'s other answer is more agreeable to reason, that so many and great affects of poysons, and remedies arise either from a certain spirit or subtil humidity; not truly, for that this spirit and subtil humidity may be dispersed over the whole body and all the parts thereof which it affects, but that little which is entered the body, as cast in by the stroak of a Spider, or the sting of a Scorpion, infects and corrupts all the next parts by contagion with the like quality, these other that are next to them, until from an exceeding small portion of the bloud, if the stroak shall light into the veins, it shall spread over the whole mass of bloud; or of phlegm, if the poyson shall chance to come to the Stomach, and so the force thereof shall be propagated and diffused over all the humours and bowels. The doubt of Antidotes is less, for these being taken in greater quantity, when they shall come into the stomach, warmed by the heat of the place they become hot, and send forth vapours, which suddenly diffused over the body by the subtilty of their substance, do by their contrary forces dull and weaken the malignity of the poyson. Wherefore you may often see, when as Antidotes are given in less quantity than is fit, that they are less prevalent, neither do they answer to our expectation in overcoming the malignity of the poyson so that it must necessarily follow that these must not onely in qualities, but also in quantity be superiour to Poysons.

Cap. 5. lib. 6. de loc. affect.

The true reason of the wondrous effects of poysons.

CHAP. III.

Whether there be any such Poysons as will kill at a set time?

No poysons kill in a set time.

TO the propounded Question: Whether there may be Poysons which within a certain and definite time (put case a Moneth or Year) may kill men? *Theophrastus* thus answers; of Poysons some more speedily perform their parts, others more slowly; yet may you find no such as will kill in set limits of time, according to the will and desire of men: For that some kill sooner or later than others; they do not this of their own or proper nature, as Physicians rightly judge, but because the subject upon which they light, doth more or less resist or yield to their efficacy. Experience sheweth the truth thereof; for the same sort of poyson in the same weight and measure, given to sundry men of different tempers and complexions, will kill one in an hour, another in six hours, or in a day, and on the contrary, will not so much as hurt some third man. You may also observe the same in purging Medicins. For the same Purge given to diverse men in the same proportion, will purge some sooner, some later, some more sparingly, others more plentifully, and othersome not at all; also with some it will work gently, with othersome with pain and gripings. Of which diversity, there can be no other cause assigned, than mens different natures in complexion and temper, which no man can so exactly know and comprehend, as to have certain knowledge thereof, how much and how long the native heat can resist and labour against the strength of poyson, or how pervious or open the passages of the body may be, whereby the poyson may arrive at the heart and principal parts. For in such (for examples sake) as have the passages of their arteries more large, the poyson may more readily and speedily enter into the heart, together with the air that is continually drawn into the body.

How poysons come to kill sooner or later.

CHAP.

CHAP. IV.

Whether such Creatures as feed upon poysonous things, be also poysonous? and whether they may be eaten safely and without harm.

DUcks, Storks, Herons, Peacocks, Turkies, and other Birds, feed upon Toads, Vipers, Asps, Snakes, Scorpions, Spiders, Caterpillers, and other venemous things: Wherefore it is worthy the questioning, whether such like Creatures nourished with such food, can kill or poyson such persons as shall afterward eat them? *Matthiolus* writes, that all late Authors, who have treated of Poysons, to be absolutely of this opinion, That men may safely and without any danger feed upon such Creatures, for that they convert the Beasts into their nature after they have eaten them, and on the contrary are not changed by them. This reason though very probable, yet doth it not make these Beasts to be wholly harmless, especially if they be often eaten or fed upon. *Dioscorides* and *Galen* seem to maintain this opinion, whereas they write that the milk, which is nothing else then the relented bloud of such beasts as feed upon Scammony, Hellebore, and Spurge, purgeth violently. Therefore Physicians desirous to purge a sucking child, give Purges to the Nurses, whence the milk becoming purging, becomes both Meat and Medicin to the Child. The flesh of Thrushes which feed upon Juniper-berries, savours of Juniper. Birds that are fed with Wormwood or Garlick, either taste bitter, or have the strong scent of Garlick. Whitings taken with Garlick, so smell thereof, that they will not forego that smell or taste by any salting, frying, or boiling; for which sole reason, many who hate Garlick, are forced to abstain from these Fishes. The flesh of Rabbits that feed upon Penny-royal and Juniper, savour of them; Physicians wish that Goats, Cows, and Asses whose Milk they would use for Consumptions, or other diseases, should be fed some space before, and every day with these or these herbs which they deem fit for the curing this or that disease: For *Galen* affirms that he doubts not, but that in succes of time the flesh of Creatures will be changed by the meats whereon they feed, and at length savour thereof. Therefore I do not allow that the flesh of such things as feed upon venemous things, should be eaten for food, unless it be some long space after they have disused such repast, and that all the venom be digested and overcome by the efficacy of their proper heat, so that nothing thereof may remain in taste, smell, or substance, but be all vanished away. For many die suddenly, the cause of whose deaths are unknown, which peradventure was from nothing else but the sympathy and antipathy of bodies, for that these things cause death and disease to some, that nourish othersome (according to our vulgar English Proverb, *That which is one mans meat, is another mans poyson.*)

Such things as feed upon poyson may be eaten without danger.

Lib. de simp. facult.

The occasion of sudden death in many.

CHAP. V.

The general signs of such as are poysoned.

WE will first declare what the general signs of poyson are, and then we will descend to particulars, whereby we may pronounce that one is poysoned with this or that poyson. We certainly know that a man is poysoned, when as he complains of a great heavines of his whole body, so that he is weary of himself, when as some horrid and loathsom taste sweats out from the orifice of the stomach to the mouth and tongue, wholly different from that taste that meat, howsoever corrupted, can send up: when as the colour of the Face changeth suddenly, somewhiles to black, sometimes to yellow, or any other colour, much differing from the common custom of man; when nauseousnes with frequent vomiting troubleth the Patient, and that he is molested with so great unquietnes, that all things may seem to be turned upside down. We know that the poyson works by the proper, and from the whole substance, when as without any manifest sense of great heat or coldnes the Patient swounds often with cold sweats, for usually such poysons have no certain and distinct part wherewith they are at enmity, as *Cantharides* have with the bladder. But as they work by their whole substance, and an occult propriety of form, so do they presently and directly assail the heart, our essence and life, and the fortres and beginning of the vital faculty. Now will we shew the signs whereby poysons that work by manifest and elementary qualities may be known. Those who exceed in heat, burn or make an impression of heat in the tongue, the mouth, throat, stomach, guts, and all the inner parts, with great thirst, unquietnes, and perpetual sweats. But if to their exces of heat they be accompanied with a corroding and putrefying quality, as Arsenick, Sublimate, Rose-ager, or Rats-bane, Verdegrease, Orpiment, and the like, they then cause in the stomach and guts intolerable pricking pains, rumblings in the belly, and continual and intolerable thirst. These are succeeded by vomitings, with sweats somewhiles hot, somewhiles cold, with swounings, whence sudden death ensues. Poysons that kill by too great coldnes, induce a dull or heavy sleep, or drowzines, from which you cannot easily rowze or waken them; sometimes they so trouble the brain that the Patients perform many undecent gestures and antick tricks with their mouths, eyes, arms, and legs, like as such as are frantick; they are troubled with cold sweats, their Faces become blackish or yellowish, always ghastly, all their bodies are benumbed, and they die in a short time, unless they be helped; poysons of this kind are Hemlock, Poppy, Night-shade, Henbane, Mandrag. Dry poysons are usually accompanied by heat with moisture, for although Sulphur be hot and dry, yet hath it moisture to hold the parts together, as all things which have a consistence have; yet they are called dry, by reason that drines is predominant in them: such things make the tongue and throat dry and rough, with unquenchable thirst; the belly is so bound, that so much as the urin cannot have free passage forth; all

Common signs of such as are poysoned.

Signs of hot poysons.

Signs of cold Poysons.

Signs of dry Poysons.

all the members grow ſqualid by drineſs, the Patients cannot ſleep: poyſons of this kind are Litharge, Ceruſs, Lime, Scales of Braſs, Filings of Lead, prepared Antimony. On the contrary, moiſt poiſons induce a perpetual ſleep, a flux or ſcouring, the reſolution of all the nerves and joints, ſo that not ſo much as the eyes may be faithfully contained in their orbs but will hang as ready to fall out; the extreme parts, at the Hands, Feet, Noſe, and Ears corrupt and putrifie, at which time they are alſo troubled with thirſt by reaſon of their ſtrong heat, always the companion of putrefaction and oft-times the author thereof: now when this cometh to paſs death is at hand. Very many deny that there can be any moiſt poyſons found, that is, ſuch as may kill by the efficacy of their humidity, becauſe there are no ſuch things to be found as may come to the fourth degree of moiſture. Yet there is an example that averrs the contrary, which was of one, who ſleeping on the night, was bitten by a Serpent, as *Gilbertus Anglicus* affirmeth; for dying thereof, when as his ſervant, deſirous to awaken his Maſter out of his ſleep, took him by the arm, all the fleſh being putrefied, fell off, and preſently the bones alſo fell aſunder, being deprived of their fleſh, which could not happen unleſs by exceſs of the venemous humidity which lay hid in the teeth and ſpittle of the Serpent. Alſo we have found it noted by *Hippocrates*, that in a rainy, humid, and ſoutherly conſtitution of the Year, it happened by the malign violence of the venenate and putrefying humidity, that the fleſh of the arms and legs becoming rotten, fell away by piece-meal, and the bones remained bare; yea alſo and the bones themſelves in ſome, putrefied and fell away: neither certainly doth the *Lues Venerea* kill by any other means than by a fretting and putrefying force of humidity, by whoſe efficacy the ſolidity of the bones is diſſolved, then much more the fleſh may be tainted and conſumed by putrefaction.

Signs of moiſt Poiſons.

An Hiſtory.

Sect. 3. *lib.* 3. *Epid.*

The *Lues Venerea* kills by exceſs of moiſture.

To theſe and ſuch poyſons which work by a manifeſt and elementary faculty, when as they ſhall be received into the body after what manner ſoever, you ſhall forthwith oppoſe their contraries; and if by chance it be not manifeſt what, and of what diſtinct kind of poiſon that is, you muſt know that ſuch poiſons as work by occult properties, it is not by Reaſon as yet found out how they will affect the body, but onely by Experience. Therefore to theſe you muſt oppoſe their like Antidotes, which may by their whole ſubſtance ſtrengthen the heart and vital faculty, and withſtand the ſtrength of the poiſon. But to this our diſtinction of poiſons, working by a manifeſt and elementary quality, their opinion is contrary, who affirm that the venom of all poiſonous Beaſts are therefore cold, for that ſuch as are bitten or ſtung with them, are forthwith felt to be colder than a ſtone. And that Serpents for fear of cold, when as Winter is at hand keep themſelves in holes and dens under ground, or elſe as Vipers uſe to do, lie under ſtones, under which you may often find them ſtiff and numb, and ſo unapt for motion, that you may eaſily take them up in your hand. But the coldneſs that is perceived or felt in ſuch as are bitten or ſtung, is not occaſioned by the coldneſs of the poiſon, but by the abſence of the natural heat, withdrawing it ſelf in the very inſtant of the ſtroak, from the ſurface into the center of the body, both for the defence of the heart, as the principal part, as alſo for that there is nothing which ſo much diſſipates, or ſo much oppugns the vital heat as poiſon (of what kind ſoever it be) doth.

All poiſons are not cold.

Why ſuch as are poyſoned or ſtung, are cold.

CHAP. VI.

How, or by what means to ſhun or eſchew Poyſons.

IT is a matter of much difficulty to avoid poiſons, becauſe ſuch as at this time temper them, are ſo throughly prepared for deceit and miſchief, that they will deceive even the moſt wary and quick-ſighted; for they ſo qualifie their ingrate taſte and ſmell, by the admixture of ſweet and well ſmelling things, that they cannot eaſily be perceived even by the skilful. Therefore ſuch as fear poiſoning, ought to take heed of meats cooked with much Art, very ſweet, ſalt, ſowre, or notably endued with any other taſte. And when they are oppreſt with hunger or thirſt, they muſt not eat nor drink too greedily, but have a diligent regard to the taſte of ſuch things as they eat or drink; beſides, before meat let them take ſuch things as may weaken the ſtrength of the poyſons, ſuch as is the fat broth of good nouriſhing fleſh meats; in the morning let them arm themſelves with Treacle or Mithridate, and conſerve of Roſes, or the leaves of Rue, a Walnut, and dry Figs; beſides, let him preſently drink a little draught of Muskedine, or ſome other good Wine; when one ſuſpects he hath taken any poiſon in meat or drink, let him forbear ſleeping. For beſides that the force of poiſon is oft-times ſo rapid, that it conſumes our life in a ſhort ſpace, as Fire doth Stubble, as alſo for that it is drawn more inwardly into the ſecret paſſages of the body by ſleep. Wherefore in ſuch a caſe it is better to procure Vomit by drinking *Hydræleum* warm, or Butter diſſolved in warm Oil, or a decoction of Line, or Fenugreek ſeeds, or fat Broth, for thus the received poiſon is alſo caſt forth therewith, or elſe the acrimony thereof retunded, and the belly looſed.

What ſuch as fear poiſoning muſt obſerve in their diet.

Why ſleep is hurtful.

Why and how Vomit muſt be procured.

You may ſee this by dayly experience, for Cauſticks, Veſicatories, and the like acrid things being applied to the anointed part, will not bliſter nor exulcerate the part. Neither doth the Vomit conduce onely in this, that it excludeth the poiſon, but it ſhews either by the Taſte, Smell, or Colour, the kind of the taken poiſon; ſo that then by uſing the proper Antidote, it may be the more eaſily and ſpeedily reſiſted, yet notwithſtanding if you conceive that the poiſon have deſcended deeper into the Guts, you may with a Clyſter draw away the reſt thereof which adheres to the Coats of the Guts. But if the Patient cannot vomit, then ſhall ſome purging Medicin be given him forthwith, and ſuch as are thought more particularly to reſiſt poiſon; ſuch as are Agarick, Aloes, the leſſer Centaury, Rubarb, and other things, according to the direction of the learned Phyſician. Then ſhall you adminiſter Clyſters made with

When and wherewith they ſhall be purged.

with *Caſſia*, fatty decoctions, Sheeps Suet, or Butter, or Cows Milk, with the mucilages of Line ſeed, *Pſilium* ſeeds, Quince ſeeds, and other ſuch things as are uſually given in a Dyſentery, or bloudy flux, that ſuch things may hinder the adheſion of the poyſon to the coats of the guts, and by their unctuouſneſs retund the acrimony of the poyſon, and mitigate if any thing ſhall already be ulcerated, and abſolutely defend the ſound parts from the malign effects of the poyſon. But let this be a perpetual rule, that the poyſon be ſpeedily drawn back by the ſame way it entered into the body; as if it entered by ſmelling, in at the Noſtrils, let it be drawn back by ſneezing; if by the mouth into the ſtomach, let it be excluded by vomit; if by the fundament into the belly then by clyſter; if by the Privities into the Womb, then by metrenchites or injections made thereinto; if by a bite, ſting, or wound, let revulſion be made by ſuch things as have a powerful attractive faculty: for thus we make diverſions, that by theſe we may not onely hinder the poyſon from aſſailing the heart, but alſo that by this means we may draw it from within outwards. Wherefore ſtrong ligatures caſt about the arms, thighs and legs, are good in this caſe. Alſo large Cupping-glaſſes applied with flame to ſundry parts of the body are good. Alſo baths of warm water, with a decoction of ſuch things as reſiſt Poyſon, Southern-wood, Calamint, Rue, Betony, Horehound, Penny-royal, Bays, Scordium, Smallage, Scabious, Mints, Valerian, and the like, are good in this caſe. Alſo Sweats are good, being provoked ſo much as the ſtrength of the Patient can endure. But if he be very wealthy, whom we ſuſpect poyſoned, it will be ſafer to put him into the belly of an Ox, Horſe, or Mule, and then preſently into another as ſoon as the former is cold, that ſo the poyſon may be drawn forth by the gentle and vaporous heat of the new killed Beaſt; yet do none of theſe things without the advice of a Phyſician, if it may conveniently be had.

The cure of poyſoned wounds.

CHAP. VII.

How the corrupt or venemous Air may kill a man.

THe Air is infected and corrupted by the admixture of malign vapours, either ariſing from the unburied bodies of ſuch as are ſlain in great conflicts, or exhaling out of the earth after Earthquakes; for the air, long pent up in the cavities and bowels of the earth, and deprived of the freedom and commerce of the open air, is corrupted, and acquires a malign quality, which it preſently transferreth unto ſuch as meet therewith. Alſo there is a certain malignity of the air, which accompanies Thunders and Lightnings, which ſavours of a ſulphureous virulency, ſo that whatſoever wild Beaſts ſhall devour the Creature killed therewith, they become mad, and die immediately; for the fire of Lightning hath a far more rapid, ſubtil, and greater force than other fires, ſo that it may rightly be termed a Fire of Fires.

By how many, and what means the air may be infected.

How Thunders and Lightnings may infect the Air.

An argument hereof is, that it melteth the head of a Spear, not harming the Wood, and Silver and Gold, not hurting the Purſe wherein it is contained. Alſo the air is infected by fumigations which preſently admitted into the body and bowels by the mouth and noſe in reſpiration, by the skin and arteries in perſpiration, doth eaſily kill the ſpirits and humours being firſt infected, and then within a ſhort ſpace after the ſolid ſubſtance of the principal parts, and chiefly of the heart being turned into their nature, unleſs the man be firſt provided for by Sneezing, Vomiting, Sweating, purging by the belly, or ſome other excretion. For that poyſon which is carried into the body by ſmell, is the moſt rapid and effectual, by ſo much as a vapour or exhalation is of more ſubtil and quicklier-piercing eſſence than an humour. Yet notwithſtanding, wilt thou ſay, it is not credible, that any be killed by any vapour raiſed by the force of fire, as of a Torch or Warming-pan, for that the venenate quality of the thing that is burnt, is diſſipated and conſumed by the force of the fire, purging and cleanſing all things. This reaſon is falſly feigned to the deſtruction of the lives of careleſs people; for ſulphurcous brands kindled at a clear fire, do notwithſtanding caſt forth a ſulphurous vapour. Whether do not *Lignum aloes* and Juniper, when they are burnt in a flame, ſmell leſs ſweetly?

Whether the vapour that ariſeth from a burnt thing may poyſon one.

Pope *Clement*, the ſeventh of that name, the Uncle of our Kings Mother, was poyſoned by the fume of a poyſonous Torch that was carried lighted before him, and died thereof. *Matthiolus* telleth, that there were two Mountebanks in the Market-place of *Sienna*, the one of which but ſmelling to a poyſoned Gilly-flower given him by the other, fell down dead preſently.

An Hiſtory.

A certain man not long ago, when he had put to his noſe, and ſmelled a little unto a pomander, which was ſecretly poyſoned, was preſently taken with a *Vertigo*, and all his face ſwelled, and unleſs that he had gotten ſpeedy help by Sternutatories and other means, he had died ſhortly after of the ſame kind of death that Pope *Clement* did.

The ſafeſt preſervative againſt ſuch poyſons is, not to ſmell to them: moreover ſome affirm, that there are prepared ſome Poyſons of ſuch force, that being anointed but on the Saddle, they will kill the Rider; and others, that if you but anoint the Stirrups therewith, they will ſend ſo deadly poyſonous a quality into the Rider through his Boots, that he ſhall die thereof within a ſhort time after: which things, though they be ſcarce credible, becauſe ſuch poyſons touch not the naked skin, yet have they an example in Nature, whereby they may defend themſelves; for the *Torpedo* ſends a narcotick, and certainly deadly force into the arm, and ſo into the body of the Fiſher, the cords of the Net being between them.

CHAP.

CHAP. VIII.

That every kind of Poyſon hath its proper and peculiar Signs and Effects.

AS Poyſons are diſtinct in *ſpecies*, ſo each *ſpecies* differs in their Signs and Effects; neither is it poſſible to find any one kind of poyſon which may be accompanied with, or produce all the ſigns and effects of all poyſons, otherwiſe Phyſicians ſhould in vain have written of the ſigns and effects of each of them, as alſo of their proper remedies and antidotes. For what kind of poyſon ſhall that be which ſhall cauſe a burning heat in the Stomach, Belly, Liver, Bladder, and Kidnies, which ſhall cauſe a hicketting, which ſhall cauſe the whole body to tremble and ſhake, which ſhall take away the voice and ſpeech, which ſhall cauſe convulſions, ſhall weaken the pulſifick faculty, which ſhall intercept the freedom of breathing, which ſhall ſtupifie and caſt into a dead ſleep, which ſhall together and at once cauſe a *Vertigo* in the head, dimneſs in the ſight, a ſtrangling or ſtoppage of the breath, thirſt, bleeding, fever, ſtoppage of the urin, perpetual vomiting, redneſs, lividneſs, and paleneſs of the face, reſolutions of the powers, and many other things, all which are cauſed by all ſorts of poyſon. Laſtly, No body will deny but that hot poyſons may kill more ſpeedily than cold, for that they are more ſpeedily actuated by the native heat.

Hot poyſons kill ſooner than cold.

CHAP. IX.

The Effects of Poyſons from particular venemous things, and what Prognoſticks may thence be made.

Lib. 2. cap. 27. IT is the opinion of *Cornelius Celſus*, and almoſt of all the Ancients, that the bite of every Beaſt hath ſome virulency, but yet ſome more than otherſome. They are moſt virulent that are inflicted by Venemous Beaſts, Aſps, Vipers, Water-Snakes, and all kinds of Serpents, Baſilisks, Dragons, Toads, mad Dogs, Scorpions, Spiders, Bees, Waſps, and the like. They are leſs malign, which are of Creatures wanting Venom, as of Horſes, Apes, Cats, Dogs not mad, and many other things, which though of their own nature they are without poiſon, yet in their bites there is ſomething more dolorifick and ill-natured than in common wounds inflicted by other occaſions: I believe, that in their ſlaver or *ſanies*, there is ſomething, I know not how to term it, contrary to our nature, which imprints a malign quality in the ulcer, which alſo you may obſerve in the tearings or ſcratchings of ſuch Creatures as have ſharp claws, as Lions and Cats. Moreover many affirm, that they have found by experience, that the bites of Men are not altogether without virulency, eſpecially of ſuch as are red haired and freckled, chiefly when as they are angred; it is probable that the bites of other perſons want this malignity, ſeeing that their ſpittle will cure ſmall ulcerations. Wherefore if there ſhall happen difficulty of cure in a wound, cauſed by a mans biting, which is neither red haired, nor freckled, neither angry, this happens not by means of the ſpittle, nor by any malign quality, but by reaſon of the contuſion, cauſed by the bluntneſs of the teeth, not cutting, but bruiſing the part; for being not ſharp they cannot ſo eaſily enter the fleſh, unleſs by bruiſing and tearing, after the manner of heavy and blunt ſtroaks and weapons, wounds being occaſioned by ſuch, are more hard to be cured than ſuch as are made by cutting and ſharp Weapons. But of the fore-ſaid bitings of Venemous Creatures, there are few which do not kill in a ſhort ſpace, and almoſt in a moment, but principally if the poyſon be ſent into the body by a live Creature, for in ſuch poyſon there is much heat, ; alſo there is therein a greater tenuity, which ſerves as *vehicles* thereto, into what place or part ſoever of the body they tend, the which the poyſons taken from the dead Creatures are defective of. Wherefore ſome of theſe kill a man in the ſpace of an hour, as the poyſon of Aſps, Baſilisks, and Toads; others not unleſs in two or three days ſpace, as of Water-Snakes; a Spider and Scorpion require more time to kill, yet all of them admitted but in the leaſt quantity, do in a ſhort ſpace cauſe great and deadly mutations in the body, as if they had breathed in a peſtiferous air, and with the like violence taint and change into their own nature all the members and bowels, by which theſe ſame members do in the time of perfect health change laudable meats into their nature and ſubſtance. The place whereas theſe poiſonous Creatures live, and the time, conduce to the perniciouſneſs of the poyſon; for ſuch as live in dry mountains and Sun-burnt places, kill more ſpeedily than ſuch as be in moiſt and mariſh grounds; alſo they are more hurtful in Winter than in Summer; and the poyſon is more deadly which proceeds from hungry, angry, and faſting Creatures, than that which comes from ſuch as are full and quiet; as alſo that which proceeds from young things, chiefly when as they are ſtimulated to Venery, is more powerful than that which comes from old and decrepit; from Females worſe than from Males; from ſuch as have fed upon other venemous things, rather than from ſuch as have abſtained from them, as from Snakes which have devoured Toads, Vipers which have fed upon Scorpions, Spiders and Caterpillers. Yet the reaſon of the efficacy of poyſons depends from their proper, that is, their ſubtil or groſs conſiſtence, and the greater or leſs aptneſs of the affected body to ſuffer. For hot men that have larger and more open veins and arteries, yield the poyſon freer paſſage to the heart: Therefore they which have more cold and ſtrait veſſels, are longer ere they die of the like poiſon; ſuch as are full, are not ſo ſoon harmed as thoſe that are faſting: for meats, beſides that by filling the veſſels, they give not the poyſon ſo free paſſage, they alſo ſtrengthen the heart by the multiplication of ſpirits, ſo that it more powerfully reſiſts pernicious venom. If the poyſon work by an occult and ſpecifick property, it cauſeth the Cure and Prognoſtick to be difficult, and then muſt we have recourſe to Antidotes, as theſe which have their whole ſubſtance reſiſt poyſons; but principally to Treacle, becauſe there enter into the Compoſition thereof Medicins which are hot, cold, moiſt, and dry: whence it is, that it retunds and withſtands all poyſons, chiefly ſuch

The bites of all wild Beaſts are virulent.

The bites of a red-haired man virulent

Contuſed wounds harder to heal than ſuch as are cut.

Why Treacle retunds the force of all ſimple poyſons.

as

as consist of a simple nature: such as these which come from venemous Creatures, Plants, and Minerals, and which are not prepared by the detestable Art of empoisoners.

CHAP. X.

What Cure must be used to the bitings and stingings of venemous Beasts.

CUre must speedily be used without any delay to the bites and stingings of venemous Beasts which may by all means disperse the poison, and keep it from entering into the body; for when the principal parts are possessed, it boots nothing to use Medicins afterwards. Therefore the Ancients have propounded a double Indication to lead us to the finding out of Medicins in such a case, to wit, the evacuation of the virulent and venenate humour, and the change or alteration of the same and the affected body. But seeing evacuation is of two sorts, to wit, Universal, which is by the inner parts; and Particular, which is by the outward parts: We must begin at the particular, by such to pick Medicins as are fit to draw out and retund the venom; for we must not always begin a Cure with general things, as some think, especially in external diseases, as Wounds, Fractures, Dislocations, Venemous Bites and Punctures. Wherefore hereto as speedily as you may, you shall apply remedies fit for the Bites and Punctures of venemous Beasts; as for example, the Wounds shall be presently washed with Urin, with Sea-water, *Aqua Vitæ*, or Wine, or Vinegar wherein old Treacle or Mustard shall be dissolved. Let such washing be performed very hot, and strongly chafed in, and then leave upon the Wound and round about it, linnen rags, or lint steeped in the same liquor. There be some who think it not fit to lay Treacle thereto, because as they say, it drives the poison in. But the authority of *Galen* convinceth that opinion, for he writeth that if the Treacle be applied to this kind of wounds before that the venom shall arrive at the noble parts, it much conduceth. Also reason confutes it, for Vipers flesh enters the composition of Treacle which attracts the venom by the similitude of substance, as the Load-stone draweth Iron, or Amber-straws. Moreover, The other simple Medicins which enter this composition, resolve and consume the virulency and venom, and being inwardly taken, it defendeth the heart and other noble parts, and corroborateth the spirits. Experience teacheth that Mithridate fitly given in the stead of Treacle worketh the like effect. The Medicins that are taken inwardly and applied outwardly for evacuation, must be of subtil parts, that they may quickly insinuate themselves into every part to retund the malignity of the poison; wherefore Garlick, Onions, Leeks, are very good in this case, for that they are vaporous; also *Scordium*, *Rue*, *Dictamnus*, the lesser Centaury, Hore-hound, Rocket, the milky juice of unripe figs, and the like, are good; there is a kind of wild Bugloss amongst all other Plants, which hath a singular force against venemous bites, whence it is termed *Echium* and *Viperium*, and that for two causes; the first is, because in the purple flowers that grow amongst the leaves, there is a resemblance to the head of a Viper or Adder. Another reason is, because it heals the biting of a Viper, not onely applied outwardly, but also helpeth such as are bitten being drunk in Wine, yea and will not suffer those that have lately drunk thereof to be bitten at all. Wild *Tyme* hath the like effect, though these oft-times agree with the poison in quality as in heat, yet do they help in discussing and resolving it; yet, as much as we may, we must labour to have evacuation and alteration together. It is most convenient, if the part affected will permit, to apply large Cupping-glasses with much flame and horns; also sucking is good, the mouth being first washed in Wine wherein some Treacle is dissolved, and with Oil, lest any thing should adhere thereto, for it will hinder it, if so be the mouth be no where ulcerated. It is good also to apply Horse-leeches, some wish to apply to the wound the fundaments of Hens or Turkies that lay Eggs, for that such are opener behind, first putting salt upon them that they may gape the wider, shutting their beaks and opening them now and then, lest they should be stifled, and ever and anon to substitute others in stead of such as die or are suffocated; for thus it is thought the poison is drawn forth, and passeth into the Bird by the fundament. There be others which had rather apply to the wound live Birds cut asunder in the midst, and so laid to the wound hot, for that they guess these resist poison by a natural discord. But certainly it is by their heat, whereby they do not onely digest Toads, Asps, Vipers, Scorpions, and other venemous things, but also wear asunder and sotten Sand, Stones, and most dry and stony seeds in their gizzards; wherefore we must think them very good to draw out the poison and dissipate it. But nothing is so forcible to disperse and retund the venom, as the impression of Cauteries, especially actual, for a hot iron works more effectually and speedily, and causeth an ulcer which will remain open a longer time. Wherefore to cause the speedier falling away of the Eschar, you shall scarifie it to the quick, and then plentifully anoint the place. For thus the poison will the sooner pass forth. But this must be done before the poison enters far into the body, for otherwise Cauteries will not onely do no good, but further torment the Patient, and weaken him to no purpose. Let drawing plasters be laid to the wound and neighbouring parts, made of *Galbanum*, Turpentine, black Pitch, and other gummy and resinous things. After the falling away of the Eschar *Basilicon* shall be applied, quickned with a little *Precipitate*, for it is very effectual in these cases, for that it draweth forth the virulent *sanies* out of the bottom of the wound, neither doth it suffer the wound to be closed speedily. To which purpose they put in a piece of sponge, or a root of Gentian or Hermodactyl, or some acrid Medicin, as *Ægyptiacum* or *Precipitate* mixed with the powder of Alum, or a caustick beaten to powder. But you must always observe this, that with your ointments you must always mix some Treacle or Mithridate, or the juice of *Hypericon*, or the like, which have power to attract and disperse the poison, and cleanse the ulcer; yet if too vehement heat shall cause such pain as is likely to bring a Gangrene by the dissipation of the spirits, then neglecting the cure of the proper disease for a time, we must labour to correct the symptom. But in this case you must observe this rule, that you let no bloud, give no purging Medicin nor Clyster,

A double indication in the cure of venemous bites.

Lotions fit for venemous bites.

Lib. de Theriac.

Treacle outwardly applied and inwardly taken good against venomous bites.

The force of *Echium*.

The efficacy of Cauteries against venemous bites.

The force of *Precipitate* against venemous wounds.

When hot things are not convenient for poisoned wounds.

Clyſter, nor Vomit, nor uſe no Bath, nor other thing that may procure ſweat, until three days be paſt after the bite or ſting. In the mean ſpace let the Patient ſhun all manner of labour, but chiefly Venery, leſt by cauſing an agitation of the humours, the poiſon get ſooner to the heart. Therefore then it is time to uſe univerſal evacuations, when as you ſhall ſuſpect that the poiſon is diffuſed over the veins and whole inner part of the body beſides. Before you ſhall give nothing, unleſs Medicins of Treacle and Mithridate, and the like things, which have a faculty to reſiſt poiſon, and ſtrengthen the whole body by their benign and vital vapour, although their ſubſtance go no further than the ſtomach. Thus Pills when they are ſwallowed, though they go no further than the ſtomach, yet do they draw matter out of the joints and head; and ſtrong Clyſters, though they paſs no further than the guts, yet by their quality diffuſed further with the vapour, they draw from the moſt diſtant parts; yet you muſt give an Antidote, not onely more powerful than the poiſon in quality, but alſo greater in quantity, that ſo it may the more eaſily overcome and expel the poiſon. Wherefore you muſt give it twice in a day, and continue it ſo long until you ſhall know that the ſtrength of the poiſon is weakned and overcome by the remiſſion and decay of the malign ſymptoms. Yet in the mean while you muſt not neglect the diſtemper cauſed in the part by the poiſon, but muſt rather correct it by the application of the remedies contrary to the diſtemper, as by cold things if great heat afflict the affected part and whole body; by hot things on the contrary, if it ſeem as cold as a ſtone, which oft-times happens. And let thus much ſuffice for the general cure of Poiſons: now will we come to their particular Cure.

Antidotes muſt be given in great quantities.

CHAP. XI.

Why Dogs ſooner become mad than other Creatures, and what be the ſigns thereof.

Dogs naturally ſubject to madneſs.

DOgs become mad ſooner than any other Creatures, becauſe naturally they enjoy that temper and condition of humours which hath an eaſie inclination to that kind of diſeaſe, and as it were a certain diſpoſition, becauſe they feed upon Carrion, and corrupt, putrid and ſtinking things, and lap Water of the like condition; beſides the trouble and vexation of loſing their Maſters makes them to run every way, painfully ſearching and ſmelling to every thing and neglecting their meat. An heating of the bloud enſues upon this pain, and by this heat it is turned into a melancholy, whence they become mad. But yet Dogs do not always become mad by means of heat, but alſo by occaſion of cold, that is, by contrary cauſes; for they fall into this diſeaſe not onely in the Dog-days, but alſo in the depth of Winter: For Dogs abound with melancholick humours, to wit, cold and dry. But ſuch humours as in the Summer through exceſs of heat, ſo in the depth of Winter by conſtipation and the ſuppreſſion of fuliginous excrements, they eaſily turn into melancholy. Hence follows a very burning and continual Fever, which cauſeth or bringeth with it a madneſs. Add hereto, that in the depth of Winter the heat which is contained within is redoubled, and in like manner as the ſcorching heat in Summer, it breeds and turns the humours into melancholy. Alſo Dogs become mad by contagion, as ſuch as are bitten by another mad Dog. A mad Dog hath ſparkling and fiery eyes, with a fixed look, cruel and aſquint, he carries his head heavily, hanging down towards the ground, and ſomewhat on one ſide, he gapes and thruſts forth his tongue, which is livid and blackiſh; and being ſhort breathed, caſts forth much filth at his noſe, and much foaming matter at his mouth; in his gate, as if he ſuſpected and feared all things, he keepeth no one or certain path, but runs one while to this ſide, another while to that, and ſtumbling like one that is drunk, he oft-times falleth down on the ground; he violently aſſails whatſoever he meets withall, whether it be Man, Tree, Wall, Dog, or any thing elſe; other Dogs ſhun and preſently ſent him afar off. But if another unawares chance to fall foul upon him, he yields himſelf to his mercy, fawns upon him, and privily labours to get from him, though he be the ſtronger and greater. He is unmindful of eating and drinking, he barks not, yet bites he all he meets, without any difference, not ſparing his Maſter, as who at this time he knows not from a ſtranger or enemy. For it is the property of Melancholy to diſturb the underſtanding, ſo that ſuch perſons as are melancholick, do not onely rage againſt, and uſe violence to their Friends and Parents, but alſo upon themſelves. But when as he ſees Water, he trembles and ſhakes, and his hairs ſtand up on end.

Dogs become mad, not onely in the heat of Summer, but alſo in the depth of Winter.

Why melancholick perſons hurt themſelves.

CHAP. XII.

By what ſigns we may know a man is bitten by a mad Dog.

The bite of a mad Dog not very painful at the firſt.

IT is not ſo eaſie at the firſt to know that a man is bitten with a mad Dog, and principally for this reaſon, becauſe the wound made by his teeth cauſeth no more pain than other wounds uſually do; contrary to the wounds made by the ſting or bite of other poiſonous Creatures, as thoſe which preſently after they are inflicted, cauſe ſharp pain, great heat, ſwelling, and abundance of other malign accidents according to the nature of the poiſon; but the malignity of the bite of a mad Dog appears not before that the venom ſhall invade the noble parts. Yet when you are ſuſpicious of ſuch a wound, you may acquire a certain knowledge and experience thereof by putting a piece of bread into the quitture that comes from the wound. For if a hungry Dog neglect, yea more fly from it, and dare not ſo much as ſmell thereto, it is thought to be a certain ſign that the wound was inflicted by a mad Dog. Others add, That if any give this piece of bread to hens, that they will die the ſame day they have eaten it; yet this latter I making experiment thereof, failed; for devouring this virulent bread, they became not a jot the worſe. Wherefore I think the former ſign to be the more certain, for Dogs have a wonderful and ſure ſmelling faculty, whereby they eaſily ſcent and perceive the malignity of the like Creature. But when as

Signs of the bite of a mad Dog.

the

the raging virulency hath invaded the noble parts, then the Patients, becoming silent and sorrowful, think of many things, and at the beginning make a noise with their teeth; they make no answer to the purpose, they are more testy than ordinary, and in their sleeps they are troubled with dreams and strange phantasies, and fearful vitions; and lastly, they become afraid of the water. But after that the poison hath fixed it self into the substance of the noble parts, then all their faculties are disturbed, all the light of their memory, senses, reason, and judgment is extinguished. Wherefore becoming stark mad, they know not such as stand by them, nor their friends, no nor themselves, falling upon such as they meet withall, and themselves with their teeth and nails and feet. Often twitchings like Convultions do suddenly rise in their limbs; I judge them occasioned by extraordinary drineſs, which hath as it were wholly drunk up all the humidity of the nervous parts; there is a great drineſs of the mouth with intolerable thirst, yet without any desire of drink, because the mind being troubled, they become unmindful and negligent of such things as concern them, and are needful for them; the eyes look fiery and red, and all the face is of the same colour; they still think of Dogs, and seem to see them, yea and desire to bark and bite just after the manner of Dogs. I conjecture that the virulent humour hath changed all the humours and the whole body into the like nature, so that they think themselves also Dogs; whence their voice becomes hoarse by much endeavouring to bark, having forgot all decency, like impudent Dogs, to the great horrour of the beholders. For their voice grows hoarse by reason of the great drineſs of the *aspera arteria*; they shun the light, as that which is enemy to melancholy, wherewith the whole substance of the Brain is repleniſhed; on the contrary they desire darkneſs, as that which is like and friendly to them. But they are afraid of the water (though good to mitigate their great distemper of heat and drineſs) and they fly from Looking-glasses, because they imagine they see Dogs in them, whereof they are much afraid, by reason whereof they shun the Water and all polite and clear bodies which may supply the use of a Looking-glass; so that they throw themselves on the ground, as if they would hide themselves therein, lest they should be bitten again: for they affirm that he which is bitten by a mad Dog, always hath a Dog in his mind, and so remains fixed in that sad cogitation. Wherefore thinking that he sees him in the Water, he trembles for fear, and therefore shuns the Water. Others write that the body by madneſs becometh wondrous dry, wherefore they hate the Water, as that which is contrary thereto, being absolutely the moistest element; and so they say that this is the reason of their fearing the Water. *Ruffus* writes that madneſs is a kind of melancholy, and that fear is the proper symptom thereof, according to *Hippocrates*; wherefore this or that kind of melancholy begets a fear of these or these things, but chiefly of bright things, such as Looking-glasses and Water, by reason that melancholy persons seek darkneſs and solitarineſs, by reason of the black corruption of the humour wherewith they abound. They fall into cold sweats, a foamy, stinking, and greenish matter flows from the ulcer, by reason of the heat of the antecedent cause and ulcerated part. The urin most commonly appears watery, by reason that the strainers, as it were of the Kidnies, are straitned by the heat and drineſs of the venom. Yet sometimes also it appears more thick and black, as when Nature powerfully using the expulsive faculty, attempts to drive forth by urin the melancholy humour, the seat of the venom. Also sometimes it is wholly suppreſt, being either incrassated by hot drineſs, or else the mind being carried otherways and forgetful, of its own duty, until at length the Patients, vexed by the cruelty of so many symptoms, and overcome by the bitterneſs of pain, die frantick, by reason that Medicins have not been speedily and fitly applied. For few of those who have used remedies in time, have perished of this disease.

Signs by which you may gather that the noble parts are tainted.

Why men becoming mad, bark like dogs.

Why they shun the light.

Why they are afraid of the Water.

Aphor. 25. *sect.* 6

The bite of a mad dog taken in hand in time, is for the most part curable.

CHAP. XIII.

Prognosticks.

WE cannot so easily shun the danger we are incident to by mad Dogs, as that of other Beasts, by reason he is a domestick creature, and housed under the same roof with us. The virulency that resides in his foam or slaver is hot and dry, malign venenate and contagious, so that it causeth a distemper like it self, in the body whereto it shall apply it self and spread it self over the whole body by the arteries; for it doth not only hurt when as it is taken in by a bite or puncture, but even applied to the skin, unless it be forthwith washed away with salt water or urin. Neither doth this venom hurt equally, or at all times alike, for it harms more or less, according to the inclination of the air to heat or cold, the depth of the wound, the strength of the Patients Body, and the ill humours thereof, and their disposition to putrefaction, the freedom and largeneſs of the passages. Now malign symptoms happen sooner or later, as in some about the fortieth day, in others about six moneths, and in others a year after. There be some who thereupon are troubled with the falling sickneſs, and at length grow mad; such as fall into a fear of the Water, never recover. Yet *Avicen* thinks their case is not desperate, if as yet they can know their face in a Glass; for hence you may gather, that all the animal faculties are not yet overthrown, but that they stand in need of strong purgations, as we shall shew hereafter. *Aetius* tells that there was a certain Philosopher, who taken with this disease, and a fear of Water, when as he descended with a great courage unto the Bath, and in the Water beholding the shape of the Dog that bit him, he made a stand, but ashamed thereof, he forthwith cried out, *Quid Cani cum Balneo? i. e.* What hath a Dog to do with a Bath? which words being uttered, he threw himself forcibly into the Bath, and fearlesly drank of the Water thereof, and so was freed from his disease together with his erroneous opinion. It is a deadly sign to tumble themselves on the ground to have an hoarse voice, for that is an argument that the weazon is become rough, by reason of too excessive

The venom of a mad dog applied outwardly onely, may cause madneſs.

Whether the *Hydrophobia*, or fear of Water be incurable.

An History.

drineſs. Finally, The principal parts being poſſeſſed, there is no recovery or life to be hoped for. Men may well fall mad, though they be not bit by a mad dog. For as the humours are often inflamed of themſelves, and cauſe a Cancer or Leproſie, ſo do they alſo Madneſs in melancholick perſons. The bites of Vipers and other venemous creatures cauſe not like ſymptoms to theſe that come by the biting of a mad Dog, becauſe they die before ſuch can come forth or ſhew themſelves. Great wounds made by mad Dogs are not equally ſo dangerous as little, for from the former great plenty of venemous matter flows out, but in the latter it is almoſt all kept in.

CHAP. XIV.

What cure muſt be uſed to ſuch as are bitten by a mad Dog.

An Hiſtory. THis caſe alſo requires ſpeedy remedies; for ſuch things are in vain which come long after the hurt. The Lawyer *Baldus* experienced this to his great harm, for being by chance lightly bit in the lip by a little Dog wherewith he was delighted, not knowing that he was mad, and neglecting the wound by reaſon of the ſmalneſs thereof, after ſome four moneths ſpace he died mad, having then in vain aſſayed all manner of Medicins. Wherefore obſerving theſe things both for evacuation, as alſo for alteration, which we have formerly mentioned in the general Cure of Wounds inflicted by the bite or ſting of venemous Creatures, and by all the means there ſpecified, we muſt draw forth the venom, and if the wound be large, then ſuffer it to bleed long and much, for ſo ſome part of the poiſon will be exhauſted; if it be not great it ſhall be enlarged by ſcarification, or an occult cautery, neither ſhall it be healed or cloſed up at the ſoo-

The force of Sorrel. neſt till forty days be paſſed. Sorrel beaten and applied to the wound, and the decoction thereof taken inwardly, is very effectual in this caſe, as *Aetius* affirms. To the ſame purpoſe you may with good ſucceſs make a lotion and friction with Muſtard diſſolved in Urin or Vinegar, leaving upon the wound a double cloth moiſtned in the ſame decoction: laſtly, all acrid, biting, and very attractive Medicins are convenient in this caſe. Wherefore ſome apply Rocket boiled and beaten with Butter and Salt, others take the flower of *Orobus*, and temper it with Honey, Salt, and Vinegar, and apply it hot. Horſe-dung boiled in ſharp Vinegar, or Brimſtone beaten to powder, and tempered with ones ſpittle, is good. Alſo black pitch melted with ſome ſalt, and a little *Euphorbium* mixed therewith, and ſo applied, is good. Some write that the hairs of the Dog whoſe bite cauſed the madneſs, applied by themſelves, by their ſympathy or ſimilitude of ſubſtance, draw the venom from within outwards; for ſo a Scorpion beaten and applied to the place whereas it ſtung, by drawing out the poiſon that it ſent in, reſtores the Patient to health, both theſe by often experience are affirmed to have certain event. Others chew unground Wheat, and lay it up-

The force of Docks. the wound, other roaſt Beans under hot Embers, then huſk them and cleave them, and ſo apply them. Alſo the wound may be wholſomly waſhed and fomented with a decoction of Docks, and then the herb beaten may be applied thereto; alſo the Patient may drink the decoction; and by this one remedy *Aetius* affirms that he hath recovered divers; for thus it moves Urin plentifully, which is thought much to conduce to the cure of this diſeaſe. There be ſome who apply the leaves of Betony and Nettles beaten with common Salt; others make a Medicin to the ſame purpoſe, and after the ſame manner, of an Onion, the leaves of Rue, and Salt. Yet the reſt are exceeded by Treacle diſſolved in *Aqua Vitæ* or ſtrong Wine, and rubbed hard upon the part, ſo that bloud may follow, laying upon the wound when you have wiped it, cloths dipped in the ſame Medicin;

An Hiſtory. then preſently apply Garlick or Onions beaten with common Salt and Turpentine. By this onely remedy I freed one of the daughters of *Madamoiſella de Gron* from the ſymptoms of madneſs, and healed the wound, when as a mad Dog had bit her grievouſly in the calf of the right leg. Alſo it is good preſently to eat Garlick with bread, and then to drink after it a draught of good Wine, for Garlick by its ſpirituous heat will defend the noble parts from poiſon. There be ſome who wiſh to eat the roaſted liver of the Dog that hurt them, or elſe the liver of a Goat, of which remedies, as yet I have had no experience. Others preſcribe a dram of the ſeeds of *Agnus caſtus* to be drunk with Wine and Butter. Others the powder of River-Crabs burnt and drunk in Wine. Or, ℞ *Rad. gent.* ʒ ij. *aſtacorum fluviat. in fumo combuſt. & in pollinem redact.* ʒ iij. *terræ ſigill.* ʒ ß. *miſce.* Give ʒ j. of this ſame Powder in the decoction of River-Crabs, and let them drink thereof oft, at ſundry times.

Leaping into the Sea no certain remedy againſt Madneſs. Many have caſt themſelves into the Sea, neither have they thence had any help againſt Madneſs, as *Ferrand Pozet* the Cardinal teſtifieth in his Book of Poiſons; wherefore you muſt not rely upon that remedy, but rather you muſt have recourſe to ſuch things as are ſet in the Books of Phyſicians, and approved by certain and manifold experience. But ſeeing that no poiſon can kill, unleſs it be taken or admitted into the body, we muſt not fear any harm by ſprinkling our bodies with the *ſanies* of a mad Dog, Viper, Toad, or any other ſuch like venemous Creature, if ſo be that it be preſently wiped or waſhed clean away.

CHAP. XV.

What Cure muſt be uſed to ſuch as fear the Water, but yet are able to know themſelves in a Glaſs.

The force of Antimony againſt madneſs. SUch as have not their animal faculty as yet overcome by the malignity of the raging venom, muſt have ſtrong purgations given them. Wherefore if in any caſe Antimony be uſeful, then is it in this, as that which cauſeth ſweats, looſeth the belly, and procures vomiting: For it is a part of extreme and dangerous madneſs to hope to overcome the cruel malignity of this poiſon already admitted into the bowels, by gentle purging Medicins. Aſſuredly, Such and ſo great danger is never overcome without danger. Baths alſo conduce, which may diſperſe and draw forth the

poiſon

poiſon by cauſing ſweats. Alſo many and frequent Treacle-potions are good to retund the venom, and ſtrengthen the bowels; alſo it will be fitting to give them Water and all other liquid things, which they ſo much abhor, in a cup with a cover. Always let ſuch as are poiſoned, or ſtung, or bitten by a mad Dog or other venemous Beaſt, keep themſelves in ſome warm and light place, that the poiſon which by coldneſs is forced in, may be the readilier drawn out by the means of heat, and the ſpirits be recreated by the brightneſs of the air and therefore move from the center to the circumference of the body, and let the room be perfumed with ſweet things. To eat very hot and ſalt things preſently at the beginning, as Onions, Leeks, all ſpiced meats, and ſtrong Wine not allayed, ſeem not to be beſides reaſon; becauſe ſuch things by their ſpirituous heat hinder the diffuſion of the poiſon over the body, and ſtrengthen the filled entrails. There be ſome alſo that would have them to feed upon groſs and viſcous meats, which by obſtructing the veſſels, may hinder the paſſage of the poiſon to the heart and other parts; and by the ſame reaſon it will be better to fill themſelves with meat to ſatiety than otherwiſe, becauſe the malignity of humours is increaſed by hunger, than which nothing can be more harmful to venemous wounds. Yet within a ſhort while after, as within five or ſix days they muſt return to a mediocrity, and uſe all things temperate, boiled meats rather than roaſted, and that in a decoction of opening things, ſo to move urin. Laſtly, They muſt keep ſuch a diet as melancholick perſons ought to do; neither ſhall they let bloud, leſt ſo the poiſon ſhould be further drawn into the veins; but it is good that the Patients body be ſoluble from the very firſt. Let their drink be Wine indifferently allayed with Water, *Oxymel ſimplex*, or the Syrup of the juice of Citron with boiled Water; or elſe this following Julip: ℞ *Succi limonum, & malorum citri, an.* ℥ ij. *ſuc. gran. acid.* ℥ ij. *aquæ acetoſæ, min. & roſ. an.* ℥ j. *aq. font. coq. quantum ſufficit, fiat Julep. ut artis eſt.* Sleep is to be avoided until the force of the poiſon be abated, for by ſleep the humours flow back into the bowels. All things that reſiſt poiſon muſt be given any way whatſoever, as Limons, Oranges, Angelica-roots, Gentian, Tormentil, Burnet, Vervain, *Carduus Benedictus*, Borage, Bugloſs, and the like. Let all things that are afterwards ſet before the Patient, be meats of good juice, ſuch as are Veal, Kid, Mutton, Partridge, Pullets, Capons, and the like.

Why ſleep is hurtful to ſuch as are bitten by a mad dog, and all ſuch as are poiſoned.

CHAP. XVI.

Of the biting of a Viper or Adder, and the ſymptoms and cure thereof.

THe remedies that were formerly mentioned againſt the bitings of mad Dogs, the ſame may be uſed againſt all venemous bites and ſtings, yet nevertheleſs each poiſon hath his peculiar antidote. Vipers or Adders (as we vulgarly term them) have in their gums, or the ſpaces between their teeth, little bladders filled with a virulent *ſanies*, which is preſſed out into the part that they bite with their teeth. There forthwith ariſeth a pricking pain, the part at the firſt is much ſwollen, and then the whole body, unleſs it be hindred: groſs and bloudy filth ſweats out of the wound, little bliſters ariſe round about it, as if it were burnt, the wound gnaws, and as it were feeds upon the fleſh, great inflammation poſſeſſeth the Liver and the Guts, and the whole body becomes very dry, becoming of a pale or yellowiſh colour, with thirſt unquenchable; the belly is griped by fits, a cholerick vomiting moleſteth them, the Stomach is troubled with a hicketing, the Patients are taken with often ſwounings, with cold ſweat, the fore-runner of death, unleſs you provide by fit Medicins for the noble parts, before the poiſon ſhall invade them. *Matthiolus* tells, that he ſaw a Country man, who as he was mowing a Meadow, by chance cut an Adder in two with his Sithe, which when he thought it was dead, he took the one half, whereon the head remained, without any fear in his hand, but the enraged creature turning about her head, cruelly bit him by one of his fingers, which finger, as men uſually do (eſpecially when as they think of no ſuch thing) he put into his mouth, and ſucked out the bloud and poiſon, and preſently fell down dead.

The bites of Vipers how virulent.

The ſymptom

An Hiſtory.

When as *Charles* the ninth was at *Montpelier*, I went into the ſhop of one *Farges* an Apothecary, who then made a ſolemn diſpenſation of Treacle, where not ſatisfying my ſelf with the looking upon the Vipers that were there in a glaſs, ready for the compoſition, I thought to take one of them in my hands, but whileſt that I too curiouſly and ſecurely handled her teeth which were in her upper jaw, covered with a skin, as it were a caſe to keep the poiſon in, the beaſt catched hold of the very end of my fore-finger, and bit me in the ſpace between the nail and the fleſh; whence preſently there aroſe great pain, both by reaſon of the part endued with moſt exquiſit ſenſe, as alſo by the malignity of the poiſon: forthwith I exceeding ſtraightly bound my finger above the wound, that ſo I might preſs forth the bloud and poiſon, leſt they ſhould diffuſe themſelves further over the body. I diſſolved old Treacle in *Aqua vitæ*, wherein I dipped and moiſtned Cotton, and ſo put it to the wound, and within a few days I thorowly recovered by this onely Medicin. You may uſe in ſtead of Treacle, Mithridate and ſundry other things, which by reaſon of their heat are powerful drawers, as a Quill roaſted in hot Embers, Garlick and Leeks beaten and applied, Barley-flour tempered with Vinegar, Honey, and Goats-dung, and ſo applied like a pultis. Some think it ſufficient forthwith to waſh and foment the wound with Vinegar, Salt, and a little Honey. *Galen* writes, that the poiſon inflicted by the bite of a Viper, may be drawn forth by the applying to the wound the head of a Viper, but other-ſome apply the whole Viper beaten to maſh.

An Hiſtory.

Remedies for the bite of a Viper.

Lib. de Theriac.

CHAP. XVII.

Of the Serpent called Hæmorrhous.

The *Hæmorrhous* why ſo called.

THe Serpent *Hæmorrhous* is ſo called, becauſe by biting he cauſeth bloud to drop out of all the paſſages of the wounded body; he is of a ſmall body, of the bigneſs of a Viper, with eyes burning with a certain fiery brightneſs, and a moſt beautiful skin. The back of him (as *Avicen* writes) is ſpotted with many black ſpots, his neck little, and his tail very ſmall: the part which he bites forthwith grows blackiſh, by reaſon of the extinction of the native heat, which is extinguiſhed by ſuch poiſon which is contrary thereto in its whole ſubſtance. Then follows a pain of the ſtomach and heart, theſe parts being touched with the peſtiferous quality of the poiſon. Theſe pains are ſeconded by vomiting, the orifice of the ventricle being relaxed by a *Diarrhœa*, the retentive faculty of all the parts of the belly being weakned, and the veins which are ſpread through the guts, not being able to retain the bloud contained in them. For the bloud is ſeen to flow out, as in ſtreams, from the Noſe, Mouth, Ears, Fundament, Privities, corners of the Eyes, roots of the Nails, and Gums, which putrefie, the Teeth falling out of them. Moreover there happens a difficulty of breathing, and ſtoppage of the urin, with a deadly convulſion.

Wonderful bleedings.

The Cure is forthwith to ſcarifie and burn the bitten part, or elſe to cut it quite off, if that it may be done without danger of life, and then to uſe powerfully drawing Antidotes.

The Figure of the Serpent Hæmorrhous.

CHAP. XVIII.

Of the Serpent called Seps.

The reaſon of the name, and deſcription of the *Seps*.

THe Serpent *Seps* is ſo called, becauſe it cauſeth the part which it bites, forthwith to putrefie by reaſon of the cruel malignity of its poiſon. It is not much unlike the *Hæmorrhous*, but that it curls or twines up the tail in divers circles. *Pauſanias* writes that this Serpent is of an aſh-colour, a broad head, ſmall neck, big belly, writhen tail, and as he goes he runs aſide like a Crab; but his skin is variegated and ſpotted with ſeveral colours, like to Tapiſtry. By the cruelty of his cauſtick and putrefying venom he burns the part which he hath bit, with moſt bitter pain; he cauſeth the ſhedding of the hairs, and as *Aetius* addeth, the wound at the firſt caſteth forth manifeſt bloud, but within a little while after, ſtinking filth. The putrefied affected parts wax white, and the body all over becomes of the colour of that ſcurff which is termed *Alphos*, ſo that by the wickedneſs of this putrefactive poiſon, not onely the ſpirits are reſolved, but alſo the whole body conſumed, as by fire, a peſtilent carbuncle, and other putrid tumors, ariſing from an hot and humid or ſuffocating conſtitution of the air. Now for the remedies, they muſt be ſuch as are formerly preſcribed againſt the bitings of a Viper.

The ſymptoms.

The Figure of the Serpent Seps.



CHAP. XIX.

Of the Baſilisk, or Cockatrice.

The efficacy of the poiſon of the Baſilisk

THe Baſilisk far exceeds all kinds of Serpents in the curſtneſs of its poiſon. Therefore it is affirmed by *Nicander*, that into what place ſoever he comes, other venemous creatures do forthwith flie thence, for that none of them can ſo much as endure his hiſſing; for he is thought to kill all things even with this, and not with his biting and touch onely; beſides, if any of them

them haſten to get any meat or drink, and perceive that the Baſilisk is not far from thence, he flies back, and neglects the getting of nouriſhment neceſſary for life. *Galen* writes, that the Baſilisk is a yellowiſh Serpent, with a ſharp head, and three riſings diſtinguiſhed with white ſpots, and riſing up in form of a Crown, by reaſon whereof he is ſtiled the King of Serpents. Certainly the violence of his poiſon in killing men is ſo great, that he is therefore thought to kill men and other creatures by his ſight only. *Solinus* affirms, that the body of a Baſilisk hath wondrous faculties: Wherefore the Inhabitants of *Pergamum*, in ancient times gave a mighty price for one to hang upon the Joiſts of the Temple of *Apollo*, ſo to drive away the Spiders and Birds, leſt they ſhould weave their webs, or the other build their neſts in that ſacred place. Verily no ravenous creature will touch their carkaſs; but if conſtrained by hunger, they do touch it, then they forthwith fall down dead in the ſame place: and this happens not onely by eating their body, but alſo by devouring of the bodies of ſuch Beaſts as are killed by their bitings. They kill the Trees and Shrubs by which they paſs, not onely by their touch, but even with their breath. Among the Weſtern Æthiopians is the Fountain *Nigris*, near which there is a Serpent called *Catablepas*, ſmall in body, and ſlow, having a great head, which it ſcarce can carry, but that it lies always upon the ground, otherwiſe it would kill abundance of people, for it forthwith kills all that ſees the eyes thereof, the Baſilisk hath the ſame force; he is bred in the Province of *Cyrene*, of the length of ſome twelve fingers, with a white ſpot in his head, reſembling a Crown; he chaſeth away all ſorts of Serpents with his hiſs. Weaſels are the deſtruction of ſuch monſters: thus it pleaſed Nature that nothing ſhould be without its equal; they aſſail them in their dens, being eaſily known by the barrenneſs or conſumption of the ſoil. Theſe kill them alſo by their ſent, and they die, and the ſight of Nature is ended. Thus Nature to the magnanimous Lion, leſt there ſhould be nothing which he might fear, hath oppoſed the weak creature the Cock, by whoſe crowing onely he is terrified and put to flight. *Eraſiſtratus* writes, that a golden yellowneſs affects the bitten part of ſuch as are hurt by a Baſilisk, but a blackneſs and tumour poſſeſſeth the reſt of the body, all the fleſh of the muſcles within a while after falling away by piece-meal. An Antidote againſt this muſt be made of a dram of *Caſtoreum*, diſſolved in wine and drunken, or in the juice of poppy. But *Aetius* thinks it ſuperfluous to write remedies againſt the Baſilisk, when as the ſight and hearing onely kills ſuch as either ſee or hear her.

Lib. de Theriac.

Why the Baſilisk is thought to kill by his onely ſight.

Plin. lib. 8. c. 21.

The *Catablepas*.

Nothing in Nature without its equal.

Symptoms.

Cure.

The Figure of a Baſilisk.

CHAP. XX.

Of the Salamander.

THe Salamander kills not onely ſuch as it bites, by making a venemous impreſſion, but it alſo infects the Fruits and Herbs over which it creeps, with a ſpittle or groſs moiſture which ſweats out of all the body, to the great danger of the health and life of ſuch as eat theſe things at unawares: wherefore it need not ſeem ſtrange, which is received by ſome late Writers, that ſome Families have all died by drinking Water out of the Pits whereinto a Salamander by accident was fallen. For if it ſhall creep upon a Tree, it infects all the Fruit with the qualities of cold and moiſt poiſon, wherein it yields not to Aconite.

The malignity of a Salamander.

The temper of her.

Aetius writes, that ſuch as are infected with the poiſon of a Salamander, certain parts of their body grow livid, ſo that they fall away often, being putrefied. At the firſt there appear white ſpots, over the body, then red, afterwards black with putrefaction; and the falling away of the hairs. The Cure is to procure vomit, to looſe the belly with a Clyſter, and to give them Treacle and Mithridate in potions. *Avicen* preſcribes the ſame things againſt this kind of poiſon as againſt *Opium*, by reaſon of the cold nature of them both; the proper Antidote is Turpentine, *Styrax*, Nettle-ſeeds, and Cypreſs-leaves. *Dioſcorides* writes, that the Salamander is a kind of Lizard, dull, variegated, and which is falſly reputed, not to be burnt by fire. But *Pliny* ſaith ſhe is ſo cold, that ſhe extinguiſheth the fire by her touch onely, being laid upon hot Coals. On the contrary, *Matthiolus* ſaith, that caſt into a great flame they are quickly conſumed. It is eaſie out of *Aetius* to reconcile theſe diſagreeing opinions. This creature ſaith he, paſſeth through a burning flame and is not hurt, the flame dividing it ſelf, and giving her way, but if ſhe continue any time in the fire, the cold humour being conſumed in her, ſhe is burnt. Now the Salamander is black, variegated with yellow ſpots Star-faſhion.

Symptoms.

The Cure.

Lib. 2. cap. 54.

How a Salamander may be ſaid to live in the fire.

The

The Figure of a Salamander.

CHAP. XXI.

Of the Torpedo.

The craft of the *Torpedo*.

THe *Torpedo* hath his name from the effect, by reaſon that by his touch and power the members become torpid and numb. In muddy ſhores it lives upon fiſh, which ſhe catcheth by craft. For lying in the mud, ſhe ſo ſtupefies thoſe that are nigh her, that ſhe eaſily preys upon them. She hath the ſame power over men, for ſhe ſends a numbneſs not onely into the arm of the Fiſher-man, but alſo over all his body, although his Fiſhers Pole be between them.

His ſtupefying force.

The Effigies of a Torpedo.

CHAP. XXII.

Of the bitings of Aſps.

Symptoms.

THe wound which is made by an Aſp is very ſmall, as if a needle were thruſt into the part, and without any ſwelling. Theſe ſymptoms follow upon her bite, ſudden darkneſs clouds their eyes, much agitation in all their bodies, but gentle notwithſtanding; a moderate pain of the ſtomach troubles them, their fore-heads are continually troubled with convulſive twitchings, their cheeks tremble, and their eye-lids fall gently to reſt and ſleep; the bloud which flows from the wound is little, but black; death no longer deferred then the third part of a day, will take them away by convulſions, unleſs you make reſiſtance with fitting remedies. The male Aſp makes two wounds, the female four, as it alſo happens in the bitings of Vipers. Now for that the poiſon of Aſps congeals the bloud in the veins and arteries, therefore you muſt uſe againſt it ſuch things as are hot and ſubtil of parts, as Mithridate or Treacle diſſolved in *Aqua Vitæ*, and the ſame poured into the wound; the Patient muſt be warmed by baths, frictions, walking and the like. When as the hurt part becometh purple, black, or green, it is a ſign that the native heat is extinct and ſuffocated by the malignity of the venom. Therefore then it is beſt to amputate the member, if the Patient be able to endure it, and there be nothing which may hinder. *Vigo* writes that he ſaw a Mountebank at *Florence*, who that he might ſell the more of his Antidotes, and at the better rate, let an Aſp to bite him by the finger, but he died thereof ſome four hours after. To the ſame purpoſe you may read *Matthiolus*, whereas he writes that thoſe Impoſtors or Mountebanks to cozen the better, and deceive the people uſe to hunt and take Vipers and Aſps long after the Spring, that is, then when as they have caſt forth their moſt deadly poiſon; then they feed them meats formerly unuſual to them, ſo that by long keeping and care, and at length they bring it to paſs, that they put off a great part of their venemous Nature; neither being thus ſatisfied, they make them oftentimes to bite upon pieces of fleſh, that ſo they may caſt forth into them their venom which is contained in the membrane between their teeth and gums. Laſtly, they force them to bite, lick, and ſwallow down an aſtringent medicin, which they compoſe and carry about for the ſame purpoſe, that ſo they may obſtruct the paſſages by which the venom uſed to flow out, for thus at length their bites will be harmleſs, or without great danger. This therefore is their Art, that ſo they may ſell their counterfeit Treacle to the people at a high rate, as that which is a moſt ſafe remedy againſt all poiſonous bites. *Chriſtopher Andrew* in his Book called *Oicoiatria*, writes, that the Iſlands of *Spain* are every where full and ſtored with Serpents, Aſps, and all ſorts of venemous Beaſts, againſt whoſe bites they never obſerved or found any benefit in Treacle. But the efficacy of the following Antidote is ſo certain and excellent, and approved by ſo manifold experience, that in the confidence thereof, they will not be afroid to let themſelves be bitten by an Aſp. Now this Medicin is compoſed of the leaves of Mullet, Avens, and red Stock-gillyflowers in like quantity, which they boil in ſharp

Curing.

An Hiſtory.

By what means Aſps may be made leſs hurtful. *Gal. lib. de Ther. ad Piſonem.*

Againſt the bites of what Serpents Treacle doth no good.

A certain remedy againſt the biting of Aſps.

ſharp Vinegar and the Urin of a ſound man, and therewith foment the wounded part. Yet if he have not taken nor uſed any thing of a good while after the wound, it will be better and more certain, if the Patient drink three ounces of this decoction faſting two hours before meat.

CHAP. XXIII.

Of the biting of a Snake.

An Hiſtory. I Have thought good in a true Hiſtory to deliver the virulent malignity of the bite of a Snake, and the remedies thereof. When as King *Charles* the nineth was at *Moulins*, Mouſieur *le Feure* the Kings Phyſician and I were called to cure the Cook of the Lady of *Caſtelphers*, who gathering Hops in a hedge to make a Sallet, was bit on the hand by a Snake that there lay hid, he putting his hand to his mouth, ſucked the wound to eaſe the pain by ſucking forth the venom; but his Tongue forthwith ſwelled ſo big, that he could not ſpeak his mind: beſides, his whole arm, even to his ſhoulder, was in like ſort much ſwelled, his pain was ſo vehement, that it hath made him ſwoun twice in my preſence, his face was wan and livid like to a dead body; and though I deſpaired of his recovery, yet not ſuffering him to be quite forſaken, I waſhed his mouth with Treacle diſſolved in white Wine, and gave him ſome thereof to drink, adding thereto ſome *Aqua Vitæ*. I opened his ſwollen arm with many and deep ſcarifications, eſpecially in the place where he was hurt I ſuffered the bloud which was wholly ſerous and ſanious, to flow more plentifully, I waſhed the wounds with Treacle and Mithridate diſſolved in *Aqua Vitæ*, and then I put him exceeding warm in bed, procuring ſweat, and making him to lie awake, leſt ſleep ſhould draw the poiſon inwards to the entrails. I by theſe means ſo far prevailed, that on the day after he was freed from all his malign ſymptoms. Therefore I judged it onely remained for a perfect cure, that the wound ſhould be long kept open and waſhed with Treacle; neither was I deceived, for within a few days he was perfectly recovered. The Cure.

CHAP. XXIV.

Of the bitings of Toads.

THough Toads want teeth, yet with their hard and rough gums they ſo ſtraitly preſs or pinch the part which they ſhall take hold on, that they will force their poiſon thereinto, and ſo over the whole body by the pores of the preſſed part. Moreover they caſt forth their venom by urin, ſpittle, and vomit upon herbs, but chiefly upon Straw-berries, the which they are reported greatly to affect. Hence many ſuddenly and ignorantly catch their deaths. The bites of Toads how harmful.

An Hiſtory. I heard from a man of very good credit, that there were two Merchants not far from the City *Tholouſe*, who whileſt dinner was providing, walked into the Garden that belonged to the Inn, where they gathered ſome Sage leaves, and unwaſhed as they were, put them in their Wine. They had not as yet dined, when being taken with a ſudden *Vertigo*, the whole Inn ſeemed to run round, then loſing their ſight, they fell into a ſwoun, intermixed now and then with convulſions. But they ſtammered with their lips and tongues becoming black; a froward and horrid look, with continual vomiting and a cold ſweat, the fore-runner of death, which preſently ſeized upon them, their bodies becoming exceedingly much ſwollen. But the Juſtices of the place ſuſpecting that they were poiſoned, made the Inn-keeper and the Gueſts to be apprehended; being examined they all conſtantly and with one voice, anſwered, That the dead parties ate of the ſame meat and drink which the reſt did, but onely they put Sage into their Wine. A Phyſician was asked the queſtion whether Sage might be poiſoned? he anſwered it might: but to come to the purpoſe, it muſt appear whether any venemous Creature hath poiſoned the Plant with her ſpittle or venemous ſanies. This which was lightly pronounced, and onely by conjecture, was by the eye found to be true. For at the root thereof there was found a hole in the ground full of Toads, who got out by putting in of warm Water, made it credible that the Plant was poiſoned by their ſpittle and urin, whereby you may underſtand how unwiſely they do, who devour herbs and fruits newly gathered without waſhing. Alſo we muſt take heed leſt falling aſleep in the fields, we lie not near the holes which Toads or other venemous beaſts of the ſame nature, have made their habitation. For thence a venemous or deadly air may be drawn into the Lungs. For the ſame cauſe we muſt abſtain from eating of Frogs in the Moneth of *May*, becauſe then they engender with Toads. Oxen in feeding ſometimes lick up ſmall Toads together with the Graſs, which preſently will breed their great harm, for thereupon the Oxen ſwell ſo big, they often burſt withall. Neither is the venom of Toads deadly onely being taken inwardly, but even ſprinkled upon the skin, unleſs they forthwith wipe the place, and waſh it with urin, water and ſalt. Such as are poiſoned by a Toad turn yellow, ſwell over all their bodies, are taken with an Aſthmatick difficulty of breathing, a *Vertigo*, Convulſion, Swouning, and laſtly by death it ſelf. Theſe ſo horrid ſymptoms are judged inherent in the poiſon of Toads, not onely by reaſon of the elementary qualities thereof, coldneſs and moiſture, which are chiefly predominant therein; but much rather by the occult property which is apt to putrefie the humours of that body whereto it ſhall happen. Therefore it will be convenient to procure vomit, eſpecially if the poiſon be taken by the mouth, to give Clyſters, and to weaken the ſtrength of the poiſon by hot and attenuating Antidotes, as Treacle and Mithridate diſſolved in good Wine; but in concluſion to digeſt it by Baths, Stoves, and much and great exerciſe. *Rondeletius* in his Book *De Piſcibus*, affirms the ſame things of the curſed venom of Toads, as we have formerly delivered: yet that they ſeldom bite, but that they caſt forth either their urin, the which they gather in a great quantity in a large Bladder, or elſe their venemous ſpittle or breath, againſt ſuch as they meet withall or aſſail: beſides the herbs which are tainted by their poiſonous The ſymptoms occaſioned by the poiſon of Toads. May-Frogs. The Cure.

breath,

breath, but much more such as are sprinkled with their spittle or urin, are sufficient to kill such as eat them. The Antidotes are juice of Betony, Plantain, Mugwort, as also the bloud of Tortoises made with flour into Pills, and forthwith dissolved in Wine, and drunken. *Pliny* writes, that the hearts and spleens of Toads resist poison. The vulgar opinion is false, who think that the Toad-stone is found in their heads, which is good against poison.

Antidotes against the poison of Toads.

CHAP. XXV.

Of the stinging of a Scorpion.

A Scorpion is a small creature with a round body, in form of an Egg, with many feet, and a long tail consisting of many joints, the last whereof is thicker, and a little longer than the rest, at the very end thereof is a sting it casts, in some two, hollow and replete with cold poison, the which by the sting, it casts into the obvious body; it hath five legs on each side forked with strong Claws not unlike to a Crab or Lobster, but the two foremost are bigger then the rest; they are of a blackish or sooty colour, they go aside, aside; and oft-times fasten themselves with their mouths and feet so fast to them, that they can scarce be plucked there-hence. There be some who have wings like the wings of Locusts, wasting the Corn and all green things with their biting and burning. Such are unknown in *France*. These fly in divers Countries, like winged Ants. This is likely to be true by that which *Matthiolus* writes, That the Husband-men in *Castile* in *Spain*, in digging the Earth oft-times find a swarm of Scorpions, which betake themselves thither against Winter. *Pliny* writes, that Scorpions laid waste a certain part of *Ethiopia*, by chasing away the Inhabitants. The Ancients made divers kinds of Scorpions, according to their variety or difference of colours, some being yellow, others brown, reddish, ash-coloured, green, whitish, black, dusky; some have wings, and some are without. They are more or less deadly, according to the Countries they inhabit. In *Tuscany* and *Scythia* they are absolutely deadly, but at *Trent*, and in the Island *Pharos* their stinging is harmless. The place stung by a Scorpion presently begins to be inflamed, it waxeth red, grows hard, and swells, and the Patient is again pained; he is one while hot, another while cold; labour presently wearies him, and his pain is some whiles more and some whiles less; he sweats and shakes as if he had an Ague, his hair stands upright, paleness discolours his members, and he feels a pain, as if he were pricked with Needles over all his skin, wind flieth out backwards; he strives to vomit and go to stool, but doth nothing; he is molested with a continual Fever and swouning, which at length proves deadly, unless it be remedied. *Dioscorides* writes, that a Scorpion beaten and laid to the place where he is stung, is a remedy thereto; as also eaten roasted to the same purpose. It is an usual, but certain remedy to anoint the stung place with the oil of Scorpions. There be some who drop into the wound the milky juice of Figs, others apply Calamint beaten, other some use Barly-meal mixed with a decoction of *Rue*. Snails beaten together with their shells, and laid thereon, presently asswage pain. *Sulphur vivum* mixed with Turpentine, and applied Plaster-wise is good, as also the leaves of *Rue* beaten, and laid thereto. In like sort also the herb *Scorpioides*, which thence took its name, is convenient, as also a Briony-root boiled and mixed with a little Sulphur and old Oil. *Dioscorides* affirms, Agarick in Powder, or taken in Wine, to be an Antidote against poisons; verily it is exceeding good against the stingings or bitings of Serpents. Yet the continual use of a Bath stands in stead of all these, as also sweat, and drinking Wine somewhat allaid. Now Scorpions may be chased away by a fumigation of Sulphur and Galbanum; also oil of Scorpions dropped into their holes, hinders their coming forth. Juice of Raddish doth the same. For they will never touch one that is besmeared with the juice of Raddish or Garlick, yea verily, they will not dare to come near him.

The description of a Scorpion. His Tail.

Winged Scorpions.

Symptoms.

Lib.2.cap.44. & lib.6.cap.10.

Lib.3.cap.1.

CHAP. XXVI.

Of the stingings of Bees, Wasps, &c.

Bees, Wasps, Hornets, and such like, cause great pain in the skin wounded by their stinging, by reason of the curstness of the venom which they send into the body by the wound, yet are they seldom deadly, but yet if they set upon a man by multitudes, they may come to kill him. For thus they have sometimes been the death of Horses: Wherefore because such as are stung by these, by reason of the cruelty of pain, may think they are wounded by a more virulent and deadly Creature, I think it not amiss to set down what signs follow upon their stingings. Great pain presently ariseth, which continueth, until the sting left in the part is taken forth, the part becomes red and swollen, and there riseth a push or little blister. The Cure is, forthwith to suck the wound very hard, and thereby to draw forth the stings, which if they cannot thus be gotten out, the place, if nothing hinder, is to be cut, or else temper Ashes with Leven or Oil, and so apply them: the part also may be very conveniently put into hot Water, and there fomented for an hours space, and at length washed in Sea water. Cresses beaten and applied, asswage the pain and discuss the humour causing the tumor. Ox dung macerated in Oil and Vinegar, and applied hot, doth the same. There are some who apply to the part the same Creatures beaten, as we formerly said of Scorpions; Beans chawed and laid to the part asswage pain. Vinegar, Honey, and Salt, applied exceeding hot, are good, if besides, you dip a cloth therein, and lay it upon the place; *Sulphur Vivum* tempered with spittle hath the same effect. The milky juice of unripe Figs incorporated with Honey, is judged very effectual, but it is much the better, mixed with Treacle. Wasps will not sting nor bite such as anoint their bodies with the juice of Mallows mixed with Oil. They may be quickly chased away with the fume of Brimstone and such like things. A Wasp is said, if she

Symptoms. The Cure.

tipd

find a Viper dead, to dip her ſting in the others poiſon, and thence men learned to empoiſon the heads of their arrows. The rough and hairy Worms, which are commonly called Bear-worms, eſpecially thoſe which breed about a Pine-tree, cauſe great itching, redneſs and ſwelling in the part which they bite, touch, or grate upon very hard. A remedy hereof is Onions beaten with Vinegar, and the reſt of the things formerly mentioned. The bites of Bear-worms.

CHAP. XXVII.

Of the bite of a Spider.

SPiders weave Webs with various art, yet in theſe they always make a lurking hole to lie in wait to catch the intrapped Flies, and ſo to prey upon them. There are many ſorts of Spiders, one is termed *Rhagium*, round and like a Black-berry, whence it taketh the name; it hath a very ſmall mouth under the midſt of the belly, and moſt ſhort feet, as if they were imperfect, her bite is as painful as the ſting of a Scorpion. Another is called *Lupus*, or the Wolf-Spider, becauſe ſhe doth not onely lie in wait to catch Flies, but alſo Bees and Waſps, and all ſuch things as may flee into her Web. The third is named *Myrmecion*, it is larger then an Ant, but headed like one, the body thereof is black, and hath white ſpots or ſtreaks running towards the back. The fourth kind may be called *Veſparium*, in other things reſembling a Waſp, but that it wants the wings; of a reddiſh colour and living onely on herbs. The Ancients have thought their bitings to be venemous. Now their poiſon is therefore thought to be cold, becauſe the ſymptoms thence ariſing are, wind in the belly, refrigerations of the extreme parts of the body, numneſs in the bitten part, with ſenſe of cold and ſhaking. The wound muſt forthwith be waſhed with very hot Vinegar, then muſt you lay thereto Onions, and ſuch like things beaten, then procure ſweat by art, as by Baths and Stoves; yet nothing is more effectual than Treacle and Mithridate. Differences of Spiders.

CHAP. XXVIII.

Of Cantharides *and* Bupreſtes.

C*Antharides* ſhine as it were with a golden colour, acceptable to the eye, by reaſon of the commixture of a blewiſh or greeniſh colour therewith, yet their ſmell is ungrateful. They are hot and dry in the fourth degree, and ſo cauſtick, corroſive and venemous, not onely by reaſon of their cauſtick quality, but becauſe of a ſecret antipathy which they naturally have againſt the urinary parts; which effects they produce not onely if they be taken by the mouth into the body, but even applied outwardly to raiſe bliſters. Such as have taken them inwardly, have the taſte of Pitch, or ſomething like *Cedria*, or Roſin of Cedars in their mouths; it is likely that this taſte proceeds from the humours diſſolved by the putredinous heat in the ſtomach, guts, and liver, and the vapours that there-hence ariſe; for taken inwardly they gnaw, exulcerate and burn all parts from the mouth even to the belly, whence enſueth a bloudy flux, excrements flowing out, which reſemble the waſhings of new killed fleſh. Then follows a burning Fever, *Vertigo*, Madneſs, Reſtleſsneſs, the Brain being diſturbed by the plenty of vapors lifted up from the corroded and burnt parts and humours, which therefore when as they appear, you may know the affect is uncurable. In the parts appointed for the receiving and conveyance of the urin they cauſe a burning inflammation, excoriation, ſtrong and continual erection of the Yard, whence enſues a bloudy and painful ſtrangury, in ſtead of which there oft-times happens or ſucceeds an *Iſchury*, or ſtoppage of the water, whence a gangrene and mortification of the part, and ſo in concluſion of the whole body beſides. When as *Cantharides* are taken inwardly, the remedy is vomiting, drinking of Cows-milk to correct the heat and drineſs, good alſo to mitigate the ulcers, and ſtay the dyſentery; it is good alſo to inject it into the guts by Clyſter. In ſtead thereof Sallet-oil or oil of ſweet Almonds is convenient to retund the acrimony of the poyſon faſtned to the ſides of the ſtomach. The reſt and whole cure of this poiſon you may learn by the following Hiſtory. A certain Whore, the better to enjoy the company of a young Abbot who loved her, entertained him with a banquet, and ſprinkled divers of their Cakes with the powder of *Cantharides*, to incite him the more to Venery. The next day, when as the Abbot caſt forth pure bloud at his Fundament and Yard which ſtood very ſtiff, he called ſome Phyſicians, who preſently by the fore-mentioned ſymptoms, which were all very apparent in him, underſtood that he had *Cantharides* given him: wherefore they purged him upwards with Vomits, and downwards by Clyſters made with French-barley, Rice, a decoction of Mallows, ſeeds of Line and Fœnugreek, Oil of Lillies, Goats ſuet: then preſently after they gave him a little Treacle with a good quantity of Conſerve of Violets, which might draw the poiſon outwards, they gave him Milk to drink, and cauſed him to uſe injections into the urinary paſſage and guts made of refrigerating things, as the juice of Lettuce, Purſlain, Cucumers, Gourds, Melons, ; of tough and viſcid things: that ſo they might ſtick the more eaſily and longer to the ulcerated parts, as the mucilages of *Pſilium*, Mallows, Quince-ſeeds, Syrup of Water-lillies, Poppies, and Violets, freſh Butter, and Oil of ſweet Almonds; and they made him drink onely Barley-water, or the common Ptiſan; they let him feed on Veal, Kid, and Pork boiled with Lettuce, Purſlain, Barley and Violet leaves, the which by their humidity might relax the belly, and by their toughneſs lenifie the roughneſs of aſperity; they applied alſo refrigerating things to the Loins, Share, and *Perinæum* to aſſwage the heat of the urin. At length they put him into a warm Bath, and to conclude, they left nothing unattempted to draw forth or weaken the poiſon. But all their endeavours were in vain, for the Abbot died, not being deſtitute of remedies conveniently preſcribed, but overcome by the contumacious malignity of the poiſon. The Phyſicians pains had far better ſucceſs in a certain Gentlewoman againſt this kind of affect; her

The deſcription of *Cantharides*. Enemies to the bladder. Symptoms. An Hiſtory. The Cure. An Hiſtory.

her whole face was deformed with red, fiery and filthy puſtles, ſo that all ſhunned her company as if ſhe had been troubled with a Leproſie, and were ready to forbid her the ſociety of men; ſhe came to *Paris*, and calling for *Hollerius* and *Grealmus* Phyſicians, my ſelf and *Caballus* being Surgeons, ſhe made a grievous complaint, and beſought us earneſtly for ſome remedy againſt ſo great a deformity of her face; having diligently conſidered her caſe, we pronounced her free from a Leproſie, but we judged it fit to apply to her whole face a veſicatory of *Cantharides*, three or four hours after the application whereof, the Medicin being come to work its effect, her bladder began to burn exceedingly, and the neck of her womb to ſwell with gripings, continual vomitings, making of water and ſcouring, a troubleſome agitation of the body and members, a burning and abſolutely fiery Fever. I forthwith called the Phyſicians, it was decreed that ſhe ſhould drink Wine plentifully, and that it ſhould be injected by the fundament into the guts, and by the urinary paſſage into the bladder and the neck of the womb, and that ſhe ſhould keep her ſelf, until the pain were mitigated, in a warm Bath made of the decoction of Line-ſeeds, the roots and leaves of Mallows, Marſh-mallows, Violets, Henbane, Purſlain, and Lettuce; and her loins and genitals ſhould be anointed with *unguentum roſatum* and *populeon* ſtirred and incorporated with *oxycrate*. By theſe means all the ſymptoms were mitigated. Her face in the interim roſe all in a bliſter, and much purulent matter came out thereof, and ſo the deformity wherewith ſhe was formerly troubled, vaniſhed away for ever, ſo that within a while after ſhe was married, and had many children, and is yet living in perfect health.

Cantharides applied to the head, ulcerate the bladder.

A remedy againſt Leprous puſtles.

Bupreſtes alſo are of the kind of *Cantharides*, being like unto them in ſhape and faculty. If an Ox or Sheep or any other Creature ſhall in feeding devour one of them, he ſhall preſently ſwell up like a Tun; whence alſo they take their name: if a Man take them inwardly, he ſhall endure the like ſymptoms as in taking *Cantharides*; and over and beſides, both his ſtomach and his whole belly ſhall be wonderfully puffed up, as if he had a Dropſie. It is probable that this inflation like a Tympany happeneth by humours diffuſed and reſolved into vapours by the fiery acrimony of the venom. They are to be cured after the ſame manner as ſuch as have drunk *Cantharides*. Laſtly, As in all other poiſons which are taken into the body, ſo alſo here, if the poiſon taken by the mouth be thought as yet to be in the ſtomach, you muſt then procure vomit. If it be gotten into the guts, then muſt it be drawn away by Clyſters. If diffuſed over all the body, then muſt you make uſe of ſuch things as may drive the poiſon forth from the center to the circumference, ſuch as are Baths and Stoves.

The reaſon of the name.

CHAP. XXIX.

Of Horſe-Leeches.

HOrſe-Leeches are alſo venemous, eſpecially ſuch as live in muddy ſtinking ditches, for thoſe are leſs hurtful which reſide in clear and pure waters. Wherefore, before they are to be uſed in caſes of Phyſick, they muſt be kept for ſome days ſpace in clean water, that ſo they may purge themſelves; otherwiſe they may chance to leave ulcers hard to cure in the places whereto they ſhall be applied, and the rather, if they be violently plucked off, becauſe they by that means leave their teeth faſtned in the part. Now he which by chance hath ſwallowed a Horſe-leech, muſt be asked in what part he feeleth her, that is, the ſenſe of her ſucking: For if ſhe ſtick in the top of the throat or gullet, or in the midſt thereof, the part ſhall be often waſhed with muſtard diſſolved in vinegar. If ſhe be near the orifice of the ventricle, it is fit that the Patient by little and little ſwallow down Oil with a little Vinegar. But if ſhe faſten to the ſtomach, or the bottom of the ventricle, the Patient, by the plucking off the part, ſhall perceive a certain ſenſe of ſucking, the Patient will ſpit bloud, and will for fear become Melancholick. To force her thence, he ſhall drink warm Water with Oil; but if ſhe cannot ſo be looſed, then ſhall you mix aloes therewith, or ſomething endued with the like bitterneſs, for ſhe will by that means leave her hold and ſo be caſt forth by vomit. You may perceive this by ſuch as are applied to the skin, on the external parts; for by the aſperſion of bitter things, whether they be full or empty, they will forſake their hold. Then ſhall the Patient take aſtringent things which may ſtop the bloud flowing forth of the bitten part, ſuch is Conſerve of Roſes, with *Terra ſigillata*, Bole-Armenick, and other more aſtringent things, if need ſo require. For if they ſhall adhere to ſome greater branch of ſome Vein or Artery, it will be more difficult to ſtop the flowing bloud.

What Horſe-leeches moſt virulent.

Divers remedies according to the diverſity of the parts.

But for that not the Earth onely, but the Sea alſo produceth venemous Creatures, we will in like ſort treat of them, as we have already done of the other, beginning with the Lampron.

CHAP. XXX.

Of the Lampron.

THe *Lampron*, called in Latin *Muræna*, is a Sea-fiſh, ſomething in ſhape reſembling a Lamprey, but ſhe is bigger and thicker, and hath a larger mouth, with teeth long, ſharp, and bending inwards, ſhe is of a dusky colour, diſtinguiſhed with whitiſh ſpots, and ſome two cubits length. The Ancients had them in great eſteem, becauſe they yield good nouriſhment, and may be kept long alive in Pools or Ponds, and ſo taken as the owners pleaſe, to ſerve their Table, as it is ſufficiently known by the Hiſtory of the *Roman Craſſus*. She by her biting induceth the ſame ſymptoms as the Viper, and it may be helped by the ſame means. Verily the Lampron hath ſuch familiarity with the Viper, that leaving her natural element the Sea, ſhe leapeth athore, and ſeeketh out the Viper in her den to join with her in copulation, as it is written by *Ælian* and *Nicander*.

The deſcription of the Lampron.

The natural friendſhip of the Lampron and Viper.

CHAP.

CHAP. XXXI.

Of the Draco marinus, *or ſea-Dragon.*

THe ſea-Dragon, called by the French *viva*, for his vivacity (and by the Engliſh a *Viver*, or as ſome ſay, a *Qua-viver*) becauſe being taken in fiſhing, and drawn out of the ſea, ſhe is ſaid long to ſurvive. Her pricks are poiſonous; but chiefly thoſe that are at the edges of her gills. Which is the reaſon that Cooks cut off their heads before they ſerve them up to the table; and at *Roven* the fiſhermen lay them not upon their ſtalls to ſell before they have cut off their head. The wounded part of ſuch as are hurt, pains them much with inflammation, a feaver, ſwouning, gangrene and deadly mortification, unleſs it be quickly withſtood. Not very long ago the wife of *Mounſieur Fromaget*, Secretary of the requeſts, was wounded with a prick of this fiſh in her middle finger, there followed a ſwelling and redneſs of the part; without much pain; but perceiving the ſwelling to increaſe, being made more wary by the miſchance of her neighbour the wife of *Mounſieur Bargelonne*, Lieutenant particular in the Chaſtelet of *Paris*, who died not long before by the like accident being neglected, ſent for me; I underſtanding the cauſe of her diſeaſe, laid to her pained finger and her whole hand, beſides a pultis made of a great Onion roſted under the coals, leaven, and a little treacle. The next day I wiſhed her to dip her whole hand into warm water, ſo to draw forth the poyſon, then I divided the skin about it with much ſcarification but only ſuperficiarily; to the gaſhes I applied Leeches, which by ſucking drawing a ſufficient quantity of blood, I put thereto treacle diſſolved in *aqua vitæ*. The next day the ſwelling was aſſwaged, and the pain eaſed, and within a few days ſhe was perfectly well. *Dioſcorides* writes, that this fiſh divided in the midſt, and applied to the wound, will cure it.

Symptoms. An hiſtory. The cure.

CHAP. XXXII.

Of the Paſtinaca marina, *or Sting-Ray, which ſome call the* Fierce-claw.

SUch as are ſtung by a Sting-Ray (as *Aetius* hath written) the place of the wound doth manifeſtly appear; there enſues thereon laſting pain and the numneſs of the whole body. And ſeeing that it hath a ſharp and firm ſting, whereby the nerves by the deepneſs of the ſtroke may be wounded, it ſo happpens that ſome die forthwith, their whole bodies ſuffering convulſions. Moreover, it will kill even the very trees into whoſe roots it is faſtned. Yet *Pliny* affirms, that it is good againſt the pain of the teeth, if the gums be ſcarified therewith, yea, and it being made into powder with white Hellebore, or of it ſelf, will cauſe teeth to fall out without any pain, or any violence offered to them. This fiſh is good meat, the head and tail excepted; ſome of them have two ſtings, other-ſome but one; theſe ſtings are ſharp like a ſaw with the teeth turning towards their heads. *Oppianus* writes, that their ſtings are more poyſonous than the Perſians arrows, for the force of the poyſon remaineth, the fiſh being dead; which will kill not only living creatures, but plants alſo. Fiſhermen, when they catch this fiſh, preſently ſpoil him of his ſting, leſt they ſhould be hurt therewith. But if by chance they be hurt therewith, then take they forth his liver, and lay it to the wound; furthermore, the fiſh being burnt and made into powder, is the true Antidote of his wound. The Sting-Ray lives in muddy places near the ſhore, upon the fiſhes that he hunteth and catcheth with his ſting, having the teeth thereof turned towards his head for the ſame purpoſe. He is not unlike a Ray, and I have here given you his figure.

The ſymptoms. *Lib. 9. cap. 48.* The virulency of her ſting.

The figure of a Sting-Ray.



CHAP. XXXIII.

Of the Lepus Marinus, *or Sea-hare.*

The deſcription of the Sea-hare.

Pliny calls the Sea-hare, a maſs or deformed piece of fleſh. *Galen* ſaith it is like a Snail taken forth of the ſhell. It is exceedingly poyſonous in the judgment of the Ancients, wherefore it is not amiſs to ſet down the deſcription of it, leſt we might eat it at unawares, too earneſtly view it, or ſmell thereto, as alſo that we may uſe it againſt the poyſon thereof; it is an inhabitant not only of the ſea, but alſo of lakes of ſea-water, eſpecially ſuch as are muddy; it is of the ſame colour as the hair of the land-hare is, it hath a whole in the head, out of which he putteth a certain piece of fleſh, and plucks it back again when as he is ſeen, *Paulus*, *Aetius*, *Pliny*, *Galen* and *Nicander* are of one opinion, and agree in this, that if a woman big with child do too earneſtly look upon one, ſhe will vomit, and preſently after abort. They which have drunk this poyſon, ſaith *Dioſcorides*, are troubled with pain in the belly, and their urine is ſtopped. If they do make water, then is it bloody; they run down with ſtinking ſweat, which ſmells of fiſh; a cholerick vomiting ſometimes mixed with blood enſues thereon.

The earneſt beholding of a Sea-hare will cauſe abortion.

The ſymptoms.

Aetius writes, that all their bodies turn yellow, their faces ſwell, and their feet, but chiefly their genital member, which is the cauſe they cannot make water freely. *Galen* writes that it is the property of the Sea-hare to exulcerate the lungs. Their Antidote is Aſſes-milk, muskadine, or honied wine continually drunken, or a decoction of the roots and leaves of Mallows. It is good for the falling away of the hair. I have here given you the figure thereof out of *Rondeletius* his book of Fiſhes.

The Antidote.

The figure of a Sea-hare.



CHAP. XXXIV.

Of the Poyſon of Cats.

A Cats hair moſt ſubject to choak.

NOt only the brain of a Cat, being eaten, is poyſonous and deadly to man, but alſo their hair, their breath, yea and their very preſence to ſome prove deadly. For although any hair devoured unawares, may be enough to choak one, by ſtopping the inſtruments of reſpiration; yet the hairs of a Cat by a certain occult property, are judged moſt dangerous in this caſe: beſides alſo, their breath is infected with a certain hurtful malignity. For *Matthiolus* ſaith, that he knew ſome, who being ſo delighted with Cats, that they would never go to bed without them, have by ſo often drawing in the air with their breath, fallen into a conſumption of the lungs, which occaſioned their death. Moreover, it is manifeſt that the very ſight of their eyes is hurtful, which appears by this, that ſome but ſeeing or hearing them, preſently fall down in a ſwound; yet I would not judge that to happen by the malicious virulency of the Cat, but alſo by the peculiar nature of the party, and a quality generated with him, and ſent from heaven. When as, ſaith *Matthiolus*, a certain *German* in winter-time, came with us into a ſtove to ſupper, whereas were divers of our acquaintance, a certain woman, knowing this mans nature, leſt that he ſhould ſee her kitling which ſhe kept, and ſo ſhould go away in chaſe, ſhe ſhut her up in a cup-board in the ſame chamber: But for all that he did not ſee her, neither heard her cry, yet within a little ſpace, when he had drawn in the air, infected with the breath of the Cat, that quality of temperament, contrary, or enemy to Cats, being provoked, he began to ſweat, to look pale, and to cry out (all of us admiring it) *Here lies a Cat in ſome corner or other*; neither could he be quiet till the Cat was taken away. But ſuch as have eaten the brains of a Cat, are taken with often *Vertigoes*, and now and then become fooliſh and mad: they are helped by procuring vomit, and taking the Antidote againſt this poyſon, that is, half a ſcruple of Musk, diſſolved and drunk in wine. There be ſome who preſcribe the confection *Diamoſcum* to be taken every morning four hours before meat. By this you may gather, that it is not ſo fabulous that the common ſort report, that Cats will kill or harm children; for lying to their mouths with the weight of their whole bodies, they hinder the paſſage forth of the fuliginous vapors, and the motion of the cheſt, and infect and ſtifle the ſpirits of tender infants by the peſtiferous air aad exhalation which they ſend forth.

The breath of a Cat moſt hurtful to the lungs.

An hiſtory.

A wonderful antipathy between a man and a Cat.

The Antidote againſt the brains of a Cat.

Cats dangerous for children.

CHAP.

CHAP. XXXV.

Of certain Poysonous Plants.

HAving described the poysons that come from living creatures, I come to speak of such as are from Plants, beginning with the *Sardonian* herb, which is also also called *Apium risus*: this is a kind of *Ranunculus*, or Crow-foot: (and, as it is thought, the round leaved water Crow-foot, called Marsh-Crow-foot, or Spear-wort) it taketh away the understanding of such as have eaten thereof, and by a certain distention of the nerves, contracts the cheek, so that it makes them look as if they laughed; from this affect came that proverbial speech of the *Sardonian laughter*, taken in evil part. His *Bezoar*, as one may term it, is the juice of Balm. *Apium risus.* His Antidote

The juice, fruit, and substance of *Napellus* taken inwardly, killeth a man the same day, or at the fartherst in three days: yea and such as escape the deadly force thereof by the speedy and convenient use of Antidotes, fall into an hectick feaver, or consumption, and become subject to the falling-sickness, as *Avicen* affirmeth. And hence it is, that barbarous People poyson their arrows therewith: For the lips are forthwith inflamed, and the tongue so swells, that by reason thereof, it cannot be contained in the mouth, but hangs out with great horror; their eys are inflamed, and stand forth of their head, and they are troubled with a *Vertigo* and swounding; they become so weak that they cannot stir their legs, they are swoln and puffed in their bodies, the violence of poyson is so great. The Antidote thereof is a certain little creature like a * Mouse, which is bred, and lives on the root of *Napellus*, being dried and drunk in powder, to the weight of two drams. In want hereof you may use the seed of Raddish or Turnips to drink, and anoint the body also with oil of Scorpions. *Napellus*, or Monks-hood. * Our Author deceived by the *Arabians*. who (it may be) mistook

the Greek word μῦα and instead thereof read μυῖ for a Flie, a Mouse: for there is no Mouse to be found, but whole swarms of Flies, which feed thereon, you may find the description of an Antidote made with them in *Lobels Stirp. adverſ. Pag.* 303.

Doricinum and *Solanum Manicum*, or deadly Night-shade, are not much different in their mortal symptoms or effects. *Doricinum* being drunk, resembleth milk in taste, it causeth continual hicketting, it troubleth the tongue with the weight of the humor, it causeth blood to be cast forth of the mouth, and certain mucous matter out of the belly, like that which cometh away in the bloudy flux. A remedy hereto are all shell-fishes, as well crude as rosted, also Sea-Lobsters and Crabs, as the broth or liquor wherein they are boyled, being drunk. Now the root of *Solanum Manicum* drunk in the weight of one dram in wine, causeth vain and not unpleasing imaginations, but double this quantity causes a distraction or alienation of the mind for three days, but four times so much kills. The remedies are the same as these prescribed against *Doricinum*. *Doricinum* and *Solanum Manicum*, or deadly Night-shade. The symptoms.

Hen-bane drunken, or otherwise taken inwarly by the mouth, causeth an alienation of the mind of like drunkenness; this also is accompanied with an agitation of the body, and exsolution of the spirits like swounding. But amongst others, this is a notable symptom, that the patients so dote, that they think themselves to be whipped: whence their voice becomes so various, that sometimes they bray like an Ass or Mule, neigh like an Horse, as *Avicen* writes. The Antidote is Pistick nuts eaten in great plenty, treacle also and mithridate dissolved in sack, also wormwood, *rue* and milk. Hen-bane. The Antidote.

Of mushroms, some are deadly and hurtful of their own kind and nature, as those, which broken presently become of divers colous, and putrefie: (such, as *Avicen* saith, those are which be found of a grayish or blewish colour) others though not hurtful in quality, yet eaten in greater measure than is fitting, become deadly; for seeing by nature they are very cold and moist, and consequently abound with no small viscosity, as the excrementitious phlegm of the earth or trees whereon they grow, they suffocate and extinguish the heat of the body, as overcome by their quantity, and strangle as if one were hanged, and lastly kill. Verily I cannot chuse, but pitty Gourmondizers, who though they know that Mushroms are the seminary and gate of death, yet do they with a great deal of do, most greedily devour them; I say, pittying them, I will shew them, and teach them the art, how they may feed upon this so much desired dish, without the endangering of their health. Know therefore that Mushroms may be eaten without danger, if that they be first boyled with wild pears: but if you have no wild pears, you may supply that defect with others which are the most harsh, either newly gathered, or dried in the Sun. The leaves, as also the bark of the same tree, are good, especially of the wild; for pears are their Antidote: yet *Conciliator* gives another, to wit, garlick eaten crude; whereunto in like sort vinegar may be fitly added, so to cut and attenuate the tough, viscous and gross humors, heaped up, and in danger to strangle one by the too plentiful eating of Mushroms, as it is delivered by *Galen*. Mushroms. Their Antidote. *In 5. Epidem.*

Ephemerum, which some call *Colchicum* or *Bulbus silvestris*, that is, medow saffron, being taken inwardly, causeth an itching over all the body, no otherwise than those that are nettled, or rubbed with the juice of a Squill. Inwardly they feel gnawings, their stomach is troubled with a great heavines, and in the disease increasing, there are strakes of blood mixed with the excrements. The Antidote thereof is womans milk, Asses or Cows-milk drunken warm, and in a large quantity. *Colchicum*, or Medow-saffron. The Antidote.

Mandrag taken in great quantity, either the root or fruit causeth great sleepines, sadnes, resolution and languishing of the body, so that after many scritches and gripings, the patient falls asleep in the same posture that he was in, just as if he was in a Lethargy. Wherefore in times past they gave Mandrag to such as were to be dismembred. The apples, when as they are ripe, and their seeds taken forth, may be safely eaten, for being green and with their seeds in them, they are deadly. For their ariseth an intolerable heat, which burns the whole surface of the body, the tongue and mouth wax dry, by reason whereof they gape continually, so take in the cold air; and in which Mandrag.

The cure. caſe unleſs they be preſently helped, they die with convulſions. But they may eaſily be helped, if they ſhall preſently drink ſuch things as are convenient therefore. Amongſt which, in *Conciliators* opinion, excel raddiſhſeeds eaten with ſalt and bread for the ſpace of three days. Sneeſing ſhall be procured, if the former remedy do not quickly refreſh them, and a decoction of Coriander or Penny-royal in fair water ſhall be given them to drink warm.

Opium. The ungrateful taſte of the juice of black poppy, which is termed *Opium*, as alſo of Mandrag, eaſily hinders them from being put into meat or drink, but that they may be diſcerned, and chiefly for that neither of them can kill, unleſs they be taken in a good quantity. But becauſe there is danger, leſt they be given in greater quantity than is fitting by the ignorance of Phyſicians, or Apothecaries, you may by theſe ſigns find the error.

Why not uſed in poyſonings.

The ſymptoms. There enſues heavy ſleep, with a vehement itching, ſo that the patient oft-times is forced thereby to caſt off his dull ſleep wherein he lay, yet he keeps his eye-lids ſhut being unable to open them. By this agitation there flows out ſweat, which ſmells of *opium*, the body waxeth pale, the lips burn, the jawbone is relaxed, they breath little and ſeldom. When as their eyes wax livid, unleſs they be drawn aſide, and that they are depreſſed from their orb, we muſt know that death is at hand. The remedy againſt this is two drams of the powder of *Caſtoreum* given in wine.

Hemlock. Hemlock drunken, cauſeth *Vertigoes*, troubleth the mind, ſo that the patients may be taken for mad men; it darkneth the ſight, cauſeth hicketting, and benums the extreme parts, and laſtly ſtrangles with convulſions, by ſuppreſſing or ſtopping the breath of the Artery. Whereof at the firſt, as in other poyſons, you muſt endeavour to expel it by vomit; then inject clyſters, to expel that which is got into the guts; then uſe wine without mixture, which is very powerful in this caſe. *Peter Aponenſis* things the Bezoar or Antidote thereof, to be a potion of two drams of Treacle, with a decoction of *Dictamnus* or *Gentian* in wine. He which further deſires to inform himſelf of the effects of Hemlock, let him read *Matthiolus* his commentary upon *Dioſcorides*, where he treats of the ſame ſubject.

The ſymptoms.

The Antidote.

In lib. 6. Dioſc.

Aconitum. *Aconitum* called of *Aconis* a town of the *Periendines*, whereas it plentifully grows. According to *Matthiolus*, it kills Wolves, Foxes, Dogs, Cats, Swine, Panthers, Leopards, and all wild beaſts, mixed with fleſh, and ſo devoured by them, but it kills mice by only ſmelling thereto. Scorpions, if touched by the root of Aconite, grow numb and torpid, and ſo die thereof; arrows or darts dipped therein, make incurable wounds. Thoſe who have drunk Aconite, their tongue forthwith waxeth ſweet with a certain aſtriction, which within a while turneth to bitterneſs; it cauſeth a *Vertigo*, and ſhedding of tears, and a heavineſs or ſtraitneſs of the cheſt and parts about the heart; it makes them break wind downwards, and makes all the body to tremble. *Pliny* attributes ſo great celerity and violence to this poyſon, that if the genitals of female creatures be touched therewith, it will kill the ſame day; there is no preſenter remedy than ſpeedy vomiting after the poyſon is taken. But *Conciliator* thinks *Ariſtolochia* to be the Antidote thereof. Yet ſome have made it uſeful for man by experimenting it againſt the ſtinging of Scorpions, being given warm in wine; for it is of ſuch a nature that it killeth the party unleſs it find ſomething in him to kill, for then it ſtrives therewith as if it had found an adverſary: But this fight is only when as it finds poyſon in the body; and this is marvelous that both the poyſons being of their own nature deadly, ſhould die together, that man may by that means live. There are divers ſorts thereof, one whereof hath a flower like an helmet, as if it were armed to mans deſtruction; but the other here delineated hath leaves like to ſows-bread or a cucumber, and a root like the tail of a Scorpion.

Lib. 27. cap 2.

Aconite good againſt the poiſon of Scorpions.

The differences.

The figure of a certain kind of Aconite.

Trees alſo are not without poyſon, as the Yew and Walnut tree may witneſs; Cattel if they feed on the leaves of Yew, are killed therewith. * But men, if they ſleep under it, or ſit under the ſhadow thereof, are hurt therewith, and oft-times die thereof. But if they eat it, they are taken with a bloudy flux, and a coldneſs over all their bodies, and a kind of ſtrangling or ſtoppage of their breath. All which things the Yew cauſeth, not ſo much by an elementary and cold quality, as by a certain occult malignity, whereby it corrupteth the humors and ſhaveth the guts. The ſame things are good againſt this, as we have ſet down againſt Hemlock; *Nicander* affirms, that good wine being drunken, is a remedy thereto. There is alſo a malignity in a Walnut-tree, which *Grevinus* affirms that he found by experience, whilſt he unawares ſate under one, and ſlept there in the midſt of Summer; For waking, he had a ſenſe of cold over all his body, a heavineſs of his head, and pain that laſted ſix days. The remedies are the ſame as againſt the Yew.

The Yew.

* This is true in ſome countries, as in *Provence*, *Italy*, *Greece*, &c. but it is not ſo here with us in *England*, as both *Lobel* and daily experience can teſtifie.

The Antidote.

The Walnut tree

CHAP.

CHAP. XXXVI.

Of Bezoar, *and Bezoartick medicines.*

FOr that we have made mention of *Bezoar*, in treating of the remedies of poysons, I judge I shall not do amiss, if I shall explain, what the word means, and the reason thereof. Poyson absolutely taken is that which kills by a certain specifick antipathy contrary to our nature. So an Antidote or Counter-poyson is by the Arabians in their mother tongue, termed *Bedezahar*, as the preservers of life. This word is unknown to the Greeks and Latines, and in use only with the Arabians and Persians, because the thing it self first came from them as it is plainly shewed by *Garcias ab horto*, Physician to the Vice-roy of the Indies, in his history of the Spices and *Simples* of the East-Indies. In *Persia* (saith he) and a certain part of *India* is a certain kind of Goat called *Pazain* (wherefore in proper speaking, the stone should be termed *Pazar* of the word *Pazain*, that signifies a Goat, but we corruptly term it *Bezar* or *Bezoar*) the colour of this beast is commonly reddish, the height thereof indifferent, in whose stomach concretes the stone called *Bezoar*; it grows by little and little about a straw or some such like substance in scales like to the scales of an onion, so that when as the first scale is taken off, the next appears more smooth and shining as you still take them away, the which amongst others, is the sign of good *Bezoar* and not adulterate. This stone is found in sundry shapes, but commonly it resembles an Acorn or Date-stone; it is sometimes of a sanguin colour, and otherwhiles of a hony-like or yellowish colour, but most frequently of a blackish or dark green, resembling the colour of mad apples, or else of a Civet-Cat. This stone hath no heart or kernel in the midst, but powder in the cavity thereof, which is also of the same faculty. Now this stone is light and not very hard, but so that it may easily be scraped or rasped like Alablaster, so that it will dissolve, being long macerated in water; at first it was common amongst us, and of no very great price, because our people who trafficked in Persia, bought it at an easie rate. But after that the faculties thereof were found out, it began to be more rare and dear, and it was prohibited by an Edict from the King of the Country, that no body should sell a Goat to the stranger-Merchants, unless he first killed him and took forth the stone, and brought it to the King. Of the notes by which the stone is tried, (for there are many counterfeits brought hither) the first is already declared; the other is, it may be blown up by the breath, like an Oxes hide; for if the wind break through, and do not stay in the density thereof, it is accounted counterfeit. They use it induced thereto by our example, not only against poysons, but also against the bites of venemous beasts, The richer sort of the Countrey purge twice a year, to wit, in *March* and *September*; and then, five days together they take the powder of this stone macerated in Rose-water, the weight of ten grains at a time: for by this remedy they think their youth is preserved, as also the strength of their members. There be some who take the weight of thirty Grains; yet the more wary exceed not twelve grains. The same Author addeth that he useth it with very good success in inveterate melancholick diseases, as the itch, scab, tetters and leprosie; therefore by the same reason it may well be given against a quartane feaver. Besides he affirmeth for certain that the powder contained in the midst of the stone, put upon the bites of venemous beasts, presently freeth the patient from the danger of the poyson, as also applied to the pestilent Carbuncles, when they are opened, it draws forth the venom. But because the small pox and meazles are familiar in the Indies, and oft-times dangerous, it is there given with good success, two grains each day in Rose-water. *Matthiolus* subscribeth to this opinion of *Garcis*, witnessing that he hath found it by frequent experience that this stone by much exceeds not onely other *simple* medicines of this kind, but also such as are termed *theriacalia*, and what other Antidotes soever, hereto also consents *Abdanalarach*; We (saith he) have seen the stone which they call *Bezahar*, with the sons of *Almarima* the observer of the Law of the God; with which stone he bought a stately and almost princely house at *Corduba*.

What poyson is.

A sign of true Bezoar.

The use of Bezoar.

Lib. 5. in Dioscor. cap. 73.

Some years ago, a certain Gentleman who had one of these stones which he brought out of *Spain*, bragged before King *Charles* then being at *Clermont* in *Avern*, of the most certain efficacy of this stone against all manner of poysons. Then the King asked of me, whether there were any Antidote which was equally and in like manner prevalent against all poysons? I answered, that nature could not admit it; for neither have all poysons the like effects, neither do they arise from one cause; for some work from an occult and specifick property of their whole nature, others from some elementary quality which is predominant. Wherefore each must be withstood with its proper and contrary Antidote; as to the hot, that which is cold, and to that which assails by an occult propriety of form, another which by the same force may oppugn it, and that it was an easie matter to make trial hereof on such as were condemned to be hanged. The motion pleased the King, there was a Cook brought by the Jaylor who was to have been hanged within a while after for stealing two silver dishes out of his masters house. Yet the King desired first to know of him, whether he would take the poyson on this condition, that if the Antidote which was predicated to have singular power against all manner of poysons, which should be presently given him after the Poyson, should free him from death, that then he should have his life saved. The Cook answered chearfully, that he was willing to undergo the hazard, yea, and greater matters, not only to save his life, but to shun the infamy of the death he was like to be adjudged to: Therefore he then had poyson given him hy the Apothecary that then waited, and presently after the poyson, some of the *Bedezahar* brought from Spain, which being taken down, within a while after he began to vomit, and to avoid much by stool with grievous torments, and to cry out that his inward parts were burnt with fire. Wherefore being thirsty, and desiring water, they gave it him; an hour after, with the good leave of the Jaylor, I was admitted to him; I find him on the

An history.

No one thing can be an Antidote against all poysons.

The cauſtick force of *ſublimate*.

ground going like a beaſt upon hands and feet, with his tongue thruſt forth of his mouth, his eyes fiery, vomiting, with ſtore of cold ſweats, and laſtly, the blood flowing forth by his ears, noſe, mouth, fundament and yard. I gave him eight ounces of oil to drink, but it did him no good, for it came too late. Wherefore at length he died in great torment and exclamation, the ſeventh hour from the time that he took the poyſon being ſcarcely paſſed. I opened his body in the preſence of the Jaylor and four others, and I found the bottom of his ſtomach black and dry, as if it had been burnt with a cautery; whereby I underſtood he had *ſublimate* given him; whoſe force the Spaniſh *Bedezahar* could not repreſs, wherefore the King commanded to burn it.

CHAP. XXXVII.

Of Mineral Poyſons.

MInerals or metals are either ſo taken forth of the bowels of the earth, or elſe from furnaces. Of theſe many are poyſonous, as arſenick, *ſublimate*, *plaſter*, ceruſs, litharge, verdegreaſe, orpiment, filings of Iron, braſs, the load-ſtone, lime and the like. Such as have taken *ſublimate*, the tongue and jaws become ſtraitned and rough, as if they had drunk the juice of unripe *ſervices*: you cannot amend this aſperity with lenitive gargariſms but with labour and time; for as ſoon as it deſcends into the ſtomach, it ſticketh to it. Therefore preſently after it frets and exulcerates; it cauſeth unquenchable thirſt, and unexplicable torments; the tongue is ſwoln, the heart faints, the urine is ſuppreſt, the cheſt can ſcarce perform the office of breathing, the belly is griped, and ſo great pains happen to other extreme parts, that unleſs they be helped, patient will die; for preſently will grow upon them, unleſs it be ſpeedily hindred, the devouring and fiery fury of the poyſon, renting or eating into the guts and ſtomach, as if they were ſeared with an hot iron, and blood floweth out of the ears, noſe, mouth, urinary paſſage and fundament, and then their caſe is deſperate. Theſe and who elſe ſoever ſhall take any corroding poyſon, ſhall be cured with the ſame remedies, as thoſe that have taken *Cantharides*.

The ſymptoms of ſuch as have taken *ſublimate*.

Verdegreaſe.

Verdegreaſe ſo ſtops the inſtruments of reſpiration that it ſtrangles ſuch as have taken it. The cure is performed by the ſame remedies as help thoſe that have taken Arſenick.

Litharge.

Litharge cauſeth a heavineſs in the ſtomach, ſuppreſſeth urine, makes the body ſwelled and livid. We remedy this, by giving a vomit preſently, then after it pigeons-dung mixed in ſtrong wine and ſo drunken. *Peter Aponenſis* wiſheth, to give oil of ſweet almonds and figs. Alſo it is good to give relaxing and humecting clyſters, and to anoint the belly with freſh butter or oil of lillies.

The ſcales of Braſs.

The ſcales of Braſs drunk, by troubling the ſtomach, cauſe a caſting and ſcouring. The remedy is, if the patient forthwith vomit, if he enter into a bath made of the decoction of Snails, if he anoint his belly and breaſt with butter or oil of lillies, and inject laxative and humecting clyſters.

The Loadſtone

The loadſtone makes them mad that take it inwardly. The Antidote thereof is the powder of gold, and an emerald drunk in ſtrong wine, and clyſters of milk and oil of ſweet almonds.

Filings of Lead and ſcales of Iron.

The filings of Lead, and the ſcales or *refuſe* of Iron, cauſe great torment to ſuch as take them down. The which we help with much milk and freſh butter diſſolved therein, or with oil of ſweet almonds drawn without fire, with relaxing and humecting clyſters uſed until the pain be perfectly aſſwaged.

Arſenick, Roſe-aker or Rats-bane.

Riſagallum, Roſe-aker or Rats-bane, becauſe it is of a moſt hot and dry nature, induces thirſt and heat over all the body, and ſo great colliquation of all the humors, that although the patients by medicines ſpeedily given eſcape death, yet can they not during the reſidue of their lives, uſe their members as they formerly did, being deſtitute of their ſtrength, by reaſon of the great drineſs and contraction of the joints. The Antdiote thereof is oil of Pine-kernels ſpeedily given, and that to the quantity of half a pint; then procure vomit, then give much milk to drink, and clyſters of the ſame, and let them ſup up fat broths.

Unquenched Lime and Orpiment.

Unquencht Lime and *Auripigmentum*, or Orpiment drunk, gnaw the ſtomach and guts with great tormenting pain, and cauſe unquenchable thirſt, an aſperity of the jaws and throat, difficulty of breathing, ſtopping of the urine, and a bloody flux, They may be helped by oil, fat, humecting, and relaxing things which retund the acrimony by lenitive potions, and ſuch as lubricate the belly; as alſo by creams, and the mucilages of ſome ſeeds, as with a decoction of the ſeeds of *Line*, mallows, marſh-mallows and other things ſet down at large in the cure of *Cantharides*.

Aqua fortis.

Thoſe exceeding acrid and ſtrong waters wherewith Goldſmiths and Chymiſts ſeparate Gold from ſilver, being taken into the body, are hard to cure, becauſe they are forthwith diffuſed over all the body, firſt burning the throat and ſtomach. Yet it may be helped by the means preſcribed againſt unquenched Lime and Orpiment.

Ceruſs.

Ceruſs cauſeth hicketting and a cough, makes the tongue dry, and the extreme parts of the body numb with cold, the eyes heavy to ſleep. The patients very often in the midſt of the day ſee ſome vain phantaſie or apparition, which indeed is nothing; they make a black and oftentimes bloody water, they die ſtrangled unleſs they be helped. The Antidote in the opinion of *Aetius* and *Avicen*, is Scammony drunk in new wine, or hony and wine, and other diuretick things, and ſuch things as procure vomit, and purge by ſtool.

Plaſter.

Plaſter, becauſe it concreteth and becometh ſtony in the ſtomach, cauſeth ſtrangulation, by ſtraitning and ſtopping the inſtruments that ſerve for breathing. The patients receive cure by the ſame remedies as thoſe who have eaten muſhroom, or drunk Ceruſs: you muſt add Gooſe-greaſe in Clyſters, and anoint the belly with oil of lillies and butter.

CHAP.

CHAP. XXXVIII.

Of Quick silver.

Quick-silver is so called because it resembleth silver in the colour, and is in perpetual motion, as if it had a spirit or living soul, there is a great controversie amongst authors concerning it, for most of them affirm it hot, among whom is *Galen*, *Halyabas*, *Rhasis*, *Aristotle*, *Constantine*, *Isaac*, *Platearius*, *Nicholas Massa*: they maintain their opinion by an argument drawn from things helping and hurting; besides from this, that it is of such subtle parts, that it penetrates, dissolves and performeth all the actions of heat upon dense and hard metals, to wit, it attenuateth, incideth, drieth, causeth salivation by the mouth, purgeth by the stool, moveth urine and sweat over all the body; neither doth it stir up the thinner humors only, but in like sort the gross tough and viscous, as those which have the *Lues venerea* find by experience, using it either in ointments or Plasters. The reason why it is so called. *Lib 4. simp. in 2. practic. c. 148. 3. ad alman. 4. Meteor.*

Others affirm it very cold and moist, for that put into emplasters and so applied, it asswageth pain by stupefaction, hindering the acrimony of pustles and cholerick inflammations. But by its humidity it softneth scirrhous tumors, dissolveth and dissipateth knots and *tophous* knobs, besides, it causeth the breath of such as are anointed therewith to stink, by no other reason, than that it putrefies the obvious humor by its great humidity. *Avicen*'s experiment confirms this opinion, who affirmeth, that the blood of an Ape that drunk Quick-silver, was found concrete about the heart, the carcass being opened. *Matthiolus* moved by these reasons, writes that Quick-silver killeth men by the excessive cold and humid quality, if taken in a large quantity, because it congeals the blood and vital spirits, and at length the very substance of the heart, as may be understood by the history of a certain Apothecary, set down by *Conciliator*; who, for to quench his feaverish heat, in stead of water, drunk a glass of Quick-silver, (for that first came to his hands;) he died within a few hours after, but first he evacuated a good quantity of the Quick-silver by stool, the residue was found in his stomach being opened, and that to the weight of one pound; besides, the blood was found concrete about his heart. Others use another argument to prove it cold, and that is drawn from the compolition thereof, because it consists of Lead and other cold metals. But this argument is very weak. For unquencht Lime is made of flints and stony matter, which is cold, yet nevertheless it exceeds in heat. *Paracelsus* affirmeth, that Quick-silver is hot in the interior substance, but cold in the exterior, that is, cold as it comes forth of the *Mine*. But that coldness to be lost as it is prepared by art, and heat only to appear and be left therein, so that it may serve instead of a tincture in the transmutation of metals. And verily it is taken for a Rule amongst Chymists, that all metals are outwardly cold, by reason of the watery substance that is predominant in them, but that inwardly they are very hot, which then appears when as the coldness together with the moisture is segregated; for by calcination they become caustick. Moreover many account quick-silver poison, yet experience denies it. For *Marianus Sanctius Boralitanus* tells that he saw a woman, who for certain causes and effects, would at several times drink one pound and a half of quick-silver, which came from her again by stool without any harm. Moreover he affirmeth that he hath known sundry who in a desperate Colick (which they commonly call *miserere mei*) have been freed from imminent death, by drinking three pounds of quick-silver with water only: For by the weight it opens and unfolds the twined or bound up gut, and thrusts forth the hard and stopping excrements; he addeth that others have found this medicine effectual against the colick, drunk in the quantity of three ounces. *Antonius Musa* writes, that he usually giveth Quick-silver to children ready to die of the worms. *Avicen* confirmeth this, averring that many have drunk Quick-silver without any harm, wherefore he mixeth it in his ointments against scales and scabs in little children; whence came that common medicine amongst country people to kill lice by anointing the head with Quick-silver mixed with butter or *axungia*, *Matthiolus* affirmeth that many think it the last and chiefest remedy to give to women in travel that cannot be delivered. I protest to satisfie my self concerning this matter, I gave to a whelp pound of Quick-silver, which being drunk down, it voided without any harm by the belly. Whereby you may understand that it is wholly without any venemous quality. Verily it is the only and true Antidote of the *Lues venerea*, and also a very fit medicine for all malign ulcers, as that which more powerfully impugns their malignity than any other medicines that work only by their first qualities. Besides, against that contumacious scab, which is vulgarly called *Malum sancti manis*, there there is not any more speedy or certain remedy. Moreover *Guido* writes, that if a plate of lead be besmeared or rubbed therewith, and then for some space laid upon an ulcer, and conveniently fastned, that it will soften the callous hardness of the lips thereof, and bring it to cicatrization, which thing I my self have often found true by experience. *In l. 6. Dios. c. 2.* An History. *Lib. 4. de nat. rerum.* *Tract. de casu & offen.* Quick-silver good for women in travel. For the disease called *Malum sancti manis.*

Certainly before *Guido*, *Galen* much commended Quick-silver against malign ulcers and cancers: Neither doth *Galen* affirm that lead is poysonous (which many affirm poysonous, because it consists of much Quick-silver) but he only saith thus much, that water too long kept in leaden pipes and cisterns by reason of the drossiness that it useth to gather in lead, causeth bloody fluxes, which also is familiar to brass and copper. Otherwise many could not without danger bear in their bodies leaden bullets during the space of so many years, as usually they do. It is reported. It is declared by *Theodoret Herey* in the following histories, how powerful Quick-silver is to resolve and asswage pain and inflammations. Not long since, (saith he) a certain Doctor of Physick his boy was troubled with *parotides*, with great swelling, heat, pain and beating; to him by the common consent of the Physicians there present, I applied an *Anodyne* medicine, whose force was so great, that the tumor manifestly subsided at the first dressing, and the pain was much asswaged. At the second dressing all the symptoms were more mitigated. At the third dressing, I wondring, at the so great effect of *Lib de comp. med. secund. loc.* Against malign ulcers. Against the *Parotides.*

an

an *Anodyne* Cataplasm, observed that there was Quick-silver mixed therewith, and this happened through the negligence of the Apothecary, who mixed the simple *Anodyne* medicine prescribed by us, in a mortar wherein but a while before he had mixed an ointment whereinto Quick-silver had entred, whose reliques, and some part thereof yet remained therein. This which once by chance succeeded well, I afterwards wittingly and willingly used to a certain Gentlewoman troubled with the like disease, possessing all the region behind the ears, much of the throat, and a great part of the cheek, when as nature helped by common remedies, could not evacuate neither by resolution nor suppuration, the contained matter greatly vexing her with pain and pulsation; I to the medicine formerly used, by the consent of the Physicians, put some Quick-silver, so within a few days, the tumor was digested and resolved. But some will say it resolves the strength of the nerves and limbs, as you may see by such as have been anointed therewith for the *Lues venerea*, who tremble in all their limbs during the rest of their lives. This is true, if any use it too intemperately without measure, and a disease that may require so great a remedy; for thus we see the Gilders, Plumbers, and such as dig in mines, by the continual ascent of the vapors of Quick silver to the brain, the fountain of the nerves, by resolving the spirits, and dissipating the radical and substantifick moisture, maketh them subject to the trembling of their joints. Verily, if it be killed and incorporate with hogs-grease, and a list besmeared therewith, which may encompass the body like a girdle, it will drive away lice, fleas and *cimices*; and anointed about the navel, it kills the worms in the guts. There are two sorts of Quick-silver, the one natural, the other artificial. The natural is found running or flowing in the veins and bowels of the earth, and amongst metals, and in the fornaces of silver-mines. The Artificial is made of *minium* (as it is in *Vitruvius*) and of the powder of Ivory. Also it is probable that by art it may be extracted out of all metals, but chiefly out of Lead and *Cinnabaris*. You may easily distinguish these kinds by the dull and blackish colour, tough and gross substance, which as it runs, leaves an impression like melted grease, being as it were the excrement of lead. The best Quick-silver of all is pure, clear, thin, and very white: it may be cleansed with the dross of lead, and becomes more then being boiled in sharp vinegar, with *sage*, *rosemary*, *tyme*, *lavender*, Or else give it by a pound at a time to a whelp to drink down, and being cast forth by it, boil it again in vinegar, for thus it hath wondrous faculties, and fitly given produceth marvelous effects; nothing is more contrary thereto than fire. For Quick-silver though of its own nature ponderous, flieth upwards by the force of the fire, and forsaketh gold by that means, than which nothing is more friendly to it.

Against lice and flies, &c. The kinds thereof.

How to purifie it.

CHAP. XXXIX.

Of the Unicorns Horn.

There are very many at this day who think themselves excellently well armed against poyson and all contagion, if they be provided with some powder of Unicorns-horn, or some infusion made therewith. Therefore I have though it good to examine more diligently how much truth this inveterate, and grounded opinion hath. The better to perform this task, I will propound three heads, whereto I will direct my whole discourse. The first shall be of the signification of this word *Unicorn*. The second, whether there be any such thing really and truly so called, or whether it be not rather imaginary; like as the *Chimera* and *Tragelaphus*? The third, whether that which is said to be the horn of such a beast, hath any force or faculty against poysons? For the first, that is, the name, it is somewhat more obscure what the word (being *Licorn*) in French may signifie, than what the Latin or Greek word is. For the French name is further from the word and signification; but it is so clear and manifest, that this word *Unicornis* amongst the Latines signifieth a beast having but one horn, as it is vulgarly known; the same thing is meant by the Greek word *Monoceros*. But now for the second, I think that beast that is vulgarly called and taken for an Unicorn, is rather a thing imaginary than really in the world. I am chiefly induced to believe thus, by these conjectures. Because of those who have travelled over the world, there is not one that professeth that ever he did see that creature. Certainly the *Romans* conquered the world, and being most diligent searchers after all things which were rare and so excellent, if any where in any corner of the world this beast could have been found, they would have found it out, and engraven it upon their coins, or arms, as they did Crocodiles, Elephants, Eagles, Panthers, Lions, Tigers, and other creatures unknown to these countries. For these that have written of the Unicorn, either that they have heard, or that hath been delivered by tradition, or what they in their minds and fancies have conceived, you shall scarce find two that agree together, either in the description of the body, or in the nature and condition of her. *Pliny* writes, that Unicorns are for the fashion of their bodies like to an horse; that is, as *Cardane* interprets it, of the bigness of an Horse, with the head of an Hart, the feet of an Elephant, the tail of a *Boar*, with one black horn in the midst of his forehead, of the length of two cubits. *Munster*, who (as *Matthiolus* jests) never saw Unicorns besides painted ones, doth on the contrary affirm them not to be of the bigness of an Horse, but of an Hind-calf of three months old, not with feet like an Elephant, but cleft like those of Goats, with an horn not only of two, but oft-times of three cubits long, of a Weazle-colour, with a neck not very long, nor very hairy, but having few and short hairs hanging to the one side of the neck, the legs are lean and small, the buttocks high, but very hairy. *Cardane* dissenting from both these, writes that he hath an horn in the midst of his forehead, but that it is only of the length of three fingers. *Andrew Thevet* mentions an Unicorn seen by a certain Turkish Sanjach, which was of the bigness of a Bull, of five or six months old, and had one horn, but that not in the midst of his forehead, but upon the top of the crown of the head; he was legged and footed like an Ass, but longer haired, and had ears not much unlike the *Rangifer*, a beast not unknown in the *subpolar* or Northern countries.

What the name imports.

That there is no such beast as an *Unicorn*.

Lib. 8. *cap.* 21.

Munsters opinion concerning *Unicorns*.

Tom. 1. *lib.* 5. *Cap.* 5. *cosmogr.*

Thus

Thus various therefore is the report concerning the shape of this Beast. Neither is there less difference concerning her nature and conditions. For *Pliny* writes, that the Unicorn is a most fierce beast, and hath a great bellowing voice, and that she cannot therefore be taken alive. *Cardane* renders a reason of this fierceness, *Because* (saith he) *it inhabits the deserts of* Æthiopia, *a region squalid, and filthy, abounding with Toads, and such like venemous creatures.* Others on the contrary affirm her to be of a most mild, amiable, and gentle nature of all others, unless one purposely offend her, or use her too harshly, for seeing she feeds not by stooping her head to the ground, because she is hindred therefrom by the length of her horn, she must necessarily feed upon the fruit that hangeth upon trees; out of cratches or mans hand she fearlesly and harmlesly takes all manner of fruits, herbs, sheaves of corn, apples, pears, oranges and pulse. And herein they have proceeded so far, that they feign they will love Virgins, entised by their beauty, so that stayed in the contemplation of them, and allured by their enticements, they by this means are often taken by hunters. In this opinion is *Lues Vartoman*, who denies that Unicorns are wild or fierce; for he saith, that he saw two, which were sent out of *Æthiopia* to the Sultan, who kept them shut up in Penns, in *Mecha*, a city of *Arabia Felix*, renowned by the Sepulcher of *Mahomet*. *Thevet* travelling thither, tells that he diligently inquired of the inhabitants, what their opinion was of such a beast, yet could he never hear any tidings thereof. Whence it is easie to discern, that such beasts have neither been in our, nor in *Vartomans* times. The so great variety of dissenting opinions, easily induceth me to believe that this word, *Unicorn*, is not the proper name of any beast in the world, and that it is a thing only feigned by Painters, and Writers of natural things, to delight the readers and beholders. For as there is but one right way, but many by-ways, and windings, so the speech of truth is but one, and that always simple and like it self; but that of a lie is diverse, and which may easily refel it self, by the repugnancy and incongruity of opinions, if one should say nothing. What therefore (will some say of what creatures) are these horns, which we see wholly different from others, if they be not of Unicorns? *Thevet* thinks them nothing else than Elephants bones turned and made into the fashion that we see them, for thus in the Eastern Countries, some crafty merchants and cunning companions turn, hollow, and being softned, draw to what length these please the teeth of the fish *Rohard*, which lives in the Red and *Æthiopian* Sea, and being so handled, they sell them for Unicorns horn. Verily that which is termed Unicorns horn, being burnt, sends forth a smell like to Ivory. Now *Cardanus* affirms that the teeth and bones of Elephants made soft by art, may be drawn forth, and brought into what form you please like as Ox-bones are. For what is there in the world which the thirsting desire of gold will not make men to adulterate and counterfeit; But it is time that we come to the third scope. Grant there be Unicorns; must it therefore follow that their horns must be of such efficacy against poysons? If we judg by events, and the experience of things, I can protest thus much, that I have often made trial thereof, yet could I never find any good success in the use thereof against poysons, in such as I have had in cure. If the matter must be tried by witnesses and authorities, a great part of the Physicians of better note have long since bid it adieu, and have detracted from the divine and admirable vertues for which it formerly was so much desired. And this they have done, moved thereto by many just, but two especial reasons. The first is of *Rondeletius*, who in this case affirms that horns are endued with no taste nor smell; and therefore have no effect in Physick, unless it be to dry: neither (saith he) am I ignorant that such as have them, much predicate their worth, so to make the greater benefit and gain by them, as of the shavings or scrapings of Unicorns horn, which they sell for the weight in gold, as that which is singular good against poysons and worms, which things, I think, Harts-horn and Ivory do no less effectually perform; which is the cause why, for the same disease, and with the like success, I prescribe Ivory to such as are poor, and Unicorns horn to the rich, as that they so much desire. This is the opinion of *Rondeletius*, who, without any difference, was wont, for Unicorns horn, to prescribe not only Harts-horn or Ivory, but also the bones of Horses and Dogs, and the stones of Myrobalanes, Another reason is, that whatsoever resists poyson is cordial, that is, fit to strengthen the heart, which is chiefly assailed by poysons; but nothing is convenient to strengthen the heart, unless it be by laudable blood or spirit, which two are only familiar to the heart, as being the work-house of the arterious blood and vital spirits: For all things are preserved by their like, as they are destroyed by their contraries, for all things that generate, generate things like themselves. But Unicorns horn, as it contains no smell, so neither hath it any aery parts, but is wholly earthy and dry; neither can it be converted into blood by the digestive faculty, for as it is without juice, so is it without flesh: For as it cannot be turned into *Chylus*, so neither is it fit to become *Chymus*, that is, juice or blood. Therefore it is joyned to the heart by no similitude, nor familiarity. Furthermore there is not a word in *Hippocrates* and *Galen* concerning the Unicorns horn, who notwithstanding have in so many places, commended Harts-horn. Therefore D. *Chapelain*, the chief Physician of King *Charles* the ninth often used to say, that he would very willingly take away that custom of dipping a piece of Unicorns horn in the Kings cup, but that he knew that opinion to be so deeply ingrafted in the minds of men, that he feared, that it would scarce be impugned by reason. Besides (he said) if such a superstitious medicine do no good, so certainly it doth no harm, unless it be to their estates that buy it with gold; or else by accident, because Princes, whilst they relie more than is fitting upon the magnified vertues of this horn, neglect to arm themselves against poysons by other more convenient means, so that death oft-times takes them at unawares. When as upon a time I inquired of *Lues Duret* the Kings Physician and Professor (by reason of the great opinion that all learned men justly had of his learning and judgment) what he thought of this horn; He answered that he attributed no faculties thereto; for the confirmation whereof he rendred the second reason I have formerly given, but more largely and elegantly; neither feared he to affirm it aloud, and in plain words to his auditory of learned men, coming from all parts to hear him. But if at any time (orecome by the fault of the times and place) he prescribed this horn; that he did it for no other intent, than to help faint-

Vartomans opinion of the nature of the *unicorn.*

What the ordinary *unicorns* horns are

The *unicorns* horn is not effectual against poyson.

Lib. de pondr. cap. 19.

Horns and bones not effectual unless to dry.

In what cases good.

ings

ings or ſwoundings that happen by the abundance of ſerous humors, floating in the orifice of the ventricle, which makes men ill diſpoſed, becauſe this mixed with other things endued with the like faculty, hath power to drink up the wateriſh humidity by its earthy drineſs. But ſome will reply, that neither the *Lemnian*, nor *Armenian* earth, have any juice in them, neither any ſmell, nor aery ſpirit. It is granted; neither truly are ſuch things truly and properly called cordial, but only by event and accident, for that by the excellent and aſtrictive faculty they have, and ſtopping the paſſages of the veſſels, they hinder the poiſon from entring into the heart. This is my opinion of the Unicorns horn, which if any do not approve of, he ſhall do me a favour, if for the publick good, he ſhall freely oppoſe his; but in the *interim* take this in good part which I have done.

The end of the one and twentieth Book.

BOOK XXII.

Of the PLAGUE.

CHAP. I.

The deſcription of the Plague.

What the Plague is.

THe Plague is a cruel and contagious diſeaſe, which every where, like a common diſeaſe, invading Man and Beaſt, kills very many; being attended, and as it were aſſociated with a continual Feaver, Botches, Carbuncles, Spots, Nauſeouſneſs, Vomitings, and other ſuch malign accidents. This diſeaſe is not ſo pernicious or hurtful, by any elementary quality, as from a certain poyſonous and venenate malignity, the force whereof exceeds the condition of common putrefaction; Yet I will not deny, but that it is more hurtful in certain bodies, times and regions, as alſo many other diſeaſes, of which *Hippocrates* makes mention. But from hence we can only collect, that the force and malignity of the plague may be encreaſed, or diminiſhed, according to the condition of the elementary qualities concurring with it; but not the whole nature and eſſence thereof to depend thereon.

Sect. 3. *aphor.*

How it comes to kill.

This peſtiferous poyſon principally aſſails the vital ſpirit, the ſtore-houſe and original whereof is the heart, ſo that if the vital ſpirit prove ſtronger, it drives it far from the heart; but if weaker, it being overcome and weakned by the hoſtile aſſault, flies back into the fortreſs of the heart, by the like contagion infecting the heart, and ſo the whole body, being ſpread into it, by the paſſages of the arteries.

Hence it is, peſtilent feavers are ſometime ſimple and ſolitary; otherwhiles aſſociated with a troop of other affects, as Botches, Carbuncles, Blanes and Spots, of one or more colours.

The original of buboes, carbuncles, &c. in the plague.

It is probable ſuch affects have their original from the expulſive faculty, whether ſtrong or weak, provoked by the malignity of the raging matter: yet aſſuredly divers ſymptoms and changes ariſe, according to the conſtitution of the body of the patient, and condition of the humor in which the virulency of the plague is chiefly inherent, and laſtly in the nature of the efficient cauſe.

I thought good, by this deſcription, to expreſs the nature of the Plague, at this my firſt entrance into this matter; for we can ſcarce comprehend it in a proper definition. For although the force thereof be definite, and certain in nature, yet it is not altogether certain and manifeſt in mens minds, becauſe it never happens after one ſort: ſo that in ſo great variety, it is very difficult to ſet down any thing general and certain.

CHAP. II.

Of the Divine cauſes of an extraordinary Plague.

IT is a confirmed, conſtant, and received opinion in all Ages amongſt Chriſtians, that the plague and other diſeaſes, which violently aſſail the life of man, are often ſent by the juſt anger of God puniſhing offences. The Prophet *Amos* hath long ſince taught it, ſaying, *Shall there be affliction? Shall there be evil in a City, and the Lord hath not done it?* On which truly we ought daily to meditate, and that for two cauſes: The firſt is, that we always bear this in mind, that we enjoy health; live, move, and have our beings from God; and that it deſcends from that Father of Light; and for this cauſe we are always bound to give him great and exceeding thanks. The other is, that knowing the calamities, by ſending whereof the Divine anger proceeds to revenge, we may at length repent, and leaving the way of wickedneſs, walk in the paths of Godlineſs. For thus we ſhall learn to ſee in God, our ſelves, the Heaven and Earth, the true knowledge of the cauſes of the plague, and by a certain Divine Philoſophy, teach God to be the beginning and cauſe of the ſecond cauſes, which we cannot well without the firſt cauſe go about nor attempt, much leſs perform any thing. For from hence they borrow their force, order, and conſtancy of order; ſo that they ſerve as inſtruments for God, who rules and governs us, and the whole world to perform all his works, by that conſtant courſe of order, which he hath appointed unchangeable from the beginning.

Amos 3. *Alis* 17.

The ſecond cauſes have their power from God as the firſt cauſe.

Wherefore

Wherefore all cauſe of a plague is not to be attributed to theſe near and inferior cauſes or beginnings, as the Epicures and Lucianiſts commonly do, who attributing too much, yea all things to Nature, hath left nothing to Gods providence. On the contrary, we ought to think, and believe in all our doings, That even as God by his omnipotent Power hath created all things of nothing, ſo he by his eternal Wiſdom preſerves and governs the ſame, leads and inclines them as he pleaſeth, yea verily at his pleaſure changeth their order, and the whole courſe of nature.

This cauſe of an extraordinary Plague, as we confeſs and acknowledge, ſo here we will not proſecute it any further, but think fit to leave it to Divines, becauſe it exceeds the bounds of Nature, in which I will now contain my ſelf. Wherefore let us come to the natural cauſes of the Plague.

CHAP. III.

Of the Natural cauſes of the Plague, and chiefly of the Seminary of the Plague by the corruption of the Air.

THE general and natural cauſes of the Plague are abſolutely two, that is, the infection of corrupt air, and a preparation and fitneſs of corrupt humors to take that infection; for it is noted before, out of the doctrine of *Galen*, that our humors may be corrupted, and degenerate into ſuch an alienation as may equal the malignity of poyſon. The general cauſes of the Plague. *Lib. 6. de loc. affectis.*

The air is corrupted, when the four ſeaſons of the year have not their ſeaſonableneſs, or degenerate from themſelves, either by alteration or by alienation: as if the conſtitution of the whole year be moiſt and rainy, by reaſon of groſs and black clouds; if the Winter be gentle and warm, without any Northerly wind, which is cold and dry, and by that means contrary to putrefaction: if the Spring which ſhould be temperate, ſhall be faulty in any exceſs of diſtemper; if the Autumn ſhall be ominous by fires in the air, with ſtars ſhooting, and as it were falling down, or terrible comets, never ſeen without ſome diſaſter; if the ſummer be hot, cloudy and moiſt, and without winds, and the clouds flie from the South into the North. Theſe and ſuch like unnatural conſtitutions of the ſeaſons of the year, were never better, or more excellently handled by any, than by *Hippocrates* in his Books *Epidemion*. Therefore the air from hence draws the ſeeds of corruption and the peſtilence, which at length, the like exceſs of qualities being brought in, it ſends into the humors of our bodies, chiefly ſuch as are thin and *ſerous*; although the peſtilence doth not always neceſſarily ariſe from hence, but ſome-whiles ſome other kind of cruel and infectious diſeaſe. How the Seaſons of the year may be ſaid to want their ſeaſonableneſs.

But neither is the air only corrupted by theſe ſuperiour cauſes, but alſo by putrid and filthy ſtinking vapors ſpread abroad through the air encompaſſing us, from the bodies and carkaſſes of things not buried, gapings and hollowneſſes of the earth, or ſinks and ſuch like places being opened: for the ſea often overflowing the land in ſome places, and leaving in the mud or hollowneſſes of the earth (cauſed by earth-quakes) the huge bodies of monſtrous fiſhes, which it hides in its waters, hath given both the occaſion and matter of a plague. For thus in our time, a Whale caſt upon the *Tuſcan* ſhore, preſently cauſed a plague over all that countrey. How the air may be corrupted.

But as fiſhes infect and breed a plague in the air, ſo the air being corrupted often cauſeth a peſtilence in the ſea among fiſhes, eſpecially when they either ſwim on the top of the water, or are infected by the peſtilent vapors of the earth lying under them, and riſing into the air through the body of the water, the latter whereof *Ariſtotle* ſaith, hapneth but ſeldom. But it often chanceth, that the plague raging in any country, many fiſhes are caſt upon the coaſt, and may be ſeen lying on great heaps. But ſulphureous vapors, or ſuch as partake of any other malign quality, ſent forth from places under ground, by gapings and gulfs opened by earth-quakes, not only corrupt the air, but alſo infect and taint the ſeeds, plants, and all the fruits which we eat, and ſo transfer the peſtilent corruption into us, and thoſe beaſts on which we feed, together with our nouriſhment. The truth whereof *Empedocles* made manifeſt, who by ſhutting up a great gulf of the earth, opened in a valley between two mountains, freed all *Sicily* from a plague cauſed from thence. *Lib. 8. hiſt. anim.*

If winds riſing ſuddenly ſhall drive ſuch filthy exhalations from thoſe regions in which they were peſtiferous, into other places, they alſo will carry the plague with them thither.

If it be thus, ſome will ſay, it ſhould ſeem that whereſoever ſtinking and putrid exhalations ariſe, as about ſtanding pools, ſinks and ſhambles, there ſhould the plague reign, and ſtraight ſuffocate with its noyſome poyſon the people which work in ſuch places: but experience finds this falſe.

We do anſwer that the Putrefaction of the Plague is far different, and of another kind than this common, as that which partakes of a certain ſecret malignity, and wholly contrary to our lives, and of which we cannot eaſily give a plain and manifeſt reaſon. Yet that vulgar putrefaction whereſoever it, doth eaſily and quickly entertain and welcome the peſtiferous contagion, as often as, and whenſoever it comes, as joined to it by a certain familiarity, and at length, it ſelf degenerating into a peſtiferous malignity, certainly no otherwiſe than thoſe diſeaſes which ariſe in the plague time, the putrid diſeaſes in our bodies, which at the firſt wanted virulency and contagion, as Ulcers, putrid Feavers, and other ſuch diſeaſes, raiſed by the peculiar default of the humors, eaſily degenerate into peſtilence, preſently receiving the tainture of the plague, to which they had before a certain preparations. Wherefore in time of the Plague, I would adviſe all men to ſhun ſuch exceeding ſtinking places, as they would the plague it ſelf, that there may be no preparation in our bodies, or humors to catch that infection (without which, as *Galen* teacheth, the Agent hath no power over the Subject, for otherwiſe in a plague-time, the ſickneſs would equally ſeize upon all) ſo that the impreſſion of the peſtiferous quality may preſently follow that diſpoſition. Peſtiferous putrefaction is far different from ordinary putrefaction. In a peſtilent conſtitution of the air, all diſeaſes become peſtilent. *Lib. 1. de diffr. feb.*

We

How the air may be ſaid to putrefie.

But when we ſay the air is peſtilent, we do not underſtand that ſincere, elementary, and ſimple, as it is of its own nature, for ſuch is not ſubject to putrefaction; but that which is polluted with ill vapors riſing from the earth, ſtanding waters, vaults, or ſea, and degenerates, and is changed from its native purity and ſimplicity. But certainly amongſt all the conſtitutions of the air, fit to receive a peſtilent corruption, there is none more fit than an hot, moiſt and ſtill ſeaſon; for the exceſs of ſuch qualities eaſily cauſeth putrefaction. Wherefore the ſouth wind reigning, which is hot and moiſt, and principally in places near the ſea, there fleſh cannot long be kept, but it preſently is tainted and corrupted

A Southerly conſtitution of the air is the fuel of the Plague.

Ferther, we muſt know, that the peſtilent malignity which riſeth from the carkaſſes or bodies of men, is more eaſily communicated to men; that which riſeth from oxen, to oxen; and that which comes from ſheep, to ſheep; by a certain ſympathy and familiarity of Nature: no otherwiſe than the Plague which ſhall ſeize upon ſome one in a Family, doth preſently ſpread more quickly amongſt the reſt of the Family, by reaſon of the ſimilitude of temper, then amongſt others of an other Family, diſagreeing in their whole temper. Therefore the air thus altered and eſtranged from its goodneſs of nature, neceſſarily drawn in by inſpiration and tranſpiration, brings in the ſeeds of the Plague, and ſo conſequently the Plague it ſelf, into bodies prepared and made ready to receive it.

CHAP. IV.

Of the preparation of humors to putrefaction, and admiſſion of peſtiferous impreſſions.

HAving ſhewed the cauſes from which the air doth putrifie, become corrupt, and is made partaker of a peſtilent and poyſonous conſtitution; we muſt now declare what things may cauſe the humors to putrifie, and make them ſo apt to receive and retain the peſtilent air and venenate quality.

Three cauſes of the putrefaction of humors.

Humors putrifie either from fulneſs, which breeds obſtruction, or by diſtemperate exceſs; or laſtly, by admixture of corrupt matter and evil juice, which ill feeding doth ſpecially cauſe to abound in the body: for the Plague often follows the drinking of dead and muſty wines, muddy and ſtanding waters, which receive the ſinks and filth of a City; and fruits and pulſe eaten without diſcretion in ſcarcity of other corn, as Peaſe, Beans, Lentils, Vetches, Acorns, the roots of Fern, and Graſs made into Bread: For ſuch meats obſtruct, heap up ill humors in the body, and weaken the ſtrength of the faculties, from whence proceeds a putrefaction of humors, and in that putrefaction a preparation and diſpoſition to receive, conceive, and bring forth the ſeeds of the Plague: which the filthy ſcabs, malign ſores, rebellious ulcers and putrid feavers, being all fore-runners of greater putrefaction and corruption, do teſtifie. Vehement paſſions of the mind, as anger, ſorrow, grief, vexation and fear, help forward this corruption of humors, all which hinder natures diligence and care of concoction: For as in the Dog-days, the lees of wine ſubſiding to the bottom, are by the ſtrength and efficacy of heat, drawn up to the top, and mixed with the whole ſubſtance of the wine, as it were by a certain ebullition, or working; ſo melancholick humors, being the dregs or lees of the blood, ſtirred by the paſſions of the mind, defile or taint all the blood with their feculent impurity.

Paſſions of the mind help forward the Putrefaction of the humors.

We found that, ſome years agon by experience, at the battel of S. *Dennis*. For all wounds, by what weapon ſoever they were made, degenerated into great and filthy putrefactions and corruptions, with feavers of the like nature, and were commonly determined by death, what medicines and how diligently ſoever they were applied; which cauſed many to have a falſe ſuſpition that the weapons on both ſides were poyſoned. But there were manifeſt ſigns of corruption and putrefaction in the bloud let the ſame day that any were hurt, and in the principal parts diſſected afterwards that it was from no other cauſe, than an evil conſtitution of the air, and the minds of the Souldiers perverted by hate, anger and fear.

CHAP. V.

What ſigns in the Air and Earth prognoſticate a Plague.

WE may know a plague to be at hand and hang over us, if at any time the air and ſeaſons of the year ſwerve from their natural conſtitution, after thoſe ways I have mentioned before; if frequent and long continuing Meteors, or ſulphureous Thunders infect the air; if fruits, ſeeds, and pulſe be worm-eaten: if birds forſake their neſts, eggs, or young, without any manifeſt cauſe; if we perceive women commonly to abort, by continual breathing in the vaporous air, being corrupted and hurtful both to the Embryon and original of life, and by which it being ſuffocated, is preſently caſt forth and expelled. Yet notwithſtanding thoſe airy impreſſions do not ſolely corrupt the air, but there may be alſo others raiſed by the Sun from the filthy exhalations and poyſonous vapors of the earth and waters, or of dead carkaſſes, which by their unnatural mixture, eaſily corrupt the air, ſubject to alteration, as that which is thin and moiſt, from whence divers Epidemical diſeaſes, and ſuch as are every where ſeize upon the common ſort, according to the ſeveral kinds of corruptions, ſuch as that famous *Catarrh* with difficulty of breathing, which in the year 1510 went almoſt all over the world, and raged over all the Cities and Towns of *France*, with great heavineſs of the head (whereupon the French named it *Cuculla*) with a ſtraitneſs of the heart and lungs, and a cough, a continual feaver, and ſometimes raving.

Why aborti-ons are frequent in a peſtilent ſeaſon.

A *Catarrh* with difficulty of breathing killing many.

This, although it ſeized upon many more than it killed, yet becauſe they commonly died who were either let bloud, or purged, it ſhewed it ſelf peſtilent by that violent and peculiar and unheard of kind of malignity.

Such

Such alſo was the Engliſh *Sweating-ſickneſs*, or *Sweating-feaver*, which unuſual, with a great deal of terror invaded all the lower parts of *Germany*, and the Low-Countries, from the year 1525 unto the year 1530, and that chiefly in Autumn. The Engliſh *Sweating-ſickneſs.*

As ſoon as this peſtilent diſeaſe entred into any City, ſuddenly two or three hundred fell ſick on one day; then it departed thence to ſome other place. The people ſtrucken with it, languiſhing, fell down in a ſwound, and lying in their beds, ſweat continually, having a feaver, a frequent, quick, and unequal pulſe; neither did they leave ſweating, till the diſeaſe left them, which was in one or two days at the moſt: yet freed of it, they languiſhed long after; they all had a beating or palpitation of the heart, which held ſome two or three years, and others all their life after.

At the firſt beginning it killed many, before the force of it was known: but afterwards very few, when it was found out by practice and uſe, that thoſe who furthered and continued their ſweats, and ſtrengthened themſelves with cordials, were all reſtored. But at certain times many other popular diſeaſes ſprung up, as putrid feavers, fluxes, bloudy-fluxes, catarrhs, coughs, phrenſics, ſquinances, plurifies, inflammations of the lungs, inflammations of the eyes, apoplexies, lethargies, ſmall pox and meazles, ſcabs, carbuncles, and malign puſtles. Wherefore the Plague is not always, nor every where of one and the ſame kind, but of divers; which is the cauſe that divers names are impoſed upon it, according to the variety of the effects it brings, and ſymptoms which accompany it, and kinds of putrefaction, and hidden qualities of the air. The Plague is not the definite name of one diſeaſe.

They affirm, when the Plague is at hand, that Muſhroms grow in greater abundance out of the Earth, and upon the ſurface thereof many kinds of poyſonous *inſecta* creep in great numbers, as Spiders, Catterpillars, Butter-flies, Graſhoppers, Beetles, Hornets, Waſps, Flies, Scorpions, Snails, Locuſts, Toads, Worms, and ſuch things as are the off-ſpring of putrefaction. And alſo wild beaſts tired with the vaporous malignity of their dens and caves in the Earth, forſake them, and Moles, Toads, Vipers, Snakes, Lizards, Aſps and Crocodiles are ſeen to flie away, and remove their habitations in great troops. For theſe, as alſo ſome other creatures, have a manifeſt power by the gift of God, and the inſtinct of Nature, to preſage changes of weather, as rains, ſhowers, and fair weather, and ſeaſons of the year, as the Spring, Summer, Autumn, Winter, which they teſtifie by their ſinging, chirping, crying, flying, playing, and beating with their wings, and ſuch like ſigns: ſo alſo they have a perception of a Plague at hand. And moreover, the carkaſſes of ſome of them which took leſs heed of themſelves, ſuffocated by the peſtiferous poyſon of the ill air contained in the earth, may be every where found, not only in their dens, but alſo in the plain fields. What ſigns in the earth foretell a plague,

Theſe vapors corrupted not by a ſimple putrefaction, but an occult malignity, are drawn out of the bowels of the earth into the air, by the force of the Sun and Stars, and thence condenſed into clouds, which by their falling upon corn, trees and graſs, infect and corrupt all things which the earth produceth, and alſo kills thoſe creatures which feed upon them; yet brute beaſts ſooner than men, as which ſtoop and hold their heads down towards the ground (the maintainer and breeder of this poyſon) that they may get their food from thence. Therefore at ſuch times, skilful husbandmen, taught by long experience, never drive their Cattel or Sheep to paſture, before that the Sun, by the force of his beams, hath waſted and diſſipated into air, this peſtiferous dew hanging and abiding upon the boughs and leaves of trees, herbs, corn and fruits. How peſtilent vapors may kill plants and trees.

But on the contrary, that peſtilence which proceeds from ſome malign quality from above, by reaſon of evil and certain conjunction of the Stars, is more hurtful to men and birds, as thoſe who are nearer to Heaven.

CHAP. VI.

By uſing what cautions in Air and diet, one may prevent the Plague.

HAving declared the ſigns foreſhewing a Peſtilence: now we muſt ſhew by what means we may ſhun the imminent danger thereof, and defend our ſelves from it. No prevention ſeemed more certain to the Antients, than moſt ſpeedily to remove into places far diſtant from the infected place, and to be moſt ſlow in their return thither again. But thoſe, who by reaſon of their buſineſs or imployments, cannot change their habitation, muſt principally have a care of two things. The firſt is, that they ſtrengthen their bodies, and the principal parts thereof, againſt the dayly imminent invaſions of the poyſon, or the peſtiferous and venenate Air. The other, that they abate the force of it, that it may not imprint its virulency in the body; which may be done by correcting the exceſs of the quality inclining towards it, by the oppoſition of its contrary: For if it be hotter than is meet, it muſt be tempered with cooling things; if too cold, with heating things: yet this will not ſuffice: For we ought beſides, to amend and purge the corruptions of the venenate malignity diffuſed through it, by ſmells and perfumes reſiſting the poyſon thereof. The body will be ſtrengthened and more powerfully reſiſt the infected Air, if it want excrementitious humors, which may be procured by purging and bleeding; and for the reſt a convenient diet appointed, as ſhunning much variety of meats, and hot and moiſt things, and all ſuch which are eaſily corrupted in the ſtomach, and cauſe obſtructions, ſuch as thoſe things which be made by Comfit-makers; we muſt ſhun ſatiety and drunkenneſs, for both of them weaken the powers, which are preſerved by the moderate uſe of meats of good juice. Change of places the ſureſt prevention of the Plague. Two things of chief account for prevention Diet for prevention of the Plague.

Let moderate exerciſes in a clear Air, and free from any venemous tainture, precede your meals.

Let the belly have due evacuation either by Nature or Art.

Let the heart, the ſeat of life, and the reſt of the bowels be ſtrengthened with Cordials and Antidotes applied and taken (as we ſhall hereafter ſhew) in the form of epithems, ointments, emplaſters, waters, pills, powders, tablets, opiates, fumigations, and ſuch like.

Make choice of a pure air, and free from all pollution, and far remote from ſtinking places, for

Diſcommodities of a cloudy or foggy Air.

ſuch as is moſt fit to preſerve life, to recreate and repair the ſpirits, whereas on the contrary, a cloudy, or miſty Air, and ſuch as is infected with groſs and ſtinking vapors, dulls the ſpirits, dejects the appetite, makes the body faint and ill coloured, oppreſſeth the heart, and is the breeder of many diſeaſes.

Why the South wind is peſtilent.

The Northern wind is healthful, becauſe it is cold and dry. But on the contrary, the Southern wind becauſe it is hot and moiſt, weakens the body by ſloth or dulneſs, opens the pores, and makes them pervious to the peſtiferous malignity. The Weſtern wind is alſo unwholſome, becauſe it comes near to the nature of a Southern: wherefore the windows muſt be ſhut up on that ſide of the houſe on which they blow, but open on the North and Eaſt ſide, unleſs it happen that the Plague come from thence.

The efficacy of fire againſt the Plague.

Kindle a clear fire in all the lodging Chambers of the houſe, and perfume the whole houſe with Aromatick things, as Frankincenſe, Myrrh, Benzoin, *Ladanum*, *Styrax*, Roſes, Myrtle-leaves, Lavender, Roſemary, Sage, Savory, wild Tyme, Marjoram, Broom, Pine-apples, pieces of Fir, Juniper-berries, Cloves, Perfumes: and let your cloaths be aired in the ſame.

There be ſome, who think it a great preſervative againſt the peſtilent Air, to keep a Goat in their houſes, becauſe the capacity of the houſe, filled with a ſtrong ſent which the Goat ſends forth, prohibits the entrance of the venomous Air: which ſame reaſon hath place alſo in ſweet ſmells; and beſides it argues, that ſuch as are hungry are apter to take the Plague than thoſe who have eaten moderately: for the body is not only ſtrengthened with meat, but all the paſſages thereof are full by the vapors diffuſed from thence, by which otherwiſe, the infected Air would find a more eaſie entrance to the heart.

Moderate repletion good for prevention

Yet the common ſort of people yield another reaſon for the Goat, which is, that one ill ſent drives away another, as one wedge drives forth another; which calleth to my mind that which is recorded by *Alexander Benedictus*, that there was a Scythian Phyſician, which cauſed a Plague, ariſing from the infection of the Air, to ceaſe, by cauſing all the Dogs, Cats, and ſuch like beaſts, which were in the City to be killed, and caſt their carkaſſes up and down the ſtreets, that ſo by the coming of this new putrid vapor as a ſtranger, the former peſtiferous infection, as an old gueſt was put out of its lodging, and ſo the Plague ceaſed. For Poyſons have not only an antipathy with their Antidotes, but alſo with ſome other poyſons.

A ſtrange Art to drive away the Plague.

The antipathy of poiſons with poiſons.

Whilſt the Plague is hot, it is good not to ſtir out of door before the riſing of the Sun: wherefore we muſt have patience, until he hath cleanſed the Air with the comfortable light of his beams, and diſperſed all the foggy and nocturnal pollutions, which commonly hang in the Air in dirty, and eſpecially in low places and Vallies.

All publick and great meetings and aſſemblies muſt be ſhunned.

Whether in the Plague-time one muſt travel by night or by day.

If the Plague begin in Summer, and ſeem principally to rage, being helped forward by the Summers heat, it is beſt to perform a journy begun, or undertaken for neceſſary affairs, rather upon the night time, than on the day; becauſe the infection takes force, ſtrength and ſubtility of ſubſtance, by which it may more eaſily permeat and enter in by the heat of the Sun; but by night mens bodies are more ſtrong, and all things are more groſs and denſe. But you muſt obſerve a clean contrary courſe, if the malignity ſeem to borrow ſtrength and celerity from coldneſs: But you muſt always eſchew the beams of the Moon, but eſpecially at the Full: for then our bodies are more languid and weak, and fuller of excrementitious humors. Even as trees which for that cauſe muſt be cut down in their ſeaſon of the Moon, that is, in the decreaſe thereof.

Why the Moon is to be ſhunned.

After a little gentle walking in your Chamber, you muſt preſently uſe ſome means that the principal parts may be ſtrengthned by ſuſcitating the heat and ſpirits, and that the paſſages to them may be filled, that ſo the way may be ſhut up from the infection coming from without. Such as by the uſe of garlick have not their heads troubled, nor their inward parts inflamed, as Country People and ſuch as are uſed to it: to ſuch there can be no more certain preſervative and Antidote againſt the peſtiferous fogs or miſts, and the nocturnal obſcurity, than to take it in the morning with a draught of good wine; for it being abundantly diffuſed preſently over all the body, fills up the paſſages thereof, and ſtrengthneth it in a moment.

Garlick good againſt the Plague.

For water; if the Plague proceed from the tainture of the Air, we muſt wholly ſhun and avoid Rain-water, becauſe it cannot but be infected by the contagion of the Air. Wherefore the water of Springs and of the deepeſt Wells are thought beſt. But if the malignity proceed from the vapors contained in the Earth, you muſt make choice of Rain-water. Yet it is more ſafe to digeſt every ſort of water by boyling it, and to prefer that water before other; which is pure and clear to the ſight, and without either taſte or ſmell, and which beſides ſuddenly takes the extremeſt mutation of heat and cold.

What water to be made choice of in the Plague time.

CHAP. VII.

Of the Cordial Remedies by which we may preſerve our Bodies in fear of the Plague, and cure thoſe already infected therewith.

Aqua Theriacalis good againſt the Plague both inwardly taken and outwardly applied.

Such as cannot eat without much labour, exerciſe and hunger, and who are no lovers of Breakfaſts, having evacuated their excrements, before they go from home muſt ſtrengthen the heart with ſome Antidote againſt the virulency of the infection. Amongſt which *Aqua Theriacalis*, or Treacle-water, two ounces, with the like quantity of Sack, is much commended being drunk, and rubbing the Noſtrils, Mouth and Ears with the ſame; for the Treacle-water ſtrengthens the heart, expels poyſon, and is not only good for a preſervative, but alſo to cure the diſeaſe it ſelf: For by ſweat it drives forth the poyſon contained within. It ſhould be made in *June*, at which time all ſimple medicines, by the vital heat of the Sun, are in their greateſt efficacy.

The

The compoſition whereof is thus: Take the roots of *Gentian*, *Ciperus*, Tormentil, Diptam, or *Fraxalla* Elecampane, of each one ounce; the leaves of Mullet, *Carduus Benedictus*, Devils-bit, Burnet, Scabious, Sheeps-ſorrel, of each half a handful; of the tops of *Rue* a little quantity; of Myrtle-berries one ounce; of red Roſe-leaves, the flowers of Bugloſs, Borage and S. *Johns* wort, of each one ounce; let them be all cleanſed, dried and macerated for the ſpace of twenty four hours in one pound of white wine or Malmſie, and of Roſe-water or Sorrel-water; then let them be put in a veſſel of glaſs, and add thereto of Treacle and Mithridate, of each four ounces: then diſtill them in *Balneo Mariæ*, and let the diſtilled water be received in a Glaſs-Viol, and let there be added thereto of Saffron two drams, of Bole-Armenick, *Terra Sigillata*, yellow Sanders, ſhavings of Ivory and Harts-horn, of each half an ounce; then let the Glaſs be well ſtopped, and ſet in the Sun for the ſpace of eight or ten days. Let the preſcribed quantity be taken every morning ſo oft as ſhall be needful. It may be given without hurt to ſucking children, and to Women great with child. But that it may be the more pleaſant, it muſt be ſtrained through an Hippocras-bag, adding thereto ſome ſugar and cinnamon. The compoſition thereof.

Some think themſelves ſufficiently defended with a root of Elecampane, Zedoary, or Angelica, rowled in their mouth, or chawed between their teeth.

Others drink every morning one dram of the root of *Gentian* bruiſed, being macerated for the ſpace of one night in two ounces of white wine.

Others take Wormwood-wine.

Others ſup in a rear egg one dram of *Terra Sigillata*, or of Harts-horn, with a little Saffron, and drink two ounces of wine after it

There be ſome that do infuſe Bole-Armenick, the roots of *Gentian*, Tormentil, Diptam, the berries of Juniper, Cloves, Mace, Cinnamon, Saffron, and ſuch like, in *aqua vitæ* and ſtrong white wine, and ſo diſtil it in *Balneo Mariæ*.

This Cordial water that followeth is of great vertue. Take of the roots of the long and round *Ariſtolochia*, Tormentil, Diptam, of each three drams, of Zedoary two drams, *Lignum Aloes*, yellow Sanders, of each one dram, of the leaves of Scordium, S. Johns-wort, Sorrel, Rue, Sage, of each half an ounce, of Bay and Juniper-berries, of each three drams, Citron-ſeeds one Dram, Cloves, Mace, Nutmegs, of each two drams, Maſtick, *Olibanum*, Bole-Armenick, *Terra Sigillata*, ſhavings of Harts-horn and Ivory, of each one ounce, of Saffron one ſcruple, of the Conſerves of Roſes, Bugloſs-flowers, water-lillies and old Treacle, of each one ounce, of Camphire half a dram, of *aqua vitæ* half a pint, of white wine two pints and a half; make thereof a diſtillation in *Balneo Mariæ*: The uſe of this diſtilled water is even as Treacle water is. A cordial water.

The electuary following is very effectual. Take of the beſt Treacle three ounces, Juniper-berries and Carduus-ſeeds of each one dram and a half, of Bole-Armenick prepared half an ounce, of the powder of the electuary *de gemmis* and *Diamargariton frigidum*, the powder of Harts-horn, and red Coral, of each one dram: mix them with the ſyrup of the rinds and juice of Pome-Citrons as much as ſhall ſuffice, and make thereof a liquid Electuary in the form of an Opiate, let them take every morning the quantity of a Filberd, drinking after it two drams of the water of Scabious, Cherries, *Carduus Benedictus*, and of ſome ſuch like cordial thing, or of ſtrong wine. A Cordial Electuary.

The folowing Opiate is alſo very profitable, which alſo may be made into tablets. Take of the roots of Angelica, Gentian, Zedoary, Elecampane, of each two drams; of Citron and Sorrel-ſeeds, of each half a dram; of the dried rinds of Citrons, Cinnamon, Bay and Juniper-berries, and Saffron, of each one ſcruple; of conſerve of Roſes and Bugloſs, of each one ounce; and fine hard Sugar as much as is ſufficient; make thereof Tablets of the weight of half a dram, let him take one of them two hours before meat: or make thereof an Opiate with equal parts of conſerves of Bugloſs and *Mel Anthoſatum*, and ſo adding all the reſt dry and in powder. An Opiate. Another. Or take of the roots of Valerian, Tormentil, Diptam, of the leaves of Rue, of each half an ounce; of Saffron, Mace, Nutmegs, of each half a dram; of Bole-Armenick prepared half an ounce; of conſerve of Roſes and ſyrup of Limons as much as will be ſufficient to make thereof an Opiate liquid enough. Or take of the roots of both the *Ariſtolochias*, of Gentian, Tormentil, Diptam, of each one dram and a half; of Ginger three drams; of the leaves of Rue, Sage, Mints and Penny-royal, of each two drams; of Bay and Juniper-berries, Citron-ſeeds, of each four ſcruples; of Mace, Nutmegs, Cloves, Cinnamon, of each two drams; of *Lignum aloes*, and yellow Sanders, of each one dram; of Male-Frankincenſe, *i. Olibanum*, Maſtich, ſhavings of Harts-horn and Ivory, of each two ſcruples: of Saffron half a dram; of Bole-Armenick, *Terra Sigillata*, red Coral, Pearl, of each one dram; of conſerves of Roſes, Bugloſs-flowers, water-lillies and old Treacle, of each one ounce; of Loaf-ſugar one pound and a quarter: a little before the end of the making it up, add two drams of *Confectio Alkermes*, and of Camphire diſſolved in Roſe-water one ſcruple, make thereof an Opiate according to art, the doſe thereof is from half a dram, to half a ſcruple. Another.

Treacle and Mithridate faithfully compounded, excel all Cordial medicines, adding for every half ounce of them, one ounce and an half of Conſerves of Roſes, or of Bugloſs, or of Violets, and three drams of Bole-Armenick prepared: Of theſe being mixt with ſtirring, and incorporated together, make a conſerve: it muſt be taken in the morning the quantity of a Filberd. You muſt chuſe that treacle that is not leſs than four years old, nor above twelve: that which is ſomewhat new, is judged to be moſt meet for cholerick perſons; but that which is old, for phlegmatick and old men. For at the beginning the ſtrength of the *Opium* that enters into the compoſition thereof, remains in its full vertue for a year: but afterwards the more years old it waxeth, the ſtrength thereof is more aboliſhed, ſo that at length the whole compoſition becometh very hot.

The confection of *Alkermes* is very effectual both for a preſervative againſt this diſeaſe, and alſo for the cure.

The quantity of a Filberd of Rubarb, with one Clove chawed or rowled in the mouth, is ſuppoſed

to repel the coming of the peſtilent air: as alſo this compoſition following.

A Confection to be taken in the morning againſt the peſtilent Air.

Take of preſerved Citron and Orange pills, of each one dram; of *conſerve* of Roſes, and of the roots of Bugloſs, of each three drams; of Citron-ſeeds half an ounce; of Anniſe-ſeeds and Fennel-ſeeds, of each one dram; of Angelica-Roots four ſcruples; ſugar of Roſes as much as ſufficeth: Make a Confection, and cover it with leaves of Gold, to take a little of it upon a ſpoon before you go abroad every morning.

A March-pane

Or take of Pine-apple-kernels, and Piſtick-nuts, infuſed for the ſpace of ſix hours in the water of Scabious and Roſes, of each two ounces; of Almonds blanched in the fore-named waters half a pound: of preſerved Citron and Orange pills, of each one dram and a half: of Angelica-roots four ſcruples: make them according to art, unto the form of March-pane, or of any other ſuch like confection, and hold a little piece thereof often in your mouth.

The Tablets following are moſt effectual in ſuch a caſe. Take of the roots of Diptam, Tormentil, Valerian, Elecampane, Eringoes, of each half a dram; of *Bole-Armenick*, *Terra Sigillata*, of each one ſcruple; Camphire, Cinnamon, Sorrel-ſeeds, and Zedoary of each one ſcruple, of the *ſpecies* of the electuary *Diamargariton frigidum*, two ſcruples; of *conſerve* of Roſes, Bugloſs preſerved, Citron-pills, Mithridate, Treacle of each one dram; of fine Sugar diſſolved in *Scabious* and *Carduus*-water, as much as ſhall ſuffice: Make thereof Tablets of the weight of a dram, or half a dram: take them in the morning before you eat.

Pills of *Ruffus*.

The pills of *Ruffus* are accounted moſt effectual preſervatives, ſo that *Ruffus* himſelf ſaith, that he never knew any to be infected that uſed them: the compoſition of them is thus.

Take of the beſt Aloes half a dram, of *Gum-Ammoniacum* two drams, of Myrrh two drams and an half, of Maſtich two drams, of Saffron ſeven grains: put them all together, and incorporate them with the juice of Citrons, or the ſyrup of Limons, and make thereof a maſs, and let it be kept in leather: Let the patient take the weight of half a dram every morning two or three hours before meat, and let him drink the water of Sorrel after it, which through its tartneſs, and the thinneſs of its parts, doth infringe the force and power of the malignity or putrefaction: For experience hath taught us, that Sorrel being eaten or chawed in the mouth, doth make the pricking of Scorpions unhurtful. And for thoſe ingredients which do enter into the compoſition of thoſe pills, Aloes doth cleanſe and purge, Myrrh reſiſts putrefaction, Maſtich ſtrengthens, Saffron exhilarates and makes lively the ſpirits that govern the body, eſpecially the vital and animal.

Other pills.

Thoſe pills that follow are alſo much approved. Take of Aloes one ounce, of Myrrh half an ounce, of Saffron one ſcruple, of Agarick in Trochiſces two drams, of Rubarb in powder one dram, of Cinnamon two ſcruples, of Maſtich one dram and a half, of Citron-ſeeds twelve grains: powder them all as is requiſite; and make thereof a maſs with the ſyrup of Maiden-hair: let it be uſed as aforeſaid.

If the maſs begin to wax hard, the pills that muſt preſently be taken, muſt be mollified with the ſyrup of Limons.

Other pills.

Take of waſhed Aloes two ounces, of Saffron one dram, of Myrrh half an ounce, of *Ammoniacum* diſſolved in white wine one ounce, of hony of Roſes, Zedoary, red Sanders, of each one dram, of *Bole-Armenick* prepared two drams, of red coral half an ounce, of Camphire half a ſcruple: make thereof pills according to art. But thoſe that are ſubject or apt to the hemorrhoids ought not at all, or very ſeldom to uſe thoſe kinds of pills that do receive much Aloes.

They ſay, that King *Mithridates* affirmed by his own writing, that whoſoever took the quantity of an hazel-nut of the preſervative following, and drank a little wine after it, ſhould be free from poyſon that day, Take two Wall-nuts, thoſe that be very dry, two Figs, twenty leaves of *Rue*, and three grains of ſalt: beat them and incorporate them together, and let them be uſed as is aforeſaid.

This remedy is alſo ſaid to be profitable for thoſe that are bitten or ſtung by ſome venomous beaſt, and for this only, becauſe it hath *Rue* in the compoſition thereof. But you muſt forbid women that are with child the uſe of this medicine; for *Rue* is hot and dry in the third degree, and therefore it is ſaid to purge the womb, and provoke the flowers, whereby the nouriſhment is drawn away from the child. Of ſuch variety of medicines, every one may make choice of that is moſt agreeable to his taſte, and as much thereof as ſhall be ſufficient.

CHAP. VIII.

Of local medicines to be applied outwardly.

THoſe medicines that have proper and excellent vertues againſt the peſtilence, are not to be neglected to be applied outwardly, or carried in the hand. And ſuch are all aromatical, aſtringent, or ſpirituous things, which therefore are endued with vertue to repel the venomous and peſtiferous air, from coming and entring into the body, and to ſtrengthen the heart and brain. Of this kind are *Rue*, Balm, Roſemary, *Scordium*, *Sage*, Worm-wood, Cloves, Nutmegs, Saffron, the roots of Angelica, and Lovage, and ſuch like, which muſt be macerated one night in ſharp Vinegar and *Aqua vitæ*, and then tied in a knot as big as an egg, or rather let it be carried in a ſponge made wet, or ſoaked in the ſaid infuſion. For there is nothing that doth ſooner and better hold the ſpirituous virtue and ſtrength of aromatick things, than a ſponge. Wherefore it is of principal uſe either to keep or hold ſweet things to the noſe, or to apply Epithems and fomentations to the heart.

Of what nature the medicines outwardly uſed ought to be.

Thoſe ſweet things ought to be hot or cold, as the ſeaſon of the year, and kind of the peſtilence is: As for example, in the Summer you ought to infuſe and macerate Cinnamon and Cloves, beaten together: with a little Saffron in equal parts, of vinegar of Roſes, and Roſe-water, into which you muſt dip a ſponge, which rowled in a fair linnen cloth, you may carry in your hand, and often ſmell to.

Take

Take of Worm-wood half a handful; ten Cloves, of the roots of *Gentian* and Angelica, of each two drams; of vinegar and Roſewater, of each two ounces; of Treacle and Mithridate, of each one dram; beat and mix them well all together, and let a ſponge be dipped therein, and uſed as above ſaid. They may alſo be incloſed in boxes made of ſweet wood, as of Juniper, Cedar, or Cypreſs, and ſo carried for the ſame purpoſe.

But there is nothing more eaſie to be carried than Pomanders: the form of which is thus: Take of yellow Sanders, *Mace*, Citron-pills, Roſe and Myrtle-leaves, of each two drams; of Benzoin, *Ladanum*, *Storax*, of each half a dram; of Cinnamon and Saffron, of each two ſcruples; of Camphire and Amber-Greece, of each one ſcruple; of Musk three grains. Make thereof a Pomander, with Roſe-water, with the infuſion of Tragacanth. Or take red-Roſe-leaves, the flowers of Water-lillies and Volets, of each one ounce; of the three Sanders, Coriander-ſeeds, Citron-pills, of each half an ounce; of Camphire, one dram; let them all be made into powder, and with Water of Roſes and Tragacanth make a pomander. Pomanders.

In the Winter it is to be made thus. Take of *Storax*, Benzoin, of each one dram and a half; of Musk half a ſcruple, of Cloves, Lavander and *Ciperus*, of each two drams; of the root of Orris, *i.e. Flower-de-luce*, and *Calamus aromaticus*, of each two drams and a half; of Amber-Greece, three drams; of Gum-Tragacanth diſſolved in Roſe-water and *aqua vitæ*, as much as ſhall ſuffice, make thereof a Pomander.

And for the ſame purpoſe you may alſo uſe to carry about with you ſweet powders, made of Amber-Greece, *Storax*, Orris, Nutmegs, Cinnamon, *Mace*, Cloves, Saffron, Benzoin, Musk, Camphire, Roſes, Violets, *Juncus odoratus*, Marjoram, and ſuch like, of which being mixed together, Powders may be compounded and made. Sweet powders.

Take of the roots of Orris two drams; of *Cyperus*, *Calamus aromaticus*, red Roſes, of each half an ounce, of Cloves half a dram, of *Storax*, one dram; of Musk, eight grains: mix them, and make a powder for a bag; or take the roots of Orris two ounces; red-Roſe-leaves, white Sanders, *Storax*, of each one dram; of *Cyperus* one ounce; of *Calamus aromaticus*, one ounce; of Marjoram, half an ounce; of Cloves, three drams; of Lavander, half a dram; of Coriander-ſeeds, two drams; of good Musk, half a ſcruple; of *Ladanum* and Benzoin, of each a dram; of Nutmegs and Cinnamon, of each two dram: Make thereof a fine powder, and ſow it in a bag.

It will be very convenient alſo to apply to the *region* of the heart, a bag filled with yellow Sanders, *Mace*, Cloves, Cinnamon, Saffron and Treacle ſhaken together, and incorporated, and ſprinkled over with ſtrong vinegar and Roſe-water in Summer, and with ſtrong wine and Muskadine in the Winter. Bags.

The ſweet Aromatick things that are ſo full of ſpirits, ſmelling ſweetly and ſtrongly, have admirable vertues to ſtrengthen the principal parts of the body, and to ſtir up the expulſive faculty to expel the poyſon.

Contrariwiſe, thoſe that are ſtinking and unſavory, procure a deſire to vomit, and diſſolution of the powers, by which it is manifeſt how fooliſh and abſurd their perſwaſion is, that counſel ſuch as are in a peſtilent conſtitution of the Air, to receive and take in the ſtinking and unſavoury vapours of *ſinks* and *privies*, and that eſpecially in the morning. Unſavory things to be eſchewed.

But it will not ſuffice to carry thoſe preſervatives alone, without the uſe of any other thing, but it will be alſo very profitable to waſh all the whole body in Vinegar of the decoction of Juniper and Bay-berries, the Roots of *Gentian*, Marigolds, S. Johns-Wort, and ſuch like, with Treacle or Mithridate alſo diſſolved in it. For vinegar is an enemy to all poyſons in general, whether they be hot or cold: for it reſiſteth and hindereth putrefaction. Neither is it to be feared, that it ſhould obſtruct the pores, by reaſon of its coldneſs, if the body be bathed in it: for it is of ſubtil parts, and the ſpices boiled in it, have virtue to open.

Whoſoever accounteth it hurtful to waſh his whole body therewith, let him waſh only his armholes, the *region* of his heart, his *temples*, groins, parts of generation; as having great and marvelous ſympathy with the principal and noble parts.

If any miſlike bathing, let him anoint himſelf with the following Unguent. Take oyl of Roſes, four ounces; oyl of Spike, two ounces; of the powder of Cinnamon and Cloves, of each, one ounce and a half; of Benzoin, half an ounce; of Musk, ſix grains; of Treacle, half a dram; of Venice-Turpentine, one dram and a half; of Wax, as much as ſhall ſuffice: make thereof a ſoft Unguent. An Unguent.

You may alſo drop a few drops of oyl of Maſtich, of *Sage*, or of Cloves, and ſuch like, into the ears, with a little Civet or Musk.

CHAP. IX.

Of other things to be obſerved for prevention in fear of the Plague.

VEnery is chiefly to be eſchewed, for by it the powers are debilitated, the ſpirits diſſipated, and the breathing places of the body diminiſhed, and laſtly, all the ſtrength of nature weakned. A ſedentary life is to be ſhunned, as alſo exceſs in diet, for hence proceeds obſtruction, the corruption of the juices, and preparation of the body to putrefaction and the peſtilence. Why Venery is to be ſhunned.

Women muſt be very careful that they have their courſes duely, for ſtopping beſides the cuſtom, they eaſily acquire corruption, and draw by contagion the reſt of the humors into their ſociety. Such as have fiſtulaes, or otherwiſe old ulcers, muſt not heal them up in a peſtilent ſeaſon; for it is then more convenient rather to make new ones and theſe in convenient and declining places; that as by theſe channels, the ſink of the humors of the body may be emptied. Running ulcers good in time of peſtilence.

The Hemorrhoids, bleedings, and other the like accuſtomed evacuations, muſt not be ſtopped, unleſs

leſs they exceed meaſure. Moreover, they muſt at ſuch times take heed that they touch or handle not any of thoſe things wherein the ſeeds or fuel of the peſtilence may lie hid; ſuch as are hemp, flax, quilts and coverings wherein ſuch as have had the plague have lain; skins and all leather things, hangings and cloaths. You muſt dwell far from Church-yards, eſpecially from thoſe where-in the corps of ſuch as have died of the plague are not buried deep in the ground, as in the Church of *Innocents* in *Paris*, in which place by the ſame reaſon it ſundry times happens that the bodies are plucked up, rent and torn by dogs. Alſo let them dwell far from places of execution, ſhambles of fleſh and fiſh, from tan-houſes, diers, tallow-chandlers, cloth-dreſſers, farriers, skinners, and from the places wherein metals are caſt or wrought. The filth and dung, eſpecially of Swine, Privies, ſtanding and muddy waters, and laſtly all things of the like evil ſmell, muſt be far remote from your habitation; the belly muſt not be emptied into thoſe places, into which the excrements of ſuch as have the plague are caſt. The company of ſuch as uſually viſit thoſe ſick of the plague, muſt be eſchewed, as of Phyſicians, Apothecaries, Surgeons, Nurſe-keepers, Grave-makers, and Bearers: For though they have not the plague, yet coming out of a peſtilent place, they may carry with them lying in their garments, the ſeeds thereof. You may gather this by ſuch as have for a little while ſtayed in a perfumers ſhop, for the perfume diffuſed in the air, beſtows the ſmell upon the garments of ſuch perſons, ſo that gone from thence, ſuch as meet them, will judg them to carry perfumes with them. They ſhall alſo ſhun long watchings, ſound ſleeping, all paſſions of the mind, eſpecially, anger, hunger, thirſt, journying in the Sun, for that hath oft times occaſioned a diary feaver, which hath not ſeldom been ſeen to turn into a peſtilent one: for by dilating the pores of the skin, they have given entrance to the peſtilent air, which by that means hath eaſily taken hold of the humor diſpoſed to putrefaction.

Places to be ſhunned in time of plague

What company to be avoided.

You muſt do nothing in a peſtilent ſeaſon whereby you may grow too hot.

CHAP. X.

Of the Office of Magiſtrates in time of the Plague.

MAgiſtrates ought to have a ſpecial care that no filth be heaped up, either in private or publick places: let all things be kept neat in every houſe, and let all the ſtreets be kept clean, the dung and filth be carried forth of the City, as alſo the dead carkaſſes of killed dogs and cats, for becauſe they oft-times lick and devour the excrements of ſuch as have the ſickneſs, therefore they may by their familiar entry into ſound houſes, there propagate the plague: Wherefore they muſt either be driven forth of the City, or killed, and ſo be carried forth and buried deep in the ground. Wells, ſprings, and rivers themſelves, muſt be freed and cleanſed from all impurity. Care muſt be had that muſty corn, tainted fleſh, nor ſtinking fiſh be not ſet to ſale. Publick baths and hot-houſes muſt be prohibited, for that in theſe, mens bodies are weakned, and made more yielding and pervious to the peſtiferous air. They ſhall commit the cure of ſuch as have the plague, to learned, skilful and honeſt Phyſicians, Apothecaries and Surgeons.

Why dogs and cats muſt be killed in a Plague-time.

Why Baths and hot-houſes are not then to be allowed.

Such as are known to have the Plague, ſhall be ſeparated from ſuch as are free there-from, and be ſent to ſuch fit places as ſhall be provided for them; for this is better and more humanely done than to ſhut up every man in his own houſe. They ſhall provide and fore-ſee that the houſhold-ſtuff of ſuch as have the plague be not ſet to ſale. They ſhall ſet ſigns and noted marks upon the houſes ſeized upon by this diſeaſe, leſt they ſhould unawares run into danger: Wherefore to the ſame purpoſe they ſhall procure that the Surgeons and others that viſit the ſick of the Plague may be known by ſome conſpicuous mark, that ſuch as paſs by them may be admoniſhed of the danger; they ſhall alſo take care that the bodies of the dead be buried as ſpeedily as may be. For they ſooner and more grievouſly putrefie in a ſhort time, than the bodies of others of what death ſoever they die Wherefore, neither birds, nor ravenous beaſts dare once touch their Bodies, though unburied; for by taſting them they ſhould quickly come to their deaths. The keepers of the gates of the City ſhall be admoniſhed, that they take ſpecial care that ſuch as are infected, or come from a viſited place, do not enter into the City; for from one, the evil may come to ſpread it ſelf further: for one ſpark may ſet a whole City on fire, and one ſcabby ſheep infect a whole flock. And becauſe there is nothing which may more perfectly purge the air, and cleanſe it from all manner of noiſomneſs and infection, than fire; they ſhall command that there be kindled and perpetually kept burning, fires made with odoriferous and ſtrong ſmelling things, as Juniper, Turpentine, Broom, and the like.

Such as die of the Plague do quickly putrefie.

In ſtead hereof *Levinus* tells, that the Souldiers of the Garriſon of *Torny* uſed in a Plague-time, to diſcharge their Cannons laded only with powder, turning their mouths upon the City, and that morning and evening; that by the vehemency of the moved air, the peſtiferous fogs might be chaſed away; and by the heat of the burned powder, the venenate and noiſom quality of the air might be amended. Laſtly, I judge it fit to admoniſh Magiſtrates, that they have their eyes and minds attentive upon a murderous and impious kind of Bearers and Nurſe-keepers; which allured with a deſire of gain (which whilſt the Plague reigns, they get abundantly) anoint the walls, doors, threſholds, knockers of gates and locks with the filth and ointments taken from ſuch as have the Plague, that the Plague within a while after ſeizing upon theſe alſo, the maſters of them flying away, and the family diſperſed, they may there reign alone, and freely and without puniſhment carry thence what they pleaſe oft-times ſtrangling ſuch as lie ready to die, leſt recovering, they might be their accuſers. This I remember, happened at *Lions*, *Anno Dom.* 1565.

Lib. 2. de occult. mat. mirac.

The villany of ſome baſe people.

CHAP.

CHAP. XI.

What caution muſt be uſed in chuſing Phyſicians, Apothecaries and Surgeons, who may have a care of ſuch are taken with the Plague.

IT is the part of Magiſtrates in the ſo great neceſſity of the afflicted Common-wealth, to appoint learned, skilful and honeſt Phyſicians, Surgeons, and Apothecaries, and ſuch as have more regard to the Law of God than to gain, to have the care and cure of ſuch as are viſited: But principally let them not take Surgeons and Apothecaries called by proclamation with ſound of trumpet, that if they will take this charge, they ſhall become free without examination or reward. But let them rather be allured by gifts and honeſt rewards, not only then when as neceſſity urgeth, but alſo after the plague is over. For ſuch ſervant-Surgeons and Apothecaries as are called by proclamation, ſo to gain freedom, are moſt commonly unskilful and unexperienced Dunces, who, conſcious of their own ignorance, and fearing to undergo the examination of the Maſters of their Companies, refuſe no hazard, however dangerous, with deſire to obtain their freedom.

It is far worſe and more dangerous to fall into the hands of ſuch, than into the hands of thieves and murderers; for theſe by providence of ſtrength, we may chance to eſcape; but we ſeek for and embrace the other, and having found them, lay our throats bare unto them, ſo by their unskilfulneſs to be butchered. Certainly by the fault of the times, and the neglect of Magiſtrates, it is almoſt come to this paſs, that if any honeſt and learned Phyſicians and Surgeons ſhall undertake this cure, they are commonly forced thereto by the Magiſtrate, for fear of baniſhment or fining: Therefore becauſe they do it againſt their wills, they ſhew themſelves leſs vigilant, cheerful and painful about the ſick. They come unwillingly, and compelled thereto, becauſe by the memory of the fore-paſt time, they ſufficiently know, how ſordid and baſely Magiſtrates, when the Plague hath been over-paſt, have been in paying the promiſed reward to men of their condition, who have ſtoutly run into danger; for thence it happens, that during the reſt of their lives they may ſit idle at home, for that they are infamous, and feared by the people only for this, that a while agon they viſited ſuch as had the Plague. Therefore I would have Magiſtrates prudent, faithful, and free in chuſing honeſt, learned and skilful men, who may undergo this ſo difficult and dangerous a charge.

CHAP. XII.

How ſuch as undertake the cure of the Plague ought to arm themſelves.

FIrſt they muſt think and hold for certain, that they are not called to this office by men, but by God, ſo directing the counſels and actions of men as he thinketh fit. Therefore they ſhall confidently enter into the cure thereof; for that our lot, life and death are in the hands of the Lord: but notwithſtanding they ought not to neglect remedies, which are given to men for prevention, leſt by the neglecting the gifts of God, they may ſeem to neglect him alſo that is the giver of ſo many good and excellent benefits. Therefore, firſt let them by purging and bleeding, evacuate the humors ſubject to putrefaction, and to conceive the ſeeds of the peſtilence. Let them make two fontanels by application of cauteries, to be as rivulets to evacuate the excrementitious humors which are daily by little and little heaped up in us; let one of them be in the right arm a little below the muſcle *Epomis*; the other the ſpace of three fingers under the knee on the inſide of the left leg. This is found by experience a very certain means of prevention. Let them waſh their whole bodies with the following lotion. ℞. *aquæ roſ. aceti roſati, aut ſambucini, vini albi aut malvatici, an.* lb. vi. *rad. enulæ camp. angelicæ, gentian. biſtortæ, zedoar. an.* ℥iii. *baccar. juniperi, & hederæ, an.* ℥ii. *ſalviæ, roriſmar. abſinth. rutæ, an.* m. j. *corticis citri,* ℥ ß. *theriacæ & mithridat. an.* ℥j. *conquaſſanda conquaſſentur, bulliant lento igni, & ſerventur ad uſum ante commemoratum.* The epithems, unguents and Bags formerly deſcribed ſhall be applied to the region of the heart. I have read it noted by *John Baptiſt Theodoſius*, that amongſt other things, Arſenick may be profitably applied tothe region of the heart, that ſo it may by little and little accuſtom it ſelf to poyſons, that afterwards it may be leſs harmed by their incurſion, firſt making their aſſault upon it.

Our lots are in the hands of the Lord.

Where to make iſſues in the time of the Plague.

Cap. 8. *Epiſt.* 2.

Let their garments be made of Chamlet, Dutch Serge, Satin, Taffaty, or the like. Or elſe if they cannot of theſe, let them be of ſome other handſom Stuff, but not of Cloth, Freeze or the like, that they may take the venenate air, and carry it with them to the infection of the ſound. They ſhall oft-times change their cloaths, ſhirts and other linnen, and perfume them with aromatick things; let them warily approach the ſick, more warily ſpeak unto him, with their faces looking away from him rather than toward him, ſo that they may not receive the breath of his mouth, neither the vapour nor ſmell of any of his excrements.

What to wear.

How to viſit your patients.

When as I upon a time being called to viſit one that lay ſick of the Plague, came too near and heedleſly to him, and preſently by ſudden caſting off the cloaths he laid him bare, that ſo I might the better view a *Bubo*, that he had in his right groin, and two Carbuncles that were on his belly, then preſently a thick, filthy and putrid vapour ariſing from the broken abſceſs of the Carbuncle, as out of a raked puddle, aſcended by my noſtrils to my brain, whereupon I fainted, and fell down ſenſleſs upon the ground; raiſed up a little after, all things ſeemed to me to run round, and I was ready to fall again, but that I ſtayed my ſelf by taking hold of the bed-poſt. But one thing comforted me, that there appeared no ſigns that my heart was affected, either by pain or panting, or the ſtrong and contumacious failing of my powers. An Argument that the animal ſpirits were only diſſipated by a venenate vapor, and that the ſubſtance of the heart was no way wronged, was a ſneeſing which took me ſo violently, that I ſneeſed ten times, and then fell a bleeding at the noſe;

An hiſtory.

which

which excretion, I believe, freed me from all the impreſſion of the malignity. Let others, warned by this mine example, learn to be wiſer and more wary in this caſe, leſt they come to worſe miſhap than befel me.

CHAP. XIII.

Of the ſigns of ſuch as are infected with the Plague.

Whence certain ſigns of the Plague may be taken.

WE muſt not ſtay ſo long before we pronounce one to have the Plague until there be pain and a tumor under his arm-holes, or in his groin, or ſpots (vulgarly called *Tokens*) appear over all the body, or Carbuncles ariſe: for many die through venenate malignity, before theſe ſigns appear. Wherefore the chiefeſt and trueſt ſigns of this diſeaſe are to be taken from the heart, being the manſion of life, which chiefly and firſt of all is wont to be aſſailed by the force of the poyſon. Therefore they that are infected with the Peſtilence, are vexed with often ſwoundings and faintings; their pulſe is feebler and ſlower than other, but ſometimes more frequent, but that is eſpecially in the night ſeaſon; they feel prickings over all their body, as if it were the pricking of needles; but their noſtrils do itch eſpecially by occaſion of the malign vapours ariſing upwards from the lower and inner, into the upper parts, their breaſt burneth, their heart beateth with pain under the left dug, difficulty of taking breath, ptiſſick, cough, pain of the heart, and ſuch an elation or puffing up of the *Hypochondria*, or ſides of the belly, diſtended with the abundance of vapours raiſed by the force of the feaveriſh heat, that the patient will in a manner ſeem to have the Tympany. They are moleſted with a deſire to vomit, and oftentimes with much and painful vomiting, wherein green and black matter is ſeen, and always of divers colours, anſwering in proportion to the excrements of the lower parts, the ſtomack being drawn into a conſent with the heat, by reaſon of the vicinity and communion of the veſſels; oftentimes blood alone, and that pure, is excluded and caſt up in vomiting; and is not only caſt up by vomiting out of the ſtomach, but alſo very often out of the noſtrils, fundament; and in women, out of the womb; the inward parts are often burned, and the outward parts are ſtiff with cold, the whole heat of the patient being drawn violently inward, after the manner of a Cupping-glaſs, by the ſtrong burning of the inner parts; then the eye-lids wax blew, as it were through ſome contuſion, all the whole face hath an horrid aſpect, and as it were the colour of lead, the eyes are burning red, and as it were ſwoln, or puffed up with blood, or any other humor, ſhed tears; and to conclude, the whole habit of the body is ſomewhat changed, and turned yellow.

The cauſe of vomiting in ſuch as have the Plague.

Their looks are ſuddenly changed.

Many have a burning feaver, which doth ſhew it ſelf by the patients ulcerated jaws, unquenchable thirſt, drineſs and blackneſs of the tongue and it cauſeth ſuch a phrenſie by inflaming the brain, that the patients, running naked out of their beds, ſeek to throw themſelves out of windows into the pits and rivers that are at hand. In ſome the joints of the body are ſo weakned, that they cannot go nor ſtand; from the beginning, they are as it were buried in a long ſwound and deep ſleep, by reaſon that the feaver ſendeth up to the brain, the groſs vapors from the crude and cold humors, as it were from green woody newly kindled to, make a fire.

Why ſome that are taken with the plague are ſleepy.

Such ſleeping doth hold him eſpecially while the matter of the ſore or carbuncle is drawn together, and beginneth to come to ſuppuration. Oftentimes when they are awaked out of ſleep, there do ſpots and marks appear diſperſed over the skin, with a ſtinking ſweat. But if thoſe vapors be ſharp that are ſtirred up unto the head, inſtead of ſleep they cauſe great waking, and always there is much diverſity of accidents, in the urine of thoſe that are infected with the Plague, by reaſon of the diverſe temperature and condition of bodies: neither is the urine at all times, and in all men of the ſame conſiſtence and colour: For ſometimes they are like unto the urine of thoſe that are ſound and in health, that is to ſay, laudable in colour and ſubſtance; becauſe that when the heart is affected by the venemous air, that entreth in unto it, the ſpirits are more greatly grieved and moleſted than the humors: but thoſe, *i. e.* the ſpirits, are infected and corrupted when theſe do begin to corrupt.

Why their urines are like thoſe that are ſound.

But Urines only ſhew the diſpoſitions of the humors or parts in which they are made, collected together, and through which they paſs.

This reaſon ſeemeth truer to me than theirs which ſay, that nature terrified with the malignities of the poyſon avoids contention, and doth not reſiſt or labour to digeſt the matter that cauſeth the diſeaſe.

Many have their appetites ſo overthrown, that they can abſtain from meat for the ſpace of three days together.

And to conclude, the variety of accidents is almoſt infinite, which appear and ſpring up in this kind of diſeaſe, by reaſon of the diverſity of the poyſon, and condition of the bodies and grieved parts: but they do not all appear in each man; but ſome in one, and ſome in another.

CHAP. XIV.

What ſigns in the Plague are mortal.

IT is a moſt deadly ſign in the Peſtilence, to have a continual and burning Feaver, to have the tongue dry, rough, and black, to breath with difficulty, and to draw in a great quantity of breath, but breath out little; to talk idly; to have Phrenſie and Madneſs together, with unquenchable thirſt and great watching; to have Convulſions, the Hicket, Heart-beating, and to ſwound very often and vehemently: further, toſſing and turning in the bed, with a loathing of meats, and dayly vomits of a green, black, and bloudy colour; and the face pale, black, of an horrid and cruel aſpect, bedewed with a cold ſweat, are very mortal ſigns.

There are ſome which at the very beginning have ulcerous and painful wearineſs, pricking under the skin, with great torment of pain; the eyes look cruelly and ſtaringly, the voice waxeth hoarſe, the tongue rough and ſtutting, and the underſtanding decaying the patient uttereth and talketh of frivolous things. Truly thoſe are very dangerouſly ſick, no otherwiſe than thoſe whoſe urine is pale, black, and troubled like unto the urine of carriage-beaſts, or lee, with divers coloured clouds or contents; as blew, green, black, fatty and oily, as alſo reſembling in ſhew, a Spiders web, with a round body ſwimming on the top. An ulcerous and painful wearineſs from the beginning ſheweth the Plague to be deadly.

If the fleſh of the carbuncle be dry and black, as it were ſeared with an hot iron, if the fleſh about it be black and blew, if the matter do flow back, and turn in, if they have a lask with greatly ſtinking, liquid, thin, clammy, black, green or blewith ordure; if they avoid Worms, by reaſon of the great corruption of the humors, and yet for all this the patient is never the better; if the eyes wax often dim, if the noſtrils be contracted or drawn together, if they have a grievous cramp, the mouth be drawn aſide, the muſcles of the face being drawn or contracted equally or unequally; if the nails be black; if they be often troubled with the Hicket, or have a Convulſion and reſolution over all the body, then you may certainly prognoſticate that death is at hand, and you may uſe cordial medicines only, but it is too late to purge, or let bloud.

CHAP. XV.

Signs of the Plague coming by contagion of the air without any fault of the humors.

YOu ſhall underſtand, that the Peſtilence proceeds from the corruption of the air, if it be very contagious, and diſperſeth it ſelf into ſundry places in a moment. If it kill quickly and many, ſo that whilſt ſundry perſons go about their uſual buſineſs, walk in the places of common reſort, and through the ſtreets, they ſuddenly fall down and die, no ſign of the diſeaſe or harm appearing, nor any pain oppreſſing them; for the malignity of the corrupt air is quick and very ſpeedy in infecting our ſpirits, overthrowing the ſtrength of the heart, and killing the Patient. The Patients are not troubled with great agitation, becauſe the ſpirits diſſipated by the rapid malignity of the poyſon, cannot endure that labour; beſides they are taken with frequent ſwoundings, few of them have Buboes, few have Blains come forth; and by the ſame reaſon their urines are like to thoſe of ſound men. Why they have no ſores.

CHAP. XVI.

Signs of the Plague drawn into the body by the fault and putrefaction of humors.

FOrmerly we have reckoned up the cauſes of the corruption of humors from plenitude, obſtruction, diſtemper, and the ill juice of meats. Now muſt we deliver the ſigns of each corrupt humor which reigns in us, that it may be reduced to ſoundneſs and perfection of nature, by the oppoſition of its contrary, or elſe be evacuated by Phyſick. Therefore if the body be more yellow than uſual, it is a ſign of choler offending in quantity and quality. If more black, then of melancholy; if more pale, then of phlegm; if more red, with the veins ſwoln up and full, then of blood. Alſo the colour of the riſing blains, tumors and ſpots, expreſs the colour of the predominant humor, as alſo the excrements caſt forth by vomit, ſtool, and otherwiſe; the heavineſs and cheerfulneſs of the affected body; the manner of the preſent Feaver; the time of the year, age, region, diet. Such things as have a cutting, penetrating, attenuating, and cleanſing faculty, take away obſtruction. By means of obſtruction, Feavers oft-times accompany the Plague, and theſe not only continual, but alſo intermitting, like tertians or quartans. Therefore that Plague that is fixed in the infection or corruption of a cholerick humor, ſhews it ſelf by the forementioned ſigns of predominating choler, to wit, the heat of the ſkin, blains, and excrements; as alſo in the quickneſs of killing, and vehemency of the ſymptoms, bitterneſs of the mouth, a painful and continual endeavour of going to ſtool, by reaſon of the acrimony of choler ſtimulating and raking the guts in the paſſage forth. That which reſides in the corrupt ſubſtance of groſs humors, as of bloud, ſheweth it ſelf by many and plentiful ſweats, by a ſcouring, by which are avoided many and various humors; and oft-times alſo bloudy matter that proceeds from corrupt phlegm, it invades with more ſound ſleep, and cauſleſs wearineſs of all the members; when they are awakened out of their ſleep, they are not ſeldom troubled with a trembling over all their joints, the entrance and way of the ſpirits into the members being obſtructed by the groſneſs of the humors. That which is ſeated in the corruption of a melancholick humor, is accompanied with heavineſs and pain of the head, much penſiveneſs, a deep and ſmall pulſe. But the moſt certain ſign of the Plague reſiding in the corruption of the humors, is to be taken from the urine. For the ſigns of the vitiated humors cannot but ſhew themſelves in the urines: therefore troubled urines, and ſuch as are like thoſe of carriage-beaſts, as alſo black and green, give certain notice thereof. But ſome are much troubled with thirſt, others not at all; becauſe choler or phlegm ſometimes only putrifie in the ſtomach or orifice of the ventricle; ſometimes beſides, they will weaken the government of the natural faculties of the part, as of the appetite. But if the Feaver happen by the default and infection both of the air and humors; then will there be a great confuſion of the forementioned ſigns and ſymptoms. Signs of choler. When the urine is to be looked upon. Why ſome are much troubled with thirſt, others not at all.

CHAP.

CHAP. XVII.

Of the Prognoſtication that is to be inſtituted in the Plague.

No certain prediction in the Plague.

YOu may well fore-tell the future motions and events of diſeaſes, when you throughly know the nature of the diſeaſe, and accidents thereof, and the condition, function, and excellency of the body and grieved parts: Although that this may be ſpoken in general, that there is no certain prediction in peſtilent diſeaſes, either to health or death, for they have very unconſtant motions, ſometimes ſwift and quick, ſometimes ſlow, and ſometimes choaking or ſuffocating in a moment, while one breaths in the venomous air, as he is going about any of his neceſſary affairs, having puſtles riſing in the skin with ſharp pain, and as though the whole body was pricked all over with needles or the ſtings of Bees. Which I have ſeen with mine eyes in the Plague that was at *Lions* when *Charles* the French King lay there. It many times cometh to paſs that the accidents that were very vehement and raging a little before, are ſuddenly aſſwaged, and the patients do think themſelves better, or almoſt perfectly ſound. Which happens to *Mary* one of the Queen-mother her maids, in that notable peſtilent conſtitution of the air, that year when *Charles* the French King lay at the Caſtle of *Roſſilion*: for when ſhe was infected, a great tumor or *Bubo* aroſe in her groin, and ſuddenly it went in again, ſo that the third day of her ſickneſs, ſhe ſaid ſhe was without any grief or diſeaſe at all, but that ſhe was troubled with the difficulty of making water; and I think it was becauſe the bladder was inflamed by the reflux of the matter; that ſhe was ſound in mind and body, and walked up and down the chamber on the ſame day that ſhe died. The ſtrangeneſs of which thing made the King ſo fearful, that he haſted to depart thence.

An hiſtory.

Why young men ſooner take the plague than old.

Although this diſeaſe doth ſpare no man of what age, temperature, complexion, diet and condition ſoever, yet it aſſaulteth young men that are cholerick and ſanguine, more often than old men that are cold and dry, in whom the moiſture, that is the nouriſher of putrefaction by reaſon of their age, is conſumed, and the ways, paſſages and pores of the skin, whereby the venomous air ſhould enter and pierce in, are more ſtrait and narrow. And moreover, becauſe old men do always ſtay at home, but young men for their neceſſary buſineſs, and alſo for their delight and pleaſure, are always more abroad in the day time, in the air, where-hence the pollution of the Peſtilence cometh more often.

What Plague moſt contagious.

That peſtilence that comes by the corruption of the humors, is not ſo contagious as that which cometh by the default of the air. But thoſe that are Phlegmatick and Melancholick, are moſt commonly grieved with that kind of Peſtilence; becauſe in them the humors are more clammy and groſs, and their bodies more cold and leſs perſpirable, for which cauſes the humors ſooner and more ſpeedily putrefie.

Men that are of an ill juice, are alſo moſt apt to this kind of Peſtilence, for in the naughty quality of the juice there is a great preparation of the humors unto putrefaction: You may know it by this, that when the Peſtilence reigneth, there are no other diſeaſes among the common people, which have their original of an ill juice, but they all degenerate into the Plague. Therefore when they begin to appear and wander up and down, it is a token that the Peſtilence will ſhortly ceaſe or is almoſt at an end.

Who leaſt ſubject to take the Plague.

But here alſo I would have you to underſtand thoſe to be of an ill juice, which have no pores in their skin, by which, as it were by rivers, the evil juice which is contrary to nature, may be evacuated and purged. And I have noted and obſerved, that thoſe are leſs in danger of the Peſtilence which have Cancerous Ulcers and ſtinking ſores in their Noſes, and ſuch as are infected with the French-Pox, and have by reaſon thereof, tumors and rotten Ulcers, or have the Kings-evil running upon them, the Leproſie or the Scab: and to conclude: all thoſe that have Fiſtulaes and running in their bodies.

I think thoſe that have quartane Feavers are the better priviledged for the ſame, becauſe that by the fit cauſing ſweat, that cometh every fourth day, they avoid much of the evil juice that was engendred.

This is more like to be true, than to think that the poyſon that cometh from without, may be driven away by that which lurketh within.

Who ſubject thereto.

Contrariwiſe, women that are great with child, as I have noted, becauſe they have much ill juice being prohibited from their accuſtomed evacuations, are very apt to take this diſeaſe, and ſo ſeldom recover after they are infected.

Signs the diſeaſe is incurable.

Black or blew impoſtumes, and ſpots and puſtles of the ſame colour, diſperſed over the skin, argue that the diſeaſe is altogether incurable and mortal.

A good ſign.

When the ſwelling or ſore goeth or cometh before the Feaver, it is a good ſign; for it declareth that the malignity is very weak and feeble, and that nature hath overcome it, which of it ſelf is able to drive ſo great portion thereof from the inner parts. But if the ſore or tumor come after the Feaver,

A deadly ſign.

it is a mortal and deadly ſign, for it is certain that it cometh of the venomous matter not tranſlated, but diſperſed; not by the victory of nature, but through the multitude of the matter, with the weight whereof nature is overcome.

When the Moon decreaſeth, thoſe that are infected with the Peſtilence, are in great doubt and danger of death, becauſe then the humors that were collected and gathered together before the Full of the Moon, through delay and abundance, do ſwell the more, and the faculties by which the body is governed, become more weak and feeble, becauſe of the imbecillity of the native heat, which before was nouriſhed and augmented by the light, and ſo conſequently by the heat of the Full Moon: For as it is noted by *Ariſtotle*, the Wainings of the Moon are more cold and weak: and thence it is that women have their menſtrual fluxes chiefly, or commonly, at that time.

In a groſs and cloudy air, the peſtilent infection is leſs vehement and contagious, than in a thin

and

and ſubtil air; whether that thinneſs of the air proceed from the heat of the Sun, or from the North wind and cold. Therefore at *Paris*, where naturally, and alſo through the abundance of filth that is about the City, the air is dark and groſs, the peſtilent infection is leſs fierce and contagious than it is in *Provence*, for the ſubtilty of the air ſtimulates or helps forward the Plague. In what air moſt contagious.

But this diſeaſe is mortal and pernicious whereſoever it be, becauſe it ſuddenly aſſaulteth the heart, which is the Manſion, or as it were the fortreſs or caſtle of life: but commonly not before the ſigns and tokens of it appear on the body: and yet you ſhall ſcarce find any man that thinketh of calling the Phyſician to help to preſerve him from ſo great a danger, before the ſigns thereof be evident to be ſeen and felt; but then the heart is aſſaulted: And when the heart is ſo aſſaulted, what hope of life is there, or health to looked for? Therefore becauſe medicines come oft-times too late, and this malady is as it were a ſudden and winged meſſenger of our death, it cometh to paſs, that ſo many die thereof. And moreover, becauſe of the firſt ſuſpicion of this ſo dire and cruel a diſeaſe, the imagination and mind (whoſe force in the diverſly much ſtirring up of the humors, is great and almoſt incredible) is ſo troubled with fear of imminent death, and deſpair of health, that together with the perturbed humors, all the ſtrength and power of nature falleth and ſinketh down. What effects fear and confidence produce in the Plague.

This you may perceive and know, by reaſon that the keepers of ſuch as are ſick, and the bearers which are not fearful, but very confident, although they do all the baſeſt offices which may be for the ſick, are commonly not infected, and ſeldom die thereof, if infected.

CHAP. XVIII.

How a peſtilent Feaver comes to be bred in us.

THe Plague oft-times findeth fuel in our bodies, and oft-times allurements, to wit, the putrefaction of humors, or aptneſs to putrefie: but it never thence hath its firſt original, for that comes always from the defiled air; therefore a peſtilent Feaver is thus bred in us: The peſtilent air drawn by inſpiration in the lungs, and tranſpiration into the utmoſt mouths of the veins and arteries ſpread over the skin, the bloud or elſe the humors already putrefying or apt to putrefie therein, are infected or turned into a certain kind of malignity reſembling the nature of the agent. Theſe humors, like unquencht lime when it is firſt ſprinkled with water, ſend forth a putrid vapor, which carried to the principal parts and heart eſpecially, infecteth the ſpirituous bloud boiling in the ventricles thereof, and therewith alſo the vital ſpirits; and hence proceeds a certain feaveriſh heat. This heat diffuſed over the body by the arteries, together with a malign quality, taints all, even the ſolid parts of the bones, with the peſtiferous venom; and beſides, cauſeth divers ſymptoms, according to the nature thereof, and the condition of the body and the humors wherein it is. Then is the conflict of the malignity aſſailing, and nature defending, manifeſt; in which, if nature prevail, it uſing the help of the expulſive faculty, will ſend and drive it far from the noble parts, either by ſweats, vomits, bleeding, evacuation by ſtool or urine, buboes, carbuncles, puſtles, ſpots, and other ſuch kinds of breakings out, over the skin, but on the contrary, if the malignity prevail, and nature be too weak, and yield, and that firſt he be troubled with often panting, or palpitation of the heart; then preſently after with frequent faintings, the patient then at length will die. For this is a great ſign of the Plague or a peſtilent Feaver, if preſently at the firſt, with no labour, nor any evacuation worth the ſpeaking of, their ſtrength fail them, and they become exceeding faint. You may find the other ſigns mentioned in our preceeding diſcourſe. The original of the Plague always from the air. Signs that nature is orecome.

CHAP. XIX.

Into what place the Patient ought to betake himſelf ſo ſoon as he finds himſelf infected.

WE have ſaid, that the perpetual and firſt original of the peſtilence cometh of the Air; therefore ſo ſoon as one is blaſted with the peſtiferous Air, after he hath taken ſome preſervative againſt the malignity thereof, he muſt withdraw himſelf into ſome wholeſom Air, that is, clean and pure from any venomous infection or contagion; for there is great hope of health by the alteration of the Air; for we do moſt frequently and abundantly draw in the Air of all things, ſo that we cannot want it for a minute of time: therefore of the Air that is drawn in, dependeth the correction, amendment, or increaſe of the poyſon or malignity that is received, as the Air is pure, ſincere, or corrupted. Change of the Air conduceth to the cure of the Plague.

There be ſome that do think it good to ſhut the patient in a cloſe chamber, ſhutting the windows to prohibit the entrance of the Air as much as they are able: But I think it more convenient that thoſe windows ſhould be open from whence that wind bloweth that is directly contrary unto that which brought in the venomous Air: For although there be no other cauſe, yet if the Air be not moved, or agitated, but ſhut up in a cloſe place, it will ſoon be corrupted. Therefore in a cloſe and quiet place that is not ſubject to the entrance of the Air, I would wiſh the Patient to make wind, or to procure Air with a thick and great cloth, dipped or macerated in water and vinegar mixed together, and tied to a long ſtaff, that by toſſing it up and down the cloſe chamber, the wind or air thereof may cool and recreate the Patient. The Patient muſt every day be carried into a freſh chamber, and the beds and the linnen cloaths muſt be changed: there muſt always be a clear and bright fire in the Patients chamber, and eſpecially in the night, whereby the air may be made more pure, clean, and void of nightly vapors, and of the filthy and peſtilent breath proceeding from the Patient, or his excrements. In the mean time, leſt (if it be in hot weather) the Patient ſhould be weakned or made more faint, by reaſon that the heat of the fire doth diſperſe and waſte his ſpirits, the floor or ground of his chamber muſt be ſprinkled or watered with vinegar and water, or ſtrowed with the branches Air pent up is apt to putrefie.

branches of Vines made moiſt in cold water, with the leaves and flowers of Water-lillies, or Poplar, or ſuch like. In the fervent heat of Summer he muſt abſtain from Fumigations that do ſmell too ſtrongly, becauſe that by aſſaulting the head, they increaſe the pain.

If the Patient could go to that coſt, it were good to hang all the chamber where he lieth, and alſo the bed, with thick or coarſe linnen cloaths moiſtned in vinegar and water of Roſes. Thoſe linnen cloaths ought not to be very white, but ſomewhat brown, becauſe much and great whiteneſs doth diſperſe the ſight, and by waſting the ſpirits, doth increaſe the pain of the head: for which cauſe alſo the chamber ought not to be very lightſome.

Contrariwiſe, on the night ſeaſon there ought to be fires and perfumes made, which by their moderate light, may moderately call forth the ſpirits.

The materials for ſweet fires.

Sweet fires may be made of little pieces of the wood of Juniper, Broom, Aſh, Tamariſk, of the rind of Oranges, Limons, Cloves, Benzoin, Gum-Arabick, Orris-roots, Myrrh, groſly beaten together, and laid on the burning coals put into a chafing-diſh. Truly the breath or ſmoak of the wood or berries of Juniper, is thought to drive ſerpents a great way from the place where it is burnt. The virtue of the Aſh-tree againſt venom is ſo great, as *Pliny* teſtifieth, that a Serpent will not come under the ſhadow thereof, no, not in the morning, nor evening, when the ſhadow of any thing is moſt great and long, but he will run from it. I my ſelf have proved, that if a circle or compaſs be made with the boughs of an Aſh-tree, and a fire made in the midſt thereof, and a Serpent put within the compaſs of the boughs, that the Serpent will rather run into the fire than through the Aſh-boughs.

Lib. 16. cap. 13.

There is alſo another means to correct the Air. You may ſprinkle Vinegar of the decoction of Rue, Sage, Roſemary, Bay-berries, Juniper-berries, Cyprus-nuts, and ſuch like, on ſtones or bricks red hot, and put in a pot or pan, that all the whole chamber where the Patient lieth, may be perfumed with the vapor thereof.

Perfumes.

Alſo Fumigations may be made of ſome matter that is more groſs and clammy, that by the force of the fire the fume may continue the longer; as of *Ladanum*, Myrrh, Maſtich, Roſin, Turpentine, *Storax*, *Olibanum*, Benzoin, Bay-berries, Juniper-berries, Cloves, Sage, Roſemary, and Marjoram, ſtamped together, and ſuch like.

Sweet candles.

Thoſe that are rich and wealthy, may have Candles and Fumes made of Wax, or Tallow mixed with ſome ſweet things.

A ſponge macerated in Vinegar of Roſes, and Water of the ſame, and a little of the decoction of Cloves, and of Camphire added thereto, ought always to be ready at the Patients hand, that by often ſmelling unto it, the animal ſpirits may be recreated and ſtrengthened.

A ſweet water to ſmell to.

The water following is very effectual for this matter. Take of Orris four ounces, of Zedoary, Spikenard, of each ſix drams; of *Storax*, Benzoin, Cinnamon, Nutmegs, Cloves of each one ounce and half; of old Treacle, half an ounce: bruiſe them into groſs powder, and macerate them for the ſpace of twelve hours, in four pound of white and ſtrong wine; then diſtil them in a Lembick of glaſs on hot aſhes, and in that liquor wet a ſponge, and then let it be tied in a linnen cloth, or cloſed in a box, and ſo often put into the noſtrils. Or take of the vinegar and water of Roſes, of each four ounces; of Camphire, ſix grains; of Treacle, half a dram, let them be diſſolved together, and put into a viol of glaſs, which the patient may often put into his noſe.

A *Nodula* to ſmell to.

This *Nodula* following is more meet for this matter. Take of Roſe-leaves, two pugils; of Orris, half an ounce; of *Calamus aromaticus*, Cinnamon, Cloves, of each two drams; of *Storax* and Benzoin, of each one dram and a half; of Cyprus, half a dram; beat them into a groſs powder, make thereof a *Nodula* between two pieces of Cambrick or Lawn of the bigneſs of an hand-ball; then let it be moiſtned in eight ounces of Roſe-water, and two ounces of Roſe-vinegar, and let the patient ſmell to it often. Thoſe things muſt be varied according to the time: For in the Summer you muſt uſe neither Muſk nor Civet, nor ſuch like hot things: and moreover women that are ſubject to *fits* of the *Mother*, and thoſe that have Feavers or the head-ach, ought not to uſe thoſe things that are ſo ſtrong ſmelling and hot, but you muſt make choice of things more gentle: Therefore things are made with a little Camphire and Cloves bruiſed and macerated together in Roſe-water and vinegar of Roſes, ſhall be ſufficient.

CHAP. XX.

What Diet ought to be obſerved, and firſt of the choice of Meat.

Why ſuch as have the Plague may feed more fully.

THe order of Diet in a peſtilent diſeaſe ought to be cooling and drying; not ſlender, but ſomewhat full; becauſe by this kind of diſeaſe there cometh waſting of the ſpirits, and exſolution of the faculties, which inferreth often ſwounding, therefore that loſs muſt be repaired as ſoon as may be, with more quantity of meats that are of eaſie concoction and digeſtion; Therefore I never ſaw any being infected with the Peſtilence, that kept a ſlender diet, that recovered his health, but died; and few that had a good ſtomach, and fed well, died.

Sweet, groſs, moiſt and clammy meats, and thoſe which are altogether, and exquiſitely of ſubtil parts, are to be avoided, for the ſweet do eaſily take fire, and are ſoon inflamed; the moiſt will putrefie, the groſs and clammy obſtruct, and therefore engender putrefaction; thoſe meats that are of ſubtil parts, over much attenuate the humors, and inflame them; and do ſtir up hot and ſharp vapours into the brain, whereof cometh a Feaver. Therefore we muſt eſchew Garlick and Onions, Muſtard, ſalted and ſpiced Meats, and all kind of pulſe muſt alſo be avoided, becauſe they engender groſs winds, which are the authors of obſtruction: but the decoction of them is not always to be refuſed, becauſe it is a provoker of urine. Therefore let this be their order of diet: let their bread be of Wheat or Barly, well wrought, well leavened and ſalted, neither too new, nor too ſtale: let them be fed with ſuch meat as may be eaſily concocted and digeſted, and may engender

Pulſe muſt be ſhunned.

The manner of Diet.

gender much laudable juice, and very little excremental, as are the fleſh of Wether-Lambs, Kids, Leverets, Pullets, Partridges, Pigeons, Thruſhes, Larks, Quails, Black-birds, Turtle-doves, Moor-Hens, Pheaſants and ſuch like; avoiding Water-Fowls. Let the fleſh be moiſtned in Verjuice of unripe Grapes, Vinegar, or the juice of Limmons, Oranges, Citrons, tart Pomgranats, Barberies, Gooſeberries, or red Currans, or of Garden and Wild Sorrel: for all theſe ſowre things are very wholſom in this kind of diſeaſe, for they do ſtir up the appetite, reſiſt the venomous quality and putrefaction of the humours, reſtrain the heat of the Fever, and prohibit the corruption of the meats in the ſtomach. Although thoſe that have a more weak ſtomach, and are indued with a more exact ſenſe, and are ſubject to the Cough and diſeaſes of the Lungs, muſt not uſe theſe, unleſs they be mixed with Sugar and Cinamon.

If the Patient at any time be fed with ſodden meats, let the broths be made with Lettuce, Purſlain, Succory, Borage, Sorrel, Hops, Bugloſs, Creſſes, Burnet, Marigolds, Chervil, the cooling Seeds, French-Barly, and Oat-meal, with a little Saffron, for Saffron doth engender many ſpirits, and reſiſteth poiſon. To theſe opening roots may be added, to avoid obſtruction; yet much broth muſt be refuſed by reaſon of moiſture. The fruit of Capers eaten at the beginning of the meal provoke the appetite and prohibit obſtructions; but they ought not to be ſeaſoned with overmuch Oil and Salt, that they may alſo with good ſucceſs be put into broths.

Fiſhes are altogether to be avoided, becauſe they ſoon corrupt in the ſtomach: but if the Patient be delighted with them, thoſe that live in ſtony places muſt be choſen; that is to ſay, thoſe that live in pure and ſandy water, and about Rocks and Stones, as are Trouts, Pikes, Pearches, Gudgeons and Crevices boiled in milk, Wilks, and ſuch like. And concerning Sea-fiſh, he may be fed with Giltheads, Gurnarts, with all the kinds of Cod-fiſh, Whitings not ſeaſoned with ſalt, and Turbuts.

Eggs potched and eaten with the juice of Sorrel are very good. Likewiſe Barly-water ſeaſoned with the grains of a tart Pomgranat, and if the Fever be vehement, with the ſeeds of white Poppy. Such Barly-water is eaſie to be concocted and digeſted, it cleanſeth greatly and moiſtens and mollifieth the belly. But in ſome it procures an appetite to vomit, and pain of the head, and thoſe muſt abſtain from it. But in ſtead of Barly-water they may uſe Pap, and Bread crummed in the decoction of a Capon.

For the ſecond Courſe let him have Raiſins of the Sun newly ſodden in Roſe-water with Sugar, ſowre Damask Prunes, tart Cherries, Pippins, and Catharine Pears. *For the ſecond Courſe.*

And in the latter end of the Meal, Quinces roaſted in the Embers, Marmalate of Quinces, and Conſerves of Bugloſs or of Roſes, and ſuch like, may be taken: or elſe this Powder following. *In the end of the Meal.*

Take of Coriander-ſeeds prepared two drams, of Pearl, of Roſe-leaves, Shavings of Harts-horn and Ivory of each half a dram, of Amber two ſcruples, of Cinamon one ſcruple, of Unicorns horn, and the bone of a Stags heart of each half a ſcruple, of Sugar of Roſes four ounces: make thereof a Powder, and uſe it after meats.

If the Patient be ſomewhat weak, he muſt be fed with Gelly made of the fleſh of a Capon, and Veal ſodden together in the water of Sorrel, *Carduus Benedictus*, with a little quantity of Roſe Vinegar, Cinamon, Sugar, and other ſuch like, as the preſent neceſſity ſhall ſeem to require.

In the night ſeaſon for all events and miſchances, the Patient muſt have ready prepared, broth of meats of good digeſtion, with a little of the juice of Citrons or Pomgranats.

This reſtaurative that followeth may ſerve for all. Take of the Conſerve of Bugloſs, Borage, Violets, Water-lillies, and Succory, of each two ounces, of the powder of the Electuary *Diamargaritum frigidum*, of the Trochiſces of Camphire of each three drams, of Citron-ſeeds, *Carduus*-ſeeds, Sorrel-ſeeds, the Roots of *Dictamnus*, Tormentil, of each two drams, of the broth of a young Capon, made with Lettuce, Purſlain, Bugloſs and Borage boiled in it, ſix pints, put them in a Limbeck of glaſs with the fleſh of two Pullets, of ſo many Partridges, and with fifteen leaves of pure Gold: make thereof a diſtillation over a ſoft fire. Then take of the diſtilled liquor half a pint, ſtrain it through a woollen bag, with two ounces of white Sugar, and half a dram of Cinamon: let the Patient uſe this when he is thirſty. Or elſe put the fleſh of one old Capon, and of a leg of Veal, two minced Partridges, and two drams of whole Cinamon without any liquor, in a Limbeck of glaſs, well luted and covered, and ſo let them boil in *Balneo Mariæ*, unto the perfect concoction. For ſo the fleſhes will be boiled in their own juice, without any hurt of the fire; then let the juice be preſſed out therehence with a Preſs: give the Patient for every doſe, one ounce of the juice with ſome cordial waters, ſome *Triſantalum* and *Diamargaritum frigidum*. *A reſtaurative drink.*

The Preſerves of ſweet fruits are to be avoided, becauſe that ſweet things turn into choler; but the Confection of tart Prunes, Cherries, and ſuch like may be fitly uſed. But becauſe there is no kind of ſickneſs that ſo weakens the ſtrength as the Plague, it is always neceſſary, but yet ſparingly and often to feed the Patient, ſtill having reſpect unto his cuſtom, age, the region, and the time: for through emptineſs there is no great danger, leſt that the venomous matter that is driven out to the ſuperficial parts of the body, ſhould be called back into the inward parts, by an hungry ſtomach, and the ſtomach it ſelf ſhould be filled with cholerick, hot, thin, and ſharp excremental humours, whereof cometh biting of the ſtomach, and gripings in the guts.

CHAP. VII.

What drink the Patient infected ought to uſe.

IF the Fever be great and burning, the Patient muſt abſtain from Wine, unleſs he be ſubject to ſwouning: and he may drink the *Oxymel* following in ſtead thereof.

An *Oxymel.* Take of fair Water three quarts, wherein boil four ounces of Honey until the third part be conſumed, ſcumming it continually; then ſtrain it, and put it into a clean veſſel, and add thereto four ounces of Vinegar, and as much Cinnamon as will ſuffice to give it a taſte. Or elſe a ſugred Water, as followeth. Take two quarts of fair Water, of hard Sugar ſix ounces, of Cinamon two ounces; ſtrain it through a woollen bag or cloth without any boiling, and when the Patient will uſe it, put thereto a little of the juice of Citrons. The Syrup of the juice of Citrons excelleth amongſt all others that are uſed againſt the Peſtilence.

A Julip. The uſe of the Julip following is alſo very wholſom. Take of the juice of Sorrel well clarified half a pint, of the juice of Lettuce ſo clarified four ounces, of the beſt hard Sugar one pound, boil them together to a perfection; then let them be ſtrained and clarified, adding a little before the end a little Vinegar, and ſo let it be uſed between meals with boiled Water, or with equal portions of the Water of Sorrel, Lettuce, Scabious and Bugloſs: or take of this former deſcribed Julip ſtrained and clarified four ounces; let it be mixed with one pound of the fore-named Cordial waters, and boil them together a little. And when they are taken from the fire, put thereto of yellow Sanders one dram, of beaten Cinnamon half a dram, ſtrain it through a cloth: when it is cold, let it be given the Patient to drink with the juice of Citrons.

Thoſe that have been accuſtomed to drink Sider, Perry, Beer or Ale, ought to uſe that drink ſtill, ſo that it be clear, tranſparent and thin, and made of thoſe fruits that are ſomewhat tart; for troubled and dreggiſh drink doth not onely engender groſs humours, but alſo crudities, windineſs, and obſtructions of the firſt region of the body, whereof comes a Fever.

The commodities of Oxycrate. To whom hurtful. Oxycrate being given in manner following, doth aſſwage the heat of the Fever, and repreſs the putrefaction of the humours, and the fierceneſs of the venom, and alſo expelleth the Water through the Veins, if ſo be that the Patients are not troubled with ſpitting of bloud, cough, yexing, and altogether weak of ſtomach, for ſuch muſt avoid tart things.

Take of fair Water one quart, of white or red Vinegar three ounces, of fine Sugar four ounces, of Syrup of Roſes two ounces: boil them a little, and then give the Patient thereof to drink. Or take of the juice of Limmons and Citrons, of each half an ounce, of the juice of ſowre Pomgranats two ounces, of the Water of Sorrel and Roſes of each an ounce, of fair Water boiled, as much as ſhall ſuffice: make thereof a Julip, and uſe it between meals. Or take the Syrup of Limmons and of red Currans of each one ounce, of the Water of Lillies four ounces, of fair Water boiled half a pint: make thereof a Julip. Or take of the Syrups of Water-lillies and Vinegar, of each half an ounce, diſſolve it in five ounces of the Water of Sorrel, of fair Water one pint; make thereof a Julip.

The drinking of cold water, to whom, and when profitable. *Lib. 3. cap. 7.* But if the Patient be young, and have a ſtrong and good ſtomach, and cholerick by nature, I think it not unmeet for him to drink a full and large draught of Fountain water, for that is effectual to reſtrain and quench the heat of the Fever; and contrariwiſe, they that drink cold water often, and a very ſmall quantity at a time, as the Smith doth ſprinkle Water on the Fire at his Forge, do increaſe the heat and burning, and thereby make it endure the longer. Therefore by the judgment of *Celſus*, when the diſeaſe is in the chief increaſe, and the Patient hath endured thirſt for the ſpace of three or four days, cold water muſt be given unto him in great quantity, ſo that he may drink paſt his ſatiety, that when his belly and ſtomach are filled beyond meaſure, and ſufficiently cooled he may vomit.

Some do not drink ſo much thereof as may cauſe them to vomit, but do drink even unto ſatiety, and ſo uſe it for a cooling Medicin; but when either of theſe is done, the Patient muſt be covered with many cloths, and ſo placed that he may ſleep; and for the moſt part after long thirſt and watching, and after long fulneſs, and long and great heat, ſound ſleep cometh; by which great ſweat is ſent out, and that is a preſent help.

But thirſt muſt ſometimes be quenched with little pieces of Melons, Gourds, Cucumers, with the leaves of Lettuce, Sorrel and Purſlain made moiſt or ſoaked in cold Water, or with a little ſquare piece of a Citron, Limmon, or Orange, macerated in Roſe Water, and ſprinkled with Sugar, and ſo held in the mouth, and then changed.

But if the Patient be aged, his ſtrength weak, phlegmatick by nature, and given to Wine, when the ſtate of the Fever is ſomewhat paſt, and the chief heat beginning to aſſwage, he may drink Wine very much allaid at his meat, for to reſtore his ſtrength, and to ſupply the want of the waſted ſpirits. The Patient ought not by any means to ſuffer great thirſt, but muſt mitigate it by drinking, or elſe allay it by waſhing his mouth with oxycrate and ſuch like; and he may therein alſo waſh his hands and his face, for that doth recreate the ſtrength. If the flux or lask trouble him, he may very well uſe to drink ſteeled Water, and alſo boiled milk wherein many ſtones coming red hot out of the fire have been many times quenched. For the drineſs and roughneſs of the mouth, it is very good to have a cooling, moiſtening, and lenifying lotion of the mucilaginous water of the infuſion of the ſeeds of Quinces, *Pſilium, id eſt*, Flea-wort, adding thereto a little Camphire, with the Water of Plantain and Roſes, then cleanſe and wipe out the filth, and then moiſten the mouth by holding therein a little Oil of ſweet Almonds mixed with a little Syrup of Violets. If the roughneſs breed or degenerate into Ulcers, they muſt be touched with the Water of the infuſion of *ſublimate*, or *Aqua fortis*.

For drineſs or roughneſs of the mouth.

For the Ulcers thereof. But becauſe we have formerly made frequent mention of drinking of Water, I have here thought good to ſpeak ſomewhat of the choice and goodneſs of Waters. The choice of Water is not to be neglected,

neglected, becauſe a great part of our diet depends thereon; for beſides that we uſe it either alone or mixed with Wine for drink, we alſo knead bread, boil meat, and make broths therewith. Many think that rain-water which falls in Summer, and is kept in a Ciſtern well placed and made, is the wholeſomeſt of all. Then next thereto they judge that Spring-water which runs out of the tops of Mountains, through Rocks, Cliffs, and Stones: in the third place they put Well-water, or that which riſeth from the foots of Hills. Alſo the River-water is good, that is taken out of the midſt or ſtream. Lake or Pond-water is the worſt, eſpecially if it ſtand ſtill, for ſuch is fruitful of and ſtored with many venemous Creatures, as Snakes, Toads, and the like. That which comes by the melting of Snow and Ice is very ill, by reaſon of the too refrigerating faculty and earthly nature. But of Spring and Well-waters theſe are to be judged the beſt which are inſipid, without ſmell and colour, ſuch as are clear, warmiſh in Winter, and cold in Summer, which are quickly hot and quickly cold, that is, which are moſt light, in which all manner of Pulſe, Turnips and the like, are eaſily and quickly boiled. Laſtly, When as ſuch as uſually drink thereof, have clear voices and ſhrill, their cheſts ſound, and a lively and freſh colour in their faces.

The choice of Waters.

Hip. ſect. 3. Aph. 26.

CHAP. XXII.

Of Antidotes to be uſed in the Plague.

NOw we muſt treat of the proper cure of this diſeaſe, which muſt be uſed as ſoon as may be poſſible, becauſe this kind of poiſon, in ſwiftneſs exceedeth the celerity of the Medicin. Therefore it is better to err in this, that you ſhould think every diſeaſe to be peſtilent in a peſtilent ſeaſon, and to cure it as the Peſtilence: becauſe that ſo long as the Air is polluted with the ſeeds of the Peſtilence, the humours in the body are ſoon infected with the vicinity of ſuch an Air, ſo that then there happeneth no diſeaſe void of the Peſtilence, that is to ſay, which is not peſtilent from the beginning by his own nature, or which is not made peſtilent.

Many begin the cure with Bloud-letting, ſome with Purging, and ſome with Antidotes. We taking a conſideration of the ſubſtance of that part that is aſſaulted, firſt of all begin the cure with an Antidote; becauſe that by its ſpecifick property it defends the heart from poiſon, as much as it is offended therewith. Although there are alſo other Antidotes which preſerve and keep the heart and the Patient from the danger of Poiſon and the Peſtilence, not only becauſe they do infringe the power of the poiſon in their whole ſubſtance, but alſo becauſe they drive and expel it out of all the body by ſweat, vomiting, ſcouring, and ſuch other kinds of evacuations.

The beginning of the cure muſt be by Antidotes.

The Antidote muſt be given in ſuch a quantity as may be ſufficient to overcome the poiſon; but becauſe it is not good to uſe it in greater quantity than needeth, leſt it ſhould overthrow our Nature, for whoſe preſervation onely it is uſed; therefore that which cannot be taken together at once, muſt be taken at ſeveral times, that ſome portion thereof may daily be uſed ſo long, until all the accidents, effects and impreſſions of the poiſon be paſt; and that there be nothing to be feared. Some of thoſe Antidotes conſiſt of portions of venemous things being tempered together, and mixed in an apt proportion with other Medicins whoſe power is contrary to the venom: as Treacle, which hath for an ingredient the fleſh of Vipers, that it being thereto mixed may ſerve as a guide to bring all the Antidote unto the place where the venenate malignity hath made the chief impreſſion, becauſe by the ſimilitude of Nature and Sympathy, one poiſon is ſuddenly ſnatched and carried into another. There are other abſolutely poiſonous, which nevertheleſs are Antidotes one unto another; as a Scorpion himſelf cureth the pricks of a Scorpion. But Treacle and Mithridate excell all other Antidotes, for by ſtrengthening the nobleſt part, and the manſion of life, they repair and recreate the waſted ſpirits, and overcome the poiſon, not onely being taken inwardly, but alſo applied outwardly to the region of the heart, Botches and Carbuncles: for by an hidden property they draw the poiſons unto them, as Amber doth Chaff, and digeſt it when it is drawn, and ſpoil and rob it of all its deadly force; as it is declared at large by *Galen*, in his Book *De Theriaca ad Piſonem*, by moſt true reaſons and experiment. But you will ſay that theſe things are hot, and that the Plague is often accompanied with a burning Fever. But thereto I anſwer, there is not ſo great danger in the Fever as in the Peſtilence, although in the giving of Treacle, I would not altogether ſeem to neglect the Fever, but think it good to miniſter or apply it mixed with cordial-cooling Medicins, as with the Trochiſces of Camphire, Syrup of Limmons, of Water-lillies, the Water of Sorrel and ſuch like. And for the ſame cauſe we ought not to chuſe old Treacle, but that which is of a middle age, as of one or two years old: to thoſe that are ſtrong you may give half a dram; and to thoſe that are more weak, a dram.

In what quantity they muſt be taken.

Why poyſonous things are put into Antidotes.

Some poiſons Antidotes to other ſome.

The Patient ought to walk preſently after he hath taken Treacle, Mithridate, or any other Antidote, but yet as moderately as he can: not like unto many, which when they perceive themſelves to be infected, do not ceaſe to courſe and run up and down, until they have no ſtrength to ſuſtain their bodies; for ſo they diſſolve Nature, ſo that it cannot ſuffice to overcome the contagion. After moderate walking the Patient muſt be put warm to bed, and covered with many cloaths, and warm Brick-bats or Tiles applied to the ſoles of his feet; or in ſtead thereof you may uſe Swines bladders filled with hot Water, and apply them to the groins and arm-holes, to provoke ſweat: for ſweating in this diſeaſe is a moſt excellent remedy, both for to evacuate the humours in the Fever, and alſo to drive forth the malignity in the Peſtilence, although every ſweat brings not forth the fruit of health. For *George Agricola* ſaith, that he ſaw a Woman at *Miſnia* in *Germany*, that did ſweat ſo for the ſpace of three days, that the bloud came forth at her head and breſt, and yet nevertheleſs ſhe died.

How to walk after the taking of an Antidote.

This Potion following will provoke ſweat. Take the roots of China ſhaved in thin pieces one ounce and half, of *Guaiacum* two ounces, of the bark of Tamariſk one ounce, of Angelica-roots two

A Sudorifick Potion.

two drams, of the ſhavings of Harts-horn one ounce, of Juniper-berries three drams: put them into a viol of glaſs that will contain ſix quarts, put thereto four quarts of running or river-water that is pure and clear, macerate them for the ſpace of one whole night on the aſhes, and in the morning boil them all in *Balneo Mariæ* until the half be conſumed, which will be done in the ſpace of ſix hours, then let them be ſtrained through a bag, and then ſtrained again, but let that be with ſix ounces of Sugar of Roſes, and a little Treacle: let the Patient take eight ounces or fewer of that liquor, and it will provoke ſweat. The Powder following is alſo very profitable. Take of the leaves of *Dictamnus*, the Roots of Tormentil, Betony, of each half an ounce, of Bole-Armenick prepared one ounce, of *Terra Sigillata* three drams, of Aloes and Myrrh, of each half a dram, of Saffron one dram, of Maſtich two drams, powder them all according to Art, and give one dram thereof diſſolved in Roſe-water, or the water of wild Sorrel, and let the Patient walk ſo ſoon as he hath taken that Powder, then let him be laid in his bed to ſweat, as I have ſhewed before.

A Sudorifick Powder.

A diſtilled water againſt the Plague.

The Water following is greatly commended againſt poiſon. Take the roots of *Gentian* and *Cyperus* of each three drams; of *Carduus Benedictus*, Burnet, of each one handful; of Sorrel ſeeds, and Devils-bit, of each two pugils; of Ivy and Juniper-berries, of each half an ounce; of the Flowers of Bugloſs, Violets, and red Roſes, of each two pugils: Powder them ſomewat groſly, then ſoak or ſteep them for a night in white Wine and Roſe water: then add thereto of Bole-Armenick one ounce, of Treacle half an ounce, diſtil them all in *Balneo Mariæ*, and keep the diſtilled liquor in a viol of glaſs well covered or cloſe ſtopped for your uſe: let the Patient take ſix ounces thereof with Sugar and a little Cinnamon and Saffron: then let him walk, and then ſweat as is aforeſaid: the Treacle and Cordial water formerly preſcribed, are very profitable for this purpoſe. Alſo the Water following is greatly commended. Take of Sorrel ſix handfuls, of Rue one handful, dry them and macerate them in Vinegar for the ſpace of four and twenty hours, adding thereto four ounces of Treacle: make thereof a diſtillation in *Balneo Mariæ*, and let the diſtilled water be kept for your uſe: and ſo ſoon as the Patient doth think himſelf to be infected, let him take four ounces of that liquor, then let him walk and ſweat. He muſt leave ſweating when he beginneth to wax faint and weak, or when the humour that runs down his body begins to wax cold, then his body muſt be wiped with warm cloths, and dried. The Patient ought not to ſweat with a full ſtomach, for ſo the heat is called away from performing the office of concoction, alſo he muſt not ſleep when he is in his ſweat, leſt the malignity go inwardly with the heat and ſpirits unto the principal parts: but if the Patient be much inclined to ſleep, he muſt be kept from it with hard rubbing, and bands tied about the extreme parts of his body, and with much noiſe of them that are about him, and let his friends comfort him with the good hope that they have of his recovery; but if all this will not keep him from ſleep, diſſolve *Caſtoreum* in tart Vinegar, and *Aqua Vitæ*, and let it be injected into his noſtrils: and let him be kept continually waking the firſt day, and on the ſecond, and third, even unto the fourth; that is to ſay, unto the perfect expulſion of the venom; and let him not ſleep above three or four hours on a day and a night. In the mean time let the Phyſician that ſhall be preſent conſider all things by his ſtrength; for it is to be feared that great watchings will diſſolve the ſtrength, and make the Patient weak: you muſt not let him eat within three hours after his ſweating; in the mean ſeaſon, as his ſtrength ſhall require, let him take the rind of a Preſerved Citron, Conſerve of Roſes, Bread toaſted and ſteeped in Wine, the meat of Preſerved Myrabolane, or ſome ſuch like thing.

Another.

What means to be uſed in ſweating.

CHAP. XXIII.

Of Epithemes to be uſed for the ſtrengthening of the principal parts.

Whereof they muſt be made

THere are alſo ſome topick Medicins to be reckoned amongſt Antidotes, which muſt be outwardly applied as ſpeedily as may be, as cordial and hepatick Epithems for the ſafety of the noble parts, and ſtrengthening of the faculties, as thoſe that drive the venenate air far from the bowels: they may be made of cordial things not onely hot, but alſo cold, that they may temper the heat, and more powerfully repercuſs. They muſt be applied warm with Scarlet, or a double linnen cloth, or a ſoft Sponge dipped in them, if ſo be that a Carbuncle do not poſſeſs the regions of the moſt noble parts: for it is not fit to uſe repercuſſives to a Carbuncle. You may make Epithems after the following forms: ℞ *Aquar. roſ. plantag. & ſolan. an.* ʒ iv. *aquæ acetoſ. vini granat. & aceti, an.* ʒ iij. *ſantal. rub. & coral. rub. pulveriſ. an.* ʒ iij. *theriac. vet.* ʒ ß. *camph.* ϑ j. *croci* ϑ j. *caryoph.* ʒ ß. *miſce, fiat epithema.* Or elſe, ℞ *Aq. roſ. & plantag. an.* ʒ x. *aceti roſ.* ʒ iv. *caryoph. ſant. rub. coral. rub. pulveriſ. pul. diamargarit. frigid. an.* ʒ j. ß. *camphuræ moſchi an.* ϑ j. *fiat epithema.* Or, ℞ *Aquar. roſar. & meliſſæ, an.* ʒ iv. *aceti roſ.* ʒ iij. *ſant. rub.* ʒ j. *caryophil.* ʒ ß. *croci* ϑ ij. *camphuræ* ϑ j. *boli arm. terra ſigill. & zedoar. an.* ʒ j. *fiat epithema.* Or elſe, ℞ *Aceti roſ. & aquæ roſat. an.* ℔ ß. *camphuræ* ʒ ß. *theriac. & mithrid. an.* ʒ j. *fiat epithema.* Or elſe, *Aqu. roſar. nenuph. bugloſ. acetoſæ, aceti roſar. an.* ℔ ß. *ſant. rub. roſ. rub. an.* ʒ iij. *flor. nenuph. violar. camphur. an.* ʒ ß. *mithrid. & theriac. an.* ʒ ij. *terantur & miſceantur ſimul omnia.* When you intend to uſe them take ſome portion of them in a veſſel by its ſelf, wherewith let the affected bowel be fomented warm.

Repercuſſives not fit to be applied to Carbuncles.

CHAP. XXIV.

Whether Purging and Bloud-letting be neceſſary in the beginning of Peſtilent diſeaſes.

Reaſons for and againſt Bloud-letting in the Plague.

SO ſoon as the heart is ſtrengthened and corroborated with Cordials and Antidotes, we muſt come to phlebotomy and purging. As concerning Bloud-letting in this caſe there is a great controverſie among Phyſicians. Thoſe that wiſh it to be uſed, ſay or affirm, that the Peſtilent

peſtilent Fever doth infix it ſelf in the bloud, and therein alſo the Peſtilent malignity taketh its ſeat; and therefore it will ſoon infect the other humours, unleſs that the bloud be evacuated, and the infection that remaineth in the bloud be thereby taken away. Contrariwiſe, thoſe that do not allow phlebotomy in this caſe, alledge that it often cometh to paſs that the bloud is void of malignity, when the other humours are infected with the venemous contagion. If any man require my judgment in this doubtful queſtion, I ſay, that the peſtilence ſometimes doth depend on the default of the air: this default being drawn through the paſſages of the body, doth at length pierce unto the intrails, as we may underſtand by the abſceſſes which break out, one while behind the ears, ſometimes in the arm-holes, and ſometimes in the groins, as the brain, heart or liver are infected. And hereof alſo come Carbuncles, and other collections of matter, and eruptions, which are ſeen in all parts of the body; by reaſon that Nature uſing the ſtrength of the expulſive faculty, doth drive forth whatſoever is noiſom or hurtful. Therefore if the Phyſician will follow this motion of Nature, he muſt neither purge nor let bloud, leſt that by a contrary motion, that is, by drawing in from without, the motion of Nature which proceeds outwardly from within, ſhould be troubled. So we often ſee in thoſe who are purged or let bloud for ſuch Buboes as come through unlawful copulation, that the matter is thereby made contumacious, and by drawing it inwardly, it ſpeedily cauſeth the French Pox.

The compoſing of this controverſie.

Wherefore when Buboes, Carbuncles, and other peſtilent eruptions appear, which come through the default of the air, we ought to abſtain from purging and phlebotomy; but it is ſufficient to forearm the heart inwardly and outwardly with Antidotes that are indued with a proper virtue of reſiſting the poiſon. For it is not to be doubted, but that when nature is debilitated with both kinds of evacuation, and when the ſpirits together with the bloud, are exhauſted, the venemous air will ſoon pierce, and be received into the empty body, where it exerciſeth its tyranny to the utter deſtruction thereof.

An Hiſtory.

In the year of our Lord God 1566. in which year there was great mortality throughout all *France*, by reaſon of the Peſtilence and peſtilent diſeaſes, I earneſtly, and diligently inquired of all the Phyſicians and Chirurgions of all the Cities (through which King *Charles* IX. paſſed in his progreſs unto *Bayon*) what ſucceſs their Patients had after they were let bloud and purged: whereunto they all anſwered alike, that they had diligently obſerved, that all that were infected with the Peſtilence, and were let bleed ſome quantity of bloud, or had their bodies ſomewhat ſtrongly purged, thenceforwards waxed weaker and weaker, and ſo at length died; but others which were not let bloud nor purged, but took cordial Antidotes inwardly, and applied them outwardly, for the moſt part eſcaped and recovered their health: for that kind of Peſtilence took its original of the primitive and ſolitary default of the air, and not of the corruption of the humours.

When purging and bleeding may be uſed.

The like event was noted in the hoarſneſs that we ſpoke of before; that is to ſay, that the Patients waxed worſe and worſe by purging and phlebotomy; but yet I do not diſallow either of thoſe remedies, if there be great fulneſs in the body, eſpecially in the beginning, and if the matter have a cruel violence, whereof may be feared the breaking in unto ſome noble part. For we know that it is confirmed by *Hippocrates*, that what diſeaſe ſoever is cauſed by repletion, muſt be cured by evacuation; and that in diſeaſes that are very ſharp, if the matter do ſwell, it ought to be remedied the ſame day, for delay in ſuch diſeaſes is dangerous; but ſuch diſeaſes are not cauſed or inflicted upon mans body by reaſon or occaſion of the peſtilence, but of the diſeaſed bodies, and diſeaſes themſelves commixed together with the peſtilence: therefore then peradventure it is lawful to purge ſtrongly, and to let a good quantity of bloud, leſt that the peſtilent venom ſhould take hold of the matter that is prepared, and ſo infect it with a contagion, whereby the peſtilence taketh new and far greater ſtrength; eſpecially as *Celſus* admoniſheth us, where he ſaith, that by how much the ſooner thoſe ſudden invaſions do happen, by ſo much the ſooner remedies muſt be uſed, yea, or rather raſhly applied; therefore if the Veins ſwell, the face wax fiery red; if the arteries of the Temples beat ſtrongly; if the Patient can very hardly breath by reaſon of a weight in his ſtomach, if his ſpittle be bloudy, then ought he to be let bloud without delay, for the cauſes before mentioned. It ſeems beſt to open the Liver-vein on the left arm, whereby the heart and ſpleen may be better diſcharged of their abundant matter; yet bloud-letting is not good at all times, for it is not expedient when the body beginneth to wax ſtiff by reaſon of the coming of a Fever; for then by drawing back the heat and ſpirits inwardly, the outward parts being deſtitute of bloud, wax ſtiff and cold; therefore bloud cannot be let then without great loſs of the ſtrength, and perturbation of the humours. And it is to be noted, that when thoſe plethorick cauſes are preſent, there is one Indication of bloud-letting in a ſimple peſtilent Fever, and another in that which hath a Bubo, *id eſt*, a Botch, or a Carbuncle joined therewith. For in one or both of theſe, being joined with a vehement and ſtrong burning Fever, bloud muſt be letten by opening the Vein that is neareſt unto the tumour or ſwelling againſt nature, keeping the ſtraitneſs of the fibres, that this being open the bloud might be drawn more directly from the part affected; for all and every retraction of putrefied bloud unto the noble parts, is to be avoided, becauſe it is noiſom and hurtful to Nature, and to the Patient. Therefore for example ſake, admit the Patient be plethorick by repletion, which is called *ad Vaſa*, *id eſt*, unto the Veſſels, and *ad Vires*, *id eſt*, unto the ſtrength; and therewithall he hath a tumour that is peſtilent in the parts belongingunto the head or neck; the bloud muſt be let out of the Cephalick or Median Vein, or out of one of their branches diſperſed in the arm on the grieved ſide. But if through occaſion of fat, or any other ſuch like cauſe, thoſe Veins do not appear in the arm, there be ſome that give counſel in ſuch a caſe to open the vein that is between the fore-finger and the thumb, the hand being put into warm water, whereby that Vein may ſwell and be filled with bloud gathered thither by means of the heat.

Aph. 22. *ſect.* 2. *Aph.* 10. *ſect.* 4.

Cap. 7. *lib.* 3.

Why bloud muſt be let on the left arm in the Plague.

If the tumour be under the harm-hole, or about thoſe places, the Liver-vein or the Median muſt be opened which runneth alongſt the hand: if it be in the groin, the vein of the ham, or *Saphena*;

or any other vein above the foot that appeareth well, but always on the grieved ſide. And Phlebotomy muſt be performed before the third day: for this diſeaſe is of the kind or nature of ſharp diſeaſes, becauſe that within four and twenty hours it runneth paſt help. In letting of bloud you muſt have conſideration of the ſtrength. You may perceive that the Patient is ready to ſwoun when that his forehead waxeth moiſt, with a ſmall ſweat ſuddenly ariſing by the aking or pain at the ſtomach, with an appetite to vomit, and deſire to go to ſtool, gaping, blackneſs of the lips, and ſudden alteration of the face unto paleneſs: and laſtly moſt certainly by a ſmall and ſlow pulſe: and then you muſt lay your finger on the vein, and ſtop it until the Patient come to himſelf again, either by Nature, or elſe reſtored by Art; that is to ſay, by giving unto him Bread dipped in Wine, or any other ſuch like thing: then if you have not taken bloud enough, you muſt let it go again, and bleed ſo much as the greatneſs of the diſeaſe, or the ſtrength of the Patient will permit or require: which being done, ſome of the Antidotes that are preſcribed before will be very profitable to be drunk, which may repair the ſtrength, and infringe the force of the malignity.

CHAP. XXV.

Of purging Medicins in a Peſtilent diſeaſe.

What Purges fit in the Plague.

IF you call to mind the proper Indications, purging ſhall ſeem neceſſary in this kind of diſeaſe, and that muſt be preſcribed as the preſent caſe and neceſſity requireth; rightly conſidering that the diſeaſe is ſudden, and doth require Medicins that may with all ſpeed drive out of the body the hurtful humour wherein the noiſom quality doth lurk and is hidden; which Medicins are divers by reaſon of the diverſity of the kind of the humour, and the condition or temperature of the Patient. For this purpoſe ſix grains of Scammony beaten into Powder, or elſe ten grains are commonly miniſtred to the Patient with one dram of Treacle. Alſo Pills may be made in this form: Take of Treacle and Mithridate of each one dream, of *Sulphur vivum* finely powdered, half a dram, of *Diagridium* four grains; make Pills thereof. Or take three drams of Aloes, of Myrrh and Saffron of each one dram, of white Hellebore and *Aſarabacca*, of each ℈ iv. make thereof a maſs with old Treacle, and let the Patient take four ſcrupples thereof for a doſe, three hours before meat. *Ruffus* his Pills may be profitably given to thoſe that are weak. The ancient Phyſicians have greatly commended Agarick for this diſeaſe, becauſe it doth draw the noiſom humours out of all the members: and the virtues thereof are like unto thoſe of Treacle; for it is thought to ſtrengthen the heart, and to draw out the malignity by purging. To thoſe that are ſtrong, the weight of two drams may be given, and to thoſe that are more weak, half a dram. It is better to give the infuſion in a decoction than in ſubſtance, for being elected and prepared truly into Trochiſces, it may be called a divine kind of Medicin.

Pills.

Antimonium is highly praiſed by the experience of many; but becauſe I know the uſe thereof is condemned by the Council and decree of the School of Phyſicians at *Paris*, I will here ceaſe to ſpeak of it.

Thoſe Medicins that cauſe ſweats are thought to excel all others, when the Peſtilence cometh of the venemous air; among whom the efficacy of that which followeth, hath been proved, to the great good of many in that Peſtilence which was lately throughout all *Germany*, as *Matthias Rodler* Chancelour to Duke *George* the Count Palatine ſignified unto me by Letters.

An effectual ſudorifick, and alſo purging Medicin.

They do take a bundle of Mugwort, and of the aſhes thereof after it is burnt, they make a lee with four pints of Water, then they do ſet it over the fire, and boil it in a veſſel of Earth well leaded, until the liquor be conſumed, the earthy dregs falling into the bottom like unto ſalt, whereof they make Trochiſces of the weight of a crown of gold: then they diſſolve one or two of theſe Trochiſces, according to the ſtrength of the Patient, in good Muskadine, and give it the Patient to drink, and let him walk after that he hath drunk it for the ſpace of half an hour; then lay him in his bed, and there ſweat him two or three hours, and then he will vomit, and his belly will be looſed as if he had taken Antimony; and ſo they were all for the moſt part cured, eſpecially all thoſe that took that remedy betimes: and before the diſeaſe went to their heart, as I my ſelf have proved in ſome that were ſick at *Paris*, with moſt happy ſucceſs. Truly Mugwort is moſt highly commended by the ancient Phyſicians, being taken and applied inwardly or outwardly, againſt the bitings of venemous Creatures; ſo that it is not to be doubted but that it hath great virtue againſt the Peſtilence.

The virtues of Mugwort.

Vid. Rondelet. lib. 7. de piſc. c. 3.

I have heard it moſt certainly reported by *Gilbertus Heroaldus* Phyſician of *Mompelier*, that eight ounces of the pickle of Anchovies drunk at one draught, is a moſt certain and approved remedy againſt the Peſtilence, as he and many other have often found by experience. For the Plague is no other thing but a very great putrefaction, for the correction and amendment whereof, there is nothing more apt or fit than this pickle or ſubſtance of Anchovies, being melted by the Sun and force of the ſalt that is ſtrewed thereon. There be ſome which infuſe one dram of Walwort ſeed in white Wine, and affirm that it drunk, will perform the like effect as Antimony. Others diſſolve a little weight of the ſeed of *Rue* being bruiſed in Muskadine, with the quantity of a Bean of Treacle, and ſo drink it. Others beat or bruiſe an handful of the leaves or tops of Broom in half a pint of white-Wine, and ſo give it to the Patient to drink, to cauſe him to vomit, looſe his belly and make him to ſweat. Truly thoſe that are wounded or bit with venemous Beaſts, if they bind Broom above the wound, it will prohibit or hinder the venom from diſperſing it ſelf, or going any further: therefore a drink made thereof will prohibit the venom from going any nearer the heart. Some take of the root of Elecampane, Gentian, Tormentil, Kermes-berries, and Broom, of the Powder of Ivory and Harts-horn, of each half a dram; they do bruiſe and beat all theſe, and infuſe them for the ſpace of four and and twenty hours in white Wine and *Aqua Vitæ* on the warm embers, and then ſtrain it, and give the Patient three or four ounces thereof to drink; this provokes Sweat and infringeth the power of the poiſons: and the Potion following hath the ſame virtue. Take good Muſtard half an ounce, of Trea-

A Potion.

cle

cle or Mithridate the weight of a Bean; diſſolve them in white Wine and a little *Aqua Vitæ*, and let the Patient drink it, and ſweat thereon with walking. You may alſo roaſt a great Onion made hollow, and filled with half a dram of Treacle and Vinegar under the embers, and then ſtrain it, and mix the juice that is preſſed out of it with the water of Sorrel, *Carduus Benedictus*, or any other cordial thing, and with ſtrong Wine, and give the Patient to drink thereof to provoke ſweat, and to repel the malignity. Or elſe take as much Garlick as the quantity of a Nut; of Rue and Celandine of each twenty leaves; bruiſe them all in white Wine and a little *Aqua Vitæ*; then ſtrain it and give the Patient thereof to drink. There be ſome that do drink the juice that is preſſed out of Celandine and Mallows, with three ounces of Vinegar, and half an ounce of the Oil of Wall-nuts, and then by much walking do unburthen their ſtomach and belly upwards and downwards, and ſo are helped. When the venemous air hath already crept into and infected the humours, one dram of the dried leaves of the Bay tree macerated for the ſpace of two days in Vinegar and drunk, is thought to be a moſt ſoveraign Medicin to provoke ſweat, looſeneſs of the belly and vomiting.

Matthiolus in his Treatiſe *De Morbo Gallico* writeth, that the Powder of *Mercury* miniſtred unto the Patient with the juice of *Carduus Benedictus*, or with the Electuary *De Gemmis*, will drive away the Peſtilence before it be confirmed in the Body, by provoking vomit, looſneſs of the belly and ſeat: one dram of *Calcanchum* or white Copperas diſſolved in Roſe water, performeth the like effect in the ſame diſeaſe. Some do give the Patient a little quantity of the Oil of Scorpions with white Wine, to expel the poiſon by vomit, and therewithall they anoint the region of the heart, the breſt and the wriſts of the hands. I think theſe very meet to be uſed often in bodies that are ſtrong and well exerciſed, becauſe weaker Medicins do evacuate little or nothing at all, but onely move the humours, whereby cometh a Fever. When a ſufficient quantity of the malignity is evacuated, then you muſt miniſter things that may ſtrengthen the belly and ſtomach, and with-hold the agitation or working of the humours: and ſuch is the confection of Alkermes.

CHAP. XXVI.

Of many Symptoms which happen together with the Plague: and firſt of the pain of the Head.

IF the malignity be carried into the brain, and Nature be not able to expel it, it inflames not onely it but alſo the membranes that cover it: which inflammation doth one while hurt, trouble, or aboliſh the imagination, another while the judgment, and ſometimes the memory, according to the ſituation of the inflammation, whether it be in the former, or hinder, or middle part of the head; but hereof cometh always a Phrenſie, with fiery redneſs of the eyes and face, and heavineſs and burning of the whole head. If this will not be amended with Clyſters, and with opening the Cephalick Vein in the arm, the arteries of the Temples muſt be opened, taking ſo much bloud out of them, as the greatneſs of the ſymptoms and the ſtrength of the Patient ſhall require and permit. Truly the inciſion that is made in opening an artery will cloſe and join together as readily, and with as little difficulty as the inciſion of the vein. And of ſuch an inciſion of an artery cometh preſent help, by reaſon that the tenſive and ſharp vapours do plentifully breath out, together with the arterious bloud. It were alſo very good to provoke a flux of bloud at the noſe, if Nature be apt to exonerate her ſelf that way. For as *Hippocrates* ſaith, when the head is grieved, or generally aketh, if matter, water or blood flow out at the noſtrils, mouth, or ears, it preſently cures the diſeaſe. Such bleeding is to be provoked by ſtrong blowing, or ſtriving to cleanſe the noſe by ſcratching or pricking of the inner ſide of the noſtrils, by pricking with an horſe-hair, and long holding down of the head.

The cauſe of Phrenſie in the Plague.

The benefit of opening an artery.

Aph. 10. ſect. 6.

The Lord of *Fountains*, a Knight of the Order, when we were at *Bayon*, had a bleeding at the noſe, which came naturally for the ſpace of two days, and thereby he was freed of a peſtilent Fever which he had before, a great ſweat ariſing therewithall; and ſhortly after his Carbuncles came to ſuppuration, and by Gods grace he recovered his health being under my cure. If the bloud do flow out and cannot be ſtopped when it ought, the hands, arms, and legs muſt be tied with bands, and Sponges wet in Oxycrate muſt be put under the arm-holes, Cupping-glaſſes muſt be applied unto the dugs, and to the region of the Liver and Spleen; and you muſt put into the noſtrils the doun of the Willow tree, or any other aſtringent Medicin, incorporated with the hairs pluckt from the flank, belly or throat of an Hare, Bole-Armenick, *Terra Sigillata*, the juice of Plantain and Knot-graſs mixed together; and furthermore the Patient muſt be placed or laid in a cool place. But if the Patient be nothing mitigated notwithſtanding all theſe fluxes of bloud, we muſt come to Medicins that procure ſleep, whoſe forms are theſe.

An Hiſtory.

To ſtay bleeding.

Take of green Lettuce one handful, Flowers of Water-lillies and Violets, of each two pugils; one heap of white Poppy bruiſed, of the Four cold Seeds, of each two drams; of Licorice and Raiſins of each one dram; make thereof a decoction, and in the ſtraining diſſolve one ounce and an half of *Diacodium*: make thereof a large potion to be given when they go to reſt. Alſo Barly-cream may be prepared in the water of Water-lillies and of Sorrel of each two ounces adding thereto ſix or eight grains of *Opium*, of the Four cold Seeds, and of white Poppy Seeds, of each half an ounce; and let the ſame be boiled in Broth with Lettuce and Purſlain; alſo the Pills *De Cynogloſſo*, *i. e.* Hounds-tongue may be given. Clyſters that provoke ſleep muſt be uſed, which may be thus prepared. Take of Barly-water half a pint, Oil of Violets and Water-lillies, of each two ounces; of the Water of Plantain and Purſlain, or rather of their juices, three ounces; of Camphire ſeven grains, and the Whites of three Eggs: make thereof a Clyſter. The head muſt be fomented with Roſe Vinegar, the hair being firſt ſhaved away, leaving a double cloth wet therein on the ſame, and often renewed. Sheeps-lungs taken warm out of the bodies, may be applied to the head, as long as they are warm. Cupping-glaſſes with and without ſcarification may be applied to the neck and ſhoulder-blades. The arms and legs muſt be ſtrongly bound, being firſt well rubbed, to divert the ſharp vapours and humours from

Medicins to procure ſleep.

from the head. Frontals may alſo be made on this manner. Take of the Oil of Roſes and Water-lillies, of each two ounces; of the Oil of Poppy half an ounce; of *Opium* one dram, of Roſe Vinegar one ounce, of Camphire half a dram; mix them together. Alſo Nodulaes may be made of the flowers of Poppies, Henbane, Water-lillies, Mandrags, beaten in Roſe water with a little Vinegar, and a little Camphire, and let them be often applied to the noſtrils: for this purpoſe Cataplaſms alſo may be laid to the forehead. As, Take of the mucilage of the ſeeds of *Pſilium, i. e.* Flea-wort, and Quince ſeeds extracted in Roſe water, three ounces; of Barly-meal four ounces, of the Powder of Roſe leaves, the flowers of Water-lillies and Violets, of each half an ounce; of the ſeeds of Poppies and Purſlain, of each two ounces; of the water and vinegar of Roſes, of each three ounces; make thereof a Cataplaſm, and apply it warm to the head. Or take of the juice of Lettuce, of Water-lillies, Henbane, Purſlain, of each half a pint; of Roſe leaves in powder, the ſeeds of Poppy, of each half an ounce; Oil of Roſes three ounces, of Vinegar two ounces, of Barly-meal as much as ſhall ſuffice: make thereof a Cataplaſm in the form of a liquid Pultis. When the heat of the head is mitigated by theſe Medicins, and the inflammation of the brain aſſwaged, we muſt come unto digeſting, and reſolving fomentations, which may diſperſe the matter of the vapours. But commonly in pain of the head, they do uſe to bind the forehead and hinder part of the head very ſtrongly, which in this caſe muſt be avoided.

A Cataplaſm.

CHAP. XXVII.

Of the heat of the Kidnies.

THe heat of the Kidnies is tempered by anointing with *unguent. refrigerans Galeni* newly made adding thereto the Whites of Eggs well beaten, that ſo the Ointment may keep moiſt the longer; let this liniment be renewed every quarter of an hour, wiping away the reliques of the old. Or, ℞ *Aq. roſar.* ℔ ß. *ſucci plant.* ℥ iv. *alb. ovorum* iv. *olei roſacei, & nenuph. an.* ℥ j. *aceti roſ.* ℥ iij. *miſce ad uſum.* When you have anointed the part, lay thereon the leaves of Water-lillies, or the like old herbs, and then preſently thereupon a double linnen cloth dipped in Oxycrate and wrung out again, and often changed; the Patient ſhall not lie upon a Feather-bed, but on a quilt ſtuffed with the chaff of Oats, or upon a Mat with many doubled cloths or Chamlet ſpread thereon. To the region of the heart may in the mean time be applied a refrigerating and alexiterial Medicin, as this which followeth. ℞ *Ung. roſat.* ℥ iij. *olei nenupharini,* ℥ j. *acet. roſ. & aq. roſ. an.* ℥ j. *theriacæ* ℥ j. *croci* ʒ ſ. Of theſe melted and mixed together, make a ſoft Ointment, which ſpread upon a ſcarlet cloth may be applied to the region of the heart. Or, ℞ *Theriacæ opt.* ℥ j. ſ. *ſucci citri, acidi, & limonii, an.* ℥ ſ. *coral. rub. & ſem. roſar. rub. an.* ʒ ß. *camphuræ & croci, an. gr.* iij. let them be all mixed together, and make an Ointment or Liniment.

An Ointment for the reins.

An ointment for the heart.

At the head of the Patient as he lies in his bed, ſhall be ſet an Ewer or Cock with a Baſin under it to receive the Water, which by the dropping may reſemble rain. Let the ſoles of the feet and palms of the hands be gently ſcratched, and the Patient lie far from noiſe, and ſo at length he may fall to ſome reſt.

The noiſe of dropping water draws on ſleep.

CHAP. XXVIII.

Of the Eruptions and Spots, which commonly are called by the name of Purples and Tokens.

THe skin in peſtilent Fevers, is marked and variegated in divers places with ſpots, like unto the bitings of Fleas or Gnats, which are not always ſimple, but many times ariſe in form like unto a grain of Millet. The more ſpots appear, the better it is for the Patient: they are of divers colours, according to the virulency of the malignity, and condition of the matter, as red, yellow, brown, violet or purple, blue and black. And becauſe for the moſt part they are of a purple colour, therefore we call them Purples. Others call them *Lenticulæ*, becauſe they have the colour and form of Lentils. They are alſo called *Papiliones, (i.)* Butterflies; becauſe they do ſuddenly ſeize or fall upon divers regions of the body, like unto winged Butterflies, ſometimes the face, ſometimes the arms and legs, and ſometimes all the whole body; oftentimes they do not onely affect the upper part of the skin, but go deeper into the fleſh, ſpecially when they proceed of matter which is groſs and aduſt. They do ſometimes appear great and broad, affecting the whole arm, leg or face, like unto an *Eryſipelas:* to conclude, they are diverſe, according to the variety of the humour that offends in quantity or quality.

The differences of the ſpots in the Plague.

Their ſeveral names, and reaſons of them.

If they are of a purple or black colour, with often ſwouning, and ſink in ſuddenly without any manifeſt cauſe, they fore-ſhew death.

When ſigns of death.

The cauſe of the breaking out of thoſe Spots, is the working or heat of the blood, by reaſon of the cruelty of the venom received or admitted. They often ariſe at the beginning of a peſtilent Fever: many times before the breaking out of the Sore, or Botch, or Carbuncle, and many times after: but then they ſhew ſo great a corruption of the humours in the body, that neither the ſores nor carbuncles will ſuffice to receive them; and therefore they appear as fore-runners of death. Sometimes they break out alone, without a botch or carbuncle, which if they be red, and have no evil ſymptoms joined with them, they are not wont to prove deadly: they appear for the moſt part on the third or fourth day of the diſeaſe, and ſometimes later, and ſometimes they appear not before the Patient be dead; becauſe the working or heat of the humours being the off-ſpring of putrefaction, is not as yet reſtrained and ceaſed.

Wherefore then principally the putrid heat, which is greateſt a little before the death of the Patient, drives the excremental humours, which are the matter of the ſpots, unto the skin; or elſe becauſe Nature in the laſt conflict hath contended with ſome greater endeavour than before (which

Why they ſometimes appear after the death of the Patient.

is

is common to all things that are ready to die) a little before the inſtant time of death, the Peſtilent humour being preſently driven unto the skin; and Nature thus weakned by theſe extreme conflicts falleth down proſtrate, and is quite overthrown by the remnant of the matter.

CHAP. XXIX.

Of the cure of Eruptions and Spots.

They are to be cured by driving forth.

YOu muſt firſt of all take heed leſt you drive in the humour that is coming outwards with repercuſſives: therefore beware of cold, all purging things, phlebotomy, and drowſie or ſound ſleeping. For all ſuch things do draw the humours inwardly, and work contrary to nature. But it is better to provoke the motion of Nature outwardly, by applying of drawing Medicins outwardly, and miniſtring Medicins to provoke ſweat inwardly; for otherwiſe by repelling and ſtopping the matter of the eruptions, there will be great danger, leſt the heart be oppreſſed with the abundance of the venom flowing back; or elſe by turning into the belly it infers a mortal bloudy flux: which diſcommodities that they may be avoided, I have thought good to ſet down this remedy, whoſe efficacy I have known and proved many times, and on divers perſons, when by reaſon of the weakneſs of the expulſive faculty, and the thickneſs of the skin, the matter of the ſpots cannot break forth, but is conſtrained to lurk under the skin, lifting it up into bunches and knobs.

The indication of curing taken from the like.

I was brought unto the invention of this remedy, by compariſon of the like: For when I underſtood, that the eſſence of the French Pox (and likewiſe of the Peſtilence) conſiſted in a certain hidden virulency and venemous quality, I ſoon deſcended unto that opinion, that even as by the annointing of the body with the unguent compounded of Quick-ſilver, the groſs and clammy humours which are fixed in the bones, and unmovable, are diſſolved, relaxed and drawn from the center into the ſuperficial parts of the body, by ſtrengthening and ſtirring up the expulſive faculty, and evacuated by ſweating and fluxing at the mouth; that ſo it ſhould come to paſs in peſtilent Fevers, that Nature being ſtrengthened with the ſame kind of unction, might unload her ſelf of ſome portion of the venemous and peſtilent humour, by opening the pores and paſſages and letting it break forth into ſpots and puſtles, and into all kind of eruptions. Therefore I have anointed many in whom Nature ſeemed to make paſſage for the venemous matter very ſlowly, firſt looſing their belly with a Clyſter, and then giving them Treacle-water to drink, which might defend the vital faculty of the heart, but yet not diſtend the ſtomach, as though they had the French Pox, and I obtained my expected purpoſe: In ſtead of the Treacle-water you may uſe the decoction of *Guaiacum*, which doth heat, dry, provoke ſweat, and repel putrefaction, adding thereto alſo Vinegar, that by the ſubtilty thereof, it may pierce the better, and withſtand the putrefaction. This is the deſcription of the Unguent.

An ointment to draw them forth when they appear too ſlowly.

Take of Hogs-greaſe one pound, boil it a little with the leaves of Sage, Thyme, Roſemary, of each half an handful, ſtrain it, and in the ſtraining extinguiſh five ounces of Quick-ſilver, which hath been firſt boiled in Vinegar with the fore-mentioned herbs; of *Sal Nitrum* three drams, the Yolks of three Eggs boiled until they be hard, of Treacle and Mithridate, of each half an ounce, of Venice Turpentine, oil of Scorpions and Bays, of each three ounces, incorporate them all together in a mortar, and make thereof an Unguent, wherewith anoint the Patients arm-holes and groins, avoiding the parts that belong to the head, breſt, and back-bone: then let him be laid in his bed, and covered warm, and let him ſweat there for the ſpace of two hours, and then let his body be wiped and cleanſed; and if it may be, let him be laid in another bed, and there let him be refreſhed with the decoction of a Capon, Reer-eggs, and with ſuch like meats of good juice that are eaſie to be concocted and digeſted; let him be anointed the ſecond and third day, unleſs the ſpots appear before.

If the Patient flux at the mouth, it muſt not be ſtopped: when the ſpots and puſtles do all appear, and the Patient hath made an end of ſweating, it ſhall be convenient to uſe Diuretick Medicins, for by theſe the remnant of the matter of the ſpots, which happily could not all breath forth, may eaſily be purged and avoided by urin.

If any Noble or Gentlemen refuſe to be anointed with this unguent, let them be incloſed in the body of a Mule or Horſe that is newly killed, and when that is cold let him be laid in another, until the puſtles and eruptions do break forth, being drawn by that natural heat, For ſo *Matthiolus* writeth, that *Valentinus* the ſone of Pope *Alexander* VI. was delivered from the danger of moſt deadly poiſon which he had drunk. *In Procm. lib. 6. Dioſc.*

CHAP. XXX.

Of a peſtilent Bubo, *or Plague-ſore.*

What a peſtilent *Bubo* is.

A Peſtilent *Bubo* is a tumor at the beginning long and movable, and in the ſtate and full perfection copped, and with a ſharp head, unmovable, and fixed deeply in the glandules or kernels, by which the brain exonerates it ſelf of the venemous and peſtiferous matter into the kernels that are behind the ears, and in the neck: the heart into thoſe that are in the arm-holes, and the liver into thoſe that are in the groin, that is, when all the matter is groſs and clammy, ſo that it cannot be drawn out by ſpots and puſtles breaking out on the skin; and ſo the matter of a Carbuncle is ſharp, and ſo fervent, that it maketh an Eſchar on the place where it is fixed. In the beginning, while the *Bubo* is breeding, it maketh the Patient to feel, as if it were, a cord or rope ſtretched out in the place, or a hardned nerve with pricking pain: and ſhortly after the matter is raiſed up, as it were into a knob, and by little and little it groweth bigger, and is inflamed, theſe accidents before mentioned accompanying it. If the tumor be red, and increaſed by little

and

The ſigns of Buboes ſalutary and deadly.

and little, it is a good and ſalutary ſign: but if it be livid or black, and come very ſlowly unto his juſt bigneſs, it is a deadly ſign. It is alſo a deadly ſign if it increaſe ſuddenly, and come to its juſt bigneſs as it were with a ſwift violence, and as in a moment, have all the ſymptoms in the higheſt exceſs, as pain, ſwelling, and burning. *Buboes* or Sores appear ſometimes of a natural colour, like unto the skin, and in all other things, like unto an œdematous tumor, which notwithſtanding will ſuddenly bring the Patient to deſtruction, like thoſe that are black; wherefore it is not good to truſt too much to thoſe kinds of tumors.

CHAP. XXXI.

Of the Cure of Buboes, *or Plague-ſores.*

The uſe of Cupping-glaſſes in curing of a Bubo.

SO ſoon as the Bubo appears, apply a Cupping-glaſs with a great flame unto it, unleſs it be that kind of Bubo which will ſuddenly have all the accidents of burning and ſwelling in the higheſt nature; but firſt the skin muſt be anointed with the Oil of Lillies, that ſo it being made more looſe, the Cupping-glaſs may draw the ſtronger and more powerfully: it ought to ſtick to the part for the ſpace of a quarter of an hour, and be renewed and applied again every three quarters of an hour: for ſo at length the venom ſhould be the better drawn forth from any noble part that is weak, and the work of ſuppuration or reſolution, which ſoever Nature hath aſſailed will the better and ſooner be abſolved and perfected: which may be alſo done by the application of the following Ointment.

Take of *Unguentum Dialthæa* one ounce and a half, Oil of Scorpions half an ounce, of Mithridate diſſolved in *Aqua Vitæ*, half a dram; this liniment will very well relax and looſen the skin, open the pores thereof, and ſpend forth portion of the matter which the Cupping-glaſs hath drawn thither: inſtead thereof mollifying fomentations may be made, and other drawing and ſuppurating Medicins, which ſhall be deſcribed hereafter.

A Liniment.

A Veſicatory applied in a meet place below the Bubo profits them very much, but not above; as for example: If the Bubo be in the throat, the Veſicatory muſt be applied unto the ſhoulder-blade on the ſame ſide; if it be in the arm-holes, it muſt be applied in the midſt of the arm, or of the ſhoulder-bone on the inner ſide: if in the groin, in the midſt of the thigh on the inner ſide, that by the double paſſage that is open for to draw out the matter, the part wherein the venom is gathered together, may be the better exonerated.

Spurge, Crow-foot, Arſmart, Bear-foot, Briony, the middle bark of Travellers joy, the rinds of Mullet, *Flammula*, or upright Virgins power, are fit for raiſing bliſters. If you cannot come by thoſe ſimple Medicins, you may apply this which followeth, which may be prepared at all times.

A compound Veſicatory.

Take *Cantharides*, Pepper, *Euphorbium*, Pellitory of *Spain*, of each half a dram; of ſower leaven two drams, of Muſtard one dram, and a little Vinegar; the Vinegar is added thereto, to with-hold or reſtrain the vehemency of the *Cantharides*: but in want of this Medicin it ſhall ſuffice to drop ſcalding Oil or Water, or a burning Candle, or to lay a burning Coal on the place: for ſo you may raiſe bliſters, which muſt preſently be cut away, and you muſt ſee that you keep the ulcers open and flowing as long as you can, by applying the leaves of red Colworts, Beets, or Ivy dipped in warm Water, and anointed with oil or freſh butter. Some apply Cauteries, but Veſicatories work with more ſpeed; for before the Eſchar of the Cauteries will fall away, the Patient may die, therefore the Ulcers that are made with Veſicatories will ſuffice to evacuate the peſtilent venom, becauſe that doth work rather by its quality than by its quantity. Let the abſceſs be fomented as is ſhewed before, and then let the Medicin following, which hath virtue to draw, be applied.

Why Veſicatories are better than Cauteries in a peſtilent Bubo.

Strong drawing Cataplaſms

Fill a great Onion being hollowed, with Treacle and the leaves of Rue, then roaſt it under the hot embers, beat it with a little Leaven, and a little Swines greaſe, and ſo apply it warm unto the abſceſs or ſore; let it be changed every ſix hours. Or take the roots of Marſh-mallows and Lillies of each half a pound; of Line, Fenugreek, and Muſtard ſeeds, of each half an ounce; of Treacle one dram, ten Figs, and as much Hogs-greaſe as ſhall ſuffice: make thereof a Cataplaſm according to Art. Or, Take of Onions and Garlick roaſted in the embers, of each three ounces: bruiſe them with one ounce of ſowre leaven: adding thereto *Unguentum Baſilicon* one ounce, Treacle one dram, Mithridate half a dram, of old Hogs-greaſe one ounce, of *Cantharides* in powder one ſcruple, of Pigeons dung two drams: beat them and mix them together into the form of a Cataplaſm. Hereunto old Rennet is very profitable; for it is hot, and therefore attractive, being mixed with old Leaven and *Baſilicon*: you ought to uſe this until the abſceſs be grown unto its full ripeneſs and bigneſs; but if preſently after the beginning there be great inflammation, with ſharp pain, as it often happeneth, eſpecially when the abſceſſes be of the kind of Carbuncles; we muſt abſtain from thoſe remedies that are hot and attractive, and alſo from thoſe that are very emplaſtick and clammy, becauſe they do altogether cloſe the pores of the skin; or becauſe they reſolve the thinner part of the collected matter, which if it might remain, would bring the other ſooner to ſuppuration: or elſe becauſe they may perchance draw more quantity of the hot matter than the part can bear, whereof cometh rather corruption than maturation: and laſt of all, becauſe they increaſe the Fever and Pain, which infer the danger of a Convulſion or mortal Gangrene. Therefore in ſuch a caſe it is beſt to uſe cold and temperate local Medicins, as the leaves of Henbane and Sorrel roaſted under the coals, *Galens* Pultiſe, and ſuch like.

Againſt ſuch as cut away Plague-ſores.

There are many that for fear of death, have with their own hands pulled away the Bubo with a pair of Smiths Pincers: others have digged the fleſh round about it, and ſo gotten it wholly out. And to conclude, others have become ſo mad, that they have thruſt an hot iron into it with their own hand, that the venom might have a paſſage forth: of all which I do not allow one; for ſuch abſceſſes do not come from without, as the bitings of virulent Beaſts, but from within, and more-

over

over becauſe pain is by theſe means increaſed, and the humour is made more malign and fierce. Therefore I think it ſufficient to uſe Medicins that relax, open the pores of the skin, and digeſt portion of the venom by tranſpiration, as are theſe that follow. Take the roots of Marſh-mallows and Lillies of each ſix ounces, of Camomil and Melilot-flowers of each half a handful, of Line-ſeeds half an ounce, of the leaves of Rue half an handful: boil them and ſtrain them, dip ſponges in the ſtraining, and therewith let the tumour be fomented a long time. Or take the crum of hot bread and ſprinkle it with Treacle-water, or with *Aqua Vitæ*, and Cows-milk or Goats-milk, and the yolks of three Eggs; put them all on ſtupes or flax, and apply them warm unto the place. Or, Take of ſowre Rie-leaven four ounces, of Baſilicon two ounces, three yolks of Eggs, Oil of Lillies two ounces, Treacle one dram: let it be received on ſtupes, and applied in like manner. Or, Take of *Diachylon* and *Baſilicon* of each two ounces, Oil of Lillies one ounce and a half: let them be melted and mixed together, and let it be applied as is above ſaid. When you ſee, feel and know, according to reaſon, that the Bubo is come to perfect ſuppuration, it muſt be opened with an inciſion-knife, or an actual or potential Cautery, but it is beſt to be done with a potential Cautery, unleſs that happily there be great inflammation, becauſe it doth draw the venom from beneath unto the ſuperficial parts, and maketh a larger orifice for the matter that is contained therein: neither muſt it be looked for, that Nature ſhould open it of her ſelf; for then there were danger that leſt while Nature doth work ſlowly, a venemous vapour ſhould be ſtirred up, with ſtriking the heart by the arteries, the brain by the nerves, and the liver by the veins, ſhould cauſe a new increaſe of the venemous infection. For fear whereof there be ſome that will not expect the perfect maturation and ſuppuration, but as it were in the midſt of the crudity and maturity, will make an orifice for it to paſs forth at: yet if it be done before the tumor be at his perfect maturity, Pain, a Fever, and all accidents are ſtirred up, and enraged, whereof cometh a malign ulcer that often degenerates into a Gangrene. For the moſt part about the tenth or eleventh day the work of ſuppuration ſeemeth perfected and finiſhed; but it may be ſooner or later, by reaſon of the application of Medicins, the condition of the matter, and ſtate of the part: when the matter cometh forth, you muſt yet uſe ſuppurative and mollifying Medicins, to maturate the remains thereof; in the mean while cleanſing the ulcer by putting mundificatives into it, as we ſhall declare in the cure of Carbuncles. But if the tumor ſeem to ſink in, or hide it ſelf again, it muſt be revoked and procured to come forth again, by applying of Cupping-glaſſes with ſcarification, and with ſharp Medicins, yea, and with Cauteries both actual and potential.

A digeſtive fomentation.

An anodyne Cataplaſm.

Why it is beſt to open a Plague-ſore with a potential Cautery.

How to draw forth a ſore that ſeems to go in again.

When the Cauteries are applied it ſhall be very good to apply a Veſicatory a little below it, that there might be ſome paſſage open for the venom while the Eſchar is in falling away. For ſo they that are troubled with the French Pox, ſo long as they have open and flowing ulcers, ſo long are they void of any pain that is worth the ſpeaking of; which ulcers being cloſed and cicatrized, they do preſently complain of great pain. If you ſuſpect that the *Bubo* is more malign by reaſon that it is of a green or black and inflamed colour, as are thoſe that come of a melancholick humour by aduſtion, turned into a groſs and rebellious melancholick humour, ſo that by the more copious influx thereof into the part, there is a danger of a gangrene and mortification; then the places about the abſceſs muſt be armed with repercuſſives, but not the abſceſs it ſelf: and this may be the form of the repercuſſives: Take of the juice of Houſleek, Purſlain, Sorrel, Night-ſhade, of each two ounces; of Vinegar one ounce, the Whites of three Eggs, of Oil of Roſes and Water-lillies of each two ounces and an half, ſtir them together, and apply it about the Bubo, and renew it often: or boil a Pomgranate in Vinegar, beat it with *Unguentum Roſatum*, or *Populeon* newly made, and apply it as is aforeſaid. If theſe things do not ſtop the influx of other humours, the abſceſs it ſelf and the places about it muſt be ſcarified round about, if the part will permit it; that the part exonerated of portion of the venom may not ſtand in danger of the extinction of the proper and natural heat, by the greater quantity and malignity of the humours that flow unto it. In ſcarifying you muſt have care of great veſſels, for fear of an irrepugnable flux of bloud, which in this caſe is very hard to be ſtaid or reſiſted, both becauſe the part it ſelf is greatly inflamed, and the humour very fierce; for the expulſion whereof, Nature careful for the preſervation of the part and all the body beſides, ſeemeth to labour and work. But yet you muſt ſuffer ſo much of the bloud and humour to flow out as the Patient is able to abide without the loſs of his ſtrength. Moreover, you may ſpend forth the ſuperfluous portion of the malignity, with relaxing, mollifying, and reſolving fomentations: as, Take the roots of Marſh-mallows, Lillies and Elecampane, of each one pound; of Line-ſeeds and Fenugreek, of each one ounce, of Fennel-ſeeds, and Anniſe-ſeeds, of each half an ounce, of the leaves of Rue, Sage, Roſemary, of each one handful, of Camomil and Melilot flowers, of each three handfuls; boil them all together and make thereof a decoction for a fomentation; uſe it with a Sponge according to Art. Alſo after the aforeſaid ſcarification, we may put Hens, or Turkies that lay Eggs (which therefore have their fundaments more wide and open, and for the ſame purpoſe put a little ſalt into their fundaments) upon the ſharp top of the Bubo, that by ſhutting their Bills at ſeveral times they may draw and ſuck the venom into their bodies, far more ſtrongly and better than Cupping-glaſſes, becauſe they are endued with a natural property againſt poiſon, for they eat and concoct Toads, Efts, and ſuch like virulent Beaſts: when one Hen is killed with the poiſon that ſhe hath drawn into her body, you muſt apply another, and then the third, fourth, fifth, and ſixth, within the ſpace of half an hour. There be ſome that will rather cut them, or elſe uſe whelps cut aſunder in the midſt, and applied warm to the place; that by the heat of the Creature that is yet ſcarce dead, portion of the venom may be diſſipated and exhaled. But if nevertheleſs there be any fear of a Gangrene at hand, you muſt cut the fleſh with a deeper ſcarification, not onely avoiding the great veſſels, but alſo the nerves, for fear of convulſion; and after the ſcarification and a ſufficient flux of bloud, you muſt waſh it with Ægyptiacum, Treacle and Mithridate diſſolved in Sea water, *Aqua Vitæ* and Vinegar. For ſuch a lotion hath virtue to ſtay putrefaction, repel the venom,

When repercuſſives may be applied.

Why too much bleeding is to be feared.

nom, and prohibit the bloud from concretion: but if the Gangrene cannot be avoided ſo, Cauteries may be applied to the part: eſpecially actual, becauſe they do more effectually repel the force of the poiſon, and ſtrengthen the part. Preſently after the impreſſion of the hot Iron, the Eſchar muſt be cut away even unto the quick fleſh, that the venomous vapours and the humours may have a free paſſage forth; for it is not to be looked for, that they will come forth of themſelves. With theſe inunctions they are wont to haſten the falling away of the Eſchar. Take of the mucilage of Marſh-mallows and Line-ſeeds, of each two ounces, freſh Butter or Hogs-greaſe one ounce, the yolks of three Eggs; incorporate them together, and make thereof an Ointment: Butter, Swines-greaſe, Oil of Roſes with the yolks of Eggs, perform the ſelf ſame thing. When the Eſchar is fallen away, we muſt uſe digeſtives. As, Take of the juice of Plantain, Water-Betony, and Smallage, of each three ounces, honey of Roſes four ounces, Venice Turpentine five ounces, Barly flower three drams, Aloes two drams, Oil of Roſes four ounces, Treacle half a dram: make a mundificative according to Art. Or, Take of Venice Turpentine four ounces, Syrup of dried Roſes and Wormwood, of each an ounce, of the powder of Aloes, Maſtich, Myrrh, Barly-flower, of each one dram, of Manna date half an ounce; incorporate them together. The unguent that followeth is very meet for putrified and corroding ulcers: Take red Orpiment one ounce, of unquenched Lime, burnt Alum, Pomgranat Pills, of each ſix drams, of *Olibanum*, Galls, of each two drams, of Wax and Oil as much as ſhall ſuffice: make thereof an unguent. This doth mundifie ſtrongly, conſume putrified fleſh, and dry up virulent humidities that engender Gangrenes. But there is not a more excellent unguent than *Ægyptiacum* increaſed in ſtrength, for beſides many other virtues that it hath, it doth conſume and waſte the proud fleſh; for there is neither Oil nor Wax that goeth into the compoſition thereof, with which things the virtue of ſharp Medicins convenient for ſuch Ulcers, is delaid, and as it were dulled and hindered from their perfect operation, ſo long as the ulcer is kept open. There have been many that being diſeaſed with this diſeaſe, have had much matter and venomous filth come out at their abſceſs; ſo that it ſeemed ſufficient, and they have been thought well recovered, yet have they died ſuddenly. In the mean while when theſe things are in doing, cordial Medicins are not to be omitted to ſtrengthen the heart: And Purgations muſt be renewed at certain ſeaſons, that Nature may be every way unloaded of the burthen of the venenate humours.

Liniments haſten the falling away of the Eſchar.

Againſt eating Ulcers.

The praiſe of *Ægyptiacum*.

CHAP. XXXII.

Of the Nature, Cauſes, and Signs of a Peſtilent Carbuncle.

A Peſtilent Carbuncle is a ſmall tumor, or rather a malign puſtle, hot, and raging, conſiſting of bloud vitiated by the corruption of the proper ſubſtance. It often cometh to paſs through the occaſion of this untamable malignity, that the Carbuncle cannot be governed or contained within the dominion of Nature. In the beginning it is ſcarce ſo big as a ſeed or grain of Millet or Peaſe, ſticking firmly unto the part and immovable, ſo that the skin cannot be pulled from the fleſh; but ſhortly after it increaſeth like to a Bubo, unto a round and ſharp head, with great pricking pain, as if it were with needles, burning and intolerable, eſpecially a little before night, and while the meat is in concocting, more than when it is perfectly concocted. In the midſt thereof appeareth a bladder puffed up and filled with ſanious matter. If you cut this bladder, you ſhall find the fleſh under it parched, burned and black, as if there had been a burning coal laid there, whereby it ſeemeth that it took the name of Carbuncle; but the fleſh that is about the place is like a Rainbow, of divers colours, as red, dark green, purple, livid and black; but yet always with a ſhining blackneſs, like unto Stone-Pitch, or like unto the true precious ſtone which they call a Carbuncle, whence ſome alſo ſay it took the name. Some call it a Nail, becauſe it inferreth like pain as a Nail driven into the fleſh. There are many Carbuncles which take their beginning with a crufty ulcer without a puſtle, like to the burning of an hot Iron: and theſe are of a black colour, they increaſe quickly, according to the condition of the matter whereof they are made. All peſtilent Carbuncles have a Fever joined with them, and the grieved part ſeemeth to be ſo heavy, as if it were covered or preſſed with lead tied hard with a ligature: There cometh mortal ſwounings, faintings, toſſing, turning, idle talking, raging, gangrenes and mortifications; not onely to the part, but alſo to the whole body; by reaſon (as I think) of the oppreſſion of the ſpirits of the part, and the ſuffocation of the natural heat, as we ſee alſo in many that have a peſtilent Bubo: for a Bubo and Carbuncle are tumors of a near affinity, ſo that the one doth ſcarce come without the other, conſiſting of one kind of matter, unleſs that which maketh the Bubo is more groſs and clammy, and that which cauſeth the Carbuncle more ſharp, burning and raging, by reaſon of its greater ſubtilty, ſo that it maketh an Eſchar on the place where it is, as we noted before.

What a Carbuncle is.

The ſigns of a Carbuncle.

When ſo called.

Symptoms of Carbuncles.

How the Matter of a Bubo and Carbuncle differ.

CHAP. XXXIII.

What Prognoſticks may be made in Peſtilent Buboes and Carbuncles.

SOme having the Peſtilence have but one Carbuncle, and ſome more, in divers parts of their body, and in many it happeneth that they have the Bubo and Carbuncle before they have any Fever; which giveth better hope of health, if there be no other malign accident therewith: for it is a ſign that Nature is the Victor, and hath gotten the upper-hand, which excluded the peſtilent venom before it could come to aſſault the heart. But if a Carbuncle and Bubo come after the Fever, it is mortal; for it is a token that the heart is affected, moved and incenſed with the furious rage of the venom, whereof preſently cometh a feverilh heat or burning; and corruption of the humours, ſent as it were from the center unto the ſuperficies of the body. It is a good ſign, when the

Why it is deadly to have a ſore come after the Fever.

the Patients mind is not troubled, from the beginning until the ſeventh day; but when the Bubo or Carbuncle ſinketh down again ſhortly after that it is riſen, it is a mortal ſign, eſpecially if ill accidents follow it. If after they are brought to ſuppuration they preſently wax dry without any reaſon thereof, it is an ill ſign: Thoſe Carbuncles that are generated of bloud have a greater Eſchar than thoſe that are made of choler, becauſe that bloud is of a groſs conſiſtence, and therefore occupieth a greater room in the fleſh: contrariwiſe, a cholerick humour is more ſmall in quantity and thin, and it taketh little room in the upper part of the fleſh onely, as you may ſee in an *Eryſipelas*. And I have ſeen Carbuncles whoſe Eſchars were as broad and as large as half the back: alſo I have ſeen others, which going up by the ſhoulders to the throat, did ſo eat away the fleſh that was under them, that the rough artery or wind-pipe might be ſeen bare, when the Eſchar was fallen away. I had once a Carbuncle which was in the midſt of my belly, ſo that when the Eſchar was fallen away, I might very plainly ſee the *Peritoneum* or Rim; and the cicatrice that remaineth is as broad as my hand; but they do not ſpread themſelves ſo far, without the great danger or death of the Patient. There alſo ſome Carbuncles which beginning at the parts under the chin, diſperſe themſelves by little and little unto the battle-bones, and ſo ſtrangle the Patient. So in many the Buboes in the Groin ariſe above a great part of the muſcles of the *Epigaſtrium*. Truly of thoſe abſceſſes that are ſo large and great in quantity, and ſo terrible to be ſeen, there is great danger of death to the Patient, or at leaſt to the grieved part; for after the conſolidation the part remaineth as if it were leprous, which aboliſheth the action of the part, as I have ſeen in many. Often-times alſo the corruption of the matter is ſo great, that the fleſh leaveth the bones bare: but Carbuncles often leave the joints and ligaments quite reſolved, through the occaſion of the moiſture that is ſoaked and ſunk into them; for they often caſt out putrefied and virulent ſanious matter, whereby eating and creeping ulcers are bred, many bliſters and puſtles ariſing up in the parts round about it; which ſhortly breaking into one, make a great ulcer. Theſe come very ſeldom and ſlowly unto ſuppuration, or at leaſt to caſt out laudable matter, eſpecially if they have their original of choler; becauſe the matter is ſooner burned with heat than ſuppurated. Therefore then, if they can be brought to ſuppuration by no Medicins, if the tumor ſtill remain black, if when they are opened, nothing at all, or elſe a very little ſharp moiſture doth come forth, they are altogether mortal, and there is ſcarce one of a thouſand who hath theſe accidents that recovereth health. Diſperſed ſmall bliſters, coming of vapours ſtirred up by the matter that is under the skin, and are there ſtaid and kept from paſſage forth, do not neceſſarily fore-ſhew death in Carbuncles. But if the part be ſwollen or puffed up, if it be of a green or black colour, and if it feel neither pricking nor burning, it is a ſign of a mortal gangrene. Buboes or Carbuncles ſeldom or never come without a Fever: but the Fever is more vehement when they are in the emunctories or nervous parts, than when they are in the fleſhy parts; yet it is leſs, and all ſymptoms are leſs and more tolerable in a man that is ſtrong and of a good temperature: Carbuncles not onely affect the outward, but alſo the inward parts, and oftentimes both together. If the heart be vexed in ſuch ſort with a Carbuncle that nothing thereof appeareth forth on the ſuperficial parts, all hope of life is paſt, and thoſe ſuddenly die, eating, drinking, or walking, and not thinking any thing of death. If the Carbuncle be in the Midriff or Lungs, they are ſoon ſuffocated: if it be in the Brain, the Patient becometh frantick, and ſo dieth: if it be in the parts appointed for the paſſage of the urine, they die of the ſuppreſſion of their water, as it happened in the Queen-mothers waiting maid, at the Caſtle of *Roſſilion*, of whom I ſpake before: if it be in the Stomach, it inferreth the accidents that are ſhewed in this Hiſtory following.

Huge peſtilent abſceſſes commonly deadly.

Deadly Carbuncles.

While I was a Surgeon in the Hoſpital of *Paris*, a young and ſtrong Monk of the order of S. *Victor*, being overſeer of the Woman that kept the ſick people of that place, fell into a continual Fever very ſuddenly, with his Tongue black, dry, rough, (by reaſon of the putrefied and corrupted humours, and the vapours riſing from the whole body to that place) and hanging out like unto a Hounds, with unquenchable thirſt, often ſwouning and deſire to vomit: he had convulſions over all his body, through the vehemency and malignity of the diſeaſe, and ſo he died the third day. Wherefore thoſe that kept the ſick people in the Hoſpital, thought that he had been poiſoned, for the certain knowledge whereof the Governours of the Hoſpital commanded his body to be opened. I therefore calling to me a Phyſician and Surgeon, we found in the bottom of his ſtomach, a print or impreſſion, as if it had been with an hot iron or potential Cautery, with an Eſchar or cruſt as broad as ones nail, all the reſt of his ſtomach was greatly contracted and ſhrunk up together, and as it were horny; which we conſidering, and eſpecially the Eſchar which was deep in the ſubſtance of the ſtomach, we all ſaid with one voice, that he was poiſoned with Sublimate or Arſenick. But behold, while I was ſewing up his belly, I perceived many black ſpots diſperſed diverſly throughout the skin: then I asked my company what they thought of thoſe ſpots? truly (ſaid I) it ſeemeth unto me that they are like unto the Purple ſpots or marks that are in the Peſtilence. The Phyſician and the Surgeon denied it, and ſaid that they were the bitings of Fleas. But I perſwaded them to conſider the number of them over all the whole body, and alſo of their great depth and depreſſion into the fleſh; for when we had thruſt Needles deep into the fleſh in the midſt of them, and ſo cut away the fleſh about the needle, we found the fleſh about the needle to be black: moreover his noſtrils, nails, and ears, were livid, and all the conſtitution of his body was contrary, and far unlike to the bodies of thoſe that died of other ſickneſſes or diſeaſes. Alſo it was credibly reported unto us by thoſe that kept him, that his Face was ſo altered a little before he died, that his familiar friends could hardly know him. We perſuaded by theſe proofs, revoked our former opinion and ſentence, and made a Certificate to be ſent unto the Governours and Maſters of the Hoſpital, ſetting our hands and ſeals unto it, to certifie them that he died of a peſtilent Carbuncle.

An Hiſtory.

How to diſtinguiſh Purple ſpots from Flea-bitings.

CHAP. XXXIV.

Of the Cure of a Peſtilent Carbuncle.

Why emplaſtick, very hot, and great drawers are not good for a Carbuncle.

BY the fore-named ſigns of a peſtilent Carbuncle, and eſpecially by the bitterneſs of the pain, malignity of the venomous matter, and by the burning Fever that is therewithall annexed, I think it manifeſt, that very hot, emplaſtick, and drawing Medicins ſhould not be applied to this kind of tumor, becauſe they prohibit or hinder the exhalation, or waſting forth of the venenate malignity, becauſe that by ſtopping the pores of the skin, they increaſe and cauſe a greater heat in the part than there was before. Therefore it is better to uſe reſolving Medicins which may aſſwage heat, and reſolve the pores of the skin. Therefore firſt the place muſt be fomented with Water and Oil mixed together, wherein a little Treacle hath been diſſolved, leaving thereon *ſtupes* wet therein: you may alſo uſe the decoction of Mallows, the Roots of Lillies, Line-ſeeds, Figs, with Oil of *Hypericon*, to make the skin thin, and to draw forth the matter; and the day following you muſt apply the Cataplaſm following.

A Cataplaſm for a peſtilent Carbuncle.

Take the leaves of Sorrel and Henbane, roaſt them under the hot aſhes, afterwards beat them with four yolks of Eggs, two drams of Treacle, Oil of Lillies, three ounces, Barly-meal as much as ſhall ſuffice: make thereof a Cataplaſm in the form of a liquid Pultiſe: this aſſwageth heat and furthereth ſuppuration.

Another.

Or, Take the roots of Marſh-mallows and Lillies, of each four ounces, Line-ſeeds half an ounce, boil them, beat them, and then ſtrain them through a Serſe, adding thereto of freſh Butter one ounce and half, Mithridate one dram, of Barly-meal as much as ſhall ſuffice: make thereof a Cataplaſm according to Art. Thoſe Cataplaſms that follow, are moſt effectual to draw the venomous matter forth, and to make a perfect ſuppuration, eſpecially when the flux of the matter is not ſo great, but that the part may bear it. Take the Roots of white Lillies, Onions, Leaven, of each half an ounce; Muſtard-ſeeds, Pigeons dung, Sope, of each one dram; ſix Snails in their ſhells, of fine Sugar, Treacle and Mithridate, of each half a dram; beat them altogether and incorporate them with the yolks of Eggs: make thereof a Cataplaſm, and apply it warm.

Other Cataplaſms.

Or, Take the yolks of ſix Eggs, of Salt powdered one ounce, of Oil of Lillies and Treacle, of each half a dram; Barly-meal as much as will ſuffice: make thereof a Cataplaſm. Take of ordinary Diachylon four ounces, of *Unguentum Baſilicon* two ounces Oil of Violets half an ounce: make thereof a Medicin. Many ancient Profeſſors greatly commend Scabious ground, or brayed between two ſtones, and mixed with old Hogs-greaſe, the yolks of Eggs, and a little Salt, for it will cauſe ſuppuration in Carbuncles, alſo an Egg mixed with Barly-meal, and Oil of Violets doth mitigate pain, and ſuppurate.

The effect of Scabious againſt a peſtilent Carbuncle.

A Raddiſh root draws out the venom powerfully.

A Raddiſh-root cut in ſlices, and ſo the ſlices laid one after one unto a carbuncle or peſtilent tumor, doth mightily draw out the poiſon. The juice of Colts-foot doth extinguiſh the heat of Carbuncles: the Herb called Devils-bit being bruiſed, worketh the like effect. I have often uſed the Medicin following to the heat of Carbuncles with very good ſucceſs; it doth alſo aſſwage pain and cauſe ſuppuration. Take of the Soot ſcraped from a Chimney four ounces, of common Salt two ounces, beat them into ſmall Powder, adding thereto the yolks of two Eggs, and ſtir them well together, until it come to have the conſiſtence of a Pultiſe, and let it be applied warm unto the Carbuncle.

The top of a Carbuncle, when, why, and with what to be burned.

In the beginning the point or head of the Carbuncle muſt be burned, if it be black, by dropping thereinto ſcalding hot Oil, or *Aqua fortis*; for by ſuch a burning the venom is ſuffocated, as touched by lightning, and the pain is much leſſened, as I have proved oftentimes: neither is it to be feared leſt that this burning ſhould be too painful, for it toucheth nothing but the point of the Carbuncle, which by reaſon of the Eſchar that is there, is void of ſenſe. After this burning, you muſt go forward with the former deſcribed Medicins, until the Eſchar ſeemeth to ſeparate it ſelf from the fleſh round about it, which is a token of the Patients recovery, for it ſignifieth that Nature is ſtrong and able to reſiſt the poiſon.

The falling of the Eſchar promiſeth health.

After the fall of the Eſchar, you muſt uſe gentle mundificatives, as thoſe which we have preſcribed in a Peſtilent Bubo; not omitting ſometimes the uſe of ſuppurative and mollifying Medicins: that while the groſs matter is cleanſed, that which is as yet crude may be brought to ſuppuration: for then the indication is two-fold, the one to ſuppurate that which remains as yet crude and raw in the part, and the other to cleanſe that which remains concocted and perfectly digeſted in the ulcer.

A twofold indication.

CHAP. XXXV.

Of the itching and inflammation happening in Peſtilent Ulcers, and how to cicatrize them.

Why the adjacent parts are troubled with itching.

THe parts adjoining to a peſtilent Ulcer, oft-times are ſuperficiarily excoriated by reaſon of ulcerous puſtles, which here and there, with burning and great itching prick and vellicate the part. The cauſe may happen either externally or internally; internally, by a thin and biting *ſanies*, which ſweating from the Ulcer, moiſtens the neighbouring parts. But externally by the conſtipation of the pores of the skin, induced by the continual application of Medicins.

A fomentation for this itch.

To remedy this the place muſt be fomented with diſcuſſing and relaxing things, as *Aqua fortis*, which the Goldſmiths have uſed for ſeparating of Metals, Alum-water, the water of Lime, Brine, and the like.

Why theſe Ulcers are hard to be cicatrized.

But Ulcers left by Carbuncles and peſtilent Buboes, are difficultly cicatrized, by reaſon of the corroding *ſanies* proceeding from the cholerick or phlegmatick and ſalt bloud, which being in fault by the corruption of the whole ſubſtance, cauſeth the abſceſs: beſides, ſuch Ulcers are commonly round, and therefore hard to be cicatrized, for that the Quitture hath no free paſſage forth; ſo the *ſanies*, of its own nature acrid and corroding, doth by delay acquire greater acrimony and nitroſity; ſo by its burning touch diſſolving the adjacent fleſh, it hinders the conjunction

and

and unition of the lips of the ulcer: but in the interim, the lips of the ulcer become callous, which unleſs they be helped by cutting, or eating Medicins, the ulcer cannot be healed; for that by their denſity they hinder the ſweating out of a ſufficient quantity of the dewy glew, to heal up the ulcer. Now the ulcer being plained and brought equal to the other fleſh, we muſt uſe Epuloticks; that is, ſuch things as have a faculty to cicatrize Ulcers by condenſing and hardning the ſurface of the fleſh: Of theſe there are two kinds; for ſome without much biting bind and dry, ſuch are Pomgranat-pills, Oak-bark, Tutia, Litharge, burnt Bones, Scales of Braſs, Galls, Cypreſs-nuts, Minium, Antimony, Bole-Armenick, the burnt and waſhed ſhells of Oyſters, Lime nine times waſhed, and many Metalline things. Others are next to theſe, by which proud fleſh is conſumed; but ſuch muſt be ſparingly uſed: Of this kind is waſhed Vitriol, burnt Alum, which excelleth other Epuloticks, by reaſon of the excellent drying and aſtringent faculty conſolidating the fleſh, which by being moiſtned by an excrementitious humour, grows lank. For that the ſcar which is made, is commonly unſightly in this kind of Ulcers, as red, livid, black, ſwollen, rough, by reaſon of the great aduſtion imprinted in the part, as by a burning coal: therefore I have thought good here to ſet down ſome means, by which this deformity may be corrected or amended. If the ſcar be too big, or high, it ſhall be plained by making convenient ligation and ſtraight binding to the part a Plate of Lead rubbed over with Quick-ſilver; but you may whiten it by anointing it with Lime nine times waſhed, (that ſo it may be more gentle, and loſe the acrimony) and incorporated with Oil of Roſes. Some take two pound of Tartar or Argal, burn it, and then powder it; put it in a cloth, and ſo let it hang in a moiſt Vault or Cellar, and ſet a Veſſel under it to receive the dropping of Liquor, which is good to be rubbed for a good ſpace upon the ſcar. The ſame faculty is thought to be in that moiſture of eggs, which ſweats through the ſhell, whileſt they are roaſted at the coals; as alſo *unguentum citrinum* and *Emplaſt. de cerußa* newly made. The three following compoſitions are much approved. ℞ *Axungiæ ſuillæ nonies lotæ in aceto acerrimo* ℥ iv. *cinab. ſucci citri, & alum. uſti, an.* ℥ ß. *ſulphur. vivi ignem haud experti,* ℥ ij. *camph.* ℈ ij. *fiat pulvis*; then let them all be incorporated together, and make an Oinment: it attenuates the skin, and cleanſeth ſpots. ℞ *Olei hyoſc. olei ſemin. cucurb. an.* ℥ j. *olei tartar.* ℥ ß. *ceræ alb.* ℥ iij. *liquefiant ſimul lento igne; deinde adde ſpermat. ceti* ℥ vj. *removeantur prædicta ab igne donec infrigid. poſtea adde troch. alb. Rhaſis pul.* ℥ iij. *camph.* ℥ j. *tandem cum mali citri ſucco omnia diligent. commiſce, fiat linimentum.* Or elſe, ℞ *Rad. ſerpent.* ℥ j. *bulliat in aquæ com.* ℔ j. *ad dimid. deinde adde ſulph. vivi ignem non experti, & alum. crudi, pulveriſ. an.* ℥ j. . *colent. prædict. & addatur caph.* ℥ j. *ſucci hyoſcyami* ℥ j. ß. Let this Medicin be kept in a lead or glaſs Veſſel; and when you would uſe it, dip linnen cloths therein, and lay them to the part. You may alſo uſe theſe Medicins againſt the redneſs of the Face; and you may fetch them off in the morning by waſhing the Face with warm Water and Bran.

Two ſorts of Epuloticks.

Remedies againſt the deformity of ſcars.

Oinments to attenuate and take away ſcars.

CHAP. XXXVI.

Of ſundry kinds of Evacuations, and firſt of Sweating and Vomiting.

THe peſtilent malignity is not onely evacuated and ſent forth by the eruption of puſtles and ſpots, but alſo by Sweat, Vomit, Bleeding at Noſe, at the *Hæmorrhoids*, by the Courſes, a Flux of the Belly, and other ways; ſo that Nature by every kind of excretion may be freed from the deadly poiſon, eſpecially that which is not as yet arrived at the heart. But chief regard muſt be had to the inclination of Nature, and we muſt attend what way it chiefly aims at, and what kind of excretion it affects. Yet ſuch evacuations are not always critical, but uſually ſymptomatical; for that oft-times Nature is ſo irritated by the untamable malignity of the matter, that it can no way digeſt it, but is forced by any means to ſend it away crude as it is. Wherefore if Nature may ſeem by the moiſtneſs of the skin, the ſuppreſſion of Urin, and other ſigns to affect a *criſis* and excretion by Sweat, you then ſhall procure it by the formerly mentioned means. It is delivered by the Ancients, that all Sweats in acute diſeaſes are ſalutary, which happen upon a critical day, which are univerſal and hot, and ſignified before the critical day. But in this rapid and deadly diſeaſe of the Plage, we muſt not expect a *Criſis*, but as ſoon as we can, and by what means we may, to free Nature from ſo dire and potent an Enemy.

Why the peſtilent malignity is not carried away by one way, but by many. We muſt have chief regard to the motion of Nature. Signs of future Sweat.

A *Criſis* muſt not be expected in the Plague.

But oft-times the tough and groſs excrementitious humours may be purged by Vomit, which could not be evacuated by ſtrong Purges. Therefore alſo by this manner of excretion may we hope for the excluſion of the peſtilent venom, if there be nothing which may hinder; and Nature by frequent nauſeouſneſs may ſeem to affect this way: the endeavour thereof ſhall be helped by giving ſome half a pint of warm Water to be drunk with four ounces of common Oil, an ounce of Vinegar, and a little juice of Raddiſh: after the taking of the potion, it is fit to thruſt into the throat a Gooſe-quill dipped in the ſame Oil, or elſe a branch of Roſemary: or elſe by thruſting in the fingers, ſo to procure vomit; alſo a portion of eight ounces of the mucilaginous water of the decoction of Line-ſeeds will procure Vomit. Or elſe, ℞ *Rad. raph. in taleol. ſect. vel ſem. ejus, & ſem. atriplicis, an.* ℥ iij. *bulliant in aquæ com. quod ſufficit pro doſi. in colatura diſſolve oxym. & ſyr. acet. an.* ℥ ß. *exhibeatur potio larga & tepida.* Or elſe, ℞ *Oxym. Gal.* ℥ vj. *ol. com.* ℥ ij. *paretur potio tepid.* But Nature muſt not be forced, unleſs of its own accord it undertake this motion, for forced and violent vomiting, diſtends the nervous fibres of the ventricle, dejects the ſtrength, breaks the veſſels of the lungs, whence proceeds a deadly ſpitting of bloud. Wherefore if the ſtomach ſhall trouble it ſelf with a vain and hurtful deſire to vomit, it ſhall rather be ſtrengthened with bags of Roſes, Wormwood, and Sanders, uſing inwardly the juice of Quinces and Berberries, and Broths made for the ſame purpoſe.

How to procure Vomit.

Why Vomit muſt not be forced.

CHAP. XXXVII.

Of Spitting, Salivation, Belching, Hicketing, and making of Water.

The effect of Spitting in Peſtilent diſeaſes

THat long evacuations may be made by Spitting and Salivation, you may learn by the example of ſuch as have a Pleuriſie; for the matter of the Pleuriſie being turned into *pus*, the purulent matter ſuckt up by the rare and ſpongeous ſubſtance of the lungs, and thence drawn into the *aſpera arteria*, is laſtly caſt out by the mouth.

The force of Salivation.

There is none ignorant how much ſuch as have the *Lues Venerea* are helped by Salivation and Spitting. But theſe ſhall be procured by a Maſticatory of the roots of *Ireos*, Pellitory of *Spain*, Maſtich, and the like; the mucilage of Line-ſeed held in the mouth will work the ſame effect.

The force of Sneezing.

That ſuch as have a moiſt brain may expel their ſuperfluous humours by ſneezing and blowing their noſes; the brain, by the ſtrength of the expulſive faculty, being ſtirred up to the excluſion of that which is harmful, may be known by the example of old people and children which are daily purged by their noſes; the brain is ſtirred up to both kinds of excretion from cauſes either internal or external: from the internal, as by a phlegmatick and vaporous matter, which contained in the brain, offends it: externally, as by receiving the beams of the Sun in the noſtrils, or by tickling them with a feather, or blowing into them the powder of Hellebore, *Euphorbium*, *Pyrethrum*, Muſtard-ſeeds, and the like Sternutamentories. For then the brain is ſtraitned by its own expulſive faculty, to the excretion of that which is troublous unto it. Sneezing breaketh forth with noiſe, for that the matter paſſeth through ſtraits, to wit, by the ſtraitning paſſages of the *Os cribroſum*, which is ſeated at the roots of the noſtrils. It is not fit to cauſe ſneezing in a body very plethorick, unleſs you have firſt premiſed general Medicins, leſt the humours ſhould be more powerfully drawn into the brain, and ſo cauſe an Apoplexy, *Vertigo*, or the like ſymptoms.

The commodities of Belching.

By Belching the flatulencies contained in the ventricle, being the off-ſpring of crudity, or flatulent meats, are expelled: theſe by their taſte and ſmell, pleaſing, ſtinking, ſweet, bitter or tart, ſhew the condition and kind of crudity of the humours from whence they are raiſed: now vomiting freeth the ſtomach of crudities, but the diſtemper muſt be corrected by contraries, as altering things to be preſcribed by the Phyſician.

Hicketting is a contraction and extenſion of the nervous fibres of the ſtomach, to caſt forth ſuch things as are too contumaciouſly impact in the coats thereof; yet repletion onely is not the cauſe thereof, but ſometimes inanition alſo; ſo oft-times a putrid vapour from ſome other place, breaking into the ſtomach, as from a peſtilent Bubo or Carbuncle; alſo all acid and acrid things, becauſe they prick, vellicate and provoke the tunicles of the ventricle, as Vinegar, ſpiced things, and the like; often and contumacious hicketting after purging, a wound or vomiting, is ill; but if a convulſion preſently happen thereon, it is deadly.

Several remedies muſt be uſed according to the variety of the cauſes: for repletion helps that hicketting that proceeds from inanition, and evacuation that which happens by repletion: that which proceeds from a putrid and venemous vapour, is helped by Treacle and Antidotes; that which is occaſioned by acid and acrid things, is cured by the uſe of groſs, fatty, and cold things.

The whole body purged by urin.

Now the whole body is oft-times purged by urin, and by this way the feveriſh matter is chiefly and properly accuſtomed to be evacuated: not a few being troubled with the *Lues Venerea*, when as they could not be brought to ſalivation by unction, have been cured by the large evacuation of urin cauſed by Diuretick Medicins. Diureticks wherewithall you may move urin, are formerly deſcribed in treating of the Stone. But we muſt abſtain from more acrid Diureticks, eſpecially when as inflammation is in the bladder; for otherwiſe the noxious humours are ſent to the affected part, whence there is danger of a deadly Gangrene. Therefore then it is better to uſe diverſion by ſweat.

When we ought to abſtain from Diureticks.

CHAP. XXXVIII.

Of the Menſtrual *and* Hæmorrhoidal *Purgation.*

How to provoke the Courſes.

NOt onely Reaſon, but alſo manifold experience induceth us to believe that Women by the benefit of their menſtrual purgation, eſcape and are freed from great, peſtilent, and abſolutely deadly diſeaſes; wherefore it muſt be procured by remedies, both inwardly taken, and outwardly applied: theſe may be taken inwardly with good ſucceſs, *Caſſia Lignea*, Cinnamon, the Bark of the Root of a Mulberry, Saffron, Agarick, Nutmeg, Savine, *Diagridium*, and divers others. But if the affect require more vehement Medicins, the roots of Tithymal, Antimony, Cantharides (taken in ſmall quantity) move the Courſes moſt powerfully; frictions and ligatures made upon the thighs and legs conduce hereto, as alſo Cupping in the inner and middle part of the thighs, the opening of the Vein *Saphena*, Leeches applied to the orifice of the neck of the Womb, Peſſaries, Nodulaes, Clyſters, Baths, Fomentations made of odoriferous things, which by the fragrancy of their odour, or rather by their heat may attenuate and cut groſs humours, open the obſtructed orifices of the Veins; ſuch are the Roots of Marſh-mallows, Orris, Parſly, Fennel, Kneeholm, the Leaves and Flowers of St. *Johns* Wort, Aſparagus, Rocket, Balm, Chervile, Mugwort, Mints, Penny-royal, Savory, Roſemary, Rue, Tyme, Sage, Bay-berries, Broom, Ginger, Cloves, Pepper, Nutmegs, and the like; the vapour of the boiling whereof, let the Woman, ſitting upon a perforated ſeat, receive by a funnel into the neck of her Womb, covering her ſelf warm on all ſides, that ſo nothing may otherwiſe break forth. Of the ſame things may be made baths, as well general, as particular. Alſo Peſſaries are good made after this manner: ℞ *Theriac. Mithrid. an.* ʒ ß.

How aromatick things provoke the Courſes.

caſtor.

caſtor. gum. ammoniac. an. ʒ j. *miſce cum bombace in ſucco mercurialis tincto, fiat peſſarium.* Or elſe, ℞ *Rad. petroſelin. & fœnug. ſub cineribus coctas, deinde contuſas cum pul. ſtaphyſag. pyreth. croco & oleo liliorum*; ſo make a peſſary in the form of a ſuppoſitory or nodula. ℞ *Pulv. myrrh. & aloes, an.* ʒ j. *fol. ſabin. nigel. artheriſ. an.* ʒ ij. *rad. Helleb. nigr.* ʒ j. *croci,* ℈ j. *cum ſucco mercur. & melle communi:* make a peſſary in cotton. This which follows is more effectual. ℞ *Succi rut. abſinth. an.* ʒ ij. *myrrh. euphorb. caſtor. ſabin. diacrid. terebinth. galban. theriac. an.* ʒ j. make a peſſary according to art; let a thred hang out of the one end of the peſſaries, that ſo you may eaſily draw them forth as you pleaſe. Peſſaries to provoke the Terms.

But if this menſtruous flux once provoked, flow too immoderately, it muſt be ſtopped by uſing meats of groſſer and more viſcid juice, by opening a vein in the arm, application of Cupping-glaſſes under the duggs, frictions and ligations of the upper parts, as the arms, putting up of peſſaries, application of refrigerating and aſtringent plaſters to the lower belly, ſhare, and loins, laying the woman in a convenient place, and not upon a feather-bed. How to ſtop the Courſes flowing too immoderately

This following injection ſtoppeth the bloud flowing out of the womb. ℞ *Aquæ plant. & fabror. an.* ℔ j. *nucum cupreſ. gallar. immatur. an.* ʒ ij. *berber. ſumach. balauſt. vitriol. rom. alum. roch. an.* ʒ ij. *bulliant omnia ſimul, & fiat decoctio:* of this make injection into the womb. In the performance of all theſe things, I would have the Surgeon depend upon the advice of a Phyſician, as the occaſion and place ſhall permit.

But if Nature endeavour to free it ſelf of the peſtilent matter by the *hæmorrhoids*, you may provoke them by frictions and ſtrong ligatures in the lower parts, as if the thighs or legs were broken, by Ventoſes applied with great flame to the inner ſide of the thigh, by application of hot and attractive things to the fundament, ſuch as are Fomentations, Emplaſters, Unguents; ſuch as is uſually made of an Onion roaſted under the embers, and incorporated with Treacle and a little Oil of Rue: after the hæmorrhoid veins, by theſe means, come to ſhew themſelves, they ſhall be rubbed with rough linnen cloths, or Fig-leaves, or a raw Onion, or an Ox-gall mixt with ſome powder of *Colloquintida*. Laſtly, you may apply Horſe-leeches, or you may open them with a lancet, if they hang much forth of the fundament, and be ſwollen with much bloud. But if they flow too immoderately, they may be ſtaid by the ſame means as the Courſes. How to provoke the *Hæmorrhoids*.

CHAP. XXXIX.

Of procuring evacuation by ſtool, or a flux of the belly.

NAture oftentimes, both by its ſelf, of its own accord, as alſo helped by laxative and purging Medicins, caſts into the belly and guts, as into the ſink of the body, the whole matter of a peſtilent diſeaſe, whence are cauſed *Diarrhœaes*, *Lienteries*, and *Dyſenteries*; you may diſtinguiſh theſe kinds of fluxes of the belly, by the evacuated excrements: For if they be thin and ſincere, that is, retain the nature of one, and that a ſimple humour, as of Choler, Melancholy, or Phlegm; and if they be caſt forth in a great quantity, without the ulceration or excoriation of the guts, vehement or fretting pain, then it is a *Diarrhœa*, which ſome alſo call *Fluxus Humoralis*. It is called a *Lienteria*, when as by the reſolved retentive faculty of the ſtomach and guts cauſed by ill humours, either there collected, or flowing from ſome other place; or by a cold and moiſt diſtemper, the meat is caſt forth crude, and almoſt as it was taken. A *Dyſenteria* is, when as many and different things, and oft-times mixt with bloud, are caſt forth with pain, gripings, and an ulcer of the guts, cauſed by acrid choler, fretting in ſunder the coats of the veſſels. What a *Diarrhœa* is. What a *Dyſenteria* is.

But if in any kind of diſeaſe, certainly in a peſtilent one, fluxes of the belly happen immoderate in quantity, and horrible in the quality of their contents, as liquid, viſcous, frothy, as from melted greaſe, yellow, red, purple, green, aſh-coloured, black, and exceeding ſtinking. The cauſe is various, and many ſorts of ill humours, which taken hold of, by the peſtilent malignity, turn into divers ſpecies, differing in their whole kind, both from their particular, as alſo from Nature in general, by reaſon of the corruption of their proper ſubſtance, whoſe inſeparable ſign is ſtench, which is oft-times accompanied by Worms. The cauſe of various and ſtinking excrements in the Plague.

In the Camp at *Amiens*, a peſtilent Dyſentery was over all the Camp, in this the ſtrongeſt Souldiers purged forth meer bloud. I diſſecting ſome of their dead bodies, obſerved the mouths of the Meſaraick veins and arteries, opened and much ſwollen; and whereas they entered into the guts, were juſt like little *Catyledons*, out of which as I preſſed them, there flowed bloud. For both by the exceſſive heat of the Summers Sun, and the minds of the enraged Souldiers, great quantity of acrid and cholerick humour was generated, and ſo flowed into the belly: but you ſhall know whether the greater or leſſer guts be ulcerated, better by the mixture of the bloud with the excrements, than by the ſite of the pain; therefore in the one you muſt rather work by Clyſters; but in the other by Medicins taken by the mouth. An Hiſtory.

Therefore, if by gripings, a *Teneſmus*, the murmuring and working of the guts, you ſuſpect in a peſtilent diſeaſe, that Nature endeavours to disburden it ſelf by the lower parts, neither in the mean while doth it ſucceed to your deſire, then muſt it be helped forward by Art, as by taking a potion of ʒ ſs. of *Hiera ſimplex*, and a dram of *Diaphœnicon* diſſolved in Wormwood water. A Potion.

Alſo Clyſters are good in this caſe, not onely for that they aſſwage the gripings and pains, and draw by continuation or ſucceſſion, from the whole body, but alſo becauſe they free the Meſaraick veins and guts from obſtruction and ſtuffing; ſo that by opening, and as it were unlocking of the paſſages, Nature may afterwards more freely free it ſelf from the noxious humours. In ſuch Clyſters they alſo ſometimes mix two or three drams of Treacle, that by one and the ſame labour they may retund the venenate malignity of the matter.

Suppoſitories. There may alſo be made for the ſame purpoſe Suppoſitories of boiled Honey, ℥ j. of *Hiera picra* and common Salt, of each ʒ ß. or that they may be the ſtronger, of Honey ℥ iij. of Ox-gall ℥ j. of Scammony, *Euphorbium*, and *Coloquintida* powdered, of each ʒ ß. The want of theſe may be ſupplied by *Nodulaes* made in this form. ℞ *Vitell. ovor.* nu. iij. *fellis bubuli, & mellis, an.* ℥ ß. *ſalis com.* ʒ ß. let them be ſtirred together, and well incorporated, and ſo parted into linnen rags, and then bound up into *Nodulaes* of the bigneſs of a Filberd, and ſo put up into the fundament; you may make them more acrid, by adding ſome powder of *Euphorbium* or *Coloquintida*.

CHAP. XL.

Of ſtopping the flux of the belly.

Violent and immoderate ſcourings, for that they reſolve the faculty, and lead the Patient into a conſumption and death; if they ſhall appear to be ſuch, they muſt be ſtaid in time by things taken and injected by the mouth and fundament. To this purpoſe may a pudding be made of Wheat-flour boiled in the water of the decoction of one Pomgranat, Berberries, Bole-Armenick, *Terra ſigillata*, and white Poppy-ſeeds, of each ʒ j. The following Almond-Milk ſtrengthens the ſtomach, and mitigates the acrimony of the cholerick humour, provoking the guts to excretion. Take ſweet Almonds boiled in the water of Barly, wherein Steel or Iron hath been quenched; beat them in a marble Mortar, and ſo with ſome of the ſame water, make them into an Almond-milk, whereto adding ʒ j. of *Diarrhodon Abbatis*, you may give it to the Patient to drink.

A haſty pudding to ſtay the lask.

This following Medicin I learnt of Dr. *Chappelain*, the Kings chief Phyſician, who received it of his Father, and held it as a great ſecret, and was wont to preſcribe it with happy ſucceſs to his Patients. It is thus: ℞ *Bol. Armen. terræ ſigil. lapid. hæmat. an.* ʒ j. *picis navalis*, ʒ j. ß. *coral. rub. marg. elect. corn. cervi uſt. & liti in aq. plant. an.* ϑ j. *ſaccar. roſ.* ℥ ij. *fiat pulvis.* Of this let the Patient take a ſpoonful before meat, or with the yolk of an Egg.

D. *Chappelains* Medicin to ſtay a ſcouring.

Chriſtopher Andrew in his *Oeconiatria*, much commendeth Dogs dung, when as the Dog hath for three days before been fed onely with bones.

Quinces roaſted in Embers, or boiled in a Pot, the Conſerve of Cornelian Cherries, Preſerved Berberries and Myrabolans, roaſted Nutmeg taken before meat ſtrengthen the ſtomach and ſtay the lask; the Patient muſt feed upon good meats, and theſe rather roaſted than boiled. His drink ſhall be Calibeate-water of the decoction of ſowre Pomgranats beaten, or of the decoction of Quince, Medlars, Services, Mulberries, Bramble-berries, and the like things, endued with a faculty to bind and waſte the excrementitious humidities of the body: theſe waters ſhall be mixed with ſyrup of red Currans, Julip of Roſes, and the like.

Drink.

Ointments. Let the region of the ſtomach and belly be anointed with Oil of Maſtich, *Moſchatelium*, Myrtles, and Quince. Alſo cut of bread newly drawn forth of the Oven, and ſteeped in Vinegar and Roſe-water may be profitably applied; or elſe a Cataplaſm of red Roſes, Sumach, Berberries, Myrtles, the pulp of Quinces, Maſtich, Bean-flour, and the Honey of Roſes made up with Calibeat-water.

Clyſter to ſtay a flux. Anodyne, abſtergent, aſtringent, conſolidating and nouriſhing Clyſters ſhall be injected. Theſe following retund the acrimony of humours, and aſſwage pain. ℞ *Fol. lactuc. hyoſc. acetoſ. portul. an.* m. j. *flor. violar. & nenuph. an.* ℥ i. ß. *fiat clyſter.* Or elſe, ℞ *Roſ. rub. hord. mund. ſem. plant. an.* p. j. *fiat decoctio, in colatura adde olei roſ.* ℥ ij. *vitell. ovor.* ij. *fiat clyſter.* Or, ℞ *Decoct. capi, crur. vitellin. & capit. vervecin. una cum pelle,* ℔ ij. *in qua coquantur fol. violar. malv. mercur. plantag. an.* m. j. *hord. mund.* ℥ j. *quatuor ſem. frigid. major.* ʒ ß. *in colaturæ* ℔ ß. *diſſolve caſſ. recenter extract.* ʒ j. *ol. viol.* ℥ iv. *vitell. ovor.* ij. *ſacc. rub.* ʒ j. *fiat clyſter.* Or, ℞ *Flor. chamæm. melil. aneth. an.* p. j. *rad. biſmal.* ℥ j. *fiat decoctio in lacte, colaturæ adde mucag. ſem. lin. fænugr. extract. in aqua malv.* ℥ ij. *ſaccar. rub.* ℥ j. *olei cham. & aneth. an.* ʒ j. ß. *vitellor. ovor.* ij. *fiat clyſter.*

Such Clyſters muſt be long kept, that they may more readily mitigate pain. When ſhaving of the guts appear in the ſtools, it is an argument that there is an ulcer in the guts; therefore then we muſt uſe detergent and conſolidating Clyſters, as this which follows:

A Clyſter for ulcerated guts ℞ *Hordei integr.* p. ij. *roſ. rub. flor. chamæm. plantag. apii, an.* p. j. *fiat decoctio, in colatura diſſolve mellis roſat. & ſyr. de abſinth. an.* ʒ j. ß. *vitel. ovor.* ij. This following Clyſter conſolidateth. ℞ *Succi plantag. centinod. & portulac. an.* ʒ ij. *bol. armen. ſang. dracon. amyl. an.* ʒ j. *ſevi hircini diſſoluti,* ʒ iij. *fiat clyſter.* Alſo Cows milk boiled with Plantain, and mixed with Syrup of Roſes, is an excellent medicin for the ulcerated guts.

A very aſtringent Clyſter. This following Clyſter binds. ℞ *Caud. equin. plant polygon. an.* m. j. *fiat decoctio in lacte uſtulato ad quart.* iij. *& in colatura adde boli armen. ſigil. ſang. dracon.* ʒ ij. *albumina quatuor ovor. fiat clyſter.* Or elſe, ℞ *Suc. plant. arnogloſ. centinod. portulac. reſidentia facta depuratorum quantum ſufficit pro clyſtere, addendo pul. bol. armen. terræ ſigill. ſang. drac. an.* ʒ j. *ol. myrrh. & roſat. an.* ℥ ij. *fiat clyſter.*

If pure bloud flow forth of the guts, I could wiſh you to uſe ſtronger aſtrictives. To which purpoſe I much commend a decoction of Pomgranat pills, of Cypreſs nuts, red Roſe leaves, Sumach, Alum, and Vitriol made with Smiths water, and ſo made into Clyſters, without any Oil. It will be good with the ſame decoction to foment the fundament, *perinæum*, and the whole belly.

Aſtringent Clyſters ought not to be uſed before that the noxious humours be drawn away, and purged by purging Medicins, otherwiſe by the ſtoppage hereof, the body may chance to be oppreſſed.

A nouriſhing Clyſter. If the Patient be ſo weak that he cannot take or ſwallow any thing by the mouth, nutritive Clyſters may be given him. ℞ *Decoctionis capi pinguis, & crur. vitulini, coct. cum acetoſa, buglooſſo, boragine lactuc. pimpinella,* ℥ x. *vel* xij. *in quibus diſſolve vitellos ovorum,* nu. iij. *ſaccari roſati, & aquæ vitæ, an.* ℥ j. *butyri recentis non ſaliti,* ʒ ij. *fiat clyſter.*

CHAP.

CHAP. XLI.

Of evacuation by insensible transpiration.

THe pestilent malignity, as it is oft-times drawn by the pores, by transpiration into the body, so oft-times it is sent forth invisibly the same way again. For our native heat, that is never idle in us, dispersеth the noxious humours, attenuate into vapours and air through the unperceivable breathing-places of the skin. An Argument hereof is, we see that the tumors and abscesses against Nature, even when they are come to suppuration, are oft-times resolved and discussed by the onely efficacy of Nature, and Heat, without any help of Art: Therefore there is no doubt but that Nature, being prevalent, may free it self from the pestilent malignity by transpiration, some Abscess, Bubo, or Carbuncle being come forth, and some matter collected in some certain part of the body: For when as Nature and the native heat are powerful and strong, nothing is impossible to it, especially when the passages are also in like manner free and open.

Tumors are oft-times discussed by the force of Nature after they are suppurated.

CHAP. XLII.

How to cure Infants and Children taken with the Plague.

IF that it happen that sucking or weaned children be infected with the Pestilence, they must be cured after another order than is yet described. The Nurse of the sucking child must govern her self so in Diet, and the use of Medicins, as if she were infected with the Pestilence her self: Her Diet consisteth in the use of the six things *Not natural*. Therefore let it be moderate; for the fruit or profit of that moderation in Diet cannot chuse but come unto the Nurses milk, and so unto the Infant that liveth by the milk. And the Infant it self must keep the same Diet, as near as he can, in sleep, waking, and expulsion, or avoiding of superfluous humours and excrements of the body. Let the Nurse be fed with those things that mitigate the violence of the feverish heat: as cooling broths, cooling herbs, and meats of a moderate temperature: she must wholly abstain from Wine, and anoint her Nipples as often as she giveth the Infant suck, with water or juice of Sorrel tempered with Sugar of Roses. But the Infants heart must be fortified against the violence of the increasing venom, by giving it one scruple of Treacle in Nurses milk, the broth of a Pullet, or some other cordial Water. It is also very necessary to anoint the region of the heart, the emunctories, and both the wrists with the same Medicin: neither were it unprofitable to smell often unto Treacle dissolved in Rose-water, Vinegar of Roses, and a little *Aqua Vitæ*, that so Nature may be strengthened against the malignity of the venom. When the children are weaned, and somewhat well grown, they may take Medicins by the mouth; for when they are able to concoct and turn into bloud meats that are more gross and firm than Milk, they may easily actuate a gentle Medicin. Therefore a potion must be prepared for them of twelve grains of Treacle dissolved with a little of the Syrup of Succory in some cordial Water, or the broth of a Capon: unless that any had rather give it with Conserve of Roses, in form of a Bole: but Treacle must be given to children in very small quantity, for if it be taken in any large quantity, there is great danger lest that by inflaming the humours, it infer a Fever. Furthermore, Broth may be prepared to be taken often, made of a Capon seasoned with Sorrel, Lettuce, Purslain, and cooling Seeds, adding thereto Bole-Armenick, and *Terra Sigillata* of each one ounce, being tied in a rag, and sometimes pressed out from the decoction. For Bole-Armenick, whether it be by its marvellous facuky of drying, or by some hidden property, hath this virtue, that being drunken (according as *Galen* witnesseth) it cureth those that are infected with the Pestilence, if so be that they may be cured by Physick; so that those that cannot be cured with Bole-Armenick, cannot be preserved by any other Medicins. But because the bodies of children are warm, moist, and vaporous, they are easily delivered of some portion of the venenate matter through the pores of the skin, by provoking sweat with a decoction of Parsly-seeds, Prunes, Figs, and the Roots of Sorrel, with a little of the powders of Harts-horn, or Ivory. But that the sweat may be more abundant and copious, apply sponges dipped and pressed out in the hot decoction of Sage, Rosemary, Lavender, Bays, Cammomil, Melilot, and Mallows, or else Swines bladders half filled with the same decoction, to the arm-holes, and to the groins. In the time that they sweat, let their Faces be fanned to cool them. Also let a Nodula of Treacle, dissolved in Vinegar and water of Roses, be applied to the Nostrils, but always use a moderation in sweating, because that children are of a substance that is easie to be dissipated and resolved: so that oftentimes, although they do not sweat, yet they feel the commodities of sweating, the matter of the venom being dissipated by the force of the heat through the pores of the skin. But in the sweating while the face is fanned, and sweet and cordial things applied to the nostrils, Nature must be recreated and strengthened, which otherwise would be debilitated through sweating, that it may be better able to expel the venom. After that the sweat is wiped away, it were very profitable to take a potion of Conserve of Roses, with the powder of Harts-horn or Ivory, dissolved in the waters of Bugloss and Sorrel, the better to cool and defend the heart. If there appear any tumour under the arm-holes, or in the groin, let it be brought to maturation with mollifying relaxing, drawing, and then with a suppurative fomentation, or Cataplasm; always using and handling it as gently as you may, considering the age of the Infant. If you have need to purge the Patient, the purgation following may be prescribed with great profit. Take of Rhubarb in powder one dram, infuse it in the water of *Carduus Benedictus*, with one scruple of Cinamon, in the straining dissolve two drams of *Diacatholicon*, of syrup of Roses laxative three drams: make thereof a small potion. This is the cure

The Nurse must be dieted when as the child is sick.

Medicins may be given to such as are weaned.

Lib. 9. simp. c. 74

The benefit of children.

The form of a Purge to be given to a child.

cure of the Peſtilence, and of the Peſtilent Fever, as far as I could learn from the moſt learned Phyſicians, and have obſerved my ſelf by manifold experience by the grace and permiſſion of God; of whom alone, as the Author of all good things that mortal men enjoy, the true and certain Preſervatives againſt the Peſtilence, are to be deſired and hoped for.

The End of the Two and Twentieth Book.

BOOK XXIII.

Of the Means and Manner to repair or ſupply the Natural or Accidental Defects or Wants in Mans Body.

CHAP. I.

How the loſs of the Natural or true Eye may be covered, hidden or ſhadowed.

The fourth duty of a Chirurgeon.

HAving at large treated in the former Books of Tumors, Wounds, Ulcers, Fractures, and Luxations, by what means things diſſolved and diſlocated might be united, things united ſeparated, and ſuperfluities conſumed or abated: Now it remains, that we ſpeak of the fourth Office or Duty of the Chirurgeon, which is to ſupply or repair thoſe things that are wanting by Nature, through the default of the firſt conformation, or afterwards by ſome miſchance. Therefore if that through any miſchance, as by any inflammation, any mans Eye happen to be broken or put out, and the humours ſpilt or waſted; or if it be ſtrucken out of its place or cavity wherein it was naturally placed by any violent ſtroke; or if it waſte or conſume by reaſon of a conſumption of the proper ſubſtance, then there is no hope to reſtore the ſight or function of the Eye, yet you may cover the deformity of the Eye ſo loſt (which is all you can do in ſuch a caſe) by this means: If that when you have perfectly cured and healed the Ulcer, you may put another Eye artificially made of Gold or Silver, counterfeited and enamelled, ſo that it may ſeem to have the brightneſs or gemmy decency of the natural Eye, into the place of the Eye that is ſo loſt.

The Forms of Eyes artificially made of Gold or Silver, poliſhed and enamelled, ſhewing both the inner and outer ſide.



But if the Patient be unwilling, or by reaſon of ſome other means, cannot wear this Eye ſo prepared, in his head, you may make another on this wiſe. You muſt have a ſtring or wire of Iron bowed or crooked, like unto womens Ear-wires, made to bind the head harder or looſer, as it pleaſeth the Patient, from the lower part of the head behind above the ear, unto the greater corner of the Eye; this rod or wire muſt be covered with ſilk, and it muſt alſo be ſomewhat broad at both ends, leſt that the ſharpneſs thereof ſhould pierce or prick any part that it cometh unto. But that end wherewith the empty hollowneſs muſt be covered, ought to be broader than the other, and covered with a thin piece of leather, that thereon the colours of the eye that is loſt may be ſhadowed or counterfeited. Here followeth the Figure or portraiture of ſuch a ſtring or wire.

The

The form of an Iron Wier wherewith the deformity of an eye that is loſt, may be ſhadowed or covered.



CHAP. II.

By what means a part of the Noſe that is cut off, may be reſtored; or how inſtead of the Noſe that is cut off, another counterfeit Noſe may be faſtned, or placed in the ſtead.

WHen the whole Noſe is cut off from the Face, or portion of the Noſtrils, from the Noſe, it cannot be reſtored or joined again; for it is not in Men as it is in Plants. For Plants have a weak and feeble heat; and furthermore, it is equally diſperſed into all the ſubſtance of the Plant or Tree, neither is it eaſie to be conſumed or waſted: for when the boughs or branches of Trees are broken, torn or cut away, the live nevertheleſs, and will grow again when they are ſet and grafted; neither is there any ſeat for the heart rightly prepared in them from whence the heat muſt neceſſarily run, and diſperſe it ſelf continually into all the parts thereof. But contrariwiſe, the ſeparated parts of more perfect living Creatures, as of Men, are incontinently deprived of life; becauſe they have their nouriſhment, life, ſenſe, and whole ſuſtentation not of themſelves, by faculties flowing or coming unto them from ſome other parts; neither are they governed by their own heat, as Plants, but by a borrowed heat: ſo that above or beſide the natural faculty of the liver, another vital faculty cometh unto it from the heart.

Why the parts of Plants being cut off, may grow again, but thoſe of Man cannot

Wherefore inſtead of the Noſe cut away or conſumed, it is requiſite to ſubſtitute another made by Art, becauſe that Nature cannot ſupply that defect: this Noſe ſo artificially made, muſt be of Gold, Silver, Paper, or linnen cloths glewed together, it muſt be ſo coloured, counterfeited, and made both of faſhion, figure and bigneſs, that it may as aptly as is poſſible, reſemble the natural Noſe: it muſt be bound or ſtaid with little threds or laces unto the hinder part of the head or the hat. Alſo if there be any portion of the upper lip cut off with the noſe, you may ſhadow it with annexing ſome ſuch thing that is wanting unto the noſe, and cover it with the hair on his upper lip, that he may not want any thing that may adorn or beautifie the face. Therefore I have thought it neceſſary to ſet down the figure or form of both theſe kinds.

The form of a Noſe artificially made, both alone by it ſelf, and alſo with the upper lip covered with the hair of the Beard.



There

A ſtrange cure for a cut off Noſe.

There was a Surgeon of *Italy* of late years which would reſtore or repair the portion of the Noſe that was cut away, after this manner. He firſt ſcarified the callous edges of the maimed Noſe round about, as is uſually done in the cure of Hare-lips: then he made a gaſh or cavity in the muſcle of the arm, which is called *Biceps*, as large as the greatneſs of the portion of the Noſe which was cut away did require: and into that gaſh or cavity ſo made, he would put that part of the Noſe ſo wounded, and bind the Patients head to his arm, as if it were to a poſt, ſo faſt that it might remain firm, ſtable and immovable, and not lean or bow any way; and about forty days after, or at that time when he judged the fleſh of the Noſe was perfectly agglutinated with the fleſh of the arm; he cut out as much of the fleſh of the arm, cleaving faſt unto the noſe, as was ſufficient to ſupply the defect of that which was loſt, and then he would make it even, and bring it, as by licking, to the faſhion and form of a Noſe, as near as Art would permit; and in the mean while he did feed his Patient with Panadoes, Gellies, and all ſuch things as were eaſie to be ſwallowed and digeſted. And he did this work of curing the place where the fleſh was ſo cut out, onely with certain Balms, and agglutinative liquors.

An Hiſtory.

A younger Brother of the Family of St. *Thoan*, being weary of a ſilver Noſe, which being artificially made, he had worn in the place of his Noſe that was cut off, went to this Chirurgeon into *Italy*, and the means of the foreſaid practice he recovered a Noſe of fleſh again, to the great admiration of all thoſe that knew him before. This thing truly is poſſible to be done, but it is very difficult both to the Patient ſuffering, and alſo to the Chirurgeon working. For that the fleſh that is taken out of the arm is not of the like temperature as the fleſh of the Noſe is; alſo the holes of the reſtored Noſe cannot be made as they were before.

CHAP. III.

Of the placing of Teeth artificially made, in ſtead of thoſe that are loſt or wanting.

IT oftentimes happeneth that the fore-teeth are moved, broken or ſtricken out of their places by ſome violent blow, which cauſeth deformity of the mouth, and hinders plain pronunciation. Therefore when the jaw is reſtored (if it were luxated or fractured) and the gums brought into their former hardneſs, other teeth artificially made of Bone or Ivory may be put in the place of thoſe that are wanting, and they muſt be joined one faſt unto another, and alſo ſo faſtned unto the natural teeth adjoining, that are whole: and this muſt chiefly be done with a thred of Gold or Silver, or for want of either, with a common thred of Silk or Flax, as it is declared at large by *Hippocrates*, and alſo deſcribed in this Figure following.

Sect. 2. lib. de Art. ſent. 15.

The Figure of Teeth bound or faſtned together.

CHAP. IV.

Of filling the hollowneſs of the Palat.

The cauſes and hurt that enſues of the loſt Palat.

MAny times it happeneth that a portion or part of the bone of the Palat, being broken with the ſhot of a Gun, or corroded by the virulency of the *Lues Venerea*, falls away; which makes the Patients, to whom this happeneth, that they cannot pronounce their words diſtinctly, but obſcurely and ſnuffling: therefore I have thought it a thing worthy the labour, to ſhew the means how it may be helped by Art. It muſt be done by filling the cavity of the Palat with a Plate of Gold or Silver, a little bigger than the cavity it ſelf is. But it muſt be as thick as a French Crown, and made like unto a diſh in Figure; and on the upper ſide, which ſhall be toward the brain, a little Sponge muſt be faſtned, which when it is moiſtned with the moiſture diſtilling from the brain, will become more ſwollen and puffed up, ſo that it will fill the concavity of the Palat, that the artificial Palat cannot fall down, but ſtand faſt and firm, as if it ſtood of it ſelf. This is the true Figure of thoſe Inſtruments, whoſe certain uſe I have obſerved not by once or twice, but by manifold trials in the battels fought beyond the Alps.

The Figure of Plates to fill or ſupply the defects of the Palat.

The Figure of another Plate of the Palat, on whoſe upper ſide there is a button, which may be turned when it is put into its place, with a ſmall Ravens bill, like this whoſe Figure is here expreſſed.



CHAP. V.

How to help ſuch as cannot ſpeak by reaſon of the loſs of ſome part of the Tongue.

CHance gave place and authority to this remedy, as to many other in our Art. A certain man dwelling in a Village named *Yvoy le Chaſteau*, being ſome four and twenty mile from *Bourges*, had a great piece of his tongue cut off; by which occaſion he remained dumb ſome three years. It happened on a time that he was in the Field with Reapers, he drinking in a woodden diſh was tickled by ſome of the ſtanders by, not enduring the tickling, he ſuddenly broke out into articulate and intelligible words. He himſelf wondring thereat, and delighted with the novelty of the thing, as a miracle, put the ſame diſh to his mouth juſt in the ſame manner as before, and then he ſpake ſo plainly and articulately, that he might be underſtood by them all. Wherefore a long time following he always carried this diſh in his boſom to utter his mind, until at length Neceſſity, the Miſtriſs of Arts and giver of Wit, inducing him, he cauſed a woodden inſtrument to be neatly cut and made for him, like that which is here delineated, which he always carried hanging at his neck, as the onely Interpreter of his mind; and the Key of his Speech.

A remedy found out by accident.

An Hiſtory.

An Inſtrument made to ſupply the defect of the Speech when the Tongue is cut off.



The uſe of the Inſtrument is this. *A* Sheweth the upper part of it which was of the thickneſs of a Nine-pence, which he did ſo hold between his cutting teeth, that it could not come out of his mouth, nor be ſeen. *B* Sheweth the lower part, as thick as a Six-pence, which he did put hard to the reſt of his tongue, cloſe to the membranous ligament which is under the tongue. That place which is depreſt and ſomewhat hollowed, marked with the letter *C*, is the inner part of the inſtrument. *D* Sheweth the out-ſide of the ſame. He hanged it about his neck with the ſtring that is tied thereto.

Textor the Phyſician of *Bourges* ſhewed me this Inſtrument: and I my ſelf made trial thereof on a young man whoſe tongue was cut off, and it ſucceeded well, and took very good effect. And I think other Surgeons in ſuch caſes may do the like.

CHAP.

CHAP. VI.

Of covering or repairing certain defects or defaults in the face.

IT oftentimes happeneth, that the face is deformed by the ſudden flaſhing of Gun-powder, or by a peſtilent Carbuncle, ſo that one cannot behold it without great horrour. Such perſons muſt be ſo trimmed and ordered, that they may come in ſeemly manner into the company of others. The lips if they be either cut off with a ſword, or deformed with the eroſion or eating of a peſtilent Carbuncle or ulcerated Cancer, ſo that the teeth may be ſeen to lie bare with great deformity. If the loſs or conſumption of the lip be not very great, it may be repaired by that way which we have preſcribed in the cure of hare-lips, or of an ulcerated Cancer. But if it be great, then muſt there be a lip of gold made for it, ſo ſhadowed and counterfeited, that it may not be much unlike in colour to the natural lip, and it muſt be faſtned and tied to the hat or cap that the Patient weareth on his head, that ſo it may remain ſtable and firm.

CHAP. VII.

Of the defects of the Ears.

SUch as want their Ears, either naturally or by misfortune, as through a Wound, Carbuncle, Cancer, or the biting of wild Beaſts: if ſo be that the Ear be not wholly wanting, waſted, conſumed, or torn away; but that ſome portion thereof doth yet remain, then muſt it not be neglected, but muſt have many holes made therein with a bodkin; and after that the holes are cicatrized, let ſome convenient thing, made like unto the piece of the Ear that is loſt, be tied or faſtned unto it by theſe holes.

But if the Ear be wholly wanting, another muſt be made of Paper artificially glewed together, or elſe of leather, and ſo faſtned with laces, from the top or hinder part of the head, that it may ſtand in the appointed place; and ſo the hair muſt be permitted to grow long, or elſe ſome cap worn under the hat, which may hide or cover the deformity, unleſs you had rather have it to be ſhadowed or counterfeited by ſome Painter, that thereby it may reſemble the colour of a natural Ear; and ſo retain it in the place where it ought to ſtand, with a rod or wier coming from the top or hinder part of the head, as we have ſpoken before in the loſs of the Eye: and the form thereof is this.



CHAP. VIII.

Of amending the deformity of ſuch as are crook-backt.

Cauſes of crookedneſs.

THe bodies of many, eſpecially young Maids or Girls (by reaſon that they are more moiſt and tender then the bodies of Boys) are made crooked in proceſs of time, eſpecially by the wrenching aſide and crookedneſs of the back-bone. It hath many cauſes, that is to ſay, in the firſt conformation in the womb, and afterwards by misfortune; as a fall, bruiſe, or any ſuch like accident; but eſpecially by the unhandſome and undecent ſituation of their bodies when they are young and tender, either in carrying, ſitting or ſtanding, (and eſpecially when they are taught to go too ſoon) ſaluting, ſewing, writing, or in doing any ſuch like thing.

In the mean while, that I may not omit the occaſion of crookedneſs, that happens ſeldom to the Country People, but is much incident to the Inhabitants of great Towns and Cities, which is by reaſon of the ſtraightneſs and narrowneſs of the garments that are worn by them, which is occaſioned by the folly of Mothers, who while they covet to have their young daughters bodies ſo ſmall in the middle as may be poſſible, pluck and draw their bones awry, and make them crooked. For the ligaments of the back-bone being very tender, ſoft and moiſt at that age, cannot ſtay it ſtraight and ſtrongly;

ſtrongly; but being pliant, eaſily permits the ſpondels to ſlip awry inwards, outwards, or ſidewiſe, as they are thruſt or forced.

The remedy for this deformity is to have breſt-plates of Iron, full of holes all over them, whereby they may be lighter to wear; and they muſt be ſo lined with bombaſte that they may hurt no place of the body. Every three moneths new plates muſt be made for thoſe that are not yet arrived at their full growth; for otherwiſe by the daily afflux of more matter, they would become worſe. But theſe Plates will do them ſmall good that are already at their full growth.

The form of an Iron Breſt-plate, to amend the crookedneſs of the Body.



CHAP. IX.

How to relieve ſuch as have their Urin flow from them againſt their wills, and ſuch as want their Yards.

IN thoſe that have the Strangury, of what cauſe ſoever that malady cometh, the urin paſſeth from them by drops, againſt their wills and conſent. This accident is very grievous and troubleſom, eſpecially to men that travel: and for their ſakes onely I have invented the inſtrument here beneath deſcribed. It is made like unto a cloſe breech or hoſe; it muſt be of Lattin, and to contain ſome four ounces: it muſt be put into the Patients hoſe, betwixt his thighs, unto which it muſt be tied with a point by the ring. Into the open and hollow mouth of this inſtrument, which is noted with the letter C, the Patient muſt put his yard; and into this concavity or hollowneſs goeth a ſtay ſomewhat deep, it is marked with the letter B, and made or placed there, both to hold or bear the end of the yard, and alſo by his cloſe joint that it muſt have unto the veſſel, to ſtay the urin from going back again when it is once in. But the letters A and D, do ſignifie all the inſtrument; that, the former part, this the hinder part thereof. Now this is the ſhape thereof.

An Inſtrument for ſuch as cannot hold their Water.

The Figure of an Inſtrument, which you may call a Baſin, *or Receptacle for the Urin.*



Thoſe that have their Yards cut off cloſe to their bellies, are greatly troubled in making of Urin, ſo that they are conſtrained to ſit down like women. For their eaſe, I have deviſed this Pipe or Conduit, having an hole through it as big as one finger, which may be made of Wood, or rather of Lattin.

A and C do ſhew the bigneſs and length of the Pipe. B Sheweth the brink on the broader end. D Sheweth the outſide of the brink. This Inſtrument muſt be applied to the lower part of *Os pectinis*: on the upper end it is encompaſſed with a brink for the paſſage of the Urin, for thereby it will receive the Urin better, and carry it from the Patient as he ſtandeth upright.

The deſcription of a Pipe or Conduit, ſerving in ſtead of the Yard in making of water, which therefore we may call an artificial Yard.



CHAP. X.

By what means the periſhed function or action of a thumb or finger may be corrected and amended.

An Hiſtory.

WHen a ſinew or tendon is cut clean aſunder, the action in that part, whereof it was the author, is altogether aboliſhed; ſo that the member cannot bend or ſtretch out it ſelf, unleſs it be holpen by Art: which thing I performed in a Gentleman belonging to *Annas* of *Montmorency*, General of the French Horſemen, who in the battel of *Dreux* received ſo great a wound with a Back-ſword upon the outſide of the wriſt of the right hand, that the tendons that did erect or draw up the Thumb were cut clean in ſunder; and alſo when the wound was throughly whole and conſolidated, the Thumb was bowed inwards, and fell into the palm of the hand, ſo that he could not extend or lift it up, unleſs it were by the help of the other hand, and then it would preſently fall down again; by reaſon whereof he could hold neither Sword, Spear, nor Javelin in his hand, ſo that he was altogether unprofitable for War, without which he ſuppoſed there was no life. Wherefore he conſulted with me about the cutting away of his Thumb, which did hinder his gripings, which I refuſed to do, and told him that I conceived a means how it might be remedied without cutting away. Therefore I cauſed a caſe to be made for it of Lattin, whereinto I put the Thumb: this caſe was ſo artificially faſtned by two ſtrings that were put into two rings made in it above the joint of the hand, that the Thumb ſtood upright and ſtraight out, by reaſon whereof he was able afterwards to handle any kind of weapon.

The form of a Thumb or Finger-ſtall of Iron or Lattin, to lift up or erect the Thumb, or any other Finger that cannot be erected of it ſelf.



If that in any man the ſinews or tendons which hold the hand upright, be cut aſunder with a wound, ſo that he is not able to lift up his hand, it may eaſily be erected or lifted up with this Inſtrument that followeth, being made of an equal, ſtraight, thin, but yet ſtrong plate of Lattin, lined on the inner ſide with ſilk, or any ſuch like ſoft thing, and ſo placed in the wriſt of the hand, that it may come unto the Palm, or the firſt joints of the fingers; and it muſt be tied above with convenient ſtays, and ſo the diſcommodity of the depreſſion, or hanging of the hand, may be avoided: therefore this Inſtrument may be called the Erector of the Hand.

The Erector of the Hand.



CHAP.

CHAP. XI.

Of helping thoſe that are Vari *or* Valgi, *that is, crook-legged, or crook-footed, inwards or outwards.*

THoſe that are ſaid to be *Vari*, whoſe feet or legs are bowed or crooked inwards. This default is either from the firſt conformation in the womb, through the default in the Mother, who hath her legs in like manner crooked; or becauſe that in the time when ſhe is great with child, ſhe commonly ſits with her legs acroſs; or elſe after the child is born, and that either becauſe his legs be not well ſwathed when he is laid into the Cradle, or elſe becauſe they be not well placed in carrying the infant; or if he be not well looked unto by the Nurſe when he learneth to go: for the bones are very tender, and almoſt as flexible as Wax. What *Varus* is.

But contrariwiſe, thoſe are called *Valgi* whoſe legs are crooked or bowed outwards. This may come through the default of the firſt conformation as well as the other; for by both, the feet alſo and the knees may be made crooked; which thing whoſoever will amend, muſt reſtore the bones into their proper and natural place; ſo that in thoſe that are *varous*, he muſt thruſt the bones outwards, as though he would make them *valgous*: neither is it ſufficient to thruſt them ſo, but they ought alſo to be retained there in their places after they are ſo thruſt, for otherwiſe they being not well eſtabliſhed, would ſlip back again. What *Valgus* is.

They muſt be ſtaid in their places, by applying of collars and bolſters on that ſide whereunto the bones do lean and incline themſelves; for the ſame purpoſe boots may be made of leather, of the thickneſs of a teſtone, having a ſlit in the former part all along the bone of the leg, and alſo under the ſole of the foot, that being drawn together on both ſides, they may be the better fitted and ſit cloſer to the leg. And let this Medicin following be applied all about the leg. ℞ *Thuris, maſtich. aloes, boli armeni, an.* ʒ j. *aluminis roch. reſinæ pini ſicc. ſubtiliſſime pulveriſ. an.* ʒ iij. *farinæ volat.* ʒ j. ſ. *albumovor. q. ſ.* make thereof a Medicin. You may alſo add a little Turpentine, leſt it ſhould dry ſooner, or more vehemently than is neceſſary. But you muſt beware, and take great heed, leſt that ſuch as were of late *varous* or *valgous*, ſhould attempt or ſtrain themſelves to go before that their joints be confirmed; for ſo the bones that were lately ſet in their places, may ſlip aſide again. And moreover, until they are able to go without danger, let them wear high ſhoes tied cloſe to their feet, that the bones may be ſtaid the better and more firmly in their places; but let that ſide of the ſoal of the ſhoe be under-laid whither the foot did incline before it was reſtored. A Plaſter to hold faſt reſtored bones.

The Form of little Boots, whereof the one is open and the other ſhut.

CHAP. XII.

By what means Arms, Legs, and Hands may be made by Art, and placed inſtead of the natural Arms, Legs, or Hands that are cut off and loſt.

NEceſſity oftentimes conſtrains us to find out the means whereby we may help and imitate Nature, and ſupply the defect of members that are periſhed and loſt. And hereof it cometh that we may perform the functions of going, ſtanding and handling with Arms and Hands made by Art, and undergo our neceſſary flexions and extenſions with both of them. I have gotten the forms of all thoſe members made ſo by Art, and the proper names of all the Engines and Inſtruments whereby thoſe artificially made are called, to my great coſt and charges, of a moſt ingenious and excellent Smith dwelling at *Paris*, who is called of thoſe that know him, and alſo of ſtrangers, by no other name than the Little *Lorain*; and here I have cauſed them to be pourtraid, or ſet down, that thoſe that ſtand in need of ſuch things, after the example of them, may cauſe ſome Smith, or ſuch like Workman, to ſerve them in the like caſe. They are not onely profitable for the neceſſity of the body, but alſo for the decency and comelineſs thereof. And here follow their forms.

The form of an Hand made artificially of Iron.



This Figure following ſheweth the back-ſide of an Hand artificially made, and ſo that it may be tied to the arm or ſleeve.



The

The Form of an Arm made of Iron very artificially.



The deſcription of Legs *made artificially of Iron.*



The Form of a Woodden Leg made for poor Men.



A *Sheweth the ſtump or ſtock of the woodden Leg.* B B *Sheweth the two ſtays which muſt be on both ſides of the Leg, the ſhorter of them muſt be on the inner ſide.* C C *Sheweth the Pillow or Bolſter whereon the Knee muſt reſt in the bottom between the two ſtays, that ſo it may reſt the ſofter.* D D *Sheweth the thongs or girths with their round buckles put through the two ſtays on either ſide to ſtay the Knee in his place firm and immovable, that it ſlip not aſide.* E *Sheweth the thigh it ſelf, that you may know after what faſhion it muſt ſtand.*

It happens alſo many times, that the Patient that had the nerves or tendons of his Leg wounded, long after the wound is whole and conſolidated, cannot go but with very great pain and torment, by reaſon that the foot cannot follow the muſcle that ſhould draw it up. That this malady may be remedied, you ought to faſten a linnen band made very ſtrong unto the ſhoe that the Patient weareth on that his pained foot; and at the knee it muſt have a ſlit where the knee may come forth in bowing of the Leg: and it muſt be truſſed up faſt unto the Patients middle, that it may the better lift up and erect the foot in going. This band is marked in the Figure following with the letters A A.



CHAP.

CHAP. XIII.

Of amending or helping of Lameneſs or Halting.

HAlting is not onely a great deformity, but alſo very troubleſom and grievous. Therefore if that any be grieved therewith by reaſon that one of his legs is ſhorter than the other, it may be holpen by putting under his ſhort foot this ſitting Crutch, which we are now about to deſcribe. For by the help of this, he ſhall not onely go upright, but alſo more eaſily and with little labour or no pain at all. It was taught me by *Nicolas Piccard* Chirurgeon to the Duke of *Lorain*. The Form thereof is this:



A *Sheweth the ſtaff or ſtilt of this Crutch, which muſt be made of Wood.* B *Sheweth the Seat of Iron whereon the thigh reſteth, juſt under the buttock.* C *Sheweth a prop which ſtayeth up the ſeat whereon all the weight of the Patients body reſteth.* D *Sheweth the ſtirrup, being made of Iron, and bowing crooked upwards, that the foot may ſtand firm, and not ſlip off it when the Patient goeth.* E *Sheweth the Prop that ſtayeth or holdeth up the ſtirrup to ſtrengthen it.* F *Sheweth the foot of the ſtilt or crutch made of Iron with many pikes, and compaſſed with a ring or ferule, ſo to keep it from ſlipping.* G *The croſs or head of the crutch which the Patient muſt put under his arm-hole to lean upon, as it is to be ſeen in the Figure.*

The End of the Three and Twentieth Book.

BOOK

BOOK XXIV.

Of the GENERATION *of* MAN.

THE PREFACE.

The distinction of Male and Female.

The cause of this distinction.

GOD the Creator and maker of all things, immediately after the Creation of the World, of his unspeakable counsel and inestimable wisdom, not onely distinguished mankind, but all other living Creatures also into a double sex, to wit, of Male and Female; that so they being moved and enticed by the allurements of Lust, might desire Copulation, thence to have Procreation. For this bountiful Lord hath appointed it as a solace unto every living creature against the most certain and fatal necessity of death: then for as much as each particular living creature cannot continue for ever, yet they may endure by their species or kind, by propagation and succession of creatures, which is by procreation, so long as the World endureth. In this conjunction or copulation replenished with such delectable pleasure, (which God hath chiefly established by the Law of Matrimony,) the Male and Female yield forth their seeds, which presently mixed and conjoined, are received and kept in the Females womb. For the seed is a certain spumous or foamy humour replenished with vital spirit, by the benefit whereof, as it were by a certain ebullition or fermentation, it is puffed up, and swollen bigger, and both the seeds being separated from the more pure bloud of both the Parents, are the material and formal beginning of the issue; for the seed of the Male being cast and received into the womb, is accounted the principal and efficient cause; but the seed of the Female is reputed the subjacent matter, or the matter wherein it worketh. Good and laudable seed ought to be white, shining, clammy, knotty, smelling like unto the Elder or Palm, delectable to Bees, and sinking down in the bottom of Water being put into it, for that which swimmeth on the water is esteemed unfruitful; for a great portion cometh from the brain, yet some thereof falls from the whole body, and from all the parts both firm and soft thereof. For unless it come from the whole body and every part thereof, all and every part of the issue cannot be formed thereby, because like things are engendred of their like: and therefore it cometh that the Child resembleth the Parent, not onely in stature and favour, but also in the conformation and proportion of his limbs and members, and complexion and temperature of his inward parts, so that diseases are oft-times hereditary, the weakness of this or that entrail being translated from the Parent to the Child. There are some which suppose this falling of the seed from the whole body not to be understood according to the weight and matter, as if it were a certain portion of all the bloud separated from the rest; but according to the power and form, that is to say, the animal, natural and vital spirits, being the framers of formation and life, and also the formative faculty to fall down from all the parts into the seed, that is wrought or perfected by the Testicles; for proof and confirmation whereof, they alledge that many perfect, sound, absolute, and well proportioned children, are born of lame and decrepit Parents.

What Seed is.

The conditions of good seed.

Seed falleth from all the parts of the body.

Wherefore many diseases are hereditary.

How seed is to be understood to fall from the whole body.

CHAP. XXIX.

Why the generative parts are endued with great pleasure.

What moveth a man to copulation.

A Certain great pleasure accompanieth the function of the parts appointed for generation; and before it in living Creatures that are of a lusty age, when matter aboundeth in those parts, there goeth a certain fervent or furious desire: the causes thereof many, of which the chiefest is, That the kind may be preserved and kept for ever, by the propagation and substitution of other living creatures of the same kind. For brute Beasts which want reason, and therefore cannot be solicitous for the preservation of their kind, never come to carnal copulation unless they be moved thereunto by a certain vehement provocation of unbridled Lust, and as it were by the stimulation of Venery. But Man that is endued with reason, being a divine and most noble creature, would never yield nor make his mind so subject to a thing so abject and filthy as is carnal copulation, but that the venereous ticklings, raised in those parts, relax the severity of his mind; or Reason admonisheth him that the memory of his name ought not to end with his life, but to be preserved unto all generations, as far as may be possible, by the propagation of his seed or issue. Therefore by reason of this profit or commodity, Nature hath endued the genitals with a far more exact or exquisite sense than the other parts, by sending the great sinews unto them, and moreover she hath caused them to be bedewed or moistned with a certain whayish humour, not much unlike the seed sent from the glandules or kernels called *prostatæ*, situated in Men at the beginning of the neck of the bladder, but in Women at the bottom of the womb: this moisture hath a certain sharpness or biting, for that kind of humour of all others can chiefly provoke those parts to their function or office, and yield them a delectable pleasure, while they are in execution of the same. For even so whayish and sharp humours, when they are gathered together under the skin, if they wax warm, tickle with a certain pleasant itching, and by their motion infer delight: but the nature of the genital parts or members is not stirred up or provoked to the expulsion of the seed with these provocations of the humours, abounding either in quantity or quality only, but a certain great and hot spirit or breath contained in those parts, doth begin to dilate it self more and more, which causeth a certain incredible excess of pleasure or voluptuousness, wherewith the genitals

genitals being replete, are ſpread forth or diſtended every way unto their full greatneſs. The Yard is given to Men whereby they may caſt out their ſeed directly or ſtraitly into the Womans womb; to Women whereby they may receive that ſeed ſo caſt forth, by the open or wide mouth of the ſame neck, and alſo that they may caſt forth their own ſeed ſent through the ſpermatick veſſels unto their teſticles; theſe ſpermatick veſſels, that is to ſay, the Vein lying above, and the artery lying below, do make many flexions or windings, yet one as many as the other, like unto the tendrils of Vines diverſly platted or folded together, and in thoſe folds or bendings the bloud and ſpirit which are carried unto the teſticles, are concocted a longer time, and ſo converted into a white ſeminal ſubſtance. The lower of theſe flexions or bowings do end in the Stones or Teſticles. But the Teſticles for as much as they are looſe, thin, and ſpongeous, or hollow, receiving the humour which was begun to be concocted in the fore-named veſſels, concoct it again themſelves: but the Teſticles of Men concoct the more perfectly for the procreation of the iſſue, and the teſticles of Women more imperfectly, becauſe they are more cold, leſs, weak, and feeble, but the Seed becometh white by the contact or touch of the Teſticles, becauſe the ſubſtance of them is white. The male is ſuch as engendereth in another, and the female in her ſelf, by the ſpermatick veſſels which are implanted in the inner capacity of the womb. But out of all doubt, unleſs Nature had prepared ſo many allurements, baits, and provocations of pleaſure, there is ſcarce any man ſo hot and delighted in venerous acts, which conſidering and marking the place appointed for humane conception, the loathſomneſs of the filth which daily falleth down into it, and wherewithall it is humected and moiſtned, and the vicinity and nearneſs of the great gut under it, and of the bladder above it, but would ſhun the embraces of Women. Nor would any Women deſire the company of Man, which once premeditates or fore-thinks with her ſelf on the labour that ſhe ſhould ſuſtain in bearing in the burthen of her child nine Moneths, and of the almoſt deadly pains that ſhe ſhall ſuffer in her delivery.

The cauſe of folding of the ſpermatick veſſels.

Womens Teſticles more imperfect.

Why many men and women abhor venerous copulapulation.

Men that uſe too frequent copulation, oftentimes in ſtead of ſeed caſt forth a crude and bloudy humour, and ſometimes meer bloud it ſelf; and oft-times they can hardly make water but with great pain, by reaſon that the clammy and oily moiſture, which Nature hath placed in the glandules called the *Proſtatæ*, to make the paſſage of the urin ſlippery, and to defend it againſt the ſharpneſs of the urin that paſſeth through it, is waſted, ſo that afterward they ſhall ſtand in need of the help of a Surgeon to cauſe them to make water with eaſe and without pain, by injecting of a little Oil out of a Syringe into the conduit of the Yard. For in generation it is fit the man caſt forth his ſeed into the womb, with a certain impetuoſity, his Yard being ſtiff and diſtended, and the Woman to receive the ſame without delay into her womb being wide open, leſt that through delay the ſeed wax cold, and ſo become unfruitful by reaſon that the ſpirits are diſſipated and conſumed. The Yard is diſtended or made ſtiff, when the nervous, ſpongeous and hollow ſubſtance thereof is replete and puffed up with a flatulent ſpirit. The womb allures or draws the maſculine ſeed into it ſelf by the mouth thereof, and it receives the womans ſeed by the horns from the ſpermatick veſſels which come from the Teſticles into the hollowneſs or concavity of the womb, that ſo it may be tempered by conjunction, commiſtion and confuſion with the mans ſeed, and ſo reduced or brought unto a certain equality: for generation or conception cannot follow without the concourſe of two ſeeds, well and perfectly wrought in the very ſame moment of time, nor without a laudable diſpoſition of the womb both in temperature and complexion: if in this mixture of ſeeds the mans ſeed in quality and quantity exceed the womans, it will be a man-child; if not, a woman-child, although that in either of the kinds there is both the mans and womans ſeed: as you may ſee by the daily experience of thoſe men who by their firſt wives have had boys onely, and by their ſecond wives had girls onely: the like you may ſee in certain women, who by their firſt husbands have had males onely, and by their ſecond husbands females onely. Moreover, one and the ſame man is not always like affected to get a man or woman-child; for by reaſon of his age, temperature and diet, he doth ſometimes yield forth ſeed endued with a maſculine virtue, and ſometimes with a feminine or weak virtue, ſo that it is no marvel if men get ſometimes men and ſometimes women-children.

Why the Strangury enſueth immoderate copulation.

What things neceſſary unto generation.

Why a male, and why a female is engendred.

CHAP. II.

Of what quality the Seed is, whereof the male, and whereof the female is engendred.

MAle Children are engendred of a more hot and dry ſeed, and women of a more cold and moiſt: for there is much leſs ſtrength in cold then in heat, and likewiſe in moiſture than in drineſs; and that is the cauſe why it will be longer before a Girl is formed in the womb than a boy. In the ſeed lieth both the procreative and the formative power: As for example, In the power of Melon-ſeed are ſituate the Stalks, Branches, Leaves, Flowers, Fruit, the Form, Colour, Smell, Taſte, Seed and all. The like reaſon is of other ſeeds; ſo Apple-grafts engrafted in the ſtock of a Pear-tree bear Apples: and we do always find and ſee by experience, that the tree (by virtue of grafting) that is grafted, doth convert it ſelf into the nature of the Siens wherewith it is grafted. But although the child that is born doth reſemble or is very like unto the Father or Mother, as his or her ſeed exceedeth in the mixture; yet for the moſt part it happeneth that the Children are more like the Father than the Mother, becauſe that in the time of copulation, the mind of the woman is more fixed on her husband, than the mind of the husband on, or towards his wife: for in the time of copulation or conception, the forms or the likeneſs of thoſe things that are conceived and kept in mind, are tranſported and impreſſed in the Child or iſſue: for ſo they affirm that there was a certain Queen of the *Æthiopians* who brought forth a white child, the reaſon was (as ſhe confeſſed) that at the time of copulation with her King, ſhe thought on a marvelous white thing,

Why men-children are ſooner formed in the womb than women.

The Seed is that in power from whence each thing cometh or floweth.

Why the children are moſt commonly like unto their Fathers.

When children should be gotten.

thing, with a very ſtrong imagination. Therefore *Heſiod* adviſeth all married people not to give themſelves to carnal copulation when they return from burials, but when they come from Feaſts and Plays, leſt that their ſad, heavy, and penſive cogitations, ſhould be ſo transfuſed and engraften in the iſſue; that they ſhould contaminate or infect the pleaſant joyfulneſs of his life with ſad, penſive or paſſionate thoughts. Sometimes it happeneth, although very ſeldom, the child is neither like the Father nor the Mother, but in favour reſembleth his Grandfather, or any other of his Kindred; by reaſon that in the inward parts of the parents, the engrafted power and nature of the Grandfather lies hidden; which when it hath lurked there long, not working any effect, at length breaks forth by means of ſome hidden occaſion: wherein Nature reſembleth the Painter, making the lively pourtraiture of a thing, which as far as the ſubject matter will permit, doth form the iſſue like unto the Parents in every habit; ſo that often-times the diſeaſes of the Parents are transferred or participated unto the children, as it were by a certain hereditary title: for thoſe that are crook-backt, get crook-backt children; thoſe that are lame, lame; thoſe that are leprous, leprous; thoſe that have the ſtone, children having the ſtone; thoſe that have the ptiſick, children having the ptiſick; and thoſe that have the gout, children having the gout: for the ſeed follows the power, nature, temperature, and complexion of him that engendereth it. Therefore of thoſe that are in health and ſound, healthy and ſound; and of thoſe that are weak and diſeaſed, weak and diſeaſed children are begotten, unleſs happily the ſeed of one of the Parents that is ſound doth correct or amend the diſeaſed impreſſion of the other that is diſeaſed, or elſe the temperate and ſound womb as it were by the gentle and pleaſant breath thereof.

Why oftentimes the child reſembleth the Grandfather.

Why ſometimes thoſe that are diſeaſed do get ſound children.

CHAP. III.

What is the cauſe why Females of all brute Beaſts, being great with young, do neither deſire, nor admit the Males, until they have brought forth their Young.

Why the ſenſe of Venereous acts is given to brute beaſts

THe cauſe hereof is, for as much as they are moved by ſenſe onely, they apply themſelves unto the thing that is preſent, very little or nothing at all perceiving things that are paſt and to come. Therefore after they have conceived, they are unmindful of the pleaſure that is paſt, and do abhor copulation; for the ſenſe or feeling of luſt is given unto them by Nature, onely for the preſervation of their kind, and not for voluptuouſneſs, or delectation. But the Males raging, ſwelling, and as it were ſtimulated by the provocations of the heat or fervency of their luſt, do then run unto them, follow and deſire copulation, becauſe a certain ſtrong odor or ſmell cometh into the air from their ſecret or genital parts, which pierceth into their noſtrils, and unto their brain, and ſo inferreth an imagination, deſire, and heat. Contrariwiſe, the ſenſe and feeling of venerous actions ſeemeth to be given by nature to Women, not onely for the propagation of iſſue and for the conſervation of mankind, but alſo to mitigate and aſſwage the miſeries of mans life, as it were by the enticements of that pleaſure: alſo the great ſtore of hot bloud that is about the heart, wherewith men abound, maketh greatly to this purpoſe, which by impulſion of imagination, which ruleth the humours, being driven by the proper paſſages down from the heart and entrails into the genitals, doth ſtir up in them a new luſt.

Why of brute beaſts the Males raging with luſt, follow after the Females.

Wherefore a woman when ſhe is with child, deſireth copulation.

The Males of brute Beaſts, being provoked or moved by the ſtimulation of luſt, rage and are almoſt burſt with a *Tentigo* or extenſion of the genital parts, and ſometimes wax mad; but after that they have ſatisfied their luſt with the female of their kind, they preſently become gentle, and leave off ſuch fierceneſs.

CHAP. IV.

What things are to be obſerved, as neceſſary unto generation in the time of copulation.

How women may be moved to Venery and Conception.

WHen the Husband cometh into the Wifes Chamber, he muſt entertain her with all kind of dalliance, wanton behaviour, and allurements to Venery; but if he perceive her to be ſlow, and more cold, he muſt cheriſh, embrace, and tickle her, and ſhall not abruptly, the nerves being ſuddenly diſtended, break into the field of Nature; but rather ſhall creep in by little and little, intermixing more wanton kiſſes with wanton words and ſpeeches, handling her ſecret parts and dugs, that ſhe may take fire, and be enflamed to venery; for ſo at length the womb ſhall ſtrive and wax fervent with a deſire of caſting forth its own ſeed, and receive the mans ſeed to be mixed together therewith. But if all theſe things will not ſuffice to enflame the woman, for women for the moſt part are more ſlow and ſlack unto the expulſion or yielding forth of their ſeed, it ſhall be neceſſary firſt to foment her ſecret parts with the decoction of hot herbs made with Muſcadine, or boiled in any other good Wine, and to put a little Musk or Civet into the neck or mouth of the womb: and when ſhe ſhall perceive the efflux of her ſeed to approach, by reaſon of the tickling pleaſure, ſhe muſt advertiſe her husband thereof, that at the very inſtant time or moment, he may alſo yield forth his ſeed, that by the concourſe or meeting of the ſeeds, conception may be made, and ſo at length a child formed and born. And that it may have the better ſucceſs, the husband muſt not preſently ſeparate himſelf from his wifes embraces, leſt the air ſtrike into the open womb, and ſo corrupt the ſeeds before they are perfectly mixed together. When the man departs, let the woman lie ſtill in quiet, laying her legs or her thighs acroſs, one upon another, and raiſing them up a little, leſt that by motion or downward ſituation, the ſeed ſhould be ſhed or ſpilt: which is the cauſe why ſhe ought at that time not to talk, eſpecially chiding, nor to cough, nor ſneez, but give her ſelf to reſt and quietneſs, if it be poſſible.

The meeting of the ſeeds moſt neceſſary for generation.

CHAP.

CHAP. V.

By what ſigns it may be known, whether the Woman have conceived, or not.

IF the ſeed in the time of copulation, or preſently after be not ſpilt, if in the meeting of the ſeeds the whole body do ſomewhat ſhake, that is to ſay, the womb drawing it ſelf together for the compreſſion and entertainment thereof, if a little feeling of pain doth run up and down the lower belly, and about the navel, if ſhe be ſleepy, if ſhe loath the embracings of a man, and if her face be pale, it is a token that ſhe hath conceived.

In ſome, after conception ſpots or freckles ariſe in their face, their eyes are depreſſed and ſunk in, the white of their eyes waxeth pale, they wax giddy in the head, by reaſon that the vapours are raiſed up from the menſtrual bloud that is ſtopped, ſadneſs and heavineſs grieve their minds, with loathing and waywardneſs, by reaſon that the ſpirits are covered with the ſmoaky darkneſs of the vapours: pains in teeth and gums, and ſwouning oftentimes cometh, the appetite is depraved or overthrown, with aptneſs to vomit, and longing, whereby it happeneth that they loath meats of goods juice, and long for and deſire illaudable meats, and thoſe that are contrary to nature, as coles, dirt, aſhes, ſtinking ſalt-fiſh, ſuch ſowre, auſtere and tart fruits, pepper, vinegar, and ſuch like acrid things, and other, altogether contrary to nature and uſe, by reaſon of the condition of the ſuppreſſed humour abounding and falling into the orifice of the ſtomach. This appetite ſo depraved or overthrown, endureth in ſome until the time of child-birth; in others it cometh in the third moneth after their conception, when hairs do grow on the child: and laſtly, it leaveth them a little before the fourth moneth, becauſe that the child, being now greater and ſtronger, conſumes a great part of the excremental and ſuperfluous humour. The ſuppreſſed or ſtopped terms in women that are great with child, are divided into three parts; the more pure portion maketh the nutriment for the child, the ſecond aſcendeth by little and little into the dugs, and the impureſt of all remaineth in the womb about the Infant, and maketh the ſecondine or after-birth, wherein the Infant lieth as in a ſoft bed. Thoſe women are great with child, whoſe urin is more ſharp, fervent, and ſomewhat bloudy, the bladder not onely waxing warm by the compreſſion of the womb; fervent, by reaſon of the bloud contained in it, but alſo the thinner portion of the ſame bloud being expreſſed, and ſweating out into the bladder. A ſwelling and hardneſs of the dugs, and veins that are under the dugs in the breaſts and about them, and milk coming out when they are preſſed, with a certain ſtirring motion in the belly, are certain infallible ſigns of greatneſs with child. Neither in this greatneſs of child-bearing, the veins of the dugs onely, but of all the whole body, appear full and ſwelled up, eſpecially the veins of the thighs and legs; ſo that by their manifold folding and knitting together, they do appear varicous, whereof cometh ſluggiſhneſs of the whole body, heavineſs and impotency, or difficulty of going, eſpecially when the time of deliverance is at hand. Laſtly, If you would know whether the Woman have conceived or not, give unto her when ſhe goeth to ſleep, ſome Mead or honied water to drink; and if ſhe have a griping in her guts or belly, ſhe hath conceived; if not, ſhe hath not conceived.

Spots or ſpecks in the faces of thoſe that are with child.

Why many women being great with child refuſe laudable meats, and deſire thoſe that are illaudable and contrary to Nature.

The ſuppreſſed Terms divided into three parts.

Hip. 1. de Morb. mul.

Aph. 41. ſect. 5.

CHAP. VI.

That the womb, ſo ſoon as it hath received the ſeed, is preſently contracted or drawn together.

AFter that the ſeeds of the Male and female have both met, and are mixed together in the capacity of the womb, then the orifice thereof doth draw it ſelf cloſe together, leſt the ſeeds ſhould fall out. There the Females ſeed goeth and turneth into nutriment, and the increaſe of the Males ſeed; becauſe all things are nouriſhed, and do increaſe by thoſe things that are moſt familiar, and like unto them. But the ſimilitude and familiarity of ſeed with ſeed is far greater than with bloud; ſo that when they are perfectly mixed and coagulated together, and ſo wax warm by the ſtraight and narrow encloſure of the womb, a certain thin skin doth grow about it, like unto that that will be over unskimmed Milk.

Why the female ſeed is nutriment for the male ſeed.

Moreover, this concretion or congealing of the ſeed, is like unto an Egg laid before the time that it ſhould: that is to ſay, whoſe membrane or tunicle that it compaſſeth it about, hath not as yet increaſed or grown into a ſhelly hardneſs about it; in folding-wiſe are ſeen many ſmall threds dividing themſelves, over-ſpread with a certain clammy, whitiſh or red ſubſtance, as it were with black bloud. In the midſt under it appeareth the navel, from whence that ſmall skin is produced. But a man may underſtand many things that may appertain unto the conception of mankind by the obſervation of twenty Eggs, ſetting them to be hatched under an Hen, and taking one every day and breaking it, and diligently conſidering it; for in ſo doing, on the twentieth day you ſhall find the Chick perfectly formed with the navel. That little skin that ſo compaſſeth the Infant in the womb, is called the ſecundine or *Chorion*, but commonly the after-birth.

A compendious way to underſtand human conception.

This little skin is perfectly made within ſix days, according to the judgment of *Hippocrates*, as profitable and neceſſary not onely to contain the ſeeds ſo mixed together, but alſo to ſuck nutriment through the orifices of the veſſels ending in the womb. Thoſe orifices the Greeks do call *Cotyledones*, and the Latins *Acetabula*, for they are as it were hollowed eminences, like unto thoſe which may be ſeen in the foot or ſnout of a Cuttle-fiſh many times in a double order, both for the working and holding of their meat. Thoſe eminences called *Acetabula*, do not ſo greatly appear in women as in many brute beaſts. Therefore by theſe the ſecondine cleaveth on every ſide unto the womb, for the conſervation, nutrition, and increaſe of the conceived ſeed.

Lib. de nat. puer.

What the *Cotyledones* are.

CHAP.

CHAP. VII.

Of the generation of the Navel.

AFter the Woman hath conceived, to every one of the aforesaid eminences groweth presently another vessel, that is to say, a Vein to the Vein, and an Artery to the Artery: these soft and yet thin vessels are framed with a little thin membrane, which being spread under, sticketh to them; for to them it is in stead of a membrane, and a ligament, and a tunicle, or a defence; and it is doubled with the others, and made of the Vein and Artery of the Navel. These new small vessels of the Infant, with their orifices, do answer directly one to one, to the *Cotyledones* or eminences of the womb; they are very small and little, as it were the hairy fibres that grow upon roots that are in the earth; and when they have continued so a longer time, they are combined together, that of two they are made one Vessel, until that by continual connexion, all those vessels go and degenerate into two other great vessels, called the Umbilical vessels or the vessels of the navel, because they do make the navel, and do enter into the childs body by the hole of the navel. Here *Galen* doth admire the singular providence of God and Nature; because that in such a multitude of vessels, and in so long a passage or length that they go or are produced, the vein doth never confound it self, nor stick to the artery, nor the artery to the vein; but every vessel joineth it self to the vessel of its own kind. But the Umbilical vein, or Navel vein, entering into the body of the child, doth join it self presently to the hollow part of the liver; but the artery is divided into two, which join themselves to the two Iliack arteries along the sides of the bladder, and are presently covered with the *Peritonæum*; and by the benefit thereof annexed unto the parts which it goes unto. Those small veins and arteries are as it were the roots of the child; but the vein and artery of the Navel are as it were the body of the Tree, to bring down the nutriment to nourish the child. For first we live in the womb the life of Plant, and then next the life of a Sensitive Creature: and as the first tunicle of the child is called *Chorion* or *Allantoides*; so the other is called *Amnios* or *Agnina*, which doth compass the seed or child about on every side. These membranes are most thin, yea for their thinness like unto the Spiders web, woven one upon another; and also connexed in many places by the extremities of certain small and hairy substances, which at length by the adjunction of their like do get strength; whereby you may understand what is the cause why by divers and violent motions of the Mother in going and dancing, or leaping, and also of the Infant in the womb, those membranes are not almost broken. For they are so conjoined by the knots of those hairy substances, that between them nothing, neither the urin, nor the sweat can come, as you may plainly and evidently perceive in the dissection of a womans body that is great with child, not depending on any other mans opinion, be it never so old or inveterate: yet the strength of those membranes is not so great, but that they may be soon broken in the birth, by the kicking of the child.

The Vein never joineth it self with the artery.

Hippocrates calleth all the membranes that compass the infant in the womb, according to the judgment of *Galen* in his Book *De usu Partium*, by the name of the Secondines.

CHAP. VIII.

Of the Umbilical Vessels, or the Vessels belonging to the Navel.

MAny of the ancient Writers have written that there are five Vessels found in the Navel. But yet in many, nay all the bodies I sought in for them, I could never find but three; that is to say, one Vein, which is very large, so that in the passage thereof it will receive the tag of a point, and two Arteries, but not so large, but much narrower,; because the child wanteth or standeth in need of much more bloud for his conformation, and the nutriment or increase of his parts, than of vital spirit.

An old opinion confuted.

These Vessels making the body of the Navel, which, as it is thought, is formed within nine or ten days by their doubling and folding, make knots like unto the knots of a Franciscan Friers girdle, that staying the running bloud in those their knotty windings, they might more perfectly concoct the same: as may be seen in the ejaculatory spermatick vessels, for which use also the length of the Navel is half an ell; so that in many Infants that are somewhat grown, it is found three or four times doubled about their neck or thigh.

To what use the knots of the childs Navel in the womb serve.

As long as the child is in his Mothers womb, he taketh his nutriment onely by the Navel, and not by his Mouth; neither doth he enjoy the use of eyes, ears, nostrils, or fundament, neither needeth he the functions of the heart. For the spirituous bloud goeth unto it by the arteries of the Navel, and into the Iliack arteries; and from the Iliack arteries unto all the other arteries of the whole Body, for by the motion of these onely the Infant doth breath. Therefore it is not to be supposed that the air is carried or drawn in by the lungs unto the heart, in the body of the child, but contrariwise from the heart to the lungs. For neither the heart doth perform the generation or working of bloud, or of the vital spirits. For the Issue or Infant is contented with them as they are made and wrought by his Mother. Which, until it hath obtained a full, perfect, and whole description of his parts and members, cannot be called a Child, but rather an Embryon, or an imperfect substance.

The child in the womb taketh his nutriment by his Navel, not by his Mouth.

How the child breatheth.

CHAP.

CHAP. IX.

Of the ebullition or ſwelling of the ſeed in the womb, and of the concretion of the bubbles or bladders, or the three principal entrails.

IN the ſix firſt days of conception the new veſſels are thought to be made and brought forth of the eminences or *cotyledons* of the mothers veſſels, and diſperſed into all the whole ſeed, as as they were *fibres*, or hairy ſtrings. Thoſe, as they pierce the womb, ſo do they equally and in like manner penetrate the tunicle *Chorion*. And it is carried this way, being a paſſage not onely neceſſary for the nutriment and conformation of the parts, but alſo into the veins diverſly woven and diſperſed into the skin *Chorion*. For thereby it cometh to paſs, that the ſeed it ſelf boileth, and as it were fermenteth or ſwelleth, not only through occaſion of the place but alſo of the bloud and vital ſpirits that flow unto it; and then it riſeth into three bubbles or bladders like unto the bubbles which are occaſioned by the rain falling into a river or channel full of water. Theſe three bubbles or bladders, are certain rude, or new forms, or concretions of the three principal entrails, that is to ſay, of the liver, heart, and brain. All this former time it is called ſeed, and by no other name; but when thoſe bubble ariſe, it is called an embryon, or the rude form of a body until the perfect conformation of all the members: on the fourth day after that the vein of the navel is formed, it ſucketh groſſer bloud, that is, of a more full nutriment out of the *Cotyledons*. And this bloud, becauſe it is more groſs, eaſily congeals and curdles in that place, where it ought to prepare the liver fully and abſolutely made. For then it is of a notable great bigneſs above all the other parts; and therefore it is called *Parenchyma*, becauſe it is but only a certain congealing or concretion of bloud brought together thither, or in that place. From the gibbous part thereof ſpringeth the greater part or trunk of the hollow vein, called commonly *vena cava*, which doth diſperſe his ſmall branches, which are like unto hairs, into all the ſubſtance thereof; and then it is divided into two branches, whereof the one groweth upwards, the other downwards unto all the particular parts of the body.

The three bladders.

When the ſeed is called an embryon.

Why the liver is called *Parenchyma*.

In the mean ſeaſon the arteries of the navel ſuck ſpirituous bloud out of the eminences or *Cotyledons* of the mothers arteries, whereof, that is to ſay, of the more fervent and ſpirituous bloud the heart is formed in the ſecond bladder or bubble, being endued with a more fleſhy, ſound, and thick ſubſtance, as it behoveth that veſſel to be, which is the fountain from whence the heat floweth, and hath a continual motion.

In this the virtue formative hath made two hollow places; one on the right ſide, another on the left. In the right, the root of the hollow vein is infixed or ingraffed, carrying thither neceſſary nutriment for the heart: in the left is formed the ſtamp or root of an artery, which preſently doth divide it ſelf into two branches; the greater whereof goeth upwards to the upper parts, and the wider unto the lower parts, carrying unto all the parts of the body life and vital heat.

CHAP. X.

Of the third Bubble or Bladder, wherein the head and the brain is formed.

THE far greater portion of the ſeed goeth into this third bubble, that is to ſay, yielding matter for the conformation of the brain, and all the head. For a greater quantity of ſeed ought to go unto the conformation of the head and brain; becauſe theſe parts are not ſanguine or bloody, as the heart and liver; but in a manner without bloud, bony, marrow, cartilaginous, nervous, and membranous, whoſe parts, as the veins, arteries, nerves, ligaments, panicles, and skin, are called *ſpermatick* parts; becauſe they obtain their firſt conformation almoſt of ſeed only: although that afterwards they are nouriſhed with blood, as the other fleſhy and muſculous parts are. But yet the bloud, when it cometh unto thoſe parts, degenerateth, and turneth into a thing ſomewhat ſpermatick, by vertue of the aſſimulative faculty of thoſe parts. All the other parts of the head form and faſhion themſelves unto the form of the brain, when it is formed; and thoſe parts which are ſituated and placed about it, for defence eſpecially, are hardened into bones.

Why the greater portion of ſeed goeth into generation of the head and brain.

The head, as the ſeat of the ſenſes, and manſion of the mind and reaſon, is ſituated in the higheſt place; that from thence, as it were from a lofty tower or turret, it might rule and govern all the other members, and their functions and actions that are under it: for there the ſoul or life, which is the rectreſs or governeſs, is ſituated; and from thence it floweth, and is diſperſed into all the whole body. Nature hath framed theſe three principal entrails, as props and ſuſtentations for the weight of all the reſt of the body: for which matter alſo ſhe hath framed the bones.

Why the head is placed on the top of the body.

The firſt bones that appear to be formed, or are ſuppoſed to be conformed, are the bones called *oſſa Ilium*, connexed or united by ſpondyls that are between them: then all the other members are framed and proportioned by their concavities and hollowneſſes, which generally are ſeven, that is to ſay, two of the ears, two of the noſe, one of the mouth, and in the parts beneath the head one of the fundament, and another of the *yard* or conduit of the bladder; and furthermore in women, one of the neck of the womb, without the which they can never be made mothers or bear children.

When all theſe are finiſhed, nature, that ſhe might poliſh her excellent work in all ſorts, hath covered all the body and every member thereof with skin. Into this excellent work or *Microcoſmos* ſo perfect, God, the author of nature and all things, infuſeth or ingrafteth a ſoul or life: which S. *Auguſtine* proveth by this ſentence of *Moſes*: *If any man ſmite a woman with child, ſo* *Exod. 20. qu. 52*

that thereby ſhe be delivered before her natural time, and the child be dead, being firſt formed in the womb let him die the death: but if the child hath not as yet obtained the full proportion and conformation of his body and members, let him recompence it with mony. Therefore it is not to be thought that the life is derived, propagated or taken from *Adam* or our parents; and as it were an hereditary thing diſtributed unto all mankind by their parents; but we muſt believe it to be immediately created of God, even at the very inſtant time when the child is abſolutely perfected in the lineaments of his body, and ſo given unto it by him.

The *Mola* in the womb liveth not as the child.

So therefore the rude lumps of fleſh called *molæ* that engender in womens wombs, and monſters of the like breeding and confuſed bigneſs, although by reaſon of a certain quaking and ſhivering motion, they ſeem to have life, yet they cannot be ſuppoſed to be endued with a life or a reaſonable ſoul: but they have their motion, nutriment and increaſe wholly of the natural and infixed faculty of the womb, and of the generative or procreative ſpirit that is ingraffed naturally in the ſeed.

But even as the infant in the womb obtaineth not perfect conformation before the thirtieth day, ſo likewiſe it doth not move before the ſixtieth day: at which time it is moſt commonly not perceived by women, by reaſon of the ſmalneſs of the motion. But now let us ſpeak briefly of the life or ſoul, wherein conſiſteth the principal original of every function in the body, and likewiſe of generation.

CHAP. XI.

Of the life or ſoul.

The life goeth not into the maſs of ſeed that doth engender the child, before the body of the child and each part thereof hath his perfect proportion and form.

THe ſoul entreth into the body ſo ſoon as it hath obtained a perfect and abſolute diſtinction and conformation of the members in the womb, which in male children, by reaſon of the more ſtrong and forming heat which is ingraffed in them, is about the fourtieth day, and in females obout the fourty fifth day; in ſome ſooner, and in ſome later, by reaſon of the efficacy of the matter working, and pliantneſs or obedience of the matter whereon it worketh. Neither doth the life or ſoul being thus inſpired into the body preſently execute or perform all his functions, becauſe the inſtruments that are placed about it cannot obtain a firm and hard conſiſtence neceſſary for the lively, but eſpecially for the more divine miniſteries of the life or ſoul, but in a long proceſs of age and time.

Why the life or ſoul doth not preſently execute all his offices.

Thoſe inſtruments of the ſoul are vitiated either in the firſt conformation, as when the form or faſhion of the head is ſhaped upwards or pyramidal, as was the head of *Therſites*, that lived in the time of the Trojan war, and of *Triboulet* and *Tonin* that lived in later years; or alſo by ſome caſualty, as by the violent handling of the midwife, who by compreſſion, by reaſon that the ſcull is tender and ſoft, hath cauſed the capacity of the ventricles that be under the brain to be too narrow for them: or by a fall, ſtroak, diſorder in diet, as by drunkenneſs, or a feaver, which inferreth a lethargy, exceſſive ſleepineſs, or phrenſie.

1 *Cor. c.* 12.

Preſently after the ſoul is entred into the body, God endueth it with divers and ſundry gifts: hereof it cometh that ſome are endued with wiſdom by the ſpirit; others with knowledge by the ſame ſpirit; others with the gift of healing by the ſame ſpirit; others with power, dominion and rule; others with propheſie; others with diverſities of tongues; and to others, other endowments, as it hath pleaſed the divine providence and bounty of God, to beſtow upon them, againſt which no man ought to contend or ſpeak. *For it is not meet that the thing formed ſhould ſay unto him that formed it, why haſt thou made me thus? hath not the Potter power to make of the ſame lump of clay one veſſel to honor and another to diſhonour?* It is not my purpoſe, neither belongeth it unto me nor any other humane creature to ſearch out the reaſon of thoſe things, but only to admire them with all humility: But yet I dare affirm this one thing, that a noble and excellent ſoul neglecteth elementary and tranſitory things, and is raviſhed and moved with the contemplation of celeſtial, which it cannot freely enjoy before it be ſeparated from this earthly incloſure or priſon of the body, and be reſtored unto its original.

What the ſoul or life is.

Therefore the ſoul is the inward *Entelechia* or perfection, or the primitive cauſe of all motions and functions both natural and animal, and the true form of man. The Ancients have endeavoured to expreſs the obſcure ſenſe thereof by many deſcriptions. For they have called it a celeſtial ſpirit, and a ſuperior, incorporeal, inviſible, and immortal eſſence, which is to be comprehended of it ſelf alone, that is, of the mind or underſtanding. Others have not doubted but that we have our ſouls inſpired by the univerſal divine mind, which as they are alive, ſo they do beſtow life on the bodies unto whom they are annexed or united. And although this life be diſperſed into all the whole body, and into every portion of the ſame, yet is it void of all corporal weight or mixtion, and it is wholly and alone in every ſeveral part, being ſimple and inviſible, without all compoſition or mixture, yet endued with many virtues and faculties, which it doth utter in divers parts of the body: For it feeleth, imagineth, judgeth, remembreth, underſtandeth, and ruleth all our deſires, pleaſures, and animal motions; it ſeeth, heareth, ſmelleth, taſteth, toucheth; and it hath divers names of theſe ſo many and ſo great functions, which it performeth in divers parts of the body. It is called the ſoul of life; becauſe it maketh the body live, which of it ſelf is dead. It is called the *ſpirit* or *breath*; becauſe it inſpireth our bodies. It is called *reaſon*; becauſe it diſcerneth truth from falſhood, as it were by a certain divine rule. It is termed the mind; becauſe it is mindful of things paſt, in recalling and remembring them: And it is called the *vigor* or *courage*; becauſe it giveth vigor and courage to the ſluggiſh weight, or maſs of the body. And laſtly, it is called the ſenſe and *underſtanding*: becauſe it comprehendeth things that are ſenſible and intelligible. Becauſe it is incorporeal, it cannot occupy a place by corporeal extention; although not-

The life is in all the whole body and in every portion thereof.

The life or ſoul is ſimple and inviſible.

Divers names and the reaſon of divers names that are given to humane forms.

withſtanding

withſtanding it filleth the whole body. It is ſimple, becauſe it is but one in eſſence, nor increaſed, nor diminiſhed: for it is no leſs in a Dwarf than in a Giant; and it is like perfect and great in an infant as in a man, according to its own nature.

But there are three kinds of bodies informed by a ſoul whereby they live: the firſt being the moſt imperfect, is of plants; the ſecond of brute beaſts; and the third of men. The plants live by a vegetative; beaſts by a ſenſitive; and men by an intellective ſoul. And as the ſenſitive ſoul of brute beaſts is endued with all the vertues of the vegetative; ſo the humane intellective comprehendeth the vertues of all the inferior, not ſeparated by any diviſion, but by being indiviſibly united with reaſon and underſtanding, into one humane form and ſoul whereon they depend. But becauſe we have ſaid a little before, that divers functions of the life are reſident, and appear in divers parts of the body, here in this place, omitting all others, we will proſecute thoſe only which are accounted the principal.

Three kinds of living bodies.

The ſuperiour ſoul containeth in it ſelf all the powers of the inferiour.

The principal functions of the humane ſoul, according to the opinion of many, are four in number, proceeding from ſo many faculties, and conſequently from one ſoul; they are theſe: The Common Senſe, Imagination, Reaſoning, and Memory. And they think that the common or interiour ſenſe doth receive the forms and images of ſenſible things, bein carried by the ſpirit through the paſſage of the nerves, as an inſtrument of the external ſenſes, as it were a meſſenger to go between them; and it ſerves not only to receive them, but alſo to know, perceive, and diſcern them. For the eye, wherein the external ſenſe of ſeeing conſiſteth, doth not know white or black. Therefore it cannot diſcern the differenees of colours, as neither the tongue taſtes, nor the noſe ſavours nor the ears ſound, nor laſtly, the hands their touching quality: yea, the eye doth not of it ſelf perceive that it ſeeth, nor the noſe that it ſmelleth, nor the ears that they hear, nor the tongue that it taſteth, nor the hands that they touch. For all theſe things are the offices and functions of the common ſenſe; for this ſenſe knoweth that the eye hath ſeen ſomething, either white, black, red, a man, horſe, ſheep, or ſome ſuch like material thing; yea, even when the ſight is gone and paſt; and ſo likewiſe the noſe to have ſmelled this or that ſavour, the ear to have heard this or that ſound, the tongue to have taſted this or that taſte, and the hand to have touched this or that thing, be they never ſo diverſe. For all the external ſenſes, and all the functions thereof do end, and are referred to the Common ſenſe, as it were the lines of a circle from the circumference into the center, as it is expreſſed in this figure.

What the common ſenſe is.

The function of the common ſenſe is double.

For which cauſe it is called the common or principal ſenſe; for that therein the primitive power of feeling or perceiving is ſituated, for it uſeth the miniſtery or ſervice of the external ſenſes, to know many and diverſe things, whoſe differences it doth diſcern and judge; but ſimple things, that are of themſelves, and without any compoſition and connexion, which may conſtitute any thing true or falſe, or any argumentation, belongeth only to the mind, underſtanding, or reaſon. For this was the counſel of nature, that the external ſenſes ſhould receive the forms of things ſuperficially, lightly, and gently only; like as a glaſs, not to any other end, but that they ſhould preſently ſend them unto the Common ſenſe, as it were unto their center and prince, which he (that is to ſay, the Common ſenſe) delivereth to be collected unto the underſtanding or reaſoning faculty of the ſoul, which *Avicen* and *Averrois* have ſuppoſed to be ſituated in the former part of the brain.

What cauſe the internal ſenſe is called the common ſenſe.

The common ſenſe underſtandeth or knoweth thoſe things that are ſimple only.

Next unto the common ſenſe followeth the phantaſie or imagination, ſo called becauſe of it ariſe the forms and *Ideas* that are conceived in the mind, called of the Greeks *Phantaſmata*. This doth never reſt but in thoſe that ſleep: neither always in them, for oft-times in them it cauſeth dreams, and cauſeth them to ſuppoſe they ſee and perceive ſuch things as were never perceived by the ſenſes, nor which the nature of things, nor the order of the world will permit. The power of this faculty of the mind is ſo great in us, that it often bringeth the whole body in ſubjection unto it.

What imagination is.

For it is recorded in hiſtory, that *Alexander* the Great ſitting at Table, and hearing *Timotheus* the Muſician ſing a Martial ſonnet unto his Cythern, that he preſently leaped from the Table, and called for arms; but when again the Muſician mollified his tune, he returned to the Table and ſate down as before. The power of imagination cauſed by muſical harmony was ſo great, that it ſubjected to it the courage of the worlds conqueror, by whoſe various motion, it would now as it were cauſe him to run headlong to arms, and then pacifie and quiet him, and ſo cauſe him to return to his chair and banquetting again. And there was one whoſoever it was, who ſome few years agon ſeeing the Turk dance on a rope on high with both his feet faſtned in a baſin, turned his eyes from ſo dangerous a ſight or ſpectacle, although came of purpoſe to ſee it, and ſtricken with ſuch fear that his body ſhook and heart quaked, for fear leſt that by ſudden falling down headlong he ſhould break his neck. Many looking down from an high and lofty place, are ſo ſtricken with fear, that ſuddenly they fall down headlong, being ſo overcome and bound with the imagination of the danger, that their own ſtrength is not able to ſuſtain them. Therefore it manifeſtly appeareth that God hath dealt moſt graciouſly and lovingly with us, who unto this power of imagination, hath joined another, that is, the faculty or power of reaſon and underſtanding; which diſcerning falſe dangers and perils from true, doth ſuſtain and hold up a man that he may not be overthrown by them.

What Reaſon is: After this, appeareth and approacheth to perform his function, the faculty of Reaſon, being the Prince of all the principal faculties of the ſoul; which bringeth together, compoſeth, joineth and reduceth all the ſimple, and divided forms or images or things into one heap, that by dividing, collecting, and reaſoning it might diſcern and try truth from fallhood.

The functions of Reaſon. This faculty of Underſtanding or Reaſon is ſubject to no faculty or inſtrument of the body, but is free, and penetrateth into every ſecret, intricate and hidden thing with an incredible celerity: by which a man ſeeth what will follow, perceiveth the originals and cauſes of things, is not ignorant of the proceedings of things; he compareth things that are paſt with thoſe that are preſent and to come, decreeing what to follow, and what to avoid. This bridleth and with-holdeth the furious motions of the mind, bridleth the over-haſty motions of the tongue, and admoniſheth the ſpeaker that before the words paſs out of his mouth, he ought with diligence and diſcretion to ponder and conſider the thing whereof he is about to ſpeak.

What memory is. After Reaſon and Judgment followeth Memory, which keeping and conſerving all forms and images that it receiveth of the ſenſes, and which Reaſon ſhall appoint, and as a faithful keeper and conſerver, receiveth all things, and imprinteth and ſealeth them as well by their own virtue and power, as by the impulſion and adherence of thoſe things in the body of the brain, without any impreſſion of the matter; that when occaſion ſerveth, we may bring them forth there-hence as out of a treaſury or ſtore-houſe. For otherwiſe to what purpoſe were it to read, hear, and note ſo many things, unleſs we were able to keep and retain them in mind by the care and cuſtody of the Memory or Brain? Therefore aſſuredly God hath given us this only remedy and preſervative againſt the oblivion and ignorance of things, which although of it ſelf and of its own nature it be of greater efficacy, yet by dayly and often meditation it is trimmed and made more exquiſite and perfect. And hence it was that the Antients termed wiſdom the daughter of memory and experience. Many have ſuppoſed that the manſion or ſeat of the Memory, is in the hinder part, or in the ventricle of the *Cerebellum*, by reaſon that it is apt to receive the forms of things, becauſe of the engrafted drineſs and hardneſs thereof.

Wiſdom the daughter of memory and experience.

CHAP. XII.

Of the natural excrements in general, and eſpecially of thoſe that the child or infant being in the womb excludeth.

What an excrement is. BEfore I declare what excrements the infant excludeth in the womb, and by what paſſages, I think it good to ſpeak of the excrements which all men do naturally void; All that is called an excrement which nature is accuſtomed to ſeparate and caſt out from the laudable and nouriſhing juice. There are many kinds of thoſe excrements.

The excrement of the firſt concoction. The firſt is of the firſt concoction, which is performed in the ſtomach, which being driven down into the inteſtines or guts, is voided by the fundament.

The excrement of the ſecond concoction is triple. The ſecond cometh from the Liver, and it uſually is three-fold, or of three kinds; one cholerick, whereof a great portion is ſent into the bladder of the gall, that by ſweating out there-hence, it might ſtir up the expulſive faculty of the guts to expel and exclude the excrements. The other is like unto whay, which goeth with the blood into the veins, and is as it were a *vehicle* thereto to bring it unto all the parts of the body, and into every capillar vein for to nouriſh the whole body; and after it hath performed that function, it is partly expelled by ſweat, and partly ſent into the bladder and ſo excluded with the urine. The third is the melancholick excrement which being drawn by the milt, the purer and thinner part thereof goeth into nouriſhment of the milt, and after the remnant is partly purged out downwards by the Hemorrhoidal veins, and partly ſent to the orifice of the ſtomach, to ſtimulate and provoke the appetite.

The excrement of the third concoction is triple. The laſt cometh of the laſt concoction which is diſſolved in the habit of the body, and breathed out, partly by inſenſible tranſpiration, is partly conſumed by ſweating, and partly floweth out by the evident and manifeſt paſſages that are proper to every part: as it happeneth in the brain before all other parts; for it doth unload it ſelf of this kind of excrements by the paſſages of the noſe, mouth, ears, eyes, palat-bone and ſutures of the skull.

Therefore if any of theſe excrements be ſtayed altogether, or any longer than it is meet they ſhould, the default is to be amended by diet and medicine. Furthermore there are other ſorts of excrements not natural, of which we have entreated at large in our book of the Peſtilence.

The uſe of the navel-ſtring. When the infant is in the mothers womb, until he is fully and abſolutely formed in all the lineaments of his body, he ſends forth his urine by the paſſages of the navel or *urachus*. But a little before the time of child-birth, the *urachus* is cloſed, and then the man-child voideth his urine by the conduit of the yard, and the woman-child by the neck of the womb. This urine is gathered together and contained in the coat *Chorion* or *Allantoides*, together with the other excrements, that is to ſay, ſweat and ſuch whayiſh ſuperfluities of the menſtrual matter, for the more eaſie bearing up of the floating or ſwimming child.

The ſigns of ſpeedy and eaſie deliverance. But in the time of child-birth, when the infant by kicking breaketh the membranes, thoſe humors run out, which when the midwives perceive, they take it as a certain ſign that the child is at hand. For if the infant come forth together with thoſe waters, the birth is like to be more eaſie, and with better ſucceſs; for the neck of the womb and all the genitals are ſo by their moiſture relaxed and made ſlippery, that by the endeavour and ſtirring of the infant, the birth will be more eaſie, and with better ſucceſs: contrariwiſe, if the infant be not excluded before all theſe humors be wholly flown out and gone, but remaineth as it were in a dry place, preſently through drineſs the neck of the womb and all the genitals will be contracted and drawn together, ſo that the birth of the child will be very difficult and hard, unleſs the neck of the womb, to amend that default, be anointed with oyl or ſome other relaxing liquor.

Moreover

Moreover, when the child is in the womb, he voideth no excrements by the fundament, unleſs it be when at the time of the birth, the proper membranes and receptacles are burſt by the ſtriving of the infant; for he doth not take his meat at the mouth; wherefore the ſtomach is idle then, and doth not execute the office of turning the meats into *chylus*, nor of any other concoction; wherefore nothing can go down from it into the guts. Neither have I ſeldom ſeen infants born without any hole in their fundament, ſo that I have been conſtrained with a knife to cut in ſunder the membrane or tunicle that grew over and ſtopped it. And how can ſuch excrements be engendred, when the child being in the womb, is nouriſhed with the more laudable portion of the menſtrual bloud; therefore the iſſue or child is wont to yield or avoid two kinds or ſorts of excrements, ſo long as he is in the womb, that is to ſay, ſweat and urine, in both which he ſwims; but they are ſeparated by themſelves, by a certain tunicle called *Allantoides*, as it may be ſeen in kids, dogs, ſheep, and other brute beaſts; for as much as in mankind the tunicle *Chorion* and *Allantoides* or *Farciminalis*, be all one membrane. If the woman be great of a man-child, ſhe is more merry, ſtrong and better coloured, all the time of her child-bearing; but if a woman-child, ſhe is ill coloured, becauſe that women are not ſo hot as men.

Children born without a paſſage in their fundament.

Aph. 24. *ſect.* 5.

The males begin to ſtir within three months and a half, but females after: if a woman conceive a male-child, ſhe hath all her right parts ſtronger to every work: wherefore they do begin to ſet forwards their right foot firſt in going, and when they ariſe they lean on the right arm, the right dug will ſooner ſwell and wax hard: the male-child ſtir more in the right ſide than in the left, and the female-children rather in the left than in the right ſide.

Aph. 47. *ſect.* 5.

CHAP. XIII.

With what travail the Child is brought into the world, and of the cauſe of this labour and travail.

WHen the natural prefixed and preſcribed time of child-birth is come, the child being then grown greater, requires a greater quantity of food: which when he cannot receive in ſufficient meaſure by his navel, with great labour and ſtriving he endeavoreth to get forth: therefore then he is moved with a ſtronger violence, and doth break the membranes wherein he is contained. Then the womb, becauſe it is no able to endure ſuch violent motions, nor ſuſtain or hold up the child any longer, by reaſon that the conceptacles of the membranes are broken aſunder, is relaxed, and then the child purſuing the air which he feeleth to enter in at the mouth of the womb, which then is very wide and gaping, is carried with his head downwards, and ſo cometh into the world with great pain both unto it ſelf, and alſo unto his Mother, by reaſon of the tenderneſs of his body, and alſo by reaſon of the nervous neck of his mothers womb, and ſeparation of the bone called *Os Ilium* from the bone called *Os ſacrum*. For unleſs thoſe bones were drawn in ſunder, how could not only twins that cleave faſt together, but alſo one child alone, come forth forth at ſo narrow a paſſage as the neck of the womb is; Not only reaſon, but alſo experience confirmeth it; for I opened the bodies of women preſently after they have died in travail in child-birth, in whom I have found the bones of *Ilium* to be drrawn the bredth of ones finger from *Os ſacrum*: and moreover, in many unto whom I have been called, being in great extremity of difficult and hard travail, I have not only heard, but alſo felt the bones to crackle and make a noiſe, when I laid my hand upon the coccyx or rump, by the violence of the diſtention. Alſo honeſt matrons have declared unto me that they themſelves, a few days before the birth, have felt and heard the noiſe of thoſe bones ſeparating themſelves one from another with great pain. Alſo a long time after the birth many do feel great pain and ach about the region of the coccyx and *Os ſacrum*, ſo that when nature is not able to repair the diſſolved continuity of the bones of *Ilium*, they are conſtrained to halt all the days of their life after. But the bones of the ſhare called *Oſſa pubis*, I have never ſeen to be ſeparated, as many do alſo affirm. It is reported that in *Italy* the coccyx or rump in all Maidens is broken that when they come to be married they may bear children with leſſer travail in child-birth; but this is a forged tale, for that bone being broken, is naturally and of its own accord repaired, and joined together again with a *Callus*, whereby the birth of the child will be more difficult and hard.

Why the infant is born ſometimes with his head forwards.

In the time of child-birth. the bones of *Ilium* and *Os ſacrum* are drawn and extended one from another.

An Italian fable.

CHAP. XIV.

Of the ſituation of the infant in the womb.

REaſon cannot ſhew the certain ſituation of the infant in the womb, for I have found it altogether uncertain, variable and diverſe both in living and dead women: in the dead by opening their bodies preſently after they were dead; and in the living by helping them by the induſtry of my hand, when they have been in danger of periſhing by travail of child-birth: for by putting my hand into the womb, I have felt the infant coming forth, ſometimes with his feet forward, and ſometime with his hands and feet turned backwards, and ſometimes forwards, as the figure following plainly deſcribeth.

The ſituation of the infant in the womb is diverſe.

I have often found them coming forth with their knees forwards, and ſometimes with one of the feet, and ſometimes with their belly forwards, their hands and feet being lifted upwards, as the former figure ſheweth at large.

Sometimes I have found the Infant coming with his feet downwards ſtriding awide, and ſometimes headlong, ſtretching one of his arms downward out at length and that was an Hermaphrodite, as this figure plainly declareth.

One time I obſerved in the birth of twins that the one came with his head forwards, and the other with his feet, according as here I have thought good to deſcribe them.

In the bodies of women that died in travail of child I have ſometimes found children no bigger than if they had been but four moneths in the womb, ſituated in a round compaſs like a hoop, with their head bowed down to their knees, with both their hands under the knees, and their heels cloſe to their buttocks. And moreover, I proteſt before God that I found a child being yet alive in the body of his mother (whom I opened ſo ſoon as ſhe was dead) lying all along ſtretched out, with his face upwards, and the palms of his hands joined together, as if he was at prayer.

CHAP. XV.

Which is the legitimate and natural, and which the illegitimate or unnatural time of child-birth.

Mankind hath no certain time of bringing forth young.

TO all living creatures, except Man, the time of conception and bringing forth their young is certain and definite; but the iſſue of Man cometh into the world, ſometimes in the ſeventh, ſometimes in the eighth, and ſometimes which is moſt frequent, in the ninth month; ſometimes in the tenth month; yea ſometimes in the beginning of the eleventh month. *Maſſurius* reports that *Lucius Papyrius* the Pretor, the ſecond heir commencing a ſuit, gave the poſſeſſion of the goods away from him, ſeeing the Mother of the Child affirmed that ſhe went thirteen months therewith, being there is no certain definite time of Child-birth. The child that is born in the ſixth month, cannot be long lived, becauſe at that time all his body or members are not perfectly finiſhed, or abſolutely formed. In the ſeventh month it is proved by reaſon and experience that the infant may be long lived. But in the eighth month it is ſeldom or never long lived: the reaſon thereof is, as the Aſtronomers ſuppoſe, becauſe at that time Saturn ruleth, whoſe coldneſs and drineſs is contrary to the original of life: but yet the phyſical reaſon is more true; for the Phyſicians ſay that the child in the womb doth oft-times in the ſeventh month ſtrive to be ſet at liberty from the incloſure of the womb, and therefore it contendeth and laboureth greatly, and ſo with labouring and ſtriving it becometh weak, that all the time of the eighth month it cannot recover his ſtrength again, whereby it may renew his accuſtomed uſe of ſtriving, and that ſome by ſuch labouring and ſtriving hurt themſelves, and ſo die. Yet ſome ſtrong and luſty women are thought to bring forth their children, being lively and ſtrong, on the eighth month, as *Ariſtotle* teſtifieth of the *Egyptians*, the Poets of the inhabitants of the Iſle of *Naxus*, and many of the *Spaniards*. Furthermore I cannot ſufficiently marvel, that the womb, which all the time of child-bearing is ſo cloſed together, that one can ſcarce

Why the child is ſcarce alive in the eighth month.

Lib. 4. de hiſt. anim. cap. 7.

put

put a probe into it, unleſs it be by ſuperfœtation, or when it is open for a ſhort time to purge it ſelf, that preſently before the time of child-birth, it ſhould gape and wax ſo wide, that the infant may paſs through it, and preſently after it cloſe up again as if it had never been opened. But becauſe that the travail of the firſt time of child-birth is wont to be very difficult and grievous, I think it not unmeet that all women, a little before the time of their firſt travail, anoint and relax their privy parts with the unguent here deſcribed. ℞. *ſper. ceti,* ℥ij. *ol. amygd. dul.* ℥iv. *ceræ alb. & medul. cervin.* ℥iij. *axung. anſ. & gallin. an.* ℥j. *tereb. venet.* ℥ij. make thereof an ointment to anoint the thighs, ſhare, privy parts and genitals. Furthermore, it ſhall not be unprofitable, to make a truſs or girdle of moſt thin and gentle dog-skin, which being alſo anointed with the ſame unguent, may ſerve very neceſſarily for the better carrying of the infant in the womb. Alſo baths that are made of the decoction of mollifying herbs, are alſo very profitable to relax the privy parts a little before the time of the birth. That is ſuppoſed to be a natural and eaſie birth, when the infant cometh forth with his head forwards, preſently following the flux of water; and that is more difficult, when the infant cometh with his feet forwards: all the other ways are moſt difficult. Therefore Midwives are to be admoniſhed that as often as they perceive the child to be coming forth none of thoſe ways, but either with his belly or his back forwards, as it were doubled; or elſe with his hands and feet together, or with his head forwards, and one of his hands ſtretched out, that they ſhould turn it, and draw it out by the feet; for the doing whereof, if they be not ſufficient, let them crave the aſſiſtance and help of ſome expert Chirurgion.

The natural and eaſie child-birth.

CHAP. XVI.

Signs of the birth at hand.

THere will be great pain under the navel, and at the groins, and ſpreading therehence toward the *Vertebræ* of the loins, and then eſpecially when they are drawn back from the *Os ſacrum*, the bones *Ilia* and the *Coccyx* are thruſt outward, the genitals ſwell with pain, and a certain Fever-like ſhaking invades the body, the face waxeth red by reaſon of the endeavour of nature, armed unto the expulſion of the infant. And when theſe ſigns appear, let all things be prepared ready to the child-birth. Therefore firſt of all let the woman that is in travail be placed in her bed conveniently, neither with her face upwards, nor ſitting, but with her back upwards and ſomewhat high, that ſhe may breath at more liberty, and have the more power or ſtrength to labour. Therefore ſhe ought to have her legs wide one from another, and crooked, or her heels ſomewhat bowed up towards her buttocks, ſo that ſhe may lean on a ſtaff that muſt be placed overthwart the bed. There are ſome that do travail in a ſtool or a chair made for the ſame purpoſe: others ſtanding on their feet, and leaning on the poſt or pillar of the bed. But you muſt take diligent heed that you do not exhort or perſwade the woman in travail to ſtrive or labour to expel the birth before the fore-named ſigns thereof do manifeſtly ſhew that it is at hand. For by ſuch labour or pains ſhe might be wearied or ſo weakned, that that when ſhe ſhould ſtrive or labour, ſhe ſhall have no power or ſtrength ſo to do. If all theſe things do fall out well in the child-birth, the buſineſs is to be committed to nature, and to the Midwife. And the woman with child muſt only be admoniſhed that when ſhe feeleth very ſtrong pain, that ſhe preſently therewith ſtrive with moſt ſtrong expreſſion, ſhutting her mouth and noſe if ſhe pleaſe, and at the ſame time let the Midwife with her hands force the infant from above downwards. But if the birth be more difficult and painful, by reaſon that the waters wherein the infant lay are flown out long before, and the womb be dry, this ointment following is to be prepared. ℞. *butyri recentis ſine ſale in aqua artemiſiæ loti,* ℥ij. *mucaginis ficuum, ſemin. lini & althææ, cum aqua ſalinæ extractæ, an.* ℥ß. *olei liliorum,* ℥j. make thereof an ointment, wherewith let the Midwife often anoint the ſecret parts. Alſo this powder following may be prepared. ℞. *Cinnamon. cort. caſſiæ fiſtul. dictamni an.* ℥jß. *ſacch. albi ad pondus omnium:* make thereof a moſt ſubtil and fine powder. Let the woman that is in extremity by reaſon of difficult and painful travail in child-birth, take half an ounce thereof at a time, with a decoction of line-ſeed, or in white wine, for it will cauſe more ſpeedy and eaſie deliverance of the child.

How the woman that travaileth in child-birth muſt be placed in her bed.

An unction to ſupply the defect of the waters that are flowed out too long before the birth.

A powder to cauſe ſpeedy deliverance in child-birth.

Moreover let the Midwife anoint her hands with this ointment following, as often as ſhe putteth them into the neck of the womb, and therewith alſo anoint the parts about it. ℞. *olei ex ſeminibus lini,* ℥jß. *olei de caſtoreo,* ℥ß. *gallinæ moſchatæ,* ℥iij. *ladani* ℥j. make thereof a liniment. Moreover, you may provoke ſneeſing, by putting a little pepper or white hellebore in powder into the noſtrils. Line-ſeed beaten, and given in potion, with the water of Mugwort and Savine, is ſuppoſed to cauſe ſpeedy deliverance. Alſo the medicine following is commended for the ſame purpoſe. ℞. *corticis caſſiæ fiſtul. conquaſſatæ* ℥ij. *cicer. rub.* m ß. *buliant cum vino albo & aqua ſufficienti, ſub finem addendo ſabinæ* ℥ij. *in colaturæ pro doſi adde cinam.* ℥ß. *croci gr.* vj. make thereof a potion, which being taken, let ſneeſing be provoked, as it is above-ſaid, and let her ſhut or cloſe her mouth and noſtrils.

Aph. 35. & 43. *ſect.* 5. &

A potion cauſing ſpeedy deliverance.

Many times it happeneth that the infant cometh into the world out of the womb, having his head covered or wrapped about with a portion of the ſecundine or tunicle wherein it is incloſed, eſpecially, when by the much, ſtrong, and happy ſtriving of the mother, he cometh forth together with the water wherein it lieth in the womb, and then the Midwives propheſie or fore-tell that the child ſhall be happy, becauſe he is born as it were with a hood on his head. But I ſuppoſe that it doth betoken health of body both to the infant and alſo to his mother; for it is a token of eaſie deliverance. For when the birth is difficult and painful, the child never bringeth that membrane out with him, but it remaineth behind in the paſſages of the genitals or ſecret parts, becauſe they are narrow. For even ſo the Snake or Adder when ſhe ſhould caſt her skin thereby to renew her age, creepeth through ſome narrow or ſtrait paſſage. Preſently after birth, the woman ſo delivered muſt take two or three ſpoonfuls

What a woman in travail muſt take preſently after her deliverance.

fulls of the oil of ſweet almonds extracted without fire, and tempered with ſugar. Some will rather uſe the yolks of eggs with ſugar, ſome the wine called Hypocras, others culliſes or gelly: but always divers things are to be uſed, according as the Patient or the woman in child-bed ſhall be grieved, and as the Phyſician ſhall give counſel, both to eaſe and aſſwage the furious torments and pain of the throws, to recover her ſtrength and nouriſh her.

The cauſe of the after-throws.

Throws come preſently after the birth of the child, becauſe that then the veins (nature being wholly converted to expulſion) caſt out the reliques of the menſtrual matter that hath been ſuppreſſed for the ſpace of nine months, into the womb with great violence, which becauſe they are groſs, ſlimy and dreggiſh, cannot come forth without great pain both to the veins from whence they come, and alſo unto the womb whereunto they go: alſo then by the converſion of that portion thereof that remaineth into wind, and by the undiſcreet admiſſion of the air in the time of the child-birth, the womb and all the ſecret parts will ſwell, unleſs it be prevented with ſome digeſting, repelling or mollifying oil, or by artificial rowling of the parts about the belly.

CHAP. XVII.

What is to be done preſently after the child is born.

Why the ſecundine or after-birth muſt be taken away preſently after the birth of the child.

PReſently after the child is born, the Midwife muſt draw away the ſecundine or after-birth, as gently as ſhe can: but if ſhe cannot, let her put her hands into the womb, and ſo draw it out, ſeparating it from the other parts; for otherwiſe if it ſhould continue longer, it would be more difficult to be gotten out, becauſe that preſently after the birth the orifice of the womb is drawn together and cloſed, and then all the ſecundine muſt be taken from the child. Therefore the navel-ſtring muſt be tied with a double thred an inch from the belly. Let not the knot be too hard, leſt that part of the navel-ſtring which is without the knot, ſhould fall away ſooner than it ought, neither too ſlack or looſe, leſt that an exceeding and mortal flux of blood ſhould follow after it is cut off, and leſt that through it (that is to ſay, the navel-ſtring) the cold air ſhould enter into the childs body. When the knot is ſo made, the navel-ſtring muſt be cut in ſunder the bredth of two fingers beneath it with a ſharp knife. Upon the ſection you muſt apply a double linnen cloth dipped in oyl of Roſes, or of ſweet Almonds, to mitigate the pain; for ſo within a few days after, that which is beneath the knot will fall away being deſtitute of life and nouriſhment, by reaſon that the vein and artery are tied ſo cloſe, that no life nor nouriſhment can come unto it: commonly all Midwives do let it lie unto the bare belly of the infant, whereof cometh grievous pain and griping, by reaſon of the coldneſs thereof which dieth by little and little as deſtitute of vital heat. But it were far better to rowl it in ſoft cotten or lint, until it be mortified, and ſo fall away.

The binding of the childs navel-ſtring after the birth.

Thoſe midwives do unadviſedly, who ſo ſoon as the infant is born do preſently tie the navel-ſtring and cut it off, not looking firſt for the avoiding of the ſecundine. When all theſe things are done, the infant muſt be wiped, cleanſed and rubbed from all filth and excrement with oil of Roſes or Myrtles. For thereby the pores of the skin will be better ſhut, and the habit of the body the more ſtrengthened.

There be ſome that waſh infants at that time in warm water and red wine, and afterwards anoint them with the fore-named oils. Others waſh them not in wine alone, but boil therein red Roſes and the leaves of Myrtles, adding thereto a little ſalt; and then uſing this lotion for the ſpace of five or ſix days, they not only waſh away the filth, but alſo reſolve and digeſt, if there be any hard or contuſed place in the infants tender body, by reaſon of the hard travail and labour in child-birth.

The defaults that are commonly in children newly born.

Their toes and fingers muſt be handled, drawn aſunder and bowed, and the joints of the arms and legs muſt be extended and bowed for many days and often; that thereby that portion of the excremental humor that remaineth in the joints, by motion may be heated and reſolved. If there be any default in the members either in conformation, conſtruction or ſociety with thoſe that are adjoining to them, it muſt be corrected or amended with ſpeed. Moreover, you muſt look whether any of the natural paſſages be ſtopped, or covered with a membrane, as it often happeneth. For if any ſuch cover or ſtop the orifices of the ears, noſtrils, mouth, yard or womb, it muſt be cut in ſunder by the Chirurgion, and the paſſage muſt be kept open by putting in of tents, peſſaries or doſels, leſt otherwiſe they ſhould join together again after they are cut. If he have one finger more than he ſhould naturally, if his fingers do cleave cloſe together, like unto the feet of a Gooſe or Duck, if the ligamental membrane that is under the tongue be more ſhort and ſtiffer than it ought, that the infant cannot ſuck, nor in time to come, ſpeak, by reaſon thereof; and if there be any other thing contrary to nature, it muſt be all amended by the induſtry of ſome expert Chirurgion.

The defaults of conformation muſt be ſpeedily amended.

Many times in children newly born, there ſticketh on the inner ſide of their mouth and on their tongue, a certain chalky ſubſtance, both in colour and in conſiſtence; this effect proceeding from the diſtemperature of the mouth, the French-men call it the white Cancer. It will not permit the infant to ſuck, and will ſhortly breed and degenerate into ulcers that will creep into the jaws, and even unto the throat, and unleſs it be cleanſed ſpeedily, will be their death. For remedy whereof, it muſt be cleanſed by Deterſives, as with a linnen cloth bound to a little ſtick, and dipped in a medicine of an indifferent conſiſtence made with oil of ſweet almonds, hony and ſugar. For by rubbing this gently on it, the filth may be mollified, and ſo cleanſed or waſhed away.

Remedies for the Cancer in a childs mouth.

Moreover it will be very meet and convenient to give the infant one ſpoonful of oil of almonds, to make his belly looſe and ſlippery, to aſſwage the roughneſs of the weaſon and gullet, and to diſſolve the tough phlegm, which cauſeth a cough, and ſometimes difficulty of breathing. If the eye-lids cleave together, or if they be joined together, or agglutinated to the coats *cornea* or *adnata*; if the watery tumor called *hydrocephalos* affect the head, then muſt they be cured by the proper remedies formerly preſcribed, againſt each diſeaſe.

Many

Many from their birth have ſpots or marks, which the common people of *France* call *Signes*, that is, marks or ſigns. Some of theſe are plain and equal with the skin, others are raiſed up in little tumors, and like unto warts, ſome have hairs upon them, many times they are ſmooth, black or pale; yet for the moſt part red. When they riſe in the face, they ſpread abroad thereon many times with great deformity. Many think the cauſe thereof to be a certain portion of menſtrual matter cleaving to the ſides of the womb, coming of a freſh flux, if happily a man do yet uſe copulation with the woman, or elſe diſtilling out of the veins into the womb, mixed and concorporated with the ſeeds at that time when they are congealed, infecting this or that part of the iſſue being drawn out of the ſeminal body, with their own colour. Women refer the cauſe thereof unto their longing when they are with child; which may imprint the image of the thing they long for or deſire, in the child or iſſue that is not as yet formed (as the force and power of imagination in humane bodies is very great:) but when the child is formed, no imagination is able to leave the impreſſion of any thing in it, no more than it could cauſe horns to grow on the head of King *Chypus* as he ſlept preſently after he was returned from attentively beholding Bulls fighting together. Some of thoſe ſpots be curable, others not; as thoſe that are great, and thoſe that are on the lips, noſtrils, and eye-lids. But thoſe that are like unto warts, becauſe they are partakers of a certain malign quality and melancholick matter, which may be irritated by endeavouring to cure them, are not to be medled with at all, for being troubled and angered, they ſoon turn into a Cancer (which they call *Noli me tangere*) thoſe that are curable are ſmall, and in ſuch parts as they may be dealt withall without danger. Therefore they muſt be pierced through by the roots with a needle and a thred, and ſo being lifted up by the ends of the thred, they muſt be cut away, and the wound that remaineth muſt be cured according to the general method of wounds.

An old fable of King *Chypus*.

Which uncurable.

Which and how they are curable.

There are ſome that ſuppoſe the red ſpots that are raiſed up into little knobs and bunches, may be waſhed away and conſumed by rubbing and anointing them often with menſtrual bloud, or the bloud of the ſecundine or after-birth. Thoſe that are hairy and ſomewhat raiſed up like unto a *Want* or Mouſe, muſt be pierced through the roots in three or four places, and ſtraitly bound, ſo that at length being deſtitute of life and nutriment, they may fall away: after they are faln away, the ulcer that remaineth muſt be cured as other ulcers are. If thereby any ſuperfluous fleſh remain, it muſt be taken away by applying *Ægyptiacum*, or the powder of Mercury, and ſuch like: but if it be doubted that it cometh from the root of the tumor that may haply remain, it muſt be burned away by the root with oyl of vitriol or *aqua fortis*.

There is alſo another kind or ſort of ſpots, of a livid or violet colour, coming eſpecially in the face about the lips, with a ſoft, ſlack, lax, thin, and unpainful tumor, and the veins as if they were varicous round about it. This kind of tumor groweth greater when it ariſeth on children that are wayward and crying, and in men of riper years that are cholerick and angry, and then it will be of a diverſe colour, like unto a lappet and flap of fleſh that hangeth over the Turky-cocks bill. When they have done crying, or ceaſed their anger, the tumor will return to his own natural colour again. But you muſt not attempt to cure it in people that are of theſe conditions.

CHAP. XVIII.

How to pull away the ſecundine or after-birth.

I Suppoſe that they are called ſecundines, becauſe they do give the woman that is with child the ſecond time, as it were a ſecond birth; for if there be ſeveral children in the womb at once, and of different ſexes, they then have every one their ſeveral ſecundines, which thing is very neceſſary to be known by all Midwives. For they do many times remain behind in the womb when the child is born, either by reaſon of the weakneſs of the woman in travail, which by contending and labouring for the birth of the child, hath ſpent all her ſtrength: or elſe by a tumor riſing ſuddenly in the neck of the womb, by reaſon of the long and difficult birth, and the cold air unadviſedly permitted to ſtrike into the orifice of the womb. For ſo the liberties of the ways or paſſages are ſtopped and made more narrow, ſo that nothing can come forth: or elſe becauſe they are doubled and folded in the womb, and the waters gone out from them with the infant, ſo that they remain as it were in a dry place: or elſe becauſe they yet ſtick in the womb by the knots of the veins and arteries, which commonly happeneth in thoſe that are delivered before their time. For even as apples which are not ripe, cannot be pulled from the tree but by violence: but when they are ripe, they will fall off of their own accord: ſo the ſecundine before the natural time of the birth can hardly be pulled away but by violence; but at the prefixed natural time of the birth it may eaſily be drawn away.

Why it is called the ſecundine.

The cauſes of the ſtaying of the ſecundines

Many and grievous accidents follow the ſtaying of the ſecundine; as ſuffocation of the womb, often ſwounding, by reaſon that groſs vapors ariſe from the putrefaction unto the midriff, heart and brain, therefore they muſt be pulled away with ſpeed from the womb, gently handling the navel, if it may be ſo poſſibly done. But if it cannot be done ſo, the woman muſt be placed as ſhe was wont when that the child will not come forth naturally, but muſt be drawn forth by art. Therefore the midwife having her hand anointed with oil, muſt put it gently into the womb, and finding out the navel-ſtring, muſt follow it until it come unto the ſecundine, and if it do as yet cleave to the womb by the Cotyledons, ſhe muſt ſhake and move it gently up and down, that ſo when it is ſhaken and looſed, ſhe may draw it out gently; but if it ſhould be drawn with violence, it were to be feared leſt that the womb ſhould alſo follow: for by violent attraction ſome of the veſſels, and alſo ſome of the nervous ligaments, whereby the womb is faſtned on each ſide may be rent, whereof followeth the corruption of blood ſhed out of the veſſels, and thence cometh inflammation, an abſceſs or a mortal gangrene. Neither is there leſs danger of a convulſion by reaſon of the breaking of the nervous bodies, neither

Accidents that follow the ſtaying of the ſecundines.

The manner of drawing out the ſecundines that remain after the birth.

The cauſe of the falling down of the womb.

neither is there any leſs danger of the falling down of the womb. If that there be any knots or clods of bloud remaining together with the ſecundine, the Midwife muſt draw them out one by one, ſo that not any may be left behind.

The accidents that come of the violent pulling of the womb, together with the ſecundine.

Some women have voided their ſecundine, when it could not be drawn forth by any means, long after the birth of the child, by the neck of their womb, piece-meal, rotten and corrupted, with many grievous and painful accidents. Alſo it ſhall be very requiſite to provoke the endeavour of the expulſive faculty by ſternutatories, aromatick fomentations of the neck of the womb, by mollifying injections: and contrariwiſe, by applying ſuch things to the noſtrils as yield a rank ſavor or ſmell, with a potion made of mug-wort and bay-berries taken in hony and wine mixed together, or with half a dram of the powder of ſavin, or with the hair of a womans head, burnt and beaten to powder, and given to drink; and to conclude, with all things that provoke the terms or courſes.

CHAP. XIX.

What things muſt be given to the infant by the mouth, before he be permitted to ſuck the teat or dug.

To draw flegm from the childs mouth.

IT will be very profitable to rub all the inner ſide of the childs mouth and palat gently with treacle and hony, or the oil of ſweet almonds extracted with fire, and if you can, to cauſe it to ſwallow ſome of thoſe things: for thereby much flegmatick moiſture will be drawn from the mouth, and alſo will be moved or provoked to be vomited up from the ſtomach; for if theſe excremental humors ſhall be mixed with the milk that is ſucked, they would corrupt it, and then the vapors that ariſe from the corrupted milk unto the brain would infer moſt pernicious accidents. And you may know that there are many excremental things in the ſtomach and guts of children by this, becauſe that ſo ſoon as they come into the world, and often before they ſuck milk or take any other thing, they void downwards many excrements diverſly coloured, as yellow, green and black. Therefore many, that they may ſpeedily evacuate the matter that cauſeth the fretting of the guts, do not only miniſter thoſe things fore-named, but alſo ſome laxative ſyrup, as that that is made of damask-Roſes. But before the infant be put to ſuck the mother, it is fitting to preſs ſome milk out of her breſt into its mouth, ſo that ſo the fibres of the ſtomach may by little and little accuſtom themſelves to draw in the milk.

Milk ſoon corrupted in a flegmatick ſtomach.

CHAP. XX.

That mothers ought to nurſe or give ſuck unto their own children.

The mothers milk is moſt familiar for the child.

THat all mothers would nurſe their own children were greatly to be wiſhed; for the Mothers milk is far more familiar nouriſhment for the infant than that of any Nurſe: for it is nothing elſe but the ſame blood made white in the dugs, wherewith before it was nouriſhed in the womb. For the mother ought not to give the child ſuck for the ſpace of a few days after the birth, but firſt to expect the perfect expurgation and avoiding of the excremental humors. And in the mean time let her cauſe her breſts to be ſucked of another, or many other children, or of ſome wholſome or ſober maid, whereby the milk may be drawn by little and little unto her breſts, and alſo by little and little purified.

For a certain ſpace after the birth, the milk will be troubled, and the humors of the body moved: ſo that by long ſtaying in the dugs, it will ſeem to degenerate from its natural goodneſs as the groſneſs of it is ſomewhat congealed, the manifeſt heat in touching, and the yellow colour thereof teſtifieth evidently. Therefore it is neceſſary that others ſhould come in place thereof when it is ſucked out, wherewith the infant may be nouriſhed. But if the mother or the Nurſe chance to take any diſeaſe, as a Feaver, Scouring, or any ſuch like, let her give the child to another to give it ſuck, leſt that the child chance to take the Nurſes diſeaſes. And moreover, mothers ought to nurſe their own children, becauſe for the moſt part they are far more vigilant and careful in bringing up and attending their children than hired and mercenary Nurſes, which do not ſo much regard the infant, as the gain they ſhall have by the keeping of it, for the moſt part. Thoſe that do not nurſe their own children, cannot rightly be termed mothers: for they do not abſolutely perform the duty of a mother unto the child, as *Marcus Aurelius* the Roman Emperor was wont to ſay. For it is a certain unnatural, imperfect and half kind of mothers duty, to bear a child, and preſently to abandon or put it away as if it were forſaken: to nouriſh and feed a thing in their womb (which they neither know nor ſee) with their own bloud, and then not to nouriſh it when they ſee it in the world alive, a creature or reaſonable ſoul, now requiring the help and ſuſtentation of the mother.

The diſeaſe of the Nurſe is participated unto the child.

Gal. lib. 12. *cap.*

CHAP. XXI.

Of the choice of Nurſes.

MAny husbands take ſuch pity on their tender wives, that they provide Nurſes for their children, that unto the pains that they have ſuſtained in bearing them, they may not alſo add the trouble of nurſing them: wherefore ſuch a Nurſe muſt be choſen which hath had two or three children. For the dugs which have been already ſucked and accuſtomed to be filled, have the veins and arteries more large and capable to receive the more milk. In the choice of a Nurſe there is ten things to be conſidered very diligently, as her age, the habit of her body, her behaviour,

the

the condition of her milk, the form not only of her dugs or breasts, but also of her teats or nipples, the time of her child-birth, the sex of her last infant or child, that she be not with child, that she be sound and in perfect health. As concerning her age; she ought not to be under twenty five years, nor above thirty five: the time that is between is the time of strength, more temperate and more wholsome and healthy, and less abounding with excremental humors. And because her body doth not then grow or increase, she must of necessity have the more abundance of blood. After thirty five years in many the menstrual fluxes do cease, and therefore it is to be supposed that they have the less nutriment for children. The best age of a Nurse.

The Nurse also must be of good habit, or square or well set body, her breast broad, her colour lively, not fat, nor lean, but well made, her flesh not soft and tender, but thick, and hard or strong, whereby she may be the more able to endure watching and taking of pains about the child; she must not have a red or freckled face, but brown or somewhat shadowed, or mixed with redness: for truly such women are more hot than those that are red in the face, by reason whereof they must needs concoct and turn their meat the better into blood. For according to the judgment of *Sextus Chæronensis*, as blackish or brown ground is more fertile than the white: even so a brown woman hath more store of milk. You must look well on her head, lest she should have the scurf or running sores; see that her teeth be not foul or rotten, nor her breath stinking, nor no ulcer nor sore about her body, and that she be not born of gouty or leprous Parents. The best habit of body in a Nurse. *Lib. de infantia.*

She ought to be quick and diligent in keeping the child neat and clean, chaste, sober, merry, always laughing and smiling on her Infant, often singing unto it, and speaking distinctly and plainly, for she is the only Mistress to teach the child to speak. Let her be well manner'd, because the manners of the Nurse are participated unto the Infant together with the milk. For the whelps of dogs, if they do suck Wolves or Lionesses, will become more fierce and cruel than otherwise they would. Contrariwise, the Lions whelps will leave their savageness and fierceness, if that they be brought up and nourished with the milk of any Bitch, or other tame beast. If a Goat give a Lamb suck, the same Lambs wool will be more hard than others; contrariwise, if a sheep give a Kid suck, the same Kids hair will be more soft than another Kids hair. She ought to be sober, and the rather for this cause, because many Nurses being overladen with wine and banquetting, often set their children unto their breasts to suck, and then fall asleep, and so suddenly strangle or choak them Of what behavior the Nurse must be.

She must abstain from copulation: for copulation troubleth and moveth the humors and the bloud, and therefore the milk it self, and it diminisheth the quantity of milk, because it provoketh the menstrual flux, and causeth the milk to have a certain strong and virulent quality, such as we may perceive to breath from them that are incensed with the fervent lust and desire of Venery. And moreover, because that thereby they may happen to be with child, whereof ensueth discommodity both to her own child that is within her body, and also to the Nurse-child: to the Nurse-child, because that the milk that it sucketh will be worse and more depraved that otherwise it would be, by reason that the more laudable bloud after the conception remaineth about the womb, for the nutriment and increasing of the infant in the womb; and the more impure blood goeth into the dugs, which breedeth impure or unclean milk: but to the conceived child, because it will cause it to have scarcity of food; for so much as the sucking child sucketh, so much the child conceived in the womb wanteth. Why the Nurse must abstain from copulation.

Also she ought to have a broad breast, and her dugs indifferently big, not slack or hanging, but of a middle consistence, between soft and hard; for such dugs will concoct the blood into milk the better, because that in firm flesh the heat is more strong and compact. You may by touching try whether the flesh be solid and firm, as also by the dispersing of the veins, easily to be seen by reason of their swelling and blewness, through the dugs, as it were into many streams or little rivulets; for in flesh that is loose and slack, they lie hidden. Those dugs that are of a competent bigness, receive or contain no more milk than is sufficient to nourish the infant. In those dugs that are great and hard, the milk is as it were suffocated, stopped or bound in, so that the child in sucking can scarce draw it out, and moreover, if the dugs be hard, the child putting his mouth to the breast, may strike his nose against it, and so hurt it, whereby he may either refuse to suck, or if he doth proceed to suck, by continual sucking, and placing of his nose on the hard breast, it may become flat, and the nostrils turned upwards, to his great deformity, when he shall come to age. If the teats or nipples of the dugs do stand somewhat low or depressed inwards on the tops of the dugs, the child can hardly take them between its lips, therefore his sucking will be very laborious. If the nipples or teats be very big, they will so fill all his mouth, that he cannot well use his tongue in sucking or in swallowing the milk. What dugs a Nurse ought to have.

We may judg of or know the nature and condition of milk, by the quantity, quality, colour, savor and taste; when the quantity of the milk is so little, that it will not suffice to nourish the infant, it cannot be good and laudable; for it argueth some distemperature either of the whole body, or at least of the dugs, especially a hot and dry distemperature. But when it superaboundeth, and is more than the infant can spend, it exhausteth the juice of the Nurses body, and when it cannot all be drawn out by the infant, it cluttereth, and congealeth or corrupteth in the dugs. Yet I would rather wish it to abound, than to be defective, for the superabounding quantity may be pressed out before the child be set to the breast. What is to be observed in the milk.

That milk that is of a mean consistence between thick and thin, is esteemed to be the best. For it betokeneth the strength and vigor of the faculty that engendreth it in the breasts. Therefore if one drop of the milk be laid on the nail of ones thumb, being first made very clean and fair, if the thumb be not moved, and it run off the nail, it signifieth that it is watery milk: but if it stick to the nail, although the end of the thumb be bowed downwards, it sheweth that it is too gross and thick: but if it remain on the nail so long as you hold it upright, and fall from it when The laudable consistence of the milk.

when you hold it a little aſide or downwards by little and little, it ſheweth it is very good milk. And that which is exquiſitely white, is beſt of all. For the milk is no other thing than bloud made white.

Why the milk ought to be very white.

Therefore, if it be of any other colour, it argueth a default in the bloud: ſo that if it be brown, it betokeneth melancholik bloud; if it be yellow, it ſignifieth cholerick bloud; if it be wan and pale, it betokeneth phlegmatick bloud; if it be ſomewhat red, it argueth the weakneſs of the faculty that engendreth the milk. It ought to be ſweet, fragrant and pleaſant in ſmell; for if it ſtrike into the noſtrils with a certain ſharpneſs, as for the moſt part the milk of women that have red hair and little freckles on their faces doth, it prognoſticates a hot and cholerick nature: if with a certain ſowerneſs, it portendeth a cold and melancholick nature. In taſte it ought to be ſweet and as it were ſugered, for the bitter, ſaltiſh, ſharp, and ſtiptick, is naught. And here I cannot but admire the providence of nature, which hath cauſed the bloud wherewith the child ſhould be nouriſhed to be turned into milk: which unleſs it were ſo, who is he that would not turn his face from, and abhor ſo grievous and terrible a ſpectacle of the childs mouth ſo imbrued and beſmeared with bloud? what mother or Nurſe would not be amazed at every moment with the fear of the blood ſo often ſhed out, or ſucked by the infant for his nouriſhment? Moreover, we ſhould want two helps of ſuſtentation, that is to ſay, Butter and Cheeſe.

Why a woman that hath red hair, or freckles on her face cannot be a good Nurſe.

Neither ought the child to be permitted to ſuck within five or ſix days after it is born, both for the reaſon before alledged, and alſo becauſe he hath need of ſo much time to reſt quiet, and eaſe himſelf after the pains he hath ſuſtained in his birth: in the mean ſeaſon the mother muſt have her breaſts drawn by ſome maid that drinketh no wine, or elſe ſhe may ſuck or draw them her ſelf with an artificial inſtrument which I will deſcribe hereafter.

Why that Nurſe that hath born a man child is to be preferred before another

Why ſhe cannot be a good Nurſe whoſe child was born before the time.

That Nurſe that hath born a man child, is to be preferred before another, becauſe her milk is the better concocted, the heat of the male child doubling the mothers heat. And moreover, the women that are great with child of a male child, are better coloured, and in better ſtrength, and better able to do any thing all the time of their greatneſs, which proveth the ſame: and moreover the blood is more laudable, and the milk better. Furthermore it behoveth the Nurſe to be brought on bed, or to travail at her juſt and prefixed or natural time: for when the child is born before his time of ſome inward cauſe, it argueth that there is ſome default lurking and hidden in the body and humors thereof.

CHAP. XXII.

What diet the Nurſe ought to uſe, and in what ſituation ſhe ought to place the infant in the Cradle.

BOth in eating, drinking, ſleeping, watching, exerciſing and reſting, the Nurſes diet muſt be divers, according as the nature of the child both in habit and temperature ſhall be, as for example, if the child be altogether of a more hot bloud, the Nurſe both in feeding and ordering her ſelf ought to follow a cooling diet. In general let her eat meats of good juice, moderate in quantity and quality, let her live in a pure and clear air, let her abſtain from all ſpices, and all ſalted and ſpiced meats, and all ſharp things, wine, eſpecially that which is not allayed or mixed with water, and carnal copulation with a man; let her avoid all perturbations of the mind, but anger eſpecially; let her uſe moderate exerciſe, unleſs it be the excerciſe of her arms and upper parts, rather than the legs and lower parts, whereby the greater attraction of the blood that muſt be turned into milk, may be made towards the dugs. Let her place her child ſo in the Cradle that his head may be higher than all the body, that ſo the excremental humors may be the better ſent from the brain unto the paſſages that are beneath it. Let her ſwathe it ſo as the neck and all the back bone may be ſtraight and equal. As long as the child ſucketh, and is not fed with ſtronger meat, it is better to lay him alway on his back, than any other way, for the back is as it were the keel in a ſhip, the ground-work and foundation of all the whole body, whereon the infant may ſafely and eaſily reſt. But if he lie on the ſide, it were danger leſt that the bones of the ribs being ſoft and tender, not ſtrong enough, and united with ſlack bands, ſhould bow under the weight of the reſt, and ſo wax crooked, whereby the infant might become crook-backed. But when he beginneth to breed teeth, and to be fed with more ſtrong meat, and alſo the bones and connexions of them begin to wax more firm and hard, he muſt be layed one while on this ſide, another while on that, and now and then alſo on his back. And the more he groweth, the more let him be accuſtomed to lie on his ſides; and as he lieth in the Cradle, let him be turned unto that place whereat the light cometh in, leſt that otherwiſe he might become purblind, for the eye of its own nature is bright and lightſome, and therefore always deſireth the light, and abhorreth darkneſs; for all things are moſt delighted with their like, and ſhun their contraries. Therefore unleſs the light comes directly into the childs face, he turneth the himſelf every way being very ſorrowful, and ſtriveth to turn his head and eyes that he may have the light; and that often turning and rowling of his eyes at length groweth into a cuſtom that cannot be left: and ſo it cometh to paſs that the infant doth either become pur-blind, if he ſet his eyes ſtedfaſtly on one thing, or elſe his eyes do become trembling, always turning and unſtable, if he caſt his eyes on many things that are round about him: which is the reaſon that Nurſes, being taught by experience, cauſe over the head of the child lying in the Cradle, an arch or vault of Wickers covered with cloth to be made, thereby to reſtrain, direct, and eſtabliſh the uncertain and wandering motions of the childs eyes.

Anger greatly hurteth the Nurſe.

The exerciſe of the arms is beſt for the Nurſe.

How the child ſhould be placed in the Cradle.

Why an arch of wickers muſt be made over the childs head lying in the cradle.

Why a ſquint-eyed Nurſe cauſeth the child to be ſquint-eyed.

If the Nurſe be ſquint-eyed, ſhe cannot look upon the child but ſide-ways, whereof it cometh to paſs that the child being moiſt, tender, flexible, and prone to any thing with his body, and ſo likewiſe with his eye, by a long and daily cuſtom unto his Nurſes ſight, doth ſoon take the like

cuſtom

cuſtom to look after that ſort alſo, which afterwards he cannot leave or alter. For thoſe evil things which we learn in our youth, do ſtick firmly by us; but the good qualities are eaſily changed into worſe. In the eyes of thoſe that are ſquint-eyed, thoſe two muſcles which do draw the eyes to the greater or leſſer corner, are chiefly or more frequently moved. Therefore either of theſe being confirmed in their turning aſide by long uſe, as the exerciſe of their proper office increaſeth the ſtrength, ſoon overcomes the contrary or withſtanding muſcles, called the *Antagoniſts*, and brings them into their ſubjection, ſo that, will they, nill they, they bring the eye unto this or that corner as they liſt. So children become left-handed, when they permit their right hand to languiſh with idleneſs and ſluggiſhneſs, and ſtrengthen their left hand with continual uſe and motion to do every action therewithall, and ſo bring by the exerciſe thereof more nutriment unto that part. But if men (as ſome affirm) being of ripe years, and in their full growth, by dayly ſociety and company of thoſe that are lame and halt do alſo halt, not minding ſo to do, but it cometh againſt their wills, and when they think nothing thereof, why ſhould not the like happen in children, whoſe ſoft and tender ſubſtance is as flexible and pliant as wax unto every impreſſion? Moreover, children, as they become lame and crook-backt, ſo do they alſo become ſquint-eyed by the hereditary default of their parents.

How children become left-handed.

CHAP. XXIII.

How to make pap for Children.

PAp is a moſt meet food or meat for children; becauſe they require moiſt nouriſhment; and it muſt be anſwerable in thickneſs to the milk, that ſo it may not be difficult to be concocted or digeſted. For pap hath theſe three conditions, ſo that it be made with wheaten flower, and that not crude, but boiled: let it be put into a new earthen pot or pipkin, and ſo ſet into an oven at the time when bread is ſet thereinto to be baked; and let it remain there until the bread be baked and drawn out: for when it is ſo baked, it is leſs clammy and crude. Thoſe that mix the meal crude with the milk, are conſtrained to abide one of theſe diſcommodities or other, either to give the meal groſs and clammy unto the child, if that the pap be only firſt boiled over the fire in a pipkin or skellet, ſo long as ſhall be neceſſary for the milk; hence come obſtructions in the meſaraick veins, and in the ſmall veins of the liver, fretting and worms in the guts, and the ſtone in the reins. Or elſe they give the child the milk, deſpoiled of its butteriſh and whayiſh portion, and the terreſtrial, and cheeſe-like, or curd-like remaining, if the pap be boiled ſo long as is neceſſary for the meal: for the milk requireth not ſo great, neither can it ſuffer ſo long boiling as the meal. Thoſ ethat do uſe crude meal, and have no hurt by it, are greatly bound to nature for ſo great a benefit. But *Galen* willeth children to be nouriſhed only with the Nurſes milk, ſo long as the Nurſe hath enough to nouriſh and feed it. And truly there are many children that are contented with milk only, and will receive no pap until they are three months old. If the child at any time be coſtive, and cannot void the excrements, let him have a cataplaſm made with one dram of Aloes, of white and black Hellebore, of each fifteen grains, being all incorporated in as much of an Ox gall as is ſufficient, and extended or ſpread on Cotton like unto a *pultis*, as broad as the palm of ones hand, and ſo apply it upon the navel warm: Moreover, this cataplaſm hath alſo virtue to kill the worms in the belly. Many times children have fretting of the guts, that maketh them to cry, which cometh of crudity. This muſt be cured by applying unto the belly ſweaty or moiſt wooll, macerated in oil of Camomil.

Three laudable conditions of pap.

How the meal muſt be prepared to make the pap withall.

Why the meal wherewith the pap muſt be made, muſt firſt be boiled or baked.

Lib. 1. de ſanit. tuend.

A cataplaſm to relax the childs belly.

For the fretting of the guts in children.

If when the childs teeth begin to grow, he chance to bite the nipple of the Nurſes breaſt, there will be an ulcer very contumacious and hard to be cured; becauſe that the ſucking of the child, and the rubbing of the cloths do keep it always raw; it muſt be cured with fomenting it with Alum water, and then preſently after the fomentation putting thereupon a cover of lead, made like unto a hat, as they are here deſcribed, with many holes in the top, whereat both the milk, and alſo the ſanious matter that cometh from the ulcers may go out; for lead it ſelf will cure ulcers.

For the ulcers of the nipples or teats.

The figure of leaden Nipples to be put upon the Nipple or Teat of the Nurſe, when it is ulcerated.

Children may be cauſed to ceaſe their crying four manner of ways, that is to ſay, by giving them the teat, by rocking them in a cradle, by ſinging unto them, and by changing the cloaths and ſwathes wherein they are wrapped. They muſt not be rocked too violently in the cradle, leſt that the milk that is ſucked ſhould be corrupted by the too violent motion, by reaſon whereof they muſt not be handled violently any other way, and not altogether prohibited, or not ſuffered to cry. For by crying the breaſt and lungs are dilated, and made bigger and wider; the natural parts the ſtronger, and the brain, noſtrils, the eyes and mouth are purged, by the tears and filth that come from the eyes and noſtrils. But they muſt not be permitted to cry long or fiercely, for fear of breaking the production of the *Peritonæum*, and thereby cauſing the falling down of the guts into the cod, which rupture is called of the Greeks *Enterocele*; or of the caul, which the Greeks call *Epiplocele*.

What moderate crying worketh in the infant.

What immoderate crying cauſeth.

CHAP. XXIV.

Of the weaning of Children.

When children muſt be weaned.

Many are weaned in the eighteenth month, ſome in the twentieth; but all or the moſt part in the ſecond year: for then their teeth appear, by whoſe preſence nature ſeemeth to require ſome harder meat than milk or pap, wherewith children are delighted, and will feed more earneſtly thereon. But there is no certain time of weaning of children. For the teeth of ſome will appear ſooner, and ſome later; for they are prepared of nature for no other purpoſe than to chaw the meat. If children be weaned before their teeth appear, and be fed with meat that is ſomewhat hard and ſolid, according to the judgment of *Avicen*, they are incident to many diſeaſes coming through crudity; becauſe the ſtomach is yet but weak, and wanteth that preparation of the meats which is made in the mouth by chawing; which men of ripe years cannot want without offence: when the child is two years old, and the teeth appear, if the child more vehemently deſire harder meats, and doth feed on them with pleaſure and good ſucceſs, he may be ſafely weaned; for it cannot be ſuppoſed that he hath this appetite of hard meats in vain, by the inſtinct of nature. Yet he may not be weaned without ſuch an appetite, if all other things be correſpondent, that is to ſay, his teeth and age; for thoſe things that are eaten without an appetite, cannot profit. But if the child be weak, ſickly, or feeble, he ought not to be weaned. And when the meet time of weaning cometh, the Nurſe muſt now and then uſe him to the teat, whereby he may leave it by little and little, and then let the teat be anointed or rubbed with bitter things, as with Aloes, water of the infuſion of *Colocynthus*, or Worm-wood, or with Muſtard, or Soot ſteeped in water, or ſuch like. Children that are ſcabby in their heads, and over all their bodies, and which void much phlegm at their mouth and noſtrils, and many excrements downwards, are like to be ſtrong and ſound of body; for ſo they are purged of excremental humors: contrariwiſe, thoſe that are clean and fair of body, gather the matter of many diſeaſes in their bodies, which in proceſs of time will break forth and appear. Certainly, by the ſudden falling of ſuch matters into the back-bone many become crook-backt.

Why children muſt not be weaned before their teeth appear.

How children muſt be weaned.

What children are ſtrong and ſound of body

An often cauſe of ſudden crookedneſs.

CHAP. XXV.

By what ſigns it may be known whether the child in the womb be dead or alive.

A moſt certain ſign of the child dead in the womb.

If neither the Chirurgions hand, nor the mother can perceive the infant to move, if the waters be flowed out, and the ſecundine come forth, you may certainly affirm that the infant is dead in the womb, for this is the moſt infallible ſign of all others: for becauſe the child in the womb doth breath but by the artery of the navel, and the breath is received by the *Cotyledon* of the arteries of the womb, it muſt of neceſſity come to paſs that when the ſecundine is ſeparated from the infant, no air nor breath can come unto it. Wherefore ſo often as the ſecundine is excluded before the child, you may take it for a certain token of the death thereof: when the child is dead, it will be more heavy to the mother than it was before when it was alive, becauſe it is now no more ſuſtained by the ſpirits and faculties wherewith before it was governed and ruled, for ſo we ſee dead men to be heavier than thoſe that are alive, and men that are weak through hunger and famine to be heavier than when they are well refreſhed, and alſo when the mother inclines her body any way, the infant falleth that way alſo even as it were a ſtone. The mother is alſo vexed with ſharp pain from the privities even to the navel, with a perpetual deſire of making water, and going to ſtool, becauſe that nature is wholly buſied in the expulſion or avoidance of that which is dead: for that which is alive will expel the dead ſo far as it can from it ſelf, becauſe the one is altogether different from the other; but likeneſs, if any thing, conjoins and unites things together: the genitals are cold in touching, and the mother complaineth that ſhe feeleth a coldneſs in her womb, by reaſon that the heat of the infant is extinguiſhed, wherewith before her heat was doubled: many filthy excrements come from her, and alſo the mothers breath ſtinketh, ſhe ſwoundeth often, all which for the moſt part happen within three days after the death of the child: for the infants body will ſooner corrupt in the mothers womb than it would in the open air, becauſe that, according to the judgment of *Galen*, all hot and moiſt things, being in like manner incloſed in a hot and moiſt place, eſpecially if by reaſon of the thickneſs or ſtraitneſs of the place they cannot receive the air, will ſpeedily corrupt. Now by the riſing up of ſuch vapors from the dead unto the brain and heart, ſuch accidents may ſoon follow, her face will be clean altered, ſeeming livid and ghaſtly, her dugs fall and hang looſe and lank, and her belly will be more hard and ſwollen than it was before. In all bodies ſo putrifying,

When the child is dead in the womb he is more heavy than he was before being alive.

That which is alive will not ſuffer that which is dead.

Lib. de tumorib.

ing, the natural heat vaniſheth away, and in place thereof ſucceedeth a preternatural, by the working whereof the putrified and diſſolved humors are ſtirred up into vapors, and converted into wind, and thoſe vapors, becauſe they poſſeſs and fill more ſpace and room (for Naturaliſts ſay that of one part of water ten parts of air are made) do ſo puff up the putrified body into a greater bigneſs. You may note the ſame thing in bodies that are gangrenate, for they caſt forth many ſharp vapors, yet nevertheleſs they are ſwollen and puffed up.

Why the belly of a woman will be more big when the child is dead within her than it was before when it was alive.

Now ſo ſoon as the Chirurgion ſhall know that the child is dead by all theſe fore-named ſigns, he ſhall with all diligence endeavor to ſave the mother ſo ſpeedily as he can, and if the Phyſicians cannot prevail with potions, baths, fumigations, ſternutatories, vomits, and liniments appointed to expel the infant, let him prepare himſelf to the work following, but firſt let him conſider the ſtrength of the woman, for if he perceive that ſhe be weak and feeble by the ſmalneſs of her pulſe, by her ſmall, ſeldom and cold breathing, and by the altered and death-like colour in her face, by her cold ſweats, and by the coldneſs of the extreme parts, let him abſtain from the work, and only affirm that ſhe will die ſhortly; contrariwiſe, if her ſtrength be yet good, let him with all confidence and induſtry deliver her on this wiſe from the danger of death.

The ſigns of a woman that is weak.

CHAP. XXVI.

Of the Chirurgical extractions of the child from the womb either dead or alive.

THerefore firſt of all the air of the chamber muſt be made temperate, and reduced unto a certain mediocrity, ſo that it may neither be too hot nor too cold. Then ſhe muſt be aptly placed, that is to ſay, overthwart the bed ſide, with her buttocks ſomewhat high, having a hard ſtuffed pillow or boulſter under them, ſo that ſhe may be in a mean figure of ſituation, neither ſitting altogether upright, nor altogether lying along on her back; for ſo ſhe may reſt quietly, and draw her breath with eaſe, neither ſhall the ligaments of the womb be extended ſo as they would if ſhe lay upright on her back, her heels muſt be drawn up cloſe to her buttocks, and there bound with broad and ſoft linnen rowlers. The rowler muſt firſt come about her neck, and then croſs-wiſe over her ſhoulders, and ſo to the feet, and there it muſt croſs again, and ſo be rowled about the legs, thighs, and then it muſt be brought up to the neck again, and there made faſt, ſo that ſhe may not be able to move her ſelf, even as one ſhould be tied when he is to be cut of the ſtone. But that ſhe may not be wearied, or leſt that her body ſhould yield or ſink down as the Chirurgion draweth the body of the infant from her, and ſo hinder the work, let him cauſe her feet to be ſet againſt the ſide of the bed, and then let ſome of the ſtrong ſtanders by hold her faſt by the legs and ſhoulders. Then that the air may not enter into the womb, and that the work may be done with the more decency, her privy parts and thighs muſt be covered with a warm double linnen cloth. Then muſt the Chirurgion, having his nails cloſely pared, and his rings (if he wear any) drawn off his fingers, and his arms naked, bare, and well anointed with oil, gently draw the flaps of the neck of the womb aſunder, and then let him put his hand gently into the mouth of the womb, having firſt made it gentle and ſlippery with much oil; and when his hand is in, let him find out the form and ſituation of the child, whether it be one or two, or whether it be a Mole or not. And when he findeth that he cometh naturally with his head toward the mouth or orifice of the womb, he muſt lift him up gently, and ſo turn him that his feet may come forwards, and when he hath brought his feet forwards, he muſt draw one of them gently out at the neck of the womb, and then he muſt bind it with ſome broad and ſoft or ſilken band a little above the heel with an indifferent ſlack knot, and when he hath ſo bound it, he muſt put it up again into the womb, then he muſt put his hand in again, and find out the other foot, and draw it alſo out of the womb, and when it is out of the womb, let him draw out the other again whereunto he had before tied the one end of the band, and when he hath them both out, let him join them both cloſe together, and ſo by little and little let him draw all the whole body from the womb. All other women or Midwives may help the endeavour of the Chirurgion, by preſſing the patients belly with their hands downwards as the infant goeth out: and the woman her ſelf by holding her breath, and cloſing her mouth and noſtrils, and by driving her breath downwards with great violence, may very much help the expulſion. I wiſh him to put back the foot into the womb again after he hath tied it, becauſe if that he ſhould permit it to remain in the neck of the womb, it would hinder the entrance of his hand when he putteth it in to draw out the other. But if there be two children in the womb at once, let the Chirurgion take heed leſt that he take not of either of them a leg: for by drawing them ſo, he ſhall profit nothing at all, and yet exceedingly hurt the woman. Therefore that he may not be ſo deceived, when he hath drawn out one foot and tied it, and put it up again, let him with his hand follow the band wherewithall the foot is tied, and ſo go unto the foot, and then to the groin of the child, and then from thence he may ſoon find out the other foot of the ſame child: for if it ſhould happen otherwiſe, he might draw the legs and the thighs out: but it would come no further, neither is it meet that he ſhould come out with his arms along by his ſides, or be drawn out on that ſort, but one of his arms muſt be ſtretched out above his head, and the other down by his ſide; for otherwiſe the orifice of the womb, when it were delivered of ſuch a groſs trunk, as it would be when his body ſhould be drawn out with his arms along by his ſides, would ſo ſhrink and draw it ſelf when the body ſhould come unto the neck, only by the accord of nature requiring union, that it would ſtrangle and kill the infant ſo that it cannot be drawn therehence unleſs it be with a hook put under, or faſtned under his chin, in his mouth, or in the hollowneſs of his eye. But if the infant lieth as if he would come with his hands forwards, or if his hands be forth already, ſo that it may ſeem he may be drawn forth eaſily that way, yet it muſt not be ſo done; for ſo his head would double backwards over his ſhoulders, to the great danger of his

After what ſort the woman in travail muſt be placed when the child being dead in her womb muſt be drawn out.

How ſhe muſt be bound.

How the Chirurgion ought to prepare himſelf and his patient to the drawing out of the child from the womb.

How the infant that is dead in the womb muſt be turned, bound and drawn out.

A caution to avoid ſtrangling of the infant in drawing out the body.

Why the child muſt not be drawn out with his hands forwards.

An hiſtory.

his mother. Once I was called unto the birth of an infant, whom the Midwives had aſſaied to draw out by the arm, ſo that the arm had been ſo long forth that it was gangrenate, whereby the child died; I told them preſently that his arm muſt be put in again, and he muſt be turned otherwiſe. But when it could not be put back by reaſon of the great ſwelling thereof, and alſo of the mothers genitals, I determined to cut it off with an inciſion knife, cutting the muſcles as near as I could to the ſhoulder, yet drawing the fleſh upwards, that when I had taken off the bone with a pair of cutting pincers, it might come down again to cover the ſhivered end of the bone, leſt otherwiſe when it were thruſt in again into the womb, it might hurt the mother. Which being done, I turned him with his feet forwards, and drew him out as is before ſaid. But if the tumor either naturally or by ſome accident, that is to ſay, by putrefaction, which may perchance come, be ſo great that he cannot be turned according to the Surgeons intention, nor be drawn out according as he lieth, the tumor muſt be diminiſhed, and then he muſt be drawn out as is aforeſaid, and that muſt be done at once. As for example, if the dead infant appear at the orifice of the womb, which our Midwives call the Garland, when it gapeth, is open and dilated, but yet his head being more great and puffed up with wind ſo that it cannot come forth, as cauſed to be ſo through that diſeaſe which the Greeks call *Mucrophiſocephalos*, the Surgeon muſt faſten a hook under his chin, or in his mouth, or elſe in the hole of his eye, or elſe, which is better and more expedient, in the hinder part of his head. For when the ſcull is ſo opened, there will be a paſſage whereat the wind may paſs out, and ſo when the tumor falleth and decreaſeth, let him draw the infant out by little and little; but not raſhly, leſt he ſhould break that whereon he hath taken hold: the figure of thoſe hooks is thus.

To diminiſh the wind wherewith the infant being dead in the womb, ſwelleth and is puffed up that he cannot be gotten out of the womb.

The form of Hooks for drawing out the infant that is dead in the womb.



But if the breaſt be troubled with like fault, the hooks muſt be faſtned about the channel-bone: if there be a Dropſie or Tympany in the belly, the hooks muſt be faſtned either in the ſhort ribs, that is to ſay, in the muſcles that are between the ribs, or eſpecially, if the diſeaſe do alſo deſcend into the feet, about the bones that are above the groin; or elſe putting the crooked knife here pictured into the womb with his left hand, let him make inciſion in the childs belly, and ſo get out all his entrails by the inciſion: for when he is ſo bowelled, all the water that cauſed the Dropſie will out. But the Surgeon muſt do none of all theſe things but when the child is dead, and the woman that travelleth in ſuch danger that ſhe cannot handſomely be holpen.

How the head of the infant if it remain in the womb ſeparated from the body, may be drawn out.

But if by any means it happeneth, that all the infants members be cut away by little and little and that the head onely remaineth behind in the womb, which I have ſometimes againſt my will, and with great ſorrow ſeen; then the left hand, being anointed with oil of Lillies, or freſh Butter, muſt be put into the womb, wherewith the Surgeon muſt find out the mouth, putting his finger into it; then with his right hand he muſt put up the hook (according to the direction of the left hand) gently, and by little and little, and ſo faſten it in the mouth, eye, or under the chin; and when he hath firmly fixed or faſtened it, he muſt therewith draw out the head by little and little, for fear of looſning or breaking the part whereon he hath hold. Inſtead of this Hook, you may uſe the inſtruments that are here deſcribed, which therefore I have taken out of the Surgery of *Francis Dalechamps*; for they are ſo made, that they may eaſily take hold of a ſpherical and round body with the branches, as with fingers.

Why the head being alone in the womb, is more difficult to be got out.

But it is not very eaſie to take hold on the head when it remaineth alone in the womb, by reaſon of the roundneſs thereof, for it will ſlip and ſlide up and down, unleſs the belly be preſſed down, and on both ſides, thereby to hold it unto the inſtrument, that it may with more facility take hold thereon.

Gryphon's

Gryphon's Talons, *that is to ſay, Inſtruments made to draw out the head of a dead infant that is ſeperated in the womb from the reſt of the body.*



CHAP. XXVII.

What muſt be done unto the woman in travail preſently after her deliverance.

THere is nothing ſo great an enemy to a woman in travail, eſpecially to her whoſe child is drawn away by violence, as cold: wherefore with all care and diligence ſhe muſt be kept and defended from cold. For after the birth, her body being void and empty, doth eaſily receive the air that will enter into any thing that's empty, and hence ſhe waxeth cold, her womb is diſtended and puffed up, and the orifice, or the veſſels thereof are ſhut and cloſed, whereof cometh ſuppreſſion of the after-birth, or other after-purgations. And thereof cometh many grievous accidents, as hyſterical ſuffocation, painful fretting of the guts, fevers, and other mortal diſeaſes.

Cold an enemy to women in travail.

What accidents follow the taking of cold in a woman that is delivered of child.

What woman ſoever will avoid that diſcommodity, let her hold her legs or thighs acroſs; for in ſo doing, thoſe parts that were ſeparated will be joined and cloſe together again. Let her belly be alſo bound or rowled with a ligature of an indifferent bredth or length, which may keep the cold air from the womb, and alſo preſs the blood out that is contained in all the ſubſtance thereof. Then give her ſome Capon-broth or Caudle, with Saffron, or with the powder called *Pulvis ducis*, or elſe bread toaſted and dipped in wine wherein ſpice is brewed, for to reſtore her ſtrength and to keep away the fretting of the guts. When the ſecundine is drawn out, and is yet hot from the womb, it muſt be laid warm unto the region of the womb, eſpecially in the winter, but in the Summer the hot skin of a weather newly killed muſt be laid unto the whole belly, and unto the region of the loins. But then the curtains muſt be kept drawn, and all the windows and doors of the chamber muſt be kept ſhut with all diligence, that no cold air may come unto the woman that travaileth, but that ſhe may lie and take her reſt quietly. The Weathers skin muſt be taken away after that it hath lain five or ſix hours, and then all the region of her belly muſt be anointed with the ointment following.

Secundines muſt be laid to the region of the womb whilſt they be warm.

℞. *ſpermatis Ceti*, ℥ij. *olei amygdal. dulcium & hypericon. an.* ℥iß. *ſevi hircini*, ℥j. *olei myrtillor.* ℥j. *ceræ novæ quantum ſufficit*; make thereof an ointment, wherewith let her be anointed twice in the day: let a plaiſter of *Galbanum* be applied to the navel, in the midſt whereof put ſome few grains of Civet or Muſk, ſo that the ſmell of the plaiſter may not ſtrike up into her noſtrils. Then let this medicine following be applied, commonly called *Tela Gualterin.* ℞. *ceræ novæ*, ℥iv. *ſpermatis Ceti*, ℥iß. *terebinth. Venetæ in aqua roſacea lotæ*, ℥ij. *olei amygdal. dulcium & hypericonic. an.* ℥j. *olei maſtich. & myrtini, an.* ℥ß. *axungiæ cervi*, ℥iß. melt them altogether, and when they are melted, take it from the fire, and then dip a linnen cloth therein, as big as may ſerve to fit the region of the belly, whereunto it is to be applied. Theſe remedies will keep the external region of the belly from wrinkling.

Unguents for the woman in travail that the region of the belly may not be wrinkled. The medicine called *Tela Gualterina.*

But of all other, the medicine following excelleth. ℞. *limacum rub.* ℔j. *florum anthos quart.* iv. let them be cut all in ſmall pieces, and put into an earthen pot well nealed with lead, and cloſe ſtopped, then let it be ſet in the dung of horſes for the ſpace of forty days, and then be preſſed or ſtrained, and let the liquor that is ſtrained out be kept in a glaſs well covered, and ſet in the Sun for the ſpace of three or four days, and therewith anoint the belly of the woman that lieth in child-bed. If ſhe be greatly tormented with throws, let the powder following be given unto her. ℞. *aniſi conditi* ℥iij. *nucis moſchat. cornu cervi uſt. an.* ℥jß. *nucleorum dactylor.* ℥iij. *ligni aloes & cinnamomi, an.* ℥ij. make thereof a moſt ſubtil powder, let her take ℥j. thereof at once with white wine warm. Or, ℞. *rad. conſolidæ major.* ℥iß. *nucleorum perſicorum, nucis moſchat. an.* ℈ij. *carab.* ℈ß. *ambræ græcæ gra.* iv. make thereof a powder, let her take one dram thereof at a time with white wine, or if ſhe have a feaver, with the broth of a Capon. Let there be hot bags applied to the genitals, belly and reins; theſe bags muſt be made of millet and oats fried in a frying pan with a little white wine.

A powder for the fretting of the guts.

What muſt be done when the groin is torn in child-birth.

But if through the violence of the extraction the genital parts be torn, as antient writers affirm it hath come to paſs, ſo that the two holes, as the two holes of the privy parts and of the fundament have been torn into one, then that which is rent muſt be ſtitched up, and the wound cured according to art. Which is a moſt unfortunate chance for the woman afterwards, for when ſhe ſhall travail again, ſhe cannot have her genital parts to extend and draw themſelves in again by reaſon of the ſcar. So that then it will be needful that the Chirurgion ſhall again open the place that was cicatrized, for otherwiſe ſhe ſhall never be delivered, although ſhe ſtrive and contend never ſo much. I have done the like cure in two women that dwelt in *Paris*.

CHAP. XXVIII.

What cure muſt be uſed to the Dugs and Teats of thoſe that are brought to bed.

To drive the milk downward.

IF great ſtore and abundance of milk be in the breaſt, and the woman be not willing to nurſe her own child, they muſt be anointed with the unguent following to repel the milk, and cauſe it to be expelled through the womb. ℞. *olei roſ. myrtini an.* ℥iij. *aceti roſat.* ℥j. incorporate them together, and therewith anointing beſprinkle them with the powder of Myrtles, and then apply the plaiſter following. ℞. *pulv. maſtichini, nucis moſchat. an.* ʒij. *nucis cupreſſi* ℥iij. *balauſt. myrtil. an.* ℥iß. *Ireos, florent.* ℥ß. *olei myrtini* ℥iij. *terebinth. Venetæ* ℥ij. *ceræ novæ quantum ſufficit*, make thereof a ſoft plaiſter.

The leaves of brook-lime, creſſes and box boiled togethe in urine and vinegar, are thought a preſent remedy for this purpoſe, that is to ſay, to draw the milk from the breaſt. And others take the clay that falleth down into the bottom of the trough wherein the grindſtone, whereon ſwords are grownd, turneth, and mix it with oil of roſes, and apply it warm unto the dugs, which in ſhort ſpace, as it is thought, will aſſwage the pain, ſtay the inflammation, and drive the milk out of the dugs. The decoction of ground-Ivy, Peruwincle, Sage, red Roſes, and Roch Allum being prepared in oxycrate, and uſed in the form of a fomentation, is thought to perform the like effect: the like virtue have the lees of red wine, applied to the dugs with vinegar, or the diſtilled water of unripe Pine-apples applied to the breaſts with linnen cloths wet therein, or hemlock beaten and applied with the young and tender leaves of a gourd.

By what reaſon, and which way cupping-glaſſes being faſtned on the groin or above the navel, do draw milk out of the breaſt.

This medicine following is approved by uſe: Take the leaves of Sage, Smallage, Rue, and Chervil, and cut or chop them very ſmall, and incorporate them in vinegar and oil of Roſes, and ſo apply it warm to the breaſt, and renew it thrice a day. In the mean time let Cupping-glaſſes be applied to the inner ſide of the thigh and groin, and alſo above the navel; For this is very effectual to draw the milk out of the breaſts into the womb by the veins whereby the womb communicateth with the breaſts. Moreover, they may let children or little whelps ſuck their breaſts, whereby they may draw out the milk that is fixed faſt in their dugs, inſtead whereof we have invented this inſtrument of glaſs, wherewith, when the broader orifice is faſtned or placed on the breaſt or dug, and the pipe turned upwards towards her mouth, ſhe may ſuck her own breaſts her ſelf.

The form of a little glaſs, which being put on the nipple, the woman may ſuck her own breaſts.

Inſtead of this inſtrument, a viol of glaſs being firſt made warm, and the mouth thereof applied to the nipple or teat, by reaſon of the heat and wideneſs thereof will draw the milk forth into the bottom thereof, as it were by a certain ſucking. The after-purgations being firſt evacuated, which is done for the moſt part within twenty days after the birth, if the woman be not in danger of a feaver, nor have any other accident, let her enter into a bath, made of marjerom, mint, ſage, roſemary, mugwort, agrimony, peny-royal, the flowers of camomil, melilote, dill, being boiled in moſt pure and clear running water. All the day following let another ſuch like bath be prepared, whereunto let theſe things following be added. ℞. *farin. fabarum & aven. an.* ℔ iij. *farin. orobi, lupinor. & gland. an.* ℔j. *aluminis roch.* ℥iv. *ſalis com.* ℔ ij. *gallarum, nucum cupreſſi, an.* ℥iij. *roſar. rub.* m. vi. *caryophil. nucum moſchat. an.* ʒiij. boil them all in common water, then ſew them all in a clean linnen cloth, as it were in a bag, and caſt them therein into the bath wherein Iron red hot hath been extinguiſhed, and let the woman that hath lately travailed ſit down therein ſo long as ſhe pleaſeth and when ſhe cometh out, let her be laid warm in bed, and let her take ſome preſerved Orange-pill, or bread toaſted and dipped in Hippocras, or in wine brewed with ſpices, and then let her ſweat, if the ſweat will come forth of its own accord.

Aſtringent fomentations for the privy parts

On the next day let aſtringent fomentations be applied to the genitals on this wiſe prepared. ℞. *gallar. nucum cupreſſi, corticum granat. an.* ℥j. *roſar. rub.* m.j. *thymi, majoran. an.* m. ß. *aluminis rochæ, ſalis com. an.* ʒij. boil them all together in red wine, and make thereof a decoction for a

fomentation,

fomentation, for the forenamed uſe. The diſtilled liquor following is very excellent and effectual to confirm and to draw in the dugs, or any other looſe parts. ℞. *caryophil. nucis moſchat. nucum cupreſſi an.* ℥i ſ. *maſtich.* ℥ij. *alumin. roch.* ℥i ſ. *glandium & corticis querni. an.* ℔ ß. *roſar. rubr.* m. j. *cort. granat.* ℥ij. *terræ ſigillat.* ℥j. *cornu cervi uſti* ℥ ſ. *myrtillor. ſanguinis dracon. an.* ℥j. *boli armeni.* ℥ij. *ireos florent.* ℥j. *ſumach. berber. Hippuris, an.* m. ſ. *conquaſſentur omnia, & macerentur ſpatio duorum dierum, in* ℔. ß. *aquæ roſarum* ℔ij. *prunorum ſylveſtr. meſpilorum, pomorum quernorum, &* ℔ ß. *aquæ fabrorum, aceti denique fortiſſ.* ℥iv. afterward diſtil it over a gentle fire, and keep the diſtilled liquor for your uſe, wherewith let the parts be fomented twice in a day. And after the fomenta- let woollen cloths or ſtupes of linnen cloth be dipped in the liquor, and then preſſed out and laid to the place. When all theſe things are done and paſt, the woman may again keep company with her husband.

A diſtilled liquor for to draw together the dugs that are looſe and flack.

CHAP. XXIX.

What the cauſes of difficult and painful travail in child-birth are.

THe fault dependeth ſometimes on the mother, and ſometimes on the infant or child within the womb. On the mother, if ſhe be more fat, if ſhe be given to gormandize or great eating, if ſhe be too lean or young, as *Savanarola* thinketh her to be, that is great with child at nine years of age, or unexpert, or more old, or weaker than ſhe ſhould be either by nature or by ſome accident: as by diſeaſes that ſhe hath had a little before the time of child-birth, or with a great flux of bloud. But thoſe that fall in travail before the full and prefixed time are very difficult to deliver, becauſe the fruit is yet unripe, and not ready or eaſie to be delivered. If the neck or orifice of the womb be narrow, either from the firſt conformation, or afterwards by ſome chance, as by an ulcer cicatrized: or more hard and callous, by reaſon that it hath been torn before at the birth of ſome other child, and ſo cicatrized again, ſo that if the cicatrized place be not cut even in the moment of the deliverance, both the child and the mother will be in danger of death; alſo the rude handling of the midwife may hinder the free deliverance of the child. Oftentimes women are letted in travail by ſhamefacedneſs, by reaſon of the preſence of ſome man, or hate to ſome woman there preſent.

The cauſes of the difficult child-birth that are in the woman that travaileth.

The paſſions of the mind hinder the birth.

If the ſecundine be pulled away ſooner than it is neceſſary, it may cauſe a great flux of blood to fill the womb, ſo that then it cannot perform his excluſive faculty, no otherwiſe than the bladder when it is diſtended by reaſon of over-abundance of water that is therein, cannot caſt it forth, ſo that there is a ſtoppage of the urine. But the womb is much rather hindred, or the faculty of child-birth is ſtopped or delayed, if together with the ſtopping of the ſecundine, there be either a Mole or ſome other body contrary to nature in the womb. In the ſecundines of two women whom I delivered of two children that were dead in their bodies, I found a great quantity of ſand like unto that which is found about the banks of rivers, ſo that the gravel or ſand that was in each ſecundine was a full pound in weight.

Alſo the infant may be the occaſion of difficult child-birth, as, if too big, if it come overthwart, if it come with its face upwards, and its buttocks forwards, if it come with its feet and hands both forwards at once, if it be dead and ſwoun by reaſon of corruption, if it be monſtrous, if it have two bodies or two heads, if it be manifold or ſeven-fold, as *Albucraſis* affirmeth he hath ſeen, if there be a mole annexed thereto, if it be very weak, if when the waters are flowed out, it doth not move nor ſtir, or offer it ſelf to come forth. Yet notwithſtanding, it happeneth ſometimes that the fault is neither in the mother nor the child, but in the air, which being cold, doth ſo bind, congeal and make ſtiff the genital parts, that they cannot be relaxed: or, being contrariwiſe too hot, it weakneth the woman that is in travail, by reaſon that it waſteth the ſpirits, wherein all the ſtrength conſiſteth: or in the ignorant or unexpert midwife, who cannot artificially rule and govern the endeavors of the woman in travail.

The cauſes of difficult child-birth that are in the infant.

The external cauſes of difficult child-birth.

The birth is wont to be eaſie, if it be in the due and prefixed natural time, if the child offer himſelf luſtily to come forth with his head forwards preſently after the waters are come forth, and the mother in like manner luſty and ſtrong: thoſe which are wont to be troubled with very difficult child-birth, ought a little before the time of the birth, to go into an half-tub filled with the decoction of mollifying roots and ſeeds, to have their genitals, womb and neck thereof to be anointed with much oil, and the inteſtines that are full and loaded muſt be underburthened of the excrements, and then the expulſive faculty provoked with a ſharp clyſter, and the tumors and ſwelling of the birth concurring therewith, the more eaſie excluſion may be made. But I like it rather better, that the woman in travail ſhould be placed in a chair that hath the back thereof leaning backwards, than in her bed, but the chair muſt have a hole in the bottom, whereby the bones that muſt be dilated in the birth, may have more freedom to cloſe themſelves again.

Which is an eaſie birth.

What cauſeth eaſineſs of child-birth.

CHAP. XXX.

The cauſe of Abortion or untimely birth.

ABortion or untimely birth is one thing, and effluxion another. They call abortion the ſudden excluſion of the child already formed and alive, before the perfect maturity thereof. But that is called effluxion, which is the falling down of ſeeds mixed together and coagulated but for the ſpace of a few days, only in the forms of membranes or tunicles, congealed blood and of an unſhapen or deformed piece of fleſh; the Midwives of our country call it a falſe branch or bud. This effluxion is the cauſe of great pain and moſt bitter and cruel torment to the woman: leaving behind

What Abortion is.

What Effluxion is.

Women are in more pain by reaſon of the effluxion than at the true birth.

behind it weakneſs of body far greater than if the child were born at the due time. The cauſes of abortion or untimely birth, whereof the child is called an abortive, are many, as a great ſcouring, a ſtrangury joined with heat and inflammation, ſharp fretting of the guts, a great and continual cough, exceeding vomiting, vehement labour in running, leaping, and dancing, and by a great fall from on high, carrying of a great burthen, riding on a trotting horſe, or in a Coach, by vehement, often and ardent copulation with men, or by a great blow or ſtroke on the belly. For all theſe and ſuch like vehement and inordinate motions diſſolve the ligaments of the womb, and ſo cauſe abortion and untimely birth.

The cauſes of Abortion.

Girding of the belly may cauſe untimely birth.

Alſo whatſoever preſſeth or girdeth in the mothers belly, and therewith alſo the womb that is within it, as are thoſe Ivory or Whale-bone buſks, which women wear on their bodies, thereby to keep down their bellies; by theſe and ſuch like things the child is letted or hindred from growing to his full ſtrength, ſo that by expreſſion, or as it were by compulſion, he is often forced to come forth before the legitimate and lawful time. Thundering, the noiſe of the ſhooting of great Ordnance, the ſound, and vehement noiſe of the ringing of Bells conſtrain women to fall in travail before their time, eſpecially women that are young, whoſe bodies are ſoft, ſlack and tenderer, than thoſe that be of riper years. Long and great faſting, a great flux of blood, eſpecially when the infant is grown ſomewhat great: but if it be but two months old, the danger is not ſo great, becauſe then he needeth not ſo great quantity of nouriſhment; alſo a long diſeaſe of the mother, which conſumeth the blood, cauſeth the child to come forth being deſtitute of ſtore of nouriſhment before the fit time. Moreover, fulneſs, by reaſon of the eating great ſtore of meats, often maketh or cauſeth untimely birth; becauſe it depraveth the ſtrength, and preſſeth down the child; as likewiſe the uſe of meats that are of an evil juice, which they luſt or long for. But baths becauſe they relax the ligaments of the womb, and hot-houſes, for that the fervent and choaking air is received into the body, provoke the infant to ſtrive to go forth to take the cold air, and ſo cauſe abortion.

How baths and hot houſes cauſe untimely birth.

Hip. aph. 53, & 37. *ſect.* 5.

Hip. aph. 45. *ſect.* 5.

What women ſoever, being indifferently well in their bodies, travail in the ſecond or third month without any manifeſt cauſe, thoſe have the Cotyledons of their womb full of filth and matter, and cannot hold up the infant, by reaſon of the weight thereof, but are broken: Moreover ſudden or continual perturbations of the mind, whether they be through anger or fear, may cauſe women to travail before their time; and are accounted to the cauſes of abortions, for that they cauſe great and vehement trouble in the body. Thoſe women that are like to travail before their time, their dugs will wax little; therefore when a woman is great with child, if her dugs ſuddenly wax ſmall and ſlender, it is a ſign that ſhe will travail before her time; the cauſe of ſuch ſhrinking of the dugs is, that the matter of the milk is drawn back into the womb, by reaſon that the infant wanteth nouriſhment to nouriſh and ſuccor it withall. Which ſcarcity the infant not long abiding, ſtriveth to go forth to ſeek that abroad which he cannot have within; for among the cauſes which do make the infant to come out of the womb, thoſe are moſt uſually named with *Hippocrates*, the neceſſity of a more large nutriment and air.

Hip. aph. 38. *ſect.* 5.

Women are in more pain at the untimely birth than at the due time of birth.

The error of the firſt child-birth continues afterwards.

A plaſter ſtaying the infant in the womb.

Therefore if a woman that is with child have one of her dugs ſmall, if ſhe have two children, ſhe is like to travail of one of them before the full and perfect time: ſo that if the right dug be ſmall, it is a man-child, but if it be the left dug, it is a female. Women are in far more pain when they bring forth their children before the time, than if it were at the full and due time; becauſe that whatſoever is contrary to nature, is troubleſome, painful, and alſo oftentimes dangerous. If there be any error committed at the firſt time of child-birth, it is commonly ſeen that it happeneth always after at each time of child-birth. Therefore, to find out the cauſes of that error, you muſt take the counſel of ſome Phyſician, and after his counſel endeavor to amend the ſame. Truly this plaiſter following being applied to the reins doth confirm the womb, and ſtay the infant therein. ℞. *ladani* ℥ij. *galang.* ℥j. *nucis moſchat. nucis cupreſſi, boli armeni, terræ ſigil. ſanguin. dracon. balauſt. an.* ℥ß. *acatiæ, pſidiorum, hypociſtid. an.* ℥j. *maſtich. myrrhæ, an.* ℥ij. *gummi arabic.* ℥j. *terebinthi Venet.* ℥ij. *picis naval.* ℥iß. *ceræ quantum ſufficit, fiat emplaſt. ſecundum artem.* ſpread it for your uſe upon leather. If the part begin to itch, let the plaiſter be taken away and inſtead thereof uſe *unguent. roſat.* or *refrig. Galen.* or this that followeth. ℞. *olei myrtini, maſtich. cydonior. an.* ℥j. *hypo. boli armen. ſang. dracon. acatiæ, an.* ℥j. *ſant. citrini,* ℥ß. *ceræ quant. ſuf.* make thereof an ointment according unto art. There are women that bear the child in their womb ten or eleven whole months, and ſuch children have their conformation of much quantity of ſeed: wherefore they will be more big, great and ſtrong, and therefore they require more time to come to their perfection and maturity; for thoſe fruits that are great will not be ſo ſoon ripe as thoſe that are ſmall. But children that are ſmall and little of body, do often come to their perfection and maturity in ſeven or nine months: if all other things are correſpondent in greatneſs and bigneſs of body, it happeneth for the moſt part that the woman with child is not delivered before the ninth moneth be done, or at the leaſtwiſe in the ſame moneth. But a male child will be commonly born at the beginning or a little before the beginning of the ſame month, by reaſon of his engrafted heat which cauſeth maturity and ripeneſs. Furthermore, the infant is ſooner come to maturity and perfection in a hot woman than in a cold, for it is the property of heat to ripen.

What children are ten or eleven months in the womb.

A male will be born ſooner than a female.

CHAP. XXXI.

How to preſerve the infant in the womb, when the mother is dead.

IF all the ſigns of death appear in the woman that lieth in travail, and cannot be delivered, there muſt then be a Surgeon ready and at hand, which may open her body ſo ſoon as ſhe is dead, whereby the infant may be preſerved in ſafety; neither can it be ſuppoſed ſufficient if the mothers mouth and privy parts be held open; for the infant being incloſed in his mothers

womb,

womb, and compaſſed with the membranes, cannot take his breath but by contractions and dilatations of the artery of the navel. But when the mother is dead, the lungs do not execute their office and function: therefore they cannot gather in the air that compaſſeth the the body by the mouth or *aſpera arteria* into their own ſubſtance, or into the arteries that are diſperſed throughout the body thereof, by reaſon whereof it cannot ſend it unto the heart by the veiny artery which is called *arteria venalis:* for if the heart want air, there cannot be any in the great artery which is called *arteria aorta*, whoſe function it is to draw it from the heart, as alſo by reaſon thereof it is wanting in the arteries of the womb, which are as it were the little conduits of the great artery, whereinto the air that is brought from the heart is derived, and floweth in unto theſe little ones of all the body, and likewiſe of the womb. Wherefore it muſt of neceſſity follow that the air is wanting to the cotyledons of the ſecundines, to the artery of the infants navel, the iliack arteries alſo, and therefore unto his heart, and ſo unto his body: for the air being drawn by the mothers lungs, is accuſtomed to come to the infant by this continuation of paſſages. Therefore becauſe death maketh all the motions of the mothers body to ceaſe, it is far better to open her body ſo ſoon as ſhe is dead, beginning the inciſion at the cartilage, *Xiphoides*, or blade, and making it in a form ſemicircular, cutting the skin, muſcles and *peritonæum*, not touching the guts: then the womb being lifted up, muſt firſt be cut, leſt that otherwiſe the infant might perchance be touched or hurt with the knife.

Why it is not ſufficient to preſerve life in the child to hold open the mouth and privy parts of the mother ſo ſoon as ſhe is dead, and the child alive in her body.

How the belly of the woman that dieth in travel muſt be cut open to ſave the child.

You ſhall oftentimes find the child unmovable, as though he were dead; but not becauſe he is dead indeed, but by reaſon that he, being deſtitute of the acceſs of the ſpirits by the death of the mother, hath contracted a great weakneſs; yet you may know whether he be dead indeed or not, by handling the artery of the navel; for it will beat and pant if he be alive, otherwiſe not; but if there be any life yet remaining in him, ſhortly after he hath taken in the air, and is recreated with the acceſs thereof, he will move all his members, and alſo all his whole body. In ſo great a weakneſs or debility of the ſtrength of the child, by cutting the navel-ſtring, it muſt rather be laid cloſe to the region of the belly thereof, that thereby the heat (if there be any jot remaining) may be ſtirred up again. But I cannot ſufficiently marvel at the inſolency of thoſe that affirm that they have ſeen women whoſe bellies and womb have been more than once cut, and the infant taken out, when it could no otherwiſe be gotten forth, and yet notwithſtanding alive; which thing there is no man can perſwade me can be done without the death of the mother, by reaſon of the neceſſary greatneſs of the wound that muſt be made in the muſcles of the belly, and ſubſtance of the womb; for the womb of a woman that is great with child, by reaſon that it ſwelleth, and is diſtended with much bloud, muſt needs yield a great flux of blood, which of neceſſity muſt be mortal. And to conclude, when that the wound or inciſion of the womb is cicatrized, it will not permit or ſuffer the womb to be dilated or extended, to receive or bear a new birth. For theſe and ſuch like other cauſes, this kind of cure, as deſperate and dangerous, is not (in mine opinion) to be uſed.

How it may be known whether the infant be alive or no.

CHAP. XXXII.

Of Superfetation.

Superfetation is when a woman doth bear two or more children at one time in her womb, and they be encloſed each in his ſeveral ſecundine: but thoſe that are included in the ſame ſecundine, are ſuppoſed to be conceived at one and the ſame time of copulation, by reaſon of the great and copious abundance of ſeed, and theſe have no number of days between their conception and birth, but all at once. For as preſently after meat the ſtomach which is naturally of a good temper, is contracted or drawn together about the meat, to comprehend it on every ſide, though ſmall in quantity, as it were by both hands, ſo that it cannot rowl neither unto this or that ſide; ſo the womb is drawn together unto the conception about the ſeeds, as ſoon as they are brought into the capacity thereof, and is ſo drawn in unto it on every ſide, that it may come together into one body, not permitting any portion thereof to go into any other region or ſide, ſo that by one time of copulation the ſeed that is mixed together, cannot engender more children than one, which are divided by their ſecundines. And moreover, becauſe there are no ſuch cells in the wombs of women, as are ſuppoſed, or rather known to be in the wombs of beaſts, which therefore bring forth many at one conception or birth. But now if any part of the womans womb doth not apply and adjoin it ſelf cloſely to the conception of the ſeed already received, leſt any thing ſhould be given by nature for no purpoſe, it muſt of neceſſity follow that it muſt be filled with air, which will alter and corrupt the ſeeds; therefore the generation of more than one infant at a time, having every one his ſeveral ſecundine, is on this wiſe. If a woman conceive by copulation with a man as this day, and if that for a few days after the conception, the orifice of the womb be not exactly ſhut, but rather gape a little, and if ſhe do then uſe copulation again, ſo that at both theſe times of copulation there may be an effuſion or perfect mixture of the fertile ſeed in the womb, there will follow a new conception or ſuperfetation. For ſuperfetation is no other than a certain ſecond conception, when the woman already with child, again uſeth copulation with a man, and ſo conceiveth again, according to the judgment of *Hippocrates*. But there may be many cauſes alledged why the womb which did join and cloſe doth open and unlooſe it ſelf again. For there be ſome that ſuppoſe the womb to be open at certain times after the conception, that there may be an iſſue out for certain excremental matters that are contained therein, and therefore that the woman that hath ſo conceived already, and ſhall then uſe copulation with a man again, ſhall alſo conceive again.

What ſuperfetation is.

A womans womb is not diſtinguiſhed into divers cells.

The reaſon of ſuperfetation.

Lib. de ſuperfœtationibus.

Why the womb after the conception of the ſeed, doth many times afterwards open.

Others ſay that the womb of it ſelf, and of its own nature is very deſirous of ſeed or copulation, or elſe being heated or inflamed with the pleaſant motion of the man moving her thereto, doth

doth at length unclose it self to receive the mans seed: for likewise it happeneth many times that the orifice of the stomach being shut after eating, is presently unlooſed again, when other delicate meats are offered to be eaten: even so may the womb uncloſe it self again at certain seasons, whereof come manifold issues, whose time of birth and also of conception are different. For as *Pliny* writeth, when there hath been a little space between two conceptions, they are both hastened, as it appeared in *Hercules* and his brother *Iphicles*; and in her which having two children at a birth, brought forth one like unto her husband and another like unto the adulterer. And also in the Procomesian slave or bond-woman, who, by copulation on the same day, brought one forth like unto her master, and another like unto his steward: and in another who brought forth one at the due time of child-birth, and another at five months end. And again, in another, who bringing forth her burden on the seventh month, brought forth two more in the months following. But this is a most manifest argument of superfetation, that as many children as are in the womb (unless they be twins of the same sex) so many secundines are there, as I have often seen my self. And it is very likely that if they were conceived in the same moment of time, that they should all be included in one secundine. But when a woman hath more children than two at one burden, it seemeth to be a monstrous thing, because that nature hath given her but two breasts. Although we shall hereafter rehearse many examples of more numerous births.

Lib. 7. cap. 11.

CHAP. XXXIII.

Of the tumor called Mola, *or a Mole growing in the womb of women.*

The reason of the name.

OF the Greek word *Myle*, which signifieth a Mill-stone, this tumor called *Mola* hath its name: for it is like unto a Mill-stone both in the round or circular figure, and also in hard consistence, for the which self same reason the whirl-bone of the knee is called of the Latins *Mola*, and of the Greeks *Myle*. But the tumor called *Mola*, whereof we here intreat, is nothing else but a certain false conception of deformed flesh, round and hard, conceived in the womb as it were rude and unperfect, not distinguished into the members, coming by corrupt, weak, and diseased seed, of the immoderate flux of the terms, as it is defined by *Hippocrates*. This is included in no secundine, but as it were in its own skin.

What a *Mola* is.

Lib. de steril. *cap. 7. lib. 4. de usu part.*

There are some that think the *Mola* to be engendred of the concourse or mixture of the womans seed and menstrual blood, without the communication of the mans seed. But the opinion of *Galen* is, that never any man saw a woman conceive either a *Mola*, or any other such thing without a copulation of man, as a Hen layeth eggs without a Cock: for the only cause and original of that motion is in the mans seed, and the mans seed doth only minister matter for the generation thereof. Of the same opinion is *Avicen*, who thinketh the *Mola*, to be made by the confluxion of the mans seed that is unfertile, with the womans; when as it, because unfruitful, only puffs up or makes the womans seed to swell as leaven into a greater bigness, but not into any perfect shape or form. Which is also the opinion of *Fernelius*, by the decrees of *Hippocrates* and *Avicen*: for the immoderate fluxes of the courses are conducing to the generation of the *Mola*, which overwhelming the mans seed, being now unfruitful and weak, doth constrain it to desist from its enterprise of conformation already begun, as vanquished or wholly overcome: for the generation of the *Mola* cometh not of a simple heat working upon a clammy and gross humor, as worms are generated; but of both the seeds, by the efficacy of a certain spirit, after a sort prolifical, as may be understood by the membranes wherein the *Mola* is included, by the ligaments whereby many times it is fastned or bound to the true conception or child, engendred or begotten by superfetation; and finally, by the increase, and great and sluggish weight. If all men were not perswaded that the conflux of a mans seed must of necessity concur to the generation of the *Mola*, it would be no small cloak or cover to women to avoid the shame and reproach of their light behaviour.

How the *Mola* is engendred.

CHAP. XXXIV.

How to discern a true conception from a false conception or Mola.

The signs of a *mola* included in the womb.

WHen the *Mola* is included in the womb, the same things appear as in the true and lawful conception. But the more proper signs of the *Mola* are these: there is a certain pricking pain, which at the beginning troubleth the belly as if it were the colick; the belly will swell sooner than it would if it were the true issue, and will be distended with great hardness, and is more difficult and troublesome to carry, because it is contrary to nature, and void of soul or life. Presently after the conception the dugs will swell and puff up, but shortly they fall and become lank and lax; for nature sendeth milk thither in vain, because there is no issue in the womb that may spend the same. The *Mola* will move before the third month, although it be obscurely, but the true conception will not: but this motion of the *Mola* is not of the intellectual soul, but of the faculty of the womb, and of the spirit of the seed dispersed through the substance of the *Mola*; for it is nourished and increaseth after the manner of plants, but not by reason of a soul or spirit sent from above, as the infant doth. Moreover, that motion that the infant hath in its due and appointed time, differeth much from the motion of the *Mola*; for the child is moved to the right side, to the left side, and to every side gently, but the *Mola*, by reason of its heaviness, is fixed, and rowleth in manner of a stone, carried by the weight thereof unto what side soever the woman declineth her self. The woman that hath a *Mola* in her womb, doth daily wax leaner and leaner in all her members, but especially in her legs, although notwithstanding towards night they will swell, so that she will be very slow or heavy in going, the

By what faculty the womb moveth.

How the motion of the *Mola* differeth from the motion of the infant in the womb.

The *mola* doth turn to each side of the womb, as the situation of the body is.

natural

natural heat forſaking the parts remote from the heart by little and little: and moreover, her belly ſwells, by reaſon that the menſtrual matter reſteth about thoſe places, and is not conſumed in the nouriſhment of the *Mola*; ſhe is ſwoln as if ſhe had the dropſie, but that it is harder, and doth not riſe again when it is preſſed with the fingers. The navel doth not ſtand out as it will do when the true iſſue is contained in the womb, neither do the courſes flow as they do ſometimes in the true conception; but ſometimes great fluxes happen, which eaſe the weight of the belly. In many when the *Mola* doth cleave not very faſt, it falleth away within three or four months, being not as yet come unto its juſt bigneſs; and many times it cleaveth unto the ſides of the womb and Cotyledons very firmly, ſo that ſome women carry it in their wombs five or ſix years, and ſome as long as they live.

The external form and deſcription of the forenamed womb.



A *Sheweth the body of the womb.*
B *The teſticle.*
C *The neck of the womb, wherein that little tumor was contained.*
D *Sheweth the end of the neck of the womb that was plucked in ſunder, and alſo the veſſels whereby it drew the nutriment unto it.*
E *Sheweth the band.*
FFF *The veſſels diſperſed through the womb.*

The Deſcription of the womb being open, and ſhewing the Mola *contained therein.*



A A *Shew the external and ſuperficial part of the womb.*
B B B B *Shew the thickneſs of the body, or proper ſubſtance of the womb.*
C *Sheweth the* Mola.
D D *Shew that concavity wherein the* Mola *was contained, or incloſed in the womb.*

The wife of *Guiliam Roger* Pewterer, dwelling in S. *Victors* ſtreet, bore a *Mola* in her womb ſeventeen years, who being of the age of fifty years, died; and I having opened her found the body of her womb to be almoſt looſed, and not tied or bound by its accuſtomed ligatures, but as it were hanging only by the neck, and furthermore cleaving to the Kall adjoining to it, having but only one teſticle, and that on the right ſide, and that ſomewhat broader and looſer than uſual: the horns were not to be ſeen except it were on that ſide, the veſſels were on the neck only, and there very manifeſt and puffed up, it was as big as a mans head. When I had taken it out of her body, I brought it home unto my houſe, that at my leiſure I might find out what was contained in it ſo long; therefore on a certain day, calling together the chief Phyſicians of *Paris*, as *Maſſilæus*, *Alexis*, *Vigor de S. Pont. Feure*, *Brovet*, *Violais*, *Grealmus*, *Ravin*, *Mareſcotius*, *Milotus*, *Hautin*, *Riolan*, *Luſſon*; and Surgeons, as *Brun*, *Cointerel*, *Guillemeau*; all theſe being preſent, I opened the womb, and A Hiſtory.

The deſcription of a *Mola* carried ſeventeen years in the womb.

and I found it in all the body thereof, and in the proper tunicle, ſo ſcirrhous, and ſo hard that I could hardly cut or make a knife to enter it: the body thereof was three fingers thick. In the midſt of the capacity thereof I found a lump of fleſh as big as both my fiſts, like unto a Cows udder, cleaving to the ſides of the womb, but in a certain place, of a very thick, unequal and cloddiſh ſubſtance, with many bodies therein, even as are commonly found in Wens and Griſtles, diſperſed through it as if it were bones. The judgment of all that were preſent was, that this great tumor at the firſt was a *Mola*, which in proceſs of time degenerated into a ſcirrhous body, together with the proper ſubſtance of the womb. Moreover, in the middle of the neck of the womb, we found a tumor as big as a Turkies egg, of ſubſtance hard, cartilaginous and bony, filling all the whole neck, but eſpecially the inward orifice of the womb, which the common people of *France* do call the *Garland*, ſo that by that paſſage nothing could go out, or enter into the womb: all that tumor weighed nine pounds and two ounces, which I, by reaſon of the novelty of the thing, keep in my cloſet, and before I have deſcribed it.

As long as the woman carried this *Mola* in her womb, ſhe felt moſt ſharp pain in her belly; the region of her belly was marvellous hard, diſtended and large, as if it were a woman that had many children at once in her womb; ſo that many Phyſicians when the time of child-birth was paſt, ſuppoſed that ſwelling of the belly to come of the Dropſie, and aſſaied to cure it as they would the Dropſie; but for all the medicines they could uſe, the belly became never the leſſer. Oftentimes the urine was ſtopped for the ſpace of three days, and then the making of urine was very painful unto her, and many times alſo her excrements were ſtopped for the ſpace of a week, by reaſon that the guts were preſſed by the weight of the *Mola*. At certain ſeaſons, as every third month, there came exceeding great fluxes; the matter thereof could not be carried through the capacity of the womb, as we ſaid before, becauſe it was exactly ſhut and ſtopped, but through the veſſels by which Virgins, and alſo certain other women great with child evacuate their menſtrual matter. If the *Mola* be expelled or caſt out in the firſt or ſecond month, as many times it ſo happeneth, it is called of women an unprofitable or falſe conception. Sometimes there are found in one womb two or three moles ſeparated one from another, and ſometimes bound or tied to the ſound and perfect infant: As it happened in the wife of *Valeriola* the Phyſician, which was delivered of a *Mola* which ſhe had carried in her womb twelve months, annexed with a child of four months old, which had deprived the Infant of its room and nutriment. For it is always to be certainly ſuppoſed, that the *Mola*, as a cruel beaſt, by its ſociety, and keeping from its nutriment and place, kills the infant that is joined unto it.

A vain or unprofitable conception.

The *Mola* kills the infant in the womb, when it is faſtned unto it.

I remember once I opened the body of a dead woman, which had a *Mola* in her womb, as big as a Gooſe-egg, which when nature had aſſaied by many vain endeavors to caſt out, remained notwithſtanding, and at length putrified, and therewith infected the whole womb, whereof ſhe died. There be ſome which judging themſelves great with child, do about the ninth or tenth month expel no other thing but ſounding blaſts of wind; whereby the womb ſuddenly falling down, and waxing more ſlender, they are ſaid in a mockery to have been delivered of a fart. To conclude, whatſoever reſembles being with child, if it be not excluded at the due and lawful time of child-birth by its own accord, or by the ſtrength of nature, then muſt it be expelled by art.

CHAP. XXXV.

What cure muſt be uſed to the Mola.

ALL things that provoke the flowers and ſecundines, and exclude the Infant, being dead, are to be preſcribed, given inwardly, put up, and applied outwardly, as Trochiſces of *myrrha*, hermodactyls, and ſuch like, firſt having fomentations that are relaxing and mollifying always applied to the places. You muſt uſe theſe medicines, and phlebotomy, diet and baths then and ſo long as it ſhall ſeem neceſſary to the Phyſician that is preſent. But if it happens that the *Mola* is ſeparated or looſed from the womb, and nature cannot expel it when it is ſo looſed, let the Chirurgion place the woman in that ſituation that we ſaid ſhe was put in, when the child was to be drawn from her. Then opening her genital parts, let him take hold on it by putting an inſtrument into it, which by reaſon of the likeneſs thereof is called a Gryphons Talon; for it cannot be taken hold on otherwiſe, by reaſon of the roundneſs thereof; for it hath no place whereon it may be taken hold of: therefore when one taketh hold on it with his hand, it cannot be holden faſt by reaſon of the ſlipperineſs thereof, but will run and ſlip back into the hollowneſs of the womb, like unto a bowl or ball; but it may be more eaſily taken hold on with the Gryphons Talon, if the belly be preſſed on both ſides that it may remain ſtill while the Gryphons Talon takes hold on it; for when it hath taken good hold on it, it may be eaſily drawn out. When the *Mola* is drawn out, the ſame cure muſt be uſed to the woman, as is uſed to a woman after that ſhe is delivered of child.

Thoſe things that provoke the flowers forcibly, do alſo conſume or waſte the *Mola*.

The Chirurgical extraction of the *Mola*.

The Figure of an Inſtrument called a Gryphons Talon, to draw out the Mola *when it is looſe in the womb.*



CHAP. XXXVI.

Of Tumors or ſwellings happening to the Pancreas *or ſweet-breads, and the whole Meſentery.*

THe tumors of other places and parts in the belly ought diligently to be diſtinguiſhed from the *Mola*, and other tumors of the womb. For when the tumors ariſe in the *glandula* called *Pancreas*, and in all the whole *Meſenterium*, many unskilful Surgeons take them for *Molaes* or ſcirrhous tumors of the womb, and ſo go erroneouſly about to cure them, as ſhall appear by theſe Hiſtories following.

An Hiſtory. *Iſabel Rolant* the wife of *John Bony* dwelling in *Paris* in the ſtreet *Moncey* near to St. *Gerviſe* his Church, being threeſcore years of age, departed this life in the year of our Lord 1578. on the two and twentieth day of *October*, and her body being opened in the preſence of Doctor *Milot* the Phyſician; he, when the Meſentery was taken out of the body, cauſed it to be carried home to his houſe, that at his leiſure he might find out the cauſe of this mortal diſeaſe, which was always ſuſpected to be in the Meſentery. Therefore on a time calling *Varadeus*, *Brove*, *Chappel*, *Mareſcotius*, *Arragonius*, *Baillutius*, *Reburtius*, and *Riolan*, all Doctors of Phyſick, and my ſelf and *Pineus* Surgeons, to his houſe to ſee the ſame: Where we found all the Meſentery and the Pancreas in the Meſentery ſwollen and puffed up with a marvellous and almoſt incredible tumor, ſo that it weighed ten pounds and an half, altogether ſcirrhous on the outſide, cleaving on the hinder part onely to the *vertebraes* of the loins; but on the fore-part to the *Peritonæum* being alſo ſcirrhous and wholly cartilaginous. Moreover, there were infinite other abſceſſes in the ſame Meſentery, every one cloſed in his ſeveral ciſt, ſome filled with a honey-like, ſome filled with a tallow-like, ſome with an albugineous, and ſome with a wateriſh liquor or humour, whereof ſome alſo were like unto pap; and to conclude, look how many abſceſſes there were, ſo many kinds or differences of matters there were. It was then eight years ſince that tumour began to grow by little and little without feeling and pain unto ſuch a greatneſs, becauſe that the Meſentery it ſelf was without pain in a manner. For the woman her ſelf could do all the faculties of Nature almoſt as well as if ſhe had been ſound and whole, except that two moneths before ſhe died, ſhe was conſtrained to keep her bed, becauſe ſhe had a continual Fever, which endured ſo long as ſhe lived, and alſo becauſe that the Meſentery, being as it were ſeparated or torn from its roots or ſeat, did rowl up and down in the belly, not without the feeling of grievous pain: for, as we ſaid before, it did ſtick but onely to the *vertebraes* of the loins and *Peritonæum*, and nothing at all to the guts and other parts whereunto it is as it were naturally knit or joined.

Apoſtumes of divers kinds in the *Meſenterium*.

The accidents that come when the *Meſenterium* is ſeparated from the bodies adjoining.

Therefore becauſe the weight and heavineſs thereof depreſſed the bladder, it cauſed a great difficulty in her making of water, and alſo becauſe it reſted on the guts, it made it very painful for her to go to ſtool, ſo that the excrements would not come down except ſhe took a ſharp Clyſter to cauſe them: and as concerning Clyſters, they could not be put up high enough by reaſon of the greatneſs of the tumor which encloſed and ſhut the way; and ſuppoſitories did no good at all. It was alſo very difficult for her to take breath, by reaſon that the midriff or *diaphragma* was compreſſed with the tumor. There were ſome that did ſuſpect it to be a *Mola*, others thought that it came by reaſon of the greatneſs of the tumor. There were ſome that did ſuſpect it to be a *Mola*, others thought that it came by reaſon of the dropſie. Aſſuredly this diſeaſe cauſed the dropſie to enſue; neither was the cauſe thereof obſcure, for the function of the Liver was fruſtrated by reaſon that the concoction or the alteration of the Chylus was intercepted by occaſion of the tumor: and moreover the Liver it ſelf had a proper diſeaſe, for it was hard and ſcirrhous, and had many abſceſſes both within, and without it, and all over it. The milt was ſcarce free from putrefaction, the Guts and Kall were ſomewhat blew and ſpotted, and to be brief, there was nothing ſound in the lower belly.

The dropſie coming of a Tumor of the *Meſenterium*.

There is the like Hiſtory to be read, written by *Philip Ingreſſias*, in his book of Tumors, of a certain Moor that was hanged for theft; for (ſaith he) when his body was publickly diſſected, in the *Meſenterium* were found ſeventy ſcrophulous tumors, and ſo many abſceſſes were contained or encloſed in their ſeveral ciſts or skins, and ſticking to the external tunicle, eſpecially of the greater guts: the matter contained in them was divers; for it was hard, knotty, clammy, glutinous, liquid and wateriſh; but the entrails, eſpecially the Liver and the Milt, were found free from all manner of a tainture, becauſe (as the ſame Author alledgeth) Nature being ſtrong had ſent all the evil juice and the corruption of the entrails into the Meſentery: and verily this

Tom. 1 tra. 3. cap. 1.

Moor, ſo long as he lived, was in good and perfect health. Without doubt the corruption of ſuperfluous humours for the moſt part is ſo great (as is noted by *Fernelius*) that it cannot be received in the receptacles that Nature hath appointed for it; therefore then no ſmall portion thereof falleth into the parts adjoining, and eſpecially into the Meſentery and *Pancreas*, which are as it were the ſink of the whole body. In thoſe bodies which through continual and daily gluttony abound with choler, melancholy and phlegm, if it be not purged in time, Nature being ſtrong and luſty, doth repel and drive it down into the *Pancreas* and the Meſentery, which are as places of no great repute, and that eſpecially out of the Liver and Milt by thoſe veins or branches of the *Vena Porta* which end or go not into the Guts, but are terminated in the Meſentery and *Pancreas*. In theſe places diverſe humours are heaped together, which in proceſs of time turn into a looſe and ſoft tumour, and then if they grow bigger, into a ſtiff, hard and very ſcirrhous tumor. Whereof *Fernelius* affirmeth that in thoſe places he hath found the cauſes of choler, melancholy, fluxes, dyſenteries, cachexiaes, atrophiaes, conſumptions, tedious and uncertain fevers, and laſtly of many hidden diſeaſes, by the taking whereof ſome have received their health, that have been thought paſt cure. Moreover *Ingraſſias* affirmeth out of *Julius Pollux*, that Scrophulaes may be engendred in the Meſentery, which nothing differs from the mind and opinion of *Galen*, who ſaith that Scrophulaes are nothing elſe but indurate and Scirrhous kernels. But the *Meſenterium* with his glanduls being great and many, making the *Pancreas*, doth eſtabliſh, ſtrengthen and confirm the diviſions of the veſſels. Alſo the *ſcirrhus* of the proper ſubſtance of the womb is to be diſtinguiſhed from the *mola*; for in the bodies of ſome women that I have opened, I have found the womb annoied with a ſcirrhous tumor as big as a mans head, in the curing whereof Phyſicians nothing prevailed, becauſe they ſuppoſed it to be a *mola* contained in the capacity of the womb, and not a ſcirrhous tumor in the body thereof.

Lib.6.part.mor. cap.7.

The *Meſenterium* is the ſink of the body.

The Scrophulaes in the *Meſenterium*.

The *Scirrhus* of the womb.

CHAP. XXXVII.

Of the cauſe of barrenneſs in Men.

How the ſeed is unfertil.

THere are many cauſes of barrenneſs in Men, that is to ſay, the too hot, cold, dry or moiſt diſtemper of the ſeed, the more liquid and flexible conſiſtence thereof, ſo that it cannot ſtay in the womb, but will preſently flow out again: for ſuch is the ſeed of old men and ſtriplings, and of ſuch as uſe the act of generation too often and immoderately: for thereby the ſeed becometh crude and wateriſh, becauſe it doth not remain his due and lawful time in the teſticles, wherein it ſhould be perfectly wrought and concocted, but is evacuated by wanton copulation. Furthermore, that the ſeed may be fertile, it muſt of neceſſity be copious in quantity but in quality well concocted, moderately thick, clammy, and puffed with abundance of ſpirits; both theſe conditions are wanting in the ſeed of them that uſe copulation too often: and moreover becauſe the wives of thoſe men never gather a juſt quantity of ſeed laudable both in quality and conſiſtence in their teſticles, whereby it cometh to paſs that they are the leſs provoked or delighted with venereous actions, and perform the act with leſs alacrity, ſo that they yield themſelves leſs prone to conception. Therefore let thoſe that would be Parents of many children uſe a mediocrity in the uſe of Venery.

How the cutting of the veins behind the ears maketh men barren.

The Woman may perceive that the mans ſeed hath ſome diſtemperature in it, if when ſhe hath received it into her womb, ſhe feeleth it ſharp, hot or cold, if the man be more quick or ſlow in the act. Many become barren after they have been cut for the Stone, and likewiſe when they have had a wound behind the ears, whereby certain branches of the jugular veins and arteries have been cut, that are there, ſo that after thoſe veſſels have been cicatrized, there followed an interception of the ſeminal matter downwards, and alſo of the community which ought of neceſſity to be between the brain and the teſticles, ſo that when the conduits or paſſages are ſtopped, the ſtones or teſticles cannot any more receive, neither matter nor lively ſpirits from the brain in ſo great quantity as it was wont, whereof it muſt of neceſſity follow, that the ſeed muſt be leſſer in quantity, and weaker in quality.

Thoſe that have their teſticles cut off, or elſe compreſſed or contuſed by violence, cannot beget children, becauſe that either they want that help the teſticles ſhould miniſter in the act of generation, or elſe becauſe the paſſage of the ſeminal matter is intercepted or ſtopped with a Callus: by reaſon whereof they cannot yield forth ſeed, but a certain clammy humour contained in the glanduls called *Proſtatæ* (yet with ſome feeling of delight).

The defaults of the Yard.

Moreover the defects or imperfections of the yard may cauſe barrenneſs: as, if it be too ſhort, or if it be ſo unreaſonable great that it renteth the privy parts of a woman, and ſo cauſeth a flux of bloud, for then it is ſo painful to the woman, that ſhe cannot void her ſeed, for that cannot be excluded without pleaſure and delight; alſo if the ſhortneſs of the ligament that is under the Yard doth make it to be crooked, and violate the ſtiff ſtraitneſs thereof, ſo that it cannot be put directly or ſtraightly into the womans privy parts. There be ſome that have not the orifice of the conduit of the Yard rightly in the end thereof, but a little higher, ſo that they cannot ejaculate or caſt out their ſeed into the womb.

The ſign of the Palſie in the Yard.

Alſo the particular Palſie of the Yard is numbred amongſt the cauſes of barrenneſs; and you may prove whether the Palſie be in the Yard by dipping the genitals in cold water, for except they do draw themſelves together, or ſhrink up after it, it is a token of the palſie; for members that have the Palſie, by the touching of cold water, do not ſhrink up, but remain in their accuſtomed laxity and looſeneſs: but in this caſe the genitals are indued with ſmall ſenſe, the ſeed cometh out without pleaſure or ſtiffneſs of the Yard, the ſtones in touching are cold, and to conclude, thoſe that have their bodies daily waxing lean through a conſumption, or that are vexed with an evil habit or diſpoſition,

ſition, or with the obſtruction of ſome of the entrails, are barren and unfertil, and likewiſe thoſe in whom ſome noble part neceſſary to life and generation exceedeth the bounds of Nature with ſome great diſtemperature; and laſtly, thoſe who by any means have their genital parts deformed.

Here I omit thoſe that are with-holden from the act of generation by inchantment, magick, witching and inchanted knots, bands and ligatures; for thoſe cauſes belong not to Phyſick, neither may they be taken away by the remedies of our Art. The Doctors of the Canon Laws have made mention of thoſe magick bands which may have power in them, in the particular Title, *De frigidis, maleficiatis, impotentibus & incantatis:* alſo St. *Auguſtin* hath made mention of them, *Tract.7. in Joan.* Magick bands and enchanted knots.

CHAP. XXXVIII.

Of the barrenneſs or unfruitfulneſs of Women.

A Woman may become barren or unfruitful through the obſtruction of the paſſage of the ſeed, or through ſtraitneſs and narrowneſs of the neck of the Womb coming either through the default of the formative faculty, or elſe afterwards by ſome miſchance, as by an Abſceſs, Schirrhus, Warts, Chaps, or by an Ulcer, which being cicatrized, doth make the way more narrow, ſo that the Yard cannot have free paſſage thereinto. Moreover the Membrane called *Hymen*, when it groweth in the midſt or in the bottom of the neck of the womb, hinders the receiving of the mans ſeed. Alſo if the womb be over-ſlippery, or more looſe, or over-wide, it maketh the woman to be barren; ſo doth the ſuppreſſion of the menſtrual fluxes, or the too immoderate flowing of the Courſes or Whites: which cometh by the default of the womb, or ſome entrail, or of the whole body, which conſumeth the menſtrual matter, and carrieth the ſeed away with it. The cauſe why the neck of the womb is narrow. The membrane called *Hymen.*

The cold and moiſt diſtemperature of the womb, extinguiſhes and ſuffocates the Mans ſeed, and maketh it that it will not ſtay or cleave unto the womb, and ſtay till it be concocted: but the more hot and dry doth corrupt for want of nouriſhment, for the ſeeds that are grown either in a mariſh or ſandy ground cannot proſper well: alſo a *Mola* contained in the womb, the falling down of the womb, the leanneſs of the womans body, ill humours bred by eating crude and raw fruits, or great, or over-much, whereof obſtructions and crudities follow, which hinder her fruitfulneſs. Furthermore, by the uſe of ſtupefactive things, the ſeminal matter is congealed and reſtrained, and though it flow and be caſt out, yet it is deprived of the prolifick power, and of the lively heat and ſpirits, the orifices or cotyledones of the Veins and Arteries are ſtopped, and ſo the paſſage for the menſtrual matter into the womb, is ſtopped. When the Kall is ſo far that it girdeth in the womb narrowly, it hindereth the fruitfulneſs of the woman, becauſe it will not permit the mans ſeed to enter into the womb. Moreover the fat and fleſhy habit of the man or woman hinder generation. For it hindereth them that they cannot join their genitals together: and by how much the more bloud goeth into fat, by ſo much the leſs is remaining to be turned into ſeed and menſtrual bloud, which two are the originals and principals of generation. Thoſe women that are ſpeckled in the face, ſomewhat lean, and pale, are more given to Venery than thoſe that are red and fat. Finally, *Hippocrates* ſets down four cauſes onely why women are barren and unfruitful. The firſt is, becauſe they cannot receive the mans ſeed by reaſon of the fault of the neck of the womb; the ſecond, becauſe when it is received into the womb, they cannot conceive it: the third is, becauſe they cannot nouriſh it: the fourth, becauſe they are not able to carry or bear it until the due and lawful time of birth. Theſe things are neceſſary to generation; the Object, Will, Faculty, concourſe of the Seeds, and the remaining or abiding thereof in the womb, until the due and appointed natural time. The cauſe of the flux of Women. *Aph.36.ſect.5. Gal. lib.14. De uſu Par.cap.9. Ariſt.in Prob. Sect. deſtr. Quæſt. 3, & 4.*

CHAP. XXXIX.

The ſigns of a diſtempered Womb.

THat woman is thought to have her womb too hot, whoſe Courſes come forth ſparingly and with pain, and exulcerate by reaſon of their heat, the ſuperfluous matter of the bloud being diſſolved or turned into wind by the power of the heat: whereupon that menſtrual bloud that floweth forth is more groſs and black. For it is the property of heat, by digeſting the thinner ſubſtance, to thicken the reſt, and by aduſtion to make it more black. Furthermore, ſhe that hath her genitals itching with the deſire of copulation, will ſoon exclude the ſeed in copulation, and ſhe ſhall feel it more ſharp as it goeth through the paſſages. That woman hath too cold a womb whoſe Flowers are either ſtopped, or flow ſparingly, and thoſe pale and not well coloured. The ſigns of a hot Womb.

Thoſe that have leſs deſire of copulation, have leſs delight therein, and their ſeed is more liquid and wateriſh, and not ſtaining a linnen cloth by ſticking thereunto, and it is ſparingly and ſlowly caſt forth. That womb is too moiſt that floweth continually with many liquid excrements, which therefore will not hold the ſeed, but preſently after copulation ſuffereth it to fall out; which will eaſily cauſe abortion. The ſigns of too dry a womb appear in the little quantity of the Courſes, in the profuſion of a ſmall quantity of ſeed, by the deſire of copulation, whereby it may be made ſlippery by the moiſture of the ſeed, by the fiſſures in the neck thereof, by the chaps and itching, for all things for want of moiſture will ſoon chap, even like unto the ground, which in the Summer by reaſon of great drought or drineſs, will chap and chink this way and that way, and on the contrary with moiſture it will cloſe and join together again as it were with glew. The ſigns of a cold Womb. The ſigns of a moiſt Womb. The ſigns of a dry Womb.

A woman is thought to have all opportunities unto conception when her Courſes or Flowers do ceaſe, for then the womb is void of excremental filth, and becauſe it is yet open, it will the more eaſily A meet time for conception.

easily receive the mans seed, and when it hath received it, it will better retain it in the wrinkles of the Cotyledones yet gaping as it were in rough and unequal places. Yet a woman will easily conceive a little before the time that the Flowers ought to flow: because that the menstrual matter falling at first like dew into the Womb, is very meet and fit to nourish the seed, and not to drive it out again, or to suffocate it.

Those which use copulation when their Courses fall down abundantly, will very hardly or seldom conceive; and if they do conceive, the Child will be weak and diseased, and especially if the womans bloud that flows out be unsound; but if the bloud be good and laudable, the Child will be subject to all plethorick diseases. There are some Women in whom presently after the flux of the Terms, the orifice of the Womb will be closed, so that they must of necessity use copulation with a man when their menstrual flux floweth, if at least they would conceive at all. A Woman may bear children from the age of fourteen until forty or fifty; which time whosoever doth exceed, will bear until threescore years, because the menstrual fluxes are kept, the prolifical faculty is also preserved: therefore many Women have brought forth children at that age; but after that time no woman can bear, as *Aristotle* writeth.

Arist. l.7. de hist. anim. c. 2. & c.5. *Lib.7.cap.14.* *Lib.6. cap.12.*

Yet *Pliny* saith that *Cornelia* (who was of the house of the *Scipioes*) being in the sixty second year of her age, bare *Volusius Saturnius*, who was Consul; *Valescus de Tarenta* also affirmeth that he saw a Woman that bare a child on the sixty second year of her age, having born before on the sixtieth and sixty first year. Therefore it is to be supposed that by reason of the variety of the air, region, diet and temperament, the menstrual flux and procreative faculty ceaseth in some sooner, in some later; which variety taketh place also in men. For in them, although the seed be genitable for the most part in the second seventh year, yet it is unfruitful until the third seventh year. And whereas most men beget Children until they be threescore years old, which time if they pass, they beget till seventy; yet there are some known that have begot children until the eightieth year. Moreover, *Pliny* writeth that *Masinissa* the King begot a Son when he was fourscore and six years of age, and also *Cato* the Censor after that he was fourscore.

Lib.7. de hist. anim.c.1.&2.6 *Lib.7.cap.14.*

CHAP. XL.

Of the falling down, or perversion, or turning of the Womb.

What is the falling down of the Womb.

THe Womb is said to fall down and be perverted, when it is moved out of its proper and natural place; as when the bands and ligatures thereof being loosed and relaxed, it falleth down unto one side or other, or into its own neck, or else passeth further, so that it comes out at the neck, and a great portion thereof appears without the privy parts. Therefore what things soever resolve, relax, or burst the ligaments or bands whereby the Womb is tied, are supposed to be the causes of this accident. It sometimes happens by vehement labour or travel in Child-birth, when the Womb with violence excluding the issue and the secundines, also follows and falls down, turning the innerside thereof outward. And sometimes the foolish rashness of the Midwife when she draweth away the Womb with the Infant, or with the secundine cleaving fast thereunto, and so drawing it down and turning the innerside outward. Furthermore, a heavy bearing of the Womb, the bearing of the carriage of a great burthen, holding or stretching of the hands or body upwards in the time of greatness with child, a fall, contusion, shaking or jogging by riding either in a Waggon or Coach, or on Horse-back, or leaping or dancing, the falling down of a more large and abundant humour, great griping, a strong and continual cough, a *Tenesmus* or often desire to go to stool, yet not voiding any thing, sneezing, a manifold and great birth, difficult bearing of the Womb, an asthmatical and orthopnoical difficulty of breathing, whatsoever doth weightily press down the *Diaphragma* or Midriff, or the muscles of the *Epigastrium*, the taking of cold air in the time of travel with child, or in the flowing of the menstrual flux, sitting on a cold marble stone, or any other such like cold things are thought oftentimes to be the occasion of these accidents, because they may bring the Womb out of its place.

The causes.

Arist. lib.7. de histor. anim. cap.2.

It falls down in many (saith *Aristotle*) by reason of the desire of copulation that they have, either by reason of the lustiness of their youth, or else because they have abstained a long time from it.

The signs.

You may know that the Womb is fallen down by the pain of those parts wherein it is fallen, that is to say by the entrails, loins, *os sacrum*, and by a tractable tumor at the neck of the Womb, and often with a visible hanging out, of diverse greatness, according to the quantity that is fallen down. It is seen sometimes like unto a piece of red flesh, hanging out at the neck of the Womb, of the bigness and form of a Goose-egg; if the woman stand upright, she feeleth the weight to lie on her privy parts; but if she sit or lie, then she perceiveth it on her back, or go to the stool, the straight gut called *intestinum rectum* will be pressed or loaden as if it were with a burthen; if she lie on her belly, then her urin will be stopped, so that she shall fear to use copulation with a man.

The prognostications.

When the Womb is newly relaxed in a young woman, it may be soon cured; but if it hath been long down in an old woman, it is not to be helped. If the Palsie of the ligaments thereof have occasioned the falling, it scarce admits of cure,; but if it falls down by means of putrefaction, it cannot possibly be cured. If a great quantity thereof hang out between the thighs, it can hardly be cured; but it is corrupted by taking the air, and by the falling down of the urin and filth, and by the motions of the thighs in going it is ulcerated, and so putrefies.

An History.

I remember that once I cured a young Woman who had her Womb hanging out at her privy parts as big as an Egg, and I did so well perform and perfect the Cure thereof, that afterwards she conceived, and bare children many times, and her Womb never fell down.

CHAP.

CHAP. XLI.

The cure of the falling down of the Womb.

BY this word, falling down of the Womb, we underſtand every motion of the Womb out of its place or ſeat: therefore if the Womb aſcend upwards, we muſt uſe the ſame medicins as in ſtrangulation of the Womb. If it be turned towards either ſide, it muſt be reſtored and drawn back to its right place, by applying and uſing cupping-glaſſes. But if it deſcend and fall down into its own neck, but yet not in great quantity, the woman muſt be placed ſo that her buttocks may be very high, and her legs acroſs; then Cupping-glaſſes muſt be applied to her navel and *Hypogaſtrium*, and when the Womb is brought into its place, injections that bind and dry ſtrongly muſt be injected into the neck of the Womb, ſtinking fumigations muſt be uſed unto the privy parts, and ſweet things uſed to the mouth and noſe. But if the womb hang down in great quantity between the thighs, it muſt be cured by placing the woman after another ſort, and by uſing other kind of Medicins. Firſt of all ſhe muſt be ſo laid on her back, her buttocks and thighs ſo lifted up, and her legs ſo drawn back as when the child or ſecundine are to be taken or drawn from her; then the neck of the Womb, and whatſoever hangeth out thereat, muſt be anointed with Oil of Lillies, freſh Butter, Capons Greaſe, and ſuch like; then it muſt be thruſt gently with the fingers up into its place, the ſick or pained woman in the mean time helping or furthering the endeavour by drawing in of her breath as if ſhe did ſup, drawing up as it were that which is fallen down.

Remedies for the aſcenſion of the Womb.

For the falling down of the Womb, properly ſo called.

After that the Womb is reſtored unto its place, whatſoever is filled with the ointment muſt be wiped with a ſoft and clean cloth, leſt that by the ſlipperineſs thereof the womb ſhould fall down again; the genitals muſt be fomented with an aſtringent decoction, made with Pomgranate Pills, Cypreſs Nuts, Galls, Roch Allum, Horſe-tail, Sumach, Berberies, boiled in the water wherein Smiths quench their Irons; of thoſe materials make a powder, wherewith let thoſe places be ſprinkled: let a Peſſary of a competent bigneſs be put in at the neck of the Womb, but let it be eight or nine fingers in length, according to the proportion of the grieved Patients body. Let them be made either with Lattin, or of Cork covered with Wax, of an oval form, having a thread at one end, whereby they may be drawn back again as need requires.

The forms of oval Peſſaries.



A *Shews the body of the Peſſary.*
B *Sheweth the thread wherewith it muſt be tied to the thigh.*

When all this is done, let the ſick woman keep her ſelf quiet in her bed, with her buttocks lying very high, and her legs acroſs, for the ſpace of eight or ten days: in the mean while the application of Cupping-glaſſes will ſtay the Womb in the right place and ſeat, after it is reſtored thereunto: but if ſhe hath taken any hurt by cold air, let the privy parts be fomented with a diſcuſſing and heating fomentation, on this wiſe: ℞ *Fol. alth. ſalv. lavend. roſmar. artemiſ. flor. chamæm. melilot. an.* m β. *ſem. aniſ. fœnugr. an.* ℥ j. let them be all well boiled in water and wine, and make thereof a decoction for your uſe. Give her alſo Clyſters, that when the Guts are emptied of the excrements, the Womb may the better be received in the void and empty capacity of the belly: for this reaſon the bladder is alſo to be emptied, for otherwiſe it were dangerous leſt that the Womb lying between them, both being full, ſhould be kept down, and cannot be put up into its own proper place by reaſon thereof. Alſo Vomiting is ſuppoſed to be a ſingular remedy to draw up the Womb that is fallen down: furthermore alſo it purgeth out the phlegm wich did moiſten and relax the ligaments of the womb, for as the Womb in time of copulation at the beginning of the conception it moved downwards to meet the ſeed, ſo the Stomach, even of its own accord, is lifted upwards when it is provoked by the injury of any thing that is contrary unto it, to caſt it out with greater violence; but when it is ſo raiſed up, it draws up together therewith the *Peritonæum*, the Womb and alſo the body or parts annexed unto it. If it cannot be reſtored unto its place by theſe preſcribed remedies, and that it be ulcerated and ſo putrefied that it cannot be reſtored unto his place again, we are commanded by the Precepts of Art to cut it away, and then to cure the

A diſcuſſing and heating fomentation.

How vomiting is profitable to the falling down of the Womb.

The cutting away of the Womb when it is putrefied.

the Womb according to Art; but firſt it ſhould be tied, and as much as is neceſſary muſt be cut off, and the reſt ſeared with a Cautery. There are ſome women that have had almoſt all their womb cut off, without any danger of their life, as *Paulus* teſtifieth. *Lib. 6.*

Epiſt. 39. lib. 2. Epiſt. med. *John Langius* Phyſician to the Count Palatine writeth, that *Carpus* the Chirurgeon took out the womb of a Woman of *Bononia*, he being preſent, and yet the woman lived and was very well after it.

Trac. de mirand. morb. cauſ. *Antonius Benevenius* Phyſician of *Florence* writeth, that he, called by *Ugolius* the Phyſician to the cure of a woman whoſe womb was corrupted and fell away from her by pieces, and yet ſhe lived ten years after it.

An Hiſtory. There was a certain woman, being ſound of body, of good repute, and above the age of thirty years, in whom, ſhortly after ſhe had been married the ſecond time, which was in *Anno* 1571. having no child by her firſt husband, the lawful ſigns of a right conception did appear: yet in proceſs of time there aroſe about the lower part of her privities the ſenſe or feeling of a weight or heavineſs, being ſo troubleſom unto her by reaſon that it was painful, and alſo for that it ſtopped her urin, that ſhe was conſtrained to diſcloſe her miſchance to *Chriſtopher Mombey* a Surgeon, her neighbour dwelling in the Suburbs of S. *Germans*; who having ſeen the tumor or ſwelling in her groin, aſſwaged the pain with mollifying and anodyne Fomentations and Cataplaſms; but preſently after he had done this, he found on the inner ſide of her lip of the orifice of the neck of the womb, an Impoſtume rotten and running, as if it had been out of an abſceſs newly broken, with ſanious matter, ſomewhat red, yellow, and pale, running a long time. Yet for all this the feeling of the heavineſs or weight was nothing diminiſhed, but did rather increaſe daily, ſo that from the Year of our Lord 1573. ſhe could not turn her ſelf being in her bed on this or that ſide, unleſs ſhe laid her hand on her belly to bear and eaſe her ſelf of the weight; and alſo ſhe ſaid when ſhe turned her ſelf, ſhe ſeemed to feel a thing like a Bowl or Rowl in her belly unto the ſide whereunto ſhe turned her ſelf, neither could ſhe go to ſtool, or avoid her excrements ſtanding or ſitting, unleſs ſhe lift up that weight with her hands towards her ſtomach or midriff: when ſhe was about to go, ſhe could ſcarce ſet forwards her feet, as if there had ſomething hanged between her thighs, that did hinder her going. At certain ſeaſons that rotten apoſtume would open or uncloſe of it ſelf, and flow and run with its wonted ſanious matter, but then ſhe was grievouſly vexed with pain of the head, and all her members, ſwouning, loathing, vomiting, and almoſt choaking, ſo that by the perſuaſion of a fooliſh woman ſhe was induced and contented to take *Antimonium*, the working and the ſtrength thereof was ſo great and violent, that after many vomits, with many frettings of the guts, and watery dejections of ſtools, ſhe thought her fundament fell down, but being certified by a woman that was a familiar friend of hers, unto whom ſhe ſhewed her ſelf, that there was nothing fallen down at or from her fundament, but it was from her womb, ſhe called in the Year of our Lord, 1575. Surgeons, as my ſelf, *James Guillemeau*, and *Antony Vieux*, that we might help her in extremity.

Antimonium taken in a potion doth cauſe the womb to fall down.

The ſigns of the ſubſtance of the Womb drawn out. When we had diligently and with good conſideration weighed the whole eſtate of her diſeaſe, we agreed with one conſent, that that which was fallen down ſhould be cut away, becauſe that by the black colour, ſtinking, and other ſuch ſigns, it gave a teſtimony of a putrefied and corrupted thing. Therefore for two days we drew out the body by little and little, and piece-meal, which ſeemed unto the Phyſicians that we had called, as *Alexius*, *Gaudinus*, *Feureus*, and *Violaneus*, and alſo to our ſelves, to be the body of the Womb; which thing we proved to be ſo, becauſe one of the teſticles came out whole, and alſo a thick membrane or skin being the relick of the *Mola*, which being ſuppurated, and the abſceſs broken, came out by little and little in matter; after that all this body was ſo drawn away, the ſick woman began to wax better and better, yet notwithſtanding for the ſpace of nine days before it was taken away, ſhe voided nothing by ſiege, and her urin alſo was ſtopped for the ſpace of four days.

After this all things became as they were before, and ſhe lived in good health three Moneths after, and then died of a Pleuriſie that came on her very ſuddenly; and I having opened her body, obſerving and marking every thing very diligently, could not find the womb at all, but in ſtead thereof there was a certain hard and callous body, which Nature, who is never idle, had framed in ſtead thereof, or to fill the hollowneſs of the belly.

CHAP. XLII.

Of the Tunicle or Membrane called Hymen.

Whether there be a membrane called *Hymen*. IN ſome Virgins or Maidens in the orifice of the neck of the womb, there is found a certain Tunicle or Membrane, called of ancient Writers *Hymen*, which prohibiteth the copulation of a man, and cauſeth a woman to be barren; this Tunicle is ſuppoſed by many, and they not of the common ſort onely, but alſo learned Phyſicians, to be as it were, the encloſure of the Virginity or Maidenhead. But I could never find it in any, ſeeking of all ages from three to twelve, of all that I had under my hands in the Hoſpital of *Paris*.

An Hiſtory. Yet once I ſaw in a Virgin of ſeventeen years, whom her mother had contracted to a man, and ſhe knew nevertheleſs there was ſomething in her privy parts that hindred her from bearing of children, who deſired me to ſee her, and I found a very thin nervous membrane a little beneath the *Nymphæa*, near unto the orifice of the neck of the womb, in the midſt there was a very little hole whereout the Terms might flow; I ſeeing the thickneſs thereof, cut it in ſunder with my Sciſſars, and told her Mother what ſhe ſhould do afterwards: and truly ſhe married ſhortly after and bore children. *Realdus Columbus* is of my opinion, and ſaith that this is ſeen very ſeldom; for theſe are his words, Under the *Nymphæa* in many, but not in all Virgins, there is another membrane which when it is preſent (which is but ſeldom) it ſtoppeth, ſo that the Yard cannot be put into the orifice of *Lib. 11. cap. 16.*

of the Womb, for it is very thick; above towards the bladder it hath an hole by which the Courſes flow out. And he alſo addeth, that he obſerved it in two young Virgins, and in one elder Maid.

Avicen writes, that in Virgins in the neck of the Womb there are Tunicles compoſed of Veins and Ligaments very little, riſing from each part of the neck thereof, which at the firſt time of copulation are wont to be broken, and the bloud run out. *Almanſor* writeth, that in Virgins the paſſage of the neck of the Womb is very wrinkled, or narrow and ſtrait, and thoſe wrinkles to be woven or ſtaid together with many little veins and arteries, which are broken at the firſt time of copulation. *Lib. 3 ſent. 21. Tract. 1. cap. 1.*

The triſles of Midwives about the membrane called *Hymen.*

Theſe are the judgments of Phyſicians of this membrane: Midwives will certainly affirm that they know a Virgin from one that is defloured, by the breach or ſoundneſs of that membrane. But by their report, too credulous Judges are ſoon brought to commit an errour. For that Midwives can ſpeak nothing certainly of this membrane, may be proved by this, becauſe that one ſaith that the ſituation thereof is in the very entrance of the privy parts, others ſay it is in the midſt of the neck of the Womb, and others ſay it is within at the inner orifice thereof, and ſome are of an opinion, that they ſay or ſuppoſe that it cannot be ſeen or perceived before the firſt birth. But truly of a thing ſo rare, and which is contrary to Nature, there cannot be any thing ſpoken for certainty. Therefore the bloud that cometh out at the firſt time of copulation, comes not always by the breaking of that membrane, but by the breaking and violating or renting of the little veins which are woven and beſpread all over the ſuperficial and inward parts of the Womb and neck thereof, deſcending into the wrinkles, which in thoſe that have not yet uſed the act of generation, are cloſed as if they were glewed together, although that thoſe Maids that are at their due time of marriage, feel no pain nor no flux of bloud, eſpecially if the mans Yard be anſwerable to the neck of the womb. Whereby it appears evidently how greatly the inhabitants of *Fez*, the Metropolitan City of *Mauritania* are deceived; for *Leo* the *African* writeth, that it is the cuſtom amongſt them, that ſo ſoon as the married man and his ſpouſe are returned home to their houſe from the Church where they have been married, they preſently ſhut themſelves into a Chamber, and make faſt the door, while the marriage dinner is preparing: in the mean while ſome old or grave Matron ſtandeth waiting before the Chamber to receive a bloudy linnen cloth the new married husband is to deliver her there; which when ſhe hath received, ſhe brings it into the midſt of all the company of gueſts, as a freſh ſpoil and teſtimony of the married wifes Virginity, and then for joy thereof they all fall to banquetting ſolemnly. But if through evil fortune it happeneth that in this time of copulation the ſpouſe bleedeth not in the privy parts, ſhe is reſtored again unto her Parents, which is a very great reproach unto them, and all the Gueſts depart home ſad, heavy, and without dinner.

What Virgins at the firſt time of copulation do not bleed at their privy parts. *Lib. 3.*

Moreover there are ſome, that having learned the moſt filthy and infamous Arts of Baudery, proſtitute common Harlots, make gain thereof, making men that are naughtily given to believe that they are pure Virgins, making them to think that the act of generation is very painful and grievous unto them, as if they had never uſed it before, although they are very expert therein indeed; for they do cauſe the neck of the Womb to be ſo wrinkled and ſhrunk together, ſo that the ſides thereof ſhall even almoſt cloſe or meet together; then they put thereinto the bladders of Fiſhes, or gall of Beaſts filled full of bloud, and ſo deceive the ignorant and young Letcher by the defraud and deceit of their evil Arts, and in time of copulation they mix ſighs with groans, and woman-like cryings, and Crocodiles tears, that they may ſeem to be Virgins, and never to have dealt with man before.

The filthy deceit of Bauds and Harlots.

CHAP. XLIII.

A memorable Hiſtory of the Membrane called Hymen.

John Wierus writeth that there was a Maid at *Camburge*, who in the midſt of the neck of the womb had a thick and ſtrong membrane growing overthwart, ſo that when the monethly Terms come out, it would not permit them, ſo that thereby the menſtrual matter was ſtopped and flowed back again, which cauſed a great tumor and diſtention in the belly, with great torment, as if ſhe had been in travel with child: the Midwives being called, and having ſeen and conſidered all that had been done, and did appear, did all with one voice affirm, that ſhe ſuſtained the pains of child-birth, although that the Maid her ſelf denied that ſhe ever dealt with man. Therefore then this foreſaid Author was called, who when the Midwives were void of counſel, might help this wretched Maid, having already had her urin ſtopt now three whole weeks, and perplexed with great watchings, loſs of appetite, and loathing: and when he had ſeen the grieved place, and marked the orifice of the neck of the womb, he ſaw it ſtopped with a thick membrane; he knew alſo that that ſudden breaking out of bloud into the Womb and the veſſels thereof, and the paſſage for thoſe matters that was ſtopped, was the cauſe of her grievous and tormenting pain. And therefore he called a Chirurgeon preſently, and willed him to divide the membrane that was in the midſt, that did ſtop the flux of bloud; which being done, there came forth as much black, congealed and putrefied bloud as weighed ſome eight pounds. In three days after ſhe was well and void of all diſeaſe and pain. I have thought it good to ſet down this example here, becauſe it is worthy to be noted, and profitable to be imitated, as the like occaſion ſhall happen. *Lib. de Proſt. damn. cap. 38.*

CHAP. XLIV.

Of the ſtrangulation of the Womb.

What is the ſtrangulation of the Womb.

THe ſtrangulation of the Womb, or that which cometh from the Womb, is an interception or ſtopping of the liberty in breathing or taking wind, becauſe that the Womb, ſwollen or puffed up by reaſon of the acceſs of groſs vapours and humours that are contained therein, and alſo ſnatched as it were by a convulſive motion, by reaſon that the veſſels and ligaments diſtended with fulneſs, are ſo carried upwards againſt the midriff and parts of the breſt, that it maketh the breath to be ſhort, and often as if a thing lay upon the breſt and preſſed it.

Why the womb ſwelleth.

The accidents that come of the ſtrangling of the womb.

Moreover the Womb ſwelleth, becauſe there is contained or incloſed in it a certain ſubſtance, cauſed by the defluxion either of the Seed or Flowers, or of the Womb or Whites, or of ſome other humour, tumor, abſceſs, rotten apoſtume, or ſome ill juice, putrefying or getting, or ingendring an ill quality, and reſolved into groſs vapours. Theſe, as they affect ſundry or divers places, infer divers or ſundry accidents, as rumbling and noiſe in the belly; if it be in the guts, deſire to vomit, after (with ſeldom vomiting) cometh wearineſs and loathing of meat, if it trouble the Stomach. Choaking with ſtrangulation, if it aſſail the breſt and throat; ſwooning, if it vex the heart; madneſs, or elſe that which is contrary thereto, ſound ſleep or drowſineſs, if it grieve the brain: all which oftentimes prove as malign as the biting of a mad dog, or equal the ſtingings or bitings of venomous beaſts.

Why the ſtrangulation that cometh of the corruption of the ſeed, is more dangerous than that that comes of the corruption of the bloud.

It hath been obſerved that more grievous ſymptoms have proceeded from the corruption of the Seed than of the menſtrual bloud. For by how much every thing is more perfect and noble, while it is contained within the bounds of the integrity of its own nature, by ſo much it is the more grievous and perilous, when by corruption it hath once tranſgreſſed the laws thereof. But this kind of accident doth very ſeldom grieve thoſe women which have their menſtrual flux well and orderly, and do uſe copulation familiarly; but very often thoſe women that have not their menſtrual flux as they ſhould, and do want and are deſtitute of husbands, eſpecially if they be great eaters, and lead a ſolitary life. When the veſſels and ligaments of the Womb are ſwollen and diſtended as we ſaid before, ſo much as is added to their latitude or breadth, ſo much is wanting in their length: and therefore it happeneth that the Womb, being removed out of its ſeat, doth one while fall to the right ſide towards the liver, ſometimes to the left towards the milt, ſometimes upwards unto the midriff and ſtomach, ſometimes downwards, and ſo forwards unto the bladder, whereof cometh an Iſchury and Strangury; or backwards, whereof cometh oppreſſion of the ſtraight Gut, and ſuppreſſion of the excrements, and the *Teneſmus*.

The cauſe of the divers turnings of the womb into divers parts of the body.

The womb is not ſo greatly moved by an accident, but by it ſelf.

But although we acknowledge the womb to decline to thoſe parts which we named, yet it is not by accident onely, as when it is drawn by the proper and common ligaments and bands, when they are contracted or made ſhorter, being diſtended with fulneſs, but alſo of it ſelf, as when it is forced or provoked through the grief of ſomething contrary to Nature that is contained therein: it wandreth ſometimes unto one ſide, and ſometimes unto another part with a plain and evident natural motion, like unto the ſtomach which embraceth any thing that is gentle and mild, but avoideth any thing that is offenſive and hurtful; yet we deny that ſo great accidents may be ſtirred up by the falling of it alone unto this or that ſide, for then it might happen that women that are great with child, whoſe wombs are ſo diſtended by reaſon that the child is great, that it doth preſs the midriff, might be troubled with a ſtrangulation like unto this; but much rather by a venomous humour breathing out a malign and groſs vapour, not only by the veins and arteries, but alſo by the pores that are inviſible, which pollutes the faculties of the parts which it toucheth with its venomous malignity and infection, and intercepts the functions thereof. Neither doth the variety of the parts receiving onely, but alſo of the matter received, cauſe variety of accidents.

Whereof come ſuch divers accidents of ſtrangulation of the womb.

The cauſe of ſleepineſs in the ſtrangulation of the womb.

For ſome accidents come by ſuppreſſion of the terms, others come by corruption of the Seed; but if the matter be cold, it bringeth a drowſineſs, being lifted up unto the brain, whereby the woman ſinketh down as if ſhe were aſtoniſhed, and lieth without motion and ſenſe or feeling, and the beating of the arteries, and the breathing are ſo ſmall, that ſometimes it is thought they are not at all, but that the woman is altogether dead. If it be more groſs, it inferreth a convulſion; if it participate of the nature of a groſs melancholick humour, it bringeth ſuch heavineſs, fear and ſorrowfulneſs, that the party that is vexed therewith ſhall think that ſhe ſhall die preſently, and cannot be brought out of her mind by any means or reaſon; if of a cholerick humour, it cauſeth the madneſs called *Furor Uterinus*, and ſuch a prating that they ſpeak all things that are to be concealed; and a giddineſs of the head, by reaſon that the animal ſpirit is ſuddenly ſhaken by the admixtion of a putrefied vapour and hot ſpirit: but nothing is more admirable, than that this diſeaſe taketh the Patient ſometimes with laughing, and ſometimes with weeping; for ſome at the firſt will weep and then laugh in the ſame diſeaſe and ſtate thereof.

The cauſe of drowſie madneſs.

An Hiſtory.

But it exceedeth all admiration which *Hollerius* writeth, uſually happened to two of the daughters of the Provoſt of *Roven*. For they were held with long laughter for an hour or two before the fit, which neither for fear, admonition, nor for any other means they could hold; and their Parents chid them, and asked them wherefore they did ſo, they anſwered that they were not able to ſtay their laughter. The aſcenſion of the Womb is diligently to be diſtinguiſhed from the ſtrangulation thereof; for the accidents of the aſcenſion and of the ſtrangulation are not one, but the woman is onely oppreſſed with a certain pain of the heart, difficulty of breathing or ſwouning, but yet without fear, without raving or idle talking, or any other greater accident.

The aſcenſion of the womb is to be diſtinguiſhed from the ſtrangulation.

Therefore oftentimes contrary cauſes infer the aſcenſion: that is, overmuch drineſs of the Womb, labouring through the defect of moiſture, whereby it is forced after too violent and immoderate

eva-

evacuations of the Flowers, and in Child-bed, and ſuch like, and laborious and painful travel in Child-bed, through which occaſion it waxeth hot, contrary to Nature, and withereth and turneth it ſelf with a certain violence unto the parts adjoining, that is to ſay, unto the Liver, Stomach and Midriff: if happily it may draw ſome moiſture there-hence unto it. I omit that the Womb may be brought unto its place upwards by often ſmelling to aromatick things, yet in the mean while it inſers not the ſtrangulation that we deſcribed before.

CHAP. XLV.

The ſigns of imminent ſtrangulation of the Womb.

BEfore that theſe fore-named accidents come, the Woman thinks that a certain painful thing ariſeth from her Womb unto the orifice of the ſtomach and heart, and ſhe thinketh her ſelf to be oppreſſed and choaked, ſhe complaineth her ſelf to be in great pain, and that a certain lump or heavy thing climbs up from the lower parts unto her throat, and ſtoppeth her wind, her heart burneth and panteth. And in many the Womb and Veſſels of the Womb ſo ſwell, that they cannot ſtand upright on their legs, but are conſtrained to lie down flat on their bellies, that they may be the leſs grieved with the pain, and to preſs that down ſtrongly with their hands that ſeemeth to ariſe upwards, although that not the Womb it ſelf, but the vapour aſcendeth from the Womb as we ſaid before: but when the fit is at hand, their faces are pale on a ſudden, their underſtanding is darkened, they become ſlow and weak in the legs, with unableneſs to ſtand. Hereof cometh ſound ſleep, fooliſh talking, interception of the ſenſes and breath, as if they were dead, loſs of ſpeech, the contraction of their legs, and the like.

The Womb it ſelf doth not ſo well make the aſcenſion as the vapour thereof.

CHAP. XLVI.

How to know whether the Woman be dead in the ſtrangulation of the Womb, or not.

IHave thought it meet (becauſe many Women, not onely in ancient Times, but in our own and our Fathers memory have been ſo taken with this kind of ſymptom, that they have been ſuppoſed and laid out for dead, although truly they were alive:) to ſet down the ſigns in ſuch a caſe which do argue life and death. Therefore firſt of all it may be proved whether ſhe be alive or dead, by laying or holding a clear and ſmooth Looking-glaſs before her mouth and noſtrils. For if ſhe breath, although it be never ſo obſcurely, the thin vapour that cometh out, will ſtain or make the Glaſs dusky. Alſo a fine downiſh feather taken from under the wing of any Bird, or elſe a fine flock being held before the mouth, will by the trembling or ſhaking motion thereof, ſhew that there is ſome breath, and therefore life remaining in the body. But you may prove moſt certainly whether there be any ſpark of life remaining in the body, by blowing ſome ſneezing powders of Pellitory of *Spain*, and Hellebore in the noſtrils. But though there no breath appear, yet muſt you not judge the woman for dead, for the ſmall vital heat, by which being drawn into the heart, ſhe yet liveth, is contented with tranſpiration onely, and requires not much attraction, which is performed by the contraction and dilatation of the Breſt and Lungs unto the preſervation of it ſelf. For ſo Flies, Gnats, Piſmires, and ſuch like, becauſe they are of a cold temperature, live unmoveably incloſed in the caves of the earth, no token of breathing appearing in them, becauſe there is a little heat left in them, which may be conſerved by the office of the arteries and heart, that is to ſay, by perſpiration, without the motion of the breſt, becauſe the greateſt uſe of reſpiration is, that the inward heat may be preſerved by refrigeration and ventilation. Thoſe that do not mark this, fall into that error which almoſt coſt the life of him who in our time firſt gave life to Anatomical adminiſtration, that was almoſt decaied and neglected.

Women living taken for dead.

How Women that have the ſuffocation of the Womb, live onely by tranſpiration without breathing.

How Flies, Gnats, and Piſmires do live all the Winter without breathing.

For he being called in *Spain* to open the body of a Noble-woman which was ſuppoſed dead through ſtrangulation of the Womb, behold at the ſecond impreſſion of the Inciſion-knife, ſhe began ſuddenly to come to her ſelf, and by the moving of her members and body, which was ſuppoſed to be altogether dead, and with crying, to ſhew manifeſt ſigns that there was ſome life remaining in her. Which thing ſtruck ſuch an admiration and horrour into the hearts of all her friends that were preſent, that they accounted the Phyſician, being before of a good fame and report, as infamous, odious, and deteſtable, ſo that it wanted but little but that they would have ſcratched out his eyes preſently: wherefore he thought there was no better way for him, if he would live ſafe, then to forſake the Countrey. But neither could he ſo alſo avoid the horrible prick and inward wound of his Conſcience (from whoſe judgment no offender can be abſolved) for his inconſiderate dealing, but within few days after being conſumed with ſorrow, he died, to the great loſs of the Commonwealth, and the Art of Phyſick.

An Hiſtory.

CHAP. XLVII.

How to know whether the ſtrangulation of the Womb comes of the ſuppreſſion of the Flowers, or the corruption of the Seed.

THere are two chief cauſes eſpecially, as moſt frequently happening, of the ſtrangulation of the Womb: but when it proceedeth from the corruption of the Seeds all the accidents are more grievous and violent: difficulty of breathing goes before, and ſhortly after comes depriVation thereof; the whole habit of the body ſeemeth more cold than a ſtone: the Woman is a Widow, or elſe hath great ſtore or abundance of Seed, and hath been uſed to the company of a man, by the

The ſigns of ſuffocation of the Womb coming of corrupt ſeed.

the abſence whereof ſhe was before wont to be pained with heavineſs of the head, to loath her meat, and to be troubled with ſadneſs or fear, but chiefly with melancholy. Moreover, when ſhe hath ſatisfied, and every way fulfilled her luſt, and then preſently on a ſudden begins to contain her ſelf; it is very likely that ſhe is ſuffocated by the ſuppreſſion of the Flowers, which formerly had them well and ſufficiently, which formerly had been fed with hot, moiſt and many meats, therefore engendring much bloud, which ſitteth much, which is grieved with ſome weight and ſwelling in the region of the belly, with pain in the ſtomach, and a deſire to vomit, and with ſuch other accidents as come by the ſuppreſſion of the Flowers. Thoſe who are freed from the fit of the ſuffocation of the womb, either by Nature or by Art, in a ſhort time their colour cometh into their faces by little and little, and the whole body beginneth to wax ſtrong, and the teeth, that were ſet and cloſed faſt together, begin (the jaws being looſed) to open and uncloſe again; and laſtly, ſome moiſture floweth from the ſecret parts with a certain tickling pleaſure; but in ſome women, as in thoſe eſpecially in whom the neck of the womb is tickled with the Midwifes finger, in ſtead of that moiſture comes thick and groſs ſeed, which moiſture or ſeed when it is fallen, the womb being before as it were raging, is reſtored unto its own proper nature and place, and by little and little all ſymptoms vaniſh away. Men by the ſuppreſſion of their ſeed have not the like ſymptoms as women have, becauſe Mans ſeed is not ſo cold and moiſt, but far more perfect and better digeſted, and therefore more meet to reſiſt putrefaction, and whileſt it is brought or drawn together by little and little, it is diſſipated by great and violent exerciſe.

The ſigns when it comes of the ſuppreſſion of the Flowers.

The ſigns of one recovering of or from the ſuffocation of the Womb.

Why the ſuppreſſion of the ſeed is not perilous or deadly to men.

CHAP. XLVIII.

Of the Cure of the Strangulation of the Womb.

The pulling of the hairs of the lower parts are profitable both for this malady and for the cauſe of the ſame.

SEeing that the ſtrangulation of the womb is a ſudden and ſharp diſeaſe, it therefore requireth a preſent and ſpeedy remedy; for if it be neglected, it many times cauſeth preſent death. Therefore when this malady cometh, the ſick woman muſt preſently be placed on her back, having her breſt and ſtomach looſe, and all her cloaths and garments ſlack and looſe about her, whereby ſhe may take breath the more eaſily; and ſhe muſt be called on by her own name with a loud voice in her ears, and pulled hard by the hairs of the temples and neck, but yet eſpecially by the hairs of the ſecret parts, that by provoking or cauſing pain in the lower parts, the Patient may not onely be brought to her ſelf again, but alſo that the ſharp and malign vapour aſcending upwards, may be drawn downwards: the legs and arms muſt be bound and tied with painful ligatures, all the body muſt be rubbed over with rough linnen cloths beſprinkled with Salt and Vinegar, until it be very ſore and red; and let this peſſary following be put into the womb. ℞ *Succi mercur. artemiſ. an.* ℥ ij. *in quibus diſſolve pul. bened.* ʒ iij. *pul. radic. enulæ camp. galang. minor. an.* ʒ j. make thereof a peſſary. Then let the ſoals of her feet be anointed with Oil of Bays, or with ſome ſuch like Oil; let a great cupping-glaſs with a great flame be applied to the belly below the navel, to the inner part of the thigh, and to the groin, whereby both the matter that climbs upwards, and alſo the womb it ſelf running the ſame way, may be brought downwards or drawn back. There may be made a fumigation of Spices to be received up into the womb, which that it may the eaſier be done, the womb may be held open by putting in the Inſtrument here following deſcribed, into the neck thereof. Let it be made of gold, ſilver, or lattin, into the form of a peſſary; at the one end thereof, that is to ſay, that end which goeth up into the neck of the womb, let there be made many holes on each ſide, but at the lower end let it be made with a Spring, that it may open and ſhut as you will have it. Alſo it muſt have two Laces or Bands by which it muſt be made faſt into a Swathe or Girdle tied about the Patients belly.

A Peſſary.

The matter of ſweet fumigations.

By what power ſweet Fumigations do reſtore the womb unto its own nature and place.

The matter and ingredients of ſweet and aromatick fumigations, are Cinamon, Calam. Aromat. Lig. Aloes, Ladanum, Benzoin, Thyme, Pepper, Cloves, Lavander, Calamint, Mugwort, Penni-royal, *Alepta moſchat.* Nutmegs, Musk, Amber, Squinant, and ſuch like, which for their ſweet ſmell and ſympathy, allure or intice the womb downwards, by their heat conſume and digeſt the thick vapours and putrefied ill juice. Contrariwiſe, let the noſtrils be perfumed with fetid and rank ſmells, and let theſe be made with *Gum. galbanum, ſagapenum, ammoniacum, aſſa fœtida, bitumen*, oil of Jeat, ſnuff of a Tallow-candle when it is blown out, with the fume of Birds Feathers, eſpecially of Partridges or Woodcocks, of Mans hair, or Goats hair, of old Leather, of Horſe-hoofs, and ſuch like things burned, whoſe noiſom or offenſive ſavour the womb avoiding, doth return unto its own place or ſeat again.

Stinking ſmels to be applied to the noſtrils.

Avicens ſecret for ſuffocation of the Womb.

Moreover it ſhall be very neceſſary to procure vomit by thruſting a Gooſe-feather down into the throat, or elſe the hairs of the Patients own head. Shortly after ſhe muſt uſe a potion of fifteen grains of black Pepper bruiſed and diſſolved in *hydromel*, or water and honey mixed together, or in ſome ſtrong Wine, which remedy *Avicen* holdeth for a ſecret.

Caſtoreum drunken.

Expreſſions into the womb

Alſo in ſtead thereof three hours before meat ʒ ß of Treacle diſſolved in ℥ j. of the water of Wormwood may be given her: alſo it is thought that one drop of the oil of Jeat dropped on the tongue, is a very profitable remedy. There be ſome that allow a potion of half a dram of *Caſtoreum* diſſolved in white Wine, or in the Broth of a Capon; alſo it is profitable not onely to give her Treacle to drink, but alſo to inject it into the womb, being firſt diſſolved in *Aqua vitæ*, and in the mean time to drop two drops of oil of Sage, or ſome ſuch Chymical Oil, into the ears. If ſhe be drowſie or ſleepy, ſhe muſt be awaked or kept waking with ſneezing powders of white Hellebore and Pellitory.

It is alſo requiſite to inject Clyſters both into the fundament and ſecret parts, which muſt be made of the decoction of things that diſcuſs wind, as of Calamint, Mugwort, Lavander, Penni-royal, Camomil, Melilot, and ſuch like; and let peſſaries or ſuppoſitories be made of Ladanum, Ginger, *Gallia moſchat.* Treacle, Mithridate, Civet, and Musk, of the oil of Cloves, Anniſeeds, Sage, Roſemary, and ſuch like,

The matter of Peſſaries.

like, chymically drawn; this following is a convenient deſcriptiou of a Clyſter. ℞ *Radic. emulæ, camp. Iræos, ebuli, ariſtoloch.* an. ʒ j. *fol. abſynth. artemiſiæ, matricar. puleg. origani,* an. m.j. *baccarum lauri, juniperi & ſambuc.* an. p.j. *ſem. amnios, cymini, rutæ,* an. ʒ ij. *florum ſtœchados, roriſmar. ſalviæ, centaur. minor.* an. p.ij. *fiat decoctio, cape colaturæ,* ℔ j. *in qua diſſolve mellis anthoſati, ſacc. rubr. & bened.* an. ʒ j. *diacharth.* ʒ ij. *olei aneth. nard.* an. ʒ j. ß. make thereof a Clyſter, and apply this plaſter following to the belly. ℞ *Maſp. empl. oxycrocei, & melilot.* an. ʒ iij. *olei nard.* as much as ſhall ſuffice to make it conveniently ſoft: make thereof a plaſter, and ſpread it on a leather, and apply it to the region of the belly when the fit is ended: if ſhe be married, let her forthwith uſe copulation, and be ſtrongly encountred by her husband, for there is no remedy more preſent than this.

A Clyſter ſcattering groſs vapours.

A quick, certain, and a pleaſant remedy for the ſuffocation of the Womb.

The deſcription of a Veſſel made with a Funnel or Pipe for to fumigate the Womb.

The form of a Peſſary to be put in the neck of the Womb, to hold it open.



Let the Midwife anoint her fingers with *oleum nardinum*, or *moſchetalinum*, or of Cloves, or elſe of Spike mixed with Musk, Ambergreece, Civet, and other ſweet Powders, and with theſe let her rub and tickle the top of the neck of the womb which toucheth the inner orifice, but her ſecret parts muſt firſt be warmed by the applying of warm linnen cloths, for ſo at length the venomous matter contained in the womb, ſhall be diſſolved and flow out, and the malign, ſharp, and flatulent vapours, whereby the womb is driven as it were into a fury or rage, ſhall be reſolved and diſſipated, and ſo when the conjunct matter of the diſeaſe is ſcattered and waſted, the womb, and alſo the Woman ſhall be reſtored unto themſelves again. Some hold it for a ſecret to rub the Navel with the juice of Garlick boiled and mixed with Aloes.

Tickling of the neck of the Womb.

CHAP. XLIX.

Of Womens Monethly Flux or Courſes.

USually they call the flux of bloud that iſſueth from the ſecret parts of Women, Monethly Flowers or Courſes, becauſe it happeneth to them every Moneth ſo long as they are in health. There be ſome which call them Terms, becauſe they return at their uſual time. Many of the French men call it *Sepmains*, becauſe in ſuch as ſit much, and are given to plentiful feeding, it endureth almoſt for the ſpace of ſeven days. Some call them purgations, becauſe that by this flux all a Womans body is purged of ſuperfluous humours. There be ſome alſo that call thoſe Fluxes the Flowers, becauſe that as in Plants the flower buddeth out before the fruits; ſo in Women-kind the Flux goeth before the iſſue, or the conception thereof.

The reaſon of the names of the monethly flux of women

For the Courſes flow not before a Woman be able to conceive, for how ſhould the ſeed being caſt into the Womb have his nouriſhment and increaſe, and how ſhould the child have his nouriſhment when it is formed of the ſeed, if this neceſſary humour were wanting in the womb? yet it may be

ſome

What women do conceive, this flux not appearing at all.

ſome Women may conceive without the flux of the Courſes: but that is in ſuch as have ſo much of the humour gathered together, as is wont to remain in thoſe which are purged, although it be not ſo great a quantity that it may flow out, as it is recorded by *Ariſtotle*. But as it is in ſome very great, and in ſome very little, ſo it is in ſome ſeldom, and in ſome very often.

What women have this menſtrual flux often, abundantly, and for a longer ſpace than others.

There are ſome that are purged twice, and ſome thrice in a moneth, but it is altogether in thoſe who have a great Liver, large Veins, and are filled and fed with many and greatly nouriſhing meats, which ſit idlely at home all day, which having ſlept all night, do notwithſtanding lie in bed ſleeping a great part of the day alſo, which live in a hot, moiſt, rainy and ſoutherly air, which uſe warm baths of ſweet waters and gentle frictions, which uſe and are greatly delighted with carnal copulation: in theſe and ſuch like Women, the Courſes flow more frequently and abundantly.

What women have this flux more ſeldom, leſs, and a far more ſhort time than others.

But contrariwiſe, thoſe that have ſmall and obſcure veins, and thoſe that have their bodies more furniſhed and big either with fleſh or with fat, are more ſeldom purged, and alſo more ſparingly, becauſe that the ſuperfluous quantity of bloud uſeth to go into the habit of the body. Alſo tender, delicate and fair Women are leſs purged than thoſe that are brown, and endued with a more compact fleſh, becauſe that by the rarity of their bodies, they ſuffer a greater waſting or diſſipation of their ſubſtance by tranſpiration. Moreover, they are not ſo greatly purged with this kind of purgation, which have ſome other ſolemn or accuſtomed evacuation in any other place of their body, as by the noſe or Hæmorrhoids.

Why young women are purged in the new of the Moon.

And as concerning their Age, old women are purged when the Moon is old, and young women when the Moon is new, as it is thought. I think the cauſe thereof is, for that the Moon ruleth moiſt bodies; for by the variable motion thereof the Sea floweth and ebbeth; and Bones, Marrow, and Plants abound with their genital humour.

Therefore young people which have much bloud, and more fluxible, and their bodies more fluxible, are ſoon moved unto a flux, although it be even in the firſt quarter of the Moons riſing or increaſing: but the humours of old women, becauſe they wax ſtiff as it were with cold, and are not ſo abundant, and have more denſe bodies and ſtraighter veſſels, are not ſo apt to a flux, nor do they ſo eaſily flow, except it be in the full of the Moon, or elſe in the decreaſe; that is to ſay, becauſe the bloud that is gathered in the full of the Moon falls from the body even of its own weight, for that by reaſon of the decreaſing or wane of the Moon, this time of the Moneth is more cold and moiſt.

Why old women are purged in the wane of the Moon.

CHAP. L.

The Cauſes of the Monethly Flux or Courſes.

The material cauſe of the Monethly flux.

BEcauſe a woman is more cold, and therefore hath the digeſtive faculty more weak, it cometh to paſs, that ſhe requireth and deſireth more meat or food than ſhe can digeſt or concoct. And becauſe that ſuperfluous humour that remaineth is not digeſted by exerciſe, nor by the efficacy of ſtrong and lively heat, therefore by the providence or benefit of Nature, it floweth out by the veins of the womb, by the power of the expulſive faculty, as its own certain and prefixed ſeaſon or time. But then eſpecially it beginneth to flow, and a certain rude portion of bloud to be expelled, being hurtful and malign otherwiſe in no quality, when Nature hath laid her principal foundations of the increaſe of the body, ſo that in greatneſs of the body ſhe hath come as it were in a manner to the higheſt top, that is to ſay, from the thirteenth to the fiftieth year of her age.

When the Monethly flux begins to flow.

The final cauſe.

Moreover, the child cannot be formed in the womb, nor have his nutriment or increaſe without this flux: therefore this is another final cauſe of the monethly flux. Many are perſuaded that women do far more abound with bloud than men, conſidering how great an abundance of bloud they caſt forth of their ſecret parts every moneth, from the thirteenth to the fiftieth year of their age: how much women great with child, of whom alſo many are menſtrual, yield unto the nutriment and increaſe of the child in their wombs, and how much Phyſicians take from women that are with child by opening of a vein, which otherwiſe would be delivered before their natural and prefixed time; how great a quantity thereof they avoid in the birth of their children, and for ten or twelve days after, and how great a quantity of milk they ſpend for the nouriſhment of the child when they give ſuck, which milk is none other thing than bloud made white by the power of the kernels that are in the dugs, which doth ſuffice to nouriſh the child, be he great or little; yet notwithſtanding many Nurſes in the mean while are menſtrual: and as that may be true, ſo certainly this may be true, that one dram (that I may ſo ſpeak) of a mans bloud is of more efficacy to nouriſh and increaſe, than two pounds of woman's bloud, becauſe it is far more perfect, more concocted, wrought, and better repleniſhed with abundance of ſpirits: whereby it cometh to paſs that a man endued with a more ſtrong heat, doth more eaſily convert what meat ſoever he eateth unto the nouriſhment and ſubſtance of his body; and if that any ſuperfluity remains he doth eaſily digeſt and ſcatter it by inſenſible tranſpiration. But a woman being more cold than a man, becauſe ſhe taketh more than ſhe can concoct, doth gather together more humors, which becauſe ſhe cannot diſperſe, by reaſon of the unperfectneſs and weakneſs of her heat, it is neceſſary that ſhe ſhould ſuffer, and have her monthly purgation, eſpecially when ſhe groweth unto ſome bigneſs: but there is no ſuch need in a man.

A woman exceeds a man in quantity of bloud.

A man exceedeth a woman in the quality of his bloud.

A man is more hot than a woman, and therefore not menſtrual.

CHAP.

CHAP. LI.

The causes of the suppression of the Courses or Menstrual Flux.

THE Courses are suppressed or stopped by many causes, as by sharp, vehement, and long diseases, by fear, sorrow, hunger, immoderate labours, watchings, fluxes of the belly, great bleeding, hæmorrhoids, fluxes of bloud at the mouth, and evacuations in any other part of the body whatsoever, often opening of a Vein, great sweats, ulcers flowing much and long, scabbiness of the whole skin, immoderate grosness and clamminess of the bloud, and by eating of raw fruits, and drinking of cold water, by sluggishness and thickness of the vessels, and also the obstruction of them by the defaults and diseases of the womb, by distemperature, an abscess, an ulcer, by the obstruction of the inner orifice thereof, by the growing of a callus, caruncle, cicatrize of a wound or ulcer, or membrane growing there, by injecting of astringent things into the neck of the womb, which place many women endeavour foolishly to make narrow: I speak nothing of age, greatness with child, and nursing of children, because these causes are not besides nature, neither do they require the help of the Physician.

The foolish endeavour of making the orifice of the womb narrow is rewarded with the discommodity of stopping of the Flowers.

Many Women, when their Flowers or Terms be stopped, degenerate after a manner into a certain manly nature, whence they are called *Viragines*, that is to say, stout, or manly Women; therefore their voice is more loud and big, like unto a mans, and they become bearded.

What women are called *Viragines*.

In the City *Abdera* (saith *Hippocrates*) *Phaethusa* the wife of *Pytheas* at the first did bear children and was fruitful, but when her husband was exiled, her Flowers were stopped for a long time: but when these things happened, her body became manlike and rough, and had a beard, and her voice was great and shrill. The very same thing happened to *Namysia* the wife of *Gorgippus* in *Thasus*. Those Virgins that from the beginning have not their Monethly flux, and yet nevertheless enjoy their perfect health, they must necessarily be hot and dry, or rather of a manly heat and driness, that they may so disperse and dissipate by transpiration, as men do, the excrements that are gathered; but verily all such are barren.

Lib. 6. Epidem. sect. 7.

The women that are called *Viragines* are barren.

CHAP. LII.

What accidents follow the suppression or stopping of the Monethly Flux or Flowers.

WHen the Flowers or monethly Flux are stopped, Diseases affect the Womb, and from thence pass into all the whole body. For thereof cometh Suffocation of the Womb, Head-ach, Swouning, beating of the Heart, and swelling of the breasts and secret parts, inflammation of the Womb, an Abscess, Ulcer, Cancer, a Fever, Nauseousness, Vomitings, difficult and slow concoction, the Dropsie, Strangury, the full Womb pressing upon the orifice of the bladder, black and bloudy Urin, by reason that portion of the bloud sweateth out into the bladder. In many Women the stopped matter of the Monethly Flux is excluded by Vomiting, Urin, and the Hæmorrhoids, in some it groweth into *Varices*. In my Wife when she was a Maid, the Menstrual matter was excluded and purged by the Nostrils. The Wife of *Peter Feure* of *Castleaudun*, was purged of her Menstrual matter by the Dugs every moneth, and in such abundance, that scarce three or four cloaths were able to dry it and suck it up.

Why the strangury, or bloudiness of the Urin followeth the suppression of the Flowers. Histories of such as were purged of their Menstrual flux by the Nose and Dugs.

In those that have not the Flux monethly to evacuate this plenitude by some part or place of the body, there often follows difficulty of breathing, Melancholy, Madness, the Gout, an ill disposition of the whole body, dissolution of the strength of the whole body, want of appetite, a Consumption, the Falling-sickness, an Apoplexy.

Those whose bloud is laudable, yet not so abundant, do receive no other discommodity by the suppression of the Flowers, unless it be that the Womb burns or itcheth with the desire of copulation, by reason that the Womb is distended with hot and itching bloud, especially if they lead a sedentary life. Those Women that have been accustomed to bear children, are not so grieved and evil at ease when their Flowers are stopped by any chance contrary to Nature, as those Women which did never conceive, because they have been used to be filled; and the vessels by reason of their customary repletion and distention are more large and capacious: when the Courses flow, the appetite is partly dejected, for that Nature being then wholly applied to expulsion, cannot throughly concoct or digest; the Face waxeth pale and without its lively colour, because that the heat with the spirits, go from without inwards, so to help and aid the expulsive faculty.

To what women the suppression of the Moneths is most grievous.

CHAP. LIII.

Of provoking the Flowers or Courses.

THE suppression of the Flowers is a plethorick Disease, and therefore must be cured by evacuation, which must be done by opening the Vein called *Saphena*, which is at the ankle, but first let the basilick Vein of the arm be opened, especially if the body be plethorick, lest that there should a greater attraction be made into the Womb, and by such attraction or flowing in, there should come a greater obstruction. When the Veins of the Womb are distended with so great a swelling that they may be seen, it will be very profitable to apply Horse-leeches to the neck thereof: Pessaries for Women may be used, but fumigations of aromatick things are more meet for Maids, because they are bashful and shame-faced. Unguents, Liniments, Emplasters, Cataplasms that serve for that matter, are to be prescribed and applied to the secret parts; Ligatures and Fri-

Why the Vein called *Basilica* in the arm must be opened before the Vein *Saphena* in the foot.

Horse leeches to be applied to the neck of the Womb.

What women do conceive, this flux not appearing at all.

ſome Women may conceive without the flux of the Courſes: but that is in ſuch as have ſo much of the humour gathered together, as is wont to remain in thoſe which are purged, although it be not ſo great a quantity that it may flow out, as it is recorded by *Ariſtotle*. But as it is in ſome very great, and in ſome very little, ſo it is in ſome ſeldom, and in ſome very often.

What women have this menſtrual flux often, abundantly, and for a longer ſpace than others.

There are ſome that are purged twice, and ſome thrice in a moneth, but it is altogether in thoſe who have a great Liver, large Veins, and are filled and fed with many and greatly nouriſhing meats, which ſit idlely at home all day, which having ſlept all night, do notwithſtanding lie in bed ſleeping a great part of the day alſo, which live in a hot, moiſt, rainy and ſoutherly air, which uſe warm baths of ſweet waters and gentle frictions, which uſe and are greatly delighted with carnal copulation: in theſe and ſuch like Women, the Courſes flow more frequently and abundantly.

What women have this flux more ſeldom, leſs, and a far more ſhort time than others.

But contrariwiſe, thoſe that have ſmall and obſcure veins, and thoſe that have their bodies more furniſhed and big either with fleſh or with fat, are more ſeldom purged, and alſo more ſparingly, becauſe that the ſuperfluous quantity of bloud uſeth to go into the habit of the body. Alſo tender, delicate and fair Women are leſs purged than thoſe that are brown, and endued with a more compact fleſh, becauſe that by the rarity of their bodies, they ſuffer a greater waſting or diſſipation of their ſubſtance by tranſpiration. Moreover, they are not ſo greatly purged with this kind of purgation, which have ſome other ſolemn or accuſtomed evacuation in any other place of their body, as by the noſe or Hæmorrhoids.

Why young women are purged in the new of the Moon.

And as concerning their Age, old women are purged when the Moon is old, and young women when the Moon is new, as it is thought. I think the cauſe thereof is, for that the Moon ruleth moiſt bodies; for by the variable motion thereof the Sea floweth and ebbeth; and Bones, Marrow, and Plants abound with their genital humour.

Why old women are purged in the wane of the Moon.

Therefore young people which have much bloud, and more fluxible, and their bodies more fluxible, are ſoon moved unto a flux, although it be even in the firſt quarter of the Moons riſing or increaſing: but the humours of old women, becauſe they wax ſtiff as it were with cold, and are not ſo abundant, and have more denſe bodies and ſtraighter veſſels, are not ſo apt to a flux, nor do they ſo eaſily flow, except it be in the full of the Moon, or elſe in the decreaſe; that is to ſay, becauſe the bloud that is gathered in the full of the Moon falls from the body even of its own weight, for that by reaſon of the decreaſing or wane of the Moon, this time of the Moneth is more cold and moiſt.

CHAP. L.

The Cauſes of the Monethly Flux or Courſes.

The material cauſe of the Monethly flux.

BEcauſe a woman is more cold, and therefore hath the digeſtive faculty more weak, it cometh to paſs, that ſhe requireth and deſireth more meat or food than ſhe can digeſt or concoct. And becauſe that ſuperfluous humour that remaineth is not digeſted by exerciſe, nor by the efficacy of ſtrong and lively heat, therefore by the providence or benefit of Nature, it floweth out by the veins of the womb, by the power of the expultive faculty, as its own certain and prefixed ſeaſon or time.

When the Monethly flux begins to flow.

But then eſpecially it beginneth to flow, and a certain rude portion of bloud to be expelled, being hurtful and malign otherwiſe in no quality, when Nature hath laid her principal foundations of the increaſe of the body, ſo that in greatneſs of the body ſhe hath come as it were in a manner to the higheſt top, that is to ſay, from the thirteenth to the fiftieth year of her age.

The final cauſe.

Moreover, the child cannot be formed in the womb, nor have his nutriment or increaſe without this flux: therefore this is another final cauſe of the monethly flux.

A woman exceeds a man in quantity of bloud.

Many are perſuaded that women do far more abound with bloud than men, conſidering how great an abundance of bloud they caſt forth of their ſecret parts every moneth, from the thirteenth to the fiftieth year of their age: how much women great with child, of whom alſo many are menſtrual, yield unto the nutriment and increaſe of the child in their wombs, and how much Phyſicians take from women that are with child by opening of a vein, which otherwiſe would be delivered before their natural and prefixed time; how great a quantity thereof they avoid in the birth of their children, and for ten or twelve days after, and how great a quantity of milk they ſpend for the nouriſhment of the child when they give ſuck, which milk is none other thing than bloud made white by the power of the kernels that are in the dugs, which doth ſuffice to nouriſh the child, be he great or little; yet notwithſtanding many Nurſes in the mean while are menſtrual: and as that may be true, ſo certainly this may be true, that one dram (that I may ſo ſpeak) of a mans bloud is of more efficacy to nouriſh and increaſe, than two pounds of womans bloud, becauſe it is far more perfect, more concocted, wrought, and better repleniſhed with abundance of ſpirits: whereby it cometh to paſs that a man endued with a more ſtrong heat, doth more eaſily convert what meat ſoever he eateth unto the nouriſhment and ſubſtance of his body; and if that any ſuperfluity remains he doth eaſily digeſt and ſcatter it by inſenſible tranſpiration. But a woman being more cold than a man, becauſe ſhe taketh more than ſhe can concoct, doth gather together more humors, which becauſe ſhe cannot diſperſe, by reaſon of the unperfectneſs and weakneſs of her heat, it is neceſſary that ſhe ſhould ſuffer, and have her monthly purgation, eſpecially when ſhe groweth unto ſome bigneſs: but there is no ſuch need in a man.

A man exceedeth a woman in the quality of his bloud. A man is more hot than a woman, and therefore not menſtrual.

CHAP.

CHAP. LI.

The cauſes of the ſuppreſſion of the Courſes or Menſtrual Flux.

THe Courſes are ſuppreſſed or ſtopped by many cauſes, as by ſharp, vehement, and long diſeaſes, by fear, ſorrow, hunger, immoderate labours, watchings, fluxes of the belly, great bleeding, hæmorrhoids, fluxes of bloud at the mouth, and evacuations in any other part of the body whatſoever, often opening of a Vein, great ſweats, ulcers flowing much and long, ſcabbineſs of the whole skin, immoderate groſsneſs and clammineſs of the bloud, and by eating of raw fruits, and drinking of cold water, by ſluggiſhneſs and thickneſs of the veſſels, and alſo the obſtruction of them by the defaults and diſeaſes of the womb, by diſtemperature, an abſceſs, an ulcer, by the obſtruction of the inner orifice thereof, by the growing of a callus, caruncle, cicatrize of a wound or ulcer, or membrane growing there, by injecting of aſtringent things into the neck of the womb, which place many women endeavour fooliſhly to make narrow: I ſpeak nothing of age, greatneſs with child, and nurſing of children, becauſe theſe cauſes are not beſides nature, neither do they require the help of the Phyſician.

The fooliſh endeavour of making the orifice of the womb narrow is rewarded with the diſcommodity of ſtopping of the Flowers.

Many Women, when their Flowers or Terms be ſtopped, degenerate after a manner into a certain manly nature, whence they are called *Viragines*, that is to ſay, ſtout, or manly Women; therefore their voice is more loud and big, like unto a mans, and they become bearded.

What women are called *Viragines*.

In the City *Abdera* (ſaith *Hippocrates*) *Phaethuſa* the wife of *Pytheas* at the firſt did bear children and was fruitful, but when her husband was exiled, her Flowers were ſtopped for a long time: but when theſe things happened, her body became manlike and rough, and had a beard, and her voice was great and ſhrill. The very ſame thing happened to *Namyſia* the wife of *Gorgippus* in *Thaſus*. Thoſe Virgins that from the beginning have not their Monethly flux, and yet nevertheleſs enjoy their perfect health, they muſt neceſſarily be hot and dry, or rather of a manly heat and drineſs, that they may ſo diſperſe and diſſipate by tranſpiration, as men do, the excrements that are gathered; but verily all ſuch are barren.

Lib. 6. Epidem. ſect. 7.

The women that are called *Viragines* are barren.

CHAP. LII.

What accidents follow the ſuppreſſion or ſtopping of the Monethly Flux or Flowers.

WHen the Flowers or monethly Flux are ſtopped, Diſeaſes affect the Womb, and from thence paſs into all the whole body. For thereof cometh Suffocation of the Womb, Head-ach, Swouning, beating of the Heart, and ſwelling of the breſts and ſecret parts, inflammation of the Womb, an Abſceſs, Ulcer, Cancer, a Fever, Nauſeouſneſs, Vomitings, difficult and ſlow concoction, the Dropſie, Strangury, the full Womb preſſing upon the orifice of the bladder, black and bloudy Urin, by reaſon that portion of the bloud ſweateth out into the bladder. In many Women the ſtopped matter of the Monethly Flux is excluded by Vomiting, Urin, and the Hæmorrhoids, in ſome it groweth into *Varices*. In my Wife when ſhe was a Maid, the Menſtrual matter was excluded and purged by the Noſtrils. The Wife of *Peter Feure* of *Caſteaudun*, was purged of her Menſtrual matter by the Dugs every moneth, and in ſuch abundance, that ſcarce three or four cloaths were able to dry it and ſuck it up.

Why the ſtrangury, or bloudineſs of the Urin followeth the ſuppreſſion of the Flowers.

Hiſtories of ſuch as were purged of their Menſtrual flux by the Noſe and Dugs.

In thoſe that have not the Flux monethly to evacuate this plenitude by ſome part or place of the body, there often follows difficulty of breathing, Melancholy, Madneſs, the Gout, an ill diſpoſition of the whole body, diſſolution of the ſtrength of the whole body, want of appetite, a Conſumption, the Falling-ſickneſs, an Apoplexy.

Thoſe whoſe bloud is laudable, yet not ſo abundant, do receive no other diſcommodity by the ſuppreſſion of the Flowers, unleſs it be that the Womb burns or itcheth with the deſire of copulation, by reaſon that the Womb is diſtended with hot and itching bloud, eſpecially if they lead a ſedentary life. Thoſe Women that have been accuſtomed to bear children, are not ſo grieved and evil at eaſe when their Flowers are ſtopped by any chance contrary to Nature, as thoſe Women which did never conceive, becauſe they have been uſed to be filled; and the veſſels by reaſon of their cuſtomary repletion and diſtention are more large and capacious: when the Courſes flow, the appetite is partly dejected, for that Nature being then wholly applied to expulſion, cannot throughly concoct or digeſt; the Face waxeth pale and without its lively colour, becauſe that the heat with the ſpirits, go from without inwards, ſo to help and aid the expulſive faculty.

To what women the ſuppreſſion of the Moneths is moſt grievous.

CHAP. LIII.

Of provoking the Flowers or Courſes.

THe ſuppreſſion of the Flowers is a plethorick Diſeaſe, and therefore muſt be cured by evacuation, which muſt be done by opening the Vein called *Saphena*, which is at the ankle, but firſt let the baſilick Vein of the arm be opened, eſpecially if the body be plethorick, leſt that there ſhould a greater attraction be made into the Womb, and by ſuch attraction or flowing in, there ſhould come a greater obſtruction. When the Veins of the Womb are diſtended with ſo great a ſwelling that they may be ſeen, it will be very profitable to apply Horſe-leeches to the neck thereof: Peſſaries for Women may be uſed, but fumigations of aromatick things are more meet for Maids, becauſe they are baſhful and ſhame-faced. Unguents, Liniments, Emplaſters, Cataplaſms that ſerve for that matter, are to be preſcribed and applied to the ſecret parts; Ligatures and Fri-

Why the Vein called *Baſilica* in the arm muſt be opened before the Vein *Saphena* in the foot.

Horſe leeches to be applied to the neck of the Womb.

ctions of the thighs and legs are not to be omitted, fomentations and ſternutatories are to be uſed, and Cupping-glaſſes are to be applied to the groins; walking, dancing, riding, often and wanton copulation with her husband, and ſuch like exerciſes, provoke the Flowers. Of Plants, the Flowers of St. *Johns* Wort, the Roots of Fennel, and Aſparagus, Bruſcus or Butchers-broom, or Parſly, Brooklime, Baſil, Balm, Betony, Garlick, Onions, Criſta Marina, Coſtmary, the Rind or Bark of Caſſia Fiſtula, Calamint, Origanum, Penniroyal, Mugwort, Thyme, Hyſſop, Sage, Marjoram, Roſemary, Hore-hound, Rue, Savin, Spurge, Saffron, Agarick, the Flowers of Elder, Bay-berries, the Berries of Ivy, Scammony, Cantharides, *Pyrethrum* or Pellitory of Spain, *Euphorbium*. The aromatick things are *Amomum*, Cinnamon, Squinanth, Nutmegs, *Calamus Aromaticus*, *Cyperus*, Ginger, Cloves, Galingal, Pepper, Cubibes, Amber, Musk, Spikenard, and ſuch like; of all which let Fomentations, Fumigations, Baths, Broths, Boles, Potions, Pills, Syrups, Apozems, and Opiats, be made as the Phyſician ſhall think good.

Plants that provoke the Flowers.

Sweet things.

The Apozeme that followeth is proved to be very effectual: ℞ *Fol. & flor. dictam. an.* p.ij. *pimpinel.* m. ſs. *omnium capillar. an.* p. j. *artemiſ. thymi, marjor. origan. an.* m. ß. *rad. rub. major. petroſelin. fœnicul. an.* ʒ j. ß. *rad. pæon. biſtort. an.* ʒ ſs. *cicerum rub. ſem. pæon. fœnicul. an.* ʒ ß. make thereof a decoction in a ſufficient quantity of Water, adding thereto Cinnamon ʒ iij. in one pint of the decoction diſſolve (after it is ſtrained) of the Syrup of Mugwort and of Hyſſop, *an.* ʒ. ij. *diarrhod. abbat.* ʒ j. let it be ſtrained through a bag, with ʒ ij. of the Kernels of Dates, and let her take ʒ iv. in the morning.

An apozeme to provoke the Flowers.

Let Peſſaries be made with *Galbanum*, *Ammoniacum*, and ſuch like mollifying things, beaten into a maſs in a mortar with a hot peſtle, and made into the form of a Peſſary, and then let them be mixed with Oil of Jaſmine, *Euphorbium*, an Ox-gall, the Juice of Mugwort, and other ſuch like, wherein there is power to provoke the Flowers, as with Scammony in Powder: let them be as big as ones thumb, ſix fingers long, and rowled in Lawn, or ſome ſuch like thin linnen cloth; of the ſame things Nodulaes may be made. Alſo Peſſaries may be prepared with Honey boiled, adding thereto convenient powders, as of Scammony, Pellitory, and ſuch like. Neither ought theſe to ſtay long in the neck of the Womb leſt they ſhould exulcerate, and they muſt be pulled back by a thred that muſt be put through them, and then the orifice of the Womb muſt be fomented with white Wine of the decoction of Penniroyal or Mother-wort.

But it is to be noted, that if the ſuppreſſion of the Flowers happeneth through the default of the ſtopped orifice of the Womb, or by inflammation, theſe maladies muſt firſt be cured before we come unto thoſe things that of their proper ſtrength and virtue provoke the Flowers: as for example, if ſuch things be made and given when the Womb is inflamed, the bloud being drawn into the grieved place, and the humours ſharpened, and the body of the Womb heated, the inflammation will be increaſed. So if there be any ſuperfluous fleſh, if there be any Callus of a wound or ulcer, or if there be any membrane ſhutting the orifice of the Womb, and ſo ſtopping the flux of the Flowers they muſt firſt be conſumed and taken away before any of thoſe things be adminiſtred. But the opportunity of taking and applying of things, muſt be taken from the time wherein the ſick Woman was wont to be purged before the ſtopping, or if ſhe never had the Flowers, in the decreaſe of the Moon; for ſo we ſhall have Cuſtom, Nature, and the external efficient cauſe to help Art. When theſe Medicins are uſed, the Women are not to be put into Baths or Hot-houſes, as many do, except the malady proceed from the denſity of the Veſſels, and the groſsneſs and clammineſs of the bloud. For Sweats hinder the menſtrual Flux, by diverting and turning the matter another way.

What cauſes of the ſtopping of the Flowers muſt be cured before the diſeaſe it ſelf.

The fitteſt time to provoke the Flowers.

Why Hot-houſes do hurt thoſe in whom the Flowers are to be provoked.

CHAP. LIV.

The ſigns of the approaching of the Menſtrual Flux.

When the Monethly flux firſt approacheth, the Dugs itch and become more ſwollen and hard than they are wont; the woman is more delirous of copulation, by reaſon of the ebullition of the provoked bloud, and the acrimony of the bloud that remaineth; her voice becometh bigger, her ſecret parts itch, burn, ſwell, and wax red. If they ſtay long, ſhe hath pain in her loins and head, nauſeouſneſs and vomiting troubleth the ſtomach: notwithſtanding, if thoſe matters which flow together in the womb, either of their own nature, or by corruption, be cold, they loath the act of generation, by reaſon that the Womb waxeth feeble through ſluggiſhneſs and watery humours filling the ſame, and it floweth by the ſecret parts very ſoftly. Thoſe Maids that are marriageable, although they have the menſtrual flux very well, yet they are troubled with Head-ach, nauſeouſneſs, and often vomiting, want of appetite, longing, an ill habit of body, difficulty of breathing, trembling of the heart, ſwouning, melancholy, fearful dreams, watching with ſadneſs and heavineſs, becauſe that the genital parts burning and itching, they imagine the act of generation, whereby it cometh to paſs that the ſeminal matter, either remaining in the teſticles in great abundance, or elſe poured into the hollowneſs of the Womb by the tickling of the genitals, is corrupted, and acquireth a venomous quality, and cauſeth ſuch like accidents as happen in the ſuffocation of the Womb.

What women do love, and what women do loath the act of generation when the moneths are ſtopped.

With what accidents thoſe that are marriageable and are not married, are troubled.

The cauſe of ſo many accidents.

Maids that live in the Country are not ſo troubled with thoſe Diſeaſes, becauſe there is no ſuch lying in wait for their Maiden-heads, and alſo they live ſparingly and hardly, and ſpend their time in continual labour. You may ſee many Maids ſo full of juice that it runneth in great abundance, as if they were not menſtrual, into their Dugs, and is there converted into milk, which they have in as great quantity as Nurſes, as we read it recorded by *Hippocrates*. If a Woman which is neither great with child, nor hath born children, hath milk, ſhe wants the menſtrual fluxes; whereby you may underſtand that that concluſion is not good which affirmeth that a Woman which hath milk in her breſts, either to be delivered of child, or to be great with child; for *Cardanus* writeth that he knew

Aph. 36. ſect. 5.

Lib. 2. de ſubt.

one

one *Antony Buzus* at *Genua*, who being thirty years of age, had ſo much milk in his breaſts as was ſufficient to nurſe a child; for the breeding and efficient cauſe of milk proceeds not onely from the engrafted faculty of the glandulous ſubſtance, but much rather from the action of the mans ſeed, for proof whereof you may ſee many men that have very much milk in their breaſts, and many women that almoſt have no milk, unleſs they receive mans ſeed. Alſo Women that are ſtrong and luſty like unto men, which the Latines call *Viragines*, that is to ſay, whoſe ſeed cometh unto a manly nature, when the Flowers are ſtopped, concoct the blood, and therefore when it wanteth paſſage forth, by the likeneſs of the ſubſtance it is drawn into the dugs, and becometh perfect milk: thoſe that have the Flowers plentifully and continually for the ſpace of four or five days, are better purged and with more happy ſucceſs than thoſe that have them for a longer time.

The efficient cauſe of the milk is to be noted.

CHAP. LV.

What accidents follow immoderate fluxes of the Flowers or Courſes.

IF the menſtrual Flux floweth immoderately, there alſo follow many accidents; for the concoction is fruſtrated, the appetite overthrown, then follows coldneſs throughout all the body, exolution of all the faculties, an ill habit of all the body, Leanneſs, the Droplie, an Hectick Fever, Convulſion, Swouning, and often ſudden death: if any have them too exceeding immoderately, the bloud is ſharp and burning, and alſo ſtinking, the ſick woman is alſo troubled with a continual Fever, and her tongue will be dry, ulcers ariſe in the gums and all the whole mouth. In women the Flowers do flow by the veins and arteries which riſe out of the ſpermatick veſſels, and end in the bottom and ſides of the womb; but in virgins and in women great with child, whoſe children are ſound and healthful, by the branches of the Hypogaſtrick vein and artery, which are ſpred and diſperſed over the neck of the womb. The cauſe of this immoderate flux is in the quantity or quality of the bloud; in both the fault is unreaſonable copulation, eſpecially with a man that hath a Yard of a monſtrous greatneſs, and the diſſolution of the retentive faculty of the veſſels: oftentimes alſo the Flowers flow immoderately by reaſon of a painful and a difficult birth of the child, or the after-birth, being pulled by violence from the cotyledons of the womb, or by reaſon that the veins and arteries of the neck of the womb are torn by the coming forth of the Infant with great travel, and many times by the uſe of ſharp Medicins, and exulcerating Peſſaries. Oft-times alſo Nature avoids all the juice of the whole body critically by the womb after a great diſeaſe, which flux is not raſhly or ſuddenly to be ſtopped. That menſtrual bloud that floweth from the womb, is more groſs, black, and clotty, but that which cometh from the neck of the womb is more clear, liquid and red.

By what pores the Flowers do flow in a Woman and in a Maid.

The cauſes of an unreaſonable flux of bloud.

The critical flux of the Flowers.

The ſigns of bloud flowing from the womb or neck of the womb.

CHAP. LVI.

Of ſtopping the immoderate flowing of the Flowers or Courſes.

YOu muſt make choice of ſuch meats and drinks as have power to incraſſate the bloud; for as the Flowers are provoked with meats that are hot and of ſubtil parts, ſo they are ſtopped by ſuch meats as are cooling, thickning, aſtringent, and ſtiptick, as are Barly-waters, ſodden Rice, the extreme parts of Beaſts, as of Oxen, Calves, Sheep, either fried or ſodden with Sorrel, Purſlain, Plantain, Shepherds-purſe, Sumach, the buds of Brambles, Berberies, and ſuch like. It is ſuppoſed that a Harts-horn burned, waſhed, and taken in aſtringent water, will ſtop all immoderate Fluxes; likewiſe *Sanguis draconis*, *terra ſigillata*, *bolus armenus*, *lapis hæmatites*, Coral beaten into moſt ſubtil powder, and drunk in ſteeled water; alſo Pap made with milk wherein ſteel hath oftentimes been quenched, and the flower of Wheat, Barley, Beans, or Rice, is very effectual for the ſame. Quinces, Cervices, Medlars, Cornelian-berries, or Cherries, may likewiſe be eaten at the ſecond Courſe. Julips are to be uſed of ſteeled waters, with ſyrup of dry Roſes, Pomegranats, Sorrel, Myrtles, Quinces, or old Conſerves of red Roſes, but Wine is to be avoided: but if the ſtrength be ſo extenuated, that they require it, you muſt chuſe groſs and aſtringent Wine tempered with ſteeled water; exerciſes are to be ſhunned, eſpecially Venerous Exerciſes, Anger is to be avoided, a cold air is to be choſen, which (if it be not ſo naturally) muſt be made ſo by ſprinkling cold things on the ground, eſecially if the Summer or heat be then in his full ſtrength; ſound ſleeping ſtays all evacuations except ſweating. The opening of a Vein in the arm, Cupping-glaſſes faſtened on the breaſts, bands, and painful frictions of the upper parts are greatly commended in this malady.

The inſtitution or order of life.

But if you perceive that the cauſe of this accident lieth in a cholerick ill juice mixed with the bloud, the body muſt be purged with Medicins that purge choler and water, as Rhubarb, Myrobalans, Tamarinds, Sebeſtens, and the purging Syrup of Roſes.

Purging.

CHAP. LVII.

Of local Medicins to be uſed againſt the immoderate flowing of the Courſes.

ALſo Unguents are made to ſtay the immoderate flux of the Terms, and likewiſe injections and peſſaries. This or ſuch like may be the form of an Unguent. ℞ *Ol. Maſtich. & myrt. an.* ʒ ij. *nucum cupr. olibani, myrtil. an.* ʒ ij. *ſucci roſar. rubr.* ʒ j. *pulv. maſtichin.* ʒ ij. *boli armen. terræ ſigillat. an.* ʒ ß. *ceræ quantum ſufficit, fiat unguentum.* An injection may be thus made. ℞ *Aq. plantag. roſar. rubr. burſæ paſtor. centinodii, an.* ℔ ß. *corticis querni, nucum cupreſſi, gallar. non maturar. an.* ʒ ij. *berberis,*

An unguent.

An aſtringent injection.

berberis, ſumach. balauſt. alumin. roch. an. ℥. j. make thereof a decoction, and inject it in a ſyringe blunt-pointed into the Womb, leſt if it ſhould be ſharp, it might hurt the ſides of the neck of the womb, alſo Snails beaten with their ſhells, and applied to the navel, are very profitable. Quinces roſted under the Coals, and incorporated with the powder of Myrtles and Bole-Armenick, and put into the neck of the womb, are marvellous effectual for this matter. The form of a peſſary may be thus:

Aſtringent Peſſaries.

℞ *Gallar. immaturar. combuſt. & in aceto extinctar.* ℥ ij. *ammo.* ʒ ß. *ſang. drac. pulv. rad. ſymphyt. ſumach. maſtich. ſucci acaciæ, cornu ceruſt. colophon. myrrhæ, ſcoriæ ferri, an.* ℥ j. *caphur.* ℈ ij. mix them, and incorporate them all together with the juice of Knot-graſs, Syn-green, Night-ſhade, Henbane, Water-lillies, Plantain, of each as much as is ſufficient, and make thereof a Peſſary.

Cooling things, as Oxycrate, *Unguentum roſatum*, and ſuch like, are with great profit uſed to the region of the loins, thighs, and genital parts: but if this immoderate flux do come by eroſion, ſo that the matter thereof continually exulcerateth the neck of the womb, let the place be anointed with the milk of a ſhe-Aſs, with Barley-water, or binding and aſtringent mucilages, as of Pſillium, Quinces, Gum Tragacanth, Arabick, and ſuch like.

CHAP. LVIII.

Of Womens Fluxes, or the Whites.

The reaſon of the name. The differences.

BEſides the fore-named Flux, which by the Law of Nature happeneth to Women monethly, there is alſo another called a *Womans Flux*, becauſe it is onely proper and peculiar to them: this ſometimes wearieth the Woman with a long and continual diſtillation from the womb, or through the womb, coming from the whole body without pain, no otherwiſe than when the whole ſuperfluous filth of the body is purged by the reins or urin; ſometimes it returneth at uncertain ſeaſons, and ſometimes with pain and exulcerating the places of the womb: it differeth from the menſtrual Flux, becauſe that this for the ſpace of a few days, as it ſhall ſeem convenient to Nature, caſteth forth laudable bloud; but this *Womans Flux* yieldeth impure juice, ſometimes ſanious, ſometimes ſerous and livid, otherwhiles white and thick, like unto Barly-cream, proceeding from flegmatick bloud: this laſt kind thereof is moſt frequent. Therefore we ſee women that are flegmatick, and of a ſoft and looſe habit of body, to be often troubled with this diſeaſe; and therefore they will ſay among themſelves that they have the Whites. And as the matter is diverſe, ſo it will ſtain their ſmocks with a different colour. Truly if it be perfectly red and ſanguin, it is to be thought it cometh by eroſion, or the exſolution of the ſubſtance of the veſſels of the womb, or of the neck thereof: therefore it cometh very ſeldom of bloud, and not at all except the woman be either great with child, or ceaſe to be menſtrual for ſome other cauſe; for then in ſtead of the monethly flux there floweth a certain whayith excrement, which ſtaineth her cloaths with the colour of water wherein fleſh is waſhed.

What women are apt to this flux.

Womens flux cometh very ſeldom of bloud.

Alſo it very ſeldom proceeds of a melancholick humour, and then for the moſt part it cauſeth a Cancer in the womb. But oftentimes the purulent and bloudy matter of an ulcer lying hidden in the womb, deceiveth the unskilful Chirurgeon or Phyſician: but it is not ſo hard to know theſe diſeaſes one from the other; for the matter that floweth from an ulcer, becauſe (as it is ſaid) it is purulent, it is alſo leſſer, groſſer, ſtinking, and more white. But thoſe that have ulcers in thoſe places, eſpecially in the neck of the womb, cannot have copulation with a man without pain.

By what ſigns an ulcer in the womb may be known from the white Flowers.

CHAP. LIX.

Of the cauſes of the Whites.

SOmetimes the cauſe of the Whites conſiſteth in the proper weakneſs of the womb, or elſe in the uncleanneſs thereof; and ſometimes by the default of the principal parts. For if the brain or the ſtomach be cooled, or the liver ſtopped or ſcirrhous, many crudities are engendred, which if they run, or fall down into the womb that is weak by Nature, they cauſe the flux of the Womb or Whites: but if this Flux be moderate, and not ſharp, it keepeth the body from malign diſeaſes; otherwiſe it uſeth to infer a Conſumption, Leanneſs, Paleneſs, and an œdematous ſwelling of the legs, the falling down of the womb, the dejection of the appetite and all the faculties, and continual ſadneſs and ſorrowfulneſs; from which it is very hard to perſuade the ſick woman, becauſe that her mind and heart will be almoſt broken, by reaſon of the ſhame that ſhe taketh, becauſe ſuch filth floweth continually; it hindereth conception, becauſe it either corrupteth, or driveth out the ſeed when it is conceived. Oftentimes if it ſtoppeth for a few Moneths, the matter that ſtayeth there cauſeth an abſceſs about the womb in the body or neck thereof; and by the breaking of the abſceſs there followeth rotten and cancerous ulcers, ſometimes in the womb, ſometimes in the groin, and often in the hips.

How a Womans flux is wholeſom. How it cauſeth diſeaſes. How it letteth the conception.

Why it is hard to be cured.

This diſeaſe is hard to be cured, not onely by reaſon of it ſelf, as becauſe all the whole filth and ſuperfluous excrements of a womans body floweth down into the womb, as it were into a ſink; becauſe it is naturally weak, hath an inferiour ſituation, many veſſels ending therein; and laſt of all, becauſe the Courſes are wont to come through it; as alſo by reaſon of the ſick woman, who oftentimes had rather die than to have that place ſeen, the diſeaſe known, or permit local Medicins to be applied thereto: for ſo ſaith *Montanus*, that on a time he was called to a Noble-woman of *Italy*, who was troubled with this diſeaſe, unto whom he gave counſel to have cleanſing decoctions injected into her womb; which when ſhe heard, ſhe fell into a ſwound, and deſired her husband never thereafter to uſe his counſel in any thing.

An Hiſtory.

CHAP.

CHAP. LX.

The Cure of the Whites.

IF the matter that floweth out in this diſeaſe be of a red colour, it differeth from the natural Monethly flux in this onely, becauſe it keeps no order or certain time in its returning. Therefore Phlebotomy and other remedies which we have ſpoken of, as requiſite for the menſtrual flux, when it floweth immoderately, is here neceſſary to be uſed. But if it be white, or doth teſtifie or argue the ill juice of this or that humour by any other colour, a Purgation muſt be preſcribed of ſuch things as are proper to the humour that offends: for it is not good to ſtop ſuch a flux ſuddenly, for it is neceſſary that ſo the body ſhould be purged of ſuch filth or abundance of humours; for they that do haſten to ſtop it, cauſe the dropſie by reaſon that this ſink of humours is turned back into the liver; or elſe a Cancer in the Womb, becauſe it is ſtaid there; or a Fever, or other diſeaſes, according to the condition of the part that receiveth it. Therefore we muſt not come to local deterſives, deſiccatives, reſtrictives, unleſs we have firſt uſed univerſal remedies according to Art. Alum-baths, baths of Brimſtone, and of bitumen, or iron, are convenient for the Whites that come of a phlegmatick humour; in ſtead whereof baths may be made of the decoction of herbs that are hot, dry, and indued with an aromatick power, with Alum and Pebles, or Flint-ſtones red hot thrown into the ſame. Let this be the form of a cleanſing decoction and injection. ℞ *Fol. abſynth. agrim. centinod. burſ. paſt. an.* m. ß. boil them together, and make thereof a decoction, in which diſſolve *mellis roſar.* ℥ ij. *aloes, myrrhæ, ſalis nitri, an.* ʒ j. make thereof an injection the woman being ſo placed on a pillow under her buttocks that the neck of the Womb being more high, may be wide open: when the injection is received, let the Woman ſet her legs acroſs, and draw them up to her buttocks, and ſo ſhe may keep that which is injected. They that endeavour to dry and bind more ſtrongly, add the juice of *acatia*, green galls, the rinds of Pomegranats, Roch-alum, Romane Vitriol, and they boil them in Smiths water and Red wind; peſſaries may be made of the like faculty.

If the flux of a Woman be red, wherein it differeth from the menſtrual flux.

A Womans flux is not ſuddenly to be ſtopped.

What baths are profitable.

An aſtringent injection.

If the matter that cometh forth be of an ill colour or ſmell, it is like that there is a rotten ulcer; therefore we ought to inject thoſe things that have power to correct the putrefaction: among which *Ægyptiacum*, diſſolved in Lie, or Red wine, excelleth. There are women which when they are troubled with a virulent Gonorrhæa, or an involuntary flux of the ſeed, cloaking the fault with an honeſt name, do untruly ſay that they have the Whites, becauſe that in both theſe diſeaſes a great abundance of filth is avoided. But the Chirurgeon may eaſily perceive that malady by the rottenneſs of the matter that floweth out, and he ſhall perſuade himſelf that it will not be cured without ſalivation or fluxing at the mouth, and ſweats. In the mean while let him put in an inſtrument made like unto a peſſary, and cauſe the ſick woman to hold it there: this inſtrument muſt have many holes in the upper end, through which the purulent matter may paſs, which by ſtaying or ſtopping might get a ſharpneſs; as alſo that ſo the Womb may breath the more freely, and may be kept more temperate and cool by receiving the air, by the benefit of a ſpring whereby this Inſtrument, being made like unto a peſſary, is opened and ſhut.

The ſigns of a putrefied ulcer in the Womb.

The virulent Gonorrhæa is like unto the flux of Women.

The form of an Inſtrument made like unto a Peſſary, whereby the Womb may be ventilated.



A *Sheweth the end of the Inſtrument, which muſt have many holes therein.*
B *Sheweth the body of the Inſtrument.*
C *Sheweth the Plate whereby the mouth of the Inſtrument is opened and ſhut, as wide and as cloſe as you will, for to receive the air more freely.*
D *Sheweth the Spring.*
EE *Shew the Laces and Bands to tie about the Patients body, that ſo the Inſtrument may be ſtaid and kept faſt in his place.*

CHAP. LXI.

Of the Hæmorrhoids *and Warts of the neck of the Womb.*

LIke as in the Fundament, ſo in the neck of the Womb there are Hæmorrhoids, and as it were varicous Veins, oftentimes flowing with much bloud, or with a red and ſtinking whayiſh humour. Some of theſe, by reaſon of their redneſs and great inequality as it were of knobs, are like unripe Mulberries, and are called vulgarly *Venæ morales*, that is to ſay, the Veins or Hæmorrhoids like unto Mulberries: others are like unto Grapes, and therefore are named *Uvales*: other ſome are like unto Warts, and therefore are called *Venæ verucales*: ſome appear and ſhew themſelves with a great tumor, others are little, and in the bottom of the neck of the Womb; others are in

The differences of the Hæmorrhoids of the neck of the Womb.

What an *Acrochordon* is.

the ſide or edge thereof. *Acrochordon* is a kind of Wart with a callous bunch or knot, having a thin or ſlender root, and a greater head, like unto the knot of a Rope, hanging by a ſmall thred; it is called of the *Arabians*, *Verruca botoralis*.

What a *Thymus* is.

There is alſo another kind of Wart, which becauſe of its great roughneſs and inequality, is called *Thymus*, as reſembling the flower of Thyme. All ſuch diſeaſes are exaſperated and made more grievous by any exerciſe, eſpecially by venerous acts: many times they have a certain malignity, and an hidden virulency joined with them, by occaſion whereof they are aggravated even by touching onely, becauſe they have their matter of a raging humour; therefore to theſe we may not rightly uſe a true, but onely the palliative cure, as they term it: the *Latins* call them onely *Ficus*, but the *French* men name them with an adjunct, Saint *Fiacrius* Figs.

S. *Fiacrius* figs.

CHAP. LXII.

Of the Cure of the Warts that are in the neck of the Womb.

What Warts of the Womb muſt be bound and ſo cut off.

THe Warts that grow in the neck of the Womb, if they be not malignant, are to be tied with a thred, and ſo cut off. Thoſe that lie hid more deep in the Womb, may be ſeen and cured by opening the *Matrix* with a dilater made for the purpoſe.

Divers Speculum Matricis, *or Dilaters for the inſpection of the* Matrix.



Another form of a Dilater, or Speculum Matricis, *whereof the declaration followeth.*



A *Sheweth the Screw which ſhutteth and openeth the Dilater of the* Matrix.
B *Sheweth the Arms or Branches of the Inſtrument, which ought to be eight or nine fingers long.*

But theſe Dilaters of the Matrix ought to be of a bigneſs correſpondent to the Patients body; let them be put into the Matrix, when the woman is placed as we have ſaid, when the child is to be drawn out of her body. That inſtrument is moſt meet to tie the Warts, which we have deſcribed in the relaxation

laxation of the Palat or *Uvula*: let them be tied harder and harder every day until they fall away. Therefore for the curing of Warts there are three chief ſcopes, as Bands, Sections, Cauteries; and leſt they grow up again, let Oil of Vitriol be dropped on the place, or *Aqua fortis*, or ſome of the lee whereof potential Cauteries are made. This Water following is moſt effectual to conſume and waſte Warts. ℞ *Aq. plantag.* ℥ vj. *virid. æris* ʒ ij. *alum. roch.* ʒ iij. *ſal. com.* ℥ ß. *vit. rom. & ſublim. an.* ʒ ß. beat them all together, and boil them; let one or two drops of this water be dropped on the grieved place, not touching any place elſe; but if there be an ulcer, it muſt be cured as I have ſhewed before. A certain man ſtudious of Phyſick, of late affirmed to me, that Ox-dung tempered with the leaves or powder of Savin, would waſte the Warts of the womb, if it were applied thereto warm; which, whether it be true or not, let Experience, the Miſtreſs of things, be judge. Verily, *Cantharides* put into unguents will do it, and (as it is likely) more effectually; for they will conſume the calouſneſs which groweth between the Toes or Fingers. I have proved by experience, that the Warts that grow on the hands, may be cured by applying of Purſlain beaten or ſtamped in its own juice. The Leaves and Flowers of Marigolds, do certainly perform the ſelf-ſame thing.

Three ſcopes of the cure of Warts in the Womb.

An effectual water to conſume Warts.

Unguents to conſume warts.

CHAP. LXIII.

Of Chaps, and thoſe wrinkled and hard Excreſcences, which the Greeks call Condylomata.

CHaps or Fiſſures, are cleft and very long little Ulcers with pain very ſharp and burning, by reaſon of the biting of an acrid, ſalt and dry humour, making ſo great a contraction, and often-times narrowneſs in the fundament and the neck of the womb, that ſcarcely the top of ones finger may be put into the orifice thereof, like unto pieces of Leather or Parchment, which are wrinkled and parched by holding of them to the fire. They riſe ſometimes in the mouth, ſo that the Patient can neither ſpeak, eat, nor open his mouth, ſo that the Surgeon is conſtrained to cut it. In the cure thereof, all ſharp things are to be avoided, and thoſe which mollifie are to be uſed, and the grieved place or part is to be moiſtned with Fomentations, Liniments, Cataplaſms, Emplaſters; and if the malady be in the Womb, a dilater of the matrix or peſſary muſt be put thereinto very often, ſo to widen that which is over hard, and too much drawn together or narrow, and then the cleft little ulcers muſt be cicatrized. *Condylomata* are certain wrinkled and hard bunches, and as it were excreſcences of the fleſh, riſing eſpecially in the wrinkled edge of the fundament and neck of the womb. Cooling and relaxing medicins ought to be uſed againſt this diſeaſe, ſuch as are Oil of Eggs and Oil of Lin-ſeed, take of each of them two ounces, beat them together a long time in a leaden Mortar, and therewith anoint the grieved part; but if there be an inflammation, put thereto a little Camphir.

What Chaps are.

The Cure.

What *Condylomata* are.

The Cure.

CHAP. XLIV.

Of the itching of the Womb.

IN Women, eſpecially ſuch as are old, there oftentimes cometh an itching in the neck of the Womb, which doth ſo trouble them with pain, and a deſire to ſcratch, that it taketh away their ſleep. Not long ſince a woman asked my counſel, that was ſo troubled with this kind of malady, that ſhe was conſtrained to extinguiſh or ſtay the itching burning of her ſecret parts by ſprinkling cinders of fire, and rubbing them hard on the place. I counſelled her to take *Ægyptiacum* diſſolved in Sea-water or lee, and inject it in her ſecret parts with a Syringe, and to wet ſtupes of flax in the ſame Medicin, and put them up into the Womb, and ſo ſhe was cured. Many times this itch cometh in the fundament or teſticles of aged men, by reaſon of the gathering together or conflux of ſalt phlegm, which when it falleth into the eyes, it cauſeth the Patient to have much ado to refrain ſcratching: when this matter hath diſperſed into the whole habit of the body, it cauſeth a burning or itching ſcab, which muſt be cured by a cooling and moiſtning diet, by phlebotomy and purging of the ſalt humour, by baths and horns applied, with ſcarification and anointing the whole body with the Unction following. ℞ *Axung. porcin. recent.* ℔ j. ß. *ſap. nig. vel gallici, ſalis nitri, aſſat. tartar. ſtaphyſag. an.* ʒ ß. *ſulph. viv.* ℥ j. *argent. viv.* ʒ ij. *acet. roſ. quart.* j. incorporate them all together, and make thereof a liniment according to Art, and uſe it as is ſaid before: *Unguentum enulatum cum Mercurio* is thought to have great force, not without deſert, to aſſwage the itch, and dry ſcab. Some uſe this that followeth: ℞ *Alum. ſpum. nitr. ſulph. viv. an.* ʒ vj. *ſtaphyſ.* ℥ j. let them all be diſſolved in Vinegar of Roſes, adding thereto *Butyr. recent. q. ſ.* make thereof a liniment for the fore-named uſe.

What the itch of the Womb.

An Hiſtory.

The cauſe of the itch.

The virtue of *unguent. enulat.*

CHAP. LXV.

Of the relaxation of the great Gut, or Inteſtine, which happeneth to Women.

MAny Women that have had great travail and ſtrains in Child-birth, have the great inteſtine (called of the Latins, *Craſſum inteſtinum*) or Gut, relaxed and ſlipped down; which kind of affect happeneth much to children, by reaſon of a phlegmatick humour moiſtening the ſphincter-muſcle of the fundament, and the two others called *Levatores*. For the cure thereof, firſt of all the Gut called *rectum inteſtinum*, or the ſtrait Gut, is to be fomented with a decoction of heating and reſolving herbs, as of Sage, Roſemary, Lavender, Tyme, and ſuch like; and then of aſtringent things, as of Roſes, Myrtils, the rinds of Pomegranats, Cypreſs-nuts, Galls, with a little Allum; then it muſt be ſprinkled with the Powder of things that are aſtringent without biting: and laſt

The Cauſe.

The Cure.

An effectual remedy.

laſt of all, it is to be reſtored, and gently put into its place. That is ſuppoſed to be an effectual and ſingular remedy for this purpoſe, which is made of twelve red Snails put into a Pot with ʒ ß of Alum, and as much of Salt, and ſhaken up and down a long time, for ſo at length when they are dead there will remain an humour, which muſt be put upon Cotton, and applied to the Gut that is fallen down.

The differences and ſigns.

By the ſame cauſe (that is to ſay, of painful child-birth in ſome women) there ariſeth a great ſwelling in the Navel; for when the *Peritonæum* is relaxed or broken, ſometimes the Kall, and ſometimes the Guts ſlip out: many times flatulences come thither, the cauſe, as I now ſhewed, is over great ſtraining or ſtretching of the belly, by a great burthen carried in the Womb, and great travel in child-birth: if the fallen-down Guts make that tumor, pain joined together with that tumor doth vex the Patient; and if it be preſſed, you may hear the noiſe of the guts going back again: if it be the Kall, then the tumor is ſoft, and almoſt without pain, neither can you hear any noiſe by compreſſion: if it be wind, the tumor is looſe and ſoft, yet it is ſuch as will yield to the preſſing of the finger with ſome ſound, and will ſoon return again: if the tumor be great, it cannot be cured, unleſs the *Peritonæum* be cut, as

An Hiſtory.

it is ſaid in the cure of Ruptures. In the Church-Porches of *Paris*, I have ſeen Beggar-women, who by the falling down of the Guts, have had ſuch tumors as big as a bowl, who notwithſtanding could go, and do all other things as if they had been ſound and in perfect health: I think it was becauſe the *fæces* or excrements, by reaſon of the greatneſs of the tumor, and the bigneſs or wideneſs of the inteſtines, had a free paſſage in and out.

CHAP. LXVI.

Of the relaxation of the Navel in Children.

OFtentimes in Children newly born, the Navel ſwelleth as big as an Egg, becauſe it hath not been well cut or bound, or becauſe the whayiſh humours are flowed thither, or becauſe that part hath extended it ſelf too much by crying, by reaſon of the pains of the fretting of the Childs guts, many times the Child bringeth that tumor joined with an abſceſs with him from his

An abſceſs not to be opened.

Mothers Womb: but let not the Chirurgeon aſſay to open that abſceſs, for if it be opened, the guts come out through the inciſion, as I have ſeen in many, and eſpecially in a Child of my Lord *Martigues*; for when *Peter* of the Rock, the Chirurgeon, opened an abſceſs that was in it, the bowels ran out at the inciſion, and the Infant died; and it wanted but little that the Gentlemen of my Lords

An Hiſtory.

retinue that were there, had ſtrangled the Chirurgeon. Therefore when *John Gromontius* the Carver deſired me, and requeſted me of late that I would do the like in his Son; I refuſed to do it, becauſe it was in danger of its life by it already; and in three days after the abſceſs broke, and the bowels guſhed out, and the child died.

CHAP. LXVII.

Of the pain that Children have in breeding of Teeth.

The time of breeding of the Teeth.

CHildren are greatly vexed with their Teeth, which cauſe great pain when they begin to break as it were out of their ſhell or ſheath, and begin to come forth, the gums being broken, which for the moſt part happeneth about the ſeventh moneth of the Childs age.

The cauſe of the pain in breeding Teeth.

This pain cometh with itching and ſcratching of the gums, an inflammation, flux of the belly, whereof many times cometh a Fever, falling of the Hair, a Convulſion, at length death. The cauſe of the pain is the ſolution of the continuity of the Gums by the coming forth of the Teeth.

The ſigns.

The ſigns of that pain is an unaccuſtomed burning, or heat of the Childs mouth, which may be perceived by the Nurſe that giveth it ſuck, a ſwelling of the Gums and Cheeks, and the Childs being more wayward and crying than was wont, and it will put its fingers to its mouth, and it will rub them on its

The Cure.

Gums as though it were about to ſcratch, and it ſlavereth much. That the Phyſician may remedy this, he muſt cure the Nurſe as if ſhe had the Fever, and ſhe muſt not ſuffer the Child to ſuck ſo often, but make him cool and moiſt, when he thirſteth, by giving him at certain times *Syrupus Alexandrinus*, *ſyrup. de Limonibus*, or the ſyrup of Pomgranats with boiled Water; yet the Child muſt not hold thoſe things that are actually cold long in his mouth, for ſuch by binding the Gums, do in ſome ſort ſtay the Teeth that are newly coming forth; but things that lenifie and mollifie are rather to be uſed, that is to ſay, ſuch things as do by little and little relax the looſe fleſh of the Gums, and alſo aſſwage the pain. Therefore the Nurſe ſhall oftentimes rub the Childs Gums with her fingers anointed or beſmeared with Oil of ſweet Almonds, freſh Butter, Honey, Sugar, mucilage of the ſeeds of *Pſilium*, or of the ſeeds of Marſh-mallows extracted in the water of Pellitory of the Wall. Some think that the brain of a Hare, or of a ſucking Pig roaſted or ſodden, through a ſecret property, are effectual for the ſame: and on the out-ſide ſhall be applied a Cataplaſm of Barly-meal, Milk, Oil of Roſes, and the Yolks of Eggs. Alſo a ſtick of Liquorice ſhaven and bruiſed and anointed with Honey, or any of the fore-named Syrups, and often rubbed in the mouth or on the gums, is likewiſe profitable: ſo

What power ſcratching of the gums hath to aſſwage the pain of them.

is alſo any Toy for the Child to play withall, wherein a Wolves tooth is ſet, for this by ſcratching doth aſſwage the painful itching, and rarifie the Gums, and in ſome weareth them that the Teeth appear the ſooner. But many times it happeneth that all theſe and ſuch like medicins profit nothing at all, by reaſon of the contumacy of the gums, by hardneſs or the weakneſs of the Childs nature; therefore in ſuch a caſe, before the fore-named mortal accidents come, I would perſuade the Chirurgeon to open the gums in ſuch places as the Teeth bunch out with a little ſwelling, with a Knife or Lancet, ſo breaking and opening a way for them, notwithſtanding that a little flux of bloud will follow by the tention of the gums: of which kind of remedy I have with proſperous and happy ſucceſs made trial in ſome of mine own Children in the preſence of *Feureus*, *Altinus*, and *Cortinus*,

Doctors

Doctors of Physick, and *Guillemeau* the Kings Chirurgeon, which is much better and more safe than to do as some Nurses do, who, taught onely by the instinct of Nature, with their nails and scratching, break and tear, or rent the Childrens gums. The Duke of *Nevers* had a son of eight moneths old, which died of late, and when we, with the Physicians that were present, diligently sought for the cause of his death, we could impute it unto nothing else than to the contumacious hardness of the gums, which was greater than was convenient for a child of that age; for therefore the Teeth could not break forth, nor make a passage for themselves to come forth: of which our judgment this was the trial, that when we cut his gums with a knife, we found all his Teeth appearing as it were in an array, ready to come forth, which if it had been done when he lived, doubtless he might have been preserved. An History.

The End of the Four and Twentieth Book.

BOOK XXV.

Of MONSTERS *and* PRODIGIES.

THE PREFACE.

WE call Monsters, what things soever are brought forth contrary to the common decree and order of Nature. So we term that Infant monstrous which is born with one arm alone, or with two heads. But we define Prodigies, those things which happen contrary to the whole course of Nature, that is, altogether differing and dissenting from Nature: as if a man should be delivered of a Snake or a Dog. Of the first sort are thought all those, in which any of those things which ought, and are accustomed to be, according to Nature, is wanting, or doth abound, is changed, worn, covered, or deformed, hurt, or not put in its right place: for sometimes some are born with more fingers than they should, other some but with one finger: some with those parts divided which should be joined, others with those parts joined which should be divided: some are born with the privities of both sexes, male and female. And Aristotle *saw a Goat with a horn upon her knee. No living Creature was ever born which wanted the Heart, but some have been seen wanting the Spleen, others with two Spleens, and some wanting one of the Reins. And none have been known to have wanted the whole Liver, although some have been found that had it not perfect and whole: and there have been those which wanted the Gall, when by Nature they should have had it; and besides it hath been seen that the Liver, contrary to its natural site, hath lien on the left side, and the Spleen on the right. Some Women also have had their Privities closed, and not perforated, the membranous obstacle, which they call the* Hymen, *hindering. And men are sometimes born with their Fundaments, Ears, Noses, and all the rest of the passages shut, and accounted monstrous, Nature erring from its intended scope. But to conclude, those Monsters are thought to portend some ill, which are much differing from their Nature.*

What a Monster is. What a Prodigy is. *Lib. 4. gen. anim. cap. 4.*

CHAP. I.

Of the causes of Monsters; and first of those Monsters which appear for the glory of God, and the punishment of Mans wickedness.

THere are reckoned up many causes of Monsters, the first whereof is the glory of God, that his immense power may be manifest to those which are ignorant of it, by the sending of those things which happen contrary to Nature: for thus our Saviour Christ answered the Disciples (asking whether *He* or his *Parents* had offended, who being *born blind*, received his sight from him) that neither *He* nor his *Parents* had committed any fault so great, but this so happened onely that the *glory* and majesty of God should be divulged by that miracle, and such great works.

Another cause is, that God may either punish mens wickedness, or shew signs of punishment at hand, because Parents sometimes lie and join themselves together without law and measure, or luxuriously and beastly, or at such times as they ought to forbear by the command of God and the Church, such monstrous, horrid and unnatural births do happen.

The

The Figure of a Colt with a Mans Face.

At *Verona*, *An. Dom.* 1254. a Mare foaled a Colt with the perfect face of a Man, but all the reſt of the body like an Horſe: a little after that the Wars between the *Florentines* and *Piſans* began, by which all *Italy* was in a combuſtion.

The Figure of a winged Monſter.

About the time that Pope *Julius* the ſecond raiſed up all *Italy*, and the greateſt part of Chriſtendom againſt *Lewis* the Twelfth, the King of *France*, in the Year of our Lord 1512. (in which Year, upon Eaſter day, near *Ravenna* was fought that mortal battle, in which the Popes Forces were overthrown) a Monſter was born in *Ravenna*, having a Horn upon the Crown of his head, and beſides, two wings, and one foot alone, moſt like to the feet of Birds of prey, and in the knee thereof an eye, the Privities of male and female, the reſt of the body like a man, as you may ſee by this Figure.

The third cauſe is, an abundance of ſeed and overflowing matter. The fourth, the ſame in too little quantity, and deficient. The fifth, the force and efficacy of imagination. The ſixth, the ſtraightneſs of the Womb. The ſeventh, the diſorderly ſite of the party with child, and the poſition of the parts of the body. The eighth, a fall, ſtrain, or ſtroak, eſpecially upon the belly of a woman with child. The nineth, hereditary diſeaſes, or affects by any other accident. The tenth, the confuſion and mingling together of the ſeed. The eleventh, the craft and wickedneſs of the Devil. There are ſome others which are accounted for Monſters, becauſe their original or eſſence full of admiration, or do aſſume a certain prodigious form by the craft of ſome begging Companions; therefore we will ſpeak briefly of them in their place, in this our Treatiſe of Monſters.

CHAP. II.

Of Monſters cauſed by too great abundance of Seed.

SEeing we have already handled the two former and truly final cauſes of Monſters, we muſt now come to thoſe which are material, corporeal, and efficient cauſes, taking our beginning from that we call the too great abundance of the matter of ſeed. It is the opinion of thoſe Philoſophers which have written of Monſters, that if at any time a Creature bearing one at once, as Man, ſhall caſt forth more ſeed in copulation than is neceſſary to the generation of one body, it cannot be that onely one ſhould be begot of all that: therefore from thence either two or more muſt ariſe: whereby it cometh to paſs, that theſe are rather judged wonders, becauſe they happen ſeldom, and contrary to common cuſtom. Superfluous parts happen by the ſame cauſe that Twins and many at one birth, contrary to Natures courſe, do chance, that is, by a larger effuſion of ſeed than is required for the framing of that part, that ſo it exceeds either in number or elſe in greatneſs. So *Auſtin* tells that in his time in the Eaſt, an Infant was born, having all the parts from the belly upwards double, but from thence downward ſingle and ſimple: for it had two heads, four eyes, two breaſts, four hands, in all the reſt like to another child, and it lived a little while. *Cælius Rhodiginus* ſaith he ſaw two Monſters in *Italy*, the one male, the other female, handſomely and neatly made through all their bodies, except their heads, which were double; the male died within a few days after it was born, but the female (whoſe ſhape is here delineated) lived five and twenty years, which is contrary to the common cuſtom of Monſters; for they for the moſt part are very ſhort-lived, becauſe they both live and are born, as it were, againſt Natures conſent; to which may

be

be added, they do not love themſelves, by reaſon they are made a ſcorn to others, and that by that means lead a hated life.

But it is moſt remarkable which *Lycoſthenes* telleth of a * Woman-monſter; for, excepting her two heads, ſhe was framed in the reſt of her body to an exact perfection: her two heads had the like deſire to eat and drink, to ſleep, to ſpeak, and to do every thing; ſhe begged from door to door, every one giving to her freely. Yet at length ſhew was baniſhed *Bavaria*, leſt that by the frequent looking upon her, the imagination of Women with child, ſtrongly moved, ſhould make the like impreſſion in the Infants they bare in their Wombs.

*The Effigies of a * Maid with two heads.*

The Effigies of two • Girls whoſe Backs grew together.

In the Year of our Lord 1475. at *Verona* in *Italy*, two • Girls were born with their backs ſticking together from the lower part of the ſhoulders unto the very buttocks. The novelty and ſtrangeneſs of the thing moved their Parents, being but poor, to carry them through all the chief Towns in *Italy* to get money of all ſuch as came to ſee them.

The Figure of a Man with another growing out of him.

In the Year 1530. there was a man to be ſeen at *Paris*, out of whoſe belly another, perfect in all his members except head, hanged forth as if he had been grafted there. The man was forty years old, and he carried the other implanted or growing out of him, in his arms, with ſuch admiration to the beholders, that many ran very earneſtly to ſee him.

The

The Figure of a Colt with a Mans Face.

At *Verona*, *An. Dom.* 1254. a Mare foaled a Colt with the perfect face of a Man, but all the reſt of the body like an Horſe: a little after that the Wars between the *Florentines* and *Piſans* began, by which all *Italy* was in a combuſtion.

The Figure of a winged Monſter.

About the time that Pope *Julius* the ſecond raiſed up all *Italy*, and the greateſt part of Chriſtendom againſt *Lewis* the Twelfth, the King of *France*, in the Year of our Lord 1512. (in which Year, upon Eaſter day, near *Ravenna* was fought that mortal battle, in which the Popes Forces were overthrown) a Monſter was born in *Ravenna*, having a Horn upon the Crown of his head, and beſides, two wings, and one foot alone, moſt like to the feet of Birds of prey, and in the knee thereof an eye, the Privities of male and female, the reſt of the body like a man, as you may ſee by this Figure.

The third cauſe is, an abundance of ſeed and overflowing matter. The fourth, the ſame in too little quantity, and deficient. The fifth, the force and efficacy of imagination. The ſixth, the ſtraightneſs of the Womb. The ſeventh, the diſorderly ſite of the party with child, and the poſition of the parts of the body. The eighth, a fall, ſtrain, or ſtroak, eſpecially upon the belly of a woman with child. The nineth, hereditary diſeaſes, or affects by any other accident. The tenth, the confuſion and mingling together of the ſeed. The eleventh, the craft and wickedneſs of the Devil. There are ſome others which are accounted for Monſters, becauſe their original or eſſence full of admiration, or do aſſume a certain prodigious form by the craft of ſome begging Companions; therefore we will ſpeak briefly of them in their place, in this our Treatiſe of Monſters.

CHAP. II.

Of Monſters cauſed by too great abundance of Seed.

SEeing we have already handled the two former and truly final cauſes of Monſters, we muſt now come to thoſe which are material, corporeal, and efficient cauſes, taking our beginning from that we call the too great abundance of the matter of ſeed. It is the opinion of thoſe Philoſophers which have written of Monſters, that if at any time a Creature bearing one at once, as Man, ſhall caſt forth more ſeed in copulation than is neceſſary to the generation of one body, it cannot be that onely one ſhould be begot of all that: therefore from thence either two or more muſt ariſe: whereby it cometh to paſs, that theſe are rather judged wonders, becauſe they happen ſeldom, and contrary to common cuſtom. Superfluous parts happen by the ſame cauſe that Twins and many at one birth, contrary to Natures courſe, do chance, that is, by a larger effuſion of ſeed than is required for the framing of that part, that ſo it exceeds either in number or elſe in greatneſs. So *Auſtin* tells that in his time in the Eaſt, an Infant was born, having all the parts from the belly upwards double, but from thence downward ſingle and ſimple: for it had two heads, four eyes, two breaſts, four hands, in all the reſt like to another child, and it lived a little while. *Cælius Rhodiginus* ſaith he ſaw two Monſters in *Italy*, the one male, the other female, handſomely and neatly made through all their bodies, except their heads, which were double; the male died within a few days after it was born, but the female (whoſe ſhape is here delineated) lived five and twenty years, which is contrary to the common cuſtom of Monſters; for they for the moſt part are very ſhort-lived, becauſe they both live and are born, as it were, againſt Natures conſent; to which may be

be added, they do not love themſelves, by reaſon they are made a ſcorn to others, and that by that means lead a hated life.

But it is moſt remarkable which *Lycoſthenes* telleth of a * Woman-monſter; for, excepting her two heads, ſhe was framed in the reſt of her body to an exact perfection: her two heads had the like deſire to eat and drink, to ſleep, to ſpeak, and to do every thing; ſhe begged from door to door, every one giving to her freely. Yet at length ſhew was baniſhed *Bavaria*, leſt that by the frequent looking upon her, the imagination of Women with child, ſtrongly moved, ſhould make the like impreſſion in the Infants they bare in their Wombs.

*The Effigies of a * Maid with two heads.*

*The Effigies of two * Girls whoſe Backs grew together.*

In the Year of our Lord 1475. at *Verona* in *Italy*, two * Girls were born with their backs ſticking together from the lower part of the ſhoulders unto the very buttocks. The novelty and ſtrangeneſs of the thing moved their Parents, being but poor, to carry them through all the chief Towns in *Italy* to get money of all ſuch as came to ſee them.

The Figure of a Man with another growing out of him.

In the Year 1530. there was a man to be ſeen at *Paris*, out of whoſe belly another, perfect in all his members except head, hanged forth as if he had been grafted there. The man was forty years old, and he carried the other implanted or growing out of him, in his arms, with ſuch admiration to the beholders, that many ran very earneſtly to ſee him.

The

The Effigies of a horned or hooded Monſter.

At *Quiers*, a ſmall Village ſome ten miles from *Turin* in *Savoy*, in the Year 1578. upon the ſeventeenth day of *January*, about eight of the Clock at night, an honeſt Matron brought forth a Child having five horns, like to Rams horns, ſet oppoſite to one another upon his head: he had alſo a long piece of fleſh, like in ſome ſort to a French-hood which Women uſe to wear, hanging down from his forehead by the nape of his neck almoſt the length of his back: two other pieces of fleſh, like the collar of a ſhirt, were wrapped about his neck: the fingers ends of both his hands ſomewhat reſembled a Hawks Talons, and his knees ſeemed to be in his hams: the right leg and the right foot were of a very red colour; the reſt of the body was of a tawny colour: it is ſaid he gave ſo terrible a ſcritch when he was brought forth, that the Midwives, and the reſt of the Women that were at her labour, were ſo frighted that they preſently left the houſe and ran away. When the Duke of *Savoy* heard of this Monſter, he commanded it ſhould be brought to him, which performed, one would hardly think what various cenſures the Courtiers gave of it.

The Monſter you ſee here delineated, was found in the middle and innermoſt part of an * Egg, with the face of a Man, but hairs yielding a horrid repreſentation of Snakes; the chin had three other Snakes ſtretched forth like a beard. It was firſt ſeen at *Autun*, at the houſe of one *Bancheron* a Lawyer: a Maid breaking many Eggs to butter, the white of this Egg given a Cat, preſently killed her. Laſtly, this Monſter coming to the hands of the Baron *Seneey*, was brought to King *Charles* the nineth being then at *Metz*.

** The ſhape of a Monſter found in an Egg.*

The Effigies of a monſtrous ♭ Child, having two heads, two arms, and four legs.



In the Year 1546. a Woman at *Paris* in her ſixth Moneth of her account, brought forth a ♭ Child having two heads, two arms, and four legs. I diſſecting the body of it, found but one heart, by which one may know it was but one Infant. For you may know this from *Ariſtotle*, whether the monſtrous birth be one or more joined together, by the principal part: for if the body have but one heart, it is but one; if two, it is double by the joining together in the conception.

In

In the Year 1569. a certain Woman of *Tours* was delivered of * Twins joined together with one head, and naturally embracing each other. *Renatus Ciretus* the famous Chirurgeon of thoſe parts, ſent me their *Sceleton.*

*The Portraiture of * Twins joined together with one Head.*

The Effigies of two ᶜ Girls being Twins, joined together by their Fore-heads.

Munſter writes that in the Village *Briſtan*, not far from *Worms*, in the Year 1495. he ſaw two • Girls perfect and entire in every part of their bodies, but they had their Fore-heads ſo joined together that they could not be parted or ſevered by any art: they lived together ten years, then the one dying, it was needful to ſeparate the living from the dead: but ſhe did not long out-live her ſiſter, by reaſon of the malignity of the wound made in parting them aſunder.

In the Year of our Lord 1570. the twentieth of *July*, at *Paris* in the ſtreet *Gratilliers*, at the ſign of the Bell, theſe two Infants were born, differing in ſex, with that ſhape of body that you ſee here expreſſed in the Figure. They were baptized in the Church of S. *Nicolas* of the Fields, and named *Ludovicus* and *Ludovica*, their Father was a Maſon, his name was *Peter Germane*, his ſirname *Petit Dieu* (*i.*) Little-God, his Mothers name was *Mathea Petronilla.*

The ſhape of the Infants lately born at Paris.



In the Year 1572. in *Pont de See* near *Angers*, a little Town, were born upon the tenth day of *July*, two Girls, perfect in their limbs, but that they had but four fingers apiece on their left hands: they clave together in their fore-parts, from their breſt to their navel, which was but one, as their heart alſo but one; their liver was divided into four lobes; they lived half an hour, and were baptized.

The Figure of two Girls joined together in their breaſts and belly.

The Figure of a Child with two heads, and the body as big as one of four moneths old.

Var. lect. lib. 24. cap. 8. *Cælius Rhodiginus* tells, that in a Town of his Countrey called *Sarzano*, *Italy* being troubled with Civil Wars, there was born a Monſter of unuſual bigneſs; for he had two heads, having all his limbs anſwerable in greatneſs and tallneſs to a Child of four Moneths old: between his two heads, which were both alike, at the ſetting on of the ſhoulder, it had a third hand put forth, which did not exceed the ears in length, for it was not all ſeen: it was born the 5. of the Ides of *March*, 1514.

The Figure of one with four legs and as many arms.

The Figure of a man out of whoſe belly another head ſhewed it ſelf.

Jovianus Pontanus tells in the Year 1529. the nineth day of *January*, there was a man-child born in *Germany*, having four arms, and as many legs.

In the Year that *Francis* the firſt, King of *France*, entered into League with the *Swiſſes*, there was born a monſter in *Germany*, out of the midſt of whoſe belly there ſtood a great head; it came to mans age, and his lower, and as it were inſerted head, was nouriſhed as much as the true and upper head.

In

The ſhape of two monſtrous Twins, being but of one onely Sex.

In the Year 1572. the laſt day of *February*, in the Pariſh of *Vinhan*, in the way as you go from *Carnuta* to *Paris*, in a ſmall Village called *Bordes*, one called *Cyprina Giranda* the Wife of *James Merchant* a Husbandman, brought forth this Monſter whoſe ſhape you ſee here delineated, which lived until the Sunday following, being but of one onely Sex, which was the Female.

The ſhape of a Monſtrous Pig.

In the Year 1572. on Eaſter Monday at *Metz* in *Lorain*, in the Inn whoſe Sign is the *Holy Ghoſt*, a Sow pigged a Pig which had eight Legs, four Ears, and the Head of a Dog; the hinder part from the belly downward was parted in two as in Twins, but the fore-parts grew into one; it had two Tongues in the mouth, with four Teeth in the upper Jaw, and as many in the lower. The Sex was not to be diſtinguiſhed, whether it were a Bore or Sow Pig, for there was one ſlit under the Tail, and the hinder parts were all rent and open. The ſhape of this Monſter, as it is here ſet down, was ſent me by *Borgeſius* the famous Phyſician of *Metz*.

CHAP. III.

Of Women bringing many Children at one birth.

WOman is a Creature bringing uſually but one at a birth: but there have been ſome who have brought forth two, ſome three, ſome four, ſome five, ſix, or more at one birth. *Empedocles* thought that the abundance of ſeed was the cauſe of ſuch numerous births: the *Stoicks* affirm the divers Cells or Partitions of the Womb to be the cauſe; for the ſeed being variouſly parted into theſe Partitions, and the conception divided, there are more children brought forth; no otherwiſe than in Rivers, the Water beating againſt the Rocks, is turned into divers circles or rounds. But *Ariſtotle* ſaith there is no reaſon to think ſo; for in Women that parting of the Womb into Cells, as in Dogs and Sows, taketh no place; for Womens wombs have but one cavity, parted into two receſſes, the right and left, nothing coming between, except by chance diſtinguiſhed by a certain line; for often Twins lie in the ſame ſide of the Womb. *Ariſtotles* opinion is, that a Woman cannot bring forth more than five children at one birth. The Maid of *Auguſtus Cæſar* brought forth five at a birth, and a ſhort while after ſhe and her children died. In the year 1554. at *Bearn* in *Switzerland*, the Wife of Dr. *John Gelenger* brought forth five children at one birth, three Boys and two Girls. *Albucraſis* affirms a Woman to have been the Mother of ſeven children at one birth; and another, who by ſome external injury did abort, brought forth fifteen perfectly ſhaped in all their parts. *Pliny* reports that it was extant in the writings of Phyſicians, that twelve children were born at one birth; and that there was another in *Peloponneſus* which four ſeveral times was delivered of five children at one birth, and that the greater part of thoſe children lived. It is reported by *Dalechampius* that *Bonaventura* the ſlave of one *Savil*, a Gentleman of *Sena*, at one time brought forth ſeven children, of which four were baptized. In our time, between *Sarte* and *Main*, in the Pariſh of *Seaux*, not far from *Chambellay*, there is a Family and Noble Houſe called *Maldemeure*, the Wife of the Lord of *Maldemeure*, the firſt year ſhe was married brought forth Twins, the ſecond year ſhe had three children, the third year four, the fourth year five, the fifth year ſix, and of that birth ſhe died: of thoſe ſix one is yet alive, and is Lord of *Maldemeure*. In the Valley of *Beaufort*, in the County of *Anjou*, a young Woman the daughter of *Mace Channiere*, when at one perfect birth ſhe had brought forth one child, the tenth day following ſhe fell in labour of another, but could not be delivered until it was pulled from her by force, and was the death of the Mother.

4. *De gen. anim. cap.* 4.

Lib. 7. *cap.* 11. *cap.* 3.

The Picture of Dorothy *great with child with many children.*

The nineth Book of the Poliſh Hiſtory.

Martin Comerus the Author of the *Poliſh* Hiſtory, writeth that one *Margaret*, a woman ſprung from a noble and ancient Family near *Cracovia*, and wife to Count *Virboſlaus*, brought forth at one birth thirty five live children, upon the twentieth day of *January* in the Year 1296. *Franciſcus Picus Mirandula* writeth, that one *Dorothy* an *Italian* had twenty children at two births; at the firſt nine and at the ſecond eleven, and that ſhe was ſo big, that ſhe was forced to bear up her belly, which lay upon her knees, with a broad and large ſcarff tied about her neck, as you may ſee by this Figure.

And they are to be reprehended here again, who affirm the cauſe of numerous births to conſiſt in the variety of the Cells of the Womb; for they feign a Womans Womb to have ſeven Cells or Partitions, three on the right ſide for Males, three on the left ſide for Females, and one in the midſt for Hermaphrodites or Scrats: and this untruth hath gone ſo far, that there have been ſome that affirmed every of the ſeven Cells to have been divided into ten Partitions, into which the ſeed diſperſed, doth bring forth a divers and numerous increaſe, according to the variety of Cells furniſhed with the matter of ſeed; which, though it may ſeem to have been the opinion of *Hippocrates* in his Book *De Natura Pueri*, notwithſtanding it is repugnant to reaſon, and to thoſe things which are manifeſtly apparent to the eyes and ſenſes.

Lib.4. de Gen. anim. cap.4.

The opinion of *Ariſtotle* is more probable, who ſaith Twins and more at one birth, are begot and brought forth by the ſame cauſe that the ſixth finger groweth on the hand, that is, by the abundant plenty of the ſeed, which is greater and more copious than can be all taken up in the natural framing of one body; for if it all be forced into one, it maketh one with the parts increaſed more then is fit, either in greatneſs or number; but if it be, as it were, cloven into divers parts, it cauſeth more than one at one birth.

CHAP. IV.

Of Hermaphrodites, or Scrats.

AND here alſo we muſt ſpeak of Hermaphrodites, becauſe they draw the cauſe of their generation and conformation from the abundance of ſeed, and are called ſo, becauſe they are of both Sexes, the Woman yielding as much ſeed as the Man. For hereupon it commeth to paſs that the forming faculty (which always endeavours to produce ſomething like it ſelf) doth labour both the matters almoſt with equal force, and is the cauſe that one body is of both ſexes.

Yet ſome make four differences of Hermaphrodites; the firſt of which is the male Hermaphrodite, who is a perfect and abſolute male, and hath only a ſlit in the *Perinæum* not perforated, and from which neither Urin nor Seed doth flow. The ſecond is the female, which beſides her natural Privity, hath a fleſhy and skinny ſimilitude of a mans Yard, but unapt for erection and ejaculation of ſeed, and wanteth the Cod and Stones; the third difference is of thoſe, which albeit they bear the expreſs figures of members belonging to both ſexes, commonly ſet the one againſt the other, yet are found unapt for generation, the one of them onely ſerving for making of water: the fourth difference is of thoſe who are able in both ſexes, and throughly perform the part of both man and woman, becauſe they have the genitals of both ſexes complete and perfect, and alſo the right breſt like a man, and the left like a woman: the Laws command thoſe to chuſe the ſex which they will uſe, and in which they will remain and live, judging them to death if they be found to have departed from the ſex they made choice of; for ſome are thought to have abuſed both and promiſcuouſly to have had their pleaſure with men and women. There are ſigns by which the Phyſicians may diſcern whether the Hermaphrodites are able in the male or female ſex, or whethe

whether they are impotent in both: theſe ſigns are moſt apparent in the Privities and Face; for if the matrix be exact in all its dimenſions, and ſo perforated that it may admit a mans Yard, if the Courſes flow that way, if the hair of the head be long, ſlender and ſoft, and to conclude, if to this tender habit of the body a timid and weak condition of the mind be added, the Female ſex is predominant, and they are plainly to be judged Women. But if they have the *Perinæum* and fundament full of hairs, (the which in Women are commonly without any) if they have a yard of a convenient largeneſs, if it ſtand well and readily, and yield ſeed, the Male ſex hath the preheminence, and they are to be judged men. But if the conformation of both the genitals, be alike in figure, quantity, and efficacy, it is thought to be equally able in both ſexes: although by the opinion of *Ariſtotle*, thoſe who have double genitals, the one of the male, the other of the female, the one of them is always perfect, the other imperfect. *Lib. 4. de genit. anim. cap. 5.*

The Figure of Hermaphrodite Twins cleaving together with their backs.

Anno Dom. 1486. in the Palatinate, at the Village *Robach*, near *Heidelberg*, there were Twins, both Hermaphrodites, born with their backs ſticking together.

The Effigies of an Hermaphrodite having four hands and feet.

The ſame day the *Venetians* and *Genoeſes* entered into league, there was a Monſter born in *Italy* having four arms and feet, and but one head; it lived a little after it was baptized. *James Ruef* a *Helvetian* Chirurgeon ſaith he ſaw the like, but which beſides had the Privities of both ſexes, whoſe figure I have therefore ſet forth, *Page* 590.

CHAP. V.

Of the changing of Sex.

Amatus Luſitanus reports that in the Village *Eſquina*, there was a maid named *Maria Pateca*, who at the appointed age for her Courſes to flow, had in ſtead of them a mans Yard, lying before that time hid and covered, ſo that of a Woman ſhe became a Man, and therefore laying aſide her Womans habit, was cloathed in mans, and changing her name, was called *Emanuel*; who when he had got much wealth by many and great negotiations and commerce in *India*, returned into his Country, and married a wife: but *Luſitanus* ſaith he did not certainly know whether he had any children, but that he was certain he remained always beardleſs.

Anthony Loqueneux, the Kings Keeper or Receiver of his Rents of St. *Quintain*, at *Vermandois*, lately affirmed to me that he ſaw a man at *Reims*, at the Inn having the ſign of the *Swan*, in the Year 1560. who was taken for a Woman until the fourteenth year of his age; for then it happened as he played ſomewhat wantonly with a Maid which lay in the ſame bed with him, his members (hitherto lying hid) ſtarted forth and unfolded themſelves: which when his Parents knew (by help of the Eccleſiaſtick power) they changed his name from *Joan* to *John*, and put him in mans apparel.

Some years agone, being in the Train of King *Charles* the Nineth, in the French Glaſs-houſe, I was ſhewed a man called *Germane Granierus*, but by ſome *Germane Maria* (becauſe in former times when he was a Woman he was called *Marie*) he was of an indifferent ſtature, and well ſet body, with a thick and red beard; he was taken for a Girl until the fifteenth Year of his Age, becauſe there was no ſign of being a man ſeen in his body, and for that amongſt Women, he in like attire did thoſe things which appertain to Women: in the fifteenth year of his age, whileſt he ſomewhat earneſtly purſued Hogs given into his charge to be kept, who running into the Corn, he leaped violently over a ditch, whereby it came to paſs that the ſtays and foldings being broken, his hidden members ſuddenly broke forth, but not without pain; going home, he weeping complained to

his Mother that his guts came forth: with which his Mother amazed, calling Phyſicians and Surgeons to counſel, heard he was turned into a man; therefore the whole buſineſs being brought to the Cardinal the Biſhop of *Lenuncure*, an aſſembly being called, he received the name and habit of a man.

Pliny reports that the ſon of *Caſſinus* of a Girl became a Boy, living with his Parents; but by the command of the Sooth-ſayers he was carried into a Deſart Iſle, becauſe they thought ſuch Monſters did always ſhew or portend ſome monſtrous thing. Certainly women have ſo many and like parts lying in their womb, as men have hanging forth; onely a ſtrong and lively heat ſeems to be wanting, which may drive forth that which lies hid within: therefore in proceſs of time the heat being increaſed and flouriſhing, and the humidity (which is predominant in child-hood) overcome, it is not impoſſible that the virile members, which hitherto ſluggiſh by defect of heat, lay hid, may be put forth; eſpecially if to that ſtrength of the growing heat ſome vehement concuſſion or jactation of the body be joined. Therefore I think it manifeſt by theſe experiments and reaſons, that it is not fabulons that ſome women have been changed into men: but you ſhall find in no hiſtory, men that have degenerated into women; for Nature always intends and goes from the imperfect to the more perfect, but not baſely from the more perfect to the imperfect.

CHAP. VI.

Of Monſters cauſed by the defect of Seed.

IF, on the contrary, the ſeed be any thing deficient in quantity, for the conformation of the Infant or Infants, ſome one or more members will be wanting, or more ſhort and decrepit. Hereupon it happens that Nature intending Twins, a Child is born with two heads, and but one arm, or altogether lame in the reſt of his limbs.

The Effigies of a monſtrous child, by reaſon of the defect of the matter of Seed.

Anno Dom. 1573. I ſaw at St. *Andrews* Church in *Paris*, a Boy nine years old, born in the Village *Parpavilla*, ſix miles from *Guiſe*; his Fathers name was *Peter Renard*, and his Mother, *Marquete:* he had but two fingers on his right hand, his arm was well proportioned from the top of his ſhoulder almoſt to his wriſt, but from thence to his two fingers ends it was very deformed; he wanted his legs and thighs, although from the right buttock a certain unperfect Figure, having onely four Toes, ſeemed to put it ſelf forth; from the midſt of the left buttock two Toes ſprung out, the one of which was not much unlike a mans Yard, as you may ſee by the Figure.

In the Year 1562. in the Calends of *November*, at *Villa Franca* in *Gaſcony*, this Monſter, a headleſs woman, whoſe Figure hereafter follows, was born, which figure Dr. *John Altinus* the Phyſician gave to me, when I went about this Book of Monſters, he having received it from *Fontanus* the Phyſician of *Angoleſtre*, who ſeriouſly affirmed he ſaw it.

The

The Figure of a monſtrous woman without a head, before and behind.



The Effigies of a man without arms, doing all that is uſually done with hands.

The Effigies of a Monſter with two heads, two legs, and but one arm.

A few years agone there was a man of forty years old to be ſeen at *Paris*, who although he wanted his arms, notwithſtanding did indifferently perform all thoſe things which are uſually done with the hands; for with the top of his ſhoulder, head and neck, he would ſtrike an Ax or Hatchet with as ſure and ſtrong a blow into a poſt, as any other man could do with his hand: and he would laſh a Coachmans whip, that he would make it give a great crack, by the ſtrong refraction of the air; but he eat, drank, plaid at Cards, and ſuch like, with his feet. But at laſt he was taken for a Thief and Murderer, was hanged and faſtned to a wheel.

Alſo not long ago there was a Woman at *Paris* without arms, which neverthelеſs did cut, ſew, and do many other things, as if ſhe had her hands.

We read in *Hippocrates*, that *Attaginis* his wife brought forth a child all of fleſh without any bone, and notwithſtanding it had all the parts well formed.

CHAP.

CHAP. VII.

Of Monſters which take their cauſe and ſhape by imagination.

The force of imagination upon the body and humours.

THe Ancients having diligently ſought into all the ſecrets of Nature, have marked and obſerved other cauſes of the generation of Monſters: for, underſtanding the force of imagination to be ſo powerful in us, as for the moſt part, it may alter the body of them that imagine, they ſoon perſuaded themſelves that the faculty which formeth the Infant may be led and governed by the firm and ſtrong cogitation of the Parents begetting them (often deluded by nocturnal and deceitful apparitions) or by the mother conceiving them; and ſo that which is ſtrongly conceived in the mind, imprints the force into the Infant conceived in the womb: which thing many think to be confirmed by *Moſes*, becauſe he tells that *Jacob* increaſed and bettered the part of the ſheep granted to him by *Laban* his Wifes father, by putting rods, having the bark in part pulled off, finely ſtreaked with white and green, in the places where they uſed to drink, eſpecially at the time they engendered, that the repreſentation apprehended in the conception, ſhould be preſently impreſſed in the young; for the force of imagination hath ſo much power over the Infant, that it ſets upon it the notes or characters of the thing conceived.

Gen. cap. 30.

We have read in *Heliodorus*, that *Perſia* Queen of *Æthiopia*, by her Husband *Hidaſtes*, being alſo an Ethiope, had a daughter of a white complexion, becauſe in the embraces of her husband, by which ſhe proved with child, ſhe earneſtly fixed her eye and mind upon the picture of then fair *Andromeda* ſtanding oppoſite unto her. *Damaſcene* reports, that he ſaw a Maid hairy like a Bear, which had that deformity by no other cauſe or occaſion than that her Mother earneſtly beheld in the very inſtant of receiving and conceiving the ſeed, the image of St. *John* covered with a Camels skin, hanging upon the poſts of the bed.

They ſay *Hippocrates* by this explication of the cauſes, freed a certain Noble-woman from ſuſpicion of adultery, who being white her ſelf, and her husband alſo white, brought forth a child as black as an Ethiopian, becauſe in copulation ſhe ſtrongly and continually had in her mind the picture of the Ethiope.

The Effigies of a Maid all hairy, and an Infant that was black by the imagination of their Parents.

There are ſome who think the Infant once formed in the Womb, which is done at the utmoſt within two and forty days after the conception, is in no danger of the Mothers imagination, neither of the ſeed of the Father which is caſt into the Womb, becauſe when it hath got a perfect figure, it cannot be altered with any external form of things; which whether it be true or no, is not here to be inquired of: truly I think it beſt to keep the woman all the time ſhe goeth with child, from the ſight of ſuch ſhapes and figures.

In *Stequer* a Village of *Saxony*, they ſay, a Monſter was born with four feet, eyes, mouth, and noſe like a Calf, with a round and red excreſcence of fleſh on the fore-head, and alſo a piece of fleſh like a hood hung from his neck upon his back, and it was deformed with its thighs torn and cut.

The

The effigies of a horrid Monſter, having feet, hands and other parts like a Calf.

The effigies of an Infant with a face like a Frog.

Anno Dom. 1517. in the Pariſh of *Kings-wood* in the Foreſt of *Biera*, in the way to *Fontainbleau*, there was a Monſter born with the face of a Frog, being ſeen by *John Bellanger*, Chirurgeon to the Kings Engineers, before the Juſtices of the Town of *Harmoy*, principally *John Bribon* the Kings Procurator in that place. The Fathers name was *Amadæus the Little*, his Mothers *Magdalene Sarbucala*, who troubled with a Fever, by a Womans perſuaſion, held a quick Frog in her hand until it died; ſhe came thus to bed with her husband and conceived: *Bellanger*, a man of an acute wit, thought this was the cauſe of the monſtrous deformity of the child.

CHAP. VIII.

Of Monſters cauſed by the ſtraitneſs of the Womb.

That the ſtraitneſs or littleneſs of the womb may be the occaſion of Monſters.

WE are conſtrained to confeſs by the event of things, that Monſters are bred and cauſed by the ſtraitneſs of the Womb; for ſo Apples growing upon the Trees, if before they come to juſt ripeneſs they be put into ſtrait Veſſels, their growth is hindred. So ſome Whelps which Women take delight in, are hindred from any further growth by the littleneſs of the place in which they are kept. Who knows not that the Plants growing in the Earth, are hindred from a longer progreſs and propagation of their roots, by the oppoſition of a Flint, or any other ſolid body, and therefore in ſuch places are crooked, ſlender and weak, but on the other part, where they have free nouriſhment, to be ſtrait and ſtrong? for ſeeing that by the opinion of Naturaliſts, the place is the form of the thing placed, it is neceſſary that thoſe things that are ſhut up in ſtraiter ſpaces, prohibited of free motion, ſhould be leſſened, depraved, and lamed.

Empedocles and *Diphilus* acknowledged three cauſes of monſtrous births: The too great or ſmall matter of the ſeed, the corruption of the ſeed, and depravation of growth by the ſtraitneſs or figure of the womb, which they thought the chiefeſt of all, becauſe they thought the cauſe was ſuch in natural births, as in forming of Metals and fuſible things, of which Statues being made, do leſs expreſs the things they be made for, if the molds or forms into which the matter is poured, be rough, ſcabrous, too ſtrait, or otherwiſe faulty.

CHAP. IX.

Of Monſters cauſed by the ill placing of the Mother, in ſitting, lying down, or any other ſite of the body in the time of her being with child.

WE often too negligently and careleſly corrupt the benefits and corporal endowments of Nature in the comlineſs and dignity of conformation: it is a thing to be lamented and pitied in all, but eſpecially in women with child, becauſe that fault doth not onely hurt the Mother, but deforms and perverts the Infant which is contained in her womb: for we moving any manner of way, muſt neceſſarily move whatſoever is within us. Therefore they which ſit idlely at home all the time of their being with Child, as croſs-legged, thoſe which

which holding their heads down, do ſew or work with the needle, or do any other labour, which preſs the belly too hard with cloaths, breeches, and ſwathes, do produce children wry-necked, ſtooping, crooked, and disfigured in their feet, hands, and the reſt of their joints, as you may ſee in the following Figure.

The Effigies of a child, who from the firſt conception, by the ſite of the Mother, had his hands and feet ſtanding crooked.

CHAP. X.

Of Monſters cauſed by a ſtroke, fall, or the like occaſion.

THere is no doubt but if any injury happen to a Woman with child, by reaſon of a ſtroke, fall from on high, or the like occaſion, the hurt alſo may extend to the child. Therefore by theſe occaſions the tender bones may be broken, wreſted, ſtrained, or depraved after ſome other monſtrous manner: and more, by the like violence of ſuch things, a Vein is often opened or broken, or a flux of bloud, or great Vomiting is cauſed by the vehement concuſſion of the whole body, by which means the child wants nouriſhment, and therefore will be ſmall and little, and altogether monſtrous.

CHAP. XI.

Of Monſters which have their original by reaſon of hereditary diſeaſes.

BY the injury of hereditary diſeaſes Infants grow monſtrous, that is, monſtrouſly deformed: for Crook-backed produce Crook-backed, and often-times ſo crooked, that between the bunch behind and before, the head lies hid, as a Tortoiſe in her ſhell: ſo Lame produce Lame, Flat-noſed their like, Dwarffs bring forth Dwarffs, Lean bring forth Lean, and Fat produce Fat.

CHAP.

CHAP. XII.

Of Monſters by the confuſion of Seed of divers kinds.

THat which followeth is a horrid thing to be ſpoken; but the chaſte mind of the Reader will give me pardon, and conceive that, which not onely the Stoicks, but all Philoſophers, who are buſied about the ſearch of the cauſes of things muſt hold, That there is nothing obſcene or filthy to be ſpoken. Thoſe things that are accounted obſcene may be ſpoken without blame, but they cannot be acted or perpetrated without great wickedneſs, fury and madneſs; therefore that ill which in obſcurity conſiſts not in word, but wholly in the act. Therefore in times paſt there have been ſome, who nothing fearing the Deity, neither the Law, nor themſelves, that is, their ſoul, have ſo abjected and proſtrated themſelves, that they have thought themſelves nothing different from Beaſts: wherefore Atheiſts, Sodomites, Out-laws, forgetful of their own excellency and divinity, and transformed by filthy luſt, have not doubted to have filthy and abominable copulation with Beaſts. This ſo great, ſo horrid a crime, for whoſe expiation all the fires in the World are not ſufficient, though they too maliciouſly crafty, have concealed, and the conſcious Beaſts could not utter, yet the generated miſ-ſhapen iſſue hath abundantly ſpoken and declared, by the unſpeakable power of God, the revenger and puniſher of ſuch impious and horrible actions. For of this various and promiſcuous confuſion of ſeeds of a different kind, Monſters have been generated and born, who have been partly Men and partly Beaſts.

The like deformity of iſſue is produced, if Beaſts of a different ſpecies do copulate together, Nature always affecting to generate ſomething which may be like it ſelf: for Wheat grows not but by ſowing of Wheat, nor an Apricock but by the ſetting or grafting of an Apricock, for Nature is a moſt diligent preſerver of the ſpecies of things.

The Effigies of a Monſter half Man and half Dog.

Anno Dom. 1493. there was generated of a Woman and a Dog an iſſue, which from the navel upwards perfectly reſembled the ſhape of the Mother, but therehence downwards the Sire, that is, the Dog. This Monſter was ſent to the Pope that then reigned, as *Volaterane* writeth: alſo *Cardane* mentions it; wherefore I have given you the Figure thereof. *Cardan. lib. 14. de var. rerum cap. 94.*

The Figure of a Monſter in Face reſembling a Man, but a Goat in his other Members.

Cælius Rhodiginus writes that at *Sibaris*, a Herdſman called *Chrathis* fell in love with a Goat, and accompanied with her, and of this deteſtable and brutiſh copulation an Infant was born, which in legs reſembling the Dam, but the face was like the Fathers.

The

The Figure of a Pig, with a Head, Face, Hands, and Feet of a Man.

Anno Dom. 1110. in a certain Town of *Liege* (as ſaith *Lycoſthenes*) a Sow farrowed a Pig with the Head, Face, Hands and Feet of a Man, but in the reſt of the body reſembling a Swine.

Anno Dom. 1564. at *Bruxels* at the houſe of one *Joeſt Dičizpeert*, in the Street *Warmoesbroečs*, a Sow farrowed ſix Pigs, the firſt whereof was a Monſter repreſenting a Man in the Head, Face, Fore-feet and Shoulders, but in the reſt of the body another Pig, for it had the genitals of a Sow-pig, and it ſucked like other Pigs: but the ſecond day after it was farrowed, it was killed of the People together with the Sow, by reaſon of the monſtrouſneſs of the thing. Here followeth the Figure thereof.

The Effigies of a Monſter half Man and half Swine.



Anno Dom. 1571. at *Antwerp*, the wife of one *Michael* a Printer, dwelling with one *John Molline* a Graver or Carver, at the Sign of the Golden Foot in the *Camiſtrate*, on S. *Thomas* his day, at ten of the Clock in the Morning, brought forth a Monſter wholly like a Dog, but that it had a ſhorter neck, and the head of a Bird, but without any Feathers on it. This Monſter was not alive, for that the Mother was delivered before her time; but ſhe giving a great ſcritch in the inſtant of her deliverance the Chimney of the houſe fell down, yet hurt no body, no not ſo much as any one of four little children that ſate by the fire-ſide.

The Figure of a Monſter like a Dog, but with a Head like a Bird.

The

The Figure of a three-headed Lamb.

Lewis Gellius writeth that he hath read in an approved Author, that an Ewe once brought forth a Lion, a Beast of an unlike and adverse nature to her.

*An.Dom.*1577. in the Town of *Blandy* three miles from *Melon*, there was lambed a Lamb having three heads, the middlemost of which was bigger than the rest; when one bleated they all bleated. *John Bellanger* the Chirurgeon of *Melo* affirmed that he saw this Monster, and got it drawn, and sent the figure thereof to me with that humane Monster that had the head of Frog, which we have formerly described.

There are some Monsters in whose generation by this there may seem to be some divine cause, for that their beginnings cannot be derived or drawn from the general cause of Monsters; that is, Nature, or the errours thereof, by reason of some of the fore-mentioned particular causes: such are these Monsters that are wholly against all Nature, like that which we formerly mentioned of a Lion yeaned by an Ewe.

Yet Astrologers (lest there should seem to be any thing which they are ignorant of) refer the causes of these to certain constellations and aspects of the Planets and Stars, according to *Aristotles* saying in his Problems; in confirmation whereof they tell us this tale. It happened in the time of *Albertus Magnus*, that in a certain Village, a Cow brought forth a Calf which was half a man: the Townsmen apprehended the Herdsman, and condemned him as guilty of such a crime, to be presently burnt together with the Cow; but by good luck *Albertus* was there, to whom they gave credit, by reason of his much and certain experience in Astrology, that it was not occasioned by any humane wickedness, but by the efficacy of a certain position of the Stars that this Monster was born.

CHAP. XIII.

Of Monsters occasioned by the craft and subtilty of the Devil.

IN treating of such Monsters as are occasioned by the craft of the Devil, we crave pardon of the courteous Reader, if peradventure going further from our purpose, we may seem to speak more freely and largely of the Existence, Nature, and Kinds of Devils. Therefore first it is manifest that there are Conjurers, Charmers, and Witches, which whatsoever they do, perform it by an agreement and compact with the Devil, to whom they have addicted themselves: for none can be admitted into that Society of Witches, who hath not forsaken God the Creator, and his Saviour, and hath not transferred the Worship due to Him above, upon the Devil, to whom he hath obliged himself. And assuredly, whosoever addicts himself to these Magical vanities and Witchcrafts, doth it either because he doubts of Gods Power, Promises, steady and great Good Will towards us: or else for that he is madded with an earnest desire of knowing things to come; or else because disdaining poverty, he affects and desires from a poor estate to become rich on the sudden. It is the constant opinion of all, both Ancient and Modern, as well Philosophers as Divines, that there are some such men; which when they have once addicted themselves to impious and devillish Arts, can by the wondrous craft of the Devil, do many strange things, and change, and corrupt bodies, and the health and life of them, and the condition of all mundane things. Also experience forceth us to confess the same; for punishments are ordained by the Laws against the Professors and Practisers of such Arts; but there are no Laws against those things which neither ever have been, nor ever came into the knowledge of men: for such things are rightly judged and accounted for impossibilities, which have never been seen or heard of.

There are Sorcerers, and how they come so to be.

What induceth them thereto.

Before the birth of Christ there have been many such People; for you may find in *Exodus* and *Leviticus* Laws made against such persons by *Moses*, by whom God gave the Law to his People. The Lord gave the sentence of death to *Ochasias* by his Prophet, for that he turned unto these kind of people. We are taught by the Scriptures that there are good and evil spirits, and that the former are termed Angels, but the latter Devils; for the Law is also said to be given by the Ministry of Angels: and it is said that our bodies should rise again at the sound of a Trumpet, and at the voice of an Arch-Angel. Christ said that God would send his Angels to receive the Elect into the Heavens.

Exod.cap.22. Levit.cap.19.

Hebr.1.14. Gal 3.19. 1 Thess.4.16.

The History of *Job* testifieth that the Devil sent fire from Heaven, and killed his Sheep and Cattel, and raised winds that shook the four corners of the house, and overwhelmed his children in the ruines thereof. The History of *Achab* mentioneth a certain lying spirit in the mouth of the false Prophets. Satan entring into *Judas* moved him to betray Christ. Devils who in a great num-

Job 13. Mat.16 34.

ber possessed the body of a man, were called and obtained of Christ that they might enter into Swine, whom they carried headlong into the Sea.

In the beginning God created a great number of Angels, that those divine and incorporeal spirits might inhabit Heaven, and as Messengers, signifie Gods pleasure to men, and as Ministers or Servants, perform his commands, who might be as Over-seers, and Protectors of humane affairs. Yet of this great number there were some who were blinded by pride, and thereby also cast down from the presence, and heavenly habitation of God the Creator. These harmful and crafty spirits delude mens minds by divers jugling tricks, and are always contriving something to our harm, and would in a short space destroy mankind, but that God restrains their fury; for they can onely do so much as is permitted them: Expelled Heaven, some of them inhabit the Air, others the bowels of the Earth; there to remain till God shall come to judge the World: and as you see the Clouds in the Air somewhiles to resemble Centaurs, otherwhiles Serpents, Rocks, Towers, Men, Birds, Fishes, and other shapes: so these spirits turn themselves into all the shapes and wondrous forms of things; as oft-times into wild Beasts, into Serpents, Toads, Owls, Lapwings, Crows or Ravens, Goats, Asses, Dogs, Cats, Wolves, Bulls, and the like. Moreover, they oft-times assume and enter humane bodies, as well dead as alive, whom they torment and punish, yea also they transform themselves into Angels of Light.

The Power of evil spirits over mankind.

The differences of Devils.

The delusions of Devils.

They feign themselves to be shut up and forced by Magical Rings, but that is onely their deceit and craft; they wish, fear, love, hate, and oft-times as by the appointment and decree of God, they punish Malefactors: for we read that God sent evil Angels into *Egypt*, there to destroy. They howl in the night, they murmur and rattle as if they were bound in chains, they move Benches, Tables, Counters, Props, Cupbords, Children in the Cradles, play at Tables and Chess, turn over Books, tell Money, walk up and down Rooms and are heard to laugh, to open Windows and Doors, cast sounding Vessels, as Brass and the like, upon the ground, break Stone-pots and Glasses, and make other the like noises. Yet none of all these things appear to us when we arise in the morning, neither find we any thing out of its place or broken. They are called by several names, as Devils, Evil spirits, *Incubi*, *Succubi*, Hobgoblins, Fairies, Robin-good-fellows, Evil angels, Sathan, Lucifer, the Father of Lies, Prince of Darkness, and of the World, Legion, and other names agreeable to their Offices and Natures.

Their Titles and Names.

CHAP. XIV.

Of the subterrene Devils, and such as haunt Mines.

What the Devils in Mines do.

Lewis Lavater writes, that by the certain report of such as work in Mines, that in some Mines there are seen spirits, who in the shape and habit of Men, work there, and running up and down seem to do much work, when notwithstanding they do nothing indeed. But in the mean time they hurt none of the by-standers, unless they be provoked thereto by words or laughter: for then they will throw some heavy or hard thing upon him that hurt them, or injure them some other way.

The same Author affirms that there is a silver Mine in *Rhetia*, out of which *Peter Briot*, the Governour of the place, did in his time get much Silver. In this Mine there was a Devil, who chiefly on Friday, when as the Miners put the Mineral they had digged into Tubs, kept a great quarter, and made himself exceeding busie, and poured the Mineral as he listed, out of one Tub into another. It happened one day that he was more busie than he used to be, so that one of the Miners reviled him, and bad him be gone on a vengeance to the punishment appointed for him. The Devil offended with this imprecation and scoff, so wrested the Miner, taking him by the head, twining his neck about, he set his face behind him, yet was not the Workman killed therewith, but lived, and was known by divers for many years after.

CHAP. XV.

By what means the Devils may deceive us.

Devils are Spirits.

Our minds involved in the earthy habitation of our bodies, may be deluded by the Devils divers ways: for they excel in purity and subtilty of essence, and in the much use of things: besides, they challenge a great preheminence, as the Princes of this World, over all sublunary bodies. Wherefore it is no marvel if they, the Teachers and Parents of Lies, should cast clouds and mists before our Eyes from the beginning, and turn themselves into a thousand shapes of things and bodies, that by these juglings and tricks they may shadow and darken mens minds.

CHAP. XVI.

Of Succubi *and* Incubi.

The reason of the name.

*Lib.*15. *de civ. Dei, cap.* 22, *&* 23.

Powerful by these fore-mentioned Arts and Deceits, they have sundry times accompanied with men in copulation, whereupon such as have had to do with men, were called *Succubi*; those which made use of Women, *Incubi*. Verily St. *Augustine* seemeth not to be altogether against it, but that they, taking upon them the shape of man, may fill the genitals, as by the help of Nature, to the end that by this means they may draw aside the unwary, by the flames of Lust, from Vertue and Chastity.

An History.

John Ruse, in his Book of the Conception and Generation of Man, writes that in his time, a certain

certain Woman of monstrous lust, and wondrous imprudency, had to do by night with a Devil that turned himself into a man, and that her belly swelled up presently after the act, and when as she thought she was with child, she fell into so grievous a disease, that she voided all her entrails by stool, Medicins nothing at all prevailing.

An History. The like History is told of a servant of a certain Butcher, who thinking too attentively on Venerous matters, a Devil appeared to him in the shape of a Woman, with whom (supposing it to be a Woman) when as he had to do, his genitals so burned after the act, that becoming inflamed he died with a great deal of torment.

An opinion confuted. Neither doth *Peter Paludanus*, and *Martin Arelatensis* think it absurd to affirm that Devils may beget children, if they shall ejaculate into the Womans womb seed taken from some man either dead or alive. Yet this opinion is most absurd and full of falsity, mans seed consisting of a seminal or sanguinous matter, and much spirit: if it run otherwise into the womb than from the testicles, and stay never so little a while, it loseth its strength and efficacy, the heat and spirits vanishing away; for even the too great length of a mans yard is reckoned amongst the causes of barrenness, by reason that the seed is cooled by the length of the way. If any in copulation, after the ejaculation of the seed, presently draw themselves from the Womans embraces, they are thought not to generate, by reason of the air entering into the yet open womb, which is thought to corrupt the seed. By which it appears how false that History in *Averrois* is, of a certain Woman that said she conceived with child by a mans seed shed in a Bath, and so drawn into her womb, she entering the Bath presently after his departure forth. It is much less credible that Devils can copulate with Women, for they are of an absolute spirituous Nature; but bloud and flesh are necessary for the generation of man. What natural reason can allow that the incorporeal Devils can love corporeal Women? And how can we think that they can generate, who want the instruments of generation? How can they who neither eat nor drink be said to swell with seed? Now where the propagation of the species is not necessary to be supplied by the succession of individuals, Nature hath given no desire to Venery, neither hath it imparted the use of generation; but the Devils once created were made immortal by Gods appointment: If the faculty of generation should be granted to Devils, long since all places had been full of them. Wherefore if at any time Women with child by the familiarity of the Devil, seem to travel, we must think it happens by those Arts we mentioned in the former Chapter, to wit, they use to stuff up the bodies of living Women with cold clouts, bones, pieces of iron, thorns, twisted hairs, pieces of wood, Serpents, and a world of such trumpery, wholly dissenting from a Womans nature: who afterwards, the time, as it were, of their delivery drawing nigh, through the womb of her that was falsly judged with child, before the blinded, and, as it were bound up eyes of the by-standing women, they give vent to their impostures. The following History, recorded in the Writings of many most credible Authors, may give credit thereto.

Averrois his History convict of falsehood.

The illusions of the Devil.

An History. There was at *Constance* a fair Damosel called *Margaret*, who served a wealthy Citizen: she gave it out every where that she was with child by lying with a Devil on a certain night. Wherefore the Magistrates thought it fit she should be kept in Prison, that it might be apparent both to them and others, what the end of this exploit would be. The time of deliverance approaching, she felt pains like those which Women indure in travail; at length, after many throws, by the Midwives help, in stead of a child, she brought forth iron nails, pieces of wood, of glass, bones, stones, hairs, tow, and the like things, as much different from each others as from the nature of her that brought them forth, and which were formerly thrust in by the Devil to delude the too credulous minds of men.

Our sins are the cause that the Devils abuse us. The Church acknowledgeth that Devils by the permission and appointment of God punishing our wickedness, may abuse a certain shape, so to use copulation with mankind. But that an humane birth may thence arise, it not onely affirms to be false, but detests as impious, as which believes that there was never any man begot without the seed of man, our Saviour Christ excepted. Now what confusion and perturbation of Creatures should possess this world (as *Cassianus* saith) if Devils could conceive by copulation with men? or if Women should prove with child by accompanying them, how many Monsters would the Devils have brought forth from the beginning of the world? how many Prodigies by casting their seed into the wombs of wild and brute Beasts? for by the opinion of Philosophers, as often as Faculty and Will concur, the effect must necessarily follow: now the Devils never have wanted will to disturb mankind, and the order of this World; for the Devil as they say, is our common enemy from the beginning; and as God is the author of order, and beauty, so the Devil, by Pride, contrary to God, is the causer of confusion and wickedness.

Wherefore if power should accrew equal to his evil mind and nature, and his infinite desire of mischief and envy; who can doubt but a great confusion of all things and species, and also great deformity would invade the decent and comely order of this Universe, Monsters arising on every side: But seeing that Devils are incorporeal, what reason can induce us to believe that they can be delighted with venerous actions: and what will can there be whereas there is no delight, nor any decay of the species to be feared? seeing that by Gods appointment they are immortal, so to remain for ever in punishment; so what need they succession of individuals by generation? wherefore if they neither will nor can, it is a madness to think that they do commix with Man.

CHAP. XVII.

Of Magick and supernatural Diseases and Remedies.

THat I may refresh the mind of the Reader, invited to these Histories of Monsters raised up by the Art of the Devil, Witches, and Conjurers, his Servants, I have thought good to add the following History of certain Diseases, and remedies supernatural, and wholly magical out of *Fernelius*. There are Diseases, which as they are sent amongst men by God being offended, so they cannot expect cure otherwise than from God, from whence they are thought supernaturally to have their essence and cure. Thus the Air oft-times, yet chiefly in the time of King *David*, being defiled with the Pestilence, killed sixty odd thousand persons.

Lib. 2. de abdit. caus. cap. 16.

Thus *Hezechias* was struck with a grievous disease: *Job* was defiled with filthy Ulcers by *Satan* at Gods command. And as the Devil, the cruel enemy of mankind, commonly useth by Gods permission to afflict those: so wicked persons by the wondrous subtilty of the Devil, offer violence and do harm to many. Some invoke I know not what Spirits, and adjure them with Herbs, Exorcisms, Imprecations, Incantations, Charms: and others hang about their necks, or otherwise carry certain Writings, Characters, Rings, Images, and other such impious stuff. Some use Songs, Sounds, or Numbers: sometimes Potions, Perfumes, and Smells; sometimes Gestures and Jugling. There be some that make the portraiture of the absent Party in Wax, and boast that they can cause or bring a disease into whatsoever part thereof they prick, by the force of their Words and Stars, into the like part of the party absent; and they have no few other tricks to bring other diseases.

Witches hurt by the Devils assistance.

We know for certain that Magicians, Witches, and Conjurers, have by charms so bound some that they could not have to do with their Wives; and have made others so impotent, as if they had been gelt or made Eunuchs. Neither do wicked men onely send diseases into mans body, but also Devils themselves. These truly are soon distracted with a certain Fury, but in this one thing they differ from simple Madness, for that they speak things of great difficulty, tell things past and hid, disclose the secrets of such as are present, and revile them many ways, and are terrified, tremble and grow angry by the power of divine words.

An History.

One not very long agon, being by reason of heat exceeding drie in the night-time, rising out of his sleep. and not finding drink, took an apple that he found by chance, and eating it he thought his jaws were shut and held fast as by ones hands, and that he was almost strangled: and also now possessed of a Devil entering into him, he seemed in the dark to be devoured of a huge exceeding black Dog, which he, afterwards restored to his former health, orderly related to me. There were divers who by his pulse, heat and the roughness of his tongue, thought him to be in a Fever, and by his watching, and the perturbation of his mind, thought him onely to rave.

An History.

Another young Noble man, some few years since, was troubled at set times with a shaking of the body, and as it were a Convulsion, wherewith one while he would move onely his left arm, another while the right arm; and also sometimes but one finger onely, somewhiles but one leg, sometimes the other, and at other times the whole trunk of his body, with such force and agility, that lying in his bed, he could scarce be held by four men; his head lay without any shaking, his tongue and speech was free, his understanding sound, and all his senses perfect even in the height of his fit. He was taken at the least ten times a day, well in spaces between, but wearied with labour: it might have been judged a true Epilepsie, if the understanding and senses had failed.

The most judicious Physicians who were called to him, judged it a Convulsion, cousin-german to the Falling-sickness, proceeding from a malign and venomous vapour impact in the spine of the Back, whence a vapour dispersed it self over all the Nerves, which pass from the spine every way into the Limbs, but not into the Brain. To remove this, which they judged the cause, frequent Clysters are ordained, and strong Purges of all sorts, Cupping-glasses are applied to the beginnings of the Nerves, Fomentations, Unctions, Emplasters, first to discuss, then to strengthen and wear away the malign quality: These things doing little good, he was sweated with Baths, Stoves, and a Decoction of *Guaiacum*, which did no more good than the former, for that we were all far from the knowledge of the true cause of his Disease: for in the third moneth, a certain Devil was found to be the Author of all this ill, bewraying himself by voice, and unaccustomed words and sentences, as well Latin as Greek (though the Patient were ignorant of the Greek Tongue:) he laid open many Secrets of the By-standers, and chiefly of the Physicians, deriding them for that he had abused them to the Patients great harm, because they had brought his body so low by needless Purgations.

The Devil shews himself by speaking of Greek.

When his Father came to visit him, he would cry out long before he came at him, or saw him, *Drive away this Visitant, and keep him from coming in here: or else pluck his Chain from about his neck:* for on this (as it is the custom of the French Order of Knights) there hangs the image of St. *Michael*. If holy and divine things were read before him, he shook and trembled more violently. When his Fit was over, he remembred all that was done, and affirmed he did it against his will, and that he was sorry for it. The Devil, forced by Ceremonies and Exorcisms, denied that he was damned for any crime, and said that he was a spirit: being asked who he was, and by what means and power he did these things, he said that he had many habitations into which he could betake himself, and in the time of his rest, he could torment others: that he was cast into this body by a certain person whom he would not name, and that he entered by his feet up to his neck, and that he would go forth again the same way, when as his appointed time was come. He spoke of sundry other things, as others which are possessed use to do.

Devils wax angry, and are terrified by divine things.

Now I speak not these things as new or strange, but that it may appear that Devils sometimes entering into the body, do some whiles torment it by diverse and uncouth ways; other whiles they

they do not enter in, but either agitate the good humours of the body, or draw the ill into the principal parts, or with them obſtruct the veins or other paſſages, or change the ſtructure of the inſtruments, from which cauſes innumerable diſeaſes proceed: of theſe, Devils are the authors, and wretched and forlorn perſons the Miniſters: and the reaſon of theſe things is beyond the ſearch of Nature.

Pliny tells that the Emperour *Nero* in his time found magical arts moſt vain and falſe: but what need we alledge profane Writers, when as thoſe things that are recorded in Scripture of the Pythoniſs, of the Woman ſpeaking in her belly, of King *Nebuchodonozor*, of the Magicians of *Pharaoh*, and other ſuch things not a few, prove that there both is, and hath been Magick. *Pliny* tells of *Demarchus*, that he taſting of the entrails of a ſacrificed child, turned himſelf into a Wolf. We read in *Homer* that *Circe* in the long wandring of *Ulyſſes*, changed his Companions into Beaſts, with an inchanted Cup or Potion: and in *Virgil*, that the growing Corn may be ſpoiled or carried away by inchantments: which things, unleſs they were approved and witneſſed by many mens credits, the wiſdom of Magiſtrates and Lawyers, would not have made ſo many Laws againſt Magicians, neither would there have been a mulct impoſed upon their heads by the Law of the Twelve Tables, who had inchanted other mens Corn. But as in magical Arts the Devil doth not exhibit things themſelves, as thoſe which he cannot make, but onely certain ſhews or appearances of things: ſo in theſe which are any ways accommodated to the uſe of Phyſick, the Cure is neither certain nor ſafe, but deceitful, captious, and dangerous.

It is but a deceitful cure that is performed by the Devil.

I have ſeen the Jaundice over the whole body, cured in one night, by a written ſcroul hanged about the neck: alſo I have ſeen Agues chaſed away by words and ſuch ceremonies, but in a ſhort while after they returned again and became much worſe. Now there are ſome vain things, and verily the fanſies of old Women, which becauſe they have long poſſeſſed the minds of men, weakened with too much ſuperſtition, we term them ſuperſtitious. Theſe are ſuch as we cannot truly ſay of them, wherefore and whence they have the faculties aſcribed to them: for they neither ariſe from the temperament, neither from the other manifeſt qualities, neither from the whole ſubſtance, neither from a divine or magical power, from which two laſt mentioned, all Medicins beyond Nature, and which are conſequently to be uſed to Diſeaſes, whoſe eſſences are ſupernatural, muſt proceed. Such like old Wives Medicins and ſuperſtitious remedies, are written Figures and Characters, Rings, where neither the aſſiſtance of God or Spirits is implored. Let me ask you, Is it not a ſuperſtitious Medicin to heal the Falling-ſickneſs, to carry in writing the name of the three Kings, *Gaſpar*, *Melchior*, and *Balthaſar*, who came to worſhip Chriſt? To help the Tooth-ach, if one whileſt Maſs is ſaying, touch his teeth, ſaying theſe words, *Os non comminuitis ex eo?* To ſtay Vomiting with certain Ceremonies and words, which they abſent pronounce, thinking it ſufficient if that they but onely know the Patients name?

Old Wives ſuperſtitious Medicins againſt divers Diſeaſes.

I ſaw a certain fellow that with murmuring a few words, and touching the part, would ſtanch bloud out of what part ſoever it flowed: there be ſome who to that purpoſe ſay this, *De latere ejus exivit ſanguis & aqua.* How many Prayers or Charms are carried about to cure Agues? ſome taking hold of the Patients hand, ſay, *Æque facilis tibi Febris hæc ſit, atque Mariæ virgini Chriſti partus.* Another waſheth his hands with the Patient before the Fit, ſaying to himſelf that ſolemn Pſalm, *Exaltabo te Deus, meus Rex*, &c. If one tell an Aſs in his Ear that he is ſtung by a Scorpion, they ſay that the danger is immediately over.

As there are many ſuperſtitious words, ſo there are many ſuperſtitious writings alſo. To help ſore Eyes, a Paper wherein the the two Greek Letters Τ and Α are written, muſt be tied in a thred, and hanged about the neck. And for the Tooth-ach this ridiculous ſaying, *Strigiles facileſque dentatæ, dentium dolorem perſanate.* Alſo oft-times there is no ſmall ſuperſtition in things that are outwardly applied. Such is that of *Apollonius* in *Pliny*, to ſcarifie the Gums in the Tooth-ach, with the tooth of one that died a violent death: to make Pills of the ſkull of one hanged, againſt the bitings of a mad Dog: to cure the Falling-ſickneſs by eating the fleſh of a wild Beaſt killed with the ſame iron wherewith a man was killed: that he ſhall be freed from a Quartan Ague who ſhall drink the Wine whereinto the Sword that hath cut off a mans head, ſhall be put; and he, the parings of whoſe nails ſhall be tied in a linnen cloth to the neck of a quick Eel, and the Eel let go into the Water again. The pain of the Milt to be aſſwaged, if a Beaſts Milt be laid upon it, and the Phyſician ſay that he cures or makes a Medicin for the Milt. Any one to be freed from the Cough, who ſhall ſpit in the mouth of a Toad, letting her go away alive. The Halter wherein one hath been hanged put about the Temples, to help the Head-ach. This word *Abracadabra*, written on a Paper, after the manner deſcribed by *Serenus*, and hanged about the neck, to help Agues or Fevers, eſpecially Semi-tertians. What truth can be in that which ſundry affirm, that a leaf of *Lathyris*, which is a kind of Spurge, if it be plucked upwards, will cauſe vomit, but broken downwards will move to Stool? You may alſo find many other ſuperſtitious fictions concerning herbs, ſuch as *Galen* reports that *Andreas* and *Pamphilus* writ, as incantations, transformations, and herbs dedicated to Conjurers and Devils. *Lib. 6. de Simp.*

I had thought never in this place to have mentioned theſe and the like, but that there may be everywhere found ſuch wicked perſons, who leaving the Arts and Means which are appointed by God to preſerve the health of Mans body, fly to the ſuperſtitious and ridiculous remedies of Sorcerers, or rather of Devils, which notwithſtanding the Devil ſometimes makes to perform their wiſhed for effects, that ſo he may ſtill keep them enſnared and addicted to his ſervice. Neither is it to be approved which many ſay, that it is good to be healed by any Art or Means, for that healing is a good work. This ſaying is unworthy of a Chriſtian, and ſavours rather of him that truſts more to the Devil than in God. Thoſe Empericks are not of the Society of Sorcerers and Magicians, who heal ſimple wounds with dry lint, or lint dipt in water: this Cure is neither magical nor miraculous, as many ſuppoſe, but wholly natural, proceeding from the healing Fountains of Nature; Wounds and Fractures which the Surgeon may heal by onely taking away the impedi-

ments, that is pain, defluxions, inflammation, an abſceſs and gangrene, which retard and hinder the cure of ſuch diſeaſes. The following examples will ſufficiently make evident the Devils maliciouſneſs, always wickedly and craftily plotting againſt our ſafety and life.

Lib.epiſt.38.ep. A certain Woman of *Florence* (as *Langius* writes) having a malign ulcer, and being troubled with intolerable pain at the ſtomach, ſo that the Phyſicians could give her no eaſe: behold on a ſudden ſhe vomited up long and crooked nails and braſs needles wrapped up with wax and hairs, and at length a great gobbet of fleſh, ſo big that a Giants jaws could ſcarce ſwallow it.

But that which happened in the year of our redemption 1539. in a certain Town called *Fugenſtal*, in the Biſhioprick of *Eyſtet*, exceeds all credit, unleſs there were Eye-witneſſes of approved integrity yet living. In this Town one *Ulrich Nuſeſſer*, an Husbandman, was tormented with grievous pain in the one ſide of his belly; he ſuddenly got hold of a iron Key with his hand under the skin, which was not hurt, the which the Barber-Surgeon of the place cut out with a Razor; yet for all this the pain ceaſed not, but he grew every day worſe than other: wherefore expecting no other remedy but death, he got a Knife and cut his throat. His dead body was opened, and in his ſtomach were found a round and loggiſh piece of wood, four ſteel knives, part ſharp, and part toothed like a Saw, and two ſharp pieces of iron, each whereof exceedeth the length of a ſpan; there was alſo as it were a ball of hair. All theſe things were put in by the craft and deceit of the Devil. Thus far *Langius*.

CHAP. XVIII.

Of the Cozenages and crafty Tricks of Beggars.

HAving treated of Monſters, it follows that we ſpeak of thoſe things which either of themſelves, by reaſon of their nature full of admiration, have ſome kind of monſtrouſneſs in them, or elſe from ſome other ways, as by the craft and cozenage of men. And becauſe to the laſt mentioned crafts of the Devil, the ſubtle devices of begging Companions are ſomewhat alike, therefore I will handle them in the next place, that the Surgeon being admoniſhed of them, may be more cautious and cunning in diſcerning them when he meets with them.

An hiſtory of a counterfeit arm.

Anno Dom. 1525. when I was at *Anjou*, there ſtood a crafty Beggar begging at the Church door, who tying and hiding his own arm behind his back, ſhewed in ſtead thereof, one cut from the body of one that was hanged, and this he propped up and bound to his breſt, and ſo laid it open to view, as if it had been all enflamed, ſo to move ſuch as paſſed by, unto greater commiſeration of him. The cozenage lay hid, every one giving him money, until at length his counterfeit arm not being ſurely faſtned, fell upon the ground, many ſeeing and obſerving it; he being apprehended and laid in priſon, by the appointment of the Magiſtrate was whipped through the Town, with his falſe arm hanging before him, and ſo baniſhed.

Another of a cancrous breſt.

I had a brother called *John Parey*, a Surgeon, who dwelt in *Vitre* in *Britain*; he once obſerved a young woman begging, who ſhewed her breaſt, as if it had a cancrous ulcer thereon, looking fearfully by reaſon of much ſordid filth, wherewith it ſeemed to defile the cloth that lay under it. But when as he had more diligently beheld the womans face, and the freſh colour thereof, as alſo of the places about the ulcer, and the good habit of the whole body agreeable to that colour (for ſhe was ſomewhat fat, and of a very good habit of body) he was eaſily hereby induced to ſuſpect ſome roguery and deceit. He acquainted the Magiſtrate with this his ſuſpicion, and got leave that he might carry her home to his houſe, ſo to ſearch her more narrowly. Where opening her breaſt, he found under her arm-pit, a Sponge moiſtned with a commixture of beaſts bloud and milk, and carried through an Elder-pipe to the hidden holes of her counterfeit *Cancer*. Therefore he foments her breaſt with warm water, and with the moiſture thereof looſeth the skins of black, green, and yellow Frogs laid upon it, and ſtuck together with Glew made of Bole-armenick, the White of an Egg, and Flour; and theſe being thus fetched off, he found her breaſt perfectly ſound.

The Beggar being caſt for this into priſon, confeſſed that ſhe was taught this trick by a Beggar that lay with her, who himſelf alſo, by putting about his leg an Oxes Milt, and perforating it in ſundry places, that ſo the fore-mentioned liquor might drop out, counterfeited an Ulcer of a monſtrous bigneſs and malignity, covering the edges of the Milt on every ſide with a filthy cloth. This Beggar was diligently enquired after, but could not be found; and ſo ſhe was whipped and baniſhed.

Of one feigning himſelf leprous.

* Cliquets are things made ſomewhat reſembling a ſmall Wool-card, but have two or three little pieces of boards ſo faſtned together with leather, that they will make a great noiſe with them, and theſe are uſed by the French Beggars.

Within leſs than a year after, there came into the ſame City a notable crafty Companion, who preſently taking up the Church-doors, laid open his Wares; to wit, a Kercher with ſome ſmalll pieces of money lying thereon, a wooden Barrel, and *Cliquets, where-with he would ever now and then make a great noiſe: his face was ſpread over with great thick puſtles, being of a blackiſh red colour, and made with Glue like thoſe that have the Leproſie: this his ghaſtly look made him to be pitied by all men, which was the cauſe that every one gave him money. Then my brother came ſomewhat nearer him, and asked him how long he had been troubled with this ſo cruel Diſeaſe; he anſwered with an obſcure and hoarſe voice, that he was born a Leper from his Mothers Womb, and that his Parents both died of this wicked Diſeaſe, ſo that their members fell away by piece-meal. Now he had a woollen ſwathe about his chaps, wherewith (having his left hand under his Cloak) he ſo ſtraitned his chaps, that much black bloud roſe into his face, and made him ſo hoarſe that he could ſcarce ſpeak; yet he could not contain himſelf, but that in ſpeaking he ever now and then ſlackned the ſwathe with his hand, the freelier to draw his breath; which when my brother had obſerved, ſuſpecting ſome cozenage, he obtained leave of the Magiſtrate to ſearch and examine the man, whether he were truly leprous, or no. Firſt therefore he took away his Swathe or Rowler that was about his neck, then waſhed his face with warm water, ſo that the counterfeit glued puſtles were diſſolved, and his face (free from all tainture) ſhewed it ſelf of a good and natu-

ral

ral colour and shape. Then he laid bare his whole body, and diligently viewed each part, and found no sign of a Leprosie, one or other. Which when the Magistrate once heard, he made him to be put in prison, and to be thrice whipped through the Streets of the City, with his Barrel hanging before him, and his Cliquets behind him, adding thereto the punishment of perpetual banishment. It happened that as he was whipped the third Market-day, the People cried out to the Hangman in jest, that he should not fear to lash him soundly, for being leprous he could not feel it; the Executioner incited by this cry of the People, did so belabour him, that the Wretch died of his Whipping within a short while after, having a just reward for his wickedness. For these Impostors, besides that they live like drones, feigning this or that Disease, and so being idle, enjoy the fruits of others labours: they also divers times conspiring together, take away the lives and goods of honest and substantial Citizens and other people: for there are some of them that in an evening, as men that have no habitation, desire lodging for a night, and it being granted them, they, when as the Master of the house and his Family are asleep, open the doors to their Comrades, men as wicked as themselves, and kill and carry away all they can.

A multitude of Beggars hurtful to the City.

Certainly we may justly affirm, that this crafty way of begging is the Mother and School of all dishonesty: for how many acts of bawdry and poisoning every where corrupt the Wells and publick Fountains? How many places have been burnt under the shew of begging? Where can you get more fit Spies? Where more fit Undertakers and Workers of all manner of Villany, than out of the crew of these Beggars?

How to discover such as counterfeit the Jaundice.

Some of them there are, who besmear their faces with soot laid in water, so to seem to have the Jaundice. But you may at the first sight find out the deceit, by the native whiteness of the outer coat of the eye, called *Adnata*, which in such as truly have the Jaundice, useth to be died and overcast with a yellowish colour; also you may be more certain thereof, if you wet a cloth in Water or Spittle, and so rub the face; for the adventitious yellowness will quickly vanish, and the true native colour shew it self.

Some there be, who not content to have mangled, and filthily exulcerated their limbs with caustick herbs, and other cauteries; or to have made their bodies more swollen, or else lean, with medicated drinks; or to have deformed themselves some other way, but from good and honest Citizens, who have charitably relieved them, they have stollen their children, have broken or dislocated their arms and legs, have cut out their tongues, have depressed the chest or whole breast; that with these as their own children, begging up and down the Countrey, they may get the more relief, pitifully complaining that they came by this mischance by Thunder or Lightning, or some other strange accident.

Lastly, They part the Kingdom amongst themselves as into Provinces, and communicate by Letters one to another, what news or new quaint devices there are to conceal or advance their Roguery: to which purpose they have invented a new Language onely known to themselves, so to discourse together, and not to be understood by others. [We here vulgarly term it *Canting*.]

Of one counterfeiting the falling of the Fundament.

Dr. *Flecelle*, a Physician of *Paris*, intreated me to bear him company to his Country-house at *Champigny*, four miles from *Paris*. Where as soon as we arrived, and were walking in the Court, there came presently to us a good lusty well flesht manly woman, begging alms for St. *Fiacre* sake, and taking up her Coat and her Smock, she shewed a great gut hanging down some half a foot, which seemed as if it had hanged out of her fundament, whereout there dropped filth like unto *pus*, which had all stained her Legs and Smock, most beastly and filthy to look upon. *Flecelle* asked how long she had been troubled with this Disease; she answered that it was four years since she first had it. Hence he easily gathered that she played the counterfeit: for it was not likely that such abundance of purulent matter came forth of the body of so well flesht and coloured a Woman; for she would rather have been very lean and in a consumption. Wherefore provoked with just anger, by reason of the wickedness of the deceit, he run upon her and threw her down upon the ground, and trod her under his feet, and hit her divers blows upon the belly, so that he made the gut which hung at her, to come away, and by threatning her with more grievous punishment, made her confess the cozenage, and that it was not her gut, but of an Ox, which being filled with bloud and milk, and tied at both ends, she put the one of them into her fundament, and let the filth flow forth at very little holes.

Of one feigning the falling down of the Womb.

Not very long ago, a Woman equally as shameless, offered her self to the Overseers of the Poor of *Paris*, intreating that she might be entered for one of their Pensioners, for that her Womb was fallen down by a dangerous and difficult birth, wherefore she was unable to work for her living. Then they commanded that she should be tried and examined, according to the custom, by the Surgeons which are therefore appointed: who seeing how the whole business was carried, made report she was a Counterfeit, for she had thrust an Oxes bladder, half blown and besmeared with beastly bloud by the neck, whereto she had fastned a little Sponge, into the neck of her Womb, for the Sponge being filled and swollen up by the accustomed moisture of the Womb, so held up the Oxes bladder that hanged thereat, that she might safely go without any fear of the falling of it out, neither could it be pulled forth but with good force. For this her device she was put into Prison, and being first whipped, was after banished. This cozenage is not much unlike theirs, who by fitly applying a Sheeps paunch to their groin, counterfeit themselves to be burstен.

Of a Beggar that feigned her self to have a Snake in her belly.

Anno Dom. 1561. there came to *Paris* a lusty, stout, and very fat *Norman* Woman, being about some thirty years old, who begging from door to door, did cast to meet with rich Women, and very familiarly and pitifully would relate unto them her misfortune, saying, she had a Snake in her Belly, which crept in at her mouth as she slept in a Hemp-land: she would let one feel her stir, by putting their hand to her Belly, adding also that she was troubled day and night with its unceasant gnawing of her guts. The novelty of this sad chance, moved all to pity and admiration; wherefore as much as they could, they assisted her with means and counsel. Amongst the rest, there was

a Wo-

a Woman of great devotion and charity, who ſending for Doctor *Hollerius Chevall* and me, asked us if this Snake could by any means be gotten forth. *Hollerius* gave her a ſtrong purgation, hoping that by ſtirring up the expulſive faculty, the Serpent might be caſt forth together with the noxious humours. But this hope had no ſuch ſucceſs. Wherefore when as we met again, we thought it fit to put a *Speculum matricis* into the neck of her womb, ſo to ſee if we could diſcern either head or tail: but I making large dilatation of her Womb, could ſee no ſuch thing; onely we obſerved a certain voluntary motion, whereof ſhe her ſelf was the author, by contracting and dilating the muſcles of the lower belly. Which when as we had obſerved, perceiving the deceit and impoſture, we thought good ſo to terrifie her, and make her confeſs the deceit, to tell her that ſhe muſt take another, but that a more ſtrong purgation; that what we could not do by the former, as more gentle, we might attain to by the latter, as far ſtronger. She diſſembling all fear, and conſcious of her craft and diſſimulation, after we were gone in the evening, packing up her ſtuff, and a great deal more then her own, ſhe ſecretly ſtole away, not bidding her Hoſteſs farewel: and thus at length the fraud was apparent, to the loſs of the honeſt Gentlewoman. I ſaw this baggage ſix days after, ſitting luſtily upon a Pack-horſe, at the Gate *Montmartre*, and laughing heartily with ſuch as brought Sea-fiſh to Town: and ſhe was returning (as it was moſt likely) into her Countrey, ſeeing her couzenage was diſcovered here.

The craft of ſuch as feign themſelves to have the Falling-ſickneſs. Of ſuch as feign themſelves leprous.

Such as feign themſelves dumb, draw back and double their tongues in their mouths. Such as falling down counterfeit the Falling-ſickneſs, bind ſtraitly both their wriſts with plates of iron, tumble and rowl themſelves in the mire, ſprinkle and defile their heads and faces with Beaſts bloud, and ſhake their limbs and whole body. Laſtly, by putting Soap into their mouths, they foam at the mouth like thoſe that have the Falling-ſickneſs. Otherſome with Flour make a kind of Glue, wherewith they beſmear their whole bodies, as if they had that Leproſie or Scab that is vulgarly termed *Malum ſancti Manis*. Neither muſt we think this Art of Counterfeiting and cheating Begging to be new, and of late invention; for long ago it flouriſhed in *Aſia*, even in the time of *Hippocrates*, as may appear in his Book *De Aere, Locis, & Aquis*. But by how much this diſeaſe hath taken more deep root, and grown more inveterate by proceſs of time, by ſo much it muſt more diligently and carefully be looked to and prevented, by cruelly puniſhing ſuch Counterfeits: for that by this feigned begging, as the Nouriſher of Sloth, and Shop of all diſhoneſty, that which is taken from the good is beſtowed upon the ill, and one wicked and counterfeit Beggar hurts all other wretched people.

CHAP. XIX.

Of ſtrange or monſtrous accidents in Diſeaſes.

Monſters happen alſo in diſeaſes.

WHat monſtrouſneſs ſoever was in the laſt mentioned parties, it was made up by the craft of Beggars for filthy gain. But if there be any monſtrouſneſs in the following narrations, it is of Nature, but working as it were miraculouſly, by ſome ſecret and occult means; for thus there are oftentimes Monſters in Diſeaſes. Before the Town of St. *John de Angeley*, a Souldier called *Francis*, of the Company of Captain *Muret*, was wounded with a Harquebuz-ſhot on the belly, between his navel and ſides; the bullet was not taken out, becauſe the Surgeons who ſearched him diligently, could not find it: wherefore he was troubled with grievous and tormenting pains, until the nineth day after he received the wound, the bullet came forth at his fundament: wherefore within three weeks after he was perfectly whole. He was healed by *Simon Crinay*, the Surgeon of the *French* Companies.

A bullet ſhot into the belly came forth at the Fundament.

A bullet ſticking in the throat and the Patient recovering.

James Pope, Lord of St. *Albans* in *Dauphine*, was wounded at the Skirmiſh at *Chaſenay*, having three Harquebuz bullets entering into his body, one whereof pierced under his throat, where it buncheth out as with a knot, near to the pipe of his lungs, even to the beginning of the *Vertebræ* of the neck, in which place the Leaden bullet ſtuck, and as yet doth remain. Hereupon he was afflicted with many and fearful ſymptoms, as a Fever, and a great ſwelling of his whole neck, ſo that for ten whole days he could ſwallow nothing but broths and liquid things. Yet he recovered, and remaineth well at this preſent, by the cure of *James Dalam* the Surgeon.

Lib. 3. anatom. cap. 9.

A crooked iron ſhot into the back, came forth at the Fundament.

Alexander Benedictus makes mention of a certain Country man, who, ſhot into the back with a dart, drawing out the ſhaft, the head was left behind, being in length about the bredth of two fingers, but hooked and ſharp on the ſides. When as the Surgeon had carefully and diligently ſought for it, and could by no means find it, he healed up the wound, but two moneths after this crooked head came forth at his fundament.

A ſwallowed needle voided by urin.

The ſame Author telleth that at *Venice* a Virgin ſwallowed a needle, which ſome two years after ſhe voided by urin, covered over with a ſtony matter, gathered about viſcous humours.

A needle running in at the buttock, came forth at the groin.

Catherine Perlan, the wife of *William Guerrier*, a Draper of *Paris*, dwelling in the *Jewry*, as ſhe rode on Horſe-back into the Country, a needle out of her Pin-cuſhion, got under her by accident, ran ſo deep into her right buttock, that it could not by any Art or force be plucked forth. Four moneths after ſhe ſent for me to come to her, and ſhe told me that as often as ſhe had to do with her husband, ſhe ſuffered extreme pricking pain in her right groin; putting my hand thereto, as I felt it, my fingers met with ſomething ſharp and hard, wherefore I uſed the matter ſo, that I drew forth the needle all ruſty: this may be accounted as a miracle, that Steel, naturally heavy, ſhould riſe upwards from the buttock to the groin, and pierce the muſcles of the thigh, without cauſing an abſceſs.

A needle in the midſt of a Stone taken forth of the bladder.

Anno Dom. 1566. the two ſons of *Laurence Collo* (men excellent in cutting for the Stone) took forth a Stone of the bigneſs of a Wall-nut, in the midſt whereof was a needle, juſt like thoſe that Shoe-makers uſe: the Patients name was *Peter Cocquin*, dwelling in the Street *Galand*, at the place called

called *Maubert* at *Paris*, and I think he is yet living. This Stone was ſhewed to King *Charles* the Ninth, for the monſtrouſneſs of the thing, I being then preſent, which being given me by the Surgeon, I preſerve amongſt my other rarities.

The Figure of a Stone taken forth of the Bladder of a Confectioner.



Anno Dom. 1570. the Dutcheſs of *Ferrara* at *Paris*, ſent for *John Collo* to take a Stone out of a Confectioner. This Stone, though it weighed nine ounces, and was as thick as ones fiſt, yet was it happily taken out, the Patient recovering, *Francis Rouſſet* and *Joſeph Javelle*, the Dutcheſs Phyſicians, being preſent. Yet not long after this Confectioner died by the ſtoppage of his water, by reaſon of two other little ſtones, which about to deſcend from the Kidnies to the Bladder, ſtaid in the midway of the Ureters. The figure of the extracted ſtone was this.

Anno Dom. 1569. *Laurenee Collo* the younger, took three ſtones out of the Bladder of one dwelling at *Marly*, called commonly *Tire-vit*, becauſe being troubled with the Stone from the tenth year of his age, he continually ſcratched his Yard, each of the Stones were as big as an Hens Egg; of colour white, they altogether weighed twelve ounces. When they were preſented to King *Charles*, then lying at St. *Maure des Fauſſez*, he made one of them to be broken with a Hammer, and in the midſt thereof there was found another of a Cheſnut colour, but otherwiſe much like a Peach-ſtone. Theſe three Stones, beſtowed on me by the Brethren, I have here repreſented to the life.

The Effigies of the three fore-mentioned Stones, whereof one is broken.



I have in the diſſecting of dead Bodies, obſerved divers Stones of various forms and figures, as of Pigs, Whelps, and the like. *Dalechampius* telleth that he ſaw a man, which by an Abſceſs of his Loins, which turned to a Fiſtula, voided many Stones out of his Kidnies, and yet notwithſtanding could endure to ride on Horſe-back, or in a Coach. *John Magnus*, the Kings moſt learned and skilful Phyſician, having in cure a Woman, troubled with cruel torment and pains of the Belly and Fundament, ſent for me, that by putting a *Speculum* into the Fundament, he might ſee if he could perceive any diſcernable cauſe of ſo great and pertinacious pain: and when as he could ſee nothing which might further him in the finding out of the cauſe of her pain (following Reaſon as a Guide) by giving her often Clyſters and Purgations, he brought it ſo to paſs, that ſhe at length voided a Stone at her Fundament of the bigneſs of a Tennis-ball: which once avoided all her pain ceaſed.

A Stone by the force of Purging Medicins voided by the Fundament.

Hippocrates tells us that the Servant of *Dyſeris* in *Lariſſa*, when ſhe was young, in uſing Venery was much pained, and yet ſometimes without pain, yet ſhe never conceived. But when ſhe was ſixty years old, ſhe was pained in the afternoon as if ſhe had been in labour. When as ſhe one day before noon had eaten many Leeks, afterward ſhe was taken with a moſt violent pain far exceeding all her former, and ſhe felt a certain rough thing riſing up in the orifice of her womb: but ſhe falling into

5 *Epid.*

A Stone coming out of the neck of the Womb.

into a ſwound, another woman putting in her hand, got out a ſharp ſtone of the bigneſs of a whirl, and then ſhe forthwith became well, and remained ſo.

*Lib.*1. *cap. de palp. cond.* In a certain Woman, who, as *Hollerius* tells, for the ſpace of four Moneths was troubled with an incredible pain in making water, two ſtones were found in her heart, with many abſceſſes, her Kidnies and Bladder being whole.

Anno Dom. 1558. I opened in *John Bourlier* a Tailor, dwelling in the ſtreet of St. *Honore*, a watry abſceſs in his knee, wherein I found a ſtone, white, hard, and ſmooth, of the thickneſs of an Almond; which being taken out, he recovered. Certainly there is no part of the body wherein ſtones may not breed and grow.

No part of the body wherein ſtones may not be found

Anthony Benevenius a Florentine Phyſician writes, that a certain Woman ſwallowed a braſs Needle without any pain, and continued a year after without feeling or complaining of it: but at the end thereof ſhe was moleſted with great pains in her belly; for helping of which ſhe asked the advice of all the Phyſicians ſhe could, making in the interim no mention of the ſwallowed Needle. Wherefore ſhe had no benefit by all the Medicins ſhe took; and ſhe continued in pain for the ſpace of two years, until at length the Needle came forth at a little hole by her Navel, and ſhe recovered her health.

A Needle ſwallowed, came forth at the Navel ſome two years after.

A Scholar named *Chambelant*, a Native of *Bourges*, a Student in *Paris*, in the Colledge of *Preſſe*, ſwallowed a ſtalk of Graſs, which came afterwards whole out between two of his ribs, with the great danger of the Scholars life. For it could not come there unleſs by paſſing or breaking through the lungs, the encompaſſing membrane, and the intercoſtal muſcles; yet he recovered, *Fernelius* and *Haquet* having him in cure.

A ſprig of Graſs ſwallowed came forth whole again between the ribs.

Carolle Chirurgeon to Monſieur the Marſhal of *Anville*, told me that *Francis Guillinet* the Chirurgeon of *Sommiers*, a ſmall Village ſome eight miles from *Mompelier*, had in cure, and healed a certain Shepherd, who was forced by Thieves to ſwallow a Knife of the length of half a foot, with a Horn handle of the thickneſs of ones thumb: he kept it the ſpace of half a year, yet with great pain, and he fell much away, but yet was not in a Conſumption, until at length an abſceſs riſing in his groin, with great ſtore of very ſtinking quitture, the Knife was there taken forth in the preſence of the Juſtices, and left with *Joubert* the Phyſician of *Mompelier*.

A Knife ſwallowed, came forth at an abſceſs in the groin.

Monſieur the Duke of *Rohan* had a Fool called *Guido*, who ſwallowed the point of a Sword of the length of three fingers, and he voided it at his Fundament on the twelfth day following, yet with much ado: there are yet living Gentlemen of *Britany*, who were eye-witneſſes thereof.

The point of a Sword ſwallowed, came forth at the fundament.

There have been ſundry Women with child, who have ſo caſt forth piece-meal children that have died in their Wombs, as that the bones have broke themſelves a paſſage forth at the Navel, but the fleſh, diſſolved as it were into quitture, flowed out by the neck of the womb and the fundament, the Mothers remaining alive, as *Dalechampius* obſerves out of *Albucraſis*.

Wonderful excretions of Infants out of the Womb

It is not very ſtrange that there have been Women, who troubled with a fit of the Mother, have lain three whole days without motion, without breathing, or pulſe that were any way apparent, and ſo have been carried out for dead.

Women troubled with the Mother laid out for dead.

A certain young man, as *Fernelius* tells, by ſomewhat too vehement Exerciſe, was taken with ſuch a Cough, that it left him not for a moment of time, until he therewith had caſt forth a whole impoſtume of the bigneſs of a Pigeons Egg, wherein, being opened, there was found quitture exquiſitely white and equal. He ſpit bloud two days after, had a great Fever, and was much diſtempered, yet notwithſtanding he recovered his health.

An Impoſtume ſpit out, of the bigneſs of a Pigeons Egg.

Anno Dom. 1578. *Stephana Chartier* dwelling at St. *Maure des Fauſſez*, a Widow of forty years old, being ſick of a Tertian Fever, in the beginning of her Fit vomited up a great quantity of choler, and together therewith three hairy Worms, in figure, colour, and magnitude like the Worms called Bear-worms, yet ſomewhat blacker; they lived eight whole days after without any food: the Chirurgeon of this Town brought them to Dr. *Milot*, who ſhewed them to *Feure*, *Le Groſs*, *Mareſcot*, and *Courtin*, Phyſicians, and to me alſo.

Worms caſt up in the Fit of an Ague.

This following Hiſtory, taken out of the Chronicles of *Menſtrele*, exceeds all admiration. A certain Frank-Archer of *Meudon*, four miles from *Paris*, was for Robbery condemned to be hanged: in the mean time it was told the King by the Phyſicians, that many in *Paris* at that time were troubled with the Stone, and amongſt the reſt the Lord of *Boſcage*, and that it would be for the good of many, if they might view and diſcern with their eyes the parts themſelves wherein ſo cruel a diſeaſe did breed, and that it might be done much better in a living than in a dead body; and that they might make trial upon the body of the Frank-Archer, who had formerly been troubled with theſe pains. The King granted their requeſt; wherefore opening his body, they viewed the breathing parts, and ſatisfied themſelves as much as they deſired, and having diligently and exactly reſtored each part to its proper place, the body, by the Kings command was ſewed up again, and dreſſed and cured with great care. It came ſo to paſs, that this Frank-Archer recovered in a few days, and getting his pardon, got good ſtore of money beſides.

This narration exceeds not only all admiration, but alſo belief.

Alexander Benedictus tells, that he ſaw a Woman called *Victoria*, who having loſt all her teeth, and being bald, yet had others come up in their places, when as ſhe was fourſcore years old.

Stephen Teſſier a Chirurgeon of *Orleance*, told me that not long ago he cured one *Charles Verignol* a Serjeant of *Orleance*, of a wound received in his ham, whereby the two tendons bending the ham, were quite cut aſunder. He took this order in the cure; he cauſed the Patient to bend his leg, then he ſewed together the ends of the cut tendons, then placed the member in that ſite, and handled with that Art, that at length he healed the wound, the Patient not halting at all. Truly this is a memorable thing, and carefully and heedfully to be imitated by the young Chirurgeon.

*Pract. lib.*64. *cap.*1.

How many have I ſeen, who wounded and thruſt through the body with Swords, Arrows, Pikes, Bullets, have had portion of the brain cut off by a wound of the head, an arm or leg taken away by a Cannon-bullet, yet have recovered; and how many on the contrary, have died of light and ſmall wounds, not worth the ſpeaking of?

A

A certain man was ſhot near to his groin with an Arrow, whom we have ſeen, ſaith *Hippocrates*, and he recovered beyond all mens expectation. The arrows head was not taken forth, for it was very deep in, neither did the wound bleed very much, neither did he halt: but we found the head and took it forth ſix years after he was hurt. Now *Hippocrates* gives no reaſon of its ſo long ſtay, but that he ſaith it might be ſuſpected it lay hid between the Nerves, and that no Vein or Artery was cut thereby. *5. Epidem.*

CHAP. XX.

Of the wonderful original, or breeding of ſome Creatures.

WE have read in *Boiſtey*, that a certain Workman of *Avignion*, when as he lived in that City, opened a leaden Coffin, wherein a dead body lay, that was ſo cloſely ſoldered that the air could not get in; and as he opened it, he was bitten by a Serpent that lay therein, with ſo venomous and deadly a bite, that it had near to have coſt him his life. Yet the original cauſe of this Creature is not ſo prodigious as he ſuppoſeth, for it is an uſual thing for a Serpent to breed of any putrified carkaſs, but chiefly of mans. *Boiſt. in Hiſtor. Prodig.* It is a common thing for a Serpent to breed of the dead corps of a man.

Baptiſta Leo writes, that in the time of Pope *Martin* the fifth, there was a live Serpent found encloſed in a vaſt but ſolid Marble, no chink appearing in ſuch denſe ſolidity, whereby this living Creature might breath. A live Serpent in a ſolid Marble.

Whileſt in my Vineyard, that is at *Meudon*, I cauſed certain huge ſtones to be broken to pieces, a Toad was found in the midſt of one of them. When as I much admired thereat, becauſe there was no ſpace wherein this Creature ſhould be generated, increaſe, or live, the Stone-cutter wiſhed me not to marvel thereat, for it was a common thing, and that he ſaw it almoſt every day. Certainly it may come to paſs, that from the more moiſt portion of ſtones, contained in places moiſt and under ground, and the celeſtial heat mixing and diffuſing it ſelf over the whole maſs of the World, the matter may be animated for the generation of theſe creatures. The cauſe of ſuch wonderful generations.

CHAP. XXI.

Of the wondrous nature of ſome marine things, and other living creatures.

THe laſt mentioned creatures were wonderful in their original, or rather in their growth: but theſe which follow, though they be not wonderful of themſelves, as thoſe that conſiſt of their own proper nature, and that working well and after an ordinary manner; yet they are wondrous to us, or rather monſtrous, for that they are not very familiar to us. For the rarity and vaſtneſs of bodies, is in ſome ſort monſtrous. Of this ſort there are many, eſpecially in the Sea, whoſe ſecret corners and receptacles are not pervious to men: as *Tritons*, which from the middle upwards are reported to have the ſhape of men: and the *Sirens*, *Nereides*, or Meremaids, who (according to *Pliny*) have the faces of women, and ſcaly bodies; yea, whereas they have the ſhape of man; neither yet can the fore-mentioned confuſion and conjunction of ſeeds take any place here, for as we lately ſaid, they conſiſt of their own proper nature. *Lib. 9.*

When *Mena* was Preſident of *Egypt*, and walked on the banks of *Nilus*, he ſaw a Sea-monſter in the ſhape of a man coming forth of the Waters; his ſhape was juſt like to a man even to the middle, with his countenance compoſed to gravity, his hair yellow, yet intermixed with ſome grey, his ſtomach bony, his arms orderly made and jointed, his other parts ended in a Fiſh. Three days after in the morning, there was ſeen another Sea-monſter, but with ſhape or contenance of a woman, as appeared by her face, her long hair, and ſwollen breaſts: both theſe Monſters continued ſo long above water, that any one might view them very well.

The Effigies of the Triton *and* Siren *of* Nilus.

In our times (ſaith *Rondeletius*) in *Norway* was a monſter taken in a tempeſtuous Sea, the which as many as ſaw it, preſently termed a Monk, by reaſon of the ſhape which you may here ſee ſet forth.

The

The Figure of a Fiſh reſembling a Monk.

The Figure of a Fiſh in the habit or ſhape of a Biſhop.

Anno Dom. 1531. there was ſeen a Sea-monſter in the habit of a Biſhop, covered over with ſcales: *Rondoletius* and *Geſner* have deſcribed it.

Geſner profeſſeth that he received from *Jerome Cardane* this Monſter, having the head of a Bear, the feet and hands of an Ape.

The Effigies of a Sea-monſter headed like a Bear.

The Effigies of a Lion-like ſcaly Sea-monſter.

Not long before the death of Pope *Paul* the Third, in the midſt of the Tyrrhene Sea, a Monſter was taken, and preſented to the Succeſſor of this *Paul:* it was in ſhape and bigneſs like to a Lion, but all ſcaly; and the voice was like a mans voice. It was brought to *Rome* to the great admiration of all men, but it lived not long there being deſtitute of its own natural place and nouriſhment, as it is reported by *Philip Foreſt.*

Lib.5. Chron.

An. Dom. 1523. the third day of *November*, there was ſeen at *Rome* this Sea-monſter, of the bigneſs of a child of five years old, like to a man even to the Navel, except the Ears; in the other parts it reſembled a Fiſh.

The

The Effigies of a Sea-monſter with a mans Face.

Geſner makes mention of this Sea-Monſter, and ſaith that he had the Figure thereof from a Painter, who took it from the very Fiſh, which he ſaw at *Antwerp*. The head looks very ghaſtly, having two horns, prick-ears, and arms not much unlike a man, but in the other parts it was like a Fiſh. It was taken in the *Illyrian* Sea, as it came aſhore out of the water to catch a little child: for being hurt by ſtones caſt by Fiſhermen that ſaw it, it returned a while after to the ſhore from whence it fled, and there died.

The Effigies of a Sea-Devil.

Geſner tells us that a Sea-Monſter, with the head, mane, and breaſt of a Horſe, and the reſt of his body like a Fiſh, was ſeen and taken in the Ocean Sea, brought to *Rome*, and preſented to the Pope.

Olaus Magnus tells that a Sea-Monſter taken at *Bergen*, with the head and ſhape of a Calf, was given him by a certain Engliſh Gentleman. The like of which was preſented lately to King *Charles* the Nineth, and was long kept living in the Waters at *Fountain-bleau*, and it went oft-times aſhore. This is much different from the common Sea-Calf or Seal.

*The Effigies of a monſtrous * Sea-Calf.*

* This here figured is the Sea-Morſe, taken commonly by our men in their *Greenland* Voyages: and I judge the Sea-boar and Elephant to be the ſame, but that the Painter hath ſhewed his skill too much in the one: and the other is an old Morſe, as this here figured is a young one.

This great Monſter was ſeen in the Ocean Sea, with the head of a Boar, but longer tuſks, ſharp and cutting, with ſcales ſet in a wonderful order, as you may ſee by the following Figure.

The Effigies of a Sea-bore.



Olaus Magnus writes that this Monſter was taken at *Thyle*, an Iſland of the North, *Anno Dom.* 1538. it was of a bigneſs almoſt incredible, as that which was ſeventy two foot long, and fourteen high, and ſeven foot between the eyes: now the liver was ſo large that therewith they filled five Hogſheads; the head reſembled a Swine, having as it were a half Moon on the back, and three eyes in the midſt of his ſides; his whole body was ſcaly.

The Effigies of a monſtrous Sea-Swine.



The *Sea-Elephant*, as *Hector Boetius* writes in his deſcription of *Scotland*, it is a Creature that lives both in the Water and aſhore, having two teeth like to Elephants, with which as oft as he deſires to ſleep, he hangs himſelf upon a Rock, and then he ſleeps ſo ſoundly, that Mariners ſeeing him at Sea, have time to come aſhore and bind him, by caſting ſtrong ropes about him. But when as he is not awakened by this means, they throw ſtones at him, and make a great noiſe; with which awakened he endeavours to leap back into the Sea with his accuſtomed violence, but finding himſelf faſt, he grows ſo gentle, that they may deal with him as they pleaſe. Wherefore they then kill him, take out his fat and divide or cut his skin into thongs, which becauſe they are ſtrong and do not rot, are much eſteemed of.

The Effigies of a Sea-Elephant.

The Brabians of Mount *Mazoven*, which runs alongſt the Red Sea, chiefly feed on a Fiſh called *Orobone*, which is very terrible and much feared by other Fiſh, being nine or ten foot long, and of the breadth agreeable thereto, and it is covered with ſcales like a Crocodile.

A Crocodile is a vaſt Creature, coming ſometimes to be fifteen foot long, and ſeeing it is a Creature that doth not bring forth young, but eggs, it uſeth at the moſt to lay ſome ſixty eggs, no bigger than Gooſe eggs, riſing to ſuch bigneſs from ſo ſmall beginnings (for the hatched young one is proportionable to the egg) ſhe is very long lived.

It

It hath ſo ſmall and uſeleſs a tongue, that it may ſeem to have none at all. Wherefore ſeeing it lives both on Land and Water; as it lives on Land it is to be taken for a tongue, but as it lives part of the life in the Water, it hath no uſe of a tongue, and therefore it is not to be reputed one. For Fiſhes either wholly want tongues, or elſe have them ſo impedite and bound, that they ſerve for little uſe. The Crocodile onely of all other things moves the upper jaw, the lower remaining unmovable: for her feet, they are neither good to take nor hold any thing; ſhe hath eyes not unlike thoſe of Swine, long teeth ſtanding forth of the mouth, moſt ſharp claws, a ſcaly skin, ſo hard that no weapon can pierce it. Of the Land Crocodile (reſembling this both Land and Water one) is made the Medicin *Crocodilea*, moſt ſingular for ſore-eyes, being anointed with the juice of Leeks, it is good againſt ſuffuſions or dimneſs of the ſight; it takes away freckles, puſiles, and ſpots; the Gall anointed on the eyes helps Cataracts, but the bloud clears the ſight.

The Crocodile onely moves the upper jaw.

Expende diligenter Plinii locum, lib. 28. c. 8.

Thevet ſaith they live in the Fountains of the River *Nilus*, or rather in a lake flowing from the ſame Fountains, and that he ſaw ſome that were ſix paces long, and a yard croſs the back, ſo that their very looks were formidable. They catch them thus: When as the Water of *Nilus* falls, the Egyptians let down a line, having thereto faſtned an iron hook of ſome three pound weight, made very large and ſtrong; upon this hook they put a piece of the fleſh of a Camel or ſome other Beaſt; which when as he ſees, he preſently falls upon it, and devours it hook and all, wherewith when he finds himſelf to be cruelly pulled and pinched, it would delight you to ſee how he frets and leaps aloft; then they draw him thus hooked, by little and little to the ſhore, and faſten the rope ſurely to the next tree, leſt he ſhould fall upon them that are about him; then with Prongs and ſuch things they ſo belabour his belly, whereas his skin is ſoft and thin, that at length they kill him, and uncaſing him, they make ready his fleſh and eat it for delicious food. *John Lereus* in his Hiſtory of *Braſil*, writes that the Salvages of that Countrey willingly feed upon Crocodiles, and that he ſaw ſome who brought into their houſes young ones, wherewith their Children gathering about it, would play without receiving any harm thereby.

Coſmograph. tom. 1. l. 2. c. 8.

How they take Crocodiles.

Cap. 10.

True (ſaith *Pliny*) is that common opinion, Whatſoever is brought forth in any part of Nature, that alſo is in the Sea, and many other things over and above, that are in no other place. You may perceive that there are not onely the reſemblances of living Creatures, but alſo of other things; if you look upon the Sword, Saw, Cucumer, like in ſmell and colour to that of the Earth, that you may leſs wonder at the Sea-feather and Grape, whoſe Figures I have here given you out of *Rondoletius*.

Lib 9. cap. 2.

The Sea-feather is like thoſe feathers of Birds which are worn in hats for ornament, after they are trimmed and dreſt for that purpoſe. The Fiſhermen call them Sea-pricks, for that one end of them reſembleth the end of a mans yard when the prepuce is drawn off it. As long as it is alive it ſwells and becomes ſometimes bigger and ſometimes leſſer; but dead, it becomes very flaccid and lank: it ſhines bright on the night like a Star.

You may by this gather, that this which we here expreſs, is the Grape whereof *Pliny* makes mention, becauſe in the ſurface and upper part thereof it much reſembles a fair bunch of Grapes; it is ſomewhat longiſh like a miſhapen Club, and hangs upon a long ſtalk; the inner parts are nothing but confuſion, ſometimes diſtinguiſhed with little glandules, like that we have here figured alone by it ſelf.

The Figure of the Sea-feather and Grape.

In the Sea near the Iſland *Hiſpaniola* in the Weſt-Indies, there may be ſeen many monſtrous Fiſhes, amongſt which *Thevet* in his Coſmography thought this moſt rare and obſervable, which in the vulgar Language of the Natives is termed *Aloes*. For it is juſt like a Gooſe, with a long and ſtrait neck, with the head ending ſharp, or in a Cone, not much unlike a Sugar-pear, it is no bigger than a Gooſe, it wanteth ſcales, it hath four fins under the belly for ſwimming; when it is above water you would ſay that it were a Gooſe.

The Sarmatian, or Eaſtern German Ocean contains Fiſhes unknown to hot Countries, and very monſtrous. Such is that which reſembling a Snail, equals a Barbel in magnitude of body, and a Stag in the largeneſs and branches of her horns: the ends of her horns are rounded as it were into little Balls, ſhining like unto Pearls, the neck is thick, the eyes ſhining like unto little candles, with a roundiſh noſe ſet with hairs like to a Cats, the mouth wide, whereunder hangs a piece of fleſh very ugly to behold. It goes on four legs, with ſo many broad and crooked feet, the which with a long tail, and variegated like a Tiger, ſerves her for Fins to ſwim withal. This Creature is ſo timerous, that though it be an *Amphibium*, that is, which lives both in the Water and aſhore, yet uſually it keeps it ſelf in the Sea, neither doth it come aſhore to feed, unleſs in a very clear ſeaſon. The fleſh thereof is very good and grateful meat, and the bloud medicinable for ſuch as

The bloud of great Tortoiſes good for the Leproſie. *Tom. lib.* 20.

have their livers ill affected, or their lungs ulcerated, as the bloud of great Tortoiſes is good for the Leproſie. *Thevet* in his Coſmography affirmeth that he ſaw this in *Denmark*.

In a deep Lake of Freſh water, upon which ſtands the great City or Town of *Themiſtitian*, in the Kingdom of *Mexico*, which is built upon Piles, like as *Venice* is, there is found a Fiſh of the bigneſs of a Calf, called by the Southern Salvages *Andura*, but by thoſe of the place, and the Spaniards the Conquerors of that place, *Hoga*. It is headed and eared almoſt like a Swine; from the chaps hang five long bearded *appendices*, of the length of ſome half a foot, like the beard of a Barbel. It hath fleſh very grateful and good to eat. It bringeth forth live young like as the Whale. As it ſwims in Waters it ſeems green, yellow, red, and of many colours, like a Chameleon: it is moſt frequently converſant about the Shore-ſides of the Lake, and there it feeds upon the leaves of the Tree called called *Hoga*, whence alſo the Fiſh hath its name. It is fearfully toothed, and a fierce Fiſh, killing and devouring ſuch as it meeteth withal, though they be bigger than her ſelf: which is the reaſon why the Fiſhermen chiefly deſire to kill her, as *Thevet* affirmeth in his Coſmography.

The monſtrous Fiſh Hoga.



Andrew Thevet in his Coſmography writes, that as he ſailed to *America*, he ſaw infinite ſtore of flying Fiſhes, called by the Salvages *Bulampech*, who riſing out of the Water, flie ſome fifty paces, eſcaping by that means from other greater fiſh that think to devour them.

This kind of flyiug Fiſh exceeds not the bigneſs of a Mackrel, is round-headed, with a bleuiſh back, two wings which equal the length of almoſt all their body. They oft-times flie in ſuch a multitude, that they fall foul upon the ſails of Ships, whileſt they hinder one anothers flight, and by this means they fall upon the Decks, and become a prey to the Sailers: which ſame thing we have read confirmed by *John Lereus* in his Hiſtory of *Breſil*.

In the *Venetian* Gulf, between *Venice* and *Ravenna*, two miles above *Quioza*, *Anno Dom.* 1550. there was taken a flying Fiſh, very horrible and monſtrous, being four foot long, it had a very great head, with two eyes ſtanding in a line, and not one againſt another, with two ears, and a double mouth, a ſnout very fleſhy and green, two wings, five holes in her throat, like thoſe of a Lamprey, a tail an ell long, at the ſetting on whereof there were two little wings. This Monſter was brought alive to *Quioza*, and preſented to the chief of the City, as a thing whereof the like had not been formerly ſeen.

The Figure of a monſtrous flying Fiſh.



There

There are ſo many and different ſorts of ſhells to be found in the Sea, that it may be truly ſaid, that Nature, the hand-maid of the Almighty, diſports it ſelf in the framing of them. In ſo great diverſity I have chiefly made choice of three to treat of here, as thoſe that are worthy of the greateſt admiration. In theſe lie hid certain little Fiſhes, as Snails in their ſhells, which *Ariſtotle* calls *Cancelli*, and he affirmeth them to be the common companions of the *cruſted and ſhell-fiſhes, as thoſe which in their *ſpecies* or kind are like to Lobſters, and uſe to be bred without ſhells; but as they creep into ſhells, and there inhabit, they are like to ſhell-fiſhes. It is one of theſe that is termed the *Hermit*. He hath two ſomewhat long and ſlender horns, under which are his eyes, always ſtanding out of his head, as thoſe which he cannot pluck or draw in, as Crabs can. His fore-feet have claws upon them, wherewith he defends himſelf, and carries meat to his mouth, having two other on each ſide, and a third being a leſſer, the which he uſeth in going. The female lays eggs, which hang forth at her back part as if they were put upon a thred, being joined together by certain little membranes. Laſtly, in the opinion of *Ælian*, the *Cancellus*, or ſmall Cray-fiſh is born naked and without a ſhell, but within a while after, ſhe of many which ſhe finds empty, makes choice of a fit one, and when as grown bigger, ſhe cannot be contained or dwell any longer therein, or elſe being ſtimulated with a natural deſire of copulation, ſhe removes into a more capacious and convenient one. Theſe little Cray-fiſhes oft-times fight together for their habitation, and the ſtronger carries away the empty ſhell, or elſe makes the weaker to quit poſſeſſion. Now the ſhell is either of a *Nerita* or *Turbo*, and oft-times of a ſmall purple; and entering into poſſeſſion, ſhe carries it about, there feeds and grows, and then ſeeks a more capacious one, as *Ariſtotle* ſaith in the formerly-cited place.

4. *De hiſt. anim. cap.* 4.

*By cruſted is meant Crabs, Lobſters, Shrimps, and ſuch like.

The deſcription of the Hermit Cray-fiſh.

Lib. 7. *cap.* 31.

They change their habitation for two cauſes.

The Effigies of the empty Shells whereinto the Cancelli *uſe to creep to dwell.*

Some think that this *Bernard* the Hermit is that kind of *Cancellus* which is by *Pliny* termed *Pinnoter*; but in truth the *Pinnoter* is not a kind of *Cancellus*, or Cray-fiſh, but of a little Crab. Now in *Ariſtotle* there is much difference between *Cancellus* and *Cancer parvus*, though *Pliny* may ſeem to confound them; for he is bred naked, having his cruſt onely, but without a ſhell: wherefore ſeeing that by Nature he wants it, he diligently ſearches for it, and dwells in it, when as he hath found it: But the *Pinnoter* is not bred by it ſelf alone, but in *Pinnæ* and ſome others, and he changeth not his habitation, becauſe (as *Ariſtotle* thinks) being of the kind of Dwarf-Crabs, it never grows big, neither dwells it in empty ſhells. Now the *Pinna*, or *Pin*, is a kind of ſhell-fiſh, it breeds in muddy places, and is always open, neither is it at any time without a Companion, which they therefore call the *Pinnoter*, or *Pinnophylax*, (*i. e.*) the Pin-keeper, as *Pliny* ſaith. Verily that theſe things are thus, you may plainly perceive by theſe words of *Athenæus*. *Chryſippus Solenſis* 5. *De Honeſt. & Volupt.* ſaith, the *Pinna* and *Pinnoter* aſſiſt and further each other, neither can they live aſunder. The *Pinna* may be referred to the kind of Oiſters, but the *Pinnoter* is a Dwarf-Crab: the *Pinna* opens her ſhell for the little fiſhes to enter thereinto; the *Pinnoter* ſtands by, obſerving if any come in; which if they do, he gives the *Pin* notice thereof by biting, who preſently thereupon ſhuts her ſhell, and ſo they feed together upon that they catch by this means. Thus *Athenæus*. She is alſo for this her craft mentioned by *Plutarch* in his Writings. The *Pinnoter* is ſometimes called by *Pliny*, *Cancer dapis affectator*.

What the *Pinnoter*, or Dwarf-Crab is.

What the *Pinna* is.

Lib. 9. *cap.* 42.

Lib. 3. *Deipno.*

The familiarity and craft of the *Pinna* and *Pinnoter*.

But that which by theſe Authors is attributed to the Dwarf-Crab, the ſame by *Cicero* is aſcribed to the little Shrimp: Now the *Pinna* (ſaith he) opening her two large ſhells, enters into confederacy with the little Shrimp for getting of food; wherefore when little Fiſhes ſwim into her gaping ſhell, then the *Pinna*, admoniſhed by the Shrimps biting her, ſhuts her ſhell; thus two unlike Creatures get their living together. But *Plutarch* ſeems to make the *Pinna* to be the Pearl-Oiſter in that Work of his, whereas he enquireth whether the craft of Water or Land-beaſts be the greater.

Lib. 2. *de nat. deorum.*

The Figure of him out of his Cell.

The Effigies of Bernard *the Hermit houſed in his Shell.*



Plin. lib. 9. c. 29.

But amongſt the moſt miraculous Fiſhes may fitly be placed the *Nautilos*, or Sailer; of ſome called *Pompylos* (it is thought to be a kind of *Polypus*) it comes with the face upwards to the top of the Sea, raiſing it ſelf by little and little, that caſting forth all the water by a pipe, as if it had a Pump, it eaſily floats; then putting back the two firſt tendrils or arms, it extends between them a membrane of wondrous fineneſs or thinneſs, which gathering air like as a Sail, and ſhe rowing with the reſt of her arms, guides her ſelf with her tail in the midſt, as a Rudder. Thus ſhe ſails along in imitation of Pinnaces, and if any thing affright her, ſhe preſently takes in Water, and ſinks her ſelf.

How the Whale may be reckoned amongſt Monſters.

The better to ſtore this Treatiſe of Monſters, abuſing the name with the Poets, we will reckon up the Whale amongſt the Sea-monſters, by reaſon of his monſtrous and wondrous magnitude. Now the Whale is the greateſt by much, of all the Fiſhes of the Sea; for moſt commonly this Beaſt is thirty ſix cubits long, eight high, the ſlit of his mouth is eighteen foot long, teeth they have none, but in ſtead thereof in each Jaw, horny black Excreſcences or Fins [which we vulgarly term Whale-bones] which by little and little end in ſmall hairs like to a Swines briſtles, which coming and ſtanding out of his mouth, are in ſtead of Guides, leſt whileſt he ſwims with a blind and rapid violence, he might run againſt a Rock. His eyes are diſtant one from the other the ſpace of four Ells, which outwardly appear ſmall, but inwardly they are bigger than a mans head; wherefore they are deceived that ſay that they are no bigger than an Oxes eyes: his noſe is ſhort, but in the middle of his fore-head he hath a pipe whereat he draws in the air, and caſts forth a whole ſhower or River of water, that therewithal he will even ſink the Veſſels or Boats of Mariners; when he hath filled himſelf beyond meaſure, he cries out or roars with ſo great or ſtrong a voice, that he may be heard two miles off. He hath two very large fins upon his ſides wherewith he ſwims, and under which in the time of danger he hides his young; he hath none upon his back. His tail in ſite is like to the tails of Dolphins, neither is it much unlike in ſhape, which when he moves, he ſo toſſeth the Sea, that he drowns and overturns the Boats that he toucheth. You may by diſſecting them find that a Whale brings forth live young, and gives them ſuck; for the male hath Teſticles and a Yard, but the female a Womb and Dugs. They are taken in divers places about Winter, but chiefly about the Coaſt of *Aquitain*, at a ſmall Town which is vulgarly called *Biarris*, ſome ſix miles diſtant from *Bayon:* whereunto I being ſent by King *Charls* the Nineth when he was at *Bayon*, to cure the Prince of *Roche Sur-Yon*, I was an eye-witneſs how they are caught; and alſo I confirmed that which I had formerly read to that purpoſe, in that excellent and moſt

A Whale brings forth young, and ſuckles them.

true

true Hiſtory of Fiſhes ſet forth by *Rondoletius*. Now at that Town there is a little hill, in the top whereof there is a Tower of very great antiquity, from which as from a watch-Tower they keep watch whether or no any Whales ſwim that way. Wherefore the Watch-men from the Tower, either ſeeing, or by the horrible noiſe hearing a Whale to paſs that way, they give warning thereof to the inhabitants by the beating of Drums, and ringing a Bell: which ſign once given they all run forthwith, as to extingniſh the City if it were on fire, being furniſhed with weapons and all things fitting for that purpoſe. For the people of that country are very diligent and expert in catching the Whale. Wherefore in each of the boats furniſhed with all things either to aſſail or flie, there are put ten luſtie rowers, and divers others furniſhed with harping irons to ſtrike the Whale, which being caſt and faſtned in her, they looſe out huge long ropes, faſtned to them, until ſuch time as he be dead, then together with the ropes, and aſſiſted by the waves of the Sea, they draw the Whale (wearied with running and labouring, and fainting by reaſon of the magnitude and multitude of his wounds, being in the time of their conflict diligently chaſed and driven toward the ſhore) on land, and merrily part the prey, each whereof hath his ſhare, according to the number of the irons thrown, the magnitude of the wound, and the neceſſity and excellency of the wounded part for life: each of their harping-irons are known by their peculiar marks. In the heat of the skirmiſh many ſtand up and down in boats, onely for this purpoſe, to take up ſuch as chance to fall into the Sea, leſt they ſhould be drowned. The Males are caught with more difficulty, the Females more eaſily, eſpecially if their young ones be with them; for whileſt they linger to help and ſuccour them, they loſe the occaſion of eſcaping. The fleſh is of no eſteem, the tongue onely is commendable; for being very large, and of a very lax ſubſtance, it is powdered, and by moſt Gentlemen accounted for a dainty. The lard is diſperſed over many Countries, to be boiled and eaten with fiſh in the time of Lent, that Gormandizers may have ſomething to ſerve them in ſtead of fleſh which is then forbidden. There is great ſtore of Fat in them in the parts under the skin and belly, which melted, concretes not again, by reaſon of the ſubtilty; they keep it to burn in Lamps, and to uſe about their Ships. The houſes of the Fiſh-eaters are built with their bones; alſo Orchards in the Coaſt of *Aquitane*, are fenced with theſe bones. The Fins that ſtand forth of their mouths, which are commonly called Whale-bones, being dried and poliſhed, ſerve to make Busks for Women, Whip-ſtaves, and little Staves, as alſo to ſtiffen garments. Many make ſeats or ſtools of the *Vertebræ*, or ſpondils of the back-bone.

How they are caught.

Why the Females are more eaſily caught then the Males.

Whale-bone.

The manner of cutting up the Whale.



In the River *Scalde*, ten miles from *Antwerp*, *Anno Dom.* 1477. the ſecond day of *July*, there was a Whale taken, of a blackiſh blue colour, ſhe had a ſpout-hole in the top of her head, out of which ſhe caſt great ſtore of water: ſhe was fifty eight foot long, and ſixteen foot high, her tail was fourteen foot broad; from the eye to the end of her noſe, was ſome ſixteen foot. Her lower jaw was ſix foot on each ſide, ſhe had twenty five teeth, which ſhe could hide in her upper jaw, there being holes for them, it being wholly toothleſs; for which one thing this Whale may be judged monſtrous, for that Nature hath denied them teeth, and for that in Creatures that are not horned, it is ſo ordained by Nature, that when they have teeth in their lower jaw, they ſhould have others alſo in the upper to anſwer them, ſo to chaw their meat. The longeſt of theſe teeth exceeded not ſix inches.

There is (as *Pliny* reports) a very ſmall Fiſh accuſtomed to live upon Rocks, it is called *Echeneis*, never exceeding the length of a foot; it is thought that ſhips go more ſlowly if this ſtick to them: wherefore the Latins have alſo given it a name of *Remora*, for that a ſhip being under ſail with a good wind, may by the *Echeneis* ſeizing on her, as if ſhe would devour her, be ſtaid againſt the Sailers wills, and ſtand ſtill as if ſhe were in a ſafe harbor. Wherefore ſhe is ſaid in the *Actiun* fight to have ſtaid the ſhip of *Marcus Antonius*, haſtening to go about and incourage his Souldiers, ſo that he was forced to enter into another ſhip, and thereupon *Cæſars* Navy came upon them too haſtily, and before they were provided.

Lib. 9. cap. 25. & lib. 32. cap. 1. The wondrous power of the *Remora*.

She alſo ſtaid the Ship of the Emperour *Caius* coming from *Aſiura* to *Antes*, his Ship of all the Navy making no way; neither did they longer wonder at this ſtay, the cauſe being preſently known, ſome forthwith leaping into the Sea to find the cauſe thereof, there found her about the Ship, even ſticking to the Rudder, and they ſhewed her to *Caius*, being wrath that this ſo ſmall a thing ſhould ſtop him, and countermand the endeavour of forty Rowers.

Therefore this little Fiſh tames and infringes the violence and madneſs of the world, and that with

with no labour, not without holding, or any other way, but onely by ſticking thereto. Certainly, however it comes to paſs, who from this example of holding of Ships, can doubt of any power or effect of Nature, in Medicins which grow naturally? Yea, and without this example, the *Torpedo* out of the Sea alſo may be ſufficient; who afar off and at a diſtance, if it be touched with a Spear or Rod, will benumb even the ſtrongeſt arms, and retard the feet, how ever nimble to run away.

The wondrous force of the *Torpedo*.

CHAP. XXII.

Of the admirable Nature of Birds, and of ſome Beaſts.

THat there be divers things not onely in the Sea, but alſo in the Air and Earth, which by the wonderful condition of their own Nature may equal that of Monſters, the onely *Eſtrich* may ſerve for a witneſs. It is the biggeſt of Birds, though indeed it partly reſembles a Bird, and partly a Beaſt, (and it is familiar to *Africa* and *Æthiopia*) as which, contrary to the nature of Beaſts, hath feathers, and againſt the cuſtom of Birds, cannot flie aloft; for it hath not feathers fit to flie, but like unto hairs, yet will it outrun a horſe. The natural force of the ſtomach in concocting, is miraculous; as to which nothing is untamable: ſhe lays eggs of a wondrous largeneſs, ſo that they may be framed into cups: their feathers are moſt beautiful, as you may perceive by this following Figure.

The Eſtrich is between a Bird and a Beaſt.

The wondrous force of her ſtomach.

The Figure of an Eſtrich.

Any one may eaſily gather of what a prodigious magnitude an *Eſtrich* is, by the greatneſs of its bones. Three of theſe Birds were kept at the Kings charge, by the Mareſchal *De Rets*: one whereof dying, it was beſtowed upon me, whereof I have with great diligence made a *Sceleton*.



The delineation of the Sceleton *of an Eſtrich.*

A *Shews the head, which was somewhat thicker than the head of a Crane, of the length of ones hand, plain from the crown even to the beak; the beak being divided to the middle region of the eye, being roundish at the end thereof.*

B *The neck a yard long, consisting of seventeen* Vertebræ, *each whereof on each side is furnished with a transverse process looking downwards, of some fingers length, excepting the two which are next the head, which want these, and are joined together by* Ginglymos.

C *The back is of a foots length, consisting of seven* Vertebræ.

D *The holy-bone of two foot long, in whose top there is a transverse process, under which there lies a great hole.*

E *Three more, but less.*

F G H *After which there follows the cavity or socket, whereinto the head of the thigh bone is received and hid. This externally and on the side produceth a perforated bone, noted with the letter* I. *perforated I say at the beginning, for it is presently united at the letter* K. *then it is forked and divided into two other bones, whereof one is bigger than the other. The less is noted with the letter* L. *then they are both united at the letter* M. *each of them is half a foot and four inches long. But from that part whereas they first begun to be divided, to that whereas they are united, there is a hole some four fingers broad, but the length of ones hand, or more, and it is noted with the letter* N. *The residue of the bone is like to a pruning Knife three inches broad, but six in length: the end whereunder is the letter* O. *it is joined by coalition.*

P *The rump consisting of nine* Vertebræ, *like to a mans. The thigh bones are two, whereof that which is noted with the letter* Q. *is of the length of a foot, and of thickness equal to a horses thigh. The other next under (which peradventure you may call the leg-bone) noted with* R. *is a foot and half long: it hath joined thereto the* Fibula, *or lesser focil of the length, but which grows smaller as it comes lower.*

S *Is the leg, to which the foot adheres, being one foot and a half long, divided at the end into two claws, the one bigger, the other less, whereof each one consists of three bones.*

T *Eight ribs, which are inserted into the* Sternon, *the three middlemost of these have a bony production like to a hook.*

V *Is the* Sternon, *consisting of one bone of some foots length, representing a buckler; to this there is joined another bone, which stretched over the three first ribs, is in stead of clavicles or collar-bones.*

X *The first bone of the wing, which is one foot and half long.*

Y *Two bones under this, equivalent to the ell and wand, under which there are six other bones composing the point of the wing, noted with* Z.

This whole *Sceleton* is seven foot long, and so many foot or more high from the feet to the beak: there are many other observable things in his composure, but I have thought fit to omit them for brevity sake.

The description of the Bird of Paradise.

Jerome Cardane in his Books *De Subtilitate*, writes that in the Island of the *Moluccas* you may sometimes find lying upon the ground, or take up in the waters, a dead Bird called a *Manucodiata*, that is in Hebrew, the Bird of God, it is never seen alive. It lives aloft in the air, it is like a Swallow in body and beak, yet distinguished with diverse coloured feathers: for those on the top of the head are of a golden colour, those of the neck like to a Mallard, but the tail and wings like Peacocks;



*it wants feet: wherefore if it become weary with flying, or desire sleep, it hangs up the body by twining the Feathers about some bough of a tree. It passeth through the air, wherein it must remain as long as it lives, with great celerity, and lives by the air and dew onely. The Cock hath a cavity depress't in the back, wherein the Hen lays and sits upon her egs. I saw one at *Paris* which was presented to King *Charles* the Nineth.

* Whosoever desires to know more of the truth of this bird, let him read *Clusius* in the *Auctarium ad lib.* 5. *cap.* 1. *Exoticorum.*

We have read in *Thevets* Cosmography, that he saw a Bird in *America*, which in that Countrey Speech is called *Touca*, in this very monstrous and deformed, for that the beak in length and thickness, exceeds the bigness of the rest of the body; it feeds on pepper, as the Black-birds and Felfars with us do upon Ivy-berries, which are not less hot than Pepper. *Tom.* 2. *l.* 21. *c.* 22.

A certain Gentleman of *Provence* brought a Bird of this kind from that Country, to present it to King *Charles* the Nineth, but dying in the way he could not present it alive. Wherefore the King wished the Mareschal *De Rets* to give her to me, that I might take forth her bowels and embalm her, that she might be kept amongst the Kings rarities. I did what I could, yet not long after she rotted: she resembled a Crow in body and feathers, but had a yellowish beak, clear, smooth, and

and toothed like a Saw, and of ſuch length and thickneſs as we formerly mentioned. I keep it yet as a monſtrous thing.

Tom.1.cap.11. lib.4. *Thevet* writes, that in the Iſland *Zocotera* there is frequently found a certain wild Beaſt called *Hulphalis*, of the bigneſs of an Ethiopian Monkey. It is a very monſtrous Creature, but in nothing more than that it is thought to live upon the air onely; the skin as if it were died in grain, is of a ſcarlet colour, yet it is in ſome places ſpotted and variegated: it hath a round head like to a bowl, with feet round, broad, and wanting hurtful nails. The Moors kill it and uſe to eat the fleſh of it, being firſt bruiſed, that ſo it may be the more tender.

Thevet. tom.1. lib.11. cap.13. In the Realm of *Camota*, of *Ahob*, of *Benga*, and other Mountains of *Cangipa*, *Plimatiq*, and *Catagan*, which are in the inner *India*, beyond the River of *Ganges*, ſome five degrees beyond the Tropick of *Cancer*, is found a Beaſt, which the Weſtern Germans call *Giraff*. This Beaſt in head, ears, and cloven feet, is not much unlike our Doe; it hath a very ſlender neck, but is ſome ſix foot long, and there are few Beaſts that exceeds him in the length of their legs: his tail is round, but reacheth no farther then his hams, his skin is exceeding beautiful, yet ſomewhat rough, having hair thereon ſomewhat longer than a Cow, it is ſpotted and variegated in ſome places with ſpots of a middle colour between white and cheſnut, ſo as Leopards are: for which cauſe by ſome Greek Hiſtorians it is called *Cameleopardalis*: it is ſo wild before it be taken, that with the good-will it will not ſo much as be ſeen. Therefore it inhabits and lives onely in deſert and ſecret places, unknown to the reſt of the Beaſts of that Region; ſhe preſently flies away at the ſight of a man, yet he is taken at length, for that he is not very ſpeedy in running away; once taken he is as eaſily and ſpeedily tamed as any wild Beaſt whatſoever. He hath above his crown two ſtrait horns covered with hairs and of a foot length. When as he holds up his head and neck, he is as high as a Lance. He feeds upon Herbs, and Leaves, and Boughs, or Trees; yea, he is alſo delighted with bread.

The Effigies of a Giraffa.



Such as ſail in the Red-ſea along the Coaſt of *Arabia*, meet with an Iſland called by the Arabians *Cademota*: in that part thereof where the River *Plata* runs, is found a wild Beaſt called by the barbarous Inhabitants *Paraſſoupi*, being of the bigneſs of a Mule, headed not unlike one, yet rough and haired like to a Bear, but not of ſo dark a colour, but inclining to yellow, with cloven feet like a Hart: ſhe hath two long horns on her head, but not branched, ſomewhat reſembling thoſe ſo much magnified horns of Unicorns. For the Natives of the place, bitten by the venomous tooth of either Beaſt or Fiſh, are preſently helped and recovered by drinking the water wherein ſuch horns have been infuſed for ſix or ſeven days ſpace, as *Thevet* in his Coſmography reports.

In

In one of the Iſlands of the *Moluccaes* there is found a Beaſt living both on Land and Water like as a *Crocodile*; it is called *Campureh*, it is of the bigneſs of an Hart, it hath one horn in the fore-head moveable after the faſhion of the noſe of a Turky-cock: it is ſome three foot and a half long, and never thicker than a mans arm; his neck is covered over with an aſh colour; he hath two feet like to a Gooſes feet, wherewith he ſwims both in freſh and ſalt-waters. His fore-feet are like to a Stags, he lives upon fiſh. Many have perſwaded themſelves that this beaſt is a kind of Unicorn, and that therefore his horn ſhould be good againſt poiſons. The King of the Iſland loves to be called by the name of this Beaſt; and ſo alſo other Kings take to themſelves the names of the wild Beaſts, Fiſhes, or Fruits, that are moſt precious and obſervable in their dominions, as *Thevet* reports.

The Figure of an Elephant.

Man-

The Indian Elephants are biggeſt than the African.

Mauritania and *Æthiopia* and that part of *Africk* that is beyond the Deſarts and Syrtes, bring forth Elephants; but thoſe of *India* are far larger. Now although in the largeneſs of their body they exceed all four-footed Beaſts, yet may they be more ſpeedily and eaſily tamed than other Beaſts. For they may be taught to do many things above the common nature of Beaſts. Their skin is ſomewhat like to a Buffles, with little hair upon it, but that which is, is aſh-coloured, his head large, his neck ſhort, his ears two handfuls broad, his noſe or trunk very long, and hanging down almoſt to the ground, hollow like as a Trumpet, the which he uſeth in ſtead of an hand, his mouth is not far from his breſt, not much unlike a Swines, from the upper part whereof two large teeth thruſt forth themſelves, his legs are thick and ſtrong, not conſiſting of one bone as many formerly have falſly believed (for they kneel to admit their Rider, or to be laden, and then riſe up again of themſelves) his feet are round like a Quoit ſome two or three hands bredth, and divided into five cleſts. He hath a tail like a Buffle, but not very rough, ſome three hands bredth long; wherefore they would be much troubled with Flies and Waſps, but that Nature hath recompenced the ſhortneſs of their tails by another way; for when they find themſelves moleſted, they contract their skin ſo ſtrongly, that they ſuffocate and kill theſe little Creatures taken in the wrinkles thereof; they overtake a man running by going onely, for his legs are proportionable to the reſt of his body.

How they keep Flies from them.

They feed upon the leaves and fruits of Trees, neither is any tree ſo ſtrong and well rooted, which they cannot throw down and break. They grow to be ſixteen handfuls high; wherefore ſuch as ride upon an Elephant are much troubled as if they went to Sea. They are of ſo unbridled a nature, that they cannot endure any head-ſtall or reins; therefore you muſt ſuffer them to take the courſe and way they pleaſe. Yet do they obey their Countrey-men without any great trouble, for they ſeem after ſome ſort to underſtand their Speech, wherefore they are eaſily governed by their known voices and words. They throw down a man that angers them, firſt taking him up with their trunk and lifting him aloft, and then letting him fall, they tread him under foot, and leave him not before he be dead. *Ariſtotle* writes that Elephants generate not before they be twenty years old: they know not adultery, neither touch they any female but one, from which they alſo diligently abſtain when they know ſhe hath once conceived. It cannot be known how long they go with young; the reaſon is for that their copulation is not ſeen, for they never do it but in ſecret. Their females bring forth reſting upon their hind legs, and with pain like Women; they lick their young, and theſe preſently ſee and go, and ſuck with their mouths, and not with their trunks. You may ſee Elephants teeth of a monſtrous and ſtupendious bigneſs, at *Venice*, *Rome*, *Naples*, and *Paris*; they term it Ivory, and it is uſed for Cabinets, Harps, Combs, and other ſuch like uſes.

Liv. 9. de Hiſt. anim. cap. 28.

It is not known how long an Elephant goes with young.

Tom. 2. lib. 23. cap. 2.

We have read in *Thevet*, that in *Florida* there are great Bulls, called in that Countrey Tongue *Beautrol*, they have horns of a foot long, a bunch on their backs like a Camel, their hair long and yellow, the tail of a Lion; there is ſcarce any Creature more fierce or wild, for it can never be tamed, unleſs it be taken from the dam. The Salvages uſe their hides againſt the cold, and their horns as an antidote againſt poiſon.

Their horns good againſt poiſon.

Tom. 1. lib. 2. cap. 10.

The ſame Author affirms, that whileſt he ſailed in the Red Sea, he ſaw a Monſter in the hands of a certain Indian Merchant, which in the bigneſs and ſhape of his limbs was not unlike a Tiger, yet had the face of a Man, but a very flat noſe: beſides his fore-feet were like a mans hands, but the hind like the feet of a Tigre; he had no tail, he was of a dun colour: to conclude, in head, ears, neck, and face it reſembled a man, but in the blackiſh and curled hair, a Moor: for the other parts they were like a Tiger; they called it *Thanacth*.

The Figure of a Beaſt called Thanacth.



This following Monſter is ſo ſtrange that it will ſcarce be believed, but by thoſe that have ſeen it: it is bred in *America*, and by the Salvages called *Haiit*, of the bigneſs of a Monkey, with a great belly, almoſt touching the ground and the head and face of a child: being taken it mourns and

and ſighs like to a man that is troubled and perplext; it is of an aſh-colour, hath the feet divided into three claws, four fingers long, and ſharper than thoſe of a Lion: it climbs Trees and lives there more frequently than upon the ground, the tail is no longer than the bredth of three fingers. It is ſtrange and almoſt monſtrous that theſe kind of Creatures have never been ſeen to feed upon or eat any thing: for the Salvages have kept them long in their houſes to make trial thereof, wherefore they think them to live by the Air.

The Figure of the Beaſt called Haiit.

I have taken this following Monſter out of *Leo*'s Affrican Hiſtory; it is very deformed, being round after the manner of a Tortoiſe two yellow lines croſſing each other at right angles, divide his back; at every end of which he hath one eye, and alſo one ear, ſo that ſuch a creature may ſee on every ſide with his four eyes, as alſo hear by his ſo many ears: yet hath he but one mouth, and one belly to contain his meat, but his round body is encompaſſed with many feet, by whoſe help he can go any way he pleaſe without turning of his body, his tail is ſomething long and very hairy at the end. The inhabitants affirm, that his bloud is more effectual in healing of wounds than any balſam.

Blood as good as Balſom.



It is ſtrange that the *Rhinoceros* ſhould be a born Enemy to the Elephant; wherefore he whets his horn, which grows upon his noſe, upon the Rocks, and ſo prepares himſelf for fight, wherein he chiefly aſſails the belly, as that which he knows to be the ſofteſt: he is as long as an Elephant, but his legs are much ſhorter, he is of the colour of Box, yet ſomewhat ſpotted. *Pompey* was the firſt that ſhewed one at *Rome*. *Plin. l. 8. c. 24.*

The Figure of the Rhinoceros.

The

The Figure of the Chameleon.



Africa produceth the *Cameleon*, yet is it more frequent in *India*: he is in ſhape and greatneſs like a Lizard, but that his legs are ſtrait and higher, his ſides are joined to the belly as in Fiſh, and his back ſtands up after the ſame manner, his noſe ſtands out not much unlike a Swines, his tail is long, and endeth ſharp, and he folds it up in a round, like a Serpent, his nails are crooked, his pace ſlow, like as the Tortois, his body rough, he never ſhuts his eyes, neither doth he look about by the moving of the apple, but by the turning of the whole eye. The nature of his colour is very wonderful, for he changeth it now and then in his eye and tail, and whole body beſide; and he always aſſimilates that which he is next to, unleſs it be red or white. His skin is very thin, and his body clear; therefore the one of theſe two, either the colour of the neighbouring things in ſo great ſubtilty of his clear skin, eaſily ſhines as in a glaſs; or elſe various humours diverſly ſtirred up in him, according to the variety of his affections, repreſent divers colours in his skin, as a Turky-cock doth in thoſe fleſhy excreſcences under his throat, and under his head: he is pale when he is dead. *Mathiolus* writes that the right eye taken from a living Chameleon takes away the white ſpots which are about the thorny coat of the eye; his body being beaten, and mixed with Goats milk, and rubbed upon any part, fetcheth off hairs; his gall diſcuſſeth the Cataracts of the eye.

Plin. lib. 8. c. 33.

Ariſt. lib. 2. hiſt. anim. cap. 12.

The ſtrange nature of the colour of the Chameleon.

CHAP. XIII.

Of Celeſtial Monſters.

PEradventure it hath not been ſtrange that Monſters have been generated upon the Earth, and in the Sea: but for monſters to appear in Heaven, and in the upper Region of the Air, exceeds all admiration. Yet have we often read it written by the Ancients, that the Face of Heaven hath been deformed, by bearded, tailed, and haired Comets; by Meteors repreſenting burning Torches and Lamps, Pillars, Darts, Shields, Troops of Clouds hoſtilely aſſailing each other; Dragons, two Moons, Suns, and the like Monſters and Prodigies.

Antiquity hath not ſeen any thing more prodigious than that Comet which appeared with bloudy hair in *Uverſtein*, upon the ninth day of *October*, 1528. for it was ſo horrible and fearful a ſpectacle, that divers died with fear, and many fell into grievous diſeaſes going from the Eaſt to the South; it endured no longer than one hour and a quarter: in the top whereof was ſeen a bending arm holding a great Sword in a threatning hand; at the end thereof appeared three Stars, but that over which the point of the Sword directly hanged, was more bright and clear than the reſt: on each ſide of this Comet were ſeen many Spears, Swords, and other kinds of Weapons died with bloud, which were intermixed with mens heads, having long and terrible hair and beards, as you may ſee in this Figure.

The Figure of a fearful Comet.

Alſo there have been ſeen great and thick bars of Iron to have fallen from Heaven, which have preſently been turned into Swords and Rapiers. At *Sugoliah* in the Borders of *Hungaria*, a Stone fell from Heaven with a great noiſe, the ſeventh day of *September*, *Anno Dom.* 1514. it weighed two hundred and fifty pound: the Citizens hanged it up with a great iron chain put through it, in the midſt of the Church of their City, and uſed to ſhew it as a miracle to Travellers of better note, that paſs that way. * *Pliny* reports that claſhing of armour, and the ſound of a Trumpet were heard from Heaven often, before and after the *Cimbrian* War. The ſame Author writes that in the third Conſulſhip of *Marius* the *Amarines* and *Tudortines* ſaw the Heavenly Armies coming from Eaſt and Weſt, and ſo joining, thoſe being vanquiſhed which came from the Eaſt. Which ſame thing was ſeen in *Luſalia*, at a Town called *Jubæa*, two hours after midnight, *Anno Dom.* 1535. But in *Anno Dom.* 1550. upon the 19 day of *July*, in *Saxony* not far from *Wittenburg*, there appeared in the air a great Stag, incompaſſed with two armed Hoſts, making a great noiſe in their conflict, and at the ſame inſtant it rained bloud in great abundance; the Sun ſeemed to be cloven in two pieces, and the one of them to fall upon the Earth. A little before the taking of *Conſtantinople* from the Chriſtians, there appeared a great army in the Air appointed to fight, attended on with a great company of Dogs and other wild Beaſts. *Julius Obſequius* reports that in *Anno Dom.* 458. it rained fleſh in *Italy*, in great and leſſer pieces, part of which were devoured by the Birds before they fell upon the Earth: that which fell upon the Earth kept long unputrified, and unchanged in colour and ſmell. *Anno Dom.* 989. *Otho* the third being Emperour, it rained Corn in *Italy*. *Anno Dom.* 180. it rained Milk and Oil in great abundance, and Fruit-bearing Trees brought forth Corn. *Lycoſthenes* tells that in the time of *Charles* the Fifth, whileſt *Maidenburg* was beſieged, three Suns firſt appeared about ſeven of the clock in the Morning, and then were ſeen for a whole day, whereof the middlemoſt was the brighteſt, the two others were reddiſh, and of a bloudy colour; but in the night time there appeared three Moons. The ſame appeared in *Bavaria*, *Anno Dom.* 1554.

* *Lib.* 2. *c.* 57.

Preſages of the taking of *Conſtantinople.*

Monſtrous Rains.

Earthquakes.

But if ſo prodigious and ſtrange things happen in the Heavens beſides the common order of Nature, ſhall we think it incredible that the like may happen in the Earth. *Anno Dom.* 542. the whole Earth quaked, Mount *Ætna* caſt forth flames and ſparks of fire, with which many houſes of the neighbouring Villages were burned. *Anno Dom.* 1531. in *Portugal* there was an Earthquake for eight days, and it quaked ſeven or eight times each day; ſo that in *Lisbon* alone it caſt down a thouſand and fifty houſes, and more than ſix hundred were ſpoiled. *Ferrara* lately was almoſt wholly demoliſhed by a fearful Earthquake. Above all which ever have been heard, is that Prodigy which happened in the time of *Pliny* at the death of *Nero* the Emperor, in the *Marucine* field, the whole Olive-field of *Vectius Marcellus*, a *Roman* Knight, going over the High-way, and the Fields which were againſt it coming into the place thereof. Why ſhould I mention the miracles of Waters, from whoſe depth and ſtreams, fires and great flames have oft broke forth. They tell out of St. *Auguſtin*, that the fire of the Sacrifice, which for thoſe ſeventy years of the Babylonian captivity endured under the Water, was extinguiſhed, *Antiochus* ſelling the Prieſthood unto *Jaſon*. What miracle is this, that the Fire ſhould live in the Water, above its force and natural efficacy, and that the Water ſhould forget the extinguiſhing faculty! Verily Philoſophers truly affirm that the Elements which are underſtood to be contrary, and to fight in variety among themſelves, are mutually joined and tied together by a marvellous confederacy.

Lib. 2. *cap.* 73.

The End of the Five and Twentieth Book.

BOOK

BOOK XXVI.

Of the FACULTIES *of* SIMPLE MEDICINS, *As alſo of their* Compoſition *and* Uſe.

THE PREFACE.

AMongſt the cauſes which we term healthful, and other remedies which pertain to the health of Man, and the expelling of Diſeaſes, Medicins eaſily challenge the prime place; which (as it is delivered by Solomon*) God hath produced out of the Earth, and they are not to be abhorred by a Wiſe man; for there is nothing in the World, which ſooner, and as by a miracle, aſſwageth the horrid torments of Diſeaſes. Therefore* Herophilus *called them fittingly adminiſtred,* The Hands of the Gods. *And hence it was that ſuch Phyſicians as excelled in the knowledge of Medicins, have amongſt the Ancients acquired an opinion of Divinity. It cannot by words be expreſſed what power they have in healing. Wherefore the knowledge of them is very neceſſary not onely for the preventirn, but alſo for the driving away of Diſeaſes.* The excellency of Medicins.

CHAP. I.

What a Medicin is, and how it differeth from nouriſhment.

WE define a Medicin to be that which hath power to change the body according to one or more qualities; and that, ſuch as cannot be changed into our Nature: contrary whereto we term that nouriſhment which may be converted into the ſubſtance of our Bodies. But we define them by the word *Power*, becauſe they have not an abſolute nature, but as by relation and depending upon the condition of the bodies by whom they are taken. For that which is medicin to one, is meat to another; and that which is meat to this, is medicin to that. Thus for example, Hellebore is nouriſhment to the Quail, but a medicin to man: Hemlock is nouriſhment to a Starling, but poiſon to a Gooſe: the Ferula is food to an Aſs, but poiſon to other Cattel. Now this diverſity is to be attributed to the different natures of Creatures. It is recorded in Hiſtory, that the ſame by long uſe may happen in men. They report that a Maid was preſented to *Alexander* the Great, who nouriſhed with *Napellus*, and other poiſons, had by long uſe made them familiar to her, ſo that the very breath ſhe breathed was deadly to the by-ſtanders. Therefore it ought to ſeem no marvel, if at any time it happen, that Medicins turn into the nature and nouriſhment of our bodies: for we commonly may ſee Birds and Swine feed upon Serpents and Toads without any harm: and laſtly,

——— Serpente Ciconia pullos
Nutrit, & inducit per devia rura lacerta:
Illi eadem ſumptis quærunt animalia pennis.
The Stork with Serpents and with Lizards caught,
In wayleſs places nouriſheth her brood:
And they the ſame purſue, when as they're taught
To uſe their Wing, to get their wiſh'd-for food.

CHAP. II.

The difference of Medicins in their matter and ſubſtance.

EVen as the concealed glory of worldly riches lieth hid in the bowels of the Earth, and depth of the Sea and Water, as Gold, Silver, and all ſorts of Metals, Gems, and pretious Stones, furniſhed with admirable Virtues; ſo we may behold the ſuperficies of this Earth cloathed with almoſt an infinite variety of Trees, Shrubs, and Herbs: where we may contemplate and wonder at the innumerable diverſities of Roots, Leaves, Flowers, Fruits, Gums, their Smells, pleaſant Taſtes and Colours, but much more at their Virtues. This ſame Mother Earth, as with her Breſts, nouriſheth marvellous diſtinct kinds of living Creatures, various in their ſpringing, increaſe and ſtrength, wherein the immenſe goodneſs of God, the great Architect and framer of all things, doth moſt clearly appear towards man, as who hath ſubjected to our government, as a Patrimony, ſo ample and plentiful proviſion of Nature for our delight in nouriſhment and neceſſity of healing. Therefore the ancient Phyſicians have rightly delivered, that all ſorts of Medicins may be abundantly had from living Creatures, Plants, the Earth, Water, and Air. The Earth the Mother of Riches and Medicins.

Medicins are taken from living Creatures either whole and entire, or elſe the parts and excrements of them. We oft-times uſe in Phyſick whole Creatures, as Foxes, Whelps, Hedge-hogs, Frogs, Snails, Worms, Crabs, and other living Creatures. We alſo make uſe of ſome parts of them, as the Liver of a Wolf or Goat, the Lungs of the Fox, the Bone of the Stags heart, *Cranium humanum*, Fat, Bloud, Fleſh, Marrow, the Cods of the *Caſtor*, or Beaver, which is therefore termed *Caſtoreum*, and ſuch What Medicins taken from living Creatures.

other particles that are uſeful in Phyſick. We know that alſo there are ſome Medicins taken from Excrements, as Horns, Nails, Hairs, Feathers, Skin; as alſo from Urin, Dung, Spittle, Honey, Eggs, Wax, Milk, Wool, Sweat, and others of this kind, under which we may comprehend Musk, Civet, Pearl, *Oeſipus*, and ſundry others of this nature.

What from Plants. We take Medicins from Plants, both whole, and alſo from their parts, whether Trees, Shrubs, or Herbs. For we oft-times uſe Succory, Marſh-mallows, Mallows, Plantain, and the like, whole: but otherwhiles onely the roots of Plants, their Pith, Wood, Bark, Shoots, Stalks, Leafs, Flowers, Seeds, Fruits, Juices, Gums, Roſins, Moſſes, and the like.

What from the Earth. Things taken from the Earth, for the uſe and matter of Medicin, are either Earths, Stones, or Minerals. The ſorts of Earth are Bole-Armenick, *Terra ſigillata*, Fullers-earth, Chalk, Potters-clay, and ſuch like. Stones, are the Pumice, Marchaſite of Gold, Silver, Braſs, Marble, the Load-ſtone, Plaiſter, Chalk, *Sulphur vivum*, *Lapis ſpecularis*, and others. Metals and Minerals, are Gold, Silver, Tin, Lead, Braſs, Iron, Steel, Antimony, Ceruſe, Brimſtone, Cinnabar, Litharge of Gold and Silver, Tutty, true Pompholyx, Verdigreece, Alum, Roman Vitriol, Copraſs white and green, Salts of ſundry kinds, both of Arſenicks, and ſuch like.

What from the Water. The following Medicins are from Freſh water, Rain water, Spring water, River water, and all things thence ariſing, as Water-Lentils, common Flags, Water-Lillies, Water-Mints, and all the Creatures that live therein. From the Salt water are taken Salt, *Alcyonium*, all ſorts of Coral, Shells of Fiſh, the Herb *Androſace* (which grows in plenty in the Marſhes at *Fontignan* and *Cape de Sete*) *Aſphaltum*, which is found in the Dead Sea.

What from the Air. From the Air proceeds *Manna*, therefore called *Mel Aerium* (*i.e.*) Honey of the Air, and alſo all other kinds of dew that are uſeful in Phyſick, by reaſon of the Virtues they receive from the Sun which raiſeth them up; from the Air, whereas they make ſome ſtay; as alſo from the Plants, whereupon they fall and reſide.

CHAP. III.

The differences of Simples in their Qualities and Effects.

ALl the mentioned ſorts of Simples are endued with one or more of the Four Faculties, whereof I now purpoſe to treat.

The firſt Faculty common to all the reſt, and as it were their foundation, flows from the four firſt qualities of the prime Bodies or Elements, that is, Heat, Coldneſs, Drineſs and Moiſture; and this either Simple or Compound, as one or two of theſe prime qualities exceed in the temper of the temper of the Medicin, as may appear by this following.

The *Simple* quality is either to Heat, Cool, Humect, or Dry.

The *Compound* ariſing from two joined qualities, either Heats and Dries, Heats and Moiſtens, Cools and Dries, Cools and Moiſtens.

Heat moderate, Heats, Attenuates, Rarifies, opens the Paſſages, Digeſts, Suppurates. Immoderate, Inflames and burns, Bites, whence follows Violent attraction, Rubrification, Conſumption, Colliquation, an Eſchar, Mortification.

Cold moderate, Cooleth, Condenſeth, Obſtructeth. Immoderate, Congeals, Stupefies, Mortifies.

Moiſture moderate, Humects, Lubricates, Levigates and mitigates, Glues. Immoderate, Obſtructs, lifts up into a flatulent tumour, eſpecially if it be a vaporous humidity.

Drineſs moderate, Dries, Rarifies, Attenuates. Immoderate, Binds, Contracts or ſhrinks, cauſeth Chops and Scales.

5. Simp. & 1. de aliment. The effect of theſe qualities is diſtinguiſhed, and as *Galen* obſerves, digeſted into theſe orders, which we term Degrees, ſo that by a certain proportion and meaſure they may ſerve to oppugn Diſeaſes, as the ſame *Galen* affirms. For to a Diſeaſe (for example) hot in the ſecond degree, no other Medicin muſt be uſed than that which is cold in the like degree: wherefore all ſimple Medicins are, Hot, Cold, Moiſt, or Dry; in the beginning, middle, or extreme, of the firſt, ſecond, third, or fourth degree.

The Heat, Coldneſs, Moiſture, Drineſs, of the firſt, ſecond, third, fourth degree, is either obſcure, manifeſt, vehement, or exceſſive.

Examples of the degrees of heat. An example of heat diſtinguiſhed thus by degrees, may be thus; warm water is temperate; that which is a little hotter, is the firſt degree of heat; if manifeſtly hot, it is in the ſecond degree; but if it heat more vehemently, it may be thought to come to the third; but if it ſcald, then we know that it hath arrived to the fourth degree of heat. Such alſo is the diſtinction of coldneſs, moiſture, and drineſs by degrees. Wherefore it will be worth our labour to give you examples of certain Medicins, diſtinguiſhed in their order and degree, by which you may the more eaſily give conjecture of the reſt.

Simple Medicins hot in the

Firſt degree. *Abſynthium*, *Althæa*, *Amygdala dulcia*, *Beta*, *Braſſica*, *Chamæmelum*, *Ladanum*, *Semen Lini*, *Saccarum*, *Ervum*, *ſive Orobus*, *Vinum novum*: for old is judged hot in the ſecond or third degree, as it is more or leſs years old.

Second degree. *Ammoniacum*, *Artemiſia*, *Anethum*, *Fœnugræcum*, *Maſtiche*, *Salvia*, *Marrubium*, *Meliſſa*, *Apium*, *Chamæpitys*, *Crocus*, *Ficus*, *Thus*, *Myrrha*, *Mel*, *Nux moſchata*, *Pix utraque*, *tum arida corporibus particuliſque ſolidioribus aptior*, *tum liquida delicatioribus*, *Scylla*, *Sarcocolla*, *Bryonia*, *Sal*, *Opopanax*, *Ammi*.

Third degree. *Abrotanum*, *Agnus caſtus*, *Aniſum*, *Aſarum*, *Ariſtolochia*, *Chamædrys*, *Sabina*, *Calamintha*, *Cinnamonum*, *Iris*, *Juniperus*, *Hyſſopus*, *Origanum*, *Sagapenum*, *Chelidonium majus*, *Ruta Sativa*.

Fourth degree. *Allium*, *Cæpa*, *Euphorbium*, *Naſturtium*, *Pyrethrum*, *Sinapi*, *Tithymalli*, *Anacardi*, *Chelido-*

Chelidonium minus, *Galeno*. Yet ours, by reaſon of the gentleneſs of the air, and moiſture of our ſoil, is not ſo acrid. *Ruta ſylveſtris*. This, as all wild and not cultivated things, becomes more ſtrong and acrid than the Garden-Rue.

Simples cold in the

First degree. *Atriplex*, *Hordeum*, *Cydonia mala*, *Malva*, *Pyra*, *Pruna*, *Roſa*, *Viola*.

Second degree. *Acacia*, *Cucurbita*, *Cucumis*, *Mala granata acida*, *dulcia enim temperata ſunt potius*, *Plantago*, *Polyganum*, *Solanum hortenſe*; *nam id quod ſomniferum dicitur*, *vi refrigerandi ad papaver accedit*.

Third degree. *Hyoſcyamus*, *Solanum ſomniferum*, *Portulaca*, *Sempervivum*, *Mandragora*.

Fourth degree. *Cicuta*, *Papaveris genera omnia*, *excepto Corniculato*; *huic enim incidendi & abſtergendi vim attribuit Gal. Certe nitroſum & ſalſum guſtu percipitur*, *quo fit ut calidæ & ſiccæ ſit naturæ*, *Opium*.

Simples moiſt in the

First degree. *Bugloſſum*, *Viola*, *Malva*, *Rapum*, *Spinacia*.

Second degree. *Ammoniacum*, *Lactuca*, *Cucurbita*, *Cucumis*, *Melones*, *Portulaca*.

Simples dry in the

First degree. *Thus*, *Chamæmelon*. *Braſſica*, *Sarcocolla*, *Crocus*, *Faba*, *Fœnugræcum*, *Hordeum integrum*.

Second degree. *Artemiſia*, *Pix arida*, *Orobus*, *Plantago*, *Balauſtia*, *Nux moſchata*, *Lens*, *Maſtiche*, *Mel*, *Sal*, *Anethum*, *Myrrha*.

Third degree. *Abrotonum uſtum*, *Abſynthium*, *Myrtus*, *Acetum*, *Aloe*, *Milium*, *Cuminum*, *Sanguis draconis*, *Galla*, *Sabina*.

Fourth degree. *Piper*, *Allium*, *Naſturtium*, *Sinapi*, *Euphorbium*.

Thoſe we have mentioned have of themſelves and their own nature all ſuch qualities; yet do they produce far other effects by accident, and beſides their own nature in our bodies, by reaſon of which they are termed accidental cauſes. This ſhall be made manifeſt by the following examples. The effects of the firſt qualities by accident.

External heat by accident refrigerates the body within, becauſe it opens the paſſages and pores, and calls forth the internal heat, together with the ſpirits and humours by ſweats: whence it follows that the digeſtion is worſe, and the appetite is diminiſhed. The ſame encompaſſing heat alſo humects by accident, whileſt it diffuſes the humours concrete with cold: for thus Venery is thought to humect.

The like may be ſaid of Cold, for that it heats, not by its proper and native, but by an adventitious force: whereof you may make trial in Winter, when as the ambient cold, by ſhutting the pores of the body, hinders the breathing forth and diſſipation of the native heat. Whence it is inwardly doubled, and the concoction better performed, and the appetite ſtrengthened. This ſame Cold alſo dries by accident, when as it by accident repercuſſes the humour that was ready to flow down into any part, and whileſt it concretes that which is gathered in the part: for thus, by the immoderate uſe of repercuſſers, an œdematous tumor proceeding from groſs and viſcid phlegm, degenerates into a *ſcirrhus*.

Drineſs and Moiſture, becauſe they are more paſſive qualities, ſhew their effects by not ſo manifeſt operations, as heat and cold do; but in compariſon of them they are rather to be judged as matter, or a ſubject.

CHAP. IV.

Of the Second Faculties of Medicins.

WE term thoſe the Second Faculties of Medicins, which have dependance upon the firſt, which are formerly mentioned, as it is the part of *Heat* to Rarifie, Attract, Open, Attenuate, Levigate, Cleanſe. Of *Cold*, to Condenſe, Repercuſs, Shut up, Incraſſate, Exaſperate, Conſtipate. Of *Moiſture*, to Soften, Relax. Of *Drineſs*, to Harden, Stiffen.

Hence we term that an attractive Medicin, which hath an attractive faculty, as on the contrary, that a Repercuſſive that repels; a detergent, that which cleanſes viſcous matter. We call that an Emplaſtick Medicin, which not onely ſhuts up the pores of the body, but reduces the liquid bodies therein contained to a certain equality and ſubſtance. Thus alſo Emollients, Relaxers, and the reſt, have their denominations from their effects, as we ſhall declare hereafter.

CHAP. V.

Of the Third Faculties of Medicins.

THe third Faculty of Medicins depends for the moſt part upon the firſt and ſecond Faculties ſometimes conjoined, otherwhiles ſeparate. Alſo ſometimes it follows neither of theſe Faculties, but a certain property and inexplicable quality, which is onely known by experience. Now the operations of this third Faculty are to agglutinate, to fill with fleſh, to cicatrize, to aſſwage pain, to move or ſtay the Urin, Milk, Seed, the Courſes, Sweats, Vomits, and perform ſuch like operations, in or about the body.

Thus the generation of fleſh is produced by the concourſe of two Faculties, that is, of drying and cleanſing. But drineſs and aſtriction produce a glutinating and cicatrizing faculty. A hot and attenuating faculty cauſeth Sweats, moves Urin, the Courſes, and the like in the body; but contrary Faculties retard and ſtop the ſame.

To mitigate pain, proceeds onely from the Faculty, to wit, from heat, or a moderately heating faculty;

faculty to procure reſt, from cold onely, or coldneſs joined with ſome moiſture. But to procure vomit, proceeds neither from the firſt nor ſecond faculty, but from a certain occult and eſſential property, which is naturally implanted in Agarick, and other nauſeous and vomitory Medicins.

CHAP. VI.

Of the Fourth Faculty of Medicins.

The fourth faculty of Medicins depends onely upon an occult property.

THe Fourth Faculty of Medicins is not of the ſame condition with thoſe that are formerly mentioned; for it depends not upon them, or any other manifeſt or elementary quality, but on an occult property of the whole ſubſtance; by means whereof it works rather upon this than that part, upon this rather than that humour. Wherefore Phyſicians cannot by any reaſon find out this faculty, but onely by experience, as we have ſaid a little before of Medicins procuring Vomit. Hence it is that names are given to thoſe Medicins from thoſe parts that they chiefly reſpect: For they are termed Cephalicks which reſpect the Head; as Betony, Marjoram, Sage, Roſemary, *Stœchas*. Pneumonicks, which reſpect the Lungs; as Liquorice, ſweet Almonds, Orris, Elecampane. Cordials, that ſtrengthen the heart; as Saffron, Cinamon, Citrons, but chiefly their Rinds, Bugloſs, Coral, Ivory. Stomachical, which reſpect the Stomach, and the orifice thereof; as Nutmeg, Mint, Aniſe, Maſtick, Pepper, Ginger. Hepaticks, which reſpect the Liver; as Wormwood, Agrimony, Spikenard, Succory, Sanders. Spleneticks, which have relation to the Spleen; as Tyme, *Epithymum*, Broom-flowers, Ceterach, Capers, the Bark of their Roots, the Bark of Tamariſk. Diureticks, ſuch as reſpect the Kidneys and Urinary paſſages; as the Roots of Smallage, Aſparagus, Fennel, Butchers-broom, the four greater Cold Seeds, Turpentine, Plantain, Saxifrage. Arthriticks, or ſuch as ſtrengthen the joints; as Cow-ſlips, *Chamæpitys*, Elecampane, Calamint, Hermodactyls, and the like.

To this Rank may be referred purging Medicins, which, furniſhed with a ſpecifick property, ſhew their efficacy on one Humour more than on another Humour, and that impact more in one part than in another. For thus Agarick chiefly draws phlegm from the Head and Joints, Rhubarb, draws choler chiefly from the Liver, and hurts the Kidneys. But let us here forbear the conſideration of things, as not pertaining to Surgery. But ſome Medicins of this kind are furniſhed with one ſimple faculty, otherſome with more, and thoſe contrary, whereof your taſte may give you ſufficient notice: for Rhubarb at the firſt touch of the tongue is found acrid and hot; but when you come to chaw and throughly to taſte it, you ſhall find it to partake of an earthly aſtriction. Therefore becauſe taſtes give notice of the faculties of Medicins, therefore I have thought good to treat of them briefly.

CHAP. VII.

Of Taſtes.

Lib. 1. *ſimpl.*

TAſte, as *Galen* delivers according to *Ariſtotle* and *Theophraſtus*, is a certain concoction of moiſture in drineſs, cauſed by means of heat, which we know or diſcern by the tongue well tempered, and fittingly furniſhed with ſpittle and his nerves. There are nine differences of taſtes; for there are three judged hot, to wit, the acrid, bitter, and ſalt: three cold, the acid, auſtere, and acerb: three temperate, the ſweet, the oily or fat, and the inſipid. Now they are thought ſo many according to the different degrees of concoction; for it appears greater in hot taſtes, and as it were a certain aſſation; but leſs in cold, but indifferent, and as it were an elixation in things temperate: therefore Nature obſerves this order in the concoction of ſapid bodies, that are the firſt the acerb taſte ſhould take place, then the auſtere, and laſtly the acid: from theſe (as it were) rudiments of concoction, ariſes an inſipid, then an oily, then a ſweet perfectly concocted and temperate. This concoction exceeding the bounds of mediocrity, there ariſes a ſalt taſte, then a bitter, and then an acrid with the higheſt exceſs of almoſt a fiery heat. Yet I would be thus underſtood, that all things that are by Nature ſapid, do not always aſcend to the height of ſweetneſs by the degrees of acerbity, auſterity, and acidity, as though it were of abſolute neceſſity, that all things that are ſweet, ſhould be acerb, auſtere, and acid. For there are many things found, eſpecially in Plants and their Fruits, which when they ſhall arrive to their perfection and maturity, are acid, bitter, or ſalt: but being yet unripe, and not come to full perfection, they have a certain ſweetneſs, which afterwards, by a further digeſtion, or perfection and concoction, acquire a bitter, auſtere, or acid taſte. For thus bitterneſs in Worm-wood and Aloes, acrimony in Pepper or Pellitory, is a perfection of Nature, as full ripeneſs and perfect concoction, and not an exceſs of heat in that *Species*. Alſo acerbity and auſterity is a perfection of Nature, and not a rudiment in Services and Cornelians; acidity or tartneſs is alſo in verjuice. But in very many things it ſo falls out, that the ſweet or fatty taſtes become ſo, and acquire their perfection by concoction, as in Grapes, Figs, Pears, Apples, and almoſt all other ſuch Fruits, as we uſually feed upon. Therefore I will now treat of each of them in order, firſt beginning with cold taſtes.

Differences of taſtes.

The acerb taſte.

The acerb taſte is cold and terreſtrial, and of a ſubſtance abſolutely groſs, being leſs humid then the auſtere, but much leſs than the acid. It notably cools and dries, it condenſates, binds, repels, eſpecially from the ſuperficies, and it alſo exaſperates; this taſte reſides, and may be found in Pomegranate Pills, Galls, Sumach, and Cypreſs-nuts.

The auſtere.

The auſtere is nigheſt in temper and effects to the acerb, but ſomewhat moiſter; for the acerb abſolutely conſiſts in a terreſtrial and cold ſubſtance. Wherefore this, increaſed by a degree of concoction, acquires more ſtore either of heat alone, or elſe of moiſture alone, or elſe of both together: moiſture,

moiſture, I ſay, and that is either Airy or elſe Watery. Therefore if theſe fruits, which before their maturity are acerb, have an acceſſion of heat, then do they become ſweet, as you perceive by Cheſnuts; but if there be an acceſſion of moiſture onely, and that more groſs, of acerb they become auſtere: for both the taſtes are in the like degree of cold, but the auſtere is the moiſter. But if to the ſame frigidity remaining in Fruits, a certain humidity accrew, then is there cauſed an acid taſte. But if they have an acceſſion of a wateriſh moiſture and heat, they will acquire a ſweet taſte, or elſe oily, if the humidity accrewing with the heat be airy.

I have judged it requiſite to admoniſh you hereof, that you might know by what means ſapid bodies mitigated become ſweet of acerb, as it were by theſe interpoſed degrees of auſterity, acidity, and oilineſs, as they acquire a various acceſſion of heat and moiſture ſeparately, or conjunctly.

Now by all that we have delivered, you may gather, that all acerb and auſtere things are cold and dry; and as they are cold, they repel and hinder defluxions: as they are dry and terreſtrial, they condenſate, incraſſate, conſtipate, and ſtraiten the paſſages; yea, and they alſo cicatrize: but acerb things perform this far more powerfully, as thoſe which are abſolutely terrene, cold, and dry, not partaking of moiſture or water. Now auſtere things conſiſt (as it were) in a middle matter, that is, in a more dilute terrene body, as it is apparent in Services, unripe Grapes, Cornelians, Medlars, Crabs, wild Pears, and all ſorts of unripe Fruits, whence it is termed a crude taſte.

The acid taſte is of a cold and wateriſh nature, but moſt ſubtle, by benefit whereof it penetrates and divides almoſt as powerfully as the acrid. It incides or divides, attenuates, bites, cleanſes, opens obſtructions, repels and dries. For by the means of the deep piercing cold, it repels all defluxions; and by the drying faculty, which is ſtrong even in its watery conſiſtence, it ſtays and ſtops all bleedings, the Hæmorrhoids and Dyſenteries. The force thereof is chiefly manifeſt in Vinegar, as alſo in the juice of Citrons, Sorrel, Cherries, Berberries, and the like. And this is the nature of cold taſtes, now it is time we ſpeak of ſuch as are temperate. The acid taſte.

The inſipid is unproperly termed a taſte, as that which is rather a privation of taſte, it is in ſome ſort cold, and of a very wateriſh and groſs nature, it inſpiſſates, conſtipates, and ſtupifies. This kind of taſte is chiefly manifeſt in Water, next in Gourds, Citruls, and many ſuch like things. The inſipid.

The oily taſte is hot, humid, airy; therefore it humects, relaxes, mollifies, lubricates. Of this kind are Oil, Butter, Fat which is not rancid by age, nor acrid by nature, as that of Lions and Foxes. The oily.

The ſweet taſte is made by a moderate and well concocting heat, conſiſting in a matter more tenuious and hot than the inſipid, but in ſomewhat more groſs than the oily, from which in the firſt qualities it doth not differ; therefore it is of a hot, airy, and temperate nature. Therefore every ſweet thing detergeth, levigates, concocts, ripens, relaxes, and aſſwageth pain. Examples of this taſte may be had in Sugar, Hony, Manna, ſweet Almonds, Milk, and other like. Now let us come to hot taſtes. The ſweet.

The ſalt taſte is hot and aſtringent, leſs earthy than the bitter, as that which reſides as it were in a middle matter. For it proceeds from an earthy drineſs, which is formerly torrified and attenuated by the force of heat in a watery humidity. Wherefore that which is ſalt contracts the pores, cuts, cleanſes, digeſts, or rather drics up the humours by the drineſs thereof, without any manifeſt ſenſe of heat, whence it is that it vindicates from putrefaction. Under this kind are contained all ſorts of Salt; as Salt-peter, *niter*, *ſal ammoniacum*, *ſal gemmæ*, common Salt, Sea-water, and ſuch other like. The ſalt.

The bitter taſte is hot, earthy, and drying; for the matter thereof is groſs and earthy, which the abounding heat hath torrified and dried up. Wherefore bitter things taken inwardly, purge and carry away ſuperfluous humours: and outwardly applied, they mundifie and deterge ulcers, they open the mouths and paſſages of the Veins oft-times by their abſtergent faculty, whence it is that they move the Courſes and Hæmorrhoids. The principal things endued with this taſte are Aloes, Gall, Wormwood, Gentian, the leſſer Centaury, Coloquintida, Fumitory, Soot, and ſuch like. The bitter.

The acrid taſte is hot, of a ſubtile and fiery nature; for it is kindled of a hot, ſubtle, and dry matter, neither can it conſiſt in any other. Therefore that which is acrid, heats, pricks, or bites the mouth by acrimony, it heats, and oft-times burns, it penetrates, opens the paſſages, attenuates, attracts and draws forth groſs humours, evacuates and ſends forth Urine, the Courſes, and Sweat: beſides it oft-times is ſeptick, bliſtering, and eſcharotick; and laſtly, burning and cauſtick. The ſeptick and putrefactive things are Sublimate, *Chamælen*, the juice of *Thapſia*. The Veſicatories are Dittander, Cantharides, Crow-foot, Muſtard, Pellitory of *Spain*, Euphorbium. But the cauſtick and eſcharotick are Lime, Oak-aſhes, and the like. The acrid.

But we know Medicins not onely by the taſte, but alſo by our other ſenſes, as Touch, Sight, Hearing, Smell. And as by the Taſte, ſo alſo by theſe we judge of, and try the goodneſs of Medicins, and diſtinguiſh the true legitimate from the adulterate. The Touch judges what are hot and cold, moiſt and dry, rough and gentle, or ſmooth, hard and ſoft, brittle or friable, glutinous and viſcid, drie or ſlippery. We approve of the goodneſs of Medicins by their colour, brightneſs or duskineſs, whereof the eye is judge; for we commend that Senna which is ſomewhat greeniſh, but diſlike the whitiſh: as alſo we like well of ſuch Caſſia as is black both within and without, ſhining and full, and not dry and ſhrunk up. Yet the judgment of the firſt qualities by the colour is deceitful, or none at all; for ſuch things as are white, or the colour of Snow, are not therefore cold: for ſundry of them are hot, as Lime. Neither are red things to be therefore judged hot, for Roſes are cool. Alſo Medicins are choſen by the ſmell; for ſuch as have a good, freſh, and a natural ſmell, are commonly hot, and in their perfect vigor. On the contrary, things that want ſmell, are for the moſt part cold and evanid. By Hearing we diſtinguiſh things full from ſuch as are empty: thus we chuſe Caſſia, which ſhaken, makes no noiſe with the grains or ſeeds ratling in it. Hitherto we have explained the firſt, ſecond, third, and fourth faculty of Medicins in general, and have

ſhewed

ſhewed how they may be found out: now muſt we more particularly treat of their ſecond and third faculties, becauſe by reaſon of thoſe they chiefly come into uſe in Surgery. Yet let me firſt briefly ſhew by what means and arts they may be prepared.

CHAP. VIII.

Of the Preparation of Medicins.

TO prepare Medicins, is nothing elſe, then by Art to make them more commodious for Uſe and Compoſition; whereby they are either made,

More gentle.

By *Bruiſing*; as when Medicins are broken by ſtriking and rubbing or grinding in a Mortar, and that either of Braſs, Iron, Lead, Glaſs, Wood, Marble, and other like; Conſidering the thing which is to be beaten, the ſtrength or force wherewith it muſt be performed, the time or ſpace, the ſituation, the things to be added, the conſiſtence which the thing beaten muſt be of.

More ſtrong.

By *Searſing*; whereby we ſeparate the Purer and Finer from the more Impure and Groſs, which is done by Sieves and Searſes made of Wood, Parchment, Horſe-hair, Silk, Lawn. Wherein is to be noted, that the ſame conſideration is to be had in Searſing, as in beating: therefore ſuch things as are to be finely powdered, muſt be ſearſed in a finer Searſe; ſuch as are more groſs, in a coarſer.

More pleaſant.

By *Diſſolving* or *Mollifying*; which is nothing elſe but a diſſolving of a Simple or a Compound Medicin of a thick or hard conſiſtence, either into a mean conſiſtence, or a little more liquid or ſoft, which is performed either by heat onely, for by heat gums and horns are mollified: or by liquor, as by Vinegar, Water, Wine, Juice of Limmons, &c.

More wholſom.

By *Deſiccation* or *hardning*; which is nothing elſe but the conſuming of the ſuperfluous and hurtful moiſture; and this is performed, either by the Sun, or by Fire. By *Infuſion*; which is nothing elſe but the tempering or macerating of a Medicin a little beaten or cut, in ſome liquor appropriate and fit for our purpoſe; as in Milk, Vinegar, Water, Oil, and the like, ſo long as the nature of the Medicin requires. To Infuſion, Nutrition may be reduced, which is nothing elſe but as it were a certain accretion of the Medicin, by being moiſtned, macerated, rubbed, or ground with ſome moiſture, eſpecially with heat. By *Burning*; that is, by conſuming the humidity which is in them. And that, either that they may be the better powdered, being otherwiſe too glutinous, or that they may lay aſide their groſs eſſence, and become of a ſubtiler temper; or that they may put off, or partly loſe ſome fiery quality, as Acrimony, *Gal. lib. 4. cap. 9. Simplicium.* Or that they may acquire a new colour. Now all things are burnt, either alone; as ſuch things as have a fatty moiſture, as Hairs, ſweaty Wooll, Horns: or elſe with ſome combuſtible matter, as Sulphur, Alum, Salt, Barley, &c.

More fit for mixture.

By *Boiling*, or *Elixation*; which is performed by a humid heat, as burning is by a drie; and that either that we may increaſe the weak faculties of ſuch Medicins as are boiled, by boiling them with ſuch as are ſtronger; or elſe to weaken ſuch as are too ſtrong, or elſe wholly to diſſipate ſuch as are contrary: Or that one faculty may ariſe of ſundry things of different faculties being boiled together, or for the longer keeping them, or bringing them to a certain form or conſiſtence: All which are done, by Fire, or Sun. By *Waſhing* or *Cleanſing*; whereby the impurity of the Medicin is waſted away or cleanſed; and ſuch things are either hard, as Metals, Stones, parts of living Creatures, condenſed Juices, and other like: Or ſoft, as Roſins, Gums, Fats, Oils. And theſe ought firſt to be finely beaten, that the water may penetrate in all their ſubſtance. Or to be diſſolved, and caſt into the Veſſel filled with Water, and ſo ſtirred, and then ſuffered to ſubſide, ſo that the Fat may ſwim aloft. And this muſt be done ſo long that the Water retain nothing thereof in colour, ſmell, or taſte.

CHAP. IX.

Of Repelling or Repercuſſive Medicins.

Aſtringents are underſtood by the name of Repellers.

The differences of Repercuſſives.

REpelling or Repercuſſive Medicins are cold, and of groſs and earthy parts; by which name alſo aſtringent Medicins are underſtood, becauſe they hinder the falling down of the humours upon the part. Repercuſſives are ſuch, either of their nature, and of themſelves, or elſe by accident, being not ſuch of their own nature. Theſe which of themſelves are ſuch, are of two kinds; for ſome are wateriſh and moiſt, without any aſtrictive faculty which almoſt wholly proceeds from an earthy eſſence; wherefore that faculty of Repelling which they poſſeſs, they have it wholly from coldneſs. Of this kind are Lettuce, Purſlain, Sow-Thiſtle, Ducks-meat, Kidney-wurt, Cucumers, Melons, Gourds, Houſe-leek, Mandrake-apples, Night-ſhade, Henbane, and the like, which cool powerfully, and unleſs they be taken away before the part wax blackiſh, they extinguiſh the natural heat. Otherſome are of an earthy eſſence, and therefore aſtrictive; but yet ſome of theſe are hot, otherſome cold. Such things as are cold of temper, and of an earthy conſiſtence, are properly and truly called Repellers. Of theſe ſome are Simple, otherſome Compound: the Simples are Plantain, Vine-leaves, Leaves of Roſes, Oaks, Brambles, Cypreſs,

preſs, Berberies, *Sumach*, all unripe Fruits, Verjuice, Vinegar, red Wine, the juice of ſower Pomgranats, *Acacia*, the Juice of Berberies and Quinces, *Hypociſtis*, Pomgranat Pills, Oak-bark, the Flowers of Wild Pomgranats, the Meal of Barley, Beans, Panick, Oats, Millet, *Orobus* mixed with Juices in form of a Pultis, Bole-armenick, *Sanguis Draconis*, Ceruſs, Litharge, *Terra Sigillata*, Fullers-earth, Chalk, Marl, the Load-ſtone, Lead, Corals, all Marchaſites, Antimony, *Spodium*, true *Pompholyx*, all ſorts of Earth, and other things of the like nature.

Now Compound things are, *Oleum roſaceum, omphacinum, myrtillorum, papaveris, cydoniorum, nenupharis, unguentum roſatum, album rhaſis, camphoratum, emplaſtrum diacalcitheos*, diſſolved in vinegar and oil of Roſes, *deſiccativum rubrum, populeon, emplaſtrum nigrum ſeu tetrapharmacum* of *Galens* deſcription, *empl. contra rupturam, de ceruſa, pro matrice.* All ſuch cold repercuſſives are more effectual if they be aſſociated with tenuity of ſubſtance, either of themſelves, or by mixture with ſome other things: for to this purpoſe we often mix Vinegar, Camphire, and the like things of ſubtil parts, with repercuſſives of groſs parts, that they may ſerve as vehicles to carry in the repercuſſive faculty. Repercuſſives of groſs parts and hot, are Wormwood, Centaury, Gentian, Agrimony, Savin, Coriander, Mint, Bay-leaves, Cardamomes, *Calamus aromaticus*, Aloes, Spikenard, Saffron, Nutmeg, Cinnamon, Amber, Salt, Alum, Coporas, *Sulphur, Oleum abſynthinum, Maſtichinum, Nardinum, Coſtinum, Ceratum, Gal. Stomachicum, Santalinum, Emplaſtrum Diacalcitheos.* But ſuch things as repel by accident, are Bandages, Compreſſers, Linnen cloths, and Rowlers of all ſorts, Caſes, Cauteries, Bloud-letting, Cupping, painful Frictions in the oppoſite parts, and other ſuch like things as are properly ſaid to make revulſion. The uſe of repercuſſives is to force back the humour which flows from any other place into the part, and thus they mitigate the heat of ſuch inflammation as that defluxion of humours hath cauſed, yea, oftimes to aſſwage and help pain, the Fever, Abſceſs, malign ulcers and mortification. Such repercuſſives muſt always be ſo oppoſed to the diſeaſe, that reſpect may be had to the temper, complexion, and particular nature of the part whereto they are applied: for all parts cannot equally bear the like force of repercuſſives, as nervous and other ſpermatick and cold parts. Furthermore there are ſome parts whereunto we may by no means apply repercuſſives, as the groins, arm-pits, and thoſe glandules or kernels which are behind the ears and brain, leſt the humour ſhould retire back into ſome of the principal parts: the like reaſon is alſo of bodies; for the bodies of Women, Children, Eunuchs, cannot endure ſo ſtrong repercuſſives and the like exceſs of cold as the manly and vigorous bodies may. Beſides, every diſeaſe requires not repercuſſives; for if the body be replete with ill humours, if it be plethorick, the uſe of repercuſſives, unleſs after general purgation, cannot be ſafe; as neither if the humour which is in motion ſhall be venenate, groſs, acrid, critical, or ſhall cauſe great pain in the part, for then on the contrary we muſt rather make uſe of attractives. But now if the diſeaſe be great, weak repercuſſives will avail nothing againſt it, as Lettuce againſt a great inflamation; and thou ſhalt do ill if thou ſet upon a ſmall defluxion with powerful repellers; for by that means the skin is ſtraitned, and the paſſages thereof ſtopt, whereby the inflamation is increaſed, or elſe brought to a *ſcirrhus*. Wherefore let the Surgeon have a care that he temper the force of his Repercuſſives according to the magnitude of the diſeaſe.

Why things of ſubtil parts are oft-times mixed with repercuſſives.

Repellers by accident.

When and to what parts repercuſſives muſt be applied.

CHAP. X.

Of attractive Medicins.

AN attractive Medicin is contrary to the repeller; the Greeks call it *Helcticum*, it is of a hot and thin ſubſtance, whereby it draweth forth into the ſuperficies of the body that which lieth hid in the center, although ſometimes it doth it by an occult quality, otherwhiles by accident, as by the acrimony. Thoſe things which by a manifeſt quality do attract, are either Simple or Compound.

What an attractive Medicin is.

The Simple are, *Bryonia, allium, cæpa, porrum, ariſtolochia, hermodactyli, cyclamen, lilium, ſigillum beatæ Mariæ, arum, aſarum, aſphodelus, gentiana, pyrethrum, ruta, ſabina, calamentum, omnes tithymallorum ſpecies, viſcum, abrotonum, anagallis, urtica, ranunculus, ſtruthium*, and ſuch like; *Ammoniacum, bdellium, galbanum, ſagapenum, euphorbium, aſphaltum, cinis è fœce vini vel aceti, calx viva, ſulphur, ſal ammoniacus, omnis ſalis ſpecies, auripigmentum, oleum vetus, adeps leonis, urſi, canis, anſeris, viperæ, ranarum, axungia porci, vetuſtate acris, aut attritu rotarum. Compoſita vero, ut oleum de ſpica, philoſophorum, de terebinthina, de croco, de ſcorpionibus, rutaceum, vulpinum, laurinum, anethinum, de vitriolo, unguentum Agrippæ, aragon, ſeu auxiliare, martiatum, enulatum, theriaca, mithridatum, empl. de meliloto, diachilon magnum & parvum, oxycroceum, divinum.*

Attractives by a manifeſt quality.

Thoſe things which draw by a ſecret property in Nature, as are the Load-ſtone, Quick-ſilver, Piony, Amber, all Antidotes and Triacles that are remedies againſt the bitings of venomous Beaſts, and all purging Medicins.

By an occult.

Thoſe which draw by accident, perform it otherwiſe than of their own Nature; they have that quality out of putrefaction and corruption, as Doves dung, Goats dung, Cows dung, Mans dung, and all kind of dungs: alſo Leven, old Cheeſe, and ſuch like.

By accident.

Cupping-glaſſes, Leeches, Syringes, rougher and harder Frictions, Sucking, Pain, ſtraight Ligations, Cauteries, do alſo draw, but after a different manner from them ſpoken of before.

Attractive Medicins muſt neither burn nor diſcuſs, and being very ſtrong and ſharp, they ſhould be tempered and mixed with Oil of Roſes, and other lenitives: but to weak ones ſhould be added Oil of Bays, *Calx viva*, and ſuch like to ſtrengthen them. The uſe of attractives is to draw poiſon toward the skin, and to haſten forward critical abſceſſes; and they make thoſe parts which are benummed and conſumed, to have life; they reſtore the refrigerated parts by drawing thither the ſpirits, they draw forth the viſcous filth of malign ulcers that lies hid in the nerves and hollow paſſages of them; they alſo draw out ſcales of bones, ſplinters of wood, nails, thorns, arrows, and that matter which is impact in hardned inflamations.

Their uſe.

CHAP.

CHAP. XI.

Of reſolving Medicins.

What a Reſolving Medicin is. The differences thereof.

THat is called a reſolving Medicin which by heat, and the tenuity of his ſubſtance openeth the pores, attenuates the humours, diſſipates and diſcuſſeth by evaporating the unprofitable matter. There are two ſorts of theſe kinds of Medicins, the one is called *Araeoticum*, or rarifying, the other is termed *Diaphoreticum*, or digeſting.

The *Araeoticum* by a mean heat, and not dry, and indued with a tenuity of ſubſtance, openeth and relaxeth the skin, and draweth forth the matter ſhut up under it, whereby it may eaſe pain, like as Anodynes, becauſe it doth not much depart from a temperate heat.

But the *Diaphoreticum* being much hotter, whatſoever ſticketh in the part being there impact, it doth by thin vapour inſenſibly diſſipate: therefore the acrid and hot things are in this caſe to be made uſe of rather than attractives, becauſe that cold and groſsneſs is more difficultly to be digeſted, and the length and involution of the ways being to be conſidered. The *Araeotick*, which we may call weak Reſolvers, are either Simple or Compound.

The Simples are theſe, *Biſmalva tota, parietaria, adianthum, mercurialis, ebulus, valeriana, roſmarinus, ſalvia, thymus, chamæmelum, melilotum, anethum, farina hordei, tritici, ſeminis lini, fœnugræci, nigella, furfur, adeps gallinæ, anſeris, anatis, cuniculi, vituli*; almoſt all Metals unleſs ſuch as are acrid. The Compounds are, *Oleum chamæmolinum, anethinum, liliaceum, catellorum, lumbricorum, Keirinum, de vitellis ovorum, de tritico, amygdalarum dulcium, unguentum de althæa, empl. diachylum, ireatum.* Diaphoreticks or digeſtives, are alſo both Simple and Compound: The Simple are *Ariſtolochia, enula campana, iris, cæpa ſcyllæ, ſigillum Salomonis, ſigillum Beatæ Mariæ, bryona, panis porcinus, dracunculus, aſphodelus, origanum, mentha, pulegium, ſabina, ſerpillum, calamentha, hyſſopus, urtica, artemiſia, lavendula, chamæpitys, aniſum, fœniculum, cuminum, piper, nux moſchata, coriandrum, baccæ lauri & juniperi, farina fabarum, lupinorum, orobi, milii, frumenti, furfur, mica panis, acetum tepidum, oxycratum, vinum vetus aut aromaticum, mel, aqua vitæ, muria, adeps tauri, equi, leonis, canis, hirci, medulla cervi, cruris bovis & arietis, ammoniacum, galbanum, opopanax, ſagapenum, myrrha, bdelium, thus, terebinthina, pix nigra, ladanum, ſtirax, calamita, benjoinum, ſtercus caprinum, columbinum, caninum, bubulum, & aliæ ſtercorum ſpecies.* Compound Diaphoreticks are, *Oleum amygdalarum amararum, juniperinum, laurinum, de ſcorpionibus, irinum, coſtinum, nardinum, de terebinthina, de croco, canabinum, raphaninum, è cucumere agreſti, vulpinum, rutaceum, philoſophorum, de lateribus, de euphorbio, de tartaro, de petroleo, de kerva, ſive recininum unguent. Arippæ, aragon, martiatum, enulatum, empl. de Vigo,* without addition, and with addition, *oxycroceum, diacalcitheos,* diſſolved in a digeſting oil to the form of a cerot.

Araeoticks are profitably uſed in the increaſe and ſtate of ſuperficial tumours.

The uſe of Diaphoreticks

But *Diaphoreticks* are not to be uſed in the increaſe of tumours, unleſs ſome aſtringent be added, leſt by their more ſtrong digeſtion, they ſhould draw and increaſe the defluxion: but when the tumors decline, they are then onely to be uſed in the parts chiefly where the skin is denſe and hard, and when the tumor is cold and groſs, and lying hid deep in the body, ſo that the virtue of Medicaments can hardly come thereto: but conſideration is to be had of the parts to which reſolutives are to be applied; for you may not apply Relaxers or Diaphoreticks to the Liver, Spleen, Stomach, or Bowels, unleſs you add ſome aſtringents, of which a great part muſt be Aromaticks.

To the parts where ſenſe is more dull, may be applied the ſtronger Diaphoreticks; but thoſe parts which are endued with a more exquiſite ſenſe, as the Eye and the Nerves, to them we muſt apply weaker. When the matter is groſs and cold, things cutting and attenuating, and then emollient are to be uſed, and ſo by degrees come to diaphoreticks; otherwiſe that onely is reſolved which is the moſt ſubtil of unprofitable matter, the groſſer becoming concrete and hardned. But if the part be afflicted with a continual defluxion, ſo that there may be danger of a Gangrene or Sphacel, it is not lawful then to make uſe of Reſolvers, but you muſt in the place where the humour flows, divide the skin by ſcarification, as it is moſt learnedly noted by *Hollerius*, in that profitable Book of his left to poſterity, whoſe Title is, *De Materia Chirurgica.*

CHAP. XII.

Of Suppuratives.

What a Suppurative Medicin is.

A Suppurative Medicin is ſaid to be that, which ſhutting the pores, and preventing tranſpiration by his emplaſtick conſiſtence, increaſeth the matter and native heat, and therefore turneth the matter caſt out of the Veſſels into *pus* and *ſanies*. It is of nature hot and moiſt, and proportionable to the native heat of the part to which it is applied, and of an emplaſtick conſiſtence, that ſo it may hinder the native heat from being exhaled; in which reſpect it differeth from emollients and malacticks, of which we ſhall ſpeak hereafter. There be two kinds of Suppuratives: for ſome do it of themſelves, and by their proper quality; others by accident. Thoſe things which by their own ſtrength do bring to ſuppuration, are either Simples or Compounds.

Differences of Suppuratives.

Simples are, *Radix liliorum, cæpa, allium, malvarum omnium folia & ſemina, bugloſſum, acanthus, ſenecio, violæ, parietaria, crocus, caules, ficus, paſſulæ mundatæ,* with a decoction of theſe things, *farina tritici, farina volatilis, farina hordei excorticati, lolii, ſeminis lini & fœnugræci, galbanum, ammoniacum, ſtyrax pinguis, ladanum, viſcum aucupatorum, thus, pix, cera, reſina, colla, adeps ſuillus, vitulinus, vaccinus, caprinus, butyrum, vitellus ovi, æſipus humida, ſtercus ſuillum, columbinum, caprinum, pueri.* Compounds are, *Oleum liliorum, lumbricorum, de croco, unguent. baſilicum, emplaſt. diachilon commune, magnum, de mucilaginibus.*

Suppuratives by accident.

Thoſe things do ſuppurate by accident, which work it onely by the means of an Emplaſtick conſiſtence

ſtence: for ſo oft-times aſtringents, becauſe they are of earthy and thick parts, are found to ſuppurate; ſuch are *unguentum de bolo nutritum*, and ſuch like. Such alſo are thoſe which by their coldneſs keep the heat in, and ſhut the pores. Hence it is that the qualities of Sorrel are commended to generate *pus*: for whileſt it keepeth the heat within, it increaſeth his effects, to the thickning of the ſuppurable matter, and the overcoming other rebellious qualities. We uſe things ripening in great inflammations, whoſe growth we cannot hinder with Repellers, or increaſe with Reſolvers or Diſcuſſers.

CHAP. XIII.

Of Mollifying things.

THat is defined to be a mollifying Medicin, which by a ſtronger heat than that which is proper to ſuppuratives, without any manifeſt quality of drying or moiſtning, again malaxeth or ſofteneth hardned bodies: wherefore this differs from that which ſuppurates, becauſe that they be hot in the firſt or ſecond degree, according to the ſeveral tempers of the body, or part to which it is applied, working rather by the quantity of heat, than the quality; contrariwiſe, that which mollifieth being indued with a greater heat, rather worketh by the quality of the heat, being otherwiſe in drineſs and moiſture temperate. *Gal. cap. 7. lib. 5. ſimp.* How Suppuratives and emollients differ.

Although as many things agree together in ſome reſpects, though of a diverſe nature, ſo many emollients are ſuch as are hot in the firſt degree, and drie in the ſecond and third, that ſo they may the better diſperſe and diffuſe that which is congealed, by taking away a little of the humidity, which is contained within the part affected: but not by exhauſting it wholly by the violence of heat or drineſs: for hereon would follow a greater hardneſs.

Things mollifying, are either Simple or Compound, and thoſe again ſtrong or weak. The weak are, *Radix liliorum alborum, cucumeris agreſtis, althææ, folia malvæ, biſmalvæ, liliorum, anethi ſummitates, viola, branca urſina, ſemen malvæ, biſmalvæ, lini, fœnugræci, carici pingues, paſſulæ mundatæ, pedum, capitum, inteſtinorum vervecinorum decoctum, adeps ex junioribus & caſtratis, domeſticis, fœminis animalibus, adeps, ſuillus, vitulinus, hœdinus, caprinus, bubulus, vulpinus, gallinaceus, anſerinus, anatinus, olorinus, efficaces.* The weaker are things more gentle; as, *Butyrum, lana ſuccida, cera pinguis, vitellus ovi, medulla ex oſſibus, cervina, ovilla, caprina.* The compound are oil, wherein are boiled mollifying herbs; as, *Oleum liliorum, chamæmelinum, amygdalarum dulcium.* Stronger emollients are, *Aceetum, adeps taurinus, urſinus, cervinus, leoninus, pardalinus, apri, equi ſevum, pinea, picea, abietina, terebinthina, ammoniacum, bdelium, ſtyrax, galbanum, ladanum, propoli, opopanax, ung. de althæa, emp. diachylon commune & magnum, de mucilaginibus, ceroneum, oxyceroeum Joannis de Vigo.* The differences of emollients.

We uſe emollients in ſcirrhous tumours of the muſcles, or in the lips of Ulcers, in any of the limbs, belly, glandules, bowels, by reaſon of a groſs, cold, and viſcous matter, either phlegmatick or melancholick. Yet thoſe tumors which come of melancholy, commonly turn to Cancers, which are exaſperated by mollifying things. On the contrary, ſuch as proceed from a phlegmatick matter, are brought to an equality of conſiſtence, by the uſe of emollients. Furthermore, there are three things obſervable in the uſe of emollients: the firſt is duly to conſider how much the affected part differs from his proper and natural temper and proportion, that ſo we may apply an equivalent remedy. The ſecond is, that we diſtinguiſh the natures of the parts. The third is, that we artificially gather after what manner this mollifying muſt be performed; that is, whether we ſhould mingle with the emollients deterſive or diſcuſſing Medicins. For there are many deſperate ſcirrhous tumours, that is, ſuch as cannot be overcome by any emollient Medicin, as thoſe which are grown ſo hard, that they have loſt their ſenſe; and thereupon are become ſmooth and without hairs. Here you muſt obſerve that the part ſometimes becomes cold in ſo great an exceſs, that the native heat plainly appears to languiſh, ſo that it cannot actuate any Medicin. That this languiſhing heat may be reſuſcitated, an iron ſtove ſhall be ſet near to the part, wherein a good thick piece of iron heated red hot ſhall be encloſed, for ſo the Stove will keep hot a long time. Their uſe. Things obſervable in the uſe of emollients.

The Figure of an iron Stove.



A *The caſe of the Stove.*
B *The iron Bat to be heated.*
C *The lid to ſhut the Stove.*

CHAP. XIV.

Of Deterſives, or Mundificatives.

A Deterſive is defined to be that which doth deterge or cleanſe an ulcer, and purge forth a double kind of excrement; of the which one is thicker, which is commonly called *ſordes*, which is drawn forth from the bottom of the ulcer, by the efficacious quality of the Medicins; the other is more thin and watery, which the Greeks call *Ichor*, the Latins *Sanies*, which is taken away by the drineſs of the Medicin; and therefore *Hippocrates* hath well adviſed that every ulcer muſt be cleanſed and dried.

Deterſives. Of Deterſives, ſome are ſimple, ſome compound, ſome ſtronger, ſome weaker. The ſimple are either bitter, ſweet, or ſowre: the bitter are *Gentiana, Ariſtolochia, iris, enula, ſcylla, ſerpentaria, centaurium minus, abſynthium, marrubium, perforata, abrotonon, apium, chelidonium, ruta, hyſſopus, ſcabioſa, artemiſia, eupatorium, aloe, fumus terræ, hedera terreſtris*; a *Lixivium* made with the aſhes of theſe things, *Lupini, orobus, amygdala amara, faba, terebinthina, myrrha, maſtiche, ſagapenum, galbanum, ammoniacum*, the galls of Beaſts, *ſtercus caprinum, urina bene cocta, ſquama æris, æs uſtum, ærugo, ſcoria æris, antimonium, calx, chalcitis, miſy, ſory, alumen*. The ſweet are *Viola, roſa, melilotum, ficus pingues, dactyli, uvæ paſſæ, glycyrrhiza, aqua hordei, aqua mulſa, vinum dulce, mel, ſaccarum, ſerum lactis, manna, thus*. The ſharp are all kind of ſowre things, *Capreoli vitium, acetum*, and other acid things. The Compound are, *Syrupus de abſynthio, de fumaria, de marrubio, de eupatorio, de artemiſia, acetoſus, lixivium, oleum de vitellis ovor. de terebinthina, de tartaro, unguentum mundificativum de apio, apoſtolorum, pulvis mercurialis*. We uſe

Their uſe. ſuch things as deterge, that the ſuperfluous matter being taken away, Nature may the more conveniently regenerate fleſh to fill up the cavity: But in the uſe of them, conſideration is firſt to be had of the whole body, whether it be healthy, plethorick, or ill diſpoſed; there is conſideration to be had of the part, which is moiſter and drier, indued with a more exquiſit or duller ſenſe. But oft-times acidents befal ulcers beſides nature, as a *Callus*, a defluxion of a hot or otherwiſe malign humour, and the like ſymptoms. Laſtly, conſideration is to be had, whether it be a new or inveterate ulcer; for from hence, according to the Indication, remedies are appointed different in quantity and quality: ſo that oft-times we are conſtrained to appoint the bitter remedy in ſtead of the ſweet. Neither truly with a painful and drie ulcer doth any other than a liquid deterſive agree: neither to be moiſt any other than that of a drie conſiſtence, as Powders.

CHAP. XV.

Of Sarcoticks.

No Medicin truly Sarcotick. THat Medicin is ſaid to be Sarcotick, which by its drineſs helps Nature to regenerate fleſh in an ulcer, hollow, and diligently cleanſed from all excrements. But this is properly done by bloud indifferent in quality and quantity. Wherefore, if we muſt ſpeak according to the truth of the thing, there is no Medicin which can properly and truly be called ſarcotick: For thoſe which vulgarly go under that name, are onely accidentally ſuch; as thoſe which without biting and eroſion, do drie up and deterge the excrements of an ulcer, which hinder the endeavour of Nature in generating of fleſh. For as by the Law of Nature, from that nouriſhment which flows to the nouriſhing of the part, there is a remain, or a certain thin excrement, flowing from ſome other place, called by the Greeks *Ichor*, and by the Latins *Sanies*. Thus by the corruption of the part there concretes another groſſer excrement, termed *Rypos* by the Greeks, and *Sordes* by the Latins. That makes the ulcer more moiſt, this more filthy. Hence it is, that every wound which requires reſtitution of the loſt ſubſtance, muſt be cured with two ſorts of Medicins, the one to drie up and waſte the ſuperfluous humidity thereof, the other to fetch off the filth: and by how much the wound is the deeper, by ſo much it requires more liquid Medicins, that ſo they may the more eaſily enter into every part thereof.

But diverſity of things ſhall be appointed according to the various temper of the part. For if the affected part ſhall be moiſt by Nature, ſuch things ſhall be choſen as ſhall be leſs drie: if on the contrary the part be drie, then ſuch things ſhall be uſed as be more drie; but many ſorts of Medicins ſhall be aſſociated with the ſarcoticks, according to the manifold complication of the affects poſſeſſing the ulcer. Therefore Nature onely is to be accounted the Workmaſter, and the efficient cauſe in the regenerating of fleſh, and laudable bloud the material cauſe, and the Medicin the helping or aſſiſting cauſe, or rather the cauſe without which it cannot be: as that by cleanſing and moderately drying without any vehement heat, takes away all hinderances of incarnation, and orders and fits the bloud to receive the form of fleſh. This kind of Medicin according to *Galen*, ought to be drie only in the firſt degree, leſt by too much drineſs it might drink up the bloud and matter of the future fleſh, which notwithſtanding is to be underſtood of Sarcoticks which are to be applied to a delicate and temperate body. For if the ulcer be more moiſt, or the body more hard than is fit, we may aſcend to ſuch things as are drie even in the third degree. And hence it is that ſuch drie Medicins may firſt be called Deterſives, and then preſently Sarcoticks. A Sarcotick Medicin is either ſimple or compound, ſtronger or weaker. Simple Sarcotick Medicins are,

Simple Sarcoticks. *Ariſtolochia utraque, iris, acorus, dracunculus, aſarum, ſymphyti omnia genera, betonica, ſanicula, mellifolium, lingua canis, verbena, ſcabioſa, pimpinella, hypericon, ſcordium, plantago, rubia major & minor, eorumque ſucci. Terebinthina lota & non lota, reſina pini, gummi arabicum, ſarcocolla, maſtiche, colophonia, manna, thuris, cortex ejuſdem, aloe, olibanum, myrrha, mel, vinum, ſanguis draconis, lithargyros, auri, ſpodium, pompholyx, tutia, plumbum uſtum lotum, ſcoria ferri*. The Compound

Compound Sarcoticks. Sarcoticks are, *Oleum hypericonis, ol. ovorum, maſtichinum, & cætera olea, quæ balſami nomine appellantur, unguentum aureum, emp. de betonica, Vigonis de janua, Emp. Gratia Dei, nigrum*. We uſe not Sarcoticks

before

before that the ulcer be cleanſed and freed from pain, defluxion, inflammation, hardneſs, and diſtemper. In uſing theſe things we conſider the temper of the body, and the affected part: For oftimes a part otherwiſe leſs dry by nature, requires a more powerful drying medicine, and ſtronger ſarcotick, than another part which is more dry, and this for ſome other reaſon, which ought to come into our conſideration: For example, the glans would be more dried than the prepuce, although it be of a temper leſs dry, becauſe it is the paſſage of the urine. Wherefore we muſt diligently obſerve the condition of the affected parts, and thence taking indication, make choice of more ſtrong ſarcoticks. Foth both that which is too little, and that which is too much ſarcotick, makes a ſordid ulcer: the firſt becauſe it dries not ſufficiently; the latter for that by its acrimony it cauſeth defluxion. Therefore diligent care muſt be uſed in the examination hereof.

CHAP. XVI.

Of Epuloticks, or ſkinning medicines.

AN Epulotick medicine is that which covereth the part with skin: it is ſaid to be ſuch as by drineſs and aſtriction without biting deſiccates, binds, and condenſates the fleſh into a certain callous ſubſtance, like to the skin, which we commonly call a cicatrice or ſcar: yet this, as the generating of fleſh, is the work of nature. A medicine therefore is ſaid to be Epulotick, for that it aſſiſts nature in ſubſtituting and generating a ſcar, in ſtead of the true skin, whilſt it conſumes the ſuperfluous humidities, condenſates, incraſſates, and binds the next adjacent fleſh: therefore it ought to dry more powerfully than a ſarcotick. Epulotick medicines are of three kinds: the firſt is the true epulotick, which onely dries and binds. The ſecond is an acrid and biting epulotick, which, for that it waſtes the proud fleſh, is called ſo; and this muſt be ſparingly uſed, and that only to hard and ruſtick bodies. The third is that which only dries without aſtriction. The things whereof they conſiſt are theſe: *Ariſtolochia utraque, gentiana, iris, centaurium majus, pentaphyllon, ſymphytum majus, chamædrys, betonica, cauda equina, cupatorium, verbenaca, plantaginis & ſymphyti folia, gallæ, baccæ myrti, glandes & earum calices, balauſtia, cupreſſi nuces, malicorium, cortex quercus, cortex tamaricis, cortex ligni aloes, acacia, colophonia, ſarcocolla, ſanguis draconis, ladanum, lithargyros auri, argenti, ceruſa, plumbum uſtum, alumen uſtum, tuthia, ſquamma æris & ferri, & eorum ſcoria, ærugo, flos æris, æs uſtum & lotum, ſulphur vivum, chryſocolla, corali, bolus armenus, terra ſigillata, cineres buccinarum, oſtreorum, ſilicis, oſſa uſta & ſiccata, caries lignorum, ung. diapompholygos, ung. alb. rhaſis, deſiccativum rubrum, emp. de ceruſa, de betonica, diacalcitheos, emp. nigrum.* Three ſorts of Epuloticks.

We uſe Epuloticks when as the ulcer is almoſt filled up, and equal to the adjacent skin. In the uſe of theſe we muſt alſo have reſpect to the tenderneſs and hardneſs of the body; for ſuch things as are corroſives to tender and delicate bodies, are epulotick to hard and ruſtick bodies. Alſo we muſt have regard, whether the body be plethorick, or replete with ill humours, for ſuch do not eaſily admit cicatrization. Alſo it is moſt worthy of your obſervation, to mark whether the ulcer that is to be cicatrized be fed or nouriſhed by the preſent defect of any part, as the liver, ſpleen, lungs, or a *varix* lying about it. for it cannot be cicatrized before theſe impediments (if any ſuch be) be taken away. Laſtly, the callous lips of an ulcer, unleſs they be ſcarified or ſoftened, hinder cicatrization. Therefore all ſuch defaults muſt be taken away, and then ſuch an epulotick applied, as may not by the too much drineſs leave the ſcar too hollow, or the too little, leave it too high. Their uſe.

CHAP. XVII.

Of Agglutinatives.

AGglutinating or agglutinative medicine is of a middle nature, between the ſarcotick and epulotick, more ſtrong than the former, and weaker than the latter, for it is dry to the ſecond degree. It by the drying and aſtrictive faculty, void of all deterſion, conjoins parts parts that are diſtant, or rather lends helping hands to nature the principal agent in this work. Glutinatives, whether they be ſtrong or weakly ſuch, do agglutinate either by their proper or accidental nature: Of this ſort are *Plantaginis omnes ſpecies, conſolida utraque, bugloſſa, millefolium, verbena, pimpinella, piloſella, cauda equina, ſempervivum, telephium, ſanicula, attractilis, folia quercus & dracunculi, ſalix, ebulus, ſambucus, pentaphyllon, veronica, cortex pini, ulmi, palmæ quercus. Aqua vitis, aq. e folliculis ulmi, ſuccus calaminthæ, vinum auſterum, terebinthina, myrrha, ſanguis draconis, bolus armenus, terra ſigillata, omnia denique acerba.* Agglutinative medicines.

Glutinatives by accident are thoſe that hinder defluxion, and bind the part, as Sutures, Bandages, Reſt, Rowlers, and the like. We uſe glutinative in green, and as yet bloudy wounds, whence the Greeks call a glutinative medicine *Enæma*, although ſometimes they are uſed to inveterate, malign, fiſtulous and ſinuous ulcers; for they hinder the defluxion from coming to the lips of ulcers. You muſt conſider, when as you intend to apply them, whether the skin be whole or no: For ulcers knit together, or heal more difficultly, if the skin be rubbed off, or cut, or otherwiſe loſt. Neither ought you to be unmindful of the forementioned cautions and indications drawn from the ſex, the tenderneſs or hardneſs of the affected body, the continuance and magnitude of the ulcer: for hence indication muſt be taken, what the quantity and quality of the medicin ought to be. Glutinatives by accident.

CHAP. XVIII.

Of Pyroticks, or cauſtick Medicines.

Three degrees of Cauſticks.

THat medicine is ſaid to be Pyrotick or Cauſtick, which by its acrimony and biting, commonly conſiſting in an earthy conſiſtence, either ſuperficially corrodes, or more deeply eats and putrefies, or laſtly, burns and conſumes the skin and fleſh, ſo that it even pierces into callous and hard bodies. Therefore there are three degrees of Pyroticks; for ſome are termed Cathereticks or corroding, for that they waſte the proud fleſh of an ulcerated or any other part, and theſe are judged the weaker ſort of the Pyroticks. Otherſome are termed Septick or putrifying, as thoſe which deſtroy and diſſolve the tender and new ſprung up fleſh, and raiſe bliſters in the skin, and theſe are more powerful than the cathereticks. Laſtly, there are otherſome termed moſt powerful Eſcharoticks, which by their fiery and terreſtrial quality cauſe eſchars or cruſts; whereupon they are alſo termed *Ruptoria*, and potential Cauteries: Now all theſe differences are taken from that they are more or leſs powerful, for it oft-times happens, that according to the different temper and conſiſtence of the parts, according to the longer or ſhorter ſtay, a Catheretick may penetrate as far as a Septick, and on the contrary, an Eſcharotick may enter no farther than a Septick. Theſe are judged

Cathereticks. Catheretick, *Spongia uſta, alumen uſtum & non uſtum, vitriolum uſtum, calx mediocriter lota, æruga, chalcanthum, ſquamma æris, oleum de vitriolo, trochiſci andronis, phaſionis, aſphodelorum, ung. Ægyptiacum, apoſtolorum, pulvis mercurii, arſenicum ſublimatum.*

Septicks and Veſicatories. Septicks and Veſicatories are, *Radix ſcillæ, bryoniæ, ſigill. beatæ Mariæ, bugloſſa, radix ranunculi, panis porcini, apium, riſus, lac tithymallorum, lac fici, euphorbium, anacardus, ſinapi, cantharides, arſenicum ſublimatum:* For all theſe weaken the native temper and conſiſtence of the part, and draw thereunto humors plainly contrary to nature.

Eſcharoticks. Their uſe. Eſcharoticks or Cauſticks are, *Calx viva, fæx vini cremata & præcipue aceti, ignis*, whereto are referred all Cauteries, as well actual as potential, whereof we ſhall treat hereafter. We uſe Cathereticks in tender bodies, and diſeaſes not very contumacious; therefore by how much they are leſs acrid and painful, by ſo much oft-times they penetrate the deeper, for that they are leſs troubleſome by delay; but we uſe Septicks, and ſometimes Eſcharoticks in ulcers that are callous, putrid, and of inexhauſted humidity, but principally in Cancers, Carbuncles, and exceſſive Hæmorrhagies. When as we make uſe of theſe, the patient muſt have a convenient diet appointed, muſt abſtain from wine: laſtly, they muſt not be uſed but with great diſcretion; for otherwiſe they may cauſe Feavers, great inflammations, intolerable pains, Swounings, Gangrenes, and Sphacels. Cauteries heedfully uſed, ſtrengthen and dry the part, amend an untameable diſtemper, dull the force of poyſon, bridle putrefaction and mortification, and bring ſundry other benefits.

CHAP. XIX.

Of Anodynes, or ſuch as mitigate or aſſwage pain.

What pain is.

BEfore we treat of Anodyne medicines, we think it fit to ſpeak of the nature of pain. Now pain is a ſorrowful and troubleſome ſenſe, cauſed ſome ſudden diſtemper, or ſolution of continuity. There are three things neceſſary to cauſe pain; The efficient cauſe, that is, a ſudden departure from a natural temper or union; the ſenſibleneſs of the body receiving the dolorifick cauſe: laſtly, the apprehenſion of this induced change, cauſed either by diſtemper or union; for otherwiſe with how exquiſite ſoever ſenſe the body receiving the cauſes indued with, unleſs it apprehend and mark it, there is no pain preſent. Hence is that Aphoriſm of *Hippocrates*, *quicunq; parte aliqua corporis dolentes dolorem omnino non ſentiunt, his mens ægrotat*, that is, Whoſoever pained in any part of their bodies do wholly feel no pain, their underſtanding is ill affected and depraved. Heat, cold, moiſture, and drineſs, induce a ſudden change of temper; and heat and cold cauſe ſharp pain, drineſs moderate, but moiſture ſcarce any at all: for moiſture cauſeth not pain ſo much by its quality, as it doth by the quantity. Both the forementioned qualities, eſpecially aſſociated with matter, as alſo certain external cauſes too violently aſſailing, ſuch as theſe that may cauſe contuſion, cut, prick, or too much extend. Wherefore pain is a ſymptom of the touch, accompanying almoſt all diſeaſes; therefore oft-times leaving theſe, they turn the counſel of the Phyſician to mitigate them, which is perfórmed either by mitigating the efficient cauſes of pain, or dulling the ſenſe of the part. Hereupon they make three differences of Anodynes: For ſome ſerve to cure the diſeaſe, otherſome to mitigate it, otherſome ſtupifie, and are narcotick. We term ſuch curative of the diſeaſes, which reſiſt, and are contrary to the cauſes of diſeaſes. Thus pain, cauſed by a hot diſtemper, is taken away by oil of Roſes, Oxycrate, and other ſuch like things, which amend and take away the cauſe of pain, to wit, the exceſs of heat. Pain cauſed by a cold diſtemper, is amended by *Oleum Laurinum, Nardinum, de Caſtoreo.* Pain occaſioned by two much drineſs, is helped by *Hydrelæum*, a bath of freſh and warm water. Laſtly, by this word Anodyne, taken in the largeſt ſenſe, we underſtand all purging medicines, Phlebotomy, Scarification, Cauteries, Cuppings, Glyſters, and other ſuch like things as evacuate any ſtore of the dolorifick matter.

What properly termed Anodynes are. But ſuch as are properly termed Anodynes, are of two ſorts: for ſome are temperate, others hot and moiſt in the firſt degree, and conſequently near to thoſe that are temperate: theſe preſerve the native heat in the proper integrity, thus they amend all diſtemperatures; of this kind are accounted Sallad oil, oil of ſweet Almonds, the yolks of eggs, and a few other ſuch like things, theſe ſtrengthen the native heat, that thus increaſed in ſubſtance, it may with the more facility overcome the cauſe of pain: beſides alſo, they rarifie, attenuate, digeſt, and conſequently evacuate both groſs and viſcid humors, as alſo cloudy flatulencies hindred from paſſing forth: ſuch are *flores chamæmeli, meliloti, crocus, oleum chamæmelinum, anethinum, oleum lini, oleum ex ſemine altheæ, lumbricorum, vorum, ex tritico, butyrum, lana ſuccida, ſuillus adeps, vitulinus, gallinaceus, anſerinus, humanus, ex anguilla enticula,*

cunicula, & aliis. Lac mulierbre, & vaccinum, mucago ſeminis lini, fœnugræci, althææ, malvæ, vel ejuſmodi ſeminum decoctum: as alſo *Decoctum liliorum, violariæ, capitis, pedum, & inteſtinorum arietis & hœdi.*

Narcoticks, or ſtupefying medicines, improperly termed Anodynes, are cold in the fourth degree, therefore by their exceſs of cold, they intercept or hinder the paſſage of the animal ſpirits to the part, whence it is that they take away ſenſe: of this ſort are *hyoſcyamus, cicuta, ſolanum manicum, mandragora, papaver, opium, arctiſſima vincula.* Narcotick improperly termed Anodynes.

You may make uſe of the firſt ſort of Anodynes in all diſeaſes, which are cured by the oppoſition of their contraries: but of the ſecond, to expugn pains that are not very contumacious, that by their application we may reſiſt defluxion, inflammation, the feaver, and other ſymptoms. But whereas the bitterneſs of pain is ſo exceſſive great that it will not ſtoop to other medicines, then at the length muſt we come to the third ſort of Anodynes. Yet oft-times the bitterneſs of pain is ſo great, that very narcoticks muſt be applied in the firſt place, if we would have the part and the whole man to be in ſafety. Yet the too frequent uſe of them, eſpecially alone without the addition of ſaffron, myrrh, *caſtoreum*, or ſome ſuch like thing, uſeth to be very dangerous: for they extinguiſh the native heat, and cauſe mortification, manifeſted by the blackneſs of the part. But intolerable pains, to wit, ſuch as are occaſioned by the exceſs of inflammation and gangrenes, may be ſooner mitigated by opening a vein, purging and ſcarifying the part affected, than either by properly termed anodynes or narcoticks, to wit, that pain may be the remedy of pain. By purgers we here underſtand not only ſuch as taken by the mouth, produce that effect; but alſo ſuch as outwardly applied perform the ſame, as thoſe whereof *Aetius* makes mention, As The uſe of them.

℞. *Pulpæ ſeu medul. colocynth. ſemin. eruc. rut. ſylveſt. elaterii, gr. cindii, lathyrid. expurgatar. galban. nitri, ceræ, ſingulorum,* ℥iv. *opopan.* ℥ij. *terebinth.* ℥vj. *terenda terito, & taurino felle paulatim irrigato, donec apte imbibantur.* Then apply it about the navel even to the ſhare, for thus it will purge by ſtool; if on the contrary you apply it to the bottom of the ſtomach, it will cauſe vomit. Another; ℞. *elaterii* ℥iij. *colocynth. ſquammæ æris radic. cucumer. agreſt. lathyrid. an.* ℥j. *aut pro lathyrid. tithymal. ſuccum terito & cribrato, at cum oleo plurimum ſalis habente ſubigito, magnam inde pilam e lana confertam hoc medicamento illitam, umbilico aut lumbis applicato.* Or, ℞. *fellis taurin.* ℥j. *gr. cindii virid.* ℥iv. *ſucci lupinor. virid.* ℥ij. *euphorb.* ℥j. *pulp. colocynth. tantundem adip. vulpin. recent.* ℥vj. *adip. viper.* ℥ij. ß. *ſtercor. muris,* ℥iv. *ſucci pæon. caſtor. ſingulor.* ℥iv *ol. liguſtrin.* ℥vi. *ol. antiq.* ℥j. *fiat unguentum vel oleum.* It purgeth without trouble, and beſides the other commodities it alſo is good againſt diſtraction or madneſs. Two ſpoonfuls is the greateſt quantity to be uſed at one time; for in ſome, one is ſufficient: anoint therewith the navel and thereabouts, and a juſt purgation will enſue thereupon, which if it ſhall flie out beyond your expectation, you may foment the belly with a ſponge moiſtened in warm wine and preſſed forth again, it will be preſently ſtayed. Moreover *Fernelius lib. 7. methodi*, makes mention of a laxative ointment. *Tetrab. 1. ſerm. 3 cap. 25.* Purgatives to be externally applied. The compoſition of a purging oil and ointment.

CHAP. XX.

Of the compoſition and uſe of Medicines.

HItherto we have ſpoken of the faculties of ſimple medicines; now we think good to ſay ſomething of the compounding of them: for ſo by the Architect are had and known every thing apart, and then he ſettles the workmen to the building, the conceived form of which hath been in his mind ever ſince he did enterpriſe it. Therefore the compoſition of divers medicaments with their qualities and effects, is a mingling appointed by the art of the Phyſician. Hence therefore *rheum, aloe, roſa, abſynthium*, although they have divers ſubſtances and faculties, yet are notwithſtanding called ſimple medicines, becauſe they have that variety from Nature, not from Art. But we many times call ſimple ſuch things as are compounded by art, as *oxym. ſimpl. oxyſacch. ſimplex*, as compared to greater compoſitions. And therefore oftentimes we uſe compound medicines, becauſe always the ſimple medicine alone, hath not ſtrength enough to oppugn the diſeaſe. For many times the ſick labour with manifold, and not ſimple affects, from which there being taken a various indication, we gather contrary ſimple medicines, to apply to every affect, in one compoſition. But oftentimes the nature of the part of the Patient, or of the body affected, requireth another kind of medicament which may be proper for the removing that diſeaſe; wherefore it is ſo made to oppugn the diſeaſe and not offend the body: and we mingle many other together, whoſe effects may temper one another. Moreover the compoſition of medicines was neceſſary, that becauſe thoſe things which have not a good taſte, colour, or ſmell, by Art, or compoſition, might be made more gratetul. Compound medicines of which we intend to ſpeak, are Glyſters, Suppoſitories, *Noduli*, Peſſaries, Oils, Liniments, Ointments, Emplaſters, Cerats, Pultiſſes, Cataplaſms, Fomentations, Embrocations, Epithemates, Veſicatories, Cauteries, *Collyria, Errhina*, Sneeling-powders, Maſticatories, Gargariſms, Dentifrices, Bags, Fumigations, Semicupiums, Baths. But firſt it is expedient that I ſay ſomething of weights and meaſures, with their notes, by which medicines commonly are meaſured and noted by Phyſicians. *Gal. 2. ſimp. 4. de ſanit. tuend.* The neceſſity of compound medicines.

CHAP XXI.

Of weights and meaſures, and the notes of both of them.

EVery weight ariſeth from a beginning and foundation, as it were; for as our bodies do ariſe of the four firſt ſimple bodies or elements, into which they are often reſolved: ſo all weights do ariſe from the grain, which is as it were the beginning and end of the reſt. Now hereby is underſtood, a barly-corn or grain, and that ſuch as is neither too dry, or overgrown with mouldineſs, or rancid, but well conditioned, and of an indifferent bigneſs. A grain the beginning of all weight. What is meant by a grain.

Obolus. Ten grains of theſe make an *Obolus*; two Oboli, or twenty grains make a ſcruple, three ſcruples,
A ſcruple. or ſixty grains make a dram, eight drams make one ounce, twelve ounces make one pound medi-
A dram. cinal,, which is for the moſt part the greateſt weight uſed by Phyſicians, and which they ſeldom ex-
An ounce. ceed; and it is reſolved into ounces, drams, ſcruples, *oboli* and grains, which is the leaſt weight.
A pound. To expreſs theſe weights we uſe certain notes; the pound is expreſſed by this note, ℔. the ounce by this ℥, the dram thus ʒ, the ſcruple thus ℈, the *obolus* with the beginning letter thus *obol.* the grain with his beginning letter thus, g. But ſometimes we meaſure the quantity of medicines by meaſures and not always by weights; and therefore we expreſs a handful by this note, m. a pugil thus, p. number thus, n. and the half part of every weight and meaſure is expreſſed by this note, ſ. put after every note of the aforeſaid weights and meaſures of the ſame ſort, as the half pound, ℔ ſ. the half ounce, ℥ ß. and ſo of the reſt. Moreover, in deſcribing the ſame medicament we uſe the notes ſometimes of weights, ſometimes of meaſures; and therefore it is to be noted that herbs, green or dry, are ſigned with theſe notes, m. p. but thoſe which are dry and to be brought to powder, with theſe notes, ℥.ʒ.p. Roots, by theſe notes, ℥.ʒ.p.m. Barks, by theſe notes, ℥.ʒ. Seeds, by theſe notes, ℥.ʒ. Fruits, by theſe notes, an.p.℥.ʒ.℈. Flowers, by theſe notes, p.m.℥.ʒ. Pulſes, by theſe notes, p.℥.ʒ.

All other medicaments either dry or liquid, are deſcribed with theſe notes, ℔.℥.ʒ.℈. obol. g.

Having expounded theſe things, let us come to the deſcription of compound medicines, beginning with glyſters firſt, as the remedy which is moſt common and familiar, and almoſt chiefly neceſſary of all others.

CHAP. XXII.

Of Glyſters.

What a glyſter is. A Glyſter is an injection prepared firſt and properly for the groſs inteſtines and fundament; for ſometimes glyſters are uſed and made for the ſtomach, ſpleen, reins, bladder, womb, meſentery, aud alſo for the head, from whence oftentimes by ſharp glyſters, the hurtful matter is brought downwards, as we ſee in Apoplexies. Therefore there is no part of the body which receives not ſome benefit by glyſters, but more or leſs according to the vicinity they have with the belly, and the ſtrength of the glyſter: for there are divers ſorts of glyſters, ſome emollients, others evacuating, ſome anodynes, ſome aſtringents, ſome cleanſing, ſome ſarcotick, and epulotick, and ſome may be ſaid to nouriſh. They may be all made of the parts of plants or beaſts, with compound medicines either ſolutive, or altering, and others according to the advice of the Phyſician. The parts of plants which are uſed to this purpoſe, are roots, ſeeds, leaves, flowers, fruits, ſhouts, juices, mucilages. Parts of beaſts are yolks of eggs and whites, hony, chickens, capons, old cocks well beaten, hands and feet of ſheep, the inteſtines, whey, milk, ſewet, axungia, and ſuch like in decoctions, wherein we mingle and diſſolve ſimple and compound medicines. We ſometimes uſe without any other medicament, to make a glyſter with oil alone, as oil of nuts for the Colick, of whey alone, the decoction of the head and feet of the ſheep alone, and of the decoction of Cicers and barly do we prepare Glyſters.

Differences of glyſters.

The materials of glyſters.

Their quantity The quantity of a Glyſter is ſometimes leſs according to the diverſe diſpoſition of men and their diſeaſes: for weak children the quantity is leſs: for women with child, and in the colick, dyſentery, lientery, or when much hardened excrement is within. But when we would abundantly move the excrement, and there is nothing that may hinder, the doſe of a glyſter for the moſt part is half a pound, one pound, or three quarters of a pound. The glyſter muſt be injected warm or hot, more or leſs, according to the nature or condition of the ſick: for being cold it offends the inteſtines, and the neighbouring nervous parts, which are cold of themſelves. It muſt be given by degrees, for being injected ſuddenly, the wind which is uſually in the guts will beat it back again, whence comes intolerable pain. But this will be more clear by that we ſhall teach concerning the differences of glyſters, whereof there ſhall be ſufficient examples.

An emollient glyſter. ℞. *malv. violar. biſmalv. acanth. an.* m. j. *radic. alth. lilior. an.* ℥j. *paſſul. ficuum ping.* ℥ ß. *fiat decoctio ap.* ℔j. *in qua diſſolve caſſ. butyr. recent. an.* ℥j. *ol. viol.* ℥iij. *fiat Clyſter.*

Glyſters that do evacuate, are prepared by the counſel of the Phyſician, and of divers Simples, being boiled for ſeveral purpoſes. Therefore if the humors be cold which are to be evacuated, the Glyſter ſhall be after this manner.

A glyſter to evacuate a cold phlegmatick humor. ℞. *Salviæ, origani, abrotoni, chamæm. melilot, an.* m. ß *ſeminum aniſi, fœnic. cumini, an.* ℥iij. *ſemin. cathar.* ʒij. Make a decoction of them, wherein diſſolve *Diaphon. Hier. Simpl. an.* ℥ ſ. *ol. aneth. chamæm. an.* ℥j. ß. *Mellis Antho. ſacc. rub. an.* ℥j. *fiat Clyſter.*

To evacuate Cholerick matter, prepare a Glyſter after this matter, ℞. *quat. remollient. paret. Cichor. endi. an.* m. ſ. *Semen. quat. frigid. Major. an.* ʒiij. *hordei integri,* p. j. Make a decoction of them, and diſſolve in it *Caſſ.* ℥j. *Ol. viol. mellis viol. an.* ℥ij. *fiat Clyſter.*

To evacuate melancholy, this Glyſter following will be uſeful. ℞. *Fumitor. Centaur. minoris, Mercurialis, an.* m. j. *Polyp. Qu. folicul. ſennæ, an.* ℥iij. *ſeminis agni caſti, Thymi, an.* ℥ij. Make a decoction and diſſolve therein *Confect. Hamech.* ℥ ß. *Caſſ. recens extract.* ℥iij. *olei violati, lilior. an.* ℥ ß. *Sac. rub. mellis viol. an.* ℥j ß. *ſalis,* ℥j. And thoſe Glyſters do not only evacuate the humors that offend, but alſo correct the diſtemper of the bowels and inward parts. For the Glyſters preſcribed againſt pituitous and melancholick matter, help the cold diſtemper; but that which is for choler, the hot diſtemper. Purging medicines, which are diſſolved in the decoction of Glyſters, are very ſtrong, as, *Confect. Hamech. Benedicta, Diaprun. Solutivum, Diaphenicon,* being uſed from ʒvj. to ℥j. at moſt: but the weaker and more gentle are *Catholicon, Caſſia, Hiera ſimplex,* from ℥vj. to ℥ij. at moſt.

An Anodyne glyſter. An Anodyne Glyſter is uſually made without ſuch things as purge or evacuate: as, ℞. *Flor. Chamæm. melil. Aneth. an.* p. j. *rad. Biſmal.* ℥j. boil them in milk, and to the decoction add, *Mucaginis ſeminis lini, fœnugræci, extractæ in aqua Malvæ,* ℥ij. *ſaccari albi, olei anethi, chamæmeli, an.* ℥j. *vitellos ovorum*

ovorum duos, fiat Clyſter. Theſe Glyſters ſhould be kept longer in the body, that ſo they may more eaſily mitigate pain.

An Aſtringent Glyſter.

The example of an aſtringent Glyſter. ℞. *Equiſeti, plantag. polygami, an.* m. j. boil them in *lacte uſtulato*, to ℥xij. to the decoction ſtrained add *Bol. armeni, ſanguinis draconis, an.* ʒij. *olei roſati*, ℥ij. *albumin. ovorum duorum, fiat Clyſter.* We uſe theſe kind of Glyſters in Dyſenteries, and in the immoderate flux of the Hæmorrhoid veins, having firſt evacuated the uſual excrements. Glyſters which be ſarcotick, epulotick, and cleanſers of the greater guts, and fit for the curing of ulcers, are to be prepared of ſuch medicines as are deſcribed before in their proper Chapters.

Nouriſhing Glyſters.

Alimentary Glyſters are made of the decoction of Chickens, Capons, Cocks, being boiled to a gelly, and ſtrongly preſſed forth. They are alſo prepared of Marrow gelly, which are not altogether ſo ſtrong as thoſe which are commonly taken by the mouth, becauſe the faculty of concoction in the guts, is much weaker than that of the ſtomach. Oftentimes alſo the matter of theſe kind of Glyſters is prepared in wine, where there is no pain of the head or fever, but more frequently in the decoction of Barly, and in Milk, adding the yolks of Eggs, and ſome ſmall quantity of white ſugar, leſt by the cleanſing faculty it move the guts to excretion. And therefore Sugar of Roſes is thought better, which is conceived to be ſomewhat binding. Here you may have examples of ſuch Glyſters. ℞. *Decoctionis Capi perfecte cocti* ℔. j. ß. *ſacchari albi*, ℥ß. *miſce, fiat Clyſter.* ℞. *Decocti Pulli & Galatinæ*, ℔. ß. *vini opt.* ℥iv. *fiat Clyſter.* ℞. *Decocti hordei mundati, & in cremorem redacti* ℔. ß. *lactis boni* ℔ j. *Vitellos ovorum duos, fiat Clyſter.* We uſe theſe kind of Glyſters to ſtrengthen children, old and weak men, and bodies that are in a Conſumption. But in the uſe of theſe there are three things to be obſerved: Firſt that the fæculent excrements may be taken away, either by ſtrength of nature, or by art, as by a Suppoſitory, or an emollient Glyſter, leſt the alimentary matter being mingled with them, ſhould ſo be infected and corrupted. The other is, that there be great quantity given, that ſo ſome may aſcend to the upper guts. That third is, that the ſick ſleep after the taking of it; for ſo it is more eaſily converted into nouriſhment, and the alimentary matter is better kept, for ſleep hindereth evacuations. In Glyſters of this kind we muſt beware of Salt, Hony and Oil; for the two firſt provoke excretion by their acrimony, and the laſt by his humidity doth relax and lubricate. They who think no kind of Glyſter can nouriſh or ſuſtain the body, rely upon this reaſon: That it is neceſſary whatſoever nouriſheth, ſhould have a triple commutation or concoction in the body: firſt, in the ſtomach; ſecondly, in the liver; thirdly, in all the members. But this is repugnant to reaſon and experience: to reaſon, for that a certain ſenſe of ſuch things as are defective, is implanted in all and every of the natural parts of our body. Therefore ſeeing nutrition is a repletion of that which is empty, without doubt the empty and hungry parts will draw from any place that nouriſhment that is fit and convenient for them, and in defect thereof, whatſoever they meet with, which by any familiarity may aſſwage and ſatisfie their deſire. But the alimentary Glyſters, by us deſcribed, conſiſt of things which agree very well with the nature of our bodies, and ſuch as are boiled and ordered with much art, ſo to apply the chylification to be performed in the ſtomach. Therefore they may be drawn in by the meſaraick veins of the guts; which according to *Galen*, have a certain attractive faculty. And thence they may be eaſily carried through the gate-vein, liver, and ſo over the whole body. And experience teacheth, that many ſick people, when they could take nothing by the mouth, have been ſuſtained many days by the help of theſe kind of Glyſters. What is more to be ſaid? We have ſeen thoſe who have taken a Suppoſitory by the fundament, and vomited it at the mouth; by which it alſo appeareth that ſomething may flow without danger of the ſick from the guts into the ſtomach.

Their uſe.

Their Argument that deny Glyſters to nouriſh.

Confuted firſt by reaſon.

Secondly, by experience.

Commonly they give Glyſters any hour of the day, without any reſpect of time; but it ſhould not be done unleſs a great while after meals, otherwiſe the meat, being hindred from digeſtion, will be drawn out of the ſtomach by the Glyſter.

The common uſe of glyſters.

Glyſters are uſed to help the weaker expulſive faculty of the guts, and by conſequence alſo of the other parts, both that ſuch as through want of age, and old people, and ſuch as by reaſon of great imbecillity by ſickneſs cannot admit of a purging medicine, may by this means at leaſt eaſe themſelves of the trouble and burden of hurtful humors. *Galen* hath attributed to Storks the invention of Glyſters, which with their bills, having drunk Sea-water, which from ſaltneſs hath a purging quality, waſh themſelves by that part, whereby they uſe to bring away the excrements of their meats, and of the body. But a Glyſter is fitly taken after this manner: whileſt the Syringe is expreſſed, let the patient hold open his mouth; for by this means all the muſcles of the *Abdomen*, which help by compreſſion the excretion of the guts, are relaxed; Let him wear nothing that may gird in his belly, let him lie upon his right ſide, bending in a ſemicircular figure; and ſo the Glyſter will the more eaſily paſs to the upper guts, and (as it were) by an overflowing, wet and waſh all the guts and excrements. It hapneth otherwiſe to thoſe who lie upon their left ſide; for the Glyſter being ſo injected, is conceived to abide, and (as it were) to ſtop in the *Inteſtinum rectum*, or *Colon*, becauſe in this ſite theſe two inteſtines are oppreſſed, and as it were ſhut up with the weight of the upper guts. A little while he may lie upon his back after he hath received the Glyſter, and preſent after he may turn himſelf on either ſide. And if there be pain in any part, ſo long as he is able, may incline to that ſide; Moreover, becauſe there are many who cannot by any reaſon be perſwaded to ſhew their buttocks to him that ſhould adminiſter the Glyſter, a fooliſh ſhamefaſtneſs hindring them: therefore I thought good in this place to give the figure of an Inſtrument, with which one may give a Glyſter to himſelf, by putting up the pipe into the fundament, lifting the buttocks a little up. The pipe is marked with this letter *A*. The body of the Syringe, whereinto the Glyſter muſt be put, with this Letter *B*.

The ſick having received the glyſter muſt turn to their ſide grieved.

The

The figure of a Glyſter-pipe and Syringe, by beneſit whereof a man may give himſelf a Glyſter.



CHAP. XXIII.

Of Suppoſitories, Nodules, and Peſſaries.

A Suppoſitory is a certain medicament, formed like unto a tent, or gobbet of paſte, ſuch as is commonly uſed to fat Fowl. It is put into the fundament, that it might excite the ſphincther-muſcle to ſend forth thoſe excrements which are knit in the guts. Anciently it had the form of an Acorn, whence it is called to this day *Glans*. The Suppoſitories we now uſually make, have the form of a Peſſary, that is round and longiſh, in the form of a Wax-Candle. They

The differences. are either weak, ſtronger, or ſharp; the weak are made of the ſtalks or the roots of Beets, of Lard, boiled Hony with Salt, or of Caſtle-ſope. The ſtronger of purging powders, as *Hiera*, with Salt and Hony, or the juices of ſharp herbs, or mingled with the galls of beaſts. It is commonly made

The form. thus: as, ℞. *Mellis* ℥j. *Salis aut pulveris alterius irritantis* ʒj.

The uſe. ℞. *Mellis cocti* ℥j. *pul. Colocynthidos* ϑ ß. *Salis gemmæ* ϑj. *fiat Suppoſitorium.* We uſe Suppoſitories, when the ſick by his infirmity is unwilling, or not able to bear or away with a Glyſter, as in burning Feavers: or, when as one being injected, is ſlow and reſteth in the guts. And we uſe the ſharper Suppoſitories in ſoporiferous affects of the head, that they might provoke the dull faculty of the guts to expulſion. As alſo when the condition of the diſeaſe is ſuch, that by the uſe of Glyſters there is manifeſt hurt; as in an *Enterocele*, where the gut ſo ſwells, that over and above if it be filled by the glyſter infuſed, it would the more preſs the *Peritoneum*, ſo that ſtraight-ways by the relaxed or broken part it might eaſily be devolved into the Cod.

Nodules have the ſame uſe with Suppoſitories, and are oftentimes ſubſtituted in ſtead of Glyſters. They are made of gentle medicines, as the yelks of Eggs with a little Salt and Butter, or of Gall and Hony tied up in a cloth in the form of a Filbert; the ſtring of it may hang forth, whereby the Nodule

The form of a Nodule. in the fundament may be drawn forth. This deſcription may be an example of Nodules: ℞. *Vitellum unius ovi, cui adde ſalis modicum, fellis vervecis, mellis an.* ℥ ß. *butyri* ʒiij. *miſce, fiant Noduli filo appenſi.*

Peſſaries. A Peſſary is groſſer than a Suppoſitory, and is appointed for the womb, being made with Cotton-Wool or Silk ſteeped in ſome medicament, and then put into the neck of the womb.

Their uſe. A Peſſary is uſed either to ulcers of the neck of the womb, or for the procuring or ſtopping of the *Menſtrua*, or againſt ſordid and hurtful humors of the womb, cauſing hyſterical paſſions, and therefore to be wafted away and evacuated. Therefore in the compoſition of Peſſaries are uſed gums, juices, ſeeds of herbs, roots, and many other things, according to the advice of the Phyſician, they are alſo made of a ſolid conſiſtence, the bigneſs of a finger, that they may enter into the neck of the womb; theſe being tied with a ſtring, which muſt hang forth to pluck it out withall when occaſion ſerves. This following may be an example of their deſcription. ℞. *myrrh. aloes an.* ʒj. *ſabin. ſemin. nigel. artemiſ. an.* ʒij. *radic. ellebor. nig.* ʒj. *croci,* ϑj. *cum ſucco mercurial. & melle fiat Peſſus*; let it be tied to the thigh with a thred. Or thus, ℞. *maſtich. thuris, an.* ʒiij. *alum. roſ. rub. nuc. cupreſ. an.* ʒij. *ladan. hypoci, ſumach. myrtil. an.* ʒiij. *fiant peſſi cum ſucco arnogloſ. & cotoniorum.* According to this example others may be made for to mollifie, to bind, to cleanſe, to incarnate, to cicatrize and cover the ulcers of the womb: they are to be put up when the patient lieth in bed, and to be kept all night,

Peſſaries are alſo made of medicinable powders, not only mixed with ſome juice, but alſo with thoſe powders alone being put into a little bag of ſome thin matter, being ſtuffed with a little cotton, that it might be of a convenient ſtiffneſs, and this kind of Peſſaries may be uſed profitably in the falling of the mother,

An example of one mentioned by Rondoletius *in his book of inward Medicines, is as followeth.*

Againſt the ſuffocation of the Mother. ℞. *Benoioini, ſtyracis, caryoph. an.* ʒj. *gal. moſchi,* gr. vi. *fiat pulvis*; this being made up with cotton, may be put up into the body.

CHAP.

CHAP XXIV.
Of Oils.

PRoperly and commonly we call oil that juice which is preſſed forth of Olives; but the word is uſed more largely, for we call every juice of a fluxible, unctuous, and aiery ſubſtance, Oil. There are three differences of theſe oleaginous juices: The firſt is of thoſe things which yield oil by expreſſion, as well fruits as ſeeds being bruiſed, that by beating the oily juice may be preſſed forth; ſome are drawn without fire, as oil of ſweet and bitter almonds, oil of nuts, of *Palma Chriſti.* Others are made to run by the help of fire, by which means is gotten oil of bays, linſeed-oil, rape-oil, oil of hemp, and ſuch like: The manner of drawing oil from ſeeds is ſet down by *Meſue* in his third book.

The ſecond ſort of thoſe oils which are made by the infuſion of ſimple medicines in oil, wherein they leave their qualities: and this is done three ſeveral ways, the firſt is by boiling of roots, leaves, tops of flowers, fruits, ſeeds, gums, whole beaſts, with wine, water, or ſome other juice, with common or any other oil, until the wine, water, juice be conſumed, which you may perceive to be perfectly done, if you caſt a drop of the oil into the fire, and it maketh no noiſe but burneth. It is to be remembred that ſometimes the ſeeds or fruits are for a certain time to be macerated before they are ſet to the fire, but it muſt be boiled in a double veſſel, leſt the oil partake of the fire. The making oils by infuſion.

After this manner is made *oleum coſtinum, rutaceum, de croco, cydoniorum, myrtillorum, maſtichinum, de enphorbio, vulpinum, de ſcorpionibus,* and many others. The ſecond is by a certain time of maceration, ſome upon hot aſhes, others in horſe-dung, that by that moderate heat the oil might draw forth the effects of the infuſed medicines into it ſelf. The third is by inſolation, that is, when theſe or theſe flowers, being infuſed in oil, are expoſed to the Sun, that by the heat thereof the oil may change, and draw into himſelf the faculty of the flowers which are infuſed: of this kind are oil of roſes, camomil, dill, lilies, of water-lilies, violets and others, as you may ſee in *Meſue.*

The third kind is properly that of the Chymiſts, and is done by reſolution made after divers manners, and of this ſort there are divers admirable qualities of divers oleaginous juices, whether they be made by the Sun or Fire, or putrefaction, as we ſhall ſpeak in his place hereafter. The manner of oils by reſolution.

We uſe oils when we would have the virtue of the medicament to pierce deep, or the ſubſtance of the medicines mingled with the oil to be ſoft and gentle. Moreover when we prepare oils that ſhould be of a cooling quality the common oil of the unripe Olive is to be uſed: of that ſhould the oil of roſes be made.

Again when we would prepare oils of heating qualities, ſuch as are *Oleum Philoſophorum,* or of Tiles, ſweet and ripe oil is to be choſen.

CHAP. XXV.
Of Liniments.

A Liniment is an external medicine of a mean conſiſtence between an oil and an ointment, for it is thicker than an oil; for beſides oil it is compounded with butter, axungia and ſuch like, which is the reaſon why a Liniment is more efficacious in ripening and mitigating pain, than ſimple oil. The varieties of Liniments are drawn from their effects, ſome cool, others heat, ſome humect, ſome ripen, others by compoſition are made for divers uſes. The matter whereof they are uſually made, is oil, axungia, ſuet, butter, all thoſe things which have an oily ſubſtance or conſiſtence, as *ſtyrax liquida,* turpentine, the mucilages of fenugreek, marſh-mallows, marrow, and other like. To theſe are ſometimes added powders of roots, ſeeds, flowers, rinds, metals, but ſparingly, that the liniment may be of a liquid conſiſtence. What a liniment is.

An example of a liniment that is good to attenuate, heat, and digeſt, is this that followeth. ℞. *Ol. amygd. amar. lilior. an.* ℥j. *axung. anat. gallin. an.* ℥ß. *butyr. ſal expert.* ℥j. *mucag. ſem. alth. fœnugr. extract. in aq. hyſſop. an.* ℥ß. *pulver. croci, ireos, an.* ℈j. *fiat linimentum.* This may be an example of a liniment to humect and mollifie. ℞. *ol. amygd. dulc.* ℥ij. *axung. human.* ℥ß. *mucag. ſemin. malv. extract. in aq. parietar.* ℥ß. *fiat linimentum*: you may add a little ſaffron. There be many others like theſe which may be made for divers affects. They are eaſily applied to every part of the body, becauſe they are not ſo liquid as oils: the reaſon is, they are more agreeable to any of the parts. If they be to enter into any crooked narrow paſſage, ſuch as the ear, they muſt be more liquid, and have more oil: if they be to ſtick on the part, they will admit of more axungia and ſuet.

They are deceived who think that the difference between liniments and ointments is, that there is no wax in liniments as there is in unguents; for there be ſome unguents which admit not any wax to be added, as *Ægyptiacum,* and all ſuch as are uſed in gangrenes, and all ſorts of putrid ulcers; becauſe to theſe kinds of diſeaſes all fatty things, as oils, fats, roſins, and wax, are enemies. Therefore we ſubſtitute in the place of them in *Ægyptiacum,* hony and verdigreaſe; for of theſe it hath his conſiſtence, and his quality of cleanſing.

CHAP XXVI.
Of Ointments.

OIntments are of a more ſolid conſiſtence than Liniments, and are therefore of more force. Their differences are partly taken from their effects; for ſome heat, others cool, ſome dry, and ſome humect, ſome cleanſe, ſome corroborate, ſome waſte dead fleſh, and others cicatrize, Ointments and their differences.

cicatrize, partly from the variety of colours, partly from the firſt inventors, as *Album Rhaſis*, *Deſiccativum rubrum*: partly from the number of the ſimple medicaments whereof they be made, as, *Tetrapharmacum*, *Tripharmacum*, or *Nutritum*: partly from that medicament which is principal in the compoſition; hence are they called *Unguentum de Lithargyro*, *de Minio*, *Diapompholygos*, and ſuch like. They are compounded of herbs, roots, ſeeds, fruits, metals, and part of Beaſts; the juices and other liquid things being conſumed away by boiling, as we have ſaid in the Chapter of compound Oils. Herbs, and the parts of them, if they be dry, muſt be powdred, and alſo metals; but being green, they are boiled and ſtrained forth, and the juice ſo preſſed is waſted by boiling. Gums and Roſins ſome are powdred, others being put to ſome convenient liquor are diſſolved by fire: ſo wax is diſſolved in the Oil. In the compoſition of unguents this proportion is uſually obſerved, that for one ounce of powder, two ounces of Wax, and eight of oil is added: notwithſtanding for that Wax ſerveth only to the conſiſtence of the ointment, it is better to leave the quantity to the will of the Apothecary; but he may be more ſparing in adding Wax to the ointments in Summer than in Winter; for the heat of Summer, drying them, addeth to the conſiſtence: by examples propounded, theſe common precepts will more plainly appear.

Unguentum aſtringens. ℞. *Olei roſ.* ℥iv. *pil. lepor. bol. armen. terræ ſigil. an.* ℥j. *bal. Gallar. an.* ℥ß. *tritis terendis, & ſimul mixtis, addita cera quod ſufficit, fiat unguentum.* Here we muſt obſerve, that there be three ways of making ointments: The firſt is of thoſe which are made only by ſtirring or grinding in the Mortar without any fire, and ſo is made *Unguentum nutritum*. The ſecond is, when we diſſolve Wax in Oil, Fat, or ſome ſuch ſubſtance with fire: and being all diſſolved, we mingle the powders according to the proportion we noted before. After which manner are made *Unguentum Aureum*, *Baſilicon*, *Diapompholygos*, *Deſiccativum rubrum*, *Enulatum*. The third ſort is, when we bruiſe herbs with a peſtel, and mingle them with Axungia, boiling them together, and then ſtraining them, and the ointmen, is that which is ſtrained. Therefore let us proceed to explain this by examples.

Unguentum nutritum. ℞. *Lithar. auri triti & loti* ℔ ß. *olei roſ.* ℔. j. *aceti roſ.* ℥iv. *fiat Unguentum.* Firſt, we put the Litharge into the Mortar, pouring in a little Oil, and working it with a Peſtel, that it may grow thick, then with the Oil we put a little Vinegar, continually working, until they mingle into one body, now and then between whiles adding ſometimes a little Oil, ſometimes a little Vinegar, until the whole be brought to the conſiſtence of an ointment. If of an ointment of this kind thou wouldſt make a black plaiſter, by degrees conſume all the Vinegar, ſo ſhall the plaiſter ſhine and grow black.

Unguentum aureum. ℞. *Ceræ citr.* ℥vj. *olei boni* ℔ij. *tereb.* ℥ij. *reſin. & coloph. an.* ℥j ß. *olib. maſtich. an.* ℥j. *croci,* ℥j. *fiat Unguentum.* Firſt, diſſolve the Wax with a good part of Oil, then add the Roſin and Colophony broken ſmall. Theſe being diſſolved, take the compoſition from the fire, and then add the Turpentine, when the whole is ſomewhat cooled; add the *Olibanum* and Maſtick being finely powdred, then the Saffron, which ſhall be macerated in the reſt of the Oil.

Ung. Tetrapharmacum, ſeu Baſilicon. Tetrapharmacon is ſo called, becauſe it is made of four ſimple medicines, Wax, Roſin, Pitch, Tallow, of each a like quantity, and ſo equally mixed.

℞. *Reſin. picis nigr. adip. vituli, & ceræ an.* ℥ij. ß. *Olei veteris olivarum maturarum,* ℔j. ß. or if you would have it harder, ß. j. that ointment is alſo called *Baſilicon*, the Wax being cut ſmall and diſſolved in Oil, then add the reſt of the things, which being diſſolved, thou ſhalt have the deſired ointment.

Ung. Diapompholygos. ℞ *Olei roſ.* ℥ix. *cer. alb.* ℥iij. *ſucci ſolani hortenſis,* ℥iv. *Ceruſ. lot.* ℥j. *Pompholygos, plumbi uſti & loti, olib. puri, an.* ℥ ß. *fiat unguentum.* Diſſolve the Wax in the Oil with a gentle fire, then you ſhall take it from the fire, and add to the reſt of the ingredients, working them together in a ſtone Mortar, pouring on the juice by degrees, at leaſt ſo much of it as will incorporate.

Ung. deſiccativum rubrum. ℞. *Lap. calam. ter ſig. an.* ℥ij. *Litharg. auri ceruſ. an.* ℥j ß. *Camphor.* ℥ ß. *ceræ,* ℥ij ß. *Olei roſat. viol. an.* ℥iij. *fiat Unguentum.* Diſſolve the Wax in the Oil, then ſet it to cool, and work in the powders with a ſpatter, and at laſt add the Camphire diſſolved in a little Oil of Roſes, or Roſewater.

Ung. Enulatum. ℞. *Rad. enul. campan. cocti. cum aceto & contuſ. ut decet* ℔ ß. *Axung. porci, olei commu. an.* ℥i ß. *argen. vivi extincti, & tereb. lot. an.* ℥j. *ſal. commu. pulveriſati,* ℥ij. incorporate them according to art. The boiled roots muſt be drawn through a Sieve, which being boiled by a gentle fire with the *Axungia*, muſt be continually ſtirred, then put to the Salt with Oil and Wax: when you ſet it from the fire to cool, then add the Quickſilver, being killed with a little *Axungia* and Turpentine.

Ung. Album Rhaſis. De Althæa. ℞. *Olei roſat.* ℥ix. *ceruſ. alb.* ℥iij. *cer. alb.* ℥ij. make it thus: let the Ceruſs be finely powdred, and put into the Oil and Wax whilſt it is hot, and ſo work the whole together until they ſhall be brought into a body. ℞. *Rad. Alth.* ℔. j. *ſemi. lini, fænugr. an.* ℔ ß. *Scyllæ* ℥iij. *Olei com.* ℔. ij. *cer.* ℔. ß. *terebinth. gum. heder. galb. an.* ℥j. *coloph. & reſin.* ℥iij. The roots and ſeeds being bruiſed, are infuſed for three days in five pints of water; boil them until three ounces be conſumed, and then draw forth the Mucilage, and boil it with the Oil, then add Wax cut ſmall: theſe being taken from the fire, the *Galbanum* being diſſolved with Vinegar, and mingled with the Turpentine, muſt be added together with the Gum *Hederæ*, Colophony, and Roſin.

Ung. Populeum. ℞. *Ocul. populi alb.* ℔. j. ß. *fol. papaveris nigr. Mandrag. hyoſcyami, lactucæ, ſempervivi parvi & magni, violæ nigræ ſolani, umbilici Veneris, ſeu cymbalar. bardanæ, an.* ℥ ß. (*Cordus, Fernelius, & Nicolaus ſingulorum* ℥iij. *præſcribunt*) *Adipis ſuilli recentis ſalis expertis,* ℔ij. *vini boni,* ℔j. *fiat Unguentum.* The popular buds and Violet leaves muſt be bruiſed and macerated in the *Axungia* for the ſpace of two months, that is until the reſt of the herbs be ready; for they cannot be gathered before the Summer time, but the Poplar buds and Violets may be had in March. They muſt be bruiſed and mingled very well, and ſet in a warm place for eight days; then add one pint of ſtrong Vinegar, and boil them till it be conſumed, which may be perceived by caſting a little of it into the fire, then ſtrain it forth, and put up the ointment.

Ung. Apoſtolorum. ℞. *Tereb. cer. alb. æruginis. an.* ℥xiv. *Opop. flor. ſeu virid. æris (nam hic flos æris non proprie accipiter pro gran. quæ ſcintillant inſtar ab ære exiliunt dum a fabr. ferrar. aqua tingitur: ſed pro viridi æris uſurpatur, cujus contra maligna ulcera notæ ſunt vires, contra quæ omnino id Unguent. eſt comparat.) an.* ℥ij. *ammon.* ℥xiv. *ariſt. lon. thur. maſc. an.* ℥vj. *myr. & galb. an.* ℥iij. *bdel.* ℥vj. *Lith.* ℥ix. *ol.* ℔ij. *fiat Ung.* The Litharge is to be mingled with two ounces of Oil for the ſpace of five hours, and with a gentle fire to be boiled until it come to the conſiſtence

ſiſtence of Honey, and be always ſtirring leſt it burn: being taken from the fire and warm, the Wax and the Roſin being diſſolved, with the reſt of the Oil, muſt be added. Then put to it, when it is cooling, the Gums diſſolved in Vinegar, boiled and incorporated with the Turpentine. Then the *Ariſtolochia*, Myrrh, and Frankincenſe are to be mingled, and laſt of all the Verdigreaſe, being in fine Powder, and ſprinkled in: and ſo the Unguent is made. ℞ *Cortic. median. caſtan. cortic. median.* Comitiſſa. *querc. cortic. median. gland. myrtil. eqneſ. cortic. fabar. acinor. uvar. ſorbor. ſiccor. immatur. meſpillor. immaturor. rad. chelidon. folior. prunor. ſylveſt. an.* ℥ j. ß. *aquæ plantag.* ℔ viij. *cer. nov.* ℥ viij. ʃ. *olei myrtillor.* ℔ ij. ʃ. Then theſe things which follow being finely powdered, are to be ſprinkled in. ℞ *Pulveris corticis mediani caſtan. corticis mediani gland. cortic. median. arb. gland. id eſt, querc. gallar. an.* ℥ j. *cineris oſſ. cruris bovis, myrtill. acinor. uvar. ſorbor. ſiccor. an.* ℥ ʃ. *Trochiſcorum de carabe,* ℥ ij. *fiat Unguentum.* Firſt make a decoction *Corticis mediani arboris quercus, acini uvar. rad. chelid. meſpil. ſorbor. equiſ. ſeminis myrtil. folior. pruni ſylveſtris, cort. fabar. cortic. mediani gland. cortic. caſtan. & gallar.* in the Plantain Water for the ſpace of two hours, then ſtrain it, and divide the liquor into nine parts, waſhing the Wax diſſolved with the Oil of Myrtils ſeven times; the liquor being all ſpent, and the Wax and Oil being melted, then inſperge the Powders, *Gruris bovis, aſſium, cortic. med. cortic. querc. med. gland. caſtan. gallar. ſorbor. meſpil. ſeminum myrtil. acinor. uvar.* and at the laſt the Trochiſces *carab.* after this manner ſhall you make this Ointment. ℞ *Olei abſynth. maſtich. de ſtic. roſat. an.* ℥ ʃ. *pulver.* *ung. pro ſtomacho.* *abſynth. roſ. major. menth. an.* ℥ j. *caryoph. cinam. maſtich. galang. an.* ℥ j. Powder thoſe things which are to be powdered, and with a ſufficient quantity of Wax make a ſoft Ointment, wherewith let the ſtomach be anointed one hour before Meals continually. ℞ *Cer. alb.* ℔ ij. *ceruſ. litharg.* *ung. ad morſus rabioſos, ex li. 1. Gal. de comp. ſec. genera.* *auri, an.* ℔ j. *myrrh. medul. cervi, an.* ℥ ij. *thuris,* ℥ j. *olei,* ℔ ʃ. Boil the Litharge in the Oil to a mean conſiſtence, then add to the Wax and Ceruſs, and when it will not ſtick to the fingers, take it from the fire and put in the *Medulla*; when it beginneth to cool, the *Myrrha* and *Thus*, being finely powdered, muſt be caſt in by little and little, and the Ointment may be put up for uſe. The chops of the fundament, and emollient Peſſaries are likewiſe made of it, and it is very good againſt the bitings of mad Dogs, and the punctures of nerves and tendons, keeping wounds ſo that they do not agglutinate. ℞ *Picis pinguis,* ℔ j. *opopanacis in aceto forti, oleo liliorum, & veteri porci axungia* 3. *De comp. med. ſec. gen.* *cocti,* ℥ iij. *fiat Unguentum. Oleum ex ſinapi,* is good againſt thoſe bitings of mad Beaſts and punctured nerves; for it doth open wounds when they are cicatrized. Ointments are uſed to overcome the contumacy of a ſtubborn evil by their firm and cloſe ſticking to, eſpecially if there ſhall need no Medicin to go further into the body.

CHAP. XXVII.

Of Cerats and Emplaſters.

SUch affinity there is in the compoſition of a Cerat and Emplaſter, that oftentimes the one is taken for the other, as is uſually done in Ointments and Liniments. A Cerat is a compoſition more ſolid and hard than an Ointment, and ſofter than a Plaſter, having his name from Wax, which taking awry the fluidneſs of the Oil, bringeth him to his conſiſtence. The differences of Cerats are taken ſome from the parts by which they are called, as *Ceratum ſtomachicum*: ſome from the effects, as *Ceratum refrigerans Galeni*: others from the ſimple Medicaments which are the chief in the compoſition, as *Ceratum Santalinum*. The proper matter of Cerats is new Wax and Oils, being appropriated to the grief of theſe or thoſe parts; ſo that Liniments and Ointments do ſcarce differ from Cerats, if they admit of Wax: for if Ointment of Roſes ſhould have Wax added to it, it were no longer an Ointment but a Cerat. What a Cerat is. The differences.

Cerats which are made with Roſins, Gums, and Metals, do rather deſerve the names of Emplaſters than Cerats. And therefore *Ceratum ad Hernias* we commonly call *Emplaſtrum contra Ruptu-ram*. If that pain or inflammation do grieve any part, we make Cerats of Plaſter diſſolved with Oil, leſt that the more hard and heavy conſiſtence of the Emplaſter ſhould be troubleſom to the part, and hinder perſpiration: and therefore laying aſide the compoſition of Cerats, let us ſpeak of Emplaſters.

An Emplaſter is a compoſition which is made up of all kind of Medicins, eſpecially of fat and dry things, agreeing in one groſs, viſcous, ſolid, and hard body, ſticking to the fingers. The differences of Emplaſters are taken from thoſe things, which the variety of Ointments are taken from. Of thoſe things which go into the compoſition of an Emplaſter, ſome are onely uſed for their quality and faculty, as Wine, Vinegar, Juices. Others to make the conſiſtence, as Litharge (which according to *Galen*, is the proper matter of Emplaſters) Wax, Oil, and Roſin. Others be uſeful for both, as Gums, Metals, parts of Beaſts, Roſin, Turpentine to digeſt, to cleanſe and dry. Of Emplaſters, ſome are made by boiling, ſome are brought into a form without boiling; thoſe which be made without fire, do ſuddenly dry, nor are they viſcous: they are made with Meal and Powder, with ſome juice, or with ſome humid matter mingled with them. But Plaſters of this kind may rather be called hard Ointments or Cataplaſms: for Plaſters properly ſo called are boiled, ſome of them longer, ſome ſhorter, according to the nature of thoſe things which make up the compoſition of the Emplaſter: Therefore it will be worth our labour to know what Emplaſters do ask more, or which leſs boiling. For Roots, Woods, Leaves, Stalks, Flowers, Seed, being dried, and brought into Powder, are to be added laſt, when the Plaſter is boiled as it were, and taken from the fire, leſt the virtue of theſe things be loſt. But if green things are to be uſed in a compoſition, they are to be boiled in ſome liquor, and being preſſed forth, that which is ſtrained to be mingled with the reſt of the compoſition; or if there be juice to be uſed, it is to be bruiſed and preſſed forth, which is ſo to be boiled with the other things, that nothing for the quality is to remain with the mixture, as we uſe to do in *Empl. de Janua, ſeu Betonica, & Gratia Dei*. The ſame is to be done Emplaſters.

with

with Mucilages, but that by their clammineſs they do more reſiſt the fire. But there doth much of Oil and Honey remain in their Plaſters when they are made. Thoſe juices which are hardned by concretion, as *Aloes*, *Hypociſtis*, *Acacia*, when they are uſed in the compoſition of a Plaſter, and be yet new, they muſt be macerated and diſſolved in ſome proper liquor, and then they are to be boiled to the conſumption of that liquor. Gums, as *Opopanax*, *Galbanum*, *Sagapenum*, *Ammoniacum*, muſt be diſſolved in Wine, Vinegar, or *Aqua vitæ*, then ſtrained and boiled to the conſumption of the liquor, and then mixed with the reſt of the Plaſter. And that they may have the exact quantity of Gums and Pitch, it is neceſſary that firſt they be diſſolved, ſtrained, and boiled, becauſe of the ſticks and ſordid matter which are mingled with them. You muſt have reſpect alſo to the liquor you uſe to diſſolve them in; for Vinegar of the beſt Wine doth more powerfully penetrate, than that which is of weak and bad Wine.

Other Gums, which are drier, are to be powdered, and are to be mingled with Plaſters laſt of all. Metals, as *Æs uſtum*, *Chalcitis*, *Magnes*, *Bolus Armenius*, *Sulphur*, *Auripigmentum*, and others, which may be brought to Powder, muſt be mingled laſt, unleſs advice be given by long boiling to dull the fierce qualities of them. The like conſideration is to be had of Roſin, Pitch, and Turpentine, which muſt be put in after the Wax, and may not be boiled but very gently; but the Fats are mingled whileſt the other things are boiling. The Litharge is to be boiled with the Oil to a juſt conſiſtence, if we would have the Plaſter dry without biting. Ceruſs may endure as long boiling, but then the Plaſter ſhall not be white, neither will the Litharge of ſilver make a Plaſter with ſo good a colour as Litharge of gold. Moreover, this order muſt be obſerved in boiling up of Plaſters: the Litharge muſt be boiled to its conſiſtence; Juices or Mucilages are to be boiled away, then add the Fats, then the dry Roſin, Wax, Gums, Turpentine, and after them the powders: You ſhall know the Plaſter is boiled enough by its conſiſtence, groſs, hard, glutinous, and ſticking to the fingers, being cooled in the air, water, or upon a ſtone. Alſo you ſhall know it by its exact mixtion, if that all the things become one maſs hard to be broken.

Signs of a Plaſter perfectly boiled.

The quantity of things to be put into Plaſters.

The quantity of things which are to be put into a Plaſter can hardly be deſcribed, but an artificial conjecture may be given, by conſidering the medicaments which make the Plaſter ſtiff, and of a conſiſtence, and the juſt hardneſs and ſoftneſs they make being boiled. Wax is not put into ſuch Plaſters wherein is *Labdanum*, for that is in ſtead of Wax. For if there ſhall be in the compoſition of a Plaſter ſome emplaſtick Medicaments, the Wax ſhall be the leſs; contrariwiſe, if they ſhall be almoſt all liquid things, the Wax ſhall be increaſed ſo much as ſhall be neceſſary for the conſiſtence of the Plaſter. The quantity of the Wax alſo muſt be altered according to the time, or the air; therefore it is fit to leave this to the art and judgment of the Apothecary. Emplaſters are ſometimes made of Ointments by the addition of Wax, or dry Roſin, or ſome other hard or ſolid matter. Some would that a handful of Medicaments powdered, ſhould be mingled with one ounce, or an ounce and half of Oil, or ſome ſuch liquor, but for this thing, nothing can certainly be determined: onely in Plaſters deſcribed by the Ancients there muſt be great care had, wherein he muſt be very well verſed, who will not err in the deſcribing the doſe of them; and therefore we will here give you the more common forms of Plaſters.

Empl. de Vigo with Mercury. ℞ *Ol. chamæm. aneth. deſpica, liliacei, an.* ℥ ij. *ol. de croco,* ʒ j. *pingued. porci,* ℔ j. *pingued. vitul.* ℔ ß. *euphorb.* ʒ v. *thuris* ʒ x. *ol. lauri,* ℥ j. ß. *ranas viv.* nu. vj. *pingued. viper. vel ejus loco human.* ℥ ij. ß. *lumbricor. lotor. in vino* ℥ iij. ß. *ſucci ebuli, enul. ana* ℥ ij. *ſchœnanthi, ſtœchados, matricar. an.* m. ij. *vini odoriferi,* ℔ ij. *litharg. auri* ℔ j. *terebinth. claræ* ʒ ij. *ſtyracis liquid.* ʒ j. ß. *argenti vivi extincti*, ſo much as the preſent occaſion ſhall require, and the ſick ſhall be able to bear, and make up the Plaſter. To one pound of the Plaſter they do commonly add four ounces of Quick-ſilver, yet for the moſt part they do increaſe the doſe, as they deſire the Plaſter ſhould be ſtronger: the Worms muſt be waſhed with fair Water, and then with a little Wine to cleanſe them from their earthy filth, of which they are full, and ſo the Frogs are to be waſhed and macerated in Wine, and ſo boiled together to the conſumption of a third part; then the Squinanth muſt be bruiſed, the Feverfew and the Stœchas cut ſmall, and they being added, to be boiled to the conſumption of one pint, and being boiled ſufficiently, the decoction being cooled ſhall be ſtrained and kept; and the Litharge is to be infuſed for twelve hours in the Oil of Chamomile, Dill, Lillies, Saffron, and the axungies above ſpoken of. Then boil them all with a gentle fire, by and by taking it from the fire, and add one quart of the decoction above ſpoken of, then ſet it to the fire again that the decoction may be conſumed, and then by degrees add to the reſt of the decoction: the Oil of Spike ſhall be reſerved unto the laſt, which may give the Plaſter a good ſmell. Then are added the juices of Walwort and Enula, which muſt be boiled until they be waſted away. Afterwards it being taken from the fire, to the compoſition is added the Frankincenſe and Euphorbium, and white Wax as much as ſhall ſuffice. When the whole maſs ſhall cool, then at laſt is mingled the Quick-ſilver extinct, Turpentine, Oil of bitter Almonds, Bays, Spike, of Line, Styrax and Axungia, being continually ſtirred, and it ſhall be made up upon a ſtone into rolls. Unleſs the Quick-ſilver be well extinguiſhed, it will run all into one place, and unleſs you tarry until the compoſition cool, it will vapour away in fume.

Ceratum œſipi ex Philagrio. ℞ *Croci* ʒ ij. *bdelii, maſtich. ammon. ſtyrac. liquid. an.* ℥ ß. *ceræ alb.* ℔ ß. *tereb.* ℥ vj. *medul. cruris vaccæ, adipis anſerini, an.* ℥ j. *œſypi, vel ſi deſit, axung. gallin.* ℥ ix. *olei nard. quantum ſatis ad magdaleones formandos, expreſſionis ſcillæ,* ʒ j. ß. *olibani, ſevi vitul.* ℥ j. The *œſypus, ſepum, adeps, medulla, cera*, are to be diſſolved together; when they cool, add the *Ammoniacum* diſſolved in the decoction of Fœnugreek and Chamomile, half an ounce, and ſo much juice of Squils, then put to the Styrax and Turpentine, ſtirring them continually; then add the *Bdelium*, *Olibanum*, Maſtick, Aloes, brought into fine Powder, and when they are perfectly incorporated into a maſs, let them be made up with *Oleum nardinum* into rolls.

De gratia Dei. ℞ *Terebinth.* ℔ ß. *reſin.* ℔ j. *cer. alb.* ℥ iv. *maſtich.* ℥ j. *fol. verben. beton. pimpinel. an.* m. j. The Herbs being green, the

the tops are to be cut and bruiſed in a ſtone Mortar, and boiled in red Wine to the conſumption of one third part. To the ſtrained Liquor add Wax cut into ſmall pieces, and being diſſolved by the fire; the liquor being conſumed put to the Roſin, when it ſhall cool add the Maſtick powdered, working it with your hands, by which it may be incorporated with the reſt of the things.

℞ *Succi beton. plantag. apii, an.* ℔ j. *ceræ, picis, reſin. tereb. an.* ℔ ß. *fiat. empl.* The Juices are to be mingled with the Wax being diſſolved, and boiling them until three parts be conſumed, add the Roſin and Pitch, which being diſſolved and hot, muſt be ſtrained, and then add the Turpentine, and make up the Plaſter. *De Janua, ſeu de Betonica.*

℞ *Croci, picis com.* (or rather *picis naval.* becauſe this emplaſter is uſed to diſcuſs and draw forth the matter which cauſeth the pain of the joints) *coloph. ceræ, an.* ʒij. *tereb. galb. ammon. thuris, myrrhæ, maſtich. an.* ʒv. ß. The *cera, pix,* and *colophonia* are by little and little to be diſſolved, to which add the gums diſſolved according to art, and mingled with the terebinth; and taking it from the fire add the *thus, myrrha,* and at laſt the *crocus* in fine powder, and then make it up into rowls with Oil of Worms. *Emplaſtrum Oxycroceum.*

℞ *Ol. com.* ℔ ij. *ceruſ. ſubtiliſ.* ℔ j. boil them together with a gentle fire, ſtirring them continually until they come to the body of an emplaſter: if you would have the Plaſter whiter, take but ʒ ix. of the Oil. *De ceruſa.*

℞ *Litharg. triti, acet. fortiſ. an.* ℔ ß. *ol. antiq.* ℔ j. *fiat emplaſtrum:* let the Oil be mingled with the Litharge for the ſpace of twelve hours, then boil them until they come to a good conſiſtence, putting in the Vinegar by little and little; but you ſhall not take it from the fire until the Vinegar be quite waſted away. *Tripharmacum, ſeu nigrum.*

℞ *Ol. vet.* ℔ iij. *axung. vet. ſine ſale,* ℔ ij. *litharg. trit.* ℔ iij. *vitriol.* ʒ iv. let the Oil be mingled with the Litharge for the ſpace of twelve hours, and boil them to a good conſiſtence, then add to the axungia, ſtirring them continually with a Spatter made of the Palm-tree, Reed, or Willow, and being ſufficiently boiled, take it from the fire, and add the Vitriol in fine powder. *Diapalmæ, ſeu diacalcitheos.*

℞ *Picis naval. aloes, an.* ʒ iij. *litharg. ceræ, coloph. galban. ammoniac. an.* ʒ ij. *viſci querni,* ʒ vj. *gypſi uſt. utriuſque ariſtoloch. an.* ʒ iv. *myrrhæ, thuris, an.* ʒ vj. *tereb.* ʒ ij. *pulveris vermium terreſtrium, gallar. utriuſque conſolid. bol. arm. an.* ʒ iv. *ſang. humani,* ℔ j. *fiat. emplaſt.* If you would have it of a very good conſiſtence, you may add of the Oil of Myrtils or Maſtick, ℔ ß. you ſhall make it thus: Take the skin of a Ram cut in pieces, and boil it in an hundred pints of Water and Vinegar until it come to a glue or ſtiff gelly, in which you ſhall diſſolve the *viſc. querc.* then add the Pitch and Wax broken into ſmall pieces, and if you will you may add the Oil with them, afterwards the *galban.* and *ammoniac.* diſſolved in Vinegar, being mingled with the terebinth, may be added. Then add the Litharge, *gypſum, bol. ariſtoloch. conſolida, vermes, & ſang. human.* At laſt the Myrrh, *thus, colophon,* and *aloe,* ſtirring them continually; and that they may be the better mingled, work the Plaſter with a hot Peſtle in a Mortar. *Contra Ruptu-ram.*

℞ *Mucag. ſem. lini, rad. alth. fœnugr. median. corticis ulmi, an.* ʒ iv. *olei liliacei, cham. aneth. an.* ʒ j. ß. *ammon. opopanac. ſagap. an.* ʒ ß. *croci,* ʒ ij. *ceræ nov.* ℔ ß. *tereb.* ʒ ß. *fiat. empl. Fernelius* hath ʒ xx. of Wax: the Wax being cut ſmall muſt be mingled with the Oils and the Mucilages, ſtirring them continually with a wooden Spatter till the liquor be conſumed. Then the gums diſſolved and mingled with the terebinthina muſt be added, and laſt of all the Saffron finely powdered. *De Mucaginibus.*

℞ *Ol. roſ. myrtil. ung. populeon, an.* ʒ iv. *pinguedinis gallin.* ʒ ij. *ſebi arietis caſtrati, ſepi vaccini, an.* ʒ vj. *pingued. porci,* ʒ x. *litharg. auri, argenti, an.* ʒ iij. *ceruſ.* ʒ iv. *minii,* ʒ iij. *tereb.* ʒ iv. *ceræ q. ſ. fiat emplaſtrum vel ceratum molle.* The *lithargyros, ceruſa,* and *minium,* are to be brought into fine powder, ſeverally being ſprinkled with a little Roſe water, leſt the fineſt of it ſhould fly away; theſe being mingled with the Oil of Roſes and Myrtles, with a gentle fire may be boiled until they come to the conſiſtence of Honey; then add the *axungiaes,* and boil them till the whole grow black, after add the *ſebum,* and that being diſſolved, take it from the fire, and then add the *unguentum populeon,* and ſome Wax if there be need; and ſo bring it to the form of a Plaſter. *De minio.*

℞ *Litharg. puri pul.* ʒ xij. *ol. irin. chamæm. aneth. an.* ʒ viij. *mucag. ſem. lini, fœnug. rad. alth. ficuum ping. uvar. paſſar. ſucci ireos, ſcillæ, æſipi, ichthyocollæ, an.* ʒ xij. ß. *tereb.* ʒ iij. *reſ. pini, ceræ flavæ, an.* ʒ ij. *fiat emplaſtrum:* The Litharge is to be mingled with the Oil before it be ſet to the fire, then by a gentle fire it is to be boiled to a juſt conſiſtence; after the mucilage by degrees muſt be put in, which being conſumed the juices muſt be added and the ichthyocolla, and they being waſted too, then put to the Wax and Roſin, then taking the whole from the fire, add the *æſipus* and *terebinthina.* *Diachylon magnum.*

We uſe Plaſters when we would have the remedy ſtick longer and firmer to the part, and would not have the ſtrength of the Medicament to flie away or exhale too ſuddenly. The uſe of Plaſters.

CHAP. XXVIII.

Of Cataplaſms and Pultiſſes.

CAtaplaſms are not much unlike to Emplaſters leſs properly ſo called, for they may be ſpred upon linnen cloths and ſtoups like them, and ſo applied to the grieved parts. They are compoſed of Roots, Leaves, Fruits, Flowers, Seeds, Herbs, Juices, Oils, Fats, Marrows, Meals, Roſins. Of theſe ſome muſt be boiled, others crude. The boiled are made of Herbs boiled tender, and ſo drawn through an hair Searſe, adding Oils and Axungiaes thereto. The crude are made of Herbs beaten, or their juices mixed with Oil and Flower, or other Powders appropriate to the part or diſeaſe, as the Phyſician ſhall think fit. The quantity of Medicins entering theſe compoſitions can ſcarce be defined, for that they muſt be varied as we would have the compoſition of a ſofter or harder body. Verily they ought to be more groſs and denſe when as we deſire to ripen any thing, but more ſoft and liquid when we endeavour to diſcuſs. We uſe Cataplaſms to aſſwage pain, digeſt, diſcuſs and reſolve unnatural tumors and flatulencies. They ought to be The matter of Cataplaſms. Their uſe.

moderately hot and of ſubtle parts, ſo to attract and draw forth; yet their uſe is ſuſpected, the body being not yet purged, for thus they draw down more matter into the affected part. Neither muſt we uſe theſe when as the matter that is to be diſcuſſed is more groſs and earthy, for thus the ſubtler parts will be onely diſcuſſed, and the groſs remain impact in the part, unleſs your Cataplaſm be made of an equal mixture of things, not onely diſcuſſing, but alſo emollient, as it is largely handled by *Galen.* *Lib. 2. ad glauc. ubi de ſcirrho.*

This ſhall be largely illuſtrated by examples. As, ℞ *Medul. panis,* ℔ ß. *decoquantur in lacte pingui, adde olei chamæm.* ℥ ß. *axung. galin.* ℥ j. *fiat cataplaſma.* Or, ℞ *Rad. alth.* ℥ iij. *fol. malv. ſenecionis, an.* m. j. *ſem. lini, fœnug. an.* ʒ ij. *ficus, ping.* nu. vj. *decoquantur in aqua, & per ſetaceum tranſmittantur, addendo olei lilior.* ℥ j. *far. hord.* ℥ ij. *axung. porcin.* ℥ j. ß. *fiat cataplaſma.* Or, ℞ *Far. fab. & orob. an.* ℥ ij. *pulv. chamæm. & melil. an.* ʒ iij. *ol. irin. & amygd. amar. an.* ℥ j. *ſucci rut.* ℥ ß. *fiat cataplaſma.* Pultiſes differ not from Cataplaſms, but that they uſually conſiſt of Meals boiled in Oil, Water, Honey, or Axungia. Pultiſes for the ripening of tumors are made of the Flour of Barley, Wheat and Milk, eſpecially in the affects of the entrails; or elſe to drie and bind, of the Meal of Rice, Lentils, or *Orobus*, with Vinegar; or to cleanſe, and they are made of Honey, the Flour of Beans and Lupines, adding thereto ſome old Oil, or any other Oil of hot quality, and ſo making a diſcuſſing Pultiſe. Alſo Anodyne Pultiſes may be made with Milk; as thus for example, ℞ *Farin. triticeæ,* ℥ ij. *micæ panis puriſſimi,* ℥ iij. *decoquantur in lacte, & fiat pulticula.* ℞ *Farin. hordei & fab. an.* ℥ ij. *far. orob.* ℥ iij. *decoquantur in hydromeilte, addendo mellis* quart. j. *olei amyg. amar.* ℥ ij. *fiat pulticula.* We uſe Pultiſes for the ſame purpoſe as we do Cataplaſmes, to the affects both of the internal and external parts. We ſometimes uſe them for the killing of Worms, and ſuch are made of the Meal of Lupines boiled in Vinegar, with an Oxes gall, or in a decoction of Wormwood, and other ſuch like bitter things.

An Anodyne Cataplaſm. A ripening Cataplaſm. A diſcuſſing Cataplaſm. How Pultiſes differ from Cataplaſms. A ripening Cataplaſm.

CHAP. XXIX.

Of Fomentations.

A *Fotus* or Fomentation is an evaporation or hot lotion, chiefly uſed to mollifie, relax, and aſſwage pain, conſiſting of Medicins having theſe faculties. A Fomentation commonly uſeth to be moiſt, being uſually made of the ſame things as Embrocations, to wit, of Roots, Seeds, Flowers, boiled in Water or Wine. The roots here uſed are commonly of Mallows, Marſh-mallows, and Lillies. The Seeds are of Mallows, Marſh-mallows, Parſley, Smallage, Line, Fenugreek. Flowers are of Camomil, Melilot, Figs, Raiſins, and the like: all which are to be boiled in Wine, Water, or Lye, to the conſumption of the third part, or the half: as,

℞ *Rad. alth. & lil. an.* ℥ ij. *ſem lini, fœnug. cumin. an.* ʒ iij. *flo. cham. melil. & aneth. an.* p. j. *ſummit. orig.* m. ß. *bulliant in æquis partibus aquæ & vini, aut in duabus partibus aquæ, & una vini, aut in Lixivio cineris ſarmentorum, ad tertiæ partis conſumptionem, fiat fotus.* In imitation hereof you may eaſily deſcribe other Fomentations, as occaſion and neceſſity ſhall require.

We uſe Fomentations before we apply Cataplaſms, Ointments, or Plaſters to the part, that ſo we may open the breathing places or pores of the skin, relax the parts, attenuate the humour, that thus the way may be the more open to the following Medicins. The body being firſt purged, Fomentations may be uſed to what parts you pleaſe. They may be applied with a female Spunge, for it is gentler and ſofter than the male: with Felt, woollen Cloths, or the like dipped in the warm decoction wrung out, and often renewed; otherwiſe you may fill a Swines bladder half full (eſpecially in pains of the ſides) of the decoction, or elſe a ſtone-bottle, ſo to keep hot the longer; yet ſo, that the bottle be wrapped in Cotton, Wool, or the like ſoft thing, that ſo it may not by the hardneſs and roughneſs offend the part, according to *Hippocrates.* *2. De victu in acutis.*

Their uſe.

CHAP. XXX.

Of Embrocations.

AN *Embroche* or Embrocation, is a watering, when as from an high we (as it were) ſhower down ſome moiſture upon any part. This kind of remedy is chiefly uſed in the parts of the head, and it is uſed to the coronal ſuture, for that the skull, is more thin in that part, ſo that by the *ſpiracula* or breathing places of this ſuture, more open than thoſe of the other ſutures, the force of the Medicin may more eaſily penetrate unto the *Meninges*, or membrans of the brain. The matter of Embrocations is Roots, Leaves, Flowers, Seeds, Fruits, and other things, according to the intention and will of the Phyſician. They are boiled in Water and Wine, to the half or third part. Embrocations may alſo be made of Lye or Brine againſt the cold and humid affects of the brain. Sometimes of Oil and Vinegar, otherwhiles of Oil onely. ℞ *Fol. plantag. & ſolan. an.* m. j. *ſem. portul. & cucurb. an.* ʒ ij. *myrtil.* ʒ j. *flor. nymph. & roſ. an.* p. ß. *fiat decoct. ad* ℔ j. *cum aceti* ℥ ij. *ſi alte ſub eundem ſit ex qua irrigetur pars inflammata.*

What an Embrocation is.

In affects of the brain, when we would repercuſs, we often and with good ſucceſs uſe Oil of Roſes with a fourth part of Vinegar.

We uſe Embrocations, that together with the air drawn into the body by the *Diaſtole* of the Arteries, the ſubtler part of the humour may penetrate, and ſo cool the inflamed part; for the chief uſe of Embrocations is in hot affects. Alſo we uſe Embrocations, when as for fear of an hæmorrhagy, or the flying aſunder of a broken or diſlocated member, we dare not looſe the bandages wherein the member is bound. For then we drop down ſome decoction or oil from high upon the bandages, that by theſe the force of the medicin may enter into the affected member.

Their uſe.

CHAP.

CHAP. XXXI.

Of Epithemes.

Epithema, or an Epitheme, is a compoſition uſed in the diſeaſes of the parts of the lower and middle belly, like to a fomentation, and not much unlike an embrocation. They are made of Waters, Juices, and Powders, by means whereof they are uſed to the heart, cheſt, liver, and other parts. Wine is added to them for the more or leſs penetration, as the condition of the hot or cold affect ſhall ſeem to require; for if you deſire to heat, more Wine muſt be added, as in ſwooning by the clotting of bloud, by the corruption of the ſeed, by drinking ſome cold poiſon; the contrary is to be done in a fainting by diſſipation of the ſpirits by feveriſh heats, alſo Vinegar may be added. The matter of the Medicins proper to the entrails is formerly deſcribed, yet we commonly uſe the *ſpecies* of Electuaries, as the *ſpecies elect. triaſantali*, the Liver being affected, and Diamargariton in affects of the heart. The proportion of the Juices or Liquors to the Powders uſes to be this, to to every pint of them ℥ j. or ʒ j. ß. of theſe, of Wine or elſe of Vinegar ʒ j. You may gather this by the following example: What an Epitheme is. In the ſixth Chapter.

℞ *Aqu. roſ. bugl. borag. an.* ℥ iij. *ſucci ſcabioſ.* ℥ ij. *pul. elect. diamarg. frigid.* ℥ ij. *cort. citri ſicci* ℥ j. *coral. roſ. ebor. an.* ʒ ß. *ſem. citri & card. ben. an.* ʒ ij. ß. *croci & moſchi, an. gr.* v. *addendo vini albi* ℥ ij. *fiat Epithema pro corde.* A cordial Epitheme.

Epithemes are profitably applied in hectick and burning Fevers to the Liver, heart, and cheſt, if ſo be that they be rather applied to the region of the lungs than of the heart; for the heat of the lungs being by this means tempered, the drawn in air becomes leſs hot in the peſtilent and drying Fevers. They are prepared of humecting, refrigerating, and cordial things, ſo to temper the heat, and recreate the vital faculty. Sometimes alſo we uſe Epithemes to ſtrengthen the heart, and drive therehence venenate exhalations, lifted or raiſed up from any part which is gangrenate or ſphacelate. Some Cotton, or the like, ſteeped or moiſtned with ſuch liquors and powders warmed, is now and then to be applied to the affected entrail: this kind of remedy, as alſo all other topick and particular Medicins, ought not to be uſed, unleſs you have firſt premiſed general things. Their uſe.

CHAP. XXXII.

Of Potential Cauteries.

That kind of Pyrotick which is termed a Potential Cautery, burns, and cauſeth an eſchar. The uſe of theſe kinds of Cauteries is to make evacuation, derivation, revulſion, or attraction of the humours by thoſe parts whereto they are applied. Wherefore they are often and with good ſucceſs uſed in the punctures and bites of venomous Beaſts, in a venomous, as alſo in a peſtilent Bubo and Carbuncle, unleſs the inflammation be great: for the fire doth not onely open the part, but alſo retunds the force of the poiſon, calls forth, and plentifully evacuates the conjunct matter. Alſo they are good in phlegmatick and contumacious tumours; for by their heat they take away the force and endeavours of our weak heat. Alſo they are profitably applied to ſtanch bleedding, or eat and waſte the ſuperfluous fleſh of ulcers and wens, to bring down the callous lips of ulcers, and other things too long here to inſiſt upon. The uſe of potential Cauteries.

The materials of theſe Cauteries are Oak-aſhes, Pot-aſhes, the aſhes of Tartar, of Tithymals or Spurges, the Fig-tree, the ſtalks of Coleworts, and Beans, cuttings of Vines, as alſo *ſal ammoniacum*, *alkali*, *axungia vitri*, *ſal nitrum*, Roman Vitriol, and the like; for of theſe things there is made a Salt, which by its heat is cauſtick and eſcharotick, like to an hot iron and burning coal: Therefore it violently looſes the continuity by eating into the skin, together with the fleſh thereunder. I have thought good here to give you divers forms of them. The matter of them.

Take of unquencht Lime extinguiſhed in a bowl of Barbers Lye three pounds: When the Lye is ſetled let it be ſtrained, and into the ſtraining put of *Axungia vitri*, or Sandiver, calcined Argol, of each two pounds, of *Sal nitrum & ammoniacum*, of each four ounces, theſe things muſt be beaten into a groſs powder, then muſt they be boiled over the fire, and after the boiling let them remain in the Lye for four and twenty hours ſpace, being often ſtirred about, and then ſtrained through a thick and double linnen cloth, leſt any of the earthy droſs get thorow together with the liquor. This ſtrained liquor, which is as clear as Water, they call *Capitellum*, and they put it in a brazen Baſin, ſuch as Barbers uſe, and ſo ſet it upon the fire, and as ſoon as it boils, they keep it with continual ſtirring, leſt the Salt ſhould adhere to the Baſin; the *Capitellum* being half boiled away, they put in two ounces of powdered vitriol, ſo to haſten the falling of the eſchar, and ſo they keep the Baſin over the fire till all the liquor be almoſt waſted away. Then they cut iuto pieces the Salt or that earthy matter which remains after the boiling away of the *Capitellum*, and with a Knife or hot iron Spatula, form them into Cauteries of ſuch figure and magnitude as they think fitting, and ſo they lay them up, or keep them for uſe in a Vial or Glaſs cloſely ſtopped, that the air get not in: Or, The forms of them.

Take a bundle or ſufficient quantity of Bean-ſtalks or husks of Colewort ſtalks two little bundles, of cuttings of Vines four handfuls, burn them all to aſhes, which put into a Veſſel of River-water, ſo let them infuſe for a days ſpace, being ſtirred ever now and then; to this add two pounds of unquenched Lime, of *Axungia vitri* half a pound, of calcined Tartar two pounds, of *Sal niter* four ounces, infuſe all theſe, being made into powder, in the foreſaid Lye for two or three days ſpace, often ſtirring it, then ſtrain the *Capitellum* or liquor through a thick cloth until it become clear. Put it into a Baſin, and ſet it over the fire, and when as the moiſture is almoſt

wholly ſpent, let two or three ounces of Vitriol be added; when the moiſture is ſufficiently evaporated, make cauteries of that which remains, after the formerly mentioned manner.

Take of the aſhes of ſound, knotty old Oak as much as you pleaſe, make thereof a Lye; pour this Lye again upon other freſh aſhes of the ſame Wood: let this be done three or four times, then quench ſome Lime in this Lye, and of theſe two make a *Capitellum*, whereof you may make moſt approved Cauteries: For ſuch aſhes are hot in the fourth degree; and in like ſort the ſtones, whereof the Lime by burning becomes fiery and hot to the fourth degree: Verily I have made Cauteries of Oak-aſhes onely, which have wrought quickly and powerfully. The *Capitellum* or Lye is thought ſufficiently ſtrong, if that an Egg will ſwim therein without ſinking. Or,

The ſign of good *Capitellum.*

Take of the aſhes of Bean-ſtalks three pounds, of unquencht Lime, Argol, of the aſhes of Oak-wood, being all well burnt, of each two pounds. Let them for two days ſpace be infuſed into a veſſel full of Lye made of the aſhes of Oak-wood, and be often ſtirred up and down. Let this Lye then be put into another veſſel, having many holes in the bottom thereof, covered with ſtrums or ſtraw-pipes, that the *Capitellum* flowing thorow theſe ſtrait paſſages may become more clear. Let it be put twice or thrice upon the aſhes, that ſo it may the better extract the heat and cauſtick quality of the aſhes. Then putting it into a Barbers Baſin, ſet it over the fire, and when it ſhall begin to grow thick the fire muſt be increaſed, and Cauteries made of this concreting matter.

The faculty of the ſilken Cautery.

The following Cauteries are the beſt that ever I made trial of, as thoſe that applied to the arm in the bigneſs of a Peaſe, in the ſpace of half an hour without pain, eſpecially if the part of it ſelf be painleſs and free from inflammation, eat into the skin and fleſh even to the bone, and make an ulcer of the bigneſs of ones fingers end, and they leave an Eſchar ſo moiſt and humid, that within four or five days ſpace it will fall away of it ſelf without any ſcarification. I have thought good to call theſe Cauteries Silken or Velvet ones, not onely for that they are like Silk, gentle and without pain, but chiefly becauſe I obtained the deſcription of them of a certain Chymiſt (who kept it as a great ſecret) for ſome Velvet and much entreaty. Their deſcription is this:

The cauſe of the name.

Their deſcription.

Take of the aſhes of Bean-ſtalks, of the aſhes of Oak-wood well burnt, of each three pounds, let them be infuſed in a pretty quantity of River water, and be often ſtirred up and down, then add thereto of unquencht Lime four pounds, which being quencht, ſtir it now and then together for two days ſpace, that the *Capitellum* may become the ſtronger, then ſtrain it through a thick and ſtrong linnen cloth, and thus ſtrained, put it three or four times upon the aſhes, that ſo it may draw more of the cauſtick faculties from them, then boil it in a Barbers Baſin, or elſe an earthen one well leaded, upon a good Charcoal fire, until it become thick. But a great part of the ſecret or Art conſiſts in the manner and limit of this boiling; for this *Capitellum* becoming thick and concreting into Salt, muſt not be kept ſo long upon the fire, until all the moiſture ſhall be vaniſhed and ſpent by the heat thereof: for thus alſo the force of the foreſaid Medicins, which alſo conſiſts in a ſpirituous ſubſtance, will be much diſſipated and weakned; therefore before it be come to extreme drineſs, it ſhall be taken from off the fire, to wit, when as yet there ſhall ſome thick moiſture remain, which may not hinder the Cauteries from being made up into a form. The made up Cauteries ſhall be put up into a Glaſs moſt cloſely luted or ſtopped, that the air may not diſſolve them, and ſo they ſhall be laid up and kept in a dry place. Now becauſe the Powder of Mercury is near to Cauteries in the effect and faculty thereof, which therefore is termed *Pulvis Angelicus*, for the excellency, therefore I have thought good to give you the deſcription thereof, which is thus:

The deſcription of Mercury or Angelical powder.

℞ *Auripigmenti citrini, floris æris, an.* ℥ ij. *ſalis nitri,* ℔ j. ℈. *alumin. rochæ,* ℔ ij. *vitrioli* ℔ iij. Let them all be powdered, and put into a Retort, having a large Receiver well luted put thereto. Then ſet the Retort over a Fornace, and let the diſtillation be made firſt with a gentle fire, then encreaſed by little and little, ſo that the Receiver may wax a little reddiſh.

℞ *Argenti vivi,* ℔ ſ. *aquæ fortis,* ℔ j. *ponantur in phiala, & fiat pulvis, ut ſequitur.*

Take a large earthen pot, whereinto put the Vial or bolt-head wherein the *Argentum vivum* and *Aqua fortis* are contained, ſetting it in aſhes up to the neck thereof, then ſet the pot over a Fornace, or upon hot Coals, ſo that it may boil and evaporate away the *Aqua fortis*; neither in the *interim* will the Glaſs be in any danger of breaking when all the water is vaniſhed away, which you may know is done when as it leaves ſmoaking; ſuffer it to become cold, then take it forth of the aſhes, and you ſhall find calcined Mercury in the bottom, of the colour of red Lead, ſeparated from the white, yellow, or black excrement; for the white that concretes in the top is called Sublimate, which if it ſhould remain with the calcified Mercury, you ſhall make it into powder, and put it in a braſs veſſel upon ſome coals, ſtirring or turning it with a Spatula for the ſpace of an hour or two: for thus it will loſe a great part of the acrimony and biting, whence it will become leſs painful in the operation.

CHAP. XXXIII.

Of Veſicatories.

What Veſicatory and rubrifying Medicins are.

VEſicatory and rubrifying Ointments, Cataplaſms, or Plaſters, are made of acrid Medicins; which have power to draw forth to the ſuperficies of the body ſuch humours as lie deep, by exulcerating the skin and cauſing bliſters. Their matter is the ſame with ſeptick medicins; as, *Sinapi, anacordus, cantharides, euphorb. radices ſcyllæ, bryon.* and the like, which with Hony, Turpentine, Leaven, Gum, or Roſin, may be made into Cataplaſms, Ointments, or Plaſters; therefore the compoſure of Veſicatories, or rather their conſiſtence differs not from that of hard or ſoft Unguents. Therefore I will give you one example or deſcription of them, which is thus:

The deſcription of a Veſicatory.

℞ *Cantharid. euphorbii, ſinapi, an.* ℥ ſ. *mellis anacardini,* ℥ j. *modico aceti, & fermenti quod ſit ſatis, excipiantur, & fiat veſicatorium.* Some of the Ancients think it better to make up theſe Medicins with

with water rather than with vinegar, becauſe experience teacheth that vinegar abates the ſtrength of muſtard. We uſe this kind of medicin in long diſeaſes, when as we cannot any thing prevail with other medicins; eſpecially in the Head-ach, Meagrim, Epilepſie, Sciatica, Gout, the bites and punctures of venomous creatures, peſtilent Carbuncles, and other inveterate and contumacious diſeaſes. Their uſe.

Alſo we uſe them. when as we would reſtore life and ſtrength to a dead or decayed part, for thus they are drawn back together with the heat; for which purpoſe we muſt make choice of more gentle Veſicatories, as ſuch which onely rubrifie, ſo that the part may onely become red, and not be burnt: the part muſt firſt be ſtrongly rubbed, that the decayed and dull heat may be rouzed and ſtirred up, the pores of the skin more opened, that the force of the Medicin may enter the deeper into the body.

CHAP. XXXIV.

Of Collyria.

A *Collyrium* is a Medicin proper for the Eyes, made of Powder finely levigated and ground into the form of *Alchohol*, as the Arabians and our Alchymiſts term it: yet the word in a more general acception, is uſed for any liquid Medicin, made with Liquors and Powders, and applied or uſed to any part. Wherefore *Collyria* are of three kinds, ſome are moiſt or liquid, which are properly called *Collyria*; others drie, which are of the ſame conſiſtence with Trochiſces; others have the conſiſtence of Honey, or a liniment. The liquid ſerve for the greater and leſſer corners of the Eyes; thoſe of the conſiſtence of Honey are meet for the Apple of the Eye, but the drie are to be made into Powder, and ſo blown into the Eyes: alſo ſometimes they are to be diſſolved in ſome juice, or other convenient liquor, that ſo they may be made into moiſt *Collyria*. What a *Collyrium* is. The differences of them. Their uſe.

Therefore *Collyria* have diverſe uſes, and are applied to ſeveral parts according to the intention and counſel of the Phyſician: for liquid *Collyria* put into the corners of the eyes do more readily mitigate the heat of their inflammation, by reaſon they enter more eaſily by the tenuity of their ſubſtance; ſuch things as have a more firm conſiſtence adhere more tenaciouſly, and work more certainly. Moiſt *Collyria* are made of Juices, Mucilages, Waters of Herbs, Flowers, Seeds, Metalline bodies, Galls, and other ſuch like Medicins, which are Repercuſſives, Reſolvers, Detergents, Anodynes, and the like, according to the nature of the preſent diſeaſe.

Sometimes they are made of Juices and diſtilled Waters onely; otherwhiles Powders or drie *Collyria* made into Powder, are mixed with them, together with the white of an Egg. Powders are preſcribed to ʒ ij. and liquors to ʒ iv. or ʒ v. in Medicins for the Eyes; but for other parts, as when it is to be injected into the Urinary paſſage, they may be preſcribed to the quantity of a pint. Drie *Collyria* are made of Powders exceeding finely beaten or ground, and incorporated with ſome juice, whence it is that they differ little from Trochiſces. Wherefore the *Collyrium album Rhaſis* is now uſually termed a Trochiſce, and kept with them. Catharetick Powders are not applied in the form of a moiſt *Collyrium*, but in the form of a liniment, that is, incorporated with Fat or Oil. All theſe things ſhall be made more plainly by the following examples. Their matter.

℞ *Aq. plant. & roſar.* ʒ ij. *album ovi unum bene agitatum, miſce, fiat collyrium.* ℞ *Aq. roſar. & viol. an.* ʒ iij. *trochiſ. alb. Rhaſ. cum. opio,* ʒ ij. *fiat collyrium.* Or ℞ *Decoct. fænug.* ʒ iij. *mucag, ſem. lini,* ʒ ij. *ſacchar. cand.* ʒ j. *croci,* ℈ j. *fiat collyr.* ℞ *Thuris, myrrh.* ℈ ij. *tut. præpar. & antimon. lot. an.* ʒ ij. *cum ſucco chelidon. fiat collyrium in umbra ſiccand.* ℞ *Fellis perdic. aut lepor.* ʒ ſ. *ſucci fœnicul.* ʒ j. *ſacchar. cand.* ʒ ij. *ſyrup. roſ. excipiantur, fiat collyrium.* A Repercuſſive *Collyrium*. An Anodyne. A Detergent.

We uſe *Collyria* in Wounds, Ulcers, Fiſtulaes, Suffuſions, Inflammations, and other diſeaſes of the Eyes.

CHAP. XXXV.

Of Errhines and Sternutatories.

ERrhines are Medicins appointed to be put into the Noſe to purge the Brain of its excrementitious humours by the Noſtrils, or to deterge ſuch excrements as are therein, by reaſon of an *Ozæna, Polypus*, or the like diſeaſe. Errhines are either liquid or drie, or elſe hard, and of the conſiſtence of an emplaſter. Liquid Errhins, which uſually are to purge the head, are made of the juices of Herbs, as Beets, Coleworts, Marjerom, Pimpernel, Hyſſop or Balm, or of their decoctions taken alone, or mixed with Wine, or Syrup, as *oxymel ſcillit.* Syrup of Hyſſop, Roſes, or *mel anthoſat.* ſometimes Powders are mixed with the Liquors, as of Pepper, *Euphorb.* Pellitory of *Spain*, Hore-hound, *nigel. Rom. caſtor.* Myrrh, white Ellebore, Sow-bread, and other like, in a ſmall quantity, to wit, to ʒ j. little more or leſs according to the vehemency of the diſeaſe. We will make this more plain by examples. What an Errhine is. Their differences.

℞ *Succi betæ, majoran. braſſic. an.* ʒ j. *depurentur, & modice bulliant cum vini albi,* ʒ ij. *oxymel. ſcillit.* ʒ ß. *fiat Errhinum.* When as you deſire to attract more powerfully from the brain, you may diſſolve in Errhins ſome purging Medicins; as Agarick, *diaphœnicon. ſenna, carthamus*, and the like: hence doth ariſe the diſtinction of Errhins into ſuch as are meet to purge phlegm, choler, and melancholy. This following example is ſet down by *Rondeletius.* ℞ *Rad. pyreth. irid. an.* ʒ j. *puleg. calam. orig. an.* m. j. *agar. trochiſc.* ʒ iij. *flor. anthos & ſtœchad. an.* p. j. *fiat decoctio in colatur.* ℔ j. *diſſolve mellis anthoſati & ſcillit. an.* ʒ iij. *fiat caput purgium.* But it is better to this purpoſe to make uſe of purging Simples, as Agarick, Turbith, Coloquintida, and the like, then of Compoſitions, as *Diaphœnicon*, for theſe make the decoction more thick, and leſs fit to enter the paſſages of the Noſtrils, and the ſieve-like bones, but apt rather there to cauſe obſtruction, and intercept the freedom of reſpiration. The form of one. An Errhine purging phlegm.

℞ *Succi betæ,* ʒ j. *aq. ſalv. & beton. an.* ʒ ij. ſ. *caſtor.* ℈ ß. *piper. & pyreth. an.* ℈ j. *fiat caput purgium.* An Errhin with Powder.

Dric Errhines that are termed ſternutatories, for that they cauſe ſneezing, are made of powders onely, to which purpoſe the laſt mentioned things are uſed; as alſo aromatick things in a ſmall quantity, as to ʒ ij. at the moſt: as, ℞ *Major. nigel. caryoph. zinzib. an.* ϑ j. *acor. pyreth. & panis porcin. an.* ϑ ß. *euphorb.* ϑ j. *terantur, & in nares mittantur, aut inſufflentur.* Errhines of the conſiſtence of Emplaſters, by the Latins vulgarly called *Naſalia*, are made of the deſcribed Powders or Gums diſſolved in the juice of ſome of the forementioned herbs, incorporated with Turpentine and Wax, that ſo they may the better be made into a pyramidal form to be put into the noſtrils. As ℞ *Majoran. ſalv. nigel.* ϑij. *pip. alb. caryoph. galang. an* ϑ j. *pyreth. euphorb. an.* ʒ ß. *panis porcin. ellebor. alb. an.* ϑ j. *terantur, & in pulverem redigantur.* And then with Turpentine and Wax as much as ſhall be ſufficient; make them up into *Naſalia* of a pyramidal or taper faſhion. We uſe Errhines in inveterate diſeaſes of the brain; as the Epilepſie, fear of blindneſs, an Apoplexy, Lethargy, Convulſion, the loſt ſenſe of Smelling: yet we firſt uſe general remedies and evacuations, leſt by ſneezing and the like concuſſion of the brain for the excluſion of that which is offenſive thereto, there ſhould be made a greater attraction of impurity from the ſubjacent parts. Liquid things muſt be drawn up into the noſtrils warm out of the palm of the hand, to the quantity of ʒ ß. the mouth being in the interim filled with water, leſt the attracted liquor ſhould fall upon the palat, and ſo upon the lungs: drie Errhines are to be blown into the noſe with a pipe or quill: ſolid ones muſt be faſtned to a thred, that they may be drawn forth as need requires, when as they are put up into the noſtrils. The morning (the belly being empty) is the fitteſt time for the uſe of Errhines. If by their force the noſe ſhall be troubled with an itching, the pain thereof muſt be mitigated by Womans milk, or Oil of Violets. The uſe of attractive Errhines is hurtful to ſuch as are troubled with diſeaſes of the Eyes, or ulcers in the noſe, as it oft-times falls out in the *Lues Venerea*: wherefore in this caſe it will be beſt to uſe Apophlegmatiſms which may divert the matter from the Noſe.

A Sternutatory.

The matter of ſolid errhines.

Their uſe.

The manner of uſing them.

To whom they are hurtful.

CHAP. XXXVI.

Of Apophlegmatiſms, or Maſticatories.

Apophlegmatiſmoi in Greek, and *Maſticatoria* in Latine, are Medicins which kept or held in the mouth and ſomewhat chawed, do draw by the mouth forth of the brain excrementitious humours, eſpecially phlegm: now they are chiefly made four manner of ways; the firſt is when as the Medicins are received in Honey or Wax, and formed into Pills, and ſo given to chaw upon. The ſecond is, when as the ſame things are bound up in a fine linnen cloth, ſo to be held in the mouth. The third is, when as a decoction of acrid Medicins is kept in the mouth for a pretty ſpace. The fourth is, when as ſome acrid Medicin, or otherwiſe drawing phlegm, as pellitory of *Spain*, Maſtich, and the like, is taken of it ſelf to the quantity of a Haſel-nut, and ſo chawed in the mouth for ſome ſpace. The matter of Maſticatories is of the kind of acrid Medicins, as of Pepper, Muſtard, Hyſſop, Ginger, Pellitory of *Spain*, and the like; amongſt which you muſt make choice chiefly of ſuch as are not troubleſom by any ingrate taſte, that ſo they may be the longer kept in the mouth with the leſs offence and loathing. Yet Maſticatories are ſometimes made of harſh or acerb Medicins; as of Berberies, the ſtones of Prunes or Cherries, which held for ſome ſpace in the mouth, draw no leſs ſtore of phlegm than acrid things; for the very motion and rowling them up and down the mouth attracts becauſe it heats, compreſſes and expreſſes: the quantity of the Medicin ought to be from ß. to ʒ j. ß. as, ℞ *Pyreth. ſtaphyſag. an.* ʒ j. ß. *maſtich.* ʒ ß. *pulverentur & involvant. nodulis in maſticatoria.* Or ℞ *Zinzib. ſinap. an.* ʒ. j. *euphorb.* ϑ ij. *piper.* ʒ ß. *excipiantur melle, & fiant paſtilli pro maſticatoriis.* ℞ *Hyſſop. thym. origan. ſalv. an.* p. j. boil them in water to waſh the mouth withall. Or ℞ *Zinzib. caryoph. an.* ʒ j. *pyreth. pip. an.* ʒ ß. *ſtaphyſagr.* ʒ ij. *maſtiches* ʒ ß, *excipiantur, fiant paſtilli pro maſticatoriis.* We uſe maſticatories in old diſeaſes of the brain, dimneſs of the ſight, deafneſs, puſtles of the head and face, and ſometimes to divert the excrements which run to the Noſe being ulcerated.

What an Apophlegmatiſm is.

The differences,

The uſe of Maſticatories

Maſticatories are very hurtful to ſuch as have their Mouths or Throats ulcerated, as alſo to them whoſe lungs are ſubject to inflammations, diſtillations and ulcers; for then Errhines are more profitable to derive the matter of the diſeaſe by the noſtrils. For though the humour drawn from the Brain into the mouth by the means of the maſticatory, may be thence caſt forth by coughing and ſpitting, yet in the interim Nature will be ſo inured to that paſſage for the humour, ſo that it will run that way when as we ſleep, and fall down upon the parts thereunder, weak either by Nature or by Accident.

To whom hurtful.

The time fitteſt for the uſe of Apophlegmatiſms is the morning, the body being firſt purged; if any ingrateful taſte remain in the mouth, or adhere to the tongue by uſing of Maſticatories, you ſhall take it away by waſhing the mouth with warm water, or a decoction of Liquorice and Barley.

CHAP. XXXVII.

Of Gargariſms.

A Gargle or Gargariſm is a liquid compoſition fit for to waſh the mouth and all the parts thereof, to hinder defluxion and inflammation, to heal the ulcers, which are in thoſe parts, to aſſwage pain. Their compoſition is two-fold, the firſt is of a decoction of Roots, Leaves, Flowers, Fruits, and Seeds fit for the diſeaſe: now the decoction is to be made either in fair water alone, or with the admixture of white or red wine, or in the decoction of Licorice and Barley, or of pectoral things, as the intention of the Phyſician is to repel, cool, or hinder inflammation; as in the tooth-ach cauſed by matter which is yet in motion; to diſcuſs, as in the tooth-ach already at the height;

What a Gargle is.

The differences thereof.

height; or to cleanſe, as in the ulcers of the mouth; or to dry and bind, as when it is fit to heal the ulcers already cleanſed.

The other way of making of Gargariſms is without decoction, which is, when as we make them either of diſtilled Waters onely, or by mixing them with Syrups, Mucilages, Milk, the Whey of Goats milk carefully ſtrained. There are mixed ſometimes with a decoction, diſtilled Waters and Mucilages, *Mel roſatum*, *oxymel ſimplex*, *diamoron*, *dianucum*, *hiera picra*, *oxyſaccharum*, *ſyrup. de roſis ſiccis*, *ſyrupus acetoſus*, and other things, as the preſent caſe ſhall ſeem to require; as Alum, *Balauſtia*, Myrrh, *Olibanum*, Ginger, Pepper, Cinamon, drie Roſes, and many ſuch things; even ſo that oft-times there enter into Gargles ſuch Medicins as have force to draw from the brain, as Pellitory of *Spain*, Carthamus, Turbith, and ſuch things as have no bitterneſs, which is the cauſe that neither Agarick nor Coloquintida ought to enter into Gargariſms. Their matter.

The quantity of liquor for a Gargariſm is commonly from ℔ ß. to ℔ j. mix therewith ſome ℥ij. of Syrups, but put Powders ſparingly, as ſome ʒ iij. Alum may ſometimes be put into ℥ vj. let mucilages be extracted out of ʒ ij. of Seeds: let theſe ſerve for ſome examples.

℞ *Plant. polygon. oxaliclis, an.* m.j. *roſar.rub.* pß. *hordei* p j. *fiat decoctio ad.* ℥ viij. *in qua diſſolve ſyrupi myrtillorum,* ℥ vj. *dianucum* ℥ ß. *fiat Gargariſma.* Or, ℞ *Chamæmel. aneth. an.*pj. *roſ.rub.*pß. *paſſul.mund. & fœnum, an.* p iij. *decoquantur in æquis partibus vini & aquæ, ad* ℥ vj. *addendo mucag. ſem. lini, & fœnugr. an.* ℥ ij. *fiat Gargariſma.* An aſtringent Gargle. An Anodyne Gargle.

Or elſe, ℞ *Aq. plantag. liguſt. abſynth. an.*℥ij. *mellis roſati colati* ℥vj. *ſyrup. roſar. ſiccar. & de abſynth. an.* ℥ vj. *fiat Gargariſma.*

We uſe Gargles in the Morning faſting after general Purgations; they are ſometimes taken or uſed cold, when as malign, acrid, and thin humours fall down, ſometimes warm; but let theſe things be done according as the Phyſician ſhall adviſe. A deterſive.

CHAP. XXXVIII.

Of Dentifrices.

DEntifrices are Medicins prepared and ſerving divers ways to cleanſe, whiten, and faſten the Teeth; for from their uſe they take their name. Of theſe, ſome are dry, otherſome moiſt: of the dry, ſome have the form of opiates, others of Powder groſly beaten, but the moiſt are commonly made by diſtillation; the matter of drie Dentifrices is taken from detergent and drying things, ſuch as are Coral white and red, Harts-horn, Scuttle-bones, Alum, Cryſtal, Pumice, Salt-nitre, myrrh, Frankincenſe, *Balauſtia*, Acorns, all ſorts of ſhells of Fiſhes: all theſe are to be made into Powder either by burning, or without it; for Scuttle-bones burnt caſt forth a ſtinking and unpleaſant ſmell. To theſe for Smell ſake are added certain aromatick things, as Cinamon, Cloves, Nutmegs, and the like: ſuch Powders if mixed with ſome Syrups, as *oxymel ſcilliticum*, or with mucilage of Gum Arabick and Tragacanth, will become Opiats, to be made into a pyramidal form of ſome fingers length, round and ſquare, and ſharp pointed, that dried they may ſerve for Dentifrices. What a dentifrice is. The differences. The matter whereof they conſiſt.

Sometimes emollient Roots are boiled with Salt or Alum, that dried again they may be uſed for Dentifrices: moiſt ones are made of drying herbs, diſtilled together with drying and aſtringent things.

All the differences ſhall appear by the following examples. ℞ *Lapidis ſpong. pumicis & cornu cervi uſt. an.* ʒ ij. *coral. rub. & cryſtal. an.* ʒ j. *alum. & ſal. uſt. an.* ʒ j. ß. *cinamon. & caryoph. roſar. rub. pulver. an.* ʒ ij. *fiat pulvis pro dentifricio.* Or, ℞ *Oſſis ſæpiæ,* ʒ ß. *maſtiches, coralli rubri uſti, an.* ʒ ij. *corn. cervi uſti,* ʒ j. ß. *aluminis, carbonis, roriſmar. an.* ʒ j. *cinam.* ʒ ij. *fiat pulvis pro dentifricio.* Or, ℞ *Oſſis ſæpiæ, alum. & ſalis uſti, an.* ʒ j. *cryſtalli, glandium, myrrhæ, thuris, an.* ʒ ij. *corticis granatorum, macis, cinam. an.* ʒ j. *fiat pulvis qui excipiatur mucagine gummi tragacanth. & formentur pyramides longæ, ſiccand. pro dentifricio.* Or ℞ *Rad. malv. junior. & biſmalv. an.* ʒ ij. *coquantur in aqua ſalſa aut aluminoſa, deinde ſiccentur in furno pro dentifricio.* ℞ *Sali* ℥ vj. *alumin.* ʒ iij. *thuris, maſtiches, ſanguis draconis, an.* ʒ ß. *aquæ roſ.* ℥ vj. *diſtillentur in alembico vitreo pro dentifricio.* A Powder for a Dentifrice.

Dentifrices are not onely known good to poliſh, cleanſe, and ſtrengthen the teeth; but we alſo oft-times uſe them for the Tooth-ach, the Diſeaſes of the mouth, and ulcers of gums. You may uſe them in the morning, before and after meat. Their uſe.

The Ancients of Lentisk-wood made themſelves Tooth-picks, and ſuch devices to ſtrengthen their looſe Teeth, which alſo at this day is in uſe with thoſe of *Languedock*, with whom this Wood is plentiful, ſo that it may be brought thence for the uſe of Noble-men and Gentlemen; Myrrh may alſo ſerve for this ſame uſe, and any other aſtringent Wood.

Our people commonly uſe the ſtalks of Fennel, yet have they no faculty to faſten the Teeth, but their ſmell is grateful.

CHAP. XXXIX.

Of Bags or Quilts.

PHyſicians term a bag or *ſaculus*, the compoſition or mixture of drie and powdered Medicins put in a bag; therefore it is as it were a drie fomentation. Their differences are not drawn from any other thing than from the variety of the part whereto they are applied: ſuch as are for the head muſt be made into the faſhion of a Cap; thoſe which be for the whole ventricle muſt be made into the form of a Cithern; thoſe for the Spleen, like to an Oxes Tongue: laſtly, ſuch as are for the Liver, Heart, and other parts, muſt be made according to the figure of thoſe parts. Their matter is uſually taken from whole Seeds fried in a Frying-pan, or made into powder; there are ſome- What a bag or quilt is. Their differences.

ſometimes added Roots, Flowers, Fruits, Rinds, Cordial Powders, and other drie Medicins, which may be eaſily brought into Powder, and conduce to the grieved parts; the quantity is different according to the magnitude of the affected parts: In the Books of Practiſers it is commonly found preſcribed from ℥ iij. to ℥ vj. ß. Sometimes Flowers and dry Herbs are preſcribed by handfuls and pugils: and here there is need of an artificial conjecture to conceive and appoint a fit quantity of Powders: but let us give you ſome examples.

A quilt for the ſtomach. ℞ *Roſar. rub.* p.j. *maſtich.* ℥ ß. *coralli rub.* ℥iij. *ſem. aniſi, & fœnic. an.* ℥ ij. *nucis moſchat.* ℥ j. *ſummitat. abſynth. & menth. an.* m.j. *tritis omnibus, fiat ſacculus conſutus & compunctus pro ventriculo.*

A cap for a cold head. ℞. *Furfuris macri,* p. j. *milii.* ℥ j. *ſalis,* ℥ ij. *roſar, rub. flor. roriſmar. ſtœchados, caryoph. an.* m ij. *fol. beton. & ſalv. an.* ℥iij. *tritis omnibus fiat cucupha, interſuta & calefacta fumo thuris, & ſandarachæ exuſtorum, capiti apponatur.*

A quilt for the heart. ℞ *Flor. borag. bugloſſ. & viol. an.* p.ij. *cortic. citri ſicci, macis ligni aloes, raſuræ eboris, an.* ℥ j. *oſſis de corde cervi, croci, an.* ℈ ij. *fol. meliſſ.* m. ß. *pulveris diambræ,* ℥ ß. *contritis omnibus fiat ſacculus e ſerico pro corde, irrorandus aqua ſcabioſæ.*

Their uſe. We uſe bags for the ſtrengthening of the noble parts, as the brain, heart, liver: as alſo for thoſe leſs noble, as the ſtomach: laſtly for diſcuſſing flatulencies in what part ſoever: as in the Colick, and in a baſtard pluriſie proceeding from flatulencies. The powders muſt be ſtrewed upon carded bombaſt, that they run not together, and then they muſt be ſewed up or quilted in a bag of Linnen or Taffaty.

We often-times moiſten theſe bags in Wine or diſtilled water, and ſometimes not with the ſubſtance thereof, but by the vapour onely of ſuch liquors put into a hot diſh: thus oft-times the bags are heated by the vapour onely, and oft-times at the fire in a diſh by often turning them. Theſe if intended for the heart, ought to be of Crimſon or Scarlet Silk, becauſe the Scarlet-berry, called by the *Arabians Kermes*, is ſaid to refreſh and recreate the heart. Certainly they muſt always be made of ſome fine thing, whether it be Linnen or Silk.

CHAP. XL.

Of Fumigations.

What a Fumigation is. Their differences and matter. *Suffitus* or Fumigation is an evaporation of Medicins having ſome viſcous and fatty moiſture: of Fumigations ſome are drie, and otherſome moiſt, the drie have the form of Trochiſces or Pills: their matter ought to be fatty and viſcous, ſo that it may ſend forth a ſmoak by being burnt: ſuch are *Ladanum*, Myrrh, Maſtick, Pitch, Wax, Roſin, Turpentine, *Caſtoreum*, *Styrax*, Frankincenſe, *Olibanum*, and other gums, which, may be mixed with convenient Powders: for they yield them a body and firm conſiſtence; the fumigations that are made of Powder only, yield neither ſo ſtrong nor long a fume.

A Cephalick Fume. The quality of the Powders muſt be from ℥ ß. to ℥ j. ß. but the Gums to ℥ ij. as, ℞ *Sandarachæ, maſtiches, roſar. an.* ℥ j. *benjoini, galang. an.* ℥ iij. *terebinthin. excipiantur, & fiant trochiſci, quibus incenſis ſuffumigentur tegumenta capitis.* ℞ *Marchaſitæ,* ℥ ij. *bdelii, myrrhæ, ſtyracis, an.* ℥j. ß. *ceræ flavæ, & terebinth. quod ſufficit, fiant formulæ pro ſuffumigio.* ℞ *Cinnabaris,* ℥ ij. *ſtyracis & benjoini, an.* ʒ ij. *cum terebinth. fiant trochiſci pro ſuffumigio per embotum.*

For the hardneſs of the ſinews. For the relicks of the *Lues Venerea.* We uſe Fumigations in great obſtructions of the Brain, Ulcers of the Lungs, the *Aſthma*, an old Cough, Pains of the Sides, Womb, and the diſeaſes of ſome other parts; ſometimes the whole body is fumigated, as in the cure of the *Lues Venerea* to procure ſweat: ſometimes onely ſome one part whereto ſome relicks of the *Lues* adheres: ſuch Fumigations are made of *Cinnabaris*, wherein there is much *Hydrargyrum.* The Fume muſt be received by a funnel, that ſo it may not be diſperſed, but may all be carried unto the part affected, as is uſually done in the affects of the Womb and Ears.

The manner of uſing them. In fumigations for the Brain and Cheſt, the vapour would be received with open mouth, which thence may paſs by the weaſon into the Cheſt, by the Palat and Noſtrils into the Brain: but in the interim let the head be vailed, that none of the vapour may flie away. Moiſt Fumigations are made ſomewhiles of the decoction of herbs, otherwhiles of ſome one ſimple Medicin boiled in oil; ſometimes a hot fire-ſtone is quencht in Vinegar, Wine, *Aqua Vitæ*, or the like liquor, ſo to raiſe a humid vapour. We oft-times uſe this kind of Fumigation in overcoming ſchirrhous affects, when as we would cut, diſcuſs, penetrate deep, and drie: take this as an example thereof.

The manner of a moiſt Fumigation. ℞ *Laterem unum ſatis craſſum, aut marchaſitam ponderis* lb j. heat it red hot, and then let it be quencht in ſharp Vinegar, pouring thereon in the mean while a little *Aqua Vitæ*, make a Fumigation for the grieved part.

Fumes of the decoction of Herbs do very little differ from Fomentations properly ſo called; for they differ not in the manner of their compoſure, but onely in the application to the affected parts: therefore let this be an example of a humid Fumigation.

A moiſt Fume for the ears. ℞ *Abſynth. ſalv. rut. origan. an.* p.j. *rad. bryon. & aſar. an.* ℥ ß. *ſem. ſinap. & cumin. an.* ʒ ij. *decoquantur in duabus partibus aquæ, & una vini pro ſuffitu auris cum emboto:* and oft-times ſuch Fumigations are made for the whole body, whereof we ſhall treat hereafter.

CHAP. XLI.

Of a particular or Half-Bath.

What an *Inſeſſus* is. A *Semicupium* or Half-bath, is a Bath for the one half of the body; that is, for the parts from the belly downwards: it is called alſo an *Inſeſſio*, becauſe the Patient ſitteth to bathe in the decoction of Herbs: in which form and reſpect a *Semicupium* differs from a Fomentation;

tation; for it is compoſed of the ſame matter, to wit a decoction of Herbs, Roots, Seeds, Fruits, but in this the quantity of the decoction is the greater, as we ſhall teach by the following example. The matter.

℞ *Malv. biſmalv. cum toto, an.* m.j. ℈. *beton. ſaxifrag. pariet. an.* m.j. *ſem. melon. milii ſolis, alkekengi, an.* ℥ iij. *cicer. rub.* p. ij. *rad. apii, graminis, fœniculi, eryngii, an.* ℥ j. *decoquantur in ſufficiente aquæ pro inſeſſu.* A half-bath for the ſtone in the kidnies.

We uſe theſe half-baths in affects of the Kidnies, Bladder, Womb, Fundament, and lower belly, or otherwiſe when as the Patient by reaſon of weakneſs and fear of diſſipating the ſpirits, cannot ſuffer or away with a whole Bath. The manner of uſing it is thus: Fill ſome Bags with the boiled herbs, or other parts of Plants, and cauſe the Patient to ſit upon them; yet in the interim keep the vapours from the head leſt they ſhould offend it, by caſting over it a linnen cloth, or elſe let him not enter thereinto until the vapour be exhaled. The uſe. The manner of uſing it.

CHAP. XLII.

Of Baths.

BAths are nothing elſe than as it were a fomentation of the whole body, both for preſerving health, and the cure of Diſeaſes: this is a very commodious form of Medicin, and among other external Medicins much celebrated by the Greek, Arabian, and Latin Phyſicians. For a Bath, beſides that it digeſts the acrid humours, and ſooty excrements lying under the skin, mitigates pains and wearineſs, and corrects all exceſs of diſtemper: moreover in the cure of Fevers, and many other contumacious and inveterate Diſeaſes it is the chief and laſt remedy, and as it were the refuge of health, ſtored with pleaſing delight. Baths are of two ſorts, ſome Natural, others Artificial. Natural, are thoſe which of their own accord, without the operation or help of Art, prevail or excel in any Medicinal quality. For the water which of it ſelf is devoid of all quality that is perceivable by the taſte, if it chance to be ſtraitned through the veins of Metals, it furniſhes and impregnates it ſelf with their qualities and effects: hence it is that all ſuch water excells in a drying faculty, ſometimes with cooling and aſtriction, and otherwhiles with heat and a diſcuſſing quality. The Baths whoſe waters being hot or warm, do boil up, take their heat from the cavities of the Earth and Mines filled with fire; which thing is of much admiration whence this fire ſhould ariſe in ſubterrene places, what may kindle it, what feed or nouriſh it for ſo many years, and keep it from being extinct. Some Philoſophers would have it kindled by the beams of the Sun, others by the force of Lightning penetrating the bowels of the Earth; others by the violence of the Air vehemently or violently agitated, no otherwiſe then fire is ſtruck by the colliſion of a Flint and Steel,. Yet it is better to refer the cauſe of ſo great an affect unto God the maker of the Univerſe, whoſe providence piercing every way into all parts of the World, enters and governs the ſecret parts and paſſages thereof. Notwithſtanding they have ſeemed to have come neareſt the truth, who refer the cauſe of heat in Waters unto the ſtore of Brimſton contained in certain places of the Earth, becauſe among all Minerals it hath moſt fire and matter fitteſt for the nouriſhing thereof. Therefore to it they attribute the flames of fire which the *Sicilian* Mountain *Ætna* continually ſends forth. Hence alſo it is that the moſt part of ſuch waters ſmell of Sulphur, yet others ſmell of Alum, others of Nitre, others of Tar, and ſome of Coperas. The Faculties of Baths. Their differences. Natural Baths.

Now you may know from the admixture of what Metalline bodies the Waters acquire their faculties by their taſte, ſent, colour, mud, which adheres to the channels through which the water runs, as alſo by an artificial ſeparation of the more terreſtrial parts from the more ſubtil. For the earthy droſs which ſubſides or remains by the boiling of ſuch waters, will retain the faculties and ſubſtance of Brimſtone, Alum, and the like Minerals: beſides alſo, by the effects and the cure of theſe or theſe Diſeaſes, you may alſo gather of what nature they are. Wherefore we will deſcribe each of theſe kinds of Waters by their effects, beginning firſt with the Sulphureous. How to know whence the Baths have their efficacy.

Sulphureous Waters powerfully heat, dry, reſolve, open, and draw from the center unto the ſurface of the body; they cleanſe the skin troubled with Scabs and Tetters; they cauſe the itching of ulcers, and digeſt and exhauſt the cauſes of the Gout, they help pains of the Colick and hardned Spleens. But they are not to be drunk, not onely by reaſon of their ungrateful ſmell and taſte, but alſo by reaſon of the maliciouſneſs of their ſubſtance, offenſive to the inner parts of the body, but chiefly to the liver. The condition of natural ſulphureous waters.

Aluminous waters taſte very aſtrictively; therefore they drie powerfully, they have no ſuch manifeſt heat, yet drunk, they looſe the belly: I believe by reaſon of their heat and nitrous quality they cleanſe and ſtay defluxions, and the Courſes flowing too immoderately; they alſo are good againſt the Tooth-ach, eating Ulcers, and the hidden abſceſſes of the other parts of the mouth. Of aluminous waters.

Salt and nitrous Waters ſhew themſelves ſufficiently by their heat: they heat, dry, bind, cleanſe, diſcuſs, attenuate, reſiſt putrefaction, take away the blackneſs coming of bruiſes, heal ſcabby and malign ulcers, and help all œdematous tumors. Of ſalt and nitrous.

Bituminous Waters heat, digeſt, and by long continuance ſoften the hardned ſinews; they are different according to the various conditions of the bitumen that they waſh, and partake of the qualities thereof. Of bituminous.

Brazen Waters, that is, ſuch as retain the qualities of braſs; heat, drie, cleanſe, digeſt, cut, bind, are good againſt eating Ulcers, Fiſtulaes, the hardneſs of the Eye-lids, and they waſte and eat away the fleſhy excreſcences of the Noſe and Fundament. Of brazen.

Iron Waters cool, drie, and bind powerfully, therefore they help abſceſſes, hardned milts, the weakneſſes of the ſtomach and ventricle, the unvoluntary ſhedding of the Urin, and the too much flowing terms, as alſo the hot diſtemper of the Liver and Kidnies. Some ſuch are in *Lucan* Territory in *Italy*. Of iron.

Leaden Waters refrigerate, drie, and perform ſuch other operations as Lead doth; the like may be Of Leaden.

be ſaid of thoſe Waters that flow by Chalk, Plaſter, and other ſuch Minerals, as which all of them take and perform the qualities of the bodies by which they paſs.

Of hot baths. How Waters or Baths help cold and moiſt diſeaſes, as the Palſie, Convulſion, the ſtiffneſs and attraction of the Nerves, trembling, palpitations, cold diſtillations upon the joints, the inflations of the members by a dropſie, the Jaundice by obſtruction of a groſs, tough, and cold humour, the pains of the ſides, colick, and kidnies, barrenneſs in women, the ſuppreſſion of their Courſes, the ſuffocation of the Womb, cauſleſs wearineſs: thoſe diſeaſes that ſpoil the skin, as tetters, the leproſie of both ſorts, the ſcab, and other diſeaſes ariſing from a groſs, cold, and obſtruct humour, for they provoke ſweats.

To whom hurtful. Yet ſuch muſt ſhun them as are of a cholerick nature, and have a hot liver, for they would cauſe a *Cachexia* and Dropſie by over-heating the liver. Cold Waters or Baths heal the hot diſtemper of the body and each of the parts thereof, and they are more frequently taken inwardly than applied outwardly; they help the laxneſs of the bowels, as the reſolution of the retentive faculty of the ſtomach, Entrails, Kidnies, Bladder, and they alſo add ſtrength to them. Wherefore they both temper the heat of the liver, and alſo ſtrengthen it, they ſtay the *Diarrhœa*, Dyſentery, Courſes, unvoluntary ſhedding of Urin, the *Gonorrhœa*, Sweats and bleedings. In this kind are chiefly commendable the Waters of the Spaw in the Country of *Liege*, which inwardly and outwardly have almoſt the ſame faculty, and bring much benefit without any inconvenience, as thoſe that are commonly uſed in the drinks and broths of the Inhabitants.

The faculties of cold baths.

The Spaw.

Of artificial baths. In imitation of natural Baths, there may in want of them be made artificial ones, by the infuſing and mixing the Powders of the formerly deſcribed Minerals; as Brimſtone, Alum, Nitre, Bitumen: alſo you may many times quench in common or rain water, Iron, Braſs, Silver and Gold heated red hot, and ſo give them to be drunk by the Patient; for ſuch waters do oft-times retain the qualities and faculties of the Metals quenched in them, as you may perceive by the happy ſucceſs of ſuch as have uſed them againſt the Dyſentery.

The faculty of a Bath of warm water. Beſides theſe, there are alſo other Baths made by Art of ſimple Water, ſometimes without the admixture of any other thing, but otherwhiles with medicinal things mixed therewith, and boiled therein. But after what manner ſoever theſe be made, they ought to be warm, for warm water humects, relaxes, mollifies the ſolid parts, if at any time they be too drie, hard and denſe; by the aſcititious heat it opens the pores of the skin, digeſts, and attracts, and diſcuſſes fuliginous and acrid excrements remaining between the fleſh and the skin. It is good againſt Sun-burning and wearineſs, whereby the ſimilar parts are dried more than is fit. To conclude, whether we be too hot or cold, or too drie, or be nauſeous, we find manifeſt profits by Baths made of ſweet or warm water, as thoſe that may ſupply the defect of frictions and exerciſes: for they being the body to a mediocrity of temper, they increaſe and ſtrengthen the native colour, and by procuring ſweat diſcuſs flatulencies: therefore they are very uſeful in hectick Fevers, and in the declenſion of all Fevers, and againſt raving and talking idlely, for the procuring ſleep. But becauſe water alone cannot long adhere to the body, let Oil be mixed or put upon them, which may hold in the water, and keep it longer to the skin.

Why we put Oil into Baths.

Theſe Baths are good againſt the inflammations of the lungs and ſides, for they mitigate pain, and help forward that which is ſuppurative to excluſion, when as general remedies according to Art have preceded; for otherwiſe they will cauſe a greater defluxion to the afflicted parts: for a Bath (in *Galens* opinion) is profitably uſed to Diſeaſes when as the morbifick matter is concocted. To this purpoſe is choſen Rain-water, then River-water, ſo that it be not muddy, and then Fountain-water; the water of ſtanding Lakes and Fens is not approved of, for it is fit that the water which is made choice of for a Bath of ſweet water, ſhould be light and of ſubtil parts; for Baths of waters which are more than immoderately hot or cold, yield no ſuch commodity but verily they hurt in this, that they ſhut up or cloſe the pores of the body, and keep in the fuliginous excrements under the skin; other Baths of ſweet or freſh water conſiſt of the ſame matter as Fomentations do; whence it is that ſome of them relax, others mitigate pain, others cleanſe, and otherſome procure the Courſes, that is compounded of a decoction of Ingredients or Plants having ſuch operations. To theſe there is ſometimes added Wine, otherwhiles Oil, ſometimes freſh Butter or Milk, as when the Urin is ſtopped, when Nephritick pains are violent, when the Nerves are contracted, when the habit of the body waſtes and wrinkles with a hectick drineſs, for this corrugation is amended by relaxing things, but it is watered, as it were fatted by humecting things which may penetrate and tranſfuſe the oily or fatty humidity into the body thus rarified and opened by the warmneſs of a Bath.

Anodyne Baths are made of a decoction of Medicins of a middle nature, ſuch as are temperate and relaxing things, with which we may alſo ſometimes mix reſolving things; they are boiled in Water and Wine, eſpecially in pains of the Colick proceeding from vitreous phlegm, or groſs and thick flatulencies contained or ſhut up in the Belly, Kidnies, or Womb. In ſuch Baths it is not fit to ſweat, but onely to ſit in them ſo long until the bitterneſs of the pain be aſſwaged or mitigated, leſt the powers weakned by pain, ſhould be more reſolved by the breaking forth of ſweat: emollients are ſometimes mixed with gentle detergents, when as the skin is rough and cold, or when the ſcails or cruſt of ſcabs is more hard than uſual, then in concluſion we muſt come to ſtrong deterſives and driers; laſtly, to drying and ſomewhat aſtrictive Medicins ſo to ſtrengthen the skin, that it may not it ſelf ſo caſie and open to receive defluxions. By giving you one example, the whole manner of preſcribing a Bath may appear.

Why we muſt not continue in the bath till we ſweat.

A mollifying and anodyne Bath. ℞ *Rad. lilior. biſmalv. an.* ℔ ij. *malv. pariet. violar. an.* m. ß. *ſem. lini, fœnug. biſmalv. an.* ℔ j. *flor. cham. melil. anethi. an.* p. vj. *fiat decoctio in ſufficienti aquæ quantitate, cui permiſceto olei liliorum & lini ana* ℔ ij. *fiat balneum in quo diutius natet æger.*

Cautions to be obſerved in the uſe of Baths though noble remedies approved by uſe and reaſon, yet unleſs they be fitly and diſcreetly uſed in time, plenty, and quality, they do much harm; for they cauſe ſhakings and chilneſs, pains,

denſity

denſity of the skin, or too much rarefaction thereof, and oft-times a reſolution of all the faculties. Wherefore a man muſt be mindful of theſe cautions before he enter into a Bath: Firſt, that there be no weakneſs of any noble and principal bowel, for the weak parts eaſily receive the humors which the Bath hath diffuſed and rarified, the ways lying open, which tend from the whole body to the principal parts. Neither muſt there be any plenty of crude humours in the firſt region, for ſo they ſhould be attracted and diffuſed over all the body: therefore it is not onely fit that general Purgations ſhould precede, but alſo particular by the Belly and Urine: beſides, the Patient ſhould be ſtrong, that can faſting indure a Bath as long as it is needful. Laſtly, the Bath ought to be in a warm and ſilent place, leſt any cold air by its blowing, or the Water by its cold appulſe, cauſe a ſhivering or ſhaking of the body, whence a Fever may enſue.

The morning is a fit time for bathing, the ſtomach being faſting and empty, or ſix hours after meat, if it be requiſite that the Patient ſhould bathe twice a day, otherwiſe the meat yet crude would be ſnatched by the heat of the Bath, out of the ſtomach into the Veins and habit of the body. Many, of all the ſeaſons of the year, make choice of the Spring and end of Summer, and in theſe times they chuſe a clear day, neither troubled with ſtormy winds, nor too ſharp an air. As long as the Patient is in the Bath, it is fit that he take no meat, unleſs peradventure to comfort him he take a little bread moiſtned in Wine, or the juice of an Orange, or ſome Damask Prunes to quench his thirſt: his ſtrength will ſhew how long it is fit that he ſhould ſtay in; for he muſt not ſtay there to the reſolution of his powers, for in Baths the humid and ſpirituous ſubſtance is much diſſipated. Coming forth of the Bath, they muſt preſently get them to bed, and be well covered, that by ſweating, the excrements, drawn unto the skin by the heat of the Bath, may break out: the Sweat cleanſed, let them uſe gentle Frictions, or Walking; then let him feed upon meat of good juice and eaſie digeſtion, by reaſon that the ſtomach cannot but be weakned in ſome ſort by the Bath.

The fitteſt time for bathing.

How to order the Patient coming forth of the Bath.

The quantity of meat is judged moderate, the weight whereof ſhall not oppreſs the ſtomach: Venery after bathing muſt not be uſed, becauſe to the reſolution of the ſpirits by the Bath, it adds another new cauſe of further ſpending or diſſipating them. Some wiſh thoſe that uſe the Bath by reaſon of ſome contraction, pain, or other affects of the Nerves, preſently after bathing, to dawb or beſmear the affected nervous part with the Clay or Mud of the Bath, that by making it up as it were in this place, the virtue of the Bath may work more effectually, and may more throughly enter into the affected part.

Theſe cautions being diligently obſerved, there is no doubt but the profit by Baths will be great and wonderful: the ſame things are to be obſerved in the uſe of Stoves, or Hot-houſes, for the uſe and effects of Baths and Hot-houſes is almoſt the ſame, which the ancients therefore uſed by turn, ſo that coming forth of the Bath they entered a Stove, and called it alſo by the name of a Bath, as you may gather from ſundry places of *Galen* in his *Methodus Med.* wherefore I think it fit in the next to ſpeak of them.

CHAP. XLIII.

Of Stoves or Hot-houſes.

STOves are either drie or moiſt: Drie, by raiſing a hot and drie airy exhalation, ſo to imprint their faculties in the body, that it thereby waxeth hot, and the pores being opened, run down with ſweat. There are divers ways to raiſe ſuch an exhalation: at *Paris*, and whereſoever there are Stoves or publick Hot-houſes, they are raiſed by a clear fire put under a vaulted Furnace, whence it being preſently diffuſed, heats the whole Room; Yet every one may make himſelf ſuch a Stove as he ſhall judge beſt and fitteſt.

The differences of Stoves.

How made.

Alſo you may put red hot Cogle-ſtones or Bricks into a Tub, having firſt laid the bottom thereof with Bricks or iron Plates, and ſo ſet a ſeat in the midſt thereof; wherein the Patient ſitting, well covered with a Canopy drawn over him, may receive the exhalation ariſing from the ſtones that are about him, and ſo have the benefit of ſweating: but in this caſe we muſt oft look to and ſee the Patient; for it ſometimes happens that ſome, neglected by their Keepers otherwiſe imployed, become faint, and their ſenſe failing them by the diſſipation of their ſpirits by the force of the hot exhalation, have ſunk down with all their bodies upon the ſtones lying under them, and ſo have been carried half dead and burnt into their beds. Some alſo take the benefit of ſweating in a Fornace or Oven, as ſoon as bread is drawn out thereof. But I do not much approve of this kind of ſweating, becauſe the Patient cannot as he will, much leſs as he pleaſeth, lie or turn himſelf therein.

Humid Stoves or Sudatories are thoſe wherein Sweat is cauſed by a vapour or moiſt heat: this vapour muſt be raiſed from a decoction of Roots, Leaves, Flowers, and Seeds, which are thought fit for this purpoſe; the decoction is to be made in Water or Wine, or both together. Therefore let them all be put into a great veſſel well luted, from the top of whoſe cover Iron or Tin pipes may come into a Bathing Tub ſtanding near thereto, between the two bottoms thereof, by means whereof the hot vapour may enter thereinto, and diffuſe it ſelf therein. Now it is fit the Bathing-tub ſhould be furniſhed with a double bottom, the one below and whole, the other ſomewhat higher and perforated with many holes, whereupon the Patient ſitting, may receive a Sudorifick vapour over all his body: now this vapour, if at any time it become too hot, muſt be tempered by opening the hole, which muſt for the ſame purpoſe be made in the top of the Pipe, that ſo it may be opened and ſhut at pleaſure. In the interim the Tub ſhall be cloſely covered wherein the Patient ſits, he putting forth onely his head, that ſo he may draw in the cold air. In defect of ſuch Pipes, the Herbs ſhall be boiled by themſelves in a Caldron or Kettle, and this ſhall be ſet thus hot into the Bathing-tub at the Patients feet, and ſo by caſting into it heated ſtones, a great and ſudorifick vapour ſhall be raiſed.

A vaporous Stove or Bath.

The

The delineation of a Bathing-tub having a double bottom, with a Veſſel near thereto, with Pipes coming therefrom, and entering between the two bottoms of the Tub.



CHAP. XLIV.

Of Fuci, *that is, Waſhes, and ſuch things for the ſmoothing and beautifying of the skin.*

THis following Diſcourſe is not intended for thoſe Women which addicted to filthy luſt, ſeek to beautifie their Faces as baits and allurements to filthy pleaſures: but it is intended for thoſe onely, which the better to reſtrain the wandring luſts of their husbands, may endeavour by Art to take away thoſe ſpots and deformities which have happened to fall on their faces either by accident or Age.

As the colour of the skin is, ſuch is the humour that is thereunder.

The colour that appears in the face, either laudable or illaudable, abundantly ſhews the temper both of the body, as alſo of thoſe humours that have the chief dominion therein: for every humour dies the skin of the whole body, but chiefly of the face, with the colour thereof: for choler bearing ſway in the body, the face looks yellowiſh; phlegm ruling, it looks whitiſh or pale; if melancholy exceed, then blackiſh or ſwarth; but if bloud have the dominion, the colour is freſh and red. Yet there are other things happening externally which change the native colour of the face, as Sunburning, cold, pleaſure, ſorrow, fear, watching, faſting, pain, old diſeaſes, the corruption of meats and drinks: for the flouriſhing colour of the cheeks is not onely extinguiſhed by the immoderate uſe of Vinegar, but by drinking of corrupt Waters the face becomes ſwollen and pale.

On the contrary, laudable meats and drinks make the body to be well coloured and comely, for that they yield good juice, and conſequently a good habit. Therefore if the ſpots of the face proceed from the plenitude and ill diſpoſition of humours, the body ſhall be evacuated by bloud-letting; if from the infirmity of any principal bowel, that muſt firſt of all be ſtrengthened; but the care of all things belongs to the Phyſician: we here onely ſeek after particular remedies which may ſmooth the face, and take away the ſpots and other defects thereof, and give it a laudable colour.

Waters where with to waſh the face.

Firſt the face ſhall be waſhed with the water of Lilly-flowers, of Bean-flowers, Water-lillies, of diſtilled Milk, or elſe with the Water wherein ſome Barley or Starch hath been ſteeped. The dried face ſhall be anointed with the Ointments preſently to be deſcribed; for ſuch waſhing cleanſeth and prepareth the Face to receive the force of the Ointments, no otherwiſe than an alumed Lye prepares the hairs to drink up and retain the colour that we deſire. Therefore the Face being thus cleanſed and prepared, you may uſe the following Medicins, as thoſe that have a faculty to beautifie, extend, and ſmooth the skin: as,

Compound liquors wherewith to waſh the face.

℞ *Gum. tragacanth. conquaſſ.* ℥ ij. *diſtemperentur in vaſe vitreo cum* ℔ ij. *aquæ communis ſic gummi diſſolventur, inde albeſcet aqua.* Or elſe, ℞ *Lithargyri auri,* ℥ ij. *ceruſ. & ſalis com. an.* ℥ ß. *aceti aquæ plant. an.* ℥ ij. *caphur.* ℥ ß. *macerentur lithargyros & ceruſa in aceto ſeorſim per tres aut quatuor horas, ſal vero & camphora in aqua quam inſtituto tuo aptam delegeris:* then filter them both ſeveral and mix them together being ſo filtered, when as you would uſe them.

Virgins milk.

℞ *Lactis vaccini,* ℔ ij. *aranciorum & limon. an.* nu.iv. *ſaccari albiſſimi, & alum. roch. an.* ℥ j. *deſtillentur omnia ſimul:* let Limons and Oranges be cut into ſlices, and then be infuſed in Milk, adding thereto the Sugar and Alum, then let them all be diſtilled together in *Balneo Mariæ*; the water that comes thereof will make the face ſmooth and lovely. Therefore about bed-time it will be good to cover the Face with linnen cloths dipped therein. A Water alſo diſtilled of Snails gathered in a Vine-yard, Juice of Limons, the Flowers of white Mullain mixed together in equal proportion with a like quantity of the liquor contained in the bladders of Elm-leaves, is very good for the ſame purpoſe. Alſo this,

℞ *Micæ panis albi,* ℔ iv. *flor. fabar. roſar. alb. flor. nenuph. lilior. & ireos, an.* ℔ ij. *lactis vaccini,* ℔ vj. *ova,* nu.viij. *aceti opt.* ℔ j. *diſtillentur omnia ſimul in alembico vitreo, & fiat aqua ad faciei & manuum lotionem.* Or ℞ *Olei de tartaro,* ℥ iij. *mucag. ſem. pſilii,* ℥ j. *ceruſ. in oleo roſ. diſſolut.* ℥ j. ſ. *borac. ſal. gem. ar.* ℥ j. *fiat linimentum pro facie.* Or ℞. *Caponem vivum, & caſeum ex lacte caprino recenter confectum, limon.* nu.iv. *ovor.* nu.iv. *ceruſ. lot. in aq. roſar.* ℥ ij. *boracis,* ℥ j. ß. *camph.* ℥ ij. *aq. flor. fabar.* ℔ iv. *fiat omnium infuſio per* xxiv. *horas, poſtea deſtillentur in alembico vitreo.*

The marrow of Sheeps-bones good to ſmooth the face.

There is a moſt excellent *fucus* made of the marrow of Sheeps-bones, which ſmooths the roughneſs of the skin, beautifies the face; now it muſt be thus extracted. Take the bones, ſevered from the fleſh by boiling, beat them, and ſo boil them in water; when they are well-boiled, take them from the fire, and when the water is cold, gather the fat that ſwims upon it, and therewith anoint

your

your face when as you go to bed, and waſh it in the morning with the formerly preſcribed Water.

℞ *Salis ceruſſ.* ʒ ij. *ung. citrin. vel ſpermat. ceti,* ℥ j. *malaxentur ſimul, & fiat linemtntum, addendo olei ovor.* ʒ ij. The *Sal ceruſſæ* is thus made: Grind Ceruſs into very fine powder, and infuſe ℔ j. thereof in a bottle of diſtilled Vinegar for four or five days, then filter it, then ſet that you have filtred in a glazed earthen veſſel over a gentle fire until it concrete into Salt, juſt as you do the *capitellum* in making of Cauteries. How to make *Sal ceruſſa.*

℞ *Excrementi lacert. oſſis ſæpiæ, tartari, vini albi, raſur. corn. cerv. farin. oriz. an. partes æquales, fiat pulvis, infundatur in aqua diſtillata amygdalarum dulcium, limacum vinealium, flor. nenuph. huic addito melis albi par poudus:* let them all be incorporated in a marble Morter, and kept in a glaſs or ſilver veſſel, and at night anoint the face herewith; it wonderfully prevails againſt the redneſs of the face, if after the anointing it you ſhall cover the face with a linnen cloth moiſtned in the former deſcribed Water.

℞ *Sublim.* ʒ j. *argent viv. ſaliv. extinct.* ʒ ij. *margarit. non perforat.* ʒ j. *caph.* ʒ j. ß. *incorporentur ſimul in mortario marmoreo, cum piſtillo ligneo, per tres horas ducantur & fricentur, reducanturque in tenuiſſimum pulverem, confectus pulvis abluatur aqua myrti & deſiccetur, ſerveturque ad uſum, adde foliorum auri & argenti,* nu. x. When as you would uſe this powder, put into the palm of your hand a little Oil of Maſtich, or of ſweet Almonds, then preſently in that Oil diſſolve a little of the deſcribed powder, and ſo work it into an ointment, wherewith let the face be anointed at bed-time: but it is fit firſt to waſh the face with the formerly deſcribed water, and again in the morning when you ariſe.

When the face is freed from wrinkles and ſpots, then you may paint the cheeks with a roſie and flouriſhing colour; for of the commixture of white and red ariſeth a native and beautiful colour: for this purpoſe take as much as you ſhall think fit of Braſil and Alchunet; ſteep them in Alum-water, and therewith touch the cheeks and lips, and ſo ſuffer it to dry in: there is alſo Spaniſh red made for this purpoſe; others rub the mentioned parts with a Sheeps-skin died red: moreover the friction that is made by the hand onely, cauſeth a pleaſing redneſs in the face, by drawing thither the bloud and ſpirits. How to paint the face.

CHAP. XLV.

Of the Gutta Roſacea, *or a fiery face.*

THis Treatiſe of *Fuci*, puts me in mind to ſay ſomething in this place of helping the preternatural redneſs which poſſeſſeth the noſe and cheeks, and oft-times all the face beſides, one while with a tumor, otherwhiles without, ſometimes with puſtles and ſcabs, by reaſon of the admixture of a nitrous and aduſt humour. Practitioners have termed it *Gutta roſacea.* This ſhews both more and more ugly in Winter than in Summer, becauſe the cold cloſeth the pores of the skin, ſo that the matter contained thereunder is bent up for want of tranſpiration, whence it becomes acrid and biting, ſo that as it were boiling up, it lifts or raiſeth the skin into puſtles and ſcabs; it is a contumacious diſeaſe, and oft-times not to be helped by Medicin. Why worſe in Winter then in Summer.

For the general method of curing this diſeaſe, it is fit that the Patient abſtain from Wine, and from all things in general that by their heat inflame the bloud, and diffuſe it by their vaporous ſubſtance: he ſhall ſhun hot and very cold places, and ſhall procure that his belly may be ſoluble, either by Nature or Art. Let bloud firſt be drawn out of the *baſilica*, then from the *vena frontis*, and laſtly from the vein of the noſe. Let Leeches be applied to ſundry places of the face, and cupping-glaſſes with ſcarification to the ſhoulders. Diet.

For particular or proper remedies, if the Diſeaſe be inveterate, the hardneſs ſhall firſt be ſoftned with emollient things, then aſſaulted with the following ointments, which ſhall be uſed or changed by the Chirurgeon as the Phyſician ſhall think fit. Remedies.

℞ *Succi citri,* ℥ iij. *ceruſ. quantum ſufficit ad eum inſpiſſandum, argenti vivi cum ſaliva & ſulphure vivo extincti* ʒ ß. *incorporentur ſimul, & fiat unguentum.* An approved Ointment.

℞ *Boracis,* ʒ ij. *farin. cicer. & fabar. an.* ʒ j. ß. *caph.* ʒ j. *cum melle & ſucco cepæ fiant trochiſci:* when you would uſe them, diſſolve them in Roſe and Plantain water, and ſpread them upon linnen cloths, and ſo apply them on the night-time to the affected parts, and ſo let them oft-times be renewed.

℞ *Unguenti citrini recenter diſpenſati,* ʒ ij. *ſulphuris vivi,* ℥ ß. *cum modico olei ſem. cucurb. & ſucci limonum, fiat unguentum:* with this let the face be anointed when you go to bed, in the morning let it be waſhed away with Roſe-water, being white by reaſon of bran infuſed therein: moreover ſharp Vinegar boiled with Bran and Roſe-water, and applied as before, powerfully takes away the redneſs of the face.

℞ *Ceruſ. & litharg. auri, ſulphuris vivi pulveriſati, an.* ʒ ß. *ponantur in phiala cum aceto & aqua roſarum:* linnen cloths dipped herein ſhall be applied to the face on the night, and it ſhall be waſhed in the morning with the Water of the infuſion of Bran: this kind of Medicin ſhall be continued for a Moneth.

℞ *Sanguinis tauri,* ℔ j. *butyri recentis,* ℔ ß. *fiat diſtillatio utatur.* The liquor which is diſtilled for the firſt days is troubled and ſtinking, but thoſe paſſed, it becometh clear and well ſmelling. Some boil Bran in Vinegar and the water of Water-lillies, and in this decoction they diſſolve of Sulphur and Camphire a fit proportion to the quantity of the decoction, and they apply a cloth moiſtned in this Medicin to the face in the evening.

℞ *Album. ovor.* nu. ij. *aquæ roſ.* ʒ j. ß. *ſucci plantag. & lapath. acut. an.* ℥ j. ß. *ſublimati,* ∋ j. *incorporentur in mortario marmoreo.* ℞ *Axung. porci decies in aceto lotæ,* ℥ iv. *argenti vivi,* ʒ j. *aluminis, ſulphuris vivi, an.* ʒ j. *piſtentur omnia diu in mortario plumbeo, & fiat unguentum, argentum vivum non debet niſi extremo loco affundi.* ℞ *Rad. lapath. acut. & aſphodel. an.* ʒ ij. *coquantur in aceto ſcillitico, poſtea tundan-*

tundantur, & ſetaceo trajiciantur, addendo auripigmenti, ℥ ij. *ſulphuris vivi,* ℥ x. let them be incorporated, and make an Ointment to be uſed to dry up the puſtles.

To dry up the Puſtles.

℞. *Rad. liliorum ſub cineribus coctorum,* ℥ iv. *piſtillo tuſis, & ſetaceo trajectis, adde butyri recentis, & axung. porci, lotæ in aceto, an* ℥ j. *ſulphuris vivi,* ℥ iij. *camphor.* ℈ iij. *ſucci limonum quantum ſufficit, malaxentur ſimul, & fiat unguentum.* ℞ *Lactis virginalis,* ℔ ß. *aluminis,* ℥ ß. *ſulphuris vivi,* ℥ j. *ſucci limonum,* ℥ iv. *ſalis com.* ℥ ß. let them all be diſtilled in a glaſs Alembick, and the water kept for the forementioned uſes.

℞ *Lapath. acut. plantag. & aſphodel. an* ℥ j. ß. *olei vitel. ovor.* ℥ j. *terebinth. venet.* ℥ ß. *ſucci limonum,* ℥ iij. *alum. combuſt.* ℥ j. *argenti vivi extinct.* ℥ j. *olei liliorum,* ℥ ß. *tundantur omnia in mortario plumbeo, addendo ſub finem argent. vivæ in mortario adhæreſcat.* The juice of Onions beaten with Salt, or Yolks of Eggs are good for the ſame purpoſe.

To kill Tetters.

For ſtaying and killing of Ring-worms and Tetters, the leaves of Hellebore beaten with Vinegar are good, the milk of the Fig-tree is good of it ſelf, as alſo that of the Spurges, or Muſtard diſſolved in ſtrong Vinegar with a little Sulphur. Or,

℞ *Sulphuris, calcanthi, & aluminis, an.* ℥ j. *macerentur in aceto forti, trajiciantur per lineum,* apply the expreſſed juice. Others macerate an Egg in ſharp Vinegar, with Coperas and *ſulphur vivum* beaten into fine powder, then they ſtrain or preſs it through a linnen cloth.

But ſeeing the forementioned Medicins are acrid, and for the moſt part eating and corroding, it cannot be but that they muſt make the skin harſh and rough; therefore to ſmooth and levigate it again, you ſhall make uſe of the following ointment.

To ſmooth the skin.

℞ *Tereb. ven. tam diu lotæ, ut acrimoniam nullam habeat, butyri ſalis expertis, an.* ℥ j. ß. *olei vitel. ovor.* ℥ j. *axung. porci in aqua roſarum lotæ,* ℥ ß. *ceræ parum, fiat linimentum ad uſum.* To the ſame purpoſe you may alſo make uſe of ſome of the fore-mentioned Medicins.

CHAP. XLI.

To black the Hair.

What things are fit to die the hair.

AT firſt the hairs (to take the *fucus* or tincture, and to retain it) muſt be prepared with Lye, wherein a little Roch-alum is diſſolved. Thus the fatty ſcales may be waſhed and taken away, which hinder, and (as it were) keep away the *fucus*, that it cannot adhere or penetrate into the body of the hair. Then muſt we come to particular or proper and fitting Medicins for this purpoſe. Theſe ought to be aromatick and cephalick, and ſomewhat ſtiptick, that by their odoriferous and aſtringent power that may ſtrengthen the animal faculty. Furthermore, they muſt be of ſubtil parts, that they may enter even into the inner roots of the hairs.

℞ *Sulphuris, vitrioli, gallarum, calcis vivæ, lithargyri, an.* ℥ ij. *ſcoriæ ferri,* ℥ ß. *in pollinem reducantur, & cum aq. communi incorporentur, ut inde fiat maſſa:* with this at bed time let the hairs be rubbed, and in the morning let them be ſmoothed with the ſame.

℞ *Calcis lotæ,* ℥ j. *lithargyri utriuſque* ℥ ß. *cum decocto gallarum, corticum nucum, fiat maſſa, addendo olei chamæm.* ℥ ij. ℞ *Litharg. auri,* ℥ ij. *ciner. clavellat.* ℥ j. ß. *calcis viv.* ℥ j. *diſſolve omnia cum urina hominis donec acquirant conſiſtentiam unguenti pro unctione capillorum.* ℞ *Calcis lotæ,* ℥ ij. *cum decoct. ſalv. & cort. granat. fiat paſta ad formam pultis ſatis liquidæ:* let the hair at bed-time be died herewith, and waſhed in the morning with Wine and Water.

How to waſh lime.

Now the manner of waſhing lime is thus: Infuſe in ten or twelve pints of fair water one pound of Lime, then pour out the water by ſtopping the veſſel, putting more in the ſtead thereof; the third time in ſtead of common water pour thereon the water of the decoction of Sage and Galls, let the Lime lie therein for ſo many hours, then in like manner pour it off by ſtopping the Veſſel; and thus you ſhall have your Lime well waſhed. There is alſo found a way how to die or black the hair by onely pouring of ſome liquor thereon: as, ℞ *Argenti puriſſimi,* ℥ ij. *reducantur in tenuiſſimas lamina, ponantur in ampulla vitrea cum* ℥ ij. *aquæ ſeparationis auri & argenti & aquæ roſar.* ℥ vj.

A water to black the hair.

The preparing of this water is thus: put into a Vial the water of ſeparation and the ſilver, and ſet it upon hot coals ſo to diſſolve the ſilver, which being done, then take it from the fire, and when it is cold, add thereto the Roſe-water. But if you would black it more deeply, add more ſilver thereto; if leſs, then a ſmaller quantity: to uſe it, you muſt ſteep the Comb wherewith you comb your head in this water.

℞ *Plumbi uſti,* ℥ ij. *gallarum non perforat. cortic. nucum, an.* ℥ iij. *terræ ſigill. ferret. biſpan. an.* ℥ ij. *vitriol. rom.* ℥ vj. *ſalis gem.* ℥ j. *caryoph. nucis moſch. an.* ℥ j. *ſalis ammon. aloes, an.* ℥ ß. *fiat pulvis ſubtiliſſimus:* let this powder be macerated in Vinegar for three days ſpace, then diſtil it all in an Alembick; the water that comes therefrom is good for the foreſaid uſe. The following Medicin is good to make the hairs of a flaxen colour. ℞ *Flor. geniſt. ſtœchad. & cardamom. an.* ℥ j. *lupinor. conquaſſat. raſur. buxi, corticis citri, rad. gentian. & berber. an.* ℥ j. ß. *cum aqua nitri; fiat lenta decoctio:* herewith bathe and moiſten the hairs for many days.

To make the hair of a flaxen colour.

CHAP. XLII.

Of Pſilothra, *or Depilatories: and alſo of Sweet Waters.*

A Depilatory.

MEdicins to fetch off hair, which by the Greeks, are termed *Pſilothra*, and *Depilatoria* in Latin vulgarly, are made as you may learn by theſe following examples: ℞ *Calcis vivæ* ℥ iij. *auripigmenti,* ℥ j. let the lime be quenched in fair water, and then the orpiment added with ſome aromatick thing: have a care that the Medicin lie not too long upon the part, otherwiſe it will burn; and this Medicin muſt be made to the conſiſtence of a Pultis and applied warm, firſt foment-

ſomenting the part with warm water: for then the hair will fall off by gentle rubbing or waſhing it with warm water: but if there happen any excoriation thereupon, you may help it by the uſe of *Unguentum roſatum*, or ſome other of the like faculty.

Another.

℞ *Calcis viv. aurip. citrin. an.* ℥ j. *amyl. ſpumæ argent.* ℥ ß. *terantur & incorporentur cum aq. com. bulliant ſimul:* you ſhall certainly know that it is ſufficiently boiled, if putting thereinto a Gooſes Quill, the Feathers come preſently off: ſome make into powder equal parts of unquenched Lime and Orpiment, they tie them up in a cloth, with which being ſteeped in water, they beſmear the part, and within a while after by gentle ſtroaking the head, the hair falls away of it ſelf. The following Waters are very fitting for to waſh the hands, face, and whole body, as alſo Linen, becauſe they yield a grateful ſmell: the firſt is Lavender-water thus to be made. ℞ *Flor. Lavend.* ℔ iv. *aqua roſar. & vini alb. an.* ℔ ij. *aq. vitæ,* ℥ iv. *miſceantur omnia ſimul, & fiat diſtillatio in balneo Mariæ*: the ſame Water may alſo be had without diſtillation, if you put ſome Lavender flowers in fair water, and ſo ſet them to Sun in a Glaſs, or put them in *balneo*, adding a little Oil of Spike and Musk. Clove-water is thus made. ℞ *Caryoph.* ℥ ij. *aq. roſar.* ℔ ij. *macerentur ſpatio* xxiv. *horarum, & diſtillentur in balneo Mariæ.* Sweet-water commonly ſo called, is made of divers odoriferous things put together; as thus, ℞ *Menthæ, marjoranæ, hyſſopi, ſalviæ, roriſmarini, lavendulæ, an.* m.ij. *radicis ireos,* ℥ ij. *caryophillorum, cinamoni, nucis moſchatæ, ana* ℥ ß. *limonum* nu. iv. *macerentur omnia in aqua roſarum, ſpacio viginti quatuor horarum, diſtillentur in balneo Mariæ, addendo Moſchi* ℈ ß.

Sweet Waters.

Lavender Water.

Clove Water.

Sweet Water.

The End of the Six and Twentieth Book.

BOOK XXVII.

OF DISTILLATION.

CHAP. I.

What Diſtillation is, and how many kinds thereof there be.

HAving finiſhed the Treatiſe of the Faculties of Medicins, it now ſeems requiſite that we ſpeak ſomewhat of Chymiſtry, and ſuch Medicins as are extracted by fire. Theſe are ſuch as conſiſt of a certain fifth eſſence ſeparated from their earthy impurity by Diſtillation, in which there is a ſingular, and almoſt divine efficacy in the cure of Diſeaſes. So that of ſo great an abundance of the Medicins, there is ſcarce any which at this day Chymiſts do not diſtil, or otherwiſe make them more ſtrong and effectual than they were before. Now Diſtillation is a certain Art or way by which the liquor or humid part of things, by the virtue and force of fire, or ſome ſemblable heat (as the matter ſhall ſeem to require) is extracted or drawn, being firſt reſolved into vapour, and then condenſed again by cold. Some call this Art *Sublimation*, or Subliming, which ſignifies nothing elſe but to ſeparate the pure from the unpure; the parts that are more ſubtil and delicate from thoſe that are more corpulent, groſs, and excrementitious; as alſo to make thoſe matters whoſe ſubſtance is more groſs, to become more pure and ſincere, either for that the terreſtrial parts are ill united and conjoined, or otherwiſe confuſed into the whole, and diſperſed by the heat and ſo carried up; the other groſſer parts remaining together in the bottom of the Veſſel. Or diſtillation is the extraction or effuſion of moiſture diſtilling drop by drop, from the noſe of the Alembick, or any ſuch like Veſſel. Before this effuſion or falling down of the Liquor, there goes a certain concoction performed by the virtue of heat, which ſeparates the ſubſtances of one kind from thoſe of another that were confuſedly mixed together in one body, and ſo brings them into one certain form or body, which may be good and profitable for divers Diſeaſes. Some things require the ſteat of a clear fire, others a flame, others the heat of the Sun, others of Aſhes, or Sand, or the Filings of Iron; others Horſe-dung, or boiling Water, or the oily vapour or ſteam thereof. In all theſe kinds of fires, there are four conſiderable degrees of heat. The firſt is contained in the limits of warmth, and ſuch is warm water, or the vapour of hot Water. The ſecond is a little hotter, but yet ſo as the hand may abide it without any harm; ſuch is the heat of aſhes. The third exceeds the vehemency of the ſecond; wherefore the hand cannot long endure this without hurt; and ſuch is the heat of Sand. The fourth is ſo violent that it burneth any thing that cometh near; and ſuch are the filings of Iron.

What Diſtillation is.

Four degrees of heat.

The firſt degree is moſt convenient to diſtil ſuch things as are ſubtil and moiſt, as Flowers. The ſecond ſuch as are ſubtil and dry, as thoſe things which are odoriferous and aromatical, as Cinamon, Ginger, Cloves. The third is fitteſt to diſtil ſuch things as are of a more denſe ſubſtance and fuller of Juice; ſuch as are ſome Roots and Gums. The fourth is fit for Metals and Minerals, as Alum, Vitriol, Amber, Jet, *&c.* In like manner you may diſtil without heat; as we uſe to do in thoſe things which are diſtilled by ſtraining, as when the more pure is drawn and ſeparated from that which is moſt unpure and earthy, as we do in *Lac Virginale*, and other things which are ſtrained through an Hypocras bag, or with a piece of cloth cut in form of a Tongue, or by ſetling, or by a veſſel made of Ivy wood: ſometimes alſo ſome things may be diſtilled by coldneſs of humidity, and we make the Oil of Tartar, Myrrh, and Vitriols, by laying them upon a marble in a cold and moiſt place.

What heat fitteſt for what things.

CHAP. II.

Of the matter and form of Fornaces.

The matter the beſt for Fornaces.

THe matter and form of Fornaces uſes to be diverſe; for ſome Fornaces uſe to be made of Bricks and Clay, otherſome of Clay onely, which are the better and more laſting, if ſo be the Clay be fat and well tempered with Whites of Eggs and Hair. Yet in ſudden occaſions when there is preſent neceſſity of diſtillation, Fornaces may be made of Bricks, ſo laid together that the joints may not agree, but be unequal; for ſo the ſtructure will be the ſtronger, The beſt and fitteſt form of a Fornace for diſtillation is round; for ſo the heat of the fire carried up equally diffuſes it ſelf every way, which happens not in a Fornace of another Figure, as ſquare or triangular, for the corners diſperſe and ſeparate the force of the fire. Their magnitude muſt be ſuch as ſhall be fit for the receiving of the Veſſel. For their thickneſs ſo great as neceſſity ſhall ſeem to require. They muſt be made with two bottoms, diſtinguiſhed as it were into two Forges, one below which may receive the aſhes of the coals or the like other fuel, the other above to contain the burning coals or fire. The bottom of this upper muſt either be an iron grate, or elſe it muſt be perforated with many holes, that ſo the aſhes may the more eaſily fall down into the bottom, which otherwiſe would extinguiſh the fire; yet ſome Fornaces have three partitions, as the Fornace for Reverberation. In the firſt and loweſt the aſhes are received, in the ſecond the coals are put, and in the third the matter which is calcined or elſe diſtilled. The third ought to have a ſemicircular cover, that ſo the heat or flame may be reflected upon the contained matter. The lower partition ſhall have one or more doors, by which the fallen-down aſhes may be taken forth, but the upper muſt have but one whereby the coals or wood may be put in. But in the top or upper part of the Fornace where it ſhall ſeem moſt fit, there ſhall be two or three holes made, that by them you may blow the fire, and that the ſmoak may more freely paſs out. But theſe fore-mentioned doors muſt have their ſhutters, much like an Ovens mouth. But in defect of a Fornace, or fit matter to build one withall, we may uſe a Kettle, ſet upon a Treefot, after the manner that we ſhall preſently declare, when we come to ſpeak of that diſtillation which is to be made by *Balneum Mariæ*.

A round form the beſt for Fornaces.

CHAP. III.

Of Veſſels fit for Diſtillation.

VEſſels for Diſtillation conſiſt of different matter and form; for they are either of Lead, Tin. or Braſs, or elſe earthen Veſſels; and theſe are ſometimes leaded, ſometimes not: or elſe they are of Gold, Silver, or Glaſs. Now for leaden Veſſels they are worſe than the reſt, and utterly to be refuſed, eſpecially when as the liquors which are drawn by them are to be taken into the body by the mouth, by reaſon of the malignant qualities which are ſaid to be in Lead; by which occaſion *Galen* condemns thoſe waters which run, and are contained in leaden pipes, which by reaſon of their ſaltiſhneſs and acrimony which ſavors of Quickſilver, cauſe Dyſenteries. Therefore you may perceive ſuch Waters as are diſtilled through a leaden head to be indued with a more acrid and violent piercing vapour, by reaſon the portion of that ſaltneſs diſſolved in them, and as it were ſhaven from the Alembick, or head, defiles the diſtilled Liquors, and whitens and turns them into a milky ſubſtance: but Copper or Braſs heads are more hurtful than Lead, for they make the Waters that come through them to ſavour or participate of Braſs. Thoſe that are of Gold and Silver are leſs hurtful; but the greatneſs of the coſt hinders us from making heads of ſuch Metals; therefore we muſt have a great care that our Veſſels for Diſtillation be either of Potters metal leaded, or elſe of Braſs, or of that Jug-metal which is commonly called *Terra Betovacenſis*, and theſe rather than of Lead, or any other Metal. Verily Glaſſes are thought the beſt; and next to them earthen Veſſels leaded, then of Jug-metal, and laſtly theſe of Tin. There is great variety of Veſſels for diſtillation in form and figure; for ſome are of an Oval or Cylindrical figure, that is, of a round and longiſh, others are twined and crooked, others of other ſhapes, as you may ſee in the beaks of the Chymiſts. Of this almoſt infinite variety of Figures I will in fit place give you the delineation and uſe of ſuch as ſhall ſeem to be moſt neceſſary.

Leaden Veſſels ill.

Braſs worſe.

The beſt Veſſels for Diſtillation.

CHAP. IV.

What things are to be conſidered in Diſtillation.

FIrſt make choice of a fit place in your houſe for the Fornace, ſo that it may neither hinder any thing, nor be in danger of the falling of any thing that ſhall lie over it. When you ſhall diſtil any thing of a malign or venenate quality, ye ſhall ſtand by it as little as you may, leſt the vapour ſhould do you any harm: when you provide Glaſs Veſſels for Diſtillation, make choice of ſuch as are exquiſitely baked, without flaws or cracks, and ſuch as are every where ſmooth. Let not the fire at firſt be very violent, not onely for fear of breaking the Veſſels, but alſo for that the firſt fire in Diſtillation muſt be gentle, and ſo increaſed by little and little. The things to be diſtilled ought not to be put in too great quantity into the body of the Still, leſt they ſhould riſe up or flie over; hot things that they may be more effectual muſt be twice or thrice diſtilled, by pouring upon them their own diſtilled Water, or other freſh materials, or elſe by diſtilling them ſeverally and by themſelves: of this kind are Gums, Wax, Fats, or Oils.

How things muſt be often diſtilled.

But

But in each other repeated distillations you must something lessen the force of the fire; for the matter attenuated by the former distillation cannot afterward endure so great heat: but aromatick things, as Cloves, Cinnamon, *&c.* as also the chymical oils of Sage, Rosemary, Thyme, *&c.* ought not to be distilled or rectified over again, for that we must presently after the first distillation have a diligent care to separate them from the phlegm, that is the more watery substance of the whole liquor, to which purpose we must have regard to that which is distilled, for there are some things which send over their phlegm, as Vinegar, others wherein it comes last, as * *Aqua vitæ.*

* By *Aqua vitæ* in this and most other places is meant nothing but the spirit of Wine.

If you would give to things to be distilled another taste or smell than that which they have naturally, you may mix them with some odoriferous thing, as Cinnamon, Camphire, or Musk, or the like, as you please, and so distil them together. The distilled liquors drawn by the heat of ashes or sand, savour of and retain a certain *empyreuma*, or smatch of the fire; for the helping of which, you shall put them into glasses close stopt, and so expose them to the Sun, and now and then open the glasses that this fiery impression may exhale, and the *Phlegmon* be consumed, if that there shall be any. But though in all distillation there are many things to be observed, yet are there two things chiefly worthy of note. The first is, the matter that is to be distilled and wrought upon, that is, of what kind it is, and what the Nature thereof may do and suffer. The other is the Furnace, which ought to be provided of a convenient matter, and figure of that which is to be distilled; for you cannot draw any thing of any matter, neither of every mixture being distilled, can you rightly expect Oil or Water: For mixt bodies do not consist of an equal portion of the four Elements, but some are more aery, others more fiery, some participate more of the Water, others more of the Earth, and that presently from their original. Therefore as watery things yield more Water; so airy and fiery things yield more Oil when they are distilled; neither are all instruments fit for the extracting of every liquor. Moreover you must note, that the watery liquor sometimes comes forth in the first place, and presently after by the help of a stronger fire follows the oily, which we find happens as often as the Plant or parts of the Plants which are distilled, are of a cold temperament; for in hot things it happens otherwise, for the first liquor which comes forth is oily, and the following waterish.

CHAP. V.

Of what fashions the Vessels for the distilling of Waters ought to be.

The parts of an Alembick.

FOr the distilling of any kind of Waters, two kind of Vessels are necessary, which are comprehended under this original name of an Alembick. They call one of them the body, or containing Vessel, the other the head, that is, the cap or top, wherein the ascending vapours are condensated or turned into water. It is called the head, because it stands over the body, like as an head; from the head there comes out a pipe or nose, whereby the distilled liquor flows drop by drop into the Receiver, as you may see by the Figure.

Of what fashion the Vessels for the distilling of Waters ought to be.



A *Shews a brass Kettle full of Water.* B *The cover of the Kettle perforated in two places to give passage forth to the Vessels.* C *A Pipe or Chimney added to the Kettle, wherein the fire is contained to heat the water.* D *The Alembick consisting of his body and head.* E *The Receiver whereinto the distilled liquor runs.*

The Effigies of another Balneum Mariæ, *not ſo eaſily to be removed as the former.*

A *Shews the Veſſel of Copper that contains the Water.*
B *The Alembick ſet in water.*

But leſt the bottom of the Alembick being half full, ſhould float up and down in the water, and ſo ſtick againſt the ſides of the Kettle; I have thought good to ſhew you the way and means to prevent that danger.



A *Shews the Veſſel or Glaſs Alembick.*
B *A plate of Lead whereon it ſtands.*
C *Strings that binds the Alembick to the plate.*
D *Rings through which the ſtrings are put to faſten the Alembick.*

You may diſtil the liquors of things by the vapour or ſteam of boiling water, if ſo be that you be provided of Veſſels and forms made after this following manner.

A Furnace with his Veſſels to diſtil liquors with the ſteam of boiling water.

A *Shew the head of the Alembick.*
B *The body thereof, placed in a braſs Veſſel made for that purpoſe.*
C *A braſs Veſſel perforated in many places to receive the vapour of the Water. This Veſſel ſhall contain the Alembick compaſſed about with Saw-duſt, not only that it may the better and longer retain the heat of the vapour, but alſo leſt it ſhould be broken by the hard touch of the brazen Veſſel.*
D *Shews the braſs Veſſel containing the water as it is placed in the Fornace.*
E *The Fornace containing the Veſſel.*
F *A Funnel by which you may now and then pour in water, inſtead of that which is vaniſhed and diſſipated by the heat of the fire.*
G *The Receiver.*

Why thoſe things that are diſtilled in *Balneo Mariæ* retain more of the ſtrength of things.

Now for the faculties of diſtilled Waters *it is* certain that thoſe which are drawn in *Balneo Mariæ* or a double veſſel, are far better and efficacious, becauſe they do not onely retain the ſmell of the things which are diſtilled, but alſo the taſte, acidity, harſhneſs, ſweetneſs, bitterneſs, and other qualities, ſo that they will neither favor of ſmoak nor burning; for the mild and gentle heat of a bath contains by its humidity, the more ſubtil parts of the Plants that are diſtilled, that they may not be diſſipated and

and exhaled, contrary to which it uſually happens in things which are diſtilled by the burning heat of Wood or Coals: for theſe have a certain nitrous and acrid taſte, ſavouring of the ſmoak of fire. Beſides, they acquire a malign quality from the veſſels out of which they are diſtilled, eſpecially if they be of Lead, whence they contract qualities hurtful to the principal, vital, and natural parts.

Therefore the Plants which are thus diſtilled, if they be bitter by nature, preſently become inſipid, as you may perceive by Wormwood-water thus diſtilled. Thoſe things which are diſtilled in *Balneo Mariæ* are contained in a glaſs Veſſel, from which they can borrow no malign quality. Therefore the matters ſo drawn are more effectual and pleaſing in taſte, ſmell, and ſight. You may draw Waters not onely from one kind of plant, but alſo from many compounded and mixed together: of theſe ſome are alimentary, others Medicinal, yea and purging; others acquired for ſmell, others for waſhing or ſmoothing of Womens faces, as we ſhall ſhew hereafter.

CHAP. VI.

How the materials muſt be prepared before Diſtillation.

THings before they be put in the Alembick muſt undergo a preparation, that is, they muſt be cut ſmall, beaten and macerated, that is, ſteeped in ſome liquor, that ſo they may be the more eaſily diſtilled and yield the more water, and retain their native ſmell and faculties; yet ſuch preparation is not convenient for all things; for there be ſome things which need no inciſion or maceration, but muſt rather be dried before they be diſtilled, as Sage, Thyme, Roſemary, and the like, by reaſon of their too much humidity; it will be ſufficient to ſprinkle other things with ſome liquor onely. In this preparation there are two things obſervable, to wit, the time of the infuſion, and condition of the liquor wherein theſe things ought to be infuſed. The time of the infuſion is different according to the variety of the matter to be macerated; for things that are hard, ſolid, dry or whole, muſt be longer macerated than ſuch as are tender, freſhly gathered or beaten: whence it is that Roots and Seeds require a longer time of infuſion; flowers and leaves a ſhorter, and the like of things. The liquors where infuſion muſt be made, ought to be agreeable to the other things infuſed. For hot ingredients require hot liquors, and cold ſuch as are cold, wherein they may be infuſed. What things need not to be macerated before they be diſſolved.

Such things as have not much juice, as Betony, Wormwood, and the like, or which are very odoriferous, as all aromatick things, would be infuſed by Wine; ſo to preſerve their ſmell, which otherwiſe by the force of the fire, by reaſon of the tenuity of the ſubſtance eaſily vaniſhes. But if we deſire that the diſtilled liquor ſhould more exactly retain and have the faculty of the things whereof it is diſtilled, then muſt you infuſe it in the juice thereof, to ſome ſuch appropriate liquor that it may ſwim in it whileſt it is diſtilled, or at leaſt let it be ſprinkled therewith. The maceration of Plants in their own juice.

CHAP. VII.

Of the Art of Diſtilling of Waters.

BEfore I deſcribe the manner how to diſtil Waters, I think it not amiſs briefly to reckon up how many ſorts of diſtilled Waters there be, and what the faculties of them are. Therefore of Diſtilled Waters ſome are medicinal, as the Waters of Roſes, Plantain, Sorrel, Sage, and the like: others are alimentary, as thoſe Waters that we call Reſtauratives; otherſome are compoſed of both, ſuch as are theſe reſtaurative Waters which are alſo mixed with Medicinal things; others are purging, as the diſtilled water of green and freſh Rhubarb; otherſome ſerve for ſmoothing the skin, and others for ſmell; of which ſort are thoſe that are diſtilled of aromatick things. The varieties of diſtilled waters.

The delineation of a Balneum Mariæ, *which may alſo ſerve to diſtil with aſhes.*



To diſtil Roſe-water, it will be good to macerate the Roſes before you diſtil them for the ſpace of two or three days, in ſome formerly diſtilled Roſe water, or their preſſed-out juice, luting the Veſſel cloſe; then putting them into an Alembick cloſely luted to his head and his Receiver, and ſo put into a *Balneum Mariæ*, as we have formerly deſcribed. Roſe-water.

A *Shews the Fornace with the hole to take forth the aſhes.*
B *Shews another Fornace as it were ſet in the other: now it is of Braſs, and runs through the midſt of the Kettle made alſo of Braſs, that ſo the contained water or aſhes may be the more eaſily heated.*
C *The Kettle wherein the Water, Aſhes or Sand, are contained.*
D *The Alembick ſet in the Water, Aſhes or Sand, with the Mouths of the Receivers.*
E *The bottom of the ſecond braſs Fornace, whoſe top is marked with* B, *which contains the fire.*

The diſtilled Alimentary liquors are nothing elſe than thoſe that we vulgarly call Reſtauratives; this is the Reſtauratives.

the manner and art of preparing them. Take of Veal, Mutton, Kid, Capon, Pullet, Cock, Partridge, Pheaſant, as much as ſhall ſeem fit for your purpoſe: cut it ſmall, and leſt it ſhould require heat, or *empyreuma* from the fire, mix therewith a handful of French Barley, and of red Roſe-leaves dry and freſh, but firſt ſteeped in the juice of Pomgranats, or Citrons and Roſewater with a little Cinnamon.

But if you deſire that this Reſtaurative ſhould not onely be Alimentary, but alſo Medicinal, you ſhall add thereto ſuch things as ſhall reſiſt the diſeaſe, ſuch as are Cordial Powders, as of *El. Diamargarit. frigid. de gemmis, aromat. roſat.* Conſerve of Bugloſs, Borrage, Roots, Herbs, Seeds, and other things of that kind. But if it be in a peſtiferous ſeaſon, Treacle, Mithridate and other Antidotes ſhall be added; each of theſe ſhall be laid in ranks or orders one over another, which is vulgarly termed *ſtratum ſuper ſtratum*, in a glaſs Alembick, and diſtilled in *Balneo Mariæ* with the heat of Aſhes, or elſe of warm Sand, as the Figure ſhews.

Another way of making reſtaurative Liquors.

There may be made other Reſtauratives in ſhorter time with leſs labour and coſt. To this purpoſe the fleſh muſt be beaten and cut thin, and ſo thruſt through with a double thred, ſo that the pieces thereof may touch each other; then put them into a Glaſs, and let the thred hang out; ſo ſtop up the Glaſs cloſe with a linnen cloth, Cotton or Tow, and lute it up with Paſte made of Meal and the Whites of Eggs,; then ſet it up to the neck in a Kettle of Water, but ſo that it touch not the bottom, but let it be kept upright by the formerly deſcribed means; then make a gentle fire thereunder, until the contained fleſh by long boiling ſhall be diſſolved into juice, and that will commonly be in ſome four hours ſpace. This being done, let the fire be taken from under the Kettle, but take not forth the Glaſs before the Water be cold, leſt the fire being hot it ſhould be broken by the ſudden appulſe of the cold air. Wherefore when as it is cold, let it be opened, and the thred with the pieces of fleſh be drawn forth, ſo that onely the juice may be left remaining; then ſtrain it through a bag, and aromatize it with Sugar and Cinnamon, adding a little juice of Citron, Verjuice or Vinegar, as it ſhall beſt like the Patients palat.

After this manner you may quickly, eaſily, and without great coſt have and prepare all ſorts of Reſtauratives, as well medicated as ſimple. But the force and faculty of purging Medicins is extracted after a clean contrary manner than the Oils and Waters which are drawn of aromatick things, as Sage, Roſemary, Thyme, Anniſeeds, Fennel, Cloves, Cinnamon, Nutmegs, and the like. For the ſtrength of theſe, as that which is ſubtil and airy, flies upward in diſtillation; but the ſtrength of purging things, as Turbith, Agarick, Rhubarb, and the like, ſubſides in the bottom. For the purgative faculty of theſe purgers inſeparably adheres to the bodies and ſubſtances.

Now for ſweet Waters and ſuch as ſerve to ſmooth the skin of the face, they may be diſtilled in *Balneo Mariæ*, like as Roſe-water.

CHAP. VIII.

How to diſtil Aqua Vitæ, *or the Spirits of Wine.*

TAke of good White or Claret Wine or Sack which is not ſowre or muſty, nor otherwiſe corrupt, or of the Lees, that quantity which may ſerve to fill the Veſſel wherein you make the diſtillation to a third part; then put on your head furniſhed with the noſe or pipe, and ſo make your diſtillation in *Balneo Mariæ*. The oftner it is diſtilled, (or as they term it) rectified, the more noble and effectual it becomes. Therefore ſome diſtil it ſeven times over.

Spirit of Wine ſeven times rectified.

At the firſt diſtillation it may ſuffice to draw a fourth or third part of the whole; to wit, of twenty four pints of Wine or Lees, draw ſix or eight pints of diſtilled liquor.

At the ſecond time the half part, that is, three or four pints.

At the third diſtillation the half part again, that is, two pints; ſo that the oftner you diſtil it over, the leſs liquor you have, but it will be a great deal the more efficacious. I do well like that the firſt diſtillation be made in Aſhes, the ſecond in *Balneo Mariæ*. To conclude, that *Aqua vitæ* is to be approved of, neither is it any oftner to be diſtilled, which put into a Spoon or Sawcer, and there ſet on fire, burns wholly away and leaves no liquor or moiſture in the bottom of the Veſſel; if you drop a drop of oil into this ſame Water, it continually falls to the bottom; or if you drop a drop into the palm of your hand, it will quickly vaniſh away, which are two other notes of the probation of this liquor.

The faculties of the Spirit of Wine.

The faculties and effects of *Aqua vitæ* are innumerable; it is good againſt the Epilepſie, and all cold Diſeaſes, it aſſwages the pain of the Teeth, it is good for punctures and wounds of the Nerves, Faintings, Swounings, Gangrenes and mortifications of the fleſh, as alſo put to other Medicins for a vehicle.

The diſtilling of Wine and Vinegar is different.

There is this difference between the diſtilling of Wine and Vinegar; Wine being of an airy and vaporous ſubſtance, that which is the beſt and moſt effectual in it, to wit, the airy and fiery liquor, comes from it preſently at the firſt diſtillation. Therefore the reſidue that remains in the bottom of the veſſel, it is of a cold dry and acrid nature; on the contrary, the Water that comes firſt from Vinegar, being diſtilled, is inſipid and flegmatick. For Vinegar is made by the corruption of Wine, and the ſegregation of the fiery and airy parts; wherefore the Wine being ſowre, there remains nothing of the former ſubſtance but phlegm; wherefore ſeeing phlegm is chiefly predominant in Vinegar, it firſt riſes in diſtillation. Wherefore he that hopes to diſtil the Spirit of Vinegar, he muſt caſt away the phlegmatick ſubſtance, that firſt ſubſtance that firſt riſes, and when by his taſte he ſhall perceive the ſpirit of Vinegar, he ſhall keep the fire thereunder until the flowing liquor ſhall become as thick as honey; then muſt the fire be taken away, otherwiſe the burning of it will cauſe a great ſtink.

The Veſſels fit to diſtil *Aqua Vitæ* and Vinegar are divers, as an Alembick or Retort ſet in Sand or Aſhes; a Copper or Braſs bottom of a Still, with a head thereto, having a Pipe coming forth thereof

which

which runs into a Worm or Pipe faſtned in a Barrel or Veſſel filled with cold Water, and having the lower end coming forth thereof; whoſe figure we ſhall give you when as we come to ſpeak of the drawing of Oils out of Vegetables.

CHAP. IX.

Of the manner of Rectifying, that is, how to increaſe the ſtrength of Waters that have been once diſtilled.

TO rectifie the Waters that have been diſtilled in *Balneo Mariæ*, you muſt ſet them in the Sun in glaſſes well ſtopped and half filled, being ſet in Sand to the third part of their height, that the Water waxing hot by the heat of the Sun, may ſeparate it ſelf from the phlegm mixed therewith, which will be performed in 12 or 15 days. The firſt way. There is another better way to do this, which is to diſtil them again in *Balneo* with a gentle fire, or if you will put them into a Retort furniſhed with his Receiver, and ſet them upon Chryſtal or Iron bowls, or in an Iron mortar directly oppoſite to the beams of the Sun, as you may learn by theſe enſuing ſigns. The ſecond.

A Retort with his Receiver, ſtanding upon Chryſtal bowls, juſt oppoſite to the Sun-beams.

A *Shews the Retort.*
B *The Receiver.*
C *The Chryſtal bowls.*

Another Retort with his Receiver, ſtanding in a Marble or Iron Mortar, directly oppoſite to the Sun.

A *Shews the Retort.*
B *The Marble or Iron Mortar.*
C *The Receiver.*

CHAP. X.

Of Diſtillation by filtring.

YOu ſhall ſet three Baſins or Veſſels of convenient matter in that ſite and order that each may be higher than other; that which ſtands in the higheſt place, ſhall contain the liquor to be diſtilled; and that which ſtands loweſt ſhall receive the diſtilled liquor. Out of the firſt and ſecond Veſſel ſhall hang ſhreds or pieces of Cloth or Cotton, with their broader ends in the liquor or upper Veſſel; and the other ſharper ends hanging down, whereby the more ſubtil and defecate liquor may fall down by drops into the Veſſel that ſtands under it; but the groſſer and more feculent part may ſubſide in the firſt and ſecond Veſſel. You by this means may at the ſame time diſtil the ſame liquor divers times, if you place many Veſſels one under another after the fore-mentioned manner, and ſo put ſhreds into each of them, ſo that the loweſt Veſſel may receive the purified liquor. In ſtead of this diſtillation Apothecaries oft-times uſe Bags.

This manner of diſtillation was invented to make more clear and pure Waters, and all juices and compoſitions, which are of ſuch a liquid conſiſtence. You may take an example from *Lac Virginis*, or Virgins milk, of which this is the deſcription. ℞ *Litharg. auri diligenter pulveriſ.* ℥ iij. *macerentur in aceti boni* ℥ vj. *trium horarum ſpatio, ſeorſim etiam in aqua plantag. ſolani, roſar. aut commun. ſal. infundatur*; then diſtil them both by ſhreds, then mix the diſtilled liquors, and you ſhall have that which for the milky whiteneſs is termed Virgins Milk; being good againſt the redneſs and pimples of the face, as we have noted in our Antidotary. *Lac Virginis.* *Cap. 44. of fucs.*

The deſcription of Veſſels to perform the diſtillation or filtration by ſhreds.



A *Shews the Veſſel.*
B *The Cloths or Shreds.*

CHAP.

CHAP. XI.

What, and how many ways there are to make Oils.

Oil's by Expreſſion.

YOu may by three means eſpecially draw to extract the Oils that you deſire. The firſt is by Expreſſion; and ſo are made the Oils of Olives, Nuts, Seeds, Fruits, and the like. Under this is thought to be contained Elixation, when as the beaten materials are boiled in Water, that ſo the Oil may ſwim aloft, and by this means are made the Oils of the Seeds of Elder and Dane-wort, and of Bay-berries. Another is by Infuſion, as that which is by infuſing the parts of Plants and other things in Oils. The third is by Diſtillation, ſuch is that which is drawn by the heat of the fire, whether by aſcent or by deſcent, or by concourſe: The firſt way is known by all; now it is thus: Take Almonds in their husks, beat them, work them into a maſs, then put them into a bag made of hair, or elſe of ſtrong cloth firſt ſteeped in Water or in white Wine, then put them into a Preſs and ſo extract their Oil. You may do the ſame in Pine-apple-kernels, Hazel-nuts, Coco-nuts, Nutmegs, Peach-kernels, the Seeds of Gourds, and Cucumers, Piſtick-nuts, and all ſuch oily things. Oil of Bays may be made of ripe Bay-berries newly gathered; let them be beaten in a Mortar and ſo boiled in a double Veſſel, and then forthwith put into a Preſs, ſo to extract Oil as you do from Almonds, unleſs you had rather get it by boiling as we have formerly noted. Oil of Eggs is made of the Yolks of Eggs boiled very hard; when they are ſo, rub them to pieces with your fingers, then fry them in a Pan over a gentle fire, continually ſtirring them with a Spoon until they becom red, and the Oil be reſolved and flow from them; then put them into a hair-cloth, and ſo preſs forth the Oil. The Oils prepared by Infuſion are thus made; make choice of good Oil, wherein let Plants, or Creatures, or the parts of them be macerated for ſome convenient time, that is, until they may ſeem to have transfuſed their faculties into the Oil, then let them be boiled, ſo ſtrained or preſſed out. But if any aquoſity remain, let it be evaporated by boiling. Some in compounding of Oils add Gums to them, of which though we have formerly ſpoken in our Antidotary, yet have I thought good to give you this one example. ℞ *Flor. hyper.* ℔ ſ. *immittantur in phialam cum flo. cent. & gum. elemi, an.* ʒ ij. *olei com.* ℔ ij. Let them be expoſed all the heat of Summer to the Sun. If any will add *Aquæ vitæ* wherein ſome Benzoin is diſſolved, he ſhall have a moſt excellent Oil in this kind. Oil of Maſtich is made *Ex olei roſati* ʒ xij. *maſtich.* ʒ iij. *vini optimi* ʒ viij.. Let them all be boiled together to the conſumption of the Wine, then ſtrain the Oil and reſerve it in a Veſſel.

By Infuſion.
By Diſtillation

Oil of Bayberries.

Of Eggs.

Oil of St. *Johns* Wort.

CHAP. XII.

Of extracting of Oils of Vegetables by Diſtillation.

ALmoſt all herbs that carry their Flowers and Seeds in an umble, have ſeeds of a hot, ſubtil, and airy ſubſtance, and conſequently oily. Now becauſe the oily ſubſtance that is contained in ſimple bodies, is of two kinds; therefore the manner alſo of extracting is two-fold. For ſome is groſs, earthy, viſcous, and wholly confuſed and mixed with the bodies out of which they ought to be drawn, as that which we have ſaid is uſually extracted by Expreſſion; this becauſe it moſt tenaciouſly adheres to the groſſer ſubſtance and part of the body, therefore it cannot by reaſon of this natural groſsneſs, be lifted up, or aſcend. Otherſome are of a ſlender and airy ſubſtance, which is eaſily ſevered from their body, wherefore being put to diſtillation it eaſily riſes: ſuch is the oily ſubſtance of aromatick things, as of Juniper, Anniſeeds, Cloves, Nutmegs, Cinamon, Pepper, Ginger, and the like odoriferous and ſpicy things. This is the manner of extracting Oils out of them; let your matter be well beaten and infuſed in water to that proportion, that for every pound of the material, there may be ten pints of water; infuſe it in a Copper bottom, having a head thereto either tinned or ſilvered over, and furniſhed with a cooler filled with cold water. Set your Veſſel upon a Fornace having a fire in it, or elſe in Sand or Aſhes. When as the water contained in the head ſhall wax hot, you muſt draw it forth, and put in cold, that ſo the Spirits may the better be condenſed, and may not flie away: you ſhall put a long necked Receiver to the noſe of the Alembick, and you ſhall increaſe the fire, until the things contained in the Alembick boil.

What Oils are to be drawn by Expreſſion.

The firſt manner of drawing Oils by diſtillation.

Another way.

There is another manner of performing this diſtillation: The matter preſerved and infuſed as we have formerly declared, ſhall be put in a braſs or copper bottom covered with his head, to which ſhall be fitted, or well luted, a Worm of Tin; this Worm ſhall run through a barrel filled with cold water, that the Liquor which flows forth with the Oil, may be cooled in the paſſage forth; at the lower end of this Worm you ſhall ſet your Receiver. The fire gentle at the firſt, ſhall be increaſed by little and little, until the contained matter, as we formerly ſaid, do boil; but take heed that you make not too quick or vehement a fire, for ſo the matter ſwelling up by boiling, may exceed the bounds of the containing veſſel, and ſo violently flie over.

Obſerving theſe things, you ſhall preſently at the very firſt ſee an oily moiſture flowing forth together with the wateriſh. When the Oil hath done flowing which you may know by the colour of the diſtilled liquor, as alſo by the conſiſtence and taſte, then put out the fire; and you may ſeparate the Oil from the Water by a little Veſſel made like a Thimble and tied to the end of a ſtick; (or, which is better, with a Glaſs Funnel or Inſtrument made of Glaſs for the ſame purpoſe.) Here you muſt alſo note that there be ſome Oils that ſwim upon the top of the water, as Oil of Anniſeeds; otherſome on the contrary, which fall to the bottom, as Oil of Cinamon, Mace, and Cloves.

What Oils fall to the bottom.

Moreover you muſt note that the wateriſh moiſture, or Water that is diſtilled with Oil of Anniſeed and Cinamon, is whitiſh, and in ſucceſs of time, will in ſome ſmall proportion turn into Oil. Alſo theſe Waters muſt be kept ſeveral, for they are far more excellent than thoſe that are diſtilled by *Balneo Mariæ*,

Mariæ, especially those that first come forth together with the Oil. Oils are of the same faculties with the bodies from whence they are extracted, but much more effectual: for the force which formerly was diffused in many pounds of this or that Medicin, is after distillation contracted into a few drams. For example, the faculty that was dispersed over one pound of Cloves, will be contracted into two ounces of oil at the most: and that which was in a pound of Cinamon will be drawn into ℥ j. ß. or ℥ ij. at the most of Oil. But to draw the greater quantity with the lesser charge, and without fear of breaking the Vessels, whereto Glasses are subject, I like that you distil them in Copper Vessels: for you need not fear that the Oil which is distilled by them will contract an ill quality from the Copper: for the waterish moisture that flows forth together therewith will hinder it, especially if the Copper shall be tinned or silvered over. I have thought good to describe and set before your eyes the whole manner of this operation.

A Fornace with set Vessels to extract the Chymical Oils, or Spirits of Sage, Rosemary, Tyme, Lavender, Anniseeds, Fennel seeds, Cloves, Nutmegs, Cinamon, Pepper, Ginger, and the like; as also to distil the spirit of Wine, of Vinegar and Aqua Vitæ. *Instead of the Barrel and Worm, you may use a head with a bucket or rowler about it.*

A *Shews the bottom, which ought to be of Copper and tinned on the inside.*
B *The Head.*
C *The Barrel filled with cold water to refrigerate and condensate the Water and Oil that run through the Pipe or Worm that is put through it.*
D *A Pipe of Braß or Lattin, or rather a Worm of Tin running through the Barrel.*
E *The Alembick set in the Fornace with the fire under it.*

Now because we have made mention of Cinamon, Pepper, and other Spices which grow not here with us, I have thought good to describe these out of *Thevets* Cosmography, he having seen them growing. Pepper grows upon Shrubs in *India*, these Shrubs send forth little branches whereon hang clusters of Berries, like to Ivy-berries, or bunches of small black Grapes or Currans: the leaves are like those of the Citron-tree, but sharpish and pricking. The description of Pepper.

The *Indians* gather those Berries with great diligence, and stow them up in large Cellars, as soon as they come to perfect maturity. Wherefore it oft-times happens that there are more than 200 Ships upon the Coast of the lesser *Java*, an Island of that Country, to carry thence Pepper and other Spices. Pepper is used in Antidotes against Poisons; it provokes urin, digests, attracts, resolves, and cures the bites of Serpents. It is properly applied and taken inwardly against a cold stomach: in Sauces it helps concoction and procures appetite: you must make choice of such as is black, heavy, and not flaccid. The Trees which bear white, and those that bear black Pepper, are so like each other, that the Natives themselves know not which is which, unless when they have their fruit hanging upon them, as the like happens upon our Vines which bear black and white Grapes. The uses thereof.

The Tree that yields Cinamon grows in the Mountains of *India*, and hath leaves very like to Bay-leaves: branches and shoots at certain times of the year are cut from this Tree, by the appointment of the King of that Province, the Bark of which is that we term Cinamon. This is sold to no stranger unless at the Kings pleasure, and he setting the price thereof, it is not lawful for others to cut thereof. The Cinamon Tree.

Galen writes that Cinamon is of very subtil parts, hot in the third degree, and partaking of some astriction; therefore it cuts and dissolves the excrements of the body, strengthens the parts, provokes the Courses when as they stop by reason of the admixture of gross humours: it sweetens the breath, and yields a fine taste and smell to Medicins, Hippocras, and Sauces. Of Cinamon there is made an excellent Water against all cold Diseases, and also against Swounings, the Plague, and Poisons. The composition thereof is this: Take of the choicest and best Cinamon one pound, beat it grosly, and put thereto of Rose water four pints, of white wine half a pint: being thus mixed, put them into a Glass, and so let them stand in infusion 24 hours, often stirring of them. Then distil them in *Balneo Mariæ*, closely luting the Receiver and Vessels, lest the spirit should flie away. *7. Simp.* An excellent Cinamon Water.

CHAP. XIII.

Another manner how to draw the Essence and Spirits of Herbs, Flowers, Seeds, and Spices; as also of Rhubarb, Agarick, Turbith, Hermodactyls, and other Purgers.

YOu may extract the Essences and Spirits of the things mentioned in the title of this Chapter, as thus: Take Sugar, Rhubarb, Cinamon, or any other Material you please, cut it small, or else beat it, then put it into a Glass with a long neck, and pour thereupon as much *Aqua vitæ* as shall be sufficient to cover the Materials or ingredients, and to over-top them some fingers bredth, then stop up the Glass very close, that no air enter thereinto: Thus suffer it to infuse for eight days in *Balneo*, with a very gentle heat; for thus the *Aqua vitæ* will extract the faculties of the Ingredients

dients which you ſhall know that it hath done, when as you ſhall ſee it perfectly tinctured with the colour of the ingredients. The eight days ended, you ſhall put this ſame *Aqua vitæ* into another Veſſel filled with the like quantity of the ſame materials prepared after the ſame manner, that it may alſo take forth the tincture thereof, and do thus three or four times, until the *Aqua vitæ* be deeply tinctured with the colour of the infuſed Ingredients.

A ſign that the ſpirit of Wine hath fetcht out the ſtrength of the ingredients.

But if the materials from whence you deſire to extract this ſpirit or eſſence, be of great price, as *Lignum Aloes*, *Rhubarb*, *&c.* you muſt not think it ſufficient to infuſe it once onely, but you muſt go over it twice, or thrice, until all the efficacy be extracted out thereof; you may know that it is all wholly inſipid.

A ſign that the ingredients have loſt their ſtrength.

Theſe things thus done, as is fitting, put all the liquor tinctured and furniſhed with the colour and ſtrength of the Ingredients, into an Alembick, filled and cloſely luted to its head, and ſo put into *Balneum Mariæ*, that ſo you may extract or draw off the *Aqua vitæ*, to keep for the like purpoſe, and ſo you ſhall have the ſpirit and eſſence remaining in the bottom.

Now if you deſire to bring this extract to the height of honey, ſet it in an earthy-pot well leaded, upon hot aſhes, ſo that the thin part thereof may be evaporated, for thus at length you ſhall have a moſt noble and effectual eſſence of that thing which you have diſtilled, whereof one ſcruple will be more powerful in purging, than two or three drams of the thing it ſelf.

CHAP. XIV.

How to extract Oil out of Gums, condenſed Juices, and Roſins, as alſo out of ſome Woods.

What a Retort is.

ALL Oils that are drawn out of Gums, Oily Woods, and Metals, are extracted by that veſſel which we vulgarly term a Retort. It muſt be made of Glaſs, or Jug-metal, well leaded, and of ſuch bigneſs as ſhall be convenient for the operation you intend, though commonly it ſhould be made to hold ſome gallon and an half of water; the neck thereof muſt be a foot and a half or at leaſt a foot long. The Receiver is commonly a Vial whereinto the neck of the Retort is fitted and inſerted. Then the Retort ſhall be ſet in an earthen filled with aſhes, or Sand, and ſo ſet into a Fornace, as you may ſee by this Figure.

The Figure of a Fornace, with his earthen Pan and Receiver.

A *Shews the Fornace.* B *The earthen Pan or Veſſel to ſet the Retort in.* C *The Retort or Cucurbite.* D *The Receiver.*

The differences of Gums.

Of Gums, ſome are liquid, ſome ſolid; and of the ſolid, ſome are more ſolid than otherſome; thoſe that are ſolid are more troubleſom to diſtil than the liquid, for they are not ſo eaſily diſſolved or melted, neither do they yield ſo well to the fire, ſo that oft-times they are burnt before they be diſſolved; whence it is that ſome for every pound of ſolid Gum, add two or three pounds of moſt clear and liquid Oil of Turpentine.

Cautions in diſtilling of Gums.

Beſides, liquid things are alſo hard to be diſtilled, becauſe when as they come to be through-hot at the fire, they ſwell up ſo much, that they exceed, or run out of the Retort, and ſo fall into the Receiver, as they were put into the Retort, eſpecially if ſo be that the fire be too hot at the firſt. Many to ſhun this inconvenience, add to the things put into the Retort, ſome Sand, as it were to balaſt it withal,

How to make Oil of Turpentine.

Oil of Roſin and Turpentine is thus made; Take two or three pounds of Turpentine and put it into a Retort of ſuch largeneſs that three parts thereof might remain empty, and for every pound of Turpentine add three or four ounces of Sand; then place the Retort in an earthen Pan filled with ſifted aſhes, and ſet it upon the Fornace as is fit, and to the neck thereof fit and cloſely lute a Receiver. Laſtly, Kindle there-under a ſoft fire at the firſt, leſt the contained materials ſhould run over; increaſe this fire by little and little, and take heed that the things become not too hot on a ſudden. At the firſt a clear and acid liquor will drop out, wherein a certain ſediment uſes to concrete; then will flow forth a moſt clear oil, ſomewhat reſembling the watry and phlegmatick liquor: then muſt the fire be ſomewhat increaſed, that the third oily, clear, thin, and very golden coloured liquor may riſe and diſtil: but then alſo a clearer and more violent fire muſt be raiſed, that ſo you may extract an Oil, that will be red like a Carbuncle, and of a conſiſtence indifferently thick. Thus therefore you may extract four kinds of Liquors out of Turpentine, and receive them being different in ſeveral Receivers; yet I judge it better to receive them all in one, that ſo by diſtilling them again afterwards you may ſeparate your deſired Oil; now there will ten or twelve ounces of Oil flow from a pound of Turpentine. This kind of Oil is effectual againſt the Palſie, Convulſions, Punctures of the Nerves, and wounds of all the nervous parts.

How to make Oil of Wax.

But you ſhall thus extract Oil out of Wax: Take one pound of Wax, melt it, and put it into a Glaſs Retort ſet in Sand or Aſhes, as we mentioned a little before in drawing Oil of Turpentine, then diſtil it, by increaſing the fire by degrees. There diſtils nothing forth of Wax, beſides an oily ſubſtance and a little *Phlegma*, yet portion of this oily ſubſtance preſently concretes into a certain butter-like matter, which therefore would be diſtilled over again: you may draw ℥ vj. or vij. of Oil from one pound of Wax.

The faculties thereof.

This Oil is effectual againſt Contuſions, and alſo very good againſt cold affects.

CHAP.

CHAP. XV.

Of extracting Oils out of the harder sorts of Gums; as Myrrh, Mastich, Frankincense, and the like.

SOme there be who extract these kinds of Oils with the Retort set in Ashes or Sand, as we mentioned in the former Chapter, *Of Oils of more liquid Gums*, adding for every pound of Gum two pints of *Aqua Vitæ*, and two or three ounces of Oil of Turpentine, then let them infuse for eight or ten days in *Balneo Mariæ*, or else in Horse dung; then set it to distil in a Retort. Now this is the true manner of making Oils of Myrrh; Take Myrrh made into fine Powder, and therewith fill hard Eggs in stead of their Yolks, being taken out; then place the Eggs upon a Gridiron, or such like Grate, in some moist place, as a Cellar, and set under them a Leaden-earthen pan; the Myrrh will dissolve into an oily water, which being presently put into a Glass and well stopped, with an equal quantity of rectified *Aqua Vitæ*, and so set for three or four moneths in hot Horse dung, which past, the vessel shall be taken forth, and so stopped that the contained liquor may be poured into an Alembick, for there will certain gross setling by this means remain in the bottom, then set your Alembick in *Balneo*, and so draw off the *Aqua Vitæ* and phlegmatick liquor, and there will remain in the bottom, a pure and clear Oil, whereto you may give a curious colour by mixing therewith some Alkanet, and a smell by dropping thereinto a little Oil of Sage, Cinamon, or Cloves.

How to make Oil of Myrrh.

How to give it a pleasing colour and smell.

Now let us shew the Composition and manner of making of Balsams, by giving you one or two examples; the first of which is taken out of *Vesalius* his Surgery; and is this,

℞ *Terebinth. opt.* ℔ j. *ol. laur.* ℥ iv. *gum. elem.* ℥ iv. ℈. *thuris, myrrhæ, gum. hederæ, centaur. majoris, ligni aloes, an.* ℥ iij. *galangæ, caryophyl. consolidæ majoris, Cinamoni, nucis moschat. zedoariæ, zinzib. dictamni albi, an.* ℥ j. *olei vermium terrestrium,* ℥ ij. *aqua vitæ* ℔ vj.

Vesalius his Balsam.

The manner of making it is thus; Let all these things be beaten and made small, and so infused for three days space in *Aqua Vitæ*, then distilled in a Retort, just as we said you must distil Oil of Turpentine and Wax. There will flow hence three sorts of Liquors; the first wateriih and clear, the other thin and of pure golden colour, the third of the colour of a Carbuncle, which is the true Balsam. The first liquor is effectual against the weakness of the stomach coming of a cold cause, for that it cuts phlegm and discusses flatulencies; the second helps fresh and hot bleeding wounds, as also the Palsie; the third is chiefly effectual against these same effects. The composition of the following *Balsamum* is out of *Fallopius*, and is this. ℞ *Terebinth. claræ,* ℔ ij. *olei de semine lini,* ℔ j. *resinæ pini,* ℥ vij. *thuris, myrrhæ, aloes, masticbes, sarcocol. an.* ℥ iij. *macis ligni aloes, an.* ℥ ij. *croci* ℥ ℈. Let them all be put into a glass Retort, set in ashes and so distilled. First there will come forth a clear water, then presently after a reddish oil, most profitable for wounds.

Fallopius his Balsam.

Now you must know that by this means we may easily distil all Axungiaes, Fats, parts of Creatures, Woods, all kinds of Barks and Seeds, if so be that they be first macerated as they ought to be, yet so that there will come forth more watry than oily humidity. Now for that we formerly frequently mentioned *Thus* or Frankincense, I have here thought good out of *Thevets* Cosmography to give you the Description of the Tree from which it flows. The Frankincense Tree (saith he) grows naturally in *Arabia*, resembles a Pine, yielding a moisture that is presently hardned, and it concretes into whitish clear grains, fatty within, which cast into the fire, take flame. Now Frankincense is adulterated with Pine-rosin and Gum, which is the cause that you shall seldom find that with us, as it is here described; you may find out the deceit thus, for that neither Rosin nor any other Gum takes flame; for Rosin goes away in smoke, but Frankincense presently burns. The smell also bewrays the counterfeit, for it yields no grateful smell as Frankincense doth. The *Arabians* wound the Tree that so the liquor may the more readily flow forth, whereof they make great gain. It fills up hollow ulcers and cicatrizes them; wherefore it enters as a chief ingredient into artificial Balsam; Frankincense alone made into Powder and applied, stanches the bloud that flows out of the wounds.

What Frankincense is.

The faculties thereof.

Matthiolus saith, that it being mixed with Fullers-earth, and oil of Roses, is a singular remedy against the inflammation of the Brests of Women lately delivered of child.

CHAP. XVI.

The making of Oil of Vitriol.

TAke ten pounds of Vitriol, which being made into Powder, put it into an earthen pot, and set it upon hot coals until it be calcined, which is when as it becomes reddish; after some five or six hours, when as it shall be throughly cold, break the pot, and let the Vitriol be again made into Powder, that so it may be calcined again, and you shall do thus so often and long until it shall be perfectly calcined, which is when as it shall be exactly red; then let it be made into Powder, and put it into an earthen Retort, like that wherein *Aqua fortis* is usually drawn, adding for every pound of your calcined Vitriol of Tile-sherds, or powdered Brick one quarter; then put the Retort furnished with its Receiver into a Fornace of Reverberation, always keeping a strong fire, and that for the space of 48 hours, more or less according to the manner and plenty of distilling liquor. You shall know the distillation is finished when as the Receiver shall begin to recover his native perspicuity, being not now filled with vaporous spirits, wherewith as long as the humour distills it is repleniished and looks white.

The sign of perfectly calcined vitriol.

A Fornace or Reverberation furniſhed with his Retort and Receiver.

Now for the Receiver there are two things to be obſerved. The firſt is, that it be great and very capacious, that it may not be diſtended and broken by the abundant flowing of vaporous ſpirits, as it doth oft-times happen; another thing is, that you ſet it in a veſſel filled with cold water, leſt it ſhould be broken by being over-hot; you may eaſily perceive all this by this Figure.



A *Shews the Fornace.*
B *The Retort.*
C *The Receiver.*
D *The Veſſel filled with cold Water.*

CHAP. XVII.

A Table or Catalogue of Medicins and Inſtruments ſerving for the Cure of Diſeaſes.

MEdicins and Medicinal meats fit for the cure of Diſeaſes, are taken from living Creatures, Plants, and Minerals. From living Creatures are taken, *Horns, Hoofs, Hairs, Feathers, Shells, Sculls, Scales, Sweats, Skins, Fats, Fleſh, Bloud, Entrails, Urin, Bones, Extreme parts, Heart, Liver, Lungs, Brain, Womb, Seeundine, Teſticles, Pizzle, Bladder, Sperm, Tail, Coats of the Ventricle, Exſpirations, Briſtles, Silk, Webs, Tears, Spittle, Honey, Wax, Eggs, Milk, Butter, Cheeſe, Marrow, Rennet.*

Smells whether they be ſtinking or ſweet, as alſo Poiſons: whole Creatures themſelves: as, *Foxes, Whelps, Hedg-hogs, Frogs, Worms, Crabs, Cray-fiſhes, Scorpions, Horſleeches, Swallows, Dungs.*

From Plants, that is, Trees, Shrubs, and Herbs, are taken, *Roots, Moſs, Pith, Sieus, Buds, Stalks, Leaves, Flowers, Cups, Fibers, or Hairy threads, Ears, Seeds, Bark, Wood, Meal, Juices, Tears, Oils, Gums, Roſins, Rottenneſs, Maſs or Spiſſament, Manna,* which falling down like Dew upon Plants preſently concretes. Whole Plants, as *Mallows, Onions,* &c.

Metals or Minerals are taken either from the Water or Earth, and are either kinds of Earth, Stones, or Metals, &c. The kinds of Earth are, *Bole-Armenick, Terra ſigillata, Fullers-earth, Chalk, Oker, Plaſter, Lime.* Now the kinds of Stones are, *Flints,* Lapis Judaicus, Lapis Lyncis, *the Pumice,* Lapis Hæmatites, Amiantus, Galactites, *Spunge-ſtones, Diamonds, Sapphire, Chryſolite, Topace, Load-ſtone, the* Pyrites *or Fire-ſtone, Alabaſter, Marble, Cryſtal,* and many other precious Stones. The kinds of Salts as well Natural as Artificial are, *Common Salt,* Sal Nitrum, Sal Alkali, Sal Ammoniacum, *Salt of Urin, Salt of Tartar,* and generally all Salts that may be made of any kind of Plants. Thoſe that are commonly called Minerals, are, *Marchaſite, Antimony, Muſcovy-glaſs, Tutty, Arſnick, Orpiment, Lazure, or Blue, Roſe-agar, Brimſtone, Quick-ſilver, White Coperas, Chalcitis, Pſory, Roman Vitriol, Colcother, Vitriol or Green Coperas,* Alumen ſciſſile, *Common Alum,* Alumen Rotundum, Alumen liquidum, Alumen plumoſum, Borax *or Burrace,* Bitumen, Naptha, Cinnabaris, *or Vermilion, Litharge of Gold, Litharge of Silver,* Chryſocolla, Scandaracha, *Red Lead, White Lead, and divers other.* Now the Metals themſelves are, *Gold, Silver, Iron, Lead, Tin, Braſs, Copper, Steel, Lattin,* and ſuch as ariſe from theſe; as the *Scales, Verdigreaſe, Ruſt,* &c. Now from the Waters, as the Sea, Rivers, Lakes, and Fountains, and the mud of theſe Waters, are taken divers Medicins, as *White and Red Coral, Pearls,* and infinite other things which Nature the Hand-maid of the great Architect of this World, hath produced for the cure of Diſeaſes; ſo that into what part ſoever you turn your eyes, whether to the ſurface of the Earth, or the bowels thereof, a great multitude of Remedies preſent themſelves to your view. The choice of all which is taken from their ſubſtance, or quantity, quality, action, place, ſeaſon, ſmell, taſte, ſight, figure, and weight, other circumſtances, as *Sylvius* hath abundantly ſhewed in his Book written upon this Subject. Of theſe Simples are made divers Compoſitions; as, *Collyria, Caputpurgia, Eclegmata, Dentifrices, Dentiſcalpia, Apophlegmatiſmi, Gargariſms, Pills, Boles, Potions, Emplaſters, Unguents, Cerats, Liniments, Embrocations, Fomentations, Epithemes, Attractives, Reſolvers, Suppuratives, Emollients, Mundificatives, Incarnatives, Cicatrizers, Putrifiers, Corroſives, Aglutinatives, Anodynes, Apozemes, Julips, Syrups, Powders, Tablets, Opiats, Conſerves, Preſerves, Confections, Rowls, Vomits, Sternutatories, Sudorificks, Clyſters, Peſſaries, Suppoſitories, Fumigations, Trochiſces, Frontrails, Caps, Stomachers, Bags, Baths, Half-baths, Virgins Milk,* Fuci, *Pications, Depilatories, Veſicatories, Potential Cauteries, Noſe-gays, Fans, Canopies, or* extended cloths to make wind, *Artificial Fountains* to diſtil or drop down Liquors.

Now thoſe that are thonght to be nouriſhing Medicins are, *Reſtauratives, Culliſes, Expreſſions, Gellies, Ptiſans, Barly-creams, Panadoes, Almond milk, March-panes, Wafers, Hydroſacchar, Hydromel,* and ſuch other drinks; *Mucilages, Oxymel, Oxycrate, Roſe-Vinegar, Hydrælium, Metheglin, Sider, Drink of Cervices, Ale, Beer, Vinegar, Verjuice, Oil, Steeled Water, Water brewed with Bread-crums, Hippocras, Perry,* and ſuch like.

Waters and diſtilled Oils, and divers other Chymical Extractions: As the Waters and Oils of hot, drie and aromatick things, drawn in a Copper Alembick, with a cooler, with ten times as much water in weight as of Herbs; now the Herbs muſt be drie, that the diſtillation may the better ſucceed.

Waters are extracted out of Flowers put into a Retort, by the heat of the Sun, or of Dung, or of an heap of preſſed-out Grapes, or by *Balneo,* if there be a Receiver, put and cloſely luted thereto. All kinds of Salt of things calcined, diſſolved in Water, and twice or thrice filtred, that ſo they may become more pure and fit to yield Oil.

Other

Other Diſtillations are made either in Cellars by the coldneſs or moiſtneſs of the place, the things being laid either upon a Marble, or elſe hanged up in a Bag; and thus is made Oil of Tartar, and of Salts, and other things of an aluminous nature.

Bones muſt be diſtilled by deſcent, or by the joining together of Veſſels. All Woods, Roots, Barks, Shells of Fiſhes, and Seed, or Grains, as of Corn, Broom, Beans, and other things whoſe juice cannot be got out by expreſſion, muſt be diſtilled by deſcent, or by the joining together of Veſſels in a Reverberatory Fornace.

Metals calcined and having acquired the Nature of Salt, ought to be diſſolved and filtred, and then evaporated till they be drie; then let them be diſſolved in diſtilled Vinegar, and then evaporated and dried again; for ſo they will eaſily diſtil in a Cellar upon a Marble or in a Bag. Or elſe by putting them into a glaſſie Retort, and ſetting it in Sand, and ſo giving Fire thereto by degrees, until all the watery humidity be diſtilled; then change the Receiver, and lute another cloſe to the Retort, then increaſe the Fire above and below, and thus there will flow forth an Oil very red coloured. Thus are all Metalline things diſtilled, as Alums, Salts, &c.

Gums, *Axungiæ*, and generally all Roſins, are diſtilled by a Retort ſet in an earthen Veſſel filled with Aſhes upon a Fornace; now the fire muſt be increaſed by little and little according to the different condition of the diſtilled matters.

The Veſſels and Inſtruments ſerving for Diſtillation are commonly theſe.

BOttoms of Alembicks. *The heads of them, from whence the liquors drop. Refrigeratories. Veſſels for ſublimation. For reverberation. For diſtilling by deſcent. Crucibles and another ſuch. Veſſels for Calcination, Hair-ſtrainers, Bags, Earthen Platters. Veſſels for circulation, as Pelicans, Earthen Baſins for filtring, Fornaces, the ſecret fornaces of Philoſophers, the Philoſophers Egg, Cucurbites Retorts, Bolt-heads, Urinals, Receivers, Veſſels ſo fitted together that the lowermoſt receives the mouth of the uppermoſt, whence they may be termed conjoined Veſſels: they are uſed in diſtilling* per deſcenſum. *Marbs exquiſitely ſmooth for diſtillations to be made in Cellars, Pots to diſſolve calcined Metals in.*

A Catalogue of the Surgeons Inſtruments mentioned in this whole Work.

RIngs *wherein little Lancets lie hid, to open Impoſthumes. Trunks or hollow Inſtruments going with ſprings. A vent, or cooler for the womb made like a Peſſary. Hollow Tents. Sundry Cauteries, as flat, round, ſharp-pointed, cutting, &c. Conſtrictory rings to twitch or bind the Columella.* Speculum Oris, Ocul. Ani, Uteri. *A Trunk or Pipe with an actual Cautery in it. Crooked Knives. A Pipe in form of a Quill. Divers Truſſes, with one or more bolſters. A ſhoulder-band to be put about the neck, to hold up a Trueſs. A Needle to draw through a golden Wier, &c. Pipes with feneſtels, and Needles fit for ſutures. Cutting Mullets. Mullets onely to hold and not to cut. Mullets to take forth ſplinters of bones. Mullets to draw Teeth. An Inciſion knife. Scrapers to plain or ſmooth the bones, or elſe to cut them. Cutting or hollow Scrapers. A leaden Mallet to drive the Scrapers or Chizzels into the ſcull. A Gimblet in ſhape and uſe, reſembling that which Coopers uſe to lift up the ſunk ſtaves of their cask withall. Levatories of which kind is the three-footed one. Old Levatories, which taken up by their handles, and their tongues being put under the depreſt bones, lift them up. Saws. A Deſquamatory Trepan. Pliers to take forth ſplinters of bones. A Gimblet to perforate the ſkull. A Trepan fit to divide the ſkull, with the Scrue, Point, or Piercer, Brace, and Cover or Cap, that keeps it from running in too far. A Plate to ſet one foot of the Compaſs upon. A cutting pair of Compaſſes both open and ſhut, a fit inſtrument to depreſs the* Dura Mater *without hurting thereof. A Syringe to make injection withall. A pair of Pincers with holes through them to take up the ſkin for making a Seton. Setons as well drie as moiſtned with ointments. The Beaks of Crows, Parats, Swans, Ducks, Lizards, Cranes, are either ſtrait, crooked, toothed, or ſmooth. Catch-hullets, and Pliers to draw forth pieces of mail, and ſplinters of bones that lie deep in. Hollow and ſmooth Dilaters diverſly made for the different wounds of the parts. Probes fit for to put flamulaes into wounds; and theſe are either ſtrait or crooked, perforated or unperforated. Scrued Mullets to draw forth barbed heads of arrows, and the like. Lancets to let bloud, and ſcarifie, as well ſtrait as crooked. A* Pyulcos, *or Matter-drawer.* Ligatures, Bands, Swathes, Thongs of Leather, Woollen, Linnen, round, ſlit, ſown together, *Again ſome are upper binders, other under-binders. Again, theſe are either expreſſing or elſe containing, and that either the applied Medicin, or the lips of wounds, or members put in a fit poſture, which therefore they call a Sarcotick Ligature. Thred, Bottoms or Clews of Thred or Yarn. Pledgets, Compreſſes, Bolſters, doubled Cloths.* Ferulæ, *or Splints. Caſſes, Boxes, Junks, Gloſſocomies.* Ambi, *a kind of Gloſſocomy. A Pully with its wheels, and wooden, and iron Pins whereon the wheels may run. Ropes as well to draw and extend, as hold up the member,* &c. *Scrue-pins, A Handvice, Hooks, Buttons or Stays to faſten to the ſkin to hold together the lips of the wouds, Lint cuſhions, Pillows, Linnen Cloths. Files,* Dentiſcalpia, Dentifricia, Dentiſpicia. *Catheters, Guiders of the Work. A Bathing Chair or Seat, Bathing Tubs, Half Tubs, Caldrons, Funnels, with all other circumſtances belonging to a Bath. Stoves, or Hot-houſes to ſweat in. Cocks to turn and let out Water. A Gimblet to break the Stone. Hooks, Hollow Probes ſlit on the upper ſides. Winged Inſtruments to draw forth ſtones. An Inſtrument to cleanſe the Bladder. Spatulaes ſtraight and crooked. Cupping-glaſſes, Horns, Pipes, or Catheters to wear Caruncles. Artificial members, as Eyes of Gold enamelled,* &c. *An Urinal or Caſe to ſave the water in. An Artificial Yard. Crutches, Nipples, or Leaden Covers for ſore Breſts. Griffins Talons to draw forth a* Mola *out of the Womb. A Sucking Glaſs to draw a Breſt withall. Peſſaries both long and oval. Syringes to give Glyſters, as alſo to make injection into the Ears and Womb.*

The Effigies of *HIPPOCRATES* of *COOS*, the Prince of PHYSICIANS.

INvictum, Hippocrates, *quòd te potuere ſuperbæ*
Eoî numquam flectere Regis opes,
Cecropidæ fronti ex auro fulgente coronam
Promeriti memores impoſuere tuæ.
Gratia ſed levis eſt, Actæis tantus Athenis
Nec fuit hinc uni quàm tibi partus honos.
Nam quòd quæ recreent languentia corpora morbo
Pæonias fueris promere largus opes;
Sed tua tam fundit, quàm magni machina Mundi
Gratia, & inſignis tam tua fama volat.

BON. GRA. *Pariſ. Medic.*

SELECT APHORISMS concerning SURGERY,

Collected out of the Aphoriſms of the *Great* HIPPOCRATES.

Aphor.27. Sect.6. WHoſoever being ſuppurate or hydropical, are burnt, or cut therefore, if all the Matter or Water flow forth at once, they certainly die.

31. 6. The drinking of Wine, or a Bath, Fomentation, Bloud-letting, or Purging, help the pains of the Eyes.

38. 6. Such as have hidden, or not ulcerated Cancers, had better not to cure them. For healed, they quickly die; not cured, they live the longer.

55. 6. Gouty pains uſually ſtir in the Spring and Fall.

28. 6. Eunuchs are not troubled with the Gout, neither do they become bald.

49. 6. Whoſoever are troubled with the Gout, have eaſe in forty days, the inflammation ceaſing.

66.5. In great and dangerous Wounds, if no ſwelling appear, it is ill.

67. 5. Soft tumours are good, but crude ones ill.

25. 6. For an *Eryſipelas*, or Inflammation to return from without inwards, it is not good; but to come from within outwards, is very good.

19. 7. An *Eryſipelas* coming upon the bearing of a bone, is evil.

20. 7. Putrefaction or ſuppuration coming upon an *Eryſipelas*, is ill.

21. 6. If *Varices* or Hæmorrhoids happen to ſuch as are mad, their madneſs ceaſes.

21. 7. A flux of bloud enſuing upon a great pulſation in ulcers, is ill.

26. 2. It is a better that a Fever happen upon a Convulſion, than a Convulſion upon a Fever.

4. 6. Thoſe Ulcers that have the skin ſmooth or ſhining about them, are evil.

18. 6. The Wound is deadly whereby the Bladder, Brain, Heart, Midriff, any of the ſmall Guts, Stomach, or Liver are hurt.

45. 6. Whatſoever Ulcers are of a years continuance or more, the bone muſt neceſſarily ſcale, and the ſcars become hollow.

2. 7. The bone being affected, if the fleſh be livid, it is ill.

14. 7. Stupidity and lack of Reaſon upon a blow on the Head, is evil.

24. 7. A *Delirium* happens if a bone (to wit, the skull) be cut even to the hollowneſs thereof.

Whileſt *Pus* or matter is in generating, Pains and Fevers happen rather than when it is already made.

18. 5. Cold things are hurtful to the Bones, Teeth, Nerves, Brain, Spinal Marrow; but hot things are good.

46. 2. Two Pains infeſting together, but not the ſame place, the more vehement obſcures the other.

74. 7. A corruption, an Abſceſs of the bone is cauſed by the corruption of the fleſh.

50. 6. *Coacar. prænot.* a livid or drie Ulcer, or yellowiſh, is deadly.

19. 6. When as a Bone, or Griſtle, or Nerve, or ſmall portion of the Cheek, or the Prepuce is cut aſunder, it neither increaſes, nor grows together.

24. 6. *Aph. & 513. Coacar.* If any of the ſmall guts be cut, it knits not again.

50. 7. Thoſe that have the Brain ſphacelate, that is, corrupt, they die within three days; if they eſcape theſe, they recover.

9. 7. Bleeding at a wound cauſing a Convulſion, is the fore-teller of death.

20. 5. Cold is biting to Ulcers, hardens the skin, cauſes pain, not eaſily coming to ſuppuration, blackneſs, aguiſh ſhakings, convulſions, cramps.

50. 8. *Coac.* Thoſe who have the Temples cut, have a convulſion upon the parts contrary to the Section.

44. 7. Whoſoever being ſuppurate are burnt or cut, if pure and white quitture ſhall flow forth, they eſcape; but if that which is bloudy, feculent, and ſtinking, then they die.

Galen Comment. ad Aphor. 29. 2. It is not fit to take in hand to cure ſuch as are in a deſperate caſe, but to leave them, one foretelling the end of the diſeaſe.

*Celſus, cap.*10. *lib.*20. It is better to trie a doubtful remedy than none at all.

The Effigies of GALEN the Prince of PHYSICIANS next to HIPPOCRATES.

ÆQuum erat Hippocratem *divino è ſemine Divûm*
Orbem muneribus conciliare ſibi:
Scripta ſed involvit tam multo ænigmate, verum
Ut quamvis ſolers nullus habere queat;
Pergamei auxilio niſi ſint monimenta Galeni,
Qui doctâ ambages ſuſtulit Arte ſenis;
Ergò mâcte eſto virtute, arcana reſolvens,
Quæ nulli fuerant nota, Galene, *priùs;*
Obſtringenſque orbem æterno tibi munere totum,
Æternis ſacras te quoque temporibus.

BON. GRA. *Pariſ. Medic.*

Rules

Rules of Surgery by the AUTHOR.

1. PRactice is an Operation agreeable to the Rules and Laws of the Theory.
2. Health is not received by Words, but by Remedies fitly uſed.
3. Remedies known and approved by Uſe and Reaſon, are to be preferred before ſuch as are unknown, or but lately found out.
4. Science without Experience gets the Phyſician no great credit with the Patient.
5. He that would perform any great and notable Work, muſt diligently apply himſelf to the knowledge of his ſubject.
6. It is the part of a good Phyſician to heal the diſeaſe, or certainly to bring it to a better paſs, as Nature ſhall give leave.
7. The Surgeon muſt be active, induſtrious, and well-handed, and not truſt too much to Books.
8. He that hath not been verſed in the operations of the Art, nor a frequent auditor of the Lectures of ſuch as are learned therein, and ſets forth himſelf for a brave Surgeon, for that he hath read much, he is either much deceived or impudent.
9. He ſhall never do any thing praiſe-worthy that hath got his Maſtery in Surgery by Gold, not by Uſe.
10. You ſhall comfort the Patient with hope of Recovery, even when as there is danger of death.
11. To change Phyſicians and Surgeons is troubleſom, but not good for the Patient.
12. Though the Diſeaſe prove long, yet it is not fit that the Phyſician give over the Patient.
13. Great wounds of large Veſſels are to be judged deadly.
14. Every contuſion muſt be brought to ſuppuration.
15. As the nature or kind of the diſeaſe muſt be known, ſo alſo muſt the remedy.
16. An Abſceſs of the bone of the Palat, is in danger to cauſe a ſtinking breath.
17. Bleeding cauſed by heat, muſt be repreſt by cold.
18. Wounds of nervous parts require Medicins which by the ſubtilty of the parts may enter in and draw from far.
19. It is not fit for ſuch as have Ulcers in their Legs, either to walk, ſtand or ſit, but to reſt themſelves in bed.
20. All biting and acrid Medicins are offenſive to clean Ulcers.
21. For reſtoring of diſlocations you muſt hold them faſt, ſtretch them out, and force them in.
22. A great Gangrene admits no cure but cutting.
23. A monſter is a thing diſſenting from the Laws of Nature.
24. Wounds of the Cheſt preſently become ſanious and purulent.
25. The wounds made by all venomous Creatures are dangerous.
26. The South wind blowing, wounded members eaſily become mortified.
27. Such as are wounded, and deſire to be quickly whole, muſt keep a ſpare diet.
28. Untemperate bodies do not eaſily recover of diſeaſes.
29. Round Ulcers, unleſs they be drawn into another figure, do not eaſily heal up.
30. An Eryſipelatous Ulcer requires purgation by ſtool.
31. Crying is good for an Infant, for it ſerves in ſtead of exerciſe and evacuation.
32. Grief is good for none but ſuch as are very fat.
33. Idleneſs weakens and extinguiſheth the native heat.
34. An ill-natured Ulcer yields not, unleſs to a powerful Remedy.
35. A Bath reſolves and diſcuſſes humours, and gently procures ſweat.
36. Cold diſeaſes are troubleſom to cold people, and hard to be helped; but in young bodies they are neither ſo troubleſom, nor contumacious.
37. Exerciſed Bodies are leſs ſubject to diſeaſes.
38. Moiſt Bodies though they need ſmall nouriſhment, yet ſtand they in need of large evacuation.
39. Sick people die ſooner of a hot diſtemper than of a cold, by reaſon of the quick and active operation of fire.
40. The quitture that flows from an ulcer is laudable, which is white, ſmooth and equal.

The End of the Seven and Twentieth Book.

BOOK

BOOK XXVIII.

How to make Reports and to Embalm the Dead.

Why a Surgeon muſt be careful in making of Reports.

NOw it onely remains that we inſtruct the Surgeon in making and framing his Report or Opinion, either of the Death of any perſon, or of the weakneſs or deprivation of any member in the function or execution of its proper office and duty. Herein it is meet that he be very conſiderate, that is to ſay, ingenious or wiſe in making his Report, becauſe the events of Diſeaſes are often-times doubtful and uncertain, neither can any man fore-tell them certainly, whether they will be for life or death, by reaſon of the manifold nature of the Subject of which we ſpeak, and alſo the uncertain condition of the humours both in their kind and motion. Which was the cauſe why *Hippocrates* even in the firſt of his Aphoriſms pronounceth that Judgment is difficult. But firſt of all, it is very expedient that a Surgeon be of an honeſt mind, that he muſt always have before his eyes a careful regard of true piety, that is to ſay, the fear of God and faith in Chriſt, and love toward his Neighbors, with hope of life everlaſting, leſt that he being carried away by favour, or corrupted with money or rewards, ſhould affirm or teſtifie thoſe wounds to be ſmall that are great, and thoſe great that are ſmall; for the report of the wound is received of the Surgeon according to the Civil Law.

What judgment is difficult.

Wounds termed great for three reſpects.

It is recorded in the Works of ancient Phyſicians, that Wounds may be called great for three reſpects. The firſt is by reaſon of the greatneſs of the diſſolved Unity, or reſolution of Continuity; and ſuch are theſe wounds, which made by a violent ſtroke with a Back-ſword have cut off the Arm or Leg, or overthwart the Breſt. The ſecond is by reaſon of the dignity or worthineſs of the part; now this dignity dependeth on the excellency of the action; therefore thus any little wound made with a Bodkin, or Knife, in any part whoſe ſubſtance is noble, as in the Brain, Heart, Liver, or any other part whoſe action and function is neceſſary to preſerve life, as in the Weaſon, Lungs, or Bladder, is judged great. The third is, by reaſon of the greatneſs and ill habit, or the abundance of ill humours, or debility of all the wounded body; ſo thoſe wounds that are made in the nervous parts, and old decaied people, are ſaid to be great. But in ſearching of wounds let the Surgeon take heed that he be not deceived by his Probe. For many times it cannot go into the bottom of the wound but ſtoppeth and ſticketh by the way, either becauſe he hath not placed the Patient in the ſame poſture wherein he was when he received his hurt; or elſe for that the ſtroke being made down-right, ſlipt aſide to the right or left hand, or elſe from below upwards, or from above downwards, and then he may expect that the wound is but little, and will be cured in a ſhort time, when it is like to be long in curing, or elſe mortal. Therefore from the firſt day it behooveth him to ſuſpend his judgment of the wound until the ninth, for in time the accidents will ſhew themſelves manifeſtly whether they be ſmall or great, according to the condition of the wound or wounded bodies, and the ſtate of the air according to his primitive qualities, or venomous corruption.

How long a Surgeon muſt ſuſpend his judgment in ſome caſes.

General ſigns whereby we judge of Diſeaſes.

But generally the ſigns whereby we may judge of diſeaſes whether they be great or ſmall, of long or ſhort continuance, mortal or not mortal, are four. For they are drawn either from the nature and eſſence of the Diſeaſe, or from the cauſe or effects thereof, or elſe from the ſimilitude, proportion, and compariſon of thoſe Diſeaſes, with the ſeaſon or preſent conſtitution of the times. Therefore if we are called to the cure of a green wound, whoſe nature and danger is no other but a ſimple ſolution of Continuity in the muſculous fleſh, we may preſently pronounce that wound to be of no danger, and that it will ſoon be cured. But if it have an Ulcer annexed unto it, that is, if it be ſanious, then we may ſay it will be more difficult and long in curing; and ſo we may pronounce of all Diſeaſes, taking a ſign of their eſſence and nature. But of the ſigns that are taken of the cauſes, let this be an example. A wound that is made with a ſharp-pointed and heavy weapon, as with an Halberd being ſtricken with great violence, muſt be accounted great, yea and alſo mortal, if the accidents be correſpondent.

But if the Patient fall to the ground through the violence of the ſtroke, if a cholerick vomiting follow thereon, if his ſight fail him, together with a giddineſs, if bloud come forth at his eyes and noſtrils, if diſtraction follow with loſs of memory and ſenſe of feeling, we may ſay that all the hope of life remaineth in one ſmall ſign which is to be deduced from the affects of the wound. But by comparing it unto the ſeaſon that then is, and diſeaſes that then aſſault Mans Body, we may ſay, that all thoſe that are wounded with Gun-ſhot, are in danger of death, as it happened in the Skirmiſhes at the Siege of *Roan*, and at the battle of Saint *Denis*. For at that time, whether it were by reaſon of the fault of the Heavens, or Air, through the evil humours of mans body, and the diſturbance of them, all wounds that were made by Gun-ſhot, were for the moſt part mortal. So likewiſe at certain ſeaſons of the year, we ſee the Small-pox and Meazles break forth in children, as it were by a certain peſtilent contagion to the deſtruction of children onely, inferring a moſt cruel vomit and laſk; and in ſuch a Seaſon the judgment of thoſe Diſeaſes is not difficult. But you by the following ſigns may know what parts are wounded. If the Patient fall down with the ſtroke, if he lie ſenſleſs as it were aſleep, if he avoid his excrements unwittingly, if he be taken with giddineſs, if bloud come out at his Ears, Mouth, and Noſe, and if he vomit choler, you may underſtand that the skull is fractured, or pierced through, by the defect of his underſtanding and diſcourſe. You alſo may know when the skull is fractured, by the judgment of your external ſenſes, as if by feeling it with your finger you find it elevated or depreſſed beyond the natural limits, if by ſtriking it with the end of a Probe, when the *Pericranium* or nervous film that inveſteth the skull is cut croſs-wiſe, and ſo divided

Wounds deadly by the fault of the air.

Signs of a fractured skull.

vided there from it, it yield a baſe and unperfect ſound like unto a pot-ſherd that is broken, or rather like to an earthen Pitcher that hath a cleft, or rent therein.

But we may ſay, that death is at hand if his Reaſon and Underſtanding fail him, if he be ſpeechleſs, if his light forſake him, if he would tumble headlong out of his bed, being not at all able to remove the other parts of his body; if he have a continual Fever, if his tongue be black with drineſs, if the edges of the wound be black or drie, and caſt forth no ſanious matter, if they reſemble the colour of ſalted fleſh, if he have an Apoplexy, Phrenſie, Convulſion or Palſie, with an involuntary excretion, or abſolute ſuppreſſion of the Urine and Excrements. You may know that a man hath his throat, that is, his weaſon and wind-pipe cut: Firſt by the ſight of his wound, and next by the aboliſhment of the function or office thereof both ways, for the Patient can neither ſpeak nor ſwallow any meat or drink; and the parts that are cut aſunder, divide themſelves by retraction upwards or downwards one from another, whereof cometh ſudden or preſent death. You may know that a Wound hath pierced into the breſt or concavity of the body, if the air come forth at the wound making a certain whizzing noiſe, if the Patient breath with great difficulty, if he feel a great heavineſs or weight on or about the midriff, whereby it may be gathered that a great quantity of bloud lieth upon the place or midriff, and ſo cauſeth him to feel a weight or heavineſs, which by little and little, will be caſt up by vomiting. But a little after a Fever cometh, and the breath is unſavoury and ſtinking, by reaſon that the putrifying bloud is turned into *ſanies*: the Patient cannot lie but on his back, and he hath an often deſire to vomit, but if he eſcape death, his wound will degenerate into a Fiſtula, and at length will conſume him by little and little.

Signs of death by a wound on the head.

Signs that the throat is cut.

Signs that a wound hath pierced in the concavity of the cheſt.

We may know that the Lungs are wounded by the foaming and ſpumous bloud coming out both at the wound, and caſt up by vomiting; he is vexed with a grievous ſhortneſs of breath, and with pain in his ſides. We may perceive the Heart to be wounded by the abundance of bloud that cometh out of the wound, by the trembling of all the whole body, by the faint and ſmall pulſe, paleneſs of the face, cold ſweat, with often ſwooning, coldneſs of the extreme parts, and ſudden death.

Signs that the Lungs are wounded.

That the heart is wounded.

When the Midriff (which the *Latins* call *Diaphragma*) is wounded, the Patient feeleth a great weight in that place, he raveth and talketh idlely, he is troubled with ſhortneſs of wind, a cough, and fit of grievous pain, and drawing of the intrails upwards. Wherefore when all theſe accidents appear, we may certainly pronounce that death is at hand.

The Midriff.

Death appeareth ſuddenly, by a wound of the hollow Vein, or the great Artery, by reaſon of the great and violent evacuation of bloud and ſpirits, whereby the functions of the Heart and Lungs are ſtopped and hindered.

The *Vena Cava* and great Artery.

The Marrow of the back-bone being pierced, the Patient is aſſaulted with a Palſie or Convulſion very ſuddenly, and ſenſe and motion faileth in the parts beneath it, the excrements of the bladder are either evacuated againſt the Patients will, or elſe are altogether ſtopped.

The ſpinal marrow.

When the Liver is wounded much bloud cometh out at the wound, and pricking pain diſperſeth it ſelf even unto the ſword-like griſtle, which hath its ſituation at the lower end of the breſt-bone called *Sternon*: the bloud that followeth from thence down into the inteſtines doth oft-times infer moſt malign accidents, yea, and ſometimes death.

The Liver.

When the Stomach is wounded, the meat and drink come out at the wound, there followeth a vomiting of pure choler, then cometh ſweating and coldneſs of the extreme parts, and therefore we ought to prognoſticate death to follow ſuch a wound.

The Stomach.

When the Milt or Spleen is wounded, black and groſs bloud cometh out at the wound, the Patient will be very thirſty, with pain on the left ſide, and the bloud breaks forth into the belly, and there putrefying cauſeth moſt malign and grievous accidents, and often-times death to follow.

The Spleen.

When the guts are wounded, the whole body is griped and pained, the excrements come out at the wound, whereat alſo oft-times the guts break forth with great violence.

The Guts.

When the Reins or Kidnies are wounded the Patient will have great pain in making his Urin, and the bloud cometh out together therewith; the pain cometh down even unto the Groin, and Yard, and Tetticles.

The Kidnies.

When the Bladder and Ureters are wounded, the pain goeth even unto the intrails; the parts all about and belonging to the Groin, are diſtended, the Urine is bloudy that is made, and the ſame alſo cometh oftentimes out of the wound.

The Bladder.

When the Womb is wounded the bloud cometh out at the privities, and all other accidents appear like as when the Bladder is wounded.

The Womb.

When the Sinews are pricked or cut half aſunder, there is great pain in the affected place, and there followeth a ſudden Inflammation, Flux, Abſceſs, Fever, Convulſion, and oftentimes a Gangrene or Mortification of the part, whereof cometh death, unleſs it be ſpeedily prevented.

The Nerves.

Having declared the ſigns and tokens of wounded parts, it now remaineth that we ſet down other ſigns of certain kinds of death, that are not common, or natural, whereabout when there is great ſtrife and contention made, it oftentimes is determined and ended by the judgment of the diſcreet Phyſician or Surgeon.

Therefore if it chance that a Nurſe either through drunkenneſs or negligence, lies upon the Infant lying in bed with her, and ſo ſtifles and ſmothers it to death: if your judgment be required, whether the Infant died through the default or negligence of the Nurſe, or through ſome violent or ſudden diſeaſe that lay hidden and lurking in the body thereof, you ſhall find out the truth of the matter by theſe ſigns following.

Signs that an Infant is ſmothered, or over-laid.

For if the Infant were in good health before; if he were not froward or crying; if his mouth and noſtrils, now being dead, be moiſtned or bedewed with a certain foam; if his face be not pale, but of a violet or purple colour; if when the body is opened the Lungs be found ſwollen and puffed up, as it were with a certain vaporous foam, and all other intrails ſound; it is a token that the Infant was ſtifled, ſmothered or ſtrangled by ſome outward violence.

If the Body or dead Corps of a man be found lying in a Field, or Houſe alone, and you be called by a Magiſtrate to deliver your opinion, whether the man were ſlain by Lightning or ſome other violent death; you may by the following ſigns find out the certainty hereof.

Signs of ſuch as are ſlain by Lightning.

For every body that is blaſted or ſtricken with lightning, doth caſt forth or breath out an unwholſome, ſtinking or ſulphureous ſmell, ſo that the Birds and Fowls of the air, or Dogs will not once touch it, much leſs prey or feed upon it: the part that was ſtricken often times ſound, and without a wound; but if you ſearch it well, you ſhall find the bones under the skin to be bruiſed, broken or ſhivered in pieces.

Lib.2.cap.54.

But if the Lightning hath pierced into the body, with making a wound therein (according to the judgment of *Pliny*) the wounded part is far colder than all the reſt of the body. For lightning driveth the moſt thin and fiery air before it, and ſtriketh it into the body with great violence, by the force whereof the heat that was in the part is ſoon diſperſed, waſted, and conſumed. Lightning doth always leave ſome impreſſion or ſign of ſome Fire either by uſtion or blackneſs: for no Lightning is without Fire.

Moreover whereas all other living Creatures when they are ſtricken with Lightning, fall on the contrary ſide, onely man falleth on the affected ſide, if he be not turned with violence toward the coaſt or region from whence the lightning came.

If a man be ſtricken with Lightning while he is aſleep, he will be found with eyes open; contrariwiſe, if he be ſtricken while he is awake, his eyes will be cloſed, as *Pliny* writeth. *Philip Commines* writeth that thoſe Bodies that are ſtricken with lightning, are not ſubject to corruption as others are.

Therefore in ancient time it was their cuſtom neither to burn nor bury them; for the brimſtone which the Lightning bringeth with it, was unto them in ſtead of Salt, for that by the drineſs and fiery heat thereof it did preſerve them from putrefaction.

Signs of wounds given to a living or dead man.

Alſo it may be inquired in judgment, Whether any that is dead and wounded, received theſe wounds alive or dead. Truly the wounds that are made of a living man, if he die of them, after his death will appear red and bloudy, with the ſides or edges ſwollen, or pale round about: contrariwiſe, thoſe that are made in a dead man, will be neither red, bloudy, ſwollen nor puffed up. For all the faculties and functions of life in the body do ceaſe and fall together by death; ſo that thenceforth no ſpirits nor bloud can be ſent, or flow into the wounded place. Therefore by theſe ſigns which ſhall appear, it may be declared that he was wounded dead or alive.

Signs whether one be hanged alive or dead.

The like queſtion may come in judgment when a man is found hanged, whether he were dead or alive. Therefore if he were hanged alive, the impreſſion or print of the rope will appear red, pale, or black, and the skin round about it will be contracted or wrinkled, by reaſon of the compreſſion which the cord hath made; alſo oftentimes the head of the *aſpera arteria* is rent and torn, and the ſecond ſpondyl, and the neck luxated or moved out of his place. Alſo the arms and legs will be pale by reaſon of the violent and ſudden ſuffocation of the ſpirits: moreover there will be a foam about his mouth, and a foamy and filthy matter hanging out of his noſtrils, being ſent thither both by reaſon that the Lungs are ſuddenly heated and ſuffocated, as alſo by the convulſion and concuſſion of the brain, like as it were in the Falling-ſickneſs. Contrariwiſe, if he be hanged dead, none of theſe ſigns appear: for neither the print of the rope appears red or pale, but of the ſame colour as the other parts of the body are, becauſe in dead men the bloud and ſpirits do not flow to the grieved parts.

Whether one found dead in the Water, came therein alive or dead.

Whoſoever is found dead in the Waters, you ſhall know whether they were thrown into the Water alive or dead. For all the belly of him that was thrown in alive will be ſwollen and puffed up by reaſon of the water that is contained therein; certain clammy excrements come out at his mouth and noſtrils, the ends of his fingers will be worn and excoriated, becauſe that he died ſtriving and digging or ſcraping in the ſand or bottom of the River, ſeeking ſomewhat whereon he might take hold to ſave himſelf from drowning. Contrariwiſe, if he be thrown into the Waters, being dead before, his belly will not be ſwollen, becauſe that in a dead man all the paſſages and conduits of the body do fall togeter, and are ſtopped and cloſed, and for that a dead man breaths not, there appeareth no foam nor filthy matter about his mouth and noſe, and much leſs can the tops of his fingers be worn and excoriated, for when a man is already dead, he cannot ſtrive againſt death.

But as concerning the bodies of thoſe that are drowned, thoſe that ſwim on the upper part of the Water being ſwollen or puffed up, they are not ſo by reaſon of the water that is conteined in the belly, but by reaſon of a certain vapour, into which a great portion of the humors of the body are converted by the efficacy of the putrefying heat. Therefore this ſwelling appeareth not in all men which do periſh, or elſe are caſt out dead into the Waters, but onely in them which are corrupted with the filthineſs or muddineſs of the Water, long time after they were drowned, and caſt on the ſhore.

Of ſuch as are ſmothered by Charcoal.

But now I will declare the accidents that come to thoſe that are ſuffocated and ſtifled or ſmothered with the vapour of kindled or burning Charcoals, and how you may fore-tell the cauſes thereof by the hiſtory following. In the year of our Lord God 1575. the tenth day of *May*, my ſelf with *Robert Gleauline* Doctor of Phyſick, was ſent for by Mr. *Hamel*, an Advocate of the Court of *Parliament* at *Paris*, to ſee and ſhew my opinion on two of his ſervants, of whom the one was his Clerk, and the other his Horſe-keeper. All his Family ſuppoſed them dead, becauſe they could not perceive or feel their Arteries to beat, all the extreme parts of their bodies were cold, they could neither ſpeak nor move, their faces were pale and wan, neither could they be raiſed up with any violent beating or plucking by the hair. Therefore all men accounted them dead, and the queſtion was onely of what kind of death they died, for their Maſter ſuſpected that ſome body had ſtrangled them; others thought that each of them had ſtopped one anothers wind with their hands: and others judged that they were taken with a ſudden Apoplexy. But I

preſently

preſently enquired, whether there had been any fire made with Coals in the houſe lately? whereunto their Maſter giving ear, ſought about all the corners of the Chamber, (for the Chamber was very little and cloſe) and at laſt found an earthen pan with Charcoal half-burned: which when we once ſaw, we all affirmed with one voice, that it was the cauſe of all this misfortune, and that it was the malign fume and venomous vapour which had ſmothered them, as it were by ſtopping the paſſages of their breath. Therefore I put my hand to the regions of their hearts, where I might perceive that there was ſome life remaining by the heat and pulſation that I felt, though it were very little, wherefore we thought it convenient to augment and increaſe it. Therefore firſt of all artificially opened their mouths, which were very faſt cloſed, and ſticking obſtinately together; and thereinto both with a ſpoon and alſo with a ſilver pipe, we put *Aqua vitæ* often diſtilled with diſſolved *Hiera* and Triacle; when we had injected theſe Medicins often into their mouths, they began to move and to ſtretch themſelves, and to caſt up and expel many viſcous excremental and filthy humours at their mouths and noſtrils, and their Lungs ſeemed to be hot, as it were in their throats.

Therefore then we gave them vomitories of a great quantity of *Oxymel*, and beat them often violently on the laſt ſpondil of the back, and firſt of the loins, both with the hand and knee (for unto this place the orifice of the ſtomach is turned) that by the power of the vomitory Medicin and concuſſion of the ſtomach, they might be conſtrained to vomit. Neither did our purpoſe fail us, for preſently they voided clammy, yellow and ſpumous phlegm and bloud.

But we not being contented with all this, blowed up into their noſtrils, out of a Gooſe-quill, the powder of *Euphorbium*, that the expulſive faculty of the brain might be ſtirred up to the expulſion of that which oppreſſed it; therefore preſently the brain being ſhaken, or moved with ſneezing, and inſtimulated thereunto by rubbing the Chymical oil of Mints on the Palate and on the Cheeks, they expelled much viſcous and clammy matter at their noſtrils.

Then we uſed Frictions to their arms, leggs, and back-bones, and miniſtred ſharp Clyſters, by whoſe efficacy the belly being abundantly looſened, they began preſently to ſpeak, and to take things that were miniſtred unto them of their own accord, and ſo came to themſelves again.

In the doing of all theſe things, *James Guillemeau* Surgeon to the King at *Paris*, and *John* of St. *Germans* the Apothecary, did much help and further us.

In the Afternoon that the matter being well begun might have good ſucceſs, *John Hauty* and *Lewis Thibaut*, both moſt learned Phyſicians, were ſent for unto us, with whom we might conſult on other things that were to be done. They highly commended all things that we had done already, thought it very convenient that Cordials ſhould be miniſtred unto them, which by ingendering of laudable humours, might not onely generate new ſpirits, but alſo attenuate and putrefie thoſe that were cloudy in their bodies. The reſt of our conſultation was ſpent in the inquiry of the cauſe of ſo dire a miſchance. For they ſaid it was no new or ſtrange thing, that men may be ſmothered with the fume and cloudy vapour of burning Coals.

For we read in the Works of *Fulgoſius*, *Volaterenus*, and *Egnatius*, that as the Emperour *Jovinian* travelled in Winter time towards *Rome*, he being weary in his journey, reſted at a Village called *Didaſtanes*, which divideth *Bithynia* from *Galatia*, where he lay in a Chamber that was newly made, and plaſtred with Lime, wherein they burned many Coals, for to drie the Work or Plaſtering, that was but as yet green on the Walls or Roofs of the Chamber. Now he died the very ſame night being ſmothered or ſtrangled with the deadly and poiſonous vapour of the burned Charcoal, in the midſt of the night; this happened to him in the eighth moneth of his Reign, the thirteenth year of his Age, and on the twentieth day of *Auguſt*. But what need we to amplifie this matter by the ancient Hiſtories, ſeeing that not many years ſince three ſervants died in the houſe of *John Bigine* Goldſmith, who dwelt at the turning of the Bridge at the Change, by reaſon of a fire made with Coals in a cloſe Chamber without any Chimney where they lay: and as concerning the cauſes, theſe were alledged; Many were of Opinion that it happened by the default of the vapour proceeding from the burned Coals, which being in a place void of all Air or Wind, infers ſuch like accidents as the vapour or Muſt of new Wine doth, that is to ſay, pain and giddineſs of the head. For both theſe kinds of Vapour, beſides that they are crude, like unto thoſe things whereof they come, can alſo very ſuddenly obſtruct the original of the Nerves, and ſo cauſe a Convulſion, by reaſon of the groſsneſs of their ſubſtance.

Lib. 9. cap. 12. lib. 23. An Hiſtory.

For ſo *Hippocrates* writing of thoſe accidents that happen by the vapour of new Wine, ſpeaketh; If any man being drunken, do ſuddenly become ſpeechleſs and hath a convulſion, he dieth, unleſs he have a Fever therewithal; or if he recover not his ſpeech again when his drunkenneſs is over. *Sect. 5. Aph. 5.*

Even on the ſame manner the vapour of the Coals aſſaulting the Brain, cauſed them to be ſpeechleſs, unmoveable, and void of all ſenſe, and had died ſhortly, unleſs by miniſtring and applying warm Medicins into the mouth and to the noſtrils, the groſsneſs of the vapour had been attenuated, and the expulſive faculty moved or provoked to expel all thoſe things that were noiſom: and alſo although at the firſt ſight the Lungs appeared to be grieved more then all the other parts, by reaſon that they drew the malign vapour into the body, yet when you conſider them well, it will manifeſtly appear that they are not grieved, unleſs it be by the ſympathy or affinity that they have with the brain when it is very grievouſly afflicted.

The proof hereof is, becauſe preſently after there followeth an interception or defect of the Voice, Senſe and Motion: which accidents could not be, unleſs the beginning or original of the Nerves were intercepted or letted from performing its function, being burthened by ſome matter contrary to Nature.

The occaſion of the death of ſuch as have the Apoplexy.

And even as thoſe that have an Apoplexy do not die but for want of reſpiration, yet without any offence of the Lungs, even ſo theſe two young mens deaths were at hand, by reaſon that their reſpiration or breathing was in a manner altogether intercepted, not through any default of the Lungs,

Lungs, but of the Brain and Nerves diſtributing ſenſe and motion to the whole body and eſpecially to the inſtruments of reſpiration. Others contrariwiſe contended and ſaid, that there was no default in the Brain, but conjectured the interception of the vital ſpirits letted or hindered from going up into the brain from the heart, by reaſon that the paſſages of the Lungs were ſtopped, to be the occaſion that ſufficient matter could not be afforded for to preſerve and feed the animal ſpirit. Which was the cauſe that thoſe young men were in danger of death, for want of reſpiration, without which there can be no life.

For the heart being in ſuch a caſe, cannot deliver it ſelf from the fuliginous vapours that encompaſs it, by reaſon that the Lungs are obſtructed by the groſsneſs of the vapour of the Coals, whereby inſpiration cannot well be made, for it is made by the compaſſing air drawn into our bodies: but the air that compaſſeth us doth that which Nature endeavoureth to do by inſpiration, for it moderateth the heat of the heart, and therefore it ought to be endued with four qualities. The firſt is, that the quantity that is drawn into the body be ſufficient. The ſecond is, that it be cold, or temperate in quality. The third is, that it be of a thin and mean conſiſtence. The fourth is, that it be of a gentle benign ſubſtance.

But theſe four conditions were wanting in the air which thoſe two young men drew into their bodies being in a cloſe Chamber.

Conditions of the air good to breath in.

For firſt it was little in quantity, by reaſon that ſmall quantity that was contained in that little cloſe Chamber, was partly conſumed by the fire of coals, no otherwiſe than the air that is contained in a Cupping-glaſs is conſumed in a moment by the flame ſo ſoon as it is kindled.

Furthermore it was neither cold nor temperate, but as it were inflamed with the burning fire of Coals.

Thirdly, It was more groſs in conſiſtence than it ſhould be, by reaſon of the admixtion of the groſſer vapour of the coals: for the Nature of the air is ſo that it may be ſoon altered, and will very quickly receive the forms and impreſſions of thoſe ſubſtances that are about it.

Laſtly, it was noiſom and hurtful in ſubſtance, and altogether offenſive to the airy ſubſtance of our bodies. For Charcoals are made of green wood burnt in pits under ground, and then extinguiſhed with their own fume or ſmoak, as all Colliers can tell. Theſe were the opinions of moſt learned men, although they were not altogether agreeable one unto another, yet both of them depended on their proper reaſons. For this at leaſt is manifeſt, that thoſe paſſages which are common to the Breſt and Brain, were then ſtopped with the groſsneſs of the vapours of the coals: whereby it appeareth that both theſe parts were in fault, for as much as the conſent and connexion of them with the other parts of the body is ſo great, that they cannot long abide ſound and perfect without their mutual help by reaſon of the loving and friendly ſympathy and affinity that is between all the parts of the body one with another.

Wherefore the ventricles of the Brain, the paſſages of the Lungs, and the ſleepy Arteries being ſtopped, the vital ſpirit was prohibited from entering into the Brain, and conſequently the animal ſpirit retained and kept in, ſo that it could not come or diſperſe it ſelf through the whole body, whence happeneth the defect of two of the faculties neceſſary for life.

Of the ſigns of Virginity.

It many times happeneth, and is a queſtion too frequently handled, concerning Womens Maidenheads; whereof the judgment is very difficult. Yet ſome ancient Women and Midwives will brag that they aſſuredly know it by certain and infallible ſigns. For (ſay they) in ſuch as are Virgins there is a certain membrane of parchment-like skin in the neck of the Womb, which will hinder the thruſting in of the finger if it be put in any thing deep; which membrane is broken when firſt they have carnal copulation, as may afterwards be perceived by the free entrance of the finger. Beſides, ſuch as are deflowered have the neck of their womb more large and wide; as on the contrary, it is more contract, ſtrait, and narrow in Virgins. But how deceitful and untrue theſe ſigns and tokens are, ſhall appear by that which followeth; for this membrane is a thing preternatural, and which is ſcarce found to be in one of a thouſand, from the firſt conformation. Now the neck of the Womb will be more open or ſtrait, according to the bigneſs and age of the party. For all the parts of the body have a certain mutual proportion and commenſuration in a well made body.

Lib. de error. popul.

Joubertus hath written, that at *Lectaure* in *Gaſcony*, a Woman was delivered of a child in the nineth year of her age, and that ſhe is yet alive, and called *Joan de Parie*, wife to *Videau Beche* the Receiver of the Amercements of the King of *Navarre:* which is a moſt evident aegument, that there are ſome Women more able to accompany with a man at nine years old, than many other at fifteen, by reaſon of the ample capacity of their womb, and the neck thereof: beſides alſo, this paſſage is enlarged in many by ſome accident, as by thruſting their own fingers more ſtrong thereinto by reaſon of ſome itching, or by the putting up of a Nodule or Peſſary, of the bigneſs of a mans Yard, for to bring down the Courſe. Neither to have milk in their breſts is any certain ſign of loſt Virginity. For *Hippocrates* thus writes: But if a Woman which is neither with child, nor hath had one, have milk in her breſts, then her Courſes have failed her.

Aph. 39. ſect. 5.

Moreover, *Ariſtotle* reports that there be men who have ſuch plenty of milk in their breſts, that it may be ſucked or milked out,

Lib. 4. de Hiſt. animal. c. 20. Lib. 12. de ſubtilitate.

Cardan writes, that he ſaw at *Venice* one *Anthony Buſſey*, ſome 30 years old, who had milk in his breſt in ſuch plenty, as ſufficient to ſuckle a child, ſo that it did not onely drop but ſpring out with violence like to a womans milk. Wherefore let Magiſtrates beware, leſt thus admoniſhed, they too raſhly aſſent to the reports of Women. Let Phyſicians and Chirurgeons have a care leſt they do too impudently bring Magiſtrates into an errour, which will not redound ſo much to the Judges diſgrace as to theirs.

But if any deſire to know whether one be poiſoned, let him ſearch for the ſymptoms and ſigns in the fore-going and particular Treatiſe of Poiſons. But that this doctrine of making Reports may be the eaſier, I think it fit to give preſidents, in imitation whereof the young Chirurgeon may frame

others.

others. The first president shall be of death to ensue; a second of a doubtful judgment of life and death; the third of an impotency of a member; the fourth of the hurting of many members.

I *A.P.* Chirurgeon of *Paris*, this twentieth day of *May*, by the command of the Council, entered into the house of one *John Brossey*, whom I found lying in bed, wounded on his head, with a wound in his left temple, piercing the bone with a fracture, and effracture or depression of the broken bone, scales and *meninges* into the substance of the brain, by means whereof his pulse was weak, he was troubled with raving, convulsion, cold sweat, and his appetite was dejected. Whereby may be gathered that certain and speedy death is at hand. In witness whereof I have signed this Report with my own hand. A certificate of death.

By the Coroners command I have visited *Peter Lucey*, whom I found sick in bed, being wounded with a Halbard on his right thigh. Now the wound was of the bredth of three fingers, and so deep that it pierces quite through his thigh with the cutting also of the Vein and Artery, whence insued much effusion of bloud, which hath exceedingly weakned him, and caused him to swound often; now all his thigh is swollen, livid, and gives occasion to fear worse symptoms, which is the cause that the health and safety of the party is to be doubted of. Another in a doubtful case.

By the Justices command I entered into the house of one *James Bertey*, to visit his own brother; I found him wounded in his right arm, with a wound of some four fingers bigness, with the cutting of the tendons bending the leg, and of the Veins, Arteries, and Nerves. Wherefore I affirm that he is in danger of his life, by reason of the malign symptoms that usually happen upon such wounds, such as are great pain, a Fever, Inflammation, Abscess, Convulsion, Gangrene, and the like. Wherefore he stands in need of provident and careful dressing, by benefit whereof if he escape death, without doubt he will continue lame during the remainder of his life, by reason of the impotency of the wounded part. And this I affirm under my hand. In the loss of a member.

We the Surgeons of *Paris*, by the command of the Senate, this twentieth day of *March*, have visited Master *Lewis Vertoman*, whom we found hurt with five wounds. The first inflicted on his head, in the middle of his fore-head-bone, to the bigness of three fingers, and it penetrates even to the second table, so that we were forced to pluck away three splinters of the same bone. The other was athwart his right cheek, and reacheth from his ear to the midst of his nose, wherefore we stitched it with four stitches. The third is on the midst of his belly, of the bigness of two fingers, but so deep that it ascends into the capacity of the belly, so that we were forced to cut away portion of the Kall coming out thereat, to the bigness of a Walnut, because having lost its natural colour, it grew black and putrefied. The fourth was upon the back of his left hand, the bigness almost of four fingers, with the cutting of the Veins, Arteries, Nerves, and part of the bones of that part; whence it is that he will be lame of that hand, howsoever carefully and diligently healed. Another in the hurts of divers parts.

Now because by hurting the spinal marrow men become lame sometimes of a leg, it is fit you know that the spinal marrow descends from the brain like a Rivulet for the distribution of the Nerves, which might distribute sense and motion to all the parts under the head; wherefore if by hurting the spinal marrow the Patients arms or hands are resolved or numb, or wholly without sense, it is a sign these nerves are hurt which come forth of the fifth, sixth, seventh *Vertebræ* of the neck. But if the same accidents happen to the thigh, leg, or foot with refrigeration, so that the excrements flow voluntarily, without the Patients knowledge, or else are totally suppresst, it is a sign that the sinews which proceed from the *Vertebræ* of the loins and holy-bone are hurt, or in fault; so that the animal faculty bestowing sense and motion upon the whole body, and the benefit of opening and shutting of the sphincter muscle of the bladder and fundament, cannot shew it self in these parts, by which means sudden death happens, especially if there be difficulty of breathing therewith.

Being to make Report of a Child killed by the Mother, have a care that you make a discreet Report, whether the child were perfect in all the parts and members thereof, that the Judge may equally punish the author thereof. For he meriteth far greater punishment, who hath killed a child perfectly shaped and made in all the members; that is, he which hath killed a live child, than he which hath killed an *Embryon*, that is, a certain concretiou of the spermatick body. For *Moses* punisheth the former with death, as that he should give life for life, but the other with a pecuniary mulct. But I judg it fit to exemplifie this report by a president. A caution in making Report of a Woman with child being killed.

I *A.P.* By the Judges command visited Mistriss *Margaret Ulmargy*, whom I found sick in bed, having a strong Fever upon her, with a convulsion and efflux of bloud out of her womb, by reason of a wound in her lower belly, below her navel on the right side, penetrating into the capacity of her belly, and the wound therein; whence it hath come to pass, that she was delivered before her time of a male child, perfect in all his members, but dead, being killed by the same wound, piercing through his scull into the marrow of the brain. Which in a short time will be the death of the Mother also. In testimony whereof, I have put my hand and seal.

The manner how to Embalm *the Dead.*

I Had determined to finish this my tedious work with the precedent Treatise of Reports; but a better thought came into my head, which was, to bring Man, whose cure I had undertaken, from his Infancy to his End, and even to his Grave; so that nothing might be here defective which the Surgeon might by his Profession perform about Mans body either alive or dead. Verily there hath scarce ever been a Nation so barbarous, which hath not only been careful for the Burial, but also for the Embalming or preserving of their dead bodies. For the very *Scythians*, who

The care of the *Scythians* in the embalming their dead.

have seemed to exceed other Nations in barbarousness and inhumanity, have done this; for (according to *Herodotus*) the *Scythians* bury not the corps of their King, before that being imbowelled and stuffed full of beaten Cypress, Frankincense, the Seeds of Parsley, and Anise, he be also wrapped in Cere-cloths. The like care hath also possessed the minds of the *Ethiopians*, for having disburthened the corps of their friends of their entrails and flesh, they plastered them over, and then they thus rough-cast them, they painted them over with colours so to express the dead to the life; they inclosed them thus adorned in a hollow pillar of Glass, that thus inclosed they may be seen and yet not annoy the Spectators with their smell. Then were they kept for the space of a year, in the hands of their next kindred; who, during this space, offered and sacrificed to them. The year ended, they carried them forth of the City, and placed them about the Walls each in his proper Vault, as *Herodotus* affirms. But this pious care of the dead did far otherwise affect the *Egyptians* than it did other Nations: For they were so studious to preserve the memory of their Ancestors, that they embalmed their whole body with aromatick ointments, and set them in translucent Urns, or glass Cells, in the more eminent and honoured part of their houses, that so they might have them daily in their sight, and might be as monuments and inciters to stir up them to imitate their Fathers and Grandsires Vertues. Besides also the bodies thus embalmed with aromatick and balsamick ointments, were in stead of a most sure pawn, so that if any *Egyptian* had need of a great sum of money, they might easily procure it of such as knew them and their neighbours, by pawning the dead body of some of their dead Parents. For by this means the Creditor was certain, that he which pawned it, would sooner lose his life than break his promise. But if all things so unhappily succeeded with any, so that through poverty he could not fetch home his pawn again, but was forced to forego it, he was so infamous amongst all men, during the rest of his life, as one banished, or forlorn; and losing his freedom he shall become a servant, yea, scorned and reviled of all men, he should be accounted unworthy to enjoy the light and society of men. And certainly the *Egyptians* understanding the life which we here lead, to be of short continuance, comparison being made with that which we are to live after separation of the soul from the body, they were more negligent in building their houses they dwelt in, but in rearing the Pyramids which should serve them in stead of Sepulchres, they were so beyond reason sumptuous and magnificent, that for the building one of these Edifices so renowned over all the World, which King *Cheopes* begun, a hundred thousand men were every three moneths, for twenty years space there kept at work: It was five furlongs, and being square, each side was 800 foot long, and so much in height. Almost all the pieces of marble went to the building thereof, were thirty foot long, engraven and carved with various workmanship, as *Herodotus* reports. But before the bodies were committed to these magnificent Sepulchres, they were carried to the Salters and Embalmers, who for that purpose had allowance out of the publick stock. These besmeared them with aromatick and balsamick Ointments, and sewed up the incisions they made, then strewed them over with Salt, and then covered them with Brine for 70 days; which being expired, they washed them, being taken thence, and all the filth being taken off, they wrapped them in Cotten cloths, glued together with a certain gum; then their Kinsmen placed them thus ordered in a woodden Coffin carved like to a man. This was the sacred and accustomed rite of Embalming and Burying dead bodies amongst the *Egyptians* which were of the richer sort. Our Countrymen the *French*, stirred up with the like desire, embalm the bodies of their Kings and Nobles with Spices and sweet Ointments. Which custom they may seem piously and christianly to have taken from the Old and New Testament, and the ancient and laudable custom of the Jews: for you may read in the New Testament that *Joseph* bought a fine linnen cloth, and *Nicodemus* brought a mixture of Myrrh and Aloes about 100 pound weight, that they might embalm and bury the body of *Jesus Christ* our Saviour, for a sign and argument of the renovation and future integrity which they hoped for by the Resurrection of the dead. Which thing the *Jews* had received by Tradition from their Ancestors. For *Joseph* in the Old Testament commanded his Physicians that they should embalm the dead body of his Father with Spices.

Lib. 3. Of the *Egyptians.*

The reason of building of the *Egyptians* Pyramids.

Lib. 2.

John 19.39.

Gen 50.2.

The manner of embalming for a long continuance.

But the body which is to be embalmed with Spices for very long continuance, must first of all be imbowelled, keeping the heart apart, that it may be embalmed and kept as the Kinsfolks shall think fit. Also the brain, the scull being divided with a Saw, shall be taken out. Then shall you make deep incisions along the arm, thighs, legs, back, loins and buttocks, especially where the greater Veins and Arteries run, first that by this means the bloud may be pressed forth: which otherwise would putrefie and give occasion and beginning to putrefaction to the rest of the body; and then that there may be space to put in the aromatick powders; the whole body shall be washed over with a Sponge dipped in *Aqua vitæ* and strong Vinegar, wherein shall be boiled Wormwood, Aloes, Coloquintida, common Salt and Alum. Then these incisions, and all the passages and open places of the body, and the three bellies shall be stuffed with the following Spices grosly powdered. ℞ *Pulv. rosar. chamæm. melil. balsami, menthæ, anethi, salviæ, lavend. rorismar. marjoran. thymi, absynthii, cyperi, calami aromat. gentianæ, ireos florent. assæ odoratæ, caryophyll. nucis moschat. cinnamomi, styracis, calamitæ. benjoini, myrrhæ, aloes, santal. omnium quod sufficit.* Let the incisions be sewed up, and the open spaces that nothing fall out; then forthwith let the whole body be anointed with Turpentine dissolved with Oil of Roses and Camomil, adding, if you shall think it fit, some Chymical Oils of Spices, and then let it be again strewed over with the fore-mentioned Powder; then wrap it in a linen cloth, and then in Cere-cloths.

How to embalm bodies when as we want spices.

Lastly, let it be put in a Coffin of Lead sure soldered and filled up with drie sweet herbs. But if there be no plenty of the fore-mentioned Spices, as it usually happens in besieged Towns, the Surgeon shall be contented with the powder of quenched lime, common ashes made of Oak-wood.

For thus the body being over and above washed in strong Vinegar or Lye, shall be kept a long time if so be that a great dissolving heat do not bear sway, or if it be not put in a hot and moist place.

And

And this condition of time and place is the cauſe why the dead bodies of Princes and Kings, though embalmed with Art and coſt, within the ſpace of ſix or ſeven days, in which they are kept to be ſhewed to the people after their embalming, do caſt forth ſo grievous a ſcent, that none can indure it; ſo that they are forced to be put in a leaden Coffin. For the air which encompaſſeth them groweth ſo hot by reaſon of the multitude of people flowing to the ſpectacle, and the burning of lights night and day, that the ſmall portion of the native heat which remaineth being diſſipated, they eaſily putrefie, eſpecially when as they are not firſt moiſtened and macerated in the liquor of aromatick things, as the Egyptians anciently uſed to do, ſteeping them in brine for 70 days, as I formerly told you out of *Herodotus*. I put in mind hereby, uſe, that ſo the embalming may become the more durable, to ſteep the bodies (being imbowelled, and pricked all over with ſharp bodkins, that ſo the liquor hindering putrefaction may penetrate the deeper into them) in a wooden Tub filled with ſtrong Vinegar of the decoction of aromatick and bitter things, as Aloes, Rue, Wormwood, and Coloquintida; and there keep them for twenty days, pouring thereinto eleven or twelve pints of *Aqua vitæ*. Then taking it forth, and ſetting it on the feet, I keep it in a clear and drie place. I have at home the body of one that was hanged, which I begged of the Sheriff, embalmed after this manner; which remains ſound for more than 25 years, ſo that you may tell all the muſcles of the right ſide, (which I have cut up even to their heads, and plucked them from thoſe that are next them for diſtinctions ſake, that ſo I may view them with mine eyes, and handle them with my hands as often as I pleaſe, that by renewing my memory I may work more certainly and ſurely, when as I have any more curious operation to be performed) the left ſide remain whole, and the Lungs, Heart, *Diaphragma*, Stomach, Splene, Kidnies, Beard, Hairs, yea and the Nails, which being pared, I have often obſerved to grow again to their form and bigneſs.

Why the bodies of our Princes, how well ſoever embalmed, corrupt in a few days.

And let this be the bound of this our immenſe labour, and by Gods favour, our reſt; to whom Almighty, All-powerful, Immortal and Inviſible, be aſcribed all honour and glory for ever and ever. *Amen.*

Labor improbus omnia vincit.

The End of the Treatiſe of Reports, and Embalming the Dead.

BOOK XXIX.

The Apology and Treatiſe, containing the Voyages made into divers places, by Ambroſe Parey *of* Laval *in* Maine, *Counſellor and Chief Chirurgeon to the King.*

TRuly I had not put my hand to the Pen, to write on ſuch a thing, were it not that ſome have impudently injured, taxed, and more through particular hatred, diſgraced me, than for zeal or love they bear to the publick good; which was, concerning my manner of tying the Veins and Arteries, writing thus as followeth:

Of what the Adverſary acuſeth the Author.

Male igitur & nimium arroganter inconſultus & temerarius quidam, vaſorum uſtionem poſt emortui membri reſectionem à veteribus omnibus plurimum commendatam & ſemper probatam damnare auſus eſt, novum quendam deligandi vaſa modum, contra veteres omnes medicos, ſine ratione, experientiâ & judicio docere cupiens, nec animadvertit majora multo pericula ex ipſa vaſorum deligatione quam acu partem ſanam profunde transfigendo adminiſtrari vult, imminere quam ex ipſa uſtione. Nam ſi acu nervoſam aliquam partem, vel nervum ipſum pupugerit, dum ità novo & inuſitato modo venam abſurde conatur conſtringere, nova inflammatio neceſſario conſequetur, à qua Convulſio & à convulſione cita mors. Quorum ſymptomatum metu Galenus non ante tranſverſa vulnera ſuere audebat (quod tamen minus erat periculoſum) quam muſculorum aponeuroſes denudaſſet. Adde quod forcipes quibus poſt ſectionem iterum carnem dilacerat, cum retracta verſus originem vaſa ſe poſſe extrahere ſomniat, non minorem adferant dolorem quam ignita ferramenta admota. Quod ſi quis laniatum expertus incolumis evaſerit, is Deo optimo maximo, cujus beneficentia crudelitate iſta & carnificina liberatus eſt, maximas gratias habere & ſemper agere debet; which is thus: Ill then, and too arrogantly a certain indiſcreet and raſh perſon would blame and condemn the cauterizing of Veſſels after the amputation of a rotten and corrupted member, much praiſed and commended, and always approved by the Ancients; deſiring to ſhew and teach us without Reaſon, Judgment, and Experience, a new way to tie the Veſſels, againſt the opinion of the ancient Phyſicians, taking no heed, nor being well adviſed, that there happens far greater perils and accidents, through this new way of tying the Veſſels (which he will have to be made with a Needle, piercing deeply the ſound part) then by the burning and uſtion of the ſaid Veſſels; for if the Needle ſhall prick any nervous part, yea the Nerve it ſelf, when he ſhall by this new and unaccuſtomed way, abſurdly conſtrain the vein by binding it, there muſt neceſſarily follow a new Inflammation; from the Inflammation a Convulſion, from a Convulſion, Death: for fear of which accidents, *Galen* never durſt ſtitch tranſverſal wounds, (which notwithſtanding were leſs dangerous) before he had diſcovered the Aponeuroſes of the Muſcles. Moreover the Pincers with which, after the ſection, the fleſh is again dilacerated, while he thinks to draw the Veſſels out which are drawn in toward their original, bring no leſs pain than the cautering irons do. And

The words of the Adverſary.

if any one having experimented this new manner of cruelty have eſcaped danger, he ought to render thanks to Almighty God for ever, through whoſe goodneſs he hath been freed from ſuch tyranny, feeling rather his executioner than his methodical Chirurgeon.

The Authors anſwer.

O what ſweet words are here, for one who is ſaid to be a wiſe and learned Doctor? he remembers not that his white beard admoniſheth him, not to ſpeak any thing unworthy of his age, and that he ought to put off and drive out of him all envy and rancour conceived againſt his neighbour. So now I will prove by Authority, Reaſon and Experience, that the ſaid Veins and Arteries ought to be tied.

Authorities.

AS for Authorities, I will come to that of that worthy man *Hippocrates*, who wills and commands the cure of Fiſtulaes in the Fundament by ligature, as well to conſume the calloſity, as to avoid hæmorrhagy. In the Book of Fiſtulaes of the Fundament, Chap. 3. Book 5. leaf 4.

Galen, Treatiſe 2. chap. 17. in his Method, ſpeaking of a Flux of Bloud made by an outward cauſe, of whom ſee here the words, *It is* (ſaith he) *moſt ſure to tie the root of the Veſſel, which I underſtand to be that which is moſt near to the Liver or the Heart.*

Avicen, Treatiſe 3. Doct. 1. chap. 3. commands to tie the Vein and the Artery, after it is diſcovered towards his original.

Guido of *Cauliac*, ſpeaking of the wounds of the Veins and Arteries, injoineth the Chirurgeon to make the ligature in the Veſſel.

Maſter *Hollier* in the 3. Book, chap. 4. of the matter of Chirurgery, ſpeaking of a flux of bloud, commands expreſly to tie the veſſels.

Calmetheus in 12. chap. of the wounds in the Veins and Arteries, tells a moſt ſure way to ſtay a flux of bloud by ligature of the Veſſel.

Celſus, Chap. 26. Book. 5. from whom the ſaid Phyſician hath ſnatched the moſt part of his Book, chargeth expreſly, to tie the Veſſels in a flux of bloud happening to wounds, as a remedy moſt eaſie and moſt ſure.

Veſalius in his Chirurgery, Chap. 4. Book 3. willeth that the Veſſel be tied in a flux of bloud.

John de Vigo, Book 1. Treatiſe 1. tteating of Hæmorrhagy in bleeding wounds, commands to tie the Vein and the Artery.

Tegaultius, Chap. 12. Book 2. treating of the means to ſtay the flux of bloud, commands to pinch the Vein or Artery with a Crow or Parrots bill, then to tie it with a very ſtrong thred.

Peter of *Argillata* of *Bullonge*, Treatiſe 4. Chap. 11. Book 1. diſcourſing of a flux of bloud, and the means to ſtop it, giveth a fourth way expreſly, which is made by ligature of the Veſſels.

John Andreas a Cruce, a *Venetian*, Book 1. Sect. 3. Chap. 16. Pag. 5. upon the 88 Chapter of the Book of *Paul*, makes mention of a method to ſtay a flux of bloud by the ligature of the Veſſels.

D' Alechamp commands to tie the Veins and Arteries.

See then (my little good man) the Authorities which command you to tie the Veſſels. As for the Reaſons, I will debate of them.

The Hæmorrhagy (ſay you) is not ſo much to be feared in the ſection of the Kall, as that of the Varices, and the inciſion of the temporal Arteries, as after the Amputation of a member. Now you your ſelf command that in cutting the Varices, the flux of bloud be ſtopped by the ligature of the Veſſels. In the Book 2. Chap. of Angealogy, leaf 176. you command the ſame in the Book of Stitches, Chap. 1. ſpeaking of the ſtitch with the amputation and ſection of the Kall, changed by the outward air; ſee here your own words: After that muſt be conſidered concerning the Kall: for if there be any part corrupted, putrefied, withered, or blackiſh: firſt having tied, for fear of a flux of bloud, you do not bid afterwards to have it cauteriſed. But to ſay the truth, you have your eyes ſhut, and all your ſenſes dulled, when you would ſpeak againſt ſo ſure a method, and that it is not but through anger and an ill will. For there is nothing which hath more power to drive Reaſon from her ſeat, than Choler and Anger. Moreover when one comes to cauterize and diſmember the parts, oftentimes when the Eſchar comes to fall off, there happens a new flux of bloud: As I have ſeen divers times, not having been yet inſpired by God, with ſo ſure a means then when I uſed the heat of fire. Which if you have not found, or underſtood this method in the Books of the Ancients, you ought not thus to tread it under your feet, and ſpeak unluckily of one, who all his life hath preferred the profit of the Common-wealth before his own particular. It is not more than reaſonable to be found upon the ſaying of *Hippocrates*, in the Chapter of Burning, Book 2. Leaf 206. upon whoſe Authority you ſerve your ſelf, which is thus. That what the medicament cureth not, the iron doth; and what the iron doth not amend, the fire exterminateth: It is a thing which ſavours not of a Chriſtian, to fall to burning at the firſt daſh, without ſtaying for any more gentle remedies. As you your ſelf write in the firſt Book, leaf 5. ſpeaking of the conditions required in a Chirurgeon to cure well; which paſſages you borrow from ſome other place: for that which may be done gently without fire, is much more commended than otherwiſe. Is it not a thing which all Schools hold as a Maxim, that we muſt always begin with moſt eaſie remedies, which if they be not ſufficient, we muſt then come to extreme, following the doctrine of *Hippocrates*? *Galen* commands in the place before alledged, to treat or dreſs the diſeaſed quickly, ſafely, and with the leaſt pain that is poſſible.

Galen in Book 4. of the *Meth.* and in the Book of Art of *Hippocrates*, Aph. 2. Book 1. In the Book of *Arte Parva.*

Let us come to Reaſon.

NOw ſo it is, that one cannot apply hot irons but with extreme and vehement pain in a ſenſible part void of a Gangrene, which would be cauſe of a Convulſion, Fever, yea, oft-times of Death. Moreover it would be a long while afterwards before the poor Patient were cured, becauſe that by the action of the fire there is made an eſchar, which proceeds from the ſubject fleſh, which being fallen, Nature muſt regenerate a new fleſh in ſtead of that which hath been burned; as alſo the bone remains diſcovered and bare; and by this means, for the moſt part there remains

Of what the Eſchar is made.

mains an ulcer incurable. Moreover there is yet another accident. It happeneth that oftentimes the cruſt being fallen off, the fleſh not being well renewed, the bloud iſſueth out as it did before. But when they ſhall be tied, the ligature falls not off until the firſt fleſh have very well covered them again: which is proved by *Galen* in the fifth Book of his *Meth.* ſaying, that Eſcharotick Medicins which cauſe a Cruſt or Eſchar, whenſoever they fall off, leave the part more bare than the natural habit requires. For the generation of a cruſt proceeds from the parts ſubject, and which are ſituate round about it, being alſo burned, as I may ſay: wherefore by how much the part is burnt, by ſo much it loſeth the natural heat. Then tell me when it is neceſſary to uſe eſcharotick Medicins, or cautering irons? 'Tis when the flux of bloud is cauſed by eroſion, or ſome gangrene or putrefaction. Now is it thus? in freſh bleeding wounds there is neither gangrene, nor putrefaction. Therefore, the cauteries ought not to be there applied. And when the Ancients commanded to apply hot irons to the mouths of the veſſels, it hath not been onely to ſtay the flux of bloud, but chiefly to correct the malignity, or gangrenous putrefaction which might ſpoil the neighbouring parts. And it muſt be here noted, that if I had known ſuch accidents to happen, which you have declared in your Book, in drawing and tying the veſſels, I had never been twice deceived; nor would I ever have left by my writings to poſterity, ſuch a way of ſtopping a flux of bloud. But I writ it after I had ſeen it done, and did it very often with happy ſucceſs. See then what may happen through your inconſiderate counſel, without examining, or ſtanding upon the facility of tying the ſaid veſſels. For ſee, here is your ſcope and propoſition, to tie the veſſels after amputation is a new remedy, ſay you, then it muſt not be uſed; it is an ill argument for a Doctor.

Words of the Adverſary.

But as for that (ſay you) one muſt uſe fire after the amputation of members, to conſume and drie the putrefaction, which is a common thing in gangrenes and mortifications, that indeed hath no place here, becauſe the practice is to amputate the part above that which is mortified and corrupted; as *Celſus* writes and commands, to make the amputation upon the ſecond part, rather than to leave any whit of the corrupted. I would willingly ask you, if when a vein is cut tranſverſe, and that it is very much retracted towards the original, whether you would make no conſcience to burn till that you had found the orifice of the vein or artery; and if it be not more eaſie onely with a Crow-bill to pinch and draw the veſſel, and ſo tie it? In which you may openly ſhew your ignorance, and that you have your mind ſeized with much rancor and choler. We daily ſee the ligature of the veſſels practiſed with happy ſucceſs, after the amputation of a part, which I will now verifie by Experiences and Hiſtories, of thoſe to whom the ſaid ligature hath been made, and perſons yet living.

Propoſitions of the Adverſary.

In Book 5. ch. 26. and Book 7. ch. 33.

In the chap. of Cutting, Book 2.

Experiences. A notable Hiſtory.

The 16. of *June* 1582. in the preſence of Mr. *John Liebaud* Doctor in the Faculty of Phyſick at *Paris*, *Claud. Viard* ſworn Surgeon, Mr. *Mathurin Huron* Surgeon of Monſieur *de Souvray*, and my ſelf, *John Charbonel* Maſter Barber-Surgeon of *Paris*, well underſtanding the Theorick and Practick of Surgery, did with good dexterity amputate the left leg of a Woman tormented the ſpace of three years with extreme pain, by reaſon of a great *Caries* which was in the bone *Aſtragal*, *Ceboides*, great and little *focil*, and through all the nervous parts, through which ſhe felt extreme and intolerable pains night and day: ſhe is called *Mary* of *Hoſtel*, aged 28 years or thereabouts, wife of *Peter Herve* Eſquire of the Kitchin to the Lady *Ducheſs* of *Uzez*, dwelling in the ſtreet of *Verbois*, on the other ſide St. *Martin* in the Fields, dwelling at the ſign of the St. *Johns* head; where the ſaid *Charbonel* cut off the ſaid leg the bredth of four large fingers below the Knee, and after that he had inciſed the fleſh, and ſawed the bone, he griped the vein with a Crow-bill, then the artery, then tied them; from whence I proteſt to God (which the company that were there can witneſs) that in all the operation that was ſuddenly done, there was not ſpilt one Porrenger of bloud; and I bid the ſaid *Charbonel* to let it bleed more, following the precept of *Hippocrates*, that it is good in all wounds and inveterate ulcers, to let the bloud run; by this means the part is leſs ſubject to inflammation. The ſaid *Charbonel* continued the dreſſing of her, who was cured in two moneths, without any flux of bloud happening unto her, or other ill accident; and ſhe went to ſee you at your lodging being perfectly cured.

The operation of *Charbonel*.

In the 7. Cent. of the Book of Ulcers.

Another Hiſtory of late memory, of a Singing-man of our Ladies Church, named Mr. *Colt*, who broke both the bones of his leg which were cruſhed in divers pieces, inſomuch that there was no hope of cure, to withſtand a Gangrene and mortification, and by conſequence death. Monſieur *Helin* Doctor Regent in the Faculty of Phyſick, a man of honour and good knowledge, *Claud. Viard* and *Simon Peter*, ſworn Surgeons of *Paris*, men well exerciſed in Surgery; and *Balthazar* of *Leſtre*, and *Leonard de Leſchenal*, Maſter Barber-Surgeons, well experimented in the operations of Surgery, were all of opinion, to withſtand the accidents aforeſaid, to make entire amputation of the whole leg, a little above the broken and ſhivered bones and the torn nerves, veins, arteries; the operation was nimbly done by the ſaid *Viard*, and the bloud ſtanched by the ligature of the veſſels in the preſence of the ſaid *Helin*, and Mr. *Tonſard* great Vicar of our Ladies Church, and was continually dreſſed by the ſaid *Leſchenal*, and I went to ſee him otherwhiles: he was happily cured without the application of hot irons, and walketh luſtily with a wooden leg.

Another Hiſtory.

Operation done by *Viard*.

In the year 1583. the 10. day of *December*, *Touſſiant Poſſon* born at *Ronieville*, at this preſent dwelling at *Beauvais* near *Dourdan*, having his leg all ulcered, and all the bones cariez'd and rotten, prayed me for the honour of God to cut off his leg, by reaſon of the great pain, which he could no longer endure. After his body was prepared, I cauſed his leg to be cut off, four fingers below the *rotula* of his knee, by *Daniel Powlet* one of my ſervants, to teach him, and to embolden him in ſuch works; and there he readily tied the veſſels to ſtay the bleeding, without application of hot irons, in the preſence of *James Guillemau* ordinary Surgeon to the King, and *John Charbonel* Maſter Surgeon of *Paris*: and during the cure was viſited by Mr. *Laſſile* and Mr. *Courtin*, Doctors Regent in the Faculty of Medicin at *Paris*. The ſaid operation was made in the houſe of *John Gobel* Inn-keeper, dwelling at the ſign of the White Horſe in the Greve. I will not here forget to ſay, that

Another Hiſtory.

Another Hiſtory. the Lady Princeſs of *Montpenſier*, knowing that he was poor and in my hands, gave him money to pay for his Chamber and Diet, He was well cured, God be praiſed, and is returned home to his houſe with a woodden leg.

A Gangrene happening by an Anticedent cauſe. A Gangrene happened to half of the leg to one named *Nicolas Meſnager*, aged 76 years, dwelling in St. *Honores* ſtreet, at the ſign of the Basket, which happened to him through an inward cauſe, ſo that we were conſtrained to cut off his leg to ſave his life: and it was taken off by *Anthony Renaud*, Maſter Barber-Surgeon of *Paris*, the 16. day of *December* 1583. in the preſence of M. *Le Fort*, and M. *La Nave*, ſworn Surgeons of *Paris*; and the bloud was ſtanched by the Ligature of the Veſſels, and he is at this preſent cured and in health, walking with a woodden leg.

Another Hiſtory. A Water-man at the Port of *Neſle*, dwelling near Monſieur *de Mas*, Poſt-maſter, named *John Bouſſereau*, in whoſe hands a Musket brake aſunder, which broke the bones of his hand, and rent and tore the other parts in ſuch ſort, that it was needful and neceſſary to make amputation of the hand two fingers above the wriſt: which was done by *James Guilleman*, then Surgeon in ordinary to the King, who dwelt at that time with me. The operation likewiſe being readily done, and the bloud ſtanched by the ligature of the veſſels, without burning irons, he is at this preſent living.

Operation done by *Guilleman*.

Another Hiſtory. Operation done by the Author. A Merchant Grocer dwelling in St. *Denis* ſtreet at the ſign of the great *Tournois*, named *the Judge*, who fell upon his head, where was made a wound near the temporal muſcle, where he had an artery opened, from whence iſſued forth bloud with great impetuoſity, inſomuch that common remedies would not ſerve the turn; I was called thither, where I found Mr. *Ruſſe*, Mr. *Cointeret*, Mr *Viard*, ſworn Surgeons of *Paris*, to ſtay bloud; where preſently I took a needle and thred and tied the artery, and it bled no more after that, and was quickly cured. Mr. *Roſſellet* can witneſs it, not long ſince Deacon of your Faculty, who was in the cure with us.

Another Hiſtory. Another operation. A Serjeant of the Chaſtlet dwelling near St. *Andrew des Arts*, who had a ſtroke of a Sword upon the throat in the Clacks Meadow, which cut aſunder the jugular vein extern: as ſoon as he was hurt he put his handkerchief upon the wound, and came to look me at my houſe, and when he took away his handkerchief, the bloud leaped out with great impetuoſity: I ſuddenly tied the vein toward the root; he by this means was ſtanched and cured, thanks be to God. And if one had followed your manner of ſtanching bloud by cauteries, I leave it to be ſuppoſed whether he had been cured; I think he had been dead in the hands of the Operator. If I would recite all thoſe whoſe veſſels were tied to ſtay the bloud, which have been cured, I ſhould not have ended this long time; ſo that methinks there are Hiſtories enough recited to make you believe the bloud of veins and arteries is ſurely ſtanched without applying any outward cauteries.

Du Bartas.

He that doth ſtrive againſt Experience,
Deigns not to talk of any learned Science.

Book 6. c. 4. Book 2. c. 4. Book 3. c. 9. Sect. 7. NOw my little Maſter, ſeeing that you reproach me that I have not written all the operations of Surgery in my Works, which the Ancients write of, I ſhould be very ſorry for it: for then indeed might you juſtly call me *Carnifex*. I have left them becauſe they are too cruel, and am willing to follow the Moderns, who have moderated ſuch cruelty: which notwithſtanding you have followed ſtep by ſtep, as appeareth by the operations, here written, extracted from your Book, which you have drawn here and there from certain ancient Authors, ſuch as follow, and ſuch as you have never practiſed nor ſeen.

The Firſt Operation.

In the ſecond Book of the Chapter of *Hypoſpatiſm*, Book 4. ch. laſt of the Meth. In the 4. ch. of the 16. Book of my Work. Book 6. c. 7. Book 2. c. 5. TO inveterate fluxions of the Eyes, and Meagrims, *Paulus Ægineta* as alſo *Albucaſis* command to make *Arteriotomy*; ſee here the words of the ſame *Ægenete*. You mark the arteries which are behind the Ears, then divide them in cutting to the very bone, and make a great inciſion, the bredth of two fingers, even till the artery be found, as you command to be done in your Book; but I holding the opinion of *Galen*, who commands to dreſs the diſeaſe quickly, ſafely, and with the leaſt pain that is poſſible; I teach the young Surgeon the means to remedy ſuch evils in opening the arteries behind the ears, and thoſe of the temples, with one onely inciſion, as a letting bloud, and not to make a great inciſion, and cut out work for a long time.

The Second.

In the 2. Book chap. of *Periſcythiſm*. In the 26. ch. of the 9. Book of my Works. TO Fluxions which are made a long time upon the Eyes, *Paul Ægenete* and *Albucaſis* command to make inciſion, which they call *Periſcythiſmos* or *Augiology* of the Greeks; and ſee here the words of *Paul*: *In this Operation firſt the head is ſhaved, then taking heed of touching the temporal muſcles, a tranſverſe inciſion muſt be made, beginning at the left temple, and finiſhing at the right*; which you have put in your Book word for word, without changing any thing: which ſheweth openly you are a right Wound-maker, as may be ſeen in the Chapter which you call the Crown-cut, which is made half round under the Coronal ſuture from one temple to another, even to the bone. Now I do not teach ſuch a cruel kind of remedy, but inſtruct the Operator by Reaſon, Authority, and notable proof of a ſure and certain way to remedy ſuch affections without butchering men in this kind.

The third Operation.

The third. Book 6. ch. 44. Book 2. ch. 3. Book 3. ch. 22. IN the cure of *Empyema*, *Paul Ægenete*, *Albucaſis* and *Celſus* commanded to apply ſome thirteen, others fifteen Cauteries to give iſſue to the matter contained in the breſt, as the ſaid *Celſus* in the aforeſaid place appointeth for Aſthmatick people, which is a thing out of all reaſon (with reſpect to their honor be it ſpoken) that ſince the Surgeons ſcope is to give iſſue to the matter therein contained, there is no other queſtion then to make apertion, to evacuate the matter in the moſt inferiour part, I have ſhewed the young Surgeon the means to do it ſafely, without tormenting the Patients for nothing.

The

The Fourth Operation.

IN Paps that are too great, *Paul Æginet* and *Albucasis* commands to make a cross-incision, to take out all the fat, and then join together the wound by stitch: in brief, it is to flay a man alive, which I have never practised, nor counsel it to be done by the young Surgeon.

Guido of *Cauliac* the 2. Treatise, doct. 1. c. 1. Book 7. c. 10. book 6. c. 46. book 2. c. 47.

The Fifth Operation.

Albucasis and *Paul Æginet* will cauterize the Liver and the Splene with hot irons, which the Moderns have never practised; for indeed Reason is manifestly repugnant thereunto.

The Sixth Operation.

IN the *Paracentesis* which is made in the third kind of Dropsie called *Ascites*, *Celius Aurelianus* commandeth diverse apertions to be made in the belly. *Albucasis* applies nine actual Cauteries, that is to say, four about the Navel, one upon the Stomach, and one upon the Splene, one upon the Liver, two behind the Spondyls, one of them near the breast, the last near the Stomach. *Ætius* is likewise of the same opinion, to open the belly with diverse cauteries. *Paul Æginet* commands to apply five actual cauteries to make the said *Paracentesis*. But abhorring such a kind of burning, of which you speak much in your third Book. I shew another kind of practice, the which is done by making a simple incision in the said belly, as may be seen in my Works, with happy success, I do not teach young men in my Works the manner of burning, which the Ancients have called *infibulare*, that is not in practice, though *Celsus* writeth of it.

In the first Book ch. 29, and 30. also in b. 2. c. 32. b. 6. c. 47, and 48. In the 5. book ch. 1. *De internis morbis*, book 1. c. 33. book 3. sect. 2. chap. 89. book 6. chap. 50. In the 3. book 12. ch. 6, 7.

The Seventh Operation.

IN the Sciatick proceeding from an internal cause, and because the viscous humours displace the bones, *Paul* commands to burn or cauterize the said joint to the bone: *Dioscorides* commands the same, which I do not find expedient, taking indication from the subjacent parts: for there where one would burn, it is in the place of four twin-muscles, under which passeth the great nerve descending from the Holy-bone; which being burnt I leave it to your censure what might happen, as *Galen* remarketh speaking of the *ustion* which must be made in the shoulders, called *humerus*.

In the 7. book c. 25. book 6. c. 76. book 2. c. 72. upon the sentence 49. of the first section of the Book of Arts.

The Eighth Operation.

IN the outward luxation of the Spondyls, *Hippocrates* commands to bind the man right upon a Ladder, the arms and legs tied and bound: then afterwards having raised the Ladder to the top of a Tower, or the ridge of an house, with a great rope in a pully, then to let the Patient fall plumb down upon the hard pavement; which *Hippocrates* says was done in his time. But I do not shew of any such way of giving the Strapado to men; but I shew the Surgeon, in my Work, the way to reduce them surely, and without great pain. Moreover I should be sorry to follow the saying of the said *Hippocrates*, in the third Book *De Morbis*, who commands in the disease called *Volvulus*, to cause the belly to be blown with a pair of Bellows, putting the nosel of them into the *intestinum rectum*, and then blow there till the belly be much stretched, afterwards to give an emollient Clyster, and to stop the Fundament with a Sponge. Such practice as this is not made now adays, therefore wonder not if I have not spoken of it. And you not being contented to patch together the operations of the aboveSaid Authors, you have also taken divers in my Works, as every man may know: which sheweth manifestly that there is nothing of your own in your *Surgeons Guide*. I leave out divers other unprofitable operations which you quote in your Book, without knowing what Beasts they are, in never having seen them practised; but because you have found them written in the Books of the Ancients, you have put them into your Book.

Sentence the 22, and 23. of the third section of the Book of the Joints, c. 16. of the 15 Book.

Moreover you say that you will teach me my lesson in the operations of Surgery, which I think you cannot do: because I have not onely learned them in my study, and by the hearing of many years the lessons of Doctors of Physick: but as I have said before in my Epistle to the Reader, I was resident the space of three years in the Hospital of *Paris*, where I had the means to use and learn divers works of Surgery, upon divers Diseases, together with the Anatomy, upon a great number of dead bodies, as oftentimes I have sufficiently made trial publickly in the Physicians School at *Paris*, and my good luck hath made me seen much more. For being called to the service of the King of *France*, (four of which I have served) I have been in company at Battles, Skirmishes, Assaults and Besieging of Cities and Fortresses; as also I have been shut up in Cities with those that have been besieged, having charge to dress those that were hurt. Also I have dwelt many years in this great and famous City of *Paris*, where (thanks be to God) I have lived in very good reputation amongst all men, and have not been esteemed the least in rank of men of my Profession, seeing there was not any cure, were it never so difficult and great, where my hand and my counsel have not been required, as I make it appear in this my Work. Now dare you (these things being understood) say you will teach me to perform the works of Surgery, since you never went further than your study? The operations of the same are four in general (as we have declared heretofore) where you may make but three; that is to say, join that which is separated, separate that which was conjoined, and to take away that which was superfluous, and the fourth which I make, is as much necessary, an industrious invention to add to Nature that which is wanting, as I have shewed here above. Also it is your will that the Surgeon make but three operations above-said, without medling to ordain a simple Cataplasm, saying it is that which comes to your part belonging to the Physician. And that the Ancients (in the discourse which you have made to the Reader) have divided the practice of Physick into three kinds, that is to say, Diet, Medicin, and Chirurgery. But I would willingly demand of you, who hath made the partition, and where any thing should be done? who are those which are content with their part, without any enterprise upon the other? For *Hippocrates*, *Galen*, *Ætius*, *Avicen*, in brief, all the Physicians, as well Grecks and Latins as Arabians, have never so treated of the one, that they have not treated of the other, for the great affinity and tie that there is between them two; and it should be very difficult to do otherwise. Now when you will vilifie Chirurgery so much, you speak against your self; for in your Epistle you have dedicated to Monsieur *Martignes*, you say, that Chirurgery is the most noble part of Physick, as well by

reason

reason of the original antiquity, necessity, as certainty in her actions; for she works *Luce aperta*, as learnedly writeth *Celsus* in the beginning of the Seventh Book; therefore it is to be believed you never went out of your Study, but to teach *Theorick* (if you have been able to do it.)

A fair similitude.

The operations of Chirurgery are learnt by the eye, and by the touch. I will say that you much resemble a young Lad of *Low-Britany*, of plum buttocks, where was stuff sufficient, who demanded leave of his Father to come to *Paris*, to take *France*; being arrived, the Organist of our Ladies Church met with him at the Palace-gate, who took him to blow the Organs, where he was remaining three years: he saw he could somewhat speak *French*, he returns to his Father, and told him that he spake good *French*, and moreover he knew well to play on the Organs: his Father received him very joyfully, for that he was so wise and learned in a short time. He went to the Organist of their great Church, and prayed him to permit his Son to play on the Organs, to the end he might know whether his Son was become so skilful a Master as he said he was; which the Organist agreed to very willingly. Being entered to the Organs, he cast himself with a full leap to the Bellows; the Master Organist bid him play, and that he would blow: then this good Master answers, *Let him play himself on the Organs if he would for him, he could do nothing but play on the Bellows.* I think also, my little Master, that you know nothing else, but to prattle in a chair; but I will play upon the Keys and make the Organs sound: (that is to say) I will do the operations of Chirurgery, that which you cannot in any wise do, because you have not gone from your Study or the Schools, as I have said before. But also as I have said already in the Epistle to the Reader, that the Labourer doth little profit by talking of the Seasons, discourse of the manner of tilling the Earth, to shew what Seeds are proper to each soil; all which is nothing if he put not his hand to the Plough, and couple the Oxen together. So likewise it is no great matter if you do not know the *Practick*; for a man may execute Chirurgery well, although he have no tongue at all. As *Cornelius Celsus* hath very well remarked in his first Book, when he saith, *Morbos non eloquentia, sed remediis curari, quæ si quis elinguis, usu discretus bene norit, hunc aliquanto majorem medicum futurum quam si sine usu linguam suam excoluerit*; that is to say, Diseases are not to be cured by Eloquence, but by Remedies well and duly applied, which if any wise and discreet man though he have no tongue, know well the use thereof, this man in time shall become the greater Physician, than if without practice his tongue were dipt with Oratory, the which you your self confess in your said Book by a Tetrastich which is thus:

To talk's not all in Chirurgions Art,
But working with the hands;
Aptly to dress each grieved part,
And guide fire, knife, and bands.

Aristotle in the first Book of his Metaphysicks, the first Chapter, saith, Experience is almost like unto Science; and by the same, Art and Science have been invented. And indeed we see these which are experimented, attain sooner to that which they intend, than those which have Reason and not Experience, because that the said Experience is a knowledge of singular and particular things; and Science on the contrary, is a knowledge of things universal. Now that which is particular is more healable than that which is universal; therefore those which have Experience are more wise and more esteemed, than those which want it, by reason they know what they do. Moreover I say, that Science without Experience, bringeth no great assurance.

Alciat, a Doctor of *Milan*, boasted one day of himself, that his glory was greater and more famous than that of Counsellors, Presidents, Masters of Request, because that it was by his Science and his Instructions that they became such: but he was answered by a Counsellor, that he was like unto a Whet stone, which made the Knife sharp and ready to cut, not being able so to do it it self; and alledged the Verses of *Horace*, that,

Fungebatur vice cotis acutum
Reddere quæ ferrum valet, exors ipsa secandi.

See you now (my little Master) my answers to your calumniations, and pray you, if you bear a good mind (to the publick good) to review and correct your Book, as soon as you can, and not to hold young Chirurgeons in this errour by the reading of the same, where you teach them to use hot irons after the amputation of members, to stay a flux of bloud, seeing there is another means and not so cruel, and more sure and easie. Moreover if to day after an assault of a City, where divers Souldiers have had arms and legs broken and shot off by Cannon-bullets, Cutlas and other instruments of War, to stay the flux of bloud, if you should use hot irons, it would be needful to have a Forge, and much Coals to heat them: and also the Souldiers would hold you in such horrour for this cruelty, that they would kill you like a Calf, even as in times past they did one of the chiefest Chirurgeons of *Rome*, which may be found written before, in the third Chapter of the Introduction of Surgery, the first Book. Now lest the Sectators of your writings should fall into such inconveniency, I pray them to follow the method aforesaid, the which I have shewed to be true and certain, and approved by Authority, Reason, and Experience.

The Voyage of Thurin, 1535.

MOreover I will here shew to the Readers the places where I have had means to learn the Art of Surgery, for the better instructing of the young Surgeon: and first in the year 1536. the King of *France* sent a great Army to *Thurin*, to recover the City and Castles which the Marques of *Guast*, Lieutenant-General of the Emperour, had taken: where the High Constable of *France* the Great Master, was Lieutenant-General of the Army, and Monsieur *de Montain* Colonel-General of the Foot, of which I was then Surgeon. A great part of the Army arrived in the Country of *Suze*;

we

we found the Enemy which ſtopt the paſſage, and had made certain Forts, and Trenches, inſomuch that to hunt them out and make them leave the place, we were forced to fight, where there were divers hurt and ſlain, as well of the one ſide as of the other: but the enemies were conſtrained to retire, and get into the Caſtle, which was cauſed partly by one Captain *Ratt*, who climed with divers Souldiers of his company upon a little Mountain; there where he ſhot directly upon the enemies, he received a ſhot upon the ancle of his right foot, wherewith preſently he fell to the ground; and ſaid then, Now is the *Ratt* taken. I dreſſed him, and God healed him. We entered the throng iuto the City, and paſſed over the dead bodies, and ſome which were not yet dead; we heard them cry under our Horſes feet, which made my heart relent to hear them. And truly I repented to have forſaken *Paris* to ſee ſuch a pitiful ſpectacle. Being in the City, I entered into a Stable thinking to lodge my own, and my mans horſe, where I found four dead Souldiers and three which were leaning againſt the wall, their faces wholly diſfigured, and neither ſaw nor heard, nor ſpake; and their clothes did yet flame with Gun-powder which had burnt them. Beholding them with pitty, there happened to come an old Souldier who asked me if there were any poſſible means to cure them; I told him no: he preſently approached to them, and cut their throats without choler. Seeing this great cruelty I told him he was a wicked man; he anſwered me that he prayed to God, that whenſoever he ſhould be in ſuch a caſe, that he might find ſome one that would do as much to him, to the end he might not miſerably languiſh. And to return to our former diſcourſe, the enemy was ſummoned to render, which they ſoon did, and went out, their lives only ſaved, with a white ſtaff in their hands; the greateſt part whereof went and got to the Caſtle of *Villane*, where there was about 200 Spaniards; Monſieur the Conſtable would not leave them behind, to the end that the way might be made free. This Caſtle is ſeated upon a little mountain, which gave great aſſurance to them within, that one could not plant the Ordnance to beat upon it, and they were ſummoned to render, or that they ſhould be cut in pieces; which they flatly refuſed, making anſwer, *That they were as faithful ſervants to the Emperor, as Mounſieur the Conſtable could be to the King his Maſter.* This anſwer heard, they made by force of arms, two great Cannons to be mounted in the night with cords and ropes, by the Swiſſers and Lanſquenets; when as the ill luck would have it, the two Cannons being ſeated, a Gunner by great negligence ſet on fire a great bag of gun-powder, wherewith he was burned together with ten or twelve Souldiers; and moreover the flame of the powder was a cauſe of diſcovering the Artillery, which made them, that all night they of the Caſtle did nothing but ſhoot at that place where they diſcovered the two pieces of Ordnance, wherewith they killed and hurt a great number of our people.

The retiring of the enemy.

Hiſtory.

Brave anſwer of the Souldiers.

The next day early in the morning a Battery was made, which in a few hours made a breach, which being made, they demanded to parly with us; but twas too late for them for in the mean time our *French* foot ſeeing them amazed, mounted to the breach, and cut them all in pieces, except a fair young luſty Maid of *Piedmont*, which a great Lord would have kept and preſerved for him to keep him company in the night, for fear of the greedy Wolf. The Captain and Enſign were taken alive, but ſoon after were hanged upon the gate of the City, to the end they might give example and fear to the imperial Souldiers not to be ſo raſh and fooliſh, to be willing to hold ſuch places againſt ſo great an army. Now all the ſaid Souldiers of the Caſtle, ſeeing our people coming with a moſt violent fury, did all their endeavor to defend themſelves, they killed and hurt a great company of our Souldiers, with Pikes, Muskets, and Stones, where the Surgeons had good ſtore of work cut out. Now at that time I was a freſh-water Souldier, I had not yet ſeen wounds made by gun-ſhot at the firſt dreſſing. It is true, I had read in *John de Vigo*, in the Firſt Book of wounds in General the eight Chapter, that wounds made by weapons of fire did participate of Venenoſity, by reaſon of the Powder, and for their cure he commands to cauterize them with oyl of Elders ſcalding-hot, in which ſhould be mingled a little Treacle, and not to fail, before I would apply of the ſaid oyl knowing that ſuch a thing might bring to the patient great pain, I was willing to know firſt, before I applied it, how the other Surgeons did for the firſt dreſſing, which was to apply the ſaid oyl, the hotteſt that was poſſible, into the wouuds, with Tents and Setons; inſomuch that I took courage to do as they did. At laſt I wanted oyl, and was conſtrained in ſtead thereof, to apply a digeſtive of Yolks of Eggs, Oyl of Roſes, and Turpentine. In the night I could not ſleep in quiet, fearing ſome default in not cauterizing, that I ſhould find thoſe to whom I had not uſed the burning oyl, dead impoyſoned; which made me riſe very early to viſit them, where beyond my expectation, I found thoſe to whom I had applied my digeſtive medicin, to feel little pain, and their wounds without inflammation or tumor, having reſted reaſonable well that night: the other to whom was uſed the ſaid burning-oyl I found them feveriſh, with great pain and tumor about the edges of their wounds. And then I reſolved with my ſelf, never ſo cruelly to burn poor men wounded with gun-ſhot. Being at *Thurin*, I found a Surgeon, who had the fame above all others, for the curing of wounds of gun-ſhot, into whoſe favor I found means to inſinuate my ſelf, to have the Receit of his Balm, as he called it, wherewith he dreſſed wounds of that kind, and he held me off the ſpace of two years, before I could poſſible draw the Receit from him. In the end by gifts and preſents he gave it me, which was this, To boil young whelps new pupped, in oyl of Lillies, prepared Earth-worms, with Turpentine of *Venice*. Then was I joyful and my heart made glad, that I had underſtood his remedy, which was like to that which I had obtained by great chance. See then how I have learned to dreſs wounds made with gun-ſhot, not by Books. My Lord Marſhal of *Montain* remained Lieutenant-General for the King in *Piedmont*, having ten or twelve thouſand men in Garriſon through the Cities and Caſtles, who often combated with Swords and other weapons, as alſo with Muskets; and if there were four hurt, I had always three of them; and if there were queſtion of cutting off an arm or a leg, or to trepan, or to reduce a fracture or diſlocation, I brought it well to paſs. The ſaid Lord Marſhal ſent me one while this way, another while that way, for to dreſs the appointed Souldiers which were beaten as well in other Cities as that of *Thurin*, inſomuch that I was always in the Country

Exemplary puniſhment.

Counſel of *Vigo*.

Experience of a bold mans happy ſucceſs.

Receit of an excellent balm for wounds with Gun-ſhot.

Country one way or other. Mounſieur the Marſhal ſent for a Phyſician to *Milan*, who had no leſs reputation in the medicinal Art (then the diſeaſed Mounſieur *le Grand*) to take him in hand for an Hepatical flux, whereof at laſt he died. This Phyſician was a certain while at *Thurin* to deal with him, and was often called to viſit the hurt people, where he always found me, and I conſulted with him and ſome other Surgeons: and when we had reſolved to do any ſerious work of Surgery: 'twas *Ambroſe Parey* that put his hand thereto, where I did it promptly, and with dexterity, and with great aſſurance, in ſo much that the ſaid Phyſician admired me, to ſee me ſo ready in the operation of Surgery, ſeeing the ſmall age which I had. One day diſcourſing with the ſaid Lord Marſhal, he ſaid to him, *Signior tu, hai un Chirurgico giovane di anni, me egli veckio di ſapere e di eſperientia. Guarde lo bene, perche egli ti fara ſervicio & honore.* That is to ſay, Thou haſt a young Surgeon of age, but he is old in knowledge and experience; preſerve him well for he will do thee ſervice and honour. But the old man knew not that I had dwelt three years in the Hoſpital at *Paris*, there to dreſs the diſeaſed. In the end Mounſieur Marſhal died with his Hepatical Flux. Being dead, the King ſent Mounſieur the Marſhal of *Annebaut* to be in his place, who did me this honour to pray me to dwell with him, and he would uſe me as well or better than Mounſieur the Marſhal *Montain*; which I would not do for the grief I had for the loſs of my Maſter who loved me intimately, and I him in the like manner; and ſo I came back to *Paris*.

Witneſs of the dexterity of the Author.

The death of Marſhal *Montain*.

The Voyage of Marolle and of Low Britany, 1543.

The voyage of *Marolle* and of *Low Britany*, 1543.

I Went to the Camp of *Marolle*, with the diſeaſed Mounſieur *De Rohan*, where King *Francis* was in Priſon; and I was Surgeon of the Company of the ſaid Mounſieur *De Rohan*. Now the King was advertiſed by Mounſieur *De Eſtampes*, Governour of *Britany*, that the Engliſh had hoiſt ſail to land in *Low Britany*, and prayed him that he would ſend Mounſieur *De Rohan*, and Mounſieur *De Laval* for ſuccour, becauſe they were the Lords of that Countrey, and for their ſakes thoſe of that Countrey would beat back the Enemy and keep them from landing. Having received this advertiſement his Majeſty diſpatched to ſend the ſaid Lords for the relief of their Countrey, and to each was given as much power as to the Governour, in ſo much as they were all three the Kings Lieutenants: they took willingly this charge upon them, and ſpeedily they went away in Poſt: and led me with them to *Landreneau*, there where we found every one in arms, the Alarm-bells ſounding on every ſide, yea, five or ſix leagues about the *Harbours*, that is to ſay, *Breſt*, *Conquet*, *Crozon*, *Le Fou Dalac*, *Laudanac*, each of them well furniſhed with Artillery, as Cannons, Demi-cannons, Culverins, Sakers, Serpentines, Falcons, Harquebuſſes: in brief, there was nothing wanting in Artillery or Souldiers, as well *Britains* as *French*, to hinder that the Engliſh made no landing, as they had reſolved at their parting from *England*. The Enemies Army came unto the very mouth of the Cannon, and when we perceived them that they would land, they were ſaluted with Cannon-ſhot, and we diſcovered our Men of War, together with our Artillery; they fled to Sea again: where I was glad to ſee their Veſſels hoiſe ſail again, which was in a great number and in good order, and ſeemed like a Foreſt which marched upon the Sea. I ſaw a thing alſo whereat I marvelled much, which was, that the bullets of great pieces made great rebounds, and grazed upon the water as upon the ground. Now to make the matter ſhort, the Engliſh did us no harm, and returned whole and ſound into *England*, and left us in peace. We ſtaid in that Countrey in Garriſon, till we were aſſured that their Army was diſperſed. In the mean time our Horſemen exerciſed their feats of activity, as to run at the Ring, fight in Duel, and others; ſo that there was ſtill ſomething to imploy me withal. Mounſieur *De Eſtampes*, to make ſport and pleaſure to the ſaid Mounſieur *De Rohan* and *Laval*, and other Gentlemen, cauſed divers Countrey Wenches to come to the Feaſts, to ſing ſongs in *Low Britain* Tongue, where their harmony was like the croaking of Frogs, while they are in love. Moreover he made them dance the *Britany Triory*, without moving Feet or Buttocks; he made them hear and ſee much good. Otherwhiles they cauſed the Wraſtlers of the Cities and Towns, to come where there was a Prize for the beſt, and ſport was ſeldom ended, but that one or other had a leg or arm broken, or the ſhoulder or hip diſplaced: there was a little man of *Low Britany* of a ſquare body and well ſet, who held a long time the credit of the Field, and by his skill and ſtrength, threw five or ſix to the ground; there came to him a great Schoolmaſter, who was ſaid to be one of the beſt Wreſtlers of all *Britany*: he entered into the Liſts, having taken off his long Jacket, in Hoſe and Doublet, and being near the little man, he ſeemed as if he had been tied to his girdle. Notwithſtanding when each of them took hold of the Collar, they were a long time without doing any thing, and they thought they would remain equal in force and skill: but the little man caſt himſelf with an ambling leap under this great Pedant, and took him on his ſhoulder and caſt him on his kidnies ſpread abroad like a Frog, and then all the Company laught at the skill and ſtrength of the little Fellow. This great *Dativo* had a great ſpight, for being caſt by ſo little a man: he roſe again in choler, and would have his revenge. They took hold again of each others collar, and were again a good while at their hold without falling to the ground: in the end this great man let himſelf fall upon the little, and in falling, put his elbow upon the pitch of his ſtomach, and burſt his heart, and killed him ſtark dead. And knowing he had given him his deaths blow, took again his long Caſſock, and went away with his tail between his legs, and hid himſelf, ſeeing that the little man came not again to himſelf, either for Wine, Vinegar, or any other thing that was preſented unto him; I drew near to him, and felt his pulſe which did not beat at all, then I ſaid he was dead: then the *Britans* who aſſiſted the Wreſtling, ſaid aloud in their jabbering, *That is not in the ſport.* And ſome ſaid that the ſaid *Pedagogue* was accuſtomed to do ſo, and that but a year paſt he had done the like in a Wreſtling. I would needs open the body to know the cauſe of this ſudden death, where I found much bloud in the *Thorax*, and in the inferiour belly, and I ſtrived to find out any apertion in the place, from whence might iſſue ſo great a quantity of bloud, which I could not do for all the diligence I could make. Now I believe it was *per Diapedeſin*, or *Anaſtomoſin*, that is to ſay, by the apertion of the mouths of the veſſels, or by their poroſities: the poor little Wreſtler was buried. I took leave of *Meſſieurs de Rohan*,

Dances of the Countrey Wenches. Wreſtlers. Little *Britain* a good Wreſtler.

The little *Britain* killed.

The body opened by the Author.

Rohan, *de Laval*, and *Eſtamps*. Mounſieur *de Rohan* gave me a preſent of fifty double Duckets, and an ambling Horſe, and Mounſieur *de Laval* another for my Man, and Mounſieur *de Eſtamps*, a Diamond of thirty Crowns, and ſo I returned to my houſe at *Paris*.

The Voyage of Perpignan, 1543.

A Little while after Mounſieur *de Rohan* took me with him Poſt to the Camp of *Perpignan*; being there, the Enemy made a Sally forth, and came and incloſed three pieces of our Artillery, where they were beaten back to the Gates of the City: which was not done without hurting and killing many, and amongſt the reſt *de Briſſac*, (who was then chief Maſter of the Artillery) received a Musket ſhot upon the ſhoulders, returning to his Tent; all the others that were hurt followed him, hoping to be dreſt by the Surgeons that ought to dreſs them. Being come to his Tent and laid on his bed, the bullet was ſearched for by three or four the moſt expert Surgeons of the Army, who could not find it, but ſaid it was entered into his body.

In the end he called for me, to ſee if I were more skilful than they, becauſe he had known me before in *Piedmont*: by and by I made him riſe from his bed, and prayed him to put his body into that poſture as it was when he received his hurt; which he did, taking a Javelin between his hands as he held the Pike in the skirmiſh. I put my hand about the wound, and found the bullet in the fleſh, making a little tumor under the *Omoplate*: having found it, I ſhewed them the place where it was, and it was taken out by Maſter *Nicholas Lavernaut*, Surgeon to Mounſieur the *Dolphin*, who was the Kings Lieutenant in that Army, yet notwithſtanding the honour remained to me for finding it. Addreſs of the Author.

I ſaw one thing of great remark, which is this: That a Souldier in my preſence gave to one of his fellows a ſtroke with an Halbard upon the head, penetrating even to the left ventricle of the brain, without falling to the ground. He that ſtrook him ſaid, he had heard that he cheated at Dice, and that he had drawn a great ſum of money, and that it was his cuſtom to cheat. I was called to dreſs him, which I did as it were for the laſt, knowing well that he would quickly die: having dreſt him, he returned all alone to his Lodging, which was at leaſt two hundred paces diſtant: I bid one of his companions ſend for a Prieſt to diſpoſe of the affairs of his ſoul: he helped him to one who ſtaid with him to the laſt gaſp. The next day the Patient ſent for me by his She-friend in a Boys apparel to come to dreſs him, which I would not do, fearing he ſhould die under my hands; and to put it off, I ſaid I muſt not take off the dreſſing till the third day, by reaſon he would die though he were never touched. The third day he came ſtaggering, and found me in my Tent accompanied with the Wench, and prayed me moſt affectionately to dreſs him, and ſhewed me a Purſe wherein he had an hundred or ſix ſcore pieces of Gold, and that he would content me to my deſire; for all that, yet notwithſtanding I left not off to defer the taking off his dreſſing, fearing leſt he ſhould die at the ſame inſtant. Certain Gentlemen deſired me to go dreſs him, which I did at their requeſt, but in dreſſing him he died under my hands in a Convulſion. Now this Prieſt accompanied him until death, who ſeized upon the Purſe, leſt another ſhould take it, ſaying, he would ſay Maſſes for his ſoul. Moreover he furniſhed himſelf with his cloaths and with all the reſt of his things. I have recited this Hiſtory as a monſtrous thing that the Souldier fell not to ground when he had received this great ſtroke, and was in good ſenſes even till death. Soon after the Camp was broken for divers cauſes; the one becauſe we were advertiſed that four Companies of *Spaniards* were entered into *Perpignan*; the other, that the Plague begun much in our Camp, and it was told us by the People of the Country, that ſhortly there would be a great overflowing of the Sea, which might drown us all; and the preſage which they had, was a very great wind from Sea, which aroſe in ſuch manner that there remained not one Tent which was not broken and overthrown, for all the ſtrength and diligence could be given; and the Kitchins being all uncovered, the wind raiſed ſo the duſt and ſand, which ſalted and powdered our meat in ſuch ſort that we could not eat it, ſo that we were conſtrained to boil it in Pots and other veſſels well covered. An Hiſtory.

Now we did not uncamp our ſelves in ſo good time, but that there were many Carts and Carters, Mules and Mule-drivers drowned in the Sea, with great loſs of Baggage. The Camp broken, I returned to *Paris*.

The Voyage to Landreſy, 1544.

KIng *Francis* raiſed a great Army to victual *Landreſy*; on the other ſide, the Emperour had no leſs people, yea much more; that is to ſay, eight thouſand *Germans*, ten thouſand *Spaniards*, ſix thouſand *Walloons*, ten thouſand *Engliſh*, and about thirteen or fourteen thouſand Horſe. I ſaw the two Armies near one another, within Canon-ſhot, and it was thought they would never part without giving battel. There were ſome certain fooliſh Gentlemen who would approach the Enemies Camp; certain ſhot was made at them, and ſome died at the place, others had their legs or arms carried away. The King having done what he deſired, which was to victual *Landreſy*, retired himſelf with his Army to *Guiſe*, which was the day after *All-Saints*, One thouſand Five hundred Forty four, and from thence I returned to *Paris*.

The Voyage of Boulogn, 1545.

A Little while after we went to *Boulogn*, where the *Engliſh* ſeeing our Army, left the Forts which they had, that is to ſay, *Moulambert* the little Paradiſe, *Monplaiſir*, the Fort of *Shatillon*, the *Portet*, the Fort *Dardelot*. One day going through the Camp to dreſs my hurt people, the Enemies who were in the Tower of *Order*, ſhot off a piece of Ordnance, thinking to kill Horſemen which ſtaid to talk with one another. It happened that the bullet paſſed very near one of them, which threw him to the ground, and 'twas thought the ſaid bullet had toucht him, which it did not at all, but onely the wind of the ſaid bullet in the midſt of his coat, which went with ſuch a force that all the ontward part of the thigh became black and blue, and he had much ado to ſtand. I dreſt him, and made

made him divers ſcarifications to evacuate the contuſed bloud, which the wind of the ſaid bullet had made; and the rebounds that it made on the ground, killed four Souldiers which remained dead in the place. I was not far from this ſtroke, ſo that I felt ſomewhat the moved air, without doing me any more harm than a little fear which made me ſtoop my head very low, but the bullet was already paſſed far beyond me. The Souldiers mocked me to be affraid of a bullet already gone. (My little Maſter) I think if you had been there, that I had not been affraid alone, and that you would have had your ſhare of it. What ſhall I ſay more? Mounſieur the Duke of *Guiſe*, *Francis* of *Lorain*, was hurt before *Bullogne* with a ſtroke of a Lance, which above the right eye, declining towards the noſe, entered and paſſed quite through on the other between the *nucha* and the ear, with ſo great violence that the head of the Lance, with a great part of the wood was broken and remained within, in ſuch ſort that it could not be drawn out but with great force, yea with Smiths Pincers. Notwithſtanding all this violence which was not done without breaking of Bones, Nerves, and Arteries, and other parts; my ſaid Lord, by the help of God, was cured: the ſaid Lord went always with open face, which was the cauſe that the Lance went through on the other ſide.

The Voyage of Germany, 1552.

I Went the Voyage to *Germany* in the year 1552. with Mounſieur *de Rohan* Captain of fifty Horſes, where I was Surgeon of his Company, which I have ſaid already. In this Voyage Mounſieur the High Conſtable of *France* was General of the Army: Mounſieur *de Chaſtillon*, ſince Admiral, was chief Colonel of the Foot, having four Regiments of Lanſquenets, under the Conduct of theſe Captains, *Reerod* and *Ringrave*, having each of them two Regiments, each Regiment was of ten Enſigns, and each Enſign of five hundred men. And beſides theſe, was Captain *Chartel*, who conducted the Troops that the Proteſtant Princes had ſent to the King. This was a very great Company of Foot, accompanied with fifteen hundred Horſe, with the following of each one two Archers, which might make four thouſand and five huddred Horſe, beſides two thouſand Light-Horſe, and as many Muſketiers on Horſe-back, of whom *de Aumalle* was General, beſides the great number of Nobility who came for their pleaſure. Moreover the King was accompanied with two hundred Gentlemen of his houſe, and likewiſe with divers Princes; there was alſo for his Troop that ſerved him, the *French*, *Scottiſh*, and *Swiſſers* Guards, amounting to ſix hundred men on Foot, and the Companies of Mounſieur the *Dolphin*, *Meſſieres de Guiſe*, *de Aumalle*, and of the Marſhal of St. *Andrew*, which amounted to four hundred Lances, which was a marvellous thing to ſee ſuch a fair Company; and in this equipage the King entered into *Thou* and *Metz*. I will not omit to tell that it was ordained that the Companions of *Meſſieres de Rohan*, of the Count of *Sancerr*, of *Iarnac*, which was each of them of fifty Horſe, went by the Wings of the Camp; and God knows we had ſcarcity of Victuals; and I proteſt to God, that at three diverſe times I had thought I ſhould have been famiſhed, and it was not for want of money, for I had enough, and we could not have victuals but by force, by reaſon that the Peaſants withdrew it all into the Cities and Caſtles.

One of the Servants of a Captain of the Company of Mounſieur *de Rohan*, went with others thinking to enter into a Church where the Peaſants were retired, thinking to find Victuals by force or love: but amongſt the reſt this man was beaten, and returned with ſeven wounds with a Sword in the head, the leaſt of which penetrated the ſecond table of the ſcull; and he had four other upon the arms, and upon the right ſhoulder, which cut more than one half of the blade-bone, or *Omoplate*. He was brought back to his Maſters Lodging, who ſeeing of him ſo wounded, and they were to depart thence the morrow after at the break of day, and not thinking ever he could be cured, made him a Grave, and would have caſt him therein, ſaying, that or elſe the *Peaſants* would maſſacre and kill him; I moved with pity, told him that he might be cured if he were well dreſt: divers Gentlemen of the Company prayed him that he would cauſe him to be brought along with the Baggage, ſeeing I had the willingneſs to dreſs him; to which he agreed, and after that I had clothed him, he was put up in a Cart upon a Bed well covered and well accommodated, which one Horſe did draw. I did the office of a Phyſician, Apothecary, Surgeon, and Cook; I dreſt him even to the end of his cure, and God cured him, in ſo much that all theſe three Companies admired at this cure. The Horſe-men of the Company of Mounſieur *de Rohan*, the firſt Muſter that was made, gave me each one, one Crown, and the Archers half a Crown.

The Voyage of Danvilliers, 1552.

AT the return from the *German* Camp, King *Henry* beſieged *Danvilliers*; thoſe within would not render. They were well beaten, and our powder failed us; in the mean time they ſhot much at our people. There was a Culverin-ſhot paſſed a traverſe the Tent of Mounſieur *de Rohan*, which hit a Gentlemans leg, which was of his train; which I was fain to finiſh the cutting off, the which was done without applying hot irons.

Another Hiſtory.

The King ſent for Powder to *Sedan*, which being come, they began a greater battery than before, in ſuch ſort that they made a breach. *Meſſiers de Guiſe* and the High Conſtable being in the Kings Chamber, told him that they concluded the next day to make aſſault, and that they were aſſured they ſhould enter into it, and that they ſhould keep it ſecret, leſt the enemy were advertiſed. And all of them promiſed not to ſpeak of it to any one. Now there was a Groom of the Kings Chamber who lay under the Kings bed in the Camp to ſleep, underſtood that they reſolved the next day to give an aſſault; he preſently revealed it to a certain Captain, and told him that for certain, the day following aſſault ſhould be given, and that he had heard it of the King, and prayed the ſaid Captain that he would not ſpeak a word of it to any body, which he promiſed; but his promiſe was not kept; ſo at the ſame inſtant he went and declared it unto a Captain, and this Captain to another Captain, and from the Captains to ſome of the Souldiers, ſaying always, *ſay nothing*. It was ſo well hid that the next day early in the morning, there was ſeen the greateſt part of the Souldiers with their round

hoſe

hoſe and their breeches cut at the knee for the better mounting of the breach. The King was advertiſed of the rumor which run through the Camp, that the aſſault muſt be given, whereof he much marvelled, ſeeing there were but three of that advice, which had promiſed one to another not to tell it to any one. The King ſent for Monſieur *de Guiſe*, to know if he had not talked of this aſſault; he ſwore and affirmed to him he had not told it to any body, and Monſieur the Conſtable ſaid as much; who ſaid to the King, he muſt expreſly know who had declared this ſecret Counſel, ſeeing they were but three. Inquiſition was made from Captain to Captain, in the end the truth was found; for one ſaid it was ſuch an one told me, another ſaid as much, till at length they came to the firſt, who declared he had learned it of a Groom of the Kings Chamber, named *Guyard*, born at *Blois*, the ſon of the deceaſed King *Francis* his Barber. The King ſent for him into his Tent, in the preſence of Monſieur *de Guiſe*, and of Monſieur the Conſtable, to underſtand from him whence he had it, and who told him that this aſſault was to be given. The King told him, that if he did not tell the truth, that he would cauſe him to be hanged; and then he declared, he lay down under his bed thinking to ſleep, and ſo having heard it, he declared it to a Captain who was a friend of his, to the end he might prepare himſelf with his ſouldiers the firſt for the aſſault. After the King knew the truth, he told him he ſhould never ſerve him again, and that he deſerved to be hanged, and forbad him ever to come again to the Court. My Groom of the Chamber went away with this ſad news, and lay with one of the Kings Surgeons in Ordinary, named Maſter *Lewis*, and in the night gave himſelf ſix wounds with a knife, and cut his throat; yet the ſaid Surgeon perceived nothing till morning, till he ſaw the bed bloudy, and the dead body by him, he much marvelled at this ſpectacle upon his waking, and was afraid leſt they ſhould ſay, he was the cauſe of this murther; but was ſoon freed, knowing the cauſe to be from deſperation, having loſt the good amity which the King bore to him. The ſaid *Guyard* was buried. And thoſe of *Danvilliers* when they ſaw the breach large enough for them to enter in, and the Souldiers prepared for the aſſault, yielded themſelves to the mercy of the King. The chief of them were priſoners, and the Souldiers ſent away without arms. The Camp being broken up, I returned to *Paris* with my Gentleman whoſe leg I had cut off. I dreſſed him, and God cured him; I ſent him to his houſe merry with his wooden leg, and was content, ſaying that he had eſcaped good cheap, not to have been miſerably burnt, as you write in your book, my little Maſter.

What it is to reveal the ſecrets of Princes.

The Voyage of the Caſtle of Compt. 1552.

A Little while after, King *Henry* levied an Army of thirty thouſand men, to go make ſpoil about *Hedin*. The King of *Navarre* who was then called Monſieur *de Vendoſme*, was chief of the Army, and the Kings Lieutenant. Being at S. *Dennis* in *France*, ſtaying while the Companies paſſed by, he ſent for me to *Paris* to come ſpeak with him; being there, he prayed me, and his requeſt was a command, that I would follow him this Voyage; and I about to make my excuſe, told him my wife was ſick in her bed; he made me anſwer, That there were Phyſicians at *Paris* to cure her; and that he as well left his own, who was as well deſcended as mine; promiſing me that he would uſe me well, and forthwith gave command that I ſhould be lodged as one of his Train. Seeing this great affection, which he had to lead me with him, I durſt not refuſe him. I went and met with him at the Caſtle of *Compt*, within three or four leagues of *Hedin*, there where there was the Emperors Souldiers in garriſon with a number of Peaſants round about; he cauſed them to be ſummoned to render themſelves; and they made anſwer they ſhould never have them but by pieces, and let them do their worſt, and they would do their beſt to defend themſelves. They put confidence in their ditches full of water, and in two hours with a great number of Bavins, and certain empty Casks, way was made to paſs over the Foot, when they muſt go the aſſault, and were beaten with five pieces of Cannon, till a breach was made large enough to enter in, where they within received the aſſault very valiantly, and not without killing and hurting a great number of our people with muſket-ſhot, pikes, and ſtones. In the end when they ſaw themſelves conſtrained, they put fire to their powder and munition, which was the cauſe of burning many of our people, and theirs likewiſe, and they were all almoſt put to the ſword. Notwithſtanding ſome of our Souldiers had taken twenty or thirty, hoping to have ranſom for them. That was known, and ordered by the Council, that it ſhould be proclaimed by the Trumpet through the Camp, that all Souldiers who had any *Spaniards* priſoners, were to kill them, upon pain to be hanged and ſtrangled, which was done upon cold bloud. From thence we went and burnt divers Villages whoſe barns were full of all kind of Grain, to my grief. We went along even to *Tournahan*, where there was a very great Tower where the Enemies retired, but there was no man found in it, all was pillaged, and the Tower was made to leap by a Mine, and then with Gunpowder turned topſie-turvy. After that, the Camp was broken up, and I returned to *Paris*. I will not yet forget to write that the day after the Caſtle of *Compt* was taken, Monſieur *de Vendoſme* ſent a Gentleman to the King to make report to him of all which had had paſſed, and amongſt other things, told the King that I had greatly done my duty in dreſſing thoſe that were wounded, and that I had ſhewed him eighteen bullets which I had taken or drawn out of the hurt bodies, and that there were divers more which I could neither find, nor draw out, and told more good of me than there was by half. Then the King ſaid he would have me into his ſervice, and commanded Monſieur *de Gognier* his chief Phyſician to write me down as entertained one of his Surgeons in ordinary, and that I ſhould go meet with him at *Rheimes* within ten or twelve days, which I did, where he did me the honour to command me that I would dwell near him, and that he would do me good. Then I thankt him moſt humbly for the honour it pleaſed him to do me, in calling me to his ſervice.

The King of *Navarre* prayed the Author to follow him.

Hiſtory of deſperate people.

The taking of the Caſtle of *Compt*.

The Voyage of Mets. 1552.

THE Emperor having beſieged *Mets*, and in the hardeſt time of winter, as each one knows of freſh memory; and that there was in the City five or ſix thouſand men, and amongſt the

The names of the Princes who were at the ſiege of *Mets*.

reſt ſeven Princes; that is to ſay, Monſieur the Duke of *Guiſe* the Kings Lieutenant, *Meſſieurs d' Anguien*, *de Conde*, *de Montpenſier*, *de La Roch* upon *Yon*, Monſieur *de Nemours*, and divers others Gentlemen, with a number of old Captains of War, who often made ſallies forth upon the enemies, (as we ſhall ſpeak hereafter) which was not without ſlaying many, as well on the one ſide as the other. For the moſt part all our wounded people died, and it was thought the medicaments wherewith they were dreſſed were poiſoned; which cauſed Monſieur *de Guiſe* and other Princes to ſend to the King for me, and that he would ſend me, with Drugs to them, for they believed theirs were poiſoned, ſeeing that of their hurt people few eſcaped. I do not believe there was any poyſon, but the great ſtrokes of the Cutlaſſes, musket-ſhot, and the extremity of cold was the cauſe. The King cauſed one to write to Monſieur the Marſhal of S. *Andrew*, who was his Lieutenant at *Verdun*, that he found

Nota.

ſome means to make me enter into *Mets*. The ſaid Lord Marſhal of S. *Andrew*, and Monſieur the Marſhal of old *Ville*, got an *Italian* Captain, who promiſed them to make me enter in, which he did, and for which he had fifteen hundred Crowns: the King having heard of the promiſe which the *Italian* Captain had made, ſent for me, and commanded me to take of his Apothecary named *Daigue*, ſuch and as many Drugs as I ſhould think fit for the hurt who were beſieged, which I did, as much as a poſt horſe could carry. The King gave me charge to ſpeak to Monſieur *de Guiſe*, and to the Princes,

Commiſſion of the Author.

and Captains who were at *Mets*. Being arrived at *Verdun*, a few days after the Monſieur the Marſhal of S. *Andrew*, cauſed horſes to be given to me, and my man, and for the *Italian*, who ſpake very good high *Dutch*, *Spaniſh* and *Walloon*, with his own natural tongue. When we were within eight or ten Leagues of *Mets*, we went not but in the night, and being near the Camp, I ſaw a league and half off bright fires about the City, which ſeemed as if all the earth had been on fire, and I thought we could never paſs through thoſe fires without being diſcovered, and by conſequent be hanged and ſtrangled, or cut in pieces, or pay a great ranſom. To ſpeak truth, I wiſhed my ſelf at *Paris*, for the imminent danger which I foreſaw. God guided ſo well our affairs that we entred the City at midnight with a certain Token, which the Captain had with another Captain of the Company of Monſieur *de Guiſe*: which Lord I went to, and found him in bed, who received me with great thanks, being joyful of my coming. I did my meſſage to him of all that the King had commanded me to ſay to him: I told him I had a little letter to give to him, and that the next day I would not fail to deliver it him. That done, he commanded me a good lodging, and that I ſhould be well uſed, and bid me I ſhould not fail to be the next day upon the Breach, where I ſhould meet with all the Princes, and divers Captains; which I did; who received me with great joy, who did me the honour to embrace me, and tell me I was very welcome, adding withall they did not fear to die if they ſhould chance to be hurt. Monſieur *de la Roch* upon *Yon* was the firſt that feaſted me, and inquired of me what they ſaid at the Court concerning the City of *Mets*: I told him what I thought good. Then preſently he deſired me to go ſee one of his Gentlemen, named Moriſieur *de Magnane*, at this preſent Knight of the Kings Order, and Lieutenant of his Majeſties Guard, who had his leg broken by a Cannon-ſhot. I found him in his bed, his leg bended and crooked, without any dreſſing upon it; becauſe a Gentleman promiſed him

Hiſtory.

cure, having his name and his girdle, with certain words. The poor Gentleman wept and cried with pain which he felt, not ſleeping night nor day, in four days: then I mockt at this impoſture and falſe promiſe. Preſently I did ſo nimbly reſtore and dreſs his leg, that he was without pain, ſlept all night, and ſince (thanks be to God) was cured, and is yet at this preſent living, doing ſervice to the King. The ſaid Lord of the *Roch* upon *Yon* ſen me a tun of wine to my lodging, and bid tell me, when it was drunken, he would ſend me another. That done, Monſieur *de Guiſe* gave me a liſt of certain Captains and Lords, and commanded me to tell them what the King had given me in charge; which I did, which was to do his commendations and thankſgiving for the duty they had done and did in the keeping of the City of *Mets*, and that he would acknowledge it. I was more than eight days in acquitting my charge, becauſe they were many; firſt to the Princes and others, as the Duke of *Horace*, the Count of *Martiges*, and his brother Monſieur *de Bauge*, the Lords *Montmorancy* and *d' Anville*, the Marſhal of *France* Monſieur *de la Chapel*, *Bonnivet Carong* now Governour of *Rohan*, the *Vadaſme* of *Chartres*, the Cont of *Lude*, Monſieur *de Biron* now Marſhal of *France*, Monſieur *de Rondan* the *Rochfoucaut*, *Boxdalle d' Etrez* the younger, Monſieur *de S. John* in *Dolphiny*, and many others which it would be too long to recite; and chiefly to divers Captains who had very well done their duty in defence of their lives and City. I demanded afterwards of Monſieur *de Guiſe*, what pleaſed him I ſhould do with the Drugs which I had brought him; he bid me impart them to the Surgeons and Apothecaries, and chiefly to the poor hurt Souldiers in the Hoſpital which were in great number; which I did and can aſſure you, I could not do ſo much as go and ſee them, but they ſent for me to viſit and dreſs them. All the beſieged Lords prayed me carefully to ſolicite above all others Monſieur

The hurt of Monſieur *de Pienne* trepand and cured.

de Pienne who was hurt at the breach by a ſtone raiſed by a Cannon ſhot in the Temple with a fracture and depreſſion of the bone. They told me that preſently when he received the ſtroke, he fell to the earth as dead, and caſt blood out of his mouth, noſe and ears, with great vomitings, and was fourteen days without ſpeaking one word, or having any reaſon; there happened to him alſo ſtartings ſomewhat like Convulſions, and he had all his face ſwelled and livid. He was trepand on the ſide of the temporal muſcle upon the *Os Coronale*. I dreſt him with other Surgeons, and God cured him; and he is at this day living, God be thanked. The Emperor cauſed battery to be made with forty double Cannons, where they ſpared no powder night nor day. Preſently when Monſieur *de Guiſe* ſaw the Artillery ſeated to make a breach, he made the neareſt houſes be pulled down to make Ramparts, and the poſts and beams were ranged end to end, and between two clods of earth, beds and packs of wool, and then other poſts and beams were put again upon them as before. Now much wood of the houſes of the Suburbs, which had been put to the ground for fear leſt the enemy ſhould be lodged, cloſe covered, and that they ſhould not help themſelves with any wood, ſerved well to repair

Princes carried the Baskets.

the breach. Every one was buſied to carry earth to make the Ramparts night and day. *Meſſieres*, the Princes, Lords and Captains, Lieutenants, Enſigns, did all carry the Basket, to give example to

the

the Souldiers and Citizens to do the like, which they did: yea, both Ladies and Gentlewomen, and thoſe which had not Baskets, helped themſelves with Kettles, Panniers, Sacks, Sheets, and with what elſe they could to carry Earth; in ſo much that the Enemy had no ſooner beaten down the Wall, but he found behind it a Rampart more ſtrong. The Wall being fallen, our Souldiers cried to thoſe without, the Fox, the Fox, the Fox, and ſpake a thouſand injuries one to another. Monſieur *de Guiſe* commanded upon pain of death that no man ſhould ſpeak to them without for fear leſt there ſhould be ſome Traitor who would give them intelligence what was done in the City; the command made, they tied living Cats at the end of their Pikes, and put them upon the Wall, and cried with the Cats, *Miau, Miau.*

Truly the Imperialiſts were very much vexed to have been ſo long making a Breach, and at ſo great expence, which was the breach of fourſcore ſteps, to enter fifty men in front, where they found a Rampart more ſtrong than the Wall; they fell upon the poor Cats and ſhot at them with their Muskets, as they uſe to do at Birds. Our people did oftentimes make ſallies by the command of Mounſieur *de Guiſe*. The day before there was a great preſs to make themſelves enrolled, who muſt make the ſalley, chiefly of the young Nobility, led by well experimented Captains. In ſo much that it was a great favour to permit them to ſally forth and run upon the Enemy: and they ſallied forth always the number of one hundred or ſixſcore armed men with Cutlaſſes, Muskets, Piſtols, Pikes, Partiſans, and Halberts, which went even to their Trenches to awaken them. Where they preſently made an Alarm throughout all their Camp, and their Drums ſounded *plan, plan, ta, ti, ta, ta, ti, ta, ta, tou, touf, touf:* likewiſe their Trumpets and Cornets ſounded, *to the ſaddle, to the ſaddle, to the ſaddle, to horſe, to horſe, to horſe, to the ſaddle, to horſe.* And all their Souldiers cried, *Arm, arm, arm, to arms, to arms, to arms, arm, to arms, arm, to arms, arm, to arms,* like the cry after Wolves, and all divers Tongues, according to their Nations: and they were ſeen to go out from their Tents and little Lodgings, as thick as little Bees, when their Hive is diſcovered, to ſuccour their fellows who had their throats cut like Sheep, The Horſe-men likewiſe came from all parts a great gallop, *Patati, patata, patati, patata, ta, ta, patata, patata,* and tarried well, that they might not be in the throng, where ſtroaks were imparted to give and receive. And when our men ſaw they were forced, they returned into the City, ſtill firing, and thoſe who run after were beaten back with the Artillery which they had charged with Flint-ſtones, and four-ſquare pieces of Iron; and our Souldiers who were upon the ſaid Wall made a volly of ſhot, and ſhoured down their bullets upon them like hail, to ſend them back to their lodging, where divers remained in the place of the combat, and alſo our men did not all come off with whole skins, and there ſtill remained ſome for the Tithe, who were joyful to die in the Bed of Honour. And when there was a Horſe hurt, he was flayed, and eaten by the Souldiers in ſtead of Beef and Bacon, and it was fit I muſt run to dreſs our hurt men. A few days after other Sallies were made, which did much anger the Enemies, becauſe they did not let them ſleep but little in ſafety. Mounſieur *de Guiſe* made a War-like ſtratagem, which was, He ſent a Peſant who was none of the wiſeſt with two pair of Letters toward the King, to whom he gave ten crowns, and promiſed the King ſhould give him an hundred, provided he gave him the Letters. In the one he ſent word that the Enemy made no ſign of retiring himſelf, and by all force made a great breach, which he hoped to defend, yea to the loſing of his life, and of all thoſe that were within; and that the Enemy had ſo well placed his Artillery in a certain place which he named, that with great difficulty it was kept that they had not entered into it, ſeeing it was a place the moſt weak of all the City: but he hoped quickly to fill it up again in ſuch ſort, that they cannot be able to enter. One of theſe Letters was ſewed in the lining of his doublet, and he was bid to take heed that he told it not to any man. And there was alſo another given to him, wherein the ſaid Mounſieur *de Guiſe* ſent word to the King, that he and all the beſieged did hope well to keep the City, and other matters which I ceaſe to ſpeak of. They made the Peſant go forth in the night, and preſently after he was taken by one that ſtood Sentinel, and carried to the Duke of *Albe* to underſtand what was done in the City, and they asked him if he had any Letters, he ſaid yes, and gave them one; and having ſeen it, he was put to his Oath whether he had any other, and he ſwore, not; then they felt and ſearched him, and found that which was ſewed to his doublet, and the poor meſſenger was hanged.

The ſaid Letters were communicated to the Emperour, who cauſed his Council to be called there. Where it was reſolved, ſince they could do nothing at the firſt breach, that preſently the Artillery ſhould be drawn to the place which they thought the moſt weak, where they made great attempts to make another breach, and digged and undermined the Wall, and endeavoured to take the Tower of Hell, yet they durſt not come to the aſſault. The Duke of *Albe* declared to the Emperour that the Souldiers died daily, yet more than the number of two hundred, and that there was but little hope to enter into the City, ſeeing the Seaſon, and the great quantity of Souldiers that were there. The Emperour demanded what people they were that died, and if that they were Gentlemen of remark or quality; anſwer was made, that they were all poor Souldiers; then ſaid he it makes no matter if they die, comparing them to Caterpillars and Graſhoppers, which eat the buds of the Earth. And if they were of any faſhion, they would not be in the Camp for twelve ſhillings the Moneth; and therefore no great harm if they died. Moreover he ſaid, He would never part from before that City, till he had taken it by Force or Famine, although he ſhould loſe all his Army; by reaſon of the great number of Princes which were therein, with the moſt part of the Nobility of *France*. From whom he hoped to draw double his expence, and that he would go once again to *Paris*, to viſit the Pariſians, and make himſelf King of all the Kingdom of *France*. Mounſieur *de Guiſe*, with the Princes, Captains, and Souldiers, and generally all the Citizens of the City, having underſtood the intention of the Emperour, which was to extirpate us all, they adviſed of all they had to do: And ſince it was not permitted to the Souldiers nor Citizens, no nor to the Princes, nor Lords themſelves to eat either freſh Fiſh, or Veniſon, as likewiſe ſome Partridges.

Woodcocks, Larks, Plovers, for fear left they had gathered ſome peſtilential air which might give us any contagion; but that they ſhould content themſelves with the Ammunition Fare; that is to ſay, with Bisket, Beef, powdered Cows Lard, and Gammons of Bacon: Likewiſe Fiſh, as Green-fiſh, Salmon, Sturgeon, Anchovies, Pilchers, and Herrings; alſo Peaſe, Beans, Rice, Garlick, Onions, Prunes, Cheeſe, Butter, Oil, Salt, Pepper, Ginger, Nutmegs, and other Spiceries, to put into Pies, chiefly to Horſe-fleſh, which without that would have a very ill taſte; divers Citizens having Gardens in the City, ſowed therein great Radiſhes, Turnips, Carrets, and Leeks, which they kept well and full dear againſt the extremity of hunger. Now all theſe Ammunition Victuals were diſtributed by weight, meaſure, and juſtice, according to the quality of the perſon, becauſe we knew not how long the Siege would laſt. For having underſtood from the mouth of the Emperour, that he would never part from before *Mets* till he had taken it by Force or Famine; the victuals were leſſened, for that which was wont to be diſtributed to three, was now ſhared amongſt four, and defence made they ſhould not ſell what remained after their dinner, but 'twas permitted to give it to the Wenches that followed the Camp, and roſe always from Table with an appetite, for fear they ſhould be ſubject to take Phyſick. And before we would yield our ſelves to the mercy of our Enemies, had reſolved to eat our Aſſes, Mules, Horſes, Dogs, Cats, and Rats; yea, our Boots, and other Skins which we could ſoften and frie. All the beſieged did generally reſolve to defend themſelves with all ſorts of Inſtruments of War; that is to ſay, To rank and charge the Artillery, at the entry of the breach, with Bullets, Stones, Cart-nails, Bars and Chains of iron. Alſo all kinds and differences of artificial Fire, as Boerres, Bariquadoes, Granadoes, Ports, Lances, Torches, Squibs, burning-Faggots. Moreover, Scalding Water, melted Lead, Powder of unquencht Lime to blind their eyes. Alſo they were reſolved to have made holes through and through their houſes, there to lodge Muſquetiers, there to batter in the flank and haſten them to go, or elſe make them lie for altogether. Alſo there was order given to the Women to unpave the ſtreets, and to caſt out at their Windows, Billets, Tables, Treſſes, Forms, and Stools, which would have troubled their brains: Moreover, there was a little further a ſtrong Court of Guard, filled with Carts and Palliſadoes, Pipes and Hogſheads filled with earth for Barricadoes to ſerve to interlay with Faulcons, Faulconets, Field-pieces, Harquebuſſes, Muskets, and Piſtols, and Wild-fire, which would have broken legs and thighs, in ſo much that they had been beaten in head, in flank, and in tail; and when they had forced this Court of Guard, there was others at the croſſing of the ſtreets, each diſtant an hundred ſpaces, who had been as bad companions as the firſt, and would not have been without making a great many Widows and Orphans. And if Fortune would have been ſo much againſt us, as to have broken our Courts of Guard, there was ſeven great Baſtallions ordered in ſquare and triangle to combat altogether, each one accompanied with a Prince to give them boldneſs, and encourage them to fight, even till the laſt gaſp, and to die all together. Moreover it was reſolved, that each one ſhould carry his Treaſure, Rings, and Jewels, and their Houſhold-ſtuff of the beſt, to burn them in the great place, and to put them into aſhes rather then the Enemy ſhould prevail and make Trophies of their ſpoils; likewiſe there was people appointed to put fire to the Munition, and to beat out the heads of the Wine Casks, others to put the fire in each houſe, to burn our Enemies and us together: the Citizens had accorded it thus, rather then to ſee the bloudy Knife upon their Throat, and their Wives and Daughters violated, and to be taken by force by the cruel inhumane *Spaniards*. Now we had certain Priſoners which Mounſieur *de Guiſe* ſent away upon their Faith, to whom was ſecretly imparted our laſt reſolution, will and deſperate minds; who being arrived in their Camp, do not defer the publiſhing, which bridled the great impetuoſity and will of the Souldiers to enter any more into the City to cut our Throats, and to enrich themſelves of our pillages. The Emperour having underſtood this deliberation of the great Warriour the Duke of *Guiſe*, put Water in his Wine, and reſtrained his great choler and fury; ſaying, He could not enter into the City without making a great ſlaughter and butchery, and ſpill much bloud, as well of the Defendants as of the Aſſailants, and that they ſhould be dead together, and in the end could have nothing elſe but a few aſhes, and that afterward it might be ſpoken of that, as of the deſtruction of *Jeruſalem* already made by *Titus* and *Veſpaſian*. The Emperour then having underſtood our laſt reſolution, and ſeeing their little prevailing by their battery and undermining, and the great Plague which was in his whole Army, and the indiſpoſition of the Time, and the want of Victuals and Money, and that his Souldiers forſook him, and went away in great companies; concluded in the end to retire themſelves, accompanied with the Cavalry of the Van-guard, with the greateſt part of his Artillery, and the Battalia. The Marqueſs of *Brandenburg* was the laſt which decamped, maintained by certain Bands of *Spaniards*, *Bohemians*, and his *German* Companies, and there remained one day and a half after, to the great grief of Mounſieur *de Guiſe*, who cauſed four pieces of Artillery to be brought out of the City, which he cauſed to be diſcharged at him on one ſide, and the other to haſten them to be gone, which he did full quickly, with all his Troops. He being a quarter of a league from *Mets*, was taken with a fear left our Cavalry ſhould fall upon him in the Rere, which cauſed him to put fire to his Munition Powder, and leave certain pieces of Artillery, and much Baggage, which he could not carry, becauſe the Van-guard, and the Battalia, and great Cannons, had too much broken the way. Our Horſe-men would by all means have gone out of the City to have fallen upon their breech, but Mounſieur *de Guiſe* would never permit them, but on the contrary we ſhould rather make plain their way, and make them Bridges of Gold and Silver, and let them go, being like to a good Shepherd, who will not loſe one of his Sheep. See now how our well-beloved Imperialiſts went away from before the City of *Mets*, which was the day after *Chriſtmas* day, to the great contentment of the beſieged, and honour of Princes, Captains, and Souldiers, who had endured the travels of this Siege the ſpace of two moneths. Notwithſtanding they did not all go; there wanted twenty thouſand who were dead, as well by Artillery, as by the Sword, as alſo by the Plague, Cold, and Hunger.

hunger, and for ſpite they could not enter into the City to cut our throats, and have the pillage: and alſo a great number of their Horſes died, of which they had eaten a great part in ſtead of Beef and Bacon. They went where they had been encamped, where they found divers dead bodies not yet buried, and earth all digged like St. *Innocents* Church-yard in the time of the Plague. They did likewiſe leave in their Lodgings, Pavillions and Tents, divers ſick people; alſo Bullets, Arms, Carts, Waggons, and other Baggage, with a great many of Munition Loaves, ſpoiled and rotten by the rain and ſnow, yet the Souldiers had it but by weight and meaſure; and likewiſe they left great proviſion of Wood, of the remainders of the Houſes of the Villages which they had pluckt down two or three miles compaſs; likewiſe divers other Houſes of Pleaſure belonging to the Citizens, accompanied with fair Gardens, and Graſs-plats filled with Fruit-trees, for without that they had been ſtarved with cold, and had been conſtrained to have raiſed the Siege ſooner. The ſaid Mounſieur *de Guiſe* cauſed the dead to be buried, and dreſs their ſick people; likewiſe the Enemies left in the Abby of St. *Arnoul* divers of their hurt Souldiers which they could not lead with them; the ſaid Mounſieur *de Guiſe* ſent them all victuals enough, and commanded me and other Surgeons to go dreſs them and give them Medicins; which we willingly did, and think they would not have done the like toward others (becauſe the *Spaniard* is moſt cruel, perfidious, and inhumane, and therefore Enemy to all Nations) which is proved by *Lopez* a *Spaniard*, and *Benzo* of *Milan*, and others who have written the Hiſtory of *America*, and the *Weſt-Indies*, who have been conſtrained to confeſs that the cruelty, avarice, blaſphemy, and wickedneſs of the *Spaniards*, have altogether alienated the poor *Indians* from the Religion which the ſaid *Spaniards* are ſaid to hold. And all write, they are leſs worth than the idolatrous *Indians*, by the cruel uſage done to the ſaid *Indians*.

And after a few days we ſent a Trumpet to *Thionville* toward the Enemy, that they ſhould ſend back for their wounded men in ſafety, which they did with Carts and Waggons, but not enough. Mounſieur *de Guiſe* cauſed them to have Carts and Carters to help to carry them to the ſaid *Thionville*. Our ſaid Carters being returned back, brought us word that the way was paved with dead bodies, and that they never led back the half, for they died in their Carts, and the *Spaniards* ſeeing them at the point of death, before they had caſt out their laſt gaſp, caſt them out of their Carts, and buried them in the Mud and Mire, ſaying, they had no order to bring back the dead. Moreover our Carters ſaid, they met by the way divers Carts loaden with Baggage ſticking in the Mire, which they durſt not ſend for back, for fear leſt thoſe of *Mets* ſhould fall upon them. I will again return to the cauſe of their mortality, which was principally through Hunger, Plague, and Cold; for the Snow was two foot thick upon the earth, and they were lodged in the caves of the earth, onely covered with a little ſtraw. Notwithſtanding each Souldier had his Field-bed, and a covering ſtrewed with glittering Stars, more bright than fine gold, and every day had white ſheets, and lodged at the ſign of the Moon, and made good chear when they had it, and paid their Hoſt ſo well overnight, that in the morning they went away quite, ſhaking their ears, and they needed no Comb to take away the down out of their hairs either of head or beard, and found always a white Table-cloth, loſing good Meals for want of Victuals. Alſo the greateſt part of them had neither Boots nor Buskins, Slippers, Hoſe, or Shoes, and divers had rather have none than have them, becauſe they were always in mud, half way of the leg; and becauſe they went bare-legged, we called them the Emperours Apoſtles. After the Camp was wholly broken, I diſtributed my Patients into the hands of the Surgeons of the City, to finiſh their Cure: then I took leave of Mounſieur *de Guiſe*, who came back toward the King, who received me with a loving countenance, and demanded of me how I did enter into the City of *Mets*. I recounted to him all that I had done, he cauſed two hundred Crowns to be given me, and one hundred I had at my going out, and told me he would not leave me poor; then I thanked him moſt humbly for the good and the honour which he pleaſed to do me.

The Voyage of Hedin, 1553.

CHarles the Emperour cauſed the City of *Therouenne* to be beſieged, where Mounſieur the Duke of *Savoy* was General of the whole Army: it was taken by aſſault where there was a great number of our men ſlain and priſoners. The King willing to prevent that the Enemy ſhould not alſo come to beſiege the City and Caſtle of *Hedin*, ſent Meſſiers the Duke of *Bouillon*, the Duke *Horace*, the Marqueſs of *Villars*, a number of Captains, and about eight hundred Souldiers, and during the ſiege of *Therouenne*, the ſaid Lords fortified the ſaid Caſtle of *Hedin*, in ſuch ſort that it ſeemed impregnable. The King ſent me to the ſaid Lord to help them with my Art, if there were any need. Now ſoon after the taking of *Therouenne*, we were beſieged with the Army: there was a quick clear Fountain of Spring, within Cannon-ſhot, where there was about fourſcore Whores and Wenches of the Enemies, who were round about it to draw Water. I was upon a Rampart beholding the Camp, and ſeeing ſo many idlers about the ſaid Fountain, I prayed Mounſieur *de Pont* Commiſſary of the Artillery, to make one Cannon-ſhot at that roguiſh Company; he made me much denial, anſwering me that ſuch kind of people were not worth the Powder they ſhould waſte. Again I prayed him to level the Cannon, telling him, *the more dead the fewer Enemies*; which he did through my requeſt, and at that ſhot fifteen or ſixteen were killed, and many hurt. Our Souldiers ſallied forth upon the Enemies, where there was many killed and ſlain with Musket-ſhot and Swords, as well on the one ſide as of the other, and our Souldiers did often make ſallies forth upon the Enemies before their Trenches were made; where I had much work cut out, ſo that I had no reſt night nor day for dreſſing the wounded. And I will tell this by the way, that we had put many of them in a great Tower, laid upon a little ſtraw, and their Pillows were ſtones, their Coverlets were their Cloaks, of thoſe that had any. Whileſt the battery was making, as many ſhot as the Cannons made, the Patients ſaid they felt pain in their wounds, as if one had given them blows with a ſtaff; the one cried his head, the other his arm, and ſo of other parts; divers of their wounds bled afreſh, yea in greater quantity than firſt when they were wounded, and then it was I muſt run to ſtay their bleeding.

My little Maſter, if you had been there, you had been much troubled with your hot irons, you had need to have had much Charcoal to make them red hot, and believe they would have ſlain you like a Calf for this cruelty. Now through this Diabolical tempeſt of the Eccho from theſe thundering Inſtruments, and by the great and vehement agitation of the colliſion of the air reſounding and reverberating in the wounds of the hurt people, divers died, and others becauſe they could not reſt by reaſon of the groans and cries that they made night and day, and alſo for want of good nouriſhment, and other good uſage neceſſary to wounded people. Now my little Maſter, if you had been there, you would hardly have given them Gelly, Reſtauratives, Culliſes, Preſſures, Panado, cleanſed Barley, White Meats, Almond-milk, Prunes, Raiſins, and other proper meats for ſick people: your ordinance would onely have been accompliſhed in paper, but in effect they could have had nothing but old Cow-beef, which was taken about *Hedin* for our Munition, ſalted and half boiled, in ſo much that who would have eat it, he muſt pull it with the force of his teeth, as Birds of Prey do Carrion. I will not forget their Linen wherewith they were dreſt, which was onely rewaſhed every day, and dried at the fire, and therefore drie and ſtubborn like Parchment. I leave you to think how their wounds could heal well. There were four luſty Whores to whom charge was given to waſh their Linen, who diſcharged their duty under penalty of the Battoon, and alſo they wanted both Sope and Water. See then how the ſick People died for want of nouriſhment, and other neceſſary things. One day our Enemies feigned to give us a general Aſſault, to draw our Souldiers upon the breach, to the end to know our countenance and behaviour: every one ran thiter; we had made great proviſion of artificial Fire to defend the breach: a Prieſt belonging to Mounſieur *Du Bouillon* took a Granado, thinking to throw it on the Enemies, and ſet it on fire ſooner than it ought to have done; it brake aſunder, and the fire fell amongſt our Fireworks, which were put into a houſe near the breach, which was to us a marvellous diſaſter, becauſe it burned many poor Souldiers: it alſo took hold on the houſe it ſelf, and we had been all burned, had not great help been uſed for to quench it; there was but one Well there wherein was Water in our Caſtle, which was almoſt quite dried up, and in ſtead of Water we took Beer and quenched it: then afterwards we had great ſcarcity of Water, and to drink the reſt that remained, which we muſt ſtrain through Napkins.

Now the Enemy ſeeing this ſmoke and tempeſt of the Fire-works, which caſt a very great flame or claſhing noiſe, they believed we had put the fire on purpoſe for the defence of our breach, to burn them, and that we had great ſtore of others. That made them to be of another opinion than to take us by aſſault; they did undermine, and dig under the greateſt part of our Walls, ſo that it was the way to overthrow wholly the Caſtle topſie-turvy, and when the Mines were finiſhed, and that their Artillery ſhot, the whole Caſtle did ſhake under us like an Earthquake, which did much aſtoniſh us. Moreover he had levelled five pieces of Artillery which they had ſeated upon a little hill, to play upon our backs when we would go to defend the breach.

The Duke *Horace* had a Cannon-ſhot upon one ſhoulder, which carried away his arm on one ſide, and the body on the other, without being able to ſpeak one onely word. His death was to us a great diſaſter for the rank which he held in his place.

Likewiſe Mounſieur *De Martigues* had a ſtroke with a bullet which pierced through his Lungs; I dreſſed him, as I will declare hereafter. Then we demanded Parl, and a Trumpet was ſent toward the Prince of *Piedmont*, to know what compoſition it pleaſed him to make us: His anſwer was, that all the Chief, as Gentlemen, Captains, Lieutenants, and Enſigns, ſhould be taken for ranſom, and the Souldiers ſhould go out without Arms; and if they refuſed this fair and honeſt proffer, the next day we ought to be aſſured they would have us by aſſault, or otherwiſe. Council was held, where I was called to know if I would ſign, as divers Captains, Gentlemen, and others, that the place ſhould be rendred up. I made anſwer it was not poſſible to be held, and that I would ſign it with my proper bloud, for the little hope that I had that we could reſiſt the Enemies force, and alſo for the great deſire which I had to be out of this Torment and Hell; for I ſlept not either night or day, by reaſon of the great number of hurt people, which were about two hundred. The dead bodies yielded a great putrefaction, being heaped one upon another like Fagots, and not being covered with earth, becauſe we had it not; and when I entered into one lodging, Souldiers attended me at the door to go and dreſs others at another; when I went forth, there was ſtriving who ſhould have me, and they carried me like a Holy body, not touching the ground with my foot, in ſpite one of another; nor could I ſatisfie ſo great a number of hurt people. Moreover I had not what was neceſſary to dreſs them withall; for it is not ſufficient that the Surgeon do his duty towards the Patients, but the Patient muſt alſo do his, and the aſſiſtants and all exteriour things, witneſs *Hippocrates* in his firſt Aphoriſm. Now having underſtood the reſolution of the yielding up of our place, I knew our affairs went not well; and for fear of being known, I gave a Velvet Coat, a Satin Doublet, a very fine Cloth Cloak lined with Velvet, to a Souldier, who gave me a ſcurvy old torn doublet cut and ſlaſht with uſing, and a leather Jerkin well examined, and an ill-favoured Hat, and a little Cloak; I ſmucht the collar of my Shirt with water in which I had mingled a little Soot; likewiſe I wore out my ſtockings with a ſtone at the knees and at the heels as if they had been wore a long time, and I did as much to my ſhoes, in ſo much that they would rather take me for a Chimney-Sweeper than a Kings Surgeon. I went in this Equipage towards Mounſieur *De Martigues*, where I prayed him that he would take order that I might remain near him to dreſs him, which he agreed to moſt willingly, and had as much deſire I ſhould remain with him as my ſelf. Soon after the Commiſſioners, who had charge to elect the Priſoners, entered into the Caſtle the ſeventeenth day of *July*, One thouſand Five hundred Fifty three, where they made *Meſſieures* the Duke of *Bouillon*, the Marqueſs of *Villars*, the Baron of *Culan*, Mounſieur *Du Pont* Commiſſary of the Artillery, and Mounſieur *De Martigues* and I to be taken through the requeſt that he made to them; and all other Gentlemen which they could perceive were able to

pay

pay any ranſom, and the moſt part of the Souldiers and the chief of Companies, having ſuch and ſo many Priſoners as they would.

Afterward the *Spaniſh* Souldiers entered by the breach without any reſiſtance, for ours eſteemed they would hold their Faith and Compoſition that they ſhould have their lives ſaved. They entered in with a great fury to kill, pillage, and to rifle all they retained: ſome hoping to have ranſom, they tied their Stones with Arquebus-cords, which was caſt over a Pike which two held upon their ſhoulders, then pulled the ſaid cord with a great violence and deriſion, as if they would ring a Bell, telling them that they muſt put themſelves to the ranſom, and tell of what Houſes they were; and if they ſaw they could have no profit, made them cruelly die between their hands, or preſently after their genital parts would have fallen into a Gangrene and total Mortification; but they killed them all with their Daggers, and cut their Throats. See now their great cruelty and perfidiouſneſs, let him truſt to it that will. Now to return to my purpoſe; Being led from the Caſtle to the City with Mounſieur *De Martigues*, there was a Gentleman of the Duke of *Savoys*, who asked me if Mounſieur *De Martigues* wound were curable, I anſwered not; who preſently went and told the Duke of *Savoy*; now I thought he would ſend Phyſicians and Surgeons to viſit and dreſs my ſaid Mounſieur *De Martigues:* in the mean time I thought with my ſelf whether I ought to make it nice, and not to acknowledge my ſelf a Surgeon, for fear leſt they ſhould retain me to dreſs their wounded, and in the end they would know I was the Kings Surgeon, and that they would make me pay a great ranſom. On the other ſide I feared, if I ſhould not make my ſelf known to be a Surgeon, and to have carefully dreſſed Mounſieur *De Martigues*, they would cut my Throat, ſo that I took a reſolution to make it appear to them he would not die for want of good dreſſing and looking to. Soon after, ſee, there were divers Gentlemen accompanied with the Phyſician and Surgeon of the Emperour, and thoſe of the ſaid Duke of *Savoy*, with ſix other Surgeons following the Army, to ſee the hurt of the ſaid Lord of *Martigues*, and to know of me how I had dreſſed him, and with what Medicins. The Emperours Phyſician bid me declare the eſſence of the wound, and how I had dreſt it. Now all the aſſiſtants had a very attentive ear to know if the wound were mortal or not; I began to make a diſcourſe that Mounſieur *De Martigues* looking over the Wall to perceive them that did undermine it, received a ſhot from an Arquebus quite through the body; preſently I was called to dreſs him, I ſaw he caſt out bloud out of his mouth and his wounds. Moreover he had a great difficulty of breathing, and caſt out wind by the ſaid wounds with a whiſtling, in ſo much that it would blow out a candle; and he ſaid he had a moſt ſharp pricking pain at the entrance of the bullet. I do believe and think it might be ſome little pieces of bones which prickt the Lungs. When they made their Syſtole and Diaſtole, I put my finger into him, where I found the entrance of the bullet to have broken the fourth rib in the middle, and ſcales of bones, which the ſaid bullet had thruſt in, and the out-going of it had likewiſe broken the fifth rib with pieces of bones which had been driven from within outward; I drew out ſome, but not all, becauſe they were very deep and adherent. I put in each wound a Tent, having the head very large, tied with a thred, leſt by the inſpiration it might be drawn into the capacity of the *Thorax*, which hath been known by experience to the detriment of the poor wounded; for being fallen in, it cannot be taken out, which is the cauſe that engenders putrefaction, a thing contrary to Nature. The ſaid Tents were anointed with a Medicin compoſed of Yolks of Eggs, Venice Turpentine, with a little Oil of Roſes. My intention for putting the Tents was to ſtay the flux of bloud, and to hinder that the outward air did not enter into the breſt, which might have cooled the lungs, and by conſequent the heart. The ſaid Tents were alſo put, to the end that iſſue might be given for the bloud that was ſpilt within the *Thorax*. I put upon the wound great Emplaſters of *Diacalcitheos*, in which I had relented Oil of Roſes and Vinegar to the avoiding of the inflammation; then I put great ſtupes of *Oxycrate*, and bound him up, but not too hard, to the end he might have eaſie reſpiration; that done I drew from him five porringers of bloud from the Baſilick vein of the right arm, to the end to make revulſion of the bloud which runs from the wounds into the *Thorax*, having firſt taken indication from the wounded part, and chiefly his forces, conſidering his youth and ſanguin temper; He preſently after went to ſtool, and by his Urin and Siege caſt great quantity of bloud. And as for the pain which he ſaid he felt at the entrance of the bullet, which was as if he had been pricked with a bodkin, that was becauſe the Lungs by their motion beat againſt the ſplinters of the broken rib. Now the Lungs are covered with a coat coming from the membrane called *Pleura*, interweaved with Nerves of the ſixth Conjugation from the brain, which was cauſe of the extreme pain he felt; likewiſe he had great difficulty of breathing, which proceeded from the bloud which was ſpilt in the capacity of the *Thorax*, and upon the Diaphragm, the principal inſtrument of reſpiration, and from the dilaceration of the muſcles which are between each rib, which help alſo to make the expiration and the inſpiration; and likewiſe becauſe the Lungs were torn and wounded by the bullet, which hath cauſed him ever ſince to ſpit black and putrid bloud in coughing. The Fever ſeized him ſoon after he was hurt, with faintings and ſwoonings. It ſeemed to me that the ſaid Fever proceeded from the putredinous vapours ariſing from the bloud which is out of his proper veſſels, which hath fallen down, and will yet flow down. The wound of the Lungs is grown great, and will grow more great, becauſe it is in perpetual motion both ſleeping and waking, and is dilated and compreſt to let the air to the heart, and caſt fuliginous vapours out: by the unnatural heat is made inflammation, then the expulſive virtue is conſtrained to caſt out by cough whatſoever is obnoxious unto it: for the Lungs cannot be purged but by coughing, and by coughing the wound is dilated, and grows greater, from whence the bloud iſſues out with great abundance, which bloud is drawn from the heart by the Vein Arterial to give them nouriſhment, and to the heart by the *Vena cava*; his meat was Barley-broth, Stewed Prunes, ſometimes Panado; his drink was Ptiſan: He could not lye but upon his back, which ſhewed he had a great quantity of bloud

ſpilt

ſpilt within the capacity of the *Thorax*; and being ſpread or ſpilled along the ſpondyls, doth not ſo much preſs the Lungs as it doth being laid on the ſides or ſitting.

What ſhall I ſay more, but that the ſaid Lord *Martigues* ſince the time he was hurt hath not repoſed one hour onely, and hath always caſt out bloudy Urines and Stools. Theſe things then *Meſſiers* conſidered, one can make no other prognoſtick but that he will die in a few days, which is to my great grief. Having ended my diſcourſe, I dreſt him as I was wont; having diſcovered his wounds, the Phyſicians and other aſſiſtants preſently knew the truth of what I had ſaid.

The ſaid Phyſicians having felt his pulſe and known his forces to be almoſt ſpent and aboliſhed, they concluded with me, that in a few days he would die; and at the ſame inſtant went all toward the Lord of *Savoy*, where they all ſaid that the ſaid Lord *Martigues* would die in a ſhort time; he anſwered, it were poſſible if he were well dreſt, he might eſcape: Then they all with one voice ſaid, he had been very well dreſt, and ſollicited with all things neceſſary for the curing of his wounds, and could not be better, and that it was impoſſible to cure him, and that his wound was mortal of neceſſity. The Mounſieur *De Savoy* ſhewed himſelf to be very much diſcontented and wept, and asked them again if for certain they all held him deplored and remedileſs; they anſwered, Yes. Then a certain *Spaniſh* Impoſtor offered himſelf, who promiſed on his life that he would cure him, and if he failed to cure him, they ſhould cut him in an hundred pieces: but he would not have any Phyſicians, Surgeons, or Apothecaries with him. And at the ſame inſtant the ſaid Lord of *Savoy* told the Phyſicians and Surgeons they ſhould not in any wiſe go any more to ſee the ſaid Lord of *Martigues*. And he ſent a Gentleman to me to forbid me upon pain of life not to touch any more the ſaid Lord of *Martigues*, which I promiſed not to do; wherefore I was very glad, ſeeing he ſhould not die in my hands, and commanded the ſaid Impoſtor to dreſs the ſaid Lord of *Martigues*, and that he ſhould have no other Phyſicians nor Surgeons but him; he came preſently to the ſaid Lord of *Martigues*, who told him:

Senor Cavallero el ſenor Duge me ha mandado que veniaſſe a curar vaſtra herida, yo os juro a Dios que antes de achio dias yo os hag a ſubir a Cavello con la lanſa en puno contaſque no ago qué yo quos togne, Comeris y biberis todis comedas que ſueren de vaſtro guſto y yo hare la dieta pro V. M. y deſto os de veu aſeguirar ſobre de mi, yo he ſanado mun hos que tenian magores heridas que la vaſtra. That is to ſay, Lord Cavallier, Mounſieur the Duke of *Savoy* hath commanded me to come dreſs thy wound; I ſwear to thee by God, that before eight days I will make thee mount on Horſe-back with thy Lance in thy hand, provided that no man may touch thee but my ſelf; thou ſhalt eat and drink any thing that thou haſt a mind to, I will perform thy diet for thee, and of this thou mayeſt be aſſured upon my promiſe. I have cured divers who have had greater wounds than thine: and the Lord replied, *God give you Grace to do it.*

He demanded of the ſaid Lord a Shirt, and tore it in little rags, which he put acroſs, muttering and murmuring certain words over the wounds; and having dreſt him, permitted him to eat and drink what he would, telling him he would obſerve a diet for him, which he did, eating but ſix Prunes and ſix bits of bread at a meal, and drinking but Beer. Notwithſtanding two days after, the ſaid Lord of *Martigues* died; and my *Spaniard*, ſeeing of him in the Agony, eclipſed himſelf, and got away without bidding farewel to any body; and I believe if he had been taken, he had been hanged for his falſe promiſes, which he had made to Mounſieur the Duke of *Savoy*, and to divers other Gentlemen.

He died about ten of the Clock in the morning, and after Dinner the ſaid Lord of *Savoy* ſent Phyſicians and Surgeons, and his Apothecary, with a great quantity of Drugs to embalm him; they came accompanied with divers Gentlemen and Captains of the Army.

The Emperours Surgeon came near to me, and prayed me kindly to open the Body; which I refuſed, telling him I was not worthy to carry his Plaſter-Box after him. He prayed me again; which then I did for his ſake, if it ſo liked him. I would yet again have excuſed my ſelf, that ſeeing he was not willing to embalm him, that he would give this charge to another Surgeon of the Company; he made me yet anſwer, that he would it ſhould be I; and if I would not do it, I might hereafter repent it. Knowing this his affection, for fear he ſhould do me any diſpleaſure, I took the Razor and preſented it to all in particular, telling them I was not well practiſed to do ſuch Operations, which they all refuſed.

The Body being placed upon a Table, truly I purpoſed to ſhew them that I was an Anatomiſt, declaring to them divers things ſhould be here too long to recite. I began to tell all the Company that I was ſure the bullet had broken two Ribs, and that it had paſſed through the Lungs, and that they ſhould find the wound much enlarged, becauſe they are in perpetual motion, ſleeping or waking, and by this motion the wound was the more dilacerated. Alſo that there was great quantity of bloud ſpilt in the capacity of the breſt, and upon the midriff, and ſplinters of the broken ribs which were beaten in at the entrance of the bullet, and the iſſuing forth of it had carried out. Indeed all which I had told them was found true in the dead body.

One of the Phyſicians asked me, which way the bloud might paſs to be caſt out by Urine, being contained in the *Thorax*. I anſwered him that there was a manifeſt Conduit, which is the *Vena Azygos*, which having nouriſhed the ribs, the reſt of the bloud deſcends under the Diaphragm, and on the left ſide is conjoined to the emulgent Vein, which is the way by which the matter in Pleuriſies and in *Empuema*, do manifeſtly empty themſelves by Urin and Stool. As it is likewiſe ſeen the pure milk of the breſts of Women newly brought to bed, to deſcend by the Mammillary veins and to be evacuated downwards by the neck of the womb without being mixt with the bloud. And ſuch a thing is done (as it were by a miracle of Nature) by her expulſive and ſequeſtring virtue, which is ſeen by experience of two glaſs veſſels called Mount-wine; let the one be filled with Water, and the other with Claret-wine, and let them be put the one upon the other, that is to ſay, that which ſhall be filled with Water upon that which ſhall be filled with Wine, and you ſhall apparently ſee the Wine

mount

mount up to the top of the veſſel quite through the water, and the water deſcend atraverſe the wine, and go to the bottom of the veſſel without mixture of both; and if ſuch a thing be done ſo exteriorly and openly to the ſenſe of our eye, by things without life, you muſt believe the ſame in our underſtanding; That nature can make matter and bloud to paſs, having been out of their veſſels, yea, through the bones, without being mingled with the good bloud.

Our diſcourſe ended, I embalmed the body, and put it into a Coffin; after that the Emperors Surgeon took me apart, and told me if I would remain with him, that he would uſe me very well, and that he would cloath me a new, alſo that I ſhould ride on Horſe-back. I thanked him very kindly for the honour he did me, and told him that I had no deſire to do ſervice to Strangers and Enemies to my Countrey: then he told me I was a Fool, and if he were Priſoner as I, he would ſerve the Devil to get his liberty. In the end I told him flat that I would not dwell at all with him.

The Emperours Phyſician returned towards the ſaid Lord of *Savoy*, where he declared the cauſe of the death of the ſaid Lord of *Martignes*, and told him that it was impoſſible for all the men in the World to have cured him; and confirmed again, that I had done what was neceſſary to be done, and prayed him to win me to his ſervice, and ſpake better of me than I deſerved.

Having been perſuaded to take me to his ſervice, he gave charge to one of his Stewards named Mounſieur *de Bouches*, to tell me if I would dwell in his ſervice, that he would uſe me kindly: I anſwered him that I thanked him moſt humbly, and that I had reſolved not to dwell with any Stranger. This my anſwer being heard by the Duke of *Savoy*, he was ſomewhat in choler, and ſaid, He would ſend me to the Gallies.

Mounſieur *de Vandeville* Governor of *Gravelin*, and Colonel of the ſeventeen Enſigns of Foot, prayed him to give me to him, to dreſs him of an ulcer which he had in his leg this ſix or ſeven years; Mounſieur *de Savoy* told him, becauſe I was of worth, that he was content, and if I rankled his leg, it would be well done; he anſwered, that if he perceived any thing, he would cauſe my Throat to be cut.

Soon after the ſaid Lord of *Vandeville* ſent for me by four *German* Halbertiers, which affrighted me much, not knowing whither they led me, they ſpake no more French than I High Dutch: being arrived at his Lodging, he told me I was welcome, and that I was his; and as ſoon as I ſhould have cured him of that ulcer in his leg, that he would give me leave to be gone without taking any ranſom of me. I told him that I was not able to pay any ranſome.

Then he made his Phyſician and Surgeon in Ordinary to ſhew me his ulcerated leg; having ſeen and conſidered it, we went apart into a Chamber, where I began to tell them that the ſaid Ulcer was annual, not being ſimple but complicated: that is of a round figure and ſcaly, having the lips hard and callous, hollow and ſordid, accompanied with a great varicous vein which did perpetually feed it; beſides a great tumour, and a phlegmonous diſtemper very painful through the whole leg, in a body of cholerick complexion, as the hair of his face and beard demonſtrated. The method to cure it (if cured it could be) was to begin with univerſal things, that is, with Purgation and Bleeding, and with this order of Diet, that he ſhould not uſe any Wine at all, nor any ſalt Meats or of great nouriſhment, chiefly thoſe which did heat the bloud: afterward the Cure muſt begin with divers ſcarifications about the Ulcer, and totally cutting away the callous edges or lips, and giving a long or a triangular figure; for the round will very hardly cure, as the Ancients have left it in writing, which is ſeen by experience. That done the filth muſt be mundified, as alſo the corrupt fleſh, which ſhould be done with *Unguentum Ægyptiacum*, and upon it a bolſter dipt in juice of Plantain and Nightſhade and *Oxycrate*, and rowl the leg, beginning at the foot, and finiſhing at the knee, not forgetting a little bolſter upon the varicous Vein, to the end no ſuperfluities ſhould flow to the Ulcer. Moreover that he ſhould take reſt in his bed, which is commanded by *Hippocrates*, who ſaith, that thoſe who have ſore legs ſhould not uſe much ſtanding or ſitting, but lying along. And after thoſe things be done, and the Ulcer well mundified, a plate of Lead rubbed with Quickſilver ſhould be applied. See then the means by which the ſaid Lord *Vandeville* might be cured of the ſaid Ulcer; all which they found good. Then the Phyſician left me with the Surgeon, and went to the Lord *Vandeville*, to tell him that he did aſſure him I would cure him, and told him what I was reſolved to do for the cure of his Ulcer, wherefore he was very joyful. He made me to be called to him, and asked me if I was of the opinion that this Ulcer could be cured, and I told him, yes, provided he would be obedient to what he ought. He made me a promiſe he would perform all things which I would appoint; and as ſoon as his Ulcer ſhould be cured, he would give me liberty to return without paying any ranſom. Then I beſeeched him to come to a better compoſition with me, telling him that the time would be too long to be out of liberty, if I ſtaid till he was perfectly well; and that I hoped within fifteen days the Ulcer ſhould be diminiſhed more than one half, and it ſhould be without pain, and that his Phyſicians and Surgeons would finiſh the reſt of the cure very eaſily. To which he agreed, and then I took a piece of Paper, and cut it the largeneſs of the Ulcer, which I gave him, and kept as much my ſelf. I prayed him to keep promiſe, when he ſhould find his buſineſs done: He ſwore by the faith of a Gentleman he would do it. Then I reſolved to dreſs him well, according to the method of *Galen*, which was, that after all ſtrange things were taken out of the Ulcer, and that there wanted nothing but filling up with fleſh, I dreſt him but once a day, and he found that very ſtrange. And likewiſe his Phyſician, which was but a Freſh-man in thoſe affairs, who would perſuade me with the Patient, to dreſs him two or three times a day, I prayed him to let me do what I thought good; and that it was not to prolong the cure, but on the contrary to haſten it, for the great deſire I had to be in liberty. And that he would look in *Galen* in the fourth Book of the Compoſition of Medicaments *ſecundum genera*, who ſaith, that if a Medicin do not remain long upon the part it profits not ſo much as when it doth continue long; a thing which many Phyſicians have been ignorant of, and have thought it hath been better to change the Plaſter often. And this ill cuſtom is ſo inveterate and rooted, that the Patients themſelves accuſe often-times the Surgeons of negligence, becauſe they do not oftner

remove

remove their Emplaſters; but they are deceived. For as you have read in my Works in divers places, the qualities of all bodies which mutually touch, operate one againſt another, and both of them ſuffer ſomething, where one of them is much ſtronger than the other, by means whereof the ſaid qualities are united; they familiarize with the time, although they are much differing from the manner, that the quality of the Medicament doth unite, and ſometimes becomes like to that of the body, which is a very profitable thing. Therefore they ſay he is to be praiſed much who firſt invented not to change the Plaſter ſo often, becauſe it is known by experience this is a good invention.

Moreover it is ſaid, great fault is committed to dreſs Ulcers often in wiping of them hard; for one takes not away onely the unprofitable excrement, which is the *pus* or *ſanies* of the ulcer, but the matter whereof the fleſh is engendered; wherefore for the reaſons aforeſaid it is not needful to dreſs Ulcers ſo often.

The ſaid Lord *Vandeville* would ſee whether that which I alledged out of *Galen* were true and commanded the ſaid Phyſician to look there, for that he would know it; he cauſed the Book to be brought upon the Table, where my ſaying was found true, and then the Phyſician was aſhamed, and I very joyful. So that the ſaid Lord of *Vandeville* deſired not to be dreſſed but once a day, in ſo much that within fifteen days the Ulcer was almoſt cicatrized; the compoſition being made between us, I began to be merry. He made me eat and drink at his Table, when there were not men of more great rank with him.

He gave me a great red Scarf, which he commanded me to wear. I may ſay I was as glad of it as a Dog that hath a clog, for fear he ſhould go into the Vineyard and eat the Grapes. The Phyſician and Surgeon led me through the Camp, to viſit their hurt people, where I took notice what our Enemies did: I perceived they had no more pieces of Cannon, but twenty five or thirty pieces for the Field.

Mounſieur *de Vandeville* held Mounſieur *de Bauge* Priſoner, the Brother of Mounſieur *de Martignes* who died at *Hedin*. The ſaid Lord of *Bauge* was Priſoner in the Caſtle of the *Heap of Wood*, belonging to the Emperour, who had been taken at *Therouenne* by two *Spaniſh* Souldiers. Now the ſaid Lord of *Vandeville* having looked well upon him, conceived he muſt be a Gentleman of ſome good Houſe; and to be the better aſſured, he aauſed him to have his Stockings pulled off, and ſeeing his Stockings and his Feet clean and neat, together with his fine white ſocks, it confirmed him the better in his opinion, that it was a man was able to pay ſome good ranſom. He demands of the Souldiers if they would take thirty Crowns for their Priſoner, and that he would give it to them preſently, to which they agreed willingly, becauſe they had neither means to keep him, nor feed him: beſides they knew not his worth, therefore they delivered their Priſoner into the hands of the ſaid Lord of *Vandeville*, who preſently ſent him to the Caſtle of the *Heap of Wood* with a Guard of four Souldiers, with other Gentlemen Priſoners of ours. The ſaid Lord *Bauge* would not diſcover himſelf, who he was, and endured very much, being kept but with bread and water, and lay upon a little ſtraw. The ſaid Lord of *Vandeville* after taking of *Hedin*, ſent word to the ſaid Lord *Bauge* and other priſoners, that the place of *Hedin* was taken, and the liſt of thoſe that had been ſlain, and amongſt the reſt, Mounſieur *de Martignes:* and when the ſaid Lord of *Bauge* heard the ſound of the death of his brother the Lord *Martignes*, he began much to weep and lament; his Keeper demanded of him, why he made ſo many and ſo great lamentations? He declared unto them that it was for Mounſieur *de Martignes* his brothers ſake. Having underſtood that, the Captain of the Caſtle diſpatched a man away quickly, to tell it to Mounſieur *de Vandeville* that that he had a good priſoner; who having received this good news rejoiced greatly, and the next day ſent me with his Phyſicians and four Souldiers to the Wood-Caſtle to know if this priſoner would give him fifteen thouſand Crowns for a ranſom, ſo he would ſend him free to his own houſe; and for the preſent he deſired but the ſecurity of two Merchants of *Antwerp*, that he would name. The ſaid Lord *Vandeville* perſuaded me that I would make his agreement with his priſoner. See then why he ſent me to the Wooden Caſtle, and commanded the Captain of the Caſtle to uſe him well, and to put him into a Chamber hung with Tapeſtry, and that they ſhould make the Guard more ſtrong, and from that time they made him good chear at his expence.

The anſwer of the ſaid Lord of *Bauge* was, that to put himſelf to ranſom he was not able; and that, that depended upon Mounſieur *de Eſtamps* his Uncle, and of Miſtreſs *de Breſſeure* his Aunt, and he had not any means to pay ſuch a ranſom. I returned with my Keepers to the ſaid Lord *Vandeville*, and told him the anſwer of his ſaid Priſoner, who told me perhaps he ſhould not get out at ſo good a rate; which was true, for he was diſcovered. And forthwith the Queen of *Hungary* and the Duke of *Savoy* ſent word to the Lord *Vandeville*, that this morſel was too great for him, and that he muſt ſend him to them, (which he did) and that he had enough Priſoners beſides him. He was put to forty thouſand Crowns ranſom, beſides other expences.

Returning toward the ſaid Lord *Vandeville* I paſſed by St. *Omer*, where I ſaw their great pieces of Battery, whereof the greateſt part was flawed and broken. I came alſo by *Therouenne*, where I did not ſee ſo much as ſtone upon ſtone, unleſs the mark of a great Church. For the Emperor gave commandment to the Country people within five or ſix leagues about, that they ſhould empty and carry away the ſtones; in ſo much, that now one may drive a Cart over the City as is likewiſe done at *Hedin*, without any appearance of Caſtle or Fortreſs. See then the miſchief which comes by the Wars.

And to return to my purpoſe, preſently after my ſaid Lord *Vandeville* was very well of his Ulcer, and little wanted of the entire cure, which was the cauſe he gave me my leave, and made me be conducted with a Paſs-port by a Trumpet to *Abbeville*, where I took Poſt, and went and found King *Henry* my Maſter at *Auſimon*, who received me with joy, and a good countenance.

He ſent for the Duke of G[illegible] the High Conſtable of *France*, and Mounſieur *d' Eſtres*, to underſtand by me what had paſſ[illegible] the taking of *Hedin*; and I made him a faithful report, and aſſured them I had ſeen the great Pieces of Battery, which they had carried to St. *Omer*. Whereof

the

the King was very joyful, becauſe he feared leſt the enemy ſhould come further into *France*. He gave me two hundred Crowns to retire my ſelf to my own houſe, and I was very glad to be in liberty, and out of this great torment and noiſe of thunder from the Diabolick artillery, and far from the Souldiers, blaſphemers and deniers of God. I will not omit to tell here that after the taking of *Hedin*, the King was advertiſed that I was not ſlain, but that I was a priſoner, which his Majeſty cauſed to be written to my wife by Monſieur *de Goguier* his chief Phyſician, and that ſhe ſhould not be in any trouble of mind for me, for that I was ſafe and well, and that he would pay my ranſom.

The Battle of S. Quintin, 1557.

AFter the Battel of S. *Quintin*, the King ſent for me to the Fere in *Tartenis* toward Monſieur the Marſhal of *Bourdillon*, to have a paſs-port by the Duke of *Savoy* to go to dreſs Monſieur the Conſtable, who was grievouſly hurt with a Piſtol-ſhot in the back, whereof he was like to die, and remained a priſoner in his enemies hands. But the Duke of *Savoy* would not give conſent that I ſhould go to the ſaid Lord Conſtable, ſaying, he would not remain without a Surgeon, and that he doubted I was not ſent only to dreſs him, but to give him ſome advertiſement, and that he knew I underſtood ſomething elſe beſide Surgery, and that he knew me to have been his priſoner at *Hedin*. Monſieur the Marſhal of *Bourdillon* advertiſed the King of the Dukes denial, by which means the King writ to the ſaid Lord of *Bourdillon*, that if my Lady, the Lord high Conſtables wife, did ſend any body of her houſe, which was an able man, that I ſhould give him a letter, and that I ſhould alſo have told him by word of mouth, what the King and Monſieur the Cardinal of *Lorrain* had given me in charge. Two days after there arrives a ſervant of the Lord Conſtables Chamber, who brought him ſhirts and other linnen, for which the ſaid Lord Marſhal gave paſs-port, to go to the ſaid Lord Conſtable; I was very glad thereof, and gave him my letter, and gave him his leſſon, of that which his Maſter ſhould do being priſoner. I had thought being diſcharged of my embaſſage to return toward the King. But the ſaid Lord of *Bourdillon* prayed me to ſtay with him at the Fere to dreſs a great number of people who were hurt, and were thither retired after the battle; and that he would ſend word to the King the cauſe of my ſtay; which I did. The wounds of the hurt people were greatly ſtinking, and full of worms with gangrene and putrefaction; ſo that I was conſtrained to come with my knife to amputate that which was ſpoiled, which was not without cutting off arms and legs, as alſo to trepan divers. Now there were not any medicines to be had at the Fere, becauſe the Surgeons of our Camp had carried all with them; I found out that the Chariot of the Artillery tarried behind at the Fere, nor had it yet been touched. I prayed the Lord Marſhal that he would cauſe ſome of the drugs to be delivered to me that were in it; which he did, and there was given to me one half at a time: five or ſix days after I was conſtrained to take the reſt, neither was there half enough to dreſs ſo great a number of people, and to contract and ſtay the putrefaction, and to kill the worms that were entred into their wounds, I waſhed them with *Ægyptiacum* diſſolved in wine and *Aqua vitæ*, and did for them all which I could poſſible, yet notwithſtanding all my diligence, very many of them died.

There were Gentlemen at the Fere who had charge to find out the dead body of Monſier *de Bois-Dolphin* the Elder, who had been ſlain in the battle; they prayed me to accompany them to the Camp to find him out amongſt the dead, if it were poſſible, which indeed was impoſſible; ſeeing that the bodies were all diſfavoured and overwhelmed with putrefaction. We ſaw more than half a league about us the earth covered with dead bodies, neither could we abide long there, for the cadaverous ſents which did ariſe from the dead bodies, as well of men as of Horſes. And I think we were the cauſe, that ſo great a number of flies roſe from the dead bodies, which were procreated by their humidity and the heat of the Sun, having their tails green and blew, that being up in the air made a ſhadow in the Sun. We heard them buz, or hum, which was much marvel to us. And I think it was enough to cauſe the Plague where they alighted. (My little Maſter) I would you had been there as I was, to diſtinguiſh the ordures, and alſo to make report to them which were never there. Now being cloyed and annoyed in that Country, I prayed Monſieur the Lord Marſhal, to give me my leave to be gone, and that I was afraid I ſhould be ſick by reaſon of my too great pains, and the ſtinks which did ariſe from the wounded, which did almoſt all die, for what diligence ſoever could be uſed unto them. He made other Surgeons come finiſh the dreſſing of the ſaid hurt people, and I went away with his good grace and favour. He wrote a letter to the King, of the pains he had taken of the poor wounded. Then I returned to *Paris*, where I found yet many Gentlemen that had been hurt, and were there retired after the battle.

The Voyage of the Camp of Amiens, 1558.

THE King ſent me to *Dourlan*, and made me be conducted by a Captain *Govaſt*, with fifty men in Arms, for fear I ſhould be taken by the enemies. And ſeeing that in the way we were always in alarums, I cauſed my man to alight, making him to be my maſter for that time, and I got upon his horſe, which carried my mail, and took his cloak and hat, and gave him my ambling Mare. My man being put upon her back, one would have taken him for the maſter, and I for the ſervant. Thoſe of *Dourlan* ſeeing us far off, thought we were enemies, and let flie their Cannon-ſhot at us. Captain *Gaveſt* my conductor, made a ſign with his hat, that we were not enemies, ſo that they left ſhooting, and we entred into *Dourlan*, with great joy. Thoſe of *Dourlan* made a ſally forth upon the enemies five or ſix days before; who killed and hurt divers of our Captains, and good Souldiers; and amongſt the reſt Captain S. *Aubin* valiant at the ſword, whom Monſieur *de Guiſe* loved very well, and for whom chiefly the King ſent me thither, who being in the fit of a quartan fever, would needs go out to command the greateſt part of his Company: a *Spaniard* ſeeing him that he commanded, perceived he was a Captain, and ſhot a muſket-bullet quite through his neck; my Captain S. *Aubin* thought with this ſtroke he was dead,

and

and with the fear (I proteſt to God) he loſt his quartan ague, and was altogether freed from it. I dreſſed him with *Anthony Portal* Surgeon in ordinary to the King, and divers other ſouldiers: ſome died, others eſcaped quite with the loſs of a leg, or an arm, or the loſs of an eye, and they ſaid they eſcaped good cheap, eſcape that can. When the enemy had broken their Camp, I returned to *Paris*. Here I hold my peace of my little Maſter, who was more at eaſe in his houſe, than I at the Wars.

The Voyage of Harbor *of Grace*, 1563.

YEt I will not omit to ſpeak of the Voyage of the *Harbor* of Grace; then when they made the approaches to plant the Artillery, the Engliſh who were within it killed ſome of our Souldiers, and divers Pioneers, who undermined, who when they were ſeen to be ſo hurt that there was no hope of curing, their fellows ſtript them and put them yet alive into the Mines, which ſerved them for ſo much filling earth. The Engliſh ſeeing they could not withſtand an aſſault, becauſe they were very much attainted with diſeaſes, and chiefly with the Plague, they vielded, their lives and jewels ſaved. The King cauſed them to have ſhips to return to *England*, being glad to be out of this place infected with the Plague: the greateſt part died, and carried the Plague into *England*, and ſince have not yet been exempted. Captain *Sarlabous* maſter of the Camp, was left there in Garriſon, with ſix Enſigns on foot, who had no fear of the plague, and were very joyful to enter therein, hoping there to make to make good cheer. My little Maſter had you been there, you had done as they.

The Voyage of Rowen, 1562.

NOw for the taking of *Rowen*, they killed divers of ours before the aſſault, and at the aſſault: the day after they entred into the City, I trepaned eight or nine, who were hurt at the breach with the ſtrokes of ſtones. There was ſo malignant an air, that divers died, yea of very ſmall hurts, inſomuch that ſome thought they had poiſoned their bullets: thoſe within ſaid the like by us, for although they were well treated in their neceſſities within the City, yet they died alſo as well as thoſe without. The King of *Navor* was hurt in the ſhoulder with a bullet ſome few days before the aſſault; I viſited and helpt to dreſs him, with his own Surgeon, named M. *Gilbert* one of the chief of *Montpelier*, and others. They could not find the bullet, I ſearched for it very exactly; I perceived by conjecture, that it was entred by the head of the *Adjutorium*, and that it had run into the cavity of the ſaid bone, which was the cauſe we could not find it. The moſt part of them ſaid it was entred and loſt within the cavity of the body. Monſieur the Prince of the *Roch upon Yon*, who intimately loved the King of *Navar*, drew me to one ſide, and askt me if the wound was mortal. I told him yea, becauſe all wounds made in great joints, and principally contuſed wounds, were mortal according to all Authors who had written of them. He inquired of the others what they thought, and chiefly of the ſaid *Gilbert*, who told him that he had great hope that the King his Maſter would be cured, and the ſaid Prince was very joyful. Four days after the King and Queen-Mother, Monſieur the Cardinal of *Bourbon* his brother, Monſieur the Prince of *Roch upon Yon*, Monſieur *de Guiſe*, and other great perſonages, after we had dreſſed the King of *Navar*, cauſed a conſultation to be made in their preſences, where there were divers Phyſicians and Surgeons: each man ſaid what ſeemed good unto him, and there was not one of them, who had not good hope of him, ſaying that the King would be cured, and I perſiſted always on the contrary.

Monſieur the Prince of the *Roch upon Yon* who loved me, withdrew me aſide, and ſaid I was only againſt the opinion of all the reſt, and prayed me not to be obſtinate againſt ſo many worthy men. I anſwered him, that when I ſaw any good ſigns of cure, I would change my advice. Divers conſultations were made, where I never changed my word, and prognoſtick, ſuch as I had made at the firſt dreſſing, and always ſaid that the arm would fall into a Gangrene, which it did, what diligence ſoever could be had to the contrary; and he gave up his ſoul to God the eighteenth day of his hurt, Monſieur the Prince *upon Yon*, having heard the death of the ſaid King, ſent his Phyſician and Surgeon toward me, named *Feure* now in ordinary to the King, and the Queen-Mother, to tell me, that he would have the bullet taken out, and that it ſhould be lookt for in what place ſoever it could be found: then I was very joyful, and told them that I was well aſſured to find it quickly, which I did in their preſences and divers Gentlemen. It was lodged in the very midſt of the cavity of the Adjutory bone. My ſaid Prince having it, ſhewed it to the King and Queen, who all ſaid my prognoſtick was found true. The body was laid to reſt in the Caſtle-Galliard, and I returned to *Paris*, where I found divers hurt men who were hurt at the breach of *Rowen*, and chiefly *Italians*, who deſired me very much to dreſs them, which I did willingly; there were divers that recovered, and others died. I believe (my little Maſter) you were called to dreſs ſome of them, for the great number there was of them.

The Voyage of the Battel of Dreux, 1592.

THe day after the battel was given at *Dreux*, the King commanded me, to go dreſs Monſieur the Count of *Eu*, who had been hurt with a Piſtol-ſhot in the right thigh, neer the joint of the hip; which fractured and broke the *Os femoris* in divers places, from whence divers accidents did ariſe, and then death, which was to my great grief. The day after my arrival I would go to the field, where the battel was given, to ſee the dead bodies: I ſaw a league about: all the earth covered, where there was by eſtimation five and twenty thouſand men and more. All which were diſpatched in the ſpace of two hours. I would (my little Maſter) for the love I bear you, that you had been there to recount it to your ſcholers, and to your children. Now in the mean time while I was at *Dreux* I viſited and dreſt a great number of Gentlemen and poor ſouldiers, and amongſt the reſt many *Swiſſer* Captains; I dreſſed fourteen in one chamber only, all hurt with Piſtol-ſhot and other inſtruments of diabolical fire, and not one of the fourteen died. Monſieur the Count of *Eu* being dead, I made no long tarrying at *Dreux*: there came Surgeons from *Paris* who perform-

ed

med well their duty towards the hurt people, as *Pigray*, *Cointeret*, *Hubert*, and others; and I returned to *Paris*, where I found divers Gentlemen wounded, who had retired themſelves thither after the Battle to be dreſſed of their hurts.

The Voyage of the Battle of Moncontour, 1596.

DUring the Battle of *Moncontour*, King *Charles* was at *Pleſſis* the *Tours*, where he heard they had won it; a great number of hurt Gentlemen and Souldiers withdrew themſelves into the City and Suburbs of *Tours*, to be dreſſed and helped, where the King and Queen-Mother commanded me to ſhew my duty with the other Surgeons, who were then in quarter, as *Pigray*, *du Blois*, *Portail*, and one named *Siret*, a Surgeon of *Tours*, a man very skilful in Surgery, and at that time Surgeon to the Kings Brother; and for the multitude of the wounded we were but little in repoſe, nor the Phyſicians likewiſe. Count *Mansfield* Governour of the Duchy of *Luxemburg*, Knight of the King of *Spains* Order, was greatly hurt in the battle, in the left arm, with a Piſtol-ſhot, which broke a great part of the joint of the elbow, and had retired himſelf to *Bourgueille* near *Towers*; being there, he ſent a Gentleman to the King, affectionately to beſeech him to ſend one of his Surgeons to help him in his hurt. Council was held what Surgeon ſhould be ſent. Mounſieur the Marſhal of *Montmorency* told the King and Queen, that it were beſt to ſend his chief Surgeon, and declared to him that the ſaid Lord *Mansfield* was one part of the cauſe of winning the Battle. The King ſaid flat he would not that I ſhould go, but would have me remain cloſe to him. Then the Queen-Mother ſaid, I ſhould but go and come, and that he muſt conſider it was a ſtrange Lord, who was come from the King of *Spains* ſide, to help and ſuccour him. And upon this he permitted me to go, provided that I ſhould return quickly. After this reſolution he ſent for me, and likewiſe the Queen-Mother, and commanded me to go find the ſaid Lord *Mansfield* in the place, where I was to ſerve him in all I could, for the cure of his hurt; I went and found him, having with me a Letter from their Majeſties: having ſeen it, he received me with a good will, and from thenceforth diſcharged three other Surgeons that dreſt him; which was to my great grief, becauſe his hurt ſeemed to me uncurable. Now at *Bourgueil* there were retired divers Gentlemen, who had been hurt at the ſaid Battle, knowing that Mounſieur *de Guiſe* was there, who had been alſo very much hurt with a Piſtol-ſhot through one leg, well aſſured that he would have good Surgeons to dreſs him, and alſo that he, being kind and liberal, would aſſiſt them with a great part of their neceſſaries. And for my part, I did help and aid them with all my Art, as much as it was poſſible; ſome died, ſome recovered, according to their hurts. The Count *Rhingrave* died, who had ſuch a ſhot into the ſhoulder, as the King of *Navar* before *Rouen*. Mounſieur *de Baſſompiere* Colonel of twelve hundred Horſe, was hurt alſo in ſuch a like place as Count *Mansfield*, whom I dreſt and God cured. God ſo bleſſed my work that within three Weeks I led him back to *Paris*, where I muſt as yet make ſome inciſions in the arm of the ſaid Lord *Mansfield*, to draw out the bones which were greatly broken and carieſed: he was cured by the grace of God, and gave me an honeſt reward, ſo that I was well contented with him, and he with me, as he hath ſince made it appear: He writ a Letter to the Duke of *Aſcot* how that he was cured of his hurt, and alſo Mounſieur *de Baſſompiere* of his, and divers others, which I had dreſt after the Battle of *Moncontour*, and counſelled him to beſeech the King of *France*, my good Maſter, to give me leave to go ſee Mounſieur the Marqueſs of *Auret* his Brother.

The Voyage of Flanders.

MOunſieur the Duke of *Aſcot* did not fail to ſend a Gentleman to the King with a Letter, humbly to beſeech him to do him ſo much good and honour, as to permit and command his chief Surgeon to come to ſee the Marqueſs of *Auret* his Brother, who had received a Muſket-ſhot near the Knee, with fracture of the bone, about ſeven moneths ſince, which the Phyſicians and Surgeons in theſe parts were much troubled to cure. The King ſent for me, and commanded me to go ſee the ſaid Lord *Auret*, and to help him in all that I could for the cure of his hurt; I told him I would imploy all that little knowledge which it hath pleaſed God to give me. I went then conducted by two Gentlemen of the Caſtle of *Auret*, which is a league and a half from *Mons* in *Hainault*, where the ſaid Marqueſs was: as ſoon as I arrived I viſited him, and told him the King had commanded me to come and ſee him, and to dreſs him of his hurt; he told me he was glad of my coming, and was much bound to the King to have done him the honour to have ſent me to him. I found him in a great Fever, his eyes very much ſunk, with a countenance gaſtly and yellow, his tongue drie and rough, and all the body emaciated and lean, his ſpeech low like that of a dying man: then I found his thigh much ſwelled, apoſtemated, ulcerated, and caſting out a green ſtinking matter; I ſearched it with a Probe, and by the ſame I found a cavity near the groin, ending in the middle of the thigh, and others about the knee, ſanious and cuniculous; alſo certain ſcales of bones, ſome ſeparated, others not. The legs were much tumified, and ſoked with a pituitous humour, cold, moiſt, and flatulent; in ſo much that the natural heat was in the way to be ſuffocated and extinguiſhed, and the ſaid leg crooked and extracted toward the buttocks, his rump ulcerated the bredth of the palm of an hand, and he ſaid he felt there a great pain and ſmarting, and likewiſe in his reins, in ſo much that he could not take any reſt night or day; neither had he any appetite to eat, but to drink enough: it was told me that he fell often into faintings and ſwoonings, and ſometimes as it were by an Epilepſie, and had oftentimes deſired to vomit, with ſuch a trembling that he could not carry his hands to his mouth. Seeing and conſidering all theſe great accidents, and the forces much abated; truly I was much grieved to have gone to him, becauſe me thought there was little appearance that he could eſcape. Notwithſtanding to give him good courage and good hope, I told him that I would quickly ſet him on foot by the grace of God, and the Phyſicians and Surgeons help. Having ſeen him, I went

a walking into a Garden, where I prayed to God that he would give me the grace to cure him, and that he would give a bleſſing to our Hands and Medicaments, to combat againſt ſo many complicated Maladies. I bethought in my mind the ways I muſt keep to do it. They called me to dinner, I entered into the Kitchin where I ſaw taken out of a great Pot, half a Mutton, a quarter of Veal, three great pieces of Beef, and two Pullets, and a great piece of Bacon, with great ſtore of good Herbs. Then I ſaid to my ſelf, this Broth was full of juice, and of good nouriſhment. After Dinner all the Phyſicians and Surgeons aſſembled, we entered into conference in the preſence of Mounſieur the Duke of *Aſcot*, and ſome Gentlemen that did accompany him; I began to tell the Surgeons that I marvelled much they had made no apertions in the Marqueſſes thigh, which was all apoſtumated, and the matter that iſſued out was foul and ſtinking, which ſhewed it had a long time lurked there, and that I found with my Probe a *Caries* in the bone, and ſmall ſcales which were already ſeparated; they made me anſwer, He would never give conſent, and likewiſe it was almoſt two Moneths ſince they could win him to put on clean Sheets on his bed, neither durſt any one ſcarce touch the Coverlet, he felt ſo great pain. Then ſaid I, for to cure him, we muſt touch other things than the Coverlet of the Bed. Each one ſaid what he thought beſt for the Lords grief, and for concluſion held it altogether deplorable. I told them there was yet ſome hope, becauſe of his youth, and that God and Nature do ſometime ſuch things which ſeem to Phyſicians and Chirurgeons impoſſible. My conſultation was, that all thoſe accidents were come by reaſon of the bullet hitting near the joint of the Knee, which had broken the ligaments, tendons, and *aponeuroſes* of the muſcles which tied the ſaid joint together with the *Os femoris*; alſo Nerves, Veins, and Arteries, from whence had followed pain, inflammation, apoſtume, and ulcer: and that we muſt begin the cure by the diſeaſe, which was the cauſe of all the ſaid accidents, that is to ſay, to make apertions, to give iſſue to the matter retained in the interſpaces of the Muſcles, and in the ſubſtance of them: Likewiſe to the bones which cauſed a great corruption in the whole thigh, from whence the vapours did ariſe and were carried to the heart, which cauſed the Syncope and the Fever, and the Fever an univerſal heat through the whole body; and by conſequent, depravation of the whole *Oeconomy*; Likewiſe that the ſaid vapours were communicated to the brain, which cauſed the Epilepſie and trembling, and to the Stomach diſdain and loathing, and hindered it from doing its functions, which are chiefly to concoct and digeſt the meat, and to convert it into *Chylus*; which not being concocted, they ingender crudities and obſtructions, which makes that the parts are not nouriſhed, and by conſequent the body dries, and grows lean, and becauſe alſo it did not do any exerciſe; for every part which hath not his motion remaineth languid and *atrophiated*, becauſe the heat and ſpirits are not ſent or drawn thither, from whence follows mortification. And to nouriſh and fatten the body, Frictions muſt be made univerſally through the whole body with warm linnen cloths above, below, and on the right ſide, and left, and round about; to the end to draw the bloud and ſpirits from within outward, and to reſolve any fuliginous vapours retained between the skin and the fleſh; thereby the parts ſhall be nouriſhed and reſtored, (as I have heretofore ſaid, in the Tenth Book treating of the Wounds of Gunſhot) and we muſt then ceaſe when we ſee heat and redneſs in the skin, for fear of reſolving that we have already drawn, and by conſequent make it become more lean. As for the ulcer which he hath upon his rump, which came through his too long lying upon it without being removed, which was the cauſe that the ſpirits could not flouriſh or ſhine in it, by the means of which there ſhould be inflammation, apoſteme, and then ulcer, yea with loſs of ſubſtance of the ſubject fleſh, with a very great pain, becauſe of the Nerves which are diſſeminated in this part: That we muſt likewiſe put him in another ſoft bed, and give him a clean Shirt and Sheets; otherwiſe all that we could do would ſerve for nothing, becauſe that thoſe excrements and vapours of the matter retained ſo long in his bed, are drawn in by the *Syſtole* and *Diaſtole* of the Arteries which are diſſeminated through the skin, and cauſe the ſpirits to change and acquire an ill quality and corruption which is ſeen in ſome that lie in a bed where one hath ſwet for the Pox, who will get the Pox by the putrid vapours which ſhall remain ſoaking in the Sheets and Coverlets. Now the cauſe why he could in no wiſe ſleep, and was as it were in a Conſumption, 'twas becauſe he ate little, and did not do any exerciſe, and becauſe he was grieved with extreme pain. For there is nothing that abateth ſo much the ſtrength as pain. The cauſe why his tongue was dry and foul, was through the vehemency of the heat of the Fever, by the vapors which aſcended through the whole body to the mouth. For as we ſay in a common Proverb, *When the Oven is well heat, the Throat feels it.* Having diſcourſed of the Cauſes and Accidents, I ſaid they muſt be cured by their Contraries, and firſt we muſt appeaſe the pain, making apertions in the thigh to evacuate the matter retained, not evacuating all at a time, for fear leſt by a ſudden great evacuation, there might happen a great decay of ſpirits which might much weaken the Patient and ſhorten his days. Secondly, to look to the great ſwelling and cold of his leg, fearing leſt it ſhould fall into a Gangrene and that actual heat muſt be applied unto him, becauſe the potential could not reduce the intemperature *De Potentia ad Actum*; for this cauſe hot Bricks muſt be applied round about, on which ſhould be caſt a decoction of Nerval Herbs boiled in Wine and Vinegar, then wrapt up in ſome Napkin, and to the feet an earthen Bottle filled with the ſaid decoction, ſtopt and wrapped up with ſome linen cloths; alſo that fomentations muſt be made upon the thigh, and the whole leg, of a decoction made of Sage, Roſemary, Tyme, Lavender, Flowers of Cammomile, Melilot, and Red Roſes boiled in White Wine, and a *Lixivium* made with Oak-aſhes, with a little Vinegar, and half an handful of Salt. This Decoction hath vertue to attenuate, inciſe, reſolve and drie the groſs viſcous humour. The ſaid Fomentations muſt be uſed a long while, to the end there may be a great reſolution; for being ſo done a long time together, more is reſolved than attracted, becauſe the humour contained in the part is liquified, the skin and the fleſh of the muſcles is rarified. Thirdly, that there muſt be applied upon the rump a great Plaſter made of the red deſic-

cative,

cative and *Unguentum Comitiſſæ*, of each equal parts incorporated together, to the end to appeaſe his pain, and drie up the ulcer, alſo to make him a little down-pillow which might bear his rump aloft without leaning upon it. Fourthly, to refreſh the heat of his Kidnies, one ſhould apply the Unguent called *Refrigerans Galeni* freſhly made, and upon the leaves of Water-Lillies. Then a Napkin dipt in *Oxycrate*, wrung and often renewed, and for the corroboration and ſtrengthening of his heart a refreſhing Medicin ſhould be applied, made with Oil of *Nenuphar*, and unguent of Roſes, and a little Saffron diſtilled in Roſe-Vinegar, and Treacle ſpread upon a piece of Scarlet, for the *Syncope* which proceeded from the debilitation of the natural ſtrength troubling the brain. Alſo he muſt uſe good nouriſhment full of juice, as Rere Eggs, Damask Prunes ſtewed in Wine and Sugar, alſo Panado made of the broth of the great Pot (of which I have already ſpoken) with the white fleſhy parts of Capons, and Partridge wings minced ſmall, and other roaſt-meat eaſie of digeſtion, as Veal, Goat, Pigeon, Partridge, and the like. The Sauce ſhould be Oranges, Verjuice, Sorrel, ſharp Pomgranats; and that he ſhould likewiſe eat of them boiled with good herbs, as Sorrel, Lettuce, Purſlain, Succory, Bugloſs, Marigolds, and other the like. At night he might uſe cleanſed Barley with the juice of Nenuphar and Sorrel, of each two ounces, with five or ſix grains of Opium, and of the Four cold Seeds bruiſed, of each half an ounce, which is a remedy nouriſhing and medicinal, which will provoke him to ſleep: that his bread ſhould be of Meſlin, neither too new nor too ſtale; and for the great pain of his head, his hair muſt be cut, and rub his head with *Oxyrrhodinum* luke-warm, and leave a double cloth wet therein upon it; likewiſe ſhould be made for him a frontal of Oil of Roſes, Nenuphar, Poppies, and a little Opium and Roſe Vinegar, and a little Camphire and to renew it ſometimes. Moreover one ſhould cauſe him to ſmell to the flowers of Henbane and Nenuphar bruiſed with Vinegar, Roſe Water, and a little Camphire wrapped in a Handkerchief, which ſhall be often and a long time held to his noſe, to the end that the ſmell may be communicated to the brain, and theſe things to be continued till that the great inflammation and pain be paſt, for fear of cooling the brain too much. Beſides, one may cauſe it to rain artificially, in pouring down from ſome high place into a Kettle, and that it may make ſuch a noiſe that the Patient may hear it; by theſe means ſleep ſhall be provoked on him. And as for the retraction of his leg that there was hope to dreſs it, when evacuation was made of the matter, and other humours contained in the thigh, which by their extention (made by repletion) have drawn back the leg, which might be remedied in rubbing the whole joint of the Knee with *Unguentum Dialthææ* and Oil of Lillies, and a little *Aquæ vitæ*, and upon it to be laid black Wool with the greaſe thereof. Likewiſe putting in the Ham a Feather pillow folded in double, and by little and little to make his leg to ſtretch out. All which my diſcourſe was approved of by the Phyſicians and Chirurgeons. The conſultation ended, we went to the ſick Patient, and I made him three apertions in his thigh, from whence iſſued out great quantity of matter and ſanies; and at the ſame time I drew out ſome ſcales of bones; nor would I let out too much abundance of the ſaid matter, for fear of too much decaying his ſtrength: Then two or three hours I cauſed a Bed to be made near his own, where there were clean white ſheets, then a ſtrong man lifted him into it, and he rejoiced much in that he was taken out of his foul ſtinking Bed. Soon after he demanded to ſleep, which he did almoſt four hours, where all the people of the houſe began to rejoice, chiefly Mounſieur the Duke of *Aſcot* his Brother.

The days following I made injections into the bottom of the cavities of the Ulcer, made with *Ægyptiacum* diſſolved ſometimes in *aquæ vitæ*, and ſometimes in Wine. I applied to mundifie and drie the ſpongy and looſe fleſh, bolſters; at the bottom of the ſinuoſities, hollow tents of lead, that the ſanies might have paſſage out; and upon it a great Emplaſter of *Diacalcitheos* diſſolved in Wine: likewiſe I did rowl it with ſuch dexterity, that he had no pain, which being appeaſed, the Fever began much to diminiſh. Then I made him drink Wine moderately allayed with Water, knowing that it reſtores and quickens the ſpirits: and all the things which were reſted on in the conſultation were accompliſhed, according to time and order; and his Pains and Fever ceaſed, he began to grow better, and diſcharged two of his Surgeons and one of his Phyſicians, ſo that we were but three with him. Now I remained there about two moneths, which was not without ſeeing divers ſick people, as well rich as poor, which came to me about three or four leagues about. They gave meat and drink to the needy, all which he recommended to me, and prayed me alſo for his ſake to help them. I proteſt I did not refuſe any one, and did to them what I poſſibly could, wherefore he was joyful. Then when I ſaw he began to mend, I told him he muſt have a Conſort of Violins and a Jeſter to make him merry, which he did: in one moneth we ſo wrought, that he could hold himſelf up in a Chair, and made himſelf to be carried and walk in his Garden, and at the Gate of his Caſtle to ſee the people paſs by. The Country people of two or three leagues about, knowing they could ſee him, came the Feaſt-day Male and Female, to ſing and dance pell mell, in joy of his amendment, all being very glad to ſee him, which was not done without good laughing and drinking. He cauſed ſtill a barrel of Beer to be given them, and they drank all merrily to his good health. And the Citizens of *Mons Hainault*, and other Gentlemen neighbors, came to ſee him in admiration, as a man coming from the Tomb. And as ſoon as he began to mend, he was not without company, and as one went out another came in to viſit him: his Table was always well covered. He was greatly loved of the Nobility and of the Common People, as well for his liberality, as for his beauty and honeſty, having a pleaſant look and a gracious ſpeech, in ſo much that thoſe that beheld his face were conſtrained to love him. The chief of the City of *Mons* came on Saturday to beſeech him to permit me to go to *Mons*, where they had a great deſire to feaſt and make me good cheer for his ſake. He told them he would pray me to go there, which he did. But I made him anſwer that they ſhould not do me ſuch honour, as alſo that they could not give me better cheer than I had with him. And he prayed me again affectionately to go thither, and that I ſhould do that for his ſake, to which I agreed. The day

after they fetcht me with two Coaches, and being arrived at *Mons* we found the dinner ready, and the chief of the City with their Wives, ſtaid for me with a good will. We went to the Table, and they placed me at the upper end, and drank all to me, and to the health of Mounſieur *D' Auret*, ſaying that he was very happy, and they likewiſe, to have obtained me to take him in hand, for that they knew that in this company he was greatly honoured and loved. After Dinner they led me back to the Caſtle of *Auret*, where Mounſieur the Marqueſs ſtaid for me with great expectation to recount unto him, what we had done in our Banquet. I told him that all the company had drank divers times to his health. In ſix weeks he began to uphold himſelf a little with Crutches, and grow very fat, and to get a lively natural colour. Now he had a deſire to go to *Beaumont*, which is the dwelling place of Mounſieur the Duke of *Aſcot*, and made himſelf be carried in a great chair with eight men by turns, and the Country-folks where we paſſed along, knowing 'twas Mounſieur the Marqueſs, fought and ſtrove together who ſhould carry him, and conſtrained us to drink, but it was but Beer, but I believe had it been Wine or Hippocras, they would have given it us with a very good will, ſo much did they ſhew themſelves joyful to ſee the ſaid Marqueſs, and prayed all to God for him. Being arrived at *Beaumont*, all the people came before us to do him reverence, and prayed God to bleſs him, and keep him in good health. We entered into the Caſtle, where there was more than fifty Gentlemen which the Duke of *Aſcot* had ſent for to come make good cheer with his Brother, who kept his Table furniſhed three days together: And after Dinner the Gentlemen ran at the Ring, played at Foils, and rejoiced to ſee Mounſieur *Auret*, becauſe they heard he would never come out of his Bed again, or be cured of his hurt. I was always at the upper end of the Table, where every one drank carouſes to him and me, thinking to make me foxt, which they could not do, for I drank but according to my old cuſtom. A few days after we returned back and took leave of Madam the Dutcheſs of *Aſcot*, who took a Diamond Ring from her finger, which ſhe gave me, acknowledging I had very well dreſt her Brother; which Diamond was better worth than fifty Crowns. Mounſieur *Auret* grew better and better, and walked all alone round about his Garden with Crutches. I begged leave of him divers times to come away to *Paris*, declaring that his Phyſician and Surgeon would well do the reſt that remained for the cure of his grief. And now to begin a little to eſtrange my ſelf from him, I prayed him to give me leave to go ſee the City of *Antwerp*, which he willingly accorded to: and commanded his Steward to conduct me thither accompanied with two Pages: we paſſed through *Malines* and *Bruxels*, where the chief of the City prayed the ſaid Steward that at our return they might hear of it, and they had a great deſire to feaſt me, as they of *Mons* had done. I thanked them moſt kindly, and told them that I was not worthy of ſuch honour. I was not two days and a half to ſee the City of *Antwerp*, where ſome Merchants knowing the Steward, prayed him to do them the honour, that they might beſtow a Dinner or Supper upon us. There was ſtriving who ſhould have us, and they were all very joyful to hear of the good health of the Marqueſs of *Auret*, doing me more honour than I expected. To conclude, we came back to the Marqueſs making good cheer, and within five or ſix days I asked my leave of him, which he granted with great grief, and gave me an honeſt Preſent, and of great value, and made me be conducted by the ſaid Maſter of his Houſe and two Pages, even to my houſe at *Paris*.

I have forgot to tell you that the *Spaniards* have ſince ruined and demoliſhed his Caſtle of *Auret*, ſackt, pillaged, rifled and burnt all the Houſes and Villages belonging unto him, becauſe he would not be of their ſide, in the ſlaughters and ruines of the Low-Countries.

The Voyage of Bourges, 1562.

THe King with his Camp remained not long at *Bourges*, but thoſe within yielded it up, and went out with their Jewels ſaved. I know nothing worthy of memory, but that a Boy of the Kings Privy Kitchin, who being near the Walls of the City before the Compoſition was made, cried with a loud voice, *Hugonot*, *Hugonot*, Shoot here, Shoot here, having his arms lifted up, and his hand ſtretched out, a Souldier ſhot his hand quite through with a bullet: having received his ſtroke, he came and found me out to dreſs him. My Lord High-Conſtable ſeeing the Boy to have his hand all bloudy, and all rent and torn, demanded of him who had hurt him. Then there was a Gentleman who ſaw the ſhot made, ſaid it was well beſtowed, becauſe he cried *Hugonot*, ſhoot here, ſhoot here. Then the ſaid Lord Conſtable ſaid, this *Hugonot* was a good Musketeer, and bare a pitiful mind; for it was very likely if he would have ſhot at his head, he might have done it more eaſily than in the hand. I dreſſed the ſaid Cook who was very ſick, but at length was cured, but with lameneſs of his hand, and ever after his Companions called him *Hugonot*.

The Battle of St. Dennis, 1567.

ANd as for the battle of Saint *Denis* there were divers ſlain as well on one ſide, as on the other: ours being hurt, went back to *Paris* to be dreſſed together with the Priſoners who were taken, whereof I dreſſed a great part. The King commanded me, by the requeſt of the Lady High-Conſtable, to go to her houſe to dreſs my Lord, who had received a Piſtol-ſhot in the middle of the ſpondyls of his back, whereby he preſently loſt all ſenſe and motion of thighs and legs, with retention of excrements, not being able to caſt out his Urin, nor any thing by the fundament, becauſe that the Spinal marrow, (from whence proceed the ſinews to give ſenſe and motion to the inferiour parts) was bruiſed, broken, and torn by the vehemence of the bullet. He likewiſe loſt his Reaſon and Underſtanding, and in a few days he died. The Surgeons of *Paris* were a long time troubled to dreſs the ſaid wounded people. I believe (my little Maſter) that you ſaw ſome of them. I beſeech the great God of Victories, that we may never be imploied in ſuch evil encounters and diſaſters.

The

The Voyage of Bayonne, 1564.

NOw I ſay moreover, what I did in the Voyage with the King to *Bayonne*, where we have been two years and more, to compaſs all this Kingdom, where in divers Cities and Villages I have been called into conſultations for divers diſeaſes with the deceaſed Mounſieur *Chaplain*, chief Phyſician to the King, and Mounſieur *Chaſtellon* chief to the Queen-Mother, a man of great honour and knowledge in Phyſick and Surgery: making this Voyage, I was always inquiſitive of the Surgeons if they had marked any rare thing of remark in their practice, to the end to learn ſome new thing. Being at *Bayonne*, there happened two things of remark for the young Chirurgeons: The firſt was, that I dreſt a *Spaniſh* Gentleman, who had a grievous great Impoſtume in his Throat: he came to have been touched by the deceaſed King *Charles* for the Evil. I made inciſion in his Apoſteme, where there was found great quantity of creeping Worms as big as the point of a Spindle, having a black head; and there was great quantity of rotten fleſh. Moreover there was under his Tongue an Impoſtume called *Ranula*, which hindered him to utter forth his words, and to eat and ſwallow his meat: he prayed me with his held up hands to open it for him, if it could be done without peril of his perſon; which I immediately did, and found under my Lancet a ſolid body, which was five ſtones, like thoſe which are drawn from the bladder. The greateſt was as big as an Almond and the other like little long Beans, which were five in number; in this apoſteme was contained a ſlimy humour of a yellow colour, which was more than four ſpoonfuls; I left him in the hands of a Surgeon of the City to finiſh his cure.

Mounſieur *de Fontain* Knight of the Kings Order, had a great continual peſtilent Fever accompanied with divers Carbuncles in divers parts of his body, who was two days without ceaſing to bleed at the noſe, nor could it be ſtanched; and by that means the Fever ceaſed with a very great ſweat, and ſoon after the Carbuncles ripened and were by me dreſſed, and by the grace of God, cured.

I have publiſhed this Apology to the end that each man may know with what foot I have always marched, and I think there is not any man ſo tickliſh, which taketh not in good part what I have ſaid, ſeeing my Diſcourſe is true, and that the effect ſheweth the thing to the eye, Reaſon being my Warrant againſt all Calumnies.

The End of the Apology and Voyages.

FINIS.

ΑΓΓΕΙΟΛΟΓΙΑ:
OR,
A DESCRIPTION OF THE VESSELS In the BODY of MAN:

Of the THREE KINDS; *i. e.*

OF THE

Veins, Arteries, and Nerves:

Especially of those in the LIMBS and HABIT of the *Body*.

Whereof there are also given

ANATOMICAL FIGURES,

The largest and fairest that ever were published with any *English* Book.

IN THREE TRACTATES.

Translated out of the ANATOMY of *ADRIANUS SPIGELIUS*, by whom these Parts are more largely and accurately described than by other Authors: the more full tractation whereof, being a part of *Anatomy* so useful in order to *Chirurgical Operations*, hath been judged very worthy to be annexed unto this present WORK.

LONDON,

Printed by *M. Clark* for *John Clark*, and are to be sold at *Mercers Chappel* at the Lower End of *Cheapside*. MDCLXXVIII.

THE
PREFACE.

OF how great consequence a more perfect knowledge of ANATOMY is to the Art of PHYSICK and CHIRURGERY, hath been frequently and abundantly made out by Anatomists, Physicians, and Chirurgeons, upon occasion, in their several Writings; though the thing it self speak so plainly in its own behalf, that much need not be said in this kind. The case is plain, that with the like facility and success may a Mariner, making out some Unknown Land, steer his course through the Main Ocean, where nothing but Sea and Skie appears, without the help of his Card and Compass, as a Physician judge of the Natural Action, or Preternatural Affect of any part of the Body: or a Chirurgeon institute any Operation about the same, without the Anatomical knowledge thereof: and therefore no more shall be said to this effect.

Anatomy may be very commodiously reduced to four distinct Kinds, or distinguished according to so many Principal Parts.

1. Σπλαγχνολογία, Splanchnologie, that is, the description of the Bowels contained in the three Cavities or Bellies of the Body, the lower, middle, and supreme.

2. Ὀστεολογία, Osteologie, which is the description of all the Bones of the Body.

3. Μυολογία, Myologie, being the Anatomical History of all the Muscles.

4. Ἀγγειολογία, Angeiologie, describing all the Vessels of the Body, i. e. the Veins, Arteries, and Nerves: these last though having no sensible Cavities, being reputed Vessels in the account of Anatomists.

Now though all these parts or kinds of Anatomy are needful both to Physick and Chirurgery, yet are they not all of a like necessity to both: but the first of more absolute necessity to the Art of Physick; the other three to Chirurgery. And therefore, though all four have been treated on by the learned Author of this Volume, yet in reason it could not but be advantagious and acceptable to Chirurgeons to have some further helps in our English Tongue, for improvement in the three latter kinds before-mentioned, or in some of them at least. Now for Osteologie, the parts themselves, or the dry bones are and may be kept at hand, for frequent view and contemplation upon them; whereby their several Figures, Articulations, and all other particulars observable about them, may be rendred familiar, in order to practice about Fractures and Luxations: and without such Autopsie, much cannot be acquired by the reading of Descriptions, or sight of Delineations. Toward Myologie there hath been a peculiar Tractate of late published in English, which may be useful in that respect to those who cannot peruse Latin Authors. So that the greatest want seemed to be in that kind or part of Anatomy, which is the last in the Enumeration, i. e. Angeiologie, or the Description of the Vessels; the more exact or particular knowledge whereof, especially of those in the habit of the body,

body, will appear, upon a true accompt, more neceſſary to the exerciſe of Chirurgical Operations, at greater certainty, and with more ſecurity, than the knowledge of the Muſcles. Upon theſe conſiderations, being conſulted by the Publiſher of this Work, what Piece or Tractate in any kind, of Chirurgery or Anatomy, I thought might to good purpoſe be added thereunto; I reſolved him that I could think of nothing more advantageous in this kind, than a fuller and more Anatomical Deſcription of the Veins, Arteries, *and* Nerves, *in the Body of Man, Tranſlated out of the* Anatomy *of* Spigelius; *adding alſo the moſt uſeful* Anatomical Figures *relating to the ſaid Deſcriptions, of the ſame largeneſs as they are in the Editions of the ſaid Author in* Folio; *which were firſt taken out of* Veſalius, *and are the largeſt and faireſt that are extant: the caſe being here, as in Mathematical Inſtruments, in which, how much the largeneſs conduceth to certainty in uſe, is well known. Accordingly he hath not ſpared for care and coſt, in procuring a Scholar every way competent to Tranſlate the Deſcriptions of theſe Parts out of the forementioned Author, and an able Artificer to Cut the Figures. And as the Work is now accompliſhed, I doubt not but good improvement may be made thereof by ſuch Chirurgeons, as being not able to make uſe of the Original, ſtand in need of ſuch helps, if they will not be wanting to themſelves for induſtry in the uſe hereof.*

J. G.

TRACT.

TRACT. I.
CONCERNING THE VEINS.

CHAP. I.

Reckons up the Branches or Propagations of the Vena Portæ *or the Gate-Vein, and explains an Aphoriſm of* Hippocrates, *that makes very much to the purpoſe.*

Note that the Letters, which are incloſed thus [ ] refer to the particular Tables at the end of that Treatiſe wherein they are ſet.

LEt us come now to the Hiſtory of the Veins, in which we will begin with the *Vena Portæ* or Gate-vein, as that which ſpreads not ſo wide and far as the *Cava* or hollow one. For it is wont to be diſtributed onely through the loweſt belly, and not at all to propagate it ſelf out of it; nor does it branch through all parts of that, but ſuch onely as are appropriated to the nutritive faculty, namely the Liver, the bladder of Gall, the Stomach, the Spleen, the Sweet-bread, Kall, Guts, and Meſentery; for the Hollow-vein ſends its propagations to the reſt, as the Reins, Bladder and thoſe parts which ſerve for generation. But that the manner of this diſtribution may be more eaſily underſtood, for our better method in Teaching, likening the whole Vein to a Tree, we will divide it into four parts, one of which we will call the *Roots*, as that part which is in the Liver; another the *Trunk*, which continues it ſelf on, and is not divided; a third the *Branches*, into which the Trunk is divided; a fourth, *Twigs* or *Surcles*, ſuch ſmall Veins as the Trunk ſhoots out at its ſides; before it be divided into its branches. Which terms ought diligently to be obſerved, becauſe we have endeavoured by the propriety of theſe words to give light to this obſcure Treatiſe concerning the Veins. But that they may more eaſily be committed to memory, and all that concerns this buſineſs be written with more brevity, following ſome very learned later Authors, we will give every part its name from the place of its inſertion.

Through what parts the Gate-vein is diſperſed.

The diviſion of the Gate-vein into the Roots, Trunks, Branches and Twigs.

From the outſide then of the Liver ſome very little hairy Veins are prolonged towards its inner Region, and by little and little meet together into greater branches, ſo that at length they become five, which again gathered together like roots about the middle of the hollow ſide of the Liver, but ſomewhat hinderly near to the back, make a notable ſtock or Trunk, which at length iſſuing forth near to thoſe eminencies of the Liver, which by the Greeks are termed Πύλαι Gates, is called the Gate-vein, and now deſerves the name of a Trunk.

The Roots.

This Trunk parting now from the Liver deſcends ſomewhat obliquely towards the left ſide, under the Gut called *Duodenum*, where above the Rack-bones it gets a firm ſeat; but before it be divided into branches, two twigs ſprout from it; the firſt of which being very ſmall, ariſing out of the uppermoſt and forepart of the Trunk, as ſoon as it is come forth from the Liver, is ſcattered into the neck and body of the bladder of Gall, or into its outer coat, with a numerous ſucceſſion of very little branches, ſuch as we have ſaid above are called hairy Veins. This twig is called in Greek Κυστικὸς, in Latin you may render it *Veſicalis*, the Vein of the bladder of Gall. *Veſalius* ſays there are two branches, which run through the bladder of Gall, whence they are called by ſome *Cyſticæ gemellæ*, the twin-veins of the Gall, but this makes no great matter. The ſecond twig being greater than the former, but lower, ariſing from the ſame fore-part, and more to the right, is inſerted into *Pylorus* or the lower mouth of the ſtomach, into whoſe hinder part which looks towards the back, it ſcatters many ſmall branches, from whence it is commonly called *Gaſtricus*, the ſtomach-branch, but perhaps for memories ſake it may be better termed *Pyloricus*, or branch of the lower mouth of the ſtomach, becauſe there are others alſo which are called Stomach-branches.

The Trunk.

The Twigs that grow out before the diviſion of the Trunk.

Cyſticus.

Gaſtricus.

Theſe two twigs being thus propagated, the Trunk runs downwards, and inclining all the way ſomewhat to the left, is divided into two notable branches, a right and a left one: the left is ſomething higher than the right, but leſſer; the right lower, but greater: the *left* ſpreads it ſelf through the Stomach, the Kall, one part of the *Colon* or Colick gut, and the Spleen; the *right* through the Guts and Meſentery; that is called *Splenica* or Spleen-vein, or the linear one; this the Meſenterick.

The two branches.

Splenica.

Now the Spleen-vein, after it is thus come forth from the Trunk, is carried athwart, being underpropt by the membrane of the Kall toward the Spleen, into which before it be conſumed, it ſhoots forth certain twigs, both from its upper part, and from its lower; from its upper part one, that aſcending obliquely to the left ſide of the Stomach that looks towards the back, is divided into three propagations, of which the outermoſt on either ſide are conveyed into the Stomach, and preſently ſcatter into more twigs; but the middle one aſcending through the ſame hinder part ſpreads it ſelf through the upper region of the Stomach, and compaſſes the left orifice or mouth round about like a crown, from whence it is called Στεφανικία or *Coronaria*, the Crown-vein of the Stomach. This again ſends forth continually ſome ſmall branches upwards to the end of the Gullet, and others downwards through the Stomach. All this branch is called *Gaſtricus*, the Stomach-branch, becauſe it is the greateſt, and moſt capacious of all thoſe, which come to the Stomach. From the lower part of the Spleen-branch ariſe two twigs; one, which is ſmall, ſending forth other little ſprigs to the right ſide of the lower membrane of the Kall, and the Colick Gut annexed thereunto, is commonly called *Epiploïs Dextra*, you may Latin it *Omentalis*, the right Kall-vein. Another anſwering to that branch, which ariſes from the higher part of the Spleen-vein, and begets the Crown-vein, is inſerted in the lower membrane of the Kall, and preſently after its riſe is divided into two branches, which parting one from another a great diſtance beget many

Circles riſing from the upper part of the Splenick-branch.

Coronaria.

Circles riſing from the lower part of the Splenick-branch.

Epiploïs dextra.

other

other twigs, which are ſpent upon the lower membrane of the Kall, which like a Meſentery ties the Colick Gut to the back, as alſo upon that part of the Colick Gut, which is ſo tied. It is cal-

Epiploïs poſtica. called *Epiploïs*, or *Omentalis poſtica*, the hinder Kall-vein. After the Spleen-branch has thus ſcat-

The diviſion of the Splenick branch. tered many twigs, now drawing near to the Spleen, it is cleft into two branches, an upper and a lower one; which are broken into others in the very *Parenchyma* or fleſh of the Spleen. From the upper, ſometimes before it enters the Spleen, ſometimes when it is already entered, there ſprouts

A propagation of the upper branch. forth a double or three-fold twig, very famous among the Writers of Phyſick, which they commonly call *Vas breve*, the ſhort Veſſel, but we the Venal, to diſtinguiſh it from the Arterial Veſſel that anſwers to it: this is inſerted into the left ſide of the bottom of the Stomach, ſometimes alſo higher and about the left orifice or mouth. Which is the cauſe why ſome Phyſicians, and commonly Anatomiſts too, have fooliſhly thought that the Melancholick humour is returned from the Spleen through this Veſſel back into the Stomach, to provoke appetite. But you may

A propagation of the lower branch. often find Bodies, in which it is altogether wanting. From the lower branch, which goes to the nether part of the Spleen, one propagation ariſes, which being pretty big, and notable, is reflected toward the right hand, like the fore-going, and compaſſes the bottom of the Stomach to the left ſide, and alſo ſends many little branches to the higher membrane of the Kall on the

Gaſtro-epiplois ſiniſtra. left ſide; it is called *Gaſtro-epiplois ſiniſtra*, the left Stomach and Kall-vein.

There is alſo another notable Branch, which is found in moſt to ariſe from the lower Spleen-branch, very ſeldom from the Spleen it ſelf. This is carried downwards, and ſcattering twigs over all the left ſide of the Colick Gut, goes on further by the whole length of the ſtrait Gut, and at length determines in the membranous ſubſtance thereof, and in the fundament with many little

Hæmorrhoidalis interna. twigs. Phyſicians make mention of this very often, and call it *Hæmorrhoidalis interna*, the inner Emroid Vein, to diſtinguiſh it from the outer, which is derived from the hollow Vein. It is truly and properly called the Emroid Vein; I ſay, properly and truly, becauſe ſometimes they call by that name the Veins of the Noſtrils, Gums, and Mouth, that caſt forth bloud, and without pain. In this large ſenſe the Philoſopher took it, 3. *De Part. Animal.* where he makes Menſtruous purgations

1. alſo a ſpecies of the Emroids. But the Emroids properly ſo called by Phyſicians, are dilatations of this Vein in the fundament, cauſed as well by black and yellow choler, as alſo by a ſalt flegm, as by the melancholick humour. And theſe are of two kinds; *Cæcæ*, blind Piles which caſt out no bloud,

2. but ſwell out like the ſtone of a Grape into the fundament, or out of it: Others *Apertæ*, open, which caſt out the bloud which they contain. The learned *Hippocrates* hath left us a peculiar Book, a golden one indeed, concerning the cure of theſe. The remaining part of the Spleen-branch is ſpent upon the whole Spleen, and therein is ſcattered into divers and very ſmall propagations, entering the very fleſh of it about the hollow and middle line. And theſe are the ſprigs which grow out of the Spleen-branch.

The Meſenterick Vein, or right branch of the Gate Vein is joined to the Meſentery, as ſoon as it comes from the back, and is divided into two chief branches, which paſſing through the Meſentery betwixt its two coats, are each of them cleft into an infinit number of ſmall branches, and they again into leſs twigs, which going to the Guts make up thoſe Veins ſo famous among Phy-

The right Meſenterick branch. ſicians, that are called the Meſaraick Veins. The firſt of theſe branches is called the right Meſenterick Vein from the right ſide, wherein it is placed, and is likewiſe two-fold; whence it came to paſs that *Veſalius*, and almoſt all others who follow him, reckon three Meſenterick Veins. This branch is inſerted into the *Jejunum* or empty Gut, the *Ileum* or Circle Gut, the *Cæcum* or blind Gut, and the right ſide of the Colick Gut, where it lies next to the Reins and Liver: and although both its branches ſhoot forth many propagations from themſelves, ſo that it is very hard to expreſs any number of them, as well becauſe they vary much by reaſon of their ſubjects, as alſo becauſe they do not obſerve the very ſame order and courſe, yet it hath been obſerved, that for the moſt part there are fourteen, which afterwards are ſcattered into an infinite company of other twigs. Theſe when they are come to the Guts, onely gape with their little mouths into their Coat, and enter not the cavity it ſelf, that being compaſſed about within with a certain cruſt. But as in moſt parts of our body, the divarications or diviſions of the Veſſels are attended with certain glandules, partly that they may make the ſafer progreſs, partly leſt they ſhould ſink down, and withall the flow and ebb of the bloud ſo very neceſſary be hindered; ſo here alſo the diviſions of the Veſſels, which are ſcattered through the Meſentery, are bolſtered up with certain glandules, which with their propagations obſerve ſuch an exact propagation, that the greater glandules do ſuſtain the greater branches, and the leſs the leſſer. When theſe Glandules ſwell with a *Scirrhus*, the Veſſels being preſt cloſe together, and the diſtribution of the *Chylus* through the Veins, and conſequently of the bloud through the body being hindered, there follows a Conſumption, and pining of the whole

The left Meſenterick. body. The left Meſenterick Vein is diſtributed into the middle part of the Meſentery, and alſo that part of the Colick Gut which runs from the left region of the Stomach as far as to the ſtrait Gut. The *Hæmorrhoidalis interna*, or inner Emroid Vein, of which we ſpake a little before, ſometimes ariſes from this Vein, as *Veſalius* hath obſerved, which affording ſome ſprigs to the Colick Gut, at laſt running forward through the whole length of the ſtrait Gut, determines in the fundament. But before the Meſenterick Trunk be divided into theſe two branches, it firſt ſends forth two

Propagations that ariſe before the diviſion of the Meſenterick. propagations, one of which is called *Gaſtro-epiplois dextra*, or the right Stomach and Kall Vein, which creeps through the right bottom of the Stomach, before and behind, as alſo through the upper membrane of the Kall: the other called by others *Inteſtinalis*, or the Gut Vein, by us the *Duodena*, reaches

Gaſtro-epiplois Dextra Inteſtinalis. to the middle of the Gut *Duodenum*, and the beginning of the Empty Gut or *Jejunum*, and deſcends all along through them.

The firſt uſe of the Gate Vein. The chief uſe of the Gate Vein is to nouriſh thoſe parts which are ſeated in the loweſt belly, and need a thicker and more fæculent bloud, ſuch as are all thoſe parts which ſerve for nutrition. For their bloud ought to be thicker, that it might be hotter, when heat is always more

powerful

powerful in a thicker body: ſo then the Roots of the Gate-vein nouriſh the Liver, the Trunk nouriſhes the *Pancreas* or Sweet-bread; of the Twigs, the *Cyſticus*, or Gall-twig nouriſhes the bladder of the Gall; the Spleen-branch, all the entrails which ſerve for nutrition, except the Meſentery, and the Guts; the Twig *Pyloricus*, or of the lower mouth of the Stomach, the *Gaſtricus* or Stomach-branch, both the Stomach and Kall-veins, and the ſhort veſſel nouriſh the Stomach. For I do not think that the ſhort veſſel was made by nature for the carrying back of melancholick humors to the Stomach, but chiefly for its nouriſhments ſake; when that blood which is generated in the Spleen, is not a melancholy and excrementitious humor, but rather the beſt, although ſomewhat thicker than other blood, and that becauſe the parts that are to be nouriſhed by the Spleen branch, needed a thicker bloud, then they which are to be nouriſhed by the Meſenterick. Both the Stomach and Kall-veins nouriſh the upper membrane of the Kall; the right and the hinder *Epiploïs*, or the Kall-veins, the lower. The Spleen is nouriſhed by thoſe two branches, into which the Spleen-vein is cleft, and which enter its *parenchyma*, or fleſh through its middle line: the Meſentery, and almoſt all the Guts by the two Meſenterick branches; the Gut *Duodenum* by the propagation called *Duodena*; but the empty Gut, the *Ileum* or circle Gut, the blind Gut, and the right ſide of the Colick or *Colon* by the right Meſenterick-branch. The left ſide of the Colick and all the ſtrait-Gut by the hæmorrhoidal vein; but the middle part which lies under the Stomach, by the hinder Kall-vein. The ſecond uſe is to attract the *Chylus*, and carry it to the Liver; whoſe veins are moſt famous for the making of bloud. But the ſame veins which nouriſh the Meſentery branch, do alſo attract the *Chylus*, as we ſhall ſhew you hereafter, when we ſhall inſiſt upon the Hiſtory of it. The third uſe is to empty out the excrements from the body through the Guts. Thus we ſee that the cholerick humour is ſometimes poured forth out of the Liver through the Meſenterick-branch in the bloody flux, and cholerick looſneſs, and the melancholick dregs through the Emroid-vein. The fourth uſe is to help the concoction of the Liver. Thus we ſee that the thicker part of the *Chylus*, which is called melancholy, is attracted by the ſplenick branch, not that the ſeat of melancholy is in the Spleen, but that it may be more attenuated, and better concocted by the benefit of the Arteries, which are moſt abounding in the Spleen, and ſo not diſturb, or hinder the concoction which is famed to be in the veins of the Liver, as it uſually happens, that whenſoever the Spleen is troubled with any diſeaſe, the work of making bloud is preſently harmed.

The ſecond uſe.

The third uſe.

The fourth.

But becauſe there has been mention made here of the Emroid veins, it ſeemed that it would not be unreaſonable if I did refer to this place the explanation of a moſt excellent Aphoriſm, which is the twelfth of the ſixth Section, when it cannot be underſtood without the Hiſtory of Anatomy, and is not ſo faithfully explained by others, as was neceſſary. *Hippocrates* writes in it, αἱμορῤῥοΐδας ἰσθέντι χρονίας ἢν μή μία φυλαχθῇ κίνδυνος ὕδρωπα ἐπιγενέσθαι ἢ φθίσιν, that is, he that is cured of old Emroids, unleſs one of them be preſerved, is in danger of falling into a Dropſie, or Conſumption. In explanation hereof we will firſt doubt of the Aphoriſm, then we will diſpute of the manner whereby a Dropſie, or Conſumption follows upon the Cure of old Emroids. But we may not without cauſe doubt of the truth of it, becauſe the ſame *Hippocrates* in a Book concerning the Emroids, which I think to be very much his own, whatſoever *Mercurialis* ſay, though otherwiſe a moſt learned man, bids us to burn the Emroids, and forbids us to leave any unburnt, but to burn them all. And truly *Aetius* in his 14. Book, deſirous to reconcile theſe two places, at thoſe words ἢν μὴ μία φυλαχθῇ, that is, unleſs one be preſerved, being overcome, thinks that a manner of diet is to be underſtood, not an Emroid, as if *Hippocrates* ſhould ſay: Thou ſhalt not cure one that hath long had the Emroids, unleſs the patient will diligenly obſerve a convenient manner of diet preſcribed by thee; for otherwiſe there is danger of his falling into a Dropſie or Conſumption. But *Galen* in his Comment upon that Aphoriſm writes expreſly, that *Hippocrates* ſays, that unleſs one Emroid be preſerved, ſuch danger will enſue, and makes no mention at all of diet. And what is more, daily experience ſufficiently witneſſes, that ſuch miſchiefs do enſue, though never ſo exact a diet be kept, and the reaſon taken from the manner, wherein they happen, and which we ſhall preſently explain, does abundantly manifeſt it. Whence it is evident, that theſe two places of *Hippocrates* are left ſtill in controverſie and contradicting one another from this anſwer of *Aetius*. But the right anſwer will be, if we ſay, that *Hippocrates* when he writes in his Book of the Emroids, that for a perfect cure they muſt all be burnt, ſpeaks not of old Emroids, but of ſuch only as are lately come, or when nature has already endeavoured to expel the humour, which was otherwiſe purged out of the Emroids ſome other way, whether it be by iſſues, or by a Fiſtula, or ſome ulcer in the Leg. For ſuch may be very well cured and without danger of Conſumption, or Dropſie, the rather, if the entrails be yet whole and ſound, and eſpecially if a good rule of diet follow. Nor does the cure of all old Emroids neceſſarily bring on a Dropſie or Conſumption, but only for the moſt part they threaten a danger of theſe diſeaſes to enſue; for ſometimes the melancholick matter being hurried up into the brains, there follows madneſs, as it happened to *Alcippus*, in *Hippocrates* 4. *Epidem.* For, ſays he, this *Alcippus* having the Emroids was forbidden to be cured, for after the cure he fell mad, but an acute Feaver following it, he was recovered. For explanation of the ſecond doubt, firſt let us hear *Galen*, for he in his Commentary upon the Aphoriſm, ſays, "That the Emroids came by reaſon of fæculent and melancholick bloud, which the Liver drives "down to the mouths of certain veins, and ſo this way being ſtopt, an abundance of groſs humors "burdens the Liver, and ſtifles the natural heat, which being extinguiſht, no more bloud is ge- "nerated, but onely water, which nature afterwards driving it into the *Abdomen*, or paunch, "makes a Dropſie. But if the Liver ſend that abundance of melancholick humour to the Lungs, "ſome veſſel being broken, there follows a Conſumption. This interpretation of *Galen*, beſides that it ſeems very obſcure to us, is not altogether agreeable to truth. For firſt, it is falſe in my judgment, which *Galen* ſets down in his Comment, that it is impoſſible, that the Emroids ſhould be

The explanation of a certain Aphoriſm of *Hippocrates*.

cauſed without an abundance of fæculent and thick blood; when it may be proved both by reaſons and authority, that they come alſo from choler and phlegm. By the Authority of *Hippocrates*, who in the beginning of his Book concerning the Emroids, witneſſes that this diſeaſe is cauſed in this manner; to wit, when choler, or phlegm falling down into the veins of the Strait-Gut, heats the blood, which is in the veins. For theſe veins being heated attract the blood out of the little veins that are near, and when they are filled, the inward part of the Seat ſwells, and the heads of the veins appear out of it. But by reaſon it is proved thus; when madneſſes are cauſed by phlegm, or choler, as *Hippocrates* witneſſeth in his Book *De Morbo Sacro*, the ſame Author in the 6. Aphoriſm, 21. profeſſes that that madneſs is taken away, if there follow ſwellings of the veins, or Emroids in thoſe that are ſo mad. Now the madneſs would not be taken away, if melancholick humors did only come forth by the Emroids; for then the cauſe of the diſeaſe would not be purged out. But I my ſelf alſo have ſeen formerly in *Germany* ſome Noblemen, that were troubled with ſalt catarrhs, afterwards recovered by a great flux of the Emroids; that I am of opinion, that not only melancholy, but alſo ſalt phlegm and choler are wont to be purged out by the Emroids. Wherefore if it happen, that one, who has been long troubled with the Emroids, be cured afterwards, that choler and phlegm, either breed obſtructions in the Liver, or Spleen, or being gathered together in ſome plenty by ſtretching the veſſels contained in the *Abdomen*, or paunch, breaks through them, or by their quality corrodes and eats their way out, and makes a Dropſie in the *Abdomen*; or elſe by raiſing obſtructions in the Liver, and extinguiſhing the natural heat, generates much water, and ſerous humour in ſtead of bloud, which paſſing through the veins, make a *ſpecies* of the Dropſie called *Leucophlegmatia*; but if the humor go back to the Breaſt, or Lungs, it breaks through, or eats out their veſſels, and hence follows a ſpitting firſt of blood, then of corrupt matter, and from thence at laſt a Conſumption, as *Hippocrates* teaches in his Aphoriſm. But in this place it is firſt of all to be obſerved, that there are two ſorts of propagations of veins, which make the Emroids: for there are ſome propagations of the Gate-vein, of which we have already treated; but there are others of the Hollow-vein, which ariſe from the Iliacal branches, of which we are to ſpeak hereafter. Now if the forementioned humors, whether melancholick, or cholerick, or phlegmatick and ſalt, flow through the propagations of the Gate-vein, the internal Emroids are cauſed, which being cured, the matters flow back into the branches of the Gate-vein, that are ſcattered through the lower Belly into which the veins being loden with theſe humors unburden themſelves, and make a *ſpecies* of the Dropſie called *Aſcites*. But if they flow through the Branches of the Hollow-vein, they cauſe the external Emroids, and theſe being cured againſt the Precept of *Hippocrates*, there is danger of a Conſumption to enſue, becauſe from hence there is an eaſie paſſage of the peccant matter through the Hollow-vein to the Lungs, nigh to the Heart. And this is that which we have of a good while obſerved, that many, who have been long troubled with Fiſtula's of the Fundament; and afterwards cured, through the ignorance of Phyſicians, have fallen into a ſpitting of blood, and then into a Conſumption. Nay, we remember, that a Maid was once cured by us in *Germany*, which had a Fiſtula in the middle of her Hip, and for three years had ſought help from many in vain, but being cured ſhe fell at length after three or four months into a ſpitting of much blood. Although ſhe was ſcarce ten years old, I let her bloud preſently in the foot on that ſide on which ſhe had been troubled with the Fiſtula, and purging her body, and laying on a cautery near the place, in which the Fiſtula had been, I eaſily freed her in this manner from imminent danger of a Conſumption. This ſpitting of blood happened from no other cauſe, but that ſharp and cholerick matter, which when it could no longer find a way out by the Fiſtula, got up afterwards to the Lungs through the branches of the Hollow-vein. But *Hippocrates* ſays expreſly that there is danger of a Dropſie, or Conſumption to follow, becauſe it ſometimes falls out, that neither of theſe happen, but rather ſome other diſeaſe inſues, as it happened to *Alcippus*, who fell into a madneſs, and from that into an acute Feaver: ſometimes alſo the bloudy flux follows, and others miſchiefs. Sometimes alſo it happens, that they who are ſo cured, are preſerved ſtill in health, by abundance of urine, ſweatings, remedies, and a good rule of diet.

CHAP. II.

Treats of the ſuperiour, or aſcendent Trunk of the Vena Cava, *or Hollow vein, and the branches which it ſcatters through the Head.*

The uſe of the Hollow-vein.

WE are now to conſider the other vein, which as we told you is called *Cava*, the Hollow one [a], which ſpreads it ſelf much wider than the Gate-vein, as being diſtributed throughout the whole body. For its office is to nouriſh all thoſe parts of our body, which conduce not to the concoction of the food, and thoſe parts being ſpread far and wide, it is neceſſary, that the Hollow vein alſo be very large, and extended to a great length: and becauſe they ought to be nouriſht with a thinner, and more elaborate blood, and not ſo thick and fæculent, as that wherewith the Stomack, Spleen, and Gall are nouriſht; therefore the bloud which the Hollow-vein makes, and carries, is alſo more pure, thin and ſincere.

The method to be obſerved in the Hiſtory of this vein.

In delivering the Hiſtory of this vein, although we are not of their opinion, who derive its beginning either from the liver, or heart, yet becauſe we muſt begin our Treatiſe of it ſomewhere, we thought fit to follow the received Cuſtom of Anatomiſts, and ſo for perſpicuities ſake, we ſhall always ſpeak of it, as if it took its birth from the Liver. It may be added, that it ſpreads certain roots as it were in the Liver, juſt like the Gate-vein, in the Hiſtory of which when for that reaſon we took our riſe from thoſe roots, we may not without cauſe begin thence alſo with the Hollow one. But this vein although it runs directly through the whole

whole Trunk of the body, and make one very notable ſtock [D] that is drawn out through the middle, and loweſt belly, like one ſtrait line continued, or rather in manner of a channel, or conduit pipe, is notwithſtanding wont to be divided into two by reaſon of the Liver, and ſoone to be called the Aſcendent Trunk, the other the Deſcendent. For indeed that is not true, to which many perſwade themſelves, that the Hollow-vein in its going forth from the Liver, like the great Artery, when it comes out of the Heart, is cleft into two Trunks; but if hereafter, they be called Trunks by me, you muſt believe, that I do it only for orders ſake in teaching. The Aſcendent therefore or upper Trunk [A D] is that which ſtands about the Liver, and is terminated about the *Jugulum*, or Hollow of the Neck; but that is called the Deſcendent, one [TV] which is beneath the Liver, and reaches down as far as the Legs. For both of them are afterwrds divided into two branches, of which they of the Aſcendent [m and q] are carried upwards to the head, as the Jugular or Neck-branches; or to the Arms, as the *Brachiales* [G and I] or Arm-veins; theſe of the Deſcendent Trunk to the Legs, and are called the Crural branches [T]. We will ſpeak therefore of all theſe in order, ſo that we firſt deliver the Hiſtory of the Aſcendent Trunk, then of its branches, that grows up partly to the Head, partly to the Arms, after that we will come to the deſcendent Trunk, and its branches, that are digeſted into the Legs.

The Aſcendent Trunk.

As therefore we have ſaid, that many little Veins like roots grow out of the Hollow ſide of the Liver, which always by degrees inſerted into the greater veins, and all of them at length meeting together about the middle of it did make a Trunk; ſo in the ſame manner out of the circuit of the Convex ſide of the Liver a numerous propagation of veins iſſues forth, which afterwards meet together in one Trunk. This Trunk makes its way through the nervous part of the midriff on its right ſide, and paſſing through it goes undivided to the *Jugulum*, or Hollow of the Neck, and becauſe it climbs upwards, it is commonly called the Aſcendent Trunk by them who conceive that the Hollow-vein riſes out of the Liver. It is much leſſer than the Deſcendent, becauſe the upper parts are nouriſhed by it alone; but almoſt all the inferiour parts, that are contained in the loweſt Belly, by the Gate-vein. But although it be not parted into any branches, until it come to the *Jugulum*; yet before that it ſpreads ſome propagations at its ſides, and of thoſe, three notable ones. The firſt [ee] is that which is called *Phrenica*, or the vein of the Midriff, on either ſide one, and is diſtributed throughout the whole Midriff, which is called φρένες, with a numerous iſſue, ſending little branches to the neighbouring *Pericardium*, or purſe of the Heart, and the *mediaſtinum*, or partition of the Cheſt; which when it has now got above, and entred the Cheſt, it inclines a little to the left hand, and enters the *Pericardium*, and being hidden very cloſe over againſt the eighth Rack-bone of the Cheſt, is very ſtrongly infixt into the right ventricle [C] of the heart; that *Ariſtotle* did not without cauſe gheſs, that it ſprung from hence. But before it be ſo infixed, it ſends out another propagation [bb] which is a notable one, and extends it ſelf by the hinder part of the Heart, and the left ſide of it, towards the forepart, compaſſing the *baſis* of the Heart like a Crown, from whence it is called *Coronaria*, or the Crown-vein of the Heart. This ſcatters many branches through all the outer ſurface of the Heart, but eſpecially through the left ſide, as that which needed a more copious aliment than the right ſide, becauſe of the continual, and greater motion there. But becauſe the fleſh of the Heart is hard, and ſolid, it ought therefore to be nouriſht with a thicker blood, from whence it is, that this branch grows out of the vein, before it enters the Heart, to wit, when the blood is ſomewhat thicker, and not yet attenuated in the cavities of the Heart. Near to the original of this there is a little valve, or floud-gate, which hinders the blood from flowing back to the Hollow-vein, as it might eaſily do by reaſon of the continual motion of the Heart. When the Hollow-vein has now gotten above the Heart, it becomes leſſer, and perforates again the *Pericardium*, and forſakes the Rack-bones of the Back, and being got above the Gullet, the rough Artery, and the *Aorta*, or great Artery, (which lean ſo upon one another, that the Gullet takes hold of the bodies of the Rack-bones, the rough Artery lies upon that, and the *Aorta* again upon this) it climbs upwards through the midſt of the diviſion of the Lungs, where the right part is ſeparated from the left. But becauſe by this means it could not get to the back, and the little branches, if it ſhould have ſent forth any ſuch, had been very liable to danger of breaking, being ſo hanged up; therefore it ſends forth a third propagation [cc] as ſoon as it is got out of the *Pericardium* or purſe of the Heart. The Greeks call this vein ἄζυγος, the Latins *ſine pari*, or *carens conjuge*, without a companion, or wanting a mate, becauſe in a man there is but one, and it has no companion, or mate on the left ſide, as other veins have; though in creatures that chew the cud, it is double, and plainly to be perceived on both ſides. But it iſſues forth about the fifth Rack-bone of the Cheſt out of the hinder part of the Hollow-vein, and the right ſide, and goes downwards, not directly, but inclining a little toward the right hand, is as it were reflected baekwards to the Back-bone: but as ſoon as it reaches the eighth, or ninth rib, it is cleft above the Spine of the Back into two branches, which running downwards paſs through the diviſion of the midriff, which is betwixt its two productions, and ſo are ſpread abroad into the loweſt Belly: Of theſe the left, which is ſometimes the greater, hiding it ſelf about the tranſverſe Proceſſes of the Rack-bones, and under the left production of the midriff and the original of the firſt bending Muſcle of the thigh, is inſerted into the left Emulgent, either near to its beginning, or (as it oft happens) into the middle of it. But the right, running on likewiſe under the membranes about the tranſverſe proceſſes of the right ſide, and the right production of the *Septum* or Midriff, and the beginning of the ſame firſt bender of the thigh, which keeps the right ſide, is implanted ſometimes into the very Trunk of the Hollow-vein, ſometimes into the firſt vein of the Loins. And we are indebted for this obſervation to the learned *Faliopius*, who would have the matter that is gathered together in the Cheſt, whether it be watery, or purulent and corrupt, or ſanguinous, to be evacuated by the benefit of the left branch

Propagations of the Aſcendent Trunk.

Phrenica.

Coronaria.

Ἄζυγος.

of this vein; of which notwithſtanding we will ſay ſomething briefly in the following Book. But this vein in its journey downwards ſhoots forth twigs on both ſides, as well right, as left, of which the right are more notable, and larger, of which there are numbred almoſt always ten; which run out to as many diſtances of the lower ribs, and make the inferiour intercoſtal veins. But I ſay they are almoſt always ten, becauſe it happens very ſeldom, that all the diſtances of the ribs receive branches from this vein, the two uppermoſt, to wit, the firſt and ſecond diſtance getting their ſurcles or twigs from the fourth branch, that is preſently to be mentioned. But theſe twigs run ſtraight forwards near to the lower ſide of the ribs, where there are cavities cut out for them, as we have taught in the ſecond Book. And truly this place is diligently to be taken notice of by Students in Chirurgery, becauſe of the opening of the Cheſt in the diſeaſe called *Empyema*, that they may know that inciſion is to be made in the uppermoſt place of the rib, becauſe in the lower the veſſels would be harmed to the great indangering of life. But theſe veins do not run through the whole length of the true ribs, but are terminated together with the bony part. But the propagations of the Mammary vein nouriſh the ſix diſtances betwen the griſtles of the ſeven true ribs, as we ſhall tell you by and by. Yet in the baſtard ribs they run even beyond the Griſtles towards the *Abdomen* or Paunch, into whoſe Muſcles they inſinuate themſelves. But there are certain other little branches propagated from the ſame vein, by which nouriſhment is derived to the marrow of the Rack-bones, and the Muſcles, to wit, thoſe about which they are carried: ſome alſo are implanted into the *Mediaſtinum* near to the back. This vein *ſine pari* without a companion, being thus conſtituted, the Hollow vein aſcends to the *Jugulum*, or Hollow of the Neck [D] being ſupported by the *Mediaſtinum*, and a certain ſoft and glandulous body, which the Greeks call θυμὸς, and is placed in the higheſt part of the Cheſt, to defend the divarications of the veins there hanging up from all danger of breaking.

The diviſion of the Hollow vein into the two Subclavian branches.

And here the Hollow-vein is firſt divided into two notable branches [EE] from which all thoſe veins ariſe, that run as well to the Head, as to the Arms, or to certain Muſcles of the *Abdomen*. Of theſe one goes to the right ſide, and the other to the left, which as long as they yet are in the Cheſt, are called *Subclavii*, Subclavian branches, becauſe they go under the *Claviculæ*, or Collar-bones; but as ſoon as they have gotten out of the Cheſt, and attain to the Arm-hole, they are named *Axillares*, the Axillary-veins [F]. From both of them very many propagations iſſue forth, ſome of which ariſe from their upper part, and ſome from their lower. In our reccital of them we will obſerve this order, that they which are neareſt to the Trunk, ſhall be firſt mentioned by us; and they laſt, which are fartheſt from it.

Propagations from the lower part of the Subclavian branches.

Intercoſtalis ſuperior.

The firſt propagation then iſſues out near the very root of the divarication or diviſion of the Trunk, and is called *Intercoſtalis ſuperior*, the upper intercoſtal-vein; [e] there is on either ſide one, which being very little, and deſcending along by the roots of the ribs, as far as to the third rib, ſends two twigs [ff] overthwart, like the *vena ſine pari*, to the two diſtances of the upper ribs. But if the *vena ſine pari* ſend its propagations to all the diſtances (as it ſometimes happens) then it is wanting not without cauſe. Sometimes the ſame vein ariſes from the Trunk of the Hollow-vein, before its diviſion into the Subclavian branches.

Mammaria.

Another vein [g] ſometimes ariſes from the forepart of the Bifurcation; ſometimes from the root of the Subclavian-branch, and is double, on either ſide one: ſometimes alſo only one grows out of the middle of the Trunk, before it be divided; which at length, when it has attained unto the Breaſt-bone, is parted into a right, and a left branch. For Nature is wont to ſport, as ſometimes in its other works, ſo eſpecially in the riſe of veins, ſo that they are not ſpread in all bodies after the ſame manner. But this is called *Mammaria*, the Mammary-vein, which, whenſoever it ariſes, going toward the fore-part; ſtrives to get up to the higher part of the Breſt-bone, and deſcends by the ſide of it, and when it comes to the Breaſt-blade, about its ſides goes out of the Cheſt, and runs on directly under the right Muſcles of the *Abdomen*, even to the Navil, near to which it is joined by Anaſtomoſis, or Inoculation [10] with an Epigaſtrick-vein [9] that aſcends and meets it; by the benefit whereof ariſes that notable ſympathy betwixt the womb and Breaſts of women, of which we ſhall ſpeak more hereafter in the eighth Chapter, when we ſhall inſiſt on that Hiſtory of the Epigaſtrick-vein. But before it leave the Cheſt, in its deſcent, it diſtributes one branch apiece to the ſix diſtances betwixt the Griſtles of the ſeven upper true ribs, of either ſide, which are terminated with the Griſtles near to the end of the bony part of the ribs, in which place we told you that the branches of vein *ſine pari*, (with the extremities of which theſe are joined) were ended. From theſe veins, which are diſtributed in this manner to the diſtances of the Griſtles, ſome others very worthy of our notice do ariſe, which are diſſeminated both in the Muſcles that lie upon the Breaſt, and into the Paps. Near to theſe a third [h] ariſes, and ſometimes alſo grows out of the Trunk, which is called *Mediaſtina*, becauſe it ſpreads it ſelf into the *Mediaſtinum*, or membrane that cloſes up the cavity of the Cheſt, being extended all along by it, with the left Nerve of the Midriff. The fourth [i] commonly called *Cervicalis*, ot the Neck-vein, is a large vein on both ſides, which running obliquely, upward, and backward, to the Tranſverſe Proceſſes of the Rack-bones of the Neck, and climbing up through their holes, (from whence perhaps it might be better named *Vertebralis*) affords ſprigs to the Muſcles that lie next upon the Rack-bones. When this vein has got above the Tranſverſe Proceſs of the ſeven Rack-bones, it derives a Notable branch to the *Sinus* or *Canale*; in the Neck, through the hole that is made for the outlet of the Nerves; and then another, when it comes above the Proceſs of the ſixth ſpondyl, or Rack-bone, and again another, when it has left the fifth Spondyl until at laſt it comes to the Proceſs of the firſt Rack-bone, which notwithſtanding it does not touch, much leſs does it paſs into the Skull, (as *Veſalius* would have it) near which it goes partly to the ſame *ſinus* or *canale*, partly it is diſtributed into the hinder part of the Neck. For there are two long *ſinus* filled with blood, which are made out of the hard membrane of the Brain, one on each ſide, being

Mediaſtina.

Cervicalis.

be ing placed at the ſides of the marrow of the Neck. From theſe little branches are diſtributed, which nouriſh the marrow of the Back-bone, and the neighbouring parts; they being about the Juncture of the head with the firſt Rack-bone, and end near to the ſeventh Rack-bone of the Neck. Theſe two *ſinus*, of which one is of the right, another on the left ſide, have ſome communion betwixt themſelves by a little pipe, and that a ſhort one, which is derived overthwart from the one to the other, for the moſt part about that region of the Neck, which is betwixt the ſecond and third Rack-bones. At laſt there is a fifth vein [l] which ariſes from the hinder part, called *Muſcula inferior*, or the lower Muſcle-vein, which is diſtributed in many branches to the Muſcles in the lower part of the Neck, (and ſo extending the Head and Neck, from whence the vein might be rightlier called *Cervicalis*, or the Neck-vein) and alſo to thoſe in the higher part of the Cheſt near to the Rack-bones.

Propagations that ariſe from the upper part of the Subclavian branches.

For the upper part of the Subclavian branches, whilſt the Hollow-vein is yet in the Cheſt, three propagations iſſue forth; two of which do very well deſerve to be noted, which take their way upward, under the Muſcles that bend the Head. The former of the two looks more inward, and is called *Jugularis interna*, the inner Jugular-vein: the other inclines to the outer parts, and is commonly called *Jugularis externa*, the outer Jugular-vein. For both of them ariſe near to the *Jugulum*, or Hollow of the Neck, and aſcend by that to the Head. The inner is greater, and the outer is leſs in a man, but in brutes it is contrary. But when almoſt all Appellations are derived, and that beſt, not from the place, through which the veins paſs, but from their inſertion, perhaps they might be rightlier named *Cephalicæ* or *Capitales*, Head-veins. The inner Jugular-vein [m] takes its original near to the joint, by which the Clavicles or Patel-bones are tied to the Cheſt, and as ſoon as it ariſes, it is joined with the *arteria Carotis*, or ſleepy Artery, and a Nerve of the ſixth pair, as companions in its journey, at the ſide of the rough Artery, and climbing to the Chops, about the middle of the way is parted into two branches, of which one is called the outer, the other the inner branch. The outer is ſo called, becauſe it comes not into the inner parts of the Head, but being divided into two at the corner of the lower Jaw, diſtributes one branch to the Chops, and the other near to the Ears and Face. The inner branch, all the way is joined to the *Arteria Carotis*, or ſleepy Artery, even to the baſis of the Skull, whither when it is arrived on the backſide, it is likewiſe cleft into two branches, but of unequal bigneſs. For the firſt [n] is greater and more hinderly, being carried backward obliquely, which having propagated ſome twigs to the Muſcles under the Gullet, and in the forepart of the Rack-bones of the Neck, through the ſecond hole of the *Occipitium* or Nowl-bone enters the Skull with the leſſer branch of the *Arteria Carotis*, through which ſaid hole the ſixth pair of the Nerves deſcends: and thus this branch enters the firſt [1] and ſecond [2] *ſinus* of the thick membrane. The ſecond branch [p] being ſmaller, and more to the forepart, quite forſaking the *Arteria Carotis*, or ſleepy Artery, goes to the forepart of the Head, and after that by the way it has beſtowed a Surcle not very notable upon the Organ of hearing, it enters the Skull through the ſeventh hole of the Wedg-bone, or *Os cuneiforme*. This is diſperſed through the *baſis*, and ſides of the thick membrane, with a numerous iſſue of branches, the prints whereof are obſerved in the inner ſurface of the bones of the forepart of the Head, as we have ſaid above in the ſecond Book. We will call theſe two branches, becauſe they go to the brain, *Encephalici*, as if you ſhould ſay *Cerebrales*, of the Brain, and that ſhall be the greater *Encephalicus*, this the leſſer. The external Jugular-vein [q] aſcending under the skin, and the *Muſculus Quadratus*, or ſquare Muſcle, that draws down the Cheeks, by the ſides of the Neck, when it comes to the Ear, is cleft into two branches [r] one of which I call *Profundus*, the deep one, becauſe it enters the Muſcles, and retires into the more inward parts, the other *Cutaneus* the skin-branch. The deep or inner one [s] in its firſt divarications meets with Glandules about the Chops, and ſends forth propagations worthy of our notice to the *Larynx* or Throttle, and the Glandules that grow to it, as alſo to the Muſcles of the Chops, and of the bones called *hyoides*, among that which creeps all along under the tongue, is a notable one, and is ſcattered into many little branches, which are ſeen, if the tongue be liſt up, even before diſſection. From this deep branch three other ariſe, which enter into the inner parts of the Head and the Skull. The firſt, after it has ſpread little branches into the Chops, and Mouth, and enters the Skull, through the firſt hole of the Temple-bone. The next [c] paſſes out of the fore part of the eye through the ſecond hole of the Wedg-bone, at which the ſecond pair of Nerves get out, and runs with ſome Surcles through the thicker Membrane upwards. The third is ſcattered out of the bredth of the Noſtrils through the hole of the *Os cribroſum*, or ſive-bone into the ſame Membrane. Theſe two nouriſh this forepart, to which the third *ſinus* reaches not, but ends near to the partition of the Mamillary Proceſſes. But the outer or Skin-branch [u] creeping by the skin of the Head, and ſtayed up with the Glandules under the Ear, which they call *Parotides*, is divided into two branches; of which the Anteriour [x] is carried upward obliquely through the Cheeks to the inner corner of the Eye, diſtributing little branches by the way to the Noſe; and going on to the Eye-brow, is joined with the remainder of the branch of the other ſide, and makes the ſtrait vein, which they call *vena frontis*, the Fore-head vein, [y] and which in madneſs is opened to very great advantage. To this the *Satyriſt* alludes, when ſpeaking of a certain fooliſh fellow, he ſays, — *Mediam pertundite venam.*

Jugularis Externa. *Profundus.* *Cutanea.*

Three branches entring the skull.

The other or Poſteriour branch is carried behind, and ſends branches to the Temples [z] and skin of the Back-part [α] of the Head. A third vein which ariſes out of the upper part of the Subclavian branches, is commonly called *Muſcula ſuperior*, the upper Muſcle-vein, in relation to another of the ſame name ariſing out of the lower part. It iſſues out near to the external Jugular-vein, and is diſperſed into the Muſcles, and skin of the back-ſide of the Neck, in regard whereof we ſhall not do amiſs to call it *Cervicalis ſuperior*, or the higher Neck-vein [6]. But now let us return to the diſtribution of the Subcla-

Muſcula ſuperior.

vian vein, from which we have digreſt. This vein, as ſoon as it gets out of the cavity of the Cheſt is called *Axillaris* [F], and when it comes to the Arm-pit, is divided into two notable branches, called *Cephalica* or Head-vein [G] and *Baſilica* [I], which are afterward diſſeminated throughout the whole Arm. But before the Axillary-vein be thus divided, it ſends forth two twigs: the firſt [γ] is called *Scapularis interna* the inner Blade-vein, and is diſtributed through the Muſcles on the inſide of the Shoulder-blade: the other [δ] is named *Scapularis externa*, or the outer blade-vein, it is a pretty big one, and is implanted into the muſcles of the outer, and gibbous part of the ſame Shoulder-blade. But the vein *Baſilica* alſo, before it enters the Arm, ſhoots out two propagations; one called *Thoracica ſuperior*, or the upper Cheſt-vein [ε] becauſe it ariſes out of a higher part than the following, it is a very notable one, and runs through the inſide of the pectoral Muſcle that brings the Arm forward to the Breſt; it diſtributes branches alſo to the other Muſcles of the Breſt, as alſo to the skin of the Dugs in women. The other is called *Thoracica inferior*, the lower Cheſt-vein [ζ], a great and notable one likewiſe, which deſcending along the ſide of the ſide of the Cheſt is diſtributed eſpe- through the third broad Muſcle or *Latiſſimus* that moves the Arm backward ſcattering many little branches from it ſelf, which afterwards are joined by *Anaſtomoſis* or inoculation, with the branches of the vein *ſine pari*, that fall out of the Cheſt. And this vein ſometimes grows out of the former, or the upper Cheſt-vein. Theſe branches being thus diſtributed, the Axillary-vein reaches into the Arm.

The Diviſion of the Axillary vein into two branches.

Its propagations before its diviſion.

Scapularis interna.

Externa.

Thoracica ſuperior.

Thoracica inferior.

CHAP. III.

Shews how the Axillary-vein is diſtributed through the Arm.

THE Axillary-vein [F] therefore is cleft into two branches, as ſoon as it comes near to the Arm, but thoſe branches are of different bigneſs. For the upper [G] which they call *Cephalicus*, the Head-branch, is ſmaller; but the lower vein [I] called *Baſilica*, is almoſt thrice greater, The Cephalick alſo is as it were wholly juſt under the skin, and ſinks not with above one branch into the deeper retreats of the Muſcles; wherefore it has neither Artery, nor nerves for its companions, they being addicted to the more inward rooms of the body. But the Baſilick vein partly creeps on under the skin, partly hides it ſelf under the Muſcles, and therefore it ought with good reaſon to exceed the other in bigneſs, as being deſtined for the nouriſhment of more parts. It hath both Nerves and Arteries as companions in its journey, which is the cauſe why upon the cutting of this vein the blood ſpins out with a force; but of the contrary, the Cephalica being cut, it comes forth ſoftly: which we ſee ſome Phyſicians unskilful in diſſections, ſtanding by whilſt the vein is opened, fooliſhly refer to the ſtrength, or weakneſs of the mind or body. We are now to ſpeak briefly of the manner of the diſtribution of both theſe veins through the Arm, beginning from the upper, as the leſſer branch.

The diviſion of the Axillary vein.

The *Cephalica* [G] therefore is called by *Vſalius Humeraria*, or the vein of the Arm, becauſe by the Arm it deſcends into the Hand; by others *Cubiti exterior*, the outer vein of the cubit, from its ſituation, becauſe it runs on the outſide of the Cubit, as the *Baſilica* contrariwiſe doth on the inſide. By ſome later writers it is commonly called *Cephalica*, the Head-vein, becauſe it is wont to be opened in diſeaſes of the Head, through the error of the Antients, who thought ignorantly that it ariſes from the external Jugular vein, and therefore empties the blood immediately immediately out of the Head. But it ariſes from the upper part of the Axillary vein, and climbing over the Tendon of the *Serratus minor*, or leſſer Saw-Muſcle, that bends the ſhoulder blade forward to the Breſt, it runs betwixt the Muſcle called *Deltoides*, which lifts up the Arm, and the beginning of the Pectoral Muſcle, which brings it forward to the Breaſt, where it ariſes from the Clavicle or Collar-bone, and ſo it runs down by the Arm to the outſide of the firſt Muſcle that bends to the Cubit, which they call *Biceps*, or the double-headed Muſcle; by reaſon whereof the more learned Chirurgeons have wiſely uſed to make iſſues betwixt the Muſcles *Biceps* and *Deltoides*; for iſſues ought always to be made at the ſeat of ſome notable vein, that the matter may more eaſily be voided out. But although this vein be not divided into branches, whilſt it is thus carried down by the upper part of the Arm, yet it ſcatters ſome twigs [u and e] of both ſides into the aforeſaid Muſcles, and the skin. At length when it is come to the Cubit, it runs under the fleſhy membrane, as a vein under the skin ſhould, and preſents it ſelf to the ſigt without diſſection. But about the very joint of the Cubit at the exernal protuberation of the Arm, *it* is wont to be divided [H] for the moſt part into three branches, an outer, an inner and a middle one. The two former run under the skin, the third deeper. The firſt or middle one, [i] which is often wanting, is very little, and deeper, and penetrates into into the ſubſtance of the Muſcles, eſpecially of thoſe two that bend the ſecond, and third joint of the finger, as alſo of the long *ſupinator* of the *Radius*, or wand of the Arm. The ſecond [x] and inner, and chief of the three branches is carried down obliquely under the skin, and joins with the inner branch of the *Baſilica*, three fingers below the joint of the Cubit, with which it makes up the vein that Phyſicians call *Mediana*, the middle vein [ʌ]. This running down obliquely by the middle Region of the Cubit, diſtributes many Surcles to the *Radius* or wand, and at length it ſelf is divided into two leſſer branches; of which the outer [ρ] goes to the inſide of the wriſt, toward the thumb: the other and inner [o] runs to the fore, and middle fingers. The outer of theſe is called by ſome *Cephalica manus*, and is opened to very good purpoſe in the diſeaſes of the Head or Teeth. Now the third branch [ ] or outer Cephalick-vein climbs up to the Muſcle called the long *ſupinator* Cubit, and in that ſame place is joined with a little branch [τ] of the Baſilick-vein; being united thereto it goes on to the outſide of the wriſt; and diſtributes veins to that part of the Hand, which of the *Radius*, or wand, diſperſing divers little veins into the skin, and ſo is carried obliquely [ ] through the *Radius*, or wand, and having attained to the middle of its length enters the outſide of the lies before the little, and Ring-fingers, as alſo to the fingers themſelves. This vein, eſpecially that which

Three branches of the Cephalick-vein.

Salvatella.

which reſpects the little finger, is commonly called *Salvatella*, and the Secti on of it is much commended by Practitioners in Phyſick in melancholy diſeaſes. Which being ſometime s called in queſtion, and I having obſerved that experience does favour thoſe Practitioners, endeavoured to find out the cauſe, and found that there are many inoculations here of this vein with the Arteries, as the inoculations are uſually more frequent about the extreme parts, as being more removed from the fountain of heat, and therefore wanting a hotter and more ſpirited blood. This vein therefore being cut, becauſe the inoculations are ſo near, it cannot be but that the blood of the Arteries ſhould be alſo let out, which cannot be ſo well done by opening the veins of the Cubit, becauſe the *Anaſtomoſes* or Inoculations are ſomewhat more diſtant from the place, in which the vein is opened. And hence it is, that the blood which is emptied out of the Hand, is much fairer and redder than that out of the Arm, becauſe the Arterious blood there always runs out together with that of the veins. But there being ſix times more Arteries then there are veins in the Spleen, it is neceſſary, that its diſeaſes be much helped, when the peccant blood is drawn out of thoſe veſſels wherein it was.

The baſilick vein.

The other branch of the Axillary-vein, that is the inner, and greater, is the *Baſilica* [I] which according to its ſituation in different arms hath found different names among writers practiſed in Phyſick. For in the right arm it is called *Hepatica* or the liver-vein; but in the left *Splenica*, or the ſpleen-vein. They chooſe that to be opened in diſeaſes of the liver, this in diſeaſes of the ſpleen. But it iſſues forth under the armpit, and diſperſing many propagations of the Glandules, that are frequent thereabout, it is carried down by the upper part of the Arm to the ſide of the double headed Muſcle, or *Biceps*, between the Muſcles that bend and ſtretch out the Cubit, and not far from its egreſs out of the Cheſt, is divided [K] into two notable branches, of which one is called *Profundus* or deep, the other *Subcutaneus*, or branch under the skin, from their ſite and progreſs. The deep one or *Profundus* [L], which for the moſt part is the thicker, all the way it goes, penetrates into the more inward parts of the Arm; having the Axillary Artery, that runs into the Arm every where for its companion, as alſo the fourth branch of the third Nerve of the Arm. But it is carried betwixt the two Muſcles, which bend the Cubit, and having paſt its joint, is cleft [M] into two branches; of which the outer [N] near to the *radius* or wand, (from whence it might be called *Radicus*) goes down to the Hand, and ſcatters little branches toward the Thumb or Fore-finger, as alſo the middle one; but the inner branch [O] paſſing near to the bone of the Cubit, (from whence it deſerves the name of *Cubitens*) diſtributes ſmall branches to the middle, and little fingers; but as the outer ſends its propagations to the Muſcles on the outſide of the Hand; ſo the inner to thoſe on the inſide. The other is the branch *Subcutaneus*, or under the skin [P] which is carried down by the inſide of the Arm, ſcattering divers iittle branches to the skin, and parts adjacent, but when it is come to the inner protuberation of the Arm, it is divided [Q] into an outer, and inner branch, like as the Cephalick is. The inner [R] is carried down obliquely; beneath the bow of the Arm, and being united with the inner branch [ϰ] of the Cephalick, makes the vein called *Mediana*, [λ] of which we ſpake before. But the outer [S] near to the inner protuberation of the Arm being divided into two branches, is carried by the greater along the Region of the *ulna* or ell downward to the wriſt, and ſcatters it ſelf into the little Finger, but by the other it is derived to the inſide of the Hand.

The branches of the baſilick vein.

Profundus.

Subcutaneus.

Its diviſion into an outer and an inner branch.

But in this place it is worth our pains to advertiſe with other the moſt learned Anatomiſts; that it ought not to be believed, that the ſame order and courſe of veins i s to be found in all men; when the diſſection of the bodies does demonſtrate, that ſcarce two in a thouſand do accurately obſerve the ſame diſtribution of the veins. Wherefore we ought not to be ſo ſcrupulous in chooſing out places for the opening of the veins, as ſome that are unexperienced, are wont; but to chooſe that vein eſpecially, which may be moſt ſafely opened becauſe it is beſt ſeen. For ſometimes the Cephalick or Head-vein is ſo ſmall, that it can hardly be diſcerned; and ſometimes on the contrary the Baſilick is ſo. Wherefore he ſhall do beſt, who will rather follow wiſe counſel, than the ſcrupulous opinion of unskilful men.

CHAP. IV.

Explains the lower, or deſcendent Trunk of the Hollow-vein.

The inferiour Trunk of the Hollow vein.

WE have done with the upper Trunk, and branches of the Hollow-vein; it remains now that we treat alſo of the lower. Nevertheleſs (as we have above alſo admoniſht) they are not indeed two Trunks, as *Galen* would have them, but one only, which reaches in one continued line from its diviſion about the fifth Back-bone of the Loins [V] as far as to the *Jugulum*, or hollow of the Neck [D]: but, for methods ſake in teaching, we thus divide it by reaſon of the Liver, which ſtanding as it were in the middle of it, ſeems to part it into an upper and a lower Trunk. As therefore that is the upper one [AD] which runs up from the Liver to the Hollow of the Neck; ſo that is the lower [TV] which beginning at the ſame Liver, is terminated at the *Os ſacrum*, or Holy-bone. And as the upper did run on undivided through the Cheſt, ſcattering only ſome propagations at its ſides; ſo the lower alſo ſlides down, intire through the whole *Abdomen*, or paunch, only ſome twigs ſprouting from it. But when it has attained to the fifth Back-bone of the Loins, it is cleft into thoſe two notable branches called *Iliaci* [XX] as the upper is into the Subclavian, which Iliacal branches afterward reaching into the Legs make the Crural-veins; as the Subclavian carried into the Arms make the *Brachiales*, or Arm-veins. Let us ſpeak therefore in this Chapter of the Trunk, and its propagations, as long as it yet is in the lower belly. Then let us come to the crural branches.

Four propagations ariſing from the Trunk before its diviſion.

For the deſcendent Trunk then [TV] before it part into the branches, ariſe four veins. For as ſoon as it is come forth from the hinder part of the Liver, it declines to the right ſide of the Back, and

Adipoſa.

and ſends forth a propagation from its own left ſide which they call *Adipoſa ſiniſtra*, the left fatty vein [on the left ſide] becauſe it paſſes to the fat and outer membrane of the Kidneys, which ariſes from the *Peritoneum* or Rim of the Belly, as alſo to the Glandule that grows above the Kidneys. There is another [♃ on the right ſide] anſwering to this on the left ſide, but which does very ſeldom grow out of the Trunk, but rather from the upper ſide of the middle part of the Emulgent vein; and becauſe it is diſtributed in the ſame manner as the left is, it is called *Adipoſa dextra*, the right Fatty vein. Yet ſometimes you may ſee the contrary alſo to happen, and this right vein to come forth of the Trunk, and the left out of the Emulgent. For there are divers ſportings of nature to be ſeen in the veins; and you cannot eaſily meet with a dead body in which you may not find ſomething new, and differing from others. After this the Hollow-vein paſſing on, when it comes beyond the middle of the back, about the firſt Rack-bone of the Loins, it brings forth a ſecond pair of veins, [♀] very notable, which haſtens directly to the Kidneys, upon whoſe ſubſtance it is wholly ſpent. And hence it is called *Renale*, the pair of Kidney-veins from its inſertion; but from its uſe *Emulgentis.* *Emulgens*, becauſe the Kidneys ſeem by this pair to milk out the whey or ſerous moiſture in the blood, and to draw it to themſelves. It is therefore very thick, but yet ſhort, and not of equal length, nor riſing directly oppoſite each to his fellow. It is ſhort, becauſe it did not need length, which for the moſt part is given by nature to veſſels for ſome previous preparation. It is unequal, becauſe it was fitting the left ſhould be longer than the right, by reaſon that it was neceſſary to bring the ſpermatical vein out of it. But the beginning of both anſwers not directly one to another, leſt one ſhould be hindered by the action of the other. And the left is higher than the right, becauſe the left Kidney is alſo ſeated higher than the right. But the Emulgent branches, as ſoon as they ariſe out of the Trunk, do not preſently go to the cavity of the Kidneys, but are firſt divided into two greater branches, and ſo accompanied with Arteries, enter the concavous ſide of the Kidneys, and afterward being broken into leſſer branches are ſcattered quite through the whole ſubſtance of the Kidneys, and at laſt determine with their ſmall hairy ends in certain fleſhy proceſſes, which they call *Mammillares*. Theſe veins do ſerve not only for the bringing of nouriſhment to the Kidneys, but alſo for the carrying down of the ſerous moiſture to thoſe fleſhy Proceſſes called *Mammillares*, through which it is ſtrained into the Pipes of the Ureters, and then gathered together into that cavity of theirs called the *Pelvis*, and ſo drops down by little into the bladder, as we ſhall ſhew, when we open the hiſtory of the Kidneys. And here the place is to be noted, in which the

The place in which the ſtones of the Kidneys are bred.

ſtones of the Kidneys are wont to be generated, which is not in the Emulgent veſſels, I mean veins, or Artery; but rather in the very cavity of the Kidneys, or in the *Pelvis* and pipes of the Ureters. For in theſe if a viſcous matter be at any time received, either it is hardened there by reaſon of a notable heat, or elſe through cold is congealed into gravel or ſtone. For this matter is not only a crude and uncocted kind of blood, which like a mucous matter ſometimes is wont to abound in the maſs of bloud, but oftentimes alſo that excrementitious phlegm which falls down from the head, through the veins and Arteries, both into the Hollow-vein and the great Artery, and ſometimes into the Stomach and Guts. Of which this ſeems to be a manifeſt ſign, that they who are ſubject to diſeaſes of the Stome, are very often troubled with reums and pains of the Colick; of which whilſt ſome perſwade themſelves that it is cauſed by wind, daily experience hath taught me, that it comes from phlegm; becauſe I have obſerved, that they who are troubled with the ſtone in the Kidneys, had their *Colon* or Colick-gut always ſtuft with plenty of this phlegm, and that this being taken away, the Stone has been no longer bred. And therefore oft times I give ſcouring Clyſters, and ſuch as gently purge phlegm, not only to ſuch as have the Stone already, but alſo to ſuch as are threatned with the breeding of it, with a great deal of benefit to the Patients. but all thoſe things are perpetually to be avoided, which drive out the ſtones, as well becauſe moſt of that nature are hot, as alſo becauſe they are able to drive down the crude matter plentifully to the Kidneys. We thought fit therefore to inſiſt upon this, that we may accommodate the ſtudy of Anatomy to the very practice of Phyſick; eſpecially ſeeing that the place wherein the ſtone is bred, is not commonly known, becauſe the moſt famed *Fernelius*, whom the greateſt number of Phyſicians does for the moſt part follow, *Lib. 6. Pathолog. c.* 12, thinks that ſmall gravel is bred in the proper ſubſtance of the Kidneys, and waſhed from thence by the flowing of the Urine and carried into the cavity, and ſo the Urine full of gravel ſlides down through the Ureters into the Bladder. But if

Why the left Kidney is more ſubject to the ſtone, than the right.

any one enquire alſo the cauſe, why the left Kidney is more ſubject to the Stone than the right; we muſt conclude that this happens, becauſe the Colick-gut lies more upon the left Kidney, in whoſe cells this phlegm, of which we ſpake, abounding, either it ſweats through the pores, and is ſuckt into the Kidneys, or elſe by reaſon of its nearneſs, the Kidneys are exceedingly cooled; experience having often taught us, that this kind of phlegmatick matter is indeed actually exceeding cold in the as they have ſufficiently perceived, who have voided it in great plenty by ſtool. After this there

Spermatica.

follows a third part [♈ and ♄] called *ſpermaticæ*, or *ſeminales*, the ſpermatical, or ſeed veins, becauſe they carry down matter for making of the ſeed. Theſe differ in their original. For the left [♄] ariſes from the inſide, and middle part of the Emulgent, and communicating ſome ſurcles to that part of the *Peritoneum*, or rim of the belly, which covers the Muſcles that lie in the Loins, it goes faſt by the ſaid *Peritoneum*, and deſcends obliquely; but when it has attained to the *Os pubis*, or the Share-bone, riding over it, it paſſes through the *Peritoneum*, and holes of the oblique and tranſverſe Muſcles of the *Abdomen*, with whoſe proceſſes being ſuſtained it is contorted into certain varicous circlings which are joined with the ſpermatical Artery by *Anaſtomoſes* or Inoculations, and at length it ends in the Teſticle of its own ſide. But the right ſpermatical vein [♈] ariſes not out of the Emulgent, but the Trunk it ſelf, and the forepart of it, a little beneath the Emulgent-vein, and afterwards obſerves a like courſe with the former. And thus they are in males, though we may obſerve nature oftentimes varying in them: but in Women, although they ariſe in the ſame manner, and obſerve the ſame courſe with thoſe in Men, as far as the Holy-bone; yet they fall not out of the *Peritoneum*,

nor

nor reach into the ſhare-bones, but before they come to the Teſticles, are cleft into two unequal branches; the leſſer of which is ſcattered into the ſides of the womb, toward the bottom of it; the greater being joined to the ſpermatical Artery, and inoculated with it, enters into the Teſticle on its own ſide. Laſt of all the fourth pair is called [X] *Lumbares*, the Loin veins [4 4 4] two, or three which the Hollow-vein ſends forth from its back-ſide, which looks towards the bodies of the Rack-bones of the Loins; and therefore they are not to be ſeen, unleſs the Trunk of the Hollow-vein be lifted up. Theſe veins go in through the holes of the Rack-bones, through which the Nerves go out, and ſo carry nouriſhment to the ſpinal Marrow. From them two other veins, tyed on both ſides to the ſide of the Marrow, aſcend toward the brain, with which afterward two veins deſcending from the internal Jugular, are joined by an *Anaſtomoſis* or Inoculation. *Lumbares.*

Theſe propagations being thus ſent out, when the Hollow-vein has almoſt attained to the *Sacrum*, or Holy-bone, about the fifth Rack-bone of the Loins, it inclines under the great Artery, and is cut into two notable branches called *Iliaci*, [XX] which having gone a little way are again cleft into two others [Y and Z] of unequal bigneſs, of which one is called the inner, the other the outer. The inner is leſs, the outer larger and greater. But before they be ſo divided, they ſcatter two other propagations, the firſt of which [5] is commonly called *Muſcula ſuperior*, the upper Muſcle-vein, which is diſſeminated overthwart, through the Muſcles of the Loins, and *Abdomen* or paunch, from whence I would call it *Muſcula lumbalis*, the Muſcle-vein of the Loins: the other [6] is named *Sacra*, or the Holy-vein, becauſe it reaches ſome little twigs to the upper holes of the Holy-bone, for the nouriſhing of the ſaid bone and the ſpinal Marrow. The diviſion of the Trunk into the two Iliacal branches. *Muſcula ſuperior.* *Sacra.*

But from both the Iliacal branches many veins iſſue, before they go out of the *Peritoneum* or Rim of the Belly toward the Legs; and from the inner branch two. The firſt [7] ariſes from the out-ſide called *Muſcula media*, the middle Muſcle-vein; becauſe it is ſcattered into all the Muſcles of the Buttocks, and into their skin: For it carries aliment to all thoſe Muſcles, which are of the out-ſide, or Back of the bone *Ilium*, Hanch-bone, as alſo to the very joint of the Hip, and that for this cauſe it ought to be eſpecially taken notice of by them who would ſomewhat curiouſly conſider the cauſe of the ach in the Hip, or the *Sciatica*. I ſhould think that this vein may not be amiſs called *Clunæa* from its inſertion, becauſe it is implanted into the Muſcles called *Clunæi*, or Muſcles of the Buttocks. The other [8] grows out of the inſide, and is a notable vein, called *Hypogaſtrica*, or the vein of the water-courſe, from its diſtribution into almoſt all the parts of the *Hypogaſtrium*, or water-courſe. From this iſſues a branch named *Hæmorrhoidalis externa*, the outer Emroid-vein, becauſe if at any time it ſwells with a more fæculent bloud, or hot, or ſalt, it makes the outward Emroids of the Fundament. This affords twigs to the holes of the *Os ſacrum*, or Holy-bone, but beſtows greater branches upon the Muſcles of the *Rectum inteſtinum*, or the ſtrait Gut, as far as to the outer skin of the Fundament. There is alſo another branch ariſing from the ſame Hypogaſtrick-vein, which we call *Cyſticus*, the Bladder-branch, and is worthy of obſervation both in men and women; in men, becauſe it is ſpent upon the Bladder; but in women, becauſe in them being ſuſtained with a fat membrane, it goes with ſome twigs to the Bladder; but with more to the bottom of the Womb; and with more manifeſt ones to the Neck of it, by which veins alone ſome think that the monthly courſes flow in Virgins, and ſome alſo think the ſame in Women. But the monthly courſes do not only flow out by theſe branches, but by thoſe alſo which we told you were ſent from the ſpermatical branch, and which go to the bottom of the womb, not to the Neck. For the menſtruous blood is uſually purged out, whether in Virgins or women, every month; not only through the Neck, but eſpecially through thoſe paſſages of the Womb, called *Cotyledons*. Which we have ſhewn here at *Padua*, publickly in the Theater, the firſt year of our being Profeſſor, in the carkaſs of a certain Woman having her monthly courſes. For we ſaw that the Hypogaſtrick branches, and the ſpermatick veſſels with the Teſticles were filled with bloud, and that the Womb it ſelf did pour out a thicker blood, the little mouths of the veins in the inner part of the Womb lying open, and manifeſtly gaping. Yet I ſaw twice in others, that the menſtruous blood came out of the veins of the Neck only, not alſo out of the womb, and in another on the contrary that it flowed out of the Womb only. But the ordinary way is for women to be purged at them both, and not at one only, except when beſides the intent of nature obſtructions do ſeem to hinder their flowing. Propagations of the inner Iliacal branch. *Clunæi.* *Hypogaſtrica.* *Hæmorrhoidalis externa.* *Cyſticus.*

But we have obſerved, and ſeen divers times, whileſt we were about the cure of Ulcers in the privy members, and the neck of the Womb, that at what time the monthly courſes do flow, the mouth of the Womb gapes. I ſaw alſo then, that thoſe parts were dilated with a certain ſtinking moiſture, and that the neck of the Womb appeared much larger than it was wont to be at other times. And therefore no man need to wonder at that, which hath been obſerved by ſome Writers of our age, that in the time of their courſes theſe parts have been ſo widened in ſome, that being new married, although they were true Virgins, they have for this reaſon been accuſed, and thought to have been defloured. Wherefore if it happen, that any who are new married, doubt of their Wives virginity, becauſe they find the privy paſſage very wide, it will behove them to conſider, whether their flowers were not at that time upon them. Now at length the remainder of the inner Iliacal Trunk makes to the Share-bone, and taking to it a propagation of the outer Iliacal, together with which it makes one vein, and ſo paſſing through the *Peritoneum*, and hole of the Share-bone, it ſpreads it ſelf into the leg, and is extended almoſt beyond the middle of the Thigh on the inſide.

From the outer branch in like manner ſome veins iſſue: and firſt of all, that which is called *Epigaſtrica*, or vein of the lower Belly [9] which ariſes from the higher part of the branch, and is ſo named, becauſe it goes to the Muſcles of the *Epigaſtrium*, to wit, the rich Muſcles of the *Abdomen*. For paſſing with its chief branch out of the *Peritoneum* or Rim of the Belly, it climbs ſtrait up on both ſides under the right Muſcle, till it come near to the Navel, where it is joined by *Anaſtomoſis* with the deſcending Mammary-veins. But this *Anaſtomoſis* or inoculation is ſeldom found in men, but Propagations of the outer Iliacal branch. *Epigaſtrica.*

but in women it is very conſpicuous, from whence alſo *Galen Lib. de Diſſect. Ven. & Arter. Cap.* 8. witneſſeth, that great ſympathy betwixt the womb and the Breſts or Dugs is cauſed by theſe two veſſels. But the moſt learned *Hippocrates* has explained this ſympathy in many Aphoriſms of the fifth Section. For in the fiftieth Aphoriſm he ſays, If you would ſtop the courſes in a woman, apply a very great Cupping-glaſs to her Breaſts. And in the thirty ſeventh; If the Breſts of a great bellied woman, do of a ſuddain become ſmall, the child proves Abortive. And in the thirty eighth; if one of the breaſts of a great bellied woman become ſmall, one of the Twins, that ſhe goes with, proves Abortive; and that a Male, if the right Breaſt be ſmall; a Female, if the left; ſo the womb being diſeaſed, the Nipples become pale; and upon a Dropſie in the Womb they ſwell up. But there is a ſympathy alſo not only by reaſon of the veins, but alſo of the Nerves, that come from the ſixth conjugation. Whence we ſee, that if the Breſts of a Woman, or Virgin be handled, they are provoked to luſt; ſo that for this reaſon alſo thoſe Women, that have great Breaſts may be accounted more luſtful, as *Afra* is in *Martial.* But it is convenient to note concerning the original of this Vein, that very often it ariſes out of the Crural branch, which we ſhall by and by deſcribe,

Pudenda. but oftner out of the Iliacal. Another vein is the *Pudenda* [11] which ariſes from the inſide of the outer Iliacal branch, after it is come out of the *Peritoneum*, or Rim of the Belly, and it is called *Pudenda*, becauſe it is ſpent upon the privities of both Sexes. For in men it is diſtributed into the *Scrotum* or Cod, and into the skin of the Yard; but in women it is propagated to the Lips and skin of the privy paſſage, to the *Nympha* or wings, and other parts of it; but in both men and women to the Glandules, that lie about the leskes, whence ariſes that conflux of matter into theſe

Muſcula inferior. Glandules, in a peſtilent or venereous *Bubo.* Laſtly, the *Muſcula inferior*, or lower Muſcle-vein [12] is that which goes to the joint of the Hip, and is diſſeminated into the skin and muſcles thereabout, by reaſon whereof in my judgment by a ſtricter Appellation it might be better called *Coxendica*, or *Coxalis*, the Hip-vein.

CHAP. V.

Reckons up the propagations, and branches of the outer Iliacal branch diſſeminated through the Crus, *or great foot, that reaches from the lower part of the Buttocks to the end of the Toes.*

THe outer branch then of the Iliacal veins [Z] when it hath ſent forth the ſaid propagations, falls out of the Rim of the Belly, and is carried to the *Inguina* or leskes through the upper and inner region of the Hip-bone, through which the firſt and ſecond bending Muſcles of the Thigh do deſcend, and makes the Crural-vein [L]. The Hiſtory whereof that we may

The diviſion. of the Crural vein into a Trunk and branches. deliver in an eaſie method, we will divide it into Trunk, and Branches. But before the Trunk be cleft into its branches, it ſhoots out four propagations; the firſt of which is that they call *Saphena*, [13] and vein of the inner Ankle, becauſe it runs near thereunto; it is alſo commonly called by Phyſicians *vena tali*, but improperly, as we have ſaid above in our firſt Book. But it ariſes

Four propagations of the Trunk before its diviſion. from the inner ſide of the Trunk, preſently after its departure out of the *Peritoneum*, or Rim of the Belly, and having no Artery for its companion, runs ſtrait downwards under the skin, through the inſides of the Thigh and Leg; and when it is now come to the inner Ankle, it ſpreads it ſelf

Saphena. into the upper part of the Foot, and ſcatters a branch overthwart, from which afterward many

Four propagations of the vein *Saphena.* others ariſe, that are diſtributed in their order to every one of the Toes. This vein ſcatters other propagations by the way, but which are ſeldom found anſwerable one to another, either in number, or bigneſs, as we have already more than once intimated, that nature is found to ſport in the veins, but eſpecially in thoſe of the joints. the firſt [17] of theſe propagations, not far from the original of the vein it ſelf, is dealt into the upper skin of the inner Region of the Thigh, in two branches; of which the outer, which is the thicker, creeps through the fore, and outſide of the Thigh, under the skin; but the inner goes more inwardly, and ſpreads it ſelf into the rim of the Belly. The ſecond [18] is propagated, when the vein has now attained to the middle of the Thigh. The third propagation [19] ariſes about the knee, and brings forth two off-ſprings, one which is diſſeminated into the skin of the forepart of the Knee, by the *Patella* or Whirl-bone, but the other into the skin of the Back-ſide, where the bending of Ham is, about which it is rowled orbicularly. The fourth [20] is carried to the middle of the *Tibia* or Leg, with ſurcles forward, and backward, over againſt the *Saphena*, another vein [14] is brought forth from the outſide of the Trunk, but ſhorter than the vein *Saphena* is, and reaches outward, and overthwart into the skin, that covers the forepart of the Hip-bone, as alſo into the Muſcles of the ſame place which the

Iſchia. later Anatomiſts call *Iſchia.* Theſe propagations being brought forth, the Trunk afterward is drencht into the Muſcles that compaſs the bone of the Thigh, and ſets out a third propagation [15]

Muſcula. which they call *Muſcula* the Muſcle-vein; and there uſe to be two of them. For the outer, which is the leſs, ſends ſhoots to the ſecond, and fourth, extending Muſcles of the *Tibia* or Leg, together with the skin; the inner, and greater, affords twigs to the third extender of the Leg, and to almoſt all the Muſcles about the Thigh. After this the Trunk turning to the Backſide, and deſcending by degrees, ſcatters ſome other twigs into the membranes of the Muſcles, and by and by

Poplitæa. ſends out a fourth vein, which runs into the backſide of the Thigh, and is called *Poplitea*, the Ham-vein [16] much ſpoken of by writers of Phyſick, but eſpecially by *Hippocrates* the chief of them, who *6. Epidem.* 1. 5. commends much the opening of it in diſeaſes of the Kidneys. But it is oftentimes ſeated too deep to be cut without very great difficulty. I have learnt by frequent experience, that iſſues made in the *Sura* or calf of the Leg, to which this vein ſpreads it ſelf, have done a great deal of good in many diſeaſes. This vein, when it is propagated, ſometimes receives the addition of a Sprig from the inner branch of the Muſcle-vein; oftentimes alſo two propagations iſſue from the Trunk, one higher, and another lower, which afterward are united in their journey.

But

But preſently after it's riſen it ſcatters ſome branches into the skin of the Thigh, about the higher and hinder part of it; then it runs down directly through the middle of the Ham, or bending of the Leg, into the Calf, to which it diſtributes many Surcles, that run on with an uncertain courſe, ſome directly, ſome overthwart, ſome obliquely. Theſe little branches being thus diſſeminated, the vein paſſes on as far as to the *Talus*, or Cockall-bone, and there at length determines.

And this is the progreſs of the Crural-Trunk, and theſe the propagations which it ſcatters, before it be divided. For lying upon the bone of the Thigh, it ſo deſcends, and runs ſide-long near to it, that when it has attained to the Knee, it is carried betwixt the two loweſt, and hindmoſt head of the Thigh, in which place [Δ] it is cleft aſunder into two branches, an outer, and an inner one. But they are of unequal bigneſs, the outer being the ſmaller, and the inner the greater, but both of them [ΘΛ] are ſcattered through the Leg, and loweſt part of the Foot. The inner [Θ] in its deſcent ſends ſome propagations of the Muſcles that are placed on the backſide of the Leg, and eſpecially thoſe which make the Calf, but moſt of all to the inner part [21] of the *Gaſterocnemius externus*, or outward Calf-muſcle, and ſo afterward continuing its courſe downward, when it is come to the lower *Appendix* of the *Tibia* or Leg, and has beſtowed ſome ſhoots upon the skin, it is reflected under the inner Ancle [22] and runs out as far as to the great Toe. The outer [Λ] is preſently cleft into two leſſer branches, that are likewiſe unequal, of which the inner [Ξ] that is the greater, and lies deep, is wholly ſpent upon the Muſcles of the Calf, running all along directly betwixt the two heads of the *Gaſterocnemius externus*, or firſt moving Muſcle of the Foot, as alſo betwixt the *Gaſterocnemius internus*, or inward Calf-Muſcle, and the *Tibiæus anticus* or forward Leg-Muſcle, and at laſt betwixt the Muſcles that bend the Toes, diſtributing ſome ſurcles every where by the way to the Muſcles, through which it paſſes. When it comes to the mid-length of the Leg, it is again ſubdivided into an inner, and an outer branch. The inner of theſe diſtributes a twig near to the joint of the *Tibia* or greater Leg-bone, and the bone called the Cockall, deſcends with the Tendons of the Muſcles, and is divided into the great, the fore, and the middle Toes. The outer paſſes on near to the *Fibula*, or leſſer bone of the Leg, and when it comes to the Ligament which ties together the greater, and leſſer bones of the Leg, it ſhoots forth a branch, which perforating the Ligaments runs into the Foot, and is ſcattered into the Muſcles which bend the Toes of the Foot outward.

The diviſion of the Trunk into two branches.

But the outer and leſs branch [Π] of the Crural-vein goes from that diviſion of the outer branch, which is made near the Ham, to the upper *Appendix* of the *Fibula*, as alſo to the outer and hinder part of the *Tibia*, where ſcattering many little branches, it goes to the outer Ankle, and at laſt ends in the Foot.

And this is the univerſal Hiſtory of the Hollow and Gate-veins, where we have perfected the whole courſe of their diſtributions. It ſeems yet to remain, that we ſpeak of the Umbilical, and Arterious veins. But becauſe the Umbilical vein is nothing elſe but a more notable propagation iſſuing out of the Gate-vein; and in a man grown performs the office of a Ligament, rather than a vein, becauſe it keeps the Liver in its place; as the ſtories of them do witneſs, who upon the cutting off, or wounding of the Navil, have ſuddenly died, their reſpiration being hindered by the weight of the Liver falling out of its place, and pulling down the *Diaphragma* or Midriff with it; we thought it not worth our pains to make any more mention of it in this place. But if any one will obſtinately contend that it is a peculiar vein, with arguments fetcht out of his own Brain, we know no better counſel that we can give him, than to conſult better with his own ſenſe, or if he will contend further, to purge his head with Hellebore, that that dimneſs of the eye-ſight may be a little taken away. But we ſhall with more convenience make mention of the *Vena Arterioſa*, or Arterial-vein, in the following Book, when we ſhall explain the hiſtory of the *Arteria venoſa*, or venal Artery, becauſe they are very like one another, and therefore the ſame pains may ſerve them both.

AN

An Explanation of the Table of the VEINS.

This Table delineates the Hollow-vein, entire, and free from all parts. Wherein we have marked the Trunks and larger branches, with pretty great letters; but the propagations with little ones; and when they are at an end, with figures.

AD THE Aſcendent Trunk *of the Hollow-vein, the beginning whereof is about* A, *which notes the place, wherein the Liver ſhould ſtand in the proportion of this figure, the end about* D. *For it paſſes on undivided from the convex part of the Liver, about which it ſcatters little branches,*

aaa a a a *as far as to the Hollow of the Neck; but it ſcatters ſome propagations, three in number.* The

æ æ firſt *of theſe,* æ æ, *is called* vena Phrenica *the vein of the Midriff, which is diſtributed on both ſides into the Midriff and* Pericardium, *or Purſe of the Heart growing thereto, as alſo into the* Mediaſtinum *or partition of the Cheſt.*

b b Another *is* Vena Coronaria *the Crown-vein,* bb, *which embraces the baſis of the heart in manner of a Crown, diſperſing many Surcles to the point of it.* The third *is the vein* Azygos, *or without a mate,*

c c cc, *which iſſuing out from the right ſide of the Hollow-vein, about the heart, about the fifth Rack-bone of the Cheſt, goes down near to the right ſide of the Rack-bones, as far as to the ſecond almoſt of the Loins.*

ddd *There are ten propagations* d d d *from this, ſent to as many bony diſtances of the ribs which are called* Intercoſtales inferiores, *the lower veins betwixt the ribs.*

B *Shews how the Trunk* A D *is bowed toward the right ſide, becauſe of the ſituation of the heart.*

C *The orifice of the Hollow-vein reaching into the right ventricle of the heart.*

D *The diviſion of the Aſcendent Trunk about the Hollow of the Neck, into two branches* EE, *which they call* ſubclaviæ, *or the veins under the Collar-bones. From theſe ariſe many propagations, ſome iſſuing from the lower, others from the upper part of them.*

EE Out of the lower part *iſſue five.* The firſt *is called* Intercoſtalis ſuperior *the upper vein between*

e *the ribs,* e, *and ſcatters two Surcles* f f, *to the diſtan-*

f f *ces of the three upper ribs.* The ſecond *is* mamma-

g ria *the vein of the dugs,* g, *which deſcending under the breſt-bone, as far as to the ſtrait Muſcles of the* Abdomen, *is inoculated* 10, *with the Epigaſtrick vein climbing upward,* 9, *giving ſurcles to the griſtly diſtances of the true ribs, as alſo to the* Mediaſtinum, *and Muſcles that lie upon the Breſt.* The third *called*

h Mediaſtina, h, *is diſſeminated into the* Media-

i ſtinum, *or partition of the Cheſt.* The fourth ver-

tebralis, *or the vein of the Rack-bones,* i, *climbs up through the holes, that are bored in the tranſverſe proceſſes of the Rack-bones of the Neck, diſtributing ſprings to the Muſcles, that lie upon the Rack-bones.* The

l fifth *is called* Cervicalis *or the vein of the hinder part of the Neck,* l, *diſtributed into the Muſcles, ſeated on the lower part of the back ſide of the neck and on the upper part of the Cheſt.* Out of the upper part *iſſue three.* The firſt *is* Jugularis interna, *the inner*

m *vein of the Hollow of the Neck,* m, *which having ſent over ſmall ſprigs from it its outer branch to the Chops. and region of the Ear, is joined by the inner all the way to the* Arteria Carotis, *or ſleepy Artery, and is divided near to the ſkull into two branches called* En-

n cephalici *or of the Brain, by* Spigelius; *of which the* hindmoſt and greater, n, *having entred into the ſkull through the ſecond hole of the Nowl-bone, is in-*

oo *ſerted* o o *into the firſt* 1, *and ſecond* 2 *ſinus of the*

p *thick membrane. But* the formoſt and leſſer, p, *having entred through the ſeventh hole of the wedg-bone, is ſcattered through the ſides of the thick membrane.*

q The ſecond *is the outer Jugular-vein,* q, *which getting up by the ſides of the Neck is divided near to the*

r *Ears,* r, *into two branches; of which the* one *called*

ſ Profundus, ſ, *is variouſly diſſeminated into the Muſcles of the* Larinx *or throttle, and the bone called hyoides, as alſo into the Tongue, the Palat, and hollowneſs of the Noſtrils, and laſtly into the ſkull with*

t *three propagations, of which that which paſſes* t, *out of the forepart of the eye, through the ſecond hole of the wedg-bone, is very well delineated here.* The other

u *called* Subcutaneus, u, *firſt of all ſpreads its fore-*

x *branch* x, *into the Muſcles and ſkin of the Face, which joins with its fellow about the top of the noſe,*

y *and makes the Forehead vein* y, *then it iſſues out another hinder branch, which partly creeps upward along the temples* z, *and partly is carried behind the ears to*

α *the ſkin of the back part of the head.* α The third,

β Cervicalis ſuperior, *the upper vein of the Neck,* β *is propagated into the Muſcles behind on the back ſide of the neck. There are three* ſinus *or ſmall channels of the thick membrane of the brain; the firſt or right one*

ι *is marked with* 1, *the ſecond or left one with* 2, *the third*

2 *with* 3. *The hinder part of this, which is nearer to*

3 *the Nowl of the Head, is ſhadowed, but the fore part, which is next to the Forehead, is ſeen manifeſtly. From this ſinus many little veins, which they call* Ductus, *are reacht forth to both ſides.*

F *Here the ſubclavian vein takes on it the name of* Axillaris *or the vein of the Armpit, and is divided into two branches, the Cephalick* G, *and the Baſilick* I. *But before this diviſion it ſcatters two twigs:* the

γ *firſt called* ſcapularis interna, *or the inner vein of the*

δ *ſhoulder blade,* γ, *the other* Scapularis externa, *the outer blade vein* δ, *the Baſilick vein alſo* I, *before it*

ε *enters the Arm, propagates two;* one *called* Thoracica ſuperior, *the upper Cheſt-vein,* ε, *which is diſtributed through the inſide of the Pectoral Muſcle, and in women, through the Dugs:* the other *called*

ζ Thoracica inferior, *the lower Cheſt-vein,* ζ, *which deſcending along the ſide of the Cheſt, goes to the Muſcle called* Aniſcalptor.

G The Cephalick-vein, *which, before its diviſion,*

η *ſends away a ſprig,* η, *into the Muſcle* deltoides, *and*

θ *another* θ, *into the Muſcle of the Cubit.*

When the Cephalick vein comes to the joint of the Cubit, at the outer bunching forth of the Arm, it is cut

H *into three branches,* H, The firſt, ι, *or deep and middle*

ι *one goes to the Muſcles ariſing from the ſaid protube-*

κ. *ration.* The ſecond, κ, *or inner goes to the making*

λ *of the vein called* Mediana λ. The third μ, *or outer*

μ *is carried obliquely,* ν, *by the* radius *or leſſer bone of the Cubit to the outſide of the Arm, and ſo creeping on obliquely all the way, when it is come to the root of the wriſt, it is joined with a little branch of the Ba-*

τ *ſilick-vein,* τ, *and makes the vein called Salvatella.*

The Baſilick-vein, *which on the right hand is called* Hepatica, *or of the Liver, on the left* Lienaris, *of the Spleen. This before its diviſion ſends out a Surcle,*

o, *to the heads of the muſcles of the Cubit*; *and then another notable one* π, *which being carried down obliquely*, *beſtows its ſurcles upon the Muſcles that ariſe from the outer protuberation of the arm.*

K *The diviſion of the* Baſilick *Vein* K, *into two branches*, *the one called* Profundus *or the deep one*, *the other* Subcutaneus, *or branch under the skin. The deep one* L, *when it comes to the bending of the Cubit, is* L *divided into two*, M, *one of which called* Radieus N, M N *at the* Radieus *or leſſer bone of the Cubit*; *the other called* Cubiteus, O, *at the greater bone of the Cubit, goes to the hand.*

P Subcutaneus, *or the branch next under the skin* P, Q *near to the inner protuberation of the arm is divided*, R *Q, into two other, of which the inner* R, *together with the inner branch of the Cephalick* ϰ, *makes up the vein* Mediana λ, *which is likewiſe divided into two branches, the outer of which* ρ, *is called by ſome* Cephalica ρ *manus, and goes to the Thumb*; σ *the inner* σ, *to the fore and middle fingers: The outer* S, S *going to the wriſt, is joined toward the little finger with the outer branch of the Cephalick vein about* τ.

τ *The little valves, which are found in the veins of the joints, are handſomely cut out here, as it were to be ſeen through.*

T *The deſcendent Trunk of the Hollow-vein which be-*
V *gins about the Region of the Liver* T, *and ends about* υ *the fifth Rack-bone of the loins* V. *There are four twigs growing from this. The firſt* υ, *called* Adipoſa Φ *or fatty vein diſtributed to the membrane of the Kidneys. The ſecond* Φ *the emulgent going to the Kidney. The third*, præparans vas, *the preparing* χ *veſſel*; *the right one* χ, *ariſing out of the Trunk* TV, ↓ *the left* ↓ *out of the left Emulgent, both afterward go-*ω *ing into the Teſticles* ω. *The fourth is the three* Lum-444 *bares or loin-veins*, 444.

XX *The diviſion of the Deſcendent Trunk* V, *into the* Y *two Iliacal branches* XX, *both which are again divi-*Z *ded into two other, an inner one* Y, *and an outer* Z. *But before this diviſion two propagations are iſſued forth,* 5 Muſcula lumbalis, *or the Muſcle-vein of the loins* 5, 6 *and* Sacra, *or the Holy-vein* 6.

Y *The Inner Iliacal-vein, before it goes out of the* Peritoneum, *or rim of the belly, ſhoots out two propa-*7 *gations, the firſt called* Glutæa 7, 8 *and the ſecond* Hypogaſtrica 8. *The remainder of it paſſing through the* Peritoneum, *is ſpent upon the inſide of the Thigh.*

Z *The outer Iliacal vein likewiſe before its going forth of the* Peritoneum *ſcatters three propagations*; 9 *The firſt called* Epigaſtrica 9, *going into the Muſcles of the Epigaſtrium, and the ſtrait ones of the* Abdomen, *where they are joined by* Anaſtomoſis, *or inoculation* 10. 10 *The ſecond called* Pudenda, 11, 11 *ſpent upon the Privy Parts. The third* Coxalis, 12, 12 *upon the Muſcles of the Hip.*

Here the outer Iliacal vein having paſt through the Peritoneum *or rim of the Belly enters the* Crus, *and* Γ *begins to be called the* Crural Trunk Γ, *that is undivided as far as to the lower heads of the Thigh. But it reaches forth four propagations before its diviſion. The firſt* 13, 13 *is called* Saphena, *which creeps through the inſide of the Leg, under the skin as far as* 14 *to the ends of the Toes. Another* 14, *called* Iſchia *is ſpread out into the skin upon the Hip-bone. The third* 15, 15 *named* Muſcula *is ſent to the Muſcles, which* 16 *extend the Leg. The fourth* 16, *named* Poplitea *is diſtributed into the Calf of the Leg.*

13 *The vein* Saphena *alſo ſcatters from it ſelf four*
17 *ſurcles, the firſt* 17, *into the upper part of the skin of*
18 *the inſide of the thigh: the ſecond* 18 *about the med-*
19 *dle of the thigh: the third* 19 *into the knee: the*
20 *fourth* 20 *is carried forward and backward to the middle of the Leg.*

Δ *The diviſion of the Crural Trunk near to the two*
Θ *lower heads of the thigh into an inner branch* Θ *and*
Λ *an outer one* Λ.

Θ *The inner diſtributes little branches to the Muſcles*
12 *of the Calf* 21, *and then runs down under the inner*
22 *ankle to the great Toe* 22.

Λ *The outer preſently is cleft into two branches*, *an*
Ξ *inner one* Ξ, *and an outer* Π. *That is ſpent wholly*
Π *upon the Muſcles of the Calf, this paſſes on near to the* Fibula *or leſſer bone of the Leg, through the outer and back ſide of the Leg.*



TRACT. II.
CONCERNING THE ARTERIES.

CHAP. I.

Shews the upper or aſcendent Trunk of the great Artery, with its propagations that are diſtributed through the Head.

THere is no controverſie among Writers of Anatomy concerning the number and original of the Arteries, but an unanimous conſent, that all the propagations, which are ſcattered throughout the body, take their riſe from one, which they call *Aorta*, and that this is derived out of the Heart. But the Heart conſiſting of two *ſinus* or cavities, a right and a left one; this great Artery grows out of the left *ſinus* or ventricle [A], where it is largeſt, and more hard, and griſly than elſewhere. But as ſoon as it is grown out, and before it fall out of the *Pericardium* or Purſe of the Heart, it preſently propagates two ſmall ſprigs [a a] one of each ſide, which they call *Arteriæ Coronariæ*, the Crown Arteries, becauſe together with the *Vena Coronalis*, or Crown Vein, they compaſs the *baſis* of the Heart in manner of a Crown, and from theſe many propagations are ſcattered downward all along the Heart. But they are more and greater about the left than the right ventricle, as we have alſo formerly ſaid concerning the Vein, becauſe the Heart needs a greater plenty of bloud on that ſide, as which beats with a perpetual and more violent motion, wherein more bloud is digeſted than the right *ſinus* or ventricle does: yet that propagation is bigger and longer, which ariſes out of the right ſide of the Artery: ſometimes alſo there is onely one, at whoſe orifice a little valve is found. Theſe propagations being thus diſſeminated, the Artery aſcends ſomewhat under the Trunk of the *vena Arterioſa* or Arterial vein, and pierces through the *Pericardium*, and having got above it, is cleft [B] into two branches, which becauſe of their natural greatneſs we will call Trunks; and becauſe one aſcends [C] and the other runs downward [Q] that ſhall be the aſcendent Trunk, this the deſcendent. Yet the deſcendent and lower one is bigger by much than the upper, becauſe that ſerves more parts than this: For the aſcendent one goes onely to ſome parts of the Cheſt, to the Head and Arms; but the lower to very many parts of the Cheſt, to all the loweſt belly and the legs. That therefore we may treat of the great Artery with more perſpicuity, we will firſt ſhew the aſcendent Trunk, and its progreſs through the Cheſt and Head; and after that its branches diſtributed through the arms. Then we will fall upon the deſcendent one, and explain the manner of its diſtribution through the Cheſt, and loweſt belly, and laſtly through the legs.

The original of the great Artery.

Arteriæ Coronariæ, the Crown Arteries.

The diviſions of the great Artery into two Trunks.

What parts both the Trunks nouriſh.

The order of that which is to be ſaid.

The Aſcendent therefore or upper Trunk of the *Aorta* [C], being faſtened to the *Oeſophagus*, or Gullet, climbs upward betwixt the rough Artery, and hollow Vein, and the *mediaſtinum* or partition of the Cheſt. Which ſituation of it they ought diligently to obſerve, who deſire to know the reaſon of that Aphoriſm, which is the four and twentieth of the fifth Section in *Hippocrates*: For ſays he, cold things, as Snow and Ice are enemies to the breſt, provoke Coughs, and cauſe eruptions of bloud, and diſtillations. Truly they are enemies to the breſt, becauſe whileſt they are ſwallowed down through the Gullet, they cool the rough Artery that lies next to it, together with the Gullet, which part being of it ſelf cold, does eaſily take harm from ſo violent a cold: hence the Cough, and other diſeaſes of the breſt follow one another in a long row. But iſſues of bloud happen in like manner, the great Artery being cooled, whereby the vital Spirits and the bloud are driven back to the Heart, and from thence are ſent up forcibly to the Head, which being ſtuffed, eruptions of bloud are cauſed by its dropping forth at the Noſtrils, as alſo Catarrhs and Diſtillations, it being driven down undigeſted to the inferiour parts. And hence alſo a reaſon may be rendered, why ſome upon drinking of cold water after vehement motions and exerciſe of body, have preſently been ſuffocated, the paſſion of the heart, and grievous ſwounings following thereupon. For the Artery being vehemently cooled, the bloud is congealed, as well that which was in the *Aorta* or great Artery, as that which abides in the Heart; from whence happen at firſt fearful ſymptoms, and then ſudden death. But we have ſeen in theſe men, that a vein being opened, the bloud hath come out thick, and cold, and with very great difficulty, whence alſo we have not found a more preſent remedy for them, than ſuch things, as by reaſon of the thinneſs of their parts have a power of diſſolving the clots of bloud. Hence alſo a reaſon may be given, why in burning Fevers the Tongue becomes black, and the diſeaſed can hardly ſwallow. For although it be true (which is the cauſe commonly aſſigned) that many vapours are ſent up from the whole body to the head; yet we may aſcribe a main cauſe of this blackneſs to the nearneſs of the Artery, which being ſet on fire and inflamed, procures much miſchief to the Gullet, and conſequently to the Tongue it ſelf.

But the aſcendent Trunk, whileſt it paſſes thus upwards, is divided into the two ſubclavian Arteries [DD], of which one runs to the right ſide, and the other to the left. They are called *ſubclaviæ* as long as they are in the Cheſt, for the ſame reaſon as the ſubclavian veins are ſo called, becauſe they run under the *claviculæ* or collar-bones: but as ſoon as ever they are fallen out of the cheſt, they change their name, and are called *Axillares* [E]. From both the ſubclavian Arteries, when they have attained to the firſt rib (for before that they ſend forth no propagations) many ſprigs iſſue out, as well from their upper as lower part. From the lower, iſſues the upper Intercoſtal Artery, or *Inter-*

The diviſion of the aſcendent Trunk into two branches.

The ſubclavian Arteries.

Intercoſtalis ſuperior, the upper artery between the ribs

Vertebralis, the artery of the rack-bones.

c ſtalis ſuperior [b], which being faſtned to the roots of the ribs, beſtows particular branches upon the diſtances of the four uppermoſt which run under the ribs, together with the veins, as far as to the griſles, from which propagations are diſperſed into the marrow of the back, and the neighbouring muſcles. From the upper part iſſues firſt that which is commonly called *Cervicalis*, or the Artery of the neck [c], but better *Vertebralis*, of the rack-bones, which ariſes more backward, and toward the bodies of the rack-bones, and aſcending obliquely, near to the ſeventh rack-bone of the neck, like the neck-vein, paſſes through the holes of the tranſverſe proceſſes, and upper rack-bones of the neck, where it ſhoots out many propagations which enter the ſpinal marrow through the common holes, at which the nerves go out. It ſends alſo a pretty company to the muſcles that are ſeated on the back-ſide of the neck, and aſcends to the nowl-bone together with the vein, through whoſe firſt notable hole, by which the ſpinal marrow deſcends out of the head, it enters the skull. After this it is joined with its fellow of the other ſide under the ſpinal marrow, which remains yet in the skull, and ſo runs ſtrait forwards, under the middle of the *baſis* of the brain; but when it hath now attained to the *ſella* or ſaddle of the wedg-bone, upon which the phlegmatick glandule lies, it is divided into two branches, a right and a left one, both which at the ſide of the ſaddle creep to the ſecond pair of nerves, where being broken on both ſides into an infinite number of ſurcles, they are diſperſed betwixt the firſt and ſecond pair of the nerves, and folden together with the thin membrane, make that complication of veſſels called *plexus Choroides*. The next is *arteria mammaria*, or artery of the paps [d], which being reflected under the breſt-bone (accompanied with the mammary vein) deſcends along its ſides, and when it comes to the griſle called *Enſi-formis*, or the breſt-blade, about the ſides thereof goes out of the cheſt, and running under the right muſcles of the *abdomen*, deſcends directly through the lower ſide of them, and at length near the navel, is joined by *anaſtomoſis* or inoculation [x] with the Epigaſtrick Artery plying upward [i]. But before it leaves the cheſt it ſcatters particular branches to the ſix diſtances betwixt the griſles of the ſeven true ribs, which branches determine together with the griſles. A third [e] is otherwiſe called *Muſcula* the Muſcle-artery, but might be better and more ſtrictly named *Cervicalis*, being it is diſſeminated into the Muſcles that are placed in the region of the neck, as far as to the *occipitium* or nowl of the head.

Mammaria, the artery of the paps.

Cervicalis, the artery of the neck.

Arteria axillaris.

Its branches before it enters into the arm.

From its lower part.

From its upper part one.

Theſe branches being ſent out, the ſubclavian artery goes out of the cavity of the cheſt, and getting above the firſt ribs tends obliquely to the arm-pit, and ſo makes the axillary artery [E] which afterward is ſpread into the arm. But before that it ſcatters ſome propagations, and from its lower part three, of which the firſt is *ſcapularis interna*, the inner-blade Artery [f] which goes to the muſcles on the hollow ſide of the ſhoulder-blade. Another is *Thoracica ſuperior*, the upper cheſt-artery [g], which goes to the pectoral muſcle, that leads the ſhoulder forward to the breſt, and the other muſcles that lie upon the breſt, and is a pretty big one. The third is *Thoracica inferior*, the lower artery of the cheſt [h], which is alſo a large one, and running down all along the ſide of the cheſt, is the greateſt part of it ſcattered into the broad muſcle called *Latiſſimus*, which moves the ſhoulder backward from the breſt. From the upper part of the axillary Artery ariſes one called *ſcapularis externa*, the outer blade-artery [i], which climbing up to the top of the ſhoulder is diſſeminated into the Muſcles that cover the gibbous ſide of the ſhoulder-blade. The remaining part of the axillary artery paſſes on in company of the Baſilick vein to the arm, upon all which it is afterward ſpent, of whoſe diſtribution we will ſpeak in the following Chapter.

The ſleepy Arteries.

The diviſion of them.

The outer, or branch of the face.

The inner, or branch of the brain.

The diviſion thereof into a leſſer and greater branch.

A ſubdiviſion of the greater.

That which remains yet of the aſcendent Trunk [L] being ſuſtained with the *Thymus* near to the upper part of the breſt-bone, is divided into two branches [MM] which they call *carotides* or *ſoporales*, the ſleepy arteries, becauſe they being obſtructed, or any way ſtopt, we preſently fall aſleep; of which *Valuerda* witneſſes in *Anatom. lib. 6. c. 11.* that *Realdus Columbus* made trial in a young man, among a great company of men. They are unequal in bigneſs, the right one being much thicker than the left, but they tend directly upward, being carried along the ſides of the neck, and faſtned to the rough artery, and to the internal jugular veins, by the benefit of a membrane, and when they are come to the cups, are divided into two branches [N] of which one is the outer, the other the inner one: that is the leſs, this is the greater. The outer [O] ſends propagations [†] to the cheeks and muſcles of the face; then when it is come to the ear, it is divided in twain; for one branch [r] of it goes to the back ſide of the ear, from which two branches under the ear enter the nether jaw through the firſt hole of it, that is ſeated at his proceſſes, and throughout the length thereof are diſſeminated into the roots of all the lower teeth, that which remains, going out at the ſecond hole, which is placed at the chin, is ſcattered into the lip. The outer branch [q] creeps through the Temples and fore-head, and is ſpent upon the muſcles of the face. The inner branch [P] of the ſleepy artery, or *arteria Encephalica*, the brain-artery, is carried into the chops; and having ſcattered ſome propagations to the tongue and throttle, is divided about the *baſis* of the skull, into two unequal branches, to wit, a greater and a leſſer one. The leſſer and hindmoſt [s] is carried together with the greater Encephalick branch of the internal Jugular-vein, to the back-ſide of the skull, enters through the ſecond hole of the *occipitium* or nowl-bone, and goes into the *ſinus* or canale of the thick membrane. The greater and more forward [t] having entered the cavity of the skull through a hole made on purpoſe for it in the temple-bone, and attained to the ſaddle of the wedge-bone, going every where under the hard membrane; firſt of all propagates a branch on both ſides into the ſide of the thick membrane, then in Beaſts ſcattering an infinite number of ſurcles makes the *Rete mirabile* or wonderful net, which indeed may be found in a Man too, but it is very little, and ſeems but a ſhadow in reſpect of that in Beaſts. Theſe ſurcles being thus placed it pierces through the thick membrane of the brain, and having got out of it, ſends another propagation out of the skull, through the ſecond hole of the wedge-bone to the eye and its muſcles, as alſo to the temple muſcle, that lifts up the lower jaw; and then going ſtraight up to the ſide of the phlegmatick glandule, it is divided into two branches, an outer, and an inner. The inner is joined with its fellow of the other ſide, and being joined they are waſted into many little arteries, which are diſperſed through the thin membrane, and the very

ſubſtance

ſubſtance of the brain, to the original of the optick nerves. The outer being reflected and ſuſtained with the thin membrane, goes into the forward ventricle of the brain; being divided into many ſurcles, which are united with thoſe little arteries which ariſe from the *vertebralis* or artery of the rack-bones; ſome with thoſe which the vertebral artery ſcatters through the *baſis* of the head under the brain, but others with thoſe which it diſſeminates through the thin membrane and ſubſtance of the brain, together with which they make the *plexus choroides*.

CHAP. II.

Declares the Hiſtoy of the Axillary Artery, being diſtributed through the Arm.

THe Axillary Artery therefore when it is come to the arm, taking the name of the Arm-trunk [FF] is carried in one undivided ſtock, beyond the bent of the cubit through the inſide of the arm, diſperſing ſome ſmall propagations on both ſides to the muſcles that lie on the inſide of the upper part of the arm. But it goes faſt by the inner or deep branch of the Baſilick Vein, as an unſeparable companion of it, whoſe conduct and ſteps it every where follows. But preſently falling down by the back-ſide of the upper part of the arm, where the muſcles which extend the cubit ſtick to it, it ſends forth two propagations [l and m] the lower of which is a very notable one, and ſo it is writhed back toward the bent of the cubit, and having attained thereunto it reaches out two ſurcles [nn] one of each ſide, ſo manifeſt, that the pulſe is there oftentimes evidently enough perceived. Then going under the bent of the cubit, through the inſide of it, and ſinking down betwixt the two muſcles that bend the ſecond and third bones of the four fingers, it is cut [G] into two notable branches, one of which is an outer, the other an inner one. The outer [H] is carried along the *radius*, or leſſer bone of the cubit (whence I call it *Radius*) and goes directly to the wriſt, in which place Phyſicians feel the pulſe, it being very manifeſt, by reaſon that the artery lies next under the skin. But not far from the root of the wriſt it ſhoots out a little branch [o] which runs under the tendons of the muſcles which extend the thumb, into the outſide of the hand, and is ſpent upon the muſcles, which are placed betwixt the firſt bone of the thumb, and that of the after-wriſt, which ſupports the fore-finger. This branch being propagated, going under the inner annular ligament of the wriſt, and the broad tendon of the palm muſcle, it is divided into three branches [ppp] like the vein and nerve that are its companions. The firſt of theſe goes to the inſide of the thumb, the ſecond to the inſide of the fore-finger, and the third to that of the middle. The firſt and ſecond are each of them parted into two branches; the third is undivided. The inner branch of the trunk of the arm [I] runs ſtrait along the *ulna* or greater bone of the cubit (and for that reaſon I call it *Cubitus*) and is diſperſed into the palm of the hand. But it is ſo hidden among the muſcles, that it is hardly perceived to beat, unleſs in lean folks; and therefore Phyſicians always lay their hands upon the outer branch when they feel the pulſe in the wriſt. But it paſſes on under the tranſverſe ligament of the wriſt, and the tendon of the palm muſcle, in company of a vein and nerve, and ſcatters two branches into the little finger, as many into the ring finger, and one into the outſide of the middle.

Brachialis teretes, the trunk of the arm.

The diviſion thereof into two branches.

The outer branch.

The inner branch.

CHAP. III.

Shews the Inferiour or Deſcendent Trunk of the great Artery, and the propagation thereof through the middle and loweſt Bellies.

WE have ſaid above, that the great Artery [A] as ſoon as it is gotten above the *Pericardium* or Purſe of the Heart, is divided [B] into two branches; of which one goes upward, the other deſcends to the parts below. We have already handled the upper branch; it remains that we explain the other alſo.

The deſcendent trunk thereof [Q] anſwering in proportion to the ſtock of a Tree, is carried down to the fifth rack-bone of the cheſt, and declining ſomewhat to the left cleaves to that ſide of the body of the rack-bones, and ſo deſcends leiſurely. When it has now paſt the midriff through that diviſion reſembling a ſemi-circle, which is betwixt the productions of the *ſeptum tranſverſum* or midriff, preſently it runs out by the rack-bones of the loins, leaning upon the middle of their body, till it come to the laſt of them, where near to the *Os ſacrum* it is divided [R] into two notable branches [SS] which with our Anatomiſts we will call *Iliacæ*, the Iliacal arteries from their ſituation. In this journey it ſcatters many propagations from it ſelf, which are very worthy to be diligently obſerved, becauſe from thence we may eaſily give a reaſon of many accidents in Diſeaſes. But they are in number eight, the Intercoſtal arteries, the two *Phrenicæ* or arteries of the midriff, the Cœliacal one, then the upper Meſenterick, the two emulgents, as many ſpermatical ones, at laſt the lower Meſenterick, and the *Lumbares*, or arteries of the loins. Of theſe the Intercoſtals are ſcattered, whileſt the trunk is yet in the cheſt; the reſt, whileſt it paſſes on through the loweſt Belly. But ſome of them accompany the branches of the gate-vein, as the Cœliacal, and both the Meſenterical arteries, others thoſe of the hollow vein, as the reſt. Now we will treat of theſe in order, begining from the Intercoſtals or arteries between the ribs, which are placed uppermoſt. Preſently therefore after the deſcendent trunk [Q] is iſſued forth, from its backſide it ſends over little branches on both ſides to the diſtances of the eight lower ribs, which they call *Intercoſtales inferiores*, the lower arteries between the ribs [uuu] in reſpect of the upper Intercoſtal, of which we have ſpoken above. Theſe aſſociating themſelves with the veins and nerves, of the ſame name, go ſtraight on by the lower ſide of the ribs; where peculiar *ſinus* or channels are cut out for them. But as the Intercoſtal veins reach in the true ribs onely to the griſles, but in the baſtard ones ſomewhat farther, to wit, to the ſides of the *abdomen*; ſo alſo the arteries end in them together with the bony parts of the ribs, but in theſe run out a little farther.

The deſcendent trunk.

Its progreſs.

Its propagations.

Intercoſtales inferiores, the arteries between the lower ribs.

farther. And theſe arteries ſend over ſome propagations through the holes of the nerves to the ſpinal marrow, and to the muſcles that lie upon the rack-bones of the back, juſt as we have ſaid the intercoſtal veins were propagated. But the uſe of them is to diffuſe the vital ſpirit, and the bloud to the muſcles betwixt the ribs, beſides which they have alſo another notable office, to wit, of carrying down the water and purulent matter that is gathered together in the cheſt, into the great artery, and from thence by the emulgent branches to the bladder. Although I am not ignorant that the moſt learned *Fallopius* and others, who have read before me in this moſt famous Univerſity of *Padua*, have ſhewn another way to their Auditors; by which either purulent matter or water might be conveyed forth by help of the kidneys, to wit, the vein *ſine pari*, or without a companion, a little branch whereof in the left ſide goes into the emulgent of the left kidney. But this way which we ſhew through the Intercoſtal arteries, is by much the ſhorter; that I paſs by this, that any matter heaped together may be more eaſily diſpatched away through the arteries than the veins. Nor needs any one here to be affraid leſt the vital ſpirits ſhould be infected from theſe excrementitious and ill humours, whereby the heart may incur fearful ſymptoms; when we willingly grant (which experience alſo hath often taught us) that whileſt the corrupt matter is emptied out by the urine, the ſick parties have often fallen into fits of ſwouning, and other diſeaſes; ſometimes alſo have died ſuddenly when the peccant humour hath been of too great a quantity, or too bad a quality, and hath offered ſo much violence to Nature, that the heat and ſpirits have been overcome therewith. But here a certain place in *Hippocrates* calls upon me to explain it, which has long and often troubled my mind. The place is in *Coacis prænotionibus*, where he ſays, They, who together with the heart have their whole lungs inflamed, ſo that it falls to the ſide, are deprived of motion all over; and the parties ſo diſeaſed lie cold, ſenſleſs, and die the ſecond or third day. But if this happen to the lungs without the heart, they live not ſo long: yet ſome alſo are preſerved. I have often thought with my ſelf, what ſhould be that ſympathy of the heart and lungs with the brain and nerves, that from the inflammation of thoſe parts, the Patient ſhould be ſo deprived of ſenſe and motion all over, when the ſame *Hippocrates* teacheth in the ſame place, that the diſeaſed ſuffer ſuch deprivation in that part, and livid ſpots appear on the outſide about the rib, whereabout the *Aortæ* (ſo he ſeems to call the lobes or diviſion of the lungs) being inflamed fall to the ſides. But if they be not much inflamed, ſo that they fall not down to the ſide; he ſays that there is a pain indeed all over, but no deprivation of ſenſe or motion, nor any ſpots appear. Having deliberated often with my ſelf, at length I came to be of this opinion; that there was no other cauſe, but the ſympathy betwixt theſe Intercoſtal arteries, and the marrow in the back-bone. This ſympathy ariſes from thoſe propagations which we told you paſt through the holes of the rack-bones of the cheſt into the back-bone. Wherefore if the lungs and heart be ſo mightily inflamed, that great plenty of bloud ruſh into the great artery, whereupon it ſwells, as alſo theſe veſſels betwixt the ribs, and conſequently thoſe ſurcles whieh go to the marrow of the back-bone; truly it cannot be, but that both the marrow and the nerves which iſſue out of it, be compreſt; from whence what elſe can follows but the reſolution of thoſe parts, into which thoſe nerves are implanted, and to which they impart the faculty of motion? This opinion ſeems to me to be wonderfully confirmed by a certain pretty obſervation, which the learned *Cornelius Gemma* hath in his Book, *De Hemitiræo Peſtilenti*. A certain ſtudious young man, ſays he, through the whole courſe of his diſeaſe, had his left eye leſs than the other. He was pained in the left ſide, eſpecially all the time the fit raged; but about the *criſis* or judication thereof, the artery of his left leg being ſwollen up was moved according to its length, that being to be ſeen by us it ſeemed to be turned upward and downward like a Rope pulled back. Who will not here willingly confeſs, that this matter was in the arteries, when the *criſis* was made by them? But from this that hath been ſaid a reaſon may be alſo given of another obſervation of *Galen*, which is *l.*4. *De locis Affect. c.*4. where he ſays thus: In a certain man who was troubled with a vehement inflammation of the lungs, as well the outer as the inner parts of his arm, from the cubit to the very ends of his fingers laboured with difficulty of ſenſe, and their motion alſo was ſomewhat impaired. In the ſame man alſo the nerves which are in the firſt and ſecond diſtances betwixt the ribs, ſuſtained harm. And a little after, This man was quickly reſtored to his health, to wit, a medicin being applied to the place from whence the nerves iſſue forth, near to the firſt and ſecond ſpaces betwixt the ribs. By reaſon of the ſame branches betwixt the ribs *John Valeriola*, the ſon of that Phyſician, whoſe obſervations we have, being yet a boy, ſuffered Convulſion-fits in a grievous Pleuriſie.

Their uſe.

The explanation of a place in *Hippocrates*.

2. *Phrenicæ*, the arteries of the midriff.

The arteries called *Phrenicæ* of the midriff, [xx] are two; one of each ſide, which ariſing out of the Trunk, preſently after it is come forth of the hollow of the cheſt, being divided into more branches, are ſcattered into the midriff, but eſpecially into the lower ſide of it, near to the rack-bones of the back. They ſprinkle ſome ſmall twigs alſo into the upper part, which afterwards go to the *Pericardium* or purſe of the heart, there where it grows to the midriff.

3. *Cœliaca.*

The *Cœliaca* or Stomach artery is but one, ſo called, becauſe it ſends over branches to the Κοιλία, that is, the Stomach. This being moſt like to the ſplenick branch of the Gate-vein, affords many branches to the Stomach, Liver, Bladder of Gall, Kall, the Gut *Duodenum*, the beginning of the *Jejunum* or empty Gut, a part of the *Colon* or Colick Gut, the Sweet-bread and Spleen. But it ariſes out of the fore-ſide of the body of the trunk, and being ſtaid up all the way by the upper part of the lower membrane of the Kall, is divided into two notable branches, but of unequal bigneſs; one of which goes to the right the other to the left: that is the leſs, this is the greater. The right branch therefore is joined with the deſcendent Gate-vein in the *Pancreas* or Sweet-bread, that is placed under the hinder part of the ſtomach, and leaning there upon the membranes of the Kall goes to the Liver; and its ſmallneſs is worth the taking notice of, if you look upon the largeneſs of the Liver, which the Ancients long ſince, and many at this day have made the Work-houſe of the Bloud. But it is inſerted in the hollow part, near to the trunk of the Gate-vein, and is ſo ſmall, becauſe that part of the Liver which entertains the roots of the Gate-vein, needed not a greater artery; but the other part which hath

The two branches thereof. The right branch.

hath the propagations of the hollow vein, receives great plenty of vital ſpirits ſent over from the heart through the hollow vein. Yet before it enters into the liver, it diſſeminates in the way many ſurcles, and thoſe partly from its upper ſide, partly from its lower: from the upper ſide two, firſt, that which I call *Pyloricus*, which ariſes in the midway, and being divided into many little branches is ſcattered into the backſide of the right orifice of the ſtomach. The outer is called *Cyſticæ gemellæ*, the Twin-arteries of the bladder of gall, which are two little branches, and go into the bladder of gall, and preſently are divided into many propagations. From the lower ſide likewiſe two ariſe. The firſt is *Epiplois dextra*, or the right kall-artery, which is implanted into the right ſide of the lower membrane of the kall, and part of the colick gut annexed thereunto. The outer is cleft into two branches, of which one is called *Inteſtinalis*, the gut-artery, paſſes on to the *duodenum*, and the beginning of the *jejunum*, or empty gut: the other named *Gaſtro-epiplois dextra*, the right ſtomach and kall-artery, ſomewhat larger than the former, turns down to the right ſide of the bottom of the ſtomach, and being ſupported by the upper membrane of the kall, iſſues out ſome ſhoots from the upper part to the fore and back-ſides of the ſtomach; but from the lower to that membrane of the kall upon which it leans.

Propagations from its upper part. 1. 2. From its lower part. 1. 2.

The left and greater branch is called *Arteria ſplenica*, the Spleen artery, which ſticking to the lower membrane of the kall and the glandules placed therein, paſſes on together with the Spleen-vein, to which it is faſtned, and in the like manner diſtributes its propagations to the Spleen. But in the way likewiſe it diſtributes branches from both parts of it: from the upper iſſues *Gaſtrica* the ſtomach artery, which reaches into the middle of the hinder part of the ſtomach, or that wherewith it leans upon the back, and aſcending from thence it compaſſes the left orifice of the ſtomach round about like a Crown, and diſperſes little twigs, partly upward to the end of the Gullet; partly downward, and thoſe greater and more numerous, into the ſtomach, and ſo it makes the *Arteria Coronaria* or Crown-artery, like to the Crown-vein, which ariſes from the Gate-vein, as we have ſaid in the fore-going Treatiſe. But from its lower ſide the Spleen-artery ſends out the *Epiplois ſiniſtra* or left Kall-artery, about that part wherewith it now attains to the Spleen, which runs out into the left ſide of the membrane of the lower part of the Kall. This artery preſently after its riſe, is cleft into two branches, which part very far aſunder from each other, from which many other arteries ariſe, that are all conſumed upon the ſaid membrane of the Kall, and the Colick gut that is tied thereto. Theſe branches being iſſued, the Spleen-artery draws nearer to the Spleen, and juſt like the vein of the ſame name, which accompanies it all the way, is cleft into two branches like the letter Y, one of which may be called the upper, the other the lower, which afterward entering by the hollow part of the Spleen are ſplintered into an infinite number of little ſprigs, ſo that there are five times more arteries there than veins. Whence it comes to paſs, that in inflammations of the Spleen, if you lay your hand to the left *Hypochondrium*, or place under the Griſle of the baſtard ribs, it ſeems to pant. But before this entery of the artery, the lower branch makes a notable *Anaſtomoſis* or inoculation with the lower branch of the vein, and propagates a twig to the lower membrane of the Kall. But from the upper branch iſſues one called *Gaſtro-epiplois ſiniſtra*, the left ſtomach and Kall-artery, which being faſtened to the upper membrane of the Kall, is derived into the left ſide of the bottom of the ſtomach, beſtowing little branches upon the fore and back-ſides of it, or alſo upon the upper part of the Kall. Another iſſuing from the upper branch, make the *vas breve arterioſum*, or ſhort arterial veſſel, carries, like the vein, its name-ſake, to the left ſide and orifice of the ſtomach. The uſe of the right branch which goes to the Liver, beſides the common one which it hath, is this, as often as the bladder of Gall is obſtructed, to carry down the choler to the Guts, and eſpecially to the *Colon*, into which ſome of its branches are implanted. Which is the reaſon, that in bloudy fluxes the Ulcers are almoſt always found in the great Guts, and eſpecially in the *Colon*, very ſeldom in the ſmall ones. For this artery, when either the Liver being over hot breeds abundance of choler, or the bladder of Gall is obſtructed receiving into it ſelf ſtore of choler, carries it directly over to the *Colon*, or Colick gut. In like manner the uſe of the left branch, or Spleen artery, beſides the common one, is to throw down choler, melancholy, and wheay humours, if at any time the Spleen abound with them to the Guts. Moreover by this ſame way the wateriſh humours in ſuch as have the Dropſie, are ſometimes committed either to the Guts, or to the Kidnies and Bladder. This ſame branch is that by which the drink paſſes ſo ſuddenly through the whole body, and by which ill humours are caſt out by Vomit. This ſame is the cauſe, that upon a full ſtomach we make little water, but more when the concoction therein is finiſhed. For the Stomach being much diſtended preſſes it, but that once empty, it can perform its office. This ſame branch teaches us that a ſlender diet is to be preſcribed to them who are to take Purges, that the way may be open for the Medicins, as well that by which the excrements are ſent over the Stomach, as that by which they are conveyed to the Guts. This ſame branch alſo, if you add the two Meſentericks, is the ſeat of the hypochondriacal Melancholy. For this diſeaſe ariſing from the obſtruction of the entrails which are contained in the loweſt belly, it is neceſſary that the arteries here ſhould ſuffer very much, which the very ſymptoms that happen in this diſeaſe, may ſufficiently inform us.

The left branch. Propagations from its upper part. From its lower part. Its diviſion. The uſe of the right branch. Why ulcers are more frequent in the great guts. The uſe of the cleft.

Meſenterica ſuperior, the upper artery of the Meſentery [y] ariſes a little below the Cœliacal, being diſtributed like the Meſeraick Vein (which is its companion) with numerous propagations in the guts called *Ilium* and *Jejunum*, as alſo that Region of the *Colon* which reaches from the hollow of the Liver as far as the right Kidney, and ſo for the moſt part into the upper part of the Meſentery. In which place it is to be obſerved, that the Artery ſometimes lies upon the Vein, ſometimes on the contrary the Vein upon the Artery, and ſo is carried betwixt the membranes of the Meſentery. But theſe Arteries in many places in the Meſentery have glandules, which were made for the free perſpiration of the veſſels, and eſpecially of the Arteries; whereby it comes to paſs, that theſe glandules labouring with a hard tumor or *ſcirrhus*, the veſſels are compreſt, and a pining away of the whole body follows thereupon.

4. *Meſenterica ſuperior.* An obſervation.

The Emulgent arteries [z] are two, one the right, and another the left one. Both iſſue out under the fore-mentioned Artery, where the firſt and ſecond rack-bones of the loins are coupled together by the ligament. But they ariſe out of either ſide of the trunk, although not directly over againſt one another,

5. *Emulgentes.*

ther, as alſo it is in the Emulgent veins, the right one being lower than the left. Theſe Arteries, when they come to the Kidney, are cleft into two branches, with which they are inſerted into the *ſinus* or channels of the cavity of the Kidnies, and like the Veins are conſumed in an infinite number of little Sprigs upon their ſubſtance. Their uſe, beſides the common one, is to purge out the whey, which is found in great plenty in the Arteries.

Their Uſe.

6. *Spermatica.* The Spermatical or Seed-Arteries [α] are likewiſe two, which ariſe out of the fore-part of the Trunk of the great Artery, their originals touching each other; for the left Artery iſſues not from the emulgent, as the left ſpermatical Vein does. Afterward in their deſcent they are made faſt to the Veins of their own ſide, and in men are carried through the proceſſes of the *Peritoneum* or Rim of the Belly to the Teſticles; but in Women, when they come ſomewhat near to the Teſticles, they are divided into two parts, one of which is carried to the Teſticles, the other to the bottom of the Womb. But the Arteries do ſo come to the Womb, that they onely water it at the ſides, and pierce not at all into the inner parts of it. Which truly came to paſs by the great providence of wiſeſt Nature, ſince it had not been ſo ſafe to have brought them down to the inner ſurface of the Womb, by reaſon that in the coming forth of the Child very great iſſuings of bloud would be cauſed, to the no ſmall danger of the Woman in Childbed, if the Arteries had been annexed to the Womb on the inſide. Hence alſo it is, that in the time of delivery they flow by little and little, not ruſhing down with violence.

7. *Meſenterica inferior.* *Meſenterica inferior*, the lower Artery of the Meſentery [δ], ariſes near to the *Os ſacrum*, or great bone, a little above the diviſion of the Trunk into the Iliacal branches, and goes into the left ſide of the *Colon*, and into the ſtrait Gut, deſcending with the hæmorrhoidal Veins to the very end of the Fundament, and making the hæmorrhoidal Arteries. It is queſtioned concerning the uſe of both the Meſentericks, whether beſides the common, they have any peculiar one. For *Galen* in his 4. Book of the Uſe of the Parts, ſeems to make mention of ſome other when he would have part of the *Chylus* to be attracted by them. And in the Book, Whether bloud be contained in the Arteries, in the fifth Chapter he ſays, If we divide the loweſt Belly, and the inner Membrane, we ſhall plainly ſee the Arteries in the Meſentery filled with Milk in Kids newly yeaned; but in living Creatures that are grown, full of ſomething elſe. In which words Anatomical experience teaches us, that not onely the Meſeraick Veins but Arteries alſo do manifeſtly draw the *Chylus* to them. Which being ſo indeed, it is altogether to be believed that the *Chylus* is either afterward tranſported by them into the Veins, or elſe turned into bloud by the Arteries themſelves. Nor will this ſeem wonderful to any one who ſhall conſider alſo that the Mothers bloud is conveyed through the Umbilical Arteries to the Child whileſt it is yet ſhut up in the Womb. But if the bloud which is received up by the Veins ought yet to be better worked, as any diligent inquirer into Nature will conclude it ought; truly that which is received by the Arteries will require to be ſo much the more exactly laboured, by how much the better it is than that of the Veins. But it is ſo laboured in the Arteries themſelves, and in the Spleen, being haled into the Cœliacal Artery and carried to the Spleen. And this is an excellent uſe of the Meſentericck Arteries, whileſt a man enjoys perfect health; beſides which we will add another alſo, as often as he leaves to be in health. For theſe Arteries take to them the excrements of the whole body, that they may carry them down to the Guts, in like manner as the Veins do, by which Nature doth both attract the *Chylus*, and likewiſe expell the noiſom humours out of the body, as choler, phlegm, and melancholy. Choler is thus expelled oftentimes in continual and intermitting cholerick Fevers, a ſolution whereof follows by a looſneſs: Phlegm is ſo expelled, as often as bloudy Fluxes happen to ſuch as have the Gout in the feet, which eaſe them of their pain, if the intent of Nature be advanced by the help of a wiſe Phyſician. Laſtly, Melancholy is conveyed out by both the Meſentericks, but eſpecially by the hæmorrhoidal branch: whence *Hippocrates* ſays, 6. *Epidem.* He which has the Emroids naturally, ſhall neither be troubled with the pain of the ſide, or inflammation of the lungs, nor with Felons or black puſtles, called *Terminthi*, nor with the Leproſie, Canker, or other diſeaſes. For there is a very great ſympathy betwixt the breſt and the hæmorrhoidal Artery, becauſe the Trunk out of which it ariſes, deſcending from the heart, preſently after it firſt iſſues from thence, propagates the intercoſtal branches. Moreover all black cholerick humors are purged by this means out of the whole body, that cankers and leproſie cannot be cauſed by them. From theſe voluntary purgings which nature it ſelf has found out, we may now judg of ſuch as are cauſed by the help of a Phyſician, and may be termed artificial. For an opinion of ſome men hath prevailed much in our age, that the body cannot be purged by clyſter, but only by thoſe medicines which are taken at the mouth. But I will not only believe, but alſo being taught it by experience can witneſs, that, if the Clyſters contain in them purging medicines, the whole body is very commodiouſly cleanſed. For the whole Colick-gut receiving the matter of the Clyſter, the vertue it ſelf of the medicine draws down the noiſome humors by the arteries out of the *Aorta* or great artery. Which being granted, we may give a reaſon (which we have ſeen very often) why Suppoſitories made of white hellebore produce the ſame ſymptoms, as are wont to be cauſed in them who have taken in white hellebore at the mouth. In like manner from hence we may fetch the reaſon why the belly is ſtrongly purged, the region about the navel being anointed with purging medicines. For the vertue of the medicine is attracted by the arteries, and by them afterward it purges. Theſe arteries are they by which the diſeaſe of the Colick is changed into the Gout, and on the contrary the Gout into the Colick, as we have it in *Hippocrates*, 6. *Epidem. Sect.* 4. where he ſays: One that was vexed with the pain of the Colick on the right ſide, had ſome eaſe whilſt the Gout held him; but this diſeaſe being cured, he was pained more. The reaſon whereof was this, becauſe that humor, which cauſed the Gout, was carried out of the joints to the colick-gut, whereby the Colick diſeaſe was increaſed. *Laurentius* inquiring into the cauſe of this, refers us to hidden and unknown paſſages, to which, it ſeems to me that we need not fly, if we ſay that the humors are brought out of the crural arteries into the Trunk, and out of this into the Meſenterick branches, and laſtly, out of theſe into the guts; for this is the

Its Uſe.

An obſervation.

Why anointing of the navel with ſuch things as purge looſens the belly.

How the Colick is changed into the Gout; and on the contrary.

ſhorteſt

ſhorteſt, and moſt convenient way. Nor is there any reaſon, that we ſhould be afraid of that pollution of the vital ſpirits, which they will object to us if the excrementitious humors paſs through the arteries; for this betrays their great ignorance as well in Anatomy as in ſolid Phyſick: and it would be very eaſie, if I would digreſs, to prove in this place, that a great part of the humors in our body flow down through the arteries. For in them the ſtrength of nature exceeds, and is more vigorous, that whenſoever it is provoked, it is moſt apt to expel; and the blood being ſtirred by their continual beating, as alſo by its own nature, makes all that is therein more fit to flow. And who will not believe that excrements are carried through the arteries, who conſiders the flowing down from the ſpleen, in which there being five times more arteries, than there are veins, truly it is neceſſary that that ballaſt of the ſpleen be carried out through the Arteries.

The four, *Lumbares* or loin-arteries [γγ] ariſe out of the backſide of the trunk of the great artery, all along as it paſſes through the region of the loins. They run through the common holes in the rack-bones of the loins, and to their marrow, and alſo into the neighbouring muſcles. And at the ſide of the marrow, after they have entred the rack-bones, they climb up on both ſides to the brain together with the veins of the loins. But they are all equally big, if you except thoſe two, which iſſue out near to the *Os ſacrum* or holy-bone, which are not only derived into the rack-bones to the marrow, and to the muſcles thereabout, but are alſo ſent overthwart throught he *Peritoneum*, and muſcle of the *Abdomen*. The two laſt are by ſome called *Muſculæ ſuperiores* the upper muſcle-arteries, and are diſtinguiſht from the *Lumbares*. And theſe are the arteries, which if we obſerve, we ſhall eaſily give the reaſons of many things, of which Phyſicians do ſtill diſpute very hotly; but eſpecially of that moſt difficult queſtion, which is controverted among Phyſicians, by what ways, and in what manner the colick ends in a palſie or in the falling ſickneſs. For we have the obſervation in *Paulus Egineta lib.* 3. *c.* 43. where he ſays: the colick, as it were by a certain peſtilent contagion, ended with many in the falling ſickneſs, with others in a reſolution of the joints or palſie, their ſenſe remaining; and they who fell into the falling ſickneſs, for the moſt part died; but they who fell into the palſie, were moſt of them preſerved; the cauſe of the diſeaſe being carried to another place in the ſolution. For the humor that cauſed the diſeaſe, came back out of the colick gut through the meſenterical arteries, from whence being afterward tranſported into the trunk of the great Artery, it came alſo to the *Lumbares* or arteries of the loins, which ſwelling with blood preſt together the neighbouring nerves, from which came the palſie in the feet. And this we have often obſerved, as well in our ſelves, as in others, eſpecially in former years, when theſe diſeaſes at *Padua* were Epidemical. Yet the Pallie is not always a perfect one, but often (as I am wont to call it) imperfect, becauſe the power to walk is not wholly taken away, but the diſeaſed ſtand on their feet with a great deal of difficulty. Many at that time being deceived in the knowledge of the diſeaſe, miſtaking this for a great weakneſs of body contracted by their ſickneſs, endeavouring to take it away by eating and drinking largely, but in vain. This alſo is the cauſe, why the Falling-ſickneſs, and Lethargies too, as we have oft-times ſeen, follow after the Colick, becauſe the matter being ſent over from the Meſenterick arteries to thoſe of the loins, may eaſily go from them into the brain, to which thoſe very veſſels are carried.

Lumbares.

How the Colick diſeaſe ends in a Palſie or Epilepſie

But the trunk of the great artery, when it is come to the laſt rack-bone of the loins, having taken its journey all the way, which we have ſhewed, under the hollow-vein at the left ſide, here gets above the vein, leſt it ſhould be worn away in that continual motion by the hardneſs of the holy-bone. But it is divided, no otherwiſe than the hollow-vein is into two notable branches [S.S.] which are called by Anatomiſts the Iliacal arteries, from their ſituation, and being carried downwards obliquely to the thigh reſemble the Υ of the Greeks turned upſide down. But they alſo juſt like the Iliacal veins, to which they are exactly anſwering, before they be implanted into the thigh, ſhoot out a pretty number of branches. But from the lower ſide of the artery before the Iliacal branches be divided, iſſue forth *ſacræ* the holy arteries, [ϑ] which are notable ones, and carried downward, leaning upon the holy-bone, paſs through the holes thereof, and run to the marrow and backſide of the bone. And through theſe alſo there is a way for the matter, that makes the Colick to cauſe the Palſie of the legs.

Sacræ.

After this a little below the diviſion of the Trunk, the Iliacal arteries are ſubdivided into two branches, one of which is the inner and leſs, the other outer and greater. *The leſs and inner* [T] iſſues out two propagations, one from its outſide, the other from its inſide. *The outer* [ε] is commonly called *Muſcula*, by us more directly *Glutæa* the muſcle of the buttocks, becauſe it runs down with its name ſake vein, betwixt the holy and hip bones, where they part one from another, and ſcatters many twigs into the muſcles which lie upon the *Os Ilium*, or hanch-bone, called *Glutæi*, or the muſcles of the buttocks; becauſe they are the authors of them.

The inner is called *Hypogaſtrica* [ζ] which is very notable, and large, and being carried directly down to the lower ſide of the holy-bone, it affords certain propagations in men to the bottom and neck of the bladder, as alſo to the ſtrait gut, which alſo may be called the Hæmorrhoidal arteries; but in women; to whom this branch is ſomewhat larger, it diſtributes a great number of propagations, beſides thoſe to the forenamed parts, into the lower region alſo of the bottom of the womb, and likewiſe into its neck. Hence we may gather the reaſon, why, if the womb reach to the middle of the hip, Convulſions are cauſed, as *Hippocrates* witneſſeth, *lib. de natura muliebri*. As alſo if the womb fall down to the hip, why the monthly flowers are ſuppreſt, and a pain is cauſed in the ſoftneſs of the ſides, and in the loweſt belly. For the blood which nature drives to the womb, cannot be laid in there, the arteries being preſt together with the falling down of it; ſo that neceſſarily flowing back, it fills the neighbouring veins and arteries, which ſwelling up cauſe theſe pains, for we have oft-times ſeen in diſſections, theſe veins ſo ſwoln, that they have been ſeven fold bigger then themſelves. Hence alſo a reaſon may be given of the thirty ſecond Aphoriſm of the fifth ſection in the ſame *Hippocrates*, where he witneſſeth, that a woman vomiting blood is rid of her diſeaſe upon the iſſuing

The diviſion of the Iliacal arteries into an inner and outer branch.

1. *Glutea.*

2. *Hypogaſtrica.*

issuing forth of her Terms. Which happening by the consent of all, by revulsion or attraction of the humour to a contrary part, and that not by the benefit of the Veins, because the veins of the Stomach arise out of the Gate-vein, but they of the Womb from the hollow one; there is no other sympathy to be sought for, than that which is caused by the Arteries, especially when the Hypogastrick or Artery of the lower part of the lowest belly is not far distant from the Cœliacal, or Artery of the Stomach. Hence likewise a reason will be given of the Aphorism that follows this, wherein he judgeth the *Hæmorrhagia* or abundant issuing forth of bloud at the nostrils to be profitable when the monethly Courses do fail. The remaining part of the lesser Iliacal Artery descends, and brings forth the Umbilical or Navel Artery [ϖ], which is carried down near to the length of the great Artery, and is tied with strong membranes to the sides of the bladder of urine. But it looses its hollowness in those that are once out of the womb. After this [θ] like the Iliacal vein which is joined to it, it goes through the hole of the share-bone or *Os pubis*, which before it be past, it takes to it a propagation issued from the outer Iliacal branch, and so goes out of the hole, and being departed from it spends it self, in like manner as the inner Iliacal vein does upon the muscles; partly those with which the hole is stopt; and partly those which arise from the share-bone. At length being terminated at the middle almost of the length of the thigh, the end of it meets [ο], and is united with the ends of the branches [ι], of the inner Muscle-artery of the Leg, of which we shall speak in the next Chapter.

Arteria umbilicalis.

Propagations of the outer or greater Iliacal branch.

1. *Epigastrica*, or the Artery of the upper part of the lower belly.

Pudenda, or the Artery of the Privy Parts.

The *greater* or outer Iliacal artery [V] produces likewise two propagations, the first of which [i] is called *Epigastrica*, which arising from the outside of it, a little before it passes through the *Peritoneum* or rim of the belly, is reflected upward, and ascends by the inside of the strait muscle, till about the Navel it be inoculated with the descendent Mammary Artery. The other [λ] is called *Pudenda*, which is a little inner propagation, being not divided into so many branches, as the vein of that name is. But it arises presently after the Artery is gone out of the *Peritoneum*, and being carried overthwart along the commissure or joining together of the share-bones, is spent at the privy parts upon the skin of the Yard. That which remains of this Trunk, goes into the *crus* [X] whereof we shall now speak.

CHAP. IV.

The Propagations of the outer Iliacal branch, which are distributed through the Crus, *or great foot, containing the thigh, leg, and foot.*

The Trunk of the Crural Artery and its propagations ere it be divided.

After that the outer branch [V] hath propagated the fore-mentioned branches, it departs out of the *Peritonæum* or rim of the belly, and at the groin is carried into the *Crus*, by the same way which the crural vein takes, under which it goes, and is joined in company therewith every where, and so it makes the Trunk of the Crural Artery [X] (as we will always call it). But presently after it hath got beyond the *Peritonæum*, it issues forth a propagation from the out-side, which is called *Muscula cruralis exterior*, the outer Muscle Artery of the *Crus*, which being carried downward is propagated into the Muscles that cover the fore-side of the bone of the thigh. Sometimes over against this, but oftner a little below, yet on the in-side another is brought forth, called

1. 2. *Muscula cruralis interna*, the inner Muscle-artery of the *Crus* [ ] which is distributed in many branches through the third bending Muscle of the thigh, called *Triceps*, and those on the inside of the thigh, as far as the Knee; the ends of which branches are joined with the end of the inner Iliacal Artery, which we told you descends through the hole of the share-bones to the *Crus*. These propagations being dispatched away, the Crural Trunk descends from the Groin, together with the crural vein; and is so bent backward near to the bone of the thigh, that when it is come to the ham, it stands betwixt hindmost heads of the thigh. For prudent Nature does always observe this, to carry down the Vessels about that side of the joint where the bending is, lest if they should go on that side whereon the joint is extended, they should be compress. But in the very mid-way as it were, as it runs down through the thigh, it sends out a propagation [π] which breaking into more surcles, runs out through the Muscles that are seated on the back side of the thigh, together with the ham-vein, and at length descending through the ham (whence it is called *Poplitea* the ham-artery) is distributed with many

3. 4. sprigs into the Calf of the leg. But whilest it stays in the ham it sends out a propagation [ρρ] on each side to the sides of the joint of the Knee, which then sinking deeper, are consumed partly in the joint it self, partly upon the Muscles called *Gasterocnemii* that make the Calf; from whence they are called *Surales*, the Arteries of the Calf.

After that the Crural Trunk lies in the Ham [Y], it sends forth a propagation from its out-side [σ] which runs down near to the *Fibula* or lesser bone of the leg, and is hid betwixt the Muscle that moves the foot outward, and the second bending Muscle of the Instep, and distributes it self into the rest, that lie on the fore-part of the leg, as far as they are fleshy, and till they begin to be contorted by the outer ankle. A little under this same another Artery [τ] is brought forth out of the back-side of the Trunk, which runs down as far as to the mixing together of the tendons of the Calf-muscles. Then another [υ] issues out of the same back-side of the Trunk, but under the second, which descending and passing through the transverse ligament, runs down by the top of the foot, and is diffused into the Muscles that move the toes outward. The remainder [Γ] of the Trunk is carried downward by the back-side of the leg, and about the inner ankle offers a surcle [φ] to the foot, which goes to the muscle of the great toe, and creeps through the top of the foot. But the Trunk it self lying hid among the tendons of the Muscles of the toes is cut [χ] into two branches; of which the inner [ψ] bestows two surcles upon the great toe; two upon the fore toe, and one upon the middle; the outer [ω] two upon the little toe, and two upon the toes next to it, on the lower side. But although the progress of the Arteries be for the most part such, as we have described, yet what we have said formerly of the Veins, that their distribution varies much, not onely according to the diversity of bodies, but also of sides in the body of the same man, is true also of the Arteries, which in divers men are diversly distributed.

An

An Explanation of the TABLE *of the* ARTERIES.

This Table compriſes the Delineation of the great Artery, entire and free from all the Parts.

A *THe large beginning of the great Artery, where it iſſues out of the left ventricle of the heart: but preſently after its riſe, and before it yet falls out of the* Pericardium *or purſe of the heart, it*

a a *ſhoots forth the two Coronary Arteries* a a, *which incompaſs the baſis of the heart in manner of a Crown.*

But preſently having paſt the Pericardium, *it is divided* B *into two trunks; one*

B C *of which is the aſcendent* C, *the other the deſcendent one* Q.

DD *The Aſcendent trunk* C, *is by and by divided into the two ſubclavian Arteries* D D, *both which when they have attained to the firſt rib, ſcatter many propagations, partly from the higher partly from the lower ſide.*

From the lower ſide iſſues Intercoſtalis

b ſuperior, *the upper Artery between the ribs* b, *communicating particular twigs to the diſtances of the four upper ribs.*

From the higher ſide iſſue three. The firſt

c *is* Vertebralis, *the Artery of the rack-bones* c, *creeping on by the tranſverſe proceſſes of the rack-bones of the neck, as far as to the ſkull. The ſecond* mammaria, *the Artery of the*

d *dugs* d, *which deſcending under the breſt bone, runs out as far as to the ſeat of the navel, and diſtributes ſprigs into the diſtances of the griſtles of the true ribs, and then into the muſcles that lie upon the breſt; at length about the navel it joins by* anaſtomoſis *or inoculatoon* x, *with the aſcending* Epigaſtrick *Artery* 1. *The third* Cervicalis, *or the Artery of the back ſide of the*

e *neck* e, *is propagated to the muſcles on the back ſide of the neck, as far as the nowl of the head.*

Theſe branches being iſſued out, the ſubclavian Artery goes to the arm-pit, and takes

E *the name of* Axillaris *about* E, *and ſo is diffuſed into the arm. Yet before it enters thereinto, it ſhoots out ſome twigs from both parts of it: from the lower three, of which*

f *the firſt* f, *is called* Scapularis interna *the inner blade Artery, becauſe it is ſpent upon the muſcles that cover the hollow ſide of the ſhoulder-blade. The ſecond is* Thoracica

g ſuperior, *the upper cheſt Artery* g, *diſperſed into the muſcles on the foreſide of the cheſt.*

h *The third* h, Thoracica inferior, *the lower Artery of the cheſt, which deſcending along the ſides of the cheſt, is inſerted into the muſcle called* Aniſcalptor, *that moves the upper part of the arm backward. Betwixt* g *and* h, *a little branch is placed, one of them which here are diſſeminated into the glandules of the arm-pit. From the upper part*

i *iſſues one* i, *called* ſcapularis externa, *the outer-blade Artery, being diſpoſed of into the*

FF *muſcles, on the outſide of the ſhoulder-blade.*

In this place the axillary Artery changes

G *its name, and is called* Brachialis, *the trunk of the Arm that is undivided as far as* G,

l m *ſcattering two twigs* l *and* m *into the muſcles that cover the bone of the upper part of the*

n n *arm on the back ſide; and two other* n n, *one of each ſide about the bending of the cubit.*

The parting in twain of the Brachial Artery under the bough of the cubit, into an

H I *outer* H, *and inner branch* I.

The outer branch of this diviſion, or Radius, *running ſtraight along the* Radius *or*

o *leſſer bone of the cubit to the wriſt, and diſtributing a branch* o *into the muſcles ſeated betwixt the firſt bone of the thumb and that of the* metacarpium *or after-wriſt, which ſuſtains the fore-finger, and then three other*

p p p *p p p; which are diſperſed into the firſt outer fingers, the thumb and the two fingers next thereunto.*

I *The inner branch or* Cubiteus *paſſing along the greater bone of the cubit, is at length conſumed in a double branch upon the two inner fingers, the ring-finger and the little one.*

L *The remaining part of the Aſcendent*

M M *trunk, which near to the upper part of the breſt-bone is cleft into two branches* M M *called* Carotides, *or the ſleepy arteries. Theſe tend directly upward by the ſides of the neck, and being come to the chops are divided into*

N O *two branches about* N, *one of which is the outer* O, *the other the inner* P.

† *The outer* Carotis *propagates twigs* † *to the* Buccæ *or cheek puffs, and to the muſcles of the face; but about the ear it is cut into*

q *two branches, a foremoſt one* q, *which is carried through the Temples; and a hinder one*

r r, *that is diſſeminated along the back ſide of the ear under the ſkin.*

P *The inner* Carotis, *going to the ſkull is*

ſ *divided near to the baſis thereof into two branches; of which the one and leſſer* ſ, *which goes into the* ſinus *on the ſide of the thick membrane, is cut off here, whereabout it ſinks*

t *into the ſkull: the other and greater* t *enters the ſkull through a peculiar hole bored for it in the temple bone.*

Q *The Deſcendent Trunk of the great Artery, reaching downward to the rack-bones of the back.*

From this before its diviſion at R, *many propagations are ſcattered, which we will now rehearſe in order.*

u u u *Firſt then are* Intercoſtales inferiores, *the lower arteries between the ribs* u u u, *diſtributed to the diſtances of the eight lower ribs, from which propagations are brought to the marrow of the back-bone, and to the muſcles that grow to the back and cheſt. After this the trunk paſſing on, diſtributes two*

x x *more, called* Phrenicæ, *the arteries of the midriff* x x, *becauſe they are diſpoſed of into the midriff. Then follows,* Cœliaca *or the ſtomach-artery. After that,* Meſenterica ſu-

y perior, *the upper artery of the Meſentery* y, *reaching out into the Guts* Jejunum *and*

. Ileum, *as alſo into that part of the* Colon *which reaches from the hollow of the Liver as far as the right Kidney. After this the*

z Emulgent Arteries z, *propagated to the*

kidnies. Then Spermaticæ, the Seed Arteries
α ries α, going to the teſticles, under which is
Meſenterica inferior, the lower Artery of
β the Meſentery β, departing into the left ſide
of the Colick, and into the ſtrait gut, and
γγγ making the hæmorrhoidal Arteries. Laſtly,
Lumbares, the Arteries of the loins γ γ γ,
which going to the rack-bones of the loins
joint by joint, are diſtributed into the peritoneum
or rim of the belly, and the muſcles
growing to the rack-bones.

R These branches being iſſued forth, the
trunk about the fifth rack-bone of the loins is
SS divided into two branches S S, called the Iliacal, both which are again broken into two
other, an inner branch T, and an outer one V.
But before this diviſion in the very parting in
twain of the trunk, ariſes ſacra, the holy
δ Artery δ, diſtributed into the holes of the Os
ſacrum, or holy bone, to the marrow thereof.

T The inner Iliacal Artery before it falls out
of the peritoneum, iſſues forth two propagations: from its outer ſide, that called Glu-
ε tæa ε, diſtributed into the muſcles of the but-
tocks; from its inner ſide, that called Hypo-
ζ gaſtrica ζ, going into the bladder and yard,
and in women alſo to the bottom of the womb.
After this it runs down, and ſends forth the
ηη umbilical arteries η η, that tend upward near
to the length of the great artery. The re-
θ mainder θ, taking to it a propagation from
the outer Iliacal Artery, ſlips down through
the hole of the ſhare-bone into the Crus, the
end of it joining about ο, with the inner muſcle
artery of the Crus ν.

V The outer Iliacal Artery likewiſe before it
is going forth of the peritoneum, produces
ι two. The firſt is called Epigaſtrica ι, digeſted into the muſcles of the Epigaſtrium, and
the ſtraight ones of the Abdomen, where it is
κ joined by inoculation κ, with the deſcending
mammary artery d. The other called Pu-
λ denda λ, goes to the privy parts.

X In this place the outer Iliacal artery having paſt the Peritoneum, enters the Crus,
and begins to be called the Crural Trunk,
which iſſues out more propagations. The
firſt is Muſcula cruralis exterior, the outer
μ muſcle artery of the Crus μ, that is propagated into the muſcles that cover the foreſide of
the thigh bone. The ſecond is the inner
ν muſcle artery of the Crus ν, digeſted through
the third bending muſcle of the thigh; and
thoſe muſcles that are on the inſide of the
thigh; the ends of it are joined with the ends
ο of the inner Iliacal artery about ο. The third
π is Poplitea, the ham-artery π, running out
into the muſcles, on the back ſide of the thigh.

ρρ The fourth is Suralis, the calf artery ρ ρ,
which is double, iſſuing out there, where the
crural trunk is hid betwixt the two lower
heads of the thigh, and ſpreading out on both
ſides into the joint of the knee, and the two
heads of the firſt extending muſcle of the
foot.

Y Here the great artery lies in the ham, where
it is divided into branches of unequal bigneſs.

σ A ſprig iſſuing from its out-ſide, and
reacht out to the fibula or leſſer bone of the
leg, betwixt the muſcle that moves the foot
outward, and the ſecond bending one of the
inſtep.

Z The trunk deſcending by the back ſide of
the leg.

τ A higher branch iſſuing out of the back
ſide of the trunk.

υ A lower branch iſſuing out of the back
ſide of the trunk.

Γ The remainder of the trunk deſcending by
φ the leg, which offers a little branch φ to the
inner ankle.

χ The diviſion of the trunk χ, into an inner
ψ branch ψ, that is propagated to the great toe,
ω and the two next; and an outer ω, propagated to the little toe, and the two next to that.

The



TRACT. III.
CONCERNING THE NERVES.

CHAP. I.

Of the Nerves of the Brain.

AMong those eight Conjugations which arise from the Marrow of the Brain drawn out in length, whilest it is yet contained within the limits of the skull, that offers it self in the first place, which makes the *Optick Nerves*, that are so famous among all the Masters of Anatomy. For these are not onely the biggest, if thou look upon their thickness; but also without doubt the softest of all the Nerves of the body. But they arise out of the middle of the *basis* of the brain, on the fore-part, according to the opinion of the Ancients, but indeed, if the head be turned upside down in the dissection (which is the proper way) out of the beginning of the former trunks of the spinal marrow, that their original is as it were in the back part of the head, and presently each of them by little and little making towards its mate, they are united (not onely joined, as some would have it) over the saddle of the wedge-bone, and making one common square body, the marrow within them being mixed together. After that presently separating again, each of them is carried obliquely into the eye of its own side, entering the orb thereof through the first hole of the wedge-bone, and entering at the very centre of the eye. In this pair we may easily shew those two membranes, which are derived to the Nerves from the two Meninges of the Brain, as also the very inner marrowy substance, which comes from the body of the Brain. Yet the Nerve it self is not cleft into more branches, (as the other are) but lying hid makes the coats of the eye; and out of the thick membrane it forms that coat which is called *Cornea*, the horny one; out of the thin membrane that is called *Uvea*, the Grapy one; but out of the substance of the marrow the *Retina*, or Coat like a Net. For as soon as it is arrived at the centre of the eye, these membranes are displayed, and making a sphere contain the humours in them. These Nerves convey the faculty of seeing to the eyes; wherefore, they being obstructed, or compress, a blindness ensues. *Galen* hath ascribed holes to them, and *Herophilus* for the same reason called them Πόρος Ὀπτικὸς, the passages of the sight, teaching that there is a sensible hollowness plainly to be seen in them, whom for all that almost all Anatomists do contradict. But I have heretofore shewed in the University of *Padua*, and in a great Assembly of them, that there are certain passages continuing from the beginning of these Nerves, as far as to the place where they meet together, and presently after that vanish away toward the eye. And therefore I shewed that the Ancients may not onely be excused, but also that they writ the truth, especially when none of them have said that these passages were great, but onely such as did not altogether escape the sight, if one would make trial thereof in a great living creature, and by a clear light, and presently after it is killed. For *Galen* himself requires these three conditions, 7. *placit.* 4. and *lib. de oculis*, that one may see them. But before we depart hence, I will bring in some Problems, that besides the History it self, I may also shew the use of that which I say, especially when in our time they onely for the most part follow the study of Anatomy, who imploy their industry in the behalf of Physick. The first therefore shall be, what is the cause that many upon sneezing often (especially when they have provoked it for the nonce) have of a sudden fallen blind. This happens, either because the branches of the sleepy Arteries, which are so near to the Optick Nerves, that they touch, are filled, and being so, press together those Nerves; or else because a copious, and that a phlegmatick humour hath fallen out of the brain into the Optick Nerves, and obstructed them. I have seen those that have been blind through the first cause, sometimes cured by a Seton; But I never remember that any, in whom this arose from phlegmatick humours, have recovered, except one having the French Pox, who being anointed with Quicksilver, all the humors melting away, was restored to health. But it is not the part of a good and pious Physician to make use of those things, which being full of danger, may do more harm, if they prove hurtful, than they can procure good, if they be profitable. And truly it is better not to cure blindness, than to cause death, although often-times Rashness helps them, whom Reason helps not, as the most elegant of Physicians *Celsus* says elegantly. In the mean time in diseases of the eyes, they who practise Physick, may learn rather to administer those things which bring the phlegm out by the Palat, then to draw the noxious humours to the nostrils. That I may conceal besides the danger which they avoid, that more profit arises from the Medicins that void the phlegm out of the head through the mouth, which both long experience hath hitherto taught, and Anatomy persuades, when the Optick Nerves in their original are not far distant from the palat, but farther from the spongy bone; and it is a preternatural way, by which the humours are carried, as hath been already demonstrated by the learned *Vesalius*. Then it is disputed by what means the Eye can fall out of its orb, the Optick Nerve not being broke, whereof we may have very many histories. But it is not hard to give an answer, to wit, that the Nerves may be very much extended in length. Whilest therefore this Nerve receives much moisture in the inflammations of the eyes, it easily comes to pass that it is slackned; but the muscles themselves

The first part of the brain.

Its original.

Progress.

Insertion.

use.

The holes of the Optick Nerves.

Problems

1

2

ſwelling very much, when they can no longer be contained in the orb, leap forth out of it. For this falling forth of the eyes moſt commonly proceeds from inflammations: ſuch as are the ſtories of
3. the moſt learned *Vega*, who cured a Woman in this caſe by procuring the flux of the terms, and a young man by digeſting Ointments. But the queſtion is very worthy to be made mention of, and that gives me an occaſion to explain it, which I have read in ſome Authors, that ſuch as were before blind, upon receiving of a wound overthwart the fore-head, and ſome upon a great looſneſs of the belly ariſing on a ſudden, have received their ſight, and that preſently. The cauſe of their blindneſs was no other than the compreſſion of theſe Nerves proceeding from the neighbour-veſſels, to wit, the Veins and Arteries being ſwollen with bloud, which ſuch a wound preſently emptied. Wherefore I alſo ſometimes, and not without ſucceſs in that *ſpecies* of blindneſs which the Barbarians call *Gutta ſerena*, open the middle vein of the fore-head, out of which I draw bloud ſo long, till it ceaſes to run of its own accord.

The ſecond pair. Its original. The ſecond pair ariſes, as the ancient Anatomiſts ſay, from the ſides of the *baſis* of the fore-part of the brain, near to the original of the firſt pair. But the new diſſection ſhews, that it iſſues out at the inſide of the beginning of the ſpinal marrow, and that they are ſo united in their original, that they make one common angle, which is the cauſe why both the eyes are moved together to the ſame ſides. It is much ſmaller, if you compare it with the firſt pair, and harder, and goes out of the skull through the ſecond hole of the wedge-bone, which is ſomewhat long, and ſo it enters into the orb of the eye. By and by it is divided into many ſprigs, which go to the muſcle of the eye; and the firſt climbing up above the firſt pair or the Optick Nerves, is diſpoſed of into the two muſcles, as well that which lifts up the eye-lid, as that which lifts up the eye. Another very conſpicuous one is diſſeminated in many ſurcles into the muſcle which moves the eye inward. The third, no contemptible one neither, being divided firſt into two fibres, and by and by into more, is ſent into the muſcle that draws down the eye. The fourth, into the lower or leſſer of the oblique muſcle that rowls the eye about toward the outer angle; at length it iſſues out ſome thin fibres, which being joined with the firſt pair are diſtributed to the outer membranes of the eye, ſo that this ſecond pair is propagated onely to four muſcles of the eye, and to that which lifts up the eye-lid.

Branches. 1. 2. 3.

uſe. The uſe of this pair is to impart the faculty of motion to the muſcles of the eyes.

The third pair. Its original. Branches. 1. The third pair ariſes with a very ſmall Nerve out of the lower, and hinder part of the marrow of the brain, and runs directly forward under the *baſis* of the brain, being tied to the ſecond conjugation; together with which it enters into the Orb of the eye through the ſaid ſecond hole of the wedge-bone. By and by it is divided into four branches, of which the firſt offers a little branch to the upper and greater of the oblique muſcles of the eye, or that called the muſcle of the Pulley, and then falling out through the hole of the fore-head bone above the orb of the eye, in the skin and muſcle of the fore-head, which ought rather to be called the muſcle of the eye-brows. This

An obſervation. branch is diligently to be taken notice of; becauſe I have long ſince obſerved, that it being hurt with a ſlight wound, the eye-lid fell down, whileſt the muſcle of the eye-brow by reaſon thereof fell into a Palſie. I have ſeen alſo the ſame Palſie cauſed by cold and narcotick Medicins, ſomewhat unreaſonably applied for the procuring of ſleep. But hence alſo a reaſon may be rendered, why *Hippocrates*, *Prognoſtick* 1. reckons it among the ſigns of death in acute diſeaſes to ſleep with the eyes half open. For this is an ill ſign for that reaſon, becauſe it ſignifies that the Nerves are very much dried, and ſo the brain it ſelf, whence it comes to paſs that they who are ſo diſeaſed, for the moſt part ſuffering Convulſions afterward die. In ſome alſo a fore-runner of the Falling-ſickneſs is wont to ariſe from the ſame cauſe in the eye-lids, the eyes and the whole face, when this third pair is pluckt by the humours begetting the Falling-ſickneſs, and ſo a convulſion of the eyes and face is
2. cauſed. The ſecond branch is carried downward, and falls out through the hole of the fourth bone of the upper Jaw, which is under the orb of the eye, and preſently ſcattering into more propagations on the fore-part of the face, is ſpent upon the muſcles that move the upper lip and wing of the noſe outward, as alſo upon the lip it ſelf, and the gums of the teeth, called *Inciſorii*, or ſhredders. The third is ſent through the hole of the ſecond bone of the upper Jaw, behind the caruncle that is placed in the inner angle of the eye, to the wide cavity of the noſtrils, being ſpread throughout its coat, whereby it comes to paſs that it is endued with a very ſharp ſenſe, and being but lightly toucht cauſes ſneezing. The fourth goes out through that creviſe which is betwixt the firſt bone of the upper jaw and the wedge-bone, in the outer angle of the eye, or through the fourth hole of the wedge-

uſe. bone, and departs to the inner ſide of the temporal muſcle. The uſe of this pair is to convey the faculty of moving to the ſaid muſcles.

The fourth pair. Its original branches. 1. The fourth pair ariſes out of the marrow of the brain on the back ſide, goes out of the skull through the ſixth hole of the wedge-bone, and running ſtrait down, propagates three branches from it ſelf. The firſt is preſently after its going out of the skull, which being writhed ſometimes about in the manner of the tendrels of a Vein or Gourd, and united to two ſprigs of the auditory Nerve (of which we are to ſpeak next) afterwards diſtributes ſurcles to the temporal muſcle that lifts up the lower jaw, and that which moves it forward from the head, as alſo to the muſcles of the cheeks. After this the pair running farther down, iſſues forth a ſecond branch, which propagates ſurcles in order to the gums of the upper cheek-teeth called the grinders, and alſo to the teeth themſelves. The third branch iſſuing forth from the back-ſide of the Nerve, and entering the hole of the lower jaw-bone that is bored in the inner ſurface of it, at the original of the proceſſes, beſtows little branches in order to the roots of the teeth, and at length going forth through the fore-moſt hole in the outer ſurface is terminated in the lower lip, and skin of it. The remainder of this Nerve is ſpent upon the coat of the tongue near to the root, and gives it the power of diſtinguiſhing ſapors or taſting.

A Note. But note in this place, that theſe two pairs which we have now recounted, I ſay, the third and fourth are commonly reckoned for one by Anatomiſts, and that the third; but with this diſtinction, that they ſay this very pair ariſes with a double root; the one ſmaller, and the other thicker. They call

call that the ſmaller root, which we ſet down for the third pair; that the thicker, which we make the fourth. But we diſtinguiſh them, becauſe indeed they are not joined together, neither in their original, nor in their progreſs. But that which they account for the fourth pair, ſeems not to be diſtinguiſhed from the third; as *Valuerda* himſelf grants, *lib.7. Anatom.cap.4.*

The fifth pair iſſues out of the marrow of the brain drawn out in length, on that ſide whereon a part of the *cerebellum* or after-brain is joined to it, ariſing out of two Nerves, of which the one is ſofter, the other harder. Theſe go out of the membrane together, and enter the organs of hearing through the hole of the temple bone, that is bored in the ſtony proceſs thereof, being a large one and winding. After this that harder part goes forthwith to the fore-ſide, being carried through a peculiar channel, and returns backward again obliquely through the ſame bone, and departs into the firſt cavity of the inner ear. From thence being more reflected, it ſends forth two propagations, one higher, the other lower; but both paſs through their peculiar holes. The upper is carried through the tranſverſe hole of the ſame bone, through which alſo a little vein paſſes into the organ of hearing; and a little after it is come forth of it, it is joined with that branch of the fourth pair (as we have delivered, but as others commonly count the pairs of the third) which we told you was writhed about, like the tendrel of a Vine. The lower goes out through the third hole of the ſame bone, which is very narrow and winding; and being carried overthwart above the muſcle of the lower jaw, that moves it ſidewards, deſcends into the chops, having diſſeminated a pretty many propagations into the noſtrils. But forthwith it is joined with the propagation of the fourth pair, that reſembles the tendrel of a Vine, or that ſprig which goes to the tongue, from which it paſſes to the roots of the teeth and muſcles of the cheeks, as alſo to the skin that goes about the root of the outer, or little ear. Anatomiſts do believe, that by the means of the branch it comes to paſs, that they who are born deaf, are for the moſt part dumb alſo. But that ſofter part of this pair is carried together with the hard part; and when it is come to that firſt cavity of the inner ear, it is ſpread throughout it in manner of a membrane, and ſo it deſerves to be called the Auditory Nerve, as miniſtring all the ſpirits that ſerve for hearing.

The fifth pair. Its original. Its two parts. The harder. The ſoft part. Its uſe.

The ſixth pair ariſes ſomewhat more toward the lower and hinder part than the fifth, and not with one, but with many little Nerves ſevered from each other, which for all that are preſently joined together, although they do not cloſe ſo as to make one onely, but two diſtinct ones always, yet are they contained in one membrane, ariſing from the *Dura meninx* of the brain, which hath deceived many, ſo that they have accounted them for one. Being thus joined, they deſcend both together out of the skull, through the ſecond and third hole of the nowl bone; through which ſame the leſſer branch of the ſleepy Artery, and the greater of the Jugular vein enter into the skull. There being then two Nerves, the one in its egreſs inclines more to the fore-part of the ſaid hole, and is the leſſer of the two; the other to the hinder part, and is the greater. That preſently after its going forth of the skull, tends ſtraight downward to the muſcles of the tongue and chops, and to the parts placed in the mouth, upon which it is wholly conſumed.

The ſixth pair. Its original. The leſſer Nerve.

This on the contrary ſends its firſt propagation to the muſcles ſeated on the back ſide of the neck, eſpecially to the firſt muſcle of the ſhoulder-blade, called *Cucullaris* or the Cowl-muſcle, and then adhering to the ſeventh pair, and the aforeſaid Artery and Vein, by the benefit of certain membranes, it runs down to the ſide of the throttle, to whoſe muſcles, eſpecially thoſe ſeated in the inner cavity, it diſtributes ſurcles overthwart. Here many propagations of Nerves meeting together, and parting aſunder again, a certain texture is made, wherein knots are found not unlike to the glandules that are tied to the divarications of the veſſels; which was firſt obſerved by the moſt learned Anatomiſt *Fallopius*, who would have it reſemble the body of one alive. But the greater Nerve it ſelf going into the middle betwixt thoſe ſame veſſels which I ſpake of, is carried leiſurely from the throttle to the rough Artery, and running down at the ſide thereof, tends to the cheſt.

The greater Nerve, and its propagations.

But before it enters thereinto, it is divided over the hollow of the neck into two branches, of which one is the outer and leſs, the other the inner and greater. We ſhall now ſpeak briefly of the diſtribution and propagations of them, but ſo that being the right Trunk is diſſeminated into another manner than the left, we ſet down the Hiſtory of each by it ſelf; and firſt of the right, then of the left.

The branches of the greater Nerve.

The outer branch then of the right Nerve ſends out propagations preſently after the diviſion to the muſcle that bends the head, called *Maſtoideus*, as alſo to that of the bone *hyoides*, called *ſterno-hyoides*, and that of the *Larinx* or throttle, called *ſternothyroides*; after this it enters the cavity of the cheſt, and when it comes to the Axillary Artery, iſſues forth from its inſide ſometimes three, ſometimes two ſurcles, one under another, which are turned about the ſaid Axillary Artery, as it were an axel-tree, or (to ſay truly) a kind of pulley, and cloſing together make one Nerve, which being faſtned to the right ſide of the rough Artery, by the benefit of a membrane, runs back from the lower part thereof to the higheſt, and haſtes to the right ſide of the throttle, leaning upon a glandule which is placed at the root of the right ſide. Having paſt this, it is forthwith divided into many ſurcles, which are ſpent upon the muſcles of their own ſide, which are placed in the throttle, and have their heads downward, giving motion to them. And this Nerve is called *Recurrens*, the returning one from its progreſs, and is very famous among all, being ſo made by skilful Nature with great wiſdom, that it might be inſerted into the muſcles of the throttle, whoſe heads look downward, when all the Nerves that give motion, ought to be inſerted into the heads, and to look towards the end, not on the contrary. And becauſe the throttle is an organ of the voice, but the voice cannot be uttered without motion of the muſcles, that either open the cartilages of the throttle, or ſhut them; therefore theſe Nerves, which impart to the muſcles the power of moving and contracting themſelves, being either bound hard or cut off, it happens for that cauſe, that the voice is taken away. This may be very handſomely ſhewn in Dogs, or in a Hog, becauſe one continually makes a noiſe with barking, the other with grunting.

The propagations of the outer branch of the right Nerve.

1.

2.

The right recurrent nerve.

For

For one of theſe Nerves being cut off, half the voice is taken away; but both being cut, it is wholly loſt. The recurrent propagation being thus conſtituted, the outer branch running down obliquely
3. under the hollow of the neck, after that by the way it hath diſtributed ſurcles of an indifferent big-
4. neſs into the *Pleura*, or membrane of the ribs, and into the coat of the lungs, and given others to the
5. *pericardium* or purſe of the heart, and to the heart it ſelf, it deſcends farther within the duplication of the *mediaſtinum*, and near to the rack-bones is divided into two branches, which make the right Nerve of the left orifice of the ſtomach, are carried obliquely, and then piercing through the midriff, together with the gullet, to which for all that they afford never a branch, are conſumed upon the left orifice of the ſtomach, with many branches like a little Net, and ſo encompaſs it together with the left Nerve, that it ſeems wholly to conſiſt of Nerves. Hence there is ſo great a ſympathy of the ſtomach, not onely with the brain but with the heart alſo; that ſuch diſeaſes as pain the upper orifice, ſeem to be of the heart, and indeed ſo they are, the ſame heart ſuffering pain, beauſe of this Nerve being pained. And this is the true cauſe, to wit, the communion of this Nerve, not the nearneſs of both the entrails, as others ſay. The inner branch goes to the inner ſide of the root of the first rib of the cheſt, and cleaving to the Rack-bones under the *Pleura*, runs down through the roots of the reſt of the ribs, taking to it a little branch from every one of the intercoſtal Nerves that iſſue out of the back bone; then paſſing through the midriff with the Deſcendent Trunk of the great Artery it is carried as far as to the *Os ſacrum* or great bone, at the region whereof it iſſues out three propagations, which are diſtributed into the natural inner parts. The firſt goes to the lower membrane of the Kall, and deſcending through it is parted into three little branches, of which one is diſtributed to the right ſide of the ſame membrane, and to that part of the Colick gut that is joined into it: Another the leaſt of them, and a very ſmall one, to the guts *duodenum* and the *jejunum* about its beginning: the third to the bottom of the ſtomach on the right ſide, and to the upper membrane of the Kall, which is ſomething the larger. That which remains of this propagation
2. is ſpent upon the hollow part of the Liver and the bladder of Gall. The ſecond goes into the
3. right kidney, and the membrane thereof. The third, which is greater than either of the former, deſcending to the firſt rack-bone of the loins, reaches into the right ſide of the Meſentery and into the Guts that are tied thereto entering the center of the Meſentery in company of an Artery and a Vein. The remainder goes into the bladder, and in Women into the right ſide of the bottom of the Womb. But the outer branch of the left Nerve ſaving that in its deſcent it hath offered ſprigs both to the *Pleura*, or membrane inveſting the rib, and to the coat of the lungs, and that outwardly, as alſo to the purſe of the heart, and heart it ſelf inwardly, at that part of the Deſcendent Trunk of the great Artery, where it firſt iſſues out of the heart, and is bowed to the back bone, it ſends forth three ſurcles which returning to the ſaid Artery cloſe together into one Nerve, which is called *ſiniſter recurrens nervus*, the left returning Nerve, and in like manner as the right one, takes its progreſs upward, and is propagated into the muſcles of the *Larinx*, or throttle. After this it iſſues out a ſmall ſprig, which is diſtributed through the *baſis* of the heart, and coat of it in manner of hairs. Afterward the remainder deſcends inclining it ſelf obliquely to the right, and goes to the upper orifice of the Stomach, in the right ſide whereof it is diffuſed, as the right branch was before into the left ſide, being divided into many little branches in manner of a Net. From this a ſurcle is carried down along the upper part of the Stomach to the *Pylorus*, or lower orifice, which when it hath as it were interwoven with ſome ſprigs, it goes into the hollow of the Liver. The inner branch firſt of all takes to it propagations from the intercoſtal Nerves, and then paſſing through the midriff is divided into three. The firſt of them goes overthwart to the Spleen, and in the way ſhoots out two ſprigs; one, which is likewiſe ſent into the lower membrane of the Kall and part of the Colick gut, which is tied thereto; another into the left ſide of the bot-
1. tom of the ſtomach, and into the upper membrane of the Kall. The ſecond propagation goes
2. into the left ſide of the Meſentery, and the guts of that place; ſometimes alſo it iſſues ſprigs, which run out with the ſeminary veſſels through the proceſſes of the *Peritoneum*, or rim of the belly to the
3. teſticles. The third goes to the left Kidney, and the fat membrane thereof. The remainder of the
uſe. branch paſſes to the left ſide of the bladder and of the bottom of the Womb. The uſe of this pair is manifeſt enough, as being very notorious, when the outer branch beſtows little boughs upon the middle bowels, but the inner upon all thoſe of the loweſt belly, and the right branch upon thoſe of the right ſide, the left on thoſe of the left. Beſides this uſe it conduces by the returning branches alſo to the framing of the voice, by imparting the faculty of motion to the muſcles of the throttle.

The ſeventh pair. Its original. The ſeventh pair ariſes in the utmoſt part of the nowl-bone, where the marrow of the brain is ready to go out of the skull, and ſo is counted the hardeſt of all the Nerves that have their original within the skull. But it ariſes in ſome roots ſeparated from each other, which joining together on both ſides into one, it goes out of the skull through the fourth and fifth holes of the nowl-bone (which are planted betwixt that greateſt one, which opens a way for the deſcent of the ſpinal marrow, and that, at which the ſixth pair goes out) and preſently after its egreſs is involved in one common membrane with the ſixth pair, whence ſome not ſo diligently obſerving it, have believed that they were mixed one with another; and thus they deſcend together. When it comes to the root of the tongue, it diſtributes ſurcles into all the muſcles thereof, ſending over ſome alſo to certain muſcles of the bone *hyoides*, and of the throttle, as alſo to thoſe which take their beginning from the *appendix* called *ſtyloides*. The uſe of this conjugation is to carry down the faculty of ſenſe and motion from the brain to the muſcles of the tongue.

Its uſe.

The eighth pair. Its original. To theſe ſeven pairs, which are commonly ſo numbred, we add an eighth, which makes the Nerves of Smelling, by which a faculty is derived from the brain of apprehending the odors of things without. Theſe are commonly affirmed to ariſe out of the marrowy ſubſtance of the brain, in the *baſis* thereof, near to the firſt pair; but the new diſſection of the brain, and which is performed

performed by turning it upside down, hath taught us that they arise at the utmost sides of the brain, in that part which is above the holes of the ears, whereby it is manifest, that hitherto onely one half of them hath been shewn. They are very sharp at their original, and distant one from the other, but going forward by degrees, betwixt the uppermost and middle prominence of the brain, they grow thicker, and draw nearer one to another, and so at length they lie down above the *sinus* or cavities of the spongy bone within the skull. These are thrust into the mammillary processes of the brain: but *Galen* and *Marinus* (whom almost all Anatomists have followed) would not call them by the name of Nerves, although they altogether agree therewith in their colour, course, and use, because they neither have productions like the rest of the nerves, nor go out of the cavity of the skull: but truly they seem to me to commit no other a sophism than they who have expelled the teeth out of the number of the Bones, because they are not invested on the out-side with a membrane, as others are, although neither this makes any thing to the essence of the Bones, nor that to the essence of the Nerves.

CHAP. II.

Concerning the Nerves of the Spinal Marrow, properly so called, and first of those of the Rack-bones of the Neck.

The Spinal Marrow.

NAture, the wise Parent of all things, as she hath framed the Nerves, that they might serve for the carrying of the faculties and spirits that are generated in the brain, because the brain it self could not be diffused through the whole body: so when the same could not conveniently bestow Nerves upon all the parts, by reason of their too great distance, she made the Spinal Marrow, which is nothing else but the marrow of the after-brain and brain, extended through the long Conduit-pipe of the Rack-bones of the back. And therefore we having already viewed those Nerves which take their original from the marrow of the brain, whilest it is yet contained in the skull; it remains now that we take a view of them also which come from the spondyls of the Back-bone: But it is called Marrow, not that it hath any affinity by reason of its substance with the marrow of the bones, but because like Marrow it is contained within the Rack-bones; but the substance thereof is like that of the brain, which it self also *Plato* called Marrow; and it is named also the Spinal Marrow, or of the Back, to distinguish it from both those that are contained in the Back-bone, but either in the skull, as the brain, or in the hollowness of the bones, as that which is properly called Marrow. This substance is covered with two membranes, no otherwise than the brain it self is, from whence it takes its original, the one thick, the other thinner, which are invested with a certain third strong and membranous covering, that *Galen* thought to be the ligament of the Rack-bones. But it was made to that end, that it might distribute sense and motion to the Muscles and Membranes, to which those pairs of the brain do not reach. Therefore when there is a good number of Nerves arising therefrom, yet we shall easily reduce them to some certain *Classes* or Companies, if we say that they all make up thirty pairs, of which seven belong to the marrow whilest it is carried through the Rack-bones of the Neck; twelve whilest it is carried through those of the chest; five through those of the loins; and lastly, six to that which is contained in the holes of the *Os sacrum*, or great bone. But these Nerves go out through the holes of the Rack-bones, and either with a double original on the fore and hinder part, as it happens in the two first conjugations of the neck, and five of the great bone, which arise not from the sides, that is, from the right or left part, but issue forth two branches before and behind; or else with a single one, through the hole bored in both sides of the Rack-bones, as happens in all the rest of the pairs, in which one Nerve issues from the right side, the other from the left. But the first and second pair have a double beginning, lest if they should arise with a single one, that being somewhat thicker might have been hurt by the joints of the Rack-bones; or if the hole should be made larger, the Rack-bone (which was small enough of it self) should be liable to breaking. Therefore that both these evils might be avoided, the wise Opificer made a double beginning, one on the fore-part, another on the hinder. But the right branches go every where to the right side, the left to the left, and they are distributed on both sides after the same manner.

Why it is called Marrow.

It is wrapt up into two Membranes.

The Conjugations or Pairs of the Spinal Marrow.

The first Pair thereof [*tab.*1.*n.*1.] arises with its first and foremost propagation [*tab.*1.B] from the fore-part of the Spinal Marrow, and passes out betwixt the nowl-bone, and the first rack-bone of the neck, near to the sides of that round ligament, wherewith the Tooth-like process of the second rack-bone is tied to the fore-side of the nowl-bone, and so it is distributed into the Muscles over the neck and under the gullet that bend the neck. With the other and hinder propagation, [*tab.*2.*fig.*1.C] it likewise falls out through the hole, that is common to the nowl-bone, and first rack-bone of the neck, towards the hinder part, but with a double sprig, one of which being small is spent upon the lesser strait muscles and the upper oblique ones that extend the head; the other reaches out into the beginning of the muscle which lifts up the Shoulder-blade

The first pair of the neck.

The second pair [*tab.*1.2.] with its fore-branch [*tab.*1.D] (which is slenderer than the hinder one, though both of them seem small enough) arising from the fore-part of the Marrow, goes forth betwixt the first and second rack-bones at the side of the Tooth-like process, which branch is distributed into the Muscles that lie upon the neck, as well as the fore-branch of the first pair, which is wrapped together with it, and is almost wholly spent upon the skin of the face. With its hinder branch [*tab.*2. *fig.*1.E] it slips out through the sides of the backward process of the second rack-bone, but presently is cleft into two branches of unequal bigness, of which that which is the thicker [*tab.*2.*fig.*1.F.] tends from the fore-part to the hinder, where the Muscles seated on both sides of the hinder part of the neck do meet together, and there being mixed [*tab.*2.*fig.*1.G] with the third propagation of the third pair of the nerves, it runs out through the middle of the said muscles, returning from the hinder to the fore-parts, and so is distributed into all the skin of the head, as far as to the top of the Crown [*tab.*2. *fig.*1.H] as also to the ears. The other branch, which is the slenderer, is inserted into the great strait muscles, and the lower oblique ones, that extend the head. *Galen* makes mention of these branches

The second pair.

lib.

lib.4. de locis affect. which place we ſhall not think much to tranſcribe hither, it making very much to the illuſtration of the uſe of this kind of learning. Not long ſince, ſays he, they ulcerated the head of a certain man, by laying on medicins vehemently heating, thinking by this means his ſenſe, that was greatly impaired, might be recovered. But we cured this very man, having found out the ſeat of the diſeaſe as well from other accidents, as from the primitive or procatarctick cauſes. For we diligently examined him about every one of them, and found that this was one; when he had walked in much rain cauſed by a violent wind, his Cloak was wet about his neck, ſo that he felt himſelf affected with a vehement cold in that part; ſo then if you know that four Nerves aſcend from the firſt Rack of the back-bone to the head, from which the skin about it receives its ſenſe, you will eaſily find out the ſeat of the diſeaſe; that therefore being healed, the skin of the head was healed alſo, as having no primary diſeaſe.

The third pair. Its fore-branch.

The third pair [*tab.*1.3.] iſſues out of the common hole in the ſides, which is betwixt the ſecond and third Rack-bones, and preſently after it gets out, is cleft into two branches, of which the more forward one [*tab.* 1.I] is ſubdivided into four propagations. The firſt [*tab.*2. K] goes to the firſt bending muſcle of the neck, or the long one: the ſecond [*tab.*1. L] runs down, and being united with a ſprig of the fourth pair [*tab.*1. Q] ends in the muſcles that lie under the gullet. The third [*tab.*1. M] climbs up, and joining with the thicker branch of the ſecond pair but now mentioned [*tab.*2.*fig.*1. F] is ſpent upon the skin of the hinder part of the head. The fourth [*tab.*1.N] is imparted to the tranſverſe muſcles, or to the firſt pair of the extenders of the neck, and to that which lifts up the ſhoulder-blade, of which two muſcles, that tends in the tranſverſe proceſſes of the neck, this begins therein; and at length it is digeſted into the ſquare muſcle that draws down the cheeks, which is called by *Galen* πλάτυσμα μυώδες. The hinder branch [*tab.* 2.*fig.*1. O] is implanted into the ſecond pair of muſcles that extend the cheſt.

Its hinder branch.

The fourth pair. The fore-branch. Its propagations. 1. 2. 3. The hinder branch.

The fourth pair [*tab.*1.*numb.*†] iſſues out of the common hole of the third and fourth Rack-bones, and like the third pair is divided into two unequal branches. The more forward and greater [*tab.*1. P] is cleft into three other twigs, of which the firſt [*tab.*1. Q] is joined with another branch of the third pair [*tab.*1. L] and goes to the firſt long pair of muſcles that bend the neck. Another [*tab.* 1. R] goes to the tranſverſe muſcle, or firſt of thoſe which extend the neck, and to the firſt of the ſhoulder-blade, called *Cucullaris*, the Cowl-muſcle. The third [*tab.*1.S] being ſmaller than the other, and joined with a muſcle of the fifth pair, and another branch of the ſixth pair, near to the *mediaſtinum* or membrane that parts the cheſt in the middle, and above the *Pericardium* paſſes on downward, that out of theſe three principles the Nerve of the midriff may be made up. The hinder branch [*tab.* 2. *fig.* 1. T] goes toward the ſpine or ridge, under the muſcles which are placed thereabout, to which alſo it affords a good number of branches, and from thence being led downward between the muſcles on both ſides of the neck, it is carried to the ſquare muſcle that draws down the cheeks.

A queſtion.

In this place it is worth our labour to inquire what may be the reaſon, that they who are troubled with a Reſolution, or deprivation of motion in the whole body, have nevertheleſs the motion of their midriff for a while free: ſome make anſwer that this happens, becauſe, although no ſpirits are ſent over from the brain, yet they may be diffuſed out of the marrow of the back. But theſe men beg the queſtion, when we ſuppoſe that no ſpirits come from hence, becauſe we ſee that all the muſcles of the whole body, to which nerves are ſent from the marrow of the back, are reſolved or deprived of motion. Therefore I thought fit to ſeek out for another anſwer, and to ſay that the midriff hath two motions, one that is voluntary, which we uſe whileſt we breath ſtrongly; another natural one, when the fibres are extended and contracted of themſelves. A man therefore is preſerved by this natural motion, when we ſee that breathing is little, and weak, and as much as ſuffices that the lungs may be moved a little.

The fifth nerve. Its fore-branch.

The fifth pair [*tab.* 1. *numb.* 5.] goes out betwixt the fourth and fifth rack-bones, and like the two laſt foregoing, is cleft into two branches. The forwarder of them [*tab.*1. U] iſſues forth ſome propagations. The firſt [*tab.*1. betwixt U and 6] goes to the muſcles that bend the neck. Another [*tab.*1. X] together with propagations of the fourth and ſixth pairs, ſometimes alſo of the ſeventh, to wit, then when the branch of the fourth is wanting, deſcends near to the ſide of the gullet through the fore part of the Rack-bones of the neck, and is implanted into the midriff, and ſo makes the midriff Nerve. The third [*tab.*1. Y] is carried through the upper part and outſide of the arm, to the ſecond muſcle of the arm, to wit, that which lifts it up, called *Deltoides*, from whence little branches are ſent over to the firſt and ſecond, that is, to the cowl-muſcle, and the lifter up of the ſhoulder-blade. The fourth propagation [*tab.*1.b] at the neck of the ſhoulder-blade is cleft into two, of which the former [*tab.*1.c] goes into the muſcle *Deltoides* at that part where it ariſes from the clavicle or canal-bone: the latter and thicker [*tab.*1. d] is inſerted into the fourth pair of muſcles of the bone *hyoides*, called *coracohyoideum*, and from thence imparts a ſmall branch to the upper muſcle over the ſhoulder-blade called *ſuperſcapularis*, and to the muſcle *Deltoides*, where it ariſes from the ſpine of the ſhoulder-blade.

The hinder branch.

The hinder branch [*tab.*2. *fig.*1. e] is writhen toward the back-bone, and diſtributed in the ſame manner as the hinder branch of the fourth pair is.

The ſixth pair. Its fore-branch.

The ſixth pair [*tab.*1.*num.*6.] goes out under the fifth rack-bone, and in like manner as the other pairs are, is divided into two branches. The forwarder and greater [*tab.*1.f] after it hath propagated that ſprig, [*tab.*1.g] which we ſaid is joined with the fourth and fifth pair, [*tab.*1. S and X] to the making up of the nerve of the midriff [*tab.*1.i] paſſing on farther is united with the two next following pairs, the ſeventh of the neck, and the firſt of the cheſt, and is again ſeparated from them, and then again being joined with them it ſo weaves a certain net-like texture, from which nerves are iſſued forth, that go to the arm.

Its hinder branch.

The hinder [*tab.* 2.*fig.*1. l] is carried to the hind muſcles which extend the head and neck.

The ſeventh pair. The fore-branch.

The ſeventh pair [*tab.*1. *n.*7.] is derived from the marrow of the neck, and iſſues forth through the common hole of the ſixth and ſeventh rack-bones. The forwarder and greater branch thereof

[*tab.*

[*tab.*1. m] is joined preſently after its egreſs with the ſixth nerve of the neck, and the firſt of the cheſt, and for the greater part is carried with the reſt to the arm. The hinder leſſer branch [*tab.*2. *fig.*1. n.] goes to the muſcles, that lie upon the neck, and to the ſquare one, that draws down the cheeks.

CHAP. III.

Concerning the Nerves of the marrow of the rack-bones of the Cheſt.

TWelve Conjugations of Nerves iſſue forth from the ſpinal marrow, whileſt it runs through the rack-bones of the back, as the moſt learned *Veſalius* hath rightly opinioned, however there are but eleven holes bored in the twelve rack-bones thereof, as *Columbus* objected, becauſe the firſt pair paſſes out between the laſt rack-bone of the neck and the firſt of the back, wherefore it ought to be numbred rather among the pairs of the cheſt, than thoſe of the neck. All theſe conjugations after their egreſs are divided into two; and the one branch which is the greater, always bends forward; the other which is the leſs is bent to the hinder parts, and to the muſcles that lie upon the back.

The firſt pair then [*tab.*1. *num.*8.] of the nerves which iſſue forth from the marrow of the cheſt, goes out of the common hole of the ſeventh rack-bone of the neck and the firſt of the cheſt, in the ſame manner as the five pairs laſt mentioned do, and in like ſort alſo is forthwith divided into two branches. The forwarder and greater [*tab.* 1. o] is united [*tab.*1. p] partly with the ſeventh nerve of the neck, partly with the ſecond of the cheſt, in that manner which we have before explained; and ſo afterward is wholly conſumed upon the arms, excepting one propagation [*tab.*1. q] which ariſing at the beginning of it, is joined with the ſaid nerves, and runs into the fore-parts near the length of the firſt rib of the cheſt to the breſt-bone, beſtowing a ſprig upon the ſubclavian muſcle, after that being reflected upward is ſpent upon the muſcles, which take their original from the top of the breſt-bone: ſuch are the muſcle that bends the head called *Maſtoideus*; that which draws down the bone *hyoides* or *ſternohyoideus*, and the firſt of them which extend the buckler-like griſtle of the throttle, called *thyroides*, or the muſcle *ſternothyroideus*. But to the two laſt ſometimes branches are ſent over from the ſixth conjugation of the brain, and the third of the cheſt. The ſame branch alſo when it hath paſt the arm-pit, being ready to go to the arm, iſſues forth a certain other propagation from its hinder part, which goes to the muſcles ſeated in the hollowneſs of the ſhoulder-blade. The hinder and leſs branch [*tab.*2. *fig.*1. r] lies hid under the muſcles which grow to the rack-bones, and imparts ſome propagations to the ſecond bending muſcle of the neck, and to them which extend the head and neck; but when it hath attained to the ſpine of the ſeventh rack-bone, it goes overthwart to the lower ſide, and diſtributes ſurcles into the firſt muſcle of the ſhoulder-blade, or that like a Monks Cowl, and in the third of the ſame, called *Rhomboides*, as alſo into the upper of the hindmoſt ſaw-muſcles.

The firſt pair.

Its fore-branch.

Its hinder branch.

The ſecond pair [*tab.* 1. *num.*9.] breaks out betwixt the firſt and ſecond rack-bones of the cheſt, and is cleft likewiſe into two branches. The forwarder [*tab.*1. s] is united with the firſt pair of the cheſt; and thus the firſt and ſecond pairs of the cheſt are united by turns, with the fifth, ſixth, and ſeventh of the neck, that the one are not diſcerned from the other, but make a net not unlike to thoſe things which hang at Cardinals hats; from which afterward all the nerves that go to the arms, iſſue forth and take their original. This ſpreads out a branch [*tab.*1. t] which goes forward through the firſt diſtance betwixt the ribs, according to the courſe of the firſt rim, as far as to the breſt bone, making the firſt Intercoſtal nerve, from which ſurcles [*tab.*1. u] are diſtributed into the muſcles that lie upon the cheſt. The hinder branch [*tab.*2. *fig.* 1. x] hath the ſame diſſemination with that of the foregoing pair.

The ſecond pair.

The fore-branch.

The hinder one.

The other ten pairs [*tab.*1. *numb.* 10, 11, 12. *and ſo on to* 19 *incluſively*] of the nerves of the cheſt, obſerve the ſame manner both of their riſe and diſtribution. For they all iſſue out of the common holes of the rack-bones at the ſides, and preſently after their egreſs are cleft into two branches of unequal bigneſs, one of which is the forwarder and greater, the other the inner and leſs. The forward branches [*tab.*1. y] (which make the nerves between the ribs) are carried into the foreſide, and each of them affords a little branch in order according to its length, to the inner branch of the ſixth pair, which deſcends under the *pleura* to the roots of the rib. Theſe branches are joined with the intercoſtal Veins and Arteries, together with which they paſs along the rib of the fore-part through the *ſinus* or channel, which is cut out on the lower and inſide of the ribs. But they which belong to the true ribs, go on as far as to the breſt-bone; but they which belong to the baſtard ones, are carried into the fore-part of the *Abdomen* above the *Peritoneum* or rim of the belly. From theſe nerves many branches are diſſeminated into the muſcles between the ribs, not onely in the inner, but the outer ones alſo, as well into the other [*tab.*1. z] which lie upon the cheſt; ſuch as are the fourth and fifth muſcles of the ſhoulder-blade, or the two foremoſt Saw-muſcles, as alſo to the broad one, called *Latiſſimus* [*tab.*1. 6] that moves the arm backward from the breſt. In like manner a propagation goes from the fifth intercoſtal nerve, about the middle of the rib paſſing through the intercoſtal muſcle into the firſt pair of the muſcles of the *abdomen* [*tab.*1.] as alſo into the skin of the cheſt; and being divided in four parts is diſtributed into the pectoral muſcle that moves the arm forward to the breſt, and alſo into the skin, from which ſome ſprigs do afterward go to the nipples of the breſt [*tab.*1.] and impart to them a very ſharp ſenſe. The hinder branches [*tab.*2 *fig.*1.] go backward to the ſpine or ridge, between the muſcles going to the rack-bones, which have the charge of extending the cheſt. Yet are they not wholly ſpent upon the muſcles, but when they have now attained to the tops of the ſpines, they fall out between the muſcles of both ſides, whereabout they are joined one to another, and ſo afterward they give nerves to all the muſcles which ariſe out of the tops of the ſpines of the rack-bones.

The other ten pairs.

Their fore-branches.

Their hinder branches.

bones. Such are the first extending muscle of the head, called *Triangularis* or *Splenicus*; the third muscle of the shoulder-blade, or *Rhomboides*; the first of the shoulder-blade or *Cucullaris*; the third broad muscle that leads the arm away from the breast, called *Anisculptor*, and the hinder saw-muscle. A good number also of sureles are distributed into the skin of the back.

CHAP. IV.

Concerning the Nerves of the Marrow of the Rack-bones of the Loins.

FRom the spinal Marrow, whilest it is carried through the first of the Loins, although there be onely four holes, yet five pairs issue forth, the first being between the last rack-bone of the chest, and the first loins. But they go forth through the common holes, and being gone forth, are distributed in like manner as we have said of the Nerve of the chest; when from every one of them presently after its going out, one branch, and that the greater, spreads it self forward; the other and less, backward. The foremost branches run to the muscles of the *abdomen*, or outer and fore-part of the lowest belly; the hindmost to them which lie upon the spines of the rack-bones, and the bones without a name, from whence they impart some little branches also to the skin that covers the loins. But the fore-branches are knit together, the first with the second, the second with the third, the third with the fourth, and the fourth with the fifth in the same fashion as we have said the nerves of the arm were, whilest they make the net-like complication.

The first pair. The first pair then [*tab.*1. *num.*20.] as the rest do also, going out under the *Peritoneum* or rim of the belly, through the common hole of the rack-bones, which is betwixt the last rack-bone of the chest and the first of the loins, presently after its egress is cleft into two branches. The fore-branch, which is greater, goes into the fleshy parts of the midriff, and into the beginning of the first bending muscle of the thigh, called Ψόας.

Its fore-branch.

The hinder one. From this Nerve a certain surcle [*tab.*1.39.] takes its beginning, reaching out for the most part with the preparing artery to the testicle. The hinder branch [*tab.*2. *fig.*1.*num.*42.] sends propagations into the muscles that lie upon the back side of the rack-bones of the loins, such as are the first and third of them which extend the chest, that being called *Dorsi longissimus*, this *Sacrolumbus*; as also the muscles which extend the loins: but when they issue out from the tops of the spines, whereabout the said muscles are joined one to another, they run to the sides, and are implanted into the broad muscle that leads the arm outward from the breast, called *Latissimus*.

The second. The second pair [*tab.*1. *num.*21.] goes out under the first bending muscle of the thigh, called Ψόας, betwixt the first and second rack-bones of the loins. The fore-branch thereof is distributed to the second bending muscle of the thigh, that fills up the cavity of *Os Ilium*, or the hanch-bone, and the first bending one of the leg, called *Fascialis*, as also to the skin of the thigh. The hinder branch going out of the *Abdomen* is distributed to the three muscles that extend the thigh, or the *Glutæi*; and to that which extends the leg, called *Membronosus*, the membranous muscle.

The third. The third pair [*tab.*1.*num.*22.] issues forth likewise under the first bending muscle of the thigh, betwixt the second and third rack-bone. The fourth branch thereof passes over near to the hanch-bones, distributing two propagations; one which goes to the knee, and its skin; another [*tab.*1.51.] which accompanies the vein of the inner ankle, called *Saphena*. The inner branch is reflected and disseminated into the muscles which lie upon the loins.

The fourth. The fourth pair [*tab.*1.*num.*23.] is the greatest of all the Nerves of the loins, and being carried under the said muscle that bends the thigh, as also under the *Os pubis* or share-bone, accompanies the Crural Ven and Artery.

The fifth. The fifth and last pair [*tab.*1.*num.*24.] issues out betwixt the fourth and fifth rack-bones; the fore-branch whereof passes through the hole which is betwixt the hip-bone, the *Os pubis* or share-bone, and the *Os Ilium* or hanch-bone, and distributes some propagations to the two muscles that turn the thigh about, called *Obturatores*, others to the second and third bending ones of the thigh, and others to the muscles of the yard. The hinder branch goes into the muscles and skin upon the rack-bones.

CHAP. V.

Concerning the Nerves of the Marrow of Os sacrum, *or the great bone.*

The first pair. LAst of all from the Marrow which is contained in the rack-bones of the *Os sacrum*, the six last pairs of the nerves of the spinal marrow do issue forth. The first of these [*tab.*1. *num.*25.] goes out betwixt the last rack-bone of the loins and the first of the great or holy bone, in the very same manner as the rest that arise out of the rack-bones of the loins, and likewise after the same sort is divided into two branches. The fore-branch, although it be mixed with the crural nerves, sends yet a surcle [*tab.*1.43.] over near to the inner region of *Os Ilium*, and is dispersed into the muscles of the *abdomen*, and into the second bending one of the thigh. The hinder [*tab.*2.*fig.*1. *num.* 44.] is disseminated into the muscles that arise from the *Os Ilium*, or hanch-bone, and especially into the first of them that extend the thigh, or the greater *Glutæus*, as also into the skin of the buttocks.

The other five pairs. The other five pairs have something proper to themselves, so that before they go out of the bone, they are every of them double on each side, and so from every one of them a double branch is carried on each side, one to the fore-part, another to the hinder, The three uppermost of the fore-branches, as that of the first pair also, go to the *Crus*, or parts of the body below the buttocks: the two lowest go into the muscles of the fundament and bladder; and in women to the neck of the womb, in men to the yard; but in both sexes to the outer privy parts. The hinder branches are distributed to the muscles seated on the backside of the bones *Ilium* and *Sacrum*. Of this sort are the first and third

ex-

extending muſcles of the cheſt, or *Dorſi longiſſimus*, the long muſcle of the back, and *ſacrolumbus*, that which bends the loins called *ſacer*, and the broad muſcle that leads the arm away from the breſt; as alſo the three which extend the thigh, being the authors of the buttocks, and therefore called *glutæi*, the buttock muſcles. And this is the utmoſt end of the ſpinal marrow, which reaching into the rump bone, called *Os coccygis* is in this manner terminated: And this is the hiſtory of the thirty pairs of the Nerves which go out of the ſpinal marrow, which is diligently and accurately to be committed to the memory, that we may know to what place remedies ought to be applied, if at any time from ſome external cauſe, as by a fall from aloft, or a bruiſe, or ſome notable compreſſion any part ſhall have loſt either motion, or ſenſe, or both. For the remedies muſt be applied always to the beginning of that Nerve, not to the place in which the ſymptom is perceived.

CHAP. VI.

Concerning the Nerves which are diſtributed through the Arms.

THoſe Nerves being now enumerated, which are diſperſed through the muſcles of the three bellies, and the parts contained in them; it remains that we deſcribe thoſe alſo, which are propagated through the *artus*, or extreme parts of the body. Here we meet with them firſt which are diſtributed through the arms, whereof there are ſix pairs commonly ſet down by Anatomiſts ariſing from the fifth, ſixth, and ſeventh pair of the nerves that come out of the marrow of the neck, and from the firſt and ſecond of thoſe which iſſue out of the cheſt. Theſe nerves go out through the common holes of the rack-bones, on both ſides, and preſently after their going out are united one among another with their forwarder and greater branches, by and by are ſeparated one from another again, and joined again, and finally ſeparated, ſo that they ſeem to make out a certain net-like texture, which cannot be better likened than to thoſe ſtrings of Cardinals Hats. This implication of Nerves goes forth under the clavicle or collar-bone, about the place where the Axillary Veins and Arteries go out of the hollow of the cheſt, and from this all the Nerves of the arm take their original. But their riſe is very uncertain by reaſon of their being ſo knit together; wherefore we in our relation of them will rather follow the footſteps of other men than our obſervations, leſt we ſhould ſeem to affect new opinions raſhly, and without neceſſity.

The firſt Nerve then [*tab.*1.ε] which is carried to the arm, is a double propagation, namely the third and fourth of the fore-branch of the fifth pair of the neck. For the one branch [*tab.*1.Y] is carried to the ſecond muſcle of the upper part of the arm called *Deltoides*, and to the skin that lies upon it: the other [*tab.*1.b] goes toward the neck of the ſhoulder-blade, where it is cleft into two branches; the former of which [*tab.*1.c] goes into the muſcle *Deltoides*, where it ariſes from the collar-bone; the latter [*tab.*1.d] is inſerted into the fourth pair of the muſcles of the bone *hyoides*, called *Coracohyoideum*, and from thence affords a little branch to the upper ſuperſcapular muſcle, and the *Deltoides* at what place it ariſes from the ſpine of the ſhoulder-blade. This Nerve runs out through the hinder ſide of the arm; but the other five are carried through the arm-pit into the arm, and in the ſame are ſcattered into more branches. The firſt nerve of the arm.

The ſecond Nerve [*tab.*1.ζ] is thicker, and takes its original from that net-like complication, of which we ſpake; yet from what nerve, cannot be evident enough. This is carried down through the middle and fore-part of the arm, into which it enters under the firſt bender of the cubit, or the double-headed muſcle, at that part where its two heads are united one with the other, and where the tendons are inſerted both of the pectoral muſcle that leads the arm forward to the breſt, and of the *Deltoides* that lifts it up. Being hid then under this muſcle it ſends forth two propagations [*tab.*1.] one of each ſide, which enters into the two heads of the muſcle *biceps*; and after that about the middle of the length of the upper part of the arm, going under the ſame double-headed muſcle, it ſhoots forth another ſprig [*tab.*1. †] by means whereof it is joined with the third nerve; and from thence deſcending it diſtributes in its progreſs a ſurcle [*tab.*1.θ] from its out-ſide to the head of the longer of the two muſcles of the *radius* or wand that turns the palm of the hand downward. When it is come to the bending of the cubit, being led to the fleſhy membrane, near to the out-ſide of the tendon of the ſaid double-headed muſcle, it is diſtributed into the skin, being divided into two branches, of which one is the outer, the other the inner; that is the ſlenderer, this the thicker. The outer then [*tab.*1.ι] being carried down a good way with a branch of the Cephalick vein through the inſide of the cubit, is diſtributed [*tab.*1.λ] to the ſecond bone of the thumb. The inner branch [*tab.*1.κ] is ſubdivided under the common vein of the arm, or the middle one called *Mediana*, into two branches, the outer whereof [*tab.*1.] going on obliquely under the skin leaving the vein goes away toward the *radius* as far as to the wriſt: but the inner [*tab.*1.ν] being faſtened to the inner branch of the Cephalick vein, when it goes more obliquely in the region of the cubit is cleft into two ſpecial branches, of which one [*tab.*1.π] is diſtributed through the region of the leſſer bone of the cubit, the other [*tab.*1.ο] through the region of the greater bone to the wriſt, and from thence, that being paſt, into the skin of the inſide of the hand. The ſecond. Its progreſs. Its propagations. Its branches. The outer. The inner.

The hinder Nerve of the arm [*tab.*1.ρ] or the third, which is carried to the arm, lies next under the ſecond, and in like manner with it ariſes from that net-like texture. This Nerve, whileſt it paſſes through the arm-pit, before it hath yet attained to the arm, brings forth a propagation [*tab.*1.σ] which is diſperſed under the skin betwixt the pectoral muſcle that leads the arm to the breſt, and the muſcle *Deltoides* that lifts up the ſame. But when it hath firſt attained to the arm, it hides it ſelf under the muſcle *biceps*, or firſt bender of the cubit, and paſſing on downward together with the ſecond nerve, it ſends out a little branch [*tab.*1.τ] into the head of the ſecond bending muſcle of the cubit. After this deſcending it receives a branch [*tab.*1.υ] from the ſecond Nerve, by means whereof they are joined one with the other, and then it goes further through the fore-part of the arm unto the bending of The third.

the cubit, being always equally distant from the second Nerve, and is carried into the protuberation of the inside of the arm, and the fore-part thereof. When it hath past this, it issues forth many propagations [*tab.*1. Φ] which together with the branches that are derived from the fifth Nerve, which is carried through the hinder region of the same protuberation, are distributed into the muscles that are seated on the inside of the cubit, and arise from the inner protuberation of the arm: such are the two that bend the uttermost bones of the fore-fingers, and that which bends the third joint of the thumb. After this it sends out another propagation, which is carried down between the said muscles through the *radius* together with a vein and artery to the wrist; and passing through under the transverse ligament, scatters some small sprigs into the muscle that moves the thumb outward from the fingers, and the two that bend the first joint of the same. After this, when it is come to the palm of the hand, it is divided [*tab.*1. χ] into three branches; the first of which scatters two twigs into the thumb, the second as many into the fore-finger, the third sends one to the middle finger on the inside.

The fourth. The fourth Nerve [*tab.*2.*fig.*1. ↓] is the biggest of all them which are carried to the arm, as being almost thrice thicker then the rest. This arises as well as the other, from the net-like complication, and from thence is carried down through the arm, in like manner as the third is, lying deep every where among the muscles, having the basilick vein and axillary artery for its companions. But presently after it hath entered the arm, it derives many, but small sprigs [*tab.*2.*fig.* ω] into the heads of the muscles that extend the cubit; and before it is come to half the length of the upper part of the arm, it is contorted obliquely downward to the bone thereof, and passes on betwixt that and the muscles which extend the cubit. But before it be wholly reflected, it sends forth a furcle [*tab.*2.*fig.*1. Γ] from its inside, which goes betwixt the said muscles, as also the second of them that bend the cubit, and is spent upon the skin that clothes the inside of the arm, some fibres being propagated upward and downward. Having disseminated this propagation it goes by degrees through the hinder part to the outside of the arm, being carried through the cavity of the outer protuberation of the upper bone of the arm that is cut out in the back side thereof, where likewise it sends out a furcle [*tab.*2.*fig.*1. Δ] going to the skin, that covers the lower part of the outside of the arm; and then another [*tab.*2.*fig.* 1. Θ] which is distributed into the skin, as far as to the wrist. After that near to the joint of the cubit it is divided into two branches, an outer and an inner one, which being hid deep, and among the muscles, as the whole Trunk also, descend to the wrist. The outer branch [*tab.*2.*fig.*1. Λ] goes along the *radius* or wand, and when it is come to the wrist, passes through the transverse ligament on the outer part, and by and by is subdivided [*tab.*2.*fig.*1. Ξ] into two branches, of which one goes with a double sprig into the outside of the thumb, the other is spent partly upon the fore-finger, partly on the middle one. But the inner branch [*tab.*2.*fig.*1. Π] reaching along the cubit scatters more propagations; the first [*tab.*2.*fig.*1. Σ] into the first muscle that extends the fingers, the second [*tab.* 2.*fig.*1. Φ] into the second that extends the fingers; the third [*tab.*2.*fig.*1. Ψ] into the inner muscle that extends the wrist. But in its progress [*tab.*2.*fig.*1. Ω] it affords propagations to the three beginnings of the muscles that take their original from the *ulna*, or greater bone of the cubit. The remainder of it ends in the wrist, [*tab.*2.*fig.*1.31.]

Its propagations.

Its two branches. The outer.

The inner.

The fifth Nerve. The fifth Nerve [*tab.*1. *num.*32.] arising lower than any of the fore-mentioned, out of the same net-like complication, and being joined to the fourth, descends through the inside of the arm, between the muscles that bend and extend the cubit. This scatters no propagation from it self, but remains entire till it be come to the inner protuberation of the arm, at whose hinder cavity it is reflected, and is distributed afterward in the same manner with the third Nerve, which passes through the fore-side of the same protuberation. For both of them bestow propagations [*tab.*1.33] upon the muscles which grow out of the inner protuberation of the arm, and keep the inside of the cubit. It issues forth a propagation also [*tab.*1.34] which being carried through the *radius* or wand, goes between the muscles which bend the second and third joints of the fingers, and so to the palm of the hand, and sends out the first branch, which being parted into two, is implanted into the inside of the little finger; then another, which being also cut in two, goes into the ring-finger, and at last another that goes to the outer part of the inside of the middle finger. But from this same fifth Nerve, and from the outside near to the middle of the length of the *radius* or wand, there grows out a certain other furcle [*tab.*1.35] which being divided into three branches is disseminated into the outer-part of the middle, the ring finger, and the little one.

The sixth. The sixth Nerve [*tab.*1.*n.*36.] issues out of the lowest part of the net-like complication, and going through the arm-pit and inside of the upper part of the arm and of the cubit, under the skin it makes haste to the inner protuberation of the upper bone of the arm, disperſing many furcles in its way to the neighbouring skin [*tab.*1.37.37.] But as soon as it hath attained to this protuberation, it is cleft into many propagations, some of which lie under the branches of the basilick vein, some lie over, and so being carried under the skin, when they are come down to the wrist, they end [*tab.*1.38.]

CHAP. VIII.

Of the Nerves that are distributed through the Crura, *or Thighs, Legs, and Feet.*

THere are four pairs of Nerves which are propagated through the *Crura*. They arise from the three lower conjugations of the loins, and the four upper ones of the *Os sacrum*, or great bone, which after they are gone forth through the common holes of the rack-bones as well as the Nerves, which are distributed through the arm, make a certain complication like the meishing of a net, but far greater than that other. Nor are these Nerves of equal bigness, but the first [*tab.*1. *num.*46.] and the third [*tab.*1.56.] are small, wherefore also they reach but to the thigh; the second [*tab.*1.50.] is somewhat thicker and reaches to the leg, but the fourth [*tab.*1.61.] alone is thicker than the three other put together, and is carried down as far as to the utmost ends of the toes.

The

The first Nerve then [*tab.*1.46.] grows out of the higher part of the Net-like complication, where the third Nerve of the loins is joined with the fourth [*tab.*1.47.] But it is presently carried downward under the rim of the belly, to the thigh; lying upon the outside of the tendon of the first bending muscle of the thigh, to which when it is come, it sends out a propagation [*tab.*1.48.] which runs out through the skin on the fore-part of the thigh, as far as to the joint of the knee, and there ends, and affords surcles [*tab.*1.49.] to the first bending muscle of the leg, as also to the second and third that extend the same. The first Nerve.

The second Nerve [*tab.*1.50.] arises out of the same complication, and below the first, over against the connexion of the third and fourth rack-bones of the loins. This together with the crural Vein and Artery, (which are the outer Iliacal branches) descends through the groin into the thigh, which when it hath attained to, presently it issues forth a notable propagation [*tab.*1.51.] from its inside, lying upon the *saphena* or vein of the inner ankle, on the fore-part, all the way it goes under the skin through the inner parts of the *crus* to the great toe. But as the vein *saphena* it self distributes some sprigs in the way to the skin next to it, so also this Nerve sends out many propagations, of which that is the chief [*tab.*1.53.] which it gives to the fore-side of the knee. But the trunk it self [*tab.*1.54.] when it hath sent out this propagation, passes together with the trunk of the crural Vein and Artery into the thigh, and is scattered into the muscles seated on the inside of the thigh, especially [*tab.*1.55.] into the third bending one of the thigh, and the fourth extending one of the leg, and so afterward it is terminated above the knee. The second. The progress of the trunk.

The third [*tab.*1.*n.*56.] grows out of the complication under the second, over against the conjunction of the fourth and fifth rack-bones of the loins. This Nerve being carried down upon the second bending muscle of the thigh, called *Iliacus internus*, passes through the hole of the share-bone, and affords propagations [*tab.*1.57] to the two muscles that turn the thigh about, which they call *Obturatores*, the stoppers, to wit, of that said hole, as also to the two muscles that erect the Yard, which arise out of the bone of the hip. From thence like the two foregoing Nerves, it descends and distributes little Nerves into the skin that cloths the inner part of the thigh [*tab.*1.58] the remaining part [*tab.*1.57] lies deep, the chief propagation whereof [*tab.*1.60] is spent partly on the second, partly on the third muscle that bend the leg. The third.

The fourth Nerve [*tab.*1.*n.*61] is made up out of the fore-branches of the four upper pairs of the great bone being united together. By reason whereof it passes the rest, yea and all the Nerves of the whole body, not onely in thickness, but in hardness also, as being made of the last, that issue out of the spine, or ridge. This enters into the hinder part of the thigh through the cavity that is in the hinder part of the hip-bone. But presently it sends forth a notable propagation [*tab.*1.62] from its backside, which stays a pretty while under the first extending muscle of the thigh, or *Glutæus magnus* the great buttock-muscle, and from thence is dispersed into the skin that covers the buttocks, and the back-side of the thigh to the middle of its length. Then it sends other propagations [*tab.*1.63] on both sides, three for the most part to the heads of the third, fourth, and fifth muscles that extend the leg, and to the third bending one of the thigh. After this the trunk of the nerve descends among the muscles seated on the hinder part of the thigh near to the bone, as far as half the length thereof, and distributes another branch [*tab.*1.64] to that fleshy lump of the fifth bending muscle of the leg, called *Biceps*, which grows to it on the inside, after it hath gone beyond the middle of the thigh. From hence also other surcles proceed, which are distributed into the skin on the backside of the thigh. But the trunk it self proceeding farther on, at length attains to the the knee betwixt the two heads of the bone of the thigh, and imparts a small branch [*tab.*1.65] on each side into the first extending muscle of the foot, and the sole muscle called *Plantaris*, and by and by is divided [*tab.*1.66] in the inner cavity of the knee, or in the ham, into two unequal branches which are distributed along through the leg and foot. For there is not any Nerve which runs out through the leg, besides these two branches of the fourth, if you except onely that notable propagation, which being derived from the second Nerve, as we have said, descends in company of the Vein *Saphena* through the inner part of the *Crus*. The outer branch [*tab.*1.67] is the smaller, and goes toward that part where the upper *appendix* of the *fibula*, or lesser bone of the leg is joined with the *tibia* or greater bone thereof, scattering a propagation [*tab.*1.68] in the way which goes to the outer ankle under the skin, distributing in the mean time many sprigs to the skin. But the branch it self [*tab.*1.69] passes between the muscles seated on the foreside of the leg, and going through the long ligament of the *tibia* and *fibula*, or two bones of the leg, passes together with the tendons of the muscles that extend the toes under the transverse ligament, and disperses little branches to the sides of the upper part of the toes. The inner branch [*tab.*1.72] is carried down through the backside of the *Crus*, lurking betwixt the muscle of the sole of the foot, and the first of them that move the foot obliquely, as also the long bending muscles of the toes; and being joined afterward with the branch of the outer, which passes through the ligament, it goes to the sole of the foot, and distributes propagations into both the sides of the lower part of the toes. The progress of the trunk. Its division.

An Explanation of the two Tables of the Nerves.

The thirty pairs of the Nerves of the marrow of the Brain, whileſt it is carried through the ſpine or ridge, are expreſt in theſe two Tables, the preſent and the following one. We have inſcribed common Characters on both of them, though many alſo be peculiar to one; after which we have preſently ſet the number of the Table.

nn. 1. t. 1. &c. — THE firſt ſhews the rack-bones of the Spine and the Nerves that iſſue from thence on the foreſide; the ſecond on the back ſide.

8 as far as 7. The ſeven rack-bones of the neck.

20 as far as 19. The twelve rack-bones of the cheſt.

25 as far as 24. The five rack-bones of the loins.

to 30. The ſix bones of the Os ſacrum. Theſe ſame figures do ſtand for the pairs of the ſpinal marrow.

A tab. 1. & 2. — The ſeat of the ſpinal marrow, where it firſt enters into the rack-bones.

1. 1. B 1. C 2. — The firſt pair of the neck, whoſe forwarder propagations is B, the hinder C.

2. 1. D E 2. — The ſecond pair, whoſe fore-propagation is D, its hinder E; from this two branches grow out, the ſlender one marked with the letter E, the other thick one with F, which is mixed with a branch of the third pair M about G. But the courſe thereof to the skin of the crown, and back ſide of the head is marked with the letter H.

E 2. F G H — The third pair of the neck, whoſe fore-braneh I is divided into four propagations. The firſt K is implanted into the muſcles that bend the neck. The ſecond L is mixed with a twig of the fourth pair Q. The third M, is mixed with the thicker propagation of the hinder branch of the ſecond pair F. The fourth N is inſerted into the muſcles that are joined to the tranſverſe proceſſes of the rack-bones.

3. 1. I 1. K 1. M 1. N — The hinder branch O.

O 2. — The fourth pair of the neck, whoſe fore-branch P is cleft into three propagations. The firſt Q, joins with the ſecond propagation of the third pair L. The ſecond R goes into the tranſverſe muſcle of the neck.

4. 1. P Q 1. R 1. — The third S.

S 1. — The hinder branch T.

T 2. — The fifth pair of the neck, whoſe fore-branch V iſſues out ſome ſurcles. The firſt goes to the muſcles that bend the neck, being to be ſeen in the firſt table between V and the number 6. The ſecond X, making the greateſt part of the nerve of the midriff. The third Y goes to the muſcle Deltoides, of which there is a propagation a, which goes to the skin that covers the muſcles Deltoides and Biceps. The fourth b, at the neck of the ſhoulder-blade is cleft into two branches; one of which c, enters into the muſcle Deltoides, at what part it grows out of the collar-bone: the other d, is implanted into the ſame, in the place where it grows out of the ſpine of the ſhoulder-blade.

5. 1. V 1. X 1. Y a 1. b 1. c 1. d 1. — The hinder branch e.

e 2. — The ſixth pair of the neck, whoſe fore-branch f, when it hath propagated that ſurcle g, which with the fourth and fifth pair S and X, makes the nerve of the midriff, is joined with the two following h, and thus it makes up the nerve of the midriff i, ſo that this ariſes out of three ſurcles S, X, and g.

6. 1. f 1. g 1. h 1. i 1. — The hinder branch l.

l 2. — The ſeventh pair of the neck, whoſe fore-branch is m, its hinder one n.

7 1. m 1. n 2. — The firſt pair of the cheſt, whoſe fore-branch o, is united p, with the ſeventh pair of the neck and ſecond of the cheſt, ſpreading a propagation q, through the upper ſide of the firſt rib. The hinder branch r.

8. 1. o 1. p 2. q 1. r 2. — The ſecond pair of the cheſt, whoſe fore-branch ſends forth a ſurcle t, running out through the firſt ſpace betwixt the ribs, and ſending ſurcles u to the muſcles of the cheſt.

9 1. t 1. u 1. — The hinder branch x.

x 2. — The pairs of Nerves from the nineth to the twentieth, which have the ſame ſeries of propagations, and eſpecially to the diſtances of the ribs. The fore-branches of theſe [fig. 1.] are ſcattered into the muſcles ſeated on the fore-part of the cheſt, and partly into their upper region, as y, partly in their lower z, which in women go alſo to the breſts; and then they ſend other ſurcles into the heads of the oblique deſcending muſcles of the abdomen α, and into that which leads the arm from the breſt β, another goes to the nipple of the breſt γ. The hinder branches δ.

10, 11, 12. &c. to 19. inclusively 1. — The firſt nerve that goes to the arm, which is ſcattered into the skin of the outſide of the arm.

y 1. z 1. α 1. β 1. γ 1. δ 1. ε 1. ζ 1. — The ſecond nerve that goes to the arm, whoſe two firſt propagations ηη go to the two heads of the muſcle biceps: then it joins with the third nerve by a ſurcle †. Thirdly, it carries a propagation to the longer muſcle that turns the palm of the hand downward θ. But about the bending of the cubit it is divided into two branches, an outer, and an inner one κ. That deſcending along the radius or wand, is inſerted at the out-ſide of the ſecond joint of the thumb λ. This ν, is by and by ſubdivided into an outer μ, and an inner branch ν. This ν is again cleft in the region of the cubit into an outer branch ο, and an inner one π.

ηη 1. † 1. θ 1. ε 1. κ 1. λ 1. μ 1. ν 1. ο 1. π 1. ρ 1. — The third nerve entering the arm ρ, before it attains to the arm, ſcatters a ſprig betwixt the pectoral muſcle and Deltoides σ. By and by having entered the arm, it diſtributes another τ, into the ſecond muſcle that bends the cubit. After that, deſcending it receives a branch υ from the ſecond nerve; when it is paſt the bought of the arm, it is diſtributed into many ſurcles Φ, at length about the palm of the hand it is divided into three branches χ.

σ 1. τ 1. υ 1. φ 1. χ 1. Ψ 2. — The fourth Nerve entering the arm, which is the greateſt of all them that go to the arm, is not marked with any letters in the ſecond table, but in the third onely, leſt the ſecond ſhould be too much blurred with letters. This ſuddenly after it hath entered the arm, reaches out ſmall ſprigs ω into the muſcles that extend the cubit, then another into the inner skin, upwards and downward Γ, and another into the lower part Δ, and another Θ, which goes as far as to the wriſt. After this near to the bought of the arm it is divided into two branches, an outer one Λ, and an inner Π. That Λ about the tranſverſe ligament is again divided into two Ξ. This Π reaching all along the cubit ſends forth more propagations, the 1. Σ, the 2. Φ, the 3. Ψ. Then another in its

ω Γ Δ Θ Λ Ξ Π Σ Φ Ψ Ω 3. 1.

31 *its progreſs* Ω. *The remainder ends in the wriſt* 31.

32 1. *The fifth that enters the arm, which about the inner protuberation of the arm, is diſſeminated*
33 34 *like to the third. Its firſt ſurcle* 33, *its ſecond*
35 34, *is third* 35.

36 1. *The ſixth Nerve of the Arm, which goes under the skin imparting many ſprigs to it* 37, 37,
37 37, *the end of it is* 38.
38

20 21 *The five pairs of the Nerves of the loins: the*
22 23 *firſt* 20, *the ſecond* 21, *the third* 22, *the fourth*
24 1. 23, *the fifth* 24. *A certain branch ariſing from*
39 1. *the firſt pair of the loins* 20, *and deſcending for the moſt part with the preparing Artery to the Teſticle.*

40 1. *The courſe of the Nerves through the muſcles of*
41 1. *the* Abdomen; *from which branches* 41 *goes into the muſcle that leads the arm outward from*
42 1. *the breſt.*

The hinder branches of the Nerves of the loins, The ſix pairs of the nerves of the great bone. Of
25 26 *theſe the firſt is* 25, *the ſecond* 26, *the third* 27,
27 28 *the fourth* 28, *the fifth* 29, *the ſixth* 30.
29 30 1.

43 1. *A ſurcle reacht out from the* fore-branch *of*
44 1. *the firſt Nerve of the great bone to the inſide of*
45 1. *the hanch-bone, and ſo to the muſcles of the* Abdomen *that ariſe from that bone. Then another ſpreading out from the hinder branch to the muſcles ſeated on the back of* Os Ilium, *or the hanch bone.*

The termination of the ſpinal marrow paſſing on without a mate, and undivided.

46 1. *The firſt Nerve entering the* crus. *This ari-*
47 *ſes where the third Nerve of the loins meets with*
48 1. *the fourth* 47. *A branch of this* 48 *goes to the*
49 1. *skin, but* 49 *it is entangled among the muſcles that are ſeated on the outſide of the thigh.*

50 1. *The ſecond crural Nerve, a notable propaga-*
51 1. *tion whereof* 51, *runs out into the ſame courſe with the vein* Saphena, *to the end of the foot, and*
52 1. *there ends about* 52. *In the mean time it proffers*
53 1. *another notable ſurcle* 53, *to the fore-ſide of the*
54 1. *knee. But the remainder of the trunk* 54 *enters deep into the thigh, and gives out a ſmall branch*
55 1. 55, *but without queſtion the chief.*
56 1.
57 1. *The third crural nerve, whoſe propagation* 57 *goes to the muſcles called* Obturatores, *and ano-*
58 1. *ther* 58 *to the skin. The remainder* 59 *lies deep*
59 1. *intangled in the muſcles whoſe chief propagation*
60 1. *is* 60, *which is implanted in the ſecond and third muſcles that bend the leg.*

The fourth, and that the thickeſt of all the
61 1. *Nerves of the* crus, *whoſe firſt branch is* 62,
62 1. *which is inſerted into the skin of the buttocks:*
63 1. *another* 63 *is diſtributed into the heads of the muſcles that ariſe from the* appendix *of the hip:*
64 1. *a third* 64 *is given to the fifth muſcle that bends*
65 1. *the leg; and others* 65 *go into the outer calf-muſcle, and that of the ſole of the foot. But about the lower heads of the thigh it is divided*
66 1. 66 *into two branches, to wit, an outer one* 67,
67 1. *and an inner* 72.
68 1. *The outer branch, a propagation whereof* 68 *is ſent under the skin that covers the outer part*
69 1. *of the leg and the outſide of the foot. But the*
70 1. *branch it ſelf* 69 *goes to the connexion of the leſſer bone of the leg with the greater; ſending*
71 1. *forth another ſurcle* 70 *to the fore-part of the leg under the skin: the remainder of it* 71 *reaches along the* fibula *or leſſer bone of the leg.*

72 1. *The inner branch, a propagation whereof*
73 1. 73 *goes through the inſide of the leg toward the calf, and inſide of the foot under the skin:*
74 1. *and then another* 74 *is ſcattered into the skin, eſpecially that which covers the calf: another alſo*
75 75 1. 75, 75 *goes into the fore-part of the leg through the ligament that joins the leſſer bone of the leg*
76 1. *to the greater, and afterward is ſpent on the up-*
77 1. *per ſide of the foot. The laſt propagation* 76 *runs out betwixt the inner and outer calf-muſcle. The remainder of the trunk goes by the inner ankle to the lower part of the foot, diſtributing two ſurcles apiece to the lower part of all the toes.*

The ſecond and third figures of the ſecond Table. Theſe two Figures do exhibit the Nerves of the arm and leg in a larger form than the firſt Table does, ſo that all which concerns thoſe Nerves, may be ſhewn more accurately herein. But they have common characters, and the ſame explanation of the ſame ſerves for both.

The





A General Table of all the chief things treated of in this Work.

A.

Abortions, why frequent in a peſtilent ſeaſon, 8. their cauſes, &c. 560
Abauctores muſculi, 150,162
Abſceſſes how to be opened, 175
Aconite, the ſymptoms cauſed thereby, and their cure, 484
Actual cauteries preferred before potential, 447. *Their forms and uſe,* ibid. *Their force againſt venemous bites,* 469
Action, the definition and diviſion thereof, 14
voluntary action, ibid.
Adders, their bitings, the ſymptoms thereon enſuing, together with the cure, 473
Adipoſa vena, 76
Adjuncts of things natural, 14
Adnata ſive conjunctiva, *one of the coats of the Eye,* 121
Ægilops *what, the differences thereof, and the cure,* 382
Ægyptiacum, *the force thereof againſt putrefaction,* 288. *a cleanſer and not ſuppurative,* 289. *deſcriptions thereof,* 281, 302. *the praiſe thereof,* 516
After-birth, ſee Secundine,
After-tongue, 130
After-wriſt, 141
Age what, the diviſion thereof,
Ages compared to the four ſeaſons of the Year,
Agony what, 25
Agues, ſee quotidian, quartan, tertian.
Baſtard Agues how cured, 194
Agglutinative medicines, 219. *their nature and uſe,* 639
Air an Element, the prime qualities thereof, 18. *the neceſſity thereof for life,* ibid. *which hurtful,* ibid. *What underſtood thereby,* ibid. *How it changes our bodies,* 19. *Though in Summer colder then the Brain,* 239. *How it becomes hurtful,* 276. *How to be corrected,* 285. *Of what force in breeding diſeaſes,* 288. *What force the Stars have upon it,* ibid. *How that which is corrupt or venemous may kill a man,* 467. *How it may be corrupted,* 493. *Pent up it is apt to putrifie,* 503. *change thereof conduces to the cure of the Plague,* ibid.
Alæ, *what,* 87
Allantoides tunica, *there is no ſuch, ſhewed by three ſeveral reaſons,* 48
Albugineus humor, *the uſe thereof,* 123
Almonds of the Throat or Ears, their hiſtory, 198. *their tumour with the cauſes and ſigns thereof, the cure,* ibid.
Almonds increaſe the pain of the Head, 239
Alopecia; *what, the cauſe, which curable, and how, and which not,* 374
Amnios tunica, *the ſubſtance and compoſure thereof,* 87
Amphibleſtroides vel retiformis tunica, 123
Amputation of a member when to be made, 302. *How to be performed,* 303. *to ſtanch bleeding thereon,* 304. *how to dreſs the part,* ibid. *To perform the reſt of the cure,* 305. *ſometimes made at a joynt,* 306
Anatomy, the neceſſity of the knowledge thereof, 50. *A threefold method thereof,* ibid. *The definition thereof,* 51
Anatomical adminiſtration of the lower Belly, 56. *Of the Sternon,* 89. *Axioms,* 101, 123, 143
Aneuriſma, *what,* 194. *how cured,* ibid. *which incurable,* ibid.
Anger, the effects thereof, 24
Angina, *ſee Squinancy.*
Anima, *how many ways taken,* 4. *ſee Soul.*
Animal parts which, 52. *Their diviſion,* 53
Anodyne medicines, 650. *For the Eyes,* 254. *in pains of the Teeth,* 267
Antidotes muſt be given in great quantities, 470. *No one againſt all poyſons,* 485. *To be uſed in cure of the Plague,* 507
Antipathy, ſee Sympathy.
Antipathy between ſome Men and a Cat, 482. *Of poyſons with poyſon,* 494.
Ants, 36. *their care,* ibid
Apes their imitation of mens actions, 45
Apium riſus, *the poyſonous quality thereof, with the cure,* 483
Apology concerning wounds made by Gun-ſhot, 287. *That ſuch wounds are not poyſoned,* 290. *Concerning binding of veſſels, &c.* 305
Apophlegmatiſms what, and their uſe, 654
Apophyſes clinoides, 116
Aphoriſms concerning Surgery ſelected out of Hippocrates, 511
of the Author, 750
Apoſtumes, ſee Impoſtume.
Apothecaries, choiſe of ſuch ſhall have care of thoſe ſick of the plague, 499
Appendices glanduloſæ, 81
Aqua fortis, *the poyſonous quality, and the cure thereof,* 486
Aqua theriacalis, *the deſcription and manner thereof,* 451, 494
good againſt the Plague, ibid.
Aqua vitæ *how diſtilled.* 668
Aqueus humour, 143
Arachnoides, ſive araneoſa tunica, 123
Araeotick medicines, 635
Archagatus *a Roman Surgeon, ſlain by the people.* 2
Argentum vivum, *ſee* Hydrargyrum.
Ariſtomachus *the Philoſopher a great obſerver of Bees,* 36
Arm or ſhoulder-bone, the fracture thereof, 145
Arm and the muſcles thereof 145. *The defect thereof, how to be ſupplied,* 532
Arſenick, the poyſonous quality thereof, and the cure, 486
Arrows, wounds made by them, and their ſeveral forms, 291
How to be drawn forth, ibid.
Artery what, 62. *The diviſion of the great deſcendent artery,* 74
Diſtribution of the left ſubclavian artery, 101. *the Axillary,* 143. *Of the crural,* 152. *Not dangerous to be opened,* 377. *Rough Artery,* 103. *Figure of the Arteries,* 102
Arteria venoſa, *and the diſtribution thereof,* 97. Carotides, 103. Cervicalis, 101. Intercoſtalis, ibid. Mammaria, ibid. Muſculoſa, 103. Humeraria duplex, ibid. Thoracica duplex; ibid. Aſpera, ibid. Muſcula, 152
Arthrodia *what,* 165
Articulation and the kinds thereof, ibid.
Aſcarides *how known,* 458
Aſcites, ſee Dropſie.
Aſp, his bite, and ſymptoms that happen thereon, with their cure, 476
Aſſes-milk how to be uſed in the cure of a Hectick, 263
Aſtragalus, 168
Atheroma *what,* 184. *The cure thereof.* ibid.
Atrophia *how helped.* 5
Attractive medicines what, 635
Auricula cordis, 96
Auripigmentum, the poyſonous quality and the cure thereof, 486
Autumn, the condition thereof, 6
Axioms anatomical, 81, 101, 123
Philoſophical, 123

B.

Back-bone and the use thereof, 133
Bags, the diversity and use, 655
Ball-bellows, 276
Balneum Mariæ, 666
Balsams fit to heal simple, not contused wounds, 289
Balsam of Vesalius's description, 735. of Fallopius his description, ibid. Anodyne, and sarcotick one, 268
Bandages, their differences, 322. What cloth best for them, ibid. Indications how to fit them, 323. Three kinds necessary in fractures, 324. Common precepts for their use, 325. uses whereto they serve, ibid.
Barrenness, the cause thereof in men, 566. In women, 567
Basilisk, her description, bite, and the cure thereof, 475
Battels where the Author was present: See Voyages,
Baths good in pain of the Eyes, 380
Baths, their faculties and differences, 657. How to know whence they have their efficacy, ibid. Their faculties, and to whom hurtful, ibid. half baths, 656
Beautrol a Beast of Florida, 624
Bear-worms, the bites and the cure thereof, 479
Bears, their craft, 34
Beasts, inventors of some remedies, ibid. Their faculty in presaging, 35. Their love and care of their young, ibid. They know one anothers voice, 45
Bees, their government, 36. Care and justice, ibid. Their stinging, and the cure thereof, 478
Beggars their cosenages and crafty tricks, 606
Belly, why not Bone, 54. The division of the lower Belly, 55
Biceps musculus, 148
Binding of the vessels for bleeding, 228. An Apology therefore, Authorities therefore, Reason, experience, Histories to confirm it.
Birds their industry in building their nests, 35. Ravenous birds, counterfeit mans voice, 45. they have taught men to sing, ibid.
Birds of Paradise, 621
Birth, See Child-birth.
Bitings of man and beast virulent, 463
Bitings of a Mad-dog, Adder, &c. See Dog, Adder, &c.
Bitter things not fit to be injected into wounds of the Chest, 260
Bladder of the Gall, 72
Bladder of Urine, 81. The substance, figure, &c. ibid. Signs of the wounds thereof, 264. Ulcers thereof, and their cure, 318, 407
Blear-eyes, their differences and cure, 379
Bleeding in wounds, how helped, 218. How stopped by binding the vessels, 228. Why devised by our Author, 305. In amputation of members, 304
Blood the temper thereof, 7. The material and efficient causes thereof, ibid. Where perfected, ibid. All the four humours comprehended under that general name, ibid. compared with new wine, ibid. the nature, consistence, color, taste, and use, ibid.
Blood-letting, whether necessary at the beginning of pestilent diseases, 503
Blood-letting, whether necessary in a Synochus, 177. When in an Erysipelas, 179. When in a Tertian, 180. In what wounds not necessary, 219. The two chief indications thereof, 241. Why necessary in the fracture of the Heel, See Phlebotomy.
Bloody urine and the causes thereof, &c. 406
Boat-bone, 160
Body how divided, 53. The forepart thereof, 54. The backpart, 55. The crookedness thereof how helped, 528
Bolsters and their use, 326
Bones, how they feel, 51. Their definition, 89. Their differences, ibid. How hurt by the Trepan, 245. What hastens their scaling, ibid. Their corruption, 248. How helped, 249
Bones of the scul, 107, 108. of the face, 118. of the nose, ibid. of the auditory passage, 127. of the arm, 145. of the back, 133. of the brest, 89. of the cubit, 146. of the wrist, and fingers, 149. Seed-bones, 149. Of the thigh, 155. of the leg, 157. Of the foot, 158. of the toes, 160. A brief recital of all the bones, 162
Bones more brittle in frosty weather, 328. sooner knit in young bodies, ibid. Their general cure being broken or dislocated, 329. How to help the symptoms happening thereon, 330. Why they become rotten in the Lues venerea, and how it may be perceived, 446. How helped. ibid.
Bones striking in the throat or jaw, how to be got out, 386
Brachiæus musculus, 148
Brain and the History thereof, 109. The Ventricles thereof, 110. The mammillary processes, ibid.
Brain, the moving or concussion thereof, 235. how cured, ibid.
Brests, 90. Their magnitude, figure, &c. ibid. How they communicate with the womb, ibid.
Brest-bone, the History thereof, ibid.
Brest-bone, the depression or fracture thereof, how helped, 333
Brevis Musculus, 148
Bronchocele, the differences thereof, and the cure, 201
Bruises, See Contusions.
Bubos, by what means the humour that causes them flows down, 152
Bubos, Venereal ones returning in again, cause the Lues venerea, 431. Their efficient and material causes, 444. Their cure, ibid.
Bubos in the Plague, whence their original, 490. the description, signs, and cure, 513, 514. prognosticks, ibid.
Bubonocele what, 205
Bullets shot out of Guns do not burn, 274. They cannot be poysoned, 274. remain in the body after the healing of wounds, 285
Bupresis their poyson and their cure, 479
Burns how kept from blistering, 273. See Combustions.
Bishop-fish, 612

C.

Cacochymia what, 23
Cæcum intestinum, 69
Calcaneum os, Calx, 160
Cæliaca arteria, 74
Callus what, and whence it proceeds, 217. Better generated by meats of gross nourishments, 328. Made more handsom by Ligation, ibid. The material and efficient causes thereof, 344. Medicines conducing to the generation thereof, ibid. How to know it is a breeding, ibid. What may hinder the generation thereof, and how to be helped being ill formed, 345
Camels their kinds and condition, 44
Cancer, the reason of the name, 189. Causes thereof, ibid. differences. Which not to be cured, ibid. The cure if not ulcerated, ibid. Cure if ulcerated, ibid. Topick medicines to be thereto applied, 191
Cancer or Canker in a childs mouth how to be helped, 546
Cannons, See Guns.
Cantharides, and their malignity and the help thereof, 479. Applied to the head they ulcerate the bladder, 480
Capons subject to the Gout, 421
Carbuncles whence their original, 490. why so called, together with their nature, causes and signs, 516. prognosticks, ibid. cure, 518
Caries ossium, 248
Carpiflexores musculi, 150
Carpitensores musculi, 150
Cartilago scutiformis, vel ensiformis, 89

Caruncles, their causes, figures, and cure, 443. *Other ways of cure*, 444
Cases, their form and use, 326
Catagmatick powders, 243
Catalogue of medicines and instruments for their preparation, 674. &c. *Of Surgical instruments*, 675
Cataplasms, their matter and use, 649
Cataracts, where bred, 124. *Their differences, causes*, &c. 383. *Their cure at the beginning*, ibid. *The couching of them*, 385
Catarrh sometimes malign, and killing many, 492
Catheretick medicines, 640
Cats their poysonous quality, and the Antipathy between some men and them, 482
Caustick medicines their nature and use, 640
Cauteries, actual ones preferred before potential, 447. *Their several forms*, 448. *Their use*, ibid. *Their force against venemous bite*, 469. *potential ones*, 651
Cephale *what*, 165
Cephalica vena, 142
Cephalick powders how composed, 449
Cerats what, their differences, 647
Ceratum œsypliex Philagrio, 648
Ceruse, the poysonous quality thereof, and the cure, 486
Chalazion *an effect of the Ey-lid*, 378
Chamelion, his shape and nature, 627
Chance sometimes exceeds art, 31. *Finds out remedies*, 272
Change of a native temper, how it happens, 117
Chaps, or Chops occasioned by the Lues Venerea, *and the cure*, 450. *In divers parts by other means, and their cure*, 583
Charcoal causeth suffocation, 682
Chemosis *an affect of the Eye-lids*, 380
Chest and the parts thereof, 90. *why partly gristly, partly bony*, ibid. *The division thereof*, ibid. *The wounds thereof*, 259. *Their cure*, ibid. *They easily degenerate into a Fistula*, 260
Child, whether alive or dead in the womb, 554. *If dead, then how to be extracted*, 555
Children why like their Fathers, and Grand-fathers, 536 *Born without a passage in the Fundament*, 543. *Their situation in the womb*, ibid. *when and how to be weaned*, 554. *Their pain in breeding teeth*, 584. *They may have imposthumes in their Mothers womb*, 347
Child-birth and the cause thereof, 543. *The natural and unnatural time thereof*, 544. *Women have no certain time*, ibid. *Signs it is at hand*, 545. *Whats to be done after it*, ibid.
China-root, the preparation and the use thereof, 435
Chirurgery, See *Surgery*.
Chirurgion, See *Surgeon*,
Choler, the temper thereof, 7. *The nature, consistence, color, taste and use*, ibid. *The effects thereof*, 8. *Not natural, how bred and the kinds thereof*, ibid.
Cholerick persons, their habit of body, manners and diseases, 10. *They cannot long brook fasting*, 421
Chorion *what*, 87. Chylus *what*, 7
Cirsocele, *a kind of Rupture*, &c. 205. *the cure*, 211
Cinnamon and the water thereof, 733
Clavicle, See *Collar-bone*. Cletioris, 87
Clyster when presently to be given after Blood-letting, 178. See *Glyster*.
Coats, common coat of the muscles, the substance, quantity, &c. *thereof*, 59. *Of the Eyes*, 121. *Of the womb*, 87
Cockatrice, See *Basilisk*,
Cocks are kingly and martial birds, 40
Colick, and the kinds thereof, &c. 409
Colon, 69
Collar-bones, or clavicles, their History, 91. *Their fracture*, 332. *How to help it*, ibid. *Their dislocation and cure*, 352
Collyria *what, their differences and use*, 653
Colour is the bewrayer of the temperament, 17
Columella, *See* Uvula,
Combustions and their differences, 297. *theeir cure*, ibid.
Common sense what, 543
Comparison, between the bigger and the lesser world, 455
Complexus musculus, 133
Composition of medicines, the neeessity thereof, 674
Compresses, See *Bolsters*.
Concoction, fault of the first concoction not mended in the after, 421
Concussion of the brain, how helped, 251
Condylomata, *what they are, and their cure*, 583
Conformation, the faults thereof must be speedily helped, 546
Congestion, two causes thereof, 170
Contusions what, their causes, 293. *general cure*, 294. *How to be handled if joyned with a wound*, ibid. *How without a wound*, 295. *how kept from gangering*, ibid.
Contusion of the ribs, their cure, 296
Convulsions, the kinds and causes thereof, 221. *the cure*, 222. *why on the contrary part in wounds of the head*, 238
Convulsive twiching in broken members and the cause thereof, 343
Conies have taught the art of undermining, 40
Cornea tunica, 122
Corone, *what*, 165
Coronalis vena, 73
Corroborating medicines, 183
Cotyle *what*, 165. Cotyledones *what*, 85, 539
Courses how to provoke them, 520, 577. *how to stop them*, 528, 579. *The reason of their name*, 575. *Their causes*, ibid. *causes of their suppression*, 577. *what symptoms follow thereon*, ibid. *sypmtoms that follow their immoderate flowing*, 579
Crabs, 43
Cramp, the cause and cure thereof, 430
Cranes observe order in flying and keep watch, 41
Cremaster muscles, 79
Cridones what disease, and the cure, 215
Crocodiles may be tamed, 48
Crookedness how helped, 528
Crural vein, 152. *Artery*, 153
Crureus musculus, 158
Crus *how taken*, 152
Crystallinus humor, 123
Cubit, the bones and muscles thereof, 146
Cubit-bones, the fractures of them, 336
Cuboides os, 160
Cupping-glasses and their use, 412. *Their use and the cure of a Bubo*, 514
Cures accidental and strange, 31. *deceitful*, ibid.
Custom how forceable, 20
Cuticle, the matter, quantity, figure, &c. *thereof*, 56
Cuttel-fish, his craft, 43
Cysticæ gemellæ, 73

D.

Dartos, 79
Death, the inevitable cause thereof, 25. *How suddain to many*, 465
Definition of Surgery, 1
Definition how different from a description, 51
Defluxion of humours how diverted, 174
Delirium, *the causes thereof*, 225. *The cure*, ibid.
Deliverance in child-birth how furthered, 545. *Which difficult*, 559. *Which easie*, ibid.
Deltoides musculus 146
Dentifrices, *their differences, matter and form*, 655
Depilatories, 662
Derma, 56

Detersives, 176, 638. *their use*, ibid.
Devils, *and their differences*, 602. *Their titles and names*, ibid. *They are terrified and angered by divers things*, 604
Devil of the Sea, 613
Diabete *what*, *the causes*, *signs*, *and cure*, 408
Diaphoretick medicines, 636
Diaphragma, *See Midriff*, *why called* Phrenes, 93
Diaphysis *what*, 157
Diary fever, *the causes and signs*, 177. *the cure* ibid.
Diarthrosis, 165
Die-bone, 160
Diet hath power to alter or preserve the temperament, 17
Diet convenient for such as have the Gout, 421. *For such as fear the Stone*, 394. *In prevention of the Plague*, 493. *In the cure thereof*, 504
Differences of muscles, 59
Digitum flexores musculi, 150, 151, 161
Digitum tensores musculi, 150, 151, 161
Diploe *what*, 108
Disease the definition and division thereof, 25. *causes*, ibid.
Diseases strange and monstrous, 31
Diseases incident to sanguine, *cholerick*, *phlegmatick and melancholick persons*, 10. *whereof some are hereditary*, 534. *supernatural*, 604. *Monstrous accidents in them*, 608
Dislocations their kinds and manner, 346. *their differences*, 346, 347. *causes*, ibid. *Signs*, ibid. *prognosticks*, 348. *The general cure*, *Symptoms that may befall a dislocated member*, 349
Dislocation of the jaw, 351. *The cure*, ibid. *Of the Collar-bone*, 352. *Of the spine*, ibid. *Of the head*, 353 *Of the neck*, ibid. *Of the Rump*, 355. *Of the ribs*, ibid. *Of the shoulder*, 356. *Of the elbow*, 363. *Of the* Styliformis processus, 365. *Of the wrist*, ibid. *Of the afterwrist*, ibid. *Of the fingers*, 366. *Of the thigh or hip*, ibid. *Of the whirlbone*, 371. *Of the knee forwards*, ibid. *Of the greater and lesser Focile*, 372. *Of the heel*, ibid. *Of the Pastern or ankle-bone*, 373. *Of the instep and back of the foot*, ibid. *Of the toes*, ibid.
Dismembring, See *Amputation*,
Distemperature and the diversity thereof, 26
Distillation and the kinds thereof, 663. *Fornaces and the vessels therefore*, 664. *What to be considered therein*, 665. *How to prepare the materials therefore*, 667. *How to distill waters*, ibid. *How* Aqua vitæ, 668. *How to rectifie them*, 669. *To distill in the Sun*, ibid. *By filtring*, ibid. *Of Oils*, 670. *Of Spirits*, 733. *Of Oils of Gums*, ibid. *Of Oil of Vitriol*, 735
Docility of Beasts, 40
Dogs their love to their masters, 38. *Their docility*, 43. *Why they become mad sooner than other creatures*, 470. *How their bites may be known*, ibid. *Prognosticks*, 471. *The cure of such as are bitten by them*, 472
Doricinum, *the poysonous quality thereof and the cure*, 483
Doves free from adultery, 38
Draco marinus, *the Sea-Dragon his poysonous puncture*, *the symptoms and cure*, 481
Dracunculus *what*, 213. *The cure*, ibid.
Dragons their craft, 42
Dreams of the sanguine, *cholerick*, *phlegmatick*, *and melancholick persons*, 10. *Not to be neglected*, 23
Dropsie what, 202. *The differences*, *symptoms and causes*, ibid. *Signs and Prognosticks*, ibid. *The cure*, 203. *Following upon a tumor of the mesentery*, 566
Dugs, *their substance*, *magnitude*, &c. 90. *What to be done to dry up milk*, 558
Duodenum, *the magnitude*, &c. 68
Dura mater *what*, 109. *The hurts thereof by Trepanning*, *and how helped*, 251. *Remedies for the inflammation and Apostumation thereof*, ibid. *Why it easily endures acrid medicines*, ibid.

E.

Ears, *their parts and composure*, 126. *Their wounds and cure*, 257. *To supply their defects*, 528. *Their Ulcers*, 316. *Their stopping*, *and things falling into them how helped*, 386
Ears of the heart, 96
Ear-wax, *for what use it serves*, 126
Earth a cold and dry element, 3
Earthquakes their cause, 276
Ecchymosis *what*, *and how cured*, 230
Echo, *the cause thereof*, 127
Effects of Phlegm, 8. *Of choler and melancholy*, ibid.
Ejaculatory vessels in men, 79. *In women*, 84
Elbow the dislocation thereof, 363. *how to restore it dislocated outwardly*, ibid. *To the inside*, 364. *Why most subject to the* anchylosis, ibid.
Elements how understood, *and their principal qualities*, 3. *what those of generation are*, 4. *What those of mixt bodies are*, ibid. *The cause of their transmutation*, 275
Elephants, *their strength*, *piety*, &c. 39. *Where bred*, *and their qualities*, 624
Embalming the dead, 748. *The manner how*, 789
Embryon, *when it takes that name*, 542
Embrocation what, *and how performed*, 650
Emollient and resolving medicines, 186
Emplasters what, *their differences*, 647. *Signs they are perfectly boyled*, 648. *Their use*, 649. *Cautions in their application*, 182
Emplastrum *de Vigo* cum Mercurio, 648. De gratia Dei, *ibid.* De Betonica sive de Janua, *ibid.* Oxycroceum, 650. De cerusa, *ibid.* Tripharmacum seu nigrum, *ibid.* Diapalma seu Diacalcitheos, *ibid.* Contra Rupturam, *ibid.* De Mucilaginibus, *ibid.* De minio, *ibid.* Diachylum magnum, *ibid.*
Empyema *what*, 201. *The cure thereof*, ibid.
Emptiness, 23
Emulgens Arteria, 74. Vena, 76
Enarthrosis, *a kind of articulation*, 165
Enteroccle *a kind of Rupture*, 205
Ephemera febris, 177. *The causes and the signs thereof*, ibid. *The cure*, ibid.
Epidermis, 56
Epididymis, 79
Epigastrium *what*, 56. *The conteining parts thereof*, ibid.
Epigastrica vena, 77
Epiglottis *what*, 130
Epiploon *what*, 66
Epiplois vena, 74
Epiplocele, 205
Epithemes to strengthen the principal parts, 632. *their composition and use*, 651
Epomis musculus, 146
Epulis *what*, *the symptoms and cure*, 197
Epulotick, *or skinning medicines*, *their kinds and use*, 639
Errhines their differences, *description and use* 653
Erysipelas *what*, 178. *what tumor referred thereto*, 172. *the differences thereof*, 178
Erythrois tunica, 79
Eschar how to hasten the falling away thereof, 516. *Medicines causing it*, 640
Escharoticks, 640. *Why used to spread ulcers*, 267
Estridg between a bird and beast, 620. *The sceleton of one*, ibid.
Evacuation and the kinds thereof, 23. *What to be observed therein*, 24
Eunuchs assimilated to women, 16
Excrements of the first, *second*, *and third concoction what*, 542
Exercise, *the use and best time for it*, 21. *The quality thereof*, ibid.

Exomphalos, *or ſtanding forth of the navel*, 205
Exoſtoſis in Lue Venerea, 446
Experience without reaſon, of what account, 28
Eye-brows, 120
Eye-lids, ibid. *To ſtay them being too lax*, 377. *To open them faſtned together*, 378. *To help their itching*, 379
Eyes their ſite and quickneſs, 121. *Figure, compoſure*, &c. ibid. *Their muſcles, coats, and humors*, ibid. *their wounds*, 124. *to hide the loſs or defect of them*, ibid. *their ulcers*, 312. *their cure*, 313. *their affects*, 377, &c. *their inflammation*. 379

F.

FAce diſcloſer of affections and paſſions, 25. *the wounds thereof*, 252. *How to help the redneſs thereof*, 661
Faculties what, 13. *their diviſions*, ibid.
Falling down of the Fundament, the cauſes and cure thereof, 211
Fat, the ſubſtance, and cauſe, &c. *thereof*, 58. *Why not generated under the skull*, 252. *How to be diſtinguiſhed from the brain*, ibid. *the cure thereof being wounded*, ibid.
Fauces *what*, 129
Faulcon, her fight with the Hern. 45
Faults of conformation muſt be ſpeedily helped, 546. *Of the firſt concoction not helped in the after*, 421
Fear and the effects thereof, 24
Fever ſometimes, a ſymptom, otherwiſe a diſeaſe,
Fevers accompanying Flegmons and their cure, 176. *Happening upon Eryſipelous tumors*, 180. *Upon Oedematous tumors*, 187. *Upon Scirrhous tumors*, 192. *The cure of baſtard intermitting Fevers*. 194
Feet and their bones, 159. *Their twofold uſe*, 160
Fierce Clare a fiſh, 481
Females of what ſeed generated 535
Fibra auris *what*, 126
Fibula, 157
Figures in Anatomy, and the firſt of the fore part of man, 54. *Of the back parts thereof*, 55. *Of the lower belly, and parts thereof*, 64. *Of the ſtomach*, 66. *of the veſſels of ſeed and urine*, 77. *Of the bladder and yard*, 82. *Of the womb*, 84. *Of ſome parts in women different from thoſe of men*, 86. *Of the hollow vein*, 99. *Of Of the Arteries*, 102. *Of the rough Artery or weazon*, 104. *Firſt and ſecond of the brain*, 110. *Third of the* Cerebellum, 111. *Fourth and fifth of the brain*, 112. *The ſixth of the brain*, ibid. *Seventh ſhewing the Nerves of the brain*, 114. *The eighth of the brain*, 115. *Of the ſpinal marrow*, 117. *Of the Eye*, 122. *Of the chief muſcles of the face*, 125. *Of the lower jaw*, 126. *Of the Ears*, 127. *Of the back-bone*, 132. *Of the muſcles in ſundry parts of the body*, 134, &c. *Of the Nerves*, 146. *Of the bones in the hands*, 149. *Of the thigh-bone*, 155. *Of the bones in the feet*, 159. *Of the Sceleton*, 163, 164
Figures of inſtruments uſed in Surgery, See *Inſtruments*.
Figures of divers ſorts of javelins, and arrow-heads, 292
Figures of monſters, 586, &c. *Of divers beaſts*, &c. *as of Succarrath*, 37. *Of the Elephant*, 39, 623. *Rhinoceros*, 41. *Of the Camel*, 44. *Of the Crocodile*, 49. *Of the Crab*, 189. *Of the Scorpion*, &c. 455. *Of the Serpent Hemorrhous*, 474. *Of the Serpent Seps*, ibid. *Of the Baſilisk*, 475. *Of the Salamander*, 476. *Torpedo*, ibid. *Of the Sting Ray*, 481. *Of the Sea-hare*, ibid. *Of the Monk and Biſhop-fiſh*, 612. *Of the Sea-devil*, 613. *Of the Sea-Mors*, ibid. *Of the Sea-Bore*, 614. *Of the fiſh Hoga*, 616. *Of a Monſterous flying-fiſh*, ibid. *Of* Bernard *the Hermite*, 618. *Of the ſailing-fiſh*, ibid. *Of the Whale*, 619. *Of an Eſtridg*, 620. *Of the bird of Paradiſe*, 621. *Of a Giraffa*, 622. *Of a beaſt called Thanaſh*, 624. *Of the beaſt Haiit, and a monſtrous African-beaſt*, 625. *Of a Cameleon*, 626
Figures of Furnaces and other things fit for diſtillation, 665, &c.
Figure of a fractured arm with a wound in a fit poſture, 337. *Of a Leg fractured with a wound and bound up*, 341. *Of Ligature for extention*, 350. *How to reſtore the diſlocated ſpine*, 354. *Of putting the ſhoulder into joynt*, 356, *to* 360. *Of the Ambi and the uſe thereof*, 361. *Of reſtoring the diſlocated elbow*, 364. *Of the thigh-bone diſlocated inwards*, 369. *Outwards*, 370. *Of reſtoring a knee diſlocated forwards*, 371
Figure of a Semicupium, 371. *Of a Barrel to be uſed in the cure of a Caruncle*, 444. *Of the Helmet flower*, 484. *Of the ſituation of the Child in the womb*, 544. *Of leaden-nipples*, 553. *Of a glaſs to ſuck the breaſts with*, 558
Figures of Artificial Eyes, 524. *Of the noſes*, 525. *Of teeth*, 526. *Palats*, 527. *How to ſupply the defect of the tongue*, ibid. *Of the Ears*, 528. *Iron Breaſt-plates*, 529. *Of an urin-baſin and Artificial-yard*, ibid. *Of an iron-finger-ſtall*, 530. *Of an Erector of the hand*, ibid. *Of boots for ſuch as are crook-legged*, 531. *Of an artificial-hand*, 532. *Of an arm and leg*, 533, 534. *Of a crutch*, 535
Filings of Lead, their harm taken inwardly, and cure, 486
Filtration the manner and uſe thereof,
Fingers and their parts, &c. 148. *their diſlocation, why eaſily reſtored*, 366. *how to take away ſuch as be ſuperfluous, and help thoſe that ſtick together*, 390. *How to ſupply their defects*, 532
Fire and the qualities thereof, 3. *The force thereof againſt the Plague*, 494
Fiſhes their induſtry, 41. *They may be tamed*, 38
Fiſherman, a fiſh ſo called, 42
Flatulent tumors, their cauſes, ſigns, and cures, 182, 183
Flatulencies about the joynts, counterfeiting the Gout, 428
Fiſtula lacrymoſa, *See* Ægylops.
Fiſtulas what, their differences, ſigns, &c. 320. *Their cure*, ibid. *In the Fundament*, 321. *The cure*, ibid. *Upon the wounds of the cheſt, and the cure*, 260
Fleſhy Panicle, the Hiſtory thereof, 57
Fleſh quickly putrifies in maritime parts, 277
Flexores muſculi, 156
Flux of blood in wounds how helped, 220
Flux of the belly how to be ſtopped, 522
Flying fiſh of a Monſtrous ſhape, 618
Focile *what*, 157. *How to cure the ſeparation of the greater and leſſer*, 372. *The ſeparation from the paſtern-bone*, 373
Fomentations and their uſe, 650. *For broken bones*, 346. *They hurt plethorick bodies*, ibid. *What to be obſerved in their uſe*, ibid.
Fornaces, their matter and form, 664, &c.
Fornix, 113
Foxes and their crafts, 40
Fracture what, and the differences thereof, 237. *Their cauſes*, ibid. *Signs and Prognoſticks*, 328. *Their general cure*, 329
How to help the ſymptoms. 330. *Why deadly in the joynt of the ſhoulder*, 333. *Why near a joynt more dangerous*, 340
Fractures of the skull, their differences, 225. *Of the cauſes and ſigns*, 227. *Signs manifeſt to Senſe*. ibid. *A fiſſure the firſt kind of fracture*, 228. *How to find it being leſs manifeſt*, ibid. *A contuſion the ſecond kind of fracture*, 230. *An effracture the third kind*, 232. *A Seat the fourth kind*, 233. Reſonitus *the fifth kind*, 234. *The prognoſticks*, 236. *general cure of them*

and their ſymptoms, 239. *They are hurt by Venery*, 241. *By noiſe*, ibid. *The particular cure*, 243. *Why trepanned*, 244

Fractures more particularly, and firſt of the noſe, 331. *Of the lower-jaw*, ibid. *Of the Collar-bone*, 332. *Of the ſhoulder-blade*, ibid. *Of the breaſt-bone*, 333. *Of the Ribs*, ibid. *Of the* vertebræ, *or Rack-bones*, 335. *Of the Holy-bone*, ibid. *Of the Rump*, ibid. *Of the Hip*, 336. *Of the Shoulder or Arm-bone*, ibid. *Of the Cubit or Ell and Wand*, ibid. *Of the Hand*, 337. *Of the Thigh*, ibid. *Of the Thigh near the joynt*, 339. *Of the* patella *or whirl-bone*, 340. *Of the leg*, ibid. *Of the bones of the feet*, 346

Fractures aſſociated with wounds, how to be bound up, 325, 341

French Pox, See Lues Venerea.

Fricſions their kinds and uſe. 21

Fuci, *how made*, 660

Fumigations, their differences, matter and form, 656

Fundament the falling down thereof, 211. *the cauſes and cures*, ibid.

Fungus, *an exereſcence ſometimes happening in Fractures of the ſcull*, 248

G.

GAlens *Effigies and praiſe*, 678

Gall and the bladder thereof, &c. 72

Ganglion, *what, properly ſo called*, 185

Gangrene, what, 299. *The general and particular cauſes*, ibid. *That which is occaſioned by cold, upon what part it ſeizes*, 300. *Signs*, ibid. *Prognoſticks*, 301. *The general cure*, ibid. *The particular cure*, ibid.

Gargareon, 129

Gargariſms, their matter and form, 642. *repelling, repining and detergent ones*, 200, 201

Garlick good againſt the Plague, 494

Gaſtrica vena, 73

Gaſtrepiplois vena, *ibid.* Major, 74

Geeſe their warineſs in flying over mount Taurus, 41

Gemelli muſculi, 161

Gemini muſculi, 146

Generation, what it is, 14. *What neceſſary thereto*, 535

Generation, of the Navil, 540

Giddineſs, See Vertigo.

Ginglymos *what*, 165

Giraffa, a ſtrange beaſt, 622

Glandula, *what ſort of tumor*, 198

Glandula lacrymalis, 121

Glandules in general, 71. *At the root of the tongue*, 129 *Their inflammation and cure*, 198

Glans penis, 83. *Not rightly perforated, how to be helped*, 391

Glyſters, their differences, materials, &c. 654. *Several deſcriptions of them*, ibid. *They may nouriſh*, ibid.

Goats dung is good to diſcuſs ſchirrous tumors, 189

Golden ligatures, how made, 208

Gomphoſis *what*, 166

Gonorrhœa, *how different from a virulent ſtrangury*, 440 *the cure*, 441

Gout the names and kinds thereof, 414. *the occult cauſes thereof*, ibid. *the manifeſt cauſes thereof*, 416. *out of what parts it may flow*, ibid. *ſigns that it flows from the Brain, or Liver*, 417. *How to know this or that humor accompanying the Gouty malignity*, ibid. *Prognoſticks*, ibid. *The general method to prevent and cure it*, 418. *Vomiting ſometimes good*, 419. *Other general remedies*, 420. *Diet convenient*, 421. *What wine not good*, ibid. *How to ſtrengthen the joynts* ibid. *The palliative cure thereof*, 422. *Local medicines in a cold Gout*, 423. *In a hot or ſanguine Gout*, 424. *In a Cholerick Gout*, 425. *What is to be done after the fit is over*, 427. Tophi *or knots how cauſed*, ibid. *The Hip-gout or Sciatica*, 428. *The cure thereof*, 429

Griſtles what, 90. *of the noſe*, 124. *of the* Larinx, 130

Groins their wounds, 266. *Their Tumors*, See *Bubos.*

Guajacum, *the choice faculties and parts*, 433. *The preparation of the decoction thereof*, ibid. *The uſe*, 434.

Gullet and the hiſtory theref, 105. *The wounds thereof*, 257

Gums overgrown with fleſh, how to be helped, 197

Guns their inventor, 270. *Their force*, 271. *the cauſe of their reports*, 276

Gun-powder not poiſonous, 273. *How made*, 274

Gutta roſacea *what*, 661. *The cure*, ibid.

Guts their ſubſtance, figure and number, 68. *Their ſite and connexion*, 69. *Action*, ibid. *How to be taken forth*, 76. *Signs that they are wounded*, 264. *Their cure*, 265. *Their Ulcers*, 217

H.

HÆmorrhoids *what, their differences and cure*, 321. *In the neck of the womb*, 582

Hæmorrhoidalis interna, 74. Externa, 77

Hæmorrhoidalis arteria, ſive meſenterica inferior, 74

Hæmorrhous, *a Serpent his bite, the ſigns and cure*, 474

Haiit, *a ſtrange beaſt*, 625

Hair, what the original and uſe, 106. *How to make it black*, 662. *How to take it off*, ibid.

Hairy ſcalp, the connexion and uſe, 106. *The wounds thereof not to be neglected*, 107. *The cure thereof being contuſed*, 242

Hand taken generally, what, 141. *The fracture thereof with the cure*, 337. *How to ſupply the defects thereof*, 530

Hares how they provide for their young, 38

Hare-lips what, 390. *Their cure*, ibid.

Harmonia *what*, 166

Hawks, 45

Head, the general deſcription thereof, 106. *The conteining and contained pars thereof*, ibid. *The muſculous skin thereof*, ibid. *Why affected when any membranous part is hurt*, 107. *The wounds thereof*, 225, &c. *The falling away of the hair and other affects thereof*, 375. *The diſlocation thereof*, 355

Hearing, the organ, object, &c. *thereof*, 14

Heart, and the hiſtory thereof, 95. *The ventricles thereof*, 96. *Signs of the wounds thereof*, 259

Heat, one and the ſame efficient cauſe of all humors at the ſame time, 7. *three cauſes thereof*, 169

Hectick fever with the differences, cauſes, ſigns, and cure, 262

Hedg-hogs, how they provide for their young, 38

Heel, and the parts thereof, 160. *Why a fracture thereof ſo dangerous*, ibid. *The diſlocation thereof*, 372. *Symptoms following upon the contuſion thereof*, ibid. *Why ſubject to inflammation*, ibid.

Hemicrania, See *Megrim.*

Hemlock the poyſonous quality thereof, and the cure, 484

Henbane and the poyſonous quality and the cure, 483

Hermaphrodites, 17, *and* 592

Heron, his fight and the Falcon, 45

Hernie, *and the kinds thereof*, 205

Humeralis, 211

Herpes and the kinds thereof, 179. *The cure*, ibid.

Hip-gout, *See* Sciatica

Hip, the diſlocation thereof, 366. *Prognoſticks*, 348. *Signs, that it is diſlocated outwardly or inward*, 367. *Diſlocated forwards*, 368. *backwards*, ibid. *How to reſtore the inward diſlocation*, 369. *the forward diſlocation*, 370. *the backward diſlocation*, ibid.

Hippocrates *his Effigies*, 676

Hoga, *a Monstrous fish*, 616
Holes of the inner basis of the scull. 116. *of the external basis ther eof*, ibid.
Holy-bone, its number of Vertebræ, *and their use*, 132. *the fractures thereof*, 335
Hordeolum, *an affect of the Eye-lids*, 378
Horns used instead of Ventoses, 413
Horse-leeches, their application and use, 414. *Their virulency and the cure*, ibid.
Hot-houses how made, 659
Hulpales *a Monstrous beast*, 622
Humeraria arteria, 103. Vena, 142
Humors their temperaments, 6. *the knowledge of them necessary*, ibid. *their definition and division*, ibid. *serous and secondary*; *as* Ros Cambium, Gluten, 9. *an argument of their great putrefaction*, 277
Humors of the Eye, 121
Aqueus, 123
Cryſtallinus, *ibid.*
Vitreus, 124
Hydatis, 378
Hydrargyrum, *the choice preparation, and use thereof in the* Lues Venerea, 436
Hydrocephalia, *whether incurable*, 471. *What cure must be used therein*, 472
Hydrocephalos *what*, 195. *The causes, differences, signs*, &c. ibid. *the cure*, 196
Hydrocele, 205, 210
Hymen, 570
Whether any or no, ibid. *A history thereof*, 571
Hyoides os, *the reason of the name, composure, site*, &c. *thereof*, 128
Hypocondria, *their site*, 55
Hypochyma, 383
Hypogaſtricæ venæ, 77
Hypopyon, 383
Hypothenar, 151

I.

Jaundise, a medicine therefore, 204
Jaw, the bones thereof, and their productions, 118, 119
The fracture of the lower jaw, 331. *How to help it*, ibid. *The dislocation thereof*, 351. *The cure*, ibid.
Ibis, *a bird, the inventor of glysters*, 34
Ichneumon, *how he arms himself to assail the Crocodile*, 39
Idleness the discommodites thereof, 22
Jejunum inteſtinum, 69
Ileon, ibid.
Iliaca arteria, 76. Vena, ibid.
Ilium os, 154
Ill conformation, 26
Imagination and the force thereof, 541
Impostors, their impudence and craft, 32, 249
Impostume, what their causes and differences, 169. *signs of them in general*, 170. *prognosticks*, 171. *What considerable in opening of them*, ibid.
Inanition, See *Emptiness*.
Incus, 108, 127.
Indication, whence to be drawn, 2. *of feeding*, 20. *what*, 26. *the kinds*, ibid. *the table of them*, 30. *observable in wounds by gun-shot*, 283
Infant what he must take before he suck, 548. *their crying what it doth*, 554. *how to be preserved in the womb when the mother is dead*, 561. See *Child*.
Inflammation of the almonds of the throat, and their cure, 198. *of the* Uvula, ibid. *of the eyes*, 379
Inflammation hinders the reposition or putting dislocated members into joynt. 372
Inſeſſus, *what, their manner, matter and use*, 656
INSTRUMENTS, used in Surgery for opening abscesses, 175. *A vent for the womb*, 192, 581. *An iron-plate and actual cautery for the cure of the* Ranula, 198. *Constrictory rings to bind the* Columella, 199. Speculum oris, 223. *A trunck with cautery to cauterize the* Uvula, 199. *An incision-kife*, 201. *An actual cautery with the plate, for the cure of the* Empyema, 202. *of a pipe to evacuate the water in the Dropsie*, 204. *wherewith to make the golden ligature*, 208. *to stitch up wounds*, 220. *A razor or incision-knife*, 228. *a chizzel*, ibid. Radulæ vel ſcalpri, 229. *a three-footed levatory*, 250. *other levatories*, 231. *Saws to divide the skull*, ibid. *a desquamatory Trepan*, ibid. Roſtra plittaci, 232. *Scrapers, pincers and a leaden mallet*, 233. *a piercer to enter a Trepan*, 244. *Trepans*, 245. *Terebellum*, 246. *A lentil-like Scraper*, ibid. *cutting-compasses*, ibid. *A conduit-pipe, and syringe*, 248. *to depress the* dura Ma[illegible]. Speculum oculi, 253. *for making a Seton*, 254. [illegible] *used in the wounds of the chest*, 261. *to draw out bullets*, 279, &c. *Dilaters and Probes to draw through flammulas*, 280, 281. *to draw forth arrow-heads*, 292. *A scarificator*, 295. *A dismembring knife and saw*, 303. *A dilator to open the mouth*, 307. *A Pyoulcos, or matter drawer*, 316. *A* Gloſſocomium, 338. *A lattin case*, 343. *A pully and hand-vice*, 350. *the* Gloſſocomium *called* Ambi, 360. *little hooks, needles and an incision-knife to take away the Web*, 381. *files for filing the teeth*, 388. *for cleansing and drawing the teeth*, 389. *cutting mullets to take off superfluous fingers*, 391. *Catheters*, 393. *Gimlet to break the stone in the passage of the yard*, 396. *other instruments to take out the stone*, ibid. *used in cutting for the stone*, 398, 403. *A lancet, and cupping-glasses*, 413. *Horns to be used for ventoses*, ibid. *Catheters to wear away caruncles*, 445. *Trepans for rotten bones*, 447. *actual cauteries*, 448. *Griffins talons*, 565. *Hooks to draw forth the child*, 556. Speculum matricis, 582
Instruments, when necessary in restoring broken bones, 329
Intercartilaginei muſculi, 140
Intercoſtalis arteria, 74, 101
Intercoſtales muſculi externi, 140. Interni, ibid.
Interoſſes muſculi, 151, 162
Inteſtinalis vena, 73
Intromoventes muſculi, 156
Joy, and the effects thereof, 24
Joints, their wounds, 268. *how to strengthen them*, 421 *how to mitigate their pains caused only by distemper*, 426
Iſchiadica vena, 152. Iſchium os, 154
Issues, or fontanels, 420
Itching of the womb, 583
Judgment, why difficult, 680
Junks, what, 326. *their use*, ibid.

K.

Kall, its substance, &c. 66. *what to be done when it falls out in wounds*, 265
Kernels of the ears, 126
Kibes, where bred, 161
Kidnies, their substance, &c. 77. *signs that they are wounded*, 264. *Ulcers, and their cure*, 317, 407. *their heat how tempered*, 512
Kings-evil, what, the cause, 186. *the cure*, ibid.
Knee dislocated forward, how to restore it, 371

Lago-

L.

LAgophthalmia, *what*, 253. *the causes and cure*, 377
Lameness how helped, 533
Lamply their care of their young, 41
Lampron, their poysonous bite, 480
Larynx, *what meant thereby*, 129. *its magnitude, figure, composure*, &c. 130
Latissimus musculus, 141
Leeches, See *Horse-leeches*.
Leg, taken in general, what, 152. *the bones thereof*, 157. *the wounds*, 266. *the fracture and cure*, 340. *the cure of the Authors leg being broken* 342. *their crookedness how helped*, 532. *defect supplied*, 531
Leprosie and the causes thereof, 460. *the signs*, 461, &c. *called* Morbus leoninus, ibid. *the Prognosticks, diet, cure*, 463. *it sometimes follows the* Lues Venerea, 431
Lepus Marinus, *the poyson, the symptoms and cure*, 482
Levator musculus 141. Levatores Ani, 69
Life what, and its effects, See *Soul*.
Ligaments, their use, 62. *why without sence*, 133. *their difference*, ibid. *their wounds*, 269
Ligatures for wounds are of three sorts, 218. *too hard, hurtful*, 250. *they must be neatly made*, 323. *for what uses they chiefly serve*, 325. *in use at this day for fractures*, 338. *how in fractures joyned with wounds*, 341. *which for extention*, 349. See Bandages.
Lightning, the wonderful nature, and the stinking smell thereof, 275. *how it may infect the Air*, 467
Lime unquencht, the hurtful quality and cure, 486
Liniments are not to be used in wounds of the chest, 260. *their matter, form, and use*. 751
Lion, his provident care in going, 39
Lion of the Sea, 612
Lippitudo, 379
Litharge its poysonous quality and cure, 486
Liver, what, 71. *its substance*, ibid. *signs of the wounds thereof*, 264. *why it is called* parenchyma, 541
Loins, their nerves, 153
Longus musculus, 148, 157
Lues Venerea, *what*, 430. *the hurt it causeth*, ibid. *the causes thereof*, 431. *in what humor the malignity resideth*, 432. *it causes more pain in the night then in the day*, ibid. *sometimes lies long hid*, ibid. *signs thereof*, ibid. *prognosticks*, 433. *how to be oppugned*, ibid. *to whom wine may be allowed*, 435. *the second manner of cure*, ibid. *the third manner of cure*, 438. *the fourth manner*, 439. *how to cure its symptoms*, ibid. *it causes bunches on the bones*, 446. *rotten bones, how perceived and cured*, ibid. *tetters and chops occasioned thereby, and their cure*, 450. *how to cure children of this disease*, 451. *it kills by excess of moisture*, 466
Lumbaris regio, sive lumbi, 153. Arteria, 75. Vena, 76
Lumbrici musculi, 151, 162
Lungs their substance, &c. 94. *signs of their wounds*, 259. *which curable*, 261
Luxation, 346. *which incurable*, 348
Lying in bed, how it must be, 22

M.

MAd dog, See *Dog*.
Magick, *and the power thereof*, 604
Magistrates office in time of the Plague, 498
Males of what seed generated, 537
Malleolus, *one of the bones of the auditory passage*, 108, 127
Mammillary processes, 111. *their use*, 113
Mammaria arteria, 101
Man his excellency, 47, &c. *the division of his body*, 53. *why distinguished into male and female*, 537
Mandrag, its danger and cure, 483
Marrow, why it may seem to have the sense of feeling, 345
Masseter *muscle*, 126
Mastoideus musculus, 134
Masticatories, their form and use, 654
Matrix, See *Womb*.
Meadow-saffron, the poysonous quality thereof, and cure, 483
Meat, the quantity and quality thereof, 19. *accustomed more grateful and nourishing*, ibid. *order to be observed in eating*, 20. *the time*, ibid. *fit to generate a* Callus, 345
Meazels, what their matter, 452. *why they itch not*, ibid. *their cure*, 453
Mediastinum *its substance*, &c. 93
Medicines their excellency, 629. *their definition and difference in matter and substance*, ibid. *in qualities and of the first faculties*, 630. *their second, third, and fourth faculties*, 631, 632. *the preparation*, 634. *the composition, neeessity and use thereof*, 641. *Megrim, the causes*, &c. *thereof*, 356
Melancholy, the tempers thereof, 8. *the nature, consistence*, &c. ibid. *the effects thereof*, 8. *of it corrupted*, 9
Melancholick persons, their complexions, &c. 10. *why they hurt themselves*, 470
Meliceris, *what kind of tumor*, 184
Membranosus musculus, 157
Memory what, 542
Menstrual flux, signs of the first approach thereof, 578. See *Courses*.
Meninges, *their number*, &c. 109
Mercury sublimate, its caustick force, 486. *the cure*, ibid.
Mermaid, 611
Mesentery its substance, &c. 70. *the tumors thereof*, 565. *the sink of the body*. ibid.
Midriff, its substance, &c. 93. *signs of the wounds thereof*, 259
Milk soon corrupts in a Phlegmatick stomack, 548. *the choice thereof*, ibid. *how to drive it downwards*, 558
Millepes *cast forth by urine*, 455
Milt, See *Spleen*.
Mola, *the reason of the name, and how bred*, 562. *how to be discerned from a true conception*, ibid. *a history and description of a strange one*, 563. *the figure thereof*, ibid. *what cure to be used thereto*, 564
Mollifying medicines, 796
Monk's hood, the poyson and cure, 483
Monstrous creatures bred in man, 455
Monsters what, 585. *their causes and descriptions*, ibid. &c. *caused by the defect of seed*, 594. *by imagination*, 596. *by straightness of the womb*, 597. *by the site of the mother, by a stroak*, &c. ibid. *by confusion of the seed of divers kinds, by the craft of the devil*, 599, &c. *Monsters of the Sea*, 611
Morse, Sea-calf, or Elephant, 613, 614
Mortification, and the signs thereof, 302
Mother, See *Womb*.
Mothers fittest to nurse their own Children, 548. *their milk most familiar to them*, ibid.
Motion, which voluntary, 15. *taken for all manner of exercise*, 21
Mouth and the parts thereof, 129. *the ulcers and their cure*, 315. *how to prevent and heal them in cure of the* Lues Venerea, 438
Mummy, frequently used in contusions, 296. *not good therein*, 297

Mundificatives, 638
Muſcles, what, 59. *their differences, and whence taken*, ibid. *and* 60. &c. *their parts*, 61. *a further inquiry into the parts of them*, ibid.
Muſcles, of the Epigaſtrium, 63. *of the fundament*, 69. *of the teſticles*, 78. *of the bladder*, 81. *of the yard*, 83. *the broad muſcle*, 120. *that open and ſhut the eye*, ibid. *of the eye*, 121. *of the the noſe*, 124. *of the face*, ibid. *of the lower-jaw*, 125. *of the bone* Hyoides, 128. *of the tongue*, ibid. *of the* Larinx, 130. *of the* Epiglottis, 131. *of the neck*, 133. *of the cheſt and loins*, 140. *of the ſhoulder-blade*, ibid. *of the arm*, 145. *of the cubit*, 146. *moving the hand*, 150. *of the inſide of the hand*, ibid. *moving the thigh*, 156, *of the leg*, 157. *moving the foot*, 161. *of the toes*, 162. *an Epitome or brief recital of all the muſcles*, 167
Muſculous skin of the head, 106. *the wounds thereof and their cure*, 241
Muſculoſæ venæ 76. Arteriæ. 103
Muſhroms, their hurtful and deadly quality, and the cure, 483
Muſick, the power thereof, 31
Mydryaſis, *a diſeaſe of the eye, the cauſe and cure*, 383

N.

Nails, why added to the fingers, 142. *why grow continually*, ibid. *whence generated.* 149
Napellus, *the poyſonous quality and cure*, 483
Narcoticks, 174. *cautions in their uſe*, 179. *improperly termed Anodynes*, 641
Nata, *what*, 184
Nates, 112
Nature oft doth ſtrange things in curing diſeaſes, 257
Natural parts, and their diviſion, 53
Natural, See *Things, Faculties, Actions*,
Navel, what, the figure and compoſure, 88. *the generation thereof*, 540. *the relaxation thereof in children*, 584. *the ſwelling or ſtanding forth thereof*, 205. *the cure*, ibid.
Nautilus, *or ſailing-fiſh*, 618
Neck, and the parts thereof, 131. *the wounds thereof*, 257. *the diſlocation thereof*, 353
Necroſis, *or mortification*, 302
Nerves what, 62. *their diſtribution to the natural parts*, 75. *of the ſixth conjugation, and their diſtribution*, 101. Ramus coſtalis, *ibid.* recurrens, ibid. ſtomachicus, ibid. *their ſeven conjugations*, 113
Nerves of the neck, back and arms, 144. *of the loins, holy-bone, and thigh.* 153
Nerves and nervous parts, their wounds, 266. *their cure*, ibid.
Night-ſhade, the deadly night-ſhade, his poyſonus quality, and the cure, 483
Nightingals ſing excellently, 44
Nipples, 91. *how to help their ſoreneſs*, 553
Nodus, *what*, 184
Nodules, *their form and uſe*, 644
Northern people how tempered, 11, 12
Noſe, and the parts thereof, 124. *the wounds thereof*, 256. *their cure*, ibid. *how to ſupply the defects thereof*, 525. *the ulcers thereof*, 315. *their cure*, ibid. *the fracture*, 331
Nurſes, their error in binding and lacing of Children, 335. *they may infect Children with the* Lues Venerea, *and be infected by them*, 431. *participate their diſeaſes to their children*, 548. *the choice of them*, ibid, &c. *of their diet, and other circumſtances*, 550, &c.
Nutrition, what, 13
Nymphæ, 87

O.

OBlique deſcendent muſcles, 63. *aſcendent muſcles*, ibid.
Obliquator externus muſculus, 150
Obturitores muſculi, 156
Oedema, *what*, 181. *which tumors referred thereto*, 172 *the differences thereof*, 181. *ſigns, prognoſticks, cure*, 182
Oeſophagus, *or gullet, the ſubſtance, attractive force*, &c. *thereof*, 105, *the magnitude, figure, ſite, temper, and action*, ibid.
Oil of whelps, the deſcription, and uſe thereof, 272. *it helps forward the ſcaling of bones*, 449
Oils and the ſeveral making of them, 645, 670. *by diſtillation*, 670. *out of gums*, 673
Ointments, their differences, deſcriptions, and uſe, 645, &c.
Old-age, and the diviſion thereof, 5. *it is a diſeaſe*, 19
Old wives medicines, 605
Olecranum, *what*, 147
Omentum, *or the Kall, the ſubſtance, magnitude, figure, and compoſure thereof*, 66. *the connexion, temper, and two-fold uſe*, ibid. *it ſometimes hinders conception*, ibid.
Operations of Surgery, of what nature, 1. *why ſome which are mentioned by the Antients, are omitted by the Author*, 690
Opium, *why not uſed in poyſoning*, 484. *the ſymptoms cauſed by it, and their cure*, ibid.
Order to be obſerved in eating our meat, &c. 20. *in lying to ſleep*, 22. *Organical parts, which*, 51. *what obſervable in each of them*, ibid. *Orifices of the heart.* 96
Orpiment, the poyſonous quality thereof, and the cure, 486
Os & oſſa, occipitis, 108. Baſiliare, *ibid.* Coronale, *ibid.* Bregmatis, ſive parietalia, *ibid.* Petroſa, *ibid.* Cuniforme, ſive phenoides, *ibid.* Ethmoides, cribroſum, ſeu ſpongioſum, *ibid.* Zygoma, ſive jugale, 118. Hyoides, hypſiloides, &c. 128, &c. Seſamoides, 149
Ilium, 154
Iſchium, ibid.
Pubis, ibid.
Innominata, 160. See *Bones.*
Ozæna, *a filthy ulcer of the noſe, the cauſe, and cure*, 315

P.

PAin and the cauſes thereof, 169
It muſt be aſſwaged, 221
The diſcommodities thereof, ibid.
In wounds how helped, ibid.
Palat, the nerves, holes, and coat thereof, &c. 129
How to ſupply the defects thereof, 526
Palmaris muſculus, 150
Palſie, the differences, cauſes, &c. *thereof*, 223. *The cure*, ibid
Follows upon wounds of the neck, 258
Pancreas, *the ſubſtance, ſite*, &c. *thereof*, 71, &c.
The tumors thereof, 565
Pannicle, See *fleſhy*,
Pap, how to be made for children, 553. *and the condition thereof*, ibid.
Paracenteſis, *and the reaſons for and againſt it*, 203
The place where, and manner how, ibid.
Paraſſoupi, *a ſtrange beaſt*, 622
Paraſtates, *their ſubſtance*, &c. 79

The TABLE.

Paronychia, *what*, 212
The cure, ibid.
Parotides, *their ſite and uſe*, 126
Their difference, prognoſticks, cure, &c. 196,197
Partridge, their care of their young, 37
Parts, ſimilar, 51
Organical, ibid.
Inſtrumental, 52
Things conſiderable in each part, ibid.
Principal parts which, and why ſo called, ibid.
Of generation, diſtinguiſhed into three, 53
The conteining parts of the lower belly, 56. *Of a Muſcle*, 61
Of the cheſt, 90
Paſſions of the mind, their force, 24
They help forward putrefaction, 492
Paſtinaca marina, *or the ſting-ray*, 481
Patella, *what*, 158
Pectoralis muſculus, 141
Pedium, *what*, 162
Pedioſus muſculus, 162
Pelvis, *the ſite and the uſes thereof*, 112
Pericardium, *and the hiſtory thereof*, 94, 95
Pericranium, *what, and the uſes thereof*, 106,107
Perinæum, *what*, 82
Perioſtium, 107
Peritonæum, *the ſubſtance and quality thereof*, 65
the figure, compoſure, ſite, uſe, &c. ibid.
Perone, 157
Peroneus muſculus, 161
Perturbations of the mind, See Paſſions.
Peſſaries their form and uſe, 644
Peſtilence, See *Plague*.
Peſtilent fever, how bred, 503
Pharinx, *what*, 129
Phlebotomy, the invention thereof, 34
Neceſſary in a Synochus putrida, 178
The uſe, ſcope, &c. *thereof*,
How to be performed, ibid. See *Blood letting*.
Phlegm, the temper thereof, 7
Is blood half concocted, ibid.
Why it hath no proper receptacle, ibid.
The nature, conſiſtence, color, taſt and uſe, ibid.
The effects thereof, 8
Not natural, how bred, and the kinds thereof,, 9
How many was it times ſo, 181
Phlegmatick perſons their manners and diſeaſes, 10
In faſting they feed upon themſelves, 421
Phlegmon, what kind of tumor, 172
What tumors may be reduced thereto, ibid.
How different from a phlegmonous tumor, ibid.
How generated, 173
The cauſes and ſigns thereof, ibid.
The cure, ibid.
The cure when it is ulcerated, 175
Phrenica Arteria, 74
Phthiſis oculi, 381
Phymoſis & paraphymoſis, *what*, 391
Phyſick, the ſubjecti thereof, 51
Phyſitians to have care of ſuch as have the plague, how to be choſen, 499
Phyſocele, 205
Pia mater, *the conſiſtence, uſe*, &c. 109
Pigeons, See *Doves*,
Pilot-fiſh, 41
Pine glandule, 112
Pinna auris, *which*, 126
Pinna & Pinnoter, 676
Piſmire. See *Ant*.
Pith of the back, 117
Plague what, 490. *How it comes to kill*, ibid. *Divine cauſes thereof*, ibid. *Natural cauſes*, 491. *Signs of the air and earth that prognoſticate it*, 492. *Cautions in air and diet to prevent it*, 493. *Preſervatives againſt it*, 494, &c. *Other obſervations for prevention*, 497. *Such as dye thereof quickly putrifie*, 498. *How ſuch as undertake the cure thereof muſt arm themſelves*, 499. *Signs of infection*, 500. *Mortal Signs*, ibid. *Signs thereof, without fault of the humors*, 501. *with the putrifaction of them*, ibid. *Prognoſticks, therein*, 502. *What to be done, when one finds himſelf infected*, 503. *Diet*, 504, &c. *Antidotes*, 507, &c. *Epithemes to ſtrengthen the principal parts*, 508. *Whether purging and bleeding, be neceſſary at the beginning*, ibid. *What purges fit*, 510, &c. *Symptoms accompanying the diſeaſe*, 511. *Spots or tokens*, 512. *Their cure*, 513 *Sores* 514, &c. See *Bubos and Carbuncles*. *Sundry evacuations*, 519, &c. *How to cure infants and children thereof*, 523
Plaiſter, and the hurtful quality thereof, and the cure, 486
Plaſter See *Emplaſters*.
Plantaris muſculus, 161
Pleura, *what, the original, magnitude, figure*, &c. 92
Pleuriſie, what, 201
Plexus choroides, 111
Pneumatocele, 210
Polypus, *the reaſon of the name*, 196
The differences, ibid.
The cure, ibid.
Poplitæus muſculus, 159
Porus biliaris, 73
Potential cauteries, 651
Pox, French-Pox. Lues Venerea
Small Pox what, their matter, 452
What pernitious ſymptoms may follow upon them, ibid.
Prognoſticks, ibid.
The cure, 453
What parts to be armed againſt, and preſerved therefrom, 454
Poyſons, the cauſe of writing them, 463
What they are, ibid.
Their differences, ibid.
All of them have not a peculiar Antipathy with the heart, 464
How in ſmall quantities they may work great alterations by touch only, ibid.
The reaſon of their wondrous effects, ibid.
None of them kill at a ſet time, ibid. *How they kill ſooner or later*, ibid. *Whether things feeding on poyſons be poyſonous*, 465
General ſigns that one is poyſoned, ibid. *How to ſhun poyſon*, 466. *The general cure of poyſons*, 467. *Whether vapours ariſing from things burnt, may poyſon one*, ibid. *Each poyſon hath its proper effects*, 468. *Their effects and prognoſticks*, ibid. *The cure of poyſonous bites*, 469.
Poyſon of Adders, Aſps, Toads, &c. See *Adders, Aſps, Toads*, &c.
Poyſonous plants, and the remedies againſt them, 483, &c.
Poyſons of minerals and their remedies, 486
Præputium, 83, *to help the ſhortneſs thereof, and ſuch as have been circumciſed*, 391. *the ulcers thereof are worſe than thoſe of the* Glans, 439
Preparations of ſimple medicines, and the divers kinds thereof, 634
Preſervatives againſt the Plague, 494, &c.
Principal parts which, and why ſo called, 52
Proceſſus mammillares, 112
Proceſſes of the Vertebræ, *right, oblique, tranſverſe*, 131, &c. *that called the tooth*, ibid. Acromium *and* Coracoides, 141
Prodigy, what, 585. *divers of them*, 586, &c.
Prognoſticks in Impoſthumes, 171. *in an* Eryſipelas, 180 *in an* Oedema, 181. *in a* Scirrhus 188. *in a quartain*

tain Ague,193. *in an* Aneurisma,194. *in the* Parotides, 197. *in the Dropsie*, 203. *in a Sarcocele*, 211. *in wounds*, 217. *in fractures of the scull*, 236. *in wounds of the liver and guts*, 264. *in a gangrene*, 301. *in ulcers*, 309. *in fractures*, 328. *in Dislocations*, 348. *in a dislocated jaw*,351. *in the dislocated* Vertebræ,355. *in a dislocated Hip*, 366. *in the stone*, 393. *in suppression of the urine*, 406. *in the ulcerated reins and bladder*, 407. *in the Gout*, 417. *in the* Lues Venerea, 433,&c. *in a virulent strangury*, 441. *in the small pox*, 452. *in the leprosie*, 462. *concerning poysons*, 468. *in the bite of a mad dog*, 471. *in the plague*, 502. *in plague sores* 516,&c.
Pronatores musculi, 150
Properties of a good Surgeon, 2
Proptosis oculi, 381
Prostates, 79,&c.
Proud-flesh in ulcers, how helped, 312
Psilothra, *their form and use*, 662
Pudendæ Venæ, 77
Pulse, the triple use thereof, 13
Pulsation in a Phlegmon how caused, 173
Pultisses how different from Cataplasms, 649
Punctus aureus, 208
Puncture of a nerve, why deadly, 266
Purging whether necessary in the beginning of pestilent diseases, 508
Purple spots, or tokens in the plague, 512
Their cure, 513
Pus, *or quitture, the signs thereof*, 175
How it may flow from the wounded part and be evacuated by urine and stool, 405
Putrefaction in the plague different from common putrefaction, 491
Three causes thereof, 492
Pies may be taught to speak 45
Pylorus, 67
Pyramidal muscles, 65
Pyroticks, their nature, kinds, and use, 640

Q.

Quadrigemini musculi, 156
Quartane ague or fever, the causes, signs, symptoms, 192
Prognosticks, and cure, ibid.
Quicksilver, why so called 487
Whether hot or cold, ibid.
Wherefore good, ibid.
The kinds thereof, ibid.
How to purifie it, 488
See *Hydrargyrum*.
Quotidian fever, the cause thereof, 187
The Signs, Symptoms,&c. ibid.
The cure, ibid.
How to be distinguished from a double Tertian, ibid.

R.

Rack-bones, their fracture, 335
Radish root draws out venom powerfully, 518
Radius, *what*, 145
Ramus splenicus, 73
Mesenteriacus, 74
Ranula, *why so called, the cause and cure*, 197
Ratsbane, or Roseager, the poysonous quality and cure, 486
Raving, See *Delirium*.
Reason, and the functions thereof, 542
Recti musculi, 133,158
Rectum intestinum, 69
Reins, See *Kidnies*.
Remedies supernatural, 604
See *Medicines*.
Remora, *the wondrous force thereof*, 619
Repletio ad vasa & ad vires, 23
Repercussives, 634
What dissuades their use, 172
When to be used, 174
Fit to be put into, and upon the eye, 380
Their differences,&c. 634
Reports how to be made, 680
Resolving medicines, and their kinds, 636
Resolving and strengthning medicines, 179, 197
Respiration how a voluntary motion, 15
The use thereof, 94
Rest necessary for knitting of broken bones, 340
Rete mirabile. 115
Whether different from the Plexus choroides, 116
Rhinocerot, 42. *His enmity with the Elephant*, 625
Rhomboides musculus, 141
Ribs, their number, connexion, and consistence, 91,92
Their contusion, and a strange symptom sometimes happening thereon, 296. *Their fracture, the danger and cure*, 333
Symptoms ensuing thereon, 334. *Their dislocation and cure*, 355
Right muscles of the Epigastrium, 63
Rim of the Belly, 65. *The figure, composure*, &c. *thereof*, ibid.
Ringworms, 179
Rotula genu, 158
Rough Artery, 103
Rowlers, See *Bandages*.
Rules of Surgery, 679
Rump, the fracture thereof, 335. *The dislocation thereof*, 355. *The cure*, ibid.
Ruptures, 205. *Their kinds*, ibid. *Their cure*, 206,&c.

S.

Sacer musculus, 140
Sacræ venæ, 76
Sacro-lumbus musculus, 140
Salamander, the symptoms that ensue upon his poyson, and the cure, 475
Salivation, 23
Sanguine persons, their manners and diseases, 10
Saphena vena, *when and where to be opened*, 152
Sarcocele, 205. *The prognosticks and cure*, 211
Sarcoticks, simple and compound, 638. *None truly such*, ibid.
Scabious, the effect thereof against a pestilent carbuncle, 518
Scales how known to be severed from the bones, 342
Scales, of brass, their poysonous quality and cure, 486
Of iron, their harm and cure, ibid.
Scal'd head, the signs and cure thereof, 375
Scalenus musculus, 135
Scalp, hairy-scalp, 106
Scaphoides os, 160
Scars how to help their deformity, 519
Scarus *a fish*, 42
Sceleton, *what*, 163, 164, 165
Sciatica, the cause, &c. 428. *The cure* 429
Scirrhus, *what*, 188. *What tumors referred thereto*, 172. *The differences, Signs and Prognosticks*, 188. *Cure*, ibid.
Scorpion bred in the brain by smelling to Basil, 478
Their description, sting and cure, ibid.
Scrophulæ, *their cause and cure*, 186

Scull

Scull, and the bones thereof, 108. *The fractures thereof*, See *fractures*. *Depressions thereof how helped*, 230. 247
Where not to be trepaned, 615
Sea-feather and grape, 615
Sea-hare, his description, poyson, and the cure thereof, 482
Seasons of the year, 6
Secundine, why presently to be taken away after the birth of the child, 546. *Why so called*, 547. *Causes of the stay, and symptoms that follow thereon*, ibid.
Seed bones, 140, 160
Seed, the condition of that which is good, 534. *The qualities*, 537. *The ebullition thereof*, &c. 541. *Why the greatest portion thereof, goes to the generation of the head and brain*, ibid.
Seeing, the instrument, object, &c. *thereof*, 14
Semicupium, *the form, manner, and use thereof*, 656
Semispinatus musculus, 140
Sense, common sense, and the functions thereof, 543
Septum lucidum, 111
Septick medicines, 640
Serpent Hæmorrhous, his bite and cure, 474. *Seps his bite and cure*, ibid. *Basilisk his bite and cure*, 475. *Asp, his bite and cure*, 476. *Snake his bite and cure*, 477
Serratus Musculus Major, 141. posterior & superior, *ibid.* minor. ibid.
Serous humour, 9
Sesamoidea ossa, 149, 160
Seton, wherefore good, 254. *the manner of making thereof*, ibid. *Sex, what, and the difference thereof*, 16. *Histories of the change thereof*, 593
Shame, and shame-fac'tness, their effects, 24, 25
Shin bone, 157
Shoulder-blade, the fractures thereof, 332. *the cure*, 333. *the dislocation*, 356. *the first manner of restoring it*, ibid. *the second manner*, 357. *the third manner*, 358. *the fourth manner*, ibid. *the fifth*, 359. *the sixth*, 360. *how to restore it dislocated forwards*, 361. *outwards*, ibid. *upwards*, ibid.
Signs of sanguine, cholerick, phelgmatick, and melancholick persons, 10
Signs in general whereby to judge of diseases, 680
Silk-worms, their industry, 37
Similar parts, how many, and which, 51
Simple medicines, their differences in qualities and effects, 630. *hot, cold, moist, drie in all degrees*, ibid. 631. *their accidental qualities*, ibid. *their preparation*, 634
Siren, 611
Skin two-fold, the utmost or scarf-skin, 56. *the true skin*, ibid. *the substance, magnitude*, &c. *thereof*, ibid.
Sleep, what it is, 22. *the fit time, the use and abuse thereof*, ibid. *when hurtful*, 188. *how to procure it*, 511
Smelling, the object and medium *thereof*, 15
Snake, his bite, and cure, 477
Solanum manicum, *the poysonous quality, and cure*, 483
Soleus musculus, 161
Solution of continuity, 26. *why harder to repair in bones*, 328
Sorrow, the effects thereof, 24
Soul or life, what it performs in plants, beasts, and men 543, *when it enters into a body*, &c. 542
Sounds, whence the difference, 130
Southern people, how tempered, 11
South winds, why pestilent, 492
Swooning, what, the causes and cure, 224
Sparrows, with what care they breed their young, 35
Spermatica arteria, 76. Vena, ibid.
Spermatick vessels in men, 78. *in women*, 83. *the cause of their foldings*, 537
Sphincter muscle of the fundament, 69. *of the bladder*, 81
Spiders, their industry, 36. *their differences and uses*, 479
Spinal marrow, the coats, substance, use, &c. *thereof*, 117. *signs of the wounds thereof*, 259
Spinatus musculus, 135
Spine, the dislocation thereof, 352, 354. *how to restore it*, ibid. *a further inquiry thereof*, ibid. *prognosticks*, 355
Spirit, what, 15. *threefold*, viz. *Animal, Vital, and Natural*, ibid. *fixed*, ibid. *their use*, 16
Spirits, how to be extracted out of herbs and flowers, &c. 671
Spleen, the substance, magnitude, figure, &c. *thereof*, 73
Splenicus musculus, 133
Splints, and their use, 326
Spring, the temper thereof, 6
Squinancy, the differences, symptoms, &c. *thereof*, 200. *the cure*, ibid.
Stapes, *one of the bones of the auditory passage*, 108, 127
Staphyloma, *an effect of the eyes, the causes thereof*, 382
Stars, how they work upon the Air, 18
Steatoma, *what*, 184
Sternon, the anatomical administration thereof, 92
Sternutamentories, their description and use, 653
Stinging of Bees, Wasps, Scorpions, &c. See *Bees, Wasps, Scorpions*, &c.
Sting-ray, the symptoms that follow his sting, and the cure, 481
Stink, an inseparable companion of putrefaction, 214
Stomack, the substance, magnitude, &c. *thereof*, 67. *the orifices thereof*, ibid. *signs of the wounds thereof*, 264. *the ulcers thereof*, 317
Stones, See *Testicles*.
Stone, the causes thereof, 392. *signs of it in the kidnies and bladder*, ibid. *prognosticks*, 393. *the prevention thereof*, 394. *what to be done when the stone falls into the ureter*, 395. *signs it is faln out of the ureter into the bladder*, 396. *what to be done when it is in the neck of the bladder, or the passage of the yard*, ibid. *how to cut for the stone in the bladder*, 398, &c. *how to cure the wound*, 402. *to help the ulcer when the urine flows out by it*, 403. *how to cut women for the stone*, ibid. *divers strange ones mentioned*, 609
Storks, their piety, 38
Stoves, how to be made, 659
Strangury, the causes, &c. *thereof*, 408. *a virulent one, what*, 440. *the causes and differences thereof*, ibid. *prognosticks*, 441. *from what part the matter thereof flows*, ibid. *the general cure*, ibid. *the proper cure*, 442. *why it succeedeth immoderate copulation*, 537
Strangulation of the mother or womb, 572. *signs of the approach thereof*, 573. *the causes and cure*, 574
Strengthening medicines, See *Corroborating*.
Strumæ, See *Kings-evil*.
Sublimate, See *Mercury*.
Subclavian, See *Artery and Vein*.
Subclavius musculus, 140
Succarath, a Beast of the West Indies, 37
Suffusio, See *Cataract*.
Suggillations, See *Contusions*.
Summer, the temper thereof, 6
Supinatores musculi, 150
Suppuration, the signs thereof, 170. *caused by natural heat*, 186
Suppuratives, 175, 185. *an effectual one*, 288. *their differences*, &c. 636. *how they differ from emollients*, 637
Superfœtation, what, 561. *the reason thereof*, ibid.
Suppositories, their difference, form, and use, 644
Suppression of Urine, See *Urine*.
Surgery, what, 1. *the operation thereof*, ibid.
Surgeons, what necessary for them, 1. *their office*, 2. *the choice*

choice of ſuch as ſhall have a care of thoſe ſick of the Plague, 499. *they muſt be careful in making Reports*, 680. *how long in ſome caſes they muſt ſuſpend their judgments*, ibid. *they muſt have a care leſt they bring Magiſtrates into an error*, 684. *how to Report, or make Certificates in divers caſes*, ibid, &c.

Sutures of the ſcull, their number, &c. 107. *want in ſome*, ibid. *why not to be trepaned*, ibid. *Sutures in wounds, their ſorts and manners how to be performed*, 219

Sweating ſickneſs, 493

Sweet-bread, 71

Sweet waters, 663

Swine aſſiſt their fellows, 41

Symptoms, their definition and diviſion, 26

Sympathy and Antipathy of living creatures, 46

Symphyſis, *a kind of articulation*, 166

Synarcoſis, Synarthroſis, Synchondroſis, Syneuroſis, 166

Synochus putrida, *its cauſe and cure*, 177

T.

TAlparia, *what*, 184

Tarentulas poyſonous bite, and cure, 31

Tarſus, *what*, 121

Taſtes what, their differences, 632. *their ſeveral denominations and natures*, ibid.

Taſting what, 14

Teeth, their number, diviſion, and uſe, 19. *wherein they differ from other bones*, ibid. *pain of them how helped*, 267. *their affects*, 387. *how to draw them*, 388. *to cleanſe them*, 389. *how to ſupply their defect*, 526. *to help the pain in breeding them*, 584

Temporal muſcle, 125, *what enſues the cutting thereof*, 247

Temperament, what the diviſion thereof, 4. ad pondus, ibid. ad juſtitiam, ibid. *Of a bone, ligament, griſle, tendon, vein, artery*, 5. *of ages*, ibid. *of humors*, 7.

Temper of the four ſeaſons of the year, 6. *native temper how changed*, 11

Temperatures in particular; as of the ſouthern, northern, &c. *people*, ibid.

Tenſores muſculi, 156

Tertian agues, or fevers, their cauſes, &c. 180. *their cure*, ibid. &c.

Teſticles their ſubſtance, 78. *in women*, 83. *their wounds*, 266

Teſtudo, *what*, 184

Tettars their kinds and cauſes, 179. *their cure*, ibid. &c. 662. *occaſioned by the* Lues Venerea, 450. *their cure*, 451

Thanatth, a ſtrange beaſt, 624

Thenar muſculus, 161, 162

Thigh the nerves thereof, 153. *its proper parts*, 154. *and wounds thereof*, 266

Thigh-bone, the appendices and proceſſes thereof, 155. *the fracture, and cure*, 337. *nigh to the joynt* 339. *its diſlocation*, 369. See *Hip.*

Things natural, 2. *not natural*, 17. *why ſo called*, ibid. *againſt nature*, 25

Thorax, *the cheſt and parts thereof*, 89

Thoracica arteria, 103

Throat, how to get out bones, and ſuch like things that ſtick therein, 386

Throttle, and the parts thereof, 130

Throws and their cauſe, 546

Thymus *what*, 103

Tibia, 157

Tibiæus anticus muſculus, 161. poſticus, ibid.

Tinea, *what*, 375

Toad, his bite and cure, 477

Tongue, its quantity, &c. 128. *its wounds, its cure*, 257. *its impediments and contraction, and the cure*, 390. *to ſupply its defects*, 527

Touſillæ, 220. *their inflammation, and their cure*, ibid.

Tooth-ach, the cauſes, ſigns, &c. 386

Tophi, *or knots at the joynts in ſome that have the Gout, how cauſed*, 427. *the* Lues Venerea *how helped*, 446

Torpedo, *his craft and ſtupifying force*, 620

Touching how performed, 15

Touca, *a ſtrange bird*, 621

Trapezius muſculus, 141

Tranſverſe muſcles of the Epigaſtrium, 64

Treacle, how uſeful in the gout, 420. *how the force of ſimple poyſons*, 468

Trepan, when to be applied 229. *their deſcription*, 245. *where to be applied*, 247

Trepaning why uſed, 244. *how performed*, 245. *a caution in performance hereof*, ibid.

Triangulus muſculus, 140

Triton, 611

Trochanters, 155

Tranſverſarius muſculus, 135

Truſſes, their form and uſe, 207

Tumors, their differences, 169. *their general cauſes, ſigns*, 170. *general cure*, 171. *which hardeſt to be cured*, ibid. *the four principal*, 172. *flatulent and wateriſh, their ſigns and cure*, 182. *of the gums*, 197. *of the almonds of the throat*, 198. *of the navel*, 205. *of the groin and cods*, ibid. *of the knees*, 212

Turtles, 38

Tympany, See *Dropſie.*

V.

VAlves *of the heart, their action, ſite*, &c. 69

Varicous bodies, 79

Varices, *what, their cauſes, ſigns, and cure*, 319

Vas breve, ſeu venoſum, 74

Vaſa ejaculatoria, 79

Vaſti muſculi, 158

Vein what, 62. *Gate-vein, and its diſtribution*, 73. *deſcendent hollow vein, and its diſtribution*, 76. *aſcendent hollow vein, and its diſtribution*, 98. *they are more then arteries*, 101. *thoſe of the eyes*, 124. *which to be opened in the inflammation of the eyes*, ibid. *the cephalick*, 142. *Median*, ibid. *diſtribution of the ſubclavian vein*, ibid. *of the axillary*, 143. *of the crural*, 152

Vena porta, 73. cava, 76. arterioſa, 97. phrenica, coronales, azygos, intercoſtalis, mammaria, 98. cervicalis, muſculoſa, *ibid.* axillaris, humeralis, jugularis interna & externa, *ibid.* recta pubis, 100. cephalica, humeraria, mediana, 142. ſalvatella, & ſplenica, 143. ſapheia, vel ſaphena, iſchiadica, 152. muſcula, poplitea, ſuralis, iſchiadica major, ibid.

Venery its diſcommodities in wounds of the head, 241

Venemous bites and ſtings how to be cureed, 469

Venom of a mad dog, outwardly applied, cauſeth madneſs, 471

Ventoſes their form and uſe, 412

Ventricle, See *Stomach.*

Ventricles of the brain, 111

Verdegreaſe, its poynſonous quality and cure, 486

Vertebræ, *and their proceſſes*, 131. *of the neck*, ibid. *of the holy-bone*, 132. *how different of thoſe of the loins*, 139. *Tenth of the back, how the middle of the ſpine*, ibid. *their diſlocation*, 353. See *Spine.*

Vertigo, *its cauſes and ſigns*, 376. *the cure*, ibid.

Veſſels for diſtillation, 665, &c.
Veſicatories, why better then cauteries in cure of a peſtilent bubo, 514. *whereof made*, 640. *their deſcription and uſe*, 652
Viper, See *Adder*.
Virginity the ſigns thereof, 684
Vital parts which, 53. *their diviſion*, ibid.
Vitreus humor, 124
Viver, or, *as ſome term it, the Weaver, a fiſh, his poyſonous prick and the cure*, 481
Ulcers, conjoyned with tumors how cured, 180. *in what bodies not eaſily cured*, 277. *their nature, cauſes*, &c. 307. *ſigns*, 309. *prognoſticks*, ibid. *their general cure*, 310. *ſigns of a diſtempered one, and the cure*, 311. *a painful one and the cure*, ibid. *with proud fleſh in them*, 312. *putrid and breeding worms*, 312. *a ſordid one*, ibid. *a malign, virulent, and eating one*, 313. *advertiſements concerning the time of dreſſing ulcers*, 314. *how to bind them up*, ibid.
Ulcers in particular, and firſt of the eyes, ibid. *of the noſe*, 315. *of the mouth*, ibid. *of the eares*, 316. *of the windpipe, weazon, ſtomach, and guts*, 317. *of the kidnies and bladder*, ibid. *of the womb*, 318. *that happen upon the fracture of the leg, rump, and heel*, 343. *how to prevent them*, ibid. *they muſt be ſeldom dreſt when the Callus is breeding*, 344
Umbilical veſſels, how many and what, 540
Unction to be uſed in the Lues Venerea, 435. *their uſe*, 436. *cautions in their uſe*, ibid. *and the inconveniences following the immoderate uſe*, 437
Ungula, *or the web on the eye, the cauſes, prognoſticks, and cure*, 381
Unguentum adſtringens, 646. nutritum, *ibid.* aureum, *ibid.* baſilicum, ſive tetraphamacum, *ibid.* diapompholigos, *ibid.* deſiccativum rub. *ibid.* enulatum, *ibid.* Album Rhaſis, *ibid.* Altheæ, *ibid.* populeon, *ibid.* apoſtolorum, *ibid.* commitiſſæ, 647. pro ſtomacho, *ibid.* ad morſus rabioſos, ibid.
Unicorn. if any ſuch beaſt, what the name imports, 488. *what the ordinary horns are*, 489. *not effectual againſt poyſon*, ibid. *effectual only to dry*, ibid. *in what caſes good*, ibid.
Voices whence ſo various, 130
Vomits their force, 23. *their deſcription, their deſcription*, 188
Vomiting, why it happens in the Colick, 69. *the fitteſt time therefore*, 419. *to make it eaſie* ibid.
Voyages and other employments, wherein the Author was preſent; of Thurin, 692. *of Morolle and Low-Britain*, 694. *of Perpignan*, 695. *of Landreſie*, ibid. *of Bologn*, ibid. *of Germany*, 696. *of Danvillers*, ibid. *of Caſtle of Compt*, 697. *Of Mets*, ibid. *of Hedin*, 701. *Battel of St. Quintin*, 707. *Voyage of Amiens*, ibid. *of Harbor of Grace*, 708. *to Roven*, ibid. *battel of Dreux*, ibid. *of Moncontour*, 709. *Voyage of Flanders*, ibid. *of Burges*, 712. *battel of St. Dennis*, ibid. *Voyage of Baion*, 713
Urachus, 88
Ureters, their ſubſtance, &c. 81
Urine ſtopt by diſlocation of the thigh-bone, 368. *ſuppreſſion thereof how deadly*, 393. *how it happens by internal cauſes*, 405. *by external*, 406. *prognoſticks*, ibid. *things unprofitable in the whole body, purged thereby*, ibid. *bloody, the differences and cauſes thereof*, ibid. *the cure*, ibid. *ſcalding thereof how helped*, 441. *a receptacle for ſuch as cannot keep it*, 529
Urines of ſuch as have the Plague ſometimes like thoſe that are in health, 500
Uteliſ, *a ſtrange fiſh*, 43
Uvea tunica, 122
Vulnerary potions, their uſe, 458. *the names of the ſimples whereof they are compoſed*, ibid. *their form and when chiefly to be uſed*, ibid.
Uvula, *the ſite and uſe thereof*, 129. *the inflammation and relaxation thereof*, 198. *the cure*, 199

W.

WAlnut tree, and the malignity thereof, 484
Warts of the neck of the womb, 582. *their cure*, ib.
Waſhes to beautifie the skin, 660
Waſps, their ſtinging how helped, 478
Watching, the diſcommodities thereof, 22
Water, its qualities, 3. *beſt in time of Plague*, 494
Waters, how to be diſtilled, 667
Watriſh tumors, their ſigns and cure, 182
Weapons, of the Antients compared with thoſe of the modern times, 271
Weazon, the ſubſtance, &c. *thereof*, 103. *how to be opened in extream diſeaſes*, 198. *the wounds thereof*, 258. *the ulcers thereof*, 317
Weakneſs, two cauſes thereof, 170
Web on the eye, which curable, and which not, 381. *the cure*, ibid.
Wedge-bone, 108
Weights and and meaſures, with their notes, 642
Wens their cauſes and cure, 184. *how to diſtinguiſh them in the breaſt from a Cancer*, 185
Whale, why reckoned among monſters, 618. *they bring forth young, and ſuckle them*, ibid. *how caught*, 619
Whale-bone, ibid.
Whirl-bone, the fracture and the cure, 340. *diſlocation thereof*, 371
White-line, 65
Whites, the reaſon of the name, differences, &c. 580. *cauſes*, ibid. *their cure*, 581
Whitlows, 212
Wine which not good in the Gout, 421
Winds, their tempers and qualities, 18
Winter, and the temper thereof, 6. *how it increaſeth the native heat*, ibid.
Wiſdom the daughter of memory and experience, 542
Witches hurt by the Devils aſſiſtance. 604
Wolves, their deceits and ambuſhes, 40
Womb, the ſubſtance, magnitude, &c. *thereof*, 85. *the coats thereof*, 87. *ſigns of the wounds thereof*, 264. *ulcers thereof, and their cure*, 318. *when it hath received the ſeed, it is ſhut up*, 537. *the falling down thereof how cauſed*, 547. *it is not diſtinguiſhed into cells*, 561. *a ſcirrhus thereof*, 566. *ſigns of the diſtemper thereof*, 567. *when meet for conception*, ibid. *of the falling down, perverſion or turning thereof*, 568. *the cure thereof*, 569. *it muſt be cut away when it is putrified*, ibid. *the ſtrangulation or ſuffocation thereof*, 572. See *Strangulation*.
Women, their nature, 16. *how to know whether they have conceived*, 537. *their travel in childbirth and the cauſe thereof*, 543. *what muſt be done to them preſently after their deliverance*, 546. *bearing many children at a birth*, 591
Wonderful net, 115
Wondrous original of ſome creatures, 611. *nature of ſome marine things*, ibid.
Worms in the teeth, their cauſes, and how killed, 388. *bred in the head*, 455. *caſt forth by urine*, 456. *how generated, and their differences*, 457. *of monſtrous length*, 458. *ſigns*, ibid. *the cure*, 459
Wounds may be cured only with lint and water, 33
Wounds termed great in three reſpects, 217, 680
Wounds poyſoned how cured, 467
Wounds of the head at Paris, *and of the legs at* Avignon, *why hard to be cured*, 284
Wounds what, the diverſe appellation and diviſion of them, their cauſes, ibid. *and ſigns*, 217. *prognoſticks*, ibid. *ſmall ones ſometimes mortal*, ibid. *their cure in general*, 218. *to ſtay their bleeding*, 220. *to help pain*, 221.

why

why ſome die of ſmall ones, and others recover of great, 236. *whether better to cure in children or in old people,* ibid. *wounds of the head,* See *fractures. Of the muſculous skin thereof,* 241. *their cure,* ibid. *of the face,* 252. *of the eye-brows,* 253. *of the eyes,* ibid. *of the cheek,* 255. *of the noſe,* 256. *of the tongue,* 257. *of the ears,* ibid. *of the neck and throat,* ibid. *of the weazon and gullet,* 258. *of the cheſt,* 259. *of the heart, lungs and midriff,* ibid. *of the ſpine,* ibid. *what wounds of the lungs curable,* 261. *of the* Epigaſtrium *or lower belly,* 264. *their cure,* 265. *of the Kall,* ibid. *of the fat,* ibid, *of the groins, yard, and teſticles,* 266. *of the thighs and legs,* ibid. *of the nerves and nervous parts,* ibid. *of the joynts,* 268. *of the ligaments,* 269

Wounds contuſed muſt be brought to ſuppuration, 277

Wounds made by gun-ſhot are not burnt, neither muſt they be cauterized, 272. *they may be dreſſed with ſuppuratives,* 273. *why hard to cure,* ibid. *why they look black,* 274. *they have no Eſcar,* ibid. *why ſo deadly,* 275. *in what bodies not eaſily cured,* 277. *their diviſion,* 278. *ſigns,* ibid. *how to be dreſt at the firſt,* ibid. *how the ſecond time,* 282. *they all are contuſed,* 287

Wounds made by arrows, how different from thoſe made by gun-ſhot, 291

Wriſt, and the bones thereof, 148. *the diſlocation thereof, and the cure,* 365.

Y.

YArd, and the parts thereof, 82. *the wounds thereof,* 266. *to help the cord thereof,* 391. *the malign ulcers thereof,* 431. *to ſupply the defect thereof for making water,* 530

Yew-tree, its malignity, 484

Z.

Zirbus, the Kall, the ſubſtance, &c. *thereof,* 66

FINIS.